This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

+ *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.

+ *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.

+ *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.

+ *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at `http://books.google.com/`

600019716U



1562 d. 89
C

RADCLIFFE LIBRARY
UNIVERSITY
OCT 16

600019716U



1562 d. 89
C

RADCLIFFE LIBRARY
UNIVERSITY
OCT 16

43D CONGRESS, 2d Session. } HOUSE OF REPRESENTATIVES. { Ex. Doc. No. 95.

THE

CHOLERA EPIDEMIC OF 1873

IN THE

UNITED STATES.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1875.

MESSAGE

FROM

THE PRESIDENT OF THE UNITED STATES,

TRANSMITTING

Reports upon the Causes of Epidemic Cholera.

JANUARY 13, 1875.—Referred to the Committee on Commerce and ordered to be printed

---

To the Senate and House of Representatives :

In accordance with the requirements of the joint resolution, approved March 25, 1874, authorizing an inquiry into and report upon the causes of epidemic cholera, I have the honor to transmit herewith reports upon the subject from the Secretaries of the Treasury and War Departments.

U. S. GRANT.

EXECUTIVE MANSION, *January* 12, 1875.

TREASURY DEPARTMENT. SUPERVISING SURGEON'S OFFICE.

CHOLERA EPIDEMIC OF 1873

IN THE

UNITED STATES.

THE INTRODUCTION OF EPIDEMIC CHOLERA THROUGH THE AGENCY OF THE MERCANTILE MARINE: SUGGESTIONS OF MEASURES OF PREVENTION.

By JOHN M. WOODWORTH, M. D.,
SUPERVISING SURGEON U. S. [MERCHANT] MARINE-HOSPITAL SERVICE.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1875.

TREASURY DEPARTMENT,
December 31, 1874.

SIR: Herewith is transmitted the report of the Supervising Surgeon of the Marine-Hospital Service upon the cholera epidemic of 1873, made in accordance with a joint resolution of Congress approved March 25, 1874.

I am, sir, very respectfully,

B. H. BRISTOW,
Secretary of the Treasury.

To the PRESIDENT.

UNITED STATES MARINE-HOSPITAL SERVICE,
SUPERVISING SURGEON'S OFFICE,
Washington City, December 30, 1874.

SIR: The Supervising Surgeon of the United States Marine-Hospital Service, in connection with a medical officer of the Army, was instructed by joint resolution of the Forty-third Congress, approved March 25, 1874, "to confer with the health authorities and resident physicians of such towns, [as were visited by the cholera epidemic of 1873,] and to collect, as far as possible, all facts of importance with regard to such epidemic," for the purpose of making a report of the same to the President of the United States, to be submitted to Congress.

In pursuance of these instructions I have the honor to transmit the accompanying report.

Very respectfully,

JOHN M. WOODWORTH,
Supervising Surgeon.

To the Hon. SECRETARY OF THE TREASURY.

THE INTRODUCTION OF EPIDEMIC CHOLERA INTO THE UNITED STATES THROUGH THE AGENCY OF THE MERCANTILE MARINE: SUGGESTIONS OF MEASURES OF PREVENTION.

THE INTRODUCTION OF EPIDEMIC CHOLERA INTO THE UNITED STATES THROUGH THE AGENCY OF THE MERCANTILE MARINE: SUGGESTIONS OF MEASURES OF PREVENTION.

In the preamble to a joint resolution of the Forty-third Congress of the United States, adopted during its first session, and approved by the President March 25, 1874, it was set forth that Epidemic Cholera had "prevailed during the year eighteen hundred and seventy-three in various parts of the United States, especially in the valley of the Mississippi, causing a deplorable mortality;" and that it is highly important, whenever such epidemics occur, that "the facts concerning the spread of the disease and its mode of propagation should be ascertained as fully as possible, with a view to the prevention or limitation of future outbreaks." It was therefore ordered that a medical officer of the Army, in connection with the Supervising Surgeon of the Marine-Hospital Service, should ascertain such facts, and "make a detailed report of the information collected, on or before the first day of January, eighteen hundred and seventy-five, to the President, to be submitted to Congress."

With the strictly narrative portion of the investigation made in pursuance of the foregoing it is not here proposed to deal. That is done most thoroughly and exhaustively by Dr. McClellan, to whom were furnished whatever facts of importance the Supervising Surgeon had been able to gather concerning the epidemic, and much of which that gentleman has incorporated in his report.*

It will rather be attempted in these pages to briefly set forth the facts which establish the connection of the mercantile marine with the importation of cholera into the United States, and to suggest what, in the present state of knowledge concerning the disease, may be done by addressing our efforts to this alleged *fons et origo* of malignant cholera in the western hemisphere, "with a view to the prevention or limitation of future outbreaks." For if it be true that "cholera has always been brought to America by ships," the task of preventing future outbreaks within our borders is a problem in preventive medicine the solution of which would seem comparatively easy. Such solution depends, however, in common with the answer to any question, upon the extent and accuracy of our knowledge of the factors of the problem. Hence it will be necessary to state compendiously what is known and accepted concerning the cause of malignant cholera—its origin, character, mode of propagation, transportation, etc.; a summary which will be of additional use in assisting to a correct estimate of the value of any suggested means of prevention or limitation. No attempt is made in this summary to decide questions which are yet *sub judice*, to discuss mere theories, or to trace the various phases through which "the distractingly confusing history of the disease" has passed. On the contrary, what is here offered is simply a series of propositions condensed from the vast mass of cumulative evidence which has been laboriously col-

* See Appendix A.

lected by a multitude of cholera-students in both hemispheres; and these propositions are intended to bear solely upon the question of the exclusion of the disease from this country:

I. *Malignant cholera is caused by the access of a specific organic poison to the alimentary canal; which poison is developed spontaneously only in certain parts of India. (Hindostan.)**

II. *This poison is contained primarily, so far as the world outside of Hindostan is concerned, in the ejections—vomit, stools, and urine—of a person already infected with the disease.*

III. *To set up anew the action of the poison, a certain period of incubation with the presence of alkaline moisture is required, which period is completed within one to three days; a temperature favoring decomposition and moisture or fluid of decided alkaline reaction hastening the process, the reverse retarding.*

IV. *Favorable conditions for the growth of the poison are found* (1) *in ordinary potable water, containing nitrogenous organic impurities, alkaline carbonates, etc.;* (2) *in decomposing animal and vegetable matter possessing an alkaline reaction;* (3) *in the alkaline contents of the intestinal portion of the alimentary canal.*

V. *The period of morbific activity of the poison—which lasts, under favorable conditions, about three days for a given crop—is characterized by the presence of bacteria, which appear at the end of the period of incubation, and disappear at the end of the period of morbific activity. That is to say, a cholera-ejection, or material containing such, is harmless both before the appearance and after the disappearance of bacteria, but is actively poisonous during their presence.*

NOTE.—It is not meant by this that the bacteria so found are the cholera-poison, since they differ in no appreciable manner from bacteria found in a variety of other fluids. Indeed, Lebert hints that the bacteria may even be the destroyers of the poison.†

VI. *The morbific properties of the poison may be preserved in posse for an indefinite period in cholera-ejections dried during the period of incubation, or of infection-matter dried during the period of activity.*

VII. *The dried particles of cholera-poison may be carried (in clothing, bedding, etc.) to any distance; and when liberated may find their way direct to the alimentary canal through the medium of the air—by entering the mouth and nose and being swallowed with the saliva—or, less directly, through the medium of water or food in which they have lodged.*

VIII. *The poison is destroyed naturally either by the process of growth or by contact with acids:* (1) *those contained in water or soil;* (2) *acid-gases in the atmosphere;* (3) *the acid secretion of the stomach.*

IX. *It may also be destroyed artificially* (1) *by treating the cholera-ejec-*

* The student of cholera-literature cannot fail to be struck with the resemblance between the early writing on *syphilis* and much of the current speculation and theory concerning cholera. It now seems incredible that the connection between sexual intercourse and syphilis should have ever been overlooked—not to say vehemently denied—and yet it is not hazarding much to say that future generations will be quite as incredulous of the delay in recognizing the true mode of cholera-propagation. Just as certainly as that contact of pre-existing syphilitic virus is necessary to produce syphilis, so certainly is contact of the pre-existing cholera-virus necessary to produce cholera in any portion of the globe outside of Hindostan.

† "Among the reasons why the disease does not fully develop under apparently favorable conditions, we may notice here again the fact that the germs may reach even an exuberant growth in the water of the soil and then be destroyed by otherwise innocent bacteria of putrefaction and fermentation before they have come into thorough contact with the human organism."—(*Cyclopedia of the Practice of Medicine.* ZIEMSSEN, vol. I, p. 374.)

tions, or material containing them, with acids; (2) *by such acid (gaseous) treatment of contaminated atmosphere;* (3) *by establishing an acid diathesis of the system in one who has received the poison.*

NOTE.—Why, when perennially endemic in India, with which country intercourse is constant, the disease becomes epidemic elsewhere only at long intervals, is beside the present purpose to inquire. What conditions, meteorologic, telluric, and diathetic, are necessary to its epidemic spread, even in India, are not yet determined; and no practical result for the object of this paper could accrue from speculation thereon. Neither are modes of treatment when the disease is established in the system any better settled; and as in these pages it is intended to deal only with generally accepted facts and measures based thereon, these topics are necessarily excluded from present consideration.

The deductions which may be legitimately made from the foregoing premises are of wide applicability. Many of them are admirably discussed in connection with specific measures of prevention on shore by Dr. McClellan, whose remarks on cholera-transportation inland, by rail and river, on local and general sanitation, and upon the duty and responsibility of the State and the Nation with reference to the public health, are replete with information and sound counsel. These deductions, however, should be first applied to the subject of modes of excluding the poison—which is, *ipso facto*, the disease—from our shores, a question logically taking precedence of that of purely terrene measures of prevention, so far as this country is concerned, and one which may be conveniently discussed under the general topic of Marine Sanitation, including in this term the Sanitary Supervision of Ocean Travel and Traffic, the Question of Quarantine, the Mode of Dealing with Cholera on Shipboard, and the Treatment of an Infected or Suspected Ship on Arrival at a United States Port.

Under the first head it may be observed it has not yet been demonstrated that merchandise, in contradistinction to passengers' luggage, is ever the medium of conveying the cholera-poison across the Atlantic. Even upon infected vessels the cargo is so protected from any chance of contact with cholera-ejections that the risk of importation from this source is of little practical moment. Of course, upon a very foul ship carrying steerage passengers suffering from cholera, there is a bare possibility of such contact; but no instance of this kind has ever been known to occur. So that the subjects of this supervision are limited to (*a*) human beings—cabin and steerage passengers, officers and crew; and (*b*) personal effects—comprising hand-luggage, (or such as is allowed in cabin or steerage for use on the voyage,) trunks, chests, bales of bedding, etc., packed before embarking and not opened until after arrival, the wardrobes of officers, and the kits or dunnage of the crew.

Under existing regulations for the emigration-service of most countries, some sort of inspection of steerage passengers is made with the avowed object of detaining such as "appear, by reason of bodily or mental disease, unfit to proceed;" and especial care is taken to prevent the embarkation of cases of infectious or contagious maladies among these. Unfortunately this inspection does not extend to the cabin-passengers nor to the crew. And yet it will hardly be questioned that sailors are among the most active and wide-spread propagators of disease, nor asserted that cabin passengers are exempt from the possibility of becoming poison-carriers. Indeed, during 1873 a fatal case of cholera occurred in the person of a gentleman returning from Europe on a vessel (the Ville du Havre) belonging to a line which ostensibly does not carry steerage passengers; and the circumstances of the case were such as to place it beyond doubt that a competent medical examination of

the individual would have attracted such attention to his condition as either to have prevented his embarkation or to have placed him at once in the surgeon's hands on board the vessel.

But even if cabin passengers and crew were both included in such inspection, it would be entirely inadequate as a measure of precaution in the case of cholera. Bearing in mind that "the morbific properties of the cholera-poison may be preserved *in posse* for an indefinite period in cholera-ejections dried during the period of incubation, or of infection-matter dried during the period of activity," and "that these dried particles of cholera-poison may be carried (in clothing, bedding, etc.) to any distance, and when liberated may find their way direct to the alimentary canal, through the medium of the air—by entering the mouth and nose and being swallowed with the saliva—or, less directly, through infected water or food in which they have lodged," and that thus the disease may be set up anew at points remote, both in time and space, from the immediate source of infection, it is obvious that the inspection of individuals, however thorough, is no positive safeguard; that not alone the passengers and crew may appear to be perfectly healthy, but the port and surrounding country may be free from cholera, and yet the disease be shipped from such port. Instance the cases of the Swanton and the New York, the sources of the cholera-epidemic of 1849. When these vessels left Havre in the autumn of 1848—October 31 and November 9 respectively—not alone was there no cholera at that port, but there had then been none in all France. It did, however, exist in Middle Europe, whence came the migrants who embarked on board these vessels. Cholera broke out on the New York on the 25th of November, when sixteen days out of port, and on the Swanton on the following day, November 26, when twenty-seven days out, and was carried by these vessels to the ports of New York and New Orleans respectively.

Similar cases occurred in 1854 and in 1866. In the former year, according to Prof. Henry Hartshorne, cholera broke out on the packet-ships Tonawanda and Tuscarora, bound for Philadelphia; the first case appearing on the Tonawanda two weeks after leaving Liverpool, at which port there was no cholera when she sailed. In 1866 the disease broke out on the steamer England, when five days out, and on the steamer Virginia, eight days out from a healthy port.

In 1873, three distinct outbreaks of the disease occurred at widely remote points in the United States, from poison packed and transported in the effects of emigrants from Holland, Sweden, and Russia. These people and the vessels in which they were carried had been perfectly healthy, and the people remained so until their goods were unpacked at Carthage, Ohio, at Crow River, Minn., and at Yankton, Dak., respectively. Within twenty-four hours after the poison-particles were liberated the first cases of the disease appeared, and the unfortunates were almost literally swept from the face of the earth.*

These instances, which might be multiplied, sufficiently demonstrate that no amount or character of inspection of persons alone will suffice to prevent the importation of cholera to this country while the disease exists on the European continent, as it has for the past ten years, and as it is likely to continue to do, owing to the increasing facility of intercourse with India. They also remove any difficulty in the way of accounting for the introduction of the disease into the United States during the winter of 1872–'73—a subject which has provoked so much discussion that the chief points may be outlined in this connection, bearing as they do so directly upon the topic under consideration.

* See McClellan for details of these cases.

As early as August, 1871, cholera began to be exported from Hamburg, and in September infected vessels arrived at Amsterdam in Holland, at Hull, Sunderland, and Hartlepool in England, and at Cardiff in Wales.

On the 6th of November of that year the steamship Franklyn put into Halifax, Nova Scotia, in distress. She had cleared from Stettin, October 10, touching at Copenhagen on the 12th and at Christiansand on the 15th. On the 23d, eight days after leaving the last-named port, the first death from cholera occurred, and before her arrival at Halifax there were twenty-eight deaths on board, two other fatal cases occurring while the ship was in harbor. The disease was carried on shore by two men who were employed in coaling and watering the vessel. Both were taken sick on the 13th of November, and one died after twelve hours' illness, while the other carried the disease to his family at Chezzetcook, a fishing-village on the southeast coast of Nova Scotia, about twenty-two miles from Halifax. Four members of this family contracted the disease, and two of them died; but the disease did not spread either in Halifax or vicinity.

After coaling, the steamer proceeded on her voyage to New York, where she arrived November 12th, having lost eleven more of her passengers, making forty-one deaths in all during the voyage. Seventy-two cases were removed from her to quarantine-hospital, among which number there occurred twelve more deaths, making a total of fifty-three deaths out of her 611 steerage-passengers. All the passengers were detained in quarantine about three weeks, or until the early part of December, and no diffusion of the disease is known to have followed.

According to that indefatigable investigator, Dr. Peters, the disease continued to be carried from Hamburg, and during the year 1872 it was sent thence "to London, Havre, Liverpool, New York, and various other places, probably also to New Orleans."*

Arrivals of vessels at both New York and New Orleans from a number of notoriously infected ports, including eleven arrivals at the former port from Taganrog and Cronstadt, were constant and numerous during the entire year; and one case of "cholera asphyxia" was officially reported as sent from the New York emigrant depot at Castle Garden to the State Emigrant and Refuge Hospital on Ward's Island, besides four cases of "cholera sporadica" treated in the Temporary Hospital at Castle Garden. Cholera is also reported to have prevailed during that year on the island of Cuba, and the neighboring island of Jamaica is known to have quarantined against Cuban vessels on that account. An examination of the consular correspondence of 1872–'73 from West Indian and South American ports, which examination was made for the purposes of this paper by the State Department at the request of the honorable the Secretary of the Treasury, shows also that cholera reached Jamaica in the autumn of 1872. Under date of September 23, the consul at Kingston reports the arrival of a cooly-ship at Bluff's Bay, upon which vessel sixty deaths had occurred on the passage, and one other fatal case, admitted to be cholera, occurred after her arrival.

This, it will be seen, brings the disease within striking distance of New Orleans, and direct communication between the two points is shown by the arrival of vessels from Jamaica at that city during the month of January, 1873. More conclusive, however, than this is the fact that while cholera thus existed at almost every European port of embarka-

*On the Origin and Spread of the Asiatic Cholera which raged in the United States in 1873. By John C. Peters, M. D., of New York City, chap. IV of Dr McClellan's report.

tion for emigrants—107 cases occurring in one week at Hamburg—there arrived at New Orleans, via Liverpool, Hamburg, and Bremen, during the months of December, 1872, and January, 1873, a total of nearly two thousand emigrants from cholera-infected districts of Europe.*

While, in the absence of direct evidence to the contrary, it may be admitted that no person actually laboring under cholera was landed in New Orleans during the winter of 1872–'73,† the unavoidable alternative is that the poison which caused the epidemic in the Mississippi Valley in the latter year was imported in the same manner as that which caused the later outbreaks at Carthage, Crow River, and Yankton, namely, in the personal effects of immigrants, sailing from healthy ports, in healthy vessels, and subjected to the usual sanitary requirements of the period.

And this suggests the very obvious query, "Of what avail, then, is quarantine as a measure of protection for this country against cholera, if the cholera-poison may thus elude—as it admittedly did in each of these latter cases—the surveillance of a quarantine establishment 'the best administered and most efficient in the world?'"‡

It is fortunately true that, from various causes, no extended epidemic outbreak of the disease followed the liberation of the poison-particles on the banks of the Ohio, or in Minnesota, or in the Territory of Dakota. But even the tyro in cholera will fail to be re-assured by this, remembering, as he must, that at times "a single case suffices to swiftly produce an epidemic or even a raging pestilence."§

The want of favoring conditions cannot always be depended upon. Sooner or later these will exist, and if the spark is then applied, a repetition of the horrors of 1832, of 1849, and of 1854 is inevitable.

The very success which Dr. Vander Poel has achieved in the administration of the quarantine of the port of New York proves that the spark is not always excluded by the present system of quarantine. It therefore remains to inquire, "What is yet wanting in this direction?" And the answer is not far to seek with reference to cholera: *Prompt and authoritative information to threatened ports of the shipment of passengers or goods from a cholera-infected district.*

If the health-officer at the port of New York, for instance, had been aware of the facts which were subsequently ascertained concerning the emigrants from Sweden, Holland, and Russia, there is no reason to doubt but that such measures would have been resorted to, on the arrival of these people, as would have effectually prevented the transportation of the cholera-poison in their effects half way across the continent. But how shall he obtain such knowledge? The law requires the master of a migrant-carrying vessel, on his arrival at a United States port, to furnish to the customs officer "a list of all the passengers taken on board the vessel at any foreign port or place; in which list he shall designate * * * the country to which they [the passengers] severally

* See tables compiled by Dr. McClellan from statistics of immigration into New Orleans during 1872–73.

† During the following summer it was alleged with much circumstantiality of detail that three Hungarian emigrants, *en route* for Texas, were landed and died of cholera in New Orleans about the middle of February, and that in consequence thereof the alcalde of Havana, acting upon dispatches from the Spanish consul at New Orleans, caused vessels from the latter port to be quarantined. Inquiry at the Spanish legation in Washington and of the consul at New Orleans failed to substantiate the report, although such action with reference to quarantine was in fact taken by the authorities in Havana soon after the appearance of the disease in New Orleans.

‡ *Vide* Annual Report Supervising Surgeon United States Marine-Hospital Service, 1873, p. 16.

§ Lebert, *loc. cit.*, p. 395.

belong;"* and to this list the health-officer, it is true, has access. But the information it gives is inadequate for the purpose under consideration, first, from lack of accuracy and fullness, and, secondly, because it is not available in season.

What is needed is that the National Government, through its consular officers, at least at each port of departure, shall acquire the necessary information, and then promptly and intelligently furnish it to the ports and localities exposed. This is entirely aside from a national quarantine-board, a national bureau of health, or other specific organization, concerning the present wisdom and expediency of which, opinion is at least not unanimous. It is a simple utilization of already-existing machinery on the part of the General Government, for the acquisition of knowledge indispensable to the general welfare. Such knowledge cannot through its own agents be acquired by a State or by a municipality; and yet upon such knowledge are the city and the State alone qualified or competent to take action; and upon such knowledge and action does the future immunity from cholera of the country at large depend.

A circular-letter from His Excellency the President, through the Department of State, instructing consular officers to place themselves in communication with the health-authorities of their respective localities; to advise promptly, by cable if necessary, of the outbreak of cholera (or other epidemic disease) at their ports or in any section in communication therewith; to inspect all vessels clearing for United States ports with reference to the original and intermediate as well as to the final points of departure of emigrants thereon; and to report, always by cable, the sailing and destination of any such vessel carrying infected or suspected passengers or goods—this should be the first step.†

And the next would be equally simple: A medical officer, selected for his good judgment and attainments in sanitary science, should collate and digest the information thus obtained, and transmit direct to the threatened ports, as well as through the public press, the note of warning. Thus advised, the threatened community would have ample time for preparation; and the publicity given to the warning would be the most efficient means of insuring proper precautionary measures.

International sanitary action is too remote, and the steps toward it have been too vacillating in the past to admit of much hope from it for the near future. But the acquisition and diffusion of general sanitary knowledge is a matter in which each nation for itself may engage, and when such knowledge becomes sufficiently wide-spread all else may be safely left to local and individual effort. Let the General Government do its share in collecting and publishing the information—a work which it alone can do—and the various and varying details of inspection, disinfection, isolation, etc., etc., will be most efficiently, economically, and satisfactorily performed by those most directly and vitally interested—the people themselves.

---

*Revised Statutes of the United States, sec. 4266.

† SEC. 1752. The President is authorized to prescribe such regulations and make and issue such orders and instructions, not inconsistent with the Constitution or any law of the United States, in relation to the duties of all diplomatic and consular officers, the transaction of their business, the rendering of accounts and returns, the payment of compensation, the safe-keeping of the archives and public property in the hands of all such officers, the *communication of information*, and the procurement and transmission of the products of the arts, sciences, manufactures, agriculture, and commerce, from time to time, as he may think *conducive to the public interests*. It shall be the duty of all such officers to conform to such regulations, orders, and instructions.—*The Revised Statutes of the United States*, p. 312.

For the rest, as to the treatment of an infected or suspected vessel on arrival, little need be said. The barbarous quarantine of detention, "a forty days' precaution 'gainst disease,"* is a thing of the past, at least where modern sanitary science holds sway. When the disease has actually appeared upon a vessel during the voyage, it may be necessary to detain the passengers for a time, varying with the conditions in each instance; in short, governing the administration of quarantine in accordance with common sense based upon exact knowledge of the evil to be dealt with. As Dr. VanderPoel observes, "No arbitrary rules can be laid down which shall be applicable to all vessels. Every arrival of a vessel with cholera must * * * be judged by the particular features which belong to that case. While, as a rule, every vessel, its passengers and crew having had cholera upon its passage, or at the time of its entry, should be subjected at least to a quarantine of observation, still this rule is not without exceptions. For instance, two steamers entered this harbor [New York] last fall, [1873,] having had deaths from cholera, and another with one well marked, and several of choleraic diarrhœa on board, neither one of which was detained more than twenty-four hours; and yet I felt quite secure in allowing them to proceed to the city. Why was this? In the first, the case was a cabin-passenger. The nature of the disease was almost immediately detected by the surgeon. At once absolute isolation was enforced, passengers from neighboring state-rooms were removed, dejections disinfected, and care taken with reference to soiled linen. Seven days had elapsed since the death; when the vessel entered, the state-room had been scrupulously cleaned and disinfected daily. Here, then, every intelligent preventive measure had been employed; the time of incubation, when any passenger having contracted the disease before entering the vessel, was past, and, in view of the measures employed, I had only to consider the possibility of contamination from the particular case. It had been limited to one; the average time of incubation was more than past since his death, without another case, and I therefore decided to let the vessel go up. Now, had a cast-iron rigidity been followed, without reference to the measures which the surgeon employed, all of the passengers should have been taken from the ship, subjected for eight or ten days to a quarantine of observation, the vessel itself thoroughly cleaned, and every part aired and daily fumigated. While such a course would have been warranted by law, and sanctioned, too, by sanitarians, I felt that the precautionary measures adopted were sufficient, and would encourage medical officers and the shipping interest to attack the disease at its *source*, rather than passively allow it to gain full headway, under the conviction that no efforts they might apply would be recognized by the sanitary authorities of the port. The other death was in the steerage, so sudden that the surgeon was not informed until actual collapse. On inquiry no dejection had taken place except at the water-closet into the sea; none occurred after the collapse; the clothing was at the time examined to see if there was any stain upon it; the body was at once thrown overboard, all the effects disinfected, and ten days had elapsed since the death, on their arrival. Wherein would a quarantine of ob-

* "Her husband sailed upon the Adriatic,
And made some voyages, too, in other seas;
And when he lay in quarantine for pratique,
(A forty days' precaution 'gainst disease,)
His wife would mount at times her highest attic,
For thence she could discern the ship with ease;
He was a merchant trading to Aleppo,
His name Giuseppe, call'd more briefly Beppo."—*Byron.*

servation have helped me in this matter? In the case of cholera which entered the port, every precautionary measure had been adopted; the most rigid examination and inquiry could not detect other cases of choleraic diarrhœa than those referred to. The period of incubation, from acquiring it before entering the ship, had passed, and, with no evidence of contamination to others, the vessel was allowed *pratique*. In acting in this manner in the above three instances, I but followed on a limited scale what is universally recognized by all the European governments, and to which all their later efforts have principally tended, viz, to suppress the disease as far as possible at its source. They feel that the great field for precautionary measures is in the home of the disease, and the local governments are, as far as possible, discouraging the great pilgrimages, with the large agglomerations of people, and their subsequent religious rites, with already an appreciable diminution in the routes of transmission.

"A vessel arriving, however, with several cases on board, would be compelled to undergo the full ordeal of precautionary measures. The passengers would be removed from the vessel, subjected to a quarantine of observation, and any sick appearing be removed to the hospital located on another island, a mile distant from the island where the quarantine of observation was enforced. In the mean time all clothing would be thoroughly washed, aired, and disinfected, and, when eight days had elapsed without the appearance of a new case, they would be allowed to leave. In the mean time the vessel, after being subjected to thorough cleansing and disinfection, would be allowed *pratique*."

In addition to the foregoing views and *dicta* of one of the foremost practical sanitarists of this country, it is urged that in thorough exposure to *acids* in some form, lies the only assured safety against the cholera-poison. All suspected goods should be treated with acidulated water or acid-gases before being landed; and twenty-four hours should suffice, with proper appointments, to render innocuous the cargo of the largest vessel.

With the admitted uncertainty of therapeutic measures in this disease, its outbreak at sea—which it now remains to consider—should be the signal for the most scrutinizing search for its origin, with the view of thence "stamping it out."

Cholera may break out upon a vessel at any time, from a few hours up to many days, after leaving port;* so that the mere passage of time cannot be relied on as security against an outbreak during cholera-years. But within certain limits the period of the appearance of the first case will furnish some clew as to its origin. If within the first few days—rarely, if ever, exceeding five—it may be set down as reasonably certain that the germs of the disease were brought on board by some passenger suffering from an apparently harmless diarrhœa, or in the hand-luggage or personal effects in immediate use. If a longer period has elapsed, it will probably be found, on careful investigation, that luggage has been recently and for the first time opened and used during the voyage. Notably this latter was the case with the outbreaks on the New York and Swanton—suddenly cold weather on the New York, leading to the unpacking and use of heavier and thicker clothing, and running

*Cholera appeared on the steam-ship City of New York on the 18th day of July 1866, the first day out from Liverpool, and was observed by the writer, who was a passenger on the vessel. On the troop-ship Renown cholera broke out on the 5th of September, 1865, thirteen days after leaving Gibraltar. On the New York, in 1848 the disease appeared sixteen days, and on the Swanton, in the same year, twenty-three days after leaving port.

into a warmer belt by the Swanton, causing an overhauling of lighter wear—in each case the disease quickly appearing after this disturbance of baggage packed in the cholera-regions of Germany.

In the first instance it should be borne in mind that *no diarrhœa is harmless during a cholera-season.* The surgeon of the vessel should make special inquiry for all cases of looseness of the bowels among the passengers; and, aside from any specific modes of treatment of the individual disorder, should exercise the most careful supervision of such cases, isolating them from the other passengers, if necessary, but in any event taking such precautions as will prevent the possibility of their excreta—oral, anal, or renal—from coming in contact with others.

If the disease cannot be traced to this source—*i. e.*, a passenger suffering from flux, cholerine, choleraic diarrhœa, etc.—it will be safe to assume that it is due to some infected article; and then thorough acid disinfection, gaseous or liquid, as may be necessary, should be at once resorted to.

For the details of sanitary measures which should be enforced on shipboard in case of an outbreak of cholera no better directions can be given than those laid down by Macnamara, whose fifteen years of consecutive labor in the endemic area of cholera entitle him to speak with authority:

"If one or more persons are seized with cholera on board a vessel, they should at once be brought on deck, and laid on a thick piece of sail-cloth, so that they may be surrounded by a free current of air, with which the organic matter emanating from their persons may be diluted as far as possible. The stools should be voided into a vessel containing sulphate of iron, and they must then and there be thrown into the sea. McDougall's and Calvert's disinfecting-powders should be freely sprinkled about the spot where the patient lies, and layers of sulphate of iron should be placed between the folds of the sail-cloth upon which he is laid. Subsequently, whatever the issue of the case may be, the patient's clothes, and anything about or near him to which the matter of the dejecta might have attached itself, should be burnt; if this cannot be done, they must be thrown overboard; and the deck on which the patient lay should be well washed with some acid agent. In cases of this description I would limit the number of attendants on the sick; let one or two men be employed for the purpose, and keep them separated from the remainder of the crew. This precaution probably somewhat exceeds the requirements of the case, but still it is better to be on the safe side, and extra care in these matters renders quarantine the less necessary—an object we should keep steadily in view, placing as few impediments on commerce as possible, and leaving it at first very much in the hands of those in charge of cholera-stricken ships to take the necessary measures for preventing the communication of the disease to others, which if they refuse or neglect to do, they must then expect to suffer the inconvenience of quarantine.

"The measures I have indicated would stop the extension of cholera on board a vessel from an individual case; but very possibly others may be attacked within three days of the first case, supposing them to have imbibed the poison at the same time; or it may be that the water in the ship's tanks is contaminated, in which case the outburst of cholera may be prolonged until the oxidation of the organic matter in the water has been accomplished, and this may take some days in the cool, dark hold of a vessel at sea. It is well, therefore, if a case of cholera occurs on board a ship at sea, particularly if more than one man is struck down with the disease, to have all the water served out to the crew or passengers properly filtered and boiled before it is used for drinking purposes. If there are condensers on board, by all means let the

water from them be drunk in place of that in the tanks, at any rate for eight or ten days, or until the water shall have purified itself by oxidation."

Meanwhile both passengers and crew should be put upon a mineral-acid regimen, with the view of establishing an *acid diathesis of the system*, or as nearly so as may be. *Sulphuric-acid lemonade* should be served out regularly, under the supervision of an officer clothed with authority to see that no one shirks its use.

As a test bearing directly on the value of such a measure in arresting an outbreak of cholera, the following statement of Dr. Curtin is given *in extenso:*

* * * * * * * *

During this last visitation [of cholera, 1866,] I was resident physician in the insane department of the Philadelphia Hospital. The disease had almost entirely disappeared from the city and from all parts of the Philadelphia Almshouse and Hospital, except from the women's wards in the insane department, where it still continued in a very virulent form. Strange to say, it was almost entirely confined to three of the seven wards on the female side of the hospital. It was so persistent that the board of health paid the hospital an official visit, but were unable to account for the presence of the disease in particular wards. It is true that the women's apartments were very much crowded, there being three hundred and fifty inmates, but the wards in which it was so prevalent had proportionately fewer inmates than others which almost entirely escaped. During the whole epidemic only two cases occurred in the male wards, while among the females one in every nine was attacked. Sex would not account for this difference, for statistics at large show that male and female lunatics are equally liable to the disease.

I was induced to try sulphuric acid by my friend Dr. James F. Wilson, with gratifying results, if I may be allowed to judge. Dr. Wilson had read an article in a British newspaper, in which the writer stated that the workmen and their families connected with a large factory had been treated with sulphuric acid as a prophylactic during an epidemic of cholera. The correspondent stated in the letter that "the result was that not one man or any of their families were attacked with diarrhœa, whilst around them death took its own course." I caught as a drowning man at this straw, for everything else had been tried, and yet the disease continued its ravages. After having concluded to use the sulphuric acid, the next thing was to administer it to all the patients, many of whom were so suspicious that they refused at all times to take medicine for fear of being poisoned. Knowing that it would be impossible to conceal it in their food or usual drinks, I concluded to administer it disguised as lemonade, and announced, through the nurses, to the patients that I intended to "treat" the whole institution to lemonade every day, which announcement was well received in general, and by some of them with enthusiasm. The drink was made in this way: About twenty drops of the dilute sulphuric acid were mixed with four ounces of water and sweetened with white sugar. Some oil of lemon and a few cut lemons greatly assisted in the disguise. What followed the administration of the sulphuric acid can best be shown by the notes taken at the time. The diary was begun on August 20, 1866, before which time seventeen cases had occurred in the insane department.

August 20.—Four new cases.
August 21.—Four new cases.
August 22.—Four new cases.
August 23.—Two new cases. Board of health visited the hospital.
August 24.—Five new cases.
August 25.—One new case. Acid given for the first time in the afternoon.
August 26.—Four new cases *during the night*, within twelve hours after the first administration of the acid.
August 27.—No new cases.
August 28.—One new case—a woman who refused to take the acid.
August 29.—No new cases.
August 30.—No new cases.
August 31.—No new cases. The acid was discontinued.
September 1.—No new cases.
September 2.—Two new cases, two days after the suspension of the acid.
September 3.—No new cases. Acid resumed. The acid was continued for some time, and no more cases occurred.

It will be seen by the above diary that up to the time of administering sulphuric acid the disease was pursuing a steady course in the female department. It is true, and should be here stated, that every means had been tried to banish the disease, such as ventilating and cleansing the wards, spreading disinfectants, scattering the patients by using the large sewing-room for a sleeping-ward, attention to diet, etc., but with-

out apparent effect. The acid was first given on the 25th of August, and continued until the 31st. Four cases occurred *within twelve hours* of the time when the acid was first given. After this only one case occurred while the acid was being used, viz, on the 28th. This was a poor ignorant (?) lunatic, who, upon tasting it, spit it out, and surprised me very much by saying, with great vehemence, "Docther, yon call this limonade, but ye can't desave me; it's nothing but ile of vitriol!" On the 31st of August it will be seen that the "lemonade" was stopped, on account of the exhaustion of the supply of white sugar in the drug-store, as without this sugar it would have been impossible to prepare the acid in such a manner as to insure the patients' taking it. On the 2d of September, *two days after the suspension of the use of the acid, two new cases occurred*, both of which proved fatal. The prophylactic was then resumed, and *no new cases* occurred in the insane department; but cases continued to arrive from the city until the 1st of November. The use of the acid was continued uninterruptedly for several weeks. My friend Dr. J. F. Wilson gave it to the patients in the surgical wards during the epidemic, and he informs me that the *cholera visited every department of the almshouse and hospital except the surgical wards.*

The question naturally arises, was it the sulphuric acid that arrested the march of the disease? I think it was, for the following reasons:

1. *The prompt disappearance of the disease within twelve hours of the time when the acid was first administered*, the only case arising during its use being that of a patient who refused to receive it. The acid was stopped on the 31st of August, and two days after this two cases occurred. The acid was then immediately resumed, and not a single case occurred afterwards.

2. *The fatality attending the disease.* When an epidemic declines from natural causes, it generally becomes less fatal. Of the four patients attacked on the 26th of August, three died, of whom one was a young robust epileptic, who lived but five hours after the first symptom; another was a strong lunatic, who succumbed in nine hours. The two cases which occurred on the 2d of September, after the suspension of the use of acid, both died; thus showing that the type was none the less fatal.

How did the sulphuric acid act? According to Dr. G. B. Wood, it has the following effects upon the system, viz, *tonic, astringent, refrigerant*, and *diuretic*. It has been largely used in the treatment of the first and second stages of cholera. Dr. Macnamara, in his work on Asiatic cholera, recommends the use of dilute sulphuric acid, in doses of fifteen minims, in the second stage. The celebrated "Austrian specific" was composed of sulphuric and nitric acid. Nitric acid had been used in India in the treatment of cholera with considerable success. It was tried in England and found to be of no avail, when further investigation proved that the nitric acid of India contained a considerable amount of sulphuric acid. The latter was an accidental product of the manufacture of the nitric acid of India. Hence the use of the combination of these two acids in the treatment of cholera. Elixir Halleri, or liquor acidi Halleri, has been much used in India, and is ordered as part of the medical stores of the British army there. It consists of sulphuric acid and alcohol. Drs. Buxton, Sansom, and Fuller, of England, used sulphuric acid with success in the first stages of cholera, especially in the choleraic diarrhœa.

From the above statements it would appear that sulphuric acid itself has some effect upon the disease; and now we will proceed to discuss its influence as a prophylactic.

It had been noticed that workers in copper were remarkably exempt from cholera, and upon investigation it was found that the air surrounding them was considerably charged with sulphurous acid, which gave rise to the supposition that this was the active preventive agent. This led to the use of sulphurous acid in cholera districts and hospitals, but with what results I have not been able to learn.

Dr. Burg, in reviewing the statistics of deaths from cholera, found that "out of thirty-two thousand artisans in copper, brass, and bronze, employed in Paris and other cities, during the last outbreak of cholera, only sixteen deaths resulted from that disease. Another interesting fact bearing on this question is that the city of Rio Tinto, surrounded as it is by copper-mines, has never been visited by this epidemic."

The sulphurous acid found near these mines proceeds from the smelting-works, in which the sulphurets of copper are generally used; other sulphurets often being associated with the copper-ore, also yield their sulphur to the atmosphere. Still further, it has been noticed that persons living near gas-works are less liable to be attacked than those living remote. Here also we find the atmosphere more or less impregnated with sulphurous gases. Almost all gas-coal contains sulphur, and the process of purification in part consists in the removal of the sulphureted hydrogen. Hence we discover a source of sulphurous gases, which gases may be the protecting agents. It may be, judging from these circumstances, that the cholera-germ is destroyed; for in the case of Rio Tinto, which is surrounded by sulphurous acid, it would seem to form an impenetrable barrier to the cholera. It is a well-known fact that sulphurous acid in the form of a sulphite will arrest fermentation; and it has been suggested that it acts in the same manner upon the zymotic cause of cholera.

But again, we find that sulphuric acid seems to have an influence over the disease.

which would lead us to ask whether the *sulphur may not be the destroying agent of the cholera-germ*, acting as a specific in the same manner that it does in the case of the itch-insect. If this be true, the disease may be easily eradicated from a ship or a house or any infected locality by fumigating with sulphurous acid, simply by burning sulphur; also disinfecting privy-wells and other objectionable places by means of sulphate of iron, and at the same time giving liquid sulphurous acid, sulphuric acid, and the sulphites, by the mouth, to those exposed.

It has already been stated that sulphuric acid may act beneficially independent of any specific action upon the cholera-germ.

I have said that it is a tonic, astringent, refrigerant, and diuretic. The vital energies are often very much reduced, digestion is poor, and the intestines and the system at large are in a relaxed condition, the result of the high temperature of summer. Here we find the condition favorable to an attack of cholera. The tonic, astringent, and refrigerant effects of the sulphuric acid would all be eminently indicated by these conditions, and its administration might tide the patient over the period of danger. It may also act beneficially in another way. We all know the depressing effect of fear, which undoubtedly predisposes to cholera. A prophylactic given in such cases would allay the fear and thus ward off the disease. But this latter condition was not a characteristic of the poor lunatics in the Philadelphia Hospital; for many of them knew no fear except that produced by their hallucinations. It is pleasant to have a preventive at hand; but in none of the text-books have I been able to find anything recommended as such in cholera. Having one, we might be able to quiet the fears of the nervous and keep them from the often injurious nostrums of those who prey upon this class.

One thing should be remembered. It is this: that sulphuric acid, when administered for a long time continuously or in too large doses, may give rise to symtoms of intestinal irritation. However, although the acid was given to the lunatics uninterruptedly for several weeks, no ill effects were observed. It should be given only to those who are greatly exposed during an epidemic of cholera; otherwise the above unpleasant effects may be produced.

It may be alleged that in the foregoing pages too great stress has been laid upon the *acid prophylaxis of cholera*, to the exclusion of all others. But the cumulative evidence of the experience of the last sixty years warrants the ground here taken. Beginning with the year 1814, the cholera-literature down to the present time abounds in proofs, clinical, physiological, pathological, and meteorological, of the efficacy of sulphuric acid, and there can be little doubt, despite the *dicta* of the last International Sanitary Conference,* that *we possess in the mineral acids a certain means of prophylaxis against cholera.*

NOTE.—The lessons of the epidemic of 1873 point strongly to the value of sulphuric acid even as a therapeutic agent against the disease. According to Dr. McClellan, the mortality among cholera-patients treated with acids was only 8 per cent., while the lowest mortality rate where other remedies were used was 23 per cent., and the highest 59 per cent.

It is safe to say that malignant cholera can be excluded from our shores with reasonable certainty through an intelligent sanitary supervision of the mercantile marine; in which supervision, while the General Government on the one hand, in exercising its delegated powers for the protection and promotion of the general welfare, shall simply acquire and furnish the necessary information; on the other, the ports themselves, thus forewarned and advised, shall be left to enforce the necessary precautionary and preventive measures in accordance with their own local conditions and requirements. For nothing is more clearly proved by the history of cholera than that epidemics of this dreaded disease can be controlled by *vigorous hygienic measures. The true remedy against cholera is preventive medicine.*

* Upon the question, are any means or processes of disinfection known by which the generative contagious principle of cholera can certainly be destroyed or deprived of its intensity, the vote stood—No, 12; abstaining, 7.—*Proceedings International Sanitary Conference*, 1874.

APPENDIX.

Vide supra, page 7.

With the view of making the collection of facts concerning the epidemic as full as possible, the Supervising Surgeon, in addition to personally visiting many of the points at which the epidemic prevailed, addressed the following circular-letter of inquiry to some two hundred and sixty physicians in the infected districts:

SUPERVISING SURGEON'S OFFICE,
UNITED STATES MARINE-HOSPITAL SERVICE,
Treasury Department, August, 1874.

DOCTOR: The Supervising Surgeon of the United States Marine-Hospital Service having been designated by joint resolution of the Forty-third Congress, approved March 25, 1874, in connection with a medical officer of the Army, "to confer with the health authorities and resident physicians of such towns, [as were visited by the cholera epidemic of 1873,] and to collect, so far as possible, all facts of importance with regard to such epidemic," for the purpose of making a report of the same to the President of the United States, to be submitted to Congress, I have the honor respectfully to solicit a detail of the facts which came under your observation concerning the propagation and spread of the disease during that year.

The following memorandum embraces substantially the points upon which information is desired:

1. Name, sex, and age of patient.
2. Residence of patient—town, street, and number.
3. Day and hour of attack.
4. Premonitory symptoms, their nature and duration.
5. Progress of the disease:
   - *a*. Day and hour of beginning of rice-water discharges.
   - *b*. Day and hour of beginning of cramps.
   - *c*. Day and hour of beginning of collapse.
   - *d*. Period and extent of suspension of renal function.
   - *e*. Nature of treatment and result.
   - *f*. Day and hour when convalescence began.
   - *g*. Day and hour when death occurred.
   - *h*. Post-mortem appearances in detail.
6. Story of house occupied, and height of floor from ground.
7. Sanitary condition of house and inclosure:
   - *i*. As to cleanliness of rooms—clean, neglected, filthy.
   - *k*. As to ventilation and light—good, defective, bad.
   - *l*. As to drainage of house—good, obstructed, absent.
   - *m*. As to drainage of ground—good, obstructed, absent.
   - *n*. As to location and condition of privies or water-closets, connection with street-sewer, mode of flushing, of ventilation of soil-pipe, disinfection, etc.
   - *o*. As to surface-water, garbage, or filth about the premises.
8. Source and quality of water-supply. If from a well or cistern, proximity of privy, sewer, or drain thereto, and chance of pollution.
9. General topography of localities in a given town where cholera prevailed.
10. Character of soil.
11. Character of drainage.
12. Occupation and habits of patient, and whether a resident of house where attacked for two weeks or over.
13. The facts in any case where the patient was attacked within two weeks after removing from an infected district into one previously free from the disease, specifying the respective districts and character of exposure.
14. The sequence of cases where more than one was attended, with their relations to each other, and to the cases of other physicians, with names of such physicians.
15. The means and agents used by the physician, by the family, and by the municipal authorities to prevent the spread of the disease, and the result of such preventive measures.

16. Public measures taken to prevent the introduction of the disease into your community, with the result.

17. Temperature, rain-fall, and prevailing winds for as long a period as practicable prior to appearance of cholera, and also during its continuance.

18. Dates of first and last cases of cholera in the locality in 1873—total number of cases and mortality.

19. Connection, if any, between first cases in 1873 and the localities of the disease in the immediately preceding epidemic.

20. Names of cities, towns, and villages known to you where cholera occurred during 1873, with any facts relating to the introduction of the disease to such, and the address of some respectable practitioner residing in each of the places named.

Contributions to this investigation, by answers to the foregoing, or to so much thereof as is practicable, will be fully acknowledged in the official report, the value of which, it is hardly necessary to say, will largely depend upon the co-operation of the profession thus sought.

Copies of any reports or papers which you may have already prepared on the subject, or of those prepared by others and annotated or emended by yourself, will also be of service, and may be forwarded, to be returned if desired.

I am, doctor, very respectfully,

JNO. M. WOODWORTH,
Supervising Surgeon.

In response to the foregoing and to subsequent letters of special inquiry, replies were received from the following gentlemen:

Dr. O. L. Crampton, Mobile, Ala.
Dr. J. J. Dement, Huntsville, Ala.
Dr. C. H. Franklin, Union Springs, Ala.
Dr. John C. Furniss, Selma, Ala.
Dr. James C. Harris, Wetumpka, Ala.
Dr. M. H. Jordan, Birmingham, Ala.
Dr. T. C. Osborn, Greensborough, Ala.
Dr. J. T. Searcy, Tuscaloosa, Ala.
Dr. R. D. Webb, Livingston, Ala.
Dr. William H. Barry, Monticello, Ark.
Dr. J. A. Dibrell, jr., Little Rock, Ark.
Dr. Wilson C. Carver, Bluffs, Ill.
Dr. E. B. Cannon, Tuscola, Ill.
Dr. William G. Cochran, Farmer City, Ill.
Dr. J. N. Danforth, Chicago, Ill.
Dr. Walter Hay, Chicago, Ill.
Dr. A. W. Heise, Joliet, Ill.
Dr. Herbert Judd, Galesburgh, Ill.
Dr. Thomas Lawrence, Goose Island, Ill.
Dr. W. R. Milam, Clear Creek, Ill.
Dr. Lloyd T. Miller, Caseyville, Ill.
Dr. Benjamin C. Miller, Chicago, Ill.
Dr. J. W. Mott, Villa Ridge, Ill.
Dr. John N. Niglas, Peoria, Ill.
Dr. David Prince, Jacksonville, Ill.
Dr. G. T. Ragan, Peoria, Ill.
Dr. James Roberts, Carbondale, Ill.
Dr. Horace Wardner, Cairo, Ill.
Dr. William Walker, Little York, Ill.
Dr. John Wright, Clinton, Ill.
Dr. J. C. Beaver, Vincennes, Ind.
Dr. M. S. Blunt, Mount Vernon, Ind.
Dr. A. F. Cummins, Bloomington, Ind.
Dr. R. O. Crandall, La Porte, Ind.
Dr. T. Henry Davis, Richmond, Ind.
Dr. W. Scott Wolfe, Elizabeth, Ind.

Dr. A. S. Maxwell, Davenport, Iowa.
Dr. S. N. Pierce, Cedar Falls, Iowa.
Dr. William Berry, Lancaster, Ky.
Dr. J. R. Best, Millersburgh, Ky.
Dr. S. B. Caldwell, Paducah, Ky.
Dr. E. S. Gaillard, Louisville, Ky.
Dr. Hugh McNary, Princeton, Ky.
Dr. D. A. Maxwell, Paducah, Ky.
Dr. S. L. Manly, Louisville, Ky.
Dr. Thomas Rivers, McCracken County, Ky.
Dr. C. G. Royster, Woodville, Ky.
Dr. R. Saunders, Paducah, Ky.
Dr. J. W. Singleton, McCracken County, Ky.
Dr. J. W. Thompson, Paducah, Ky.
Dr. F. C. Wilson, Louisville Ky.
Dr. S. M. Bemis, New Orleans, La.
Dr. C. B. White, New Orleans, La.
Dr. F. W. Dancy, Holly Springs, Miss.
Dr. John R. Hicks, Vicksburgh, Miss.
Dr. J. B. Alexander, Lexington, Mo.
Dr. W. L. Barret, Saint Louis, Mo.
Dr. W. S. Edgar, Saint Louis, Mo.
Dr. Jas. G. Hickman, Hannibal, Mo.
Dr. J. E. Tefft, Springfield, Mo.
Dr. A. Bowen, Nebraska City, Nebr.
Dr. J. P. Bing, Portsmouth, Ohio.
Dr. William Clendenin, Cincinnati, Ohio.
Dr. George A. Crew, Cadiz Junction, Ohio.
Dr. Thomas L. Neal, Dayton, Ohio.
Dr. E. S. Nichols, Xenia, Ohio.
Dr. William H. Herd, Philadelphia, Pa.
Dr. W. Snivley, Pittsburgh, Pa.
Dr. Strickland Albright, Ducktown, Tenn.
Dr. J. S. Barnes, Chattanooga, Tenn.
Dr. F. K. Bailey, Knoxville, Tenn.
Dr. John Blackinship, Maryville, Tenn.
Dr. Paul F. Eve, Nashville, Tenn.
Dr. B. F. Gardner, Chattanooga, Tenn.
Dr. H. A. Schell, Gallatin, Tenn.
Dr. E. M. Wight, Chattanooga, Tenn.
Dr. Alexander W. Acheson, Denison, Tex.
Dr. James Johnston, Denison, Tex.
Dr. J. S. Cabell, Richmond, Va.
Dr. R. P. Davis, Parkersburgh, W. Va.
Dr. E. L. Jepson, Wheeling, W. Va.
Dr. Robert D. Murray, Surgeon U. S. Marine-hospital Service.
Dr. George Purviance, Surgeon U. S. Marine-hospital Service.
Dr. Orsamus Smith, Surgeon U. S. Marine-hospital Service.

These replies embraced facts concerning the epidemic in one hundred and thirty localities, as follows:

ALABAMA.

Tuscaloosa.
Union Springs.

ARKANSAS.

Plantation near Little Rock.

INDIANA.

Aurora.
Evansville.
Indianapolis.
Indian Creek, (near Princeton,)

Mount Vernon.
North Vernon.
Terre Haute.
Vincennes.
Wabash.

ILLINOIS.

Bluffs.
Carmi.
Cairo.
Caseyville.
Chicago.
Clear Creek.
Galesburgh.
Goose Island.
Jacksonville.
Little York.
Monmouth.
Okaw.
Villa Ridge.

IOWA.

Davenport.

KENTUCKY.

Ashland.
Bowling Green.
Beaver Creek Ridge, (near.)
Between Woodburn and Franklin.
Ballard County, (near Cairo, Ill.)
Burkesville.
Cromwell.
Columbia.
Cadiz.
Caldwell County.
Claysville.
Elizabethtown.
Grayson.
Henderson.
Henry County, (near Hardin's Bottom.)
Hopkinsville.
Hartford.
Louisville.
Lancaster.
La Grange.
La Rue County.
Logan County, (near Shocho.)
Maysville.
Mason County.
Madison Mills.
Millersburgh.
North Fork Ridge.
Newport.
Oddville, (near.)
Owensborough.
Paducah.
Paris.
Princeton.
Simpson County.
Shelby County.
Stanford.
Taylor County.
Woodburn.
Woodville.
Worthville.
West Point.

LOUISIANA.

New Orleans.

MISSOURI.

Fayette.
Hannibal.
Louisiana.
Poplar Bluffs.
Perryville.
Saint Louis.

OHIO.

Carthage.
Cincinnati.
Cleveland.
Columbus.
Dayton.
Portsmouth.

PENNSYLVANIA.

Philadelphia.
Pittsburgh.
Temperanceville.

TENNESSEE.

Blue Springs, (near Midway.)
Belleview.
Chattanooga.
Craggy Hope.
Carter's Station.
Campbell County.
Clarksville.
Ducktown.
Decatur.
Eaton's and Dry Creeks.
Erin.
Edgefield.
Farmington.
Fountain Head.
Gallatin.
Goodletsville.
Greeneville.
Hartsville.
Jonesborough.
Knoxville.
Lavergne.
Limestone Station.

Lebanon.
Loudon, (near.)
Memphis.
Morristown.
Murfreesborough and County.
Maryville.
Mungle's Creek.
New Haven.
Nashville.
Nolensville.
Ooltewah.
Pegram Station.
Reynold's Station.
Russellville.
Rogersville.
Shelbyville.
Sulphur Spring.
Swan Spring.
Union City.
Unionville.
White Bluffs.
Whitesburgh.
Yates Spring.

TEXAS.

Denison.

VIRGINIA.

Richmond.

Finding that Dr. McClellan, the medical officer of the Army detailed by the Secretary of War, had also covered, with few exceptions, the points above named, and concurring with him in the opinion that one narrative embracing all the points would be more valuable than two independent and fragmentary ones, the mass of material thus obtained was placed at his disposal.

The Supervising Surgeon desires to express his individual obligation to Dr. Ely McClellan, Dr. Elisha Harris, Dr. F. W. Reilly, Dr. J. S. Jewell, and Dr. P. H. Bailhache, as well as to those gentlemen whose details of their own personal observation and experience during the epidemic, form such an important contribution to the literature of cholera in the United States.

INDEX.

Page

Acid as a prophylactic against cholera....8, 9, 15, 17–19
—— as a therapeutic agent, *note*.... 19
—— suspected goods to be treated with.... 15
Appendix.... 21
Army, medical officer of....7, 21, 25
Bacteria.... 8
Carthage, Ohio, introduction of cholera into.... 10
Cholera, at Jamaica in 1872.... 11
—— brought to Halifax and quarantine, New York, in 1871.... 11
—— —— —— the United States in 1872.... 11
——, clew to its origin on shipboard.... 15
——, consular officers to furnish information.... 13
——, cumulative evidence in favor of sulphuric acid as a prophylactic.... 19
——, exclusion of, from the United States.... 12–19
——, epidemic of, 1849, 1854, and 1866, source of.... 10
——, —— —— 1873, source of.... 10, 11
——, fatal case, cabin-passenger on Ville du Havre.... 9
——, how introduced into the United States.... 10
——, joint resolution of Congress relative to epidemic of 1873.... 7
——, literature abounds in proofs of efficacy of sulphuric acid.... 19
——, localities where prevailed.... 23
—— may break out on vessels at any time.... 15
——, manner of obtaining information from infected ports.... 13
——, mode of dealing with, on shipboard.... 14–16
—— outbreak at sea, how treated.... 15, 16
—— on board ships England and Virginia.... 10
—— —— —— —— Franklyn.... 11
—— —— —— —— Tonawanda and Tuscarora.... 10
—— —— —— —— Swanton and New York.... 10, 15
——, prevention of....8, 9, 12–19
—— statistics, see Appendix.... 21
——, sulphuric acid as a prophylactic....8, 9, 17–19
——, —— —— —— —— therapeutic agent, *note*.... 19
——, threatened communities notified.... 13
——, true remedy against.... 19
——, workers in copper-ores exempt from.... 18
Cholera-poison, character of, and where endemic.... 8
——, conditions necessary for its action.... 8
——, —— favorable for its growth.... 8
——, destruction of, naturally.... 8
——, —— ——, artificially.... 8
—— found only in ejections where not endemic.... 8
—— may be preserved for an indefinite period.... 8
—— —— —— carried any distance.... 8
——, period of morbific activity.... 8
——, —— —— —— —— —— ——, how characterized.... 8
Cholera-season, no diarrhœa harmless.... 16
Congress, joint resolution of.... 7
Consular officers, to furnish information.... 13
Contributors of information relative to epidemic of 1873.... 22
Crow River, Minn., introduction of cholera into.... 10
Curtin, Dr., test of sulphuric acid as a prophylactic.... 17–19
Emigrants, personal effects of.... 9
General Government, collect and publish information.... 13
Infected ports, arrival of ships from.... 10, 11
—— ——, manner of obtaining information from.... 13
Infected ships, treatment of, on arrival at United States port.... 9, 14
—— ——, sanitary measures to be enforced.... 14, 1

	Page.
International sanitary action	13
Inspection of steerage-passengers	9
—— —— infected ships	9
—— no positive safeguard	10
Law of the United States in relation to immigrants	12
Macnamara, treatment of cholera-patients on shipboard	16
McClellan, Dr. Ely, U. S. A	7, 9, 12, 19, 25
Medical officers to collate and digest information	13
Merchandise not a medium of conveying cholera-poison	9
Mode of dealing with cholera on shipboard	9
National Government to acquire necessary information	13
New Orleans, introduction of cholera into	10
New York City, introduction of cholera into	10, 11
Ocean-travel, sanitary supervision of	9
Passengers, personal effects of	9
Prevention of cholera	7, 12–19
Propositions—cholera-poison: I, character of, and where endemic	8
II, found only in ejections where not endemic	8
III, conditions necessary for its action	8
IV, conditions favorable for its growth	8
V, period of its morbific activity, how characterized	8
VI, may be preserved for an indefinite period	8
VII, may be carried any distance	8
VIII, destruction of, naturally	8
IX, destruction of, artificially	8
Deductions from foregoing	9
Quarantine, question of, etc	9, 12, 14, 15
——, what is lacking in present system	12, 13
——, as administered at New York	14
Sailors as propagators of disease	9
Sulphuric acid as a prophylactic against cholera	8, 9, 15, 17–19
—— ——, action upon the system	18, 19
Special acknowledgments of the Supervising Surgeon	25
Statistics in relation to epidemic of 1873	21, 25
——, contributors to	22
The President empowered by law to obtain information conducive to the public interests	13
Therapeutic agent against cholera	19
Treatment of an infected ship on arrival at a U. S. port	9, 14
Yankton, Dak., introduction of cholera into	10

WAR DEPARTMENT, SURGEON-GENERAL'S OFFICE.

CHOLERA EPIDEMIC OF 1873

IN THE

UNITED STATES.

REPORTS PREPARED

UNDER

THE DIRECTION OF THE SURGEON-GENERAL OF THE ARMY.

A.—HISTORY OF THE CHOLERA EPIDEMIC OF 1873 IN THE UNITED STATES.
By ELY McCLELLAN, M. D., Assistant Surgeon U. S. A.

B.—HISTORY OF THE TRAVELS OF ASIATIC CHOLERA.
By JOHN C. PETERS, M. D., of New York City, and ELY McCLELLAN, M. D., Assistant Surgeon U. S. A.

C.—BIBLIOGRAPHY OF CHOLERA.
By JOHN S. BILLINGS, M. D., Assistant Surgeon U. S. A.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1875.

H. Ex. 95——III

ERRATA.

On page 36, for miscroscopic read microscopic.
On page 59, for Libert read Lebert.
On page 328, for present read prevent.
On page 409, for borborygm read borborygmi.

Illinois contributors, add names of—
Dr. R. F. Cuningham, Lebanon, Ill.
Dr. F. W. Lytle, Lebanon, Ill.
Dr. L. T. Miller, Caseyville, Ill.
Dr. A. B. Tadlock, Knoxville, Tenn.

WAR DEPARTMENT,
Washington City, January 11, 1875.

To the PRESIDENT:

SIR: As required by the joint resolution of Congress, approved March 25, 1874, I have the honor to inclose letter of the Surgeon-General of the Army, and report, therewith transmitted, of Assistant Surgeon Ely McClellan, upon the causes of epidemic cholera.

Very respectfully,
Your obedient servant,

WM. W. BELKNAP,
Secretary of War.

WAR DEPARTMENT,
SURGEON-GENERAL'S OFFICE,
Washington, D. C., January 2, 1875.

To the Hon. SECRETARY OF WAR:

SIR: I have the honor to transmit herewith a detailed report of facts collected by Assistant Surgeon Ely McClellan, United States Army, the medical officer detailed to inquire into and report upon the causes of epidemic cholera, under a joint resolution of Congress, approved March 25, 1874, together with his letter forwarding the report.

This comprises all the information obtained on the subject, and is hereby respectfully reported for publication, in accordance with the final clause of said resolution.

Very respectfully,
Your obedient servant,

J. K. BARNES,
Surgeon-General.

WAR DEPARTMENT,
SURGEON-GENERAL'S OFFICE,
Washington, D. C., January 1, 1875.

To the SURGEON-GENERAL OF THE ARMY:

SIR: I have the honor to present the report made in accordance with the joint resolution of Congress, approved March 25, 1874, authorizing the Secretary of War to detail a medical officer of the Army to inquire into and report upon the causes of epidemic cholera. A copy of the joint resolution, with copies of the orders under which I have acted, and a detailed account of the work performed, is herewith respectfully submitted.

I.

General Orders. } WAR DEPARTMENT,
No. 29. } ADJUTANT-GENERAL'S OFFICE.
Washington, April 8, 1874.

The following joint resolution of Congress is published for the information and government of all concerned:

JOINT RESOLUTION authorizing the Secretary of War to detail a medical officer of the Army to inquire into and report upon the causes of epidemic cholera.

Whereas epidemic cholera prevailed during the year eighteen hundred and seventy-three in various parts of the United States, especially in the valley of the Mississippi, causing a deplorable mortality; and whereas it is highly important that, whenever such epidemics occur, the facts concerning the spread of the disease and its mode of propagation should be ascertained as fully as possible, with a view to the prevention or limitation of future outbreaks; therefore,

Resolved by the Senate and House of Representatives of the United States of America in Congress assembled, That the Secretary of War be, and he is hereby, authorized and directed to detail one medical officer of the Army, who shall, during the present year, under the direction of the Surgeon-General of the Army, in connection with the supervising surgeon of marine hospitals, acting under the direction of the Secretary of the Treasury, visit the towns at which cholera prevailed during eighteen hundred and seventy-three, or such of them as, in the opinion of the Surgeon-General and Secretary of the Treasury, may be necessary, confer with the health authorities and resident physicians of such towns, and collect, so far as possible, all facts of importance with regard to such epidemic, and shall make a detailed report of the information collected, on or before the first day of January, eighteen hundred and seventy-five, to the President, to be submitted to Congress. And the Surgeon-General is hereby authorized and directed to report to the Secretary of War, for publication, such information on the subject as he may have or shall obtain.

Approved March 25, 1874.

By order of the Secretary of War:

E. D. TOWNSEND,
Adjutant-General.

II.

Special Orders. } WAR DEPARTMENT,
No. 85. } ADJUTANT-GENERAL'S OFFICE,
Extract. *Washington, April* 18, 1874.

18. To carry out the provisions of the joint resolution of Congress, approved March 25, 1874, Assistant Surgeon Ely McClellan is, on the recommendation of the Surgeon-General, hereby detailed to inquire into and report upon the causes of epidemic cholera. He is relieved from duty in the Department of the South, and will report in person to the Surgeon-General for instructions.

By order of the Secretary of War.

E. D. TOWNSEND,
Adjutant-General.

Official:
L. H. PELOUZE, *Assistant Adjutant-General.*

III.

WAR DEPARTMENT,
SURGEON-GENERAL'S OFFICE,
Washington, D. C., May 7, 1874.

Assistant Surgeon Ely McClellan having been ordered by Special Orders No. 85, Adjutant-General's Office, April 18, 1874, to report in person to the Surgeon-General for instructions to carry out the provisions of the joint resolution of Congress, approved March 25, 1874, and having duly reported in person to the Surgeon-General, in accordance with said order, is hereby directed to proceed to Louisville, Kentucky, from whence he will visit those towns in the States of Louisiana, Mississippi, Alabama, Arkansas, Tennessee, Kentucky, Missouri, Illinois, Indiana, Ohio, West Virginia, Pennsylvania, Iowa, and Minnesota, and in the Territories of Dakota and Utah, at which cholera prevailed during the year 1873, for the purpose of ascertaining as fully as possible the facts concerning the introduction and spread of the disease. He will confer with the health authorities and resident physicians of said towns, collect so far as possible all facts of importance with regard to the epidemic, and submit to this Office, as soon as practicable, a detailed report of the information collected.

J. K. BARNES,
Surgeon-General U. S. A.

Official:
C. H. CRANE,
Assistant Surgeon-General U. S. A.

On assuming charge of this work, in obedience to the foregoing orders, it was found that the area of infection extended over the following States and Territories:

States.	Number of infected localities.	States and Territories.	Number of infected localities.
Louisiana	12	Pennsylvania	2
Texas	3	Ohio	20
Mississippi	11	Indiana	15
Alabama	7	Illinois	46
Georgia	4	Missouri	31
Arkansas	6	Iowa	4
Tennessee	43	Minnesota	2
Kentucky	52	Dakota	3
West Virginia	2	Utah	1

Making a grand total of two hundred and sixty-four infected localities from which information should be obtained. The total number of days allotted to the work was two hundred and thirty-eight. It was therefore a matter of physical impossibility to accomplish the task by personal inspection alone.

At many points, as the cities of New Orleans, Memphis, Nashville, Cincinnati, Chicago, and Saint Louis, the work demanded patient investigation and careful study, which could not be accomplished in a hurried visit; it therefore became necessary to issue the following circulars, and by dint of unceasing correspondence, through their use, much valuable information has been collected:

[Circular No. I.]

LEBANON, MARION COUNTY, KY.,
——— ——, 1874.

Doctor ———, ———:

DEAR SIR: Having been detailed to carry out the provisions of a joint resolution of Congress, directing the Secretary of War to detail a medical officer to investigate and report upon the epidemic of cholera of 1873, under the direction of the Surgeon-General of the Army, I am most anxious to obtain a complete record of all cases of the disease which occurred in ——— during the last year.

The task assigned me is a laborious one, and I can only hope for success in placing before the profession a history of any scientific value by securing the active co-operation of my professional brethren.

With this you will please find a set of blank forms, upon which I would respectfully ask that you will record all cholera cases which came under your care during the last year, those who recovered as well as those who died; and further, that you will embody in a note any valuable information you may have obtained of the epidemic, such as the history of the early cases, the history of groups of cases occurring in one house or in public institutions, and any facts which you may possess of the mode by which the disease in question was introduced into your locality.

Allow me to urge, in view of the scientific importance of this investigation, that you will extend to me your prompt and hearty co-operation, and that you will address to me your answers at Lebanon, Marion County, Kentucky.

Very respectfully,
Your obedient servant,

ELY McCLELLAN,
Assistant Surgeon, U. S. Army.

[Circular No. II.]

LEBANON, MARION COUNTY, KY.,
November 1, 1874.

Doctor ———, ———:

DEAR SIR: I have the honor to ask your attention to my letter of ———, and to urge upon you the importance of favoring me with an answer without further delay. If you are unable to send me full lists of cases, I would earnestly ask that you will

send me a letter descriptive of the epidemic as you witnessed it, giving me, if possible, an account of the introduction of the disease into your community, how, where, and from whom the early cases were infected, and the manifestations of the disease as regards its spread, its intensity, and its decline. Any local influences which may have favored the spread of the disease, the source and character of the water-supply, should be noted.

To do this will cost you but little time and labor, and will enable me to complete the chain of evidence, while your neglect will cause a gap which cannot be filled. I am in possession of a large amount of evidence. The profession of the South and West have, in the great majority of instances, responded promptly to my call. I would earnestly beg that you will aid me in presenting to the next Congress a report from the medical men of the Mississippi Valley, complete in its scientific information. Any contribution with which you may favor me will be fully acknowledged in my report.

I am, dear sir, very respectfully,

Your obedient servant,

ELY McCLELLAN,
Assistant Surgeon, United States Army.

[Circular No. III.]

LEBANON, KY., ———, 187 .

Doctor ———, ———:

I have the honor to ask your attention to my previous letter, asking information as to the cholera epidemic of 1873. The facts as to the demonstration of the disease at ——— are as yet incomplete, and, unless furnished at once, will of necessity be omitted from the narrative of the epidemic. I would earnestly ask that you will send me, with as little delay as possible, a note of all facts in your possession, addressed to me, in care of the Surgeon-General United States Army, Washington, D. C.

Very respectfully,

Your obedient servant,

ELY McCLELLAN,
Assistant Surgeon, United States Army.

From Dr. John M. Woodworth, Supervising Surgeon of the Marine-Hospital Service, who was associated with this work, I have received valuable contributions, which will be found duly accredited in the narrative of the epidemic.

At my request, Assistant Surgeon John S. Billings, United States Army, has prepared a most exhaustive bibliography of cholera, which will be found to be one of the most valuable contributions to the literature of the century.

To Assistant Surgeon J. J. Woodward, United States Army, Dr. John C. Peters and Dr. Elisha Harris, of New York City, I am especially indebted for aid and counsel.

From the officers of the Army, stationed at or near points of infection, I have received valuable assistance.

From Hospital Stewards Charles E. Lord, Richard Keogh, and F. M. Guyon I have received clerical aid, which was rendered in addition to their official duties.

At all points of the area of infection, I was most courteously received, and every facility was afforded the investigation. To the medical gentlemen or the South and West my thanks are due.

During the prevalence of the epidemic of 1873, Dr. A. B. Judson, of New York City, assumed the task of daily compiling the cholera announcements made by the press throughout the United States. The vast manuscript thus formed was placed at my service, and to the points thus obtained the success of the work is in a great measure due.

I am, sir, very respectfully,

Your obedient servant,

ELY McCLELLAN,
Assistant Surgeon, United States Army.

TABLE OF CONTENTS.

CHAPTER I.—Clinical history of the epidemic of 1873.
II.—Etiology of the epidemic of 1873.
III.—On the prevention of cholera.
IV.—On the origin of the epidemic cholera that reached the United States in 1873.
V.—Narrative of the epidemic in Louisiana.
VI.—Narrative of the epidemic in Mississippi.
VII.—Narrative of the epidemic in Arkansas.
VIII.—Narrative of the epidemic in Tennessee.
IX.—Narrative of the epidemic in Illinois.
X.—Narrative of the epidemic in Missouri.
XI.—Narrative of the epidemic in Kentucky.
XII.—Narrative of the epidemic in Ohio.
XIII.—Narrative of the epidemic in Indiana.
XIV.—Narrative of the epidemic in Alabama.
XV.—Narrative of the epidemic in West Virginia.
XVI.—Narrative of the epidemic in Georgia.
XVII.—Narrative of the epidemic in Minnesota.
XVIII.—Narrative of the epidemic in Pennsylvania.
XIX.—Narrative of the epidemic in Texas.
XX.—Narrative of the epidemic in Iowa.
XXI.—Narrative of the epidemic in Dakota.
XXII.—Narrative of the cholera cases in New York Harbor.
XXIII.—Epidemic as it affected the United States Army.

ACKNOWLEDGMENTS.

In carrying this work through the press, our thanks are due for much courteous consideration to the Hon. A. M. Clapp, Congressional Printer; to Capt. H. T. Brian, Foreman of Printing; and to the compositors and proof-readers of the establishment.

From Acting Assistant Surgeon T. W. Wise, United States Army, of the Library of the Surgeon-General's Office, we have received valuable aid.

To Messrs. W. S. McPherson, T. L. Miller, L. M. Penfield, and F. J. Foster, clerks in the Office of the Surgeon-General of the Army, we are indebted for clerical aid.

CHAPTER I.

CLINICAL HISTORY OF THE EPIDEMIC OF 1873.

During the year 1873, cholera prevailed throughout the entire valley of the Mississippi. The early cases of the disease occurred at the city of New Orleans. From that city, the disease was carried northward, when it became epidemic at all points attacked, although it assumed a pandemic form at none. The occurrence of this epidemic gave rise to a most extended discussion in medical circles, during which there was a greater diversity of opinion expressed than had been occasioned by any disease which had appeared upon the American continent during the past century.

The vast majority of the medical men of the United States who were engaged in combating the disease during the progress of the epidemic, both in hospitals and in private practice, are unanimous in pronouncing it to have been Asiatic cholera of foreign origin; making use, in their reports of cases, of the synonym which was individually most acceptable, namely, cholera, cholera epidemica, cholera spasmodica, cholera asphyxia, serous cholera, malignant cholera, &c.

A second class, composed of a most respectable number of gentlemen, both numerically and intellectually, recognized the disease to have been cholera in a fatal form, but announced it as American cholera, not epidemic but endemic, having its origin in certain local and malarial influences.

A third class reject entirely the cholera hypothesis, and pronounce the disease to have been "pernicious bilious fever of an algid type," "congestive malarial fever," etc., and, when pressed by facts, take refuge behind such terms as sporadic or septic cholera.

The key-note to this discussion will be found in the obscurity which surrounds the infection of the initial cases, the consideration of which is referred to the narrative of the epidemic.

From the study of this demonstration of the disease, in which the writer has been engaged almost constantly since August, 1873, during which time the records of some seven thousand cases have been obtained from physicians at all portions of the field of infection, he does not hesitate in announcing the disease to have been *malignant epidemic cholera*. During the entire season, the epidemic was governed by the same well-defined laws that have been presented by all other demonstrations of the same disease. That the intensity of the epidemic was modified and its advance checked at most points was due to the general diffusion of sanitary knowledge throughout the country during the last few years, and not to any change of type in the disease itself; but, at the same time, it is shown that whenever the infection of cholera found a fitting and unmolested nidus, then and there the disease exhibited its fatal malignancy. The truths upon which this assertion is based were most vividly impressed upon the mind of the writer by the direct contact in which, from the necessities of his work, he was placed with a very large number of the medical gentlemen residing in the

great valley of the Mississippi; and the fact that the disease did not assume its accustomed epidemic form in the larger cities, but that its malignant demonstrations were confined to the smaller towns and villages, is robbed of the significance assigned to it by many observers. The narrative demonstrates that cholera was present in the large cities of the Mississippi Valley, but at the greater number of such points the virulence of the epidemic was controlled by the prompt and energetic action of the health-boards, assisted by the active co-operation of the medical profession and municipal authorities.

At the present day, almost every village and hamlet throughout the United States contains medical men who are versed in sanitary science, who demand from local authorities that all efforts be made to preserve the public health, and who are engaged in the diffusion of sanitary knowledge among the members of their respective communities. Each year, the suggestions of local medical societies are received as edicts for the public good. It is claimed for the medical men of the Mississippi Valley that, as practical sanitarians, they are the peers of sanitarians in any other section of the country.

How great the change effected in the last decade, and how mighty will be the revolution when the state confers upon health-boards autocratic powers upon all points which may influence or affect the public health! Eternal vigilance is the price paid for the safety of the republic; and eternal sanitary vigilance should be exercised by national, State, and municipal authorities.

As, in the narrative of the epidemic, space cannot be taken to note in detail individual instances of the disease, it has been thought best, at this time, to present a history of the symptoms and general course of the epidemic, as it occurred in the Mississippi Valley from February to October, 1873.

The clinical history demonstrates that no age, sex, color, or condition in life was exempt from its influences. Fatal cases are recorded as having occurred at all ages, from that of one month to that of one hundred and eighteen years; and it is demonstrated that pregnancy affords no immunity to the disease. The greatest mortalities are recorded between the twentieth and fortieth years of age. Males suffered from the disease more severely than females, and, in proportion to their numbers, blacks than whites. A larger number of cases occurred among those who were married than among the single. The disease was most malignant among the lower orders of each community, but the better classes were by no means exempt. Many who lived in healthy localities, who obeyed all obvious sanitary regulations, suffered in their persons and families.

During the epidemic of 1873, the disease presented the four distinct stages, and the characteristic symptoms of each stage, which are now so well recognized as pathognomonic of cholera.

THE FIRST STAGE: THAT OF THE PRODROMATA.—In the vast majority of cases which have been reported, the disease was ushered in by a distinct stage, which was characterized by general malaise, borborygmi, and diarrhœa; the latter passive, painless, but attended with increasing languor and fatigue. This stage, in the greater number of cases, was from one to five days in duration. Exceptions to this are, however, reported, in which the patient, who was apparently in perfect health, after but one dejection passed into the stage of well-defined cholera. This was especially noticeable in the cases of children, many of whom are reported as retiring to bed at night in their usual good health, to be awakened at an early hour of the morning by a strong

desire to go to stool. One copious dejection, and the symptoms of the second stage were immediately developed. In these cases, no definition of stages could be determined; the patient after a single profuse dejection becoming exhausted, and collapsed before medical attention could be procured.

SECOND STAGE.—In the majority of the reported cases, the attacks of cholera were announced at an early hour of the morning; the largest number having occurred at or about 3 o'clock a. m., the patient awaking with an active desire to go to stool, which was accompanied with more or less nausea. One profuse dejection was generally followed by active vomiting, and together the two symptoms increased in severity.

The dejections were universally described as "rice-water" in character. At first passed with a sensation of relief, from the overdistention of the rectum, they increased rapidly, both as to frequency and quantity, and became at the last involuntary; the exhaustion as becoming more and more profound after each dejection. Fatal cases are recorded in which the diarrhœa had scarcely been present during the attack; but the first handling of the body after death was followed by copious discharges per anum of the "rice-water" fluid.

The vomit is described as consisting at first of the contents of the stomach at the moment of attack; but, as the disease progressed, the fluid, diluted by the water which had been drank, or mixed with the substances which had been swallowed, presented the rice-water characteristics. Some instances are reported in which the vomiting could scarcely be designated as a symptom of the disease, the act consisting in the simple squirting-out of a mouthful of fluid at a time. The thirst in all instances was intense, and the call for cold water incessant.

The cramps were confined, in the majority of instances, to the extremities, commencing invariably in the fingers and toes. But few instances are reported of the abdominal or pectoral muscles becoming involved. One terrible instance of cramping of the pectoral muscles was witnessed by the writer. The voice was described as changed, low, husky, lost, or unnatural. Profuse perspiration was present in all cases. A sensation of intense heat, generally referred to the abdomen, while the surface of the body was so benumbed that sacks containing ashes that had been raked from beneath brisk fires and dampened were borne without the least complaint. Intense restlessness was observed. In many instances, it was with difficulty that the patient could be confined to bed. Lividity and shrinking of the skin were present. Change of facial expression was so great that, in many instances, patients who were before the attack in the full vigor of health presented the appearance of being aged and decrepit. Suppression of urine was marked in all cases, and in many instances this symptom was present far into the stage of reaction.

Temperature.—Variations of temperature in the second stage are noted, ranging from 98°, the highest, to 95°, the lowest recorded. One interesting case is recorded by Acting Assistant Surgeon S. L. S. Smith, United States Army, in which, during the second stage of a cholera attack, the temperature in the axilla was 97°, under the tongue 96°. 6, and in the rectum 102°. The fact that the temperature of the body is lowered by severe cramping is especially noted in some reports.

The duration of the second stage is noted at from two to six hours, but many notable instances are recorded of the patient having rapidly passed through the second stage, and one instance exists of the patient being fully collapsed within twenty minutes from the time of the first vomit and dejection. In this case, the blending of the stages was so

complete that it was impossible to determine where one stage ended and another began.

THIRD STAGE: COLLAPSE.—In the majority of the instances reported, as the patient became collapsed, there was a perceptible diminution in the frequence of the act of vomiting. The dejections were still passed involuntarily, and in some instances of profound collapse ceased altogether; the pulse becoming more and more feeble, until at last it was imperceptible in the extremities, and could only be determined close to the heart. The respiration was hurried and accompanied with sighing. An interesting observation, made in a case reported by Dr. J. Paschal, of Louisville, Ky., shows that five minutes before the death of a patient from cholera at the Louisville city hospital, the act of respiration was performed as follows:

On the first of the five minutes, there were twenty respirations.

On the second of the five minutes, there were fifteen respirations.

On the third of the five minutes, there were twelve respirations.

On the fourth of the five minutes, there were six respirations.

During the fifth minute, there was one long and deep respiration, and the patient died.

During this stage, complete aphonia existed; dyspnœa was developed; and the physiognomonic changes were most striking. The intense thirst and sense of abdominal heat continued. The shrinking and lividity of the skin became more marked. The cramping of the muscles of the extremities continued. In some instances, an intense cramp was complained of along the course of the great arteries, attended with violent action of the heart. During this stage, blunting of the special senses was apparent; in no way was this more marked than in the utter apathy of the patient as to his condition.

Temperature.—A gradual rise of the temperature as collapse deepened has been noted. One case characteristic of many is recorded. A female, in cholera collapse:

At 10 o'clock a. m., recorded 97°.

At 10.45 o'clock a. m., recorded 98¼°.

At 11.15 o'clock a. m., recorded 100°.

At 12 o'clock m., recorded 101°.

At 1 o'clock p. m., recorded 103½°.

At 2 o'clock p. m., patient dead.

The duration of the third stage was from four to thirty-six hours.

THE FOURTH STAGE: THAT OF REACTION.—In a large number of the reported cases, the stage of reaction was ushered in by a condition which closely resembles the "tepid stage" of the Indian observers. A gradual subsidence in the intensity of the collapse occurred. The vomiting, purging, and cramps ceased. The patient lay upon the bed in a listless and in some cases almost a comatose condition. The respiration was less hurried, more natural, but was still labored, and a tendency to nausea was noted.

In favorable cases, the skin became dry, the pulse at the extremities perceptible, and the patient complains of no discomfort beyond that of intense thirst. The variations of the thermometer between the axilla, rectum, or vagina, were less marked. During sleep, the physiognomy became more natural. The urine was again secreted, and in the few observations recorded was found to contain albumen.

In less favorable cases, the period of reaction ushered in a condition which has been termed typhoid; the lividity of the skin gave place to a "dusky-red color;" the eyes were injected; the pulse became rapid and flickering; the temperature of the body raised; the tongue brown and

dry. Intense cerebral excitement was observed in some cases, while in others life passed away in a low muttering delirium.

In some few cases reported, the convalescence was rapid and without drawback; but in the vast majority of cases the process was tedious, slow, and requiring the exercise of constant watchfulness and care.

The evidence collected is confirmative of the expression of Jaccoud that the duration of convalescence is in direct proportion to the difficulty of "repair; in the most favorable cases, the patient's digestive organs remain irritable and susceptible of cardialgia and chronic catarrh. In other cases, there is anæmia, which culminates in marasmus, and finally terminates fatally after a variable duration. Relapses are common enough, especially when a judicious regimen is not carefully observed."

The sequelæ of cholera which have been reported are:

I. URÆMIA.—Many fatal cases are reported of individuals, who reacted from the collapse of cholera, to die ultimately of urænia, or in the typhoid condition, of which suppression of the urinary secretion, either partial or absolute, is an invariable symptom. It was observed that these cases were most frequently recorded of individuals to whom opium or alcohol had been exhibited in large doses. Cases are reported of individuals who lived many days in this condition, and who ultimately recovered. The large majority of such cases, however, terminated fatally. In one, severe demonstration of the disease, the initial case, lived in this typhoid state for twelve days, during which eighteen persons, who had been infected through him, died.

II. HÆMORRHAGE FROM THE BOWELS.—A large number of instances are reported of severe dysenteric attacks following the reaction from choleraic collapse. At some localities, an epidemic of dysentery succeeded that of cholera, the mortality of the second epidemic being as great if not greater than that of the first.

III. UTERINE COMPLICATIONS.—In the great majority of instances in which pregnant women were attacked with cholera, labor occurred generally when the patient was in the collapsed stage. The fœti were invariably still-born; their bodies were shriveled and blue, as if their blood had been drained of its serum; but they presented no other of the characteristic symptoms of cholera poisoning. Two pregnant females are reported as having died undelivered. Several are noted who recovered from the cholera, although the attack had been complicated by labor. No cases of uterine hæmorrhage were noted. The occurrence of cholera in the persons of puerperal females, so far as has been reported, invariably led to fatal results. It is probable that other sequelæ of the disease occurred, but the facts are not stated in the record.

We append a series of typical cases, with notes upon the treatment of the disease, from gentlemen whose experience has not been noted in the body of the narrative.

CASE 1.—*Reported by Dr. John D. Jackson, of Danville, Ky.—Cholera—Second stage—Recovery.*

J. R., æt. 17 years, white, male, a student of Center College, left his home in Lebanon, September 1, cholera being at the time epidemic in that town, a fatal case having occurred August 30, in the immediate vicinity of his father's residence. On the 4th, early in the day, was obliged to leave his class-room from sickness. During the evening had one or two actions of his bowels. After dark, was taken with purging and vomiting, which continued through the night. No physician was

called; the family with whom he resided attempted treatment by compresses and enemata of cold water after each dejection. A small quantity of quinine in brandy was also administered.

Early on the 5th, his condition becoming critical, Dr. Jackson was called in haste. "Found him in the blue stage of cholera; his skin covered with a clammy moisture; his pulse was yet moderately full; his extremities not actually cold, but he presented the bluish, leaden-hued skin of epileptics after the long-continued use of nitrate of silver. The matter vomited at this time was perfectly transparent and odorless, with a mucoid-looking material in it, and the alvine dejections were like distilled water, with flocculi, resembling the boilings of rice-gruel, floating in them. They were without the slightest odor."

Mustard was substituted for the wet compresses; morphia sulphatis, gr. ½, hypodermically, and Hydrg. submur., gr. iij, were at once administered; the last being vomited was at once repeated. A teaspoonful of the following mixture, in two ounces of water, was directed every hour while the vomiting and purging continued: R. Acid. sulph. dil., f℥i; morph. sulph., gr. ij. M.

The vomiting and purging continued until after the administration of the third dose; two more doses were given, and by 2 p. m. reaction was fully established. The last dejection occurred at 1 p. m., and was still of the rice-water character. About dark of that evening, a relapse was imminent, but by a steady perseverance in treatment it was averted. The acid and morphia mixture was continued in diminished doses and at longer intervals for twenty-four hours. No dejection until the morning of the 6th, when he had a large, perfectly thin, watery evacuation, tinged, of a faint greenish brown, and offensive in odor. Convalescence regular; nausea existing for two or three days. Urine secreted in from thirty-six to forty hours from time of seizure. Bile re-appeared in dejections in from forty to forty-four hours. Urine free from albumen; sp. gr. 1020; presented a few broken tube-casts and quantities of renal epithelium.

The vomit and dejections were disinfected immediately upon their discharge, and thrown into a small pit, together with the water used in rinsing the vessels, then covered with six inches of fresh earth. Dilute sulphuric acid was administered to all the occupants of the house, in doses of fifteen drops three times daily. No other cases occurred on the premises.

CASE 2.—*Reported by S. P. Craig, M. D., of Stanford, Ky.—Cholera—Fully developed—Recovery.*

"Lynn Hansford, æt. 14 years, negro, male, was attacked by diarrhœa on Monday morning, September 1. His mother had died of cholera on the previous day. Was a resident of the infected portion of the town of Stanford. Hyd. submur., gr. iij, with opii pulv., gr. ¾, were ordered every two hours. After the third dose, his diarrhœa was checked, and remained checked until evening, when it re-occurred, attended with vomiting, to relieve which sinapisms were applied to the epigastrium. About 4 o'clock in the evening, he had several large rice-water discharges. Commenced giving calomel in gr. ij doses every hour. At 6 o'clock p. m., his pulse became very feeble, and his extremities began to get cool. Gave him one-sixtieth of a grain of atropia hypodermically. At 7 p. m., he was still colder; put him in hot bath, and applied fresh sinapisms. At 8 p. m., gave another dose of atropia, (one-sixtieth of a grain.) At 9.30 p. m., he was pulseless at the wrist, and cold to the knees and elbows; gave atropia,

one-thirtieth of a grain, and left with instructions to keep up the hot applications *until he died.* At daylight on the morning of the 2d found him alive. There was a little more warmth, but still no pulse at the wrist. Gave atropia, one-fortieth of a grain. At 9 a. m., repeated the same amount of atropia; pulse perceptible. At 12 m., pulse improving; repeated atropia in same dose. At 3 p. m., reaction was completely established. Secretion of urine was established in seventy-eight hours from inception of disease. Patient made a rapid recovery. After reaction was established, diuretics were freely used."

CASE 3.—*Reported by L. S. McMurtry, M. D., of New Orleans, La., (visiting in Garrard County, Kentucky)—Cholera—Fully developed—Death.*

L. R., æt. 48 years, negress, a stout, healthy woman, and the mother of a large family of children, was taken with diarrhœa at 5 a. m., September 2, 1873, which continued, accompanied with vomiting and cramps, until 2 o'clock p. m., when Dr. McMurtry was asked to see the case.

"On arrival, found her in complete collapse. No pulse in the radial artery, and barely perceptible in the brachial. Aphonia. Pinched expression of face. Suppression of urine. Involuntary, odorless, and colorless passages. Severe and painful cramps in muscles of leg and hand. Temperature, 97°. Treatment consisted of the hypodermic use of morphia, sinapisms to the epigastrium, and friction of the entire surface of the body. Death at 8 o'clock p. m.

"It is of interest and value to note that this woman had been in no choleraic district, remaining at home during the entire summer, and had committed no imprudence of diet. The drinking-water was, however, not very pure, and the ventilation of the house was very defective.

"A searching inquiry into the causes affecting this case, furnished Dr. McMurtry with the fact that a black boy, ten years of age, was living with this woman, and had been in the family for several days prior to her attack, who had come from the infected district of the town of Lancaster.

"Several members of the same family suffered with diarrhœa, before and after the death of L. R., from which two small children died, with no symptoms of cholera other than a severe diarrhœa. The boy from Lancaster, however, remained in perfect health."

CASE 4.—*Reported by W. B. Harlan, M. D., of Danville, Ky.—Cholera—Second stage—Recovery.*

A. P. B., æt. 33 years, white male, a farmer in comfortable circumstances, temperate in his habits, living six miles from Danville, was attacked at 8 o'clock on the night of August 30, 1873, with profuse vomiting and purging. Had a slight diarrhœa for some hours previous to attack. Dr. Harlan saw this patient at 11 o'clock p. m. "Rice-water discharges fully established. Body bathed in profuse perspiration. Cramps of abdominal muscles and those of lower extremities. Skin cold and markedly blue. Pulse 100. Thirst intense.

"Sinapisms were applied to surface. Morphia was exhibited hypodermically. Hydrg. submur., gr. ij were ordered every hour for four hours. Acid. sulph. dil., gtt. xx, with quiniæ sulph., gr. iij, were ordered every hour until four doses were taken.

"Disease arrested and reaction established by the twelfth hour. Patient recovered."

CASE 5.—*Reported by I. S. Warren, M. D., late of Lancaster, Ky. Cholera—Fully developed—Death in eleven hours.*

"Mrs. R., æt. 22, white, was attacked at 3 a. m., August 24, 1873, with cramps, vomiting, and diarrhœa. Pure 'rice-water discharges' were soon established, and, by 5 o'clock a. m., she was fully collapsed.

"When first seen, the vomiting, purging, and cramping were violent and constant. Pulse imperceptible. Sinapisms and dry heat were applied, and morphia, gr. $\frac{1}{8}$, atropia, gr. $\frac{1}{60}$, were at once exhibited hypodermically. In fifteen minutes, the vomiting had ceased. Cramps considerably relieved. Temperature, 96°.

"At 6 o'clock a. m., temperature the same. Had occasional cramps; vomited once on taking ice-water. Restricted to cracked ice.

"At 7 o'clock a. m., gave capsicum and quinine, which were at once ejected. Pupils not dilated, and atropia, gr. $\frac{1}{40}$, exhibited.

"At 8 o'clock a. m., temperature 97°, pupils still not affected

"At 9.30 o'clock a. m., seems worse. Temperature 95°. Extremities icy-cold, lips livid, vomiting recommenced. Gave morphia, gr. $\frac{1}{8}$, atropia, gr. $\frac{1}{60}$, hypodermically. Bladder empty.

"At 10.45 o'clock a. m., temperature 98°.4. Extremities much warmer; no cramps, vomit, nor dejections; pupils partially dilated. Comatose.

"At the expiration of an hour, temperature 100°, pulse just perceptible, feet not quite so cold. At 12 o'clock m., temperature 101°. Still comatose. In an hour, temperature 103°.5. Comatose. 2 o'clock p. m., died.

"The husband of this patient died early of same day from cholera."

CASE 6.—*Reported by I. S. Warren, M. D., late of Lancaster, Ky.—Cholera—Fully developed—Death in twelve hours.*

"E. H., a private of E Company, Sixteenth United States Infantry, was taken with diarrhœa at 4.30 o'clock a. m., of August 29, 1873. Up to 6 o'clock a. m., when the doctor was called to the case, had frequent discharges, and was found much prostrated by them. Temperature 97½°. Sinapisms were applied to abdomen, and atropia, gr. $\frac{1}{60}$, was given hypodermically; and a powder containing full doses of opium, camphor, calomel, and bismuth, given every third hour. The first powder was vomited, the second retained.

"At 8 o'clock a. m., temperature 96°. Had one rice-water discharge. Atropia, gr. $\frac{1}{60}$, repeated, and hyd. submur., gr. v, to be given every hour and a half. Dry heat to extremities.

"At 9.30 o'clock a. m., temperature 97°.8. About one drachm of urine was drawn from the bladder, and the following ℞. alb. ovi, No. i; sodæ chlor., gr. x; spts. frumenti, ℥ss M.; to be repeated as might be required.

"At 10 o'clock a. m., temperature 98°.2, restless, great dyspnœa. Morphia, gr. ¼, atropia, gr. $\frac{1}{60}$, were exhibited hypodermically; this relieved him, and was followed by sleep.

"At 11 o'clock a. m., patient sleeping soundly, temperature normal.

"At 12 o'clock m., temperature 98°.4; profuse perspiration; and tinct. digitalis, gtt x; spts. ether. nit., ℥j, was ordered to be taken every third hour.

"At 2 o'clock p. m., temperature was 102½°; pulmonary congestion was developed; and the patient died at 4 o'clock p. m. No urinary secretion."

CASE 7.—*Reported by I. S. Warren, M. D., late of Lancaster, Ky.—Cholera—First stage—Recovery.*

"W. G., a private of E Company, Sixteenth United States Infantry, was taken at 10 o'clock a. m., September 4, 1873, with diarrhœa. One

drachm of Squibb's mixture was given every three hours. Had during the day four evacuations of watery character; an occasional vomit.

"At 10 o'clock a. m., September 5, temperature 98°.5. Had a pure rice-water evacuation. Introduced a catheter, but found bladder empty. Exhibited hypodermically morphia sulph., gr. $\frac{1}{4}$; atropia, gr. $\frac{1}{60}$.

"At 10.30 a. m. had another rice-water discharge, and vomited. Hydrg. submur., gr. x, ordered to be taken every hour until five doses have been taken.

"At 4 o'clock p. m., another evacuation; consistency and color improving.

"At 7 o'clock p. m., another dejection; urinated freely.

"At 8 o'clock p. m., another action of the bowels; color improving. Temperature 98°.

"Convalesced rapidly."

CASE 8.—*Reported by S. P. Craig, M. D., of Stanford, Ky.—Cholera—Fully developed—Death in twenty-three hours.*

Mrs. Jos. L., æt. 31 years, a resident of the infected portion of the town of Stanford, but who had left the town as soon as cholera became epidemic, and did not return until ten days or two weeks had elapsed from the occurrence of the last case, was taken Sunday, September 28, about 12 o'clock m., with looseness of the bowels. Dr. Craig, having been called, prescribed some powders of opium and tannin, which temporarily checked the tendency to diarrhœa. At 6 o'clock p. m., the looseness continuing, a powder was administered containing opium, gr. j; plumbi acet., gr. iij, and she was requested to inform the doctor at once if this failed to check the discharges.

"At 5 o'clock a. m., September 29, was informed that Mrs. L. had a very profuse diarrhœa during the night. On reaching her residence was informed that she had passed two ordinary-sized chamber-vessels full of thin watery fluid since midnight, and that there was another one still full in the house. Examination of this chamber determined it to be full of rice-water dejections. The patient was much prostrated, but quite cheerful. Her thirst was intense, and she complained of great internal heat. Crampings and vomiting soon came on; the skin of fingers and toes became shriveled, and the countenance became anxious; eyes sunken, voice changed, and became low and husky; pulse smaller and smaller. Collapse quickly followed.

"Succeeded in getting her quite warm several times after the collapse, by means of hot water, atropia, &c., and she died with a warm surface. The contractions of the muscles after death were astonishing; an hour after death, they were observed.

"The residence of this lady was about fifty yards from where there had been three cases of cholera during the second week of the epidemic; but, from the fact of the absence of the family the house was closed, and Mrs. L. was not attacked until a full week after their return. The water used was brought from a well in town at some distance from their residence, and the same well had been used by a number of families without developing any disease."

"On the same day, Mr. L., æt. 33 years, was taken with looseness of bowels, and frequent disposition to go to stool, for which he was treated, but without effect. On the morning of the 29th, this looseness threatening to become violent, he was placed in bed, dry heat applied to surface of his body, and morphia sulph., gr. $\frac{1}{4}$, exhibited hypodermically, and a powder, containing calomel, gr. ij, camphor, gr. ij, was given

every hour until he had taken eight doses. During the next twenty-four hours the morphia-injection was repeated two or three times, and several weak brandy-toddies were given. Reaction was fully established, and at 11 o'clock a. m. he had two dejections containing a little fecal matter. Convalesced slowly."

CASE 9.—*Reported by W. W. Cleaver, M. D., of Lebanon, Ky.—Cholera—Fully developed—Death on the tenth day.*

Miss B. S., æt. 16 years, residing upon the Rolling Fork, while on a visit to the house of an aunt on the 29th of August, was, during the night, taken with vomiting and purging. Had eaten her supper, and retired to bed in her usual health, but, about 11 p. m., was awakened by violent nausea, followed by profuse vomiting. In a few moments a dejection occurred. The vomiting and purging continued for the space of an hour, when cramps in the lower extremities were established.

An express rider was dispatched to Lebanon, a distance of seven miles, for Dr. Cleaver, as soon as the cramps occurred, and, by using all haste, the patient was first seen by Dr. C. at a little before 3 o'clock a. m. of the 30th.

"The vomiting and purging at the time of this visit consisted of pure rice-water; violent cramps of both extremities occurred. The surface of the body was covered with a profuse perspiration. Extremities icy-cold; skin of fingers and toes shriveled; tongue cold. Slight pulse could be distinguished in the radial, and was counted to 130 beats to the minute. Features contracted, anxious, and pinched; eyes sunken; voice changed and scarcely audible. Complained of the most intense thrist. Dejections involuntary; complete suppression of the urine. A sinapism was applied to the abdomen, and covered with a large, hot poultice; dry heat to the spine and extremities. Hydrg. submur., gr. ij, with opii pulv., gr. ss, was exhibited every hour until three doses had been taken, when the same powder, with the addition of bismuth subnit., gr. iv, camphor, gr. j, was given until three doses had been taken, when the interval was increased to three hours. This was continued during the day, with the addition of occasional doses of quiniæ sulph., gr. ij, and a drachm of spts. æther. nit., the last to be given at three-hour intervals.

"After the first three powders had been taken, the vomiting and purging were notably lessened, and the interval between the paroxysms much increased.

"August 30, at 7 p. m., found the pulse increased in volume. Surface of body moist with perspiration; extremities warm. Face less anxious. Voice stronger. Thirst still excessive, but vomiting and purging had ceased. No urine had been voided. The treatment was continued.

"August 31, 10 o'clock a. m., general condition was found much improved. Reaction established. Had slept some during the night, and on awaking had vomited slightly. No urine yet secreted. Discontinued the calomel-powder. Substituted bismuth, gr. iv, every four hours, and the following mixture, a teaspoonful of which to be taken every three hours:

"℞. Tinct. opii camph.,
Ext. ginger fluid, āā ℥ij.
Tinct. camphor,
M. Tinct. capsici, āā ℥ij.

"The quinine and nitre to be continued.

"September 1, at 10 o'clock a. m., found the patient decidedly improved. During the past twenty-four hours had but three dejections, still watery, but colored. No more vomiting. No urine yet passed. Expressed a desire for food. Treatment of previous day was continued. Milk and a light soup allowed.

"September 2, early in the day the patient was removed to her father's house, a distance of three-quarters of a mile; but by the time she reached the house vomiting and purging were re-established. At 5 p. m. of the same day the pulse was found to be thread-like. Skin warm, except at the extremities. Countenance anxious and distressed. Complaining of intense abdominal pain. Having thin watery discharges. Had passed several ounces of urine.

"Placed her upon powders of calomel, opium, and bismuth, one every hour, and in the interval the camphorated mixture was continued. Discontinued quinine and spirits of nitre.

"September 3, 11 a. m., diarrhœa arrested. Skin dry and warm. Pulse small, hard, and rapid. Tongue brown and dry. Urinary secretion nearly natural. Had slept none during the previous night. Continued treatment and nourishment, with the addition of milk-punch.

"September 4, 11 a. m., no change in her condition; still complaining of the intense abdominal pain. This pain was constant. No improvement occurred in the next three days, when the patient died."

CASE 10.—*Reported by B. E. Avritt, M. D., of Lebanon, Ky.—Cholera—Fully developed—Recovery.*

M. A., æt. 12 years, female, white, living on the Rolling Fork, from the 1st to the 5th of September complained of diarrhœa, for which no treatment was asked, although the county was suffering severely from the epidemic.

At 12 o'clock m. of the 5th was taken with violent purging, which was soon followed by vomiting and cramps of the feet and hands.

At 1 p. m. she was first seen by Dr. Avritt. The vomit and dejections were of "pure rice-water." Her face was livid. Eyes shrunken and surrounded by a discolored ring. Extremities cold; skin of fingers and toes shriveled. Tongue cold as ice. Extremely restless, tossing from side to side, and complaining of burning heat. Voice nearly lost. Thirst most intense, calling constantly for water, which her friends had refused. A powder, consisting of opium, gr. ss, plumbi acetatis, gr. ij, bismuth, gr. v, was given, but it was immediately ejected. Morphia acetatis, gr. ¼, was given hypodermically. She became quiet; vomiting was arrested. Chloroform, 3ss, brandy, 3j, in water, was given, and repeated every fifteen minutes. The powder, of lead, opium, and bismuth, was given and retained, and was ordered to be repeated every two hours. Dry heat was applied to the body, sinapisms to abdomen and extremities. Ice-water and cracked ice allowed freely. The diarrhœa became less frequent and the quantity of water lost at each discharge was diminished. Extremities became warmer. Gradually, reaction was established. Urine was not secreted freely for seventy-two hours. Convalescence slow and tedious.

CASE 11.—*Gooden family—Reported by Drs. Cleaver and Avritt—Cholera—Death and recovery.*

On the morning of August 31, Robert Gooden, æt. 20 years, single, white, was taken with vomiting and purging, attended with prostration,

while on a visit to the town of New Market. Dr. Porter prescribed for him; he was placed in bed; and the severity of the symptoms was relieved. On the 3d of September he returned, on horseback, to his father's house, a distance of a mile and a half, reaching home about 5 o'clock p. m. Said he felt well but tired, and soon went to bed. At midnight he was taken extremely ill, vomiting and purging, with cramps of his hands and feet, soon extending to the entire limbs. His mother described the rice-water discharges exactly. In a very few moments he became perfectly collapsed, and he died at 10 a. m. of the 4th. His father describes him as "the coldest and wettest human" he ever saw. No physician could be found until just before his death. This young man had attended the Marion County fair.

On the 6th, James, æt. 22, single, the eldest son of the family, was attacked with a looseness of the bowels, which continued all day. At 3 o'clock a. m. of the 7th was vomiting, and had profuse watery evacuations, which rapidly assumed the rice-water characteristics. Cramps commenced in his feet and rapidly involved the entire body. Became icy-cold, but had but a slight perspiration. Complained of intense internal heat, and the most excessive thirst. Skin of fingers and toes became shriveled. Urine suppressed. Sinapisms were applied to his body, with dry heat, and he was supplied with all the ice-water he wished. (This had been denied to his brother.) No doctor could be procured until the 8th, when Dr. Palmer saw him. The collapse was fully developed. Bags of salt were heated as hot as possible and packed around him. Heat to abdomen. Chloral hydrate administered freely. Calomel and morphia were exhibited. Reaction was gradually established, and in twelve hours from Dr. Palmer's visit the case was considered out of danger.

The father, Lewis Gooden, æt. 50 years, was attacked on the 9th with excessive purging of a watery character, which soon became "rice-water." They were attended with excessive prostration and intense thirst, but which yielded to absolute rest and the calomel and opium treatment, and, as the patient insists, the free use of ice-water.

Three other members of the same family were on the 10th attacked with symptoms identical with those presented by the father; but in each the disease was arrested in the first stage.

The family resided in an isolated position among the "Knobs," north of the Rolling Fork. No local influences could be discovered, and all the family were in their usual health until the return of the son, Robert, from the Marion County fair.

No efforts at disinfection or the use of prophylactics were attempted.

CASE 12.—*Reported by B. E. Avritt, M. D., of Lebanon, Ky.—Cholera—Second stage—Recovery.*

Charles, a negro, æt. 35 years, single, after a few hours of diarrhœa, was attacked with vomiting and purging, attended with excessive prostration. Cramps of hands and feet were rapidly developed. The discharges assumed the rice-water character. Skin of fingers and toes was shriveled. He was first seen by Doctor Cleaver at 6 o'clock p. m. of September 10. The patient was in an old shanty, without any of the comforts of a sick-room. Some one had made up a bed for him, but at the time of the visit he was alone. He was placed upon full doses of opium, calomel, and bismuth, and Doctor Avritt was asked to take charge of the case.

At 7 o'clock p. m., Doctor Avritt exhibited a full dose of chloroform;

continued the powders. At 8 o'clock p. m. the chloroform was repeated, and quinine, gr. ij, was added to the powder already noted. Finding it impossible to obtain any nurse for this man, Dr. Avritt made him as comfortable as the circumstances would admit; placed by the side of his bed a bucket of ice-water and a glass, and visited him as often as possible during the night. The vomiting and purging continued during the night, but at lengthening intervals, and as water from the tumbler did not satisfy him, he drank from the bucket as long as he could tilt it to his mouth. During the night he drank all the water that was provided. At 6 o'clock a. m., September 11, surface of his body was not so intensely cold, a slight pulse, no vomiting or purging; by noon was fully reacted; and on the 13th was able to sit up.

CASE 13.—*Reported by W. W. Cleaver, M. D., of Lebanon, Ky.—Cholera —Fully developed—Recovery.*

W. E. R., æt. 35 years, male, white, residing in the Pleasant Run district of Marion County, was attacked September 10, 1873, at midnight. His father-in-law had died of cholera a few days before. His wife was at that moment *in articulo mortis* of the same disease.

At 11.30 p. m. of September 9, this gentleman left the room of his wife, went into an adjoining chamber, and threw himself for a few moments upon a lounge, fell asleep, and, as he had been in constant attendance upon his wife for three days and nights, his friends permitted no one to disturb him. A few minutes before midnight he was awakened by sudden and uncontrollable nausea; springing to his feet, he shook Dr. Cleaver, who was sleeping in the same room, and before a vessel could be secured vomited upon the floor. Expressed a strong desire to evacuate his bowels; the borborygmus being distinct to all in the room. He was at once placed in bed, and at the earnest solicitation of Dr. Cleaver made effort to restrain the inclination to evacuate the contents of his rectum. Hydrg. submur., grs. iij, opii pulvis, gr. j, was administered, and in less than an hour the same amount of calomel with half a grain of opium was given. Sinapisms and dry heat were at once applied. In twenty minutes' time, his extremities were very cold; his face was pinched and contracted; his voice was husky; and he had slight cramps of the hands and feet, and, shortly, of the abdominal muscles. Intense thirst was at once established. Ice was allowed freely. From 1 o'clock a. m. he slept for about half an hour, (probably from the exhaustion of his previous watching.) On awaking, he still complained of his desire to go to stool. Vomiting recurred. Becoming extremely nervous, potass. bromid., gr. xxx, was exhibited, and, in a few moments, a third powder of calomel and opium. He again slept for nearly half an hour. On awaking, he insisted on going to stool, but yielded to the desire of his attendants, and made no further attempt. He rested quietly, with occasional naps, unti 5 o'clock a. m. of the 11th instant, when a fourth powder of calomel and opium was given. No more vomiting had occurred, but his extremities were much colder, his body was bathed in perspiration, and his pulse was small, weak, and rapid.

At 7 o'clock a. m. had vomited once more, a tinged fluid. A fifth powder of calomel and opium was given. He was growing decidedly worse. Ordered calomel, gr. ij; opium, gr. ss; plumbi acet., gr. ij; to be given every two hours.

Up to this time, Dr. Cleaver had remained in constant attendance, and by his personal control over the patient had restrained him from

purging ceased. In a few moments after Dr. C. left the house the patient yielded to a desire, and had two large watery actions, but voided no urine. The diarrhœa then ceased, soon assumed the rice-water character: vomiting was re-established, of the same grade: the cramps increased in severity: and all these symptoms continued late in the evening. The treatment of the morning was the administration of small doses of quinine, and ice persistently.

At 7 o'clock p. m. Dr. Chaney returned and remained in charge of the case. The vomiting, purging, and cramping had been arrested. Reaction had commenced. Body still cold, and pulse imperceptible. He was placed upon a mustard-flannel, and ordered capsicum, and ice.

At 9 o'clock p. m. he had two large rice-water discharges, with vomiting of the same character. Calomel, gr. iij, pulv. opii, gr. ss, was exhibited. A severe and violent paroxysm of cramping followed the second action. Symptoms and dry heat.

At midnight had another small rice-water dejection. Thirst becoming intense. Ice-water was allowed at pleasure. No urine had been passed for twelve hours. Bladder empty. Spts. ætheris nit. in drachm-doses, repeated every two hours, was ordered.

At 1 o'clock a. m. sleeping quietly. No more vomiting or purging.

September 11, at 6 o'clock a. m. skin dry: extremities comfortably warm: no nausea or disposition to go to stool: thirst continued excessive.

At 7 o'clock a. m. had one small, dark, but watery dejection. Still no urine. Directed the urine to be examined every three hours, and, if the dejections should become frequent, a powder to be taken every two or three hours of lead and opium. Milk and gruel. During the day had but one action. No nausea. Urine secreted freely, and convalescence was established. The excessive thirst continued for several days. Recovery very slow and tedious.

Case 14.—*Reported by W. E. Mattingly, M. D., of Lebanon, Ky.—Family of W. T. Spalding, esq.—Cholera—Death—Recovery.*

Residence upon the Rolling Fork, some six miles from Lebanon. The majority of the family and the servants had attended the Marion County fair.

At 4 o'clock a. m. on Sunday, August 31, Steve Smith, æt. 21 years, white, a farm-hand, was taken with diarrhœa: was given a "home-remedy," which arrested the discharges, and at 9 o'clock a. m. he went to church. While at church had several actions of his bowels, and reached home about 12 o'clock m. Diarrhœa became more violent, vomiting was established, and, by 7 o'clock p. m., when Dr. Mattingly reached the patient, he was vomiting and purging incessantly, and suffering with cramps of both extremities. The surface of body and tongue was very cold: countenance pinched and anxious: voice low and husky: skin on fingers and toes shriveled: intense thirst: urine suppressed: cyanosis rapidly developing: pulse imperceptible. Sinapisms to abdomen and extremities. Dry heat. Calomel, gr. x, bismuth, gr. x, morphia, gr. j, as a powder, and directed to be given every hour. Enema of starch water, containing tinct. opii, every hour. Whiskey and water. Water allowed freely.

Improvement manifested.

September 1, a. m., at residence of Mr. S., who occupied a room with Smith.

was taken with the same disease; the attack, although severe, yielded to treatment.

Miss L. S., æt. 17 years, was taken on the 2d of September with the premonitory symptoms, which increased in severity; had several rice-water discharges; but the case yielded to treatment as in former case, before the second stage of the disease was fully developed.

Mrs. S, æt. 45 years, at 12 o'clock midday on the 4th day of September, had the premonitory diarrhœa for some hours before the disease was developed. Vomiting and purging of rice-water, with violent cramps. Surface of body cold and shriveled; profuse perspiration. Suppression of urine.

When the violent symptoms occurred, her husband gave, on his own responsibility, calomel, gr. x, and applied sinapisms and dry heat. Dr. Mattingly saw the patient at 3 o'clock p. m. The symptoms were becoming more severe. Hydrg. submur., gr. ij, opium, gr. ss, bismuth, gr. xv, to be taken every three hours. Ordered, after each dejection, cold starch-water enemata; cold drinks.

At 10 o'clock a. m., of the 5th September, vomiting had been arrested; one dejection during the night, of a dark, watery character. A disposition to diarrhœa was developing. Starch-water enemata, containing quinine, gr. iv, ordered after each action. No urinary secretion; hot turpentine stupes to spine.

September 6, at 10 o'clock a. m., reaction established; during the night voided a small quantity of urine.

Convalescence very slow.

N. R., æt. 30 years, male, white, son-in-law, September 6, at 4 o'clock a. m., was taken with profuse diarrhœa, attended with great exhaustion and thirst.

Arrested in five hours by rest in a recumbent posture, and the use of calomel, opium, and bismuth.

W. T. S., æt. 50 years, married, male, white, September 7, was taken with profuse watery diarrhœa, which yielded to rest and treatment as in former case.

F. S., æt. 16 years, single, male, negro, September 7, was taken, about 4 o'clock a. m., with vomiting and purging. He was placed in a spring-wagon and taken one mile to his home.

Cholera was fully developed in this case; by 5 o'clock p. m. was collapsed, and died at 2 o'clock a. m. of September 8th.

J. R., æt. 1 year, white, female, grandchild, on the 9th of September was taken at 5 o'clock a. m. with vomiting and purging; went rapidly into collapse, and died at 8 o'clock p. m. of same day.

I. S., æt. 14 years, white, male, September 10, attacked about 4 o'clock a. m. with premonitory symptoms, which threatened to become severe, but yielded to calomel, opium, and bismuth, and rest.

S. S., æt. 16 years, white, female, September 14 attacked about 3 o'clock a. m. with premonitory symptoms, which yielded to the treatment as in former case.

The district in which this family live has always been considered healthy. The water-supply was good. No local causes could be discovered. The family were in easy circumstances.

CASE 15.—*Reported by N. G. Leake, M. D., of New Haven, Ky.—History of the Wheeler family—Cholera—Three deaths.*

T. W., æt. 20, male, white, at 8 o'clock a. m., August 20, had a large rice-water discharge from the bowels; vomiting of the same character

and cramps in different parts of the body followed immediately. In an hour, the pulse had disappeared at the wrist; the extremities became cold, and the entire body was bathed in a cold sweat; intense thirst; tongue and breath cold; urine suppressed. At 1 o'clock p. m. was fully collapsed; pulsation at the carotids was scarcely perceptible; the features were pinched and changed; the skin of extremities wrinkled. Sinapisms were applied to the surface of body and extremities; dry heat. Stimulants and full doses of quinine, camphor, capsicum, and strychnia were exhibited.

At 5 o'clock p. m. died.

Two other cases in the same family, one a female and the other a male, were attacked the same day. The onset of the disease was violent in each case. In one, death occurred in fifteen hours; in the other, in ten hours. This family lived some eight miles from a physician. Several hours elapsed before they could be visited professionally, and in each case the patient was *in articulo mortis* when first visited.

CASE 16.—*Reported by N. G. Leake, M. D., of New Haven, Ky.—Cholera—Second stage—Recovery, with abortion.*

Mrs. M. C., æt. 25 years, two months pregnant, was attacked late in the evening of September 8 with copious watery discharges. In two hours from their occurrence, violent vomiting and cramping took place, and the symptoms of the second stage were quickly and perfectly developed. It being impossible for the case to be seen at that time, Dr. L. prescribed—R. Quiniæ sulph., capsicum, camphor, and calomel, āā gr. xij; morphia sulph., gr. j, divided into four powders, one of which to be given every hour until the violence of the symptoms should subside. Chloroform, gtt. v; tinct. capsici, gtt. xv; tr. opii, gtt. v; creasote, gtt. j; oil cloves, gtt. iij, suspended in mucilage, to be given every fifteen to thirty minutes until no longer indicated. Sinapisms, dry heat, and crushed ice.

September 9, at 4 o'clock a. m., the patient much depressed; very frequent and feeble pulse; extremities cold; body bathed in cold sweat; skin of extremities corrugated; thirst intense. Vomiting had ceased, but the dejections were constant and involuntary. All these discharges were of pure rice-water. The amount of calomel and quinine was reduced to gr. ij each, and with this exception the powder of the previous night was exhibited every hour until reaction was established. The symptoms gradually subsided, and by 6 o'clock p. m. the reaction was complete. Powders given at intervals of two hours.

September 10, improving very slowly; some indication of the disease still present. Urinary secretions re-established early in the day. Powders continued at intervals of four hours.

September 11, fully reacted. Prescribed quinine, gr. xij; camphor, gr. xviij, divided into six powders; one to be given every four hours.

September 12, the patient aborted. Placenta removed with difficulty. Recovery slow, but perfect.

CASE 17.—*Reported by S. T. Chandler, M. D., of Campbellsville, Ky.—Cholera—Second stage—Recovery.*

H. H. C., æt. 16 years, male, white, visited the town of Lebanon on the 31st of August, and indulged to some excess in water-melons: was on the following day attacked with a slight diarrhœa, which continued in spite of treatment until the 2d day of September, at 7 o'clock p.

m., when the diarrhœa became violent, attended with severe vomiting and cramps. All the symptoms of the second stage of cholera were rapidly developed. Sinapisms and dry heat were applied, and calomel and morphia were exhibited, but little relief was obtained.

September 3, at 3 o'clock a. m., was placed upon the use of dil. sulphuric acid, with an immediate subsidence of the violence of his symptoms. Quinine was substituted for the calomel; sinapisms and heat continued. The dil. sulphuric acid was freely used with the effect of relieving the nausea and intense thirst. Reaction was established by a perseverance in this treatment, but convalescence was extended over seven or eight days.

Three young ladies of the same family were attacked on the 3d of September with the premonitory diarrhœa, but, by the free use of dil. sulphuric acid, the disease was arrested. Each of these three cases would, in Dr. Chandler's opinion, have terminated in an acute attack of cholera but for the early treatment which their cases received.

CASE 18.—*Reported by D. O. Polin, M. D., of Springfield, Ky.—Cholera—Fully developed—Three deaths.*

1. L. T., negro, æt. 50 years, attended Marion County fair. Was taken during the night of August 30 with diarrhœa, which passed rapidly into second stage of cholera. At 9 o'clock a. m. of the 31st was fully collapsed, and died at 4 o'clock p. m. of the same day.

2. Dr. M. L., æt. 50 years, was attacked with choleraic diarrhœa September 3. Had eaten freely of fruit, and drank a quantity of new cider. The diarrhœa continued during the day and succeeding night, and at 9 o'clock a. m., September 4, the symptoms of the second stage were fully developed. At 2 o'clock p. m. was fully collapsed. Up to that hour had resisted all treatment. Symptoms powerfully marked. Atropia was actively used, with a strong ammoniacal solution, both hypodermically, but without favorable results. September 5, at 10 o'clock a. m., died.

3. Mrs. N. R., æt. 23 years, a daughter of above, was attacked September 7, at 9 o'clock a. m., with vomiting and purging. Was placed upon calomel, gr. iij, opium, gr. ss, which was repeated every two hours until three doses had been taken. After first dose had one large "pure rice-water" dejection, which was not repeated for thirty-six hours. She was never fully collapsed. Her pulse was always perceptible; but from the time of the dejection on the 7th, there was complete suppression of urine, which lasted a period of sixty-six hours. Every effort was made to re-establish the urinary secretion; she gradually became comatose and died in seventy-two hours after the onset of the disease.

It is interesting to note that all the white members of this family and several of the negroes employed were taken with fully-developed cholera. One or more of these cases are reported in detail elsewhere, having been under the care of different physicians. The results were [illegible] and two recoveries. All the persons attacked had attended the fair County fair.

CASE 19.—*Reported by William Berry, M. D., of Louisville, Ky.—History of the Singleton family—Death—Recovery.*

On Tuesday, August 19, Captain Singleton, a resident [illegible] together with his wife and four children, all grown, went to the country, about five miles, and lived with his son-in-law, leaving his son, Hunley Singleton, to care for [illegible]

Said son was complaining at that time of slight diarrhœa. A few days thereafter he followed his father to the country, and on Monday, August 25, was attacked with vomiting and purging large quantities of rice-water discharges. Husky, whispering voice; cold skin, and cramping in the extremities and abdominal muscles, together with almost entire suppression of urine. At this time, he was seen by Dr. O. P. Hill.

"On Tuesday I saw him, with Dr. Pettus, at which time no urine had passed for nearly twelve hours. He had reacted, and at that time his pulse was small and 90 to the minute, with hot, dry skin, and great thirst, but vomited everything. All purging had ceased. Dr. Pettus saw him on Wednesday. A catheter was passed, but only a few drops of urine found. He was then given infusion of digitalis and spirits of nitre, and had cloths wet with hot water placed on the hypogastrium, and in a few hours passed about a pint of urine; after which he began to improve, and was able to be up on Saturday."

"About the same time, John R. Singleton, a grandson of Captain Singleton, and who had been in town on a visit of several days, returned to the country, and was attacked with vomiting and purging rice-water, with some evidence of cramp. Was treated by Dr. Pettus, and recovered in three days. His voice was husky and urine scanty."

"On Sunday, August 24, Mattie Singleton, who had moved with her father to the country, was attacked with purging; light-colored watery stools and vomit; scanty urine and weak voice. Some cramping in the legs. Was treated by Dr. Pettus, and recovered in about a week."

"About the same time, George Singleton was attacked with vomiting and purging; yellow-looking watery discharges; scanty urine, and husky voice. Great nausea. Pain in legs, but no decided cramps. Was treated by Dr. Pettus, and recovered in a week."

"On Tuesday night, August 26, Mrs. F., a daughter of Captain Singleton, but who had removed from the house in which the cases previously noted had occurred, (having used the same infected privy as the rest of the family for a week previous to her removal,) was attacked about 11 o'clock, and died in eighteen hours, with fully-developed symptoms of cholera. She had been unwell on Saturday and Sunday, but was well enough to do some washing on the day she was attacked. This was the only case that had cholera in the county that had not been to town, of which I could hear during the two weeks I remained in Lancaster."

"On Thursday, John Singleton, who had nursed Hunley Singleton, his brother, had diarrhœa, which lasted one day. He also passed but a small quantity of urine on that day."

"On the same day, Clayton Finley returned from the grave of his wife with cold skin, sweating on face and hands, and complaining of feeling very cold. Had cramps in all his limbs and in some of the abdominal muscles. Had no vomiting or purging, but had considerable nausea. He was treated with sulph. atropia, gr. $\frac{1}{40}$, hypodermically. Had no other medicine. Was convalescent in twenty-four hours."

CASE 20.—*Reported by F. Paschal, M. D., of Louisville, Ky.—Cholera—Fully developed—Death.*

P. F. K., male, white, æt. 28 years, single, nativity and occupation unknown, was admitted into the Louisville City hospital on July 23, at 7.15 p. m. He had arrived two days previously from Elizabethtown, Ky., where the cholera was prevailing at the time he left. He stated

that two days before his admission he had been drinking quite hard; had a slight diarrhœa for two days; had not eaten anything for twelve hours; and had slept the night previous in the open air. On the morning of July 23, was taken with vomiting and purging. When admitted to hospital, his eyes were sunken, surfaces were cold and clammy, pulseless; thirst intense; severe cramps down the thighs and legs; subsultus tendinum marked; voice shrill and weak; urine totally suppressed; nausea and vomiting. He had no operation after admission.

At 7.20 o'clock p. m., temperature at axilla 96°; in rectum 99°. Sulph. morphia, gr. ¼, given hypodermically.

At 7.40 o'clock p. m., gave him, in same manner, $\frac{1}{16}$ gr. sulph. morphia and $\frac{1}{50}$ gr. atropia.

At 8 o'clock p. m., cataplasms of mustard applied to abdomen and lower extremities.

At 9 o'clock p. m., pulse could be felt for the first time, beating 120 to the minute.

At 9.30, temperature in axilla 99½°; in rectum 101°; and at 10 o'clock he commenced sinking rapidly. Five minutes before death, which occurred at 11 o'clock p. m., his respirations were, 1st minute, 20; 2d, 15; 3d, 12; 4th, 6; 5th, 1 deep inspiration. After death, muscular contractions were very marked.

CASE (21) *of Asiatic cholera brought from Evansville, Ind., to Louisville, on the 8th of June, 1873—Reported by Dr. J. A. Metcalf, of Louisville, Ky.*

"John Rankin, æt. 29 years, a native of Indiana, arrived in Louisville June 8, 1873, at 5 a. m., after a trip from Terre Haute, Ind., via Evansville. Was taken sick with vomiting and purging at 5.30 a. m., half an hour after arrival from Evansville, where there were cases of cholera. The above symptoms continued increasing in severity until 5.45 a. m., when he was so much prostrated as to be forced to lie down on the sidewalk. He was brought to the city-hospital a short time afterward by the police. When I first saw him, he had very much the appearance of a cyanotic child; his extremities were cold; and there was profuse sweating, principally of the hands and feet. He had a peculiar, anxious stare, which, however, soon passed away. He was put to bed after a warm bath, (being filthy when taken to the ward,) and tr. opii, gtt. xl, administered, which checked the purging immediately. The vomiting continuing, I gave him small bits of ice instead of water, which he begged for constantly. Every two minutes, there were well-marked spasmodic contractions of the muscles of the entire body; gave him hypodermically morphia sulph. gr. ¼, with sulph. atropia, gr. $\frac{1}{60}$, gradually increasing both. Had one action from the bowels half an hour after admission. He was ordered the following mixture:

"℞. Chloroformi, f℥iij.
Tr. capsici, tr. opii, ãã f℥ij.
Aquæ camphor., f℥iij.
Acaciæ pulv., ℥ij.
Mix. ft. sol.

A dessertspoonful every two hours until easy; then as needed.

"After taking of this mixture two doses, the bowels were perfectly quiet. There was excruciating pains during one of the crampings, and the nurse gave him tr. opii, ℥ss. After this, at 9.30 a. m., the cramps seemed almost confined to the inner side of the thighs and the whole of the arms. His face was wet, and as cold as if it had been bathed in

ice-water. Cataplasms of mustard were applied to the abdomen and inner side of the thighs.

"June 8, 11.30 o'clock a. m., the cramps are very much less severe from the subcutaneous use of morphia sulph., gr. ½, and atropia sulph., gr. $\frac{1}{30}$. He constantly spoke of his condition in the most indifferent manner, saying if he 'recovered from this attack, which he did not think he would, he wanted his feet cured;' there being ulceration of the stumps, after Hayes's operation through the tarso-metatarsal articulations. At 3 o'clock p. m., patient's respiration assumed a gasping character, and he gradually became worse and died at 4.37 p. m.

"There was complete suppression of urine from the first. The fingers were of the peculiar shriveled appearance characteristic of this condition. This case was treated by Dr. Frank C. Wilson and myself. It was seen by a number of medical gentlemen, all of whom were of the opinion that there was no doubt of its being genuine cholera of the Asiatic type."

CASE 22.—*Reported by Turner Anderson, M. D., of Louisville, Ky.—Cholera—Fully developed—Death.*

W. R., æt. 56 years, male, white, single, subject to paralysis agitans for seven years, was attacked June 16 with diarrhœa, at 5 o'clock a. m. No medical aid was called until 11 o'clock a. m., when he was found fully collapsed; livid; cold tongue; profuse perspiration; complete suppression of urine; shriveled hands; great restlessness; intense thirst. Vomiting and purging were arrested. Saw him about 12 o'clock m. Treated by albuminous drinks; injections of tepid water. Died at 4 o'clock p. m., without having made any effort at reaction.

CASE 23.—*Reported by Turner Anderson, M. D., of Louisville, Ky.—History of Bauer family.*

Residence on south side of Green street, between Fourteenth and Fifteenth. Frame cottage, low and damp; kitchen floor several inches below the surrounding ground. No provision for drainage. Privy, wash-house, and coal-shed under one roof, and all in dirty condition.

Family consisted of mother, two single daughters, two married daughters with their husbands, and two grandchildren. On the 30th of July, at 11 o'clock p. m., was called to see a married daughter, Mrs. G. Found her with vomiting, purging, and cramps. The attack was sudden and without any known cause. Morphia was exhibited, hypodermically, and quinine, gr. v, ordered for every second hour. This treatment was followed by the relief of all symptoms, and in forty-eight hours she was out of bed. On the 22d of August, this lady went to Bowling Green to visit her husband, who was detained by business in that city. On the 25th, while in Bowling Green, she was taken with cholera, and died after twelve hours' illness. Her body was brought to Louisville to her mother's house on the 28th prior to burial. The coffin was opened, and the remains viewed by her friends.

On the 2d of September, the child of Mrs. G., two years of age, was taken with vomiting and diarrhœa, which were attended with great prostration. Treatment: albuminous drinks, soda, morphia, and mint-water. Recovered. Quinine was used for several days.

September 4, was called to see one of the single daughters (æt. 14 years) at 7 o'clock a. m. Found that she had been taken ill at 5 o'clock

a. m. When first visited she was fully collapsed, and died at 1.30 o'clock p. m.

The same day, a child of Mrs. G., four weeks old, was taken with cholera, and died in forty-eight hours.

September 6, the second married daughter, Mrs. A., was taken with cholera at 10 o'clock p. m., after a slight premonitory diarrhœa, and died within twenty-four hours.

All the remaining members of Mrs. Bauer's family (after the death of Mrs. G.) took quinine in decided doses, except Mrs. A., who was afraid to do so from the fact that she was seven months pregnant. All the other members of the family had more or less diarrhœa, and suffered severely from fright, but all escaped the disease.

CASE 24.—*Reported by Dr. S. A. Foss, of Jefferson County, Ky.—Cholera —Death.*

Mathias Hahn, native of Würtemberg, Germany, æt. 68 years, farmer, married, in comfortable circumstances; residence eleven miles south of Louisville, Jefferson County, on right bank of Bearcamp Creek, bed of which had been dry for three weeks, and south of Pond Creek five hundred yards. Elevation of dwelling 45 to 50 feet above bed of nearest stream. Stable 150 feet south of house. Drinking-water from well 15 feet deep, situated 50 feet north of house, and protected from surface-drainage. Water soft. No privy on premises.

After slight supper, retired. Slept well till 12.30 a. m., August 17, when he awoke with desire to purge. Had seven stools of thin fecal matter in two hours and a half; stools then became watery, apparently containing bile; passages every 45 or 50 minutes for two hours, when they assumed a rice-water character. Had six rice-water dejections up to 12 o'clock m., when I saw him. Pulse 92, very feeble. Surface blue, cold; features pinched, hands and feet shriveled; bathed in cold perspiration. Tongue nearly clean, cool, lessened. Respiration 30. Voice husky. Since 9 a. m., cramps in muscles of abdomen and extremities almost constant. Thirst not great. Did not complain of feeling hot. Complained of mustard on extremities, but jugs of hot water pleasant. Insisted that he had voided urine frequently up to 9 a. m.; passed none after I saw him. Had only one stool of about 8 ounces "rice-water" after I saw him. He declined steadily; pulse barely perceptible at 6 p. m., extinct at 9 p. m. Died at 12.30 a. m. August 18. Mind clear throughout illness. Cramps ceased 30 minutes before death.

Hahn had not been near or in contact with any person suffering with disease for weeks; had habitually slept in second story of house, which was occupied by self and wife only. Six persons, aged from 15 to 70, assisted in nursing him; none were attacked with the disease.

CASE 25.—*Reported by Dr. S. A. Foss, of Jefferson County, Ky.—Cholera —Death.*

"M. Russell, negro, æt. 55 years, farm-laborer, married, loaded his farm-wagon on the evening of August 17; took supper; was unusually cheerful; slightly intoxicated; slept well till 1 a. m. August 18, when he was awakened to go to market. Said he did not feel very well, turned over, and began to vomit. Purging immediately followed. Both continued at short intervals, accompanied by cramps in voluntary muscles. Thirst urgent; complained of great heat, and died in three hours from commencement of attack.

"This man resided eight miles south of Louisville, on east side of Salt River turnpike. House one and one-half story log; sanitary condition better than usual for that class of people. No stagnant water within half a mile. Drinking-water brought one-third of a mile, from a well fifty feet deep to coarse sand and gravel. One hundred people using same well with no bad effect. No stable or privy on premises. Ground thoroughly dry under and around the house. Russell had been in the habit of visiting the Louisville market weekly. He slept on first floor of house.

"Two people in contact with him during illness, six after death; none were attacked with disease. The locality where these cases occurred is decidedly malarial, but there have been fewer cases of malarial disease this autumn than since 1854."

History of a case of cholera, by Assistant Surgeon Charles Styer, U. S. A.

Edgar M. Cummings, private Company E, Second United States Infantry, æt. 21, admitted to post-hospital, Chattanooga, Tenn., June 23, 1873.

Was admitted to hospital at 8 p. m., at which time he was first seen. He stated that he had slight diarrhœa for several days, but not severe enough to induce him to apply for treatment. During the afternoon, he had been working, assisting in repairing a gun-carriage, and felt pretty well up to sunset. Shortly before I saw him, the diarrhœa had become worse, and he had cramps.

When I saw him in the barracks at the above hour, he was lying in his bunk with his limbs drawn up, and complaining of severe cramps in legs and arms. Pulse at the wrist barely perceptible, and sweating profusely. I ordered his immediate removal to the hospital, where he had to be carried.

I then found his legs up to the knees and his arms to the elbows were of dark-purple appearance, and no pulse perceptible in radial or tibial. The skin felt doughy and clammy, and the capillary circulation seemed to have entirely ceased. The cramps were of terrible severity, the countenance anxious, and the eyes sunken. His thirst was extreme, but there was no vomiting, nor was there any up to his death, although there was considerable retching. The symptoms indicated cholera; and, as this disease was reported in the town of Chattanooga, I so diagnosed the case.

I ordered pulv. opii, gr. j; calomel, gr. iij, mixed, which dose was repeated at 9 p. m., and again at 12.

June 24, but little change took place until 2 a. m., when he became more easy and fell alseep. During this time, the cramps had been incessant. Turpentine and chloroform were used freely externally, and also hot blankets dry.

I saw him again at 6 a. m. The attendant reported that from 2 to 6 he had slept at intervals, the cramps had not been troublesome, his stools had been infrequent; there was, however, no change in his general condition. His answers to questions were coherent and his mind rational, but the circulation in the limbs showed no sign of returning.

The discharges during the night were characteristic of cholera in color, consistence, odor. Mustard had been used freely all night externally over the whole surface of the abdomen. At 8.30 a. m., he rallied, seemed better than he had been during the night, and asked for a cup of tea. In about ten minutes, when the tea was made, he was utterly speechless, unable to swallow, and comatose, evidently dying.

Death occurred about 9 a. m., (24th.) There was no true collapse until just before death. At 6 a. m., I thought his recovery probable; at 8.30, I considered him out of danger; and at 9 he was a corpse.

I learned subsequently that, on the 23d, this man had eaten largely of unripe blackberries and had drank enormous quantities of water. He never indulged in alcoholic drinks, and was one of the most robust men in the garrison. He had not been to the town of Chattanooga for several days.

Case reported by Dr. Edgar, of Saint Louis, Mo.

Mr. P., æt. 62 years, merchant, remained late at his store on Fifth street, between Olive and Locust, actively employed until 11 o'clock, when he complained of feeling too tired to go to his dwelling on Pine street, between Eleventh and Twelfth. Having a bed in one of the upper stories over the store, he retired on that a little before 12 o'clock at night. At about 2 a. m. he was called up to the water-closet, which was in the building, hence the character of the stool was not known further than that it was "thin as water;" from this time until 6 o'clock in the morning he had six more stools, all of the same character, during which time nothing had been taken, except a spoonful of brandy occasionally with the water he drank. He now, at 6 o'clock, vomited freely a liquid thin as water, after which he was so exhausted as to alarm his clerks, who were with him, and who procured a carriage and removed him to his residence on Pine street, as above. A few moments after his arrival, about 6½ o'clock a. m., I saw him, and the stool which had just passed him, which was copious and rice-water in character; also the vomited matter was similar; skin cold, and covered with perspiration; no discharge of urine since the attack; cramps were slight, voice husky and feeble. The patient was placed on a mattress, head low, extremities at once enveloped in flannels wrung out of hot mustard-water; also the same were placed over the bowels and chest. Pounded ice, with a few drops of whisky, was fed to him almost constantly; and twenty drops of the following recipe, commonly known as Hartshorn's mixture, was given every fifteen minutes, viz:

R. Chloroform,
Tr. opii.,
Tr. camphor,
Arom. spts. ammonia, aa ℥iss.
Creosote, gtt. iij.
Oil cinnamon, gtt. v℥j.
M. Spts. vini gallici, ℥ii.

S. Dose, 20 drops every 10 or 15 minutes until relieved.

The mustard-fomentations were kept up faithfully, and all the ice allowed that was desired.

The vomiting continued more or less for an hour, the intervals of relief being prolonged until it ceased; also, but one discharge took place from the bowels after the first portion of medicine was taken. As a slight acid odor seemed to come from the vomited matter, *chalk* was added, five grains to each dose, until thirty grains had been taken. As the circulation improved (the pulse having been 60 and small) and the surface became warm, he was wiped dry, and lightly covered with a blanket; no food allowed for twenty-four hours after the vomiting ceased, only ice and brandy in small quantity, and not the slightest muscular effort permitted. Convalescence commenced about twelve

hours after the attack, and about six hours after treatment was commenced. Although I have had patients to die under the above method of treatment, I am confident my success has been better with it than by the mercurial or any other method I have tried. I keep the medicine ready prepared, as it takes time to put it up, and particularly to get a clerk up at night to prepare it. The case I have reported was a well-to-do merchant, living in a clean, healthy part of the city. The vessels receiving the dejections from his body were provided with disinfectants liberally. No other case occurred in the house, or store where some ten or twelve clerks were employed; and I don't remember to have had a case during the season where a second case followed in the same family or house, except in one case where they used *water from a well* near the house, in a densely-populated part of the city. On my first visit to this house, several of the family had premonitory symptoms. I warned them not to use the well-water. They all recovered; but the father, who thought it a mistake about the water, and drank from the well, relapsed a third time, when he narrowly escaped death, but satisfied himself finally that it was the well-water.

Cholera case at the Cook County hospital, Chicago, Ill.

Name and age, Amelia Bazseler, fourteen years; nativity, Germany; diagnosis, cholera; admitted July 5, 1873; died July 6, 1873.

Ten days ago, the patient and family arrived from Germany. Soon after arriving, settled in a portion of the city in which they were obliged to drink surface-water. Father, mother, and one sister soon died of cholera morbus, or, perhaps, the cholera.

July 5, patient admitted about 4 p. m.; was taken with diarrhœa and vomiting during the morning. Had five dark-brown stools during the afternoon, and six during the night; the stools all the time becoming lighter.

July 6, rested none last night; had incessant calls for water. Had a stool about 6 o'clock this morning, and another about 8 o'clock. These stools were watery in consistence, resembling rice-water. Vomited frequently during the night. The vomited matter was green in color, and a great portion of it was what she drank. Patient manifested considerable uneasiness during the night, throwing herself from one side to the other, and troubled with cramps in the extremities. This morning (9 a. m.) patient looks dark and hollow about the eyes; extremities purple and cold; tongue covered with a yellow fur, through which the *red papillæ* appears; drinks much, but soon rejects it.

Ordered the following: Tr. capsici, oz. ij; tr. camphoræ, oz. ij; tr. opii, oz. j; syr. simp., add oz. ij; M.; S.; drachm j, every three hours; also, fifteen grs. of bismuth and five of piperine, every hour; morphia hypodermically; hot bottles to the extremities. Pulse 148; temperature 96½; respiration 26. A. murmur is heard in the base of the heart, accompanying the first sound. During the middle of the day vomited but little. Soon after taking the above medicine, the patient's extremities, which were cold, became warmer, and she began to perspire, but was still troubled with cramps in the lower portion of right leg. Called frequently for water. Afternoon, the extremities again became cold: pulse almost imperceptible, beats about 120 per minute; eyes sunken, dark color around the lids; lips very purple. She now (2 p. m.) became quiet, and was sinking; had one stool in the afternoon; sank and died about 4 p. m.

Notes of treatment.

NOTE I.—Dr. F. R. Alpuente, of New Orleans, reports a case in which chloral hydrate was exhibited with most satisfactory results. The vomiting and purging was arrested, a sleep ensued, during which convalescence was established.

NOTE II.—Dr. George T. Trezevant, of Tullulah, La., reports that the treatment adopted by him consisted of mercury, opium, and astringents, bromide and chlorate of potash, ammonia, chloroform, carbolic acid, stimulating embrocations, dry heat. During convalescence, alterative doses of mercury with ipecac and digitalis.

NOTE III.—Dr. S. Allen, of Centreville, La., reports the treatment employed was dry heat to extremities, ice-bag to spine, small but frequent doses of calomel, iced water *ad libitum*. When the preparations of opium were used, they were exhibited hypodermically. Dr. Allen reports the recovery of a female, five months pregnant, under this treatment, without miscarriage.

NOTE IV.—Dr. C. P. Whitehead, of Transylvania, La., reports his treatment to have been morphia, calomel, and iced water.

NOTE V.—Dr. James Johnston, of Denison, Texas, reports the recovery of a male from profound cholera collapse, after "enormous" doses of strychnia had been administered hypodermically.

NOTE VI.—Dr. Edward S. Frost, of Willmar, Minn., reports that the only cases among the Norwegians who recovered (two in number) were treated with tincture of catechu and opium at the commencement of the attack.

NOTE VII.—Dr. Le Grand G. Capers, of Vicksburgh, Miss., reports a case of pronounced cholera, in which, by the use of frictions, ice to the spine, morphia, capsicum, and calomel internally, atropia and quinine hypodermically, the patient reacted slowly. The note reads: "Commenced to react at 2 o'clock p. m. Left patient a 7 o'clock p. m.; reaction then apparently complete; pulse 105; respirations 23; face flushed; surface warm and apparently about 101°; no action on bowels since 2 o'clock p. m.; stomach perfectly quiet; urinated freely; regarded the case as safe; discontinued all medication; ordered absolute quiet, and a light broth to be taken if desired. On calling the next morning, found patient had slept comfortably until 10.30 o'clock p. m., when he had been suddenly aroused by a return of active symptoms, and died about 11 o'clock p. m., half an hour later."

NOTE VIII.—Dr. P. T. Baley, of Jackson, Miss., reports that the disease was easily checked in its early stage, when opiates, astringents, and mercurials were used. Absolute rest in the recumbent position was the most important aid to any treatment. In some cases, dilute sulphuric acid, with tincture of opium, was of advantage.

NOTE IX.—Dr. J. A. Tillman, of Deer Creek, Miss., writes: "The use of chloroform and camphor, as was recommended by Dixon, was unsatisfactory; and we relied almost exclusively upon mercurials, opiates, astringents, and stimulants, as the symptoms presented themselves."

NOTE X.—Drs. Felts and Palmer, of Osceola, Ark., report the successful employment of calomel, opium, and camphor in combination, and that chloroform or chloral hydrate, exhibited as stimulants, were more efficacious than alcohol in any of its forms. These gentlemen note the extreme difficulty of procuring efficient disinfection in country practice, from the isolation of families as well as from the apathy or penuriousness of individuals. Dr. Palmer obtained satisfactory results from a combination of morphia and chloral hydrate when used hypodermically, and notes the occurrence of several deaths from the injudicious use of opium.

NOTE XI.—Dr. H. P. Crute, of Chicot, Ark., notes the necessity of treating the disease when in the stage of the prodromata. Used chloral hydrate with most decided relief of four patients when fully collapsed. He was induced to exhibit the remedy on account of the extreme restlessness of his patients, and the results were so satisfactory that the doctor regretted his not having used the remedy more freely during the epidemic.

NOTE XII.—Dr. J. R. Dale, of Little Rock, Ark., reports that quiniæ sulph., tinctura ferri chloridi, tinctura opii, and brandy gave more satisfaction than any other combination of remedies.

NOTE XIII.—Dr. R. W. Mitchell, of Memphis, Tenn., writes: "When satisfied that I had cholera to contend with, as indicated by rice-water discharges, vomiting, cramps, and shrinkage of extremities. I ceased medication by the stomach, and used the formula given hypodermically:

"℞. Acidum sulphuricum, ℥ss.
Morphia sulphas, gr. ½
Spt. vini gallici, ℥iss.
Aquæ dist., ℥iij. M.

"The above was injected under the skin of the arms, legs, and over the stomach every hour until the symptoms of the disease were relieved."

NOTE XIV.—Dr. T. D. Johnson, of Clarksville, Tenn., reports the general treatment adopted was, internally, calomel, opium, and capsicum, with stimulants; externally, sinapisms, frictions, and heat.

NOTE XV.—Dr. G. B. Thurston, of Memphis, Tenn., writes: "The general treatment that I adopted was about as follows: Calomel and opium in alterative doses, say in two of the former to one of the latter, repeated every hour for several hours. In conjunction with this, used the following:

"℞. Ext. canabis indica, gr. xvj.
Gum camphor, ℥ss.
Chloroform, ℥ss.
Ol. terebinthium, ℥ij.
Mucilage accacia, syrup simplex, ää. ℥ss.
M. Aquæ cinnamomi, ℥i.
"S. Dose, a spoonful every one or two hours."

NOTE XVI.—Dr. J. T. Jones, of Nashville, Tenn., reports that, in the cold stage of cholera, he has used creasote with greater success than any other article of the materia medica, and suggests the following formula:

℞. Creasote, gtt. j.
Aquæ camphoræ,
Infus. gentian. comp., ää. ℥vj.

M. At a dose, and repeated every two hours.

Dr. Jones relies upon calomel, opium, camphor, creasote, and ice in the treatment of cholera, and deprecates the practice of loading the patient with bed-clothing in the vain hope of restoring surface-heat.

NOTE XVII.—Dr. W. F. Glenn, of Tennessee, reports that, when called at the inception of a case of cholera, he gave 30 or 40 drops of laudanum, and calomel, gr. ij, with camphor, gr. j, as frequently as required. Dr. Glenn states that whenever the dejections became rice-water in character, he never knew the exhibitions of opium to be of any benefit. In the stage of collapse, ice, iced water, and stimulants, in as large quantities and as often repeated as the patient could bear; but states that but two patients recovered who had become collapsed.

NOTE XVIII.—J. M. Meyer, M. D., of Boyle County, Kentucky, reports: "In regard to the treatment of the cholera-cases that occurred under my care, in the first three cases, I was called to see them at the earliest indications of disease; they all had copious stools, which were assuming the 'rice-water' aspect; strength giving way; thirst intense; some tendency to cramp. Ordered perfect rest in horizontal posture; warm clothing; *no frictions;* frequent potions of a strong solution of soda, hydrg. submur., and opii pulv., āā gr. j, to be repeated as often as necessary until the stomach became tolerant; then added quinine, gr. ij, and to be then repeated every two or four hours, as required. As soon as any discoloration made its appearance in the stools, the calomel to be omitted. *Water absolutely forbidden*, but cracked ice to be freely used.

"The fourth case had progressed further when first seen. The cramps were more positive, and the evacuations were clear and perfectly free from smell. The same general plan of treatment was more vigorously applied. Not having the means to give a full warm bath, I ordered light blankets soaked in hot water doubled, so as to cover the entire chest and bowels, wrung as dry as possible, and applied closely to the body, with warm covering; dry heat to the extremities; ice freely given. This case, although yielding to treatment, lapsed into secondary fever, which continued about ten days.

"The fifth case had progressed still further when first seen. Diarrhœa, which had existed during the previous day, became violent about midnight. He purged and cramped fearfully. Symptoms became all fully developed. The means already indicated were vigorously used. Morphia, gr. ¼, was given hypodermically, and this was repeated in an hour. In two hours' time, the violence of symptoms seemed to subside, and he was inclined to sleep. The symptoms, however, were again vigorously developed, and the case died in a few hours.

"Some time after death, the muscular irritability was distinctly visible."

NOTE XIX.—S. P. Craig, M. D., of Stanford, Ky., in conclusion of report of epidemic in Lincoln County:

"The following plan of treatment of the initiatory stage of cholera has, I think, presented better results than any other I have tried.

"Rest absolute and prolonged; hypodermic use of morphia repeated as often as may be indicated; calomel and camphor in sufficient doses; dry heat to surface of body and extremities. I have tried the sulphuric-acid treatment in two or three cases, with no good results."

NOTE XX.—L. D. Knott, M. D., of Bradfordsville, remarks upon his report: "Three of the fatal cases reported were fully collapsed, and

so nearly dead when I first saw them that no treatment was adopted. Calomel was freely exhibited; creasote and plumbi acet. were found of value as affecting the vomiting and purging; chloroform was useful for the cramps; and opium, bismuth, tannin, and sulphuric acid were freely used."

NOTE XXI.—D. O. Polin, M. D., of Springfield, Ky., reports that, during the continuance of epidemic cholera in Washington County, he obtained no results which encouraged him to place faith in the prophylactic effects to be obtained from the exhibition of quinine; nor did he obtain beneficial results from the use of atropia. He obtained good results from the use of veratria and dilute phosphoric acid.

In the cases which had not advanced beyond the stage of acute diarrhœa, when seen early enough, always found the exhibition of calomel and opium to be efficacious.

NOTE XXII.—I. B. Evans, M. D., of Riley's Station, Ky., reports that during the months of July, August, and September, nearly all the families in his practice suffered from malarial causes. Most of the cases of cholera seen by him had attended the Marion County fair, and nearly all had eaten freely of fruits, &c. In the treatment of cholera, Dr. Evans relied upon calomel, in doses of from grs. iij to grs. v, and the hypodermic use of morphia; dry heat, acid drinks; ice-water *ad libitum*. Discarded stimulating embrocations, but sponged the body freely with ice-water.

NOTE XXIII.—N. G. Leake, M. D., of New Haven, Ky.: In the majority of cases which came under the observation of Dr. Leake in the town and vicinity of New Haven, Ky., there was premonitory diarrhœa of a day or two before the violent symptoms occurred.

In all the cases that terminated fatally, uremic coma was fully developed in from fifteen to twenty hours. All the cases reported were the subjects of suppression of urine.

NOTE XXIV.—W. T. Chandler, M. D., of Taylor County, Ky.: cholera; four cases; two recoveries; two deaths.

In reporting four cases of cholera which occurred near to the Muldraugh Hill tunnel of the Ohio and Cumberland Railroad, Doctor Chandler remarks that these cases were preceded by many cases of cholera-morbus and dysentery. The cases were isolated and at no time had come in contact with each other. They had all been residents of the "Hill" for some months, and neither of the four cases had been under any treatment for the premonitory diarrhœa. He reports many cases of acute diarrhœa which occurred among the employés of the railroad-company. All who applied for treatment at the commencement of the attack recovered. Great reliance was placed on the free use of dilute sulphuric acid.

NOTE XXV.—Dr. James A. Carr, of Kentucky, reports that the remedy most relied on in the treatment of cholera was opium in combination with camphor and calomel; and that, if used in sufficient doses during the stage of premonitory diarrhœa, the disease was most effectually checked. The exhibition was made in the form of pills, each containing opium, gr. j; calomel, gr. ij; camphor, gr. iij. Dr. Carr states that although he frequently gave as many as four of these pills after each dejection, in no instance was narcotism induced.

Dr. Carr joins in the opinion that when cholera is prevailing as an epidemic, *every diarrhœa is cholera*, and that in this stage the disease is as readily controlled by opium and calomel as intermittent fever is checked by the use of quinine. Dr. Carr is convinced by his observations that by the use of calomel, the consecutive symptoms of the disease will be far less troublesome. In from eight to ten hours after a choleraic diarrhœa has been checked by the use of opium and calomel, Dr. Carr has recourse to castor-oil.

NOTE XXVI.—Dr. B. J. Moore, of Saint Mary's, Ky., reports 19 cases of cholera; 11 recoveries, 8 deaths.

Dr. Moore reports that eleven of the cases had been in attendance on the Marion County fair. Six of these eleven cases terminated fatally. He relied principally upon calomel, opium, and camphor, using chloroform, stimulants, hot baths, and heat as the cases demanded. Nitric acid and opium were also found useful, but opium was used with caution, and not as had been the practice in former epidemics.

NOTE XXVII.—S. T. Chandler, M. D., of Campbellsville, Ky., who treated, during the epidemic of cholera in 1854, some sixty to seventy cases of the disease in its various stages, records his experience as having been largely in favor of the use of dilute sulphuric acid in full doses and repeated every 15 to 30 minutes, until the vomiting and purging are arrested. In the epidemic of the present year, the same plan of treatment was adopted, and with like results. "The acid relieves the nausea, arrests the vomiting like a charm, and gradually the dejections are stopped."

The experience of Dr. Chandler as related in this note and in case 17, taken in connection with the note of his son, W. T. Chandler, and the case (1) of Dr. Jackson, goes far to corroborate the views expressed by Dr. Curtin in the July 12th number of the Medical Times.

NOTE XXVIII.—Dr. John W. Culley, of Lizton, Ind., writes: "Considerable reliance was, by Dr. H., placed on the following:

"℞. Ætheris sulphurici, f℥j.
Tinct. olei cinnamomi,
Tinct. capsici et myrrh., āā, f℥j.
Tinct. opii, f℥ss.
M. Tinct. camphor, f℥j.

"S. Dose, from one-half to one and a half teaspoonfuls every hour, or after each discharge from stomach or bowels.

"This, Dr. H. used in the first stage, and until the discharges were checked. It would not control the discharges in my hands. But one case that reached the third stage recovered. In all cases the urine was albuminous."

NOTE XXIX.—Dr. L. T. Miller, of Caseyville, Ill., reports that during the epidemic of cholera he relied upon opium, calomel, camphor, and capsicum, and that every case to whom this mixture was administered in the early stage of the disease recovered.

Dr. Miller writes: "From my limited experience with cholera, I am satisfied that many cases prove fatal which might terminate favorably if prompt attention was given them. Cholera seems above all others the disease in which 'an ounce of prevention is worth a pound of cure.' Many of my cases might have been cured had the 'looseness of the bowels' been attended to promptly; but, in the majority of the fatal cases, nothing was taken until after the occurrence of the cramps."

NOTE XXX.—Dr. J. J. Fyke, of Odin, Ill., writes: "The cases that died received no treatment until the disease was far advanced. There was scarcely any person in the infected portions of the town who did not have the premonitory symptoms, but the disease yielded readily to treatment when taken in the early stages. Treatment consisted in external warmth, hot cloths, sinapisms; internally, the preparations of mercury, carbolic acid, camphor, quinine, and ammonia. Those which proved most successful were opium, calomel, and camphor."

NOTE XXXI.—Dr. A. K. Van Horne, of Jerseyville, Ill., reports the case of a gentleman who was attacked with cholera after assiduously nursing a son who had died of the disease. As soon as he was taken sick, he commenced taking powders of calomel, opium, camphor, and capsicum. He did not vomit at all, *but the medicine passed through him in a few moments after taking each dose.*

During the epidemic at the town of Lebanon, Ky., a gentleman who was suffering from profuse and watery diarrhœa was given at night by his physician six powders, with directions to take one after each dejection. Having occasion to empty his bowels many times during the night, he went into his wood-shed, and had the dejections upon the light, dry soil. The powders were all taken during the night, each enveloped in a light wafer. At daylight, he found all six powders, still enveloped, lying upon the ground, where they had been passed during the night. In this case, the diarrhœa was with extreme difficulty arrested.

NOTE XXXII.—Dr. F. J. Foster, of Carmi, Ill., reports satisfactory results obtained from the exhibition of creasote and acetic acid.

NOTE XXXIII.—Dr. E. L. Stewart, of Carmi, Ill., found the use of dilute sulphuric acid and tincture of opium to relieve the intensity of the symptoms.

NOTE XXXIV.—Dr. R. E. Young, of Jefferson City, Mo., physician to the State penitentiary, reports that the treatment adopted at that institution consisted of the application of dry heat, dry frictions, morphia exhibited hypodermically, and calomel internally. Under this line of treatment, out of thirty-three cases treated at the penitentiary but three died. Four other cases, who were treated by digitalis hypodermically, all died.

NOTE XXXV.—Dr. John Baker, of Jefferson City, Mo., reports that his treatment of four cases of cholera consisted of calomel and morphia, with sinapisms and turpentine stupes, ice, and iced water *ad libitum*. Of these cases, two died. One of the cases who recovered was salivated.

NOTE XXXVI.—Dr. George B. Winston, of Jefferson City, Mo., notes that in the epidemic "there were some cases without any premonition whatever other than perhaps a psychical influence, strengthened by night and darkness, since it would seem that there was a decided nocturnal preference, or periodicity, in the occurrence of a very large majority of the cases."

Dr. Winston's line of treatment was morph. sulph., gr ¼, dissolved in a teaspoonsful of cold water, with calomel, gr. ij, floating upon the water, repeated after each vomiting, and as soon as the stomach would bear it; quinine, in 2 or 3 grain doses, repeated every two hours for ten or twelve hours.

NOTE XXXVII.—Dr. U. S. Wright, of Fayette, Mo., reports that, becoming discouraged by the unfavorable results which had attended the stimulating methods of treatment, placed a negro man, who had become fully collapsed without receiving treatment, upon full doses of calomel, without combination with any other drug, and adds, "to my intense surprise, he recovered."

NOTE XXXVIII.—Dr. James A. Ward, of Troy, Mo., reports that, in the treatment of the cholera cases under his care, he gave calomel and opium; used blisters, sinapisms; allowed no ice and but little water, but frequently sponged off the body with iced water, after which friction was made with a coarse towel. Found the following combination of use:

℞. Chloroform,
Spt. ammonia dil., āā, ʒj.
M. Cinnamon-water, ʒiv.

S. Half to be given at a dose, which was repeated every two hours.

The 7,356 cases of which full records have been collected, are presented as representing but a small portion of the actual number of cases which occurred during the course of the epidemic. Several months had passed after the subsidence of the disease before the extended work of collecting material for this report was commenced; and it was found that many obstacles existed to the individualization of a larger number of cases than those herewith presented. The deaths of several medical gentlemen, of much prominence in their respective communities; the devastating floods to which the lower valley of the Mississippi was subjected during the spring of 1874; and the unsettled social condition of a considerable portion of the area of infection, combined to form the principal obstacles to the more complete performance of the duty.

It is impossible to present a detailed report upon the treatment which was adopted during the epidemic of 1873. The data upon this point which were obtained are imperfect and not absolutely reliable; having, in the majority of instances, been supplied from memory, no records of treatment having been made during the progress of the disease.

The greater number of cases reported were treated with calomel, either singly or in combination with opium, acetate of lead, and stimulants. It would seem that the vast majority of the physicians who were actively engaged in the treatment of the epidemic adopted, and relied chiefly upon, this line of treatment.

Calomel was exhibited in heroic doses by some gentlemen, who claim for the remedy thus employed the most beneficial results. By others, it was given in small but frequently-repeated doses. Opium was largely used in combination by many; but others discard its exhibition by the stomach, and employ its alkaloids hypodermically. By many, favorable results are claimed for the combination of calomel, opium, and acetate of lead; others, yielding to a natural impulse, sought to induce reaction in the cold stage by the use of alcohol.

The cases which have been collected show that, in the treatment by calomel, in large and small doses, there was a mortality of 23 per cent.; calomel and opium, there was a mortality of 31 per cent.; calomel, opium, and acetate of lead, the mortality was 40 per cent.; calomel, opium, and stimulants, the mortality was 50 per cent. In cases where stimulants alone were employed, the mortality was increased to 59 per cent. Where the preparations of iron were used, the mortality was 33 per cent.; while from the acid treatment but 8 per cent. is recorded; of

the latter, the cases reported are scarcely numerous enough to afford reliable data, (64 cases with 5 deaths.)

In the 7,356 cases which have been collected, the mortality was 52 per cent.

The necessity of instituting treatment at the earliest moment after the occurrence of a diarrhœa was most generally recognized throughout the area of infection. Wherever physicians, during the progress of the epidemic, ceased the attempt to diagnose between cholera, cholera-morbus, and diarrhœa, and treated all cases that occurred as cases of cholera, the lists of mortality were reduced; while, on the other hand, increasing mortality was shown wherever too great reliance was placed upon diagnostic powers.

The evidence is conclusive that the exhibition of opium, followed by alterative doses of calomel, and absolute rest in the recumbent posture, almost invariably arrested the disease when in the premonitory stage. In the advanced stages, the entire range of the pharmacopœia seems to have been brought into use, with no better results than have been obtained in previous epidemics.

The experience of the writer is strongly corroborative of the beneficial results which may be obtained from the use of sulphate of iron and dilute sulphuric acid as prophylactics during an epidemic of cholera; and, further, that the most successful treatment of the disease is to be found only in all that is implied in the word sanation.

It will not be out of place at this time to note a most interesting series of experiments made by Nedswetzky during the epidemic of 1872, which were undertaken with the view of ascertaining the effect of the various medicines which have been employed in the treatment of cholera upon the bacteria found in cholera-dejections.

EXPERIMENT I—*Quinine.*—To two separate portions of rice-water discharges, each two drachms in quantity, was added, to one ten grains of the sulphate, to the other ten grains of the muriate of quinine, both in concentrated solution. On the second and third days, no changes could be observed. The bacteria lived and moved as before. On the fifth day, a film had formed on the surface of the fluid, which consisted of a granular mass. The forming bacteria made their appearance.

EXPERIMENT II—*Camphor.*—To two drachms of rice-water discharges, half a drachm of camphor was added. On the second day, no change could be seen in the bacteria. Small particles of the camphor floated upon the fluid, and between them swam the bacteria. On the fifth day, a granular mass had collected upon the surface of the fluid, and a new crop of bacteria.

EXPERIMENT III—*Carbolic acid.*—To two drachms of cholera-discharge, five drops of strong carbolic acid was added. On the second day, bacteria were found to be alive and moving. On the fifth day, the same was observed. Five drops more of the carbolic acid were added, (on the fifth day,) and the bacteria still lived and did not alter.

EXPERIMENT IV—*Tar.*—To two drachms of rice-water discharge; there was added one drachm, and in another experiment two drachms of tar, which floated upon the surface, and the bacteria remained alive. Although the fluid was several times violently shaken, they continued to live below the tar, and showed their usual movements.

EXPERIMENT V—*Calomel.*—To two drachms of rice-water discharge, ten grains of calomel were added. On the next day, the whole fluid had assumed a blackish color, and a sediment had formed at the bottom of the vessel. Between the particles of calomel, the bacteria lived and

moved as in their normal condition. On the fifth and sixth days, a new granular mass had formed.

EXPERIMENT VI—*Opium.*—To two drachms of rice-water discharge, one drachm of tincture of opium was added. On the second and third days, the bacteria remained alive. On the sixth day, a portion only of them had lost their ability to move.

EXPERIMENT VII—*Nux vomica.*—To two drachms of rice-water discharges, one drachm of tincture of nux vomica was added. The action upon the bacteria was similar to that of opium. On the tenth day, the bacteria were living, and only a portion of them remained motionless.

EXPERIMENT VIII—*Tannic acid.*—To two drachms of rice-water discharges, ten grains of tannin were added. In two hours, the fluid had divided into two nearly equal layers. The upper layer was transparent as distilled water. The lower layer, on the contrary, was thick, opaque, and had a grayish-white color. In the upper layer was a very small quantity of motionless bacteria. In the deposit there were altered epithelial cells, lumps of mucus, and an innumerable quantity of cholera-bacteria without life or motion. On the fifth and also on the tenth day, all the bacteria remained without motion; and when they were afterward transferred to distilled water they showed no sign of life.

EXPERIMENT IX—*Chloroform.*—To two drachms of rice-water discharges, one drachm of chloroform was added. The bacteria ceased at once to move, and remained in this seemingly dead condition for several days; but when transferred to distilled water, a few came to life.

EXPERIMENT X—*Sulphate of iron*, in concentrated solution, acted fatally upon bacteria in the rice-water fluid. They ceased at once to move, and assumed the position and shape of dead bacteria, and when transferred to distilled water they did not come to life.

EXPERIMENT XI—*Chlorine-water*, (chlorine, ℥ss; aquæ, ℥vj.)—To two drachms of the rice-water discharges, two drachms of dilute chlorine-water were added. In this the bacteria died at once.

EXPERIMENT XII—*Sulphuric acid*, (acid, gtt. xx; aquæ, ℥j.)—To two drachms of rice-water discharges, two drachms of dilute sulphuric acid were added. In this the bacteria died at once.

EXPERIMENT XIII—*Muriatic acid*, (acid, gtt. iij, to aquæ, ℥vj.)—To two drachms of rice-water discharges, two drachms of dilute muriatic acid were added. In this the majority of the bacteria died, and only a small number remained alive, but in a greatly-altered condition.

EXPERIMENT XIV—*Nitric acid*, (acid, gtt. xx; aquæ, ℥j.)—To two drachms of rice-water discharges, two drachms of dilute nitric acid were added. In this the bacteria died.

EXPERIMENT XV—*Chloral hydrate.*—To two drachms of the rice-water discharges one drachm of chloral hydrate was added. The bacteria remained alive.

STATISTICS OF AGES.

STATES.	Under one month.	One month.	Two months.	Three months.	Four months.	One year.	Two years.	Three years.	Four years.	Five years.	Five to ten years.	Ten to twenty years.	Twenty to thirty years.	Thirty to forty years.	Forty to fifty years.	Fifty to sixty years.	Sixty to seventy years.	Seventy to eighty years.	Eighty to ninety years.	One hundred and thirteen years.	Unknown.	Total.
Arkansas	.....	.....	.....	.....	1	.....	3	3	.....	1	2	25	33	38	19	4	2	.....	1	.....	5	137
Alabama	.....	.....	.....	.....	.....	4	12	13	9	2	18	28	45	74	37	22	6	5	1	.....	7	283
Dakota	.....	.....	.....	.....	.....	.....	.....	.....	.....	2	1	2	.....	3	.....	1	1	2	.....	.....	43	55
Georgia	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	1	1	.....	.....	.....	.....	.....	.....	.....	2
Indiana	.....	.....	.....	.....	.....	4	6	3	6	6	26	40	57	70	30	21	14	6	1	.....	151	441
Illinois	.....	.....	.....	.....	2	4	3	4	5	4	21	39	71	68	44	24	16	6	1	.....	11	323
Iowa	.....	.....	.....	.....	.....	.....	1	.....	.....	.....	1	2	7	8	8	1	.....	.....	.....	.....	4	32
Kentucky	2	1	1	2	.....	21	29	20	17	13	48	231	373	355	265	165	101	37	6	1	24	1,712
Louisiana	.....	.....	2	1	.....	16	16	9	8	9	11	23	108	68	54	42	14	1	.....	.....	23	405
Mississippi	.....	.....	.....	.....	.....	.....	.....	1	.....	1	4	12	16	22	10	6	1	.....	.....	.....	.....	73
Minnesota	.....	.....	.....	.....	.....	.....	.....	1	.....	.....	1	2	2	1	.....	.....	.....	.....	.....	.....	.....	7
Missouri	.....	1	.....	.....	.....	5	11	14	11	11	41	81	147	154	100	63	34	9	1	.....	63	746
Ohio	.....	.....	.....	1	1	18	23	21	7	10	42	56	143	164	105	62	38	6	3	.....	40	740
Pennsylvania	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	1	3	2	.....	.....	.....	.....	.....	.....	6
Tennessee	.....	1	.....	1	3	33	68	44	39	34	94	212	541	480	264	112	66	10	4	.....	315	2,321
Texas	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	1	15	7	7	3	1	.....	.....	.....	.....	34
Utah	.....	.....	.....	.....	.....	.....	2	.....	.....	.....	.....	.....	.....	.....	2	.....	.....	.....	.....	.....	.....	4
West Virginia	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	2	5	6	9	6	5	2	.....	.....	.....	35
Grand total	2	3	3	5	7	105	174	133	102	93	310	756	1,565	1,522	956	532	299	84	18	1	686	7,356

STATISTICS OF SOCIAL CONDITION AND RESULTS.

STATES.	Male.	Female.	White.	Black.	Married.	Single.	Widowed.	Condition in life unknown.	Recoveries.				Deaths.				Record incomplete.				Total recoveries.	Total deaths.	Total results unknown.	Grand total.
									White.		Black.		White.		Black.		Cases.	Results.						
									Male.	Female.	Male.	Female.	Male.	Female.	Male.	Female.		Recoveries.	Deaths.	Unknown.				
Arkansas	88	49	69	68	55	80	2	.....	22	12	19	10	25	10	22	17	.....	.....	.....	.....	63	74	.....	137
Alabama	168	115	151	132	129	153	1	.....	54	28	15	5	38	31	61	51	.....	.....	.....	.....	102	181	.....	283
Dakota	10	2	12	.....	5	5	2	.....	7	1	.....	.....	3	1	.....	.....	43	1	42	.....	9	46	.....	55
Georgia	1	1	2	.....	2	.....	.....	.....	.....	.....	.....	.....	1	1	.....	.....	.....	.....	.....	.....	.....	2	.....	2
Indiana	203	171	353	21	212	148	14	.....	112	91	2	5	81	69	8	6	67	56	.....	11	266	164	11	441
Illinois	179	144	312	11	183	108	27	5	39	27	.....	1	132	114	8	2	.....	.....	.....	.....	67	256	.....	323
Iowa	23	9	32	.....	15	17	.....	.....	8	5	.....	.....	15	4	.....	.....	.....	.....	.....	.....	13	19	.....	32
Kentucky	954	750	1,051	653	979	672	53	.....	342	246	137	124	264	199	211	181	8	.....	.....	8	849	855	8	1,712
Louisiana	252	153	217	188	203	174	6	22	33	37	19	9	93	54	107	53	.....	.....	.....	.....	98	307	.....	405
Mississippi	39	34	32	41	30	27	5	11	14	5	7	14	8	5	10	10	.....	.....	.....	.....	40	33	.....	73
Minnesota	3	4	7	.....	2	5	.....	.....	.....	2	.....	.....	3	2	.....	.....	.....	.....	.....	.....	2	5	.....	7
Missouri	420	267	624	63	314	311	40	22	99	24	13	5	279	222	29	16	59	4	55	.....	145	601	.....	746
Ohio	373	356	687	42	354	293	39	43	171	187	12	5	180	149	10	15	11	.....	.....	11	375	354	11	740
Pennsylvania	4	2	6	.....	5	1	.....	.....	1	.....	.....	.....	3	2	.....	.....	.....	.....	.....	.....	1	5	.....	6
Tennessee	1,179	875	1,229	825	930	930	66	128	488	332	231	173	237	172	233	198	267	255	12	...	1,469	852	.....	2,321
Texas	27	7	33	1	9	22	3	.....	10	4	.....	.....	16	3	1	.....	.....	.....	.....	.....	14	20	.....	34
Utah	4	.....	4	.....	1	3	.....	.....	.....	.....	.....	.....	4	.....	.....	.....	.....	.....	.....	.....	.....	4	.....	4
West Virginia	23	12	33	2	28	6	1	.....	11	2	.....	.....	11	9	1	1	.....	.....	.....	.....	13	22	.....	35
Total	3,950	2,951	4,854	2,047	3,456	2,955	259	231	1,411	1,003	445	351	1,393	1,047	701	550	455	316	109	30	3,526	3,800	30	7,356

CHAPTER II.

THE ETIOLOGY OF THE CHOLERA EPIDEMIC OF 1873.

The joint resolution of Congress under which we have had the honor to act, calls for a report upon the causes of epidemic cholera, which is herewith presented, embraced under a series of propositions.

PROPOSITION I.

That Asiatic cholera is an infectious disease resulting from an organic poison, which, gaining entrance into the alimentary canal, acts primarily upon and destroys the intestinal epithelium.

While no miscroscopic changes have been found in the dejections that are peculiar to cholera, or which differ in any way from those observed in ordinary intestinal catarrh, certain abnormal conditions are always found in the bodies of those who die from the disease.

Macnamara, who has closely studied the disease, discusses this subject at length. From his work we abstract the following summary of the morbid anatomy of cholera:

I. The epithelium of the nasal passages and of the mouth is found almost completely destroyed after death during the collapse of cholera.

II. The epithelium of the pharynx and of the œsophagus is shed in large patches, and near to the orifice of the stomach is often found entirely destroyed. Similar changes in the cell-lining of the stomach are observed, the basement membrane between the orifices of the gastric follicles being covered by a whitish, mucilaginous-looking substance, beneath which the injected walls of the stomach may be seen. The trunks of the peptic glands are full of a similar material, which consists of epithelial particles, many of the cells having been destroyed and massed into patches of molecular matter imbedded in the mucous stratum lining the walls of these tubes.

III. In the small intestines the villi are found extensively to have shed their epithelium, and if the exudation with which they are found to be covered is removed by a stream of water, much of the basement membrane will be found denuded of its epithelium. The same condition is found in the tract of the large intestine.

IV. The epithelium in other portions of the body is found involved after death from cholera. The urinary tracts, and the cells lining the tubules of the pyramidal portions of the kidney, present the changes indicative of detached and altered epithelial cells.

Similar changes are found in the cells lining the alveolar portion of the lungs. The epithelium of the pleuræ, the abdominal cavity, and choroidal plexuses is also found involved. *Thudichum* asserts that the nerve-tubes and ganglionic cells of the gray matter become affected in the algide stage; "*that the cylinder axis separates and the nerve-marrow curdles.*" It is, however, probable that the changes noted in this paragraph are for the most part post mortem.

V. On opening the walls of the abdomen after death, in the collapse stage of cholera, the viscus lie back in a compact form deep in the abdominal cavity. No constant anatomical changes are to be found in the stomach, beyond the changes already described in the epithelium. Occasionally patches of ecchymosis are observed, but in many cases the organ is not even congested.

The mucous surface of the intestines in the majority of instances presents a uniform arborescent injection, with ecchymosed spots; this, however, is not constant, for the mucous surface of the intestine is often found to be pale and exsanguine. The veins are filled with a plug of thick, viscid blood.

The solitary glands and Peyer's patches are indurated. The mesenteric glands are in a state of hyperæmia. The spleen, from loss of blood, is lighter in weight and color than normal. The liver weighs less, its cellular structure is contracted, and its capsule wrinkled. The portal veins are filled with viscid blood. The gall-bladder is full of dark, viscid bile. The kidneys present only the epithelial changes. The lungs are collapsed and of but one-half their natural weight, congested; the posterior portions soft and easily broken.

In the majority of instances, the right side of the heart, the jugular veins, the cava and the coronary veins are full of blood, but the left side of the heart is empty and contracted, the pericardium containing but little if any fluid.

The sinuses of the dura mater are loaded with dark blood. The veins of the pia mater are in the same condition. Serous effusions have been observed in the arachnoid cavity, the meshes of the pia mater, and the sheath of the spinal cord.

During the epidemic of 1873, at Paris, Hayem conducted a series of post-mortem examinations, upon which he makes the following observations:

The only organs constantly involved are the intestines. The capillaries, the different layers of the epithelium, the sets of glands, and the villi had all undergone certain changes, but differed in no way from the changes observed in ordinary intestinal catarrh. In the blood there was found an increase of the white corpuscles and small fragmented globules. These are explained by the stasis of the blood in the algide period and the decrease in the proportion of water. No microscopic characters peculiar to cholera were found.

Through the kindness of Dr. Ben. C. Miller, the sanitary superintendent of Chicago, we are able to present the results of a series of microscopic examinations, which were made at his request by Dr. I. N. Danforth, of Chicago, the autopsies from which the specimens examined were obtained having been made by Dr. Marshall W. Wood, now of the United States Army. These reports are possessed of an additional interest from the fact that they are as yet the only published American investigations conducted in the epidemic of 1873.

CASE I.

The clinical history of this case is provokingly meager and deficient, especially when the fact is taken into consideration that the patient died in a public hospital, subject to the disciplinary regulations thereof. The brief notes before me were furnished by Dr. Hyde. From them I am able to record the following: The patient (I am not informed whether male or female) was admitted to the cholera hospital August 26, 1873; was married three weeks previously; had cicatrices of buboes and syphilides on the cutaneous surface, and an ulcer over the internal aspect of the left thigh which was probably syphilitic. The prominent symptoms of epidemic cholera were pronounced, namely, "vomiting, purging, cramps, cold breath, and rice-water discharges." I infer that collapse came on soon after the patient's admission, as I learn from Dr. Hyde's notes that milk was injected into the veins on the night of the 26th, or shortly after admission. Death occurred on the following day (August 27), and the necropsy was made by Dr. Wood on the evening of the 27th, between the hours of eight and eleven. Concerning the post-mortem appearances, I have exactly no information at all; the notes in my possession do not so much as indicate the sex of the patient. Dr. Hyde, however, was kind enough to send me the following specimens:

(1.) Termination of ileum and commencement of colon.

(2.) The lower six inches of the ileum, empty.

(3.) Section of the ileum, about six inches long from its central portion, with its contents imprisoned in the intestine by ligatures applied previous to removal.

(4.) Portion of mesentery, eighteen inches from ileo-cæcal valve.

As no pathological appearances are recorded in connection with the remaining organs of the body, it is fair to presume that they were all in healthy condition. Of course my own observations must be confined to the specimens enumerated above.

(1.) *Termination of ileum; that is, that portion of the canal immediately above the commencement of the colon.* The mucous membrane looked swollen, soft, of a peculiar ashy hue in some spots, unusually pale or blanched in other spots, and unnaturally red in still other places. Hence the surface of the membrane presents a singularly mottled or "speckled" appearance. An enormous number of elevated papules, each the size of a pin's head, may be both felt and seen. If the specimen be gently put upon the stretch and held between the eye and a strong light, groups of arborescent or stellate vessels may be seen which are not apparent in health. Under a hand-glass of moderate power, numerous minute vessels, turgid with blood, some of them tortuous and elongated, are brought into view; but it may also be observed that the inter-vascular spaces are unusually pale and translucent. The elevations or papules alluded to above are also brought more prominently into view, and are seen to be quite symmetrically arranged, thus indicating their origin in swollen Peyer's or solitary glands. If the finger be passed gently over the mucous surface, the minute elevations, consequent upon the swelling of these glands, can be readily felt, as well as a peculiarly soft, delicate, velvety feeling, which I do not remember to have seen described.

Microscopy.—Before detailing the morbid microscopic appearances, it will be expedient to recall the structure of the intestinal canal in health, that we may have some reliable

standard for comparison. A transverse (vertical) section of healthy small intestine, well-prepared and mounted, presents the following appearances: two well-defined compact layers, namely, a mucous layer and muscular layer; between these, a loose net-work of areolar tissue (the so-called submucous connective tissue) which binds the two layers together, and also serves as a support to the vessels in their passage toward the mucous membrane; in connection with, sometimes imbedded within, sometimes projecting slightly below the mucous layer, we find Peyer's glands (the so-called agminate glands) huddled together in "schools" or patches, and the solitary glands, which are slightly larger than the former, but precisely similar in structure. In addition to this, we find those peculiar projections of mucous membrane, called "villi," which float their free extremities in the lumen of the intestine for the purpose of absorbing, by virtue of their epithelial structure, the nutrient material within their reach. The villi as well as the floor of the intestine are coated with a compound layer of conoidal epithelium, which can readily be seen with a quarter-inch objective.

We are now prepared to appreciate the changes found in our choleraic specimens. I have examined several sections cut from the specimens above described. Under a power of about eighty diameters, the following appearances are noted: the mucous and muscular layers seem to have been much disturbed in their relations, and separated widely apart; between them a very beautiful, loosely-woven web of areolar or connective tissue is seen, sending its delicate filaments across the intervening space, with here and there a little vessel, making its way toward the mucous layer; the latter is unusually thin and unusually smooth on its free surface; not a single perfect villus can be seen, but a few "stumps" of villi are easily made out, as though the missing portion had been rudely torn away. Under a power of 260, the surface of the mucous layer is seen to be almost, in fact *quite*, denuded of epithelium, since not a single normal club-shaped cell can be seen. The mucous membrane seems to have passed through some scene of violence, during which its villi have been wrenched from their attachments, and its clothing of epithelium stripped from its surface and carried away. It seems almost beyond belief that a few short hours could have so totally changed the intestinal surface, but every section which I have examined from the specimen of intestine now under consideration presents precisely the same appearances. Peyer's glands do not seem to be much altered, quite to my surprise. Possibly they are slightly swollen, but not otherwise perceptibly altered. But, after all, this is not so surprising; the storm is too brief to affect tissues beneath the surface to any great extent. It is rather like a terrible tornado, desolating everything within its reach, but limited in its ravages to objects presenting salient points of attack. The submucous connective tissue and the muscular layer are both beautifully displayed, but neither present any evidence of disease, unless the unusual separation of the mucous and muscular layers be regarded as such.

(2.) *Commencement of the colon; that is, that portion immediately below the ileo-cæcal valve.*—With the exception of an unusual turgidity of the smaller vessels, no abnormal appearances were detected by the unaided eye. Nor does the microscope disclose anything in respect to the mucous membrane of the colon which could be classed as peculiar or distinctively abnormal, save the loss of its epithelium, as in the case of the specimen last described. The same singular tendency to separation from the muscular layer, upon the slightest pressure, is also to be noticed in the specimen now under consideration, and of course the same elegant display of intervening connective tissue.

(3.) *Portion of the ileum, about six inches above its termination in the colon.*—To the unaided eye the mucous membrane seems a little swollen; it is quite pale, and presents the same papulated appearance alluded to in connection with specimen No. 1; numerous stellate groups of turgid vessels are easily seen, and it is also observed that they sometimes appear irregularly distended and tortuous, with knob-like enlargements or protrusions here and there, as though they had been suddenly and forcibly injected with blood, and had, as a consequence thereof, suffered forcible rupture of their inner tunics in certain localities. To the touch the mucous surface seems soft, velvety, and water-soaked or *sodden*, as though it had long been macerated in tepid water.

Microscopy.—Under the microscope this specimen looks much more natural, and appears to have suffered much less violence than the one first examined. A power of 80 diameters shows the mucous and muscular strata sustaining their normal relations to each other; both layers, with the interconnective tissue, are handsomely shown, as well as the lumina of the over-distended vessels. Confining our attention to the mucous layer, we find that its free surface gives evidence of having passed through some violent convulsion, and of having sustained serious injury thereby. Most of the villi are gone; their ragged proximal ends or points of attachment are still seen, broken and torn, like the stumps that mark the course of a recent cyclone; some of them are half gone, leaving behind the proximal half more or less damaged; a few remain apparently intact, but *only* apparently, as we shall shortly see. Peyer's glands and the solitary glands are enlarged, swollen, and filled with a confused mass of cells, probably the half-grown epithelium violently hurried from its legitimate home. It now becomes evi-

dent that the little elevations or papules already referred to are the swollen and distended solitary glands.

Under a power of 260 diameters, the ragged remains of numerous villi are seen with great distinctness, and those which are apparently perfect are now seen to be shriveled and contracted, and also to be totally stripped of their characteristic epithelial covering. The shriveling of the villi is so great as to quite change their appearance, and suggest atrophy in marked degree. Of course some allowance must be made for the altered size of the villi, on account of the absence of the conoidal epithelium; but after making all possible allowance for that, the shriveling is yet undeniably great. The free surface of the mucous membrane is entirely deprived of its usual epithelial coating, in place of which we see an irregular layer of small, round cells, which are doubtless the progenitors of the future perfect ephithelial cells; in other words, the upper, exposed, and full-grown layer is gone, having been hurried away in the general uprooting of the epithelial structure; the lower layer still remains, and had the patient recovered, would soon have developed into a perfect conoidal epithelial coating, in accordance with its own law of type. Under the higher power, the huddled mass of cells, which in some instances completely fill the solitary glands, shows with greater distinctness, but the cells themselves present nothing requiring extended remarks.

(4.) *Specimen of the ileum, with its contents retained by ligatures, from the middle third of the canal.*—The intestine. The intestinal wall is excessively thin, and the inter-vascular spaces quite diaphanous; the vessels are intensely congested; the solitary glands are swollen and elevated above the surface; no ulceration.

Microscopy.—A low power (80 diameters) shows that the mucous layer is surprisingly thin, and that the slight pressure of the glass cover is sufficient to produce a wide separation between the mucous and muscular layers, thus displaying the areolar tissue and vessels intervening; the villi are mostly present, but much shriveled and contracted, and in some instances torn. Increasing the power to 260 diameters we are able to see that, although the villi are pinched and shriveled, they are not, like those already examined, entirely deprived of epithelium, but that they are generally clothed with a single dense layer of small, round, or polygonal cells, and that a true conoidal cell may occasionally be seen. But this layer of polygonal cells must not be mistaken for the true epithelium, which consists always of conoidal or club-shaped cells, and these, as I have just stated, are only occasionally seen. The upper layer of true conoidal cells is missing; the lower layer of cells, which would be conoidal if let alone, is still in place, and, in the event of the patient's recovery, would have been developed into typical conoidal epithelial cells. The floor of the intestine is also covered with a layer of similar cells; the exceeding thinness of the mucous membrane is still apparent, but nothing like ulceration, or localized loss of substance or solution of continuity, is apparent

(5.) *Microscopy of the intestinal contents.*—It will be remembered that the specimen now under consideration was sent to me with its contents retained by ligatures. The ligatures were removed immediately upon receiving the specimen, and the contained liquid allowed to flow into a conical glass. It was thin, watery, dirty clay or ash color, and in a short time separated into two parts—a dense grayish deposit and a clear watery fluid. A drop of the deposit magnified 260 times is seen to consist mainly of cells, but partly of granular matter in rather coarse granules. Concerning the cells I find: (1.) Single full-grown and quite perfect conoidal cells scattered here and there in disorderly groups; and these, it seems to me, are the few remaining cells of those which clothed the villi and coated the floor of the intestine at the commencement of the attack. These worn-out and cast-off conoidal cells are generally present in great number in the intestinal canal; in this present instance the majority of them had been carried away by the earlier discharges, but a few still remained, probably by lodging in the corrugations of the intestinal mucous membrane. (2.) Large patches of cells, nearly or quite full grown, which formed the first layer of cohering cells composing the epithelium of the villi. By "cohering cells," I mean cells so joined together by their peripheries as to adhere with sufficient tenacity to admit of being torn away from the villi, and probably carried out of the intestinal canal without very much disturbing their relations to each other. (3.) Smaller and more symmetrical, as well as more intimately united patches of cells, which are obviously the deeper layer of epithelial cells from the villi. These are half-grown cells, hurried off while yet in their childhood, and therefore prior to their having entered upon their functional life. While it is well known that the intestinal epithelium, like that of all other parts of the body, is being constantly thrown off in the form of individual worn-out cells, it is also equally well known that patches of cohering cells are *never* found free in the intestinal canal, except in conditions of grave and generally acute and, indeed, violent disease. In chronic intestinal diseases, a few cohering cells from the upper layer, usually in a granular or fat-bearing condition, may occasionally be found; but when large patches of still adherent cells, from the lower as well as the upper layer, are thickly scattered over the field of the microscope, we may confidently predict that the patient is in a condition desperate indeed, if not necessarily fatal; for it indicates the flooding of the intestinal canal by the most violent exosmotic action; a condition of things

which, when not produced by local irritants, or the most drastic cathartics, speaks of the invasion of the system by a profound "zymotic" poison. (4.) I also find an occasional isolated uncleated cell which has every appearance of being a white blood corpuscle; such I believe it is. In view of the well-established fact that these cells, under conditions of intense excitement, speedily become migratory in their habits, I think it is altogether probable that many of them acquire the power of ameboid movement, and, being aided somewhat by the out-flowing current of serum, escape from the vessels and make their appearance in the intestinal canal. In the latter stages of cholera this supposition becomes almost a certainty. For, in the first place, the villi have been stripped of their natural clothing of epithelium, which brings the capillaries almost to the surface—in some places, probably, they are quite exposed. In the next place, collapse is by this time fully established, and, if the exosmotic action is now less violent, the profound relaxation of tissue, especially of contractile tissue, produces the precise condition most favorable for migration of the corpuscles; lastly, the corpuscles themselves are by this time in the "ameboid" state, and are therefore ready to take advantage of the conditions which favor their escape. The presence of the white corpuscles in the intestinal canal, therefore, is not a matter to be wondered at: it is merely the inevitable result of the operation of established laws of pathology. As the specimen of mesentery, before alluded to, presented nothing abnormal, no remarks concerning it will be necessary.

CASE II.

The patient, Joseph Schere, was admitted to Saint Luke's Hospital on the 7th of September, 1873, with well-pronounced symptoms of cholera. Shortly after, he was sent to the Cholera Hospital, and from the time of his admission there, came under the notice of Dr. J. N. Hyde, who furnished me the clinical history, so far as he could obtain it, and notes of a post-mortem examination, made by himself. I cannot do better than insert Dr. Hyde's account of the case at length, which is as follows:

"The patient, an Alsatian, had been admitted from Saint Luke's Hospital to the Cholera Hospital, Chicago, on the 7th of September, 1873. When examined, almost immediately after admission, he was discovered to be in a condition of collapse, but was still vomiting and purging freely. The emesis was checked by the administration of a solution of carbolic acid, (gr. i ad oz i;) the purging, however, continued in spite of the medication pursued, which consisted chiefly of stimulants and the administration of beef-tea. Soon after the exhibition of the latter the stools lost their "rice-water" characteristics, and consisted largely of the undigested and unabsorbed nourishment given. The patient exhibited the "facies choleraica," had a coolness of the expired air which was very noticeable, and suffered from cramps. Specimens of twelve of his dejections were preserved for examination, in separate bottles, and numbered in the order of their occurrence. The entire surface of the body had been cool and damp, the lips, tongue, and cutaneous superficies were livid; there had been also extreme restlessness, thirst, feeble, rapid pulse, dyspnœa, complete suppression of urine, sunken countenance, mental apathy, half-opened eyelids, and a partial recognition of his condition. Consciousness continued up to within a half hour of his death, which occurred twenty-three hours after his admission. The patient died in great agony, and was so violent that the attendants were obliged to hold him forcibly in bed. This was all of the previous history of the patient I could gather from the officials of the hospital. The patient was said to have been exposed to the disease in the State of Indiana.

"*Necroscopy* at 10 a. m. of September 9. Rigor-mortis was fully established. The body appeared to be that of a man not far from thirty-five years of age, somewhat emaciated. The skin of the face and neck was exceedingly dark; that of the abdomen and lower limbs of a natural color. The eyes were sunken, the abdomen not depressed, and resonant on percussion. The dura mater and pia mater of the brain were deeply congested, and the sinuses of the brain were filled with fluid, dark-red blood. The hemispheres, on section, presented an enormous number of "puncta cruenta," and the floors of the lateral ventricles, the velum interpositum, the pes hippocampi, and the valve of Vieussens, were all equally injected; a similar condition was found over the entire surface of the base of the brain, the surface of the cerebellum, the pons varolii, and the medulla oblongata. The arachnoid membrane everywhere was translucent and normal. No evidences of pathological products were anywhere visible. The lungs were of a dark slate color, and in their posterior portions were deeply congested. They were everywhere crepitant on pressure, and were neither solidified nor bound down by pleuritic adhesions.

"The heart was large, firm, and filled with fluid, dark, almost black blood. Firm, white heart-clots were found in each ventricle, well attached to the tendonous columns of the valves; the latter were of normal appearance. The right side of the heart was more fully expanded by dark blood than the left, but it was not evident that the left was entirely empty. The liver was of a normal size, of a dark-purple hue, and a section appeared to be gorged with venous blood. The gall-bladder was moderately distended, and its mucous lining smeared with a dark tenacious and tarry bile. The

spleen was enlarged to at least twice its normal size and was deeply congested, almost black on section. The kidneys were of natural size and color externally, but were also, on section, found to be congested and of a darker color than was normal. The apices of the pyramids were particularly engorged. The bladder was contracted fully and completely. It did not contain, as far as could be ascertained, a single drop of urine. Its mucous lining was entirely normal in external appearance, and presented no traces of the congestion so marked in the other viscera. The stomach was distended with fluid contents, consisting largely of beef-tea, and was not manifestly altered. The entire intestinal tract was moderately distended with fluid contents, of offensive, but not excessively offensive, odor, of the consistency and color of reddish pea-soup. The external surface of the intestines presented a color very peculiar, suggestive of a light chocolate, a tan and yellow combination; and this was true of every portion of the tract, but especially of the small intestines. The rectum was merely smeared with a reddish-yellow secretion, not sufficient to constitute "contents." The pancreas was unaltered; the mesenteric vessels injected; the omentum diaphanous and normal; the peritoneal membrane, abdominal glands, prostate, glands of Cowper, cerebro-spinal nerves, ureters, larger arteries and supra-renal capsules all appeared in a normal condition. No pericardial fluid was discovered.

"The following specimens were preserved for microscopic examination:

"Section of right hemisphere of brain; floor of lateral ventricle; pons varolii and medulla oblongata; left and right heart-clots; sections of liver, spleen, and both kidneys; ilio-cæcal section; portion of central tract of ileum, (the latter with contents undisturbed;) bladder entire, with attached prostate and a portion of the walls of the gall-bladder. The muscular tissue was normally red and firm. Description of the mucous lining of the intestinal tract to be found in the report on the specimens preserved."

Upon microscopic examination of the specimens of the various parts and organs sent to me, I found nothing, except evidences of recent congestion, save in the specimens of intestine; to those, and to the microscopic appearances of the alvine discharges, therefore, our attention may be limited. The intestinal specimens consist of the middle third of the ileum, the lower extremity of the same, and the upper extremity of the colon.

(*a.*) *The central portion of the ileum under a low power.*—It is evident that the mucous lining of the intestinal canal has undergone great and violent alterations. The appearances do not vary greatly, except in degree, from those observed in connection with Case I. The villi are nearly all torn away, and the remaining stumps present a rather ragged appearance. The solitary glands cannot be recognized; the disposition to separate from the muscular layer is much less than in the former specimens; the connective and muscular tissues seem quite normal. Under a higher power (260 diameters) patches of shriveled Peyer's glands are seen; the damaged condition of the villi is more apparent, and the mucous membrane appears to have been nearly stripped of epithelium.

(*b.*) *Ileum, near ileo-cæcal valve.*—In this location the villi seem to be almost destroyed; Peyer's glands are scarcely recognizable; the mucous membrane shows hardly a trace of epithelium, and in fact the intestine in its entire structure is so changed, that an expert might be pardoned for failing to recognize it.

(*c.*) *Colon near ileo-cæcal valve.*—This specimen does not show any very material change. In fact, with the exception of a somewhat shriveled and pinched appearance, and the loss of the upper stratum of its epithelial coating, there is nothing about it worthy of mention.

Microscopy of the choleraic discharges.—I received from Dr. Hyde eleven bottles containing specimens of the dejections, numbered from one to eleven, in the order of their occurrence. I am not informed at what stage of the disease the first discharge occurred, or how long before death the last one took place. As, subsequent to the passage of the first two or three specimens, the patient was assiduously plied with beef-tea, the greater portion of which was unabsorbed, the microscopic appearances are largely modified and masked, and their value correspondingly lessened thereby. A great amount of granular matter was present, in the form of very large oblong masses of a light gray or ash color. On being gently compressed by the covering glass these masses separate into smaller masses, and if the pressure be still increased, these secondary masses are separable into very minute granules, which are probably composed of albuminous matter derived from the blood. I also observed occasional oblong patches of small round or polygonal cells, probably epithelial cells thrown off from the villi and floor of the intestinal canal; and, scattered here and there, an occasional full-grown epithelial cell, not yet carried out of the intestine, but looking cloudy and nebulous, as though it had been for some time macerated in the intestinal contents. About the same appearances, with the addition of a few free oil globules. The sediment consists largely of oil globules and floating masses of granular matter; an occasional patch of aborted epithelial cells may be seen, but they are less abundant than in preceding specimens. The appearances are chiefly marked by the presence of extraneous matter derived from the beef-tea, of which the patient partook frequently.

elements by thorough filtration and the other not. *The effect in both instances was the same.*

To determine the final points, a current of air was made to pass through fresh cholera-discharges, both disinfected with carbolic acid and not disinfected, and then conducted through two separate vessels which contained respectively an indifferent fluid-medium, and one adapted to the support and development of any living forms which the current should bring to it. The two fluids used were distilled water and the fluid of Cohn. In a short time, in the fluids communicating with the undisinfected discharges, a considerable number of form-elements had accumulated, which proved to be almost exclusively the bacteria which are usually found in putrid animal-fluids. In twelve hours Cohn's fluid had become clouded and milky; in twenty-four hours it was covered with a thick bluish-green fungous slime, and emitted a foul odor. The distilled water remained clear.

Both of these fluids when injected into the veins of dogs and rabbits caused the same symptoms as after the injection of the cholera-discharges themselves. This was also true of the fluid of Cohn, after its fungous element had been quite removed by filtration, showing that these elements are at least not the only source of infection. Similar experiments with discharges which had been disinfected with carbolic acid showed that the organisms which the air-current brought to Cohn's fluid were incapable of propagation. Upon injection of the distilled water and fluid of Cohn, after previous disinfection of the discharges by carbolic acid, only symptoms of carbolic-acid poisoning were manifested.

Drs. Lewis and Cunningham, in a report of microscopical and physiological researches into the nature of the agent or agents producing cholera, (Calcutta, 1874,) after a series of experiments which consisted in injecting into the veins of large dogs alvine solutions obtained from both healthy and choleraic subjects, arrive at the following conclusions:

It appears from these results that the dejections of persons suffering from cholera, and also those of persons in good health, when injected into the veins, act in some cases as a poison; have the power of producing a definite effect on the intestinal mucous membrane, resulting in a disorganization of its substance.

The symptoms and pathological changes induced by both varieties of material, the choleraic and non-choleraic, present no differences; but, so far as our experience goes, the proportion of cases in which this result is attained when choleraic fluids are employed is considerably larger than when non-choleraic material is used.

It is advanced that the conclusions obtained from the series of experiments noted are a sufficient reply to and explanation of the circumstances which in 1833 led to the assertion that cholera was not an infectious disease. So conclusive seemed the facts that individuals who had tasted and drunk of cholera dejections, had fed the same to animals, or had inoculated themselves with the discharges, and yet all escaped the disease, that the dogma of non-infection is adhered to by many.

It has been urged against the theory of the infectiousness of cholera the supposed immunity to the disease enjoyed by the attendants upon cholera-sick. It has been asserted that in hospitals medical attendants, nurses, and laundresses are but seldom attacked with the disease, and this supposed fact is advanced as one proof of non-infection. Is not this a question worthy of careful study? Experience has profoundly impressed us with the belief that, proper precautions having been taken, cholera attendants may enjoy the most perfect security from the disease; but the question is, are those attending upon a case of cholera safe when the disease and its products are left to nature alone?

The narrative of the last epidemic furnishes sufficient evidence in answer to the assertion and the consequent inquiries. While in the majority of instances the attendants of cholera-sick escaped the disease, yet a sufficient number of instances are recorded to demonstrate the danger that exists. During an epidemic of cholera all the members of a community are not attacked. No pandemic has yet occurred upon the American continent. An epidemic of cholera does not occur at every locality which may be infected by cholera arrival. Of the nine-

teen men who drank of the infected water, as described by Macnamara, but five were attacked with cholera; fourteen remained uninjured.

During an epidemic of cholera, it is particularly those whose systems are vitiated by other diseases; those who are suffering from depression of the nervous forces from any cause, but especially that which attends excessive fatigue, fear, or debauches; those who live in open violation of all hygienic laws; those impoverished by want, who are especially liable to the disease. Anxiety, mental depression, alarm, overindulgence in unripe or unwholesome fruit or vegetables, the physical exhaustion produced by debauches of all kinds, the use of impure water, all may result in derangement of the digestive organs and diarrhœa, but they cannot of themselves produce cholera; in each and every instance it is essential that the specific poison be introduced. We have endeavored to demonstrate how the system of a healthy person may resist the invasion of the disease, but these individuals have nothing to resist with, and therefore succumb.

The assertion of the Registrar-General of Great Britain, "that the person who contracts cholera in England is *ipso facto* demonstrated, with almost absolute certainty, to have been exposed to excremental pollution, excremental sodden earth, excrement-reeking air, or excrement-tainted water," is peculiarly applicable to the American epidemic of 1873, as will be demonstrated by the narrative.

PROPOSITION III.

That cholera-dejecta coming in contact with and drying upon any objects, such as articles of clothing, bedding, and furniture, will retain indefinitely their power of infection. That in this manner a sure transmissibility of the cholera infection is effected, and that a distinct outbreak of the disease may occur by such means at great distances from the seat of original infection.

At the recent international sanitary conference it was unanimously affirmed that "Cholera can be transmitted by personal effects coming from an infected place, especially such as have served for the sick from cholera; and certain facts show that the disease can be carried to a distance by these effects if shut up so as to prevent free contact with the air."

To demonstrate the value of the facts upon which this proposition is based, it is but necessary to recall the experiments of Macnamara. This observer mixed a quantity of fresh cholera-dejecta with some fine sand, and allowed it to dry in the heat of the sun. The material was then inclosed in a packet and stored securely. After the lapse of seven years, a small quantity of this earthy-looking stuff was placed in pure water and again exposed to the rays of the sun. A careful examination of the water thus infected failed to determine any differences between it and water which had been treated in the same manner with a fresh cholera-stool.

If the organic matter of a cholera-dejection retained its characteristics in a mass of dry sand for an indefinite period, and only resumed the process of decomposition on coming in contact with water, the same phenomena may reasonably be expected from fabrics that have been subjected to the same influences. The only essentials demanded for the revival of activity in the infection is moisture and heat.

Numerous instances illustrative of this proposition are recorded in the narrative. Conspicuous among them is the instance of an aged lady who slept one night in the same room and upon the same bed that was

occupied by the initial case of cholera in the epidemic at Lancaster, Ky. The next morning this lady was taken with cholera and died. Thirty days had elapsed since the death of the former cholera-occupant of the bed, and sixteen days since the occurrence of the last of the preceding cases of the epidemic.

To refute the theory of infection, as illustrated under this proposition, the fact is brought forward of clothing which was infected with cholera-discharges having been washed with impunity on the part of those performing the work. It has further been asserted that this supposed immunity is the rule and not the exception. Instances will, however, be found in the narrative disproving such assertions, and it is advanced that when such work is performed with impunity, the security which the workers have is to be found in the limitation which exists to the infecting power. Clothing soiled with cholera-discharges is generally washed out immediately after use, and the water repeatedly changed. In hospitals where all soiled articles of bed-furniture are acted upon by steam, in closed caldrons, a very practical disinfection is secured; but instances are too numerous of cholera-attacks following work over the wash-tubs in which were cholera-infected articles, to allow the assertion to stand.

During the virulent epidemic of cholera in 1873, at the Winfrey House, at Columbia, Ky., the bed-linen and other articles which were soiled with the cholera-discharges were placed in tubs of water, which were left in the yard in rear of the hotel. At the close of the second day of the epidemic the building was abandoned, nothing but the dead was removed, and no one attempted to visit the house until some weeks had passed. At the re-occupancy of the building the clothing and other articles were found unmolested in the tubs. These articles were now washed by several negro women, and with entire immunity. Surely the limitation of the stage of infectious decomposition is sufficient explanation.

But more positive and conclusive is the evidence collected in the narrative of the distinct importation from Europe of the cholera-infection, which developed an epidemic of the disease immediately upon the arrival of emigrants at their point of destination, and only then after they had unpacked and proceeded to take into use articles of clothing that had been packed in cholera-infected Europe. These instances will bear enumeration.

I. The family of Tent Havre, from Holland, all of whom died of cholera at Carthage, Ohio, and from whom one cholera-death occurred in the town, and the disease was carried into Longview Insane Asylum.

II. The family of Antonson, from Sweden, who died, with but two exceptions, after their arrival at Crow River, Minn., and who communicated the disease to their friends, who had been for some years in this country.

III. The party of Russians, who, coming from the Odessa district of Russia, died of cholera after their arrival at Yankton, Dak., and who communicated the disease to the inhabitants of that city.

The portability of cholera having been established, a most interesting field of study is open, in which the agency of common carriers in the rapid diffusion of the disease is most prominent for consideration.

That the merchant-marine and war-vessels upon the high seas are active agents in the diffusion of contagious diseases has been demonstrated and accepted for ages. In the days of her prosperity, Venice recognized this agency, and as early as 1448 her authorities not only established the quarantine, but detecting one method by which disease

was diffused, decreed the destruction of the effects of those who died of the plague, the epidemic of that day.

Epidemic cholera having escaped the cordon of quarantines, the agency of common carriers (those who transport persons or goods by either land or water for hire) in effecting a wide diffusion of the disease is presented for earnest consideration. Conspicuously at the head of all carriers are railway and steamboat companies, the great porters of cholera-infection.

The age demands rapid transit. A traveller, anxious to arrive at his distant home, avails himself of the one of the many competing lines of railway that offers the greatest annihilation of space. So urgent is this demand that the journey which in the olden time consumed months, at the present is but a matter of days or even hours. A map of the United States is almost gridironed, and the community is primitive, indeed, that is not served by actual contact with or by close proximity to a railway in active operation.

A passenger-train upon any of these roads consists of a baggage-car, one or more coaches for the general traveling public, and generally a sleeping or parlor car for the more exclusive, in addition to the engine furnishing the motive-power. A railroad-train thus constituted becomes an active agent for the transportation of any contagious disease. The plush or rep-cloth coverings of the seats offer an asylum in their meshes to contagion, while the misnamed salons at the end of each car afford unequaled facilities for the distribution and transportation of disease.

Especial attention is asked to the interior of the salons. They will be found fitted with a urinal, which, connecting with a pipe, allows the urine therein deposited to fall upon the ground below the car; a commode, with a hinged cover, containing a funnel-shaped vessel, which empties below the car all dejections therein deposited; a large reservoir, with movable cover, which contains the drinking-water furnished for the occupants of the car. This in the majority of coaches completes the furniture of the salon; but upon some roads a small wire-gauze-covered box containing chloride of lime is added.

Upon well-appointed roads the urinal and the vessel of the commode, as well as their conducting-pipes, are made of a glazed earthenware, which admits of thorough washing; but many coaches are daily occupied by the public in which the material used is zinc, tin, or iron, and the least possible attention is paid to their cleanliness.

The reservoir of drinking-water is securely fastened to the partition-wall between the salon and the coach. A silver-mounted spigot in the general interior of the car compensates the traveler for the polluted source from which the water flows, and unless he has been thoughtful enough to provide his own drinking-glass, he must use the mug of tin or pewter, which, polluted by the contact of many lips, is unmolested in its filth.

What rational man would place the water-cooler which contains the drinking-water of his family in the water-closet or privy of his establishment? And yet upon all the lines of travel this violation of hygienic law is found.

Upon a railway-train, thus equipped, the task of proving an active agency in the diffusion as well as the transportation of disease is far from difficult.

At the Vienna conference it was unanimously affirmed "that man is the propagator of cholera when he comes from a place where the germ of the disease already exists." It is almost universally acknowledged that the excreta of individuals infected with cholera are the active

agents by which the disease is disseminated. That this diffusion may occur from actual contact with the excreta, or from the inhalation of an atmosphere impregnated with their products, or from the imbibition or deglutition of fluids or other substances infected with the same.

An individual at an infected point enters a coach which is a portion of a railway-train. The man may be at the moment suffering from the premonitory diarrhœa, or he may be seized with the same after the departure of the train. The commode of the salon is called into active use, and whenever the desire is present, with the egotism of the American traveler the contents of the rectum are discharged. It matters little to the individual whether the car may be at the moment passing an unoccupied portion of the country, drawn up at a railroad-station, or passing through a populous town or city; the instinct is satisfied, and the poisonous dejection falls below the car.

It is true that upon roads ballasted with sand a partial disinfection occurs, but who is prepared to assert that in the cloud of dust caused by the passage of the succeeding trains the active agent of cholera is not present? It is true that many of these dejections take place in isolated positions, where no one can be injured, but it is also true that the lines of railroads frequently pass in close proximity to dwellings and other habitations, and that the bed of the railroad is very frequently at a considerable elevation above the buildings.

At the city of Columbus, Ohio, the Pittsburgh, Cincinnati and Saint Louis Railroad, in the southwestern portion of the city, passes along an embankment and trestle-work from Randolph street until the Scioto River is crossed. On Spring street west the railroad is in front of the Ohio State penitentiary. On Spring street east and immediately under the bank of the railroad, is the small house at which the initial case in the epidemic of 1873 occurred. Crossing Spring street is the culvert to which reference is made in the narrative as having been tapped for the use of the penitentiary, and immediately below the trestle-work on which the railroad crosses the street is a large man-hole or vent which communicates with the sewer. Cholera was epidemic at Cincinnati and Saint Louis, as well as at other smaller points along the line of this road, and it is quite as rational to account for the occurrence of the epidemic at Columbus as due to the transportation of the cholera-poison from points previously infected with that disease, as to urge that a special endemic agency was established for that city.

The fetid atmosphere of the *salons* of many coaches is a matter of daily comment among those who are obliged to travel much during the heated term; and if any one doubts the effect of the noxious gases of these rooms upon the drinking-water stored up in them, a small quantity of the permanganate of potash will demonstrate the condition of the water after remaining a night in the reservoir.

Americans demand that transit should be not only rapid but luxurious. This demand is fully met by the Pullman Car Company, whose coaches are attached to nearly all railway-trains. These coaches are divided during the night into "sections," which are separated from each other by wooden partitions, and from the remainder of the coach by thick woollen curtains. Equipped for a night's travel, each section forms two beds; the lower composed of the covered seats, a mattress covered with some woollen fabric, two sheets, two pillows, (generally in woollen cases, which for use are covered with linen,) and one or more heavy blankets. The upper bunk is the counterpart of the lower, save that the frame-work of the bed is not covered with the same class of material,

and during the day is not exposed to contact with the persons of those who may be diseased.

Double glass sash protect each window, and heavy woollen curtains are further provided to protect the traveller from air, sun, and dust. The ventilation of these coaches is a matter of much care upon the part of those having them in charge, but the total air-space of an unequipped car is but 10,080 cubic feet; and allowing but two persons to each section, exclusive of the conductor and his porter, there would be *per capita* a vital air-space of 504 cubic feet. The vital capacity of the coach is, however, materially reduced by the *salons* and by the heavy furniture, which certainly occupy fully one-tenth of the air-space. In many of these coaches an apartment is partitioned off for the use of the more luxurious or exclusive travellers, differing in no way but its isolation from the remainder of the car.

To the credit of the company owning these coaches it must be said that great care is taken to keep all appliances in the most perfect order as regards cleanliness. The coach is ventilated as often as circumstances will admit. The furniture is cleaned frequently during each trip, and the entire coach is stripped and cleaned after each journey. The bed-linen is supposed to be used but once. The mattresses and pillows are aired and beaten. Indeed, so many and so great are the precautions adopted to secure cleanliness that at the first glance it would seem unjust and unnecessary to suggest further precautions, but the evils which have been enumerated exist, and until some remedy has been found, will continue to affect the health of communities through which they may pass.

During an epidemic of cholera, the construction and repair trains upon lines of railroad are as active agents in the dissemination of the infection as are fully-equipped passenger-trains. A construction-train gives employment to a large number of workmen, generally Irish and negroes. These hands sleep and eat upon the train, and the cabin-cars which they inhabit are often filthy in the extreme. Such a train moving over a road, passing the night at the switch or side track nearest the point at which the work is being performed, constantly visiting all stations along the line of the road, when once infected with cholera, will infect in turn each station that it may visit, unless extraordinary precautions are adopted.

Freight-trains are less active but still absolute porters of cholera-infection. Various articles of merchandise and baggage that may have become infected with the disease are by such trains conveyed great distances. The propagators of the disease are represented in the employés necessary for the management of the train. Numerous instances exist in the history of the epidemic of 1873 of the initial cases of the disease in local demonstrations being in the persons of employés of freight-trains.

All that has been said of passenger-trains applies with equal force to emigrant-trains, and during the years that cholera may be upon its westward journey, when such trains will in all probability convey large numbers of individuals from cholera-infected districts of Europe, there is occasion for unceasing watchfulness on the part of all communities through which they may be transported.

Upon the roads controlled by the Pennsylvania Company there is now in process of construction an especial car for emigrants, in which, while comfort is secured, there will be no fixtures which will prevent the coach being washed out at any and all times by a full stream of water, and in

this way not only filth will be removed, but the car will be kept from much which results from the presence of disease.

The class of common carriers who, next to railway companies, are most actively employed in the transportation and diffusion of infectious diseases are the vessels of all descriptions which are engaged in the navigation of rivers and other inland lines of navigation.

During the American epidemic of 1873 many striking and well-defined instances of their agency in the distribution of the cholera occurred. During the month of May, in that year, the disease was first brought northward along the line of the Mississippi River by infected boats; and during the ensuing months their agency was felt upon the Arkansas and Ohio Rivers, as well as streams of lesser magnitude. Nor was it in conveying the disease from the seat of original infection that their agency was evinced, for we find that the line of infection was turned, and that they conveyed the disease upon return trips to re-enforce the epidemic at the original point of departure. An inspection of one of the large steamboats that navigate the western waters will be all-sufficient to convince the most skeptical.

These vessels, compelled from the necessity of the waters navigated to be of light draught, are built with broad, deep decks. The lower deck, which is the largest, is for the accommodation of the machinery, freight, crew, and deck-passengers; the second deck, the sides of the greater portion of which are lined with state-rooms, is for the use of cabin-passengers; and an upper deck, or "the texas," upon which is a row of state-rooms for the use of the boat's officers; the whole is surmounted by the pilot-house.

All the available space upon the lower deck is occupied during a trip by freight, which consists of merchandise of all classes. The provision-chests and ice-boxes of the boat are generally found upon this deck, and to it are confined the class known as deck-passengers and the crew. A deck-passenger is one who cannot pay full fare, and in America at once indicates the individual as belonging to those classes of the community among whom infectious diseases find their most numerous victims. These persons are furnished with nothing but transportation. They sit during the day and sleep during the night in such positions as they may best secure; and this is generally found to be upon those piles of freight which will be for the longest time unmolested. In this they are but little better off than the crew, who when not at work occupy any place they may select.

It is among the deck-passengers of a river-steamer that infectious diseases, cholera especially, is conveyed from point to point. As the disease almost always occurs in a community unprepared for its advent, so it is upon these vessels. The disease may have been announced in cities or towns upon the route of the vessel, but it is not until the disease is absolutely fastened upon the boat that the officers are inclined to adopt any precautions. Thus it was in 1873. Boat after boat passed up the Mississippi and Ohio Rivers from infected points, upon which cases of cholera occurred; but the existence of the disease was denied, and the sickness was attributed to green fruit and vegetables, or to cholera morbus, that useful scape-goat!

A deck-passenger taken with choleraic diarrhœa uses the close and wet closet provided for his accommodation, and returns with soiled clothing to the pile of freight. The second stage of the disease occurs, and he vomits indiscriminately. The vomit and the involuntary dejections soak into the packages. The patient may advance to the stage of collapse, or the case may terminate fatally before attention is called to

it. It is impossible to define to what extent articles of merchandise may become infected. Science has not yet defined the stage of the disease in which the excreta are most actively infectious, although it seems to be indicated that the excreta of cases in the stage of acute painless diarrhœa and the dejections of those convalescent, or who have passed into the stage of typhoid, are absolutely more virulent in their infecting properties than those which are drenched with watery constituents; and the recent series of experiments at St. Petersburg show that the urine of individuals infected with cholera is capable of reproducing the disease.

The class of persons who are known as cabin-passengers are those whose systems are most generally in the condition to resist the invasion of the disease. The accommodations afforded them are ample for comfort. Every effort is made to secure cleanliness. The food furnished is good and well cooked. But among this class of individuals, those who may have contracted the disease before starting on the journey, or who are infected with the disease at any stage of its progress, will inevitably carry the infection with them; and the articles of bed-furniture which have become soiled will, when washed, the destination of the vessel being reached, affect the health not only of those who perform the work, but also that of the communities in which the workers reside.

It is suggested, as a remedy to the evils herein enumerated, that during any season in which cholera may have been declared epidemic in any portion of the United States, precautions be adopted upon all river-steamers to prevent deck-passengers and the crew of such vessels coming in contact with freight in said boats other than in the necessary handling; that a constant surveillance be kept upon the crew and deck-passengers, and every case of diarrhœa promptly treated; that during any season in which cholera is epidemic each steamer carrying passengers be compelled to add a medical man to the officers of the boat; that he be absolute in all matters of sanitary importance; and that he be provided with all stores that may be required for the use of the sick.

The General Government exercises supervising influence over common carriers of this class. The hull and machinery are subjected to rigid inspections. The captains and pilots are licensed. Costly hospital arrangements have been provided for the sick among the crew, and yet no provision has been made to prevent these carriers from transporting contagious diseases to and fro, as their owners may see fit. It is claimed for the Medical Department of the United States Army the original denunciation of these existing sanitary abuses.

The remarks herein made apply to vessels of all classes. The flat-boat, conveying a house in which live a family, who are generally the keepers of a store or drinking-saloon and the owners of a cow or other domestic animals; the barge, laden with heavy merchandise; the canal-boat or raft, all exercise a decided activity in the diffusion of contagious diseases.

PROPOSITION IV.

That the specific poison which produces the disease known as cholera originates alone in India, and that by virtue of its transmissibility through the persons of infected individuals or in the meshes of infected fabrics, the disease is carried into all quarters of the world. That cholera has never yet appeared in the western hemisphere until after its route of pestilential march has been commenced in the eastern world, and that its epidemic ap-

pearance upon the North American continent has invariably been preceded by the arrival of vessels infected with cholera-sick or laden with emigrants and their property from infected districts.

At the meeting of the International Sanitary Conference of 1874, it was unanimously affirmed "that the Asiatic cholera, susceptible of epidemic extension, is not developed spontaneously, except in India, and when it appears in other countries it is invariably by introduction from without."

During the year 1873, Pelikan startled the medical world by announcing the fact that cholera had become endemic in Russia, that the last outbreaks of the disease in Eastern Europe were not from new importations from Asia, but were from the seeds of the disease having remained latent from former epidemics.

The evidence upon which this opinion was based seemed, at the time it was advanced, to be unanswerable; but at the meeting of the British Medical Association of the same year, Netten Radcliffe, representing the medical department of the privy council, demonstrated the erroneousness of the conclusions to which Pelikan had arrived. It was conclusively shown that, although the disease lingered at Kiev, the Holy City of Russia, during the years of 1865, 1866, 1867, and 1869, it had been constantly re-enforced by successive cholera arrivals by way of the Red Sea, Persian Gulf, and North Persian route. One year later, and a conference of European scientists confirm the opinion contended for by Radcliffe, and India must continue to be recognized as the birth-place of cholera.

That cholera is a portable disease, is at the present day denied but by few observers; even among those who reject the contagiousness of the disease this fact is recognized.

The histories of all epidemics demonstrate that the disease appears wherever there are routes of human intercourse; that the infection is inevitably confined to such routes, and that the rapidity of its advance is regulated by the rate of human travel. Macnamara has shown—

"That as the communication between India and Europe has become more constant and rapid, so has epidemic cholera become more frequent in its visits to that continent, invariably pursuing the route followed by man in his passage to and from India, halting for a time in intermediate countries, where the seeds of the disease have been sown to bear fruit in due season, whence fresh germs have been again transmitted to other men, who have carried it a step farther toward the west. Thus has the malady been propagated from one human being to another until its influence has spread from the east as far as the western shores of America, *But cholera has never appeared in America unless Europe has been first affected; it has never broken out in the west of Europe unless the eastern part of the continent has been previously under its influence; and it has never been generated in the east of Europe unless correlated with an outburst of the disease in Turkey in Asia, Arabia, or Persia, nor have these countries been affected until the disease had previously burst out with violence over Bengal and traveled by slow and steady steps to the west of India.*"

Those nations nearest the *nidus of infection* suffer most frequently from cholera; those farthest removed suffer no less surely, but being at so great a distance from the focus from whence is the radiation of the disease, it is of necessity but an occasional visitant. So much is reasoned from the histories of past epidemics. What may be the future is beyond the range of human vision; but as the great laws of nature remain unchanged, and as heretofore no disposition has been observed on the part of natural forces to adapt their workings to the theoretical wishes of individuals, it is safe to conclude that the same great order of events will repeat themselves, influenced as to frequency by the rate of human ingenuity in the annihilation of space.

The only countries upon the inhabitable globe to which cholera has not as yet been carried, are the islands of the South Pacific, Australasia, the Cape of Good Hope and the western coast of Africa, the islands of St. Helena, Ascension, and Bermuda, the islands of the North Atlantic, and the western coast of South America. These localities are all separated from India by a wide extent of ocean, and during the past have had little or no commercial intercourse with that country. Lebert, in his retrospect over the course of this disease up to the present time, states that those portions of the globe not yet visited by cholera owe the immunity "partly to their comparative isolation and partly to accident." That cholera has not yet become acclimated in any portion of the globe outside the confines of India may be safely affirmed, while at the same time the well-established fact should be noted that in all the provinces of Hindostan the endemicity of the disease is not shown. From its birth-place in the Delta of the Ganges, the disease has effected a permanent lodgment in the provinces of Bengal, Madras, and Bombay, while in those that lie to the west and northwest, such as the Sinde, Rajpootana, the Punjab, it occurs but as an epidemic, developing itself only at the great religious and commercial gatherings, when the inhabitants of Bengal, Madras, and Bombay, with those of all other Indian provinces, as well as those of the adjacent nationalities, are congregated.

Hurdwar, in the Punjab, at the foot of the Himalaya Mountains, is spoken of as "a great nursery of cholera." At this city cholera has never originated *de novo*, but has always been developed during the great Hindoo festivals and fairs. Of these festivals Hurdwar is cursed with two; a yearly, which, occurring in the month of April, draws together a vast concourse of people, and one every twelfth year, which is attended by an almost fabulous number of human beings. Inspector-General Murry reports that at the Hurdwar festival of 1867 nearly three millions of people were gathered together, because of a report among the Hindoos that this would be the last of the great fairs, Hurdwar having lost its sacred character from the waters of the Ganges having been profanely diverted into the Ganges Canal. This immense number of human beings were collected together upon a bare, level, sandy plain, on the banks of the Ganges. The encampment occupied a space of about twenty-five square miles, and was regularly subdivided into streets and lanes. Shops were established from which an ample supply of good food was furnished, and pure water was provided from the Ganges. The people were placed in tents or in grass huts, where cleanliness was provided for and carried out strictly and effectually, the encampment being under the supervision of sanitary officers.

The people began to assemble during the end of March, but the fair was not regularly opened until April 3; at noon on the 12th of April the grand ceremony of bathing in the sacred Ganges was performed by the host, and during the evening of the same day cholera broke out. Up to this time, but five cases of the disease had occurred in this vast crowd; these cases had been at once isolated and treated. The cause of this outbreak is to be found in the fact that, during February of the same year, cholera had occurred along the range of the Himalaya Mountains; during March the disease was epidemic at Benares, far down the Ganges, and on the 25th of the same month it broke out at the sacred city of Allahabad. From all of these points pilgrims had gone to Hurdwar. By April 15 the vast crowd had dispersed, carrying cholera with them, and it is making no idle assertion to state that the cholera infection which was thus exported from the Hurdwar fair of 1867 died in the valley of the Mississippi in 1873.

It has been asserted by some American physicians that the epidemic of 1873 in the United States originated at or near the city of New Orleans; "that an importation of the disease was unnecessary, as the germs are always and everywhere present, only awaiting favorable circumstances to multiply and produce the effects customarily experienced from the general and abundant presence of cholera-poison."

By others it is asserted that the local peculiarities of the delta of the Ganges are reproduced in that of the Mississippi, and that as it has positively been demonstrated that the disease originates in the swamp-country through which flow the many streams that empty the waters of the Ganges into the Bay of Bengal, it may also originate in the swamps around the mouths of the Mississippi.

In support of such arguments, the interesting and seemingly plausible narrative of Estrazulas, which attempts the demonstration of an original development of cholera in the heart of South America during the year 1866 and the Paraguayan war, to originate which there were apparently all the factors of cholera present as they have been studied in the Sunderbunds, has of late been frequently advanced. But his narrative is robbed of its interest by the statement of Rego, the president of the Imperial Academy of Medicine at Rio de Janeiro, by which it is shown that before the disease occurred in Paraguay the cities of Pernambuco, Guanzy, and Rio de Janeiro had been infected by European importation; that prior to the outbreak of the disease in Paraguay, a troop-ship left Rio for the seat of war; that when two days out from port the troops on this vessel were attacked with cholera; that after entering the Parana River, but before coming within the lines of the army, she was turned back and placed in quarantine at the island of Santa Catharina. It is shown that this cholera-infected troop-ship was on the Plata and Parana Rivers a sufficient length of time to communicate with other vessels that did proceed to the seat of war.

It is recorded by historians that cholera has been endemic at the delta of the Ganges for centuries, and that as early as 1543 the disease was *exported*. It was a disease almost exclusively confined to the natives, and it was supposed that in them it was induced by their exposed persons, filthy habits, and poor food. After the English occupation of India the troops were frequently attacked, and as early as 1774 Paisley noted the efficacy of withdrawing troops from infected camping-grounds. At that time the disease was designated *true cholera morbus*, but at a later date Barnes supposed that cholera stood in the place of *periodical remittent fever*.

The sum of all observations that have been made by cholera-students goes to show that to produce an epidemic of the disease there must be a combination of certain powerful factors, each of which may of itself produce disease, some of the symptoms of which may resemble cholera, but that epidemic cholera is the result alone of their combination.

Peters points out as the principal factors of an epidemic of cholera:

1. An atmosphere impregnated with the products of fermenting human excrement.
2. An elevated temperature, with a still, stagnant, and peculiarly oppressive condition of the atmosphere.
3. Such meteorological conditions as have a marked tendency to favor the chemical decomposition of organic substances.
4. Lowness of site, swampy ground, moist soil, decomposition of vegetable matter, and all those causes which tend to produce bilious and remittent fevers.
5. Foul camping-grounds, filthy streets and yards.
6. Impure water.
7. Bad, spoiled, or defective food.

The summary of cholera-causes by Dr. Montgomery may be added to the list of Peters. It is as follows:

1. Undue exposure to the vicissitudes of climate, especially during cold nights following hot days.
2. Physical fatigue and nervous depression.
3. Undue abstinence or deprivation of food.
4. Excesses in eating, drinking, and licentiousness.
5. Vitiated atmosphere from all causes.
6. Direct exposure to the contagion of disease.

It has time and again been demonstrated that only in India do all these factors exist; that India alone, from her two hundred million inhabitants, the vast majority of whom are utterly reckless as regards sanitary laws, and are "naturally devoid of habits of cleanliness and decency," can furnish the dense masses of humanity among whom, when gathered together for their religious ceremonies and public fairs, cholera in an epidemic form originates.

It is difficult to appreciate the line of reasoning that could convince a healthy mind that any similarity exists between the delta of the Ganges and that of the Mississippi. The physical conformation may be similar, but certainly the condition of even the lowest, poorest negro living upon one of the Mississippi bayous is far removed from that of the Hindoo. It is readily to be conceived that did a congregation of from one hundred thousand to half a million American negroes annually come together in the swamps of the Mississippi delta, that among them cholera might possibly be developed. But America has never had occasion to witness such an event. The narrative of Estrazulas, before referred to, was the nearest attempt of the western world to manufacture cholera, but Dr. Rego has robbed the event of its charms of novelty and truth.

The spring-rains of 1874, in the valley of the Mississippi, were most extraordinary. The great western rivers refused to be confined to their banks. The Mississippi River in front of Memphis, "the City of the Bluffs," was more than forty-five miles wide. The levees were broken, and Arkansas, Mississippi, and Louisiana were inundated. Nor was this inundation confined to the Mississippi alone; all the streams and watercourses of the South overflowed their banks, causing immense loss of property and much human suffering.

Into Mississippi and Louisiana was swept the floating organic matter of the mighty river, and as the flood subsided the surface of the inundated country was covered with decomposing animal and vegetable organic matter and which were exposed to the fierce rays of the southern sun. What was the result? During the summer we received frequent accounts of congestive remittent fevers, terminating in a collapse resembling that of cholera, but the season passed away, and cholera, to the chagrin of the "indigenous theorists," failed to devastate the Mississippi Valley.

PROPOSITION V.

That the respiratory and digestive organs are the avenues through which individual infection is accomplished; that through the atmosphere of infected localities, cholera is frequently communicated to individuals; that water may become contaminated with the specific poison of cholera, from the atmosphere, from surface-washings, from neglected sewers, cess-pools, or privies, and that the use of water so infected will induce an outbreak of the disease.

The majority of observers unite in the opinion that by the medium of infected air, water, and food the cholera-poison gains access to the sys-

tem. Dr. Ball, of the Hôtel Dieu, thinks that although the digestive tube is the habitat, as it were, of the choleraic poison, yet the lungs are the principal viæ of infection. Dr. Murray, in his admirable paper on the "Channels through which Cholera is Communicable," records his opinion that in some instances the cholera-poison enters the system through the skin; and further states that the profuse cold perspiration of a cholera-patient, from its peculiar and characteristic odor, is an evidence of the elimination of the disease by the same means.

That the atmosphere of infected localities is an active agent in the diffusion of the disease is held by many observers.

Upon this point the investigations of Niemeyer induced the following record of his views:

> The cholera-poison is rarely taken into the system by drinking water containing it. As a rule, it undoubtedly enters the nose and mouth with the air, and is swallowed with the saliva. Using infected privies is so dangerous, because they are the favorite lurking-places for cholera-germs, and the gases arising always contain dust-like particles.

The results of Pettenkofer's theory are that the emanations from infected soil impregnate the atmosphere with the cholera-poison. It is indisputable that when cholera dejections are deposited in impure privies, cess-pools, or drains, the poison is propagated and diffused. Adair County, Kentucky, furnishes a marked instance.

In the rear of a livery-stable situated in the town of Columbia was a privy, the vault of which was filled to overflowing with putrid excrementitious matter, and the ground in its vicinity was saturated with the drainage from it. During the months of July and August some attempts were made to cause this privy to be disinfected and cleaned. These attempts at sanitary reform were resisted by the proprietor of the stable. Late in the month of August a negro boy, who had become infected with cholera in another county, came to this stable, suffering from diarrhœa, and made use of this privy. The diarrhœa became cholera, and he died; and from that infected privy an epidemic of cholera spread, which cost that community twenty-six valuable lives.

Water undoubtedly performs a most important part in the diffusion of cholera. Macnamara insists that an epidemic outburst of cholera can only occur through the drinking-water of the place becoming contaminated with cholera-matter.

The investigations of Dr. Snow in London, during the epidemics of 1849, 1853, and 1854, prove that cholera may be actively distributed through the medium of drinking-water.

The persistence of a cholera epidemic in Russia during the winter season was only partially accounted for by the habits of the Russian peasants, the construction of their houses so as to exclude all air, the faulty heating-apparatus, &c., until Dr. Routh pointed out that in the Russian settlements everything is thrown out around the dwellings; and that, owing to the intense cold and the great expense of transporting drinking-water, the inhabitants are in the habit of drinking the water from melted snow; that the snow used for this purpose has been frequently that upon which the cholera-stools have been thrown; and that by this impure drinking-water the epidemic is prolonged there can scarcely be any doubt.

The epidemic in Central Kentucky furnishes a striking illustration of the power of drinking-water in disseminating the disease.

Several isolated cases of cholera had occurred in the town of Lebanon, near to a small creek which forms one of the drains of the town. A few days after their occurrence the Marion County Fair was held upon

the grounds near Lebanon. As the water-supply was less than the demand, the deficiency was supplied from the town. Unfortunately a well was selected on low ground and quite near to the banks of this creek. On the second day of the fair a violent rain-storm deluged the country. The creek was filled to overflowing, and it was impossible that the surface-washings should not have infected this well. On the third and fourth days of the fair the water of this well was served as usual; and on the night of the last day (August 31) cholera, malignant in its type, was developed in all localities inhabited by those who had visited the grounds and drunk the water.

Great stress is laid upon the fact that subsequently the water from the same well was used by individuals with impunity, for which certainly the theory of vibrionic decomposition, which has been so fully noted, offers a sufficient solution.

PROPOSITION VI.

That the virulence of a cholera demonstration, the contagion having been introduced into a community, is influenced by the hygienic condition of the population, and not by any geological formation upon which they may reside.

It is shown by Macnamara that the large majority of the inhabitants of the world live upon alluvial soils; that they are crowded together in cities, towns, and villages; and that the lower classes, when thus congregated, especially suffer from diseases consequent on faulty hygienic conditions. The oxidation of their tissues being imperfect, and their food often unwholesome and scanty, the secretions of their stomachs must frequently be far less healthy than they would be under better sanitary conditions; and hence, such people coming in contact with cholera infection, would be more subject to its deadly influence than their healthier brethren.

Pringle, after an experience of twenty years in the service of the Bengal Presidency, notes the fact that comparatively few cases occur among the healthy, well-fed Europeans, when contrasted with the awful mortality among the weak and ill-fed pilgrims to the shrine of Juggernaut.

Libert writes:

> Nothing can be more capricious than the variation in the intensity of cholera in different places and at different times, even at different times in the same places. An imported case may end in a local attack confined to a single room or house; even a simultaneous importation of a number of cases at different points may exhaust itself in a number of local epidemics, while at other times a single case suffices to swiftly produce an epidemic or even a raging pestilence.

The narrative of the epidemic of 1873 affords many new and striking instances of the truth of this proposition and the assertions of the eminent observers who have been quoted. The writer has already presented his views as to the causes which modified the intensity of the epidemic and which stamped out the disease in many of its lines of ramification; but sufficient number of instances are recorded to show that wherever the disease found a suitable nidus prepared that there it was rapidly propagated, and that a virulent epidemic was instituted; but, on the other hand, when the cases of cholera were brought into communities in which hygienic regulations were in force, the disease was in many instances at once stamped out of existence.

It is submitted that in no way is the grand law of the transmissibility of cholera more strongly shown than in the instances which have been

so often quoted as proving that human intercourse has no agency in the diffusion of the disease.

The cordon de santé established by Austria and Prussia, in which a corps d'armée of each nation was employed, was ineffectual in shutting out the disease. Why? Because the line was repeatedly passed by Polish Jews engaged in smuggling, through whose agency the disease was introduced within the Austrian dominions. During the late war, the Government of the United States were never able to absolutely prevent intercourse at blockaded ports, and blockade-runners have passed into history.

Cholera exists wherever the disease has been carried, and finds a fitting and unmolested nidus. The disease does not of itself make sudden and mysterious transfers. Much has been said during the past forty years of the mysterious bound of cholera to New York City, in 1832, from Quebec; the last-named having always been held as the original point of infection in North America for that year; but the truth will no longer be concealed, and it has at last been demonstrated that New York City was infected with cholera by importation from the British Islands before the first cases occurred upon the Saint Lawrence River.

In no way is the transmissibility of the disease more clearly shown than in the eccentricity of its course in the development of the early cases of an epidemic. Cholera may appear in the heart of a populous city, concentrate its poison in certain localities of that city, and the small towns and villages in its immediate vicinity may escape entirely; or the outbreak may occur at a point of less note, and from there be only carried to larger towns after the epidemic has been fully developed. If in such instances an earnest investigation be had into all the circumstances of the origin and spread of an outbreak, it will invariably be found that the individuals engaged in establishing foci of infection have derived their power from a common cause. To illustrate, cholera has never yet appeared upon the North American Continent until after its advance has been announced in foreign territory, and hitherto the earliest cases of epidemics have occurred at the ports of entrance to the country. From the port of entrance the disease is distributed. A traveller infected with the disease at the point of original outbreak reaches his home at an inland city. Here he passes through the various stages of the disease. The excreta are thrown into the privy of his premises, and all individuals who use this privy are liable to the disease from the infected atmosphere. On the other hand, they may be thrown into drains, from which they may pass into sewers, which in small towns are only flushed with water after rain falls. In these sewers the specific poison of cholera comes in contact with organic matter of all description, and the process of molecular decomposition is rapidily advanced. The next outbreak of the disease will probably occur close to the outlet of said sewer, and at a considerable distance from the point of original infection; or, the drains of private houses which communicate with the sewer being unprotected by proper traps, the cholera-infected air of the sewer is discharged into the houses. The excreta of the cholera patient thrown carelessly upon the ground may by surface-washings contaminate the water supply of the family, and all who drink of the water thus infected become liable to the disease, although but a small number of the individuals thus exposed may be the subjects of an explosion.

The occurrence of a case of cholera is almost invariably followed by a scene of terror and confusion. In the excitement of the moment the

discharges are allowed to soil articles of clothing, to fall upon the floor, or vessels containing the excreta are allowed to stand many hours uncared for. There is good reason for supposing that the dejections of the first and last stages of the disease are more absolutely infectious than those which are drenched with the serum. Nedswetzky has shown that the vomit and urine of cholera subjects present the same characteristics of the dejections. It is an acknowledged fact that in the large majority of the early cases in a cholera epidemic disinfectants are not employed.

In a sick-room as thus described, all present may become infected, and the disease developing at the homes of the individuals, new foci are established.

It is earnestly urged that a recognition of the infectiousness of cholera robs the disease of its terrors, and that by cleanliness and disinfection it may be stamped out. That where these precautions are adopted, the occurrence of a case of cholera will influence the health of the other inmates of a house to no greater extent than they would be by a case of intermittent fever.

Small-pox is a contagious disease, and the unprotected individual coming in contact with the disease is always liable to it.

Cholera is an infectious disease, but this fatal power is developed only after the molecular matter contained in the excreta of the patient arrives at a certain stage of decomposition. Prevent this process of decomposition from taking place, and the disease is stamped out.

What vaccination is to small-pox, disinfection is to cholera.

PROPOSITION VII.

That one attack of cholera imparts to the individual no immunity to the disease in the future, but that the contrary seems to be established.

The assertion of Lebert that an attack of cholera usually protects an individual from a second attack, has not been sustained by the evidence collected during the epidemic of 1873. Numerous instances are recorded of individuals who recovered from an attack of cholera to succumb to the disease at a later period of the same epidemic; and indeed does this seem to be in the natural order of events. What more rapidly vitiates the constitution than an attack of cholera? The conditions being present that are recognized as the great auxiliaries of the disease, it is but logical to suppose that the specific poison of cholera reaching the alimentary canal, a fatal explosion of the disease would almost of necessity follow.

CHAPTER III.

ON THE PREVENTION OF CHOLERA, AS ILLUSTRATED BY THE EPIDEMIC OF 1873.

It being demonstrable that cholera is an infectious disease which is spread by the dejections of individuals suffering from choleraic diarrhœa as well as from the fully developed disease; that fabrics upon which these dejections have dried, are but the custodians of the poison which they are ever ready to deliver; and finally that this infection, in whatever shape it may arrive, only reaches the shores of North America after *a positive importation;* it becomes a matter of vital importance to inquire what means may be employed to prevent or arrest the development of the disease whenever it may appear upon the sea-coast.

That the importation of cholera in the persons of individuals may be prevented by proper precautions, or that the disease may be stamped out whenever importation is accomplished, is shown by the evidence collected to be most certain; but to secure the advantages which may be derived from this fact, concerted action is necessary. Of what avail is it that the most elaborate and costly defense is erected at all principal ports of entrance, if but a single opening be left unguarded? It is true that the greater the port the greater the danger, and the more complete should be the precautions; but the neglect of a nation's arming at all points has cost thousands of valuable lives. Of what avail is it that the health-officials at one point recognize the infectious properties of cholera, and concentrate their sanitary forces upon the disease whenever it may arrive at their gates and utterly stamp it out, when those of a sister city fail to attain to the same appreciation of the disease, open wide their gates, close their eyes to the entrance of the disease, and allow a focus of infection to be established from which pestilence and death stalk hand in hand. The results obtained by experienced observers demonstrate that the national means of precaution against a general epidemic of cholera are to be found in the *quarantine of observation.*

It is not proposed to enter into any lengthy consideration of the subject of quarantines. The literature of this subject is so extended, and the demonstrations so perfect, that only by means of quarantines conducted in accordance with the most enlightened hygienic requirements, can the health of a nation be preserved from contagious diseases of exotic origin, that to continue the discussion would be but to reiterate the opinions and expressions of far more experienced observers.

The term quarantine no longer implies that exercise of arbitrary power which has called out such hearty denunciations, and has given rise to so many powerful enemies to the establishment; no longer implies the detention of healthy individuals in the close and infected cabins of a vessel, which in times past cost the sneer "that quarantine instead of preserving actually involves a sacrifice of life;" no longer implies a loss to the mercantile interests of the nation that may amount to millions.

It has been clearly demonstrated that the city of New York was, in the year 1873, secured from four distinct importations of epidemic cholera by the "rigorous quarantine of observation," which, under the

superintendence of Health-Officer Vanderpoel, has more nearly approached perfection than any other similar institution which the United States has known. In the instances alluded to the most rigid and searching investigation was made into the history of all cases that had occurred. The fact that each case had been isolated, that disinfectants had been judiciously employed, and that the full period of incubation had elapsed; the vessels in three instances were allowed pratique, in the fourth instance the detention was less than forty-eight hours. No cases of cholera were developed upon either vessel after leaving the quarantine grounds, and none occurred among the passengers or crews after landing.

The narrative which is presented elsewhere demonstrates how searching was the investigation instituted, and the effect of such a quarantine is most evident. No longer will the officers of vessels when approaching land strive to conceal all evidence of disease which may have occurred during the voyage, but knowing that the hygienic precautions which they may adopt to isolate the sick and to prevent the spread of the disease will meet with a prompt recognition, they are stimulated to still more active exertions. It would be well for the nation were such enlightenment exhibited at all stations, but it is shown in the exhaustive report of Assistant Surgeon H. E. Brown, United States Army, "on quarantine in the southern and gulf coast," that the diversity of laws and the conflicting interests which at present govern all quarantine stations, render the performance of uniform and rigorous quarantine service inoperative if not impracticable.

But while the port of New York was closed to the introduction of the visible disease, yet vessels bearing infected fabrics passed to the city, and from them points of infection were established far in the interior of the United States. The history of the cholera epidemic of 1873 demonstrates that the disease was originally imported into the United States by means of infected fabrics; that during the summer of that year the epidemic received re-enforcements by the same means, and that the medium of infection was the clothing and other property of emigrants from the cholera-infected districts of Europe.

It was found that the individuals who became the mediums in this wide diffusion of the disease, arrived at the port of New York upon uninfected vessels; and that it was not until after their arrival at their points of destination, not until after their effects had been unpacked and exposed to the atmospheric influences, that any demonstration of the disease occurred.

European emigrants arrive at ports of embarkation either singly or in small bands; but large numbers, from all portions of the continent, are not unfrequently gathered together in miserable tenements, awaiting the hour of departure. The crowded quarters which they occupy upon shipboard prevent their access to the bulk of their effects, and the individual is limited to the use of hand luggage. Upon their arrival at the port of entrance, the natural desire to reach that point at which rest and a home is to be secured, demands rapid transit from the seaboard to the interior of the continent. The journey ended, boxes, bales, and bundles are unpacked, their contents exposed to the air, and immediate steps are taken which denote the establishment of a home. We would most earnestly insist, that during the years in which cholera is upon its westward march, that this moment, when the emigrant from Europe has secured his home, is the period freighted with the utmost importance to the inhabitants of North America; and that unless at such times extraordinary sanitary precautions are adopted, precautions

which include the personal property as well as the person of individuals arriving from cholera-infected districts, the United States will always be liable to the invasion of the disease.

It is respectfully submitted that the great sanitary necessity of the present is the establishment of a national sanitary bureau, which, in the hands of the chief medical officers of the Government, could be rapidly and economically organized.

It is submitted that through the influence of the General Government alone can reliable sanitary information be promptly collected from all quarters of the world; and that a daily or weekly health-bulletin from such a bureau would be of incalculable advantage to all local Boards of Health, to whom a national sanitary bureau would stand but as an advisory head.

Such a bureau, in receipt of information from reliable agents, would be able to designate to the health-officer of a port at which an immigrant-vessel was about to arrive the individuals among the lists of passengers whose former residence had been within the lines of infection, thus enabling that health-officer to isolate the effects of said individuals for prompt and efficient disinfection. We are most profoundly impressed with the necessity which exists for such action, and it is asserted that had such a bureau been in operation during the year 1873 thousands of valuable lives would have been saved.

During the months of August and September, 1873, it was the fortune of the writer to witness the epidemic of cholera in the counties of Garrard and Marion, of the State of Kentucky, and at a later period to investigate the manifestations of the disease as it appeared in eighteen States of the Union. In noting the effect produced upon the public when the epidemic of that year was developed, he was impressed with the following facts:

I. *The eagerness with which the public mind fastened upon anything which could give information as to the cholera.*

II. *The terror which was exhibited in most localities on the development of the disease, and the inefficient means adopted to prevent its spread.*

III. *The utter impossibility of instituting proper sanitary regulations in a cholera-district, after the disease had become epidemic.*

IV. *A wide-spread disinclination to admit the infectiousness of cholera, lest the terror of infected communities be increased and the sick be left uncared for.*

Experience teaches that the safety of a community threatened with an outbreak of cholera is to be found in the full recognition of the infectiousness of the disease; and it is submitted that when the laity have become possessed with the truth of this fact, when they learn that cholera should be met by sanitation, as small-pox is with vaccination, that the virulence of cholera epidemics will be lessened, and that its lines of advance will be checked. We are writing of America, and to the inhabitants of the American continent, who alone can be reached by cholera after it has accomplished ocean-transit.

The second great preventive of cholera is cleanliness. Cleanliness in what? Cleanliness in everything. To maintain the perfect sanitary condition of a large city, trained minds are devoted, and thousands of money are lavishly expended; but in the small interior towns, with some few bright exceptions, little or no attention is paid to the subject, each property-holder following the bent of his own mind. In these towns the streets and natural drainage-sources are the receptacles of filth. The ground within and around outhouses is the depository of human excrement. The negro in his cabin is permitted to rival the pollutions

of Jessore or Madras, while the only scavengers to be found are the hogs that roam the streets. The latter, after devouring indescribable filth, are presently served as articles of food.

To secure the best sanitary condition of a town, it should be the duty of the trustees to appoint an inspector, who should have at his command an efficient corps of laborers. By this inspector all that is detrimental to the public health should be removed.

To what should his attention be directed?

I. *To the condition of each house and its surrounding premises.*—Débris of all kinds should be collected in heaps and destroyed by fire. No rank vegetation, which too often conceals pernicious substances, should be allowed to stand, and when cut down should be destroyed by fire. Outhouses of all kinds should be inspected. Privies, stables, chicken-houses, &c., should be cleaned and disinfected. The débris should be buried in such position as not to affect the water-supply. Dirty and damp cellars should be cleansed, ventilated, and disinfected.

The water-supply should be rigidly examined, and property-holders required to place their wells and cisterns in good condition. Débris should not be permitted to accumulate upon the ground around the well. The well should be securely covered and closed. The sides should be banked up, so that the surface-washings may be from, not to it.

Despite all theories to the contrary, the action of the soil as a filter surpasses all others, and from a carefully-kept well pure drinking-water may always be obtained. If a privy-vault should be close to a well, or if a house or other drain should pass in its immediate vicinity, the walls of that well should be rigidly and frequently examined and water taken from the bottom of the well carefully tested, lest contaminating drainage may occur; and all wells so situated that they must inevitably receive impure drainage or surface-washings must be closed in such manner as will absolutely prevent access to their contents. Localities which in a past season had been infected, and where systematic disinfection had not been instituted during the prevalence of the disease, should be most carefully cleansed. Every portion of the premises upon which cases of cholera had occurred should be reached by the disinfecting agents. It should be borne in mind that it is far more prudent to err from over-zealous cautiousness than from negligence.

Individuals arriving in any community from a locality known to be infected should be at least subjected to a close surveillance. If their effects have been so situated that by any possibility they could have become infected, they should be subjected to sufficent disinfection. The individuals should be required to use a carefully disinfected privy until the uttermost limit which can be placed on the period of the incubation of cholera has been passed. For the efficient disinfection of clothing, &c., no plan proposed exhibits more favorable results than that of Dr. Ransom. In the use of the hot-air closet it was found that a temperature 250° F. was effectual in destroying the contagion of small-pox.

A rigid house-to house system of inspection, once having been established, should never be abandoned. An occasional inspection amounts to nothing. Eternal vigilance is the price of safety.

II. *To the condition of the natural drainage of the town.*—Water-courses and other natural drains should be kept free and unobstructed, and disinfectants should be constantly used throughout their length. The vegetation which almost invariably lines the streets of small towns and chokes the road-side drains should be removed; and then not left to decay in the center of the road, but should be removed beyond the town limits and there destroyed with fire. Ponds and pools of stagnant

water within or near the limits of the town should be filled up; filled up not with the *debris* of the town, but with fresh earth, which is one of the most valuable disinfecting agents.

Cholera having appeared in a town, it is desirable that the authorities select an isolated building, which may be used as a hospital. The house selected should be sufficiently commodious to prevent overcrowding, and to admit of the separation of the convalescents from the sick. This building should be placed in the charge of a competent physician, who should be assisted by a corps of nurses, and the hospital should be furnished with all necessary appliances. To this building all cases of cholera which occur should be removed. This suggestion referring only to that class of individuals who are unable to properly care for their sick, and to adopt such measures as will protect those who reside in their immediate vicinity from the infection.

A distinguished physician of Nashville has pointed out that in an epidemic of cholera want of proper food and the privations to which the lower classes are always subjected during an extensive epidemic adds fuel to the fire, and his suggestions of immediate relief of their wants is worthy the consideration of all town authorities.

The general cleanliness of a town having been secured, there remains to be noted that of individuals. Scrupulous care of the person secures the removal of what may and often does prove the nucleus of disease. Personal cleanliness is best secured by a daily bath. In the sultry and oppressive weather in which cholera most frequently makes its dread appearance, the bath, as hot as can be borne with comfort, affords the most efficient relief that one can secure. A thorough soaping and rubbing of the body with a flannel cloth removes all effete matter from the skin, and the free use of hot water imparts a cooling freshness, a solace from which none may be debarred; and which, taken in the early morning, invigorates to meet the fatigues of the day, and at night encourages refreshing and strengthening sleep.

The under-garments should be frequently changed, and those which have been worn during the day should invariably be removed on retiring to bed. Clothing that has been worn through the day should never be exposed in the sleeping-apartments during the night-hours, and should be well cleansed and aired before being again used.

Trivial and unnecessary as such rules may seem, the observance of them will be found of incalculable value.

III. DISINFECTION.—What vaccination is to small-pox hygienic regulations are to cholera. The rigid observance of sanitary laws presents to this virulent disease a wall which is almost insurmountable. The foundation of this wall—this line of demarkation between health and disease, between life and death—is undoubtedly laid in disinfectants. If the port of entry is passed by cholera, if the embargo there laid upon the disease has been insufficient to arrest its progress, it behooves each community to raise the wall for their own protection, and it is all the more necessary that the foundations are made sure.

The day has passed in which nauseous-smelling substances are looked upon as disinfectants. "To change the odor is not to disinfect. The odor produced by a putrescent animal mass may be covered, but the effete matter, the product of decomposition, is still present in the air that is breathed, although the nostrils, overpowered, fail to detect its presence." To borrow the words of Dr. Craig, "a true disinfectant must be antiseptic; that is, it must possess the power to destroy or to render inert the products of decomposition of organic matter or of morbid action in the living body through the agency of a reaction in which

the disinfectant itself undergoes chemical destruction." Therefore that agent is the most acceptable and useful which destroys utterly and for all time the effete matter with which it may come in contact.

A study of these agents renders it necessary that some one or other of the classes into which they have been divided should be adopted; but as it is unnecessary in a report of this character to enter fully into the study, and as we will endeavor to point out those which will be most valuable in the emergency of which we are treating, we will pass over the complicated classifications of Jeannel and others and adopt that of Dr. Craig.

1. *Destructive disinfectants*, "which act by oxidizing and consuming whatever organic matter they may come in contact with, attacking the more advanced product of putrefaction first."

2. *Conservative disinfectants*, "which destroy effluvia and organic matter when in small quantities, but are inert upon large masses."

The action of the agents which are classed under these grand divisions, and their application, will be considered when treating of the emergencies which demand their use, and those only will be noted that are attainable by all classes of individuals.

Experience has taught us that water, that indispensable element, is a most efficient agent in the diffusion of cholera-poison.

The question naturally arises, can water which is contaminated with organic matter be detected, and when detected can it be rendered by any process of purification safe for human use? Facts based upon extended observation demand an affirmative answer. To detect impure water, or water which has been contaminated by organic matter, Rawlinson says:

> If the water from a certain well or tank be placed in a tall glass, covered and exposed to the sun, and after twenty-four hours a drop be examined under the microscope, we find its surface covered with molecular matter and vibriones. We may be almost certain that the organic matter from which these vibriones are formed is capable of inducing cholera, supposing it, of course, to have been derived from cholera-ejecta.

This method of examination is certainly beyond the popular reach. Few individuals are skilled in the use of the microscope. Chemistry, however, affords a simpler means, and one which is within the reach of all.

Place a quantity of the suspected water in a glass vessel, and add, drop by drop, a solution of the permanganate of potash (which may be obtained from any chemist) until a pink color is imparted to the liquid. If after standing a short time the color disappears, it indicates the presence of organic matter. Add again the solution of the permanganate until the color is again produced. If the organic matter has all been decomposed, the water will after the lapse of hours retain the pink color; but if organic matter is still in solution, the color will again disappear. The greater the amount of the salt decolorized before the water retains the pink color, the larger the quantity of organic matter present in the water.

Before proceeding to the subject of the purification of water it is well to examine into the sources from which water for domestic purposes is ordinarily obtained.

In communities not provided with a carefully-delivered water-supply the purest water that can be employed for domestic purposes is that obtained from securely-guarded wells and from cisterns which are supplied with rain-water. They alone can be protected from surface-washings. Cistern-water, however, must be as carefully examined and tested as the well-water. Rain-water, it is well known, may contain or-

ganic matter of animal or vegetable origin. Even when it has been collected in a clean glass vessel, before it has come in contact with roof or soil, it has been found to be impure from organic matters, &c., which it has derived from the atmosphere in its passage through it, when taken near inhabited places.

Snow and snow water is much less pure than rain-water, for the crystals of which it is composed imprison the impurities of the atmosphere; and it is said "that snow frequently contains so much organic matter as to show confervoid vegetation under exposure to light."

The water of rivers, marshes, ditches, canals, and ponds is contaminated with organic matter derived from decaying animal and vegetable remains, and from *débris* of all kinds which necessity or surface-washings empties into them. Necessity demands that the water of large rivers shall be employed by the cities and towns upon their banks. In such instances all the aids which science affords are employed in the purification of the fluid before it is distributed for general use. But stagnant water, or the water of nearly dry streams or that of marshes, should never be employed for domestic purposes until it has been deprived of its deleterious constituents.

Spring-water may be contaminated from surface-washings or from organic matter with which the strata of soil through which it passes may be impregnated.

Impure water may be rendered serviceable and fit for use by boiling, which act precipitates most of the mineral constituents and destroys utterly all molecular matter.

Dr. Taylor, a returned missionary from China, reports that during a residence of many years among the Chinese no cases of cholera came under his observation; and this absence of the disease he attributes to the fact that tea is the beverage of the country; consequently nearly all the water which the inhabitants drink has been boiled.

By the process of filtration water may be thoroughly purified. Indeed, so perfectly does the combination of boiling and filtration purify water, that it is asserted that water in which cholera-discharges have been mixed loses entirely its infecting properties on being subjected to these simple expedients.

Dr. Peters suggests an excellent filter for the poor "in one of the largest-sized common red flower-pots, suspended at a convenient height in a shady place, and having the hole in its base plugged with a sponge, so as to permit only an exceedingly fine stream of water to pass through; the sponge to be frequently washed." Filters containing the black oxide of iron are said to be efficient in removing organic matter from water.

Of such vast importance does this subject become that during an epidemic of cholera in any community each family should be provided with drinking-water only after it has been subjected to some such process. Water so prepared, to which ice is added, is not only harmless but palatable. Ice may be used with impunity, for it is one of the purest forms of water when taken from a deep lake or pond. Faraday demonstrated the fact that water in freezing deposits nearly all of its constituents, and that the unfrozen portions contain the impurities.

Not unfrequently individuals are placed in such positions that they are unable to procure water which has been purified by either boiling or filtration. The permanganate of potash, which has already been noted, now becomes invaluable. The action of this salt is explained by Dr. Craig as follows:

When the permanganate is added in suitable quantities to impure water it converts the organic matter into carbonic acid, water, &c., undergoing itself a gradual decom-

position, with the deposition of insoluble deutoxide of manganese. * * * A method which will destroy organic matter in water without adding to it anything unpleasant or injurious is an evident desideratum at all times, and especially during the prevalence of cholera, and there is, perhaps, no method more effectual and convenient than that by treatment by the permanganate.

The practical application of this agent requires the use of from half a grain to one grain of the salt to the gallon of water, and about two hours are required for its action. In smaller quantities the solution should be added, drop by drop, until the pink color is evident. In a tumblerful of water but a few moments are required for its purification. At some of the Indian stations, where the water was offensive from decaying organic matter, a few drops of the permanganate purified the water almost instantly.

The peroxide of hydrogen, an autozone, is said to be still more efficient in the purification of water. It is a powerful oxidizer, and completely destroys organic matter with which it comes in contact.

The late Ashantee war called forth, among other notes of moment, the invaluable memorandum of Crooks on the purification of drinking-water. This observer demonstrates: 1. That the organic matter in impure water may be divided into three classes: (*a*) Matter in a state of putrefaction; (*b*) Matter ready to become putrid; (*c*) Matter which is slow to decompose. 2. That the permanganate of potash acts powerfully upon organic matter of the first class, but that its power over substances of the remaining classes is not only slow but uncertain. 3. That a mixture, consisting of permanganate of lime, one part; sulphate of alumina, ten parts; fine clay, thirty parts, is the most effectual purifier of drinking-water now known.

The use of impure water almost invariably results in the development of diseases of the alimentary mucous membrane, and of specific diseases, such as malarial and typhoid fevers and other affections; but simply impure water will not induce the disease known as cholera. To produce cholera from water, it is essential that the *water must have received a portion of the organic matter from the dejecta of an individual who is infected with the disease.*

An unknown traveler infected with cholera may deposit his dejections in such position that the water-supply of a community will become infected. None knew of his arrival; his departure was not noted; therefore when days have passed and cholera has been developed in persons who have used this contaminated water, the members of the community are at a loss to account for its development; but invariably a prompt and persistent inquiry along the line of infection will result in the detection of the individual who has scattered the disease.

It has been shown that privies, cess-pools, and sewers, the receptacles of human excrement and of other forms of filth, become hot-beds for the dissemination of the cholera infection, when the dejections of an individual suffering from the disease are mixed with their contents. It has been further shown that the effluvia from such localities is impregnated with decomposing organic matter, and that when inhaled this organic matter becomes mixed with the saliva, is swallowed, and the disease is reproduced.

Experience, that mighty expression of power, has demonstrated that certain agents, classed under the general head of destructive disinfectants, will most effectually destroy this poison. Of these agents we will select but those whose efficiency has been well tested, and whose small cost places them within the reach of all classes—namely, *sulphate of iron or copperas, lime, and charcoal.*

Each of these agents belongs to the class of destructive disinfectants;

each acts promptly and powerfully upon organic matter, and a combination of the three procures a most powerful disinfecting agent for the purposes now under consideration. Dr. H. C. Wood thus describes the disinfecting action of copperas:

It is antiseptic, but it also decomposes sulphureted hydrogen, precipitating sulphide of iron. It is decomposed by ammonia; the oxide of iron, a persistent, powerful ozotizing agent, being precipitated. It slowly but persistently attacks organic matter about it, oxidizing it, and being reduced to a sulphide of iron.

The experiments of Eckstein, made in a privy which was in daily use by a large number of persons, confirmed the value which has been assigned to this agent.

Macnamara found in cholera-dejections which were treated with sulphate of iron the infusoria and molecular action was instantly destroyed and did not recommence. His experiments fully substantiate the statements made by Dr. Budd in 1866, and by Dr. Angus Smith in 1869.

Lime as a disinfectant is of value from its power of destroying organic matter by the process of oxidation, as well as by its powerful affinity for water. The chloride of lime as a disinfectant is claimed by Eckstein to be equal if not superior to sulphate of iron. Macnamara found, however, that although its presence in a cholera-dejection arrested the action going on in the molecular matter for a time, it was very soon resumed. Charcoal acts as a mechanical disinfectant, entangling the organic matter in its meshes.

The most advantageous use which can be made of these agents is as follows: a mass composed of two parts of unslaked lime and one part of charcoal is cast upon the exposed surface of an impure privy or cesspool; upon this is poured after a few hours a solution of sulphate of iron, which has been prepared by adding the salt to boiling water in the proportion of five pounds to the gallon. A sufficient amount of this solution to saturate the mass should be used, and its application should be made daily.

In the consideration of agents which act as disinfectants to human excrement the value of fresh earth must not be overlooked. Its value during the late war in privy-sinks, which were daily used by large numbers of men, was fully demonstrated. The practice which is so universal through the Southwest, of defecating upon the ground and of leaving the excrement uncovered, should be rigidly discountenanced, and the use of sinks which may be disinfected should be insisted upon. The modern earth-closet, which is simple in its construction and so cheap as to be within the reach of all, should be universally provided for the use of females. Goodell has shown how many and how serious are the disorders to which the female is liable, arising from the miserably faulty closet conveniences which, especially in the country, are provided for their use.

During the prevalence of cholera it is most prudent for those persons living in the immediate vicinity of infected localities to adopt some measures by which the disinfection of the atmosphere may be accomplished. It has been shown by various experiments that during the prevalence of cholera there is an absence of ozone in the air. Ozone is a peculiar element, which is supposed to be oxygen acted upon by electricity. It is characterized when in a concentrated form by a peculiar, pungent odor, "and by its intensely oxidizing and bleaching power, so that substances on which common oxygen produces no effect, are rapidly oxidized on contact with air which contains only a small portion of this odorous principle."

To detect the presence or absence of ozone in the atmosphere, Schön-

bein, the discoverer of this element, prepared slips of paper, which, having been soaked in distilled water, were placed in a solution of iodide of potassium and starch, in which they were left for five or six hours. They were then dried in a cool, dark place, in the horizontal position, so that the iodide solution might be equally diffused.

The experiment is performed by hanging these papers in a box from which the bottom has been removed. They should not touch or rub against each other, and on being exposed for observation should be moistened with distilled water. If ozone is present in the atmosphere, the slips are rendered blue; if the ozone is deficient, no change of color is produced.

Various other processes have been described by which these papers may be prepared and the presence of ozone determined. Conspicuous among them are the methods of Moffat, Lowe, and Beard.

Although by some authorities the peculiar properties ascribed to ozone are doubted, still the majority of observers describe it as the vital element of the air; "*that from its presence oxygen is life-supporting, and that in the absence of ozone offensive products in the air are increased, and all diseases which show a putrefactive tendency are influenced injuriously.*"

Several methods for the artificial production of ozone are described: the slow oxidation of phosphorus, the slow combustion of sulphuric ether. The method of Boeltzer, of adding one part of sulphuric acid to two parts of permanganate of potash, is attainable by all. This mixture will continue to give off ozone for several months.

For the purification or disinfection of the air many other expedients are suggested as of practical value: *Charcoal*, from its rapid absorption and subsequent oxidation of organic emanations. *Chloride of lime*, exposed in a shallow vessel and moistened with water, gives off chlorine, which is supposed to destroy organic matter. *Bromine;* this substance, diluted and exposed in saucers, is a popular aërial disinfectant. *Nitrous acid*—the gas may be evolved by placing a small portion of copper in dilute nitric acid—is a most powerful disinfectant. *Sulphurous acid*, most easily evolved by burning sulphur, is also supposed to act powerfully on organic matter.

It is prudent that during a cholera epidemic one or other of these disinfectants should be exposed in all rooms of houses, especially those used as sleeping-apartments; but if bromine, nitrous or sulphurous acid be employed, great care should be used that the gas is disengaged slowly.

The theory that flies may become the carriers of cholera-poison has been advanced; and as the idea carries with it an air of plausibility, effort should be made to counteract any injurious influence which they may exert. The most scrupulous cleanliness, not only of cooking-utensils and table-furniture, but of the rooms in which food is stored or prepared, should be observed. Gauze covers for dishes should be used, and every appliance which may prevent their entrance into houses should be adopted.

The occurrence of a case of cholera in any community should lead to a general and complete disinfection of all points at which the individual may have been during the few days previous to his attack. With the first symptoms of the disease the house in which the patient lies should be put in order. The various vessels and appliances for the sick should be without excitement placed ready at hand. The vessels from which drink and medicine are to be administered should be placed in the room, and not mixed indiscriminately with those in use by the healthy mem-

bers of the family. A deep but narrow pit should be dug in the yard adjoining the house, in such position that no possible drainage can be established with the water-supply, and the bottom of this pit should be covered with crystals of the sulphate of iron. A large supply of a saturated solution of copperas should be prepared, and after each vomit or dejection of the patient a quantity of this solution should be added, and the whole intimately mixed. They should be at once carried from the house, emptied into the pit, and the vessel which contained them should be carefully washed, and the water used for that purpose should also be emptied into *the pit*. Upon each dejection a few inches of earth should be thrown.

It has been suggested that, in place of earth, fresh sawdust be used. It is claimed that the advantages arising from its use are double. First, that the acids of the wood will arrest the decomposition of the molecular matter. Secondly, that the mass may be utterly destroyed with fire. While in crowded communities some advantage may be derived from the use of sawdust, we are decidedly in favor of the absolute and instantaneous disinfection by the sulphate of iron, and of depositing the matter thus treated below the earth.

At some localities necessity demands that the excreta of cholera-patients be emptied into drain-pipes which connect with sewers. In such instances it is of vital importance, not only that each vessel containing excreta be thoroughly disinfected, but that a complete flushing of the drain-pipe be frequently made with a concentrated solution of the sulphate of iron.

A strong solution of the sulphate of zinc, or of chlorinated soda, in a large wash-tub should be in a convenient position, into which all cloths or articles of clothing should be cast as soon as removed from the patient. And in a similar solution, or in water strongly acid with vinegar, the attendants should frequently rinse their hands. When the dejections are passed involuntarily, cloths saturated with the sulphate of zinc solution, or with vinegar, should be placed to receive them. The floors, carpets, or other articles of furniture that may become soiled with the excreta should be carefully washed with strong vinegar, with which also the excreta of the patient should be treated until the disinfectants which have been suggested are obtained. Should the case terminate fatally, all articles of clothing which have been on or around the body should be at once removed and instantly thrown into the tub containing the disinfecting fluid. The body should be washed in one or other of the disinfecting fluids, and all water which has been used on the person or on the clothing should be treated, as regards its ultimate disposition, as has been suggested in regard to the excreta. Should the mattress be found soiled with the discharges, it should be burned at once. Indeed, it would always be more prudent to destroy by fire all fabrics which have been soiled by these fatal dejections than to risk the development of a single new case. The body having been placed in the casket, crystals of sulphate of iron or of permanganate of potash should be placed around it, so as to act upon any product of decomposition which may occur prior to burial, which in no case should be delayed.

It is prudent and well for the healthy occupants of a house in which cholera has become developed to at once subject themselves to some prophylactic treatment. Experience seems to indicate that an acid mixture containing quinine and iron is most efficient. Should a second case occur, at its termination the house should be abandoned, at least until a most careful system of disinfection shall have been instituted.

IV. INDIVIDUAL HABITS.—Niemeyer, writing in 1870, says:

Certain influences appear to increase the predisposition to the severer forms of the disease, or to diminish the resisting power of the organism to the action of the poison. Chief among these are errors of diet, emetics, and laxatives, catching cold, and other debilitating influences. It is true, foolish people seek to excuse their excesses at the time of cholera epidemics by saying that the mode of living can have no effect in inducing cholera, because persons who lead the most proper lives are attacked by and die of the severest forms of the disease. Whoever is exposed to a poison whose action kills many persons, while others recover from it, is foolish to subject himself to injurious influences which lessen his chances of recovery, even if the avoidance of these injurious influences gives no guarantee of a favorable termination.

We have quoted the remarks of Niemeyer in full, so applicable are they to a class in every community who find in times of public danger only fresh and additional excuses for self-indulgence.

On the development of an epidemic of cholera it is well for all persons in whose power it may be to at once leave the infected locality. Niemeyer's rules were:

(1) *To start soon enough.*

(2) *To go as far as possible.*

(3) *Not to return until the last trace of the disease had disappeared.*

Admirable rules, if adopted and carried out to the letter. But one who starts too late may carry the disease in his person; one who travels too short a distance may be overtaken by the disease; while those who return to their homes with the same haste that attended their departure not infrequently fall victims to the disease.

Flint recommends that the removal of persons in districts where, *owing to the activity of auxiliary causes, the disease is especially rife, should be enforced as a sanitary measure by municipal authority.*

Those individuals who remain in an infected locality during an epidemic of cholera, from necessity or from philanthropic motives, will do well to observe rigidly fixed rules as to their individual habits, which may properly be considered under several heads. Of personal cleanliness sufficient has as already been noted; we therefore pass to other considerations.

1. *Dress.*—The surface of the body should at all times, both of the day and of the night, be fully and warmly protected. Under-garments which have become saturated with perspiration should be removed, the surface of the body briskly rubbed, and dry articles substituted. Whatever may suddenly check perspiration or induce a chilliness is considered dangerous and should be avoided. A broad flannel bandage worn over the abdomen and around the person, even in the oppressive weather of summer, will impart a sense of comfort and a decided relief to the abdominal malaise, so universally experienced during a cholera season.

2. *Diet.*—While it is advisable for all persons to be careful in their diet, and rigidly to avoid all articles of food that are known to be indigestible, it is still as necessary not to produce too sudden and radical a change in the diet. In other words, excesses of all kinds should be avoided; the digestive apparatus should be encouraged to the performance of its duty by the presence of good, well-prepared, wholesome food. Beef, mutton, poultry; rice, hominy, farina; wheat, corn, rye; coffee, tea, chocolate; and the various condiments, as salt, pepper, mustard, and other spices, may be freely used. Nor can we see any reason why such articles as butter, milk, eggs, &c., which a distinguished physician prohibits under the generalization of animal products, should be prohibited. Wine, brandy, and malt liquors may not only be allowed, but when used in moderation are extremely useful in averting those debilitating influences which so often prevent the system from repelling the

bers of the family. A deep but narrow pit adjoining the house, in such position that established with the water-supply, and the covered with crystals of the sulphate of i urated solution of copperas should be p or dejection of the patient a quantity of t and the whole intimately mixed. They s the house, emptied into the pit, and the should be carefully washed, and the wat also be emptied into *the pit.* Upon each should be thrown.

It has been suggested that, in place o It is claimed that the advantages arisi that the acids of the wood will arrest lar matter. Secondly, that the mass While in crowded communities some the use of sawdust, we are decidedly i taneous disinfection by the sulphate ter thus treated below the earth.

At some localities necessity den patients be emptied into drain-pipes instances it is of vital importance, excreta be thoroughly disinfected. drain-pipe be frequently made wi phate of iron.

A strong solution of the sulph large wash-tub should be in a co articles of clothing should be e And in a similar solution, or attendants should frequently are passed involuntarily, clot tion, or with vinegar, should carpets, or other articles of excreta should be carefully the excreta of the patient s have been suggested are all articles of clothing w be at once removed an disinfecting fluid. The disinfecting fluids, an on the clothing shou as has been suggest found soiled with t it would always h have been soiled of a single new tals of sulphate around it, so a occur prior to

It is prud cholera ha prophylac mixture e

MAP of the Invasion of Persia by Cholera in 1865, 67, 69 and 71, from India by way of Peshawur, Kunaches & Bombay. From Mecca in 1865; from Alexandria, Beyrout, Smyrna & Constantinople in 1865

by Dr J. C. Peters.



(ASIA)

MAP of Persian Gulf & Red Sea Routes
by J. C. PETERS M.D.



CHAPTER IV.

ON THE ORIGIN AND SPREAD OF THE ASIATIC CHOLERA WHICH REACHED THE UNITED STATES IN 1873.

By JOHN C. PETERS, M. D., *of New York City.*

The late outbreak of Asiatic cholera in this country, which commenced in New Orleans in February, 1873, was preceded by a great prevalence of the disease in North Germany, Poland, Hungary, and Austria for at least three years, viz: in 1870, 1871, and 1872; and by extended outbreaks in Russia in 1869, 1870, 1871, and 1872; while it had also been present in Persia every year since 1865; and notably so in 1867, 1868, 1869, and 1870.

It is well known to be in operation in India, especially in the province of Bengal, every year; more particularly every third, sixth, ninth, and twelfth years, in connection with the great pilgrimages to Juggernaut, Hurdwar, and their affiliated shrines. The influence of the Juggernaut pilgrimages, or of the worshipers of Shiva, the Destroyer, can be traced from 1781 through the great twelve-year epidemics of 1817, 1829, 1841, 1853, and 1865 in India, stretching north to Calcutta and south to Madras, on the east coast of Hindostan; while the pressure of the adorers of Vishnu, the Preserver, to Hurdwar, in the north of India, and to numberless other sanctuaries, may be seen in the great outbreaks of 1819, 1831, 1843, 1855, and 1869, in India and adjacent places.

The great epidemic of 1865 issued from India, by way of Bombay, to Makallah, and from there up to Mecca by steamships; and was forwarded by Suez, Cairo, and Alexandria to the Mediterranean Sea, and from thence by steamships to Beyroot and back to Damascus in Syria, towards Persia; also to Smyrna, and through Asia Minor again towards Persia. Also, from Alexandria to Constantinople, and from there east through the Black Sea to Trebizond, and down through Armenia, also toward Persia, from the northwest.

It was also forwarded from Bombay, up the Persian Gulf, to Bushire, and from there into Persia, by way of the south. And, finally, returning Persian pilgrims from Mecca carried it back to the Persian Gulf, to Bushire, and Bassorah, from the southwest. (See maps 1, 2, and 3.)

The presence, persistence, and recurring activity of cholera in Persia for so many years, viz, from 1865 to 1872, although paralleled by previous periods of equal continuance, led some observers, especially Dr. Tholozan, principal physician to the Shah, and director of the sanitary administration of Persia since 1843, to conclude that the disease had become naturalized there; and to hint that Persia, rather than India, was the source of the late epidemic in Europe and this country. The entire subsidence of cholera in Persia, however, since 1872, has now finally disproved that supposition; while all the best epidemiologists have again returned to their former conclusions, that the central position of Persia, between India and Europe, exposes it to frequent importation and invasion of cholera, which scarcely allows one outbreak to subside before another is introduced.

We have already seen that these implantings of the pestilence are much more numerous and occur from many more directions than is generally supposed; but we have not yet exhausted the list: for it is frequently conveyed up the Persian Gulf from Kurrachee, at the mouth of the river Indus, as well as from Bombay. From both places it is forwarded to Bushire, the only great Persian port on the gulf, and from there through Shiraz, Yedz, Ispahan, and Kashan, due north to Teheran, the capital of Persia; which is only seventy miles south of Reshdt, the principal port on the south shore of the Caspian Sea; from which it is easily sent up to Russia in Europe. (See map.)

It is also frequently deported from Bombay to Bassorah, at the head of the Persian Gulf; and from there up the rivers Tigris and Euphrates to Hillah, Bagdad, Damascus, Aleppo, and other great cities in Syria and Asia Minor, and then trends toward the Mediterranean and Black Seas.

From Bassorah, near the united mouths of the Tigris and Euphrates, it is frequently carried by pilgrims to the holy shrines of Kerbela (Meshed Hossein) and Nedjef, (Meschid Ali,) just south of Bagdad. From W. A. Shepherd's book (From Bombay to Bushire and Bassorah, p. 10) we learn that Bassorah, at the head of the Persian Gulf, has many pilgrim-boats, which are always crowded with the living and the dead, going up to Kerbela and Nedjef. The living cargoes, consisting of men, women, and children, are huddled together like pigs; from one hundred to one hundred and fifty being crowded together in a space of forty feet by twenty, with twenty-five or more dead bodies piled about; forming rather close packing in the warm season. As these pilgrim-boats passed or went to windward the scent was anything but pleasant; and it was difficult to say whether the living or the dead were most disagreeably fragrant. Then the Arabs living along the shores of the rivers not only stop the vessels and rob the living, but also take and hold the dead bodies in pawn till the price they set upon them is paid by the sorrowing relatives; who believe that their own souls and those of their defunct relatives will never reach paradise, unless they get their bodies to the tombs of Hossein or Ali, at Kerbela or Nedjef. But these pilgrimages of dead and living bodies to Meshed Hossein and Meschid Ali are more than outrivaled by those which proceed to Great Meschid, which is situated in North Persia, due east of Teheran, toward India; and to all three of them, huge congregations of devotees proceed from all parts of Persia, north, south, east, and west. At Kerbela, (Meshed Hossein,) Nedjef, (Meschid Ali,) and Great Meschid, (Meschid Reza,) the gorgeous mosques are hardly less sacred to the various sects of Mohammedans than is the mosque at Mecca. Kerbela, Nedjef, and Great Meschid are (see Lancet, September 18, 1872) probably the most important fostering-places of cholera in North and South Persia; for they are the burial-places of Hossein, Ali, and the Imam Reza, the three most highly rated saints next to Mohammed; to whose shrines not less than one hundred and twenty thousand pilgrims flock annually from Persia and India, bringing with them many hundred corpses in all stages of decomposition, for interment in the sacred soil of these great holy cities

Again and again the congregation of pilgrim hordes at these places has been the occasion of grave outbreaks of cholera; the disease having been introduced by the incoming Persian and Indian devotees; and carried back by others to the Ottoman dominions. The pestilence, fostered by overcrowding and the unwholesome conditions which always prevail in the so-called sacred cities, attaches itself to other pilgrims going homeward or passing elsewhere; and thus is disseminated widely by them through the districts they traverse.

J.C.PETERS' PERSIAN GULF ROUTE.
followed in almost every epidemic.



J. C. PETERS' MAP of the North Persian & Central Asiatic routes, the former followed in many epidemics – the latter in several.



The pilgrim caravans are difficult to avoid by day; but at night, on the road, one is apt to be awakened from slumber by the shouts of advancing drivers and the tinkling of bells, announcing a passing crowd. By the faint light of the moon or stars one perceives a sea of long black boxes surging by, on scores of mules and camels. Each animal is laden with two of these mysterious objects, one on each side; and many of them are so loosely nailed together that another sense than that of sight soon convinces one that they are coffins. In fact they contain the putrefying bodies of the devout, who, having died in the true Mohammedan faith, are now being taken for burial in holy ground at Meschid, Kerbela, or Nedjef. They are often carried hundreds of miles, and a sickening stench always comes up from their gaping seams; causing nausea and faintness in the drowsy and unsuspecting traveler; who finds it impossible to extricate himself promptly from their disgusting contact, as they come crowding on in the dark, with apparently no limit to their numbers.

While this was going on in Southern and Western Persia in 1865 and 1866, aided by the return of four thousand Persian pilgrims, in boats, from Mecca, by way of the Red and Arabian Seas and Persian Gulf; and double that number by the great Damascus caravan; and a not inconsiderable multitude through Central Arabia, by Medina and Deraia to the west coast of the Persian Gulf; fresh invasions of cholera were coming to Northern Persia from Northwestern Hindostan in 1867, 1868, and 1869. In 1867, after the great Hurdwar epidemic of April 12, 1867, over forty-three thousand deaths occurred from cholera in the Punjaub, or Northwestern province of India. Macnamara (see Treatise on Cholera, p. 25) says: "The epidemic crossed the western frontier of India toward Persia with a large party of Hurdwar pilgrims on May 19, 1867. It prevailed in Afghanistan with fearful virulence in July, 1867, and continued until September. Passing due west through Herat and Great Meschid, with this early start, it appeared at Teheran, the capital of Persia, just below the Caspian Sea, toward the close of 1867. It was reproduced in Teheran and Meschid, in June and July, 1868; and then extended to Astrabad and Reshd, on the Caspian Sea."

Macnamara then said: "Europe, therefore, is again threatened from Persia, *via* Russia and Turkey."

In 1867, Dr. J. Murray, inspector-general of hospitals, watched cholera arise at the great twelfth-year festival at Hurdwar, at the source of the Ganges, and pass through the northwest corner of India, by way of Lahore, Attock, and Peshawur, with the returning pilgrims to Afghanistan and Persia; and foretold that it would spread over Northern Persia to Russia and Europe. He was no false prophet, for it reached Teheran in 1867 and 1868, and was raging in Persia; while in Russia it was just commencing. (See Map 4.)

This vast irruption of 1867 in Northern India was followed by another in the Punjaub in 1869, when over ten thousand deaths occurred among the British white and native troops and residents. (*See Sixth Annual Report of the Sanitary Commissioner with India*, p. 33.)

It prevailed again in Peshawur, the extreme northwestern border town, in August, September, and October, 1869.

Dr. Bryden says, (ibid., p. 220:) "The cholera of 1869 did not stop at the Peshawur frontier. In the first week of September we hear of it above the Kybar Pass, at Jelalabad; and before the middle of September, 1869, its appearance in Cabul, still farther west, was reported."

The Lancet of August 31, 1872, says: "To the pilgrimage at Hurdwar, in 1867, and to Great Meschid, in Northern Persia, in 1867 and

1868, may probably be traced the diffusion of cholera in Russia and Europe during the past three years, viz, from 1869 to 1872."

The Times and Gazette of June 29, 1872, says: "India has lately had two great shocks of cholera, viz, in 1867, at Hurdwar; whence it spread northwest into Afghanistan and Persia with the returning pilgrims; and a somewhat similar irruption, in 1869, soon extended as far as the Persian frontier. From Great Meschid, in Northern Persia, where it is known to have prevailed, on both occasions, it was easily distributed over Northwestern Persia to the Caspian Sea; as it is a place of great resort, both by merchants and pilgrims, coming and going from the east and west."

Dr. Renzy, sanitary commissioner of the Punjaub, (see Times and Gazette, April 27, 1872,) says: "Epidemics of cholera are becoming more and more frequent in the upper provinces of India; and from thence are easily carried over into Persia. The winds are the same, but travel has much increased. Calcutta and Lahore, only twenty years ago, were five months' journey apart; now only five days. Tens of thousands of Hindoo villagers now travel where few did before; and the facilities of importation of cholera from Bengal are becoming portentous; so that even the natives now complain that the disease is brought to them, far too frequently by troops, travelers, and pilgrims. At Peshawur, since 1858, there have been four terrible outbreaks; those of 1867 and 1869 being awful; the thirty-sixth regiment alone losing 15 per cent. of its men in thirty days."

Thus we have seen that we have ample proof that there were importations and invasions of cholera in Persia in 1865, '66, '67, '68, and '69; and in the Lancet of August 27, 1870, we read: "During the last four years, viz, in 1866, '67, '68, and '69, cholera has prevailed more or less in various parts of Persia, and particularly in those districts bordering on the Caspian Sea, which are in constant communication with Russia, by means of steamships carrying goods and passengers, which run weekly from the port of Astrabad, in the southeast corner of the Caspian Sea, and from Reshd, on the south coast, to Astrakan, at the mouth of the Volga; stopping at various places, especially at Baku on the middle west coast, in a direct line with Tiflis to Poti, on the east coast of the Black Sea."

Although the Persian minister denied that there was any cholera in Persia, he was flatly contradicted by the English resident, who proved that it could have been carried to Russia in 1867, '68, or '69. We also read in the Lancet of October 1, 1870, that the Shah of Persia was about to undertake a pilgrimage either to Meschid or Kerbela, in the hope that the devastations of cholera in his dominions, which had been very great during the last four years, viz, in 1866, '67, '68, and '69, might thereby be diminished. Unfortunately better counsels prevailed, and the Shah was induced to favor some pretended sanitary reforms, instead of perhaps proving in his own person the folly and danger of such pilgrimages."

Early in 1869, (see Lancet, August 14, 1869,) the French government sent Dr. Prout to explore the west shores of the Caspian Sea, from Astrakan to Baku in the west, and from thence to Reshd in the south, and as far as Teheran, the capital, to ascertain if possible the causes and local conditions which have forced cholera always to follow this route in extending from Persia into Russia and Turkey; and to impress upon the Persian government the necessity of carrying out the rules of the sanitary conference with the European powers as agreed upon in 1867, and which had remained almost a dead letter in Persia. Also, to


INDIA
BAY
OF
BENGAL

stop if possible, during the prevalence of the pestilence, the practice of carrying the bodies of those deceased of this or other diseases, with the caravans of living pilgrims.

It had been remarked, (says the Lancet of April 29, 1871,) for several years previous to 1870, that the recurring outbreaks in Teheran had almost invariably followed the arrival of pilgrims; and the annual exhumation of bodies for transportation to Meschid and Kerbela.

This quotation furnishes another proof, if any were wanted, that cholera had been in Teheran, which is only seventy miles south of the Caspian Sea, for several years previous to 1870, and we have already seen that it was there in 1865, '66, '67, '68, and '69. The epidemic at Teheran was very virulent. It commenced at the caravanserais near the principal gates of the city, as if coming with pilgrims and travelers; and rapidly extended into the town, in various directions. This outbreak was again attributed to the exhumation of bodies, preceding the annual pilgrimages to Kerbela and Meschid; for not less than three hundred were dug up at Teheran; the greater number of which had died of cholera during the previous autumn and winter. It was again regarded as proven that in Persia the routes of commerce and pilgrimages were also the highways of cholera; and after the disease had prevailed for six years in succession, viz, from 1865 to 1871, a quarantine was at last established below Bagdad, on vessels ascending the Tigris from Bassorah.

Thus it will be seen that Dr. Tholozan was very far from being justified in his positive and enthusiastic assumption that the numerous visitations of cholera in Persia were merely the outbursts of the smoldering embers of their predecessors. There are many flaws of great magnitude in his evidence, which go far to nullify the importance of his conclusions. The first is his ignorance or utter disregard of the numerous importations of the disease from India, Arabia, Syria, Asia Minor, and Turkey; also possibly from Russia.

Drs. Bryden and Cunningham, the statistical officers of India, were guilty of still greater carelessness and positiveness, when they assumed that the cholera of 1869, in Persia, was blown over that country from India to Astrabad, on the Caspian Sea, in the course of a few days; when we have already seen that it marched over the border of India with the Hurdwar pilgrims, as early as April 1867, and reached Meschid and Teheran, to the west, in the fall of 1867; and persisted in 1868. Besides, according to Lieut. Col. Sir Alexander Burnes, (see Narrative of a Journey to and Residence in Cabul, p. 77)—

"The most extensive arrangements have long been made to convey pilgrims and merchandise, (and with them cholera,) to and from Northern India and Persia. The Lohanee Afghans are a migratory, commercial, and pastoral people, who proceed annually from the borders of Persia down into Hindostan, in order to purchase merchandise. At the end of October, as winter approaches, they leave Khorassan, in Persia, and descend into India, (where they remain until after the great fair at Hurdwar.) They commence their return toward the end of April; and all reach Cabul and Kandahar by the middle of June; in time to dispatch their investments to Herat and Bokhara; and then pass on into Khorassan, in Persia, where they remain during the summer. They march in three great divisions; the first has twenty-four thousand camels; the second, nineteen thousand; the third, seven thousand." (See map.)

The arrangements for the conveyance of pilgrims, merchandise, travelers, and disease still farther west into Persia are equally complete, according to Sir James Connolly. Due west of Cabul and Herat lies

Meschid, the holy city of Northern Persia. For eight months in the year all the roads, to and from Meschid, are thronged with pilgrims. Nearly sixty thousand come up from India, Cabul, and Afghanistan; and as many more from Turkey in Asia, the Caucasus, and shores of the Black and Caspian Seas.

Cholera has followed this North Persian route very many times, and that of 1869 was at Cabul early in September. Next it was still farther west, at Herat; then, on September 21, 1869, the English political agent at Teheran writes: "It is now some time since the cholera appeared here, and there are from fifty to sixty cases a day."

And still farther west, the agent at Astrabad, in the southeast corner of the Caspian Sea, says: "The cholera made its appearance here on September 8, 1869. It first broke out among the soldiery and irregular cavalry; and these being dispersed, it spread into the town of Astrabad, where it is very virulent."

Here we have a continuous chain of the disease from India, due west, over the old caravan and pilgrim route, through Cabul, Herat, Meschid, and Astrabad, to the shores of the Caspian Sea. But, according to the Lancet of August 27, 1870, it had already been still farther west on the Caspian Sea, viz, at Reshd, the principal port on the south coast, where an outbreak occurred in August, 1869; and a little later it made its appearance at Astrabad, viz, early in September. Again, the Lancet of August 14, 1869, says: "Cholera was reported in the middle of July, 1869, as prevalent at Teheran, only eighty miles south of Reshd, and that there was some danger of it spreading along the shore of the Caspian Sea to Russia and Turkey."

RUSSIA.

Thus cholera had been standing on the borders of Russia for years, when its presence was suddenly announced in one or more places, especially at the holy city of Kiev, on the river Dnieper; more than one hundred miles above Odessa, at its mouth, in July, 1869.

This was regarded as a recrudescence from the great epidemic of 1865 and 1866, without the intervention of any new importation. But in the Times and Gazette of December 2, 1871, we read that Robert Lawson, inspector-general of hospitals, and president of the London Epidemiological Society for 1871, affirms: "There had been a severe outbreak in Persia to the south and east of the Caspian Sea in the autumn of 1868, which continued into 1869; and, in the course of that year it was to be expected in Southern Russia."—*Ib.*, June 25, 1872.

The outbreak in 1869 in Russia corresponded with an exacerbation in Northern Persia, where the disease had been more or less prevalent from 1865 to 1866, as well as in 1867, 1868, and 1869. The Times and Gazette of August 9 says: "The presence of cholera in Persia in 1867 and 1868 converts the probability almost into the certainty that a fresh importation into Russia did occur."

In the British Journal of August 26, 1871, we read: "At Constantinople the opinion is entertained, based upon documents, that the Russian cholera of 1869 and 1870 was due to importation from Persia. The disease is declared to have broken out at Nijni Novgorod, east of Moscow, at the time of the great fair in 1869, and with the arrival of Persian merchants."

According to Dr. Flauvel, one of the most competent French authorities, it was early in 1870 that the alarm was given at Constantinople of an outbreak of cholera at Taganrog, at the head of the sea of Azof, and

Map of the course of the cholera in Europe from 1869 to 1873 by Dr. J. C. Peters.



at Rostoff, on the river Don; from whence it spread to the principal cities on the Russian coast of the Black Sea, both east and west; so that the disease was quickly announced at Kertch and Theodosia in the Crimea; at Odessa at the mouth of the Dnieper; and even at Poti on the east coast of the Black Sea. It was assumed that it had been carried from Astrabad and Reshd up to Baku on the west coast of the Caspian Sea; from there by the new railroad, which had just been completed through Tiflis to Poti; and from there to Taganrog, as that is the first Russian port which is cleared of ice, in the spring.

As usual, (says Flauvel,) the rapid propagation along the coast of the Black Sea coincided with the arrival by steamships of travelers from infected places. No less than seventy vessels arrived off Constantinople, from infected Russian ports; but a strict quarantine was established and the pestilence did not break out in Constantinople until 1871. (See map 5.)

The Lancet of August 27, 1870, says: "In August, 1869, an outbreak occurred at Reshd, at the foot of the Caspian Sea, and a little later at Astrabad in the southeast corner; whence it could easily have been carried up into Russia, by the weekly steamers to Baku and Astrakan; and from there up the Volga to Nijni Novgorod. In September, 1869, it broke out in Nijni Novgorod, just after the great fair in July and August, to which over two hundred thousand merchants from all parts of Russia, Persia, Central Asia, and other places assemble."

The Lancet (*ibid.*) states: "Later in the year 1869 it appeared at Kiev and Moscow. It also broke out in Taganrog, but did not gain much headway till early in 1870. In 1869, two new lines of railway from Kiev to Odessa, and to Taganrog, came into operation. So that if cholera came out by way of Baku, Tiflis, and Poti, it could be readily and rapidly carried up to Kiev."

From June, 1869, (see Lancet February 19, 1870,) "there had been numerous cases of choleraic diarrhœa in Kiev; but up to October, 1869, there had been only sixty-nine cases of algid cholera; and up to December 11, only one hundred and fifteen cases in all. So that the Nijni Novgorod epidemic seems to have been not only earlier, but more severe and extensive."

This moot point will now probably never be cleared up. The Russian authorities claim that the great epidemic of 1865, 1866, and 1867 left Russia with only eighty-three cases of cholera in 1868; principally in Kiev; to which fifty thousand pilgrims come annually; but also assert that the first case there came from beyond Nijni Novgorod.

In 1869 there were nine hundred and eleven cases reported in Russia; which are said to have spread from Kiev, as a center, northeast through Orel to Moscow, and from there to Nijni Novgorod; also down the river Dnieper to Odessa; and from there to various parts of the Black Sea. In 1870 there were no less than twenty thousand one hundred and forty cases in Russia; and in 1871, three hundred and five thousand two hundred and twenty cases. (See Practitioner, October, 1873, p. 308. See map 6.)

From Kiev it was said to have been carried by way of Orel to Moscow, and from there to St. Petersburg; and thence by rail southwest to Riga, Konigsberg, Wilna, and Warsaw.

It was also forwarded from Kiev, by river and canal, to Warsaw; and along the river Vistula up to Dantzic; and again to Konigsberg on the Baltic. The arrival of cholera in Konigsberg, and Dantzic, from the north and the south, was for a long time a great puzzle to the authorities; but was finally cleared up.

From Kiev it was also said to have been carried down the river

Dnieper to Odessa and by steamship to Constantinople, and also from Odessa by the well-known overland route due west through Jassy, Debretzin, and Pesth to Vienna.

From Pesth it was conveyed down by rail to Italy; especially to Trieste, Treviso, and along North Italy to Genoa; from whence it was sent by two steamships down to Rio Janeiro, and Brazil. (See map 7.)

It reached Hamburg in 1872; and was sent from there to London, Havre, Liverpool, New York, and various other places; probably also to New Orleans.

It was carried from Odessa to England; also from Riga and Dantzic; and from Havre. But the English authorities stamped it out promptly, every time.

From the wretched sanitary condition of these places, outbreaks occurred year after year, especially in Kiev, Moscow, and St. Petersburg; and gradually extended to Archangel in the north; Orenburg in the east; Astrakan, Taganrog, and Odessa in the south; and the border provinces of Moldavia, Galicia, Poland, and Pomerania in the west. Wherever outbreaks occurred they were regarded as recrudescences from the unexpired diffusion of 1865 to 1868; although it was also claimed that the pestilence which began at Kief, in 1869, extended from that city, as from a center, and of course must have been carried from it.

At Toula, just below Moscow, the first four cases died at the railway station, about November 13, 1869; yet the disease was pronounced a recrudescence. It did not attain any great extension in Taganrog until June, 1870; yet it was solemnly declared that the outbreak at Taganrog must be looked upon as a recrudescence of the epidemic diffusion of 1865 to 1869; although that city had been in communication with infected places for more than a year. It commenced in Moscow in December, 1869, and did not reach St. Petersburg until August 17, 1870, yet a sanitary commission agreed that it could not have been imported. It is not easy to understand how this body satisfied itself that the disease was not imported, for St. Petersburg had been in direct railway communication with scores of infected places, for many months; and cases had been scattered so freely along the lines of railway leading to and from St. Petersburg, that cholera stations and ambulances were established at the railway junctions, with six beds and one physician to each. The first case in Cronstadt was in the person of an officer from St. Petersburg, which was followed by four others. The disease was scattered down southwest from St. Petersburg, along the line of railroad leading to Warsaw, through Wilna. Officers, soldiers, and conscripts died in various Lithuanian and Baltic towns. It lingered in Wilna, directly east of Konigsberg, on the Baltic, for four weeks; with ten to fifteen deaths daily, before it reached the latter city; and then was brought in by Russian-Polish Jews. Some of the residents of Konigsberg, living in the same hotels and lodging-houses with the Russian merchants, peddlers, vagrants, beggars, and boatmen who introduced the disease, died, while the latter were still only affected with choleraic diarrhœa; but a Russian merchant was among the earliest victims. The Russian physicians, with the simplicity of children, regarded the first death in each place as the initial case of cholera; and made no reference to diarrhœa in relation to cholera. The early cases and groups of cases at Nijni Novgorod, Taganrog, and Kiev were believed to be ordinary cholera nostras, occurring at a time of fairs and pilgrimages; and they were seemingly quite unaware of the chronological relationship of the appearance of cholera in Russia in 1869, with preceding movements of the disease in India and Persia in 1867 and 1868.



Advance of Cholera from Odessa to Genoa in 1870 to 1873 by Dr. J. C. Peters

or several years, viz, from 1870 to 1873, the great force of the disease ned to be confined between the forty-first to the sixtieth degree of h latitude, and from the fortieth to the fifteenth degree of east gitude; but especially from the forty-first to the fifty-fifth degree atitude, and the fifteenth to the thirtieth degree of east longitude. his square patch, bounded by Odessa, Kiev, and Smolensk, on the t; Odessa, Jassy, Pesth, and Vienna, on the south; Wilna, Konigs- g, Dantzic, Stettin, Lubeck, Altona, and Hamburg, on the north; Vienna, Prague, Dresden, Berlin, and Stettin, on the west, the pes- nce raged in its fullest force. In the west of Russia, rivers that r north and south, to the Baltic and Black Seas, take their rise under shadow of the same trees; when in the flood they convert the swamps nd their source into one continuous lake; so that a traveler may s by boat, without interruption, from the Baltic to the Black Sea. e river, the Pripet, a branch of the Dnieper, upon which Kiev is sit- ted, creeps south to the Dnieper through a swamp as long as England. e rivers Niemen, Vistula, and Oder arise in this place and flow north the Baltic near Tilset, Konigsburg, Dantzic, Elbing, and Stettin; while e Dnieper, the Bog, and Dneister run south to the Black Sea, near essa. In Poland, the Niemen and Vistula are connected by canals ith the Dneiper; so that there is an uninterrupted water-communication om Odessa and Kiev to Konigsberg and Dantzic. Over forty thousand olish raftsmen descend the Niemen and Vistula to the Baltic every ar, and when the disease was once established in Galicia, which is e west of Kiev, and in Poland, the Baltic provinces were flooded ith it every year from 1871 to 1874. And when Hungary was drawn nto the vortex, Austria and Italy soon began to suffer.

In Galicia, due west of Kiev, from the first reported case on May 4, 871, there had been thirty-eight thousand four hundred and forty-eight ases; in three hundred and forty-six different towns and villages.

From October, 1871, to December 13, 1873, there had been four hun- dred and thirty-three thousand two hundred and ninety-five cases in Hungary, in more than six hundred and two localities.

In Poland, in 1872, there had been thirty-seven thousand five hundred and eighty-six cases.

Various importations and exportations of cholera took place. In September, 1871, the steamer Orion, from Konigsberg, was allowed to go up to the islands at Amsterdam, although the captain had died of cholera. In 1871 an infected vessel from Cronstadt was permitted to come into the Thames. Two infected ships arrived at Hull, England, in 1871. In September, 1871, the schooner Marshall came to Sunder- land, England, with her captain dead of cholera. In September, 1871, a fatal case occurred at Hartlepool, England, on board of the Hamburg steamer Uhlenhurst. The United States vessel, Loretto Fish, arrived at Cardiff, Wales, in September, 1871, with four fatal cases, from Ham- burg.

The first cases, sixteen in number, in Altona, near Hamburg, occurred August 9, 1871; and the initial attacks happened in Hamburg, August 28, 1871. On September 23, 1871, the ship Alster, from Hamburg, arrived in England, with cases.

In June, 1872, the Austrian steamer Diana carried cholera from Con- stantinople down to Alexandria. In June, 1872, the steamer Rainbow, of Newcastle, came from Odessa, direct to England, with the disorder. On August 3, 1872, an infected ship from Odessa also arrived at Fal- mouth, England. In 1872, it forty-seven cases were carried from War- saw, in Poland, down the Vistula to Dantzic, and spread east and west along the Baltic. In 1872, Cuban vessels were quarantined at Jamaica

against cholera. In Dresden, in 1872, the first case came from Pesth, in Hungary, but was reported as cholera morbus. In August, 1873, it was brought to London, from Hamburg. In June, 1873, several cases were brought to Dresden from Bohemia, (Prague,) on two Elbe steamboats. It was brought to Liverpool by the ships Rosanne and Hortense, from Havre, which had derived the disease from Hamburg. In August, 1872, there were one hundred and seven cases, in one week, in Hamburg. The schooner Inhama, from Calais, France, arrived at London in 1873. Cholera broke out again in Hamburg, in June, 1873. At Thorn, in East Prussia, on the Vistula, it was brought by Polish raftsmen. At Thorn, the Vistula is connected by a canal with the Oder, and the pestilence was carried down to Stettin. The Oder is also united to the Elbe by another canal, and thus the disorder was brought around from the Baltic, to the North Sea. In 1873, there were twelve hundred and twenty-five cases of cholera in Hamburg. In August, 1873, cases occurred on board the Hamburg steamer Rhine. At Dordrecht, Holland, it was introduced by the bark Freia, from the Baltic, with three deaths on the voyage. In 1872 and 1873, it was carried from Russia to Sweden. In August, 1873, three fatal cases occurred in London, in emigrants who came from Sweden to Kiel, in Denmark, and from there went by rail to Hamburg, and from thence by steamer to London. Cholera prevailed in all three places. In September, 1873, a steamer arrived at London from Cronstadt with cholera. Hamburg had over seven hundred cases from July 26 to August 23, 1873.

In the British Medical Journal, August, 1871, we read: "On board three steamers from Cronstadt, bound for Hull, England, there had been fatal cases of cholera, especially upon the Bingos. These vessels were stopped, and the Privy Council of England ordered all bedding and clothing used by cholera patients on board to be destroyed."

The Lancet of October 11, 1873, says: "The steamer Leibnitz, from Liverpool, has been declared affected with cholera, and put into quarantine at Lisbon. It is well known that two steamers from Genoa, Italy, carried the disease down to Rio Janeiro in 1873; but it is not as well known that there are very large colonies of Italians in Brazil who are apt to import the disorder."

The principal points closely connected with the origin and spread of this last epidemic of cholera from India, in 1867, to Europe and the United States up to 1873 and 1874, which have come out with renewed prominence, are: the fearful amount of contamination of the soil and water; and also, of the air of infected houses and hospitals, arising from the habits, not only of the Hindoos and Persians, but of Europeans and Americans.

The Hindoos take the lead merely in point of numbers, for they amount to nearly two hundred millions; and the greater heat of their climate. It is estimated that one hundred and fifty millions of them have no privies, and always defecate upon the open ground. Albeit many thousands of tons of human offal have thus been daily deposited upon the surface of the earth, for some thousands of years, yet some little sense of decency is kept up. The women and children of the better classes always have little screens near their houses, behind which they retire, and their accumulations are removed every week by an outcast sweeper-tribe. The males go to the fields, with the ceremony and regularity of prayers, every morning; and all, both men and women, invariably carry with them a little vessel of water, for ablution, which is performed with the left hand only. Then a small quantity of earth is put on the recrement, as in old Mosaic and modern earth-closet times.

But the result has been an enormous defilement of the surface, with a corresponding degree of saturation of the subsoil, and a consequent extensive pollution of the drinking-water everywhere.

In Persia, the huge inclosed caravanserais, in which hundreds of men and animals are shut up every night, have no privies; and their wells are in the center. The flat roofs of the Persian houses, on which the inhabitants sleep in warm nights, are used as places of conveniency; and the dried deposits are commonly used for fuel. Thus all their cisterns and rain-water supplies are apt to become contaminated.

In Russia, Germany, and Italy the majority of the cess-pits or privy-vaults are in the cellars of the houses; while the seats are often near the kitchen-fire, for warmth and comfort, while paying tribute to Cloacina.

A remarkable outbreak occurred at Delhi, in connection with this subject of coprology, at a funeral feast given November 26, 1871, by a Righur, in commemoration of the death of his brother. All the male Righurs, a peculiar sect, numbering five hundred in all, were present; and none others. The provisions consisted of cooked rice, wheat, and barley, garnished with sugar and melted butter. The sole drink was water; for meats, liquors, and women are excluded from these solemn repasts. The food was good and carefully cooked; but the huge mass had to be spread upon mats on the floor, and among them was a new mat upon which the dead brother had lain. He had been falsely reported as dead of fever; but it was subsequently discovered that he died, after an illness of a few hours, from severe vomiting and purging. The remains of the feast were carried home to the women and children; so that every man, woman, and child partook of more or less of it. No bad effects were observed for nearly two days, when several began to vomit and purge; and by noon of the third day, there had been forty-five attacks and eleven deaths; and up to the eighth day, seventy seizures and forty-four bereavements. Up to the fifth day, all the cases of cholera were limited entirely to the Righurs; fifteen families of whom lived at some distance. After that it spread to others.

New water-works were opened in Calcutta in 1870, up to which time there had always been from three to six thousand deaths from cholera, per year, in that city. In 1870 the number of deaths fell to fifteen hundred and sixty; in 1871 to seven hundred and ninety, and in 1872 to about six hundred. In December, 1871, an outburst, confined to the inmates of three excellent houses in a fine block of buildings in Russell square, Calcutta, occurred. The three residences formed one boarding establishment, with a kitchen in common. There had been no cholera in that neighborhood for four years. On the night of December 5, all the lodgers were in good health, but in forty-eight hours the large majority of them were sick; among them Archdeacon Pratt, who went to Ghazipoor, three hundred miles off, was seized on the 7th, and died the next day. Only one native servant partook of the food prepared for the Europeans, and he fell a victim. The water and milk were brought by carriers who lived in a suburb called Bhowanipoor; and within a stone's throw of the tank from whence the milkman and water-carrier obtained their water, there had been eight cases of the disease from two to five days before; and it had been prevalent in the neighborhood for a week. The disease was carried in the drinking-water and in the milk diluted with it.

Cholera prevailed in St. Petersburg from 1870 to 1874. Dr. Monall states that the sanitary condition of the city is disgraceful to civilization. The soil is so little above the level of the river Neva that it is saturated with sewage, and the place seems almost floating on a mass of

filth; for the excrementitious matters from the houses are conducted into porous cess-pits, whence the liquid portions permeate the surrounding earth, and find their way into the open canals which intersect the city, everywhere. High tides or west winds always force back much of the refuse which has reached the river, so that there is no good drainage, or pure pump, or well-water supply. It has long been notorious that the islands, in the river, especially those farthest opposite St. Petersburg, often escape; but this is because the outscourings of the city are not carried over to them; and their drinking-water is much better.

Konigsberg, Elbing, Dantzic, Stettin, Lubeck, and other Baltic towns were in an equally unwholesome condition. In Lubeck, according to the official report of Dr. Cordes, more than one-half of the privies are inside of the houses; and the greater part of the other half, are in the wash-houses. Wooden pails are generally used as receptacles, which are emptied twice a week, in the day-time, by the market-gardeners, who carry off the feculence in open carts, for agricultural purposes. Every three days, the houses, streets, and whole city are pervaded with abominable foulness. Of those who drank of the dirty waters of the Trené and Wakenitz streams, one in six, to one in nine died; of those who used the not very pure supplies from three rather better sources, from one in thirteen to one in fifteen, and one in thirty-one succumbed; in almost strict proportion to the purity, or impurity of the fluid.

Professor Forster, of Breslau, (1873,) has just given (see "Spread of Cholera by Means of Wells") a list of towns which have never had large epidemics of cholera, although surrounded by it on all sides, and actually invaded by importations. All these have a pure-water-supply, conveyed in pipes, from distant reliable sources; and an equally good system of sewerage and drainage. He also gives a register of parts of towns which invariably escape, although other parts of the same city are almost always attacked. The former have good pipe-water; the latter, foul wells and pumps. The Orphan Asylum in Hallé has always been immune, although the city has often suffered. It is on a hill, and has a separate, unsullied water-supply.

Breslau, with two hundred and eight thousand inhabitants, escaped in 1873, with only fifty-nine cases, in consequence of the recent introduction of chemically pure water, of good taste, and free from all organic and decomposing substances; by cutting a canal to the river Ohlau, by which all the refuse and filth of the heart of the city were carried off: and by early and strict attention to the cleanliness of the city, and the most thorough disinfection.

Dresden, Wurzburg, and Lyons are always spared, from the same reason. But in 1867 and 1873, the Julius Hospital in Wurzburg had rather serious outbreaks, connected with bad water and imperfect privy arrangements.

The great Exposition in Vienna in 1873 happened just before the new water-supply was introduced. The tragic death of the celebrated Dr. Henry Bennet's sister, Mrs. Brewster, is full of warning and instruction. She was in the prime of life, in perfect, vigorous health, and had never had a serious illness. She arrived in Vienna on June 10, 1873, and put pu at the Hotel Donau, a large, new, and luxurious building, just open to the public. She complained of the drinking-water on the first day; and put cologne into it, even to wash with. Herself, niece, and maid were all attacked with diarrhœa, as were many of the servants and visitors, who were led to believe that it was a summer bilious complaint, caused by the heat. But the hotel-water became worse and worse. Mrs. B. complained of it to the proprietors, and in her letters home. She then

resorted to milk and mineral water, until she found that the one was diluted, and the other made out of the water on the premises. On the fifteenth day (June 25) the hot water for tea at breakfast smelt so offensively that the hotel-keeper was sent for, who said that one of the drainage-pipes had broken into his well, but that a dozen workmen were rapidly repairing it. Her niece refused to taste the tea, but Mrs. B. had already swallowed some of it. She remained well all day, but was seized with vomiting and purging at 11 p. m., and in six hours was cyanozed and in full collapse, and died in fifteen hours. It was then found that a gentleman had already died of cholera in the hotel, two days before; four more died on the same day with Mrs. B., and nine more soon after; or fourteen deaths among the guests in six days; while many of the servants and others were sent to the hospital, where they also died. The police then interfered, analyzed the water, found it contaminated with sewage, and finally closed the hotel. Whilst the water was merely polluted with ordinary fecal discharges, a harmless, disagreeable, and troublesome diarrhœa prevailed for eleven or thirteen days; but when the two cases of true cholera came to the hotel, and their evacuations got into the well, the Asiatic pestilence broke out with explosive virulence. Cholera had been creeping about in Vienna since April; but its presence, not only there but in Hungary, and all the Austrian dominions, had been carefully concealed, so as not to interfere with the success of the great exposition. If alarm had not been sounded in the English medical journals, and in the London Times, by Dr. Bennet, thousands of valuable lives would have been lost. This country was completely thrown off its guard. Many careful epidemologists watched the foreign periodicals until the midsummer of 1873, without detecting a trace of any warning of a pestilence which culminated with one hundred and forty thousand deaths in Hungary; forty thousand in Galicia; sixty thousand in Poland; and thirty-seven thousand in Prussia. It was generally believed that there was none in Europe, except perhaps in some very distant and insignificant places.

Hamburg concealed her epidemic so well, that France was misled; and when it broke out in Paris in September, 1873, its course had to be traced back to Havre and Rouen, whence it was imported both by a family from Hamburg, and by a Hamburg vessel which put in at Havre, and had an outbreak soon after its arrival. The celebrated Jules Guerin stoutly denied that genuine cholera had invaded France, for he knew not where it could have come from. Lecadre, Médecin des Épidémies at Havre, admitted the occurrence of numerous sudden deaths from cholera nostras, but denied that they were Asiatic. Finally, two hospital-physicians at Havre proved that Lecadre and Guerin must have very carelessly observed their cases, both in hospital and private practice, or they would sooner have been convinced, that they were genuine Asiatic.

Where concealment is indulged in, proper, rigorous precautions are rarely taken. Hence out of two hundred and ninety-one cases treated in the Paris hospitals from September 16 to November 10, 1873, no less than one hundred and one, or 35 per cent., originated in the hospitals, among the patients suffering with other diseases. One of the Havre cases imported into England is suggestive, but slightly ridiculous. While the steamship Alliance was lying at Havre, among the cholera-ships, one of her men fell overboard, head foremost, into the dock-mud. He vomited a quantity of black, filthy water, which he had swallowed, and on September 6, when the Alliance arrived at Southampton, he was taken to his own house, and from there to the hospital, where he died of fully-developed cholera. His house was cleansed and disinfected; his bed-

ding and clothes destroyed, and the cab in which he had ridden was purified. A similar case occurred in London. The English authorities gave the greatest publicity to the arrival of every cholera-infected ship, and to the occurrence of every decided case from 1870 to 1874. They concealed nothing; the people were always fully informed, and capable of judging of the amount of danger; and of the efficacy of the means taken to obviate it. Their quarantine was the shortest, and at the same time the sharpest and strictest, that had ever been instituted. Commerce was as little interfered with as possible; while the country was thoroughly protected by the rapid but efficient purification of infected vessels, crews, passengers, clothing, and baggage. The health-authorities of every port in England were held to a strict accountability in all their proceedings; and were always helped and supervised in any emergency, by those great sanitarians, Buchannan, Parkes, Netten-Radcliffe, Burdon Sanderson, and their ever-watchful chief, John Simon. To their intelligence and activity England owes her escape, and they were emulated with no great disparity of comparison at New York.

Some fixed points about the mode and degree of infection have been obtained during this epidemic. Of Macnamara's nineteen persons who drank of cholera-water, only four were attacked; or only about one in five were affected, when the cholera-poison had actually been swallowed down into the stomach. In the Righur outbreak of about five hundred persons who ate of polluted food, there were only seventy attacks, and forty-four deaths; *i. e.*, less than one in ten died, and about one in seven were attacked. In Professor Botkin's forty experiments on dogs, viz. sixteen with subcutaneous injections with cholera-urine, sixteen with cholera-stools, eight with cholera-vomits; only twelve, or about 38 per cent., were disordered in any way; and only five died of pure cholera; while four more succumbed from mixed choleraic and putrid poisoning. Hence more than three to one escaped, even from hypodermic injections into the cellular tissue and blood. But it is not a little surprising that seven out of twelve were poisoned by injections of cholera-urine. All going to prove that there are immune persons as well as places.

In four thousand two hundred and three affected houses in the Berlin epidemics of 1866 and 1873, as many as two thousand two hundred and seventy-seven had only one case; proving that cholera has but little inclination to spread, in more than half of all the attacks. There were two cases in eight hundred and ninety-five houses, showing that the tendency to produce two cases is less than twice as small as to induce one case. In four hundred and thirty-five houses there were three cases; four cases, in two hundred and thirty-one houses; five cases, in one hundred and forty-six; six cases, in seventy-two; seven cases, in forty-four; eight cases, in twenty-seven; nine cases, in twenty-eight; ten cases, in seventeen; twelve cases, in six; thirteen, in seven; fourteen, in five, and fifteen cases, each, in five houses; while sixteen, seventeen, eighteen, nineteen, twenty-one, twenty-eight, thirty-two, forty-three, and fifty-four cases, each, occurred in one house. Hence the larger number of houses have a tendency to very small extension of the disease; while a few produce a large number of cases. Hence more than three-fourths of all the affected houses will have only one or two cases. If it were not for this comparative immunity of towns, houses, and persons, the whole world would soon be ravaged by cholera; and it may safely be assumed that any large number of cases occurring in any town or house, points to some great sanitary defect, or carelessness in these places; or to some contamination of food or water, or perhaps milk.

There have been more or less severe outbreaks in the Vienna, Berlin, Wurzburg, Munich, Paris, and Havre hospitals. In strict proportion to the amount of ventilation, cleanliness, purity of the food and water-supply, perfection of the privy and washing arrangements, and to the watchfulness and intelligence of the physicians, nurses, and patients, will be the greater or less extension of the disease. In the Paris Insane Asylum, (Salpetiere,) of five thousand inmates, nearly twelve hundred became victims of the disease. Von Gietl, privy medical counselor and physician to the King of Bavaria, professor and physician-in-chief to the Munich hospital, was sent in 1831 to observe cholera in Berlin, Breslau, Silesia, Bohemia, and Vienna. In the first Berlin cholera hospital, a private dwelling, without hospital conveniences, he saw forty-six out of eighty-one hospital attendants sicken, with the disease, contracted from the patients. In Breslau, four patients, out of eight, in one ward, together with three nurses and one washerwoman. In the first epidemic in Munich, in 1836, of three hundred and twenty-six cases, ninety-four occurred in the wards. In 1854, of seven hundred and thirty-two cases, less than fifty were contracted in the hospital. In 1873 and 1874, of six hundred and seventy-three cases, only forty-eight received the disease in the Munich hospital. Von Gietl is the original suggestor and persistent advocate of the diarrhœal conveyance of cholera; from observations in Bohemia, in 1831, where he noticed a married beggar-man who was sent back from a cholera-infected town to his native village while suffering with premonitory diarrhœa. His wife refused to wash his filthy clothes, which were cleansed by a poor woman in another house, where she hung them up in her room to dry. In two or three days the washerwoman's husband was attacked and died, forming the first fatal case in the village; in two days more, three others died in the same and neighboring houses; and on the third day the washerwoman died, and the husband of the second victim. Then the disease spread. The beggar who introduced it, however, recovered. This succession of cases, corroborated by others, scarcely less clear, led Von Gietl, in the Munich epidemic of 1836, to have a government order issued directing attention to the infection contained in diarrhœa-stools. This Von Gietl theory was enthusiastically adopted by Pettenkofer in 1854, in which year the fecal origin of cholera became very evident in Munich, in connection with the great exhibition there. Pettenkofer almost died from an attack contracted by having his office in the exhibition-building located just above the privies: but soon followed the hypothetical ground-water theory in preference to that which clearly laid under his eyes and nose. Von Gietl has steadily watched for forty-three years the conveyance of the disease by the diarrhœal-sick, their clothes, utensils, privies, and the food and water contaminated by them. He has traced the disease to publicans, cooks, butchers, pork-, sausage-, and dried-fish merchants; to bakers, milk dealers, washerwomen, foul privies, and polluted water. He places more stress upon indoor privies, than upon subsoil water; more upon emanations from cholera-evacuations than from under-ground waters; more upon surface-filth, than subterranean exhalations; more upon soiled clothes than aerial vapors; more upon vegetables and fruits handled by dirty people, than upon those which are clean, ripe, and well cooked in pure water; more upon mouldy and filthy pork, dried-fish, bacon, sausages and cheese, than upon unstained articles of the same kind. His greatest recent triumph has been in tracing the prolonged epidemic among the Bavarian government horses to pasturage manured with the

human offal from the large fever-hospitals, while Pettenkofer was seeking for subsoil water.

Bryden's aerial theory received its heaviest blow when he claimed that the cholera of India was blown to Astrakan and Kief in a few days, in 1869, although it was shown that it had been traveling overland through Persia since 1867; and when he asserted that the Zanzibar outbreak was blown from India to the east coast of Africa, in a few days, while it was proven that it had been traveling down the interior of Africa, from the Red Sea, and absolutely came out from Central Southern Africa to Zanzibar, on the coast, with the slave caravans.

Von Gietl is a stanch advocate of the portability and transmission of cholera by means of diarrhœal cases; and insists that in large cities the initial cases are rarely the first fatal ones. This is well exemplified in the Lancaster, Ky., outbreak in 1873, in which Mr. Bewley, who introduced the disease, did not die until eighteen others, who had contracted it from him and his surroundings, had preceded him to the grave. Attached to the Munich hospital was a detached building containing twenty-three female patients, some with chronic diseases, and others convalescent from cholera, but still afflicted with diarrhœa. In the course of eight days six fatal cases of cholera occurred, and six severe choleraic attacks among the twenty-three patients. He says, in towns and cities, the initial cases are frequently or generally diarrhœal, and are then followed by fatal collapse cases; so that the origin of the epidemic is often veiled in obscurity, from all but the closest and most careful observers.

The death of Dr. Obermeir, Virchow's assistant in the Berlin hospital, followed in consequence of his audacious boldness in the endeavor to detect the cause of cholera. He had many specimens of cholera-disease in his room, and finally injected cholera-blood, hypodermically, into his arm, and died in six hours, while endeavoring to examine his own blood microscopically.

Dr. Nedswetzky, of Yaroslav, near Moscow, has apparently discovered the cholera-bacterium, which is developed in enormous quantities in the discharges. He found that quinine, camphor, carbolic acid, tar, calomel, and chloral had no effect upon them; that opium, nux vomica, and chloroform killed them slowly; while tannin, sulphate of iron, chlorine water, (aq. oxymuriat,) and dilute sulphuric, nitric, and muriatic acids killed them rapidly. He suggests the latter six remedies as the most efficient against cholera.

CHAPTER V.

ATIVE OF CHOLERA EPIDEMIC OF 1873 IN THE UNITED STATES.

ubmitting the narrative of the epidemic of cholera, as it occurred United States during the year 1873, it has been thought best to t as distinct groups the cases of the disease that occurred in ommonwealth.

order of the narrative is governed by the dates at which the eases at each locality occurred; for which reason the history of idemic as it affected each county is presented as a distinct paper. have endeavored so far as was in our power to present the views gentlemen who witnessed the demonstrations of the disease; and ith present several most valuable contributions from physicians esided within the area of infection.

dates of all initial cases have been subjected to a rigid scrutiny, is believed that those presented are absolutely correct.

submit a table of the dates of the initial cases of cholera in each which was included in the area of infection. This table demon- es the erratic course of the epidemic, and it is suggested that in it e found a strong argument in favor of the portability of the disease.

siana	February 9.	West Virginia	June 9.
sissippi	April 8.	Georgia	July 2.
nsas	April 14.	Minnesota	July 3.
nessee	April 15.	Pennsylvania	August 1.
ois	May 2.	Texas	August 1.
souri	May 11.	Iowa	August 14.
tucky	May 21.	Utah	August 18.
o	May 27.	Dakota	August 25.
anaa	May 29.	New York	September 10.
bama	June 3.		

t is a matter of regret that full information could not be obtained m all points of the area of infection. The extensive inundation of e States of Louisiana and Mississippi, together with the unsettled dal condition of the population of those States, prevented our ob- ining any information at many points. In the narrative of each oup of cases, the date of the initial case at each infected locality, om which information could be obtained, is given; and, as an appen- ix, meteorological records, from the report of the Chief Signal-Officer of ne Army, are reproduced.

LOUISIANA GROUP.

LOUISIANA CONTRIBUTORS.

Dr. C. B. White, president Louisiana board of health.
Dr. S. C. Russell, secretary Louisiana board of health.
Prof. S. M. Bemiss, New Orleans.
Prof. Jos. Jones, New Orleans.
Prof. F. Hawthorn, New Orleans.
Dr. E. Souchon, New Orleans.
Dr. A. W. Smyth, New Orleans.
Dr. J. R. Halderman, New Orleans.
Dr. J. T. Scott, New Orleans.
Dr. Alfuente, New Orleans.
Dr. S. S. Herricks, New Orleans.
Dr. T. H. Dennis, New Orleans.
Dr. D. C. Holliday, New Orleans.
Dr. P. C. Boyer, New Orleans.
Dr. W. R. Riley, Algiers.
Dr. G. S. Henry, Jefferson Parish.
Dr. S. Allen, Saint Mary's Parish.
Dr. A. S. Gates, Saint Mary's Parish.
Dr. S. W. Hamilton, Madison Parish.
Dr. Ricordan, Madison Parish.
Dr. A. J. Gibbs, Madison Parish.
Dr. G. T. Trezevant, Madison Parish.
Dr. C. R. Whitehead, Carroll Parish.
Dr. R. C. Strother, Ouachita Parish.
Dr. F. Rogers, La Fourche Parish.
Dr. P. M. Lambremont, Saint James Parish.

Surgeon James Simons, U. S. A., Medical Director Department of the Gulf.

Assistant Surgeon Van Buren Hubbard, U. S. A.

Assistant Surgeon R. S. Vickery, U. S. A.

Assistant Surgeon Clarence Ewen, U. S. A.

Acting Assistant Surgeon W. R. Mandeville, U. S. A.

DATES OF INITIAL CASES.

Orleans Parish	February 9.
Jefferson Parish	April 15.
Saint James Parish	April
East Baton Rouge Parish	May 7.
Madison Parish	May 10.
La Fourche Parish	May 10.
Ouachita Parish	May 11.
Saint Mary's Parish	May 30.
Concordia Parish	June 11.
Carroll Parish	June 22.

LOUISIANA.

The earliest cholera-record in the United States, of the epidemic of 1873, is to be found in the city of New Orleans, La., as having occurred upon the 9th day of February, and the following summary, taken from the records of the State board of health, shows that at that city the fatal cases of the disease occurred as follows:

	Deaths.		Deaths.
February	3	August	1
March	16	September	1
April	90	October	0
May	125	November	1
June	18		
July	4	Grand total	259

Through the kindness of Dr. C. B. White, president of the Louisiana board of health, who has placed at our disposal all the notes and other material from which the annual report of the Board of 1873 was prepared, we are able to present the following outline of the early cases of cholera that occurred at the city of New Orleans:

"*Case* No. 1.—Peter Thomson, a sailor, said to be a German, aged fifty-six years, died of cholera February 9, at 39 Ferdinand street.

"Thomson went to Pensacola, Fla., from Galveston, Tex. At Pensacola, finding no work, he left his children and came to New Orleans *two months* before his illness. He found no work until two days before his death, at which time he began to assist in discharging a general cargo from a Liverpool vessel, one and one-half blocks below the head of Ferdinand street. Four squares below lay a Bremen bark. At 2 p. m. of February 8, the second day of his labor, he was taken sick, and died at 9 a. m. the next morning, February 9.

"Eight other men who worked on the levee with him boarded in the same house. None of these suffered from the disease. There had been no sickness on the ship.

"No other case of cholera occurred in this vicinity until May 20, case No. 192 of the record, distant in space one and one-half blocks in direct line, and distant in time one hundred days.

"Thomson was a temperate, steady man. The attending physician reported the case one of sporadic cholera, in his opinion, caused by eating largely of cabbage while suffering from diarrhœa.

"*Case No.* 2.—Justice Coig, native of France, aged twenty-six years, died February 10, of cholera morbus, at the corner of Hancock and Levee streets, a point two squares above the United States barracks, and about *two miles* distant from the locality of case No. 1.

"This man was a butcher, a hard drinker; occupation, slaughtering beeves for his brother at the abbattoir, just below the Jackson United States Barracks.

"He was taken sick during the night of the 9th February, and died on the morning of the 10th. He had resided in the city four years, living with his brother at the locality mentioned; had not been absent from home, save at work, for some time, and had visited no ships. No ships lie near that part of the city.

"Surgeon R. S. Vickery, U. S. A., who was called to attend him, says: 'I found him in bed, in a cold, barn-like loft, in a place used for storing

green hides. He was in a state of collapse, cold extremities, pinched features, speechless or nearly so.'

* * * * * * *

"From a comrade who had been with him a part of the time, I learned that he was seized in the night with an attack of bilious cholera, which soon passed into serious vomiting and purging. This had ceased from exhaustion before I saw him, and the evacuations had all been thrown away." Dr. Vickery attributed the fatal termination of the case partly to the extreme cold of the weather.

He also remarks: "Not having heard of any similar case in the neighborhood, I reported it cholera morbus, but some weeks later should most probably have called it true cholera."

"*Case No.* 3.—Joseph Honoci, (creole,) colored, native of the State, speaking French, aged fifty-two, died February 28, of cholera, on Dumaine street, between Roman and Derbigny streets.

"This death occurred eighteen days after the death of case No. 2, in a locality far removed from either of the first two cases, and having no connection with either of them.

"Honoci was employed as a laborer, unloading the Belle Lee, a river steamboat, at the head of Canal street, on February 27, came home that evening, and died the same night at 12 o'clock.

"The sister and wife of Honoci, his brother-in-law, and three children, occupied the house, which Honoci owned, with the deceased. No other case occurred on the premises, and none in that vicinity, until May 13, case 152 of the record.

"It is to be remembered that the shipping and steamboat landings are at different portions of the levee; that ships are never landed or unloaded at the steamboat levee, or *vice versa*, and that those who unload ships seldom work on steamboats, and steamboat-hands are rarely employed about ships.

"*Case No.* 4.—Hannah Nelson, female, black, aged twenty-one, died March 1, of cholera, at 166 Franklin street.

"While returning from the funeral of her husband on the afternoon of February 28, she became too ill to go to her residence, 55 Burgundy street, and stopping at the house of a friend, remained there until her death, which happened the next day.

"The husband, Edward Nelson, by the neighbors was stated to have died by disease similar to that of the wife. His physician gave a certificate of death by acute gastro-enteritis, and upon after-inquiry being made, insisted on the correctness of the diagnosis already given.

"Nelson came into the city on the Mississippi River boat R. E. Lee, February 24; worked on her during the 25th, and until 3 p. m. of the 26th, at which hour he was carried home, and died the next morning. The premises were in good condition, seven rooms, six occupants. No one here had anything to do with shipping. Nelson visited no other parts of the city between his arrival and death.

"*Case No.* 5.—Margaret Woods, female, black; four and a half years of age, died of cholera-morbus, March 2, at 536 Goodchildren street. In the same house, on March 8, died No. 10 of the record, Isabella Woods, her sister, aged two and a half years.

"On March 1, Perry Scott, uncle of these two children, living at the same place, died, and was buried by the coroner, who gave a certificate of death by diarrhœa. He, however, had the body interred in haste, giving as a reason that Scott had died of a dangerous disorder, and the safety of the community required speedy burial. The case was not re-

ported to the board of health, and the facts stated were elicited in the investigation made of the Woods cases. Scott was a laborer on the steamboat levee.

"The house where these cases occurred was small, crowded, with a very foul privy vault. This was disinfected, and the premises vacated. No other deaths occurred in this immediate vicinity for the next ninety days.

"*Case No.* 6.—Robert Banks, male, black, aged fifty years, died of cholera, March 3, corner of Prytania and Polymnia streets.

"Banks kept an eating-house on the levee, near Canal street, went to his business in the morning, and died at 2 p. m. on the same day. No circumstances connect this case with the shipping. The premises in which he lived and died were in bad sanitary condition, the house old and leaky, stable filthy, privy vault overflowing into yard. The premises were disinfected, vacated, and remain unoccupied. Case No. 22 occurred five blocks distant and twenty-eight days later. Case No. 36, two blocks distant and forty days later. No connection between the two cases traceable.

"*Case No.* 7.—George Williams, male, black, twenty-nine, taken sick March 2, at No. 59 Erato street, removed to Charity Hospital, died March 4, of cholera morbus.

"Williams came to the city from one of the Red River parishes fifteen days before his death, worked on the steamboat levee, unloading barges from Saint Louis, one of which he "pumped out" the night he was taken sick. He did not lodge at 59 Erato street, but somewhere about the New Basin.

"*Case No.* 8.—Daniel Donovan, white, male, native of Illinois, aged eighteen years, 'homeless,' admitted to Charity Hospital March 3, died March 6, of cholera morbus; came from Natchez, Miss.; had been in the city *five* days.

"*Case No.* 9.—Mrs. Nairnes, thirty-four, died March 8, of cholera morbus, at 132 Dryades street.

"Previous to the sickness of Mrs. Nairnes, the husband, by trade a tailor, had an attack said to be similar to that of the wife, but recovered. After the death of Mrs. Nairnes, their child was attacked and recovered.

"The habits of both husband and wife were bad, the latter being reported a hard drinker.

"The family had no connection with either boats or shipping. The premises are unhealthy, being low and damp. Stagnant and filthy water was found in the yard. No. 12 was three blocks distant from this place, but no connection existed between them.

"*Case No.* 10.—Isabella Woods, black, aged two and a half years, died of cholera morbus, at 533 Goodchildren street, a sister of case No. 5. The history has already been given.

"*Case No.* 11.—Frank Baisey, male, black, forty-five, died of cholera morbus, March 7, at 308 Perdido street.

"Baisey was employed on the steamboat levee; had not been at work the day upon which he was taken sick. His physician attributed his attack to an immoderate meal of pigs' feet, eaten just before going to bed at night. He had visited no sick persons. His child, wife, and another woman living in the house did not have the disease. No connection with shipping could be ascertained.

"The premises were in good order, lot well filled, yard paved. The location is back of Galvez Canal, one of the foul draining ditches of the city, and subject to both swamp and sewage poison.

"*Case No.* 12.—James Johnson, male, black, aged sixty years, died March 10, of cholera, at the corner of Lafayette and Basin streets.

"Diarrhœa for a week preceded the marked symptoms of cholera.

"Johnson occupied a room extending over a portion of the privy vault, the odors of which came up through the floor, near which he slept upon a low bed. By the attending physician his illness and death were attributed to the effects of the poisonous air from the vault.

"Johnson was a laborer on the steamboat levee. No connection could be traced with shipping. No other case occurred here.

"*Case No.* 13.—Charles Higgins, black, one year, died March 15, of cholera morbus, at the corner of Dauphine and Marigny streets.

"The child and mother have been living on the premises for *five months*. Neither the mother, the two remaining children, nor the six other persons living there, suffered with the disease. No connection with the shipping ascertainable.

"*Case No.* 14.—Mary Adams, female, mulatto, two years of age, died March 23, of cholera, at 128 Toulouse street.

"The premises, although containing fourteen rooms, occupied by twenty-six persons, were in good sanitary order. An uncle of the child, just from Saint Charles Parish, a few miles above the city on the river, was reported as having eaten of fish a few days previously; as having been taken ill, fallen into a typhoid state, and finally died at this house. This statement was made by the physician who attended him. There was no connection with shipping.

"*Case No.* 15.—Kate Duane, white, aged seven, died of cholera morbus March 28, on Claiborne street, between Cypress and Lafayette streets. Her illness lasted twenty-four hours. The father of the child drove a grocery wagon; had nothing to do with shipping. No connection with suspicious persons or places could be traced Three other persons occupying the premises escaped similar illness.

"*Case No.* 16.—William Brady, white, forty years, 'homeless,' two days in the city from Texas, admitted to the Charity Hospital March 30, and died the same day. Certificate, cholera morbus.

"*Case No.* 17.—William Johnson, white, male, twenty-three years, died of cholera, March 30, on steamboat Sabine, just from Ouachita River, lying at the foot of Customhouse street. Certificate of coroner. No history could be ascertained. His death occurred on the same day on which the boat arrived in the city.

"*Case No.* 18.—Isidore Naines, black, male, twenty-seven years, died of cholera, March 31, at No. 76 Treme street.

"Naines was a steamboatman, had been running in the Ouachita River trade for a month previous to his illness, and upon the steamboat Sabine, as had Johnson, case No. 17.

"He was taken sick the day the boat arrived in port, dying the next day at 3 p. m. No other cases occurred at the locality of his death.

"*Case No.* 19.—Sarah Jackson, three and a half years, white, died of cholera, March 31, at No. 146 Chartres street.

"*Case No.* 20.—Henrietta Jackson, sister of Sarah, white, five years, died at the same house, of the same disease, the next day, April 1.

"These cases had no connection with the levee, or with suspicious persons or places. The premises were filthy, and abutted on the foul and offensive vaults of a row of tenement cottages, at that date not reached by the annual house-to-house inspection.

"The vaults and premises of this and neighboring houses were disinfected. No other cases in the immediate vicinity.

"*Case No.* 21.—Louis Davis, white, thirty-five, died of cholera, April 1, at 17 Jackson street.

"Davis was a sailor, had been living four months at the locality named. Just before his death, the day of the attack, he had been employed shifting ballast in the hold of the ship Research, from Galveston.

"The attending physician considered the disease to have been caused by drinking very largely of cold water while overheated by work in the vessel's hold. The premises where deceased lived were in good sanitary condition. No other cases at this locality.

"*Case No.* 22.—Charles A. Wilson, white, thirty, died April 1, of cholera, on Prytania, near Jackson street, a grocer, a man of means, living in the best portion of the city, having had no connection with shipping, nor with infected places or persons. He had committed serious errors in diet the day preceding his attack, which terminated in death in twelve hours. No other members of the family attacked. No other case occurred within six blocks, save No. 182 of the record, May 16.

"*Case No.* 23.—George Patterson, black, forty-five years, laborer, died March 30, of cholera, at No. 5 Theresa street.

"Patterson had been working at Hoelzel's corn-mill, corner Tchoupitoulas and Calliope streets, four weeks previous to his death; was at church March 30, and died at 12 m. the next day. Three men living in this house worked on the steamboat-landing. The premises were crowded, thirty persons in eight rooms, and were in filthy condition, as was the neighborhood.

"The physician attending, attributed the illness to the damp and bad condition of Patterson's lodging-room, and to the improper and unhealthy quality of his food.

"*Case No.* 24.—J. Baptiste, male, black, twenty-six years, laborer, died of cholera, April 2, at the corner of Marengo and Tchoupitoulas streets.

"The usual occupation of Baptiste was wheeling coal, but he had been at work at the salt warehouse, near Jackson street, two or three days before his last illness; had lived eight months in the neighborhood where his death occurred; premises in good order; no other case in the vicinity.

"*Case No.* 25.—B. Johnson, male, black, aged twenty years, died of cholera morbus at the Hotel Dieu, April 1; was admitted from the Saint Louis steamboat Continental in a dying condition. The Continental arrived at the levee March 31.

"Of these first twenty-five cases, the white numbered eleven; colored, fourteen."

In the consideration of the above twenty-five cases, attention is asked to the fact that the narrative actually includes the history of thirty-one cases, of which two were recoveries.

The report of the President of the Board of Health represents the opinions as to the epidemic of 1873, held by so large a proportion of the physicians of the city of New Orleans, that we present the most important portions of said report in detail:

"The first deaths of cholera, or cholera morbus, occurred February 9 and 10. On the 7th the range of temperature was 24.5° F.; on the 10th 19.5° F. It will be recollected that Surgeon Vickery, in his account of the second case, thought the unusual depression of temperature had much to do with its fatal result.

"The third death of cholera occurred February 28. On the 24th,

25th, and 26th, the ranges of temperature were respectively 18°, 19°, and 17°.

"During the first ten days of March, nine deaths occurred, accompanied by very considerable daily oscillations of temperature, the mercury ranging on one day 18°, on another 20°, and on two days 20.5°.

"The months of March and April throughout, present remarkable daily ranges of temperature.

"It seemed pretty evident that in many cases the exciting cause of the attack was sudden and considerable change of temperature.

* * * * * * *

"April and May are the diarrhœa months of New Orleans. The attacks are seldom severe, and in most cases yield immediately to a very moderate dose of some mercurial, with or without opiates or astringents.

"This, too, is the cholera-infantum period of the year in New Orleans. Our small mortality from that disease occurs almost entirely in the first half of the year.

"The comparative exemption of New Orleans is probably in a considerable degree attributable to the evenness of our summer temperature.

"The summer thermal lines, given in the last report of the board of health of New Orleans, afford an interesting comparison with those of the board of health of New York for the same period.

"In calling attention to rain-fall, it is to be remembered that in 1873 April and May, meteorologically, seemed to have changed places. April is usually a showery month, and May almost unvaryingly pleasant—literally a month of sunshine.

"The chart shows April of 1873 very dry, and May a month of heavy and repeated rain-falls. In New Orleans one-half inch of rain-fall is only an ordinary shower, whose effect immediately disappears, unless it has been preceded by others.

"With the high, cool, and dry winds prevailing, the whole city during the month of April was enveloped in clouds of dust.

"Several days entirely without fall of rain preceded the appearance of the first cases of cholera in February, and again preceded the first cases in March.

"There is a general coincidence between the occurrence of cholera cases and the lack of rain-fall, which is more noticeable by the table of cases than on the chart, as lines of the latter are drawn to show deaths by weeks.

"New Orleans should be free from contagion of drinking-water by cholera-poison, as usually caused, because of its water-supply.

"The larger portion of its inhabitants drink rain-water from cisterns which are invariably above ground. The remainder drink hydrant-water from the Mississippi. Water from wells is never used for cooking or drinking.

"The clouds of dust alluded to might be considered as affording a means of conveyance of poison-germs to the food and water of the people, and would certainly give them abundant access to the lungs, if that be considered a mode of entrance for them.

"By those who think that no evidence exists of the presence in New Orleans of the peculiar poison of Asiatic cholera, this meteorological condition, and its result of continuous foul dust and exhalations, are considered ample cause for the prevalence of the disease under discussion.

"The street-cleaning of New Orleans consists mainly in scraping the

lecaying animal and vegetable matter from the gutters, and throwing it up into piles, or scattering it upon the streets. Theoretically, this filth is moved every day; practically, occasionally.

"These matters, left upon the streets, are pulverized by passing vehicles and animals, and in the dry and windy weather are lifted into the air, penetrate all dwellings, and reach the food, drink, and lungs of the people.

"The dust of our ordinary earth-streets contains 15 per cent. of animal and vegetable matter. What the contents of our gutters are, their possible capacity of elimination of noxious gases, when undisturbed and uncleaned by frequent summer rains, the following extract from the late report of Dr. A. W. Perry, chemist to the board of health, will show:

"A gutter the length of one square—say 300 feet, 3 inches deep, and 15 inches wide—contains about 6,000 pounds of semi-fluid mud, of which 25 per cent. is solid matter. This, by the figures of the above analysis, contains 63 pounds of animal matter, and 420 pounds of vegetable matter.

"Four different samples of foul mud (gutters) were examined, with the following results:"

Number.	Dry residue weight per cent.	Per cent. of animal matter.	Per cent. of vegetable matter.	Amount contained in the two gutters along one block.	
				Animal matter.	Vegetable matter.
				Pounds.	*Pounds.*
1	21	4.50	20.50	135.00	412
2	23	3.40	30.20	106.40	422
3	21	1.41	25.20	50.40	366
4	21	1.38	28.60	36.60	372

"Comment is unnecessary.

"SUBSOIL WATER.

"The universal opinion in New Orleans has been that the varying distance of its subsoil water from the surface was entirely dependent on the height of the river.

"Daily observations, continued throughout the year 1878, corroborate those of former years, showing that the oscillations of the ground-water are independent of the rise or fall of the river, and are connected with the presence or absence of rain-fall. They are not believed to have causative connection with the rise, prevalence, or decline of [illegible], but have an interest as being a coincidence of the rain-fall, which seems to exercise control over the cause of disorder.

"There seems to be good reason to accept the rain-fall as largely efficacious in checking the progress of the disease, and continuous rains thereafter as having removed the cause, [illegible] having been coincident with that removal.

"The rain-fall of May was 3.12 inches. The total rain-fall [illegible] 21.87 inches.

"Statements have been made that New Orleans owed [illegible] exemption from epidemics [illegible] to the having [illegible] state of cleanliness and [illegible] perfection [illegible]

secondly, to the energetic 'stamping-out' (so called) measures employed by the board of health.

"The board of health is accustomed to begin an inspection of all premises of the city in the early days of January, proposing to have all vaults emptied, all yards cleaned, &c., by May 1 to 15, and thereafter to maintain such repeated re-inspections of those portions of the city in the worst sanitary condition as are practicable.

"This work of inspection and re-inspection is done by members of the metropolitan police force, detailed to duty with the board of health and under its orders. The police force, being a part of the State militia, is liable to be recalled in periods of public emergency. Such emergency occurred at the close of 1872, and continued into 1873, and in consequence of the withdrawal of the force, this house-to-house inspection, and general yearly cleansing, was not commenced till the last of March. It is the opinion of the board of health that, had its sanitary operations not been thus interfered with, cholera might have been much less general and less fatal.

"Therefore the statement that a remarkably favorable sanitary condition of the city existed, antecedent to the date of the appearance of cholera, is incorrect.

"After the disease was recognized as having a striking likeness to epidemic cholera, disinfection was practiced in all cases coming to the cognizance of the board of health. A circular, through the public journals, was issued to the citizens, giving instruction on disinfection; and many physicians took all precautions against the disease, by the usual modes of disinfection of excreta, &c. Others took no precaution whatever; therefore, in these and those other hundreds of cases where no physician was called, and no precautions practiced, there existed sources of infection ample to have poisoned the whole community and created a general epidemic.

"Disinfection in the cases of cholera can scarcely be credited with the escape of New Orleans from universal pestilence.

"NATURE OF THE DISEASE.

"The doubt that existed in the minds of medical men, as to the nature of the disease, is in some degree set forth by the diverse nomenclature employed in the certificates of death given during the first few weeks of the prevalence of the disease.

"As, for example—

"Cholera morbus.
"Cholera spasmodica.
"Cholera sporadica.
"Cholera nervous.
"Cholera asphyxia.
"Cholera.
"Cholera nostra.
"Apparently cholera.

"Cholera Asiatica appearing but infrequently.

"Of the first eighty deaths, forty-six received certificates of death by cholera morbus.

"Even at this time the opinion of the physicians of New Orleans is divided upon the subject.

"Medical men connected with hospitals, seeing few save fatal cases, unhesitatingly pronounce the disease Asiatic cholera.

"A large portion of New Orleans physicians consider it not to have

been Asiatic cholera; all, however, agreeing that in fatal cases no distinction can be drawn between the cholera sporadica of 1873, at New Orleans, and genuine Asiatic cholera.

"The few holding that when no distinction exists, there is no difference, unhesitatingly pronounce the disease Asiatic cholera, and suggest that importation is not necessary; that the germs of that disease are always and everywhere present, only awaiting favorable circumstances to multiply and produce the effects customarily experienced from the general and abundant presence of cholera-poison.

"Most physicians, however, although admitting the difficulty of differential diagnosis in fatal cases, consider that the character of the disease, its course and progress as a whole, warrant the belief that it was not Asiatic cholera. Some of the considerations influencing them to such belief are—

"1st. The non-importation of the disease.

"2d. That no evidence of portability or infection was exhibited in the city, where every facility existed for ascertaining its natural history.

"3d. The appearance of the disease at many localities remote from each other, and from anything that could be considered a common cause, and in all parts of the city, at dates synchronous, or nearly so.

"4th. The small mortality of those attacked with vomiting and purging, during the presence of the disease; attacks similar to which, during the presence of former epidemics, have customarily proved the beginning of that usually fatal disorder.

"The death-rate of persons thus attacked is variously estimated at from 3 to 12 per cent.

"5th. The fact that so general diffusion of the disease existed without resulting in a great epidemic.

"Had the disease possessed the portability and infectiveness attributed to Asiatic cholera, its course and results would have been the reverse of the actual occurrence.

"6th. The fact of the long-continued presence of the disease in New Orleans, without flaming up to epidemic proportions, shows absence of the peculiar characteristics of Asiatic cholera, as generally admitted. The disorder seemed endemic, not epidemic.

"7th. Cholera occurred at the season of the year when intestinal disorders appear in New Orleans, April being the diarrhœa month of the year.

"The city's small mortality of cholera infantum occurs also in the first half of the year.

"The prevalence of cholera at the same period of 1873 may be viewed as the natural tendency of that portion of the year, exaggerated into serious, and deadly, and somewhat general disease, by the presence of local poison, engendered by filth and magnified by unusual meteorological conditions.

"8th. The amenability to treatment of what were in appearance serious cases.

"Under the hypodermic use of morphine and atropia, or morphine alone, immediate relief and ultimate recovery was the rule. Under treatment by calomel and quinine, recovery also seemed speedy. Also, under domestic remedies, many cases were restored to health.

"A large number of persons were taken ill with profuse vomiting and purging, sometimes preceded by faintings and cramps, with great subsequent weakness, who recovered without any aid whatever, save the *vis medicatrix naturæ*.

"9th. The small number of multiple cases is considered an evidence of its non-infective or epidemic character."

It being our earnest desire that the opinions of the profession of New Orleans upon the origin of the epidemic of 1873 should be fully and accurately stated, we have herein reproduced: I. An editorial from the September (1873) number of the New Orleans Medical and Surgical Journal, by Prof. S. M. Bemiss. II. Extracts from a letter of Assistant Surgeon Van Buren Hubbard, United States Army, in which he gives the results he obtained from a series of interviews with the most prominent medical gentlemen of that city.

I. Extract of an editorial of the New Orleans Medical and Surgical Journal for the month of September, 1873, by S. M. Bemiss, M. D.

* * * * * * *

The epidemic of cholera which is at the present time traversing the United States devolves upon the medical profession several questions of difficult solution. The first is with regard to its origin; the second, its mode of diffusion; the third is with regard to its nature, as it respects identity with Asiatic cholera. The greater interest should attach to a discussion of the first inquiry, from this stand-point, because it seems to be an admitted fact that the epidemic first made its appearance in this city.

Whether the disease originated here, or was conveyed hither in vessels or clothing, it is not at this time possible to establish by the testimony of any known and incontrovertible facts. All that has been said or written about its importation in ships from Germany or Russia remains without foundation in any ascertainable events.

It is certainly but little calculated to inspire confidence in the scientific accuracy of the medical profession when its members adopt as truths mere rumors, whose entire want of liability might have been so readily learned by a letter addressed to the board of health of this city. No ship had landed in this city from a Baltic port for nearly, or quite, six months before the outbreak of the cholera epidemic.

We must admit, however, that the negative fact, that it cannot be shown in what manner cholera was brought here, is not sufficient to confirm a belief in its domestic origin. The opinion, long since advanced, that the deltas of the Ganges, Nile, and Mississippi possess so much similitude in climatic and geological condition that it may be assumed that they will give origin to similar diseases, is not supported by the past history of cholera.

Those who believe in the spontaneous origin of cholera, in countries so remote as these from that which has been for centuries known to be its place of perpetual prevalence, may place the late epidemic of New Orleans along with the Saint Kilda outbreak, and successfully challenge all opponents to prove importation by an array of facts. I believe, however, that one important circumstance always attends these mysterious epidemics, which is that they are not known to occur, except when cholera has been previously diffused among a population from whom there is at least a bare possibility of their germs having been imported.

The facts are that three deaths from choleraic symptoms occurred in February; one near the 1st of the month, another on the 10th, and the third on the 28th. The first of these deaths was at 39 Ferdinand street, the second at the Slaughter-House Company's buildings, and the third at the corner of Demaine and Derbigny. The deaths were separated in point of time by intervals unusually long for a disease generally so rapid in its first assaults as Asiatic cholera. The distances which separated the localities where the deaths occurred were from one to two miles. There was but little possibility of intercommunication between the first victims, and no facts have been revealed to show the starting point of the infection.

To show more particularly how the epidemic comported itself in respect to its mode of diffusion, attention is called to the following statement of facts. It was in March that the disease first began to assume an epidemic character, and during this month seventeen deaths occurred. Taking the first seven fatal cases as a fair type of the whole number, they will be found to have occurred under the following circumstances, as it respects dates and localities. In the mention of locality, the distance from the nearest case is also given.

Case 1.—March 1, Franklin street, No. 166, one and a quarter miles from last case.

Case 2.—March 2, Goodchildren street, No. 533, half mile from case No. 1.

Case 3.—March 4, Prytania and Polymnia streets, one mile from case 1.

Case 4.—March 4, Erato street, No. 59, one-half mile from case 3.

Case 5.—March 4, homeless.

Case 6.—March 8, Dryades street, No. 132, eight squares from case 1.

Case 7.—March 8, Goodchildren street, No. 533, in same house with case 2.

The duration, waxing, and waning of the epidemic are shown by the following tabular statement:

	Deaths.
February	3
March	17
April	82
May	108
June	18
July	4
Total	232

The houses in which two fatal cases occurred were five. Three fatal cases occurred in one house only, and more than three in none. None of the houses having multiple deaths were contiguous to each other. The greatest localization of epidemic intensity was observed in a part of the city bounded by Claiborne, Baronne, Common, and Julia streets. This space is about one-half a mile square, and is quite densely inhabited by a population principally colored. Within these limits twenty-eight deaths occurred.

Now, with regard to the influence of any artificial measures designed to prevent the spread of cholera by destroying its germs, in causing the epidemic of this city to have been so mild and short-lived, it is well to mention here the means employed by the board of health for disinfecting the abodes and clothing of the sick. The houses, yards, drains, and sinks were sprinkled with carbolic acid. The clothing was soaked in a solution of carbolic acid, one part to one hundred. I am indebted to the courtesy of the zealous member of the board of health, Dr. A. W. Perry, for these facts, and their accuracy is unquestionable. Although they do not explain either the mode of ingress or of origin of the cholera-poison, they constitute an important matter for reflection and forecast by the medical profession. Shall we hold that cholera-poison is susceptible of *de novo* origin in whatever part of the globe the peculiar climatic and geological conditions which favor its development chance to exist? Under this belief we must either deny to the cholera-poison a specific germ, or we must accord to this germ the quality of panspermatism, and say that it is everywhere diffused, and only awaits favorable telluric states to awaken it to life and activity. Or shall we admit that cholera germs were transported to this city in some manner quite impossible to be ascertained, and having been let loose at a period of the year not so favorable to their development as the warmer months, their activity and virulence were thereby greatly lessened? The latter seems to be the more reasonable conclusion.

In these periods of human history when, by the aid of steam, travel and intercourse are accelerated and vastly multiplied, we must expect to find all those diseases whose spread is in any manner assisted by human intercourse, to have their area of prevalence enlarged, and their outbreaks rendered more frequent and unaccountable through patent facts. That cholera belongs to this category, none familiar with its epidemic history will deny.

In these remarks I leave entirely out of view the theory of cholera-clouds passing over the earth. While every experienced observer is ready to admit that cholera-germs are susceptible of being air-borne over limited areas, I think that a hypothesis which holds that the earth, in its vast transit through universal space, passes through meteoric "cholera-banks," is quite as well supported by history as that theory which teaches that "cholera-clouds" traverse seas, and thus diffuse the disease upon remote continents previously uninvaded. The symptomatology of cholera in this city was, in the genuine cases, strikingly characteristic. I make this statement entirely upon the assertions of my medical confrères. It is probable that fully one-half of the profession here did not meet with a case during its prevalence. I belong to this number. The fatal cases, and some which recovered, had rice-water stools and vomiting, cramps, collapse, and suppression of urine.

It is a somewhat singular fact that coetaneously with this epidemic of undoubted cholera, there should have occurred such a general tendency to diarrhœa as was manifested in a large proportion of the population, and yet that the cholera deaths should have been so few in number. During the epidemic I visited and prescribed for about seventy-five patients suffering with diarrhœa or dysentery. Only one of this number could with any degree of propriety be classed as suffering from the diarrhœa premonitory to cholera. A girl aged fifteen years, living at the corner of White and Terpsichore streets, was attacked suddenly in the night of April 13 with painless watery purging and vomiting. She had cramps, feeble pulse, cold hands and feet, and shrunken features, but no collapse or suppression of urine. A powder of calomel gr. j., sulph. morphia gr. ¼, was placed upon the tongue and washed down with ice-water. The purging was promptly arrested. On the succeeding night the symptoms returned, and the parents, unwilling to disturb me, renewed the prescription and administered two powders. The girl was slightly ptyalized, but made a good recovery.

* * * * * * *

From the commencement I supposed the epidemic to be purely catarrhal in its origination, and was very slow to give in my adhesion to the assertions of my brethren in the profession, who, having viewed the epidemic from a different stand-point, were firm in declaring cholera to be among us.

No efforts were made to perfect a diagnosis by examining the urine for albumen. In truth, my present convictions are that in the zymotic affections the presence of albumen in the urine is more valuable as a point of prognosis than of diagnosis.

II. *Extract from a communication of Assistant Surgeon Van Buren Hubbard, U. S. A., dated New Orleans, La., January* 30, 1874.

* * * * * * *

As a résumé of the results of my inquiries, it may be set down as the unqualified opinion of all the physicians with whom I have consulted in the city of New Orleans, that the cholera of the spring of 1873 in that city and vicinity was native in its origin; that is, it was not brought here from abroad.

That it was Asiatic in character.

That it was mild in type, the percentage of cases to population and mortality to cases being small. Cases that were fatal were in the majority of instances rapidly so, death often supervening in a few hours after the first symptoms.

That the epidemic tendency was not marked—single cases often occurred in isolated localities; that in no single instance, so far as I have been able to learn, did the epidemic depopulate whole neighborhoods, or even families.

I will here state my impression, though not my opinion, (for it would require more extended research to state the latter,) that had the disease died out here and not spread northward through the valley of the Mississippi from this city as its focal point, it might, and perhaps would, have passed into history as "cholera sporadica," the name by which the disease was known weeks after its first appearance. Physicians were for a long time reluctant to characterize the disease by any other name, and it is questionable whether they ever would have done so had it not been for the sterner type the disease assumed as it spread up the valley.

Lastly, that the subjects and victims of the disease were, saving exceptional cases, from the lowest of the population of the city, chiefly negroes.

* * * * * * *

In pressing the investigation which was committed to our charge, the attempt alone was made to develop all facts which might possibly throw light upon the subject of the introduction of the disease into the city of New Orleans.

It has been found utterly impossible to establish the arrival of individuals who were personally affected with cholera, but the investigations have developed certain most significant facts.

Upon the accompanying map of New Orleans we have located the point at which each of the first twenty-five cases of cholera died; and also the points at which the cases of the same disease occurred in the town of Algiers, which town is located upon the west bank of the Mississippi river, and opposite to New Orleans.

The report of the board of health, in almost every instance, locates the point at which the cholera-subject worked prior to his sickness. Reference to the report of cases which we have reproduced will show that the majority of these cases originated upon the steamboat and ship levees.

Upon the map it is shown that in ascending the Mississippi river the



HOTO-LITHOGRAPHIC Co. N.Y. (OSBORNE'S PROCESS)

levee in front of the city of New Orleans is divided into distinct localities, to each of which is assigned a certain class of vessels: I. Tow-boats; II. Ships and steamers; III. Small craft, (the Picayune levee;) IV. Ships; V. Steamboats; VI. Ships and steamers; VII. Barges of all descriptions.

Now, by drawing a line from the locality of death to the point at which the board of health tells us that the majority of these early cases were employed at the time they were taken with cholera, it will be seen that these lines concentrated upon the steamboat and ship levees.

In the narrative of cases furnished by the board of health, it is stated that "the shipping and steamboat landings are at different portions of this levee; that ships are never landed or unloaded at the steamboat-levee, or *vice versa*, and that those who unload ships seldom work on steamboats, and steamboat-hands are rarely employed about ships." This is strictly true, but incomplete. The steamboat-levee is between the ship and steamer levees, and the communication between the three points is constant. The majority of the blacks who work at all in New Orleans work upon these levees, the great majority upon steamboats. A constant communication is thus established between the levees and the portions of the city occupied by the families of these men.

It is necessary to comment upon some of the facts and conclusions presented in the admirable and exhaustive report of Dr. White. It is, however, reluctantly entered upon, and the comments are advanced with no spirit of controversy with, or criticism of, a gentleman who has placed at our disposal all the means at his command through which information might be acquired; but the theory that the cholera-epidemic of 1873 originated *de novo* at New Orleans certainly cannot be received as immutable, unless the facts upon which it is based are impregnable.

Case No. 1.—If Peter Thompson died of cholera upon the 9th day of February, after unloading a Liverpool ship, it is certainly by no means an unusual event in the history of cholera-epidemics that "the eight other men who worked upon the levee with him, and boarded at the same house," did not take the disease. Of the nineteen men in India, all of whom were known to have drunk infected water, but five took the disease.

Case No. 4.—It is stated in the report, "No one here had anything to do with shipping;" and yet the narrative shows that Edward Nelson, the husband of case 4, died of a disease similar to that of the wife the previous day; and that at the time of his attack he was working on the steamboat levee.

It is stated that case No. 6, Robert Banks, was not connected with the shipping. He was, however, a negro who kept an eating-house upon the steamboat-levee.

Case No. 9, with her husband and child, lived, as is shown upon the accompanying map, within the circle which is drawn around the original point at which the infection occurred.

Case No. 11.—It is stated that "no connection with shipping could be ascertained," and yet the narrative shows that the subject had worked upon the steamboat-levee.

To case No. 12, the same comment applies.

We have been informed that the father of case No. 15 was constantly called by his business to the steamboat-levee.

Cases 19 and 20 were both children, who lived but one block away from the lower ship-levee. It is not shown what was the occupation of the adult residents of this house.

Case No. 22 was attacked after gross imprudence in his diet. We are informed by Prof. S. M. Bemiss that at midnight, prior to his attack,

he had eaten a large beef-steak with mushrooms, after a prolonged fast. This man was a grocer, and his business called him frequently into the portion of the city in close proximity to the steamboat-levee.

We have purposely omitted until this time the consideration of a few cases. Of case No. 2 of the record, it is stated that the patient "had not been absent from home, save at work, for some time, and had visited no ships." Justice Coig was a hard drinker. Just previous to his illness he had been upon a spree, and with a man of his character, when drinking, it is difficult to undertand how any assertions can be positively made as to where he had or had not been. He was first seen by Dr. Vickery when in *articulo mortis*, lying "in a cold, barn-like loft, in a place used for storing green hides." It is submitted that the doubt which surrounds this case, and the presence of causes which were capable of producing a like result, is sufficient to exclude the case from further consideration.

Case No. 13 was a negro child, one year of age, residing with his mother at a house which was also occupied by eight other individuals. The statement is made, "no connection with the shipping ascertainable," but it is not shown at what work the adult occupants of this house were engaged.

No connection with shipping was required in case No. 14, as a negro man had, a few days before her attack, died in a "typhoid state," after a sudden and violent illness, at the same house.

We would further suggest that it is an inaccuracy to speak of the general diffusion of cholera over the city of New Orleans in 1873. Upon the accompanying map a circle has been described, the center of which rests upon the river-front of Canal street. The diameter of this circle is long enough to include the locality at which case No. 15 died. It will be observed that the circle embraces but the heart of the city of New Orleans, and that a large portion of the city is without its limits. By a comparison of this map with that which accompanies the paper of Dr. White in vol. I, Public Health Reports and Papers for 1873, it will be found that the vast majority of the cholera-deaths in 1873 occurred within the area of this circle.

On the 21st of July, 1873, Dr. George Howe, then resident physician quarantine station, Mississippi river, addressed a letter to the president of the board of health, New Orleans, of which the following is an extract: "Since January 1, 1873, there have passed and been personally examined six hundred and thirty-eight vessels of all kinds, and in no instance has there been cholera in any form, nor has there been, as far as I could ascertain, any cholera during the passage of any vessel to this port. My information has been in every instance obtained from the master of the vessel, as well as from the medical officer, when there was one on board. In some instances, when vessels have arrived from ports where cholera was supposed to exist, I have required a sworn statement from the master, signed by himself, which are kept on file as additional evidence. And in no instance have I had reason to doubt the truth of any statement or sworn affidavit."

The tone of this extract is positive, and the evidence seemingly conclusive.

Desiring, however, additional facts, upon August 5, 1874, we addressed a letter to the quarantine physician of the Mississippi station, from which letter we make the following extracts:

I. Will you inform me if, during the months of December, 1872, and January and February, 1873, the quarantine upon the Mississippi river was rigidly enforced?

II. If during the months named any vessels from supposed infected

ports (in original letter, ports were enumerated) arrived at the quarantine station upon the Mississippi river?

III. If vessels from any of the ports named arrived at the Mississippi quarantine station, I would respectfully ask information as to the character of the inspection to which they were subjected.

In answer to these questions, we received from Dr. A. W. Perry, late quarantine physician of the Mississippi river station, a communication, dated August 21, 1874, of which the following is extracted: "*Quarantine in the months you refer to was confined to asking each captain the questions I here inclose.*" We reproduce the list of questions:

Number of permit?
Date?
Name of tow-boat?
Kind of vessel?
Name?
Name of master?
Name of pilot?
Where from?
Number of crew?
Kind of cargo?
Number of passengers, foreign?
Number of passengers, domestic?
Where are passengers from?
Any sickness while out?
What kind?
Any deaths?
What cause?
Are all well now?
Have you a bill of health?
Number of days out?

The letter of Dr. Perry further contains a list of 175 vessels that arrived at New Orleans during the three months named, bringing into that port from the localities before alluded to 1,844 passengers and 3,500 of crew, a total of 5,344 individuals, the majority of whom were from localities suspected of cholera.

From an examination of the monthly reports of the Mississippi quarantine station, which were furnished through the kindness of the President of the Board of Health, the following tables have been prepared:

I.—*A tabular statement of the number of vessels, with the number of passengers and the number of crew, that arrived at the port of New Orleans, La., during the month of December, 1872, and the first six months of* 1873.

Month.	Number of vessels.	Number of passengers.	Number of crew.
December, 1872	150	2,204	2,684
January, 1873	134	1,169	2,667
February, 1873	100	550	1,884
March, 1873	118	726	2,254
April, 1873	121	804	2,285
May, 1873	86	708	1,592
June, 1873	60	406	1,365
Total	769	5,163	14,731

A grand total of 15,294 individuals.

II.—*A tabular statement of the number of vessels, with the number of passengers and the number of the crew, that arrived at the port of New Orleans, La., during the month of December, 1872, and the first six months of 1873, from European, West Indian, and South American ports.*

Month.	Number of vessels.	Number of passengers.	Number of crew.
December, 1872	68	1,407	1,145
January, 1873	53	820	1,52[illegible]
February, 1873	41	278	[illegible]
March, 1873	65	453	1,1[illegible]
April, 1873	57	491	1,24[illegible]
May, 1873	31	481	6[illegible]
June, 1873	27	329	6[illegible]
Total	342	4,249	7,2[illegible]

A grand total of 11,498 individuals.

Following further this line of investigation, from the Annual Report of the Commissioners of Emigration for the State of Louisiana, we quote the following:

STATISTICS OF IMMIGRATION.

The number of foreign immigrants arrived at the port of New Orleans during the year ending December 31, 1873, is as follows:

From Bremen	2,938
From Hamburg	576
From Liverpool	1,834
From Bordeaux	151
From Havre	239
From Marseilles	6
From Palermo	121
From Messina	3
From Genoa	1
From West Indian and South American ports	210
Total	6,079

Five thousand six hundred and eighty-seven arrived in steamships, and three hundred and ninety-two in sailing-vessels.

Classification of immigrants, according to age.

Under ten years	735
From ten to twenty years	1,012
From twenty to thirty years	3,217
From thirty to forty years	720
From forty to fifty years	203
From fifty to sixty years	119
Over sixty years	73
Total	6,079

Of these were born in:

Germany	2,627
Austria	732
France	506
Ireland	683
England, Scotland, and Wales	1,016
Italy	125
Spain	60
Sweden	23
Russia	9
Belgium	14
Holland	11
Switzerland	63
West Indies, Mexico, and South America	210
Total	6,079

Of this number, four thousand one hundred and twenty-two were males; one thousand nine hundred and fifty-seven were females.

Through the kindness of Mr. H. Von Werthen, the agent of the emigration bureau, we obtained much valuable information as to the emigrants who arrive at the port of New Orleans; and from the facts thus obtained we are able to present the following table:

A tabular statement as to the number of emigrants who arrived at the port of New Orleans, La., during the month of December, 1872, and the first six months of 1873, with the port from which they sailed for the United States.

Port of departure.	December.	January.	February.	March.	April.	May.	June.	Total.
Liverpool	467	424	65	190	112	94	244	1,596
Hamburg	491	.....	.....	91	109	.....	.....	681
Bremen	417	169	153	53	224	345	.....	1,361
Barcelona	2	.....	.....	.....	.....	.....	.....	2
Marseilles	3	.....	.....	.....	.....	.....	.....	3
Bordeaux	11	.....	.....	.....	.....	3	.....	14
Havana	8	3	15	18	8	11	9	72
Vera Cruz	.....	.....	3	26	.....	32	.....	61
Palermo	.....	.....	.....	114	6	.....	2	122
Totals	1,399	596	236	482	459	485	255	3,912

Prior to the outbreak of cholera at New Orleans, it was an ascertained fact that cholera was upon its westward march, and that the disease had already, in one instance at least, reached the shores of North America. On the 6th of November, 1871, the steamship Franklyn, from Stettin, arrived at Halifax, having had an outbreak of cholera on the voyage. Two men from the shore who were employed, after her arrival, on this steamer, were taken with cholera. One died of the disease at his home in Halifax; the other man, after he became sick, went to his home at Chezzetcook, a small fishing-village twenty-two miles southeast of Halifax, and there died. At Chezzetcook four other cases occurred in the family of this man, (Lepiere,) two of which were fatal.

The most efficient sanitary precautions were at once adopted at Hali-

fax, and no other cases occurred. After it was known that the disease had been carried to Chezzetcook, the government adopted stringent sanitary measures, and at once checked the spread of the disease.

During the series of inspections instituted at New Orleans, during 1874, it was several times intimated to us, by sanitary observers, that cholera existed in the West Indies during the late months of 1872, but that the fact of its existence had been suppressed. We have most carefully investigated this matter, without, however, obtaining any very definite results. The only clew that could be found was obtained through the Supervising Surgeon of the Marine Hospital Service, who furnishes us with a letter of the honorable the Secretary of State, from which the following extract is made:

"Under date of September 23, 1872, the consul at Kingston, Jamaica, reports the arrival of a coolie ship at Bluff's Bay in that island, and that one case of cholera had occurred since the arrival, resulting in the death of one of the coolies. It was reported also that some sixty of the coolies died on the passage, but the disease was not ascertained by the consul."

The list of the vessels that arrived at the port of New Orleans during January, 1873, shows that direct communication was established between that city and Jamaica and the adjacent islands. January 21, 1873, the schooner Mai arrived from Port Antonio. January 24, 1873, the schooner Challenger arrived from Grand Cayman.

The facts which have thus far been obtained go to prove:

I. That prior to the outbreak of cholera at New Orleans, in 1873, a coolie ship infected with the disease had arrived at Jamaica; and that after her arrival at least one cholera-death had occurred on that island.

II. That at the Mississippi river quarantine, during the last month of 1872 and the early months of 1873, the only inspection to which vessels arriving at that station were subjected, consisted in receiving as final the answers which the officers of vessels saw fit to make to an imperfect list of questions.

III. That during the months named a large number of emigrants arrived at the city of New Orleans from cholera-infected districts.

Upon pushing the investigation further, we are informed that the commissioners of emigration exercise no control over emigrants who arrive at the port of New Orleans, other than of an advisory nature. That the effects of emigrants are inspected upon ship-board by a customs officer, and that upon landing the emigrant follows unmolested his personal inclinations. That the large majority of the emigrants who arrived at the port of New Orleans in the month of December, 1872, went at once to the State of Texas, but that during the succeeding months large numbers passed into the interior of the United States by the Mississippi river route. Emigrants for Texas are usually shipped direct by the Morgan line. The depot of this company joins the ship and the steamboat levee; and individuals availing themselves of this route are seldom detained over night at New Orleans.

Emigrants who desire to pass northward by the Mississippi river remain sometimes for days in the city, *and lodge at emigrant boarding-houses, which face the river upon the steamboat levee. It is an ascertained fact that during the months of January, February, and March many of these houses were filled with individuals of this class.*

We have, therefore, traced individuals from cholera-infected districts of Europe directly to that locality of the city of New Orleans at which the report of the Board of Health states the earlier cases of the disease became infected.

The evidence, although circumstantial, is certainly strong that the unfortunate individuals who contracted cholera upon or near the steamboat levee came in contact with the poison which had been imported in the effects of emigrants from the cholera-infected districts of Europe, from which infected districts it is shown that emigrants did arrive prior to the occurrence of the initial case in the city of New Orleans. This is certainly more reasonable, more in accordance with history, than it is to suppose that a *de novo* development of Asiatic or epidemic cholera occurred at the beautiful Crescent City.

The doctrine of "non-importation" will not stand.

We fully admit that by the board of health, whose officials were earnest in the endeavor to discover the arrival of individuals who might be infected with cholera, every effort was made to develop the facts attending the introduction of the disease. We have with the greatest care gone over the ground which had been previously investigated by the President of the Board of Health, and have been able to determine three additional facts:

I. The arrival of a cholera-infected ship at Jamaica, in September, 1872, and the fact that at least one case of the disease occurred upon that island after the arrival of this ship.

II. The utterly worthless and unreliable quarantine which was maintained at the Mississippi river station during December, 1872, and January and February, 1873. It must be remembered that this station is on the Mississippi river, at a very considerable distance below the city of New Orleans, and therefore far removed from the direct control of the Board of Health.

III. The arrival of emigrants from cholera districts, and the location of such emigrants at the very point in the city of New Orleans at which the early cases of the disease occurred.

It is submitted that these facts destroy utterly the theory of the original development of cholera in 1873 in the United States.

During the epidemic at New Orleans, two hundred and fifty-nine fatal cases of cholera occurred. The number of the non-fatal cases can never be determined; we have made every effort to obtain even an approximation to the number, but without success.

In concluding this paper, we desire to express our obligation to and appreciation of the kind offices which we received at the hands of the officers of the Board of Health.

These gentlemen are most efficient and zealous in the performance of their duty, and it is with regret that we record comments upon the able report which they have made.

From New Orleans cholera was distributed to the interior of the continent by water transportation. It has been found almost impossible to collect information as to the steamboats which became infected, from a mistaken idea on the part of persons employed in the business, that the reputation of the boats would be injured should publicity be given to the fact that they had been infected with cholera. Sufficient evidence, however, has been obtained, as will be developed in the narrative, to demonstrate their agency in the diffusion of the disease.

Since the above narrative was written, we have received the special report of the Board of Health of the State of Louisiana, dated New Orleans, December 31, 1874. From pages 9 and 10 of said special report we make the following significant extracts:

"In April, (1874,) upon the recommendation of this board, Dr. Alfred W. Perry was appointed quarantine physician at the Mississippi station.

* * * * * * *

"Much to the regret of the Board of Health, on the 14th of October, Dr. Perry was superseded by Dr. Howe, who held the position about five weeks, during which period all attempts at economy were disdained, and the expenses brought up to the former rate of about $15,000 per annum.

"At the request of the Board of Health, made in consequence of this official extravagance, and also because of disobedience to positive instructions of the board directing disinfection of vessels from infected ports, Dr. Howe, on November 20, was superseded by Dr. Julius S. Clark."

Upon page 13 we read:

"During the time that Dr. Perry was resident physician of the Mississippi quarantine station, April 11 to October 14, 1874, several vessels which had yellow fever on board, either while in West Indian ports or during the voyage to this port, were disinfected under his supervision. In not one of these did yellow fever make its appearance after the vessel arrived in this city. Two days after the station passed into the charge of Dr. Perry's successor, and contrary to the explicit instructions of the Board of Health, a vessel from Cuba was passed without disinfection. A week after the vessel was laid to wharf and the contents of her hold discharged, yellow fever broke out on the vessel. This may be only a coincidence, but bears strongly the apparent relation of cause and effect."

These extracts are submitted without comment, further than the statement that the gentlemen to whom they refer had control of the Mississippi quarantine station during the winter of 1872 and 1873.

At the town of Algiers a few cases of cholera occurred, which have been recorded by Dr. W. H. Riley.

The first of this series of cases occurred on the 11th day of May, the last upon the 9th of September. With but one exception, these cases were in the persons of individuals who either worked upon or lived in close proximity to the levee. Two of these cases, however, are suggestive.

I. On the 16th of May, a Norwegian sailor, employed upon the Morgan line, was taken with cholera.

II. The mate of the ship Screamer, just arrived from England, was taken with cholera September 9. Both cases recovered.

Jefferson Parish.

Carrollton, Jefferson Parish, is located on the left bank of the Mississippi river, seven miles above the city of New Orleans. This town is connected with the city by a passenger-railway, and many businessmen of New Orleans reside at this point.

For an account of the few cases of cholera which occurred at Carrollton in 1873 we are indebted to Dr. S. L. Henry.

April 15.—A white man, forty-five years of age, by occupation a raftsman on the Mississippi, was taken with cholera and died after an illness of twenty-four hours.

May 19.—A negro child, two years of age, was taken with cholera and died after twenty hours. The parents of this child were very poor; their occupation was unknown.

May 20.—A white man, flat-boatman by employment, was brought ashore at Carrollton sick with cholera, and died the next day.

Eight other cases are reported, but one of whom died. One of the recoveries was in the person of a flat-boatman from the Upper Missis-

sippi. The disease lasted at Carrollton until September 19. Many cases of choleraic diarrhœa are reported, but all cases that were treated during the stage of diarrhœa recovered.

SAINT JAMES PARISH, LOUISIANA.

The untimely death of Dr. Charles Gray, a gentleman of great local reputation, has deprived us of full and complete records of the epidemic as it occurred at this point. Dr. Gray, at the time of the unfortunate circumstance which led to his death, was engaged in the preparation of an elaborate report, but in the confusion which followed his demise the paper has been lost.

Dr. P. M. Lambremont was absent from the parish during the year, and therefore cannot throw light upon the subject; but from Dr. L. De Poorter the following letter has been received:

"CONVENT POST-OFFICE,
"*Saint James Parish, La., 4th 8br*, 1874.

"DEAR SIR: It has been impossible to me to come to a satisfactory statement of the particulars that accompanied the invasion of the epidemic of cholera that prevailed in this parish in the months of April and May, 1873. I will, however, cheerfully, as a testimony of respect to a distinguished member of our profession, state what I know on the subject.

"Asiatic cholera attacked some white laborers working on the plantation of Mr. B. Tureau, situated on the river about seventy-five miles above New Orleans. All those who were attacked died, eight upon the plantation and about as many in different places. The men having fled panic-stricken, their places were supplied by a gang of about forty white men, most of whom were Irish, and who came from points upon the river. These men were at work building a new levee when they were suddenly smitten with the disease, and nineteen died in a few hours. No case that was attacked recovered.

"The symptoms were not violent; a few characteristic evacuations from the intestines and the stomach, muscular spasm, and a gradual sinking, a steady decrease of the phenomena of life. The men lay pulseless, as cold as ice, with their full mental powers, eyes wide open to an ominous and unavoidable danger, when death, a peaceful death, would end their suffering. No treatment had the least efficacy; the calomel and opium plan, however, appeared the best, but they all died; all praying for water, water, iced water, which was given *ad libitum*, but with no better result. For a short time the disease had a tendency to spread. A few negro families living in the neighborhood were affected, and, notwithstanding the most diligent attention, not one escaped; the physician assisting powerless to the most lamentable spectacle the imagination can possibly conceive. * * * * * * * * * *

"I am, indeed, very sorry that I did not take notes at the time on the above subject. * * * * * The Convent of the Sacred Heart and the Jefferson College, two magnificent public establishments a mile apart, that I attend professionally, and between which my residence is situated, escaped the disease.

"Most respectfully,

"L. DE POORTER, M. D.

"Dr. ELY MCCLELLAN."

MADISON PARISH.

The epidemic as it affected Madison Parish was confined to the town of Delta, the village of Tollulah, and the adjacent plantations. At Tollulah and its vicinity the disease is reported to have appeared on the 10th of May, 1873; and to Dr. George T. Trezevant we are indebted for the following valuable information:

Tollulah is a station on the North Louisiana and Texas Railroad, six miles west of the town of Delta. This station is a trading center for the great cotton delta that surrounds it. It is located upon the banks of Brushy Bayou, the banks of which stream have been cleared from its origin at Grassy Lake to its mouth, varying in width from one to three miles. This bayou furnishes the negroes living along its banks with water for all domestic purposes; the better class of whites are, however, provided with cisterns. Immediately in rear of these clearings is a low marshy wood about two miles in width. Brushy Bayou empties into Roundaway Bayou about two miles below Tollulah; the water of both streams is polluted by animal and vegetable matters of all kinds. The "infected district" comprised about five miles on Roundaway, and three miles on Brushy Bayou. The disease first made its appearance at the upper limit of the area of infection on Roundaway, and spread toward Tollulah. Dr. Trezevant is of the opinion that the disease was not imported, "as the first and second cases were parties that had not been abroad in months, nor had they in any manner had it communicated by others." From the first case it can be determined that no others originated, but from the second case (three miles distant from the first case, with which no connection can be traced) there is traced a direct chain of communication, shown in the members of the family and the nurses, despite all precautions to prevent its spread. From this case that of Ruea Sheilds, on May 14, nine cases may be traced, seven of which terminated fatally. Four of these nine cases occurred in a family named Fitzhugh, and during their illness a negro man named Williams was employed as their nurse by the parish authorities. While on duty, Williams was taken ill with cholera, and died before medical aid could be furnished. To this date (June 5) the disease had been confined to the Roundaway district. In spite of professional opposition the body of Williams was carried to Tollulah, and there inspected by his many friends, remaining exposed for more than twenty-four hours. Several members of the family of Williams were taken with the disease; the village of Tollulah and the adjacent plantations were infected. The fact is noted that it is utterly impossibe to prevent a contagious disease from spreading after it once invades the negro ranks; they hold it a very great sin and crime for any one of their number to fail to visit the sick and attend the funeral-rites through fear. The communication of Dr. Trezevant closes with an expression of opinion that the disease was beyond doubt very contagious.

A record of twenty-four cases has been obtained from the Tollulah demonstration, fifteen of which were fatal. Fourteen of the cases reported were males, eleven were females. Six of these cases occurred in the persons of whites, eighteen were negroes. Of the fatal cases, fourteen occurred among negroes, but one among the whites.

The line of treatment adopted was calomel and opium, bromide and chloride of potash, ammonia, chloroform, carbolic acid, with stimulating embrocations and dry heat. Brandy and whisky used with moderation. In cases of convalescence, alterative doses of mercury, with ipecac. and diuretics. Rooms and bed-pans were in all cases disinfected. Bedding

and clothing were burned in all cases where it could be enforced. All cases that were prescribed for in the first stage of the disease, with but two exceptions, recovered. Of the excepted cases, one neglected to carry out the instructions received; the other died on the second day of inanition, no symptom of cholera being present.

In the vast majority of the fatal cases that occurred, in one hour from the inception of the disease the patient was collapsed.

Through the kindness of Dr. S. W. Hamilton, of Delta, we are able to present an outline of the epidemic as it affected the eastern portions of the parish.

Delta is situated on a peninsula, which is bounded on the north, east, and southwest by the Mississippi River, and on the west by a wide scope of country. The town has a population of about six hundred inhabitants. From its location upon the river, and from the fact that the town is the eastern terminus of the North Louisiana and Texas Railroad, Delta is a cotton-market of some importance. The water-supply is obtained from the Mississippi river; some few premises are provided with cisterns.

"The first case of cholera that occurred at Delta was in the person of a white man named Sykes, who came from Milliken's Bend, a point upon the river, some twenty miles northwest. This man was vomiting and purging when he arrived, on the 13th day of May; at 10 o'clock a. m. cholera was developed, and at 5 o'clock p. m. the same day he was dead. As the disease was at the time epidemic on Roundaway Bayou, this case occasioned great alarm. The circuit court, which was in session, was adjourned, and every effort was made to arrest the disease. No other cases of cholera occurred in town until June 3, when it was brought in from the infected district on Roundaway, and was confined almost exclusively to the negroes, many of whom died without receiving medical aid. In some families many cases of the disease occurred, and the attendants upon the cholera-sick were by no means exempt. The prevalence of the disease among the negroes is accounted for on the ground that they, regardless of consequences, ate freely of fruits and melons. The negro loses all fear of disease when his stomach makes a demand on him. There were many cases upon the river-steamers; one boat buried a cholera-subject near Milliken's Bend, early in May; other boats buried cases at different points, of which I have not been able to obtain all the facts. I feel assured that the disease reached us through that channel."

Sixteen cases of cholera occurred at the town of Delta, six of whom died. Of the individuals attacked, eleven were whites, five were negroes. Four whites and two blacks died. Fourteen of these cases were males, two were females.

Upon the Ballard plantation, near Delta, seven cases occurred, with five deaths. All of these individuals were blacks; three were males, four were females.

At the California plantation, two cases occurred; both were fatal, and both were in the persons of negro females.

At the Nebraska plantation, fifteen cases occurred. All were negroes, eleven of whom died. Nine of these individuals were males, six were females.

Five employés of the North Louisiana and Texas Railroad died of the disease; all were whites.

A vast number of diarrhœa-cases occurred, that were successfully treated and the disease arrested; and it is most probable that the figures noted only approximate to the number of cases of the disease.

Owing to the death of Dr. Riordan, which occurred early in the year 1874, we have been unable to obtain much valuable information which he possessed as to the epidemic on the Roundaway Bayou. Through Dr. Riordan it is most probable that the facts concerning the introduction of the disease into Madison Parish could have been determined.

La Fourche Parish.

It has been found almost impossible to obtain any information as to the demonstration of cholera in La Fourche Parish. Early in the spring of 1874, from the extensive overflow and inundation from the breaks in the Mississippi river levee, nearly the entire parish was under water. The disease was confined almost exclusively to the negro employés upon plantations, and in many instances the physicians who attended them have removed to other localities where they could not be communicated with.

The primary outbreak of the epidemic occurred among the employés on the Oak Grove plantation, near Thibodeaux, and upon the Bayou La Fourche. The first case occurred after contact with a trading-boat directly from New Orleans. The epidemic was confined to four plantations near Thibodeaux and Raceland, and about one hundred cases occurred, the majority supposed to have been fatal.

Dr. Fulton Rogers, the parish physician, in a letter dated Thibodeaux, July 25, 1874, states that no cholera occurred in the parish, but that many cases of cholera morbus occurred, caused by eating unhealthy fish, and that, during the overflow of 1874, a number of similar cases occurred.

Ouachita Parish.

All possible effort was made to secure an account of the epidemic as it affected Ouachita Parish, but without securing any information of value. The following letter demonstrates the willingness of the profession of the parish to aid in the undertaking, as well as the causes which have prevented our collecting the desired facts:

"Monroe, La., *July* 6, 1874.

"Sir: Your letter of June 1st was received by due course of mail and contents carefully noted. Before replying to it I desired to have a full conference with each one of our physicians, and as one of them was absent, who had seen a good deal of the cholera last summer, I awaited his return and thus delayed my answer. I find that none of our physicians made notes of a single case, and it will, therefore, be impossible for me to provide you with the information you desire. In a general way I may state the disease prevailed almost exclusively among the negroes in the suburbs of our little city, and among the poor class of whites, only one white person having died from the disease who was surrounded with the comforts of a good home, and his death was due to neglect of the premonitory cholerine. About seventy deaths occurred in all, a large majority of whom were negroes. Not one-half of those who died among the negroes received medical attention, from an ill-founded and absurd notion among them that the physicians, glad of an opportunity to slyly kill them, would either give them wrong medicines or poison. One peculiarity I may mention. In nearly every case that died, death was preceded from twenty-four to forty-eight hours by suppression of urine, and in many instances the patient seemed to die more from this complication than from the choleraic symptoms.

"I regret that I cannot give you a more satisfactory answer; but so little interest was felt by the physicians in the cholera as it appeared here, on account, mainly, I presume, of the class of persons affected, that no notes were taken, and of course I can make no other report.

"Very respectfully, your obedient servant,

"R. C. STROTHER, M. D.

"ELY MCCLELLAN, M. D.,

"*Assistant Surgeon, U. S. A.*"

Persistent application has been made to other physicians of Monroe and Ouachita Parishes, but with no other result than an expression of regret that, as no notes or records of the epidemic were kept, accurate information could not be furnished.

BATON ROUGE PARISH.

Baton Rouge, the former capital of the State of Louisiana, is located on the east bank of the Mississippi River, one hundred and twenty-nine miles above New Orleans. The city is built upon the first bluff which is met in ascending the river, giving to the site an altitude of 25 or 30 feet above the highest overflowings. This city has the reputation of being one of the healthiest in the Lower Mississippi Valley. The population in 1870 was 6,498 individuals.

On the 7th of May, a white man named Martin, fifty-four years of age, who was employed at the coal-wharf in coaling river-steamers, was taken with cholera, and died after an illness of seventy-two hours. The day before he was taken sick he had been at work on a barge that had arrived from Port Hudson, at which point cases of cholera had occurred.

May 13.—A daughter of this man was attacked with cholera, but recovered. At the same house, on the 15th, a female child died.

We are informed by Assistant Surgeon C. Ewen, U. S. A., stationed at Baton Rouge, that subsequently two negro men who were employed at this coal-yard died of cholera; and that upon the Highland road, south from the city, several deaths occurred among negroes.

In addition to the family of Martin, four cases are reported, two of which were fatal.

CONCORDIA PARISH.

No returns have been received from this parish, although persistent effort was made by letters, which were addressed to all medical gentlemen whose names could be obtained.

We have, however, unofficial reports that about June 11 a number of cholera cases occurred upon the plantation of Mr. Lambdon, and that ten of these cases died.

About the 19th of June, the same reporter states that at the plantation of Mr. David Miller twenty-six cases of cholera occurred, with six deaths.

Both of these plantations are near the town of Vidalia.

CARROLL PARISH.

One case of cholera is reported as having occurred at Transylvania, Carroll Parish, on the 23d of June, in the person of a negro laborer upon a cotton plantation. The case recovered.

Dr. C. R. Whitehead states that no other case came within his knowledge; and he is of the opinion that cases of cholera occur every year on the Mississippi river.

SAINT MARY'S PARISH.

We are able to present an interesting account of the epidemic as it occurred in Saint Mary's Parish, from the pen of Dr. S. Allen:

"GENTREVILLE, LA., *May* 12, 1874.

* * * * * * *

"SIR: The first as well as the greatest number of cases of cholera happened on the plantation of Mr. Thompson. This beautiful estate is situated directly upon the Bayou Teche, about twelve or thirteen miles west of Brashear, and is one the best-cultivated, best-drained, and generally best-managed plantations in the parish.

"Some time during the latter part of May, 1873, I was called in haste to visit Mrs. N., aged about fifty years. I found the patient on board a trading-boat, lying at Thompson's wharf. She was suffering with every symptom of cholera, with a rapid tendency to collapse. I learned that about six hours before my arrival she had been suddenly attacked with "violent and frequent" vomiting, attended with terrible "pain and cramps;" that these symptoms were followed in the course of an hour by copious and frequent alvine dejections. About one hour before my arrival the nausea and vomiting had in a great measure ceased, but I soon discovered that they had not departed finally, as I found her not only vomiting, but purging almost continuously and involuntarily pure rice-water. The extremities were cold and damp, the forehead covered with large drops of sweat; abdominal and gastrœnemic muscles contrasted into knots, bladder empty, no urine having been discharged during the past four hours. There was inordinate thirst.

"The patient recovered readily under the following treatment: The free and general application of dry heat and sinapisms externally. One grain of calomel was given every twenty minutes, until a change in the color of the dejections was noticed. Iced water was given *ad libitum*.

"The above was the first case that occurred on or near the Thompson place, and probably was the first in the parish.

"On July 5, Esau Tilghman (a laborer on the Thompson place) was attacked, and died on the 9th. On the 10th, Ann Watts was taken sick, and died on the 14th. On the 14th, Mary Jackson, Andrew Jackson, and Rhoda White died after a few hours' sickness. There seems to have been a special malignity about the last three cases, as they were perfectly well at breakfast-time, all ate heartily, yet by 3 o'clock the same afternoon all were dead. On the 18th of July, the boy Harry died, sick about two days. August 11, Alexis Frederic died, after a few hours' illness. During somewhat over a month's time there were forty cases, with eight deaths.

"I have recently been informed by my friend, Dr. H. J. Saunders, (who owns a plantation situated about one and a half miles below that of Mr. Thompson,) that he had about twelve cases of pure cholera, none of which terminated fatally, though one was in a collapsed condition for several hours. His treatment consisted in the active administration of an opiate and astringent mixture, together with the external application of the cold douche and wrapping in sheets wrung out from cold water. Dr. Saunders also informs me that there were a few cases on the Torian and Geneve plantations, all of whom, together with those on his own place, took the disease, he feels assured, after visiting the sick at the Thompson place. At any rate, no case happened on his place among those who had not visited Thompson's, more or less frequently, after cholera was developed there.

"Dr. A. S. Gates, of Franklin, informs me that but one case occurred

at that town during the past summer, and that in the person of a deck-hand on the steamboat Ida, a boat that plied regularly between New Orleans and Saint Martinsville. The patient was moribund when Dr. G. saw him, and had evidently contracted the disease in New Orleans. On comparing dates, I find that cholera already existed on the Thompson place at the time the Ida brought the above case to Franklin.

"The trading-boat upon which the first case occurred had been for months engaged in simply moving up and down the Bayou Teche, trading at the different plantations; had been nowhere, at any rate, where cholera prevailed. The only connection she had with New Orleans consisted in the packages of goods received from there via Morgan's Railroad. I could discover nothing in the water or food generally used on the plantation of an impure or unhealthy character.

"There were two plantations near Thompson's, on which a rigid quarantine was exercised. On one, by my advice, all the houses in which the employés lived were whitewashed and thoroughly cleansed, and carbolic acid was freely applied. No cases of cholera occurred upon either of these plantations, with but one exception, that of a man and his wife who violated the quarantine rules and attended funerals at the Thompson place.

"Very respectfully,

S. ALLEN.

"Dr. C. B. WHITE,
"*President of the Board of Health.*"

Dr. Allen states at a later date that after a most thorough and exhaustive examination he was unable to discover either a local or imported cause sufficient to account for the original outbreak. Probably no plantation in the State is better managed; well drained, having an abundant supply of good cistern-water, food of the best quality, and the houses in which the employés resided were roomy, well ventilated, and raised some three or four feet from the ground. At this plantation (Thompson's) the disease was localized, ("endemic.") All the other cases were directly traceable to infection received while the subjects were visiting or attending funerals on the Thompson place.

The letters of Dr. Allen demonstrate that the cholera-infection, so far as it affected Saint Mary's Parish, had for its initial case the woman at the wharf of the Thompson plantation upon a trading-boat, and that this boat had been for months upon the Bayou Teche, passing up and down stream. But there is nothing to show that the employés of this boat (one of the small craft to which attention has been given elsewhere) had not been from her either to the city of New Orleans, or upon steamboats from that city. Owing to the overflow which devastated the section of the country during the early spring, we have been unable to obtain as full records as were to be desired; but from facts that have incidentally come to our knowledge we are led to the opinion that there was communication between the trading-boat and the steamer Ida prior to the outbreak.

CHAPTER VI.

MISSISSIPPI GROUP.

MISSISSIPPI CONTRIBUTORS.

Dr. P. F. Whitehead, Warren Co.
Dr. W. T. Balfour, jr., Warren Co.
Dr. D. W. Booth, Warren County.
Dr. J. F. O'Leary, Warren County.
Dr. P. A. Quin, Warren County.
Dr. Le Grand G. Capers, Warren County.
Dr. H. Shannon, Warren County.
Dr. J. A. Tillman, Washington Co.
Dr. T. J. Mitchell, Hinds County.
Dr. P. F. Bailey, Hinds County.
Dr. Geo. St. C. Hussey, Adams County.

DATES OF INITIAL CASES.

Vicksburgh, Warren County.....April 8.
Jackson, Hinds County.....June 1.
Deer Creek, Washington County.....June 14.

MISSISSIPPI.

WARREN COUNTY.

The city of Vicksburgh is built on the east bank of the Mississippi river, equidistant from New Orleans and Memphis. Its altitude is 175 feet above the level of the sea. The town is upon hills, whose steep sides afford fine natural drainage into the river and two bayous; one of which flows westward through the northern portion of the town and empties into the river just above the city landing, the other flows south, parallel with and empties into the river several miles below the city.

There is but one underground sewer in the city, that commencing at the highest point on Washington street, near the Railroad depot, and running north to the river some seven or eight blocks.

The police and sanitary regulations are bad; most of the time no attention is given to this matter, but when there is a threatened or actual invasion of epidemic diseases, a board of health and a health officer are appointed, whose term of service expires with the exigency that called them into being. At the time at which the cholera made its appearance the condition of the city was unusually good. The small-pox epidemic, but just past, had caused a board of health, who had done what they could to clean the city, and had ordered the continued use of disinfectants.

Dr. J. M. Hunt reports that on the 8th day of April he treated a young man named Maiden, who was sick with cholera. This man lived on Levee street, just in front of the wharf-boat, at a boarding-house frequented by river-men. Maiden was taken ill at 1 o'clock a. m., and died at 8 o'clock a. m. the same day. Dr. Hunt reports this as a typical case of cholera. Had cramps, rice-water discharges, and died fully collapsed. Had recovered from an attack of syphilis a short time before. Was a dissipated man, but, as far as can be learned, had not been out of the city.

May 12, A. P. Kuhn, a dissipated white man, who was just over an attack of delirium tremens, and had gone upon another spree, was taken with cholera. Where he had been for two days prior to his attack is unknown; he had been away from his home, but it is thought that he had not been out of the city. This man recovered after an illness of five days.

On the 14th of May the steamer John Kilgore, from New Orleans, arrived at the wharf-boat, having a cholera-case on board. Dr. D. W. Booth, of Vicksburgh, took charge of the case, and to him we are indebted for the following account:

"The patient, Mr. John Schenck, of Ohio, had been troubled for some days before leaving New Orleans with diarrhœa, which continued after he took passage on the Kilgore for Cincinnati. During the early hours of May 14 this diarrhœa became more violent, and was accompanied with vomiting and cramps. He had been very imprudent in his diet, eating freely of fruit both in New Orleans and on the boat. When first seen by Dr. Booth, the condition of the patient bordered on collapse, pulse barely perceptible, washer-woman's fingers, profuse colliquative sweat, tongue cold and pale, extremities cold, and the usual pinched expression of countenance. The discharges had ceased, and did not again occur until after death. Nausea was not excessive, the vomiting only occasional. Mr. Schenck died at a point about fifty miles above Vicks-

burgh. The excreta were thrown overboard without being treated; and there is nothing to show that any unusual care was exercised in regard to the clothing, beds, and bedding."

Dr. Booth left the Kilgore at Lake Providence, some seventy-five miles above Vicksburgh. At that time no other cases had occurred on the boat, but Dr. Booth notes a fact of much significance: "the Kilgore was crowded with passengers, many of whom were on deck." The body of Mr. Schenck was carried to Memphis, where it was removed to an undertakers, placed in a metalic casket, and forwarded by rail to his family in Ohio. The Kilgore proceeded on her passage to Cincinnati, with what results will be noted hereafter.

Dr. Booth reports that after he left the Kilgore at Lake Providence on the 16th of May, he saw a case of cholera at that point which terminated fatally.

May 16, Mrs. Kuhn, the wife of the case of the 12th instant, was taken with cholera, and died the next day. This lady, who was in very feeble health, had been living in the country, about one mile from the town. During her husband's illness she was brought into the city and to his sick room, when she was herself attacked.

From this date the disease is reported as having occurred throughout the community. We have not succeeded in obtaining full lists of all the cases that occurred, but a record of thirty cases have been obtained: this record, as to twenty-three cases, is full and complete, showing that twelve cases occurred in the persons of males and eleven in females. Eleven were blacks and twelve were whites; fifteen died, eight recovered.

By Dr. Le Grand G. Capers, a prominent physician of Vicksburgh, we are informed "that there was a general tendency to bowel affections during and subsequent to the visitation of the disease;" that a very large number of such cases were treated, and that an unusual number of cholera-morbus cases occurred during the same time.

To Doctor P. F. Whitehead we are indebted for much of the information upon which the Vicksburgh narrative is based.

It is known that cholera existed at several points in this State, upon the line of the river, and below the city of Vicksburgh, but we have been unable to collect the information.

Hinds County.

Jackson, the capital of the State of Mississippi, is located upon the right bank of Pearl river, forty-five miles east of Vicksburgh. The Vicksburgh and Meridian and the Mississippi Central Railroads pass through the town; the latter being a great trunk line of railway to and from the city of New Orleans.

We have made every effort to obtain full information of the epidemic as it occurred at this point, but without success.

From a letter written by the late Dr. J. F. Harrington, of Jackson, to Prof. N. S. Davis, of Chicago, we are able to gather the following facts:

The first cases of the disease that occurred at Jackson were on the 1st day of June, 1873, upon which day three cases of the disease occurred. One was in the person of a man from Memphis, Tenn., who had been at Jackson one week prior to his attack; the other two individuals were residents of Jackson. The sanitary condition of the city was bad at the time of the outbreak. That while the first pronounced cases did not present themselves until the 1st of June, the entire community had been suffering from diarrhœa for some two or three weeks

previous. We have made every effort to follow out the clew contained in the letter of Dr. Harrington, but as circumstances conspired to prevent any lengthened personal inspection, we were compelled to intrust the work of collecting data to other hands, and obtained the most discouraging results.

At the State penitentiary, which is located at Jackson, it is reported that eleven cases of cholera occurred with but one death. This fatal case occurred within the penitentiary walls on the 15th of June, and died within twenty-four hours. We are unable to obtain any facts as to the outbreak at this penitentiary.

No cases occurred at the Lunatic or Deaf and Dumb Asylums. Dr. P. F. Bailey states that the larger portion of the citizens of Jackson were affected with diarrhœa, which was, however, readily checked. Every fatal case was traceable to atmospheric influences, irregular habits, and impure water.

Dr. T. J. Mitchell states that the disease was chiefly confined to the negro population, and that over 50 per cent. of the cases were fatal. That among the negroes the course of an attack of the disease was exceedingly rapid; a few hours, in the majority of the instances, terminating the case.

One interesting case illustrative of the portability of the disease is related. A negro girl who was employed as a servant in a family living in the city was taken with cholera and died after an illness of fourteen hours. The family of this girl lived in the country, some miles from town. A few hours after her death her father and mother arrived to see her; and after her death removed her bedding and clothing to their home. One week later the entire family, consisting of the parents and five children, sickened with cholera, and all, with the exception of the father, died.

Washington County.

The only return which we have received from Washington County is from the locality known as Deer Creek, and that through the kindness of Dr. J. A. Tillman.

Greenville, the county town, located upon the east bank of the Mississippi river, was infected with cholera early in the season of 1873, but we have been unable to present any history of this demonstration, from the fact that during the fire of the summer of 1874, that destroyed nearly the entire business portion of the town, the office of Dr. Stewart White, who had been engaged in collecting the information of the local epidemic, was consumed, and with it all his notes and records, which could not be reproduced.

From Dr. Tillman we learn that the cholera appeared on the 14th of June, among a gang of laborers upon a plantation, and that the first three cases, all of whom died, lived at the same house. The previous history of these cases we have been unable to obtain. Dr. Tillman writes: "The most peculiar attendant of the epidemic was its inclination to attack certain localities, leaving a large scope of country, or a number of plantations, intervening, and again descending on others with almost universal fatality, and on others in a more modified form; yet the premonitory symptoms were universal in all. After the communities in which the epidemic prevailed became convinced that diarrhœa was a premonitory symptom of cholera, and after they had taken the precautionary steps to adopt an early treatment, we saw but comparatively few cases, and very soon the disease disappeared from the county,

leaving us as much amazed at its rapid decline as at its sudden appearance."

Dr. Tillman reports twenty-five cases of the disease, with fourteen deaths. Many of these cases occurred in families of which two or more members were attacked with the disease. One instance is of interest. A negro man stole, from a house that had been abandoned on account of cholera, some articles of clothing and carried them to his own house. Within three days this man, his wife, and his three children, were prostrated with cholera, from which the wife alone escaped with her life.

The other physicians of this locality failed to report their experience with the disease.

Dr. W. Y. Allen, of Skipwith Landing, Washington County, reports that no cases of cholera occurred at that point, although he saw "six or seven cases of cholera morbus."

HOLLY SPRINGS, MARSHALL COUNTY.

It having been reported in a newspaper of Memphis, Tenn., that three deaths from cholera had occurred at Holly Springs, Miss., on July 6, 1873, we carefully investigated the report, and have been informed from the leading physicians of that place "that no cases of cholera occurred at that point in 1873."

MERIDIAN, LAUDERDALE COUNTY.

Dr. John D. Kline, of Meridian, states that no cases of cholera occurred at that town in 1873.

FRIAR'S POINT, COAHOMA COUNTY.

We have been informed by a gentleman residing near Friar's Point that cholera prevailed extensively among the negroes employed upon his plantation; but we have failed in all endeavors to obtain information from the medical gentleman who treated the cases.

Although it has been found impossible to collect the information from those who possess the knowledge, we do not hesitate to state that during the months of March and April the cholera was prevalent upon both sides of the Mississippi River as far north as Memphis; that it was confined chiefly to the negro employés on plantations and the residents of the various landings upon the river.

We confess to the discouraging failure which in this locality attended our efforts to collect the facts of the epidemic; the most persistent and long-continued efforts were unavailing.

In answer to a communication addressed to him, Dr. George St. C. Hussey, health officer of the city of Natchez, writes: "We have never had Asiatic cholera in this city;" and adds information which, although not pertinent to the investigation, is still possessed of so much interest that we offer the extract:

"We have had but one visitation of yellow fever in the past ten years—that of 1871—when the disease was brought from New Orleans on board a steamboat, which had evaded the quarantine and passed that city. At Natchez a sick man was put on shore, and he was carried through the streets for several hours, in an open cart, before a place could be found for him. In a few days the city had cases of yellow fever in every portion, and, strange to say, it commenced in some of our best and most careful families, with whom it proved the most fatal.

The disease found our city in its ordinary sanitary condition, which is generally good, requiring but little effort to keep it so, the drainage of almost the entire city being most excellent. The last visitation of 1873, that had such fatal results at Shreveport, La., and Memphis, Tenn., was effectually prevented by a close observance of our quarantine regulations and rigid sanitary improvement, and we had not a case in the city.

"As to our supply of water, we use none other than pure cistern-water, which, it is said by some of the oldest citizens, was the cause of cholera not prevailing here, when known to be all around us."

CHAPTER VII.

ARKANSAS GROUP.

ARKANSAS CONTRIBUTORS.

Dr. A. L. Breysacher, Pulaski Co.
Dr. P. O. Hooper, Pulaski County.
Dr. W. G. Wright, Pulaski County.
Dr. R. G. Jennings, Pulaski County.
Dr. J. R. Dale, Pulaski County.
Dr. Thompson, Pulaski County.
Dr. D. H. Dungan, Pulaski County.
Dr. J. H. Lenow, Pulaski County.
Dr. W. C. Gillespie, Pulaski Co.
Dr. J. M. Holcomb, Jefferson Co.
Dr. R. A. Burton, Phillips County.
Drs. Felts and Palmer, Mississippi County.
Dr. V. E. Kersh, Lincoln County.
Dr. H. P. Crute, Chicot County.

Acting Assistant Surgeon J. H. Carroll, U. S. A.

DATES OF INITIAL CASES.

Osceola, Mississippi County.....April 14 and September 8.
Chicot, Chicot County.....May 19.
Pine Bluff, Jefferson County.....June 25.
Little Rock, Pulaski County.....June 30.
Starr City, Lincoln County.....July 17.
Helena, Phillips County.....July 20.

ARKANSAS.

Epidemic of 1873 at Osceola, Mississippi County.

REPORTED BY DRS. FELTS AND PALMER.

The town of Osceola is located upon the west bank of the Mississippi river, eighty-seven miles above the city of Memphis. The country is level and interspersed with numerous lakes and bayous. The nearest hill is forty miles distant, a ridge which extends from the Ozark Mountains in Missouri to Helena, Ark. This district, which is known as the "sunk lands," from the effect produced by the earthquakes of 1811 and 1812, is drained by the Saint Francis and Little rivers. The region is highly malarial. Osceola is a town of some two hundred inhabitants, who depend upon river-transportation alone for communication and supplies.

On the 17th day of April, 1873, a white man, forty-eight years of age, was attacked with cholera and died after an illness of a few hours. He lived in a miserable hovel a short distance north of the town. This cabin was filthy in the extreme, and contained but one room, in which two families, consisting of ten individuals, lived. April 18, the wife of this man was taken with the same disease. She was at once removed from this house; was carefully nursed, and recovered after an illness of six or eight days. The same day that this woman was attacked, a man named Lawrence, who also lived at the same cabin, was taken with cholera, and the next day his wife was also attacked. The two last cases also recovered, after having been collapsed from twenty-three to seventy-three hours.

It was subsequently ascertained that Lawrence, who was a vagrant, had, some two or three days before the first case occurred, returned from Memphis, and that he was then suffering from diarrhœa. The other occupants of this cabin had more or less diarrhœa, but in each instance the disease was checked. The cabin and surrounding grounds were cleansed and disinfected. The excreta of all the cases were disinfected and buried. No other cases occurred.

On the 8th of September, a negro woman, twenty-eight years of age, living in the town, was taken with cholera and died after a few hours' illness. The next day a man who lived with this woman, and who had been in constant attendance upon her during her illness, was taken and died after eight hours' illness. It was supposed that this man had been employed upon some of the river-boats, but it cannot be definitely determined.

September 9, a white man named Sowers, who lived some five miles north of Osceola, was attacked with cholera and died the same day. It is not known where he contracted the disease. He lived three-quarters of a mile from the river; was extremely poor, and worked at any employment he could obtain. That just before his attack he had obtained some work, is shown from the fact that the day before he died he had purchased a quarter of beef, and, as he and his family had been deprived for some time of meat of any kind, they gorged themselves.

From this point, however, there is no obscurity in the transmission of the disease. Sowers lived in a cabin which was one of a group of similar structures that had been formerly used as quarters for negroes. The

other cabins were occupied by families named Waddell, Lucas, and Cabels; and in each family a fatal case occurred.

A man named Maples, who was exposed to the infection at the quarters where Sowers had died, was taken ill at his home, some miles distant, and died, after twenty-four hours, on the 14th of September.

September 15, a Mrs. Ashley, who had been visited by persons from the infected houses, was taken with cholera and died the next day. A few hours after she was attacked, her daughter, three years of age, sickened and died about the same time as her mother. These two cases were nursed by their relatives, and among them three other cases occurred, two of which terminated fatally.

During the course of the epidemic, twenty-three well-defined cases of cholera occurred, in addition to those which have been already noted. Fourteen of these cases occurred in the persons of males, nine in females. Fourteen were whites, nine were blacks. Seven of the cases died, sixteen recovered. Seven were in the persons of children, of whom three died. The greatest age noted was eighty-one years; this patient recovered after an illness of six days.

During the epidemic, one medical man died of cholera. He had, however, not been exposed directly to the infection, having been for many months an invalid.

So far as can be ascertained, but in one instance was the disease carried to any great distance in the country. After the death of Maples on September 14, his brother, at whose house he had died, moved westward with his family. The journey was undertaken in wagons. It was afterward known that cholera broke out in his family while *en route*, that Maples had died in a camp, after but a short illness. Some effort has been made to trace up this family, but nothing can be learned of them after they left the camp at which Maples died.

The treatment adopted was calomel and camphor in full doses, and opium was used with extreme care. Alcoholic stimulants were avoided, and in their place chloroform and chloral hydrate were exhibited. In one case hypodermic injections of morphia sulphatis, gr. $\frac{1}{4}$, with chloral hydrate, grs. ij, were used with beneficial results.

Carbolic acid, permanganate of potash, bromo-chlorallum, chloride of lime and quick lime were employed as disinfectants. It was noticed that wherever the free use of disinfectants was instituted the disease was arrested; but the utmost difficulty was experienced in securing disinfection in families living in the country.

Chicot County.

The history of the epidemic as it affected Chicot County is contained in the following letter:

Chicot, Ark., *November* 5, 1874.

My Dear Doctor: The first case of genuine cholera occurred at this place on the 19th of May, 1873, in the person of Joseph Fowles, a man of regular and steady habits, and who was at no time during my acquaintance with him ever guilty of any personal excesses. He was an engineer by profession, and ran an engine upon the Little Rock and Pine Bluff Railroad from this point to Collins station, a distance of about twenty-eight miles, and was of necessity exposed a good deal at night to the inclemency of the weather.

On the Saturday night previous to his attack, he came into my office to consult me, thinking that he had experienced a slight chill, which was followed by a moderate fever. I gave him a prescription, with

instructions to report to me the next evening, if he had another chill. He did not return. On Monday morning he was much better, so much so that he felt able to take charge of his engine. About two hours after leaving Chicot, he left the engine at a way station to go to stool, and when he returned, remarked to his assistant that he believed he had discharged at least two gallons from his bowels, and that he felt chilled through. They administered to him such stimulants as they could get, but he continued to grow worse until they reached Collins, where he was put to bed, and received the care of the physicians of that place. The engine returned to Chicot as rapidly as possible for me. I reached Collins about 8 o'clock p. m. Although he had received all the care and attention that could have been given him, he continued to sink. I found him collapsed, and at 10 o'clock p. m. he was dead.

This is a fair history of all the fatal cases that occurred in this vicinity; and in every case in which the disease was allowed for two hours after the first symptoms to go on without treatment, no impression could be made by any treatment and the attack was fatal. Four cases yielded to the free administration of chloral hydrate in twenty-grain doses, repeated every twenty minutes until the severity of the attack was arrested. The majority of the cases were laborers upon the railroad; and those of them who were careless in their habits, intemperate, and who lived upon badly-cooked vegetables, were the most frequently attacked.

My impression is that the disease originated here. We have fallen into the habit of attributing all the ills to which the human flesh is heir in this portion of the country to malaria. Whether this is scientifically true, I am not prepared to say. I do know that, so far as I was able to discover, there was no local cause for cholera that had not existed here for nearly two years previous to the outbreak of the disease. About this time usually we have been in the habit of having intermittent fever in its mildest form; but during the prevalence of the cholera not a single case of intermittent fever occurred, nor was there any evidence of fever of any kind shown in the community during the forty days that cholera prevailed.

The disease appeared at many places along the banks of the Mississippi river almost simultaneously, proving to my mind conclusively that the predisposing cause of the disease was to be found in some peculiar condition of the atmosphere. At certain seasons along the line of the Mississippi river, when the atmosphere becomes impregnated with that subtle influence which we call malaria, certain diseases prevail, which are more or less severe according to the intensity of the poison. Thus, in certain conditions of the atmosphere we have intermittents, in others bilious remittent, cholera, and yellow fever. These changes sometimes follow each other in regular succession, and as each new change occurs a different grade of disease predominates. Thus, during the prevalence of cholera last year, every change in the system of any character resulted in a choleraic tendency, and one month later the diseases were all intermittent; in three months the yellow-fever type predominated.

The cholera here was easily managed when treated in time; but if allowed to go on without medical interference, even for two or three hours, it was as severe as I have ever known it at any other place.

H. P. CRUTE, M. D.

Dr. ELY MCCLELLAN, U. S. A.

JEFFERSON COUNTY.

On the 25th of June a white man, named L. L. Martin, was attacked with cholera at Pine Bluff and died after an illness of about twenty hours.

Pine Bluff is located upon the right bank of the Arkansas river, forty-eight miles below Little Rock.

We have utterly failed to obtain any information as to the history of Mr. Martin, but his death leads to the history of an interesting group of cases, for which we are indebted to Dr. J. M. Holcombe.

Mr. Martin died of cholera June 26; four days later (June 30) Mr. Cosart, a son-in-law of Martin, and who resided in the same house, was taken with the same disease and died the next day. July 3, Mrs. Cosart was taken with the disease, but recovered. July 5, O. A. Bradshaw, a white man, forty-one years old, who had nursed Martin, was attacked with cholera, and died within ten hours; and the same day a negro woman, who was the cook in Bradshaw's family, also died of cholera.

Martin and Cosart lived in the lower portion of the city and upon the bank of the river. Bradshaw lived in the upper portion of the city, but quite close to a branch which flows through the town.

PULASKI COUNTY.

One of the most interesting demonstrations of the cholera-epidemic of 1873 is to be found in the records of the city of Little Rock, Ark. This beautiful city is located upon a high bluff on the south bank of the Arkansas river, three hundred miles from its mouth. The city has railway communication with Memphis, Tenn., one hundred and fifty-five miles northeast, by the Memphis and Little Rock Railroad, and with Saint Louis, Mo., three hundred and forty-six miles northeast, by the Saint Louis, Iron Mountain, and Southern, and the Cairo and Fulton Railroads; and with Austin and Galveston, Texas, over five hundred miles to the southwest, by the Cairo and Fulton, the Texas Pacific, and the International and Great Northern Railroads.

In 1870 Little Rock had a population of 12,380, of whom 7,101 were white.

The report of the vital statistics of Little Rock for the first six months of 1873, made by Dr. R. G. Jennings to the Arkansas State Medical Society, shows a total of but 315 deaths from all causes, as shown in the condensed recapitulation.

Diseases.	From April 1 to December 31, 1871.			1872.			From January 1 to June 30, 1873.		
	White.	Colored.	Total.	White.	Colored.	Total.	White.	Colored.	Total.
CLASS I.									
Miasmatic diseases	73	28	101	79	29	108	49	57	[illegible]
Enthetic diseases	.....	1	1	2	2	4	2	1	
Dietetic diseases	5	.....	5	11	.....	11	3	.....	
CLASS II.									
Diathetic diseases	3	.....	3	3	1	4	4	.....	
Tubercular diseases	25	26	51	39	38	77	9	1[illegible]	
CLASS III.									
Diseases of the nervous system	17	17	34	46	15	61	22	15	
Diseases of the throat, heart, lungs, and digestive organs	53	33	86	56	50	106	50	34	

Diseases.	From April 1 to December 31, 1871.			1872.			From January 1 to June 30, 1873.		
	White.	Colored.	Total.	White.	Colored.	Total.	White.	Colored.	Total.
Diseases of the urinary and genital organs	2	1	3	6	8	14	4	3	3
Diseases of the bones	1	.....	1	1	.....	1	.....	.....	.....
Diseases peculiar to females	1	.....	1	3	1	4	3	1	4
CLASS IV.									
Violent diseases	9	7	16	9	10	19	5	3	8
Unclassified diseases	14	31	45	25	31	56	10	22	32
Total	203	144	347	280	185	465	161	154	315
Children under five years (included above)	71	61	132	95	79	174	35	59	94

It will be observed that the malarial diseases of Little Rock represent a greater number of cases than any other class. This is owing principally to the fact that a large percentage of cases either come here, saturated with the poison, for medical treatment, or are brought here, as is frequently the case, for interment.

The proportion of diseases of the miasmatic class, in Little Rock, is not above the general average of the country, and, as compared with that of the entire State of Arkansas, is believed to be greatly below the average.—[Extract from report on vital statistics.]

The first case of cholera which occurred at Little Rock in the season of 1873 was in the person of Mrs. Mary L. L., nineteen years of age, who arrived at the city on the 29th of June, from some point upon the Cairo, Little Rock and Fulton Railroad, in the northern division. Mrs. L., upon arriving, went to her home in a tenement-house in the southern portion of the city. The next day she was taken ill, and when first seen by Dr. Thompson, who reports the case, was in the collapse stage of cholera, and died after an illness of twelve hours. The excreta were carefully disinfected. Every precaution was adopted to isolate the case, and no spread of the disease occurred.

July 2, George Steel, a negro deck-hand on a steamer from Memphis, Tenn., was admitted late at night to the county poor-house. This institution is composed of a number of rough pavilion huts, each about 50 feet long by 20 feet wide. These buildings were in miserable condition. The ground under and around the huts was covered with *débris* of all kinds, concealed by rank vegetation. Upon being admitted Steel was placed in a hut with others of his color, but the physician of the institution, Dr. J. R. Dale, was not notified until the next day. The excreta of the case were thrown out into the yard, and when Dr. Dale arrived, at daylight on the 3d, the patient was collapsed. Immediate and energetic efforts were made to disinfect all that had come from the case. The ground over which the dejections had been thrown was treated with a strong solution of sulphate of iron, and the *débris* carefully removed. All soiled clothing was removed from about the patient, and every precaution was adopted, but by the 8th of July eight fatal cases of the disease had occurred, and some twenty others of the inmates had shown decided symptoms of the infection. In some of these cases the disease advanced to extremity, but the patients re-acted; in others the attack was confined to the prodromata. It is greatly to the credit of Dr. Dale to record that infection did not extend beyond the walls of the poor-house, as but for his very energetic action, the focus having been established, a most malignant epidemic would have occurred.

July 6, an Irish railroad-laborer named Kelly came into Little Rock from the line of the Cairo and Fulton Railroad. He went to a hotel of his order, in the eastern portion of the city, where he was taken with cholera and died after an illness of twelve hours. This case was attended by Dr. J. H. Lenow, who isolated it by every means in his power. The excreta were disinfected and thrown into the privy-vault, which was treated with decided quantities of sulphate of iron and lime.

On the night of July 5, a case of cholera occurred at the State penitentiary, which is on the western borders of the city, some half-mile from the poor-house. The case terminated fatally within ten hours. The subject was a convict named Johnson, whose term of service had nearly expired, and who from his uniform good conduct had earned admission to the class of individuals known as "trusties." To these men unusual liberties are granted; they can leave the prison during the day without guard, and may employ their day to their own profit. On the morning of July 5, Johnson left the penitentiary at an early hour and went into the city; his own account of the day was that he first worked in unloading a steamboat from Memphis, Tenn.; that job being completed, he went to the depot of the Memphis and Little Rock Railroad and aided to unload freight-cars also from Memphis; that among other material that he handled was a lot of railway-iron. He was absent all day, but returned as usual to the penitentiary before the hour of closing.

The building occupied as the Arkansas penitentiary is old, damp, and badly ventilated. The cells are arranged in tiers, honey-combing a mass of masonry; the whole inclosed under one roof, a house within a house. Each cell is furnished with a wooden bucket without cover which answers the purpose of a night-chair, and this bucket is placed within the cell and against the grated door, and there it remains from the hour of closing until reveille the next morning, by which time the air of the cells and the corridor is fœtid with the excretions of several hundred prisoners.

Johnson, however, was not lodged in an ordinary cell, but, with two other "trusties," occupied a strong room, having four large windows opening into the prison-yard, and so situated that the windows being open the draught of air would pass from this large room into the corridor around the tiers of cells. Shortly after he was locked up for the night Johnson was taken with violent diarrhœa; the inevitable bucket was repeatedly used, and by midnight, when the attention of the guard was called to him, he was "purging, vomiting, and cramping violently." He was removed from the cell to the hospital, became fully collapsed, and died the next day.

July 6, a convict, named Roberts, whose cell was upon the first tier, and directly opposite that occupied by Johnson, was taken with cholera and died within ten hours. Three other fatal cases of cholera and several that recovered are reported to have occurred in the penitentiary, and the majority of the inmates were affected with diarrhœa. One of the fatal cases occurred in the person of a nurse in the hospital who had been in attendance upon prior cases. Owing to the death of Dr. J. H. Carroll, who was the physician to the penitentiary, and also the fact that a change had occurred in the wardenship, more accurate data cannot be obtained. From an old convict, a man of some intelligence, who during the "cholera-days" was the hospital-steward, we learn that disinfectants were freely used—carbolic acid and sulphate of iron in the sinks, lime in each cell, and chloride of lime in the corridor. The soiled clothing was treated with superheated steam. The dietary of the prison was

improved, and what threatened to become a most serious epidemic was arrested and stamped out.

This history is deemed of value as demonstrating that four times an alarming importation of cholera occurred in the city of Little Rock:

I. In a dirty tenement-house inhabited by railroad-laborers.

II. At the county poor-house, where, if an especial effort had been made to offer an asylum to the contagion of cholera, human ingenuity could scarcely have succeeded better.

III. At a hotel frequented by the lower classes of society, those among whom cholera finds its readiest victims.

IV. At the State penitentiary, where, although its inmates are supposed to be secluded from society, it is shown that the disease was introduced in the person of a convict who had worked upon a cholera-infected steamboat from a cholera-infected city.

In either instance the demonstration was sufficiently positive to have originated an epidemic; yet at each point the health of the city was guarded and impending destruction averted by the energetic and efficient medical men in whose care the initial cases occurred.

During the investigation of the cholera demonstration at Little Rock, we were especially indebted to Drs. A. L. Breysacher and P. O. Hooper for their valuable aid, without which our personal efforts would have been unavailing.

On the 22d of July cholera appeared at a negro settlement upon the banks of the Arkansas river, about sixteen miles below the city of Little Rock. This settlement was upon the Perkins plantation, was known as "The Quarters," and was occupied by about one hundred negroes. The inhabitants were a low class of negroes, filthy in their persons and cabins, and extremely poor.

The first case occurred in the person of a female, twenty years of age, who had the day prior to her attack eaten largely of unripe peaches. This case was at first considered by Dr. Reynolds to be one of cholera morbus; but the patient died, after an illness of twelve hours, fully collapsed.

The next day (July 23) three other cases of the same disease occurred, all of whom died within ten hours.

In the next few days the disease spread rapidly. Thirty-eight cases occurred, twenty-three of whom died. The last death occurred August 3, the subject having been attacked July 31. The last individual attacked by the disease was on August 1. This case was convalescent on the 6th.

It has been contended that "the residents at 'The Quarters' had been confined closely to their crops for a number of weeks previous to the outbreak of the disease, and it could not be ascertained that any newcomer had appeared on the place for at least several weeks previous to this outbreak."

It has, however, been ascertained that prior to the outbreak (it being impossible to establish the exact time) a trading-boat had stopped at "The Quarters" and had remained there for one week, and there is nothing to show that other boats had not made the same landing.

HELENA.

A group of cholera-cases having been reported at Helena, Ark., we communicated with Dr. D. A. Linthicum, from whom we have received the following information:

"But one family was infected with cholera in 1873. This family, consisting of seven persons, lived in a filthy, dirty cabin, upon the dividing ridge between East and West Helena. They were miserably poor. Their

diet consisted chiefly of fish. The water used was contaminated with organic matter. No member of the family had been away from home for months. They did not come in contact with river-steamers; they did not wash for any person, even themselves.

"The symptoms were marked. The attack was severe. In the family of seven individuals, six died in the course of three days; the first case terminating July 22, the last case July 25. All were whites; four were females, three males. Four cases occurred in the persons of children aged respectively fifteen years, twelve years, three years, and eighteen months. The recovery was a girl fifteen years old, whose convalescence was slow and tedious on account of her chlorotic condition.

"The excreta of these cases were disinfected and buried, and their clothing burned. The last three cases were removed to a more comfortable house, and the infected cabin was burned."

These cases were regarded by Dr. Linthicum as being sporadic in character, produced by the filthy location and habits of the individuals, the miserable food which they ate, and the impure water they drank. It is considered by him that they had no connection with the cholera epidemic of 1873.

CHAPTER VIII.

TENNESSEE GROUP.

TENNESSEE CONTRIBUTORS.

Dr. J. H. Erskine, Shelby County.
Dr. A. Erskine, Shelby County.
Dr. F. L. Sim, Shelby County.
Dr. A. Szerénji, Shelby County.
Dr. J. E. Black, Shelby County.
Dr. S. J. Quimby, Shelby County.
Dr. J. S. White, Shelby County.
Dr. C. C. Churchill, Shelby County.
Dr. G. B. Thurston, Shelby County.
Dr. R. W. Mitchell, Shelby County.
Dr. W. R. Hodges, Shelby County.
Dr. W. R. Lowry, Shelby County.
Dr. W. A. Edmonds, Shelby Co.
Dr. S. P. Green, Shelby County.
Dr. W. J. Armstrong, Shelby Co.
Dr. R. B. Maury, Shelby County.
Dr. D. D. Saunders, Shelby Co.
Dr. R. H. Taylor, Shelby County.
Dr. T. F. Peyton, Shelby County.
Dr. J. S. Nowlin, Marshall County.
Dr. E. T. Lewis, Houston County.
Dr. L. D. Johnston, Montgomery Co.
Dr. A. Eldridge, Montgomery Co.
Dr. J. F. Outlaw, Montgomery Co.
Dr. S. W. Godwin, Obion County.
Dr. W. R. Hebbett, Obion County.
Dr. W. J. Edwards, Obion County.
Dr. D. M. Pearse, Obion County.
Dr. J. D. Plunket, president board of health, Nashville.
Dr. Morton, health-officer, Nashville.
Dr. G. P. Henry, physician to penitentiary, Nashille.
Dr. T. A. Atcherson, Nashville.
Dr. T. G. Brocking, Nashville.
Dr. L. D. Hogle, Nashville.
Dr. W. R. Revels, Nashville.
Dr. J. T. Jonas, Nashville.
Dr. J. P. Dake, Nashville.
Dr. J. H. Callender, Nashville.
Dr. T. L. Powell, Nashville.
Dr. G. Schiff, Nashville.
Dr. W. C. Cook, Nashville.
Dr. T. R. Kimbrough, Nashville.
Dr. R. D. Winsett, Nashville.
Dr. S. M. Anderson, Wilson County.
Dr. J. L. Fifte, Wilson County.
Dr. G. L. Robinson, Wilson County.
Dr. J. Bryant, Wilson County.
Dr. Jas. B. Murfree, Rutherford Co.
Dr. J. Patterson, Rutherford Co.
Dr. H. H. Clayton, Rutherford Co.
Drs. Ransom and Byrn, Rutherford County.
Dr. J. E. Wendell, Rutherford Co.
Dr. R. S. Wendell, Rutherford Co.
Dr. L. W. Knight, Rutherford Co.
Dr. J. J. Rucker, Rutherford Co.
Dr. G. D. Cronchrist, Rutherford Co.
Dr. J. W. Davis, Rutherford Co.
Dr. R. J. Turner, Rutherford Co.
Dr. R. B. Haines, Rutherford Co.
Dr. T. J. Elam, Rutherford County.
Dr. Thos. Lipscomb, Bedford Co.
Dr. J. Christopher, Bedford Co.
Dr. R. F. Evans, Bedford County.
Dr. G. W. Moody, Bedford County.
Dr. J. H. McGrew, Bedford County.
Dr. J. H. Van Deman, health-officer, Chattanooga.
Dr. J. Norris, Hamilton County.
Dr. R. D. Hamilton, Hamilton Co.
Dr. B. D. Reves, Hamilton County.
Dr. D. G. Curtis, Hamilton County.
Dr. F. Painter, Hamilton County.
Dr. O. L. Gielmann, Hamilton Co.
Dr. E. M. Wight, Hamilton Co.
Dr. B. F. Gardner, Hamilton Co.
Drs. Goodwin and Barter, Hamilton County.
Dr. T. H. Roddy, James County.
Dr. F. K. Bailey, Knox County.
Dr. M. M. Alexander, Knox County.
Dr. C. Deaderick, Knox County.
Dr. D. S. Boynton, Knox County.
Dr. J. W. Stewart, Knox County.
Dr. S. M. Burnett, Knox County.
Dr. C. D. Riggs, Hamblen County.
Dr. E. L. Deaderick, Washington Co.
Dr. W. R. Sevier, Washington Co.
Dr. A. J. Williams, Anderson Co.

Dr. J. B. W. Nolen, Nashville.
Dr. G. W. Currey, Nashville.
Dr. Jas. F. Fryar, Davidson Co.
Dr. C. E. Ristine, Davidson Co.
Dr. H. A. Schell, Sumner County.
Dr. J. R. Kirkpatrick, Davidson Co.
Dr. H. M. Hollingsworth, Ander
County.
Dr. J. R. Walker, Hawkins Cou
Dr. R. P. Mitchell, Hawkins Co
Dr. C. M. Emmert, Carter Coun
Dr. J. F. Broyles, Greene Coun

Assistant-Surgeon Wm. D. Wolverton, United States Army.
Assistant-Surgeon D. G. Caldwell, United States Army.
Assistant-Surgeon Charles Styer, United States Army.

DATES OF INITIAL CASES.

Shelby County	April 15.	Greene County	June 2
Davidson County	May 11.	Houston County	June 2
Sumner County	May 29.	Knox County	June
Bedford County	May 31.	Obion County	June
Rutherford County	June 1.	Anderson County	July
Wilson County	June 8.	Hamblen County	July
Montgomery County	June 8.	Washington County	July
Marshall County	June 18.	Union County	July
Hamilton County	June 20.	Carter County	July
James County	June 21.	Hawkins County	Aug

MAP OF A PORTION OF THE CITY OF MEMPHIS

Showing location of Cholera cases in Epidemic of 1873.

TENNESSEE.

SHELBY COUNTY.

Epidemic of 1873 *at Memphis, reported by Dr. J. H. Erskine, late president board of health.*

In submitting the following report of cholera as it appeared in Memphis in 1873, I must premise that after a close and careful investigation of all the facts I have been able to collect, I find them so general, not to say meager, that the best account I will be able to furnish will be cursory and brief.

It was brought by boat from the Lower Mississippi. The researches of Dr. J. C. Peters, of New York, who came South under the auspices of the New York board of health to investigate its origin, supply indubitable evidence of its prevalence in New Orleans in the month of February, and of its successive appearance at points higher up the river in March and April. The first case which occurred here was as early as April 15. It was attended by Dr. Samuel J. Morrison, in company with Dr. Jno. R. Frazer, one of the oldest and most highly esteemed practitioners. Both pronounced it cholera. It was in the person of an Irishman by the name of Kelly, who had but a few days before come up the river, on what boat is not known, and was lodging at 136 Front street, between Market and Exchange, in an Irish boarding-house, the surroundings of which were filthy. He died, after an illness of sixteen hours, in collapse.

The next case was an Italian by the name of Cuneo, who kept an eating-house immediately on the river at the point where the Memphis and Ohio and the Memphis and Paducah Railroads discharge their freight He died on the 30th of April in collapse, under the care of Dr. D. D. Sanders. It must have been from this case that the outbreak on the Paducah road so soon appeared.

The third case was a conductor on this road, Patrick Smith, who died twenty miles out from the city, but who lived in the square on which Kelly died, and by the nature of his vocation must have been exposed in the neighborhood of Cuneo's stand. He was attacked on the 1st of May, at his camp, section 26 of the road, and died on the 3d.

Almost at the same time cases occurred at another camp, seven miles nearer the city than this, and in both spread very rapidly, producing a panic, and scattering the laborers, some of whom returned to the city, re-introducing the disease. I think it more methodical, and will be more satisfactory, to detail thus early in my report the history of this local outbreak. I have obtained most reliable information in regard to it from Dr. Jno. E. Black, of Kersville, and from the chief engineer, Mr. J. L. Meigs, who has kindly furnished extracts from letters written at the time to the president, Mr. E. Norton. In a letter written on the 7th of May, Mr. Meigs says:

A serious illness, resembling cholera, made its appearance on May 1, in a convict camp, section 19, Paducah and Memphis Railroad, and Mr. P. Smith's camp, section 26. The camps are seven miles apart. There were nine deaths on Friday and Saturday, May 2 and 3, the illness not lasting longer than twenty-four hours in any case. The contractor, P. Smith, died May 3, and a panic ensued among the men in sections 21 and 26. There have been five deaths since Saturday, and the disease has been less violent, though more protracted. Forty men in the convict camp, and two in Smith's camp, sick on the 6th. There have been during the last month excessive rains in that region, and the dead bodies of myriads of caterpillars have been washed into the streams and running branches, together with much vegetable matter, and the physi

cians attribute the illness to these streams. Up to the 10th, from the 7th, there were ten deaths, forty cases in all; none on section 26, where Smith died. At this date, the 13th, the disease is abating in violence in section 21, having disappeared from section 26.

I suppose the partial cause of this was the scattering of the men.

From a letter to W. F. Norton, May 19, the disease had disappeared, but from its outbreak had produced nineteen deaths. Mr. Meigs states that the company began to lay their track from Memphis northward May 3, and by the 20th had put down eight and one-sixth miles. The men working at sections 19 and 21 were convicts from the Tennessee penitentiary, while those at section 26 were hired laborers, who were generally sent from Memphis to section 26 on the Memphis and Ohio Railroad, as far as Shelby Depot, twenty miles out, where they walked twelve or thirteen miles to the Memphis and Paducah Railroad, and after the track-laying began the company passed the hands over the road to its terminus. Inasmuch as the disease appeared simultaneously at sections 19 and 26, seven miles apart, others must have been attacked here besides Smith, who conveyed it to section 26. No doubt the impure water rendered the disease more fatally malignant.

When the outbreak occurred at Lucy Depot, on the same road, in July and August, cholera had long existed as an epidemic in Memphis, and might easily have been communicated from the city, there being constant travel all along the line. Simultaneously with its appearance at our wharf, and its ravages on this railroad, it began at first slowly, and afterward more rapidly, to dot about in different parts of the city. A case came under the observation of my brother, Dr. Alexander Erskine, as early as the 4th of May, at least three-quarters of a mile from the river. This was so isolated, and had so little apparent connection with any other case, it was that far anomalous, and might at a glance have induced the belief of its spontaneous origin. Indeed, it had appeared on our coast so insidiously and noiselessly, and had entered Memphis so unheralded, the profession was taken by complete surprise, and in the daily press much acrimonious discussion followed among our editors as to its origin. This case was in a negress, named Augusta White, who lived near the corner of Orleans street and Marshall avenue, not far from the eastern limits of the city. She was in her usual health in the morning, had had no indisposition, was attacked about 11 a. m. with cholera, and died at 5 p. m. in collapse. Her residence was in a locality highly favorable to the development of the disease. She lived in a small neat cottage upon the edge of a large pond of stagnant water, filled with the filth of the lots whose rear sloped from the adjacent more elevated streets. It was under the declivity, and near it was the offensive water, whose surface was covered with a green vegetable mold of rank and noxious growth. The atmosphere was full of miasma, and supplied the *nidus* for the development of any malignant disease whose germs might be wafted to it. No contact, either direct or indirect, could be traced in this instance.

On the 8th of May Dr. G. B. Thornton admitted his first case into the wards of the City Hospital, after which it began to spread, and by the middle of the month became so general as to scatter the community, and soon thereafter became epidemic.

In its incipiency it was conveyed by direct or indirect personal contact; within a short time it was borne upon the winds to all points of the city.

With its first appearance there was exhibited an unusual epidemic condition of the atmosphere. Everywhere there existed a tendency to disordered bowels. The profession was busy from day to day prescrib-

ing for naught but diarrhœa, a diarrhœa which was all choleraic, sudden, painless, profuse, unexpected, passing out the contents of the intestines, and then colorless water, which soon became true rice-water stools. This was easily controlled if taken at once in hand, otherwise it soon became unmanageable; within a few hours nausea and vomiting set in, with prostration, extreme coldness, blueness, cramps, and collapse. Death soon followed, or reaction, feeble, partial, and slow, or febrile, with protracted, uncertain recovery. The epidemic did not, like yellow fever, confine itself strictly to localities; and while it is true that certain places suffered more severely than others, yet the poison was blown to every point of the compass. The negroes were the greatest sufferers, and those residing in the extreme southern limit were more generally and fatally attacked. The square and adjacent street in which cholera prevailed most fatally was one mile from its point of departure. This area is bounded by South or Calhoun street on the north, Clay on the south, De Soto on the east, and Hernando on the west; in this space there were about fifty families living, thickly crowded in small, ill-ventilated cabins; filthy, careless in habit and diet, purchasing cheap vegetables, stale and unsound, and using water from an alkaline well which, though apparently pure, disordered the bowels and developed diarrhœa. Dr. S. J. Quimby, who attended the most of these cases, states that this well was higher than the adjacent ground, and their privies could not have drained into it. The mortality in this section was fearful, sweeping away eighty persons, and extending up Calhoun street to the river, leaving in many families no surviving member. It is difficult to say why this section should have suffered more than others which were equally unclean and neglected.

The entire city was most favorable for its spread. Its sanitary condition was shameful and a disgrace. There was virtually no board of health and no health-officer. The existing board was absolutely powerless, and without a dollar to spend. It was embarrassed and restrained by an ordinance which limited it to advisory powers. It was optional with the city authorities to accept or reject their suggestions, and they were so supine and ignorant of sanitary laws that nothing was done until the epidemic was beyond control. There was such a disinclination to allow the medical profession to disburse public money, that it was only after the fearful lessons of cholera and yellow fever that the authorities yielded to the public demand and organized a board of health, with power to cleanse the city and destroy the sources of general disease.

When cholera was announced the streets were unclean, the alleys reeking with filth, the back yards, even in the case of our prominent citizens, who blushed to be made the subjects of public exposure, were full of slops and garbage. Vessels filled with the refuse of kitchens and laundries were emptied into the streets, to decay or be devoured by the swine, the only scavenger-carts of the city. Privies had remained unemptied for years, and were in many places running over with the foul accumulations. In many parts of the city ponds of water were undrained and stagnant, evaporating the filth the streets and lots which poured into them. The place was rife with the elements of a great plague, and only needed the specific germ to diffuse it widely and fatally amid a people who had forgotten that such things existed as the laws of health and disease. In both the epidemics of 1873 Happy Hollow was the starting-point, beyond which they soon attacked the entire city. Our atmosphere was at that time peculiar. It was unseasonably cool, excessively damp, the rains being very heavy and constant. With the renewed heat after each succeeding rain the malignancy of the poison seemed to increase. By reference to the meteorological report herewith appended

the amount of rain-fall from April to August inclusive reached the mean of 18 inches; the range of temperature, 76° 8′.

Cholera prevailed in Memphis from the middle of May to the middle of August, and had scarcely disappeared when yellow fever followed. Like an invading army, while its vanguard was busy in Nashville and the interior towns of Middle Tennessee and North Alabama, its rear was still at work, and its effects still visible upon the stragglers who were doomed to fall victims along the line of travel upon which it had made its desolating march. As to its prevalence here, if we leave out those cases which were called choleraic diarrhœa, which yielded readily to treatment, and never passed beyond that point into actual cholera, the number of cases did not exceed a thousand, and I think fell beneath it. This must be regarded as within the limits of entire accuracy, because from the mortuary statistics, as gleaned from the books of the different undertakers, the only reliable source of information at that time, there died only two hundred and seventy-six persons with that disease. If we regard the choleraic diarrhœa as cholera—all the population had this—the percentage of deaths would become insignificant. I do not consider it pertinent to this report to detail the outline of the treatment pursued in the epidemic, inasmuch as it differed in no material point from what has heretofore been adopted. Without attempting to follow the march of the epidemic as it moved along the lines of all the roads leading out of Memphis, there was one locality it visited which I desire to detail on account of its fearful malignancy, and because of its proximity to the outbreak at the beginning of the season. It is the Depot Lucy, on the Memphis and Paducah Railroad, about fifteen or twenty miles from the city, and upon a plantation four miles out from the depot. It is easy to account for its appearance at the depot, for it began there in July and August, when it was everywhere else, and the communication with Memphis was unobstructed. There was a colored church, New Hope, at which the negroes were constant worshipers, while a gang of convicts worked near them on the railroad. We have no positive evidence, but the presumption is very strong that there was among the negroes one Jack, a constant visitor, who went to and fro to the plantation of a Mrs. Hill, at whose house lived an old man named Webb, blind and infirm, on whom Jack waited. Jack and Webb were attacked and died July 28, and the discharges of Webb were emptied carelessly out in the yard of the farm, and the vessels were washed near the well, from which all the residents drank. According to Dr. Thomas Peyton, who is authority for the following facts, and has most clearly reported them, "the well of water used by two or three families was curbed with poplar plank about twenty years ago. This had rotted near the surface, the ground being low all around it. On the 1st of August a rain fell to the depth of from four to six inches, burst the curb, overflowed the well, and washed into it the entire surface drainage of at least 15,000 feet of ground No attention was paid to this, and the water was used as before. It had become so offensive, that its use was at once forbidden, but too late to save the family, nine of whom died of cholera. In addition, two boys from a free school who used water from it, both died, as did also two negroes from an adjoining farm who drank from this well." Dr. Peyton says he traced all the cases to impure water. His description of the farm-yard of Mrs. H. presents a fearful picture of a disregard of every sanitary law. "I found yard sweepings, slops, rubbish of all kinds festering around the houses, old, rotten cabins crumbling down unoccupied, large banks of ashes rotting, the gatherings of years, moldy and green, beneath heavy shades, and a general neglect of everything around the premises. I had all this thoroughly

OF
mic of 1873
ELLAN.
rgeon U.S.A.
STER

cleaned, lime scattered everywhere, and the work was over. I passed through the epidemics of 1849, 1851, 1853, 1867, and up to this date, and must pronounce this the most violent I ever witnessed." The attack did not last more than from six to twelve hours, and from July 28 to August 5, and in that time nine out of twenty died.

I have thus attempted to give the origin, progress, duration, extent, and mortality of the invasion. By reference to the map, it will be seen that it developed in localities distant and separate, dependent upon surroundings more or less favorable to its spread. In some of these it was exceedingly malignant, in most of them mild and more controllable. It left the community enfeebled and alarmed, the more ready victims for yellow fever, which so soon followed. Since the disappearance of these, the health of Memphis was never better.

DAVIDSON COUNTY.

The city of Nashville is located upon the north bank of the Cumberland river, two hundred miles from its mouth. The city is built upon a limestone ledge which rises to an altitude of 175 feet above the river. This ridge extends in a southerly direction, attaining its greatest altitude at about eight hundred yards from the river-banks, thence descending for a distance of about six hundred yards to regain the level of the river. Upon each side of this ridge flow two small streams, Lick Branch upon the north, and Wilson's Spring Branch upon the south. The distance from one creek to the other upon a base-line is somewhat over one mile. In the space thus described is located the business portion of the city, and many of the finer class of private residences. From Cherry street, the third block from the Cumberland river, the descent to the bed of each stream is precipitous. The same is true of the streets south and west of Vine street, upon which street is located the State capitol building.

The banks of Lick Branch, (as shown upon the accompanying map,) for a distance of at least one mile back from the river, with a varying width of from a quarter to a half mile, are subjected to annual spring inundations. The principal streets crossing this low ground are upon causeways, bridged or arched to admit of the passage of the stream; but these causeways act as dams whenever the water rises above the level of the creek banks. Along the line of Lick Branch are several large springs from which a large portion of the lower class of the inhabitants obtain their water for all domestic purposes. To these springs special attention will hereafter be asked.

The banks of Wilson's Spring Branch are also subjected to annual overflows, which extend backward about half a mile with a width of about one-fourth of a mile. Upon this branch are found Hackberry and Wilson's springs, both favorite watering-places for the lower classes.

North and west of Lick Branch is a hill of considerable elevation, known as McGavock's, upon which has been built North Nashville. This portion of the city is occupied by dwellings, retail stores, cotton and other factories, and the United States barracks.

South and east of Wilson's Spring Branch is a considerable hill, known as College Hill, upon which has been built South Nashville. This portion of the city is occupied by private residences, the Nashville University, and at its height by the reservoir, from which flows the official water-supply of the city.

South and west of the valley, at the foot of Capitol Hill, through which flows a small stream emptying into Lick Branch, is high ground, crowned by Meridian, Saint Cloud, and Kirkpatrick Hills, at the base of

which lie the localities known as New Bethel and Rocktown, to w reference will hereafter be made.

Crossing the Cumberland river near Locust street, and following t line of Lick Branch, is the line of the Louisville, Nashville and Gre Southern Railroad. This road passes upon an extensive trestle-wor crossing the various streets in this portion of the city. From the nor west this line of trestle-work is joined by the Saint Louis and Sou eastern Railroad. At the foot of Capitol Hill, and on the west, is th line of the Saint Louis, Nashville and Chattanooga Railroad, which roa is crossed by the line of the Tennessee Pacific Railway. Nashville a railroad-center. Through cars for Louisville, Saint Louis, and Hic man, upon the north and west, New Orleans, Atlanta, Chattanooga upo the south and east, constantly pass through the city. If trains of a descriptions are considered, it will be seen that this city is in almo hourly communication with the outside world.

Nashville, a beautiful and attractive city, is possessed of filthy a repulsive suburbs. The small streets and lanes that surround the bas of Capitol Hill are occupied exclusively by the lower classes. The houses are dirty and filthy in the extreme, the streets and gutters are filled with filth. Gutters and sewers upon either side empty into the branches, which afford the only efficient drainage of the city.

The banks of Lick Branch, from Watkins street to College street, are unoccupied, save in the street upon the lowest bench of each hill, whic Wilson's Spring Branch flows through a dense population.

Upon the banks of Lick Branch, and in the western suburb of the city, is located the Tennessee State penitentiary. All drains from thi institution empty into Lick Branch. From privies, urinals, cess-pools kitchens, and wash-houses, drains empty into the branch.

Beyond the walls of the penitentiary, and upon the banks of Lic Branch, are several slaughter-houses that discharge their offal into th stream.

The facts herein stated have existed for years, and it is scarcely to b wondered that Nashville, at each visitation of cholera, has been a hot bed for the epidemic.

The water-supply of the city is obtained from the Cumberland rive at a point about three-fourths of a mile above the Edgefield bridge The river-water is pumped into a reservoir, and from thence is supplie to the city. At the time these water-works were erected they wer sufficiently above the town to secure pure water, but the growth of th city has been so great upon the east that, in addition to objections to b hereafter noted, the drainage from a considerable area of dwellings after all rain-falls, is into the river immediately above the suction-pipe

Water for domestic purposes is also obtained from the public well and springs that have already been noted. Of the latter there is i constant use by a large number of inhabitants, *Judge's spring*, on th banks of Lick Branch, near Vine and Washington streets; the *Sulphu well*, on the same stream, between Hamilton and Washington streets and upon the line of Wilson's Branch the *Bilbo spring*, on Stevens street between Fairmount and Deluge; from this spring the inhabitants o Rocktown obtain their water; *Buck spring*, on Ash street, near Ewin avenue; the *Wilson spring*, on Vine street, near McEwen; the *Hackbur spring*, on Front street, near Molloy.

Standing at either of these springs and looking up at the great lime stone ledge, suggests unpleasant thoughts to a reflective mind trouble with a thirsty body.

As additional evidence, we extract from a former report made to th Nashville board of health the following:

REPORT OF COMMITTEE ON HYGIENE OF BOARD OF HEALTH.

NASHVILLE, TENN., *August* 28, 1866.

"THE WATER WE DRINK."

* * * * * * *

"The mouth of Brown's Creek is about three-fourths of a mile above, nd on the same side with the engines supplying the reservoir. The pography of the southern slopes from the city shows that a large basin f country emptied its drainage into this stream. The northern bound- ry of this basin is a ridge starting from the river at the city reservoir, nning south of west through the university ground, north of the city emetery, to Fort Negley, thence across a country in a line with the uter defenses of the city. All of that portion of the city south of this ne is naturally drained into Brown's Creek. It is unnecessary to dwell n detail upon the immense amount of garbage and filth of every descrip- ion which accumulates about tenements, and with every rain finds its ay into this creek. The meadows and plains as far back as Trimble's Spring, a distance of about a mile and a half, are strewn with the car- asses of hundreds of animals of every description, besides being the great depot for the rubbish and garbage of the south end of the city. It would also appear from the great number of barrels and other evi- dences, that the cleanings of all the privy-vaults of the city were de- posited, not only along the banks, but actually in the channel of this stream. There is also a large tanyard near the Nolensville pike, im- mediately upon its banks, the offal of which assists in poisoning its waters. Your committee would especially invite your attention to the fact that four cemeteries are drained into this creek, viz, the city ceme- tery, the Catholic cemetery, the Federal burying-ground, and Mount Olivet. It requires but a glance at the topography of the country to understand that all the escapage which drains from these resting-places of the dead naturally finds its way into this stream, and thence into the city reservoir. It is a matter of great astonishment to your committee that the authorities ever permitted cemeteries to be located anywhere up the river, and especially where it is so palpable that their drainage empties above the point from which the city is supplied with water. We would respectfully suggest that no burying-ground should be located south of the Harden pike. And we would recommend, in view of the above facts, that the attention of the city authorities be immediately invited to the propriety of changing the point of supply by removing the engines, &c., above the mouth of Brown's Creek, as the only remedy for a growing evil, which cannot, in the nature of the case, be abated while the city continues to extend in a southern direction. Indeed, a radical reform is clearly indicated in reference to this subject. The mere recital of the above facts is offensive to every refined sentiment of human nature, and will doubtless unite our entire population in an earnest demand to have the evil abated at whatever cost.

* * * * * * *

"In reference to the public springs your committee found them gener- ally in a very bad condition. This is especially true of Wilson's spring, and the branch leading from it; also the spring at or near the barracks

of the Sixteenth United States Regulars, and the one on Broad-str pike, beyond McNairy street. The poor mainly use from those sprin Chemical analysis, as well as medical observation, sustains the conc sion that these waters are less pure (as will be seen below) and m fertile in producing disease than the river-water. Every considerati demands that the authorities should take immediate action in referen to their improvement. Instead of being nuisances to the neighborho in which they are located, they might, with a small outlay of money, made ornaments to the city, pleasant and refreshing retreats; and th waters, instead of being filthy and fertile in producing disease, would pure and wholesome. A little money well invested here would be l the sprig the prophet threw into the fountain of Marah, which chang its bitter and poisonous waters into a sweet and refreshing stream.

"At our request, Dr. D. G. Sherman and Mr. J. C. Wharton have f nished us with a qualitative analysis of Cumberland river water, Wilson's spring, and Judge's spring. These gentlemen, without a concert of action, have arrived substantially at the same conclusi The former, after giving a detail of his various experiments, remar that 'the foregoing examination proves the greater purity of our riv water (hydrant not muddy) by the comparative absence of chlorid sulphates, carbonates, and organic matter.' Wilson's spring is sho to be most abundant in these impurities, especially in the organic i purity. A comparative quantitative as well as qualitative analysis, fu nished by the latter, is as follows:

"*Cumberland River water, taken from the upper wharf, (analysis expres in wine-gallons.)*

"One gallon contains:

	Grain
"Organic suspended matter, (sediment and floating)	3.
"Organic and mineral, (in solution and suspension)	9.
Total	13.

"The organic matter appears to be mostly vegetable. The miner matters are as follows, and their relative proportion as indicated b their order:

"Silicate of alumina.

"Protoxide of iron.

"Chlorides of the alkaline earths, and alkalies.

"Sulphates of the alkaline earths, and alkalies.

"Wilson's spring water contains, in one wine-gallon, organic and mi eral matters 30.80 grains.

"It will thus appear from the foregoing that the river-water is by fa purer than the spring-water, and that Wilson's spring contained th maximum of both organic and inorganic impurities.

"It must be observed that these analyses were made after a very unusu ally protracted dry spell, when all the impurities would exist in a mini mum quantity. It is generally conceded that the amount of organi matter determines its hygienic importance, and that an excess of thes decaying elements determines to diarrhœa and dysentery.

"The popular theory at this time, and that which has the ablest sup porters, is that Asiatic cholera is developed more frequently from th use of waters loaded with decaying organic matters than from an other cause.

"It is a fact admitted by the medical faculty of Nashville that, in the sitations of cholera, those who used the spring-water, and especially Wilson's spring, suffered very much more than those who used river-ater.

* * * * * * *

"N. L. MADDIN, M. D.
"G. A. CHEATHAM, M. D.
"J. R. BUIST, M. D."

We have been informed that it was proposed to obtain the water-supply of the city from the Cumberland at a point some eight miles above he site of the present water-works and above the junction of Stone iver. This having been accomplished, Nashville will be secured in a ll supply of pure freestone water.

The privies of Nashville are either upon the surface or consist of pits ng to the surface rock, into which a shaft is either drilled or blasted. he last applies to all water-closets, cess-pools, and house-drains. From he geological formation upon which the city is built, these pits are lmost always dry and clean. We have been told by a gentleman of he city that twenty-five years ago, when he erected his present resilence, he had a privy-vault blown out of the rock in the rear of his ouse, and that from that time to this, although it has been in constant se, he has never been obliged to clean it out. In the rear of the company quarters of the United States barracks, situated upon the highest point of McGavock's Hill, is a large privy, which is daily used by a large number of men; the contents of this pit are constantly disinfected, rendered fluid by water, and then each day pumped up into a covered drain that leads into a covered cess-pool. Once in the cess-pool, which was formed by blasting into the rock, the excrement disappears. After each rain-fall the contents of all privies in the city are fluid, and are rapidly drained off, where, is a question of undoubted interest to the drinkers of water from the wells and public springs.

As shown upon the accompanying map, and as it has already been stated, the sewers and surface-drainage of the city empty into the two north and south streams; and, in addition, it will be remembered that Lick Branch receives the offal of slaughter-houses and the entire excrementitious matter of the penitentiary.

Dr. Bowling, in "An account of the cholera as it appeared at Nashville in the year 1873," writes: "Nashville has the best natural drainage of any town on the continent. Every drop of water that falls upon College Hill finds its way either to Brown's Creek on the south, or to Wilson's Spring Branch on the north, both of which go with rapid currents to the river. * * * On each side of this ridge are many springs, whose branches find their way into the larger streams which divide the lowlands on each side of Capitol Hill. These streams drain thoroughly the north side of College Hill and the whole of the south side of Capitol Hill. The north side of Capitol Hill plays watershed to Lick Branch, which also receives the water from the south side of McGavock Hill, while the north side of this hill is a part of the water-shed of McGavock Spring Branch."

This description is most admirable, and were nature unobstructed or unmolested, were the country a wilderness, the natural drainage would be perfect, and nature's provisions all that could be desired. But Capitol Hill teems with human life; McGavock's and College Hills are covered with tenements. From all, the drainage is simply into the valley of each natural drain. The necessities of man have obstructed this

natural drainage, the streams are no longer "rapid currents to the river," and man has not rendered an equivalent for what he has destroyed. All that we have said of Lick Branch is recognized in the report of Dr. Bowling, before referred to. We quote from page 5:

"On each side of the creek, and between the fills, (each serving as a dam to keep back from the river the accumulating filth above,) exists a common deposit of every imaginable abomination, which lies rotting seething, and weltering in the unobstructed summer's sun."

We are informed by competent authority that, prior to the explosion of cholera in 1873, the city of Nashville was in a very objectionable sanitary condition. No board of health, with power to act, had been in existence for several years. The sanitary history of this city shows a most lamentable negligence on the part of her authorities upon the most important matter. Cholera once having been developed, every effort was made to improve the condition of the city, but even then, as will hereafter be shown, much of the work of policing was performed by individuals from the point of original infection, who were thus constantly distributing the infection over the city.

During the month of May, 1873, the Nashville Industrial Exposition was the *furor* in the State of Tennessee. The city was full to overflowing with strangers from all portions of the State. Into this dense mass of humanity, on the 12th day of May, (as will hereafter be shown,) came a gang of convicts, from a cholera-infected camp upon the line of the Memphis and Paducah Railroad. Every one of these convicts, every one of their guards, was suffering from choleraic diarrhœa. True, after their arrival, they were shut up within the walls of the State penitentiary, whose walls should have formed a *cordon de santé* to the doomed city; but we have shown how the drain from the penitentiary—privies, cess-pools, wash-houses, &c.—emptied into Lick Branch, whose waters run through almost the heart of the city, and in close proximity to the springs from which so many of the inhabitants obtain their drinking water.

The water from these springs is cooler and more palatable to many than is the river-water. When strangers are near a sulphur-spring custom decides that it is "quite the thing" to drink of the water; how many of these unsuspecting strangers drank of these deadly waters can never be determined.

The shadow of a suspicion that the National Government might possibly assert a sanitary control over the great cities of the nation called forth an expression of public opposition of which the following is a sample:

"And why should it be necessary to have a national board for the exercise of such control? Is it possible that the large cities are so destitute of sanitary learning and experience that they must be remanded to the guardianship of a board commissioned by the General Government? We are willing for a while yet to do our own thinking in regard to public health and the needs of our own city, ready as this *sanitary ring* may be to do it for us at Government expense."

What is the experience of the city of Nashville that called forth this violent demand to work out her own salvation? Not cholera a time or two, as was stated among other misrepresentations, but whenever cholera has been upon the North American continent, Nashville has been decimated. Her noblest citizens, as well as the most degraded, have been counted victims by the score, simply because "doing their own thinking" has been productive of no sanitary reforms, has resulted in the utter ignoring the wise and prudent suggestions of her own sanitarians, and

the local defects that were present to add to the epidemic of 1833, were present to augment the severity of the same disease in 1873, and still exist at the close of 1874, while those to whom the vital interests of the city are confided debate upon the total abolition of the only sanitary institution within the city-lines, the board of health.

With the dispersion of visitors to the exposition, cholera was carried along the lines of all railroads leading out of the city of Nashville.

A strong and persistent effort has been made to prove that the disease of which so many convicts suffered at the camp in Shelby County was not cholera. The evidence, however, cannot be controverted. We are informed by Dr. W. M. Wright, the superintendent of Tennessee prisons, that during the latter part of April, 1873, he was notified by letter from the deputy warden in charge of a party of convicts, who were employed as laborers upon the line of the Memphis and Paducah Railroad, that a fatal disease had broken out among said convicts. Dr. Wright at once proceeded to said camp, which was some twenty miles from Memphis. The day he arrived at camp there were three or four deaths, one occurring in the person of a convict who had left camp in perfect health the morning of the same day, but who died within five hours of the inception of the disease. The disease was pronounced by the physicians in attendance to be malarial congestion, but the cases that Dr. Wright saw had all the well-marked symptoms of epidemic cholera, and as such he had no hesitancy in pronouncing it.

Dr. Wright ordered this camp to be broken up, and the men to be returned to the penitentiary. The deputy warden and several of the convicts were so ill at the time the party were moved that they were left in camp. The warden recovered, but the men died. Dr. John E. Black, of Kerrville, Tenn., reports that from May 8 he attended the convict-camp regularly every day, having from four to ten cases of illness each day; that on the 13th of May he prescribed for thirty-two sick men, three of whom were recently attacked; the remainder, however, were those cases that had been accumulated from April 30. May 14 the authorities removed the convicts to Nashville. Of the thirty-two cases, but one died. There had died previously eleven cases. Dr. Black writes: "It is safe to assert that there were sixty cases of genuine cholera, with many cases of premonitory diarrhœa among the convicts."

We submit herewith a most interesting letter from Dr. George P. Henry, the surgeon of the penitentiary, which throws much light upon the Nashville epidemic of 1873:

STATE PENITENTIARY,
Nashville, Tenn., December 15, 1874.

SIR: In response to your request, I have prepared the accompanying tabular statement of cases of cholera which occurred in the Tennessee State prison in the year 1873, with a hope it may aid you in your important undertaking.

The prison was erected in the year 1828, and was completed for the reception of prisoners about 1833; it is situated about one mile west of the public square, between Church and Cedar streets, 104 feet above the Cumberland river, (low-water mark,) and 47 feet above high-water mark, and on a level with the square. The headwaters of Lick Branch run parallel with and about 75 feet from the north wall of the prison-inclosure, one of its tributaries flowing within 10 feet of the northwest corner from a marshy flat scope of country. The fact may be mentioned that the cholera first made its appearance in this immediate vicinity in the year 1866. But to the prison and its sewerage. The prison-

inclosure proper embraces five acres, surrounded by a stone wall 30 feet high, the south wall being joined by the main building, in which are embraced the cells, hospital, officers' quarters, &c.; within these walls are the workshops, and in fact everything pertaining to the institution, save the laundry and female department, all of which are situated outside of the southeast corner of the wall. The number of female prisoners is thirty-five or forty. The sewerage for these quarters is unsatisfactory, running on the surface of the east wall and the west side of Carroll street for 100 feet, when it enters an underground sewer, and is by that conducted into Lick Branch, near the northeast corner of the prison-wall.

The first case of cholera outside the penitentiary, that came under my observation in 1873, occurred within 100 feet diagonally across West Carroll street, opposite the entrance of this surface-drain, before entering the sewer before-mentioned; this was the case of Mr. Ensley, which proved fatal in twelve hours.

The grounds within the prison-inclosure have an inclination from south to north of about five degrees. The sewerage conveying offal and excrement from the interior of the prison-inclosure is very well constructed, and empties into the branch above mentioned about 75 feet from the north wall of the prison. The stench from that sewer has been the subject of very great complaint on the part of the citizens in that vicinity, so much so that this summer we have been compelled to adopt other means to get rid of the excrement, offal, &c.

The cells occupied by the prisoners at night have a space of 250 cubic feet, and are ventilated by a grating in the door of the cells, 14 inches square, opening into the main corridor. The prison is so much crowded that in most cases two prisoners occupy one of the cells.

The hospital arrangement consists of the two wards on the second and third floors of the south building, and are wholly inadequate in every particular, and we are frequently compelled to use cells for our sick.

The water used at the prison is furnished by the city water-works, and is such as is used by the citizens generally, the water used for drinking purposes being first conducted into a well 40 feet deep, in order to render it cool and palatable before use. This well and two others were formerly used for drinking-purposes during the summer-months, but in consequence of the opinion that the water was unwholesome, producing diarrhœa and other troubles, their use was discontinued, and the wells closed, which opinion was verified by a decided abatement of the diseases supposed to arise from their use.

On the 11th day of May, 1873, we had in the prison-walls three hundred and fifty prisoners, and of that number only twenty were on the sick-list. Early in May I was advised that some malignant disease had made its appearance among the convicts then at work on the Memphis and Paducah Railroad, West Tennessee, and that the mortality was frightful. The officers in charge, with commendable zeal, hastened to the relief of the unfortunate prisoners, and at once removed them to the city for treatment. On their arrival, seventy-five in number, I found the entire party troubled with diarrhœa, copious watery stools, accompanied in very many cases with nausea and vomiting, fever in many instances, all of this being based on a scorbutic diathesis. Now, what must be done, was the *questio vexata* with me. From a malarial district, in a broken-down condition from disease and fatigue, I would have been glad to have given calomel had I felt that it was advisable, but it was not, and I ordered at once such diet as I thought proper, having dubbed the disease scorbuto-malaria. I ordered vegetables, sour-kraut, &c.,

my remedial agents being tincture of iron and quinine freely given, with chlorate of potash as an adjuvant. On the day after their arrival I was notified that one of my patients was in a dying condition, and, to my surprise, I found him in collapse, with all the symptoms of a genuine case of cholera. I made a post-mortem examination, which developed nothing peculiar, other than the gall-bladder was distended with a thick, tar-like substance. I will state that the deceased was in so much better condition than the others on their arrival the day before, and not having room in the hospital, I did not admit him, and yet the next day he was a corpse. I confess it surprised me no little. The remainder recovered rapidly, and in a few weeks most of them were at work. Sixteen of their comrades, who were with them on the aforesaid road, died, all being attacked and diseased alike; these sixteen were never removed from the road, but died suddenly, while others were sent, as before stated, to the city. Upon interrogating John Wyice and Richard Loney, two of those returned with the seventy-five, both white men, I learned that there were two camps of convicts on said road, about four miles apart, one in charge of a Mr. John Eastman, the other in charge of John Chambly; that the disease broke out suddenly at Eastman's camp, and almost immediately at the others. I learned further that the convict-labor was kept separate from the free labor, except the dumpers of the carts, who were free men. These men lived during work-hours with the convicts, but ate and slept in a house with the guards. I learned further that one of the guards was attacked with a similar disease and died; also that Mr. Chambly was attacked with the same disease, and barely escaped with his life, being unable to return with the convicts, but was left in Shelby County, where he ultimately recovered. From the record of the penitentiary hospital we form the following table:

Number of Sick Convicts reported at the Tennessee State Penitentiary from May 11 to June 7, 1873.

Date.	No. of convicts sick in hospital.	No. of convicts sick in cells.	Date.	No. of convicts sick in hospital.	No. of convicts sick in cells.	Date.	No. of convicts sick in hospital.	No. of convicts sick in cells.
1873.			1873.			1873.		
May 11	12	8	May 21	31	31	May 31	29	12
May 12	24	69	May 22	28	36	June 1	26	17
May 13	33	24	May 23	31	25	June 2	20	27
May 14	34	26	May 24	33	40	June 3	23	40
May 15	32	31	May 25	36	10	June 4	25	49
May 16	33	37	May 26	18	34	June 5	27	31
May 17	39	35	May 27	31	24	June 6	31	17
May 18	44	6	May 28	31	30	June 7	25	23
May 19	40	22	May 29	29	26	June 8	23	8
May 20	44	23	May 30	28	27			

On the 8th day of June, 1873, the fact was recognized that cholera was epidemic within the penitentiary-walls. John Thomas, a white convict, thirty years of age, was attacked and died within twelve hours. The prison-diet at the time being—

Breakfast: Coffee, bread, bacon or beef.

Dinner: Bread, bacon or beef, vegetables, and soup.

Supper: Bread, coffee, molasses or rice.

On this day I issued an order that all vegetables be withdrawn, also all fruits, and the diet to consist only of bacon, bread, rice, and coffee.

Only one who was present could imagine the consternation when it became known that the cholera had invaded the prison, and dozens were prostrated at once. Fortunately for me, I had able counsel in the person of Dr. Thomas Menees, whose cool, calculating mind added largely to any success we may have had. With such support I felt satisfied to make a square fight. The prison had been placed in a good sanitary condition, and disinfectants, such as lime, carbolic acid, sul. iron, bromo-chloralum, were used freely. With all the precaution, however, we could not check the disease, and our only hope was, if possible, to cure the unfortunate sick. Our treatment was as follows: Calomel and opium in small doses, repeated quite frequently. Quinine freely given either by mouth or hypodermically, with blister to stomach and bowels, and in collapse, beef-tea saturated with chloride of sodium. In the main this constituted our treatment. The hospital being insufficient, we occupied a large furniture-room, which allowed each prisoner that was sick a reasonable amount of air.

Much diversity of opinion existed in the city among medical men as to the cause of the trouble. Many contended that while it exhibited many symptoms characteristic of Asiatic cholera, yet that disease could not be traced to that source from whence it generally made its appearance on previous occasions, and again that the course of the disease did not in every particular map out true Asiatic cholera; that this was something very similar, but evidently a native disease, wholly independent of anything like a germ from India or elsewhere; while others simply asserted that it was cholera, and that they had nothing to do with its origin.

It is proper to state that among the convicts who had been working on the railroad were four female convicts who had been employed as cooks. All four were seriously ill on their return to the penitentiary. Mr. Ensley, the first case taken sick outside the penitentiary-walls, lived directly upon the drain from the female department of the penitentiary.

Very respectfully, your obedient servant,

GEORGE P. HENRY,
Physician in charge of Hospital.

Dr. E. McCLELLAN,
Assistant Surgeon U. S. A.

Through the kindness of Dr. J. D. Plunket, president of the board of health, to whom we are indebted for many acts of courtesy and for efficient aid in the prosecution of our researches, we were honored by a meeting of the physicians of Nashville, who were actively engaged in the treatment of the epidemic of 1873.

At this meeting much valuable information was obtained, and the causes of the epidemic in the city ascertained beyond a doubt. We submit accurate minutes of the meeting.

Minutes of a meeting of the physicians of Nashville, Tenn., held December 16, 1874, at the rooms of the Board of Health; present about fifty gentlemen.

Shortly after 7 o'clock p. m., Dr. J. D. Plunket, president of the board of health, called the meeting to order, and stated that its object was to aid Assistant Surgeon McClellan, United States Army, in obtaining the *facts* connected with the late epidemic of cholera.

Dr. John Maddin suggested that as Dr. Henry was the penitentiary physician at the time the cholera broke out in that institution, he might probably be able to give some very important facts.

Dr. HENRY. In reference to the cholera in the penitentiary: On the 12th of May, there were some seventy-five convicts sent from the Memphis and Paducah Railroad. All of them were sick, more or less, with diarrhœa, nausea, vomiting, and some of them with fever. On the 13th of May one of them died with symptoms of the cholera. With that the disease continued on until the 8th day of June, when we decided that we had an epidemic of cholera in the prison, and cut off vegetable diet. Dr. Menees came to my assistance. We had a great many sick. After the sick convicts arrived from Memphis we fed them on sour-krout and vegetables, and subsequent to this, after the 8th of June, we treated the patients with quinine, calomel, and opium. I heard of a case of cholera outside of the prison. Dr. Morton saw the patient first. It was a young man named Ensley. He died on Carroll street on the 22d day of May. I heard of no other case in the city for several days afterward. On the arrival of the convicts from West Tennessee I did not suppose they had cholera. I called it malaria. They had a good deal of scurvy. The physicians then claimed that it was cholera, and believed that they traced it to that section. I know of no case that occurred earlier than the 22d of May. We have a female department outside of the prison-walls. The women who came back with the prisoners were quite sick. The sewerage of the prison ran into Lick Branch at the time of the epidemic, and we paid a good deal of attention to the sanitary condition of the prison.

Dr. MENEES. So far as the beginning of the epidemic is concerned, I will say that on the 25th of May Dr. Buist felt unwell and was making preparations to leave the city. He requested me to go and see a little patient whom he had been called to see in North Nashville, on Summer street, beyond Jefferson. Several hours after he made the request I saw the patient, who was a child about one year old. When I saw her she was in a collapse, in a dying condition, and she did die soon after my arrival. I supposed it was a malignant case of cholera infantum running a very rapid course. A few days after that I was called to see a colored fellow on High street south of Broad. I found him in a collapse, pulseless, shriveled, and having cholera discharges. Upon inquiring into the history of the negro, I learned that he had been engaged in digging a well on Thursday. On Friday he did not feel well and took a dose of medicine, and then lingered on until Sunday, when he died. I attributed his death to his neglect in working in the water and in taking imprudent medicine. Cases transpired here and there until the morning of the 9th of June. On that day I was engaged by the lessees of the penitentiary to assist Dr. Henry. There had been a violent explosion on the day and night before of what was supposed to be cholera. There had been three deaths during the day and night. I learned that they had been eating vegetables, and had been acting a little imprudently. It was a violent outbreak of the disease. Upon arriving at the prison I found Dr. Henry struggling with a number of very sick patients in the hospital. After passing through the hospital, we went around through the wings where there were patients for whom there was no accommodations in the hospital. We requested the lessees to furnish better and more extensive accommodations, and they kindly agreed to allow us the use of the building known as the hemp-factory, into which the patients were transferred. We put them upon a restricted diet, and cut them off from using green vegetables and fruit, making a selection of such as we thought admissible. It will be remembered by gentlemen here that on the 9th June there was an unusual explosion of the disease throughout the whole city. We put the patients upon what we conceived to be proper

treatment, using calomel, opium, and camphor when the case was far advanced, and we used it boldly until the diarrhœa and vomiting were checked; and we used also quinine very freely, which I thought aided very materially in the rebuilding and convalescence of the patients. As to what benefit it would do when the case was in an explosive stage, I am not prepared to say. Under these circumstances we uniformly, before collapse came on, succeeded in arresting the vomiting by the introduction under the skin of a solution, using quinine and dry calomel, in any way we could get it to remain. The convicts were engaged at work at the gas-works, and at the capitol. They would be taken with the disease at these places, and by the time they would reach the prison they would be in a state of collapse. I had heard Dr. T. L. Maddin say in 1866, that in cases of collapse of cholera, to use salt-water in small quantities and frequently repeated; I did so, and succeeded in rallying a few patients. In 1873, profiting by this experience, I dissolved the salt in essence of beef, and in cases of collapse gave it to the patients about every five minutes, and would find them pulseless and cold and shriveled, yet, under the administration of this salted beef-tea, I have seen the shriveled form begin to fill up, the cold surface resume its heat, the pulseless wrists begin to beat again with vibrations of life, and the eyes illumine again with the light of convalescence. We had more than one case of that sort. I might hesitate to speak of these things if it was a matter behind the screens, but it is a matter of public record. In regard to the management of these cases, we did not rely upon the opiates; we relied upon using the calomel and opium freely, feeling that, when there was a disease that had seized upon the vitals of a patient with a violence that would destroy him in a few hours, we had better do something to rescue him. I used opium and calomel freely in the early stage of the disease. Upon observations of others, I began to use calomel, opium, and camphor in 1849. With the use of these agencies, before the body is drained of its serum, you can as certainly arrest the disease of cholera as you can that of malarial fever. With regard to the statistics of the penitentiary, I suppose we treated, in the hospital and out of it, about four or five hundred patients. There were about five hundred prisoners and *attachés* at the penitentiary, and almost every man, woman, and child there were affected with the epidemic. From the 9th of June to the 12th of July there were twelve deaths. There were some who had old chronic diseases, and when they were attacked by the cholera they would die.

Dr. MORTON. On the morning of the 28th May, I was called upon to go and see Mr. Ensley. I will say that I had but very little to do with the cholera when it was raging here last year. I find from my diary reports that I waited on a few individuals. There are other gentlemen here who had much experience in the treatment of cholera whom I would like to hear dwell upon this subject.

Dr. HENRY. The first case we observed was that of Mr. Ensley. I forgot the date, and called upon the family, and they told me that it was on the 22d May. Dr. Morton saw the patient in the morning, and I saw him in the evening when he was dying. He died on the 22d of May, so the family told me.

Dr. COMPTON. The cholera epidemic began and was upon the city as an epidemic before I believed it existed among us. I did not see any case for eight or ten days after I heard there was cholera in our midst. I was doing a general practice. About the 8th or 10th of June I was called to see a case under the Capitol Hill, on Gay street. I found a marked case of cholera. While there I was called to five or six patients,

all of which proved to be cases of cholera with the exception of two. I inquired where these patients worked, and learned that they were general paupers and idlers, working no place and living on cheap food bought from the market, and green groceries, and drinking water from a spring. I called the next evening and found that some of them had been relieved, from the medicine I had given them. Two of them were dying from opium. They were blacks and whites, and very poor. It was a constant run here and there. None of them were using hydrant-water. I was called the next day to see a class of people living near the place known as the magazine property. I found a neighborhood of poor waifs living in cheap houses, not over two hundred yards from the Franklin pike. In the first house to which I went I found a child dead in bed; the father in the bed with collapse, another child in collapse, three little children playing about, and the mother walking around. I saw them at half past 7 in the morning, and at 11 o'clock the father was dead, the little child in collapse was better, and two of the little children that been had running about were dead. I then went to other houses in the neighborhood, and found dead and dying in all of them. All of them were living on cheap purchased food, and drinking from a sulphur spring. I was not called to the family living in the Bilbo house. A man and his wife and six children lived within a stone's throw of these houses, and not a case occurred among them during the epidemic. They got their water from a deep well on the grounds. They would not permit their neighbors to come in and get water on account of their being such a great annoyance. On the hill above Rocktown the people drink water from a surface spring, and are living on garbage, cheap stuff. I was called over into New Bethel and saw patients dying, and learned that they were using water from a surface spring. On Rolling Mill Hill I learned the same fact. I found isolated cases of cholera during the last epidemic in Edgefield, across the river; they may have been cholera morbus. One of the patients died. Mr. Chambley came here sick about the 9th of June from near Memphis, where he had been working a number of convicts on a railroad. The newspapers stated that these prisoners were dying down there. There are two springs down between Pearl and Gay streets, near the trestle. There are a number of springs around there that families get water from.

Dr. WINSETT. I was living in what is called Rocktown, within one hundred yards of the Bilbo place, and used water out of a well 60 feet deep. There were four persons in my family; neither one of us had the cholera. We lived judiciously and on good diet; took care of ourselves. A family lived across from us and used water from the same well. A little girl was taken early in the first week of June, at 7 or 8 o'clock in the evening, and at 11 o'clock at night she died. I do not know what kind of diet the family used. Only two families used water out of that well. The balance of the families around there used water out of surface springs. Four persons who lived right back of my house died.

Dr. HENRY. There were about twenty convicts at work at the capitol at the time the case occurred near there that Dr. Compton spoke of.

Dr. PLUNKET. Dr. Atchison reported a case of a negro man who had gone into the Hackberry Spring district from the penitentiary, and died of cholera.

Dr. CONNELL. A father and daughter were attacked with the cholera at Parrish's. One died and the other recovered. After the 7th or 8th of June there was no question as to the character of the disease at all among the physicians, but before that time there was some doubt.

Dr. COMPTON. I know of five or six deaths among women in places

where there was no cholera, and where it did not spread. Upon inqui I learned this of their history: that they were washerwomen, and h washed the clothes of cholera patients. I saw them in North Nashvil beyond the limits of our hydrants.

Dr. MENEES. It will be remembered that under our system here t convicts were hired out at various points, and that at the time of t outbreak of cholera here they were working at the capitol, gas-work and other points in the city. At this time the lessees of the penite tiary very generously extended the aid of the prison in sending out the carts to aid in cleaning up the city.

Dr. MCCLELLAN. On the 20th day of May a negro woman, nam Rhoda Edwards, was very low with the cholera, and on the 30th of M died of consecutive fever. I obtained the record of that case from t Colored Benevolent Society. I counted the number of cases record on their books. I found a half-dozen negroes who knew all about t case, but could not find out what doctor attended her. In regard these early cases of cholera, there is one point that is of importan which has not come up yet for consideration, and that is the occurren of the Exposition, and the strangers that were brought into the ci from elsewhere. Does the Exposition have any bearing upon the ep demic?

Dr. HENRY. During the Exposition hundreds of people visited t penitentiary, and went through it every day.

Dr. JOHN L. MADDIN. I saw the first case of cholera on the 5th da of June in the bottom to the left of the Chattanooga depot. I sa cases all over the city among all classes of society. I saw them amon people who drank hydrant-water and well-water. The second case saw was on Rutledge Hill on the 6th of June. This is a very health place. My experience was the same as that related by the other gentl men. My brother saw an old lady; she ate her breakfast, and at 1 o'clock she was in collapse, and died about two hours afterward.

Dr. MCMURRAY. I saw the case on Rutledge Hill on the night of th 4th of June. I prescribed, and went back next morning, and the p tient was dead. I began to inquire into the case, and they told me th he had come home in the evening before and drank buttermilk for sup per. The next case I saw was near Buck spring, in a high location. think that was on the 6th. I went to see the patient the night befor and found him in a collapse. As I was returning next morning to s him, I met Dr. Bowling and I asked him if he had seen any cholera in t city. He said no. I told him that this was the first epidemic I ha been in, and that if this was not a case of cholera I did not know wh the books meant. He went with me to see the patient, and on comin out of the house he said that it was really the cholera. The man died tw hours afterward. He worked very hard the day previous to his deat and drank a good deal of water. He ate a good many cold vegetable for supper.

Dr. HUGHES. I did not refresh my memory with my books befor coming here. My first case was on the 26th of May, at No. 116 Sout Summer street, beyond Broad, in a little frame house not far from th Wilson Spring Branch. A negro man about thirty years old had bee sick with diarrhœa for two or three days. When I saw him he had wha I though were symptoms of cholera. Dr. T. L. Maddin passed my office and I asked him if he had seen anything of cholera in his practice That man died in about forty-eight hours after being attacked. I d not know his history. The next case I saw was a negro woman o Front street, between Church and Broad, about 9 o'clock in the morn

ing; I found her in a state of collapse. I think that was on the 28th of May. My next case was a Mrs. Jones, on North Summer street, near Cedar. I was called to see her about 1 o'clock in the day, and found her suffering from what I believed to be the cholera. I asked if she had a family physician. She said that she had—Dr. Williamson. I told her she had better send for him. I passed along there that night and learned that she was dead. This was about the 4th of June. About 11 or 12 o'clock that same night I was called out to see a lady that had the diarrhœa; that was on the corner of Cedar and McLemore streets. On my return I found an order to call at Jones's again; when I got there, about 1 o'clock in the morning, I saw a little girl six or eight years old in bed. I gave my opinion that it was cholera. She died the next morning about 8 o'clock. My next case was on Union street, between Summer and High streets, very near Dr. Bowling's office. She was a nurse for a family, was taken sick on Saturday night, and died on Sunday night. That was the first Sunday in June. About this time the epidemic became general, and my experience does not teach me that it was confined to any particular locality. I found the patients drinking branch and spring-water. (The first five cases I saw died.)

Dr. COOK. I saw a great deal of the cholera while it prevailed here. The first case was about the last of May, and was a patient of Dr. Winston. She was a negro woman, and lived above Buck Spring, on Ash street, near Ewing's avenue. A lady was also sick in the same neighborhood; both of them died, the negro woman dying that same night. This was the first case of cholera I ever saw in my life. It was not admitted by the profession that there was cholera in the city until after the 6th of June. This patient died at 4 o'clock on the morning of the 5th of June. She had eaten a hearty dinner, especially snaps. It was the Maury family, a mother and two sons. The cholera existed more alarmingly in New Bethel, a mile or two from where the Maurys lived. This was a little village inhabited by negroes entirely; they lived in huts 8 by 10 feet. The first house I visited I found two persons dead and five children sick; two of them with cholera and three with the measles. Three of the children died, and the other two recovered slowly. The cholera prevailed there for several days, and nearly every person on the hill had it. There was not a house there that was free from it. These negroes were exceedingly poor, badly clad, badly housed, and still worse fed. Some of them told me that they had not eaten anything for two or three days. They got water from a spring below. I think the cholera originated in the neighborhood of springs. I only remember one isolated case; a gentleman died in Edgefield, who did business in the city. He went home at night, and about midnight was taken with cholera. I saw him the next morning. He was suffering from discharges. I gave him calomel, camphor, and opium, and succeeded in checking his discharges. He died in three or four days afterward. His name was Henderson. He drank water in Nashville.

Dr. SCHIFF. The first case I saw was on the 5th of June, on Market street, a few doors below Union. She had just come here from Huntsville, Ala. She had a very light attack. About a week or two later she was attacked with flux. The second case I saw was on Capitol avenue a day later. I did not see many cases in the suburbs. I saw a few cases in South Nashville, but none of them proved fatal.

Dr. RAINEY. I had three cases six miles from the city, in a very healthy section of the country. They occurred within a few hundred yards of each other. Two of the patients were not very regular in their

habits, but the other was; two of them died and the other got well. They used water from an excellent spring. This was at the Hope Institute, to the left of the Murfreesborough pike.

* * * * * * *

It is submitted that the evidence presented in the foregoing pages fully establishes the introduction of cholera into the city of Nashville. This evidence will admit of recapitulation.

On the 11th of May a gang of convicts arrived at Nashville from the line of the Memphis and Paducah Railroad works. The camp which they had left was infected with cholera. A number of their comrades had died. The deputy warden was so ill of the disease that the party were sent from their camp without him. We have in evidence the statement of Dr. Wright, the superintendent, that he had ordered the men returned to the penitentiary on account of the cholera being epidemic at the camp they then occupied. Dr. Erskine, of Memphis, has shown how this camp became infected.

Upon their arrival at the penitentiary the entire gang, some seventy-five or eighty in number, were placed in the buildings with the convicts who had not been away from the institution. In this convict-gang were four women, who had been employed as cooks and washerwomen for the working-party.

The entire gang were sick with diarrhœa when they arrived, and were at once placed under treatment. The four women were dangerously ill for some time. On the 13th of May a returned convict died in the penitentiary hospital of cholera. He had not been very sick when he arrived from Shelby County, and was therefore treated in his cell, where a few hours before his death he was found collapsed. It has been shown how the drainage of the penitentiary is managed, and this fact opens the way to the development of the initial cases in the Nashville epidemic of 1873.

On examining the records of a colored benevolent association, and inquiring as to the cases there on record, we found that a negro woman named Rhody Edmonds, who lived east of the penitentiary and directly upon the drain from the female department, was taken with cholera on the 20th of May, but that she did not die until the 31st. The case was described accurately by several persons who had been in attendance upon her.

May 22d, Mr. Ensley, the case reported by Drs. Henry and Morton, died of cholera. The house at which this man lived was nearly opposite the exit of the drain from the female department of the penitentiary; a narrow street only divides his property from the prison.

June 1, a negro man, who had some three or four days previous been discharged from the penitentiary, died of cholera at a shanty on South College street, near Wilson's Spring. It was found upon investigation that several of the convicts had been discharged after their return from Memphis. The majority were negroes, and at once resumed their former social status in the city.

From these cases and from such means did the epidemic strike the city of Nashville. It has been shown that convicts were employed upon the State capitol grounds, that they were employed in cleaning the streets, and that the fatal cases that occurred at the penitentiary were among men thus employed. It has been shown that, during the exposition, the penitentiary was daily visited by large numbers of individuals. Could human ingenuity have devised a more effectual mode for the dissemination of the disease than that which was adopted? Nashville

uffered in 1873 from the obstinacy and bigotry of her officials, as she ad suffered in past years from the same cause.

The efficient moment for action was lost amid the discussion and eated feeling that grew from the discussion as to the nature of the isease. We are strongly of the opinion, from facts that have come to ur knowledge, that prior to the cholera explosion an epidemic of ma- arial fever was upon the city. There are no records from which this ay be proved. We gather the fact from conversations with prominent hysicians; and that the knowledge of this existing disease masked he judgment of the cholera opponents. How fatal was this error the leath-roll demonstrates.

Dr. Bowling has collected statistics showing that from June 7 to July there had occurred 244 white deaths and 403 colored deaths, a total f 647 deaths. This number includes the 72 deaths of June 20, "the Black Friday." It is known that large numbers of negroes died who were buried by their friends, and of whom no record was made. This s especially true of the localities described as Rocktown and New Bethel. It is computed by parties who had every opportunity of obtain- ing full information that, from the inception of the disease to its close, t least one thousand deaths occurred. There is, however, no possibility of obtaining absolute information upon this point.

The map of Nashville, which accompanies this report, designates the localities at which the disease was most virulent. It is not intended to convey the impression that cases of cholera did not occur upon Capitol and other hills. The epidemic was confined to no special locality, although it exhibited points of greatest malignancy, and fully sustained the theory that cholera will exist wherever it is carried and wherever local causes exist that favor the rapid reproduction of the specific cause.

The cholera was carried to various points in Davidson County from the city of Nashville. One of the most interesting demonstrations we present in the following account of

THE EPIDEMIC OF CHOLERA IN 1873 AT GOODLETSVILLE, TENN.

By Dr. I. R. Kirkpatrick.

Goodletsville is a station on the Saint Louis and Southeastern Rail- road, twelve miles northwest of Nashville.

On the 16th of June I was called in consultation with Dr. Robert Guzzard to visit a negress at the residence of Mr. Payne, at Ridgefield Junction, ten miles north of Nashville. The woman, who was about thirty years of age, came from Nashville, the evening before, to serve as cook in the family of Mr. Payne. She had been suffering for some days before she arrived from diarrhœa, and she came from one of the suburbs of Nashville, in which tenements occupied by negroes are closely packed in narrow lanes and winding alleys, the abodes of filth, wretchedness, vice, and misery. The woman cooked supper for the family, and at about 3 o'clock a. m. of the next day was taken with severe and alarming symptoms. She received no medical attention until about 10 o'clock a. m., when she was found fully collapsed. She was treated with calomel, opium, camphor, aromatic sulphuric acid, without obtaining any good results, and she died in a few hours.

A few days after the death of this woman I was called to see one Forester, a laborer upon the railroad. He had drunk a large quantity of water the day before, and had eaten for supper, among other things, a mess of cold boiled cabbage. He was taken with severe vomiting and

purging at 3 o'clock a. m. Being absent from home, I did not see thi case until 1 o'clock p. m., when I found Dr. P. Byrne in attendance. Th characteristic symptoms of cholera were present in their most aggra vated form, attended with rapid prostration and approaching collaps

The treatment had been calomel in decided doses, and sinapisms We immediately gave a hypodermic injection in each arm of the fo lowing:

℞. Quinine, gr. viij.
Acid. sulph. aro., gtt. x.
Spt. ammon. aro., ʒj.
M. Morphiæ sulphas, gr. ½.

Ordered that he should have as much ice, and iced water in whic a quantity of salt had been dissolved as he wanted; and of this he drau largely. Chicken-soup, seasoned with salt and cayenne, was given, an dry frictions with flannels ordered.

The next day there was apparently no change in his condition; th same treatment was continued, with the addition occasionally of a solu tion of chlorate of potash as a drink, and the following pill every fou or five hours:

℞. Calomel, gr. xxiv.
Pulv. opii, gr. viij.
Pulv. camph., gr. x.
M. Ft. pil. No. viij.

In two days, by careful nursing, reaction was established, and h slowly but surely advanced to recovery. This was one of those extraor dinary recoveries of which we may occasionally boast, and it was due no doubt, to the hypodermic injections and the free use of salt and ice water. Had we met with the same success in every case that attende our efforts in Forester's case, it would be a pleasure to write this article but the facts are demanded.

There was but very little, if any, diarrhœa, cholera morbus, or dysen tery before the occurrence of the first well-defined case of cholera, bu after that case there was not much skirmishing before the enemy showe his strength, and such was the panic produced by the rapidly-fatal case that occurred, that the majority of residents supplied themselves wit medicines and medical advice; a precaution which saved many lives an greatly lessened the mortality of the epidemic.

There was nothing new or peculiar in the symptomatology of the di ease as it came under my observation. In some cases the discharge were slightly colored, and in many cases cramps were wanting.

The line of treatment which was adopted will be found laid down i the following case:

June 20, was called to see J. D., a stout, vigorous fireman upon th railroad. He presented all the symptoms of cholera in an aggravate form. Absolute rest was enjoined, ice and iced water were allowed, an one pill of calomel, opium, and camphor (the formula for which ha already been given) was ordered to be taken every two hours. Alter nating with the pill, a teaspoonful of the following mixture was given

℞. Acid. sulph. aro., f3x.
Tinct. opii, f3v.
M. Aqua camphoræ, f℥iv.

June 21.—Still vomiting and purging, but not so frequently. Com plains of great weakness; thirst intense. Continued treatment, wit

the addition of chlorate of potash treatment. Later in the day an injection per anum of the following was ordered:

R. Quinine, gr. xx.
Tinct. opii, gtt. xl.
M. Spt. vini galici, ʒiv.

To be repeated every four hours.

June 22.—At 4 o'clock a. m. patient easy, seemingly improved. At 10 o'clock a. m. much worse, rapidly passing into collapse, having involuntary discharges, ice-cold extremities, profuse perspiration, &c. I hurriedly gave him a hypodermic injection, in each arm, of quinine, aromatic sulphuric acid, spirits of ammonia and morphia. Returned in three hours, expecting to find him dead, but found a radical change for the better. All the symptoms were under control, and reaction was fully established.

As an evidence of the virulence of the epidemic, another group of cases is offered.

Was called to see J. C., aged twenty-one years, a healthy farmer, and found him in profound cholera collapse after but a few hours' illness. The acid mixture was injected into each arm, and the exhibition was repeated many times in various portions of his body. He was wrapped in a sheet wrung out from iced water and covered with blankets, but he died in a few hours. This death was followed by the occurrence of three other cases in the same family within a few days, two of which were fatal.

Some cases were very slow in convalescing, which state was accompanied by an irritable condition of the lower bowel and an inability to control it.

SUMNER COUNTY.

Gallatin, the county town of Sumner County, is located upon the line of the Louisville and Nashville Railroad, twenty-five miles northeast of Nashville, and three miles north of the Cumberland river.

The history of the cholera epidemic at this point is given in the following letter received from Dr. H. A. Schell:

The urgent duties devolving upon me during the cholera epidemic of last year prevented, in a great measure, my keeping a record in detail of cases as they occurred; however, I will endeavor as nearly as possible to furnish you the more prominent particulars of its history.

The first case occurred May 29, in the person of a mulatto widow named Lucy, aged about seventy years, who had returned the evening prior to her attack from Nashville, where she had been on a visit of a few days. She had a diarrhœa for several days, which she attributed to an over-indulgence in vegetables while in Nashville. No remedies had been used until 6 o'clock a. m. on the 29th. Symptoms becoming urgent, Dr. Malone was called. He thought the case a suspicious one at least, and if cholera morbus, very aggravated. Gave morphia hypodermically, ordered sinapisms and heat to the extremities, ice, and left calomel and bismuth. After his second visit, Dr. Malone was so firmly impressed with the belief that the case was one of genuine epidemic cholera, that he invited me to see it. As it was not convenient to go immediately with the doctor, I called by myself about an hour later. Four o'clock p. m. I found the patient semi-conscious, voice husky and whispering, tongue cold, fingers shriveled, no pulse; in short, collapsed. Died at sunrise on the morning of the 30th.

In view of Lucy's age, together with the imprudent indulgence in articles of diet to which she was unaccustomed, fatigue and exposure to the sun she had undergone, the change of water to which she had been

subjected, and the positive denial of there having been a case of cholera at Nashville, we agreed to diagnose the case cholera morbus.

On June 1, James Stepleton, colored, aged about twenty-four years, a habitual drinker, who had also been visiting Nashville, from which city he had returned at the same time as Lucy. He also had diarrhœa, for which no remedies were employed save whisky. On the day of his attack he arose early and went as usual to sweep out a saloon for which he was a waiter; before completing his work (his diarrhœa having increased in its severity) he became so much exhausted as to require assistance to get him to his home. Drs. Tompkins and Bresh attended him, and diagnosed the case to be Asiatic cholera. The man died in collapse at 2.30 o'clock the same evening, having been ill less than ten hours.

These cases occurred in different portions of the town, but at each locality the ground was low and flat, surface-water abundant except when very dry, scarce any drainage, and hygienic surroundings in general very bad. No new cases supervened in these localities for several days; in fact, we were beginning to hope that the efficient use of sanitary measures would ward off the threatened epidemic, but our people could not be aroused until too late, when the disease was fully developed.

Case No. 3.—Amanda Munday, colored, aged about forty years, was attacked at night about four days after the death of case No. 2. She lived on the lot next adjoining the saloon where James Stepleton was taken seriously ill. The common privy was built on the division-line. The excreta for case No. 2 were not disinfected either at the saloon or at his home, and Amanda used habitually this privy. She collapsed, and died within twelve hours.

On the evening of the same day, a colored woman, aged thirty years, who lived on a lot adjoining the one of Amanda Munday, was attacked, collapsed in four hours, and died in six hours. During the next forty-eight hours the disease became epidemic in this locality, and several new cases occurred in the immediate vicinity of the house at which case No. 1 had died. At the locality where cases 2, 3, and 4 had died, and which was near the depot of the Louisville and Nashville Railroad, the disease raged severely, and spread in a northeast direction up a hollow, where there is a negro settlement. The water these people used might properly be called seep-water, it being obtained at a depth of from 10 to 25 feet.

The disease in the neighborhood where Lucy (case No. 1) had died was more circumscribed; in fact, it confined itself to the immediate locality, with now and then a case, for a week or more. These people obtained their water from a town-pump that supplied all the business-portion of the town, and is at the bottom of a hill.

The district next attacked was on Main street, only a few doors east of the public square. Mrs. J. White, aged about twenty-five years, was attacked about 3 o'clock a. m. on June 13. Dr. Malone saw her about 6 o'clock a. m. I saw her an hour and a half later. Had rice-water discharges when first seen, collapsed two hours later, and died at noon. The father of this woman lived in the immediate vicinity of cases Nos. 2, 3, and 4. He did not remove from his house; his daughter visited him constantly, and although there is no direct history of her having contracted the disease from the infection of the locality, it is quite fair to presume so. She had premonitory diarrhœa for several days as we learned after her death. The surroundings of this patient and the immediate neighborhood were anything but cleanly; in fact, the lots back and adjoining were most miserably filthy. After the death of Mrs. W., several

negro families living on the back lots suffered from the disease, each losing one or more members. A white family living next door to Mrs. W. had three cases, but all recovered. From this immediate locality the disease did not spread.

The next locality attacked was on the southwestern part of the town, outside the corporation limits, and nearly three-quarters of a mile from the infected vicinities. This point was at the cotton-mills. There was constant communication with the town. Preparations were being made to rebuild the factory, which had been destroyed by fire the winter before. A number of negroes who lived in the second infected district were employed on this work. The mill-buildings are upon high ground, but bounded on the north and west by swamps. The cemetery where all the dead from cholera were buried is northwest of the mills, not exceeding three hundred yards distant, and only separated from the factory-grounds by a narrow street. These grounds, during wet seasons, are covered with water. The water-supply for the factory is in most part obtained from bored wells; one of these is 100 feet deep, another is 70 feet, and a third is fed from surface-water.

The next portion of the town attacked was the highest and most cleanly portion, but was not far from the point at which case No. 1 had died. The patient, a mulatto woman twenty-six years of age, was first seen an hour after her symptoms became alarming. She had premonitory diarrhœa for several days; was a servant in the family at whose house she was taken ill, but slept at her own house, which was quite close to that in which case No. 1 died, and she had frequently visited Lucy during her illness. This woman was severely ill, but recovered. Following this case, three cases occurred in the family to whom she was servant, one of which terminated fatally. Among the family living in the adjoining house three cholera cases occurred, with one death; and some ten or twelve cases occurred upon the same street, with two deaths.

A few cases occurred out of town, of which I know nothing, save in one family. A young lady who resided at Nashville visited her grandmother, who lived about two and a half miles from Gallatin, for safety during the epidemic. She was taken with cholera at midnight on the 25th of June, a few days after her arrival, and died at daylight. The servant-woman of this family took the disease, and died in a few days. The other members of the family left the house.

Numbers of our citizens who deserted the town went to Epperson Springs, a watering-place some twenty-two miles from Gallatin, situated on a high ridge, with good surroundings. Several cases of cholera occurred there among those who had left the town, resulting in two deaths—one a white boy some five or six years old, the other a servant-man about twenty-four years. The disease did not become epidemic.

A white man named Mungals, who lived in the county, some twenty miles from Gallatin, visited Nashville on business in June. On his return home he sickened and died of cholera. All the members of his family had the disease—his wife, son, son-in-law, and his daughter—all of whom died except the daughter. A negro family waited on the Mungals; all took the disease and died. A man named Parker visited the house during the epidemic, and also died. The other neighbors, becoming panic-stricken, deserted their homes and fled to the hills, when the disease abated.

At Gallatin the disease began to abate in the latter part of July, and by the middle of August had disappeared from among us; neither did there appear another case among any of our citizens, large numbers of whom had abandoned their homes during the epidemic and were now

returning. But in the early part of September we had two more cas under the following circumstances. The colored people's fair was goi on at this time. One Brown, white, aged about thirty-five years, wh business was traveling with some kind of lottery-trap or game of cha was there. A few days before he had left Lebanon, Ky. On the seco day after his arrival, about noon, having had diarrhœa for a day or t previously, he was violently attacked at the fair-grounds with chole He came immediately to town, had all the attention that could be a forded him, but at 8 o'clock p. m. was collapsed, and died at 3 o'cloc a. m. the next day.

A white man, twenty-six years of age, came to Gallatin about t same time Brown did, but from an altogether different direction a locality, chanced to meet Brown at the hotel, went with him to the fa grounds, visited him while sick, and after Brown's death was frequen in his room. Two days after the death of Brown this man was tak with cholera; was collapsed in four hours; reaction took place dur the next seventy-two hours, but he died of consecutive fever on t fifteenth day. This man had been on a debauch for ten days or t weeks prior to his attack.

The dejections from these two patients were disinfected and burn the bedding and clothing were burned; the bodies were disinfect No other cases occurred.

About one hundred and twenty deaths occurred from cholera at G latin, four-fifths of whom were negroes. Very few cases occurred am those who observed proper hygienic precautions. The cases of dis which were seen early and which were properly cared for, for the m part recovered. Those who drank to excess and ate freely of the co vegetables, when attacked seemed to defy all remedies. Excit nervous, easily-alarmed subjects were most susceptible to attack. succumbed to the disease most readily. The majority of the case curred at the early hours of the morning.

The weather during the entire time of the epidemic was wet cloudy, with frequent thunder-storms. There was but one day du the month of June that it did not rain.

From a careful study of this demonstration, I am convinced that dejections from both stomach and bowels, as is also the cadaver af certain stage of decomposition has taken place, are capable of gen ing a specific poison peculiar to cholera, and upon which the propag of the disease depends; that certain conditions of the atmosp together with animal or vegetable decomposition, either or all, ten intensify the malignancy of the poison; that the lungs, stomach, probably the skin are the avenues by which it is conveyed; tha proper hygienic regulations and the free use of disinfectants the ease may be "stamped out," and that precautions in the same d tion are safeguards against the disease; that the water-supply ha influence in propagating the disease, except it be directly infected cholera-poison.

Very many different modes of treatment were tried, but from observation, and that of the professional gentlemen who saw the di with me, anti-spasmodics and anodynes, calomel, with or without muth, together with external means—sinapisms, artificial heat, ice, & proved most effectual.

Yours, very truly,

H. A. SCHEI

DR. E. MCCLELLAN,
Assistant Surgeon U. S. A.

The man Brown, who is noted by Dr. Schell as having died of cholera Gallatin early in September, was present at the Marion County fair ld at the town of Lebanon, Ky. He was a perfectly sober man, who pported his family by a "dollar-store" enterprise, with which he vis-ed the county fairs of Kentucky during 1873.

On the 29th of August, while at the town of Lebanon, Brown com-lained of a diarrhœa, for which he was treated by the writer. The next ay, (August 30,) although he was not entirely over his diarrhœa, he ft town upon the noon train. During the ensuing night the Marion ounty epidemic of cholera was developed.

EDFORD COUNTY.

Shelbyville, the county-town of Bedford County, is located upon a imestone bluff upon the banks of Duck river, which stream flows round the northern and eastern sides of the town. The bluff slopes pon the north and west to the level of the river; this valley is, how-ver, denuded of alluvial deposits, and presents all the geological char-cteristics of the bluff, upon which is the business portion of the town nd the residences of a large proportion of the inhabitants. That por-ion of the town which is built upon low ground consists of small ouses and the cabins of negroes; with the exception of the Murfrees-orough turnpike, which is lined by the residences of the wealthier citizens.

Shelbyville is the terminus of a branch of the Saint Louis, Nashville and Chattanooga Railroad, by means of which road the town is in daily communication with travel north and south. The town has about 3,000 inhabitants.

The water-supply of the town is in the greater part obtained from a series of springs that line the foot of the bluff. One, a bold stream, issues from beneath a ledge of rocks; its line follows the course of the river, and it can be traced for miles from its point of exit by means of sink-holes, from which water can be obtained at all seasons of the year.

Upon the high ground the majority of the houses are supplied with wells, which are in all instances formed by blasting into the rock. The houses of the best class are furnished with cisterns. The privies are either upon the surface of the ground or consist of shallow pits blasted in the rock.

The sanitary condition of the town of Shelbyville during the early months of 1873 is described as being bad; but it is to be supposed that in this it differed in no particular from inland towns of its class. In these small towns no attention is paid to public hygiene until absolute danger awakens the supine authorities. In the town of Shelbyville, as in so many others of its class, the hot-bed was most assiduously pre-pared for the arrival of cholera, and when the disease became a positive presence, valuable time was lost in discussing the theory that the dis-ease had originated from miasmatic causes.

It is impossible to obtain full lists of the cases of cholera that occurred at this town, although from a personal inspection and con-ference with the medical gentlemen of the town, much valuable informa-tion has been obtained.

As to the origin of the disease, it is determined that on the 31st of May, Mr. H. J. George, who resided some four miles northeast of the town of Shelbyville, returned to his home from the city of Nashville, where he had been a visitor to the Exposition. Mr. George was suffer-

ing from diarrhœa when he arrived; this diarrhœa continued unchecked for two days, when the symptoms of cholera were developed, and when he was first visited by his physician he was found to be profoundly collapsed. This case terminated fatally in twenty-four hours from the occurrence of the violent symptoms.

The day after Mr. George's death (June 4) his widow was attacked with cholera, from which she recovered only after a long and tedious illness.

Mr. William George came to his brother's house with his family to assist in taking charge of the sick prior to the first death. This gentleman and his young child were both attacked with cholera, to which they had only been exposed at this house. The father recovered, the child died.

On the 15th of June, Caroline Thompson, a negro woman, who lived in the lower portion of the town, was taken with the diarrhœa, which was ascribed to some imprudence in diet. As the diarrhœa increased the exhaustion became pronounced, and attention was first called to her case by her having been found upon the floor of her cabin in an unconscious state. The case, however, was protracted; she reacted under treatment, but died of consecutive fever upon the 19th.

Upon the day that Caroline Thompson died, a Mr. Vance, who had been a clerk at the Battle House at Nashville, but who had left that city on account of the cholera, was taken violently ill at his home at Shelbyville; the symptoms of cholera were fully developed, and he died after an illness of eight hours. This man had been in Shelbyville for some five or six days before he was attacked by the disease, but upon each of these days he had complained of a diarrhœa which was exhausting him. He, however, did not remain quiet, but was constantly visiting in the town, and to his presence the diffusion of the disease throughout the town can in great measure be ascribed. The two cases that have been noted were not the only residents of Shelbyville and its vicinity who had been within the area of cholera-infection at Nashville. During the early days of June this town was full of individuals returning from the Exposition. Whether others were at the time suffering from diarrhœa it is not now possible to determine, but enough is known to prevent the case of Caroline Thompson from being considered as an isolated demonstration of the disease.

On the 19th of June a third cholera-case occurred. Sarah Davidson, a negress, who had nursed Caroline Thompson, was also taken with the cholera, and died after a short illness. During the night of the 19th and 20th of June a young child, the daughter of Mr. Vance, died of cholera.

June 20, the husband and mother of Sarah Davidson were taken with cholera, and both died after short illnesses.

After the death of Mr. Vance his widow went to the house of her father, a Mr. Russell, who lived about one mile south of what may be considered as the infected district of the town. At Russell's house was now congregated a family of seventeen individuals. Among these individuals seven cases of cholera followed the arrival of Mrs. Vance. Two of these cases terminated fatally.

Caroline Thompson, Vance, and the Davidsons had been visited by large numbers of individuals. In these early cases no effort was made to disinfect the excreta, which were thrown upon the ground in rear of the houses.

From these cases the disease spread and became epidemic. Each of the three houses became a focus from which the disease radiated; but the

family of Caroline Thompson, consisting of her husband, two daughters, and three sons, escaped entirely, although each adjoining house became infected.

The epidemic having been established, numerous instances of the infectiousness of the disease occurred. Multiple cases in families were frequent; in many houses six and eight cases occurred. One notable instance is related by Dr. Lipscomb. At a cabin which was occupied by a negro family several cholera-deaths occurred. The cabin was abandoned and remained unoccupied until after the epidemic was supposed to have been arrested, when a man who was sick with rheumatism moved into this cabin. On the second day of his occupancy he sickened and died of cholera.

The physicians of Shelbyville recognized the importance of treating all cases of simple diarrhœa, as the inception of an attack of cholera. They report that all such cases were amenable to treatment; that at this stage the disease was within human control; but that whenever the disease advanced to the stage of full development but little good could be accomplished by therapeusis. Several cases of recovery from profound collapse are, however, reported.

It is stated that some four hundred cases of the disease, more or less well marked, were treated at this town during the epidemic, with some eighty deaths. The treatment that was found to be the most effective was calomel, in full doses, combined with small doses of morphia, absolute rest, and a free supply of iced water.

After the epidemic influences were fully established, a most active system of disinfection and general police of the town was attempted.

At Wartrace, a station of the Saint Louis, Nashville and Chattanooga Railroad, in Bedford County, and also the eastern terminus of the Shelbyville Branch Railroad, a few cases of cholera occurred.

Early in June an aged negress, named Kitty Stokes, who lived with a man who was employed as a laborer upon the railroad, was taken with cholera, and died after a few hours' illness. During her illness she was nursed by one Newton and his wife. A few days after the woman's death Newton was taken with cholera, but recovered after a tedious illness, during which illness three of his children took cholera and died.

Later in the month a negro man, employed upon the construction-train of the railroad, was put off at Wartrace in the collapse stage of cholera, and died in a short time.

In each of the cases enumerated, after that of Kitty Stokes, disinfectants were employed.

Wartrace is a village of about fifty inhabitants.

Rutherford County.

A STATEMENT AS TO THE CHOLERA EPIDEMIC OF 1873 AT MURFREESBOROUGH, AND RUTHERFORD COUNTY.

By Dr. J. B. Murfree.

Murfreesborough is a healthy, well-located town, in very nearly the geographical center of the State of Tennessee. It is upon the line of the Nashville and Chattanooga Railroad, thirty-two miles southeast from the city of Nashville. The town has a population of about 4,000 inhabitants. During the month of May, 1873, cholera appeared in the city of Nashville, but was not early recognized, having been designated as cholera morbus or sporadic cholera. The Exposition at Nashville was

open during this time, and attracted many visitors from all portions o the State; large numbers went from Murfreesborough. During the entir epidemic no attempt was made to quarantine the town; no attempt wa made to prevent the introduction of the disease from Nashville; on th contrary, the freest intercourse possible existed between the two cities Murfreesborough is situated on rather an elevated plain, and the drai age is good except at two or three points. There is a small stream o water coursing through the southwestern portion of the town. Its cha nel is broad, and is composed of dirty, miry clay; the declivity is ver slight; consequently the stream is sluggish. Its banks are only elevate above the usual plane of the water 12 or 14 inches, and recede from th stream on the same level, in some places as far as one hundred yard After heavy rains this whole bottom is inundated, and, the drainag being so imperfect, the water is retained until absorption and evapor tion effect its removal.

During the spring of 1873 a great deal of rain fell, and this botto was almost constantly covered with water, which could find no way o escape. During the epidemic the vast majority of the cholera case occurred in persons who either lived in the vicinity of this branch o whose daily vocation required them to pass it more or less frequentl during the day. It is not believed that this marshy district originate cholera, but it is believed that it aided its development; that there th cholera germ found congenial soil, a proper *nidus* where it could res and multiply. The Nashville and Chattanooga Railroad passes throug this marshy flat, making three crossings of Lytle's Creek.

The water-supply is obtained from wells scattered over the town, an from three large and fine springs. The character of the water is lime stone, pure and cold. Many private houses are provided with cisterns

The sanitary condition of the town was not good prior to the develop ment of cholera in 1873. The streets and by-ways were filthy; th majority of the privies were upon the surface. As soon as the disease developed, a scavenger-force was organized, and the general police o the town was made as rapidly as it could be effected.

On the 1st day of June, Littleton Rucker, a negro man some forty three years of age, who resided at Nashville, came to Murfreesborough to visit his relations. Immediately after he arrived he was taken with cholera, and passed almost immediately into the stage of collapse. There was remarkably little vomiting and purging. The case terminated fatally after an illness of about ten hours. This man was sick and died at a cluster of negro cabins known as Bethany, on the eastern suburbs of the town. The excreta of this case were disinfected, and no case of the same disease occurred in the vicinity of the house at which this man died during the entire epidemic.

June 12 a negro woman fifty years of age, living in the northwest por tion of the town, was taken with cholera; she was sick eight days, but recovered. This woman had not been away from home, excepting to visit a sick daughter who lived quite close to the railroad depot. Her hus band, a blacksmith, at that time was working in a carriage-shop near the region of cholera-infection. The house of this woman was not fre quented by strange negroes, but they had much company among their friends and neighbors.

June 14, Millie James, a negro prostitute and the keeper of a bagnio, was taken with cholera, and died after an illness of twelve hours. The house of this woman was much frequented. Being quite near the rail road depot, many of her customers were railroad hands; and it is known that persons from Nashville were at the house.

June 15, Mattie Tate, a white prostitute who lived in the house of Millie James, was attacked with cholera, but recovered; and on the 17th her two children, aged respectively five and two years, were taken sick with the same disease, but recovered, the first in three, the other in five days. This woman was the mistress of a man who was a town policeman.

Mattie Tate had nursed Millie James. A negro woman named Williams was also constantly with both cases, and on the 20th she was taken with the same disease at her house, about two hundred yards distant, and died the next day. After a few days' time the husband of the last case was attacked and died, and subsequently two other cases occurred in the same house.

A negro woman living in a small room had three children aged respectively three, five, and seven years. These children were attacked with cholera at varying intervals. The mother, destitute of that instinct which causes even the brute to care for its offspring, grossly neglected her children. Sarah Ledbetter, a colored woman who lived in an adjoining room, but who was in no wise connected with these children, seeing them neglected by their mother, with a courage, devotion, and self-sacrifice which ought to constitute her a heroine, gave up her employment and devoted her whole time, day and night, to caring for these neglected little ones. Two of the children died; one recovered. Within a few days after the termination of the last case Sarah was herself attacked, and after a severe and well-nigh fatal illness recovered.

Believing that the cholera-germ was contained in the dejections of the patients, I was particularly careful to direct the nurses to promptly remove and bury them.

The disease was attended with all the symptoms which characterize Asiatic cholera: the vomiting and purging, the rice-water discharges, spasm of the muscles, collapse, suppression of urine, husky voice, and pinched features were well marked, and left no room to doubt the nature of the disease. There were 142 cases of cholera, with 53 deaths, showing a mortality of more than one-third. Of the total number of cases, 30 were whites and 112 were blacks.

The treatment which gave the most satisfactory results was absolute rest, light diet, morphine, calomel, and quinine, with counter-irritation by blisters, and the maintaining the temperature of the body by artificial heat. I insisted very strongly upon every one who complained of any gastric or intestinal disturbance taking their beds and quietly remaining here until relieved; and I feel satisfied that some recovered from the disease by strictly observing this injunction, while others lost their lives by disregarding it. As an instance, I cite the following case: I was called early one morning to see a little girl with cholera. It was a violent attack, and the entire family were greatly excited, but particularly the father, who busied himself in running to and fro upon every errand. He soon began to complain of diarrhœa and pains in his bowels. I told him that he must lie down and keep perfectly quiet, but he positively refused to leave his child. Finally he became so much prostrated that he was forced to take to his bed. He soon collapsed, and died in a few hours. That this man's death was hastened, if not produced, by his refusing to take his bed early in the attack I have no doubt.

At the inception of the disease I used the following formula:

R. Morphiæ sulph., gr. iv.
Hydrarg. chlor. mit., gr. iv.
Quiniæ sulph., gr. xvj.
M. et fiat pilulæ, No. vij.

One to be given every hour or two hours, as the urgency of the symptoms required.

When there was thirst or nausea, bits of ice were allowed to be swallowed; iced water was given in small quantities whenever desired. When the vomiting became excessive I used the ice freely. Put 20 grains of calomel upon the tongue, to be swallowed with a sup of ice-water; applied mustard over the stomach, and injected morphia hypodermically. During the stage of collapse I gave alcoholic stimulants, and endeavored to maintain or to raise the temperature of the body by dry heat. When convalescence began I gave my patients a bitter tonic, with iron, and ordered them a light but nutricious diet, still insisting upon rest and quietude.

A number of points in Rutherford County were infected after cholera became epidemic at Murfreesborough.

Dr. L. W. Knight, residing five miles south of Murfreesborough, reports the occurrence in his practice of ten cases of cholera, seven of which proved fatal. Of these cases five were males, five were females. Four were whites, six were negroes; seven were married, three were unmarried. The respective ages range from six to thirty-five years; four cases occurred in one family, three cases in another, and one case in three others. The treatment adopted was morphia, calomel, stimulants, sinapisms, and ice.

Dr. J. J. Rucker, residing five miles west of Murfreesborough, reports in his practice, from June 27 to July 19, twenty cases of cholera, but two of which were fatal. Of these cases twelve were males, eight were females; seven were whites, thirteen were blacks; eleven were married, nine were single. The ages range from three to forty years. In two instances two cases occurred in families, the other cases were isolated.

The treatment adopted was opiates, with calomel, and enemata of capsicum, nut-galls and quinine, sinapisms, absolute rest, ice.

Dr. R. I. Turner, residing five miles southwest of Murfreesborough, reports the occurrence of twenty cholera cases, of which five were fatal. Of these cases twelve were males, eight were females; eight were whites, twelve were blacks; eleven were married, eight were single, one was a widow. The ages range from eight months (a fatal case) to forty-nine years. Four cases occurred in one family, four in another, while duplicate cases occurred in several instances.

Dr. Thomas J. Elam, residing six miles southeast of Murfreesborough, reports five cases of cholera. These cases were all treated at the inception of the disease with opium, calomel, and quinine. Absolute rest. No deaths occurred.

Dr. G. D. Cronchwait, of Florence Station, reports five developed cases of cholera, one of which was fatal; and a large number of cases in which the disease did not advance beyond the premonitory stage. Treated by opium and calomel. "The stomach was emptied by a brisk emetic in cases in which it was loaded. Calomel seemed to produce more actual stimulation than any other remedy."

Dr. Joseph W. Davis, of Smyrna, reports five cases of cholera, two of which were fatal. Treated by calomel, quinine, morphia, and stimulants. "From his observation cholera prevails only as an epidemic, and it is not believed to be contagious or portable."

Dr. R. B. Haines, of Jefferson, reports nine cases of cholera, six of which were fatal; two cases in the persons of children, two and three years of age, both of whom died. One recovery was in the person of a man seventy years of age. The treatment adopted was calomel, opium, and quinine, in small doses.

WILSON COUNTY.

Lebanon, the county-town of Wilson County, is located in a fertile country, thirty miles due east of Nashville, with which city it is connected by railway. It is a town of some little importance; at it is located Cumberland University. The manufacturing interests are represented by large cotton and woolen mills.

The town is built upon an elevated limestone ridge, and around a large town spring, which empties into Sinking Creek. This creek, which rises in the hills four miles south of Lebanon, flows through the town and empties into Bartin's Creek, one mile below. During the summer months this creek is dry, but after heavy rains the current is rapid and the bed of the stream is thoroughly cleansed.

Two miles east of Lebanon is Spring Creek, and one mile west is Bartin's Creek. The country watered by Spring Creek is generally high and healthy, and free from malaria. The water is pure and clear and the stream never runs dry. The country watered by Bartin's Creek is liable to malarial diseases. The soil is black, soft, and porous. During the summer months Bartin's Creek is dry. During freshets it leaves large deposits of mud in its bed and on the low places along the banks.

The Big Spring, from which the town is supplied with water, rises at one corner of the public square, and gives off a stream of sufficient volume to wash thoroughly the bed through which its waters flow. It is shown that the natural drainage of the town is good. In 1849 Lebanon had been desolated by cholera; and in 1873, as soon as it was known that the disease was epidemic at Nashville, every effort was made to place the town in the very best sanitary condition.

On the 6th day of June, two young men named Wilkerson and Whitmore arrived at Lebanon from Nashville. On the 8th Wilkerson was attacked with cholera, and died the same day. On the 10th Whitmore fell sick with the same disease, and died upon the 12th.

July 17.—Three negro women who had been at Nashville were taken with cholera; two died within twenty-four hours, one made a tedious recovery.

July 18.—Seven cases of cholera occurred, three of which terminated fatally. The disease having become epidemic, spread rapidly over the town, confining itself to no particular locality. Every street and neighborhood had its few cases of cholera, and from the town the disease was carried into the country. Three miles from Lebanon, lower down Spring Creek, were two fatal cases. Four miles east of Lebanon, one case died. Four miles down the creek was another fatal case. There were no cases on Bartin's Creek, nor any on Sinking Creek, outside the limits of the town.

Nine-tenths of those who died, and the history of whose cases could be had, had been imprudent in eating vegetables, or had neglected cases of diarrhœa; frequently both. No case is known of a cholera death where the subject had been prudent in diet, and had taken treatment early. A few doses of astringent medicines, in incipient cholera, with absolute rest, in the cases of persons who had been prudent in diet, invariably gave prompt relief. Dr. J. L. Fifte, to whom we are indebted for this report, writes: "I gave quinine by the stomach, the bowel, and under the skin, and gave it freely, and in a great many cases; but I am sorry to say, contrary to my expectations, for I did believe it would *cure* cholera, it seemed to do but little if any good. Once I believed I could cure cholera by the hypodermic use of quinine; now I know I cannot. With the present lights before me, if it becomes my misfortune to deal with cholera again, I shall rely on small, but frequently repeated doses

of calomel and opium, with large and frequently repeated doses of i as a general treatment."

To Drs. S. M. Anderson and G. L. Robinson we are indebted for mu valuable information, received through our friend, Dr. Fifte.

Cholera appeared at the town of Lebanon on the 8th day of Ja 1873, and the epidemic influences remained in force until July 17.

Seventy-nine cases of cholera are reported as having occurred in t town of Lebanon; of these twenty-six died. Of the total cases, for five were males, thirty-four were females; thirty-six were among whit forty-three were blacks. Of the fatal cases, eleven occurred among t whites, fifteen among the blacks. Of the total cases, nineteen occurr among those whose ages were less than twenty years; eleven of the were less than ten years old. Of the cases which occurred betwe one and ten years of age, five died, six recovered. Of those betwe ten and twenty years of age, but one died.

September 27.—A negro man named Martin was attacked with chole and died after an illness of ten hours.

We are indebted to Dr. J. Bryant, of Shop Springs, for an outline the cholera demonstration at that village. Shop Springs is a little v lage on the Sparta turnpike some six miles southeast of Lebanon. is one mile from the line of Spring creek, a high, healthy, and no malarial neighborhood. To this village cholera was carried from Le anon. The first case occurring June 26, and the epidemic continu until July 3. Ten cases are reported, four of which terminated fatall With but a single exception the disease was confined to the white those who died were all whites. Two cases occurred in the persons infants; one two years, the other eighteen months old; both died. T two other deaths occurred in adult males, one of whom attempted arrest the premonitory diarrhœa by a whisky debauch. The other w attacked after neglecting a diarrhœa for some five days. Of the tot cases, but three occurred in the persons of females. Dr. Bryant treat the cases under his care with calomel and opium, in alterative doses.

Montgomery County.

Clarksville is located upon the right bank of the Cumberland riv at the point of junction of the Red river, fifty miles northwest Nashville, and one hundred and ninety-nine miles northeast of Me phis. The town is located upon the Memphis division of the Louisvill Nashville and Great Southern Railroad, and in 1870 had a populati of about 2,500 inhabitants.

Clarksville is a clean, prosperous town, built upon a bluff, and is e ceedingly well drained. The water supply is obtained from cistern very few families use water from wells. Privies are upon the surfac This town is the center of a considerable tobacco trade.

On the 23d of June, two negroes employed upon the railroad, can into the town. They were guilty of great indiscretion in eating and drin ing, and the same night were both attacked with cholera. One of the men recovered after an illness of eight days, the other died upon t third day after his attack. It is supposed that these men had been points along the line of the railroad that were infected with the disea These cases were followed by the occurrence of six other cases, whic are dated from the 28th of June to the 14th of July. Four occurred i the persons of negroes, two among the whites; four were females, tw were males. In but two instances did two deaths occur in the sam family. One a father aged twenty-eight years and his female child twel

months. The other a negro woman aged fifty-eight years, and her daughter aged twenty-three years. Those first noted lived on the highest portion of the city, and used cistern-water; the occupation of the man was that of a bar-keeper; those last noted were both laundresses by occupation, lived upon low ground, and used spring-water.

PALMYRA.

We are indebted to Drs. A. Eldridge and J. F. Outtaw for the following outline of the epidemic as it occurred at Palmyra, Montgomery County.

Palmyra is a small town situated on the south bank of the Cumberland river, and directly upon the Louisville and Memphis Railroad. The town is surrounded by large hills divided by narrow bottom-lands leading from the river. These bottoms are subject to frequent overflows. Previous to the appearance of cholera in 1873, there had been an unusual high rise of the river after vegetation had advanced, which caused the decay of a great deal of organic matter. The water in domestic use is strongly impregnated with lime, and is as a general thing obtained from springs.

The first case that Dr. Eldridge was called to see did not prove as severe as those that followed. The epidemic commenced at a house that was nearest the bottom that had been inundated, and was about three hundred yards from the river. The disease seemed to follow that side of the street, house by house—one at a time—until it reached the river. These cases were the most severe. All the deaths that occurred were on that side of the street, and so far as could be observed there was not a single case of cholera, except those who contracted the disease in this locality. There were several cases in the country, but they had been in this immediate locality just previous to their being taken with the disease. After about ten days or two weeks the town was deserted, and there were no new cases, though we had strong symptoms of cholera all over the neighborhood for several weeks.

Dr. Eldridge is of opinion that there was a local cause for the disease.

The Cumberland river is navigable, and during the season many of the boats upon the stream were infected with cholera. Palymra is twelve miles southwest of Clarksville and sixteen miles northeast of Erin. The epidemic is reported as commencing at Palymra on the 8th of June, and, therefore, was prior to the outbreaks at Clarksville and Erin.

MARSHALL COUNTY.

The village of Farmington is located in the eastern portion of the county of Marshall, fifty miles south of Nashville, and fifteen miles west of Shelbyville, Bedford County; with the last named the village is in daily communication.

It is represented by Dr. Nowlin that Farmington is located in the center of the great geological basin of Middle Tennessee; that the section of country is decidedly malarial. That all diseases of 1873 were of a malarial type, and opened the way to cholera. That an epidemic of dysentery followed that of cholera. That in the winter of 1873–'74 there was a marked epidemic of typhoid fever. After the outbreak of cholera the malarial diseases subsided, and that, with the exception of dysentery, the year 1874 was the healthiest season known for many years.

The history of the cholera outbreak at Farmington is, however, as

follows: On the 17th of June, a young man named Scott Carpen arrived at Farmington after a visit to the Exposition at Nashville. C penter was accompanied by a friend from Nashville, and when th arrived both were suffering from diarrhœa. This friend remained Shelbyville, where in a few days he died of cholera.

June 18, Carpenter was taken with cholera at Farmington. H attack although violent was not fatal, and after an illness of eight da he was pronounced to be convalescent. Four days from that time oth cases of the disease made their appearance, and before the epidem subsided sixty cases occurred, many of which proved fatal.

It is claimed by some of the physicians of Farmington that the d ease was of local origin, and that Scott Carpenter could not have be the means of introducing it, from the fact that only those persons w drank water from a certain well in the village had the disease. Fa lies who obtained all their water from this well, suffered in nearly their members; where only certain members of a family drank of they alone were affected. "The sick-bed of Scott Carpenter was ju *forty steps* from this well."—(Extract from letter of Dr. Nowlin, Aug 19, 1874.)

We have failed to elicit any information on the subject of disinf tion, but as by the principal physicians of the town the disease is n considered *contagious*, it is safe to presume that disinfectants were n used; and that this well was infected from the excreta of Scott Carp ter, although the assertion is made that this did not occur. If the sic bed of this young man was but *forty steps* from the well, the ground the privy where his excreta were thrown must have been within t area of drainage of this well, and it is certainly more plausible to su pose that, in the natural course of events, the water became infect than it is that a special providence existed for that well, which pr vented any of the excreta from reaching the water.

In two localities beyond the town did the disease occur. Farmingt is located upon the banks of Rock creek, and upon what is known the Horseshoe Bend. Upon this creek, one-quarter of a mile from tow lives a family named Coffey, four in number, three of whom had ch era. This family were certainly within the area of infection; they we so close to town that undoubtedly it was resorted to for domestic pu poses; and persons going to or from the town of necessity passed the house.

Half a mile from the town, down the creek, lived a family of negro named Mayfield, seven of whom had the disease, with three deaths. is hard work to establish the fact that a family of negroes remain constantly at home, in the mind of any one familiar with the southe negro. They are utterly unaccountable for their actions, and after ran ing over a country side all night, visiting friends, &c., will invariab insist that they had not been away from home. This Mayfield famil were certainly near enough to visit Farmington many times each da and it is far more rational to suppose they did so than that they a stained for weeks from going to the town.

It is asserted that the floods of the early spring of 1873 filled th springs, from which these two families obtained their drinking-wate with vegetable matter; and because two families who lived betwee Mayfield's and the town did not have the disease, *ergo*, the water of th spring infected the Mayfield family.

Two other individuals living in the country had the disease, whic lasted from June 18 to August 5, but they both confessed to have bee in the town.

HAMILTON COUNTY.

Chattanooga, the county-seat of Hamilton County, is a city of 6,000 inhabitants, located in the valley and upon the east bank of the Tennessee river. The valley in which this town is built is bounded upon the north and west by the Tennessee river, on the south by Lookout Mountain, and upon the east by a range of high hills.

Chattanooga is a railroad center, being the eastern terminus of the Saint Louis, Nashville and Chattanooga Railroad; the southern terminus of the East Tennessee, Virginia and Georgia Railroad, the northern terminus of the Alabama Central, and the western of the Western and Atlantic Railroads.

The city is divided (as is shown upon the accompanying map) into five wards. The first four are supplied with water from the Tennessee River, which water presents no peculiarities. The water-supply of the Fifth ward is obtained from surface-wells and cisterns. This water is strongly impregnated with carbonate of lime. At the foot of the hills around the city many springs are found, yielding water of the same character.

The drainage of the city is very imperfect, although not more so than the majority of southern towns; the only measures that have been provided are upon the surface. The privies consist of pits dug into the red or yellow clay, or they are upon the surface of the ground.

The sanitary condition of the city at the time of the outbreak of cholera was not more imperfect than it usually was at the same seasons of former years; an apathy as regards the possible introduction of the disease possessed the majority of the residents of the town, and but few precautionary measures were adopted. Even after the arrival of the first case from Nashville, and after the earlier cases among the residents of the city had occurred, few efforts were made to stay the disease. The dejections of the cholera-sick were thrown out upon the ground, and upon or into masses of *débris*.

Under the supervision of Health Officer Van Deman, a thorough system of disinfection was adopted. We present in full the report of this gentleman, and, in addition, a most interesting paper, from the pen of Dr. E. M. Wight, of Chattanooga.

CHOLERA IN CHATTANOOGA, TENN., DURING THE SUMMER OF 1873

By J. H. VAN DEMAN, M. D., *late Health Officer of Chattanooga.*

During the latter part of May, 1873, the cholera first appeared in Nashville, Tenn., and raged there with great violence until about the first of July, when its decline commenced, and a few days more numbered it among the things that were in that city. Previous to its disappearance there the first case was noted in Chattanooga, Tenn., one hundred and fifty-one miles south of Nashville, and it was that of a brakeman running upon the Nashville and Chattanooga Railroad. Before leaving Nashville he had frequent attacks of diarrhœa, and the *very day of his departure* was seized with that peculiar painless diarrhœa; he, however, came on his train to this point, was taken with vomiting and purging, rice-water discharges, in fine, with all the symptoms of cholera well defined. Collapse set in, and in a very few hours he was ready for his coffin.

Several other cases of a similar nature appeared within the next twenty-four or forty-eight hours, and all among the employés of that road, or the Alabama or Chattanooga Railroad, every patient either having left Nashville, Tenn., or Birmingham, Ala., where the disease was then

raging, with cholera symptoms, or had been exposed to the infecti
while there. Our next case was a Mrs. Richards, the proprietress of
boarding-house, where most of the railroad employés connected wi
these different railroads were in the habit of stopping when in the ci
This patient had a well-marked attack of cholera, and the violence
the same was so great that she lived but a few hours. From these ca
it spread rapidly, first among the railroad men, then in the immedi
neighborhood of their boarding-house, and very soon we discovered t
disease, well discernible all over the city, being felt slightly upon t
hilly parts of the city, but very severely in the lower, flat, and mars
regions. Indeed, I might say, without fear of contradiction, that ni
tenths of all persons here who were attacked with cholera either liv
in these marshy and low grounds, or else transacted business there d
ing the day, and came home at night only to procure their natural re
and the most fatal of all these cases enumerated was in the limesto
formations, where it cropped out close to the surface. The disease a
"laid in wait," so to speak, for our poverty-striken, the destitute, wh
squalor, filth, and dissipation did most abound, though a few of our ve
best citizens succumbed to the scourge.

The first case of cholera that appeared in this city was upon the 2
of June, 1873, and rapidly spreading over the different wards, until Ju
4, when it apparently had reached its acme, then gradually subsidi
until July 16, when it disappeared for about one month, and then,
turning for a few days, more fatal in its nature, left the city, may
hope, never to return.

Our mortality for the first few days was greater among the wh
than the colored population; males more than females, and adults m
than children; but soon it changed its base, and the poor ignorant
groes suffered terribly, probably owing to their diet, their peculi
habits of cooking, their filth and utter disregard of cleanliness, (a
class,) &c.

In proportion to those attacked, the mortality was about one in fi
and while the population of our city, at the outbreak of the disea
was supposed to be about twelve thousand inhabitants, now, during
visitation, we lost, *from all causes*, about one in seventy; by cholera alo
one in every two hundred; and when we consider that our whole nu
ber of deaths from all sources, *during the same period of time* in 18
was only forty-three, while this year it footed up one hundred and s
enty, this difference then being justly charged to "cholera accoun
we see our death-rate becomes a fraction over one in every one hundr
of our entire population. During the progress of the epidemic, abo
two thousand of our population left the city for what they suppos
were more healthy locations; but of that number who "refugeed," sev
teen died from that which was reported to us as cholera, showing th
they must have had the germs of the disease in their system when th
left, and that their mortality was at least as great, if not greater, th
those who remained at home among their friends and nurses, took ca
of their persons, lived carefully, washed cleanly, ate sparingly, and we
governed by the advice of their physicians, whose services could
procured when needed.

We have heretofore stated that the mortality was greater among t
inhabitants of the lower and marshy portions of the city; and when
state that fully one-half of our people live upon the hills, and that on
five deaths are reported from among them, and all the rest are desi
nated as having lived in the low lands of the city, the statement becom
still more apparent.

Again, an indiscriminate use of vegetables during its visitation here paved the way very plainly for its attack, the free use of them and fruits being almost equivalent to certain death; while those who abstained from their use entirely either were not attacked at all, or, if they were, recovered with but little medication. During the epidemic our local authorities prohibited their *sale*, and *recommended* that no one should even use them, and this being seconded by the entire medical faculty, their order and recommendation were very generally observed. In proof of this statement, we would cite the following facts: On the last days of June the daily death-rates dropped down to a point where we were consoling ourselves that the pestilence was about to leave us. By some means the fruit and vegetable gardeners found out that the sales of their products were to be stopped, and at once they almost gave them away; the effects of which were seen immediately by the mortality reaching its acme upon the 4th of July—being directly attributable to the free use of their vegetables and fruits. Second. On the 16th of July the last case of cholera was seen in the city, and on the 20th the embargo on fruits and vegetables was raised. About the 1st of August, 1873, cholera again re-appeared and raged with *great severity* (within very narrow limits) for a few days. This attack could be traced directly to the intemperate use of unsound water-melons and fruits, occurring as it did almost exclusively among the negroes and a miserable class of whites, but little superior to the negro. And this last attack of cholera did not cease until the embargo was again laid upon all fruits and vegetables, when it promptly yielded.

During the past two years, as health-officer of this city, I have kept a complete record of all deaths that have occurred, with the cause of the same; and during this epidemic an official copy of said record of the day before was published by our daily press, which, being published every morning, did much to quiet the excited public, calming the fear of the timid, nerving the hopeful, and at once "bringing to grief" those old croakers who are always ready and more than willing to magnify statements to the injury and detriment of not only the public, but also of their infinitesimal narrow-minded souls.

Nearly every town between Nashville and this place suffered more or less from cholera during its visitation to the former place, except Stevenson, Ala., (where no one sick was allowed to be put off the train,) and, fortunately for them all, it subsided there simultaneously with its decline at Nashville, spending its whole force upon *our city* after its disappearance there—the same existing in all the towns south of us, the cholera disappearing *with them* at the same time as it did with us.

In Nashville, during its prevalence there among the soldiers on duty, is an item of note. Upon its introduction into that city, Dr. D. G. Caldwell, the surgeon in charge, advised the removal of the troops to some high point, far distant from the city, which was accordingly done; and having pitched their camp some eleven miles distant on a beautiful grassy knoll, near splendid waters, and considerably elevated above the surrounding country, he proceeded to quarantine them there, endeavoring to protect them from all outsiders; and strict guards being set, no one was allowed to return *to* the city, and if from any cause whatsoever the order was disobeyed, the one violating it was not allowed to return to camp. Strict sanitary rules and regulations were laid down and enforced, and the result was just what we would foresee; that not a single case of cholera appeared from that day in the camp, while of the few who remained in garrison at Nashville, most of them were attacked, and some of them with fatal results.

In regard to the sanitary condition of this city at the *onset* of t scourge, I have but little to say; but *then* our local authorities aroun themselves and took very active measures to have every place put the very best sanitary condition possible. Human excrementitio matter was either at once buried or disinfected. Local cleansing, a the disinfection of most every part of the city was resorted to and forced by especial sanitary police; lime, carbolic acid, sulphate of iro (commercial,) &c., &c., were freely used; and to their especial use, a the untiring energies of our mayor and a few of our council who mained in the city, unawed by the danger everywhere around the to them and the entire medical faculty, their aid and instruction fre given at all hours, and the truth *published every morning* of the mortali the day before, we owe the rapid decline of the disease in this city.

From Chattanooga it spread along the line of our railroads, provi fatal in about the same proportion of cases as here (except in the towns where trains were not allowed to stop, and in such places no o was attacked.) Knoxville, Jonesborough, and Greeneville, in East Te nessee, suffered more or less from the pestilence, and in proportion their sanitary condition, so their mortality-record shows. In the latt place the mortality was fearful; at least one-half of the citizens the having contracted the disease, and their ratio of deaths about the sa as in other places—fully one in every five, and all owing to the wretched sanitary condition; a large spring, from which most of h citizens drew their supply of water, having been contaminated by p sonous matter being thrown upon the hills contiguous thereto, whi after the first shower destroyed the purity of its flow.

In Birmingham, Ala., at a height of 650 feet above the level of t sea, with a clear, compact, and yellow clay soil, underlaid in some plac with shales of limestone, the mortality was the most fearful of any o city in the South. The first case appeared there about the 1st of Jun 1873, shortly after its appearance in Nashville, and being upon the li of the North and South Railroad, one of the links of the great southe chain leading from Louisville through Nashville to the South, the cau of the disease, or rather the locality from whence it came, was perfect clear. Here, its course was very singular; from the date mentione only one case appearing every five days until the 21st of June, then o every day for seven days, and from three to ten every day for the ne fourteen days, when it suddenly disappeared, at about the same time its subsidence in Chattanooga; and while it did not seem to be so ve contagious then, it was plain to be seen that it culled its victims fro the low and filthy portions of the place, where poverty and squal wretchedness prevailed, and where the free use of limestone-water w indulged in by the people; and while the moderate use of vegetabl did not seem detrimental, still it was noted that those who used the indiscriminately suffered most when attacked. The mortality was he as is usual in other places in the South, greater among the color citizens than the whites; among males than females; among adul than children; greater where sanitary rules were disobeyed than amo those who adhered to them strictly. The whole number of deaths fro all causes in this city was, from June 1 to July 18, (from its outset to i subsidence,) one hundred and seventy-five, while cholera claimed o hundred and thirty of that number, and this, too, in a population of le than four thousand inhabitants, when all were at home; but as all b five or six hundred had left the place for more healthy climes, the mo tality is fearful to contemplate.

From these facts thus briefly set forth as to cholera, a few inferenc

may advantageously be drawn: That a strict quarantine should be observed between every city and place where cholera is known to exist, allowing no trains of passengers to land, nor the removal of any clothing from the infected district to other places. That a strict observance of well-established sanitary rules and regulations should be had in every town and city, and, "cleanliness being next to godliness," should be enforced; pure water only should be used—spring, river, or cistern—in preference to limestone-water.

OBSERVATIONS ON THE CHOLERA EPIDEMIC AT CHATTANOOGA, TENN., IN THE SUMMER OF 1873.

By DR. E. M. WIGHT.

Through Supervising Surgeon United States Marine-Hospital Service.

* * * * * * *

The rain-fall in the early part of the growing season of 1873 was very great, extending through March, April, May, and the first days of June. The season was like that of 1867, excepting that the rain was distributed through a somewhat longer period of time, and the river-rise in March, although it covered some of the lower parts of the town, was less by nearly 20 feet than that of 1867. Vegetation in June of both these years was very luxuriant; in 1873 it was remarkably so. The rains ceased about the 10th of June, and from that time until after the cholera-epidemic was over, there was very little rain. A gentle wind from the southwest prevailed during most of the time.

Nashville, where cholera had prevailed for a month previous to its appearance in Chattanooga, is northwest from this place one hundred and fifty-one miles by rail.

On the very day when it first made its appearance here, June 20, seventy-eight deaths occurred from it in that city. On that day two men were attacked in Chattanooga, both having come from Nashville a day or two before. One of these died on the 22d. Three deaths from cholera occurred on the 23d, and from one to ten died from this cause every day after, excepting three, until the 15th of July following.

After the cholera had taken possession of our town, but few more cases occurred at Nashville or along the line of the Nashville and Chattanooga Railroad. It seems to have been traveling, and to have moved its forces as it went, leaving only its dead and wounded upon the battle-field at its departure.

Nearly all the small towns on the railroad-route from Nashville to this city suffered from its visitation, between the 15th and 30th of June, and thus far I have not been able to find an account of a single case occurring this side of Nashville prior to the 20th, excepting within a few miles of that city.

All cases occurring on the line of the Nashville and Chattanooga Railroad had a traceable connection with Nashville or some other cholera-cases, so far as I can learn.

Here, our first twelve cases of authentic and trustworthy diagnosis had direct connection with Nashville, either by a visit to that city a day or two previous to the attack, or by daily association with the employés of the Nashville and Chattanooga Railroad Company, and all the cases which occurred up to the 1st of July could be traced to contact with

some other cholera-cases or locality. After that time we were s
so effectually by the "cholera-grip" that cases began to take pla
their own account, so to speak, and so continued up to the 15th of
which was the commencement of the intermission, which lasted
the opening of the water-melon trade, on the 1st of August.

Our worst day was July 3, on which nineteen deaths occurred,
being five from cholera five from *cholera morbus*, four from unk
causes, one from *cholera infantum*, one from marasmus, one from
gestion of the liver, one from *general* debility, (whatever that is,
one from diarrhœa.

The greatest number of cholera-deaths occurred on the 7th,
there were ten reported, there being but eleven deaths in all—(th
being from dysentery.)

It is a fact to be noted here, that during the days when cholera
worst here, it was taking its departure from Nashville, or had alr
taken it.

The whole number of deaths reported at the office of the city p
cian, from the 20th of June to the 20th of July, which, for the sa
comparison, although cholera ceased on the 14th, is made to cove
month of the year 1873, was one hundred and seventy-three, six
which were recorded as having died of cholera.

The whole number of deaths reported at the same office for the
period of time in the year 1872, was but forty-three, the increas
the number of deaths (with an increase in the population of about
twelfth) being one hundred and thirty; more than four times as m
dying this year than the year previous in the same time. Calcula
from all causes, after deducting from the whole number of death
sixty reported as cholera, the number will still remain three time
great as that of last year.

The number reported as cholera should have been much large
false reports were often made by irregular practitioners, and se
were unlawfully buried outside the city, of whom no report was m
but for the sake of facts, the official report is taken as it was mad
the time.

Aside from this cholera month, however, the number of deaths du
the warm months of this year were less than those of the previous y
one of these months affording but few more than half as many de
as the same month the year before; so this increase of deaths could
be from its being a sickly year, aside from cholera and its influence

The whole increase of deaths for that month—the difference betw
forty-three and one hundred and seventy-three—may be justly cha
to the account of cholera, there being sixty killed by it directly
seventy indirectly.

Our population being twelve thousand, we lost from all causes du
that month one from every seventy of our whole people. By cho
the loss was one from every two hundred. Charging the increase
the loss of the previous year to the cholera account, the deaths bec
a fraction more than one from every one hundred.

Of the sixty deaths from cholera, twenty-five were white people
thirty-five were colored. The mortality among the blacks was five ti
as great, in relation to their number, as among the whites.

In the commencement of the epidemic, however, cholera was c
fined almost entirely to white people. Of the first eleven deaths,
were whites, and the other was more white than black, a mulatto,
all but one of these eleven *had been exposed to cholera* by direct cont
with persons infected, or with those who were daily exposed to s

ontact. As before stated, the first two had been in the city of Nashville ut a few hours previous to their attack. Three more who died from his first eleven were daily associated—sleeping and eating in the same house—with men who visited Nashville every other day, in the performance of their duties as employés on the Nashville and Chattanooga Railroad.

Fully three-fourths of all the deaths were from that class accustomed to hard labor and poor living.

The disease was confined almost entirely to the low parts of the town. One-half of our people live upon the hills, and from this half there were but five deaths, the other forty-five occurring in the lower flats and valleys. This is partly accounted for by the fact that the poorer classes live mainly in the lower flats of the city, and their habits of life are such as to invite the attack; while the class of well-to-do people, who dwell upon the heights, exercised more discretion as to their diet, and lived in a more comfortable manner generally.

While the alarm was at its height, about fifteen hundred people left the city, as reported by the sanitary police. Some were able to emigrate in good order, having means and conveniences for comfort, while others went, actuated solely by fear, and looking only to escape the danger which they thought so imminent. Of the fifteen hundred who "refugeed," seventeen died in the country from what has been reported as cholera, and about half as many more died from other causes. Twice as many deaths from cholera, in proportion to their number, occurred among those of our people who fled to escape it, as among those who remained comfortably at home. This alarming and unusual mortality among those who left home was due, in a great measure, to their improper diet after leaving the town; their lack of medical attention; their improper and indiscriminate use of "anti-cholera mixture," "cholera cure," "sure preventives," and all the laudanum and camphor they could carry; and the development of the cholera, which they certainly must have had about them, and carried with them, by undue and ill-timed exposure, and change of food and water.

It was observed that during all this time of the stay of epidemic cholera, there was a "cholera feeling" existing among all classes of the community. It was not a matter of fancy in all cases, for many of the most sensible and least fanciful men and women felt its influence for days. There was certainly something in the condition of the atmosphere decidedly oppressive and prostrating. This is further shown by the deaths occurring at the time, in so greatly increased numbers, from diseases other than cholera.

Regarding the contagiousness of cholera as an undecided question, the manner of its working here becomes very puzzling and incomprehensible. Certainly those who were employed to nurse the sick and care for the bodies of the dead were very frequently attacked. Those who were attacked with the disease were almost invariably persons who had associated with cholera patients. Three of our physicians were at one time sick with it, and one came near losing his life.

At the house of a poor widow in the Fourth ward a little boy, six years of age, lay sick with pneumonia following measles. The family was visited on the night of the 21st of June by two men who left Nashville that morning, one of whom then had choleraic diarrhœa and afterward died. There was no cholera at that time anywhere in that neighborhood, and but two or three cases in the city; yet on the 23d, two days after, that little boy was in the collapse of cholera. Four days

after, two other children of the same family were attacked, and s after the mother. Both the children died.

A family living within about 50 feet of these people, who assis n nursing them, were attacked two days after, and both man and died. This last-named family was nursed part of the time by a colo woman who lived in another part of the city, where there had bee cholera, and who was attacked the day after she returned home, died in a few hours. The next day a black man was taken sick in same house, and died in a few days of cholera.

The boy who drove the dead-wagon that carried the pauper dea the cemetery, after bearing company with more than thirty dead f cholera to their place of final rest, himself took the disease, and was bu with those whose coffins had been his seat.

From ten men employed to bury the dead, five were attacked, three died.

A colored woman employed by the Board of Health to care for children whose mother had died of cholera, instead of destroying infected bed-clothing as directed to do, thought best to save a port and the bedding was saved and well washed, but the washer-wo was dead before the clothing was dry.

A poor travelling stranger came to the city, and, late at night, t lodging in an unoccupied cabin, recently vacated by deaths from chol The stranger was found dead in the cabin the next day.

These facts seem to me to indicate that our cholera was contagi communicable by contact alone, without any other assisting circ stances. It seemed, too, to be more than contagious, for it had po to go wherever it was invited. It was so tenacious in its grasp, and its victims so well prepared for its visit, that it was only necessar violate a simple law, or disregard a sanitary rule, to be in danger of terrible chastisement of this skeleton demon.

This completes, briefly, an account of my observations during the f visit of the scourge.

The return, which took place two weeks after the first abateme was a matter of entirely another sort, and the statements here m would not apply to these later cases in many particulars. It did return as an epidemic, nor did I know of any cases occurring dur August, the time of the second visitation, except invited by some gr indiscretion, mainly the ingestion of fruits and vegetables, the excess use of alcoholic liquors, and riotous living.

There were fourteen deaths during the second visitation, all occurri during the first half of August.

James County.

Ooltewah is a post-village of James County, of about one hundred a fifty inhabitants, located upon the line of the East Tennessee, Virgin and Georgia Railroad, fifteen miles northeast from Chattanooga. T village is located upon rolling table-land, at the foot of a range of hi hills. The water-supply is good, obtained from wells, and is limesto in character. The privies are upon the surface of the ground; otherwi the town is in good sanitary condition.

Dr. T. H. Roddy reports that the first cases of cholera that occurr at Ooltewah, in 1873, were among families who had fled from Chattano after the disease became epidemic at that city. The first case occurr July 10; the disease came on after a painless diarrhœa of a few da was well-defined in its characteristics, but the patient recovered after illness of eight days.

July 18, a man arrived from Chattanooga, with a diarrhœa from which he had been troubled from four to six days. After his arrival at Ooltewah, he went upon a drunken spree; the next day his diarrhœa had increased in severity, and the drinking was continued; the next day, July 20, cholera was developed, and he died after an illness of ten hours.

July 21, a white female from Chattanooga was taken with cholera, and died after fifty-two hours.

July 31, a white female, also from Chattanooga, was taken with a diarrhœa, which continued for five days. She was exceedingly imprudent as to her diet, eating water-melons and cucumbers. August 4, she was taken with cholera, and died after an illness of twenty hours.

Thirteen cases of fully-defined cholera, with six deaths, are reported. Of these cases, seven occurred in the persons of males, six in females; all were whites. Three of the fatal cases were attendants, or lived in the houses at which the deaths of the individuals who had contracted the disease at Chattanooga had died of cholera. All the cases exhibited a painless diarrhœa, which was neglected until violent and urgent symptoms occurred. In addition to these cases of developed cholera, Dr. Roddy reports a number of cases of choleraic diarrhœa, which were characterized by large, watery evacuations, which were attended with prostration and with relaxation of the sphincter ani. This condition occurred especially among the attendants of the cholera sick. All cases that submitted to treatment and regimen during the stage of painless diarrhœa recovered. The treatment consisted of calomel, camphor, and hypodermic injections of morphia and quinine.

GREENE COUNTY.

Greeneville, the county town of Greene County, is located upon the East Tennessee and Virginia Railroad. The town has about one thousand inhabitants.

We have been unable to obtain from the profession of Greeneville a detailed statement as to the epidemic of cholera at that point. The following, however, are the main facts:

About the 20th of June a Dr. Mallony, residing at Greeneville, returned from a visit to the city of Nashville, cholera being at the time epidemic at the last-named point. After his return Dr. Mallony was attacked with cholera, but recovered. The next person attacked was one Piper, a near neighbor of Dr. Mallony. This case terminated fatally, and the body was carried some ten miles into the country for burial. A Mr. Stevens attended the funeral, contracted the disease, and died. One Miller was present when Stevens was taken with the disease; Miller went for the physician, and then returned to his home, some four or five miles distant, where he also was taken with cholera, but recovered after a tedious illness.

No other case occurred at the residence of Mr. Stevens, but several occurred in the vicinity of Miller's house. From these cases the disease spread and became epidemic.

We present the following paper:

THE CHOLERA OF 1873 AT GREENEVILLE, TENN., INCLUDI TOPOGRAPHY AND SANITARY CONDITION OF THE TOW

By A. B. Tadlock, A. M., M. D., *Health Officer, Knoxville.*

On the 24th of June, 1873, William Rule, then mayor of Knoxvi Tenn., received a telegram from H. H. Ingersoll, esq., of Greeneville, follows:

"To Hon. William Rule, *Mayor, &c.*

"One of our physicians is sick and the other exhausted. Can send two immediately? Answer.

"W. H. H. INGERSOLL,
"*For the Citizens.*

Mayor Rule, on receipt of this telegram, hastened to solicit my goi and desired me to choose another physician to accompany me. As next train left for Greeneville within less than an hour, I had no ti to consider, and but little for arranging my affairs, but consented to and named four or five physicians from among whom he could sele however, none of them were found able or willing to leave that d and I went alone.

Arriving at Greeneville at about 4 o'clock p. m., I at once commen visiting patients with the resident physician, Dr. Smith. We first w to the house of Mr. F. Mitchell, which was a two-story frame, la and commodious, situated on high, rolling ground, with the best of s itary surroundings; nothing objectionable could be seen. One ch six or eight years of age, had died that day; another was violently and died a few hours afterward, when the third (Ruth) was also tak violently. Of this one I had exclusive charge, studying every feat of the case, and watching it with extreme anxiety night and day, a ually serving in the capacity of nurse, sitting by the pallet on wh the dying child lay, and sometimes, worn-out and overcome, reclini on the bed on which the other two had died. I mention this to sh how much I was exposed, and yet escaped an attack of the disease, which I may have occasion to refer to hereafter.

All of the family were affected, more or less, but only one other (w the exception of a young man visiting the family) had what could called cholera. I must not neglect to state that I had the benefit consultations with Dr. Boyles, Dr. W. R. Sevier of Jonesborough, a Dr. Frank A. Ramsey of Knoxville, all most reputable and emine physicians.

In the treatment of little Ruth, who died of uremic fever eigh eight hours after her attack, the remedies used were at first, in t main, tinct. ergot and chlo. potass. Afterward, in consulting with D Boyles, it was agreed to administer a large dose of calomel; subseque remedies were varied according to symptoms and circumstances.

In answer to a letter of inquiry, I received the following from t father of little Ruth, which will be of interest here:

"Greeneville, Tenn.,
"*August* 19, 1874

"Dear Sir: Yours of the 17th received and contents noted. O daughter Ruth, that you attended, was two and a half years old. W use cistern-water, (acknowledged to be the best in town.) It is fr

orty to fifty yards from the privy; the privy is down the hill from the istern, at least 25 or 30 feet below the level. It had been cleaned out ate in the winter, and had no rain let in it since the 1st of April. I am atisfied in my own mind that the first case of cholera that appeared here was that of young Mallony. He returned from Nashville on Sunday, and on the Tuesday following he took it at Godfrey's Hotel. Piper, the first case that died, lived down the hill from the hotel some hundred or so yards. Ivah, the last that took it, got well; her case was mild. She was six years old. Our children had used no vegetables or fruits for two weeks before they took sick. They had been fed on boiled milk, boiled middling, toasted light-bread, and rice. None of them had been within two hundred yards of any one that had the cholera.

"F. E. MITCHELL.

"Dr. A. B. TADLOCK, *Knoxville, Tenn.*"

I have given the report of this case and the family because of its importance for future reference.

Having finished our visit and consultations at Mr. M.'s, we, Dr. S. and myself, started for a ride of about three miles into the country and back. Our course was down the creek, which drains the town and suburbs and flows in a southerly direction. About three-quarters of a mile from town I saw case No. 2, just taken sick, which at Dr. S.'s request I prescribed for, and subsequently treated till recovery. Other members of the same family were affected more or less.

In reference to the topography and sanitary relations of the town, it will be seen that this case is significant, and will be noticed further on.

Riding about three miles farther down the creek I saw the third case, and thence across the country about a mile we struck another stream, which ran parallel with the one above mentioned, but had not its origin in the town. Here I saw cases four and five, daughters of a well-to-do farmer. These were the first cases occurring on this creek, and were entirely occasioned by the family having communication with diseased persons on the other creek; subsequently one or more cases occurred on this creek, supposed to have had the same origin.

We then returned to town, arriving between sundown and dark, and having visited several more patients with Dr. S., I took lodgings at the Godfrey House, (the hotel mentioned in Mitchell's letter.)

But few people as yet had left the town, though greatly alarmed at the fatality and constant spreading of the disease. The most of them yet disbelieved the character of the distemper; hence my opinion was sought with eagerness, and it being given in the affirmative, with advice for all to leave town that possibly could get away, caused a stampede the next day, which left the town almost deserted, and no doubt was the means of saving more lives than could have been preserved by any other means known. By thus fleeing the deadly pestilence, that seemed to lurk in every habitation, and contaminate the water, and every breath of air or morsel of food, there can be no question that scores of them escaped immediate death. Truly, the kind words of thanks and appreciation from the Ex-President of the United States and many citizens, assuring me that when the people returned my services should be recognized substantially and in a manner commensurate with the deed, would seem but natural and faithful expressions (expressed or understood) of a religious or civilized people. However, after the people returned, it took the magnates three months' deliberation to allow me the paltry sum of $100, and that in a warrant which after eighteen months I had to sue for, and enjoy a stay of eight months more. (Be-

sides furnishing medicines from my private case to fill prescriptio
had to pay my hotel bill and full railroad fare.) I have mentioned
not only as a warning to physicians having such calls to risk their li
but to add evidence of the low valuation by the people of professi
services and of sanitary preventive medicine.

I remained in Greeneville seven days and six nights, making (n
and day together) one hundred and one visits, and prescribing in
aggregate for over sixty patients. Only three or four cases occu
after I left. Five of my patients died, two of whom killed themsel
I am satisfied, by using too freely patent medicines, of which an a
dance disgraced the mantel-pieces of nearly every house; and I l
been informed that the very liberal fathers of the town council v
an appropriation to thus supply the poor, thus furnishing the de
warrant, and making each one his own executioner. Nothing be
however, could be expected.

The whole number of deaths from cholera at Greenville and vici
was estimated at forty.

The remedies I used I have furnished in detail on a separate sh
and it is not important here to mention it.

Topography.—Greeneville is located in Upper East Tennessee, a
36° 20′ north latitude, at an elevation of 1,580 feet above the lev
the sea; has a population of about 1,039, (United States census 18
and is the county-seat of Greene County. It is situated immediatel
the line of the East Tennessee and Virginia Railroad, about seventy
miles east of Knoxville. Silex, limestone, and clay are the predomi
ing elements of her earth foundation.

The town is built upon very hilly ground, and is surrounded on
south, east, and north by high detached hills, with gently rising gro
to the west.

The basin thus formed and occupied by the town receives, thro
the deeply furrowed ravines and hollows, the surface-drainage f
this extensive water-shed.

The water-supply is furnished by cisterns, wells, and springs. N
the center of the town is a very large spring, affording water for a l
stream, which flows southward, and, with the accession from numer
small springs along its banks, affords sufficient water-power for a gr
mill at the lower part of the town.

After the creek has passed between the two hills situated on the so
and east, it flows through valleys mostly made into meadow-land. T
this stream is the natural and only drain for the whole town. Its fo
tain-head, and the smaller springs along the banks, furnish water
spring-house facilities for a large portion of the inhabitants. Whet
these waters, leaping from the creviced rocks, having passed un
numerous cess-pools and sinks, are as pure as Castalia's fountains, I
afford to leave uncriticised. Entertaining the supposition that they
pure when first they sparkle in the sunlight and begin their dance d
the pebbly way, let us see how long that virgin purity is likely to
maintained, and examine if its purity is any longer an important
ment.

Spring and creek water contaminations.—Some of the above-mentio
ravines and hollows, which traverse the town in almost every directi
have been washed by the surface-drainage until large gutters or r
have been made, over which Cloacina (for convenience, rather than
a holy regard for the ocular and nasal functions of human kind) h
planted her modest temples. Again, she laid her foundations all al
the banks of the creek, irrespective of the close vicinity of springs

spring-houses below, in which butter, beets, cucumbers, melons, &c., are kept to cool; while her pit-less representatives, dotted all over the hills, added in wet weather each its quota of unclean rills, flowing down to the adjacent streams, which were visited by rats and other unclean animals, carrying with them into habitations filth and pestilence. In addition to this, the time having arrived when it was considered necessary to empty the vault at the court-house of its contents, which had not been done for a great many years, the authorities had this mass of putrefaction conveyed to one of the adjacent water-shed hill-sides and there deposited; this was done a short time before the cholera made its appearance, and many of the barrels in which it was transported were said to remain unemptied, exposed to the rain and hot summer sun.

The supposition was entertained by some that old cholera germs were thus exposed and developed into activity, and that this was the cause of "the prevailing epidemic," as the disease was here termed.

This is by no means my opinion, but that the disposition of such material in the heat of summer offered the most favorable opportunity for the elementary development of malarial disease, and furnished inviting nests for the incubation and rapid diffusion of either native or exotic disease-germs cannot be questioned.

Still more reprehensible was the frequent and uncivilized practice of some stores and residences being entirely unprovided with privy accommodations, in which case the fecal matter was deposited upon the surface of the ground—thus exposed to the elements and to the depredations of animals and insects. Is it any wonder, then, that the streams became contaminated, and the springs at high tide received an impure sediment which subsequently mixed with and poisoned the articles of daily food and drink?

Agencies of communication.—We have already seen what extraordinary facilities were here offered for the incubation, development, multiplication, and spreading of any contagious or infectious *materies morbi;* let us for a moment examine the very feasible means ready at hand for its successful application to the human system.

While other agencies were most effective in the general spread of the disorder at this place, we think it clearly shown by the course of attack that the creek conveyed and introduced *ab initio* the first fruits of the infection. The first fatal cases giving warning of the true type and malignancy of the distemper occurred in families living along the creek, even to the distance of four or five miles below the town. One whole family was swept away, and several others lost one, two, or three of their members. Besides using the infected water of their springs along the banks, as stated above, their domestic animals drank out of the creek, the women washed their clothing, and no doubt in some cases washed also the butter and vegetables, which, besides supplying their own tables, by barter partly supplied the town.

Case No. 2 belonged to a family that used water from a spring which rose on the edge of the creek in low meadow-ground. No. 3, a mild case, was located on this creek three miles below town; but Nos. 2, 3, 4 and 5, all were attacked several days after the greatest fatality of the same neighborhood, and after the whole town had become as it were a pest-house or hospital, and Nos. 2 and 3 seem to have been caused by a second installment of the infection from the town.

Having seen how numbers were poisoned from creeks and adjacent springs, the inquiry becomes pertinent, How was the disease communicated to the dwellers on high ground, (Mr. Mitchell and many others are examples,) who used cistern-water exclusively? The answer is easy

when we consider the instincts and habits of insects and domestic animals, and their acknowledged liability to disease.

The disposition of excrementitious matter has been shown to be fa able for the attack of these creatures. Thus the swine becomin fected and leaving their poisonous droppings upon the streets, wh being pulverized into impalpable powder, was inhaled. Rats and poisoned in the same manner would seek their hiding-places in ho and become a prey for cats, or in seeking to satiate their thirst w fall into cisterns and wells. Flies also contaminated whatever they touched, and poisoned the very air of the nursery. It has bee marked that these insects die during cholera epidemics, and such notably the fact in this instance, for they lay dead everywhere, and quently, in spite of fly-brushes, they dropped into various dishes or dining-table, until, when the disease had disappeared, scarcely a li representative remained.

It may be therefore easily understood why children whose clothi most frequently washed and changed, and who play about the h with the domestic animals, and those who, on account of poverty, poorly and go much from house to house, are more generally and fat attacked.

The history of this epidemic at Greeneville furnishes a sad comm on the neglect of sanitary laws, and shows the great need of Nati and State boards of health.

I will conclude by stating that though myself perceptibly affected the contagion, I attribute my comparative escape to my not drin any water or eating cold food, and to the avoidance as far as possib the inhaling of mephitic air.

KNOXVILLE, TENN., *January* 1, 1875.

HOUSTON COUNTY.

Erin, Houston County, Tennessee, is a village of some three hund inhabitants, located on the line of the Memphis division of the Lo ville and Nashville and Great Southern Railroad, as it passes thro the valley of Well's Creek. This valley is surrounded by a ch of hills, having a limestone base, which open on the west to ad Well's Creek and opens again on the east for its exit. Well's Cr empties into the Cumberland River six miles east of Erin. The T nessee River is distant sixteen miles to the south.

The village is located at the narrowest portion of the valley, wh at its eastern end is not more than thirty rods wide. The soil is and boggy, being constantly fed with springs which flow from the b of the hills. At the lower end of the village there was a slough ab one hundred yards long, lying parallel with the line of the railroad, over this slough was erected the railroad depot, a hotel, and a num of business houses, all clustered together along the platform of the pot—the rear of all these buildings resting on piles. These buildin have been erected within the past ten or twelve years, immediately o the ground formerly occupied by a saw-mill and tan-yard, the *débri* which has never been removed; and as this is the lowest point in valley, whenever there is a washing rain, or the creek overflows banks, the deposit of decaying animal and vegetable matter at this po is augmented; and as the privies of the town are all above ground considerable amount of the mixture is human excrement. The r us of most of the business houses are used as dwellings. The dw f the poorer classes are upon the low ground on the north of

railroad, while those of the better class are upon the surrounding hills. The water supply of this village is obtained from the creek, from the springs at the base of the hills, and from surface-wells.

The excessive rains of June, 1873, had washed into the slough already described excrementitious matter from privies, stables, and hog-pens, with all the *débris* on the surface of the ground. The slough under the majority of the houses was covered with a "green skim," and from it an intense odor was emitted.

On the 22d of June a man named Osburn, who was employed as a fireman upon the railroad, arrived at his home in Erin, in the immediate vicinity of this slough, sick with cholera, having been taken with the disease at Clarksville, twenty-six miles distant, and died after an illness of eighteen hours. The excreta in this case were not disinfected, but were planted in the "hot-bed" prepared for them.

June 23.—A Mrs. Dowdy and a negro named Daily, who had both been in contact with and who lived in the immediate vicinity of Osburn, were attacked with cholera, and both died, the first in twenty-four, the second in eight hours.

June 25 and 26.—Each had a fatal case of the disease.

June 28.—Six cases are reported, three of whom died.

During the month of July eight cases of cholera are reported, with five deaths; and from August 3 to the 16th, twenty-three cases of cholera occurred, ten of which died; a total of forty-two cases, with twenty-two deaths. Thirty-seven of these cases were whites, five were blacks; thirty were males, twelve were females. Four cases occurred in the persons of children between six and three years of age.

Four fatal cases of the disease occurred in the surrounding country, in each of which the infection was distinctly traced to the town. The majority of those who were able to do so left the town during the epidemic; of those who remained nearly all suffered more or less with diarrhœa.

At the time of the epidemic Erin was a center-point of the railroad trains, as both day and night trains met, and there was generally three or four sets of employés constantly at the town. From each freight-train, as it arrived, the caboose was uncoupled, and, with the train-hands as occupants, it stood upon a side-track until the schedule-time for again joining a train. The construction-train had its headquarters at this point, and many of the workmen upon it resided in the village.

The occurrence of the entire epidemic cannot be attributed to the arrival of Osburn sick with cholera on the 22d of June, although his was undoubtedly the initial case of the outbreak; for we find that on June 23, Thomas Fentress, a negro employed upon the construction-train, arrived at his home in Erin sick with cholera, and died within ten hours of his arrival. On July 30, Henry Johnson died of cholera a few hours after his removal from the same train; and on August 3, Bill Patrick also died, and his body was removed at Erin from the work or construction-train.

The symptoms presented by these cases differed in no way from those generally ascribed to the disease. In the cases of the four children, two of whom were members of the same family, there was, however, no premonitory diarrhœa. In each instance the child was awakened toward daylight with a diarrhœa, which from the first effort was copious and watery; the stage of collapse being reached rapidly.

It is reported by Dr. E. T. Lewis, of Erin, to whom we are indebted for much of the material of this statement, that while no case which became fully collapsed recovered, yet those who were attacked and who

applied for medical aid at the onset of the disease, and who care
carried out the directions received as to absolute and perfect rest,
almost invariably relieved.

The treatment from which the best results was obtained was cal
in full doses, combined with opium; the latter in grain doses, repe
every four or five hours.

Every effort was made to improve the sanitary condition of the t
Sulphate of iron and lime were used as disinfectants.

KNOX COUNTY.

CHOLERA AT KNOXVILLE, TENN., IN THE YEAR 187

BY F. K. BAILEY, M. D., *late Health-Officer.*

Knoxville, Tenn., lies about on the thirty-seventh degree of north
tude, and is the principal town in the eastern division of the State
is situated on the north bank of the Tennessee (late Holston) River,
as will be seen, in a favorable location in regard to health. From
river there is an abrupt elevation to the height of from 100 to 115
which extends northward nearly half a mile, on still ascending gro
This plateau, from east to west, is bounded by creeks (First and Sec
which empty into the river at about right angles, and is that po
upon which the original town was laid out in 1792. About the
1812 the village was extended eastward across First Creek, and qu
number of houses erected west of Second Creek. The land lay in
mons, or was cultivated for crops, for more than half a century.

In 1838 the town began to extend northward. The ascending gro
alluded to above as extending northward suddenly drops about 100
to a low strip of land which was originally known as the "flag-po
Along this depression is laid the track of a railroad connecting Bri
Va., and Chattanooga. Farther north, and a short distance from
railroad-track, is a slight elevation which gradually rises till it rea
a high ridge three miles from the river. The present town, with
suburban additions, extends about a mile north and south, and ne
the same distance east and west. The surface-drainage, except in
locality upon which the railroad is built, is almost perfect. The so
a solid ferruginous clay, intermixed with a fragile limestone rock, w
is filled with seams, and in some places cavernous openings, thro
which water can pass off to an unknown depth, but probably on a l
with the bed of the river.

The streets, although narrower than in more modern laid out ci
are very well graded and generally provided with gutters, which c
off water falling from the clouds, immediately either to the creeks or
river. The creeks descend rapidly and give fall enough for mill-s
The creek-bottoms are rocky, a formation made by the outcroppin
the underlying solid structure of the general surface. Numer
ravines which ran across, at different angles, the whole original site h
been filled from time to time with material taken from cellar-exca
tions; the removal of hillocks, and the ordinary *débris* formed in
gutters and back yards of buildings. Streets and alleys have also b
leveled across these ravines, and hence more or less of the surfac
composed of made ground. The drainage being so good on accoun
the general surface not being level, but little noxious emanation
arise from this filling and the general grade formed, without preju
to health, except along the railroad-track.

e original water-supply for the inhabitants came from numerous gs which for ages appear to have gushed forth along the edges of reeks and the river-bank. The water from these springs is as pure y of the kind, and is never rendered otherwise except when the ms are flooded by heavy rains.

stern-water has been used extensively in families from the earliest of municipal existence, especially at points remote from the gs. For many years no house of any pretensions has been erected out being provided with a large and substantial cistern, and a more or less effective attached. The mildness of the climate ers it practicable to have cisterns easily constructed, it not being sary to go below a frost-line as in the more northern States.

kewise, from the fact that it is not necessary to provide against ex- e cold, there are less cellars made in which to store vegetables in r. Hence there is comparatively little of decaying matter under ouses to cause sickness. In fact, but few lay by a store of vege- s and fruit, the main dependence being upon small purchases made ort intervals in the market.

ere are no low places of any extent in which water can become nant, even in the suburbs, except where the grading of streets has fered with natural drainage.

ere are no animals slaughtered very near the city limits, but the ghter-houses are in some instances along the banks of one of the ks, and more or less impurity finds its way into the stream to pass the river.

mparatively little animal matter, however, is deposited for any th of time, as the rapid current and frequent floodings from rain to carry everything away.

sewerage system has as yet been inaugurated, but the United es Government building (court-house and post-office) is drained by as of a deep sewer, which empties near the river into one which already made. Some of the property-owners along the street ugh which it passes have made openings into which they may dis- rge drains, and one gentleman has already availed himself of this rtunity, in order to carry off sewage from his premises.

is example will soon be followed by others, and before many years e will probably be a plan devised for supplying the city with water n the river, and this movement will forcibly suggest the sewer sys- .

ne important drawback to the present and future health is the ner in which privy-vaults are constructed, or rather their non-con- ction. For nearly a century the soil has been filling up with effete ter accumulating in a series of privy-vaults which have been at es dug, used, filled, and others substituted.

Whether animal matter has to any extent been conveyed by percola- through the soil to the several springs is uncertain, but we are told ne instance in which coloring matter was found to have been carried n a tannery to a spring from which many families procured water. s occurred in 1854. The probability is, however, that surface-water y is likely to affect the water-sources which nature so abundantly plies.

t will be seen, then, that the natural location of Knoxville is favora- to health, and that time, with improvements made from year to year, e not served to render it insalubrious.

Cholera prevailed here in 1849, 1854, and 1866. It was very fatal at h period, and the people had the usual dread of the disease.

During the month of May, 1873, there was noticed a tendenc looseness of the bowels and cholera-morbus. There were also case vernal remittent fever, and more than the usual number that assu an intermittent type. It is common every year more or less to n with diarrhœa among children from April to July 1, and no appre sions were felt that it would be more severe or general during season than usual in others preceding. Early in June, however, disease began to be choleraic, but of a mild type and easily control Among the adult population cholera-morbus made its appearance a the middle of the month. Both white and black were attacked, none died for more than a week after the first case occurred. The n ber of deaths from all causes in May and June was below the n ratio.

Case I.—The first case that was considered undoubted cholera, w patient of Dr. C. Deaderick. He was taken, about 5 p. m., June with severe vomiting and purging. The doctor saw him very soon a his attack, and found that collapse had already set in. At 8 o'clock voice was sepulchral; skin of the characteristic doughy feel, and hands presenting the "washerwoman's" appearance; pulse imperce ble at the wrist at 8.30 o'clock a. m., beating 110 at the temporal reg From this time there was jactitation, hippocratic visage, and coldnes the tongue. Died at midnight.

I learned the following facts in the history of this man: He about fifty years of age, married, and in comfortable circumstanc full, sanguine temperament; imprudent in all his habits; a great ea gross in appearance, and weighing about 225 pounds. Drank dail whisky. On the morning of his attack he remarked to some one t he had no fear of cholera, and, with an oath, stated that he could vegetables to any amount with impunity. Those who took dinner w him state that he ate very freely of cucumbers, green beans, and ot vegetables, drank a quantity of cold water, and during the aftern was seen to take whisky and ice-cream.

This man lived a short distance north of the railroad, and there nothing of a local character to particularly excite the disease.*

Case II.—June 23, at 7 o'clock p. m., I was called to see a white wom about thirty-two years old, married, and advanced about seven mon in utero-gestation. Forty minutes previous to my calling she was ta with a copious evacuation from the bowels, attended with nausea a vomiting. Pulse small and feeble, but about natural in frequency; tremities cool; tongue coated white, with a brownish color at the b There had been severe cramping in the stomach, together with spas of the arms and muscles of the neck from the commencement, and w I entered the room she was unconscious, lying with closed eyes, and muscles generally rigid. She had walked since noon about half a m in the hot sun, and on returning drank freely of water.

The family came from Georgia about the first of the month, and had not felt well since their arrival. Her husband was intemperate, a inattentive to her, and she was in a state of mental depression.

I gave at once, dry, upon the tongue, sub. nit. bismuth, gr. v, calom gr. i, sulp. morphine, gr $\frac{1}{8}$, and sub. carb. soda, gr. vi, to repeat in hour, and sinapisms to pit of stomach and extremities.

At 8.30 there had been no return of symptoms. Slept a few minut

* In the report of the case of Robert Brown, the first one that proved fatal in Kn ville, it is proper to add that he kept a boarding-house for the accommodation of r road-men, who stopped off from trains coming from Chattanooga, and the seeds cholera might have been brought by some of these boarders

24th, 9 a. m.—No vomiting or purging through the night; able to sit up in bed.

This case, although wanting in the characteristics of true cholera, was severe, and suggestive of what we had reason to fear. I noticed the peculiar odor, which in former epidemics had been very obvious; still, the urine was free, the voice clear and sharp, and the diagnosis noted as cholera vulgaris.

The apartment occupied by this woman was in the rear of a saloon, and the premises far from clean. Conditions personal to the patient were sufficient to induce vomiting and purging, and they were, walking in the sun, &c., as stated.

Case III.—Jacob Eastuday, German, aged fifty, with a large family; teamster; was taken about July 1 with cramping and vomiting, with purging early in the morning, after having been wet on the previous day without changing his clothes. Died at night. Could not learn any definite history of this case, but was informed that he sank from exhaustion, after vomiting and purging all day. Habits, intemperate for years. He lived in the northern limits of the city proper, but not in an unhealthy locality; causes must have been wholly personal.

Case IV.—July 3, Mrs. R., widow, about forty-five years old, died at 8.45 p. m. Taken sick on the 1st, with choloraic symptoms, and employed a homeopathist. Was no better on the morning of the 3d, and then sent for Drs. James Rodgers and F. A. Ramsey, of this city, who decided the case to be one of true cholera. I have no details of symptoms or of treatment. This case occurred in the old part of the city, and near Second Creek. The surface condition of this locality was good, but on the lot were two privies, one of which had been used for thirty years, and still open. The other was recent.

Dr. Ramsey informs me that a fatal case of cholera occurred in the same house in 1854, and, as the old privy was still open, the germ might have remained, waiting for circumstances favorable to developing the disease.

Case V.—A white man of sixty; lived near the river, west of the city limits, nearly half a mile from Case IV, and still more remote from the others. Had cholerine for some days, which had been kept at bay by some means, but on July 4 he relapsed, after drinking freely of cold water.

Case VI.—July 9, Fanny Nelson, a colored girl, aged twenty-one, slender, but not sickly; at 9 o'clock p. m., vomiting and purging violently; dejections watery and nearly odorless; great prostration. Pulse 90 and small; tongue slightly coated; distress at præcordia, but no cramping; extremities warm and somewhat moist; urine very scanty. Gave calomel, gr. ii, pulv. doveri, gr. v, at once. Sinapisms to stomach and ankles. Small pieces of ice to be slowly dissolved in the mouth.

10th, morning.—Less vomiting; stools of a yellowish tinge; much prostration; jactitation and insomnia. Gave bismuth and morphine every two hours; iced tea. 9 o'clock p. m., has slept some; one or two stools, but no vomiting.

11th, 8 o'clock a. m.—Slept nearly all night; amelioration of all the symptoms. Without further details I will say that this girl slowly recovered her usual health. The disease evidently was controlled at first, but the symptoms were characteristic. This case was near First Creek, but in an old house, and location bad.

Case VII.—William Johnson, white, married, and about forty years of age. He was taken on Saturday, July 13, at an early hour. A friend

gave him some homeopathic pills, which was all that he had as medi during the day and succeeding night.

Monday morning Dr. Burnett was called in, and also Dr. Boyn When first seen he was in a state of collapse. Morphine hypodermica stimulants, enemata of laudanum, and other measures were adopted, without avail. I called in frequently during the day in the capacity health-officer, and will say that no better marked case of true alg cholera ever occurred. (The house nearly opposite the one in which c VI occurred.) Johnson was living alone, his family having gone to country to avoid cholera. He prepared his own food, and, it is s would not properly cook it because it would take him from his work a mechanic. He lived on green corn, side meat, and some bread poo baked.

Case VIII.—"Aunt Vina," a colored woman, about fifty years of a July 11, I was called to visit her, and found that she had had some d rhœa since the 7th, which, with a feeble condition from previous sickn and exposure, reduced her very much. Stools watery, and vomit freely of a colorless substance; great depression; pulse slow and sm extremities warm and moist; tongue coated; very thirsty, and is c stantly tossing about in the bed, but does not complain of pain; e sunken; features so much changed that she is scarcely recognizab voice feeble, but not husky; urine scanty; slight cramping in the l at times. Gave nit. bismuth, gr. v, calomel, gr. ii, sulph. morphine, g dry, on the tongue, every three hours. Sinapisms to the extremities pit of stomach. Ice in small lumps to be dissolved in the mouth.

Saturday, 12.—Nine a. m., stools are changed to a brownish-yell not copious or very frequent, but offensive. Took but three powd when the stools changed in color. Less vomiting. To take bism and morphine every two, three, or four hours, as required.

Sunday, 13.—Appearances improved. Slept some during the ni Stools dark and bilious, voided only once in three or four hours. Sc quantity of urine. Pulse about 80. Soft, creamy coat on the cente the tongue, with the tip and edges red. Can retain rice and chicken so

Monday, 14.—Is no worse. Can raise up on one elbow; some sl during the night. To continue bismuth and morphine; rice-soup.

Tuesday, 15.—More gastric disturbance and great thirst; frequ attempts at vomiting, and passes small green stools with some cons ence; scarcely any urine voided. To continue same treatment.

Thursday, 17.—Has failed in forty-eight hours fast. Some stup and is roused with difficulty. Gave stimulants, with quinine and sul acid dilut. Six p. m., is unwilling to swallow anything but water, a that is taken with difficulty. Patient died at 2 a. m., Saturday, 19.

This case occurred in the same house as Case VI. I have given tails, from the fact that gastro-enteric symptoms set in at an early sta with dark stools. Recovery might have been obtained in a youn and more vigorous person, for the morbid appearances were not m severe than those of Fanny Nelson, (Case VI.)

Case IX.—Leanna H———, a very light mulatto, aged twenty-f years, mother of five children.

July 9, 4 o'clock p. m.—She called at my office complaining of a "k in the stomach," but no nausea. Gave her a dose of calomel with muth, to be taken as soon as she arrived at her house. Called n morning and found that the cathartic had moved the bowels; but th was nausea and vomiting, with some coldness of the extremities, hus voice, and pinched features. Gave bismuth and morphine in free dos sinapisms, and only a small allowance of drinks.

n.—Gradual improvement, and to-day she had a natural evacua-
This case was decidedly choleraic, and arrested by timely treat-

e *X.*—Rosa H., member of the same family, had diarrhœa when
a was taken. A decided dose of calomel at once arrested the
ess, and she was about the next day.

e *XI.*—July 13.—A French lady, patient of Dr. J. M. Boyd, was
with characteristic symptoms. Prompt medication arrested the
e. On Monday was apparently doing well, but Tuesday morning
ed, and she died at 7.30 p. m.

e *XII.*—Spencer K———, an African of sixty or more, and hus-
of "Aunt Vina," was taken suddenly, July 13, with diarrhœa,
continued some hours. I gave calomel and morphine, which
ted at night. On Monday morning he was able to be about the
and take care of his wife, but was very feeble. On Tuesday he
about, but on Wednesday morning I found him vomiting. Gave
small dose of bismuth and morphine, but he soon went into col-
dying at 4 or 5 o'clock p. m. He was intemperate, and broken
generally.

e *XIII.*—Julia, daughter of the above, aged sixteen, a stout,
y girl, was taken with diarrhœa while her mother lay sick, but it
t once checked by a dose of calomel and bismuth.

e *XIV.*—July 18, Friday, a young man, patient of Dr. Burnett,
aken sick, and before medicines could be effective, went into col-
He lingered till the 22d at 5 o'clock p. m. There were some indi-
s at one time of a rally, the stools changing in color, and slight re-
ary fever coming on.

e above, commencing with Case VI, all occurred on Crozier street,
runs parallel with First Creek, about one-fourth of a mile from
outh; all but two were on adjoining lots within a short distance
each other. The water used by these families was procured from
ng which bubbles from the bed of the creek, and available only
at a low stage. After heavy rains the spring is overflowed, and
the water is used when mixed with the flushing of rains.
to July 26 a few cases occurred in different localities, but no more
s than those reported above.

e *XV.*—Pleasant M. Miller, aged sixty-four years, white, rather
e health from exposure in the Army, and pensioned therefor,
r-in-law of Johnson, (Case VIII,) who was in attendance about
-six hours upon Johnson, and upon his death took the corpse to
ouse nineteen miles distant. It is said that he took the bed-clothes
which his son-in-law died into a wagon and rode upon them.
r soon after sickened and died. It was reported that two daughters
iller, and the physician who attended the family, all died within
days. They lived in a healthy, rural locality, and it is evident
the disease was communicated as above stated. There were also
cases in the vicinity, but no more deaths.

y 30, a negro man, forty-five or fifty years of age, died after a few
's illness. He was very intemperate, and had been drinking freely
efore the attack.

se *XVI.*—July 30. I will give verbatim a history of this case as
dy reported in the Nashville Medical and Surgical Journal, April,

On the mid-day train Mrs. P., a married woman of thirty or
, came to her home in this city from Jonesborough, one hundred
s northeast. On the 26th she went to Jonesborough in response to

a dispatch stating that her mother was sick. She found both fa and mother sick, and they died on Monday and Tuesday. Sunday n she was taken with diarrhœa, and started for home at 7 o'cloc Wednesday morning. While in the car she vomited, and was much depressed at 1 p. m. When I saw her, out of five nights she only slept four, and the death of her parents added to her weak condition. Her extremities were warm; pulse weak, but slow and s what full; voice natural in tone, and no washerwoman's hands; to slightly coated, but red; urine secreted in small quantities. Prescr as follows: R. calomel, gr. viii, sub. nit. bismuth, grs. xv, sulph. phine, gr. s. s. F. pulv. No. 4, sig., one every two hours, dry, on the to Sinapisms to extremities and pit of the stomach.

"There was no vomiting or purging after her arrival until abo o'clock. The stool was green, and the vomited matter also ti with greenish yellow. At dark there was increased gastric irrita with more depression. Before midnight the hands and feet became c vomiting increased, countenance more dejected and eyes sunken. In untary stools passed off in bed; tongue cold; no cramping till a midnight, when it commenced in the legs. At daylight the pulse ce to beat, hands and forearms cold, also legs to the knees; emaci rapidly going on; vomiting of green water, with curdles resembling green scum upon frog-ponds.

"At noon on Thursday she was still living; voice not changed in and stronger than it was last night; vomits everything swallowed.

"At 6 p. m. pulse slightly perceptible; extremities still cold; st passing involuntarily, and so much as to run through upon the f No urine passed during the day; vomiting continuous, of a dark bil character; tongue coated, and brown in color; thirst intense, only peased by ice, or iced water, which is rejected after a quantity is a mulated. Takes iced brandy.

"Friday, August 1, 8 o'clock a. m.—Still living, but general appearan unchanged since last night. Vomits a dark-colored substance, with wa which she is constantly begging for; pulse barely perceptible, and more than 80.

"Saturday, 2d, 7 o'clock a. m.—No vomiting or purging since yester pulse slightly improved in volume, but not in strength; inclines wander after sleeping; feet some warmer, but hands still cold, and m tled red and purple; no urine since Thursday that can be ascertai

"Sunday, 3d.—Died at 2.30 a. m. This case, although cholerai most points, was more of the nature of gastro-enteritis. She inform me that her first vomiting and purging were dark in color, and atten with pain and distress in the præcordia.

"The flow of urine for the first few days, absence of the husky v and shriveled fingers, indicated another pathological condition t true cholera. Warmth was kept in the extremities some time after radial pulse was nearly imperceptible."

Case XVII.—A few days after this woman died, Jennie, a yo sister, single, and about twenty years of age, was taken, but I did attend her. The symptoms were violent vomiting and purging, dep sion, and rapidly-failing strength. She lived about two days.

The house in which Mrs. P. died was the same one occupied by C XI. Whether the one influenced the other is uncertain. Mrs. P. be attacked at Jonesborough, might have contracted the disease there, the predisposition may have been carried with her.

Case XVIII.—Isaac, brother of Jennie and Mrs. P., was taken a August 1, and barely escaped death. He was in the room of Mrs. P.

of the time of her illness, as also Jennie. They had gone to another before being taken sick, but must have been predisposed from sure and want of rest, &c.

se XIX.—On Monday, the 11th, a girl, aged fourteen, feeble, scrof- diathesis, was taken with diarrhœa, which, at 8 o'clock, became ise. Collapse soon ensued, and death occurred at 2.30 a. m. on the This girl was of poor parentage, and for four years or more had subject to palpitation and severe pain in the chest. The family of the worst character in all their habits, and during the day the sed, with an older sister, had eaten unripe peaches. The house in a low ravine where filth had accumulated for years, and the was foul. Dr. Burnett was called, but collapse had occurred, and dies were of no avail. The locality was less than two blocks from e Case IV occurred.

se XX.—August 14, an old man, white, of low, uncouth habits, reported sick with cholera, and Dr. Stewart saw him. He lived in urban neighborhood, northeast from the city, and the house was a hovel. Died at sunrise on the 15th. At the suggestion of Dr. J. ndlow, who was also in attendance, the hot pack was used, which the only case where it was tried during the season. On one corner e lot on which this man lived was a large pile of manure, which ccumulated from the keeping of a cow. He had been advised to ve it, but insolently refused.

se XXI.—August 15, Mrs. S., aged fifty-five or more, mother of nu- us adult children, was taken at noon with profuse diarrhœa, watery nvoluntary stools. Had some looseness for a day or more, but paid no tion to it. I saw her at 4 o'clock p. m., with Dr. Boyd, the attendant. e slow and soft; extremities warm; no nausea. Tongue had a yel- oat; no pain; voice a little husky. Had taken eight grains of calo- and three-fourths of a grain of morphine.

th.—Some improvement. Recovered. This case was on Second k. Will refer to locality further on.

se XXII.—Sunday, August 17, a man, white, aged forty-eight, this a. m. at 6 o'clock. He was a carpenter, and worked during the ious week till Friday. Walked in the hot sun on Saturday, which ravated a diarrhœa which had been troublesome for two or three . I visited the house after his death to inspect the premises, and d a daughter—

se XXIII—who had been walking the streets the preceding night "nymph du pave," much depressed from fear, and a diarrhœa at- ded with vomiting. I gave her calomel, gr. vi, at once. She was er next morning (Monday) from effect of cathartic. Followed up morphine and bismuth, and she was well in a week.

se XXIV.—August 17, colored infant nineteen months old. Found collapse at 6 o'clock a. m. Died at noon same day. I gave it mel, gr. iii, which acted at once, bringing away seeds and skins of atoes, eaten the day before.

se XXV.—The mother of above, when I called to see the child, nearly collapsed, with profuse diarrhœa, soapy and brownish; t distress at stomach; great jactitation and depression. Gave cal- l, gr. v, at once, repeated at 10 a. m. and 6 p. m. Bowels moved from ffect before dark.

8th, 9 o'clock a. m.—Better and made a good recovery.

ase XXVI.—On the 15th, the day on which Mrs. S. (Case XXI) took , I was subsequently told a young girl, niece of Mrs. S., was taken h diarrhœa, and also a child of five years. In the same neighbor-

hood some six or eight cases occurred on the 16th, some of which w decidedly choleraic. I saw none of these cases. Their medical attend told me they were all relieved by calomel and morphine.

A spring from which most or all the families procured water found to be impure from surface-water; all were advised to substi rain-water, and no more cases occurred. The family in which C XXIV and XXV occurred, and also Case XIX, used water from spring. The street upon which most of these families lived ran par with Second Creek, and there is a large tannery near. There is a near the tannery, made to direct the water into a mill-race. Into pond thus caused more or less fleshings of hides and the excrement privy find lodgment. This privy is used by about twenty-five men. has no pit or vault. In dry, hot weather a very offensive smell a from this locality. In previous epidemics cholera had occurred in same neighborhood, and it is very certain that its prevalence influenced by the conditions mentioned above.

Case XXVII.—About August 1, a young man employed on the L Tennessee, Virginia and Georgia Railroad, by the name of Dunn, brought into the city from the station. He was a patient of Dr. J Boyd, and I saw him only while on an official visit to the house. C plete collapse did not obtain, but the symptoms were characteristic. was treated with calomel and opiates, and after a struggle between and death for five or six days, he rallied and made a good recov This man had frequently passed through Jonesborough and Greenev while cholera was prevailing in those towns. He did not reside here, consequently brought the disease with him. No case occurred in house where Dunn lay sick.

Case XXVIII.—About the same time Dunn was brought in, a yo man by the name of Perry was attacked. He was treated by Dr. B Treatment, mercurials and opiates. This man had suffered inten from fear of cholera all summer, and would not eat anything but ba and bread, from a notion that vegetables would induce the disease. was sick about a week, and made a good recovery.

Case XXIX.—Mrs. D., wife of Case XXII, and mother of Case XX was taken August 18, very suddenly, about 3 o'clock p. m., with copi diarrhœa, but no vomiting. I saw her within thirty minutes, and g at once, calomel grs. viii, and sulph. morph, grs. ½; sinapisms and in bed.

19th, 9 o'clock a. m.—Bowels moved freely and copiously with gr stools; some vomiting attending the action of the bowels.

22d.—Had improved slowly, with no more untoward appearances. to-day there was a relapse of vomiting, with some purging. Pulse v feeble, countenance sunken, voice weak, but not unnatural in to tongue whitish yellow; great thirst for iced water; feet and ha clammy, but not cold. Gave morphine, bismuth, soda; sinapis This woman slowly recovered, but the case was aggravated by mental condition. Fear of cholera, added to grief from the loss of husband, and the conduct of her daughter, contributed as a ca There is no doubt of the choleraic nature of her attack; but the dise was gastro-enteric in its development, and was well-nigh fatal to life

Case XXX.—August 21. A strong colored man, an industrious wor in an iron-mill for four years past; aged about forty years. He had d rhœa for some days, but paid no attention to it. On the 20th he ate c bage freely at noon, and had indulged for some days in the use of wa melons. I did not visit the premises till after his death, but was formed he was taken at night (21st) and died before morning-light.

ıation from the bowels after collapse set in, but he vomited freely. ocality is near Second Creek, above the tannery spoken of. He had water from a spring upon the edge of the creek and near the mill e he had worked.

e XXXI.—August 22. Reuben Emmett, colored, aged sixty or ; hand-cart drayman; habits good, and generally respected. He wo evacuations before noon yesterday, but kept about till nearly when he went home. Dr. Stewart, his physician, states that he ice-water stools, and died at 2 a. m. next morning. He lived on a elevation east of First Creek, and had used cistern-water. His ıad been unrestricted. The premises were neat and tidy.*

e XXXII.—August 3, S. B. Scott, aged about thirty; bilious san-, and intemperate for a few months past. He had been in the city day lounging about in the saloons, but lodged in a building on the s of First Creek, east of the city. There was a very filthy privy on ɔremises, having been used by workmen in a tobacco-factory. s watery and very copious; very much prostrated, but complete ɔse did not occur. Treated with calomel, bismuth, morphine, sin-ıs, and rest on the back. Slowly recovered, but left in a feeble tion.

as constantly engaged in treating cases and visiting infected local-till August 24, when an attack of fever prostrated me, and ren-l it impossible for me to be about much till the disease was checked. ill add, however, as *Case XXXIII*, Hon. T. A. R. Nelson, an eminent er and jurist, who was taken August 23 with some diarrhœa, to which ıid but little attention. During the night he was worse, and sunk e 9 a. m. The symptoms were reported by his physicians as de-lly choleraic. It is said that he abstained from fresh beef for some but ate fruit freely. Timely interference undoubtedly would have l him.

uring the last days of August and the first two weeks of September, t two cases occurred upon the extreme borders of the corporation along the banks of First Creek. This was northeast from the cen-f the city and not far from a slaughter-house, which was reported eing so situated that the offal and other filth found their way into a ng near by, as well as the creek. The subjects were principally ts of both colors, and soon succumbed.

here were some cases which occurred during the summer, the sub-s coming from abroad. One was a young man from Missouri who attacked on the journey, but the initiatory symptoms made their earance before he started. He was much prostrated, and life was paired of for a few days. He came from Troy, Mo., and told me that era was prevalent in the town before he left.

nother case was that of a man who came here from some place in ginia with the intention of leaving soon. He was attacked within a k, and died with undoubted choleraic symptoms. The disease was prevalent in the place from which he came, but he passed in his ney through infected towns.

noxville is a favorable locality for the prevalence of cholera, being erlaid with lime-formation, and the springs are loaded with lime-

n the case of Reuben Emmett, who lived upon the elevation, I am told by Dr. art, his attending physician, that the chamber-vessels were emptied outside the upon the ground during a shower of rain. They were living upon the edge of a ne, and everything emptied upon the ground was carried down the hill. Within w days there were five or six cases of cholera near and just below the house of nett.

salts. A majority of the cases occurred in localities where the sprin water was most used for drinking and cooking purposes. Compar tively few were affected who lived in the higher and best-drained place As a general rule, it was found that an old neglected privy stood on near an infected house, and the grounds about the premises were ree ing with the wash from cess-pools, and in very many instances fro pig-pens, which became exceedingly offensive in hot weather.

As soon as it became evident that cholera would prevail among t the city council appointed a board of health with sufficient authori to abate nuisances; but, in addition, the writer was made health offic with almost unlimited authority to act in the enforcement of sanita measures. It was deemed of great importance to prevent, if possibl the occurrence of a second case in the same house, and generally th effort was successful.

The plan was to use a solution of sulphate of iron in every pri about the city, and where a case occurred it was strictly insisted upo Solution of carbolic acid was placed in the chamber-utensils used the sick, the cholera or diarrhœa dejections were buried immediatel and the clothes either burned or boiled at once in water with lime carbolic acid added. Lime was distributed very generally through t city, and all had it to sprinkle in damp places, or where secretions h been emptied. The sale of unripe vegetables and fruit was prohibite and water-melons were contraband. A special police was appoint whose duty it was to visit every place where a case was reported, a to see that the proper precautions were carried out. Dry earth was e tensively used for filling up privy-vaults which had become offensiv and in a great many instances there were new privies ordered to constructed without delay and the old pits filled up.

The city practitioners were all very attentive to sanitary details wh giving attention to patients. There was a general concurrence on t part of the people to use any and every precaution which experien and good sense seemed to suggest.

One very common precursory symptom complained of by those a tacked was a feeling of heaviness, as if there was a "load in the sto ach." Some said they felt as if a ball the size of the fist had be swallowed. This feeling was generally accompanied by constipation a short time previous. Diarrhœa, unattended with vomiting, was gen ally considered salutary, because there was more or less relief from t gastric distress. It will be seen that most of the persons whose cas are described above were over twenty years of age. While adults we most liable to the disease, those in feeble health from previous sickne or bad habits were most obnoxious.

While it is not proposed to offer any theoretical opinions regardi causes, it will not be amiss to state some leading facts which are at lea suggestive.

The first case that occurred in Knoxville was that of a man who had n been out of the city to become exposed. There had been many cases befo any one was found with the disease who had been away. There is t way in which we can suppose that cholera was brought here fro abroad through the ordinary lines of travel.*

* In this paragraph Dr. Bailey seems to have overlooked the statement which he h previously made, that the first cholera death occurred in the person of a man w kept a boarding-house which was frequented by railroad employés engaged betwe Knoxville and Chattanooga; and that at later dates a sufficient number of cholet infected persons arrived at Knoxville from infected districts to account for the diffus of the disease.—E. McC.

e cases were scattered here and there, to-day one in the north and orrow another in the south part of the city. It would seem that a ral predisposing cause was operating; that local or personal in- ces, in conjunction with the predisposition, excited an attack t these several influences may be, no one has been as yet able to rmine.

will be seen that the most effectual remedial agents employed in ing the cases above described were calomel, bismuth, and the arations of opium. Where collapse had obtained before medical vas called, recovery was rare, and only resulted, it would appear, e vitality was so strong that life being prolonged, sufficient time ed for remedies to be effective.

e whole number of cases that occurred in the city and suburbs it possible to ascertain. The total could not have exceeded one hun- and twenty, and the number of deaths did not probably reach five.

will repeat the following facts which were mentioned in my report cholera, as published in the Nashville Medical and Surgical Jour- for April, 1874. It is in reference to a family which came from ttanooga, arriving in Knoxville on the 1st or 2d of July, as subse- ntly ascertained.

n their arrival in the city, one of the number, a boy of eight or years of age, had diarrhœa. His mother took him to the office of J. M. Boyd, who prescribed for him. They went the same day into country four miles distant, and the next day some of them had era, and, within a few days, six died. None of the residents of the hborhood had cholera, but were troubled with diarrhœa, which was ly controlled.

he county authorities immediately sent a physician to the locality, authorized him to use whatever measures were requisite to check disease from spreading. I am informed that the bedding and cloth- of the affected family was burned at once. From the fact that no died except those who came from Chattanooga, we see the disease pretty effectually stamped out. This locality is well known in this ion as Fountain Head, and is the source of First Creek, so often tioned in this paper. There is a large spring from which the creek es its rise, and near by is a camp-meeting ground. I have never ted the place, but am told that the family referred to above did not e near the spring or creek, and that it is not probable that any excre- nt could have found its way into the stream, to be conveyed to the r. It will be seen that the first cholera cases in this city occurred ring the week previous to the arrival of the family above, and that disease was not conveyed by them to our midst. If this family had pped in town, and occupied some uncleanly tenement, they might ve spread the disease in our thickly-settled city, but having left im- diately, such a source of disease was obviated. There are so many ntingencies of which we have no cognizance in the movements and ings of mankind, that we cannot say what causes have operated to read disease in a given locality. From the fact that a great propor- n of the cases which occurred in and around Knoxville were on the e of this same creek, and that as the season advanced this fact was ore apparent, it is presumable that cholera-germs had been conveyed some means in the water and deposited upon the banks. Just out- le of the city limits was a slaughter-house but a few rods from the eek, and it was ascertained that the wash of the establishment found way into a spring from which many families in the infected district

procured water. This would render people more liable to contract disease which was prevailing at the time, even if no specific germs were conveyed from the decomposition of offal around a slaughter-pen.

Since writing the above I have been told that the family referred *did* empty some of their utensils in places where the contents could washed into the creek. On their way there must have been dejecti left near, if not upon the banks of, the creek.

A woman died of cholera about one mile from the city limits on road taken by this family, and the privy used by her family was imm diately over the stream.

It seems altogether probable, from what can be gleaned from source and another, that the waters of both First and Second Cre were in some way infected, because a great majority of all the ca which occurred in the city were along their banks.

Obion County.

Union City is located in Obion County, at the junction of the Mob and Ohio Railroad with the Nashville and Northwestern Railroad. T town is one hundred and fifty miles from Nashville and ten miles fr Troy, the county-town. On the west bank of the Obion River there a belt of land some two miles wide, which is crawfishy and subject overflow. The soil is thin; black on top and lying upon a bed of whit clay. Next comes a belt of land about three miles wide extending fr the outside of the belt of overflowed lands to the hill. The soil of second belt is a rich alluvial, very dark and deep, and remarkably p ductive. In almost the center of this last belt Union City is locat

The water of this town is obtained from wells and cisterns. The we are from 10 to 50 feet deep. In some portions of the town they yi freestone-water, but in the great majority of instances the water hard. The drainage of the town is good.

June 25, a Mr. J. A. Cardwell, who had, while at Nashville a few da previous, been in attendance upon friends sick with cholera, was attack with the same disease. Later on the same day Mrs. Cardwell w attacked, and the next day their young child. All three cases reco ered.

July 1, George Frank, a German baker, who had in his employ seve refugee bakers from Nashville, was seized with cholera and died af a few hours' illness. The Nashville men lived at Frank's house.

July 7, a lady whose residence was at no great distance was attack and died after an illness of a few hours. After the last case the e demic influence seemed centered at the house of Dr. S. T. Evans, w had attended all the previous cases. At this house there were elev persons at a dinner on the 13th, and on the 15th six individuals w had been present were dead, and three others died within the next for eight hours. Dr. Evans was himself attacked and barely escaped wi his life.

From these houses the disease spread to the town and county. Six cases are reported, of whom twenty-eight died.

Anderson County.

Clinton, the county-town of Anderson County, is located upon t right bank of the Clinch River, and upon the line of the Knoxville a Ohio Railroad, eighteen miles northwest of Knoxville and one hundr and seventy-five miles east of Nashville. In 1870 Clinton had a popu tion of about one thousand inhabitants. The town is located in an e vated, healthy, and fertile country.

the 10th day of July, 1873, a white woman who had been on a to Knoxville was taken with cholera. When first seen by Dr. H. ollingsworth, who has been kind enough to furnish us with a rt of this demonstration of the disease, she was purging, vomiting, ramping. Collapse was imminent. She was treated by sinapisms, on, and a mixture of tincture ferri, tincture opii, and acid muriatic exhibited in full doses every hour.

two hours the vomiting, purging, and cramps were arrested; re- n was fully established. The next day she was placed upon doses lomel and ipecacuanha. The secretion of urine was re-established, good recovery was effected. The excreta of this case were care- disinfected with sulphate of iron, and buried.

ery effort was made to isolate the case, and no case followed that l in any way be connected with it.

ly 18, a white man, named Hutchinson, who had come into Clinton ll, from Knox County, was found fully collapsed from cholera, and before any medical assistance could be procured. Hutchinson had ed the evening before and remained overnight at the house of the r, who reported that he had heard him get up two or three times g the night and go down-stairs. As he called no one, no attention given to the occurrence, but at daylight the next morning he found lying upon the porch profoundly collapsed. Disinfectants freely used wherever it was supposed that he could have had a tion, and no illness occurred at the house or in its vicinity.

gust 10, a white man, named Cross, was taken with cholera, after it of some days to Knoxville. He was treated by hypodermic in- ons of morphia and atropia, by which the cramps were effectually ved. The tinct. of iron, opium, and muriatic acid was used inter- . In this case the urine was suppressed for thirty-six hours. The recovered. Active disinfection was again employed.

fatal case occurred at a later date in the person of a negro man received no medical aid during his illness, but of this case we have unable to obtain any particulars.

allace Cross-Roads is a post-village of Anderson County, situated fertile valley. The village is well supplied with pure limestone- r, and has always been considered an unusually healthy locality.

uring the latter part of the month of August, 1873, a Mr. Reynolds, Knoxville, visited this village, and was entertained at the house of William Wallace. During his visit Mr. Reynolds suffered from e diarrhœa, for which he received no medical treatment other than estic remedies. No attention was given to the dejections of his , which was voided in the privy used by the family.

n the 29th of August Mr. Wallace was taken with cholera, and died r a few hours' illness. So intense was the alarm induced by this h that the body was buried during the night.

ugust 30, Edward Reed, a young white man who had nursed Mr. llace, and who had prepared his body for the grave, was attacked the same disease, and died the same day.

eptember 1, two members of the Wallace family were taken with era, but recovered.

ese cases were followed by the outbreak of the disease in two other ilies, whose infection can be clearly traced to the original case. In of these families three deaths occurred between the 12th and 15th September, one being in the person of a female infant but one nth old.

HAMBLEN COUNTY.

Russellville, the county-seat of Hamblen County, is located in th New Market Valley, upon the line of the East Tennessee and Virgini Railroad, two hundred and thirty miles east of Nashville, forty-eigh miles northeast of Knoxville, and twenty-six miles west of Greenevill

The first case of cholera at Russellville in 1873 occurred in the pe son of a peddler who had just returned to his home from Knoxvill On the 15th of July this man was taken with diarrhœa, which he pe ceeded to cure by the use of whisky, and in the attempt became ve drunk. The next day he was taken with cholera, from which disea he died upon the 19th instant.

July 19, a man returned to his home at Russellville from Tat Springs, a small watering-place some twelve miles distant, at whi point some two or three cases of cholera had occurred in the persons refugees from Knoxville. On the day of his return this man was tak with cholera, and died in a few hours.

July 20, the widow of the first case was taken with cholera, but s recovered. July 24 the mother of the last case, who resided in the sa house, took the disease and died after a lingering illness.

At this point the disease remained in existence until August 10. is noted that all cases which were treated in the first stage of the disea recovered.

This demonstration is of interest from the fact that to this town c be traced the individual who originated the epidemic of cholera in t counties of Garrard and Lincoln, of the State of Kentucky. It w near Russellville that Mr. Bewley lived; at this town he was treat by Dr. C. D. Riggs for an exhausting diarrhœa; from this town, duri the prevalence of the epidemic, Bewley started upon the journey wh terminated at Lancaster, Ky.

WASHINGTON COUNTY.

Jonesborough, the county-town of Washington County, is located up the line of the East Tennessee, Virginia and Georgia Railroad, eigh miles east of Knoxville. We present the following narrative of

EPIDEMIC CHOLERA OF 1873 AT JONESBOROUGH, TEN

BY W. R. SEVIER, M. D.

It is to be regretted that no record of the number of cholera-ca that occurred at Jonesborough in 1873 was kept. From memory record of thirty deaths has been made. Of that number, fifteen we white and fifteen were negroes. Sixteen were males; fourteen femal Two cases were under one year of age; one case was ten years o three cases were between ten and twenty years; five cases were b tween twenty and thirty years; two cases were between thirty a forty years; three cases between forty and fifty years; ten cases b tween fifty and sixty; one case between sixty and seventy years; t cases between seventy and eighty; one case between eighty and nine years.

Jonesborough is the oldest town in the State of Tennessee. In 1870 t town had about 1,500 inhabitants. The location is most admirable, i beautiful and healthy valley surrounded by stately hills, and having altitude of 1,734 feet above tide-water. The health of this communi prior to the advent of cholera was all that could be desired, no sickn of an epidemic form having occurred for several years.

e water-supply of the town is abundant and of pure limestone, ned from springs and wells. A creek of considerable size flows the southern side of the town, having its origin some half-mile de of the corporation limits.

e first case of cholera occurred June 29, 1873, in the person of a ee from Greeneville. This case was violent in its character, but the nt recovered. The next case was on the 4th of July, and was also efugee from the same place. Both of these cases were assiduously d by one of our poorer class of citizens. The last patient was by this man to his residence, a humble but healthily-located ing. The patient slept overnight in the family room. The next e was removed to a vacant house some two hundred yards distant, e he remained until he recovered.

e next case in succession, and the first among the resident popula- was the wife of the man who had so kindly cared for the stranger. woman died on the fourth day of her illness. Four laborers, es, who belonged to the gang working on the gravel-train of the ad, were the next to exhibit violent features of the disease. Two ese men died within a few hours after their attack. A third, who one mile from town, recovered; but his mother, a feeble woman, occupied the same house, contracted the disease and died. The h died of consecutive fever some weeks later.

e disease now rapidly assumed the character of a malignant epi- c. The majority of our population fled.

e periods marked by the greatest fatality were respectively 29th 30th July, and the 1st August. The estimated mortality up to this d was fully 50 per cent. The general plan of treatment had been l on the use of mercurials, opiates, quinine, brandy, sinapisms, &c. e results were anything but satisfactory. True, many gratifying, in some instances surprising, recoveries took place; but, on the hand, a number of deaths occurred, which I am now sure would ave resulted under the treatment subsequently employed.

anxious desire, stimulated by the appalling mortality referred to, mprehend more clearly and satisfactorily the true pathology of the se, led to a more diligent examination at the bedside; to a more ct grouping and analysis of symptoms; and finally, to a result in y and treatment eminently satisfactory and successful.

e disease known as Asiatic cholera is essentially "toxicæmia," or d-poisoning, and the facts and arguments supporting this theory s follows:

t. Some patients when first visited were found to be in a dying condi- while inquiry revealed the fact in individual cases that the nt had suffered but little purging, perhaps but one or two dis- ges, and no vomiting at all. The most rapidly fatal case we had that of a negro man who belonged to the grave-digging force; he in a little more than four hours after the attack, notwithstanding entire absence of both vomiting and purging. A near relative of writer died in the town of Greeneville after some ten or twelve s' illness, who suffered but two discharges from the bowels and no iting.

l. A case occurred where death ensued twelve or fourteen hours after ischarges had ceased, notwithstanding the best directed and most gent efforts at stimulation and alimentation.

l. The mental lethargy, depressed condition of the heart and arteries, le respiration, suppressed functions of skin, liver, and kidneys, are

not singly but collectively of value as symptoms of such poisoned
dition of the blood.

4th. The separation of the constituent elements of the blood, cou
with the rigid cramping of the voluntary muscles, points to the s
fact.

5th. The almost uniform effect of remedies of conceded disinfec
and depurative virtues was the prompt amelioration of symptoms.
lieving such to be the correct theory in regard to the pathology of
disease, I expressed the opinion that "chlorine, in some of its mul
dinous combinations," would be found the effective remedy. The rea
ing and facts were submitted to my friend, Dr. Deadrick, who prom
and cordially co-operated with me in the practical application of
theory and the remedy.

The first case selected was that of an unfortunate *nymph du pave*
had been pulseless for several hours. A strong solution of chlorat
potash was injected hypodermically over each breast, and 1½ to 2 gr
administered internally every half-hour to hour. Twenty-four h
afterward she was found to be still living, but still destitute of p
The tincture sesq. chlor. ferri was then ordered in doses of 10 t
drops every half-hour to hour. Another twenty-four hours passed,
she was found to be still living, but still pulseless; she was then pl
on sol. perchlor. ferri without appreciative advantage. She died, hav
been more than sixty hours as pulseless as a stone. A recovery mi
perhaps, have been obtained in this case, but for a miscarriage, wh
occurred a few hours after the attack.

The litmus test applied the day before to the ejections and dejecti
of a lady dying of cholera revealed the strong alkalinity of these
charges. In view of this fact, and that the features of a well-develo
case of cholera indicated it, I ordered the following:

℞. Tr. sesq. chlor. ferri, ℥vj.
Hydrochloric acid, ℥j.
Tr. opii, ℥j. M.

Sig. 15 to 30 drops to be taken in a wineglassful of water every half-hour to h
according to diarrhœa.

Caution.—Do not give from a spoon or metallic vessel. Use no mercurials w
taking this mixture.

In cases unattended with vomiting and purging, the mixture
advised to be used as directed until unmistakable evidences of react
appeared. The dose suggested, I am satisfied may, in cases requir
it, be safely doubled, tripled, or even quadrupled; but not, of course
such short intervals as are designated for smaller doses. A ne
woman, suffering an attack of diarrhœa, took a tablespoonful of
mixture undiluted. No ill effect or even inconvenience was sustain
beyond the copious and loud eructations of gas from the stomach.
gentleman gave to his child, nine years old, a teaspoonful. The ch
era was in each case promptly arrested; a second dose not hav
been required by either. The security from its effects, in such cases
doubtless due to the alkalinity referred to.

The diet in connection with the plan of treatment is regarded a
matter of some importance. I prefer rich animal broths, such as beef-
essence of beef, chicken-broth, &c., to rich milk, for the reason that
latter will form curds with the mixture, which may prove irritating a
indigestible, and which will necessarily engross the most import
element in the prescription in their formation, to a considerable ext
at least.

Of some forty-five or fifty cases occurring after the formula was adopt

we lost but two, both old brain-cases; one laboring under copious serous discharges from the ear, coupled with loco-motor ataxia, and the other a case of hemiplegia of right side of many months' standing. Shortly after the beneficial effects of this plan of treatment were established, the remaining part of our population, as well as those living in infected districts elsewhere, were advised to employ the mur. tinc. of iron in doses of 11 to 15 drops every four to six hours, as a preventive means. The suggestion proved salutary, as it is not remembered that a single person contracted the disease who had rigidly conformed to the prescription. Two ladies who had been refugees were attacked on the day of their return; but it is understood that they had used the tincture irregularly, and perhaps in insufficient doses. Their cases yielded readily to the use of the mixture. From 4 to 6 drops of muriatic acid, used in like manner, would probably prove equally protective; but owing to the necessity generally existing during such epidemic prevalence of the disease for the use of such a tonic, I prefer the tincture of iron. The addition of a single drop of the acid to each dose, however, would doubtless increase its efficacy as a preventive.

I take occasion here to repeat a conviction expressed elsewhere, viz: that under the opportune use of the means indicated, and leaving out of the calculation that class of cases afflicted with pre-existing disease of vital organs, the mortality from cholera will not exceed 10 per cent.

GENERAL OBSERVATIONS.

Much has been said and written of cholera, its diagnostic and prognostic features, which our observation of the epidemic in question failed to verify.

The "quick pulse" and "cold skin, covered with a clammy sweat," were of such unusual occurrence as to be undeserving the importance of symptoms. The skin was, indeed, in nearly all instances of icy coldness, but generally dry; while the pulse, as often as otherwise, excepting in force and violence, exhibited no departure from its normal standard. The contracted pupil was not observed in any case, except as the result of narcotism.

The "painless diarrhœa" constituted, generally, the initial stage of the disease; while vomiting and purging, coupled with "rice-water discharges," were characteristics of the malady in a more active and advanced stage of development. There were, however, exceptions in which the last-mentioned symptoms were not prominent, and a single case in which they were totally absent.

Death rarely results, we think, in cholera from exhaustive discharges. The most rapidly fatal cases will, we conceive, be found to be of that character where they do not exist; for the reason that such discharges are in a large measure eliminative—the method and the channel through which nature seeks to rid herself of the poison. The excretory functions are all suppressed, and in the emergency, should the only remaining outlet, through the medium of the bowels, be closed, the pent-up poisons will only act with more deadly certainty and vigor.

Suppression of urine was a very common feature of the disease as it existed among us. I drew from a male patient, on the fourth day after I had been called in consultation, something over an ounce—the first discharged in about five days. Dr. Deadrick drew from a female patient, on the fifth day, one-half ounce, the first voided within that period; yet both patients recovered without any untoward symptoms.

The catheter was introduced in each case simply for the purpose o ascertaining the condition of this important function.

Important questions here naturally arise touching the probable exis ence of uremic poisoning in this class of cases. The general symptom of uremia, as an idiopathic affection, so far as the nervous system concerned, do not correspond with those observed in cholera. We d not think that such is the case; and the most plausible explanation w can probably offer for the non-existence of the disease is to be found the greatly impoverished and altered condition of the blood, and th vicarious discharge of urea through the bowels.

This explanation will, perhaps, suffice in that class of cases whe copious vomiting and purging exist, and where these symptoms a absent death generally ensues too soon to be ascribable in any measu to such a cause.

The confident assurances given to us during the past year that chole made its attacks only "in the still watches of the night," were negativ to such extent that we may literally and truthfully say "day and nig were alike" to it. Nor was it more regardful of topical features; s visitations not more frequent nor more ruthless to the dwellings b the water's side than to those occupying more elevated and ar situations.

Opium and brandy were, in some instances, found serviceable duri the initial stage of the disease. This is principally and particularly tr of the latter; its *modus operandi* being, doubtless, the same as in t bite of venomous serpents. But, while this is true, it must also said that narcotism and intoxication were alike found to be conditio which co-operated powerfully with the original morbific cause in t rapid destruction of life.

Opium in full and repeated doses is, we conceive, under any circu stances to be avoided as a practice fraught with hazard, and not i frequently followed by irretrievably mischievous results.

Circumstances of local or general filth serve to undermine the healt and thus predispose to atttacks of cholera; for we hold it as an axi that those laboring under enfeebled or deranged health suffer most this, as in all other epidemics. We shall have occasion to observe, mo over, in the further examination of this subject, that all such causes s to be regarded in the light of tributary sources of supply for the pois generating cholera. Therefore, "cleanliness next godliness" become fit motto for general observance by municipalities, families, and in viduals.

What is the peculiar nature of the morbific principle? Where do it emanate, and in what manner does it operate to produce the sym toms witnessed in the disease? These questions have constituted t theme of elaborate and profound discussion for more than fifty yea past, and yet all that has been said and written has been designated the "endless and perplexing literature" of cholera. At the risk being classed among the contributors of this same sort of material, w shall offer some facts and some observations which we hope may n be deemed altogether unimportant.

In a report to the American Public Health Association on the subje of this epidemic, we employ the following language: "If it be true. physiologists assert, that hydrochloric acid naturally exists in the sto ach of every healthy person, we need not task ourselves very greatly comprehend the design of the great Creator in placing it there. It wa by virtue of its antiseptic power, to prevent the decomposition of o food before its appropriation by the assimilative organs."

ith the view of testing the solvent power of the acid, we instituted ies of experiments, the grand result of which was that fresh beef sted in water containing 33 per cent. of the acid for four and a half s at 100° Fahrenheit, and subsequently allowed to remain in the ra-mixture for twenty days longer, showed no appreciable solvent whatever. *The beef, however, when removed was remarkably firm, from taint, and in a perfect state of preservation.*

e known virtues of chlorine as a disinfectant, and those of its com- ds, chloride of sodium, chlorate of potash, bichloride of mercury, ide of zinc, &c., as antiseptics, give collateral support to this opin- ouching the true office of muriatic acid in the stomach.

ese experiments appear to negative the opinion so uniformly ex- ed by authors touching the office of this agent in the system. its solvent virtues may be enhanced by the presence of pepsin, as ested in a communication from my eminent friend Dr. J. W. Draper, that of acetic or other acids of the stomach, we are not prepared ny; but, in the absence of any proof of this fact, we are compelled cognize its prominent and principal virtues, as demonstrated by ex- ent, to be those of an antiseptic. If we are correct in our opinion ecting this property and office of hydrochloric acid in the stomach, ll readily be seen that its influence and importance are far greater have heretofore been ascribed to it.

a familiar but striking illustration of its effects in the way indi- l, we instance the result from a surfeit, particularly of animal food; *rrhœa emitting a highly putrescent odor usually succeeds.* Here the unt of food is simply in excess of the amount of acid present in the ach, and decomposition necessarily follows. One or two doses of atic acid, or of the hyperchlorinated tincture of iron, will generally e to correct the evil. But the field of its operations is not restricted e stomach. It has been found equally efficient in correcting chol- nd other poisons after they have entered the circulation. It will, fore, be readily understood why the existence of atmospheric ons, as during the epidemic prevalence of cholera creates, so to k, a double demand for hydrochloric acid in the stomach. If the ly of this agent is sufficient to repress the septic tendencies of our , and to correct the poisons which are continually entering the cir- tion through the medium of the lungs, no detriment to health will w; but if the supply is insufficient to meet this increased demand, ood will undergo decomposition, septic poisons will be generated, we shall thus have, figuratively, "a fire in both front and rear"— ons without and within—operating to produce the same results.

view of these facts, we can more fully understand why certain les of diet have been known to provoke an attack of cholera. The ting cause may be a highly-poisoned condition of the atmosphere, may be a piece of putrid pork in the stomach of the patient.

fore adverting to the effects of certain classes of morbific agencies pport of this opinion, we wish to express our individual regret that ors have generally found occasion to devote so little space to a con- ration of the diseases produced by them; for the causes are by no ns uncommon, and the symptoms are of the most alarming charac- For the twofold purpose, therefore, of exhibiting the importance is defect, as well as the influence of a class of poisons closely related f not identical with, those producing cholera, we instance—

t. *The effects resulting from eating putrid meats.*

mong other symptoms enumerated by Apjohn are: Absence of fever,

vomiting and purging, an extremely cold skin, a small pulse, and a *pended condition of the secretions.*

2d. *The symptoms occasionally following the eating of cheese, boiled tard, &c.*

We have not had access to a single author, besides the one just quo who devotes even a passing notice to the disease resulting from th causes. Fortunately, however, our own experience supplies the des information. In the year 1864 or 1865 a malady suddenly made its pearance in Cincinnati, Ohio, characterized by an absence of fe purging and vomiting, violent cramping of the voluntary muscles, skin, feeble pulse, and a general and extreme prostration of the powers, &c. We do no injustice to our intelligent professional frie there, who were engaged with us in the treatment of the disease, w we say that much difficulty was experienced and much care exerc before we were able to determine whether the disease was or was n genuine form of cholera. It was ascertained, however, the next that all the cases owed their existence to a cheese sold by an ho German at "Lower Market" the day previous. All who partook o were similarly affected.

We witnessed in this town, some two years since, similar results f eating boiled custard, a whole family, consisting of husband, children, two guests, and servant, all "down with the same complai at the same time.

The cause of illness is apparent in cases resulting from the us putrid meats; but there was no appreciable taint or impurity of kind in either the cheese or the custard.

We have adduced the effects of these respective agencies for the pose of exhibiting the parallelism of results from the palpable and palpable poisons. "Like causes will produce like results" is an ax not less true, *cæteris paribus*, we conceive, in medicine than it is in p ics. If decomposed organic matter *en masse* will produce the re observed from eating such substances, the same poisons will prod the same effects in an aeriform or miasmatic condition, modified, it m be to some extent, by the presence of exhalations from decaying ve table matter. The former, perhaps owing to their condensed form, require less time to operate than the latter.

* * * * * * *

Neither local nor general filth controlled, in any measure, the prese or character of the disease. A rigid surveillance was kept up by municipal authorities for fully a month prior to its advent; and town, for once at least "within the memory of the oldest inhabita was considered clean. Nor was defective drainage or ventilation served to exist in connection with any residence visited by the disea

A very general belief occupies the public mind that persons drink limestone-water are peculiarly liable to its attack.

We are not disposed to attach much importance to this popular c viction; but it must be admitted that the epidemic in its recent in former visitations has given some ground for this belief. If it w possible for the lime, existing in the water, to displace the hydro and give us chloride of lime, instead of muriatic acid, in the stoma we should regard the matter as plausible at least. But the possibi and probability of such displacement and combination in the alle presence of acetic and other acids, are questions which we leave to solution of the practical chemist.

UNION COUNTY.

A Mr. Pleasant Miller, who lived some eight or ten miles from L

Roads, Raccoon Valley, was at the city of Knoxville during the nic of cholera, in attendance upon his son-in-law who died of the e. Upon his return home Miller was taken with the same disease. s attended by a Dr. Lewis. Miller lived several days. On the sit of Dr. Lewis to Miller's house he found his patient dead. Be- e left the house Dr. Lewis was himself taken with the disease, and fter an illness of a few hours.

r the death of Miller, his son visited the family of Mr. Caswell living at Loy's Cross-Roads. This young man had been constantly is father during his illness. While at Mr. Sharp's, young Miller ken with a diarrhœa, attended with exhaustion; from this, how- e recovered after a few days' illness.

s case was followed by the death of Mrs. Sharp from cholera, and y the occurrence of three other fatal cases in persons who had in attendance upon Mrs. Sharp, and several cases of choleraic rea.

ER COUNTY.

abethtown, the county-town of Carter County, is located upon an at the confluence of Watauga and Doe Rivers, and is a short dis- off the line of the East Tennessee, Virginia and Georgia Railroad. own is situated in a mountain-district; the water-supply is good trongly impregnated with lime. The natural drainage of the y is good. Numerous sink-holes collect the surface-water. By this feature is supposed to influence the water of springs which e in their vicinity.

first case of cholera that occurred in this county in 1873 was in erson of one Perrion Daniels, a white man, seventy years of age, as taken with cholera July 30 and died August 1. This man had eturned from Jonesborough, where he had spent some hours with nd sick of the same disease. The day of Daniels's death his son ttacked, but recovered. These cases were followed by three others, whom had been in contact with the first case, but all recovered.

KINS COUNTY.

gersville is a small village of six or eight hundred inhabitants, and lways been noted for its healthfulness and the longevity of its in- ants. It is a valley shut in by hills and mountains. A small creek kett's) runs through the town and acts somewhat as a sewer. A h railroad some fourteen miles in length connects the town with East Tennessee and Virginia Railroad at a point called the Rogers- Junction. The town is distant by a straight line twenty-five miles Greeneville.

e first case of cholera occurred about the 6th of August, 1873, in erson of a man named Drain, an engineer on the branch railroad, ving been exposed to the disease by nursing a cholera-case at the ion some two or three days previous. Mr. D. lived in a house on reek near the grave-yard of the Presbyterian church, and used well- r. The water was not good, and suggested the probability of its olating from the grave-yard. The atmosphere at this time was very , oppressive, hardly a leaf stirring. Vegetation very rank. The es of the town at night-fall very offensive; no disinfectants had used.

e morning after Drain's death there was a general stampede of citi- many persons leaving with their families and thus considerably cing the population. Those that remained scattered lime, used sul- e of iron, carbolic acid, and attempted to purify the atmosphere.

Drain's clothing and bedding were burned and his house disinfected. His family removed to Knoxville.

On the 23d of August, two cases, both colored men, occurred on the same creek. These cases having been seen early, recovered, although slowly. On the same street, about three or four hundred yards from the house of the first case, a Mr. John Spitzen was taken on the 24th of August, and died the next day. Other cases followed in rapid succession. The citizens having been impressed with the importance of early treatment, most of the cases recovered. The total number of cases about twenty-five; the total deaths three, or one in every eight cases. No case reaching the stage of collapse recovered.

After the first cases the disease was not confined to any particular locality, but was scattered all over the village. Of the twenty-five cases, none occurred in families using cistern-water; those only were attacked who used spring or well water.

The treatment found most efficacious at first was calomel, morphia, and quinine, with external applications. This was afterward abandoned, and the treatment recommended by Dr. Sevier, during the epidemic at Jonesborough, substituted. This method of treatment was found to be efficacious. Ice and iced water were used freely.

Dr. J. R. Walker, to whom we are indebted for this history, writes: "The impression made upon my mind at the time was that the disease was portable; that it was brought to Rogersville from the junction by Drain; that it found a suitable nidus in the condition of our village, and that it propagated itself somewhat as other epidemics; that those individuals who used well or spring water were more liable to the disease; that the disease was very amenable to treatment if seen early, but that in the later stages no treatment was effective. Among the number of well-marked cases of the disease who recovered from the attack, three individuals were never again in good health. One died from organic disease of the stomach, the other two from chronic diarrhœa."

GREENE COUNTY—*Continued.*

In the narrative of the epidemic at Greeneville, Tenn., a note of some importance, for which we are indebted to Dr. James F. Breyles, was, through an unavoidable accident, overlooked. As this note contains some facts of importance, it is inserted at this point.

On the 1st of July, some days after the cholera-explosion of 1873 at Greeneville, ex-President Andrew Johnson was attacked with the disease. Shortly after the inception of the disease, Dr. Breyles was called to the charge of the case. "Found him laboring under a severe attack of what was undoubtedly epidemic cholera. Had copious rice-water discharges, attended with nausea and cramps. In great haste we administered calomel, gr. xx, with directions to his attendant to watch the effect, and if it did not procure consistent discharges in a given time, to repeat the dose. In three hours it procured a mixed evacuation. According to directions, a second dose, of the like amount, was given, which, in about five hours, produced the desired effect."

Mr. Johnson stated the next morning that all his uncomfortable feelings subsided when the cathartic effect of the medicine was procured.

After procuring consistent discharges in this case, whenever the bowels were too active, they were checked by an astringent mixture. Absolute rest of both mind and body was enjoined; the diet given was bland, with mucilaginous drinks. His recovery was slow, and could not be considered as fully established until after a lapse of about fifteen days.

CHAPTER IX.

ILLINOIS GROUP.

The narrative of the cholera-epidemic, as it affected the State of Illinois, is herewith presented so far as reliable statistics could be obtained. That other localities than those herein noted were infected with the disease is well known, but from the majority of them we were unable to obtain any information, while from others the facts were too meagre to admit of narration.

ILLINOIS CONTRIBUTORS.

Dr. Benjamin C. Miller, sanitary superintendent, Chicago.
Dr. John Reid, Cook County.
Dr. M. Tucker, Cook County.
Dr. W. M. Boyd, Cook County.
Dr. George Dale, Cook County.
Dr. C. I. Simons, Cook County.
Dr. N. S. Davis, Cook County.
Dr. L. Redford, Cook County.
Dr. W. E. Quine, Cook County.
Dr. W. Martin, Cook County.
Dr. H. Hayman, Cook County.
Dr. E. G. H. Mitzler, Cook County.
Dr. J. P. Rose, Cook County.
Dr. F. M. Wilder, Cook County.
Dr. H. P. Merryman, Cook County.
Dr. C. E. De Wolf, Cook County.
Dr. P. Metzmacher, Cook County.
Dr. A. W. Bosworth, Cook County.
Dr. G. Hepert, Cook County.
Dr. S. A. McWilliams, Cook Co.
Dr. A. H. Cook, Cook County.
Dr. Deanhurst, Cook County.
Dr. C. C. Buckley, Cook County.
Dr. E. W. Lee, Cook County.
Dr. L. Sauer, Cook County.
Dr E. R. Smith, Cook County.
Dr. G. G. Gull, Cook County.
Dr. Befeler, Cook County.
Dr. D. Cooley, Cook County.
Dr. E. V. Anderson, Cook County.
Dr. E. Landis, Cook County.
Dr. F. B. C. Bockins, Cook County.
Dr. S. D. Twining, Cook County.
Dr. N. I. Lund, Cook County.
Dr. V. E McClure, Cook County.
Dr. R. H. Harcourt, Cook County.
Dr. R. H. Bringham, Cook County.
Dr. F. Meyer, Cook County.
Dr. F. Hemotin, Cook County.
Dr. H. Wanzer, Cook County.
Dr. W. E. Frazier, Cook County.
Dr. C. D. Hews, Cook County.
Dr. J. J. Gordon, Alexander County.
Dr. G. G. Pabhler, Alexander Co.
Dr. C. W. Dunning, Alexander Co.
Dr. H. Wardner, Alexander Co.
Dr. T. Lawrence, Alexander Co.
Dr. J. D. Culley, Hendricks County.
Dr. Thomas, Greene County.
Dr. Brewster, Greene County.
Dr. Higbee, Greene County.
Dr. A. W. Foreman, Greene Co.
Dr. W. Vance, Randolph County.
Dr. W. M. Pierce, Washington Co.
Dr. J. McIlwaine, Washington Co.
Dr. Pace, Washington County.
Dr. J. J. Fyke, Marion County.
Dr. F. B. Haller, Fayette County.
Dr. E. Day, Jackson County.
Dr. R. T. Higgins, Fayette Co.
Dr. J. H. Stewart, Scott County.
Dr. E. L. Herriott, Jersey County.
Dr. W. O. Langdon, Jersey County.
Dr. A. K. Van Horn, Jersey County.
Dr. J. T. Pollock, Randolph County.
Dr. Patrick Gregg, Rock Island County.
Dr. Thomas Galt, Rock Island County.
Dr. F. B. Schultz, Jackson County.
Dr. L. H. Spencer, Jackson County.
Dr. G. M. McHenry, White County.
Dr. F. J. Foster, White County.
Dr. C. Cook, White County.
Dr. E. L. Stewart, White County.

Assistant Surgeon M. W. Wood, United States Army.

DATES OF INITIAL CASES.

Alexander County ..... May 2d and J
Cook County .....
Jackson County .....J
Greene County .....J
Marion County .....
Saint Clair County .....
Jersey County .....J
White County .....J
Scott County .....J
Washington County .....Au
Knox County .....Aug
Rock Island County .....Septe
Warren County .....Date not

ALEXANDER COUNTY.

Through Dr. Thomas Lawrence, of Goose Island, we have re the following interesting narrative of an outbreak of cholera occurred in his vicinity during the early days of May, 1873.

During the month of October, 1866, the steamer Belle of M landed at Goose Island, Illinois, and buried the bodies of three who had died on the boat from cholera.

Early in the spring of 1873 a saw-mill was located upon the a portion of which was occupied by these three graves. Before ever, the buildings were completed, the old graves were opene the boxes containing the remains of the cholera dead were remo new graves that had been prepared at some little distance. E the morning of May 3, the day after this work had been perf Dr. Lawrence was called to see a man named King, who was one party who had been employed in the removal of the coffins, and him in the collapse stage of cholera. He died within a few hours

During the next eight days eleven cases of cholera occurred employés of the saw-mill or in the persons of individuals living immediate vicinity. Of the eleven cases eight were fatal within hours of the attack.

Effort has been made to obtain a more elaborate history demonstration, but without success, owing to the illness Lawrence.

CAIRO, ILL.,

Is located upon a narrow point of land formed by the confluence the Ohio and Mississippi rivers. The location of the town is l subjected to frequent inundations. This town is the southern te of the Illinois Central and the Cairo and Vincennes Railroads, a northern terminus of the Mobile and Ohio and the Cairo and roads.

The facts upon which the account of the demonstration of the at Cairo is based have been obtained through the kindness of Wardner, of that city.

On or about June 15, 1873, a negro man from New Orleans cholera on Commercial avenue, in the city of Cairo. He had b only a few hours. The location was most miserable, and was oc by negro river-boatmen.

On the 20th of June a white man, from Memphis, Tenn., was

pon the streets of Cairo. He was taken to the city jail, where ight he was attacked with cholera. Early in the morning he harged, and a few hours later was found lying on the streets te of collapse. He was at once removed to hospital, where he a few hours.

23, the wife of the jailer, whose room was immediately over the ; had been occupied by the man from Memphis, took the disease, l after an illness of about seventy-two hours.

l, the wife of a German died, after a few hours' illness, of cholera. she had come in contact with the infection was not ascertained.

l, an Irish widow woman, who kept a filthy fish-stand and lunch- ar the depot of the Illinois Central Railroad, on the Ohio levee, cholera after twenty-four hours' illness.

st 16, a negro man from Carmi, Ill., arrived at his home in Cairo. having rice-water discharges when he arrived. In six hours he lapsed, and died within twenty-four hours.

s cases are given by Dr. Wardner as the only instances of occurring at Cairo during the summer of 1873. When it was ed that cholera was in the United States the city authorities the city to be thoroughly policed. All low, damp places, all , water-closets, and cess-pools, were disinfected with sulphate of rbolic acid, and lime. The cases that occurred were, with the on of the Memphis man, isolated, and their excreta thoroughly cted. It is undoubtedly the fact that by this thorough system of tion the city of Cairo escaped a most serious epidemic; for the ve of the epidemic, as it affected the counties lying upon the river, demonstrates that during the summer of 1873 the river- rs between New Orleans, Cincinnati, and Saint Louis were all l to a greater or less degree with cholera.

COUNTY.

RT ON THE CHOLERA-EPIDEMIC IN CHICAGO AND VICINITY DURING THE SUMMER OF 1873.

BY BEN. C. MILLER, M. D., *Sanitary Superintendent.*

cago, in common with many places in the West and Southwest, g the summer of 1873, was visited by epidemic cholera.

e cholera, since its birth in India, has at different times swept over orld, carrying death and terror in its course. Sanitary science has much to rob this most terrible of diseases of many of its terrors, n no epidemic has it been more clearly shown than in this. The e struck hardest where sanitary laws were least observed; but e good water, perfect drainage, and a strict observance of sanitary were observed, the disease was to a certain extent controllable.

e cases of cholera occurring in and about Chicago during the sum- f 1873 were principally in the Fifth ward, south of Thirty-seventh and west of State street, and in the adjoining town of Lake, is a continuation of this district, being separated from the city irty-ninth street. This district is a low, flat plain with sandy soil, werage, and imperfect surface-drainage, the house-drains empty- nto the open street-gutters in front of the same.

e water used at the commencement of this epidemic was from shal- ells supplied with surface-water, the wells being ordinarily from

5 to 15 feet in depth, walled up with pine boards, with the water ing from 2 to 10 feet, according to the state of the weather.

The inhabitants of this district are principally foreigners—Ger Swedes, and Poles—the families living in small rooms poorly vent and subjected at all times to the ill-effects of overcrowding.

From the beginning active measures were taken by the officers board of health; people were warned not to use the water from s wells, and the board of works were requested to supply the distric lake-water. This was done on Butterfield street on June 24; Bu street on July 13; Arnold street June 10 to 20. At Thirty-ninth public hydrants were placed for the benefit of the town of Lake. the wells were fouled with carbolic acid, so that they could not be u drinking or culinary purposes. There were outside of this distric teen cases of death reported from cholera in different parts of the ci most of them from two to four miles from where the first cases occ and in one exception in districts where filth and overcrowding w rule. No direct connection from the district where the disease prevailed and where most of the cases occurred was establishe no doubt the disease was carried from that portion of the city in to the various points in different parts of the city, as many perso the district as soon as the disease was known to be cholera. were six cases in the Fifteenth ward, (five miles from the district in the Third, one in the Eighth, three in the Sixth, one in the Thirt and one in the Twelfth.

The first case that occurred here was on May 24. at No. 444 A street, in the person of John McFee, a bridge-builder, who had working near Memphis, and left on account of the cholera. Wh arrived in Chicago he had diarrhœa, which remained unchecke after a week or ten days developed active symptoms, which resul death.

The second case occurred at 945 Butterfield street, on June 1 Danish family named Anderson, two miles from the first case. [I house a man named Lang was sick with what was supposed typhoid fever; he had lately arrived in this country by way of Orleans. At that time it was not suspected that the disease mig the continued fever of cholera. He recovered and left the house. house was occupied by several Danish families, and was very crowded.] After an illness of twelve hours the patient died. The was reported as "death from cholera morbus."

The third case occurred in the same house; a daughter of And was attacked on the 12th day of June and died in ten hours.

The fourth case, the wife of Anderson, was attacked on the 14th died on the same day, after an illness of twelve hours.

The fifth case occurred June 25, in the same house, in the pers F. Boessel, who had assisted in nursing the Anderson family. W nine hours from beginning of active symptoms he died.

The sixth case occurred June 30, at 922 Butterfield street, a directly across the street, in the wife of F. Boessel; she had rem from 445, but had been present during the sickness of the And family, and had cared for her husband during his sickness. She the second day of the attack.

The seventh case occurred on July 5, on Arnold street, between Th eighth and Thirty-ninth streets, a woman who had nursed the wom 922 Butterfield street. She died the same day she was attacked.

The eighth case occurred on the same day on the corner of Went

e and Fortieth street, a person who had nursed the seventh case roved fatal.
ninth case occurred at the corner of Arnold and Forty-first street. erson had nursed the eighth case; it proved fatal. The house in this case occurred was on the west side of the street. The excreta he patient were thrown out in the street in front of the house on st side of the street in which the tenth case occurred; from this lhe disease spread over the southern portion of the district. Other occurred in the vicinity of 945 and 922 Butterfield street, and from oint the disease spread south on Butterfield and South Dearborn .
n the retirement of Dr. Rauch I was appointed sanitary superin- t, and visited the district for the first time with Dr. C. J. Simons, sician residing in the district, and visited ten or twelve cases.
Simons was appointed a special sanitary inspector to enforce the ry regulations of the district. Thorough disinfection was done sanitary police, carbolic acid being used largely with sulphate of n the water-closets and for the disinfection of excreta. The above ectants were also placed, free of charge, in different portions of strict and the people urged to use them. Every house in the dis- was visited daily, and all cases of diarrhœa hunted up and re- l to the inspector, who took care of them immediately.
holera-hospital was opened for the care of patients, and all cases boarding or tenement houses taken there. A home was also d for the care of children in families where cholera occurred. All ren were promptly sent there, bathed, and clean clothing put on , and every care and attention given to their diet. Before the ng of the home the disease was as frequent among children as g adults, but of those sent to the home, thirty-five in number, one case occurred, and that did not prove fatal.
the cholera-hospital twenty-one cases were admitted, many of n were in the stage of collapse; these invariably died. Of those ved early in the disease, a large percentage recovered. Of the e number admitted, eleven died and ten recovered. The active sures used, the thorough disinfection and care taken, after a time, the use of pure lake-water, and the isolation of patients, seemed ontrol the disease. The cases that occurred here were evidently lar to those that occurred at Evansville and Mount Vernon, Ind., Nashville, Tenn.
n September 8, John Sheen was attacked with the disease on his ar- l in the city, he having just come from Evansville, Ind. His case ented all the symptoms, and was in every respect similar to the s that occurred here. The case terminated fatally after an illness of day. After this time no case occurred in the city. The first case stated came from Memphis. The second, third, and fourth cases lived in the city for some time, (but in the house with the patient posed to have typhoid fever.) The fourth case was an immigrant who been in the country two weeks, and in the house (No. 945 Butter- l street) one week. He had been feeling ill for a day or two, and r a dose of cathartic medicine was taken with purging and vomit- and died in nine hours. After this, all cases occurring here were ersons of residents, with the exceptions of eight or ten immigrants o had been in the city from two days to two weeks. At the time, the tory of these cases, (immigrants,) in the press of business, was neg- ted, and many points that would be of the utmost value in tracing course of the epidemic lost.

The effects of cleanliness on families and individual cases was mar
Those who observed sanitary laws, attended to the disinfectiou of
creta, and who were prompt in calling a physician, with few except
recovered, and the occurrence of a second case in such families was
On the other hand, where the excreta was not cared for and the v
permitted to lie on the floor, and the bedding (principally feather-b
used without being properly cleaned and disinfected, and where n
as paid to ventilation or personal cleanliness, several c
would generally occur, and, as a rule, prove fatal.

As but few cases were reported at the health-office until they
proved fatal, and then the treatment was not given, we had no d
aside from the cases at the cholera-hospital, by which to form an
mate of any plan of treatmen .

Dr. Simons, special inspect r, who had charge of the cholera
trict and hospital, reports that no treatment was pre-eminently
cessful.

The following will show the order of the value of the different m
ods of treatment:

I. The antizymotic (sulphurous acid) was perhaps the most sati
tory.

II. Anodyne, hypodermic injections, and Squibb's mixture.

III. Alteratives, calomel, &c.

Of the cases neglected in the beginning, 50 per cent. died unde
treatment; of the cases taken early in the premonitory diarrhœa, be
vomiting had occurred, 90 per cent. were saved. I think the percen
given in both cases much too high, taking the cases that occurred at
hospital.

The prescription used in the antizymotic plan was composed as
lows, with the morphine varying to suit the case, (Squibb's:)

℞	Sulphurous acid	℥ij.
	Sulphite magnesia	℥ij.
	Tr. capsici	℥iv.
	Aqua	℥ij.
	Morphia	q. s.

Dose: As a preventive, half teaspoonful morning and evening, without morphia
a remedy, with morphia, teaspoonful every half to one hour.

The annexed tables will show the number of cases, average durat
of disease, and the meteorological conditions during the time the
ease prevailed in the city.

At South Chicago, ten miles south of the city, on the Michigan So
ern Railroad, several cases occurred similar in every respect to th
occurring in the city. Cases also occurred at Roseland, on the Illin
Central, and also in the immediate vicinity.

r statement of fatal cases of cholera and cholera morbus reported to the Board of Health; also of fatal cases occurring south of the city limits.

Ward.	May.	June.	July.	Aug.	Sept.	Total.
			2			2
		4	14	3	2	23
	1		1	1		3
			1			1
				1		1
th				1		1
h				4	2	6
l				10	1	11
tal	1	4	18	20	5	48
uth of the city limits reported rd of health			3	12	2	17
at Oakwoods Cemetery from e the city limits—not reported			1	8	6	15
tal			4	20	8	32
and total	1	4	22	40	13	80
e duration of the disease	2 weeks.	16½ hrs.	45 hrs.	40 8-10 h.	35 hrs.	
morbus			16	8	8	32
morbus, (south of city limits)			2	1	1	4
tal			18	9	9	36
umber fatal cases cholera and a morbus	1	4	40	49	22	116

* * * * * * *

ew medical gentlemen of the city of Chicago deny that epidemic ra existed in that city during the year 1873, contending that the cases that occurred were cases of septic cholera, and that there ed sufficient local causes to account for their occurrence. In this of the case we present a most interesting letter from the pen of a ul observer:

CHICAGO, ILL., *September* 5, 1874.

DEAR SIR: In compliance with your request, I have the honor with to furnish a brief statement of some of the local influences to h the inhabitants were subjected in the principal districts of Chi- in which the so-called Asiatic cholera epidemic prevailed during months of May, June, July, August, and September, 1873. These ences may very properly be considered under the heads of—

The situation;
The water-supply;
The drainage;
The food; and,
Other hygienic influences.

ere was reported in May, 1 case; in June, 4 cases; in July, 18 s; in August, 20 cases; and in September, 5 cases, (*vide* report of d of health.) Brevity forbids a more lengthened description ot situation than this. This district is one of the lowest parts of this riously low city. The soil is a very porous, sandy loam, underlaid stratum of quicksand; near the surface of the ground water stands ughout the year. The water-supply was from surface wells of the known as "drive-wells," (*i. e.*, sections of fenestrated pipe suc- ively driven to the required depth, and through which the water was ined by suction-pumps,) and was so obviously impure that the in- itants were accustomed to first pump out the *stagnant* water from pipe and use that only which succeeded, and which was freshly

filtered, (for some know these wells as filter-wells.) An average spe
men of the *purest* water, which I carefully examined, was found to c
tain 91+ grains of oxidizable organic matter to the gallon. Yet t
water contained no impurity visible to the naked eye until after sta
ing for some hours. The specimen which I examined I pumped int
clean vial, quickly closed it with a new cork, immediately covering
cork and neck of the vial with sealing-wax.

The only drainage artificially provided was that obtained by
ditches on either side of the roadway, from which only sufficient ea
had been removed to raise the roadway to a height sufficient to ren
it passable during the wet seasons, at which time only light-draug
wagons can safely venture upon these streets. The privies, where su
luxuries existed, were of necessity very shallow, from 1½ feet to 4 f
in depth, and sufficiently near to the wells to insure their contamin
tion. In many cases the excreta were either voided upon the ground
into vessels which were emptied upon the ground. The refuse from
kitchens, garbage, and slops of every kind, were generally thrown fr
the back-doors of the houses upon the ground.

It will readily be seen, thus, that the principal source of drainage
through these wells, which were frequently driven to a depth of 7 o
feet; generally, however, but about 6 feet.

The inhabitants were composed largely of the families of unskill
laborers, who, on account of their ignorance and imperfect knowled
of the English language, were imposed upon to such an extent that
per day was considered good wages among them.

From this pittance, in many instances, large families were fed
clothed; rent from $8 to $18 was to be paid; and a part was to be l
by for the home of which they all expect sooner or later to beco
possessors.

Their meat-supply was of the poorest; the meat-market in the vicini
compelled to sell them meat from 3 to 7 or 8 cents a pound, was una
to furnish for them any but the poorest of Chicago's poor meat, (for it
a well-known fact that a large part of the meat sold in the city is s
as will not pay for transportation to eastern markets, *vide* board of he
report.) The animals on their arrival here are assorted; the poorer o
the weaker ones, and the maimed ones, are turned over to the slaugh
houses here, for the supply of the Chicago market, and the better o
are forwarded; and yet Chicago has *one* meat-inspector!

Something of this may be learned by consulting pages 166 and 16
the board of health report; from which we learn that, among m
other articles, there were condemned: 611 quarters of beef, 21,880
corn-beef, 13,434 heads of cabbage, 2,476 dozen eggs, 2,693 musk-m
ons, 2,067 lbs. fish, &c., &c. And as to how much was eaten that sho
have been condemned we can only conjecture. And these things w
furnished to poor people to enable them to live *cheaply!* Their suppl
of vegetables were obtained from hucksters, who each morning obtai
from the markets the unsalable and stale articles which had been l
over from the previous day; thus they were enabled to sell cheaply!

Some of the other unfavorable hygienic influences to which these p
people were exposed were—

a. Personal filthiness;
b. Customs of life;
c. Overcrowding, and consequently—
d. Defective ventilation;
e. Proximity to sources of emanations of foul gases; and—
f. Prevalent winds.

These people were very filthy in their persons; whole families were ten crowded into a small room reeking with filth; sleeping between thy feather-beds; keeping the windows closed, in many instances, to event draughts.

In the direction from which the prevalent winds come (*i. e.*, the south-est and the west) are located the great Union stock-yards, the slaugh-r-houses of the city, several rendering establishments, where the dead imals of the city are disposed of, (of which we learn from the re-ort of the board of health that there were 11,347 during the year 1873;) rge glue factories are also located here; and, but a few feet distant om the greater part of this district are the tracks of the Lake Shore d the Rock Island Railroads, on which were kept standing long trains empty cattle-cars, filthy in the extreme.

An idea of the odors from these sources may be obtained from a con-deration of the fact that many times, when the southwest wind came suddenly, vomiting and purging were caused even among the accli-ated.

The board of health thus sum up the causes of the offensive smells:

a. The filthy condition of the slaughter-houses;

b. The operation of rendering;

c. The contamination of the river by their sewage;

d. The deposit of offal within the city limits and adjacent thereto.

The mean temperature for the eleven weeks ending August 30, 1873, d during which time this so-called Asiatic cholera prevailed, was 72¼°, and that the rain-fall during this period was 6¼ inches.

Very respectfully,

M. W. WOOD, M. D.

Dr. E. McCLELLAN,
Assistant Surgeon U. S. A.

Doctor Wood's letter is of great value, as demonstrating the sanitary ondition of the locality in which the disease occurred. It would have een difficult to have found a locality presenting more favorable aspects an this; the hot-bed for the propagation of disease was made ready, t cholera did not appear until after the Memphis and New Orleans rivals.

ACKSON COUNTY.

This county is in the southern portion of the State of Illinois, border-g on Missouri. The county is bounded on the southwest by the Mis-ssippi river, and is intersected by the Big Muddy river and other reams. The epidemic of cholera in this county, so far as we are able obtain information, was confined to the town of Grand Tower, which wn is the terminus of the Grand Tower and Carbondale Railroad, and also a stopping-place for river-packets.

The information which we have been able to collect is embraced in the llowing letters:

GRAND TOWER, ILL., *October* 21, 1874.

MY DEAR DOCTOR: In forwarding you a statement of the few cases cholera Asiatica which came under my observation during the prev-ence of the disease in 1873, I would remark that nothing new was veloped, or at least detected, giving any new features to this formida-e malady, and nothing new discovered in regard to its remedial man-gement. In Grand Tower the disease was of a sporadic character, and did not manifest its usual portability or contagiousness, as two per-ns only were attacked by it in the same house.

All or nearly all the cases of cholera that occurred here, of which t
previous history of the patient could be obtained, were found to ha
been induced by some departure from their usual habits—some exc
in eating, drinking, or physical exercise—some palpable violation of
hygienic laws of health.

The first cases in this portion of Jackson County occurred on
Muddy, about six miles from this place, in a locality rife with malari

Very respectfully, &c.

E. DAY, M. D

Dr. E. McCLELLAN, *U. S. A.*

II. GRAND TOWER, ILL., *November* 12, 187

MY DEAR DOCTOR: I herewith acknowledge the receipt of your fa
of the 28th ultimo, asking for further information, in addition to th
already communicated in my report, relative to the exposure of my
tients of last year to cholera infection.

In regard to my first case, William Potter, after the most pati
inquiries, I am unable to ascertain that he had been in any way expo
to the infection of cholera; indeed I think that, up to the time of
attack, no cases had yet occurred in the city. He was not away fr
his home or neighborhood for some months prior to his attack, with
exception.

On the 4th of July, contrary to his usual habits, he walked five
six miles into the country, (the heat of the weather at the time be
excessive, the thermometer ranging from 96° to 100° in the sha
drinking freely of water, and returned home the same day much fatigu
He visited no locality where the disease existed. On the evening
the 5th of July he was taken sick with probably prodromic diarrh
I saw him for the first time at 7 o'clock a. m. on the morning of the 6
and found him in a state of collapse, almost pulseless, vomiting a
purging, with cramps, and with a cyanosed skin. He rallied under tre
ment, but sank again and died early on the morning of the 7th.

The evacuations from the bowels of this patient, on the morning
the death were of a *dark red color*, resembling beef-brine, very thin a
containing much flocculent matter. This peculiarity of color in the ev
uations was observed by Dr. Spencer with his cases of cholera wh
terminated fatally on Big Muddy River, in June of the same year.

My second case was McCoy, a colored man, who came from Cobd
Ill., about the 20th of August. He had had a diarrhœa for a we
before the attack of cholera. Was engaged at the Big Muddy Iro
Works in this place, and on the morning of the 28th of August, at
o'clock, was taken sick. I visited him for the first time at 2 o'clock
m., and found him in a state of collapse from cholera; vomiting, ri
water discharges, cramps, and the vox choleraica. He died at
o'clock p. m. August 28. In this case I also failed to discover any
posure to cholera infection.

A negro woman named Dye, the mother-in-law of McCoy, who h
nursed him during his illness and had washed his clothing after his deat
was taken sick on the 1st of September and died the same evening.
other cases occurred in this neighborhood.

My third and last case was J. S. Duncan. He was an active busine
man, although he had suffered for many months with chronic diarrh
On the 30th of August he walked from the city to the Big Muddy Riv
and returned the same day, a distance of about twelve miles. He w
taken sick early on the 31st. I visited him for the first time about
o'clock p. m., and found him in a state of collapse from cholera, wi

the usual symptoms. He never reacted, but died about 12 o'clock the
ne night. No other cases occurred in this neighborhood.
t is possible that this patient may have been exposed to the infec-
n while in the locality he visited on Big Muddy, as the cholera first
de its appearance there in June, although I can obtain no proof that
visited this exact nidus of the disease.

Very respectfully, &c.,

E. DAY, M. D.

Dr. E. McCLELLAN, *U. S. A.*

GRAND TOWER, ILL., *November* 3, 1874.

DEAR SIR: In answer to your inquiry concerning the cholera cases
orted by me, I find, upon inquiry, that Cummings (my first case)
only been a short time in this locality. His history prior to this is
known. He was a fisherman by occupation, very dissipated in his
bits, and had been upon a prolonged debauch when he was attacked.
his case the disease lasted but a few hours, and he died fully col-
sed. Of the individuals who were about him during his illness, five
es occurred during the next four days; of these cases three died.
e exact number of persons who were present in his sick-room I cannot
ascertain, but think they were about fifteen.

Respectfully,

L. H. SPENCER, M. D.

Dr. E. McCLELLAN, *U. S. A.*

Prior to the occurrence of the first case in the town of Grand Tower,
Spencer reports ten cases as having occurred on the Big Muddy
er, six miles from the town. The first of these cases occurred June
the last July 3. Of the first ten cases five were fatal.

July 4, the patient of Dr. Day walked out into the country six or eight
les. The next day he was taken with cholera. From the 7th of July,
date of death of Dr. Day's first case, until the 28th of July, there are
ht cases reported as having occurred at Grand Tower by Doctors
encer and Schulz. Of these eight cases five were fatal.

From July 28 to August 28 but one case is reported, viz.: on August
by Doctor Spencer. This case terminated fatally, but the record does
t show whether this case occurred in the town or on the Big Muddy.

August 28 a negro man, from a point on the Illinois Central Railroad,
obden,) forty-two miles north of Cairo, Ill., died with cholera after
diarrhœa of a week's duration.

August 30, a gentleman walks out to the Big Muddy, and dies of
olera the next day.

September 1, the mother-in-law of the negro who died on the 28th,
kes the disease and dies.

September 3, Doctor Spencer records a recovery in the person of a
dy living near the Big Muddy.

A total of twenty-four cases is reported, fifteen of which were fatal.

WHITE HALL, GREENE COUNTY.

White Hall is a small prairie town of Greene County, Illinois, about
enty-five miles southwest of Jacksonville, with which city it is in rail-
ad communication.

At this point the earliest cases occurred July 4 and 5, in the persons
Mr. and Mrs. Peter and Mr. Charles Ballou, who all three arrived at
White Hall, bringing the body of the father of Mrs. Peter, who had died

of cholera at Louisiana, Mo. Of these cases Mr. Peter died; the ot two recovered.

It is stated that at an earlier date (June 21) a young man nar Morris, who was a Saint Louis "drummer," had an attack assimila cholera, from which, however, he was ill but a few hours.

A few cases followed the arrival of the Peter family, two of wh proved fatal.

We are indebted for the foregoing particulars to Dr. E. Thoma Greene County.

MARION COUNTY.

Odin is a small town of Marion County, located at the intersectio the Ohio and Mississippi and the Chicago branch of the Illinois Cen Railroads. The town is sixty-five miles east of Saint Louis, one hund and twenty-one miles north of Cairo, and about two hundred south Chicago.

We present the following extracts from a communication of Dr. J Fyke, of Odin, in which the facts of the demonstration are narrated

"The first cholera patient was a young man who had been at w harvesting in the bottom. He had been eating and drinking more t he was accustomed. He returned home in the evening of July 4 w a diarrhœa. During the evening he wandered about town, and at t o'clock a. m. was seized, while at the railroad depot, with vomiting a cramps. When first seen by a physician he was in collapse, and died about five o'clock p. m. It is stated that there had been sev deaths of the same disease in the neighborhood (near the Mississi river) where he had been working.

"On the evening of July 7 there was a violent storm of wind and ra by which most of the privy-vaults in the town were filled to overflo ing, and on the 8th cholera became epidemic in the town, continuing force until the middle of September.

"The weather was very warm, with occasional showers of rain. T streets and alleys were in a very dirty, filthy condition. The wa for domestic use was all obtained from shallow wells, and is limesto in character. Most of the wells were filled from surface-washings duri the storm. From two to three cases occurred every week until t middle of September, when the authorities put a force of men to wo cleaning the streets, when the disease suddenly disappeared. The cas that died were not seen by the physicians until in collapse. Near every person in the town had more or less of the premonitory symptom but they yielded readily to treatment whenever they were taken in t early stage. The treatment consisted in external warmth, the use opium, mercury, carbolic acid, camphor, quinine, ammonia."

SAINT CLAIR COUNTY.

We have received information as to the cholera epidemic of 1873 as affected two townships of this county.

I. Lebanon, a small town upon the line of the Ohio and Mississip Railroad, twenty miles east of the city of Saint Louis, having a popul tion of about two thousand. This town occupies a high and well-draine site, and is the center of a rich farming district.

Dr. R. F. Cunningham, of Lebanon, furnishes the following histor of the epidemic:

"The first case of cholera occurred July 4, in the person of Charl Schmidt, aged twenty-three years, living six miles northwest of th

n, who at 9 o'clock a. m., in the harvest field, was taken with diar-
a, which increased in violence; was accompanied with vomiting, and
ips of the extremities. At noon I was sent for; arrived at the case
t 2 o'clock p. m.; found the patient in collapse, and with all the
acteristic symptoms of cholera. He died in an hour after my
val.

There had been up to this time in the district no indications of the
ase, nor had there been more than the usual number of cases of
le diarrhœa. It came upon us like a thunder-clap from a cloudless

At the time Schmidt was attacked with cholera there were three
ngers, of whose history I know nothing, at work in his (Schmidt's)
est-field. These men also having diarrhœa, became alarmed, and
ing the field in the afternoon, came to Lebanon. On the road their
ptoms increased in severity so much that it was with difficulty
reached the hotel on the railroad one mile south of the town. In
ort time after their arrival I was called, and found one man in the
nning of, and another well advanced in, the second stage of the dis-
. Although actively treated, both died. The third man left the
n, and his fate is unknown.

July 7.—Mrs. S., aged forty-four, and her daughter, aged seven years,
mother and sister of Schmidt,) were taken during the night with
rrhœa, followed by vomiting and cramps. They were immediately
ed under treatment, and both recovered.

July 8.—Charles Busch, aged thirty-five years, living one mile from
midt's, and nearer town, was taken with the premonitory symptoms,
recovered.

July 11.—Two children of C. Haas, aged respectively eleven and
teen years, living one mile nearer town than Busch, were taken with
lera; one died, the other recovered.

July 17.—George Drissell, aged thirty years, died of the disease.

July 19.—Mrs. Busch, the wife of the third case, was taken with
lera, and died the next day.

These cases were followed by eight others in the same community,
whom three died.

All of these persons were well-to-do Germans, whose manner of liv-
was as is customary with their nation. The time was during and
t after harvest, when their indulgence in food and drinks was greater
an usual, and no doubt acted as predisposing causes, aided by the ex-
ustion consequent upon increased work and intense heat. The dis-
ct in which they lived was a rolling country, timbered with oak, hick-
, and black-jack, which latter growth, from its abundance, had given
name to the lower portion of this settlement. A creek flows diago-
lly through the settlement, but all the farms are upon high or rolling
ound. The district is not considered unhealthy. The soil is a dark
m, and the subsoil clay. The water is slightly limestone, and is
tained by digging from 25 to 30 feet. There was no accumulated
h outside the habitations. The wells were in fair condition and the
ter good. There was no local cause known to me by which the dis-
se could have been produced.

"It will be remembered that two of the harvest-hands on Schmidt's
rm died of cholera at the railroad hotel on the 5th day of July. Seven
ses of cholera occurred among persons living in the vicinity of this
otel, three of whom died.

"This district lies at the foot of the ridge on which the town of Leb-
non is built, and is distant about one mile from the town proper. The

town during the entire season was unusually healthy, there bein more, if there were as many, cases of common diarrhœa as is usu that season of the year."

From Dr. F. W. Lytle, also of Lebanon, we learn that the funer Schmidt was attended by his neighbors, and that among them the sequent cases occurred. That in the depot-addition to the town of anon there were seventeen cholera-deaths, being 10 per cent. o population of that portion of the town. That in addition to deaths fully one-half of the residents suffered from diarrhœa.

The treatment adopted was calomel and opium, in moderate often repeated; hypodermic injections of morphia; sinapisms to men; embrocations of ammonia and turpentine; chloroform, tinct. sicum and camphor, with alcoholic and diffusible stimulants in the stages.

CASEYVILLE.

Caseyville is a small town of Saint Clair County, Illinois, upon line of the Ohio and Mississippi Railroad, ten miles west of the ci Saint Louis, Mo. The location is decidedly in a malarial region, surrounded on the east by a broken hilly country, and on the wes the Mississippi bottom, which is interspersed by small lakes of stag water.

On the 8th day of July, 1873, a child of Patrick Roach, a sec "boss" on the Ohio and Mississippi Railroad, was taken ill with at the time was considered by Dr. L. T. Miller, who was called to at the case, an attack of cholera infantum. The child had not been o the village, but the father was constantly exposed to passing trains, to contact with other railroad employés. The case terminated fatally few hours.

The next day the father was taken with vomiting, purging, cramps; rice-water dejections soon occurred, and collapse was immi This man had been troubled with a looseness of the bowels for a da two, but had utterly neglected it. A few hours after Roach was tacked, his wife was taken with the same disease and passed rap through the stages. At the end of the first twenty-four hours R seemed to be reacting, but the wife presented every symptom of proaching dissolution. At the end, however, of the next twenty- hours this condition of affairs was reversed: the wife reacted and a tedious recovery, but the man relapsed and died.

In a house adjoining that occupied by the Roach family lived Shannon, whose daughter, a girl twelve years of age, repeatedly vis the sick-room in the Roach house. This girl was taken with cho and died after a short illness. During her illness she was visited by brother, who lived several squares distant; he took the disease died, but without infecting any other person in his house.

The disease next appeared in the family of one Clark, who was a relation of the Shannon family, and whose family had been in cons attendance upon the previous cases. John Clark, jr., aged about e teen years, was the first attacked, and in rapid succession his sis sixteen years old, his aunt, his mother, and young brother were tacked; the first four proved speedily fatal. In this family the im ative orders of Dr. Miller were not carried out. The dejections were mitted to remain in the room and upon the floor.

William Schaeffer, aged about thirty-five years, who lived close to Clark family, and Thomas Booth, who lived in a portion of the Ro

, were next attacked, and died; but the disease did not spread them, with but one exception.

on of A. J. Bunker, who lived about a block from where Schaeffer ied, was next attacked, and died. The father had been in attend- upon Schaeffer, and passed constantly from the sick-room to his ouse.

on of John Jones, aged about eight years, whose mother had been ntly in the sick-rooms of the Clark family, was attacked with a, but recovered.

Miller is strongly of the opinion that many of these cases might been saved had they been subjected to treatment at the inception disease. He reports that a great number of cases occurred of œa, attended with exhaustion, that yielded to rest and treatment. to the use of disinfectants, Dr. Miller writes: "So soon as I be- satisfied that we had true cholera in our midst, I advised the st cleanliness in all families affected by it. I urged upon the town rities the necessity of having all the premises disinfected, and all nces about the town abated. At first my advice was unheeded; emed to treat the matter lightly, as though each case would be the ot seeming to comprehend the necessity of disinfection. But when aw it beginning to be a serious affair they all went to work. Crude lic acid, chloride of lime, and copperas were freely used in all neces- ocations. From the time we began the use of disinfection not a new case of the disease appeared; whether from the use of disin- nts, or coincidently, I am, of course, unable to say. Disinfection was nued about one week, when, the excitement and the cholera having led, it was discontinued."

EY COUNTY.

fton is a small town, of about 1,500 inhabitants, located on the ssippi river, and receives its supplies by river transportation.

e following letter contains the only information we have received the epidemic at this point:

GRAFTON, ILL., *October* 29, 1874.

AR DOCTOR: While our little town of only about 1,500 inhabitants, hey scattered over a considerable territory, is never subjected to demoralized sanitary conditions as that of large, compactly-built , and especially those of the warmer climates, we are left untram- l in many of the speculative suppositions that are connected with atter localities, and we should be able to arrive at a more concise lusion as to the nature and cause of the disease under consideration is locality than in many others.

very close proximity to our town are extensive rock quarries. equently a goodly portion of our population are laborers and quarry- mostly Irish, many of whom are transient residents, of bad habits, rowded into low boarding-houses. But, instead of this being the attacked, the disease of 1873 occurred chiefly among those in circumstances, who could not possibly have been exposed to a n emanating from a previous case.

me of these patients used cistern-water, others well-water of good acter.

1866 the first cholera case was in the person of a blacksmith of ated habits. Nearly all the cases that followed were transient ents who lived in crowded boarding-houses.

1873, except in two instances, but single cases occurred in the

same house, and in the two exceptions there was no reason to l
that either one was induced by contagion.

In 1866 we were of the opinion that the disease was transmitte
the city of Saint Louis, as it prevailed there at that time extensi

In 1873 it was claimed by some of the leading physicians of th
that they did not have a genuine case of Asiatic cholera, and bu
few cases simulating it; so there is but one rational conclusion t
can arrive at, so far as can be observed in this locality, and that
the cause existed in the atmosphere in certain localities of the
probably in the shape of poisonous gases, producing the disease i
systems most peculiarly susceptible at the time of contact.

Not being a microscopist, I was not able to examine the bloo
there was one peculiarity I wish to mention that I have never ob
in any other cases; that is, on the introduction of the hypodermic
after penetrating the epidermis, it would then go any length w
meeting with scarcely any resistance, and the skin could be raised
as if almost the whole covering was detached from the tissue
neath.

As a prophylactic I advised from one to two grains of quinine,
two or three times a day; and although I have no positive proof
did good, I have the satisfaction of knowing that no one who to
medicine was attacked with the disease.

Respectfully,

E. L. HERRIOTT, M

DR. E. MCCLELLAN, *U. S. A.*

The first case at Grafton occurred on the 15th day of July
person of a white laborer.

The second case occurred July 16 in the wife of a ship-carpente

The third case occurred July 17 in the wife of the superintend
the stone quarry, and upon the same day the two young children
white laborer were attacked.

July 18 the wife of a contractor was taken ill.

July 19 a German shoemaker was attacked.

July 30 a white laborer and the wife of a white laborer are bo
ported.

July 31 a white female, the keeper of a boarding-house, was
sick.

August 2 a widow lady was taken sick. All the preceding
terminated fatally. Two other cases are reported, both of who
covered; one the wife of a prominent physician of the town, the
a laborer.

It is submitted as a comment upon the list of cases which Dr. He
has kindly furnished, that they all, with but a single exception, occ
in the class of persons who would be most exposed to an insidio
fection.

The epidemic is next reported in Jersey County, at the town of
a small town upon the line of the Chicago and Alton Railroad, fou
miles northwest of Alton and thirteen miles from Grafton. A
point, on the 20th day of July, a young man named Watson was
with cholera, and died after an illness of twenty-four hours.

July 22, Mrs. Fuller, the mother-in-law of Watson, who had nursed
was taken with cholera, and died within ten hours. Four other me
of the same family were subsequently attacked and three d
occurred.

ing the remaining days of July four other cases occurred at with one death.

ust 17 a young man named Sunderland was taken with cholera. case, although collapse was profound, reaction occurred and he red.

rother of Sunderland came from a distance to assist in nursing On the 22d of August this young man was taken with cholera, ed after a few hours' illness. The same day the father was attacked ed within twenty-four hours. Subsequently, four other members same family, and Dr. Langdon, who had been in assiduous attend- pon them, were attacked, but all five recovered. The house at these cases occurred was upon a high hill, and removed from all al influences.

Langdon reports that in the families where cholera occurred every er suffered with diarrhœa. "I must say that this location is the last place you would expect to find cholera, being very high ell drained. The town is small and scattered, and all the cases ccurred, except one, were in good, clean families. From July 20 gust 25 I treated over twenty-five bad cases of cholera morbus arrhœa."

treatment adopted was eliminatives, with astringents and stimu- warm applications, frictions, &c. Disinfectants were use in every

E COUNTY.

mi, the county town, is situated in the center of a rich agricultural ry, located upon the west bank of the Little Wabash River, and point of junction of the Cairo and Vincennes, and the Saint Louis outheastern Railways. This town has about two thousand inhab-, fifty of whom are negroes. The district is decidedly malarial, ugh the community has not in previous years suffered to any extent epidemic diseases. The town is built upon a bluff, which is broken rregular by ravines, which had been formed by the drainage into ver. The soil is a rich alluvial upon a sandstone base. The water- y is obtained principally from wells of from 18 to 20 feet in depth. better class of residences are, however, supplied with cisterns. The es consist of pits dug 6 or 8 feet.

1873, cholera having become epidemic at the city of Evansville and town of Mount Vernon, the first thirty-six miles, and the latter teen miles east of Carmi, an effort was made to place the town in od sanitary condition. A board of health was organized, which sted of Dr. E. S. Stewart, who was at that time the mayor of the and Drs. Linthicum and Cook. All *debris* possible was removed destroyed, stables and other out-houses were cleansed, privies were fected, and every possible precaution was taken to leave no spot in ition favorable to the rapid propagation of the cholera-poison, should carried into the town. Early in the epidemic a pest-house was nized, to which cases were removed.

bout the 13th day of July, a man named Frederick Sell went to nsville, Ind., to attend the funeral of his father-in-law, who had died at city of cholera. On the 15th he returned to his home at Carmi, the next day (July 16) was attacked with cholera. Sell was a brick- er, lived near to his yard, and a number of the hands in his employ l in the house he occupied. After an illness of eight or ten days ecovered and was able to resume his business.

uring the evening of July 16, William Sell, aged 16 years, the son

of Frederick, was attacked with cholera. The disease was fully oped. After being collapsed for some hours, reaction was estab but committing some imprudence he relapsed, and died upon Jul

July 19 a Mrs. Taylor, who occupied a portion of the same hou attacked, and died at an early hour the next day.

July 21 Mrs. Sell and her daughter, and a man named Haffal was in the employ of Sell, were taken sick; the women recover the man died after an illness of eight hours.

July 22 a man named May, also an occupant of the same hou attacked and died.

July 24, a man named Deitz, who also lived at this house, died same disease.

July 25, a young child of Sell also died.

During the progress of these cases, the excreta had been buried careful disinfection with carbolic acid; but as it was determin this process had not reached all the material that had become in the survivors were removed, and all articles of bedding and cl were destroyed with fire. From this house the disease spread a came epidemic in the town. Thirty-four cases are reported, with deaths, as having occurred after the last case at the Sell house.

On the 31st of July, a Mrs. Burrell was attacked with cholera home in Carmi, and died after a few hours' illness. Before she di brother, Mr. Rabstock, a farmer, living some five miles north of came to visit her. He remained until after the death of Mrs. B when he returned at once to his home. The next day Rabsto diarrhœa, which was neglected for several days, and on Au cholera was developed, from which he was not convalescent unt tember.

August 10, Mrs. Rabstock was taken sick and died after a few illness. Before the death of the mother, her three children had taken with the same disease, one of whom died.

August 11, a young daughter of Rabstock was taken ill; she re but, being excessively imprudent, the disease was redeveloped, a died on the 16th.

This family had been nursed during their illness by a married d ter and her husband, named Swale. After the death on the 16 survivors moved to a house some miles distant that had been u pied for a length of time; but on the day after their removal both and his wife died of the same disease.

During the illness of Mrs. Burrell, a young man of depraved h named Honn, who lived at Phillipstown, a small village nine miles Carmi, came to town and got upon a spree. He slept the night a Burrell's house and the next day returned home. After a few during which he neglected a diarrhœa, he was attacked with ch and died after an illness of ten hours. He was nursed by his si Mrs. Ray and Miss Honn, and by his brother.

August 8, two days after Honn's death, Mrs. Ray was attacke died the next day.

August 12, the brother was attacked, but recovered after a s illness.

August 14, Miss Honn was attacked and died.

August 15, Mrs. Honn, who had been in attendance upon her hus who was still ill, and upon her two sisters-in-law, took the same di and died.

August 16, Dr. George B. Tucker, who had attended professio this group of cases, also died.

ust 31, a man named Birdsong, who had been at Carmi upon a
or several days, was taken with cholera at his home in the coun-
ree miles west of the town. The disease was developed at 3
a. m., and at 1 o'clock p. m. he was dead. Every member of his
suffered from diarrhœa, but by rest and active treatment all re-
l.
tal of fifty-five cases are reported as having occurred in White
, of which thirty-four terminated fatally. Of these cases thirty
nales, twenty-five females. Fifty-four were in the persons of
one was a negro. Twelve cases occurred in individuals less
enty years of age, six of whom died.

COUNTY.

CHOLERA AT EXETER, ILL., IN 1873.

BY W. C. CARVER, M. D.

er is one of the oldest towns in Scott County. In selection of
a sanitary point of view, it competes favorably with any in the
being a rural, picturesque village of between four and five hun-
habitants, built on the brow and sloping side of a hill, around
se of which winds its serpentine course the Mauvaisterre Creek;
il a mixture of clay, loam, sand, and gravel, the clay largely in
of the other constituents. Through the subsoil, and for a con-
ble depth, is plentifully distributed lime and sandstone, with
ying strata of bituminous coal. The water-supply of the town
wells, which vary in depth from 28 to 40 feet. This water is very
mpregnated with lime, and during times of drought becomes very

Mauvaisterre Creek is skirted on either bank by ranges of hills
uffs, with their corresponding valleys, gulches, and ravines; the
are filled in many places with old and decaying drifts, the relics
ing freshets, &c.
n statements of old settlers I learn that Exeter has been at other
visited with cholera. First in 1834, when the disease prevailed as
eral epidemic throughout the country. Again, in the fall of 1848,
sease appeared in that village. This time it was a local attack, a
ses, however, being taken from Exeter to neighboring towns.
time about 1852 or 1853 the disease again appeared at Exeter;
s occasion the disease was purely local, and the general condi-
were similar to those preceding the last epidemic of 1873.
spring of 1873 was ushered in unusually early; vegetation grow-
oundantly and luxuriantly under the genial influence of early
's warm sun. Early in the month of March the severe winter
nly gave way, and a season of rain followed; about the middle
e month we had a very heavy rain, which overflowed the banks of
auvaisterre, sweeping large amounts of *débris*, plentifully mixed
lead hogs, &c., into the ravines already referred to. The receding
s left them saturated with moisture, to become in a short time beds
l, putrefying matter. The weather soon settled down to a steady
th: April, attended with its showers; May, with little rain and
warm weather; June came in hot, dry, sultry, and oppressive.
wells beginning to fail; many entirely dry; all very low, muddy,
rackish; the creek, ordinarily a running stream, was dried up to
, stagnated, over whose surface a foul green mold was spreading

itself. The piles of rotting filth and garbage in the ravines alo creek, decomposing and fermenting, diffused their nauseating odo disease-producing germs through the air, perceptible for consid distance. By the middle of June there were but very few well were not dry; good, pure drinking-water could not be had at all. weather had grown more oppressive and humid, yet few peopl plained of ill feelings, only that produced by the heat. The night but small improvements on the days, persons arising in the m stupid, dull, tired, and altogether unrefreshed.

On the 22d day of June occurred the first case. The subject, somewhat advanced in years, is suddenly seized with vomiting an ing; soon he has cramps, speedily followed by collapse and deat

Now we come to the question—What was the cause of this c cholera? What conditions or morbid processes were combined production of this dreaded disease? Can we satisfactorily exp find the conditions by which this affection sprung into existence?

First, let us look more closely into the antecedents or previous h of this case. We find upon inquiry that it is not an imported c is generally the fact. The man has not been from home for ov weeks, only to visit some neighbors and relations; none of those v before or afterward, having any signs or symptoms of cholera. Th furnishing water for the house was strongly impregnated with very low and muddy; it was, however, situated far above the cha contamination from the creek.

So far as can be ascertained he had not been near a person h choleraic diarrhœa, or cholera in any of its stages, and did not use a at all, but had been in usual good health for a long time precedi day upon which he was attacked. At noon of the day of the atta had indulged to excess in green-gooseberry pie, and had a mo diarrhœa; he had been drinking the water from the well. This is all we can learn of the preceding history of this case. Two milder occurred about the 26th or 27th, which recovered. On July 4, the f case was reported in the person of an elderly woman. This woma attending a pic-nic about four miles distant from her home; she was to a neighboring house, where she died in a few hours. She, too, had using impure water, but had not eaten anything to excess. About th of July the disease had reached its height, continuing without s ment until the second week in August, when it began to declin last case, a fatal one, occurring on the 3d of September.

As to the propagation of the disease: After its origination or out more than one-half of all the cases can, without doubt or questio put outside the possibility or probability of contagion or infection. smaller half may have been in some way related to intercourse those sick of cholera.

Meteorological conditions.—The months of June, July, and Augu now memorable for their intense heat, sultriness, and close atmosp and the absence of the usual pleasant summer winds and showers thermometer ranging from 90° to 104°, (Fahr.,) with a barometer cating constant high atmospheric pressure of 29 to 30½ inches. O 5th of July a very heavy rain-storm passed just east of Exeter. rain fell in torrents, and in such volume as to again cause the Ma terre to overleap its normal boundaries, flooding the fields and lowl adjoining the creek, sweeping before it immense quantities of wheat the shock, green growing corn, weeds, &c., into the ravines, where already rotting vast beds of organic vegetable and animal matter. they were left by the receding waters to rot, putrefy, and stink. F

te to September 1, little or no rain fell, the weather each day
gly growing hotter, vegetation and fruit prematurely ripening and
up from drought and hot sun. The atmosphere appeared per-
tagnant; evidently deficient in ozone and in negative electric con-
thoroughly saturated with the emanations from the beds of
osing organic matter and ponds of stagnant water, the creek
eing dry. These various poisons loading the air, on being wafted
y the light winds, were disseminated throughout the neighbor-

pidemic extended over a period of ten weeks, reaching its height
our weeks from its origin, or the time when the first case occurred,
2. From the 20th of July to the 20th of August there was little
batement; from this time, however, there was a gradual decline,
fatal case being reported September 3.
we have four weeks disease increasing, four weeks stationary,
o weeks decline. Six of the cases that occurred at Bluffs may be
to one source or origin, a person bringing it from Exeter. Those
pin were imported cases, two of them having been in attendance
se sick of the disease. Fifty-three cases occurred at Exeter,
-six of which proved fatal. Allowing 500 population to that vil-
would make one in nine and a half of the inhabitants attacked,
death-rate of one for every nineteen persons, and a proportion of
cent. deaths for the number of persons attacked, and 6 per cent.
inhabitants.
grand total number of cases, mild and severe, so far as it is pos-
o ascertain, including Chapin, Exeter, Bluffs, and Maples, is sixty-
with a death-rate in this number of forty-one cases, about 65 per
atal. * * * * * *

ffs is a small village of about one hundred and fifty inhabitants,
ed on the line of the Toledo, Wabash and Western Railway, four
east of Naples and the Illinois river.
village is built upon a dark, rich loam, with a moderate admixture
nd overlying a stratum of clay. The water is good, but strongly
gnated with lime.
e first case of cholera at Bluffs occurred in the person of an em-
of the railway company, who was attacked July 17, at 8 o'clock
The attack was pronounced, but the patient recovered after an
s of ten days. Disinfectants were freely used, and no other cases
red in the house. The second case of the series occurred August
the person of Mrs. Hatfield, a lady forty-two years of age, who
ed one mile east of Bluffs. She had neglected a diarrhœa for two
, and, when first seen by her physician, was purging, vomiting, and
ping violently. The characteristic symptoms of cholera were
ent, and the patient died at 9 o'clock a. m. of the 10th.
igust 12, at 7 o'clock a. m., Mrs. Sarah Smith, a daughter of Mrs.
ield, was taken with a copious painless diarrhœa. This lady, who
twenty-four years of age, and at the time four months pregnant,
some days before her mother was taken with cholera, arrived from
home at Exeter, which town she had left on account of the cholera.
en first seen by the physician, but an hour after the first rice-water
harge, Mrs. Smith was rapidly becoming collapsed.
he was actively treated with stimulants, opium, and camphor. At
clock p. m. had fully reacted; pulse 126 and of considerable volume;
face of body warm and bathed with a moderate perspiration; secre-
of urine re-established. At 8 o'clock the patient, to use her own

words, "felt very good." Has had some sleep. Pulse 110. Is n thirsty; has taken some beef-tea.

During the next two days this lady continued to improve. O 15th her husband and sister were taken with cholera and died, but a few hours' illness. The effect produced upon Mrs. Smith was depressing, but no re-development of the disease occurred.

August 16, Mrs. Smith learned unfortunately of the death of a se sister and a brother-in-law, who had left them but the morning b in perfect health, and who resided at Chapin, some eight miles ea Bluffs. The shock produced by this intelligence was so profound the patient could not be roused; but she lingered in this condition the 23d, when she died. Upon removing her body from the bed, it found that the bed was covered with blood, in which a fœtus, with placenta, &c., was found. She had aborted without evincing a sig such complication, and had undoubtedly died of uterine hemorrhag

The cases of the daughter and son-in-law of Mrs. Hatfield, who at Chapin, present some points of importance. Upon learning of illness of the mother, these people had left their home and hastene her sick-bed, the daughter coming one day in advance of her husb The daughter remained at Mr. Hatfield's about three days; her husb but one day, when he returned to his home. This man, on reac home, was taken with a mild diarrhœa. At noon he sent for a physi who found him purging rice-water. The wife was immediately graphed, and she returned on a train, reaching Chapin at 4 o'clock p to find her husband dead. A coffin was hastily constructed, and a sundown the body was taken to the place of burial. On the way to grave the wife was taken with cholera, and in three or four hours dead.

In the same family, Mrs. Hatfield's two daughters, aged fifteen eighteen, and one son about eight years old, remained; of these youngest daughter and the son had cholera in a mild form; both covered, the older one escaping without any symptoms of the dise One of the nurses, (a female,) about one week later, took the disease died; but she had during this week another patient in Exeter, th and a half miles distant, and had washed the clothing of the bed of charge, who had also died of the disease. Four of these cases, the first and the two last, were under the care of other physicians, an have no correct knowledge of symptoms or treatment.

As to the sanitary conditions of the house where so many cases curred:

The house, a one-story frame structure of four rooms, and a cell feet 2 inches deep. It is situated upon an elevated point, three or f hundred feet above the level of the bottom-land, one mile east of Blu The house is on the southern edge of a two-acre clearing, clo in on the east, north, and west by timber; on the south there a gentle slope of about half a mile of cultivated land; this slope ter nates at a creek, which at this season of the year is dry. The soil mixture of loam, clay, and sand, and very productive. The drain by nature is of the very best, as during a heavy fall of rain all ac mulations are washed away. The house above ground was clean, w lighted, and thoroughly ventilated. The cellar was in a very neglec condition, pervaded with a close, musty air, which was perceptible the room above it. The water-supply for drinking purposes and ho use was furnished from a well on the premises 28 feet deep, at this ti almost dry, and utterly unfit for use.

As means of preventive and disinfecting, I had the cellar cleared

ge, whitewashed, well aired, and sprinkled with chloride of lime; nate and chloride of lime scattered liberally about the premises. house carbolic was the chief agent, but bromo-chloralum and lphate of iron were also used.

tribute the severity of the disease in this house mainly to the supply and crowded condition of the house, there not being suf- room for so many persons, as the cooking and eating were all done the same roof, and in close proximity to those who were sick. I d no more water to be used from the well.

the morning of August 16, a man seventy-three years of age was with profuse and exhausting diarrhœa. For some two or three previous he had complained of a looseness of his bowels, for which l received some treatment, but without much effect. The symp- were rapidly developed, and at 10.30 o'clock p. m. he was dead.

e other cases occurred, one of which proved fatal. Disinfectants freely used in all cases.

INGTON COUNTY.

ORY OF THE CHOLERA EPIDEMIC OF 1873 IN WASHINGTON COUNTY, ILLINOIS.

By Dr. W. M. Pierce, *of Addieville, Ill.*

an important part of the history of the cholera epidemic of 1873, pose to give a brief account of the disease as it occurred in Wash- n County, Illinois. In the preparation of this paper I shall use only material as came under my own immediate notice, or such as I to be entirely trustworthy, the general correctness of which can tested by several other medical gentlemen of this and adjoining ties who visited the locality during the prevalence of the epidemic.

ashington County is bordered on the north and west in part by the r or Kaskaskia river, a stream of considerable size, with wide bot- , subject to frequent overflows. Emptying into this river from the are several large creeks, with low banks and muddy beds, and on f these creeks, divided by it into two nearly equal parts, is Okaw- a village of between three and four hundred inhabitants. Okaw- is near the line of the Saint Louis and Southeastern Railway, h runs through the county from northwest to southeast, and which its termini at Saint Louis and Evansville, and it was at this place the epidemic assumed a malignancy scarcely ever equaled in this try.

olera prevailed in several localities along the line of the South- ern Railroad early in the summer, and was more than usually fatal ount Vernon, Ind., and Carmi, Ill.

uring the month of July very heavy rains fell in the west end of ounty, and the creek upon the bank of which Okawville is situ- was very high, flooding the country around the town and depositing rge amount of organic matter, the washings of the prairie fields e the town, in close proximity thereto. Unusually hot weather suc- ed, and miasmatic diseases, which are very prevalent in this locality, n to make their appearance and threatened to be of a more than ordi- y severe type.

n the 11th of August, H. H., a merchant, living near the center of town, was attacked with cholera. He had returned two days before n Saint Louis, where cholera was then prevailing, and where he had

doubtless been on a debauch, as he was of dissipated habits
though he apparently improved for several days, he finally died
thirteenth day from the date of attack. Although the physic
attendance pronounced his disease Asiatic cholera, the citizens ge
were incredulous, and no precautions were taken to prevent the
of the disease. Living in the most public part of the tow
acquainted with all the citizens, many visited him before and af
death; no disinfectants were used, and every possible facility wa
for the spread of the disease. As a natural consequence of this
dence, in a few days other cases occurred. On the 18th, M. B., f
aged thirteen, living near the residence of the first case, sickene
died on the 20th. An infant in another family took the disea
died.

Mrs. Catherine Wolff was taken on the 20th, and lived but
hours. Her husband, Philip Wolff, was attacked the same day sh
and died that night. And now the cases followed each other i
succession. Whole families were swept away before the breath
pestilence, and though many fled the plague-stricken town, very
a fifth of the inhabitants fell victims before the epidemic ceas
ravages, which was about the close of September.

Addieville is a small village, a station on the Saint Louis and
eastern Railroad, four miles east of Okawville. It is on the open p
and there are no surroundings that indicate any local miasmatic infl
Several families left Okawville about the 1st of September on acco
the cholera, and occupied an unfinished house in Addieville. Abo
20th several men, putting up a new line of telegraph-wire on the ra
boarded in the village and lodged there at night. Among these
young man, George Carroll, who resided at Mount Vernon, Ind., an
had an attack of choleraic diarrhœa in July. As I learned subsequ
this man had a return of the diarrhœa while working near Addievill
several times deposited his dejections in a barn near the house occ
by the families from Okawville, and used by them for the same pu
On the evening of the 20th of September, Mrs. J. G., one of the occu
of this building, a remarkably robust, healthy young woman,
stricken with the disease. Notwithstanding the most energeti
persistent treatment, she died the next morning. The next morn
was called to George Carroll, the young man from Mount Vernon
found him far gone in a collapse. He died the same day. F. G
band of the first case, came into my office about noon of the sam
and said he "believed he had cholera." He had not vomited, d
even feel any nausea, no cramping. There was no one to attend
as the families living in the same house had all left as soon as hi
was attacked, and no one else could be procured, so I put him
lounge in my office, and gave him all the attention I was able.
ing that was done, however, seemed to have the slightest influen
the course of the disease, and before morning he died. Henry Sc
blacksmith, living near the house where Carroll boarded, and
water from the same well, died on the 21st. Fritz Hugo, wh
worked on a house in the village on the 20th, had gone a few mi
the country. On his return home he was attacked, and died the
of the 21st. C. G. M., a farmer in comfortable circumstances, liv
mile south of Addieville, came into town on the 21st, and before
aware he entered the office from which the corpse of F. G. ha
been removed. On the 23d he was attacked with the disease, b
covered, though for some days he seemed very near death. There
but two other cases outside of Okawville, in this county, that I

ge of, and both of these cases can be traced directly to
The Rev. Mr. Fithian, a travelling minister, stopped all
awville the night of the 29th of August. On the 31st he
Ashley to Richview, three miles, and became overheated,
being quite warm. In a few hours he was attacked with
died in twelve hours. A young lady, Miss J. W., was visit-
me house in Okawville at which the Rev. Mr. Fithian staid
d left for home the same day. On her arrival at Ashley,
from Okawville, on the same railroad, she also was stricken
ease, but recovered. On the next day after these two per-
family of W. C. B., where they had been visiting, was
d six cases occurred in three days, all of whom died. The
W. W., who was first attacked, had been nursing F. Cruze,
the disease three days before. No precaution, sanitary or
as taken to prevent other members of the family from be-
cted; from which neglect resulted eight cases and seven
f the twelve persons who were in the house on the night of

ng up the cases which occurred in Washington County we
ville, forty cases, no recovery; Addieville, six cases, one
shley, one case, one recovery; Richview, one case, no re-
tal, forty-eight deaths and two recoveries.
several points of more than ordinary interest presented in
g imperfect history.
narkable mortality, uncommon, I believe I may say unpre-
any former epidemic in this country. The only approach
l-authenticated account of a cholera epidemic that occurred,
y, within four miles of the present location of Okawville
ears ago. On that occasion a man who had been to Saint
the disease raged at that time, 1850, had a mild attack of
is return. In a few days sixteen cases and fifteen deaths
lace in a small neighborhood of a few families. The condi-
ery much the same as those in Okawville in 1873.
ensity of the disease at this particular locality, Okawville,
n with its low, malarial situation, and the violation of all
anitary precautions to arrest or control the epidemic. True,
vas nearly as fatal at Addieville; but of the six cases that
that vicinity, two were residents of Okawville, another had
at place shortly before, and Carroll, the young man from
on, Ind., died from a relapse of the disease. The young
d the disease at Ashley had only been on a visit to Okaw-
find that of the four persons who had an attack, who were
of Okawville, two died and two recovered, a mortality not

ieville, where the most rigorous measures were adopted for
disinfectants, and the destruction of bedding and articles
contaminated by contact with the disease, it was stamped
ays.
tors are evidently necessary for an epidemic of cholera—a
disease such as existed in an eminent degree at Okawville,
c poison, just such as we can trace from New Orleans to
d Nashville, Tenn., and then to both termini of the Saint
outheastern Railroad, Saint Louis and Evansville, Ind. We
ave at Okawville a like condition, as far as miasmatic influ-
ncerned, but we have no cholera, because the specific poison
Bring the two conditions together, and let there be the

same criminal neglect of all the precautions that experience has ta to be indispensable in controlling this dread disease, and we will al have just such disastrous results.

5. The total inefficiency of any medical measures, either as pro lactics or as treatment, after the invasion of the disease, is notice As far as could be seen, those who were vigorously and thoroughly icated, and those who had no treatment, fared alike. There seeme be absolutely no antidote to the morbific agent that did its work in brief hours, and there seemed to be no power in the systems of t attacked to rally. In such epidemics we have as yet no remedy; important, then, to make such impossible by guarding against the vasion, or by such sanitary measures as experience has prove numerous instances, to be efficacious in their management.

Knox County.

Galesburgh, a city of ten thousand inhabitants, is situated upo Chicago, Burlington and Quincy Railroad, one hundred and sixty miles southwest of Chicago.

At this city, so far as our information reaches, but one case of ch occurred during the epidemic of 1873.

On the 14th of August a young man named Cowan was taken fr train on the railroad on account of an attack of cholera. He had come from the city of Burlington, Iowa, where it was reported several cases of cholera had occurred in the portion of the town he visited. At 12.30 o'clock p. m. the patient was profoundly collap and at 6 o'clock p. m. he was dead. Disinfectants were freely used. other cases of the disease occurred.

Rock Island County.

The city of Rock Island is located upon the Mississippi river, miles above the mouth of Rock river. It derives its name fro island in the river, which is three miles in length and which pres a perpendicular front of limestone 20 or 30 feet high. The main c nel of the river is upon the west side of the island. This city has munication with the city of Davenport, Iowa, upon the opposite b of the Mississippi, by a bridge and by steam ferries.

On the 3d day of September, 1873, Joseph Hertzberg was found Dr. T. Galt to be in the collapsed stage of cholera. The surface of body was cold and of a dusky hue; the face was pinched and with anxious expression; tongue and mucous membrane of mouth cold; ha and feet shrunken and wrinkled; great prostration; cramping in muscles of the legs; constant vomiting and purging, and suffering f extreme thirst.

It was ascertained that he had spent the previous Sunday in Da port, where cholera was at the time epidemic. He had a painless d rhœa in the morning when he went to his work; it continued thro the forenoon. At dinner he ate some soup and drank two bottle soda-water. After dinner he started to return to his work, but obliged to go to bed. Shortly after he was seized with vomiting cramps. The treatment adopted was hot fomentations, sinapisms, st ulating applications and frictions, the hypodermic use of belladon No remedies could be given internally, as vomiting was continuous. five hours from the time at which he went to bed he was dead.

Disinfectants were freely used in the water-closets and drains. excreta were disinfected as soon as voided. The privy, which had b

man during the forenoon, was disinfected. After death, the thing were burned. The room was fumigated, scrubbed and d.

occurred at a third-class boarding-house, full of people who ed to the use of beer and bad whisky, very untidy in their rregular in their habits.

cases occurred in this house or in the city of Rock Island, ndoubtedly due to the prompt measures taken at disinfec- re indebted to Dr. T. Galt and to Acting Assistant Surgeon . A., for the report of this case.

ne of the cholera epidemic at Davenport, in 1873, there were the Rock Island Arsenal five commissioned officers of the with their families, and about seventy soldiers and ordnance A *cordon de sante* was established as regards Davenport. l man escaped through this cordon, went to Davenport, got remained all night in the room of a person ill with cholera. turn to the post he was secluded; no ill effects occurred to his imprudence, nor was he himself ill at any time.

e city of Rock Island adopted the Holley system of water- during 1873 the supply of river-water was abundant, taking the well-water formerly used. It is noted as a significant opposite city of Davenport had made no such provision, that city the supply was obtained, as in former years, and cisterns. One city escaped the epidemic; the other erely.

OUNTY.

n is located upon a beautiful prairie, and upon the line of and Burlington Railroad. The town has a population of housand inhabitants.

own no epidemic of cholera occurred, although one death ease is reported as having occurred in the person of a man en the few days previously at Burlington, Iowa.

rk is a small village of Warren County, situated about northwest of Monmouth. The village has from eighty to one abitants; is located on a prairie about eighty rods from a vn as Cedar Creek. The first case occurred in the person nt who had just returned from Burlington, Iowa, where he a business visit. Six other cases occurred among the per- ere in communication with his sick-room, all of whom died.

E.

Mott reports but two cases of cholera as having occurred at

Ware, a negro, thirty-five years of age, a deck-hand on a river steamboat, came to his home about one mile east of 28th of June. He was taken with cholera a few hours after the symptoms were fully developed, but he reacted and re-

ice, a negro, aged sixty, the father-in-law of Ware, and who same cabin, was taken with cholera July 2, and died within

cases occurred.

CHAPTER X

MISSOURI GROUP.

MISSOURI CONTRIBUTORS.

Dr. W. L. Barret, Saint Louis Co.
Dr. G. F. Dudley, Saint Louis Co.
Dr. R. H. O'Brien, Saint Louis Co.
Dr. T. F. Prewitt, Saint Louis Co.
Dr. George Homan, Saint Louis Co.
Dr. W. Wyman, Saint Louis Co.
Dr. R. S. Anderson, Saint Louis County.
Dr. Charles Reiss, Saint Louis Co.
Dr. O. A. Wall, Saint Louis Co.
Dr. Charles Vastine, Saint Louis County.
Dr. F. M. Hauck, Saint Louis Co.
Dr. A. Green, Saint Louis County.
Dr. A. K. Hartman, Saint Louis County.
Dr. C. Brockhausen, Saint Louis Co.
Dr. O. Greimer, Saint Louis Co.
Dr. G. S. Walker, Saint Louis Co.
Dr. F. C. Castlehaw, Saint Louis County.
Dr. F. M. Hauck.
Dr. C. L. Young, Saint Louis Co.
Dr. E. Rose, Saint Louis County.
Dr. A. D. Webster, Saint Louis County.
Dr. F. J. Artzt, Saint Louis Co.
Dr. C. Gercke, Saint Louis Co.
Dr. A. Gulney, Saint Louis Co.
Dr. V. H. Auler, Saint Louis Co.
Dr. E. F. Rabaudt, Saint Louis Co.
Dr. J. Ringe, Saint Louis County.
Dr. R. C. Atkinson, Saint Louis Co.
Dr. W. W. Finlay, Saint Louis Co.
Dr. L. S. Reber, Saint Louis Co.
Dr. A. J. Mullen, Saint Louis Co.
Dr. J. Conzelman, Saint Louis Co.
Dr. W. H. Cooper, Saint Louis Co.
Dr. J. C. Campbell, Saint Louis Co.
Dr. C. Grundelack, Saint Louis Co.
Dr. W. Coles, Saint Louis County.
Dr. C. Spinzig, Saint Louis Co.
Dr. C. G. Rohlfing, Saint Louis Co.
Dr. S. L. Nidelet, Saint Louis Co.
Dr. A. Schlosstein, Saint Louis Co.
Dr. D. Kuhn, Saint Louis County.
Dr. W. B. Outten, Saint Loui
Dr. H. Wickmann, Saint Loui
Dr. T. Irwin, Saint Louis Cou
Dr. G. F. Bang, Saint Louis C
Dr. C. Garcia, Saint Louis Cou
Dr. W. Stapp, Saint Louis Co
Dr. J. J. Dean, Saint Louis Co
Dr. B. R. Tyler, Saint Louis Co
Dr. A. Hillegrist, Saint Louis
Dr. J. Middleton, Saint Louis
Dr. A. Green, Saint Louis Co
Dr. E. Voerster, Saint Louis Co
Dr. N. C. Washington, Saint L
County.
Dr. C. O. Curtman, Saint Louis
Dr. L. M. Lee, Saint Louis Co
Dr. E. C. Carrington, Saint Loui
Dr. M. Yarnell, Saint Louis Co
Dr. E. E. Webster, Saint Louis
Dr. D. P. January, Saint Louis
Dr. W. B. Outten, Saint Louis
Dr. W. T. Hillman, Saint Louis
Dr. J. P. Trohue, Saint Louis
Dr. L. P. Pollman, Saint Louis
Dr. J. L. Fitzporter, Saint Louis
Dr. C. H. Hughes, Saint Louis
Dr. J. B. McClure, Saint Louis
Dr. F. H. Hammond, Saint Loui
Dr. B. Linton, Saint Louis Cou
Dr. P. Rogers, Saint Louis Cou
Dr. J. L. Cassiley, Saint Louis
Dr. W. Standing, Saint Louis
Dr. R. M. Oliphant, Saint Loui
Dr. S. H. Broken, Saint Louis
Dr. G. T. Allen, Saint Louis C
Dr. N. B. Carson, Saint Louis
Dr. J. E. Faber, Saint Louis C
Dr. P. G. Robinson, Saint Louis
Dr. L. De Leurd, Saint Louis C
Dr. W. H. Remick, Saint Louis
Dr. J. S. Pearson, Pike County
Dr. S. B. Ayres, Pike County.
Dr. C. Pearson, Pike County.
Dr. J. R. Buchanan, Pike Cou
Dr. J. A. Greer, Butler County
Dr. J. Nixon, Butler County.

ight, Howard County.	Dr. H. Kinner, Saint Louis Co.
ller, Saint Louis Co.	Dr. W. G. Miller, Howard County.
isliniere, Saint Louis	Dr. W. M. Gross, Wayne County.
	Dr. James A. Ward, Lincoln Co.
Saint Louis County.	Dr. J. Baker, Cole County.
egory, Saint Louis Co.	Dr. S. V. Sterner, Morgan County.
lly, Saint Louis Co.	Dr. Isaac Moore, Saint Charles Co.
ve, Saint Louis Co.	Dr. J. L. Thomas, Saint Charles Co.
grist, Saint Louis Co.	Dr. G. B. Winston, Cole County.
nall, Saint Louis Co.	Dr. C. A. Thompson, Cole County.
o, Saint Louis County.	Dr. A. C. Davison, Cole County.
hsler, Saint Louis Co.	Dr. O. Elston, Cole County.
idley, Saint Louis Co.	Dr. R. E. Young, Cole County.

B. F. Clements, United States Army.
Assistant Surgeon Charles Reiss, United States Army.

DATES OF INITIAL CASES.

County.....May 11.	Cole County .....June 22.
nty.....June 6.	Lincoln County .....June 22.
.....June 13.	Saint Charles County..June 26.
nty.....June 14.	Howard County.....July 17.
y... .....June 19.	Morgan County .....August 18.

known that cholera was epidemic in the counties of Boone, Iron, and but we have failed utterly to elicit any information from the physi-counties.

SAINT LOUIS COUNTY.

Many conflicting statements have been set before the public as epidemic of cholera, as it affected the city of Saint Louis, Mo., the spring and summer of 1873. At one time it was announced t cases of the epidemic type had occurred, but that the disease ma appearance about the middle of June in isolated and sporadic Again great stress is laid in some quarters upon the expressed do several of the most distinguished physicians of that city, "that was a single genuine case of epidemic cholera in that city duri entire season." In the annual report of the health officer, the s is disposed of in the following words: "The disease appeared fi the southern portion of the city and lingered there until it ha nearly run its course. Much of this part of the city is situated low ground and is supplied with water from wells and cisterns, m which have been long in use, and in many instances the water h come impure, as was shown by chemical analysis. The populatio is dense, much overcrowded in tenement-houses or living in b built upon alleys back from the street. To this add ill ventil dampness of soil, neglected water-closets, deficiency of conn between premises and sewers, want of "traps" where there is suc nection, and you will no doubt have the chief circumstances an roundings which contributed to the virulence and continuation disease in this locality. As the disease began to subside in the ern part of the city, it leaped over the central portion and for lodged in the northern part of it; here, too, in localities in respects in similar condition to those in the southern part of the

Despite the statements and assertions which have been noted, it ascertained fact that an epidemic of cholera existed in the city of Louis from the month of May to that of October, 1873; that th ease was imported into that city from a cholera-infected locality that the epidemic influences were confined to certain localities o city, in which foci of infection had been established.

Every effort has been made to obtain full and complete lists o cases of cholera that occurred, with but, however, slight success. have received from the health officer a list of three hundred and ni two fatal cases of cholera, and one hundred and thirty-seven fatal of cholera-morbus. The records of but very few non-fatal cases be obtained. We have, however, succeeded in obtaining the pa lars as to the early occurrence of the disease, which are herewith sented in a series of three distinct papers.

I.—EPIDEMIC CHOLERA AT SAINT LOUIS, MO., IN 1873.

BY WM. L. BARRET, M. D., *formerly health-officer.*

(Through supervising surgeon United States marine-hospital service.

The first cases of cholera that occurred in the city of Saint Louis ing the epidemic of 1873, or the first cases of cholera morbus, as ch cases were usually at that time designated by the attending physic and invariably recorded by the clerk of the board of health, wh pronounced by the physician in attendance to be cholera or ch morbus, came under my observation as the then health-officer o city.

I obtained the history of each of the early cases; examined the and general sanitary surroundings of the places at which they occu

tain the cause or causes that led to the propagation of the
directed the execution of such measures as were thought
nt to stay the spread of the malady.
ase of the epidemic was that of John Washburn, who died
f May, 1873. The history obtained of the case was, that
ad recently returned to Saint Louis from New Orleans, in
place cholera was then prevailing. Within a few days after
was taken sick with what his physician regarded a severe
lera morbus and of which he died after the lapse of a day
was taken ill and died at 1515 South Seventh street, where
l had retained a room during his absence in New Orleans.
nost of the cases occurring in the early part of the epidemic,
to the board of health as one of cholera morbus, and attracted
tention until several days after the death had occurred
es of the same kind manifested themselves in the same
in a week from the occurrence of this death, five or seven
residing under the same roof were attacked with severe
miting, muscular cramps, collapse, and finally death;
nilar to those which characterized the first case mentioned.
those who died, several others were affected in the same
only recovered after a dangerous and protracted illness.
occurrence of the first two or three deaths, I visited the
pany with Dr. D. V. Dean, the city chemist, and then
h of the information already related, and learned the fur-
ng and important facts. After the death of Washburn,
ars was without friends or legal representatives, the sick-
the furniture and effects contained in it were left wholly
and securely closed, in its exact condition at the time of
The room thus converted into a hot-bed for the prolification
s very small, with low ceilings, dark, and illy ventilated.
that it had at all times been very filthy, but was most
lthy at the time of its closure. The bed-clothes and floor
have been repulsive in the extreme, and filthy with the sub-
d from the stomach and excreted from the bowels of its
ant during his last illness. Unfortunately, the occupants
had taken alarm at the terrible sickness and fatality that
enly fallen upon them, and connecting their misfortunes
y, vacant room, had it emptied, cleaned, and most of its
troyed before our arrival, so that we were unable to make
amination of its original condition, and therefore enabled
the statements of others.
in which, as above indicated, I believe the cholera epi-
had its origin, is one of the oldest tenements in the city.
fashioned log-house, weather-boarded on the outside, and
constructed in the infant days of the city. It constitutes
w remaining monuments of a former civilization. It is one
tories high, and contains eight rooms, including those in
half story, which are in reality only attic rooms. Four of
are on the first or ground floor, and the other four immedi-
em. It was in one of these attic rooms that the first case
he logs of which the house is built are decayed and moldy,
e low in pitch, poorly lighted, and badly ventilated. This
first or ground floor, while the second floor is nothing
very poor garret.
all structure four families resided, comprising in all eight-
and within a week of the first death seven of the eighteen

persons died, while several others were dangerously ill, and only e
death after a tedious lingering illness. The general sanitary su
ings of the house were fair. The house is built upon high grou
natural drainage of which is good, and the sanitary condition
neighborhood in which it is situated, as indicated in the perfectio
sewerage, the character of its buildings, and the character and
of its inhabitants, is of average excellence. I may as well sta
however, that the northern and southern portions of the city, t
a whole, are the most deficient parts of the city in point of s
perfection. In these districts each successive epidemic, of w
nature, that has visited the city for years, has been generated,
strength has here been fostered. The local sanitary surrounding
from the presence of the infected room, the defective constru
the tenement, and its overcrowded, ill-ventilated condition,
alluded to, were of the worst kind. The sewer connecting with th
vault was obstructed and the vault full to overflowing, while th
ran within eight or ten feet of a well sunk in alluvial soil. T
derived its water from surface-seepage, and, if I remember co
was found, upon examination, to contain fifteen grains of organ
ter to the gallon, and to be strongly contaminated with sewag
sewer above mentioned probably communicated with the well, a
well was the only source of water-supply with which the tenan
provided.

The house was whitewashed, renovated throughout, and disin
The privy and sewer were also cleaned and disinfected. The w
closed, and the premises supplied with hydrant or Missouri river
Subsequent to the enforcement of these measures no other cases oc
at the same place during the time I was connected with the
department, and, so far as I have learned, no other cases occurred
during the epidemic.

The next two cases that occurred were those of two employés
nail-mill, on the Iron Mountain Railroad just north of the United
arsenal, and about seven or eight blocks southeast of the loca
which the first cases occurred. These persons had resided in the ci
long time prior to their sickness and death, and I could not connec
illness with any foreign contagion. One of the victims resided on
street, about four squares distant from the mill. The other
at the mill. Both were taken suddenly ill with the symptoms of c
while at work in the mill. The discharges were rice-water in cha
the muscular cramps were severe, the skin became blue and shr
the voice was lost, the urine suppressed, and they collapsed an
within a few hours of the first attack. The residence of the o
lived on Sidney street was high, cleanly, well lighted, well vent
and well drained; in all respects healthful except in one part
and this defect consisted in the use of cistern-water, that on ex
tion proved to contain four or five grains of organic matter per g
but no contamination with sewage was detected. The sanita
roundings of the mill, where both had worked all day and were
sick, were not so good. The mill is situated in a low bottom and j
the bank of the Mississippi river, where the malarial influence is p
as strong as in any other locality in the city. At the base of th
runs a deep ravine or open sewer; indeed, it collects the offal and
and sewer drainage of a large and populous district of the city.
ravine during the dry summer weather contains very little wate
small stagnant pools here and there throughout its length. In the
of this ravine, surrounded on almost every side by stagnant sewer-

level with its top, the mill company had sunk a well, and the hands of the mill were supplied with water to drink examination of the water by Dr. Dean demonstrated that hly impregnated with organic matter, (I think seven or er gallon,) and that it responded promptly to the test for nination. In other respects save those mentioned, viz, ation and the dangerous quality of the water-supply, there ause that I could detect at the mill to engender disease. tic measures adopted at this place were confined to a well, and I believe no other cases occurred there. The was that of a German woman, on the corner of Columbus ts. This locality is in the same part of the city and not blocks removed from the places where all the other cases re we found a low, filthy, German boarding-house, of which as the landlady. The house in which the case occurred in all respects of sanitary importance, and supplied with well sunk in made ground and strongly contaminated atter, but contained no free ammonia.

nd last instance of an outbreak that occurred during my case of a negro man near the corner of Ninth and Pine was clearly an imported case. The man was a boatman, returned to the city from New Orleans two days before landed in the city with the premonitory diarrhœa, and day after his arrival was seized with cholera and died in urs.

currence of the last case mentioned—and the cases above clude all that occurred prior to the 2d of June—my con- he health department ceased, and I have no further nterest concerning the progress of the epidemic, and have obtain any other.

an, the city chemist, who continued to observe the course the epidemic, has informed me that in a large proportion erward reported the use of impure water in the infected emonstrated.

association of the use of impure water-supply with the the disease stimulated a pretty thorough examination of ly of the city, and particularly that derived from wells. nces wells apparently *very dangerous* were being used oduction of ill-health.

of the cases above enumerated in life; but they were all mpetent physicians, who had abundant opportunities for former epidemics, and I think their impartial diagnoses stworthy.

deaths occurring in May and in June were reported as s, when the attending physician was firmly convinced cholera, because the disease was not then recognized as they did not wish to create a sensation or excite public ers of them were reported as cases of cholera, but re- health authorities as cholera morbus for the same reasons. viction is, that all the deaths reported as due to cholera eally cases of true cholera, or were engendered by the ence then undoubtedly prevalent. Such a thing as nine holera morbus between the 11th of May and the 1st of ty-two deaths from the same cause during the month of er before heard of in Saint Louis, and, I venture to say, r again, except under similar influences, viz, an epidemic

tendency. It is true that every year we have a few deaths, more than half a dozen, from cholera morbus; but the victims a whose general health is already enfeebled by age or chronic dise they never occur until the latter part of July and 1st of Augus the weather is oppressively warm and the supply of green veg and fruits is abundant in the markets. These articles at that sold in a stale, green, or decayed condition, are invariably the causes in our sporadic cases. The cases that occurred at the com ment and toward the close of the epidemic were milder, yield readily to treatment, and were less strongly marked in their cl features than those which occurred at the height of the epide these peculiarities are true, I think, of the whole epidemic, as co with the epidemics of 1866 and 1867.

The epidemic in Saint Louis was almost wholly confined to the n and southern portions of the city, and in its progress from the s the north, the direction in which it extended, it seemed to jur the central part of the city.

The northern and southern parts, as already mentioned, ar parts in which the sanitary improvements are least perfect, wl population is least intelligent and least provident. The central the city is that in which the sewer system is most perfect, the broadest and cleanest, the tenements most airy and comforta public water-supply almost, if not quite, universally enjoyed. which the characteristics of the population is the reverse of t tributed to the northern and southern parts.

The means adopted by the board of health to crush out the e and prevent its spread was the stoppage of the use of impur in all instances where its use was detected, and a disinfection premises where cholera cases occurred, together with a general tion and disinfection, so far as it could be effected, of all houses a surroundings where the disease showed itself. This included privies, sewers, &c.

The first case, as will be seen from the inclosed list, occurred 11th day of May, and the last on the 26th of October. The tot ber of cholera morbus cases was 137; the total number reporte corded as cholera was 392. These numbers make a total of and cholera morbus combined of 529.

The facts set forth present a true account of the invasion of t by the disease, and give a correct history of the first eleven or cases.

II. The Cholera epidemic of 1873 at the Quarantine Hos

The Quarantine Hospital, a public charity of the city of Saint is located upon the west bank of the Mississippi river, twelv south of the city. The Iron Mountain Railroad passes in close p ity to the hospital, and affords rapid transit to and from the ci this point is also located the city pest-house, to which patie conveyed by wagon transportation. Daily communication exi tween the hospital and that portion of the city of Saint Louis w known as Carondelet.

At this hospital, on the 26th day of May, a female named Mc was suddenly seized with cholera and died after but a few hours' This woman had been an inmate of the institution for some tim under treatment for syphilitic rheumatism, and had not been awa her ward for weeks.

In the same ward, and occupying the next bed to Annie McA

as a woman named Duncan, with two children. This woman was sick with diarrhœa for some days before Annie was taken with cholera. Before Annie died Mrs. Duncan was taken with cholera, and died at an early hour on the 27th, and at a later date her two children died of the same disease. It was subsequently ascertained that Mrs. Duncan had absconded, with her children, from her home in the extreme southeastern portion of the State.

June 3.—A man named James Watt was carried to the hospital from a river-steamer in the collapse stage of cholera, and died within a few hours. No record was made as to the boat from which he was removed, other than the fact that she was from Memphis, Tenn., and bound for Saint Louis.

The epidemic was at first confined to the female ward in which McAnally and Duncan had died, and to the male ward in which Watt died; but cases were soon developed in other wards. The disease assumed a severe and fatal type. From the 16th of May to the 15th of September, sixteen fatal cases occurred, with many of recovery; of the last mentioned no record was preserved. Of the fatal cases twelve were males, four were females. The ages ranged from one month to fifty-two years. All were white.

Dr. R. S. Anderson, the medical superintendent, is kind enough to inform us that "the treatment adopted was experimental. Internally, astringents, opiates, carminatives, stimulants, and cathartics were employed in different cases. Hypodermic injections of both morphia and atropia were resorted to. Externally, frictions with mustard, hot baths, and general applications of warmth were used." Disinfectants were freely used. The patients were isolated as completely as was possible, and scrupulous attention was paid to cleanliness and the removal of the excretions.

III. The following letter from Dr. Charles Reiss, late Acting Assistant Surgeon United States Army, presents the history of the second group of cholera-cases which occurred at the city of Saint Louis in 1873:

"SAINT LOUIS, MO., *November* 1, 1874.

"SIR: I have the honor to transmit herewith a list of the cases of cholera which came under my observation during the epidemic in the year 1873.

"Early in the morning of May 28 I was called to see a man at the corner of Ninth and Lynch streets, named Dinert, who had come home sick from his work at the Saint Louis Railroad Fastening Company's shops. These shops are situated due north of the United States barracks, upon the banks of the Mississippi river, or rather, on the Iron Mountain Railroad, between the barracks and Dorcas street, in the southern portion of the city. I found the man Dinert to be suffering from cholera.

"Upon my return home I was called to return in haste to the same locality, and there found an aged lady named Roberts also attacked with cholera. In a few hours both cases were dead. These being the first cases of the disease, and as they occurred at the same place, my attention was given to discovering the cause of the outbreak. I had heard nothing of cholera in the city up to this date, although bowel-complaints were frequent. I had prescribed for several cases at these works, in the persons of new-comers to this city from points upon the lower river; among them a man named Butler, who had for some time a troublesome and exhausting diarrhœa. This man had made constant use of the privy which was also used by Dinert and Mrs. Roberts.

"As will be seen by the accompanying diagram, north of row of tenement-houses occupied by the employés. These built upon a lime stone ledge, which upon the north has been quarried. The water used by both the workmen at the n occupants of the tenement-houses, was obtained from a we been dug in the quarry. Standing at the mouth of this found to be some 20 feet below the level on which the buil that it (the well) was surrounded by pools of stagnant wa it was flanked east and west by the weather beaten lime exposed by the former quarry-work.

"Upon the bank, and at the edge of the quarry, were privies for the use of the workmen and their families. Th consisted of pits which had been dug into the surface-rock, tion of the rock below these privies was full of crevices. T the well was clear, cold, and odorless.

"I had the well closed at once, and caused the locality privies) to be thoroughly disinfected with carbolic acid an Instructed the people to use the dirty river-water which th ment pumped for manufacturing purposes, rather than the c water of the neighborhood.

"I heard and saw nothing more of cholera, although bowel continued to be frequent until June 12, when I was called to employé of this company, but who resided on Dorcas stre great many of his fellow-laborers lived at the time. This poi three or four blocks of the mill. The people lived in small were furnished with wells in close proximity to privies, whic the rock-formation, were very superficial.

"The treatment which I adopted was strictly symptomatic and stimulants, with ice.

"Very respectfully, your obedient servant,

"CHARLES REISS, M

"*Acting Assistant Surgeon, United Stat*

"Asst. Surg. ELY MCCLELLAN, U. S. A."

It is well to note that upon the river immediately above t described by Dr. Reiss, is a point on the levee at which steam and at which they are frequently tied up for cleansing purpo

It was undoubtedly from the three points of infection that described that the epidemic at Saint Louis in 1873 originated. of May 11, although classed as cholera morbus, was certainly with the cholera which, at the time, was epidemic at New Or at many points upon the Lower Mississippi River.

There can exist no doubt that the case which occurred at t tine hospital on the 26th of May was infected from the fema soon thereafter was a victim of the disease herself. The evid the cases of May 28 is certainly conclusive. It was from t that the disease spread. The violence of the epidemic was the southern sections of the city, in which the infection ha veloped.

About the middle of June the board of health became a cholera was in the city. The health-officer in his annual re that "steps were taken to at once place an abundant suppl fectants at all the police stations and substations throughou and through the aid of the police-force printed and verbal given to all persons who were not able to purchase disinf


GENERAL VIEW
IRON MOUNTAIN RAIL ROAD
ROAD
ROAD
DWELLING
DWELLING
SPIKE FACTORY
SHEDS
POND
PUMP
ST. LOUIS BARRACKS
PRIVIES INDICATED THUS
PLAN

emselves, of the ample gratuitous provisions which had been made r the disinfecting of their premises; and through these means, and the gilant and unceasing efforts of the board and its officers, all places here cholera made its appearance were constantly visited and thorghly disinfected."

We most fully agree with the Health-Officer when he states "that ere is no doubt that the active and energetic course pursued by the oard of health did much toward preventing the spread of the disease, nd tended to stamp it out."

As additional evidence, we reproduce from the Saint Louis Medical nd Surgical Journal an article from the pen of the accomplished senior ditor:

"CHOLERA-EPIDEMIC IN SAINT LOUIS IN 1873.

"As early as May (possibly in April) we had indications of a tendncy to bowel-affections, although in that month but three deaths were eported at the office of the board of health as caused by cholera norbus.

"The time and exact location of the first case of cholera which occurred in Saint Louis this year cannot now be ascertained, as it was doubtless reported as a case of cholera morbus. Our city authorities were active in furnishing disinfectants at the police-stations, free of expense to all unable or unwilling to pay.

"In the month of June, bowel troubles became more prevalent, and 35 deaths from cholera morbus were reported to the board of health. This was at the time deemed a very large number of deaths from cholera morbus, as we were not aware that cholera morbus was ever commissioned to do any considerable amount of killing, while cholera has persistently sustained its high pretensions in this regard, cutting down about one-half attacked in all countries, whatever treatment or obstacles interposed. In the month of July the mortality, as published, reached the ..ard number of 210 deaths from 'cholera morbus.' It now began to be suspected that the less alarming name of cholera morbus had been adopted to prevent disturbing trade; and it was generally conceded by medical men that we were passing a mild epidemic of cholera, which opinion received confirmation from the mortality-report the following month of August, when 109 deaths from cholera morbus and 80 from cholera were reported. September reported 50 deaths from cholera morbus and 12 from cholera, after which the disease disappeared from the mortality-reports.

"Having passed through several epidemics of Asiatic cholera, particularly that of 1849, in this city, I felt sufficiently familiar with the disease to be certain that the disease designated 'cholera morbus,' last year, in our mortality-reports, was genuine cholera; and I have no doubt that the improved sanitary condition of the city, together with the universal custom of physicians to make free use of disinfectants immediately on being called to visit a patient giving any indications of the disease, and the fear lest the epidemic should increase in severity, causing care on the part of citizens, helped to check the disease. However this may be, the disease passed over us lightly, and the present 'heated term,' although hotter than 1873, and although our markets are filled with fruits, *often stale*, yet it is rare to hear of a death from cholera morbus, and thus far (September 16) no sporadic case of cholera has appeared on our health reports.

* * * * * * *

"The following table shows the monthly mean temperature an
fall during the period the disease lingered about the city:

May, 66.2 F.; quantity of rain, 3.91 inches.
June, 68.5 F.; quantity of rain, 5.24 inches.
July, 69.2 F.; quantity of rain, 5.88 inches.
Aug., 68.9 F.; quantity of rain, 0.04 inches.

"During the month of September the disease disappeared fr
city. The total number of deaths from cholera, by the board of
published, was 92; total during the same time of cholera morbus w

* * * * * *

"If it can be shown that cholera originates in the valley of th
sissippi as well as that of the Ganges, the opinions of sanitary sci
throughout the civilized world are in error, and their efforts to e
the disease from Europe are absurd, if not farcical.

"The International Council, just in session at Vienna, on this
having unanimously agreed to its only origin being the valley
Ganges, and having proposed certain precautions by land, and q
tine by sea, to confine the disease to as limited space as possible,
it is indigenous, what argument or evidence our health-officer
well authenticated and so conclusive as to outweigh the combine
ions of the most eminent leaders in sanitary science in this c
and abroad, does not yet appear.

"Again, we are compelled to demur to the statement that c
morbus was epidemic in Saint Louis in 1873, at the time chole
vailed. The cholera-germ theory being generally received, we ma
cede a case to become dangerous or otherwise, as a larger or s
dose is received and the system has more or less power of tolera
resistance to the poison. The case may appear one of simple dia
with or without vomiting. That such cases are as properly chole
mild case of variola with a few pustules is a true case of variola, a
something else; hence the large number of deaths reported in 1
from *cholera morbus*, with a comparatively small number of death
cholera, we think should have been reversed, as cholera morbus s
we repeat, has but little of the killing agent in it."

At our request, Dr. William S. Edgar has been kind enough t
pare the following statement as to—

DEATHS FROM BOWEL-AFFECTIONS IN SAINT LOUIS DURING THE
1872, 1873, AND 1874, AS PUBLISHED BY THE BOARD OF HEAL

"It should be observed that sufficient care in the nomenclature o
nosis has not been observed—a large portion of those set down t
mer-complaint being cases of cholera infantum, and a large porti
ported as cholera morbus were doubtless cholera. Notwithsta
these inaccuracies, the report may be of some value as showing t
crease of mortality from the epidemic influence.

	1872.	1873.
Deaths from diarrhœa	138	132
Deaths from dysentery	144	132
Deaths from cholera		383
Deaths from cholera morbus	53	147
Deaths from cholera infantum	255	439
Deaths from summer-complaint	68	112
Total of all ages, from bowel-affections	658	1345

"The only variations in the above from the published mortality-reports re in the number of deaths from cholera in place of cholera morbus, as orrected in the health-office; also, in the number of deaths from cholera infantum being as much *greater* as the deaths from summer-complaint re *less* than the published reports—the totals from *all bowel-affections* ach year corresponding exactly with the published reports from the ealth-office. The cholera epidemic influence of 1873 is boldly outlined y comparison with the deaths from bowel-affections the year before nd the year after, being respectively 656 and 658, while the year between it was 1,345. Who can doubt that a specific influence operated hat year to increase the mortality?"

We have received, through the courtesy of the officers of the board of health, a record of 392 fatal cases of cholera that occurred during the period from May to October, 1873.

Of these cases there occurred in that portion of the city which is—

	Deaths.
South of Choteau avenue	184
North of Washington avenue	135
Between Choteau and Washington avenues	5
West of Grand avenue	8
At the city hospital	60
Total	392

In the southern district the first case was reported.....May 28.
In the northern district the first case was reported .....July 9.
In the central district the first case was reported.....June 1.
In the western district the first case was reported.....June 27.
At the city hospital the first case was reported.....June 22.

In the southern district the last case was reported.....October 2.
In the northern district the last case was reported.....October 15.
In the central district the last case was reported .....August 23.
In the western district the last case was reported .....July 30.
At the city hospital the last case was reported.....September 30.

The following tables are presented, as being of some statistical value:

I.—*Sex and color.*

Males, white	198
Females, white	179
Males, blacks	12
Females, blacks	3
Total	392

II.—*Condition in life.*

	No.
Single	179
Married	182
Widowed	31
Total	392

III.—*Ages.*

Under 10 years	80	From 60 to 70 years	
From 10 to 20 years	42	From 70 to 80 years	
From 20 to 30 years	64	From 80 to 90 years	
From 30 to 40 years	84		
From 40 to 50 years	63	Total	
From 50 to 60 years	32		

IV. *Number of deaths in each month.*

May	2	August	
June	34	September	
July	184	October	

V. *Table of intestinal diseases.*

Month.	Dysentery.	Diarrhœa.	Cholera morbus.	Ch in
May	2	3	10	
June	19	3	40	
July	18	19	33	
August	22	27	24	
September	37	43	15	
Total	98	95	122	

Every effort in our power was made to secure a record of reco in this we were uniformly unsuccessful, even at the City Hospital; al a list of fatal cases was furnished, our request for a full list w with no response. By Dr. F. F. Prewitt, who was resident physici ing the epidemic, and from whom we received much courteous con tion, we were informed that 183 cases were treated at the hosp whom 114 were discharged cured. These figures, taken from the report of the resident physician of the city hospital, show a discr of nine cases between that report and the statement of the officer, and would swell the death-roll to 401 cases.

We were also informed by Dr. Prewitt that carbolic acid and su of iron were freely used throughout the hospital; that the treatme sisted in the hypodermic use of morphia, and the exhibition of c in small doses.

During the epidemic one assistant physician was attacked wi disease, but recovered. One inmate of the hospital, an old ma of cholera.

We were informed by Dr. George Homan, from whom we re kind attentions, that the first case that came under his observati a female who had arrived by steamboat from some point on the river. To Dr. Walter Wyman we are indebted for much va information.

MARION COUNTY.

Hannibal, a city of some ten thousand inhabitants, is located the banks of the Mississippi River, one hundred and fifty-three above the city of Saint Louis. This city has railroad-communi with all points east and west.

The information which can be obtained of the cholera epidemic of 873, at this point, is of the most meager description, from the fact that ll the notes of the epidemic which were in the hands of Dr. James G. Hickman, the city physician, were lost.

We learn, however, that the first recognized case of the epidemic ccurred on the 6th day of June, in the person of an aged negro. This ase, however, recovered, but during his convalescence his wife and two laughters, who occupied the same house, died of the disease. Where his negro came in contact with the disease, or how he contracted it, is ot stated. Other cases followed in rapid succession, and at least one undred deaths occurred.

The disease was almost entirely confined to the district known as South Hannibal, which is built upon a low flat, subjected to overflow. In this district the water-supply is obtained from wells and cisterns. The privies were in bad condition. The disease was confined to the lower classes of society. In houses where one case occurred, others were almost sure to follow if the people remained in the house.

An attack of the disease could not always be traced to improper food. The disease caused no uneasiness among the citizens, and the large majority will never believe that cholera, as an epidemic, existed among them.

Palmyra, the county town of Marion County, had no cases of the disease.

PIKE COUNTY.

The epidemic of 1873, as it affected this county, was developed at—

1. *Louisiana*, a town of about 3,500 or 4,000 inhabitants, located upon the west bank of the Mississippi River, one hundred and fifteen miles above the city of Saint Louis, and upon the line of the Chicago and Alton Railroad; which road at this point crosses the Mississippi River.

On the 13th of June, Sam Early, a negro deck-hand upon a Mississippi River steamer engaged in the Memphis trade, was attacked with cholera at the town. He was treated by Dr. S. B. Ayres, with calomel and opium, and recovered. An active system of disinfection was instituted, but on the 18th a negress named Williams, at whose house Early had been sick, was taken with the disease and died within twelve hours. Disinfectants were again employed, and no new cases occurred until the 24th, when three negro men, who were also deck-hands upon a river-steamer, arrived at their homes in Louisiana, from Memphis. These men all had diarrhœa, and complained of malaise when they arrived. In each of these men cholera was rapidly developed. Two of them recovered after having been collapsed, one forty-two, the other forty-eight hours. The third case died after a lingering illness. June 25, a negro named Shannon, also employed upon a river-steamer, was attacked and recovered.

At this time the railroad company was engaged in the construction of the bridge across the Mississippi River. A large number of hands were employed on this work, who lived in crowded and dirty boarding-shanties; among these people the disease next appeared, and from them it spread to the city. It was noted that those persons who used the water from wells, which is strongly impregnated with lime, suffered more severely than any others. Dr. Pearson was informed by the two survivors of the three cases which he reports, that prior to their leaving Memphis they had been at the house of one of their friends, who was sick just as they were, and that some members of the family had died.

We have received a record of thirty-eight cases of cholera that oc-

curred at Louisiana from June 13 to October 1. This is, howe
no means a full record, but we have been unable to obtain retur
other physicians. Of these thirty-eight cases, twenty-one wer
Twenty-nine were whites, nine were negroes. Twenty-five were
thirteen were females. The ages ranged from six months to
years. Five cases were in the persons of children of less than te
of age, all of whom died.

Dr. Jno. S. Pearson states that at least 250 cases of cholera o
at Louisiana, 75 per cent. of which were fatal.

Dr. Ayres reports favorable results obtained from calomel, m
subnitrate of bismuth, and carbonate of ammonia.

Dr. C. Pearson used, with some advantage, quinine and stry
and Dr. Jno. Pearson obtained favorable results from strychn
galvanism.

The disease, having been contracted by the employés and othe
men on the Chicago and Alton road, was carried westward alo
line of that road.

II. *Clarksville* is a small town of Pike County, located upon t
sissippi River, fifteen miles below Louisiana.

The following letter shows that while at Louisiana there was
ficulty in recognizing and isolating the initial cases of the epide
physicians in other portions of the county failed to trace the
tion, although the same causes would affect both localities. Th
boats that brought cholera-infected negroes to Louisiana touc
Clarksville; and the county which is tributary to Clarksville i
ersed by the Chicago and Alton Railroad.

"CLARKSVILLE, PIKE COUNEY, MO.,
"*November* 4,

"DEAR SIR: I find upon inquiry that the initiatory case of ch
this section of the county occurred about twelve miles from this po
was in the person of a colored woman, the cook and house-maid
of our most wealthy families. Her diet consisted of just such
family used. The sickness occurred during the absence of the
but it is hardly to be supposed that it was induced by any inor
indulgence in diet, since she had always been used to the best th
try afforded. This farm is situated on the waters of Ramsey's
Near its head and in the valley of this stream nearly all the ca
curring in this section were found. This is pre-eminently a lim
valley. The stream is about twenty miles in length, and drains
wealthy and productive valley of about an average width of
miles. This valley lies in a northwestern direction from the m
the stream, and is bounded on both sides by rows of knobs appro
to the size of mountains. Springs and wells of living water abo
all parts of this valley, and their water is used for domestic purp
a large number of the inhabitants. This water is strongly impre
with the carbonate of lime.

"It is not known that this woman had any connection with a
from whom it is possible that she could have received the germs
disease; neither had any of the cases which followed in quick suc
on this any connection with her; but in every case, so far as I hav
able to get the data, the patient had been drinking freely of this lim
water. In the Brown-family epidemic, which consisted of seven
know that they all used this character of water. They used water

well situated near a smoke-house, where they usually kept several sacks of salt. The roof of this house was in bad condition; during each rain the salt was wet, and from it the ground was impregnated. The well was without curbing, and had not been cleaned out for fifteen years. The yard was filthy. These, coupled with the fact that the family was an intemperate one, both in eating and drinking, seem to be sufficient causes for the ravages of the disease in this family.

"All the cases in this valley amounted to about thirty-four, with twenty-nine deaths. The treatment adopted was calomel, morphia, vegetable astringents, aromatics, sinapisms, and stimulating injections. This plan of treatment was found eminently satisfactory.

"J. R. BUCHANAN, M. D.

"DR. E. MCCLELLAN,
"*Asst. Surgeon, U. S. A.*"

WAYNE COUNTY.

Mill Springs is a station upon the Saint Louis division of the Iron Mountain Railroad, one hundred and thirty-four miles south of Saint Louis, and thirty-two miles north of Poplar Bluff.

At this town, on the 15th of June, a railroad-employé, a man thirty-five years of age, was taken with the cholera, and died after a few hours' illness. The next day a married female was attacked, but recovered after an illness of a few days.

June 17, a man forty years of age, also an employé of the railroad, was attacked, and died after an illness of three days. Three other cases occurred, two of which were fatal.

Although the disease was distinctly brought into the village by railroad-employés, it is claimed that the cause is to be found in imprudence in diet and in intemperance. It is noted that all who had the disease were intemperate, and that all who avoided alcoholic excesses escaped.

The solution is found in the fact that all the six cases were connected. The disease was introduced by railroad-man No. 1; from him Mrs. Witham was infected, her infant being the next case; then railroad-man No. 2, then Henry Witham, and finally Mrs. Maples completes the group.

BUTLER COUNTY.

Poplar Bluff is a small village of Butler County, and a station on the Saint Louis and Texas division of the Iron Mountain Railroad, one hundred and sixty-six miles south of Saint Louis. It is also a terminal point of the Cairo, Arkansas and Texas Railroad, being seventy-one miles from the city of Cairo.

In the month of June, 1873, this town was in a filthy condition; the railroad-extension brought into it a large number of Irish laborers, who lived in boarding-shanties in utter defiance of all sanitary requirements. On the 19th of June a man named Axtel, who was a contractor upon the railroad, arrived from Saint Louis. The disease was fully developed soon after his arrival, and he died within ten hours. Although the necessity was strongly urged by Dr. James A. Greer, no precautions were adopted, and the body was allowed to remain until it was in an advanced stage of decomposition before it was buried. Those persons who remained near his body were the next attacked, and from them the disease was communicated to others and became epidemic.

We have been unable to obtain reports from all the physicians of this town, Drs. J. A. Greer and J. Nixon alone responding to the application

for information. By these gentlemen twenty-one fully-developed are reported; of them fifteen proved fatal. Many of these cas their course very rapidly. Two cases are reported in which th termination was reached in one hour after the disease was deve and three others in which it lasted but from two to six hours.

Dr. Greer reports that fully 90 per cent. of the cases were fr lowest class of the community, and among the feeble and old. persons who were addicted to intemperance were especially liable disease.

In the cases which have been reported great care was had to di and bury all the discharges and to disinfect soiled clothing.

COLE COUNTY.

Jefferson City, the capital of the State of Missouri, is situated south bank of the Missouri River, which stream is a mile wide a point. The city is built upon broken bluffs, with high hill-lands e ing south for miles. The location has been considered perfectly h there being no local causes of disease, other than the supposed matic region of the rich and fertile bottom immediately opposite, north side of the river.

In past years this city has been visited two or three times by epi cholera; in 1849 in a fearfully aggravated and fatal form. In 18 city was threatened with the disease, but by resorting to the most disinfection the danger was averted. In each instance the outbre been traced to exotic cholera-germs transported by the travel cholera-patients.

Jefferson City being upon the line of the Missouri Pacific Ra and also the southern terminus of the Chicago and Jefferson City l of the Chicago and Alton Railroad, is in constant communicatio the cities of Saint Louis, Mo., and Chicago, Ill.

The earliest record of cholera which can be obtained at Je City, in the epidemic of 1873, is reported by Dr. C. A. Thomps having occurred on the 22d of June, in the person of one Sau who had arrived the day preceding from the city of Saint Louis. man was seriously ill, but was convalescent by the end of the m June 27 a negro man named Scruggs, who had been working at th grounds, was taken with cholera and died the same day.

With these cases the demonstration subsided, and no cases ported until the 26th of July, when cholera suddenly appeared Missouri State penitentiary, in the person of a convict named W in a few hours a convict named Williams was attacked; both cas minated fatally within a few hours.

These men both belonged to a gang of convicts who had bee ployed in loading stone from a quarry upon the river-bank on a Louis boat. In this work the men crossed and recrossed the Mi Pacific Railroad track innumerable times each day.

July 30 two other men in the same gang were both attacked cholera; one died. From this date the disease became epidemic i prison, but was confined to one building, and to the shops at whic men worked whose cells were in that building.

From Dr. R. E. Young, the surgeon of the penitentiary, we ha ceived much valuable information.

"Except in four cases that occurred at the penitentiary, no exc cause could be found. In two cases it was said that green grape been eaten, but sixty other men ate of the same kind of grape

ere not attacked. Four days elapsed between the first two and the ird case; the last had no chance to eat grapes.

"Great care was taken in the male department of the penitentiary regard to diet, ventilation, and disinfection, and thirty-four cases oc-rred. Among thirty females closely crowded together in a poorly entilated building, no cases occurred. No connection existed between he male and female departments. Nineteen of the cases occurred in he persons of men employed outside the prison walls. One man only as on night-work. Fifteen were in the persons of men working in the hop. Only five slept in poorly-ventilated cells. Of the nineteen out-oor laborers, sixteen used a common privy. The fifteen who worked n the shops used a privy under which flowed a stream of water. One uard, who used this last privy, and was exposed to the drain from it, as attacked and died. Of one thousand men and women within the alls, nine hundred and seventy-five were treated for diarrhœa during he cholera epidemic. In all cases the liquid purged and vomited was t some time free from bile. Rice-water discharges occurred in all the holera cases, with cramps and vomiting. In the majority of the cases cyanosed appearance was present. In all cases the urine was either uppressed or notably decreased. The breath was cold and the temper-ature lowered.

"Of the thirty-seven cases not one occurred in the day. Twenty oc-curred before midnight, sixteen after midnight but before day. Of the thirty-seven cases, twenty-two were strong, active men, doing daily labor. Fifteen at the time of their attack were sick of other diseases.

"The diet of the convicts at the time of the outbreak was wheat-bread, beef, potatoes, onions, tomatoes, coffee, and tea."

The drains from the penitentiary privies, &c., empty into a small stream east of the walls of the institution, at its junction with the Missouri river. During the epidemic two men arrived in a fishing-boat from Kansas City, and pitched a tent upon the river-bank, just opposite to the mouth of this drain. Both men died of cholera within a few days of their arrival.

From the penitentiary the disease was carried into the city. A total of sixty-three cases are reported. Of these, fifty-six were males, seven were females. The ages ranged from one year to seventy years. The condition of life was good in fourteen cases, and very bad in forty-nine. The social condition of the vast majority of the cases was unknown.

The treatment adopted was opiates, calomel, and astringents. Carbolic acid was exhibited in some cases. Ammonia was the stimulant most used.

Lincoln County.

Troy, the county-town of Lincoln County, has about seven hundred inhabitants. The town is located near the Cuivre River, about sixty miles northwest of Saint Louis.

We have no definite information as to how the epidemic originated at this point. Dr. J. A. Ward, who alone responded to our call for information, is of the opinion that it was due to atmospheric influences.

The first recognized case occurred in the person of a negro, on the 22d day of June. We quote from a letter of Dr. Ward, dated September 29, 1874:

"The first two or three cases of cholera caused an alarm among our people, whereupon an ordinance was passed by the city council ordering all the sinks, privies, cellars, &c., to be thoroughly cleansed. This was

done, and by the stirring up of the same, together with the newly streets, let loose all the noxious gases contained in the same, f ing a cause for the disease, then almost everywhere in the atmos

SAINT CHARLES COUNTY.

This county occupies a neck of land formed by the confluence Missouri with the Mississippi River. The county is well draine is alternately hilly, rolling, and level. It overlies a limestone Saint Charles, the county-town, is upon the Missouri River, twen miles above its mouth. At this town no cases of cholera occu 1873, as we have been informed by Dr. B. W. Rogers.

Portage des Sioux is a small village of Saint Charles County, up Mississippi River, a few miles above the mouth of the Missouri information as to the epidemic of 1873 at this point, which w been able to obtain, is contained in the following letters:

"PORTAGE DES SIOUX, MO., *October* 17,

"The cases I have given you are what I term *cholera cases.* been opposed by my worthy friend, Dr. J. L. Thomas, of this plac terms them congestive fevers and congestion of the bowels. The no suppression of urine in my cases of congestive fever, while it oc in cholera cases. I claim that there are many differences betwee disorders. As to the cause of this disease it is hard to determine. my cases were of the working-class, who mostly labor in the su drink a great deal of water, perspire profusely during the day, night (which is the usual time of the attack) sleep in a draught of am rather inclined to think that the disease is malarial, and ab during the hours of rest.

"In the treatment of the cases which came under my care, I upon large doses of calomel, with columbo and ipecacuanha.

"Respectfully,

"ISAAC MOORE, M

Under date of November 20, 1874, Dr. J. L. Thomas, from P des Sioux, writes as follows:

"The epidemic commenced here about the 1st of July, and con about two months, more or less. The symptoms were those of c epidemica, but the cases were confined to a very malarial district and a half or three miles in circumference. There were, I su twenty-five or thirty deaths, the most of which occurred without m aid. The locality in which it broke out was on a slough or back from the river. The Lineman family was quite large, and abou thirds of them died. Their residence was almost surrounded by nant water. The water they drank was thought by many to have c the disease.

"It is quite clear to my mind that the symptoms of this epi from its incipiency to the last stages, was that of a bilious cha The attack was either ushered in with a slight chill, or ended as an mittent. The symptoms were those of marked congestion: vomiti purging; cramps slight; shriveling of skin of the fingers and toes lessness; intense thirst; dark hue of the skin; sunken eyes; p sweating; rose-colored specks or papillæ on the trunk. The disch that I saw were not rice-water."

Dr. Thomas details his favorable experience in the use of quini

HOWARD COUNTY.

Fayette is a small town of about one thousand inhabitants, the county town of Howard County. It is located upon Bonne Femme Creek, about sixty miles northwest of Jefferson City. The Missouri river approaches within ten or twelve miles of the town at two nearly opposite points.

Howard County is the largest tobacco-producing county in the State; the surface is undulating, the soil remarkably fertile, and upon a limestone formation. The town has connection with the Saint Louis, Kansas City and Northern Railway.

The information that we have been able to gather of this demonstration of the disease is most unsatisfactory. We learn that the first case occurred late in July, in the person of a Swede who had been employed upon the railroad. This man had been drinking for several days, came into the town, was taken with cholera, and died after a few hours' illness.

The next ten or twelve cases occurred among railroad laborers with whom the first case had been in contact. They were living in an old stable that had been turned into a boarding-house for the railroad hands. These cases were all fatal.

From this locality the disease was carried into a negro settlement, and a number died. From this point the disease spread, and a number of the very best citizens of the town were infected. It is stated that a total of fifty-six cases occurred, and that but three of these cases recovered.

The free exhibition of calomel was found successful in the treatment of cases that did not advance to collapse.

MORGAN COUNTY.

Versailles, the county town of Morgan County, is the center of a fertile farming district, forty miles southwest of Jefferson City.

Drs. Thurston and Williams report that the first case of cholera in 1873, at this point, occurred on the 18th day of August in the person of a white man sixty-eight years of age, who had the day before returned from a visit to the State of Illinois.

The second case occurred August 26 in the person of Dr. John Boone. The record does not state whether or not Dr. Boone had been in attendance upon the first case. Both cases terminated fatally. Thirteen cases are reported, of whom eleven died.

These gentlemen report that they treated over one hundred cases of painless diarrhœa during the epidemic, and that the disease was always to be controlled when early attention was paid to the cases. It is also noted that where a tendency to collapse existed, opium did harm.

Dr. S. V. Sterner, also of Versailles, is of the opinion that "there was no real Asiatic cholera at that point in 1873, although there were some cases of choleraic diarrhœa attended with cramps."

CHAPTER XI.

KENTUCKY GROUP.

KENTUCKY CONTRIBUTORS.

Dr. J. W. Thompson, McCracken County.
Dr. J. W. Becker, McCracken Co.
Dr. B. Tauber, McCracken Co.
Dr. J. A. Maxwell, McCracken Co.
Dr. D. D. Thompson, McCracken County.
Dr. R. Saunders, McCracken Co.
Dr. P. K. Worthen, McCracken Co.
Dr. C. R. Royster, McCracken Co.
Dr. A. C. Wright, Warren County.
Dr. J. F. McElroy, Warren Co.
Dr. Miller, Warren County.
Dr. Van Meter, Warren County.
Dr. Waggoner, Warren County.
Dr. L. C. Porter, Warren County.
Drs. Combs and Atchison, Warren County.
Dr. Thomas, Warren County.
Dr. Lackey, Warren County.
Dr. Malloy, Simpson County.
Dr. Foline, Simpson County.
Dr. G. W. Duncan, Simpson Co.
Dr. Edwards, Simpson County.
Dr. James Duncan, Simpson Co.
Dr. W. R. Bryan, Simpson County.
Dr. Milliken, Simpson County.
Dr. Suddeth, Simpson County.
Dr. Simmons, Simpson County.
Dr. Richards, Simpson County.
Dr. Hawthorn, Simpson County.
Dr. B. Letcher, Henderson Co.
Dr. J. H. Letcher, Henderson Co.
Dr. J. J. Diehl, Henderson Co.
Dr. J. A. Hodge, Henderson Co.
Dr. J. O. Collins, Henderson Co.
Dr. W. D. Furman, Henderson Co.
Dr. J. L. Cook, Henderson Co.
Dr. Thompson, Henderson Co.
Dr. J. B. Cook, Henderson Co.
Dr. W. M. Hanna, Henderson Co.
Dr. James Beaty, Henderson Co.
Dr. J. A. Carr, Caldwell County.
Dr. H. T. McNary, Caldwell Co.
Dr. J. A. Maxwell, Caldwell Co.
Dr. L. W. Jones, Caldwell County.
Dr. Charles H. Todd, Davie
Dr. Haines, Daviess County
Dr. Stewart, Daviess Count
Dr. W. D. Sturman, Davies
Dr. B. H. Hobbs, Daviess C
Dr. O. Newland, Christian C
Dr. J. D. Woods, Barren C
Dr. H. McDowell, Harrison
Dr. J. K. McCreary, Shelby
Dr. W. R. Pusey, Meade C
Dr. N. B. Lewis, Carroll Co
Drs. Davis and Taylor, W
County.
Dr. L. Prichard, Carter Co
Dr. J. W. Prichett, Hopkin
Dr. W. McNarey, Hopkins
Dr. N. L. Taylor, Adair Co
Dr. J. C. Cassidy, Crittend
Dr. W. S. Graves, Crittend
Dr. Lindsey, Trigg County.
Dr. Stanrod, Trigg County.
Dr. Slaughter, Hardin Cou
Dr. Anderson, Hardin Cou
Dr. Pusey, Hardin County.
Dr. A. Warfield, Hardin C
Dr. Davis, Hardin County.
Dr. Fletcher, Hardin Coun
Dr. Berry, Oldham County.
Dr. Douden, Oldham Coun
Dr. David Keller, Bourbon
Dr. J. F. Hickman, Nelson
Dr. N. G. Leake, Nelson C
Dr. Wilkinson, Nelson Cou
Dr. Wise, Nelson County.
Dr. A. Smith, Nelson Coun
Drs. Chandler and Bass,
County.
Dr. W. T. Chandler, Taylor
Dr. Hodgen, Taylor County
Dr. Schively, Taylor Count
Dr. J. S. Warren, Garrard
Dr. S. L. S. Smith, Garrard
Dr. W. Berry, Garrard Cou
Dr. F. C. Wilson, Garrard
Dr. L. S. McMurtry, Garra
Dr. Reid, Garrard County.

Dr. P. B. McGoodwins, Caldwell County.
Dr. J. A. King, Caldwell County.
Dr. Lewis Rogers, Jefferson Co.
Dr. S. L. Manly, Jefferson County.
Dr. T. Anderson, Jefferson County.
Dr. Atchison, Jefferson County.
Dr. S. A. Foss, Jefferson County.
Dr. F. Paschel, Jefferson County.
Dr. John M. Duke, Mason County.
Dr. Adamson, Mason County.
Dr. Schackelford, Mason County.
Dr. Pickett, Mason County.
Dr. J. W. Williamson, Union Co.
Dr. W. A. Jones, Union County.
Dr. W. W. Henderson, Kenton Co.
Dr. A. Kullman, Kenton County.
Dr. J. T. Wise, Kenton County.
Dr. J. F. Christian, Kenton Co.
Dr. J. M. Riffe, Kenton County.
Dr. J. J. Temple, Kenton County.
Dr. F. H. Noonan, Kenton Co.
Dr. J. B. Stevens, Kenton Co.
Dr. D. H. Jessup, Kenton Co.
Dr. C. F. Thomas, Kenton County.
Dr. J. H. Blane, Kenton County.
Dr. E. H. Luckett, Daviess Co.

Dr. S. P. Craig, Lincoln County.
Dr. W. H. Spillman, Mercer Co.
Dr. J. D. Jackson, Boyle County.
Dr. W. B. Harlan, Boyle County.
Dr. J. M. Meyer, Boyle County.
Dr. W. W. Cleaver, Marion Co.
Dr. W. H. Hopper, Marion County.
Dr. M. Schuck, Marion County.
Dr. J. Shuck, Marion County.
Dr. W. E. Mattingly, Marion Co.
Dr. B. W. Avritt, Marion County.
Dr. Palmer, Marion County.
Dr. Warren, Marion County.
Dr. Blenco, Marion County.
Dr. B. J. Moore, Marion County.
Dr. H. B. Peterson, Marion Co.
Dr. L. D. Knott, Marion County.
Dr. W. R. H. Carr, Marion Co.
Dr. J. B. Evans, Marion County.
Dr. Porter, Marion County.
Dr. D. O. Polin, Washington Co.
Dr. J. R. McGee, Washington Co.
Dr. J. Debo, Washington County.
Dr. B. F. Wood, Washington Co.
Dr. McElroy, Washington County.
Dr. James Fields, Russell County.
Dr. L. M. Lovelace, Ballard Co.

Surgeon William J. Sloan, U. S. A., Medical Director Department of the South.
Acting Assistant-Surgeon R. G. Redd, U. S. A.
Acting Assistant-Surgeon S. L. S. Smith, U. S. A.
Surgeon P. H. Bailhache, U. S. Marine-Hospital Service.

DATES OF INITIAL CASES.

McCracken County .....May 21.
Warren County .....June 3.
Simpson County .....June 5.
Jefferson County .....June 8.
Henderson County .....June 16.
Trigg County .....June 16.
Union County .....June 16.
Carter County .....June 20.
Kenton County .....June 22.
Caldwell County .....June 29.
Ballard County .....June 29.
Mason County .....June 29.
Henry County .....July 6.
Oldham County .....July 8.
Hardin County .....July 8.
Bourbon County .....July 10.
Taylor County .....July 12.
Carroll County .....July 12.
Christian County .....July 12.
Barren County .....July 19.
Daviess County .....July 19.
Hopkins County .....July 20.
Meade County .....July 27.
Webster County .....July 31.
Garrard County .....August 10.
Marion County .....August 11.
Nelson County .....August 20.
Lincoln County .....August 29.
Adair County .....August 29.
Washington County .August 30.
Boyle County .....August 30.
Clinton County .....August 31.
Mercer County .....September 6.
Russell County .....September 9.

NOTE.—The disease prevailed in Fulton, Harrison, and Crittenden counties, but from want of sufficient information these counties are not embraced in the narrative.

olently ill; was carried to his home; cholera was fully developed, and e case terminated fatally after an illness of eight hours.

There is a popular report among certain citizens of Paducah that on e day preceding the death of Mr. Baldwin, a young girl who lived ar the steamboat-landing, and who had returned to the city from a sit to some point below Paducah on the steamer Kilgore, died of the me disease. The physician who attended this case being now in irope, and the family to which she belonged having removed from the y, no accurate information as to the case can be obtained.

Mr. Baldwin was attended, during the few hours that his illness sumed a violent form, by his friend, Mr. P. E. Calhoun; and by this ntleman the last services to the body of his dead friend were ren-red. On the 23d of May, Mr. Calhoun was seized with symptoms of olera, and at once secured medical attendance. The disease was fully veloped, and the patient barely escaped with his life.

Three cases, none of which terminated fatally, occurred among ne-oes frequenting the wharf-boat and tobacco-warehouses.

With these cases the disease subsided, as far as can be discovered, til June 3, when a Mrs. Mary W. Bechtold, a German woman, thirty-e years of age, arrived at her home, after a visit to Memphis, Tenn. rs. B. arrived by the noon train on the Memphis and Paducah Rail-ad, and after reaching her house was in perfect health and spirits, d so continued until a few moments after she retired to bed at 10 lock p. m., when experiencing an urgent desire to empty her rectum, e left her bed and went to stool. A few moments later and the desire turned; this time the action was profuse and watery. Others fol-wed in rapid succession; by midnight she was fully collapsed, and at o'clock a. m. the next day (June 4) she died.

During the illness of Mrs. B., she was nursed by her friend, Mrs. rsa Engle, who resided in the next block. By Mrs. E. all the excreta re emptied, the clothing was removed, and the body prepared for the ve. After the funeral on the 5th of July, Mrs. E. was taken with a ght diarrhœa, which continued for three days, or until the 8th, when e severity of the symptoms increased, cholera was fully developed, d the case terminated fatally after an illness of forty-eight hours.

From these two cases the disease spread. The location of the dwell-gs in which these deaths occurred is shown upon the map, and it ll be seen that they form the initial point in the infected district of e city. It is also an ascertained fact that the majority of the river-eamers that touched at the wharf-boat of this city during the month June were more or less infected with cholera.

On the 10th of June, a deck-hand of the steamer Quickstep was carried the city hospital, where he died of cholera the next day. Dr. R. nders reports the cases of two negroes who were removed from the eamer Fisk to their homes in the city on the 19th with cholera. On 21st the body of a negro who had died of cholera was removed by city sexton from the same boat; and on the 22d the same vessel d a fatal case to the city hospital. Early in June a few fatal cases cholera occurred among the laborers employed at, and the individu-who frequented, the tobacco warehouses. Of the last-named class, case of Mr. R. S. Cobb is illustrative. Mr. C. was a gentleman f eight years old, in easy circumstances, whose residence was in one e best locations of the city. This gentleman was a tobacco-buyer, frequented the warehouses devoted to that trade. He was temper-nd methodical in his mode of life. June 15 he was awakened at an hour of the morning by an uneasy sensation in his bowels, which

resulted in two or three rather loose actions. He, however, breal as usual, and after visiting the market paid his morning visit warehouses. While at the Planters' tobacco warehouse, (Buch Terrell,) the severity of the diarrhœa was increased and he had large, watery, and exhausting actions. At 12 o'clock m. he v moved to his home; at 3 o'clock p. m. he was perfectly collapse died at 11.30 o'clock a. m. the next day.

The case of Henry Fletcher, an employé of Buckner & Terrell Planters' warehouse, is illustrative of the onset of the disease his class. This man, an active and most respectable negro, forty of age, was taken with a light diarrhœa June 10, which contin three days, during which he remained at his work, using the c privy of the warehouse, (Mr. Cobb used the same privy before an his attack.) June 14, the diarrhœa still continuing, Fletcher dose of cathartic pills, and attended the funeral of a child that h the day before of cholera. While at the grave he was take cramps; was carried to his home, where he died at 2 o'clock p. same day. This man had been a religious leader among the n and previous to his attack had visited all who had been taken w disease.

It will be noted by reference to the accompanying map that cases occurred in that portion of the city overlying the bed of red of which mention has already been made; and it is worthy of no but one multiple instance occurred within these limits, which pied almost entirely by the better classes of the community, houses were invariably supplied with cistern-water.

In that portion of the city which is located upon alluvial so which is represented by the deep shadings upon the map, the was epidemic and raged with virulence. This portion of the inhabited by the middle and lower classes, Germans, Irish, and n whose drinking-water was obtained from wells which could supplied by surface-water. Some few residences of individuals better classes in this portion of the city, which were supplie cistern-water and kept in good sanitary condition, were not vis the disease. On the 25th of June the sale of vegetables was pro in the city, and the mortality among the negroes began to de this, however, did not apply to the German population, who, reg of the prohibition, on each Sunday would visit the country and in vegetable food, besides bringing into the city a supply for the and it became a recognized fact that each Monday a larger nun persons from this class were buried than on any other day of th

We are informed by the physicians of this city, who remaine stantly at their post, that it was by no means an uncommon t find negroes upon the streets in all stages of the disease, and th seemed particularly applicable to those who worked upon the wharf. No physician died of the disease, but all suffered more with the premonitory symptoms. Those who attended the si cared for the dead were not exempt from the disease. An illus of this will be found in the case of Sister Ursula, who nursed de the wife of a drayman named Donovan, until released by the d the patient, when she was herself attacked with the disease at th ious house of which she was a member, and died June 23, after short illness. Her death was followed by numerous cases of acut rhœa among the other inmates of this house, which were all, be arrested in the second stage. Disinfectants were actively use every effort was made to improve the sanitary condition of the i

istrict; but from the 14th of June to the 29th of July the disease raged maintained undoubtedly by constant cholera arrivals from infected oints both on the river and railroads.

The medical men were indefatigable in their battling with the disease. When any one of their number was prostrated, the additional labor was ngrudgingly performed by the well, and to their honor be it said, that his excess of labor was almost entirely gratuitous. While constantly orking by day and night, it was among a class of the community who ere unable to reward their physician that demanded his expenditure f time and skill, this personal exposure to contagion, but in all instances he necessities of the poor were as promptly considered as were those of the wealthy, and this when the existence of the disease almost ntirely destroyed the professional income of these brave, devoted men.

The treatment most relied upon during this demonstration of the disease was calomel, opium, and stimulants. In all instances where the patient was reached in the early stage of the disease it was arrested, and convalescence resulted. Some few instances of recovery from prolonged collapse are reported. Dr. Saunders reports very strongly in favor of the hypodermic use of atropia, and under date of October 26, 1873, states in some forty or fifty cases in which he made such exhibition of this remedy, none of the cases advanced beyond the second stage of the disease. December 4, 1873, Dr. S. writes, in all cases which came under his observation, in the first or second stage of cholera, he exhibited hypodermically, atropia gr. 1-30, morphia gr. 1-6, and repeated in from four to six hours as required.

In McCracken County cholera was developed at but two points outside of the city of Paducah. On the 29th of May, a farmer living at what is known as the Cross-roads, some six miles distant from Paducah, who had been in the city on the previous day, was taken with cholera. The disease was fully developed, but after an illness of ninety-six hours the patient was pronounced convalescent. This case was followed by the occurrence of five distinct cases of cholera, two of which terminated fatally. In this group the connection of the cases with Mr. Morrow, who contracted the disease at Paducah, is absolute.

The demonstration of cholera at Woodville, a village some twelve miles to the southwest of Paducah, is of great interest.

On the 13th day of June, a man named Taylor, who resided three and a half miles from Woodville, went on business to Paducah, and remained one day and two nights at that city. On the 15th he returned to his home and complained somewhat of diarrhœa. In a few hours cholera was fully developed. Early on the 16th he was found by Dr. Marshall, of Woodville, in collapse, and in a few hours died. Disinfectants were freely used, and no other cases occurred in the neighborhood.

On the 28th of June, a Mrs. Benton, who lived two miles north of Woodville, was taken with cholera and died in a few hours. This woman, who was a widow, lived in an isolated position, in an old dilapidated log-house upon the banks of a small creek. The yard around this house was covered with high grasses and weeds. The ground was covered with *débris*. The family used water from a well on the hill-side, some 60 or 80 yards from the creek. This well was curbed with planks which were rotten. It was supposed that this woman could in no way have been exposed to the infection of cholera. Dr. C. G. Royster, of Woodville, who reports the case, did not reach her bedside until the patient was hopelessly collapsed.

June 29, John Rogers, aged thirty years, a son of Mrs. Benton, and who resided with his mother, was attacked with cholera, and died after

an illness of but six hours. Rogers was a single man, of no fixed ployment, worked whenever he could obtain work, and it was f that during the previous week he had visited several trading-boats point on the river some five miles from his home. For two days vious to his attack Rogers had suffered from diarrhœa, and on the before his mother was attacked had many painless dejections on ground in the vicinity of the house.

After Mrs. Benton was taken sick on the 28th, her married daug Mrs. Sink, who lived nine miles distant, was sent for and arrived a mother's house two or more hours before Mrs. Benton died. Mrs. was accompanied by her husband and young child. These peopl mained at this house until after the funeral of Rogers, when, as they about to return to their home, the young child was taken with a pr watery diarrhœa. Dr. Royster administered a full dose of calomel directed absolute rest. The next day (June 30) the child's cond being much improved, preparations for departure were again m when Mrs. Sink was suddenly taken with an urgent desire to go to and had a large watery dejection, which prostrated her so severely she was carried into the house. Laudanum, calomel, and brandy administered, and the surface of her body was covered with sinap While Mrs. Sink was being treated, her husband was attacked almost identical manner, and the same line of treatment was ado In both cases absolute rest was enjoined upon the patients. Ju Mr. and Mrs. Sink, with their child, all being convalescent, starte their home, accompanied by Phil. and Tom Rogers, and Ida Be the young brothers and half-sister of Mrs. Sink. The family arriv home safely, but during the succeeding night the disease was a developed in the person of Mr. Sink, and soon after daylight he violently ill. Failing to secure medical attendance, a runner was patched to Woodville. At 8 o'clock a. m. (on the 3d) Phil. Rogers attacked with cholera; at 11 o'clock a. m., Mrs. Sink was taken the same disease; and when Drs. Royster and Marshall arrived Woodville, at 3 o'clock p. m., Mr. Sink was dead; Phil. Rogers w *articulo mortis;* Mrs. Sink was hopelessly collapsed; and she died o'clock p. m. the same day.

About 6 o'clock the same evening Tom Rogers had a large, wa and exhausting dejection. He was placed at once in bed, and landa calomel, and quinine were administered. During the same night Benton was attacked in the same manner, and the same treatment had. Both cases recovered, although the convalescence in both tedious and slow. No other cases occurred. A sister-in-law of Sink was assiduous in her attention to the sick in this demonstra She remained alone in the house during the night of July 3 with two sick children and the dead, but did not at any time exhibit symptoms of the disease.

Warren County.

Bowling Green, the county seat of Warren County, is a well-loc inland city, situated nearly in the center of the county, upon the of the Louisville and Nashville Railroad, and one mile from the be navigation of the Barren River. Railway communication with L ville, Memphis, and Nashville is almost hourly. Twice each we steamboat arrives from Evansville, Ind.

The data of the epidemic of cholera at Bowling Green is unsati tory, from the fact that none of the physicians had preserved recor

heir cases. The burial permits of the county clerk, however, furnish eliable information as to fatal cases.

June 3, the first case of cholera occurred in the person of a white nan, forty-three years of age, who left Gallatin, Tenn., at the time chol, ra was epidemic at that point, on a business visit to the Horse Cave station, some few miles north of Bowling Green. He was taken ill on his arrival at Horse Cave, and took the next train, endeavoring to reach his home.

By the time the train arrived at Bowling Green the disease was fully leveloped. He was carried to a hotel, where, after a lingering illness, he died. The excreta of this case were disinfected and buried. No other case, as far as can be learned, is to be traced to any connection with it.

June 13, the second case occurred in the person of a negro woman, fifty-five years old, who had the day before washed the clothing of a man who died of cholera on a steamboat during its trip from Evansville, Ind. The case terminated fatally in thirty-six hours. From this case the disease spread and became epidemic; but was confined almost exclusively to that portion of the city which is located on low ground between the railroad and the river, while the inhabitants of the main portion of the city escaped almost entirely. The drinking-water of the infected portion of the city was obtained almost universally from wells; while that of the districts which escaped the epidemic was supplied from the Barren river by the reservoir system. We have recovered the facts of 86 cases of cholera which occurred at Bowling Green between June 13 and August 10; of these cases 65 terminated fatally.

The disease was carried from Bowling Green to a point in the country some ten miles to the southeast of the town by a refugee negro man, and at the house at which he found employment six fatal cases occurred.

Woodburn, a small village of Warren County, located upon the line of the railroad, about half way between the city of Bowling Green and the town of Franklin, suffered most severely from the epidemic, over one hundred cases having occurred, a large number of whom died. We are unable to obtain any satisfactory information as to this demonstration. Although the village is in such close communication with two large towns where the disease was introduced, and became virulently epidemic, Drs. Lackey and Williams failed to detect the introduction of the disease into Woodburn, and are rather inclined to ascribe its occurrence to malarial influences. They report one case of recovery after the administration of half an ounce of quinine; another recovery in which two-thirds of an ounce of quinine was used. In both cases, however, opium and calomel were administered.

Simpson County.

Franklin, the county-seat of Simpson County, is situated on the line of the Louisville and Nashville Railroad, six and a half miles from the State line. The town has a population of 1,240 inhabitants, 569 of whom are blacks. (Census of 1870.)

One mile east of the town flows the west fork of Drake's Creek. The town is situated on rather an elevated position; is well drained by two ravines which pass through the town, one to the east and the other to the west of the court-house, which building forms the center of the town. These drains come together north of the town and empty into the creek.

The inhabitants of this town have constant communication with all

points on the railroad, and a number of the section-hands of this
working on the section between Franklin and Millersburgh, Tenn., r
in the town. During the month of May the town was in good san
condition: much *débris* had been removed and destroyed. No cas
serious illness occurred in the town until the 5th of June, when
Hayes, a negro woman, forty years of age, who had been on a vi
Gallatin, Tenn., was taken with cholera at her home the day of h
turn, but recovered after a serious illness. The house in which sh
sick was one of a cluster of cabins occupied by negroes on the n
east outskirts of the town, and although all the local conditions se
favorable for the spread of the disease, no other cases occurred. I
fectants were freely employed.

June 10 a white man, thirty-eight years of age, who had ret
from a visit to Gallatin, Tenn., was attacked with cholera, but recov

June 12 a white man fifty-one years of age, also from Gallatin, T
was taken with cholera, and died after an illness of ten days.
physician who attended this case was attacked with the disease
13, and recovered after a serious illness. A little daughter of this
sician was attacked, June 14, with the same disease, and died in
hours. In the excitement and dismay caused by this last case, the
cautions which had been adopted in the earlier cases were negl
The excreta were not disinfected, but were thrown upon a heap of
against the rear fence of the back-yard.

Four days elapsed without the development of new cases, wh
white man, forty years of age, who lived near the point at which
excreta of the little girl had been deposited, was taken with th
ease and died. From the 19th to the 28th of June, six fatal case
curred.

From the 28th of June to the 1st of July the disease was in abey
but on the last-named date seven cholera deaths occurred, and in the
fifteen days fifty deaths are reported as resulting from this disease.
July 20 a fatal case occurred, and cases of the same character are rep
on the 28th of July and 4th of August. During the course of the
demic, seven of the physicians of the town were seriously ill of the
ease, one of whom died. One case of cholera occurred at the co
jail in the person of the wife of the jailer, who died after a few h
illness. The prisoners were at once removed from the building, an
cases occurred among them.

From Franklin the disease was carried into the county. A Mr. V
left the town July 1, and went to a farm six miles distant; afte
arrival he was attacked with cholera, and died after an illness of
eight hours. July 8 the mother-in-law of Vance, who resided in
same house, was attacked with the disease and died, and within
days a young child of the same family, and a visitor at the house,
attacked and died. A Mrs. Pearson, after nursing many cholera-ca
the town, went to the farm of her son-in-law, four miles from tow
a rather isolated position. Mrs. P. was not sick, or suffering in any
except from the physical fatigue induced by her Christian effor
caring for the sick. The family of the house to which she went ha
been exposed to the infection; no member of the family had been i
infected district, and no one but Mrs. P. had come from that
trict; yet, two days after her arrival, the son-in-law was taken
cholera and died. All the other members of the family suffered
or less with diarrhœa.

A number of recoveries are reported.

COUNTY.

ase of cholera which is recorded as having occurred in Jef-
y, in 1873, was in the city of Louisville, on the 8th day of
a white man twenty-nine years of age was admitted to the
with cholera. He had arrived in the city at 5 o'clock a. m. the
m Evansville, Ind. At 5.30 a. m. he was taken with purging
g, which increased so rapidly in severity that he was obliged
on the sidewalk. From this position he was removed by
d taken to the hospital. Cholera was fully developed, and
e disease at 4.37 p. m. of the same day.

gentleman, forty years of age, living on Walnut street,
venth and Eighth streets, was taken with cholera follow-
œa of a few days' duration. The second stage was fully
hen the disease was arrested.

conductor on the Louisville and Nashville Railroad, who
ken ill at Nashville, Tenn., arrived at his home on Eleventh
Broadway, still suffering with the acute diarrhœa. Cholera
y developed, and the case terminated fatally after twenty-
lness.

e 12 to August 16, inclusive, twenty-one cases, all of which
atally, are reported in the city. In the majority of these
plosion of the disease was in the persons of individuals who
to the city from infected districts.

th and 18th of August, two deaths from cholera are reported
small town of Jefferson County, some ten miles distant
lle. It is not known in what way these individuals came
ith the infection, other than that they were in the habit of
Louisville market once a week. The district in which these
d was decidedly malarial, but the cases of disease from that
at summer been unusually infrequent. No cases followed
who nursed these cases and performed domestic offices for

r 4, at Louisville, a young female, fourteen years of age, died
fter nine hours' illness, and the same day and in the same
te child four weeks old was taken with the same disease,
er forty-eight hours. The history of this family is of great
the report is transcribed in detail.

ORY OF CHOLERA IN THE BAUER FAMILY.

BY TURNER ANDERSON, M. D., *Louisville, Ky.*

of family on the south side of Green street, between Four-
Fifteenth, frame cottage, low and damp; kitchen floor several
the surrounding ground; no provision for drainage. Privy,
and coal-shed under one roof, and all in dirty condition.
sisting of the mother, two single daughters, two married
one son-in-law, and two grandchildren.

t 11 p. m., was called to see Mrs. G., one of the married
Found her vomiting, purging, and cramping. The attack
udden, and without any known cause. Morphia was exhib-
rmically, and quinine, gr. v., ordered to be given every second
was followed by the prompt relief of all symptoms of the
in forty-eight hours she was out of bed. Two weeks pre-
lady had been delivered of a male child. On the 22d of
. G. went to Bowling Green, Ky., to visit her husband, who

was engaged in business at that town. August 25, two days afte
arrival in Bowling Green, Mrs. G. was taken with cholera, and died
twenty-four hours' illness. August 28 the body of Mrs. G. was bro
in a wooden coffin to Louisville, and taken to her mother's house.
to burial the coffin was opened and the remains of Mrs. G. were vi
by her family.

September 2, a child of the late Mrs. G., two years of age, was t
with diarrhœa and vomiting. It was treated with albuminous dr
soda, morphia, and mint-water, and recovered.

September 4, a single daughter of Mrs. B., fourteen years of age
taken with cholera at 5 o'clock a. m. At 7 o'clock a. m., when call
the case, found the patient collapsed, and she died at 1.30 o'clock
The same day the infant of Mrs. G., four weeks old, was taken
cholera, and died after forty-eight hours' illness.

September 6, Mrs. A., the second married daughter of Mrs. B.
taken with cholera after a slight diarrhœa, and died within twenty
hours. The day of her attack this lady had been removed from
mother's house to the second story of a building on Market s
between Tenth and Eleventh streets. Mrs. A. was seven months
nant.

The night upon which Mrs. A. died the remaining daughter, a
teen years of age, was taken with acute symptoms of the disease, l
was arrested by the hypodermic use of morphia.

After the occurrence of the case which followed the arrival o
remains of Mrs G., all the members of the Bauer family who sur
were placed upon quinine in decided doses, with the exception of
A., who declined to do so on account of her pregnancy; and alth
all suffered from diarrhœa, in none did vomiting and cramping oc

LOUISVILLE, KY., *October*, 1873.

September 8, a medical man of Marion County, Ky., who had vi
Louisville to attend a sick member of his family, was violently atta
with cholera, and died at St. Joseph's Infirmary, after twenty-four h
illness.

During the night of September 3 and 4, this gentleman had be
attendance upon Dr. Mat. Logan, of Washington County, and had
hurriedly called to Louisville to see his father, who supposed hi
attacked with cholera.

HENDERSON COUNTY.

Henderson, the county seat of Henderson County, is situated on
south bank of the Ohio river, two hundred and twelve miles belo
city of Louisville, Ky., and twelve below Evansville, Ind. In 1870
city had a population of 4,171 individuals, of whom 1,489 were neg

Henderson is a thriving river-town, and is the tobacco market o
greater portion of the Green river country. The city has daily
munication with all points upon the Ohio River by several lin
river packets, and with Saint Louis, Mo., and Nashville, Tenn., b
Saint Louis and Southeastern Railway. This road south of Hend
connects with the Louisville, Paducah and Southwestern, the Louis
Nashville and Great Southern, and the Nashville, Chattanooga
Saint Louis Railroads.

The city is built upon an alluvial bed, overlying a strata of clay w
is several feet in thickness, when sand and gravel is reached. I
eastern portion of the city, at a depth of 8 feet, a blue mud is rea

a most offensive odor. The peculiarities of the natural levees
een already noted as existing along all western water-courses
nerica are here observed, and as no system of artificial drain-
age has been attempted, ponds and pools of stagnant water
nd within the town limits. During the wet months the
roads are almost impassable, and the cellars of houses in
portions of the town fill with water.
btained from wells and cisterns alone, although the most
atural facilities exist for the establishment of a water-
the reservoir plan. Privies are upon the surface of the
e sanitary condition of the town was bad prior to the
reak. No board of health had been in existence for several
hen cholera arrived in 1873 a hasty organization was estab-
perty-holders were required to police their premises; ponds
stagnant water were drained off and filled with fresh earth.
fectants were actively used.
e afternoon of May 20, 1873, Mrs. Deacon, a lady fifty-seven
, who had spent the morning working in her vegetable and
en, after a hearty dinner of early vegetables and pastry,
e without the aid of her artificial teeth, was attacked with
minal pain attended with nausea, vomiting, and diarrhœa.
as sudden and without any premonition other than a sensation
t from the amount of food taken into the stomach. In the
ner regular medical attendant, Dr. W. M. Hanna was called
case. Dr. Hanna found the patient prostrated, restless, and
h a cold skin and small, feeble pulse. The matter vomited
ndigested food; the dejections were the fecal contents of
s. Morphia sulphas, gr. ½, was administered hypodermically,
l the severity of the symptoms. At 6 o'clock p. m. Dr.
who was the family physician, saw the case. There had
urn of the vomiting or purging. Quinine, gr. x, calomel,
de into two powders, and it was directed that during the
hould be given.
The patient had rested well during the night, but was found
a weak pulse and cold surface, and constantly disposed
he was given capsicum, gr. i, carbonate of ammonia, gr. v,
v, and a dose of the same character was ordered to be taken
ours. She remained quiet during the day, with no change
toms until between 7 and 8 o'clock p. m., when she had an
her bowels, which is described by Dr. Thompson, and Dr. J.
who was in consultation, as soap-suds in character, and at
gallon in quantity. After this dejection the patient sank
l died in collapse at 2 o'clock a. m. the next day.
th it was learned that, during the first night, a powder of
ich Dr. Hanna had left with a member of the family, to be
se of a return of the vomiting and purging, prior to Dr.
taking charge of the case, had been given without any ne-
g apparent, and without the knowledge of the medical at-
lt was also learned that during the 21st instant at least a
sky had been administered; this also without professional

able excitement was produced by this death in the town. It
nced by many to have been a case of cholera, but no cases
spicious character occurred until after a lapse of twenty-one
a case of cholera by direct importation is reported.
versational meeting of the Henderson Medical Club on the

16th of July, 1874, which the writer had the honor to attend, this was fully discussed. The fact that all the characteristic symptom cholera were absent was demonstrated by the medical attendants, the gentlemen present (all the practitioners of the city) with but exception, united in discarding the case from cholera consideratio

On the 10th of June, 1873, a horse-trainer named McGavit, a n about twenty years of age, arrived at Henderson with some ho He had come directly from Nashville, Tenn., and went at once to Henderson County fair-grounds. He was troubled with diarrhœ fore he arrived at Henderson, and within a few hours after he rea the fair-grounds became seriously ill. Dr. J. D. Collins was call the case, but on arrival found the patient fully collapsed. Morphia atropia were exhibited hypodermically, and camphor was given i nally. Frictions and dry heat were ordered to the surface of the During the evening he partially reacted, but relapsed during the n and died early on the 12th instant. This man was nursed by Mr. C the superintendent of the race-horses, and by the stable-boys. He visited by a number of negroes living in Henderson. Mr. Craft not attacked, and the stable-boys escaped with but a single excep One man had diarrhœa, vomiting, and cramps, but was relieved by and some "cholera-medicine." It cannot be determined who the negroes were who visited this case.

Dr. J. H. Letcher reports a case of acute diarrhœa, attended with prostration, in the person of an elderly man named Fields, who employed about the depot of the Henderson and Nashville Rail This man was promptly treated, and recovered after an illness of days.

June 21, a Mrs. Haslett, who had arrived on the 19th instant Nashville, Tenn., at which city she resided, and where, prior to her de ure, some members of her family and many of her near neighbors died of cholera, was taken seriously ill. The disease was diagnose Dr. Ben. Letcher to be cholera. This woman had been attacked diarrhœa previous to her leaving Nashville, but had not informed friends, fearing that they might prevent her journey. During Jun this diarrhœa was profuse, exhausting but painless, and when the tient was first visited by Dr. Letcher, violent vomiting and cram had occurred. This case presented all the recognized symptoms of nounced cholera; partially reacted, but relapsed, and died June She had been sick, and died at a second-class boarding-house freque by railroad-hands.

June 23, Dr. J. D. Collins reports a negro man named Smit having been attacked with cholera. He was in collapse when seen, but under the hypodermic use of morphia and atropia rea and on the twelfth day of his illness was pronounced convalescent. is not known where this negro became infected, but it is probable he worked whenever he could obtain employment at the railroad-y

On the same day a young man named Watson was taken with ch some three miles out of town, at a saw-mill where he worked. The ease was fully developed, and he died after an illness of twenty- hours. This man had been a frequent visitor in Henderson, where frequented a drinking-house quite near the railroad depot.

June 24, a man named Kennedy is reported as suffering from an a diarrhœa, attended with great exhaustion. The diarrhœa was contr and in a few days he was convalescent. This man was a "brake on a through freight-train" between Henderson and Nashville.

ed in Nashville one and a half days after each trip, and
e hours in Henderson.
a man named Beasley, who was a fireman on the "yard-
taken with painless and exhausting diarrhœa, which was
l, and he recovered. This man boarded at the house in which
t was sick and at which she died.
day the negro woman employed as cook at this boarding-
who had assisted in washing the body of Mrs. Haslett after
aken with diarrhœa, which demanded active treatment, and
d.
wo cases of recoveries are reported.
man named Simmons was taken with cholera, at a board-
n Water street to which he had removed from the house in
Haslett died. Simmons had diarrhœa some two or three
s to this attack. The symptoms of the second stage were
Treated with morphia hypodermically, and recovered. The
young man named Keogh was taken ill in an adjoining
rice-water discharges, and cramped for two hours. He was
similar manner, and recovered.
Letcher, a negro washwoman living in a cluster of cabins
negroes in the southwestern portion of the city, was taken
ease, and died after an illness of twenty-four hours.
man named Robert Miller was taken with cholera, and
boarding-house on Water street at which Simmons was

med John Harker was taken with the same disease at a
on Water street close by the infected house. He lingered
t hours, when he died. The same day three cases are re-
recovered.
a traveler named Winston arrived from Memphis, Tenn.
of his arrival he suffered from diarrhœa; vomiting at-
cramps soon came on. He was treated with morphia and
dermically, and recovered.
ht cases of cholera, with four deaths, are reported. The
s fully established.
infection was established in the southwest portion of the
in a block eight fatal cases occurred, and two others died
l to the temporary hospital. The first case in this group
he person of a negro child, five years of age, whose mother
rwoman. The child was attacked with vomiting and purg-
he night of July 4, and died early on the following morning.
taken of the dejections. During the night of July 5, the
attacked and died at 3 o'clock a. m. the next day. After
f the woman, her remaining children, four in number, were
isolated building which had been arranged for a cholera-
at the time had contained no patients. Here all four chil-
aken with cholera, and two of them died. After the re-
t in which they had lived was pulled down, when it was found
nage of the ground around the cabin had been into a de-
ow the floor, and that a cess-pool had been established.
hy hole the dejecta of the child had been thrown. In the
ch the Towles family had lived four other houses had been
them five deaths occurred.
e epidemic one hundred and sixteen cases of cholera oc-
e town of Henderson, thirty-five of which were fatal. Of

these cases sixty-three were males, fifty-three were females; se
three were whites, forty-three were blacks.

We are especially indebted to Dr. John L. Cook for aid in coll
the information herewith presented.

Trigg County.

The epidemic of 1873, as it affected Trigg County, was confined
towns of Cadiz and Rock Castle, and to the establishment kno
Trigg's Furnace.

Cadiz, the county town, is located upon the banks of Little
nine miles from its confluence with the Cumberland. It has a p
tion of about twelve hundred individuals, and is up to the aver
towns of its size in the state.

Rock Castle is a village located upon the banks of the Cumb
river.

The information received from this county is of an unsatisf
nature. The first case of cholera in the county occurred June 16,
person of a black female living at the town of Cadiz, who died af
illness of a few hours. No other case occurred until the 25th, w
negro man died of the same disease, and on the 30th two other fatal
occurred, also in the persons of negroes.

On the 1st of July the disease became epidemic at Rock Castle.
first cases here were in the persons of negroes; but on the 3d a
female was attacked, and from that date until the subsidence
disease on the 22d, but two negroes were attacked, twenty-four
having occurred, twenty-two of whom were whites, eight of
died.

It is asserted by Dr. L. Lindsay, to whom we are indebted fo
facts in our possession, that the early cases occurred in the pers
individuals who had not been away from home for a long time, an
had had no communication with boats upon the Cumberland rive
is inferred that the disease had a local malarial origin, from the fac
the first case occurred in a cabin the cellar of which was partly
with stagnant water.

At Trigg Furnace the parties first attacked were wood-choppers
had, so far as is known, no communication with persons from inf
districts.

After the death of the lady who was taken with cholera at
Castle on the 3d, her body was taken for burial to Cadiz. At the fu
the husband was taken sick, and was carried to the house of Dr.
Jefferson, where he died of cholera. On the second day after
man's death, Dr. Jefferson took the disease and died, and on the
day the negro man who had nursed the first case at Dr. Jefferson's h
also died.

Union County.

The epidemic of cholera of 1873 in Union County is possess
much interest, although the absolute contact of the initial case
town of Caseyville cannot at this time be traced.

Caseyville is a small town of about three thousand inhabitants, lo
upon the banks of the Ohio river. It is a point which is const
touched at by all steamboats upon the river.

The amount of information which we have received as to the outb
at this town is exceedingly limited. The physician in whose car
majority of the cases occurred states his opinion that "the epid

by a special miasm traveling through the air," and has
impart further information.
ost reliable source, however, we learn that, prior to the out-
eyville, a steamboat, on board of which there were a number
ases, touched at the wharf-boat and discharged both passen-
ight. That the first recognized case of cholera occurred in
f a Mr. Reinfrane, whose business called him frequently to
d that he had returned home immediately prior to his attack
oint upon the river.
Williamson reports favorably upon the use of atropia, hy-
exhibited, in the treatment of cholera.

William A. Jones, residing at Hazelwood, a village of Union
seven miles south of Caseyville, a most valuable contri-
history of the epidemic has been received:
lera had become epidemic at Caseyville, Mr. Harrison
dent of that town, came into the country to escape its in-
some two or three days he complained of a diarrhœa, which
of July became profuse, violent, and exhausting. Absolute
ined upon the patient. Under careful treatment he reacted,
days was convalescent.
Ir. Luther Gilchrist, who resides some eight miles from
hich town he was obliged constantly to visit, was attacked
. The attack was not very severe. His system responded
ines exhibited, and in a few days he was well.
e mother of this case, a lady sixty-seven years of age, who
wo preceding days had nursed her son, was attacked, and
illness of nearly twenty hours.
negro woman seventy years of age, who resided with the
nily, was taken with cholera, and died within twenty-four

vo other members of this family were taken with the same
both recovered.
med Smith, who resided at Caseyville, left the town after
became epidemic, and went to the house of his friend, Mr.
lburn, who lived some eight or nine miles in the country.
rrived Smith complained of diarrhœa. The next day the
ntinued, and he vomited considerably, but by absolute rest
ielded, and he supposed himself to be convalescent. There
cholera in this neighborhood prior to the arrival of Smith.
th of July, Smith left the house of Bradburn and went to
his sister, Mrs. Hopkins, a widow lady who lived some four
from his first stopping-place. The same day he was taken
with cholera, and died in a few hours.
the morning of July 25, as Mrs. Bradburn was cooking
r her family, she was suddenly taken with diarrhœa; one
ction was followed by violent vomiting and cramps, and in
venty minutes from the action of her bowels, she was fully
d died in a few hours.
day two of Bradburn's children were taken with the same
died, the other made a tedious recovery. All the other
this family suffered more or less severely from diarrhœa.
Irs. Hopkins, at whose house Smith had died, and her negro
an, were attacked with cholera. The attack of the servant
nant as that of Mrs. Bradburn, and in three hours from the
the disease she was *in articulo mortis*.

Mr. William Wallace, who is a relative of the Bradburns, and who resided some six miles from the infected locality, assisted at the funeral of Mrs. Bradburn. Wallace placed the remains in the coffin, drove the wagon to the grave, and getting into the grave, adjusted the coffin. Wallace then returned to his house, which was in a neighborhood up to that time perfectly free from the disease. A few hours after he arrived Wallace was attacked with cholera, but recovered. A young child of a brother of Wallace, who lived in the same house, died of cholera during the convalescence of the first case, and all the other members of the family had diarrhœa.

Mr. Phillip Snow, who was also a relative of the Bradburn family, and who lived at Boxville, some six or seven miles distant, came to Bradburn's house to attend the funeral and assist in nursing the sick. He remained several days, and then started for his home. When he arrived at Boardley, a village some four miles distant from the infected house, he was taken with cholera, and died at the house of Dr. Bradburn. One week after his death Mrs. Bradburn was taken with cholera. She recovered from the disease, but never regained her strength, and died of a low form of fever a few weeks later.

A daughter of Dr. B. M. Long, who lived with her father at Casey's Mines, was, at the time when cholera was prevailing in Caseyville, giving music-lessons in the town. She called at Mr. Kerney's, whose son was ill with cholera. A few days subsequently, while at home, she was taken with the same disease, and died within thirty-six hours from its inception. Disinfectants were actively used in this case.

Mr. John Calloway, a brother-in-law of Dr. Long, who lived in Crittenden County, a few miles distant, was next taken with the disease, and soon afterward one of his children. Mr. Calloway recovered; the child died.

A Mr. Miller, who visited the last case during his illness, was next taken with cholera. He recovered, but six or seven fatal cases occurred at Long's Mines, where Mr. Miller lived, being the manager.

The treatment adopted by Dr. Jones was opium and acetate of lead given cautiously; sinapisms and heat to the surface of the body; iced milk and soup given as constantly as called for.

CARTER COUNTY.

CHOLERA EPIDEMIC OF 1873 IN CARTER COUNTY.

BY DR. P. H. BAILHACHE,
Surgeon United States Marine-Hospital Service.

(Received through the Supervising Surgeon Marine-Hospital Service.)

Carter is a county in the northeastern portion of the State of Kentucky, bordering upon Virginia, from which State it is separated by the Big Sandy River, a navigable stream. Grayson, the county-town, has a population of about fifteen hundred inhabitants. This town is located upon the Little Sandy River, in a hilly region which abounds in coal and iron ore.

On the 19th or 20th of June a number of railroad employés, who were working on a railroad cut some four miles south of the town of Grayson, were suddenly taken sick with vomiting and purging. Seven of these men died in three or four days, and as it was supposed that they had been poisoned; all left the work and the neighborhood.

June 23, Mike Vincent, a laborer, at that time hauling for the rail-

ing one mile below the place where the negroes who had
nsed, was taken with a similar disease, but recovered.
ames Bryson, who lived about two miles from Vincent, was
he same disease, and died.
es who were first attacked had their cabins along the banks
Sandy Creek. Vincent lived one mile below these cabins,
two miles below upon the same stream. The negroes, Vin-
yson (no one else lived between them) all drank of the
his stream. In other words, the washings from the negro
past Vincent and Bryson, who both used the water. The
s of the railroad were constantly going and coming to and
o river boats.
son's house the disease was carried by his father up the
Iron Hill Furnace, where he died of the disease. At this
explosion of the disease occurred. The employés were
trash" and negroes, who were huddled together in ill-ven-
shanties, drinking stagnant and unhealthy water.
r three cases of the disease occurred in the town of Gray-
se cases were easily traceable to communication with the
he furnace.
cases are reported, with twenty deaths.
hard reports that he depended upon the early treatment
ic injections of morphia.

NTY.

Covington is located on the south bank of the Ohio river,
of the Licking river, by which stream it is separated from
ewport.
is directly opposite the city of Cincinnati, and from the
ntercourse, which consist of a suspension-bridge (crossed
ilroad) and a steam ferry, many persons doing business in
side at Covington. So intimate is this connection that any
cting the public health of one city would have direct influ-
e other. The northern terminus of the Kentucky Central
t Covington.
ase recorded at Covington was in the person of a white
years of age, whose husband was employed in Cincinnati.
n with cholera June 22, and died after a few hours' illness.
n found impossible to trace the lines of infection in the
ses. The majority, however, were employed at or were in
tact with persons who worked at the city of Cincinnati.
the disease was confined almost exclusively to the lower
several cases occurred among those individuals possessed
nforts of life.
hann reports an interesting group of cases that occurred in
nement-houses in the western part of the city. These cases
n number; two cases occurred in two houses, three cases in
ese cases were all connected with the initial case of the
curred July 20. Six of these cases died.
ase of this series, a Mrs. Klewes, before she was taken with
ed the clothing of Schmidt, the second case of the series.
l ten days before Mrs. Klewes. His clothing had been shut
om in which he died until the morning of July 31, when
ought to be washed. After performing this work the woman
l died within ten hours.

Several cases are reported of the wife being attacked after n
the husband sick with the cholera, and *vice versa*.

A total of seventy-five cases are reported, with twenty-five d
Of these cases, thirty-nine were males, thirty-six were females;
nine were whites, six were blacks; fifty were married, twenty-fiv
single.

The ages range from six months to seventy-five years.

Caldwell County.

Princeton, the county-seat of Caldwell County, is located on the
ville, Paducah and Southwestern Railroad, one hundred and e
three miles southwest of Louisville, and forty-four miles northe
Paducah. This town is also in direct communication with Nas
Tenn., one hundred and twenty-six miles southeast, by means
Saint Louis and Southeastern Railway, which crosses the Paduca
at Nortonsville Junction, which point is thirty-one miles e
Princeton.

The town is built upon undulating ground, gradually ascending
the northwest until it reaches an elevation that forms a ridge
nearly encircles the town. North and east the country is broke
hilly, while to the south and west is a beautiful fertile plain th
which flows a branch that is formed by the water of a large spri
called, but in reality a brook flowing from a cave which has be
plored for over two miles) which runs from beneath a ledge of sh
rock on the southern edge of the town, and passes on to the Cu
land River, a distance of twelve miles. From the foot of the
north of the town, is a ravine which, passing across the eastern s
the town, affords drainage for many acres. This ravine has w
considerably; gullies have been formed, and after heavy rains the
is collected in many places, forming pools that have some influenc
the health of the individuals living in the vicinity.

In the month of July, 1873, Princeton was in an excellent sa
condition, with the single exception that the privies of the town
without vaults, and were therefore influenced by surface-washing
other local causes were found to account for the presence of any epi
disease. Dr. James A. Carr, a distinguished physician of the c
writes: "There were no local causes in or around the town calc
to produce cholera that are not found every year, and therefore not
ble of promoting it."

On the 29th day of June a Mr. Kruse arrived at Princeton fro
infected city of Paducah. At the time of arrival he was compl
of malaise, and proceeded to the room of his friend, Dr. J. A. Ma
when a painless diarrhœa, attended with great exhaustion, was
oped. Mr. Kruse remained for some hours with Dr. Maxwell, wh
was removed to a hotel, and by careful nursing and the judicio
of opiates and mercurials, the severity of the attack was succes
combatted, and after an illness of about a week the patient was c
lescent.

The next day Dr. Maxwell, who had been in constant attendance
his friend, was similarly attacked, but recovered after an illnes
tedious convalescence of some two weeks' duration.

No other cases of the disease were recognized in the town, fro
occurrence of the two noted, until July 19; but the fact is estab
that during the period alluded to, viz, from June 29 to July 19, a
ber of persons from Paducah and other points infected with ch

e town. The body of a railroad employé, who had died
a point west of Princeton, had been brought to that town
no restriction was placed upon negroes (who are notorious
om coming into the town from any point upon the line of
Prior to July 19 cholera had become epidemic in fourteen
entucky, from any of which the infection of cholera could
ried into Caldwell County, (counties of Hickman, Ballard,
rittenden, Union, Henderson, Daviess, Trigg, Christian,
ren, Hardin, Meade, and Jefferson.)
Ildred Wyle, a homeless, friendless negro woman, who
doned on account of her worthlessness by her husband,
h cholera in the town of Princeton, and died of the disease
four hours. This woman had been away from the town
, and had returned only a few days before she was taken
natter of impossibility to determine at this date where she
t it is known that she returned from some point on the
f Princeton, and it is highly probable that after she had
ed by a family who had employed her as a domestic, and
nt twenty miles from Paducah, that she had visited that
urning to Princeton.
negro woman employed as the cook at one of the hotels
with cholera, and died on the succeeding day.
wo cases occurred, one of which proved fatal.
fatal case is reported.
wo cases occurred; both recovered.
ree cases with one death, and July 30 four cases with two
orted, and the epidemic may be considered as established.
of July to the 22d of August sixty-eight cases of cholera,
wo deaths, are reported; a total of seventy-eight cases,
ne deaths. Of these cases forty-five were males, thirty-
ales; thirty-six were whites, forty-two were negroes. Of
s, nine occurred among the whites, twenty among the
e total cases, seven occurred among children from one to
ge, five of whom died. In the demonstration, the last
rred August 15. The maximum of intensity was reached
on which day eight cases, with four deaths, are reported.
was distributed over the entire village, but the district
fection was intense was found to be along the line of the
of the town. In one family, eight cases of the disease
four deaths. In two families three cases occurred, with
n one family two fatal cases are recorded, and in seven
ses occurred, and in three instances the attack was fatal.
nces the disease was carried from the town into the sur-
try.
a Mr. William Perryman, who was at Princeton attending
tacked with cholera, and was conveyed by his friends
Hopkins County, where he died of the disease, August
st 4, Dr. Shackelford, who attended this case after it
kins County, died of the disease. On the 31st of July,
aig, who resided in a most desirable location, some five
st of Princeton, where for the three preceding days he had
as a juryman, was taken with cholera, and died after an
ours.
Ir. Robert Craig, who had been in constant attendance
, Mr. Hugh Craig, was taken with cholera, but recovered.
Mr. T. J. Morse, residing eight miles north of Princeton,

where he had also been attending court on the preceding days, w tacked with cholera, and died after an illness of twenty hours. No case occurred in his neighborhood.

August 10, a young lady who resided some six miles east of Pri was, while on a visit to the town, so severely attacked with the d that she was unable to return to her home. Her illness, which nated fatally, lasted for forty-eight hours. The mother of this woman came at once to Princeton to care for her daughter, and the funeral returned at once to her home. The same day, Aug the mother sickened and died of the same disease within ten hou this family several cases, which recovered, occurred.

Ballard County.

During the summer of 1873, a party of laborers engaged in the sion of the Mississippi Central Railroad from Jackson, Tenn., to Ill., moved into camp at the foot of a bluff some three miles back Mississippi River, nearly opposite to the city of Cairo, Ill. Nea camp was a spring of water that flowed from the foot of a blu summit of which had for years been used as a graveyard. The this party, twenty in number, had been recently paid off and ha indulging in whisky. They cleaned out the spring on Saturday, th day of June, drank freely of the water during Sunday, and on Mo July 1, cholera, most malignant in its character, broke out among and during the next five days sixteen of the twenty men were de

Some of the men reached Cairo and died at that city; other upon the road-side. One case, a young man employed as a tea came to Cairo on July 1 with diarrhœa. He went into a drug-st obtain some medicine, fell fainting from exhaustion upon the floo was carried to a house about one hundred yards distant and pla bed. The characteristic rice-water discharges at once set in, with iting and cramps. He sank rapidly, and died after a collapse of ten hours.

A young Irish girl, seventeen years of age, who had been emp at the boarding shanty of the same gang of laborers, was admitt hospital at Cairo on the 3d day of July with a diarrhœa, which soo on the rice-water character, with vomiting and cramps. In tw four hours she was collapsed, in which state she remained for thir hours, when she died.

It has been found impossible to obtain full lists of this demonstr The four survivors of the party are not to be found, and nothin known of them other than that they had come from some point in nessee. The line of extension of this road was through Union Tenn., at which point a formidable epidemic occurred.

For the facts of this demonstration we are indebted to Dr. H. V ner, of Cairo.

Dr. L. M. Lovelace, of Milburn, Ballard County, reports that f five cases of cholera occurred at that town, but that all yielded to ment.

Mason County.

So much of the epidemic of cholera in 1873 as affected the cou Mason, was confined to the city of Maysville, located upon the bank of the Ohio river, sixty miles above Cincinnati. Mayswill city of some importance, being the entrepôt for the greater port Northeastern Kentucky, having a considerable tobacco-trade, and the most extensive hemp-market in the United States. The manuf

re large and growing. According to the census of 1870, a population of 4,705 individuals, of whom 681 are

uilt upon an elevated, well-drained position, at the foot of uge of hills, by which it is nearly encircled. It has daily with Cincinnati, Ohio, Parkersburgh, and Wheeling, ll intermediate points, by river-steamers, and with Lex- xty miles to the southwest, by the Maysville and Lexing- The hills or bluffs in rear of the city are composed, wen's geological survey, entirely of limestone, clay, and

, in 1849, cholera remained in force from the month of tober; and there seemed to be just grounds for appre- ous epidemic in 1873, but the city escaped almost entirely. 9 to July 25, but fourteen cases occurred, seven of whom ily of negroes.
oung man just returned from Cincinnati was attacked ut recovered.
lady, resident of the city, was taken with cholera, but

Shackelford reports the first of a most interesting group e person of a negro woman, who died after an illness of hours.
laughter, aged twenty years, was taken with cholera, and hours' illness. The same night a young child of the last n ill and died. The next day (July 6) after the funeral ad died the previous day, the cabin was abandoned. In hereafter the husband of the second case and her two ken with cholera. These cases were treated at the city an and one of the women died.
gress, who had been in attendance upon the first two en with cholera, and died the next day.
of negroes had resided in a small cabin on a hillside. ound was extremely filthy, and the drainage and surface- is filthy yard were into the well from which they obtained under the cabin.
5 to August 18, no new cases of cholera are reported in he last date a white female, in destitute circumstances, to the city from some point upon the river. She died of n illness of three days.
negro man was brought to Maysville from a town twenty- e on the river. He was attacked with cholera before his disease, however, did not advance beyond the second

negro man, named Purcell, was brought to Maysville by ough collapsed from cholera, *was placed in a spring-wagon Millersburgh, Bourbon County, where he died two days after*

instances of the importation of cholera produced no epi- ville. For the notes of the last-mentioned cases we are r. M. F. Adamson.
ion of Maysville from a fatal epidemic of cholera in 1873, lon of Dr. Jno. M. Duke, a distinguished physician of that witnessed the effects of each epidemic since 1832, due to versal substitution of cistern for well water.

HENRY COUNTY.

The information as to the epidemic in Henry County that w
been able to collect, is contained in a letter from Dr. James K. Mc
of Shelby County, which we present in detail:

"BAILEY'S STORE, KY., *August* 29,

"DEAR SIR: Having been called out of my locality to see the
cases, I am not sufficiently acquainted with all the facts of eve
to enable me to fill out the blank forms you send. Therefore I
narrative, hoping that it may be of some service to you.

"The first case of cholera occurred on the 6th day of July in a
known as Hardin's Bottom, on the Kentucky river about twe
miles below Frankfort. The subject was a young man (marri
had eaten various fruits and vegetables through the day, the
occurring at night; he died before daylight, having been treate
cholera-mixture. His residence was situated on high groun
healthy surroundings.

"The second case was a middle-aged lady of family living w
mile of the above. She had been eating freely of various fru
vegetables, and was laboring under excitement over a family tr
the time of her attack. She was taken on the evening of the 1
died on the 12th from uræmia.

"The third case was a young married lady, living in Lecompte's
six miles up the river from Hardin's Bottom. The attack was a
Patient had eaten a great many cucumbers for dinner, and ha
in the hot sun during the afternoon. I treated this case succ
with hypodermic injections of morphia, with calomel, bismuth,
and capsicum internally, and with dry heat to the surface of th

"The fourth case occurred at the mouth of Sand Ripple, which
way between the above-named places. The subject was the wif
first case. She had moved to her father's after the death of h
band. I saw her when in collapse, and prescribed a mixture of
form, spirits of camphor and tincture of capsicum, with dry hea
surface. Under this she soon reacted, but died in a few day
uræmia.

"On the morning of the 13th I was asked to see an old la
lived in Hardin's Bottom in sight of the first case. I found her col
from which she soon rallied under the mixture and dry heat, bu
from the opium that she got in a cholera-mixture of unknown
that she had taken before I arrived. At this point I found my
the midst of a prevailing epidemic which was causing the wil
citement among the people. So great was the excitement that
left their children, and children their parents, to seek safety i
localities. Those who remained had resigned themselves to die.

"To check the epidemic was the problem that presented itself.
this I interdicted the use of fruits and vegetables. Placed in the
of every one pills of lead and opium, with instructions to stop
rhœa at its onset. In forty-eight hours I had treated eight well-
cases of cholera, with a loss of two. I remained here one week
were but few cases and no deaths after the first two days. Dur
week two fatal cases occurred at the mouth of Sand Ripple.
was nothing in the entire district that I could regard as an
cause for the epidemic. It is true that there was a slough wit
stagnant water close by, but there was no case of malaria in th

fact there was no sickness of any kind, except a few cases
mplaint among infants.
excitement had subsided and everybody felt hopeful that
e no more cholera, an imprudent practitioner told the
mouth of Sand Ripple that there was no danger to be
he use of fruits and vegetables. This caused a family to
se, by making an unreasonable meal of roasted corn for
and to eat freely of musk-melons in the afternoon. That
es of cholera occurred in the family, both of which proved
hours. That night the remainder of the family started
place. Two children sickened, and one died on the
re daylight; the other lived for two or three days. A
f the family, who went to the burying-ground with the
two children, was taken ill during the interment and lived
rs. There were other cases in this family who recovered.
come to look after the causes of cholera we must consider
ing cause an imperceptible effluvium relative in nature to
causes of the exanthemata, each of these being a specific
ion of its own malady. There is no doubt of this poison
ed in India, reaching us through the air, as its circulating
ucing a cholera atmosphere. With this as a prime cause,
local causes, we have the true causes of the disease. If
tagious, it does obey the laws of contagious diseases; if
unlike all other diseases of the class and does not yield
emedies.
or its alkaloid we have an agent, when properly adminis-
capable of arresting the disease. If administered by the
the repeated acts of vomiting, we never know how much
is retained, and when to repeat the dose. After the dis-
ed, opium is injurious, for it suppresses the secretions.
liuretics are required, with diet and moderate stimulation.

"JAMES K. McCREARY, M. D.

McClellan,
t Surgeon U. S. A."

ndeavored, but unsuccessfully, to obtain additional evi-
is demonstration of the disease, the questions suggested
ve remaining unanswered. It is, however, worthy of con-
t, at about the same dates cholera was epidemic upon the
ouisville, Cincinnati and Lexington Railroad; that the
range was attacked, and that, the construction-train of the
company becoming infected, the negro employés were
nd that they scattered through the adjoining counties.
any of these people reached Hardin's or Lecompt's bot-
e mouth of Sand Ripple, caused our inquiries, which re-
ered.

NTY.

Oldham County, is located on the line of the Louisville,
nd Lexington Railroad, twenty-seven miles from the city
The town is built upon a ridge and is drained by four
the foot of this ridge, and along the line of those ravines,
ses of the community reside. In this portion of the town
e upon the surface of the ground, and are cleaned by sur-
alone. Well-water is almost exclusively used, and many

of these wells are so situated, that after each rain-fall they are c
inated from the surface-washings. This is especially true in reg
the well from which the family, in which the disease was first dev
obtained their drinking-water.

The gentlemen who observed this demonstration of the d
although they decline any positive expression of opinion, incline
theory of the malarial origin of the disease, from the fact "th
room in which the family, among whom the disease first occurred
was over a dirty cellar, in which were several inches of stagnant
and that the well from which the drinking-water was obtained wa
ated on low ground, and into it the filth of the yard had wa
They are kind enough to write further: "During the months o
and July a succession of violent rain-storms alternated with
tensely hot sun; the ravines were repeatedly filled to overflowin
washings from the high lands were spread upon the low grounds,
were covered with luxuriant vegetation." It was along these
that the epidemic was particularly virulent.

Prior to the outbreak at La Grange, cholera had been develo
nine counties of Kentucky, and had appeared in the cities of Lou
Covington, and Newport. The town, being upon a main line of ra
was in daily communication with infected districts, and the rain
which have been noted were severe enough to have washed "
stuff" from even the line of the railroad to the low grounds wh
disease was developed.

From July 8 to August 4, thirty-nine cases of cholera are repo
this county. Of these cases, eighteen terminated fatally. In
families two individuals were attacked; in two other families th
curred; in one four, and in the other five cases. A few individuals
in the county became infected in the town.

Hardin County.

Elizabethtown, the county town of Hardin County, is locate
the line of the Louisville and Nashville, and the Elizabethto
Paducah Railroads. This town is therefore in almost hourly co
cation with the cities of Nashville, Memphis, Paducah, and Lou
as well as all intermediate towns.

The site of the town is well drained by a small creek which flo
southwestern direction between the town and the line of the Na
Railroad. On the banks of this creek, and heading from Main
toward the northeast, is a small street known as Race alley. The
over which this alley passes slopes to the creek, and is lined up
side of the pass-way by negro cabins. During the month of Jun
the roadway of this alley was filled several inches above the leve
surrounding grounds, and the drainage thus obstructed floo
ground under the cabins on the western side of the alley with th
ings from the higher ground upon which the main portion of th
is built.

The ground around these cabins was filthy in the extreme
covered with *débris* of all kinds in the various stages of animal a
etable decomposition; and although the first case of cholera did n
among the inhabitants of this row of cabins, yet, the disease o
veloped in this locality, its virulence was exhibited.

A careful examination into the surrounndings of this demonstr
cholera determined the following significant fact: On the 4th o
1873, a negro celebration was held at Elizabethtown, which ga

by a large number of negroes living at towns upon the road. A large number came from Bowling Green, at that infected with cholera. These negroes arrived early on the ined over the 5th, returning to their respective homes on t.

day of July a case of cholera occurred in the person of an an, who, although not living on Race alley, was in con- ication with the families who did. This case terminated ve hours.

case occurred on Race alley, July 10, and died after an ours. From that date until September 2 the disease was rty-one cases occurred, twenty-two of whom died. The lmost entirely confined to Race alley; one or two cases e town late in the epidemic.

living upon the banks of the creek, in the northeastern town, five individuals were taken with cholera, one of On the creek southwest of the town, in another family, were attacked, all of whom died.

ry stated that on the 26th of August a farming community, s southeast of the town, were infected by a refugee from ur cases of cholera occurred in rapid succession, all of ted fatally.

on reports a case in which the infection was carried by a the house of a friend in the country, where a fatal case urred.

t of August 14 cholera was developed in a group of cabins borers employed on the extension of the Elizabethtown and road, at a point called Round Hollow, about three miles of West Point.

s were built upon the banks of a small branch which back-water from the Ohio river. They were miserably re occupied by Irish and negroes, who lived indiscrimi- , in utter defiance of all hygienic laws. The ground around as covered with filth of all kinds, which drained into the e banks of which were built stables, pig-pens, &c. From ich at this season of the year was almost dry, water for urposes was obtained.

4th to the 28th of August, the epidemic of cholera was g the inhabitants of this settlement. Thirty-four cases of reported to have occurred, of which twenty-two died. isinfection and orders as to the proper disposition of the e negatived by the indifference of these people. After the eveloped many left the settlement and were taken with surrounding country. In each of these instances the amped out.

his way to Indianapolis, Ind., reached the town of West e was stricken down with the disease. Through the in- Davis, he was received into a house and every precaution prevent the spread of the disease. At this house he was ursed until he recovered, and no member of the family was

reports that none of the families who lived on the creek ase occurred, and who used water from wells remote from e affected. That at a railroad settlement one and a half ame creek above Round Hollow, where spring water was ed, no cholera occurred.

Dr. H. R. Pusey, of Garnettsville, who attended many of the c
Round Hollow, states that all the persons living in the localit
affected with the premonitory symptoms, which in the incipient
were relieved by the free use of calomel and opium. Dr. Pusey
case recover that had advanced to the stage of collapse.

The exact facts as to the importation of cholera to Round
cannot now be obtained; but as railroad employés are essent
migratory people, it is more than probable that it was carrie
Elizabethtown.

Bourbon County.

Millersburgh is a small town of Bourbon County, about twel
east of Paris, the county-town, and forty-eight miles east of Fra
the capital of the State. The town is the center of a rich farmin
munity, and is one of the principal towns of the county.

We present herewith a paper which has been prepared by our
friend Dr. David Keller, of Paris, one of the most prominent a
complished medical gentlemen of the State. The article of Dr.
is most elaborate, and we present it in detail (although we are cons
to dissent from much that is therein expressed) as it represents n
his own individual views, but those of a large body of gentlemen
ing in the valley of the Mississippi.

THE CHOLERA EPIDEMIC OF 1873 AT MILLERSBURGH, KY

By David Keller, M. D.

Millersburgh, with a population of about nine hundred, is loca
the waters of Hinkston Creek, in Bourbon County, Kentucky, a
the exception of its liability to cholera, from which it has suffere
and again since 1833, has enjoyed an average degree of healt
other towns in the blue-grass region. The town is well and fa
located; but, as in many other places, the health of the inhabita
been put in jeopardy by the establishment of artificial ponds,
which, located within the corporate limits, and in connection w
mill-pond, will, we think, be found active agents in the produc
the recent epidemic, which for fatality has been rarely equaled
country.

The accompanying diagram will show the location of the tow
the relation it bears to the above-named causes. It will be ob
that the town is located on the northeast side of the creek, that t
a mill-dam very near the foot of Back street, which has for many
backed up the water for a considerable distance above the town.
this time the accumulation in the bottom of the pond has increase
the depth of the creek-bed has been very greatly lessened, a
summer, although not a very dry one, has not given rain enou
raise the waters of any of our creeks for several months, and the
has been an unusual low stage of water. In this pond, accord
my own observation, there was a diminished supply, with ext
exposure of mud surface along the northern bank above the town
water was stagnant, and so impure that the whole surface in the m
September was covered with a green mossy scum. This pond, a
creek below the town, embrace the town on two sides, beginnin
and running southwe s', and finally leaving the town on its southw
border, having traversed about one mile in getting around th
limits. The extreme eastern view of the pond is cut off from the

CHOLERA MAP or MILLERSBURG_ KENTUCKY

Epidemic of 1873, by David Keller M.D. of Paris_Ky.



portion of the town by a high range of land, which gradu-
as the town is approached by the creek. Next will be seen
wn as McNunn's pond, located at the extreme northeast
e town limits, and stands at the head of a deep hollow on
and is protected to a great extent from leakage by a heavy
oss its southern border. The western border of this hollow
ck street, and is probably 50 feet above the drain-level, and
with Back street nearly to the depot of the Maysville Rail-
it gradually falls off, like the ground on the opposite side
ad, to the level of the low lands in the circle of the creek.
r of this pond and its surroundings are so well described by
izens of Millersburgh (a non-professional man) in a letter
Kentuckian, that I herewith transcribe it:
the dread disease strictly confined to one particular locality,
ement along the course of a branch running on the eastern
e town and parallel with the railroad, passing under the
bove the depot."
from cause to effect, and from effect to cause, we attribute
of the disease to unhealthy and stagnant water. "A care-
the grounds along the course of this stream reveals in
aces swampy spots covered with grass, under which is soft
by the decay of vegetation, while here and there are to be
s sunken in the ground filled with water, filtered from
marshes. Of these supposed springs the surrounding
ve been drinking and using the water for culinary purposes.
undred yards farther up, McNunn has a large pond which
up with a blue mud, composed chiefly of leaves and other
etation. This pond is the chief feeder of the marshes and
below. As this particular locality only is infected, it is
lisease had its origin in the use of unhealthy and impure
ned with imprudent diet and ill ventilation."
depot is another pond of stagnant water standing just in
the northeast wind coming over the upper mill-pond and
ond. From this pond also the ground gradually falls off
ral level of the lower portion of the town. It will now be
ectually the upper and healthy portion of the town was
m malarial influence by these natural barriers, while the
would receive the full force of it. On the south side of
d there is an elevation of probably 60 feet of abrupt
tending down to the railroad bridge which crosses at the
street, and offering an effectual barrier to the passage of
hat direction, and thus again forcing it down upon the
rict in the circle of the creek.
er will now turn to this diagram he will find the black
nting the localities where the disease prevailed, standing
e range of the then prevailing east wind, with some few
hich will yet be explained.
ptional cases all had their origin in the infected district in
ortion of the town, or in the vicinity of McNunn's pond,
near the depot, not a single case originating above Fifth
tside of this described boundary. The cases marked as oc-
he bluff on the south side of the creek, now pointed to by
ts of the malarial theory as an argument against the same,
d that malaria would not rise to that height; but in answer it
t, on inquiry made by the writer, it was ascertained certainly
hese had been visiting the sick in the infected district, with

one exception, and that the case of the woman who lived in
marked ⊙ and very near the bridge, and at the gorge or bre
bluff, and it is by no means certain that this case had not been
fected district. The strong probability is she had, as her death
almost simultaneously with that of others near McNunn's
when the lower portion of the town had not been attacked.
but few public buildings in Millersburgh. The two colleges,
female, are located in the upper part of the town, and were n
sion during the prevalence of the disease. There are three h
located on the corner of Main and Fifth streets, another on s
of Fifth and Third, the Saint James, an Irish boarding-house
of Back street, near the bridge, and here the disease was terri
who did not die left the place, and the house stands closed to
On the 10th of July a case of cholera, and the first one, occu
immediate vicinity of McNunn's pond, (see map;) this case t
fatally in six hours. On the 11th five cases occurred in th
cinity, and in from twelve to thirty-six hours all died. O
other cases died. One of these was the woman mentioned as d
the bridge. These cases were all negroes; three adult fe
adult male, and four children, the first case being a child two
With the occurrence of these deaths the disease subsided,
its appearance on the night of the 28th August, and in four
the population thinned out by death and flight of nearly all
get away, there was, on Monday, September 1, twenty-one bur
a population numbering less than two hundred, of which abo
six were whites. The announcement of this terrible mortality
to the most exaggerated reports, which were taken up and
until it was stated in one newspaper that there was scarcely
left in the place. The intensity of the disease continued unti
ber 11, when it moderated, and from that time no new cases
and at this time there was a decided moderation in the int
and to this cause, and the want of material in the infected dis
be attributed the departure of this most unwelcome visitor.

The number of deaths foots up seventy-six from the first to t
of the second visitation, confined almost exclusively to the
negroes, who, as a general rule, set at defiance all sanitary rules
lations. With a few exceptions, the houses are single story, b
tilated, and with surroundings anything but inviting to the
From all the facts connected with the cholera in Millersburgh
appearance of the first case to that of the last, the condition of the
its surroundings, I think it is clearly shown that the disease was i
to the place, of malarial origin, and to the manor born; that i
imported, the first case occurring in a child living on the ground
not been from home, and there is not, and cannot be found, the
evidence to show that any case had been brought to Millersb
abroad; that the subsequent cases occurred under exactly the
cumstances with the first, and it is, therefore, reasonable to con
all originated from the same cause. That it is not contagious, i
or portable, and cannot be propagated by these means, we
following cases will clearly demonstrate, to wit: Daniel Mar
ored man, resident of Paris, nine miles distant from Mill
visited the latter place on Sunday, August 31, to see some sick
or friends; spent the day and probably Sunday night in th
district, returned to Paris, had cholera, and died on Tuesday
surrounded by his family and friends, and no effort made to p
spread of the disease, if there was any such tendency, and

olera resulting from contact with this patient. This case
ated, for a negro woman, Harriet Wheeler, came up from
about the same time, and died in the same or adjoining
larks, and on visiting the house the next day in company
D. Barnes, we found on inquiry that all of the dejections
own out near the front door. Dr. Barnes directed that fresh
be thrown over the ground where this had been done, but
was done or not the writer does not know. The city coun-
ed the burning of the bed-clothing, &c. There was no new
eighborhood.
kner, a colored man, came to Paris from Cynthiana, and
urban negro village, in bad sanitary condition, surrounded
mber of negroes, in very hot weather, and no sort of pre-
ecautions taken whatever, and there was no spreading of
this case.
ner came to Paris from Millersburgh, and died in another
ity from all of the above cases; was visited by a number
nd there was no new case arising from contact with her.
that orders were given by her physician to have all of the
vered up in the ground. Whether this precaution was ob-
riter cannot say.
Miller visited Millersburgh frequently during the epidemic,
with cholera, and died at home several miles in the coun-
ded by his family and friends, and no new case occurred in
rhood. So with Mr. Owen, who left Millersburgh and died
thirty miles distant, and no new case occurred where he

y of the cholera in Lexington, Ky., in 1833, is strongly con-
the malarial origin of the disease. The first cases which
that city were in the immediate vicinity of a low, wet piece
f about one acre, which had for years been the receptacle
al of the neighborhood; sixty-six deaths in this immediate
h a population not dense, and of the whole number of
which occurred in the months of June and July, within
hirds of the whole number occurred in the low, wet situa-
he season advanced cholera subsided, and was succeeded by
sentery, diseases known and admitted by all to be of ma-
(Trans. Journal, vol. 1, page 194.) If we are asked to
it is that cholera, if a disease of malarial origin, is not uni-
ced with the return of hot weather in malarial regions, we
we cannot tell, and, in return, ask why is it that we observe
he places remittents one year, intermittents another, and
tery, and some seasons all occurring in company? When
ined we may probably answer the first; until then we will
atisfied with the facts as they exist. It is true there is some
n the condition of the sick which leads them to have inter-
emittent fever rather than dysentery, or cholera rather than
that peculiar condition must have a cause; but there is no
y in explaining why a few persons have cholera in the midst
ghbors, or even their own family, who are suffering under
entery, than why many should not suffer under the same cir-
Let the objector explain the peculiarity in the one case,
explain it in the other. But whatever that explanation
ever can do away the fact that cholera arises in the very
stance in which fever and dysentery arise.
na conference of July, 1874, declared unanimously that chol-

era was spontaneously produced in India; but that in all other
where it breaks out it has always been produced from withou
as the latter part of this declaration is concerned, it is very d
conceive how the conference arrived at this conclusion, unles
cede that they are omniscient. There were no possible mean
possession by which they could have arrived at this conclu
facts for its basis, and therefore the declaration is pretentiou
reference to the transmissibility of cholera by man, this conf
clared unanimously that the disease is transmissible by ma
from an infected medium, but man is not considered the speci
apart from the influence of locality. The influence of locality
fore necessary to the production of cholera, and cannot be
from the list of producing causes.

Estragulas, in his account of the cholera as it occurred
America, is decided in the expression of opinion that it had
in Paraguay; for, says he, "it was not until 1866 that the ch
came known to the countries of La Plata, and prior to the ap
of the epidemic in Paraguay, not a single vessel from infected
arrived either at Montevideo or Buenos Ayres, and not a singl
curred at either city before it had been imported from Paragu

Further he says, "If we are to accept the decompositions
table matter in India's indigenous flora as one of the causes of
we have to admit that analogous decompositions could be alik
results, for the flora of the Himalaya and the Cashmere Valle
analogous type to that of Paraguay, and the results of decomposi
be also similar." But it has never been shown what there is s
the soil of India which gives rise to cholera, and it can scarc
mitted that, independently of other causes, the source of ch
peculiar unique condition of soil there, for its analogue is to
in other parts of the world. "Now, in cholera the combination
we conceive are soil-changes, vegetable and animal decompos
mospheric influences, over-crowding, filthiness, &c. Why, the
not the same combination of causes give rise to cholera in oth
of the world where they exist?"

In Paraguay before these causes were present there was no
when these causes appeared cholera appeared, and when the
ceased there was a total disappearance of the disease. He say
troops coming from Brazil did not bring cholera to Paraguay,
was none in any Brazilian port or city at the time." The Par
army, when the disease first appeared, was secluded from th
the world and completely blockaded by land and water."

Sydenham, in his account of the cholera in London in 1669
very accurate description of the disease, as witnessed at the pre
He says, "It comes almost as constantly at the close of sum
toward the beginning of autumn, as swallows in the beginning
and cuckoos toward midsummer." There is no intimation tha
ease was imported into London.

Dr. Cooke, in his "Remarks on Cholera," as it occurred in L
Ky., in 1833, gives a full and explicit account of the epidemic
curred in that city, and attributes its origin to malaria, and p
the locality where the first case originated, and there is nothi
ever said about the disease being brought from abroad.

The communication at this time between Lexington and V
only twelve miles apart, was uninterrupted, and yet there was n
in the latter place during 1833, while in 1834 it was severely
and Lexington was exempt. What becomes of the transmiss

instance, which "is known not to travel faster than man
the people of these two places were constantly in com-
id not a case in existence in the two places at the same
e same year?
cholera broke out on the plantation of the writer's father
ama, where there had been no cholera in the county up to
here were a large number of whites and blacks on the
d yet only about one-third of the number were attacked,
lying in twelve hours; the balance recovered. No sort of
measures were adopted, and the intercourse between the
ell was uninterrupted.
ng desire to arrive at the truth, and having closely ob-
h three different epidemics of cholera, the circumstances
ngs under which it occurs, he has in no instance seen
ever which led him to believe it was contagious, or that
ansmitted from one point to another by personal inter-
n the contrary, believes it to be as free from all infection
intermittent fevers. The experience of others has led
ferent conclusions, but after all, the adoption of that plan
est calculated for the relief of our patients is the first
ortant point to be arrived at. In the language of a dis-
dical man, in a recent letter to the writer, "we can afford
over our differences of opinion as to the cause of cholera,
e on its treatment."
nce to treatment, it is not pretended that anything new
be offered in this paper. The writer's views as to pa-
eatment have in a great measure been derived from the
en teachings of Prof. John E. Cooke, strengthened and
his own observation and experience, running through
r of years, during which time he has seen cholera in all of

be cured by producing and keeping up a free secretion
and its discharge from the bowels. The best remedy
effect this object is calomel. In cholera it is particularly
ause from its small bulk, weight, and freedom from taste,
y taken and retained than any other medicine, because
es tend more or less to produce liquid discharges, and
y profusely so; and because from the rapid course of the
est remedy ought to be relied upon as far as is safe. In
demics peculiar to hot weather, the first cases occurring,
le, will be found typical of all subsequent cases in so far
y of medicine to produce a given effect is concerned. If
pidemic two drachms of calomel are required to allay
produce free biliary secretion in the first few cases, the
that this quantity will be required in all subsequent
ce the same effect, and should be given without hesita-
ger quantity is required in the first cases, so will it be in
ones, and no hesitation should be had in giving the dose
oduce the desired effect, for upon this depends the recov-
ent. In this connection the writer desires to record his
alomel: That of all the so-called potent and dangerous
looks upon this as the most useful, harmless, and at the
st abused and misrepresented of all others; that the
ation, with which the ignorant are every day frightened,
in one case out of thousands, with proper care in its ad-
nd subsequent management.

Cholera is a disease of congestion of all the internal organs, a in the great majority of cases with complete suspension of the s of bile, and as the restoration of this secretion is all-import administration of opium in any shape or form cannot, in the op the writer, fail to be detrimental in its action, from the fact th creases the difficulty which we should be anxious to remove, to locked-up secretion of the liver. Given generally with the checking watery purging, its failure is signal, from the fact that not remove the condition of things on which this purging depen the writer knows no other remedy that will, aside from calome chief reliance.

The experience of the resident physicians of Millersburgh in demic of 1873, in reference to the use of opium, morphia, subcu injection of atropia, &c., was anything but satisfactory.

Dr. J. R. Best informed the writer that, so far as he had obser action of these remedies, they were failures. Dr. John D. E. another resident practitioner of Millersburgh, testifies to the sam These two gentlemen were unremitting in their attentions upon from the first to the closing of the epidemic. Dr. Smith, anothe resident physicians, was actively engaged, until prostrated by from which he did not recover until the close of the epidemic. physicians, like the faithful sentinels of an army, remained on the peril of their own lives, thus again illustrating the self-sa character of the medical profession in the hour of danger.

In confirmation of the correctness of the above views of tre the writer herewith records the following cases which occurred lersburgh, and in which this treatment was adopted:

Case 1.—My first visit was on Monday, September 1, to see a Dr. D. E. Jarnett, who was supposed by her father to have chole had been actively treated, and when I saw her she was measur lieved. The remedy relied on in this case was calomel in decide

Case 2.—The second case visited in company with Dr. D. was woman by the name of Wheeler, aged twenty-two years, (the of one child,) and at this time five months advanced in pregnan had been sick for two days, and under charge of Dr. D. E. Jarne features were shrunken, extremities cool, pulse feeble, very hoa not able to speak above a whisper. The vomiting and purging h arrested, but her condition was a very critical one. No ad medicine was given at this time, (12 o'clock.) She was badly p for, and without any of the necessary appliances or comforts o room. Visited her six hours afterward; the vomiting and purg returned, and her case was considered much worse. Two dra calomel rubbed up with a small quantity of charcoal were given promptly arrested the vomiting and purging, and after the lapse twelve hours she had several free bilious actions, and her gene dition improved, but on the next night, in the absence of Dr. was then sick, she was induced to take some cholera-nostrum which labor-pains came on, ending in miscarriage attended w siderable hemorrhage, resulting in her death on Friday, six da the beginning of the attack. But for the occurrence of the mis she might possibly have recovered.

Case 3.—A child of this woman, a boy aged two years, was sic time of our first visit with cholera fully developed, vomiting an ing, with involuntary discharges; his features were shrunken tremities cool. He took half-drachm doses of calomel and charc made a rapid recovery.

hild of Caroline Wood was visited at 2 o'clock Monday
n sick several hours; was collapsed, and in a dying con-
at 3 a. m. No medicine given.
d 7.—America Parker, mulatto, aged about twenty-two
her of several children, living on the bluff south side of
e had active rice-water discharges; she took two drachms
l charcoal, and was promptly relieved. The mother of
s then dying in the same room from cholera, after an ill-
few hours; also, one of America's children, aged about
second child just attacked was subjected to same treat-
t of the mother, and made a rapid recovery. The first-
d took medicine, but was in a state of collapse and no
ertained of its recovery.
young mulatto woman, Matilda Robinson, aged twenty-
er of several children, was visited early Tuesday morn-
a violent and fully-developed case of cholera, incessant
purging attended with cramps. Two drachms of calo-
al were given, and part of which being thrown up, the
ted immediately, and by great effort was retained, the pa-
ld down in bed by two assistants, and the face freely
old water. In a few minutes the vomiting and watery
, and was followed in twelve hours by free bilious evacu-
rapidly recovered. A strong and robust negro man died
ame day, after an illness of a few hours. The treatment
calomel and opium, two grains each, at short intervals.
1, *and* 12.—Lucy Armstrong, aged about forty, and her
living in an adjoining house, all had active cholera dis-
s time were subjected to the calomel treatment, and were
ed. There had been a number of deaths in this and the
es. One of the physicians present when these cases were
was asked his opinion of their condition. He replied,
such cases as have been dying in six hours."
15, *and* 16.—We next visited four patients of Dr. D. E.
ere convalescent, all of them showing strong marks of
ggle through which they had passed; these were all
gro men, and had been subjected to the calomel treat-
ames were George Brown, Horace Wood, Tom Lawson,
vson.
orge Conway, a colored man, aged about forty years, had
velve hours. This case was visited on Thursday evening
company of Dr. L. D. Barnes, of Paris; the case was an
xtremities cold up to the body, features shrunken and
rface bathed in a cold, thin perspiration, eyes sunken,
feeble at the wrist. The discharges were involuntary,
stant. He took two drachms of calomel, and directions
m as much powdered ice as he desired, being very thirsty.
as left with the impression on the minds of us both that
ad in a few hours. Returning to Millersburgh Saturday
some other patients, the writer called at the house of
und him entirely relieved of all symptoms of cholera, and
ound there had been no action of the bowels since taking
He was ordered to take a dose of castor oil, and no other
perienced. He was not salivated, and made a rapid re-

l 19.—Two daughters of George Conway, aged respect-
and seventeen years, were treated in the same way, and

were soon well. These cases were not violent, but were ha
rice-water discharges. Several deaths had occurred in this ar
joining family.

Cases 20 *and* 21.—Two children of Milly Armstrong were tre
first, aged four years, died; the second, aged two years, recov

The writer saw several other cases in company with other p
to whom large doses of calomel were given, and they recovered
other medicines were subsequently given or not he does not k

Some slight inaccuracies may have occurred in this report,
they have been unavoidable, but do not affect the general re
curacy has been aimed at; but it is impossible, in the alarm
fusion incident to a violent cholera epidemic, to keep a record
case exactly as it occurs.

In a letter from Dr. J. R. Best, he says: "In the late ep
cholera there were more than twenty recoveries from cholei
indefinite number from cholerine." The writer is indebted to
who has kindly furnished him with a list of deaths occurring d
visitation.

To make Millersburgh as healthy as any other town in the l
region, it is only necessary to wipe out these malarial spot
work is done.

PARIS, KY., *December*, 1874.

It is but just that the converse of this history should be g
however, attempting this, and in stating facts which are invari
looked or set aside by the opponents of the theory of the infec
of cholera, who advocate the malarial origin of each demons
the disease, we disclaim any spirit of criticism of the able pa
we have presented. Dr. Keller has most ably presented and
his views upon the subject of the epidemic. We simply pres
facts that have come to our knowledge, being convinced that
the chain that connects the epidemic of cholera at Millersbu
the disease that was at the time traversing railroad lines and
gable waters of the Mississippi Valley.

The first recognized case of cholera in the epidemic of 1873 a
burgh occurred on the 10th day of July, in the person of a ne
two years of age, who died after an illness of six hours.

On the 11th of July five cases of cholera occurred, all of w
after from twelve to thirty-six hours' illness.

On the 12th of July two cases of cholera occurred, and bo
one in twelve, the other in twenty-four hours.

These eight cases constituted the first epidemic at Miller
1873. These cases all occurred in the persons of negroes; of w
were males, three were females. They all, with but one e
lived in the immediate vicinity of the first case. The exc
female, died of the disease at her home, some distance outsid
infected district, *but she had been visiting the cholera sick*.

The locality at which these cases occurred was close to the li
Maysville Railroad, in fact almost under the line of the
embankment, and in a cluster of cabins occupied by negroes,
whom were employed by the railroad company.

It can be conclusively shown that on or about the 6th day of J
a railroad employé named Pat. Daily, while at work at the
cut just above town, was taken suddenly sick with diarrhœa an
ing. He was carried by his friends to the town; on the road he
in front of the cabin of Horace Woods to get a drink of water,

" the old hotel " in town. He recovered in about a week ; ving been pronounced cholera-morbus. Daily was re- city of Maysville.
wife of Horace Woods, at whose house Daily had ter, was taken with diarrhœa, vomiting, and cramping. ges were of pure rice-water, attended with suppression led skin, and as on the 10th the patient was collapsed, pronounced by Dr. Smith, her medical attendant, to be she recovered, the case was recorded as *cholera-morbus.* the same house with the Woods family, the young child or was attacked with cholera, and died, as before stated ; y-eight hours two other cholera deaths occurred in the

es of July 12 the disease expired, and no more was known ust 22, when it suddenly re-appeared with redoubled viru-

een no meteorological changes between July 12 and account for the cessation and redevelopment of the nces ; but the facts go to show that there was no more of il after the arrival of two railroad employés from Mays- enry Carrington and Harvy McIlvain, who both died of old hotel." These men were sick when they arrived, cases had become pronounced, the disease spread from which they took refuge to the lower portions of the town. be remembered that on August 28 the negro Purcel ersburgh from Maysville, when in collapse from cholera, not die until the third day after his arrival.
al case of the first epidemic occurred at a point at which e been no possible connection with the cholera infection ; cases of the second epidemic not followed a positive im- disease, the malarial theory would have been unassailable. n of all the first cases was such as to directly subject d persons, and the importation of the second epidemic ted.
influences were present at Millersburgh during the sum- not doubted, but cholera did not occur until the disease to the town. The malarial influences of 1874 were positive ughout the Southwest, but no epidemic cholera occurred, pontaneous development had been prophesied by some

d that in the history of a cholera demonstration the first absolutely to nothing ; the fact of importance is the first , painless diarrhœa. It has been shown that the initial rminate until after others have succumbed to the disease ; rter of the specific poison does not always himself exhibit e disease.
aid in obtaining the facts herein set forth, we are in- eon P. H. Bailhache, United States Marine Hospital-serv- t Louisville, Ky.

TY.

of the epidemic of cholera in Taylor County is most inter- e fact that in this county, undoubtedly, is to be found the chain of infection which spread to most of the counties tucky.

Early in the month of July a negro man applied for work the construction-parties of the Ohio and Cumberland Railro later date it was ascertained that he had come from Western T where he had been working on the Memphis and Paducah The man obtained work on the tunnel-section at Muldrough's was given quarters in a group of cabins occupied by other ne men and their families. Not many days after his arrival he with an acute diarrhœa, from which he was confined to his be eight days. This attack was attended with great prostration eral constitutional disturbance.

The dejecta from this case were thrown out on the ground the cabin, which was built upon a hill-side. Immediately in below this cabin was a spring, from which the neighborhoo drinking-water. On the 14th, 15th, and 16th days of July ther siderable rain-fall, and by surface-washings the spring was ne with *débris*. On the 17th of July two violent and fatal cases o occurred in the cabins adjoining the one in which the diarrho was residing. Both of these cases died within ten hours. O the person of a negro woman, who was eight months pregnan came on during the second stage of the disease, and the p delivered of a dead child while fully collapsed.

These cases were treated by Mr. W. T. Chandler, of Campb student of medicine, and who has since graduated with dis honors.

From these cases the disease was carried along the line o road-works to Campbellsville, the county town, and to Lebano County.

Thirteen cases of cholera are reported as following the cas enumerated, eleven of which terminated fatally. Dr. Hodgen bellsville, a reliable observer, reports the occurrence in the san of eighteen cases of acute diarrhœa which demanded active

The town of Campbellsville escaped the epidemic almost and this point is of exceeding interest, as demonstrating the of disinfectants in protecting a community which is exposed fection of cholera. Six instances were either cases of choler into the town, or the disease was developed after the arrival o vidual from an infected point.

The Campbellsville cases are as follows:

I. July 20, a negro man, who had contracted the disease on the railroad, died of cholera.

II. August 10, a white man, who had contracted the dise line of the railroad, died of cholera.

III. August 21, a negro man, a refugee from the infected Lancaster, Garrard County, died of cholera.

IV. September 2, a white boy from Lebanon, was taken wit but recovered.

V. September 2, a gentleman from the infected town of Adair County, died at the Campbellsville hotel of cholera.

VI. September 8, a gentleman from the infected town of Marion County, was attacked with cholera and died.

Each of these cases were isolated as far as it was practica excreta of each case were disinfected and buried, and every precaution was adopted. Among the residents of the town cholera occurred, although during July and August cases of s rhœa were frequent. The inhabitants of this town had d attend the Marion County fair.

handler, of Campbellsville, reports strongly in favor of the ic-acid treatment in cholera cases, maintaining the value n ascribed by others to the use of the dilute acid.

UNTY.

epidemic of 1873, the only cases of cholera that are found ed in Carroll County are found upon the construction- uisville, Cincinnati and Lexington Railroad, at the village , a point nearly midway between the cities of Louisville, innati, Ohio.

ewis, to whom we are indebted for the facts of this demon- ms us that the hands upon this construction-train were d up at Louisville, Frankfort, Covington, and La Grange. hich the hands lived were in the most miserable sanitary uring June and July, there had been frequent cases of cholera morbus among them. Frequently sick negroes at their homes, of whom no further information can be

a day of July, a negro named Norman was taken with his train at Worthville, and died within twelve hours. On Conner, who was employed as cook for the hands, a white aken sick; her attack was violent, but she recovered. The e train dispersed to their homes. Dr. Lewis has been in- f these men five cases died after they reached their homes. l that through the workmen employed upon this construc- infection of the town of La Grange, Oldham County, was as the homes of some of these men were at that town.

OUNTY.

e, the county town of Christian County, was invaded in July by cholera; from what cause the development of ccurred the reports which have reached us fail to deter-

located upon the line of the Saint Louis and South East- and the inhabitants are in daily communication with Mo., Evansville, Ind., Henderson, Ky., by south-bound ith Nashville, Tenn., by all north-bound trains. Close moreover made with the Louisville, Paducah and South- oad.

month of June, strenuous efforts were made by the au- lace the town in the highest possible sanitary condition. kinds was removed from public and private property. were freely used wherever required.

s. T., aged forty-eight years, was taken with cholera, and -six hours.

egro woman, fifty-four years of age, was attacked, but re-

Mrs. H., thirty-two years old, died in thirty-six hours.

John, a negro, twenty-eight years old, was attacked, and illness of twelve hours.

im, a negro, thirty years old, died after a few hours' illness. ere isolated, with the exception of the negroes. All had imprudence in diet.

UNTY.

e to present the following letters descriptive of the cholera- 873 in Barren County.

"GLASGOW, KY., *November* 30,

"MY DEAR SIR: * * * * * *

"My report is confined strictly to cases exhibiting all the char tics of genuine cholera. The tendency to cholera in the dis which the cholera was confined was exceedingly marked, choleri vailing quite extensively. Cholera appeared a mile north of ou on the most elevated lands in this very broken and well-drained ity. It occurred, so far as a critical investigation demonstrate no intercourse between the subjects of its ravages and any infect trict. The disease had been prevailing epidemically at Gallatin, and Franklin, Ky., and in a sporadic form at Bowling Green haps two or three weeks, when suddenly, without premonition, it i near Glasgow in a most alarming and fatal form. Six or seven died in as many days, and all in a small negro settlement on an el and well-drained ground. No local causes could be developed appearance. It next appeared a mile northeast in a country overflowed by a creek running a number of miles, and poisoned laria, and was principally confined to that locality during its prev

"The locality of its invasion wars against the malarial theory; sequent settling argues in its favor, and the non-communicatio first subjects with any infected district militates forcibly agai contagious theory.

"My own impression, derived from close personal observation, i the belief that it was materially influenced by malarial poiso later movements. Cholera-specifics I found not only wholly i cious, but perniciously hurtful. The remedy which I relied up which did not disappoint me in the stages preceding collapse, follows:

℞. Hydrg. submur.,
Camph. pulv., ā ā gr. xxx.
Opii pulv., gr. iv.
Acet. plumbi, gr. xx.
M. Ft. chart. no. xv.

Sig., one to be given every hour until the discharges change in characte

"The number of cholera-cases in this neighborhood I do not nor can they be accurately determined, as the physician who at the majority has since died.

"The number of cases was probably not over thirty-five, with deaths

"Very respectfully,

"JNO. D. WOODS, M

"ELY MCCLELLAN, M. D."

The earliest case is reported on the 19th of July; this case li until the 22d, when it died.

On July 22, Dr. E. R. Williams, of Glasgow, was attacked, an on the 23d.

Glasgow is the terminus of the Glasgow branch of the Louisvi Nashville Railroad, and the town is in communication with the line by two daily trains. It is about thirty miles distant from B Green, and we have been informed that negroes who fled from th named town during the epidemic, took refuge among their friend near Glasgow.

NTY.

OLERA-EPIDEMIC OF 1873 AT OWENSBOROUGH, KY.

By E. H. Luckett, M. D.

ugh is a thriving town of about four thousand inhabitants, the south bank of the Ohio river, one hundred and fifty- ow the city of Louisville. This town is a large tobacco- s the shipping-point of a number of counties. The town onnection with the Louisville, Paducah and Southwestern

of the cholera-epidemic of 1873 at this city is embraced g cases:

as an importation from Nashville, Tenn., at which place d at the time of the departure of Brown, colored, aged , married. Brown was sick with diarrhœa when he started which was on the 19th of July, arriving the next day. He Dr. Harris on the 21st, and died on the 25th. When seen ng, purging rice-water, and in collapse.

Henry Hayden, colored; married; aged about forty years; Louisville, Ky., July 30; arrived here next day. Hayden nd on a steamboat plying between Louisville, Ky., Evans- Henderson, Ky., at all of which places cholera existed at

Miss O'Donald, twelve years old, was taken sick Septem- omiting, purging, and cramping; was ordered calomel, sicum. Dismissed cured on September 13.

achael Lee, colored; aged thirty-five years; attacked Au- seen by Dr. Stewart on the same day at 3 o'clock p. m. We found her vomiting, cramping, and passing large rice- es. In collapse when seen. Ordered mixture of chloro- of opium, pulverized camphor, tincture of ginger, and odyne. A dose to be taken every hour. She died on the th, at midnight. Rachael Lee lived opposite case No. 1, ently in Brown's house during and after his illness. She r of three children. After her death the children were squares distant to a higher location.

nma Lee, aged twelve years, oldest daughter of Rachael sick August 24 with the same symptoms as her mother. same way. Died August 25, thirty hours after date of

oe. Crabtree, colored; married; aged twenty-six years; Lee and the other children of Rachael Lee to his house, died. He was taken sick on the 24th of August, the date sickness. The symptoms were the same, but less aggra- ment the same. Recovered. (One of the remaining chael Lee was moved back to Second street, one square dence of Brown, where it sickened and died with diarrhœa, lness.)

Mrs. Nichols, white; married; aged thirty years; attacked h vomiting, purging, and cramping. Died the same day. t days previous.

—Samuel Nichols, white; aged thirty-five years; husband convalescing from remittent fever; attacked August 19 ymptoms. Died same day. Mr. N. was a mail-carrier

between this place and the city of Henderson, where cholera v
vailing at the time.

Case IX.—Tom Nichols, son of cases Nos. 7 and 8, white, aged f
years; attacked with cholera August 19. Recovered.

Case X.—Miss Reinberger, German, aged ten years; taken si
cholera-symptoms August 20. Recovered. She occupied a po
the house in which the Nicholses resided.

Case XI.—Tom Reinberger, German, aged eight years; sicken
vomiting, purging, and cramping on the 21st of August. Rec
Lived in a part of the Nichols house.

Case XII.—Frank Winter, German, married. Visited by Dr. S
on August 30, at night. Had had a diarrhœa for two or thr
When seen by Dr. Stewart he was vomiting, purging, cramping
a cold sweat. Was ordered three twenty-grain doses of calo
chloroform-mixture. Recovered.

Case XIII.—Frank Hahn, German, aged thirty years; dis
attacked at midnight, September 1, with cholera. Treatment
previous case. Died at midnight, September 2.

Case XIV.—Mrs. Winter, wife of Frank Winter, German, aged
six years; sickened September 6 with same symptoms as cases
and 13. Pregnant; aborted on the 9th; recovered. These la
cases were near neighbors of the Nicholses and Reinbergers, and
them during their sickness.

Case XV.—Mrs. Barrick, white, aged about thirty-two years,
mother of several children; attacked with cholera September
died on the night of the 3d. She lived opposite the Winters, and
that family during their sickness.

Case XVI.—Mrs. Buckley, mother of several children, was ta
with cholera on the 5th of September. In collapse six or eig
after commencement of the attack. Treatment: Sulphate of
and subnitrate of bismuth, beef-tea, and chicken-broth. Recov

Case XVII.—Nannie Buckley, daughter of Mrs. Buckley, (c
attacked with choleraic diarrhœa on the 8th of September. Re

Cases XVIII, XIX, and XX.—E. C. Berry, Mrs. Berry, his w
Henry Berry, their son, aged respectively fifty, thirty-eight,
years, were relatives of Mrs. Buckley, (case 16,) and waited upo
her sickness—the son driving the wagon for his mother—were
attacked with chol eraic diarrhœa on the 12th and 13th of Sep
Treatment, calomel and opium; recovered. This family reside
one mile from town. They had three other children who did
Mrs. Buckley, neither of whom were sick.

Case XXI.—Mrs. Green, German, aged fifty years, waited up
Barrick; was taken September 5, and died the same day.

There can be no doubt upon the mind of any unprofessiona
that the cholera was introduced into this city from three
sources, two of the points being sources for the spread of the
In following the history of the disease, starting from Brown,
Nashville, we have, first, the disease developed in Rachael Lee, w
across the street, and was in daily communication with the famil
in her daughter, who sickened and died of cholera, notwithstan
removal to a higher and healthier locality, and one entirely ou
cholera-district, who, in turn, communicated the poison to Jo. C
to whose house she was removed after the death of her mother.
probable, also, that a sister of Emma Lee, aged two years, died
disease, as in about a week after Emma's death the sist er was ta
a purging, and died in two or three days.

no spread of the disease from Hayden's house, (case No. 2,)
d of his, who died suddenly three or four days after he died,
se. Of this I have no proof, being unable to get a history
the family moving off.
point of introduction of the poison was by Nichols, the mail-
was making tri-weekly trips between this city and Hend-
cholera was prevalent; but there is no evidence that he
contact with the disease, nor was there any investigation
nt. During his last trip from Henderson to this place he
k with a remittent form of fever, from which he was cured
ur days. Two or three days after his recovery his wife was
th cholera, and died in a short time. She was quite feeble
being in a puerperal condition. The second day after her
s takes the disease, and dies the same day; his son then
the two Reinbergers, who occupy part of the house, are
last three recovering. Frank Winter, who lived in the
visited the Reinbergers, was next stricken with the dis-
llowed by Hahn, who lived with him; and then Winter's
cked. The next case was Mrs. Rarrick, who lived opposite
and waited upon Mrs. Winter. Mrs. Rarrick was nursed
n, who, in two or three days after Mrs. Rarrick's death,
died with the disease; and then Mrs. Buckley, who made
s shroud in the room occupied by Mrs. Rarrick during her
attacked with the disease, but happily recovered. Her
ther, sister-in-law, and nephew, who were constant in their
her, were all taken sick with a diarrhœa which lasted sev-

erein presented do not absolutely prove the portability of
hey strongly corroborate much that has been proved, as I
ne only question that can throw a suspicion of doubt upon
s as to how the Nichols family contracted the disease. I
ples in believing that Nichols was the means of its convey-
ouse, and that it was either his having another disease at
as subjected to the poison, or because of an unfavorable
his system to its implantation at that time that he owed his
mark how readily the poison acted as soon as his nervous
ed a shock, as it did by the death of his wife.
asked, what was the sanitary condition of these localities
prevailed? In the Nichols locality bad, very bad; in the
es not worse than other portions of the city. Nor was the
lition of the Nichols locality as bad as a portion of the city
d fever was then prevailing.

UNTY.

y escaped almost entirely the epidemic which raged with
in the towns of the adjoining counties.
Prichett, of Madisonville, under date of August 12, 1874,
o case of the disease occurred in that town during 1873.
is located upon the line of the Evansville, Henderson and
lroad, and as cholera was epidemic at the terminal points
the escape of this community is remarkable. Dr. P. re-
number of aggravated cases of cholera morbus occurred,
e characteristic features of cholera were wanting," and none
tally.
hat of A. R. Bradley, occurred July 20. Mr. B. was taken

sick at Nashville, and at once returned home; the diarrhœa wa
hausting, cramps were developed, but the case yielded to treat
Disinfectants were freely used.

MEADE COUNTY.

Dr. H. R. Pusey, of Garnetsville, Meade County, reports tha
cases of cholera occurred within the limits of the county, but in
portion that is adjacent to the infected-district in Hardin.

On the 27th of July B. A. Jones, who resided close to the line
railroad, and who had been for several days at Elizabethtown, was
with cholera, but recovered.

July 28, a Mrs. Torance, who lives on the turnpike road from
abethtown to the Salt River, was taken with cholera, and died a
short illness. The country at this time was infested with tramps
Elizabethtown, and some of these wanderers had been at Tor
house.

July 29, a Mr. L. C. Danley, who lived three miles west of
Hollow, was taken with cholera at his home, and died after a sh
ness. This man was a colporteur, and had recently been with
lines of infection in Hardin County.

Two other cases are reported, both of whom recovered.

WEBSTER COUNTY.

The only demonstration of cholera in 1873 that can be found in
ster County was at the village of Providence.

On the 31st of July a Mr. Perryman, while attending court at
ton, Caldwell County, was taken with a profuse and exhausting
rhœa. As cholera was at this time epidemic at Princeton, Mr.
man left as soon as possible for his home. He, however, was a
reach the house of a Mr. Dixon, near Providence, where he died
2d of August from cholera. Upon the day that Perryman die
physician, Dr. John Shackelford, was taken with cholera, and d
the 4th of the month.

These cases were followed by the illness of Mrs. Dixon and he
both of whom recovered. A few days later a lady who had visite
Dixon was attacked with cholera, but recovered.

GARRARD COUNTY.

The epidemic of cholera in this county was confined almost exclu
to the town of Lancaster, and to refugees from that town, aft
development of the disease.

Lancaster is situated nearly in the center of the county. In 18
town had a population of about 1,200 inhabitants, one-third of
were negroes. Among the people of this town the memory of th
demic of 1833, at which time the town had been almost depopula
the ravages of cholera, had been kept green, and this fact accou
the terror which the disease occasioned in 1873.

In 1833 the cholera had been directly introduced into the tow
way so patent that, among the older inhabitants of Lancaster, it
be difficult to find an intelligent person who doubted the infectio
and the portability of the disease.

On the 18th day of June, 1833, late in the evening, a wagon,
with merchandise for the store of Mr. William Cooke, who was a
time the principal merchant of the place, arrived at Lancaster.
goods had been purchased at the city of Philadelphia, Pa.; the

MAP OF LANCASTER, KY.

SHOWING THE LOCATION OF EACH CASE OF CHOLERA 1873.



rted to Wheeling, Va.; from thence by steamboat on the sville, Ky.; from thence to Lexington, Ky. At the last- they were loaded on the wagon from which they were Mr. Cooke. The wagon was unloaded the evening of its ncaster; the goods were unpacked and placed upon the r. Cooke's store, and before noon the next day Mr. Cooke, and two or three men who had handled these goods, were olera.

ese cases there had been no sickness in the town, but from ase spread, became epidemic, and from the 19th of June July one hundred and sixteen deaths occurred. Of these, curred in the persons of whites; of them, thirty-two were y-one were females, and five were young children. Two curred in the persons of medical men, and duplicate cases nany families.

s later the same disease visited this town, concealed in the ick stranger. This man, as will be shown hereafter, came an infected district in the State of Tennessee. He was holera after his arrival at Lancaster; he lingered for twelve l; but before he died, cases of the same disease occurred ns who came in contact with him; from them the infection ers, and eighteen fatal cases occurred.

of Lancaster is built upon undulating ground, some 600 level of the Ohio river. The business portion of the town is drained. On the eastern side of the town, Richmond street uptly into a valley through which a small stream flows in rn direction. This stream is fed by some small springs rom the foot of a hill occupied by a cemetery, and affords the main portion of the town. Its banks are marshy and wild grasses and weeds. Beyond this stream the Rich- ascends a considerable hill, upon the summit of which is arracks of the United States troops. The space between and the town is occupied by private residences. Upon the he drain, and upon the low ground in which it empties, the Sugar Creek road, a number of cabins are occupied ilies. Upon the banks of the drain, outside the limits of s a filthy slaughter-house, the effluvia from which at the d the entire town.

th of August, 1873, the sanitary condition of this town l. No attention had been paid to its police. Filth of all attered around the negro-cabins, and human excrement was the surface of the ground. The water-supply of this town n the main, from wells. Those wells in public use are so after each rain-fall they inevitably receive a large amount ashings. One of these wells, that of Richmond street, to nt reference will be made, is directly on the line of the . Above this well, on the slope of the hill, at the foot of ll was dug, are stables, cow-sheds, pig-pens, and privies; torious that after each rain-fall the water of this well has o be tainted. When the fact is taken into consideration out the Southwest the stables and their adjoining premises y used by the males as privies, it is clear that the fluid con- well must have been contaminated by a certain amount of

h day of August a man named Bewley, who had traveled ville, Tenn., which town, at the date of his departure, was

infected with cholera, arrived at Lancaster and lodged at the h
a friend who resides on Richmond street, upon the hill-side, and
diately above the well and the eastern drain. We are inform
Dr. C. D. Riggs, of Russellville, Tenn., that prior to Bewley's de
from that town cholera had become epidemic, and that Bewley
had been the subject of a "suspicious diarrhœa" before he star
Kentucky. Bewley was ill when he arrived, and stated to his
that he had been sick several times on the trip, which he had m
horseback. He was so ill that he was obliged to at once go
Vomiting, purging, and cramps were soon developed; the man
collapsed, remained in that stage for several hours, reacted, pass
a typhoid condition and lingered until the twelfth day of his
when he died. The excreta of this case were not disinfected, bu
thrown out upon the ground in rear of the out-houses.

This case was not recognized as cholera by the attending phys
although one gentleman expressed himself as being suspicio
having no knowledge of the epidemic from which the patient
caped, and not having informed himself of the gradual nor
advance of the disease, concluded that the case was not one of c

On the 14th day of August a negro man named Jenkins died
cabin, nearly at the head of the eastern drain, of unmistakable c
This man had, up to the day on which he died, waited upon Bewle
Jenkins all vessels containing the dejections and vomit had been e
This man obtained his drinking-water from the well on Richmond
The excreta of this case were not disinfected, and they were t
into the drain.

August 15, the father-in-law of Bewley, a Mr. Turner, who resid
miles northeast of the town, was taken with cholera and died a
illness of eight hours. This man had come to Lancaster to visit B
He remained with him one day and slept in the sick-room one nigh
next morning he started for home and was taken sick on the roa

August 16, a negro woman named Bailey, who lived upon the
street as Bewley, and one short block distant, in a miserably dirty
was taken sick and died after an illness of twenty-two hours. T
creta of this case were added to the general mass of filth arou
cabin. No disinfectants were used.

August 19, four fatal cases occurred in cabins and rooms immed
adjoining the room in which the woman Bailey had died. The d
in no case continued longer than ten hours. The same day a lad
lived in the vicinity of the slaughter-house abandoned her hou
with her family fled to the house of friends upon the bank of the
tucky River, some ten miles distant from the town. Upon the ro
was attacked with the disease, and died within a few hours after
ing a place of safety.

August 20, three new cases were reported and all terminated f
One, Fanny Bailey, was the daughter of the woman of that nam
died on the 16th. Fanny had continued to occupy the room in
her mother had died. The second case of that day, Sam. Sa
negro, lived with his wife and sister in a cabin upon the banks
eastern drain and close to the cemetery. The excreta were throw
the privy which was used by the two women. The third case
the person of a negro woman who had fled to Camp Nelson, on the
tucky River, twenty miles from the infected district.

It has been positively ascertained that until this date all wh
been attacked with cholera had not only lived in the vicinity

h Bewley was ill, but that they had obtained their drink-
m the Richmond-street well.
ning of this day the writer, in obedience to orders, arrived
to inspect the garrison so far as its sanitary condition was
d to make any necessary arrangements to secure to the
d competent medical attention.
vas found to be almost entirely deserted. All who could do
ve a few brave men and devoted women, who remained to
ase, comfort the sick, subsist the destitute, and put away
is well to note that the authorities of this little town ex-
33,000 in charity during the epidemic. This amount of
ot contributed by foreign charity, but was in and of the
f Lancaster alone.
date, August 20, disinfectants, outside of the barrack-
not been used. An effort was made to institute a thorough
far as was practicable, the ground already infected was
a solution of the sulphate of iron, and each householder
to supply himself with disinfectants for use on his premises.
, five fatal cases are reported, and on this day the first
out of the infected district was attacked. This was in
f a negro named West, who had been employed by the
ies as a cholera-nurse. A second case was husband of one
n who died on the 19th. This man had continued to oc-
n in which his wife had died. The third and fourth cases
he wife and sister of Sam. Salter, who died on the 20th.
had, after the death of the husband, separated. The wife
er father's house, on the southwest side of town. The
ne to Stanford, Lincoln County, where she was taken with
was carried back to Lancaster. These women both died
ours' illness. The last case occurred in the person of Mrs.
had left her home, which was upon the same street as the
h Bewley had been ill, and died in the country of cholera.
a white man, forty-five years of age, of intemperate habits,
constantly drunk for the past week, was seized with chol-
in ten hours. A negro man named Ned. Cecil, who lived
next to that at which Edna Salter had died, and who had
y in which the cholera-dejections of the women had been
taken with cholera while on the public square. He was
an unfinished building and carefully attended, but died
ss of twenty hours. The excreta of this case *were* disin-
same day a young carpenter, named Spoonamore, who had
d at work upon the new building of the national bank, died
his home near Stanford, Lincoln County. On the evening
Bewley, the initial case of the epidemic, died.
, a fatal case occurred at the United States barracks.
curred in a married soldier, who lived with his wife in a
ear of an officer's quarters.
, two fatal cases occurred. The first in the wife of the
lied on the preceding day.
t of these persons with the infection was for a time obscure.
y occupied was scrupulously clean. The location was high
ned. Neither of the individuals had been in the town dur-
lence of the disease. They had not used the water of the
reet well, as has been charged in a history of this demon-
ished in October, 1873. It has, however, been determined
tigation instituted by Acting Assistant Surgeon Smith,

United States Army, the medical officer of the command, that th
ing of this couple had been washed by a negro woman who live
infected quarter of the town, and that this lot of clothing was r
back but a short time before the attack. On this day a lady w
nursed Bewley in his illness died of cholera in the country.

August 25, a young man named Singleton was attacked with
at the residence of his brother-in-law, who lived some four mil
Lancaster, upon the Sugar Creek. Singleton had a diarrhœa f
days before his attack, during which time he used the common
the family. In this case the disease was well marked. Dr. Ber
reports the case, states that there was complete suppression of th
for forty-eight hours. The system, however, responded to the tre
and the case recovered. During this illness a brother and siste
mild attack, which yielded to treatment and rest. The house o
by this family, in the town of Lancaster, was upon Richmond
and the family obtained their supply of water from the pub
to which reference has so frequently been made. The family co
of Singleton, his wife, and four children.

August 26, Moses Doty, the father of Alice Salter, and at whos
she died, was attacked, and died after an illness of eight hours.
the evening of the same day the sister of Singleton, Mrs. Finl
attacked, and died in eighteen hours. This lady had used the
which the diarrhœal discharges of young Singleton were deposit
when the disease under which he was suffering became pronounce
Finley and her husband left the house for another about one mile
where she sickened and died.

August 27, a negro man sixty-eight years of age, named French
died of cholera after an illness of sixty hours.

August 28, a negro child thirty months old, the son of a man em
by the authorities as a nurse for the cholera sick, died of chole
an illness of six hours.

August 29, two soldiers, named Rathjon and Hasbrouck, wer
with cholera and died, the first in sixteen, the last in twelve
One of these men had nursed and assisted in preparing for bu
remains of the private, Rushbrook, and his wife, who died on
and 24th instant.

The second of these cases, Private Hasbrouck, had not been in
contact with the cholera sick, but he was the "bunkee" of
Rathjon; that is, these men occupied the same tent and bed.
were both dissipated, reckless men, and it is supposed that th
both visited negro cabins in the infected district of the town.

Mr. and Mrs. Stephens, who lived in the infected district, occ
a portion of the house that was abandoned by the family of Co
the 19th instant, were both taken with cholera in the country
wife died, the husband recovered. The same day a male neg
after an illness of sixteen hours.

September 1, Ellen Lusk, the grandmother of the child wh
August 28, was taken ill and died. This old woman had nur
grandchild during its illness, but after its death had returned
own home.

September 2, Charity Dunn, a negro woman, who had been c
to her house with rheumatism for two months, was take
diarrhœa. At first bilious in its character, in a few hours she
fully-developed cholera, and died in about twenty-four hours.
case of the disease had occurred at a house within a few yards
one in which this woman was sick.

ick, some nine miles distant from Lancaster, a negress Reid, the mother of a large family, was taken with diar- ock a. m. At 2 o'clock p. m., when she was visited by Dr. ry, of Danville, who reports the case, she was in collapse, o'clock p. m. This woman had been in no cholera-district, ined at her home during the entire summer. She had com- rudence in diet. Her cabin was clean and comfortable, tion at night was very bad. A careful inquiry instituted rty into the history of this case developed the fact that vas then living in the family who had some days pre- from the infected district of Lancaster after his parents ne disease. The only possible connection that this family d was through the person of this boy; after the death of ro children sickened and died, but the boy who was the disease remained well. The same day a man named , who lived in a distant portion of the Paint Lick town- n sick, and died after an illness of thirty-six hours.

3, Ann Mason, who lived quite near to the house at which ad died, was taken with cholera, and died after twenty- The same day William Arnold, who is the undertaker of who lived quite near to the houses at which Alice Salter, st, and Ann Mason had died, was taken ill, but was con- ur or five days.

4, Private W. Graff was taken sick at the camp, some miles n, to which the troops had been removed, but recovered llness.

5, a negro woman named Burdett, the mother of the child ust 28, and the daughter of Ellen Lusk, who died on the s taken sick. She recovered, as did also a man named rris, who sickened the same day.

st date no new cases occurred. Those sick rapidly con- the inhabitants of the town who had fled from their homes disease, returned. Individuals living in the country began he town; business was resumed; but on September 21 the s alarmed by the occurrence of another case.

named Guthrie had come from her home in the country te family, at whose house Bewley had been sick of cholera, had died. The day after her arrival (September 20) she cholera was rapidly developed, and she died after an ill- six hours.

osed the demonstration of the disease; but it is a singular l and terminal cases of the epidemic occurred and died ouse, the same room, and on the same bed.

sick at Lancaster were treated by Drs. Pettus, Jackman, he town; Drs. J. L. Warren and S. L. S. Smith, who were the troops; and by Drs. William Berry and F. C. Wilson, Louisville. Dr. Warren abandoned a lucrative practice at ard Springs, Drs. Smith, Berry, and Wilson their pro- gements at Louisville, to render professional aid to the this stricken town.

TY.

ne county town of Marion County, is located upon the nch of the Louisville and Nashville Railroad, situated enter of the county; it is not only the market-town of the

farming community, but is the base of supplies and shippi
several small towns and hamlets. The railroad passes th
center of the town, from east to west, upon low ground,
the course of a small stream, which, heading in a spring to
east, forms within the corporation limits two ponds for the use
road company and a large flouring-mill. From these ponds
to which the name of Jordan has been given flows through
in a southwest direction. The course of this stream is pr
stone walls, and the crossings of the several streets are secure
This stream is the receptacle of filth of all kinds. Flowing
the buildings on the north side of the main street, the priv
establishment facing upon the street is built over it.

Upon the southeast of the town is a small stream, the he
din's Creek, fed by impure springs and the drainage from hi
These two streams form the natural drainage of the town.
supply of the town is obtained from wells, which are all more
fluenced by surface-washings. Some few dwellings are sup
cisterns. The public water-supply consists of two wells, one
in front of the court-house, supplies the inhabitants of the ce
town; the other, upon lower ground, is used by negroes and
classes almost exclusively. Both of these wells were in miser
tion, and through their defective walls surface-drainage ga
to each well.

The street through which passes the railroad is lined with
some few of which are comfortable, but the largest numbe
occupied by negroes. At the head of this street is located
mill.

During the months of June and July the earnest solicitat
physicians of Lebanon, who had formed themselves into
association, secured one cleaning and disinfection of Jorda
removal of much *débris* of all kinds from public and private
An offensive effluvia from the lower rooms of the flour-mill
attention thereto, it was found that the flooring of the base
was raised a few inches from the ground, which space was n
with decomposing vegetable matter, and that from one corner
the foundation wall, a spring of very considerable volume iss
water was drained off into the Jordan. The *débris* was disin
removed.

On the 19th of July, a negro man, thirty years of age, wo
the line of the Ohio and Cumberland Railroad, some six
Lebanon, was suddenly taken ill. His case presented all the
of cholera, and he died after a few hours' illness, perfectly
He had been guilty of great imprudence in his diet, and th
at first rated as one of cholera morbus. The case of July 1
railroad in Taylor County, having come to the knowledge of
cian, some pains were taken to ascertain if any contact ha
between the two cases; when it was discovered that on the da
to his attack he had been on a visit to the cabin in which the
sick, and that the communication was constant between th
tions and the town of Lebanon. This case was followed b
acute diarrhœa among the other employés of the road, but in
it advance to a stage of danger.

On the 11th day of August, a negro woman, fifty-five ye
living in the western district of Lebanon, between the line of
ville Railroad and the Jordan, was taken ill. She present
symptoms of cholera, and died collapsed after ten hours' illn

rtained that some days previous to her attack this woman
home in Lebanon to attend her son, who was sick on the
lroad in Taylor County, where it will be remembered the
existence. When the man was convalescent his mother
to her home at Lebanon, and where she was attacked with
se the following day. The excreta of this case were not
t were thrown upon the ground in rear of the hut. From
he 18th of August several cases are known to have oc-
the lower classes of the negroes, having symptoms more or
ed. No record of these cases can now be obtained, from
he physician in whose care they occurred died himself of
a later date. These cases occurred in the vicinity of the
th instant. In none of them were disinfectants used.
a white man, fifty years of age, residing on the railroad
e house in which the case of the 11th instant had died,
th cholera, and remained perfectly collapsed for nearly
ours, when he reacted, and made a tedious recovery. No
were used, and the excreta were thrown upon the ground
house.
a young lady, eighteen years of age, living in the same
ttacked with a similar disease, from which she made a

portance to note that the preceding cases were rated at
olera morbus; each had been the subject of some impru-
h the violence of the symptoms were attributed, and it
a subsequent study of each case that its true status was

me day (August 19) a white man, thirty-five years of age,
h, well-drained portion of the town, was attacked with
symptoms were terribly violent; no relief could be ob-
e most active measures, and he died in ten hours from the
he disease. In this case the excreta were carefully disin-
thing was washed in a strong solution of carbolic acid,
ess on which he died was burned. This death occurred
which was high and well drained; the place of business of
equally well located; he had not been away from the town
d was thought not to have come in contact with the cases
eady occurred. It was, however, subsequently determined
ually passed a portion of each night with a female who
use in the immediate neighborhood of those in which the
lready occurred.
a negro man, living in a small house built over Jordan,
me disease. This man had passed several days preced-
among the railroad hands at the section of the Cum-
Ohio Railroad. In this case the excreta were not disin-
re emptied into the bed of Jordan, in which at the time
flowing.
e day a white man having charge of the town cemetery
few hours' illness, with symptoms almost identical with
ed by the preceding cases. In this case, however, the
ed an immoderate use of iced water when overheated by
n.
n of August the Marion County Fair was commenced upon
near the town of Lebanon, and many visitors attended from
he adjoining counties. So great had been the popular pre-
t announcing the fact that any cholera deaths had occurred

in the town of Lebanon, that during the week preceding the
this fair a handbill was prepared, stating that cholera had no
at Lebanon, which circular was apparently signed by a num
physicians resident in the town, among others the writer, w
time the circular was issued was on duty at the town of
some fifty miles distant, and who in no way authorized the
name. This handbill was extensively circulated in the count
ing Marion.

The water-supply of the Marion County fair-grounds being
contract had been made to carry water from the town to
deficiency. A well was selected in the western portion of
on low ground, and within 40 feet of Jordan, and in the
vicinity of the houses in which the cases of cholera had alre
red. The individuals having this matter in charge selecte
because it was easy of access, and because they supposed th
be pure, and to be far better than they could obtain from
locality. No suspicion of blame could be attached to them
lection, for, even if they had recognized the fact that sever
cholera had occurred in its immediate vicinity, they had b
the theory of non-contagion by the laborious newspaper artic
viduals who were held as oracles.

The well was old, having been dug in 1854, on what was
drain leading from an elevation upon which is a grave-ya
been sunk through a shaly kind of mud-stone, and the first
entered the well came in about 8 feet from the surface, an
direction of Jordan.

On the evening of August 27 a violent rain-storm deluge
try, the banks of Jordan were overflowed, and the well was
So great an amount of water fell that the surface of the
completely washed, and nothing but a direct interposition of
could have prevented the surface-washings from contami
water contained in the well.

During August 28 and 29 the attendance upon the fair
The water from this well was served as upon the former days
of violent illness had occurred in the town since the 25th. A
rity seemed to possess all, but on the night of August 29, an
hours of the 30th, the blow was struck. It might be said, sim
thirteen cases of cholera occurred, and within ten hours twel
minated fatally; one case lingered for nine days and then di
the individuals who were thus attacked had been in constant
upon the fair; the cases were not confined in any one locality
scattered over the entire town. At almost the same hour a
Lebanon outbreak occurred four cases occurred at the tow
Mary, in the same county, and five miles distant from Le
one case occurred at Raywick, also of Marion County, and
distant. These cases all terminated fatally; all had attende

During August 30 cholera was epidemic in all portions
County. Wherever individuals who had attended the fair
the water resided, there cholera was developed, no matter h
or how healthy the location. From August 30 to September
was epidemic in Marion County, and isolated cases of
occurred until October 1, when it disappeared.

The disease was not confined to the lower classes of the comm
was confined to those who indulged in the water at the fair-gr
to those who came in contact with the sick. In many instan
member of a family attended the fair; that individual ha

olera after his return home, communicated the disease to
of the family, and one or more cases occurred.
fection of the excreta was employed in the majority of the
s noticeable that wherever this method of precaution was
econd case occurred. The same remark may be made of
instances in which no disinfectants were used, but many
an be noted in which the neglect of such precautionary
llowed by the occurrence of several cases of the disease.
of United States Infantry occupied the barracks in the
on during the entire epidemic. In the management of
raordinary precautions were adopted. They were kept
loyed, their food was carefully inspected, and the water
m which alone they were allowed to drink, was constantly
purity. A constant vigilance was employed to discover
its incipient stage. Whenever a man was observed, by a
ned officer detailed for the purpose, to visit the company-
once, he was at once reported to the hospital, where the
was received in a commode and carefully inspected. The
to diarrhœa was treated. The commanding officer sec-
e medical officer of the post, all of whose sanitary recom-
re rigidly enforced. No case of the disease occurred in the
ugh during the epidemic cases of acute diarrhœa were
ecurrence, but all yielded to treatment. The child of a
r who resided with his family outside the garrison-limits,
ot subjected to the same sanitary regulations, died Sep-
olera. This death occurred late in the day. On the 9th
ivate William Moore, while arranging for the funeral,
of whisky, in each drink of which he placed a quantity
which he had purchased an ounce, under the impression
revent his taking the disease. At 11 o'clock p. m. of the
man was found in his bed collapsed, and he died before

of Lebanon, during the epidemic, in but one instance did
case occur in a private house; in that instance a mother
g daughter both died of the disease. At the Guthrie
lroad-hotel, five cases occurred, three of which terminated
ther hotel, distant about one hundred and fifty yards, was
disease. No cases occurred in any of the county institu-
y or correction.
of the physicians adopted the calomel and opium treat-
d with camphor or aromatics. The opium was used with
rable results were obtained by atropia. In all instances
blow of the disease upon the community) in which the
bjected to active treatment and perfect rest in the first
isease, it was found to be perfectly amenable to treatment.
f September a case of some interest occurred in the per-
o man about forty years of age, who was found by Dr.
e writer, lying on the floor of a deserted cabin fully col-
e was absolutely nothing in the room; the man had no
deserted by his kind. A bed was procured, upon which
comfortable; a large dose of calomel was administered,
found utterly impossible to obtain a nurse he was pro-
light, some calomel-powders, and a large bucket of iced
cup. He was vomiting occasionally, having involuntary
s pulseless and voiceless; his body was icy cold, and
fuse perspiration. Other cases demanding attendance,

the man was of necessity left to himself; at midnight Dr. Avr
him, replenished his ice, but left him without being able to dis
favorable change in his condition. At daylight he was agai
and was found to have reacted; his recovery was gradual. D
night, which was passed absolutely alone, with the excepti
midnight visit of Dr. Avritt, he had drank every drop of wa
the bucket.

NELSON COUNTY.

The history of the epidemic of cholera, as it affected Nelson
is of value as demonstrating the portability of the disease.

The first cholera-case which occurred in this county was in th
of a young man who resided upon a farm some six miles nor
the town of New Haven. This man was taken with cholera
20th of August, the day after he had returned from the town
anon. While at Lebanon he had visited the house of a friend
died in that town of cholera, and had assisted in preparing
for the grave.

In this instance the disease lasted but nine hours from its i
and when Dr. N. G. Leake, who had been summoned when th
toms became violent, arrived at the house the patient was dea

The dejections had not been disinfected, but had been thrown
the grass around the house. Dr. Leake attempted the disin
the premises, but was unsuccessful, for the next day, Augus
mother and brother of the first case, who resided in the sam
were both taken with cholera, and within fifteen hours both w

August 23, a married lady, the sister of the first case, and
band, who had both been in constant attendance upon the sic
house, were attacked with the same disease, and both recover
lingering illness.

August 25, the grandmother of preceding cases, a lady six
of age, who also resided at the same house, died of cholera
illness of eighteen hours.

August 26, an aunt of the same family, who also lived at
house, was taken with cholera but recovered.

The residence of this group of cases was not in a malarial d

September 2, a white man, twenty-six years old, was atta
cholera at his home, near New Haven, and died after an illness
hours. The day before his attack he had visited the house o
relative in Marion County. At this house several cases of cho
occurred, and at the time of his visit two of the family were
disease. He did not enter the house, but sat upon a back por
which the dinner was that day served.

The head of this house being fully convinced of the non-con
bility of cholera, had declined to make use of disinfectants, an
excreta of the patients had been thrown upon a heap of *débris*
few feet of the porch.

These cases were followed by the occurrence of twelve othe
town of New Haven. In each case the infection was traced
the Marion County fair, or to the two localities, the infection
has been noted.

BOSTON.

The second demonstration in Nelson County was at the town
ton, ten miles west of New Haven, and upon the line of the K
branch railroad.

n on second of September, a negress, who had just arrived
of Lebanon, was taken with cholera, but recovered after
es.
as followed by six others in the same house, all of whom
occurring September 8.
9, three deaths occurred in the persons of individuals
he infected house after the outbreak of the disease. This
ated upon low, wet ground, and its sanitary condition was
e.

emonstration was at the county-town. Bardstown is sit-
northern portion of the county, and is an inland town of
nce. It is the terminus of the Bardstown branch of the
Nashville Railroad. The town is in constant communi-
joining counties.
impossible to obtain full information as to this demonstra-
sease. We are informed by Dr. Alfred Smith that the
ch occurred in that vicinity was in the latter part of
e person of a young man who had been on a business-trip
Lebanon; that several persons had died of the disease,
called to see a man who had been in attendance upon
nd found him, within five hours from the inception of the
ndly collapsed, and he shortly died. Disinfectants were
nd no other cases occurred.
w days of this case, Dr. Smith was called to a man sick
ouse, in the town, with cholera. This man had just come
. He died after a short illness.
as followed by two others, who had come from Lebanon,
al among the inhabitants of Bardstown and its vicinity.
ributes to the use of dilute sulphuric acid the most favor-
hich were obtained.
wn, as at many other points, a diversity of opinion existed
dical men as to the genuineness of the disease. That the
ay be represented, we append the following letter:

"BARDSTOWN, KY., *December* 4, 1874.

r: I am sorry that I am not able to give you any available
hat may aid you in making up your report, and this is the
ot reply immediately after your first letter came to hand.
e months of July, August, September, and October, 1873,
reat deal of sickness, nearly all showing a malarial type,
est to the most severe grade. Those of the last usually
ix to eighteen hours, if not seen immediately by a physi-
en large doses of quinine. They were attacked usually
of the surface and great enervation of the nervous sys-
, and after a time a haggard and worn-out expression of
ea, vomiting, great thirst, and diarrhœa that varied in its
f reaction was not soon produced, death was the result.
no notes of the cases that I treated, I will give you from
count of some cases that occurred at the residence of a
d a half miles from the town on the 4th day of October.
north side of this house there was an old cellar that was
d with *débris* of all kinds, the sweepings of house and yard.
pecified this cellar was nearly full of rubbish, upon which

the family were in the habit of throwing all wash-water. Fr
most offensive odor was emitted.

"I was first called to see the lady of the house and her little gi
eight years old. The mother had simple bilious fever, the daug
same, complicated with dysentery. On the next day I found thre
of this family sick, a negro servant-girl with the fever, and tw
girls twelve and fourteen years of age. One of the last noted h
taken in the early part of the previous night with diarrhœa an
ing, but as she and her sister had eaten freely of green tomat
it was thought she was not much sick, and no attention was gi
until I arrived at the house. The first case (of the young girls)
six hours; the other, who was similarly affected, recovered.

"Both had cold surfaces, pale, haggard expression of the coun
great thirst, nausea, vomiting and purging. After a time the de
became serous, without odor, and producing scarcely any discolo
the bed-linen. The same treatment was adopted in both case
nine in large doses, diffusible stimulants, and calomel. Must
applied to the extremities, abdomen, and along the spine, and d
These two cases were more marked than any I had, and at the
did not regard them as cholera, but as pernicious fever, descr
Wood and others.

"Respectfully,

"JAMES MUIR, M

"Dr. ELY MCCLELLAN,
Assistant Surgeon U. S. A."

Dr. J. F. Hickman reports a series of fifteen cases, but two o
died. The first of these cases occurred July 10. Seven of the
occurred in one family, with no deaths. No history of the case
panies the list, and we are unable, therefore, to include them in
rative.

The last case reported by Dr. Hickman was on the 30th of
and in the person of a white man who had that day returned to h
from the Marion County fair.

LINCOLN COUNTY.

The epidemic of cholera in Lincoln County, so far as reports
obtained, was confined exclusively to the immediate vicinity of the
town. To Dr. S. P. Craig, of Stanford, who was constantly in
ance upon the cholera-sick, we are indebted for the notes upo
the history of this local demonstration of the disease is based.

Cholera, of a malignant type, made its appearance in Stanfor
morning of the 29th of August. About five days previous to the
ance of the disease in the town a young man named Spoonam
of cholera at his home, about two miles east of the town. Two
days previous to his death Spoonamore left Lancaster, where
been engaged at some carpentering-work during the epidemic
point, and passed through Stanford on his way home, where a
two later he was taken sick.

During the prevalence of the disease at Lancaster, where it co
until after it had become epidemic at Stanford, a large a number
who were refugees from the first-named town, are known
stopped at Maxville, that portion of the town of Stanford where
first made its appearance, but as far as can be determined none
refugees had the disease or any symptoms of it. This point, h

n much uncertainty, for negroes being notorious wanderers,
e refugees made but a few hours' rest at Maxville, and then
ther points. One of the number is known to have died of
Campbellsville, Taylor County, a distance of nearly sixty
est.

of Stanford is situated in a little valley, through which
Asiphs Branch, a small stream of very pure water, having
n the celebrated Buffalo Springs, about one mile from the
s always been considered a remarkably healthy town. It
een free from miasmatic diseases. Epidemics of any kind
. The portion of the town where cholera first appeared
Maxville. It lies northwest of the depot of the Knoxville
e Louisville and Nashville Railroad; is the most elevated
he town, and is inhabited almost exclusively by negroes.
condition of the town at the time of the cholera-appear-
y bad. The authorities had used considerable efforts at
rm; had succeeded somewhat in the main portions of the
Maxville, like all negro settlements, remained filthy.
of the houses where the disease first broke out was a sink
rds in diameter. On the northern edge of this sink, and
yards from the houses, was the privy of the neighborhood.
ern edge were two small springs of muddy, impure water
nto the sink about 20 or 30 feet from the privy, which, being
ge number of persons, was filled to overflowing with *putrid*
us matter.

rom this privy and sink, in the latter of which there was
nic matter of all kinds, pervaded the entire neighborhood.
as used by the Lancaster refugees, and beyond doubt
hot-bed of pestilence."

st day of the epidemic (August 29) five cases of cholera
Maxville, in houses close to the sink already described.
were all in the persons of negroes, (four of whom were
ne a child five years of age,) and all were dead within
s.

in the same group of cabins, four other cases occurred.
as still confined to the negroes, and was equally divided
he case was in the person of a boy seven years old. In
all the cases had terminated fatally. On this day the
ties took possession of a church used by the negroes, and
g organized a cholera-hospital, which was placed under
Dr. Craig.

ust 31 to September 14, eleven cases of cholera occurred
six of which were fatal.

e for some days was confined to Maxville, and to those of
ts who had fled from their homes after the first fatal cases.
idemic had been some five or six days in existence, the
otted with cases. Four occurred near the center of the
the portion occupied by the whites, but only one of the
as in the person of a white. Of these four cases two
ne house; the others were in separate houses, but all three
gether. The person first attacked in this group of cases,
died. About the same time cholera appeared in the west-
of the town; three cases occurred, all of whom died.

14th to the 28th day of September no new cases occurred
f Stanford; but on the last-named date a gentleman and
g quite near Maxville, were both taken sick with cholera.

The case of the lady terminated fatally within twenty hours husband recovered slowly. This family had abandoned their h the first day of the epidemic, and had remained in a healthy l until a period of ten days had elapsed from the last reporte During the absence of this family their house had remained *clo unoccupied*. Upon their return to the town they returned at this house, and no other precautions were adopted than that of ing the drinking-water of the family from a well in a portion town that had not been infected. In each of these final cases th acters of the disease were exhibited. Malaise, painless diarrhœa was neglected for two days, in both instances ushered in the att

During this epidemic disinfectants were freely used. Sulphate and chloride of lime were added to the contents of the privy a at Maxville. Whenever any excretra were thrown upon the or into a privy by the attendants, the spot was at once disinfecte far as possible all excreta were received in vessels containing c of lime; after use, a fresh supply of the chloride was added and th buried.

The line of treatment adopted was the hypodermic use of m in the first stage of the disease, and of atropia in the others; and camphor by the mouth; dry heat; sinapisms; hot baths; *libitum*.

Dr. Craig reports favorably on the use of atropia in the treat cholera. The history of one case is given in full as indicative of sults obtained in several cases. (See page 6, case 2.)

Adair County.

In Adair County the epidemic of cholera was confined to th of Columbia, to one locality of that town, and to a few cases wh ing visited the infected locality, returned to their homes in the su ing country.

Columbia has a population of about six hundred inhabitants. few negroes reside within the corporation limits. The town upon a hill-side, and is by nature most admirably drained. rangement of the town is upon a square, in the center of which the court-house, and from the square streets are laid off to the south, east, and west.

Opposite the court-house, and at the corner of the street north, is a hotel known as the Winfrey House. Upon the side and opposite to the hotel, is a large barn, which is used as a live sale stable, under the charge of the proprietor of the hotel. In of this stable is a large covered privy, which was used not only b ors but by nearly all the male inhabitants of the town.

Columbia has always been considered a healthy town. The ep of the past were cholera in 1833 and 1835, from which disease th suffered severely; dysentery in the fall of 1849, from which disea sixty persons died; congestive intermittent fever in 1862, from disease a large number of persons died; but from that time un no disease could be classed as epidemic.

In the month of August, 1873, the sanitary condition of the t bad. The ground around the dwellings, as well as the streets, was with *débris* of all kinds. The privies, with the exception of that of the Winfrey House stables, were built on the surface. Stab pens, chicken-houses were unclean, and around them human ex was mixed with other *débris*. The rear premises of the Winfre

n worse condition than is ordinarily observed at country
rear of the lot upon which the stable stands is lower than the
lots which had been built upon. The privy was over a pit
e ground, but this pit was full to overflowing with excre-
he washings of the yard after each rain-fall being into it,
n all directions was saturated with the fluid contents of this
ar windows of a row of brick buildings that face upon the
e open into this stable-yard.
was made early in August by the physicians of the town to
sanitary condition. In some instances they succeeded in
operty-holders to clean their premises, and an effort was
ard at least the stable of the Winfrey House; this effort
by the proprietor as an unwarrantable interference with

th day of August a negro boy, fourteen years of age, who
a hostler, at the Marion County fair, returned to Columbia
o work at the stables of the Winfrey House. He had a
en he arrived, and during the evening made frequent use
-privy.
y hour the next day (August 30) a negro man who was in
ese stables was suddenly taken with cholera. He was car-
asement-room of the hotel, where he died after an illness of
ours. About 8 o'clock a. m. the same day, the boy whose
Lebanon has been noted, was found in a mule-shed adjoin-
le in collapse. He was carried into the stable preparatory
ed in a bed, but died in a few moments. Later in the same
lady twenty years of age, the eldest daughter of Mr. Winfrey,
, and died after an illness of ten hours; and a white man,
some fifteen miles from the town, upon Carey's Creek, but
n in the town on the previous day, and who was known to
e stable-privy, was attacked at his home with the same dis-
ed after six hours' illness. This outbreak of the disease
a time when the town of Columbia was full of non-residents.
ourt was in session, and a large number of strangers were
the hotel, where were also congregated a number of regular

, the proprietor of the hotel was attacked, and died within
s, and during the early hours of the same day five members
rey family and six boarders at the hotel were taken ill, a
ve cases in one house, all being attacked within a few hours
er, and within eighteen hours eight deaths had occurred.
is day all who were able to do so left the house; among
r. Vaughn removed his wife to Cane Valley, a small village
miles east of Columbia, when Mr. V. returned to the Win-
to render aid to the sick. At about 3 o'clock p. m. Mrs.
taken with cholera, and her husband was recalled from the

r 1, four persons who had boarded at the hotel were taken
thin sixteen hours all had died. Of this group of cases Dr.
ns, the rear windows of whose office opened into the stable-
ho had been assiduous in his attention to the sick, was,
himself attacked, carried to his home in the country, where
nother gentleman, Col. Robert Miller, who had the day be-
hotel and had gone to the Griffin Springs, some six miles
attacked, and died after an illness of sixteen hours. A

negro man who had nursed the negro who was the first case r on the 30th, died after an illness of fifteen hours.

On the same day Mr. Vaughn, who had left the town on the p night to nurse his wife, sick with cholera at Cane Valley, was tak the same disease. The lady recovered, but Mr. V. died after a illness. A white man, fifty years of age, who had used the i privy on the 30th of August, died at his home, on Green River, illness of fourteen hours; and a young girl living on Casey's whose father died of cholera on the 30th, was taken ill and die ten hours' illness.

September 2, a white boy who had frequented the hotel and was attacked, but recovered. Two white men, father and son, w nursed the sick at the hotel, and had made the coffins for some dead, were taken ill. The father, aged seventy years, died; the covered. A farmer who lived some four miles north of the tow who had been in the hotel-stables the previous day, was taken ill home and died in twenty-four hours. A gentleman who had left bia on Sunday, August 31, died of cholera at the hotel at Cam ville, Taylor County.

During the three following days no new cases occurred.

September 6, a young daughter of Mrs. Winfrey was attacke recovered.

September 8, four cases occurred in persons who had been expo the infection at the hotel. The attack was mild in each instan all recovered.

September 10, an aged man and his wife, residing in a seclude tion some two miles from the town, were both taken with c The husband recovered; the wife died. It is not known how the subjected to the infection.

September 20, a man aged seventy-five years was taken with c and died after a few hours' illness, and on the 23d his wife died same disease.

After the disease had become epidemic, a general police of th was made. The Winfrey House was closed. The stable was aba after the privy had been disinfected and filled with fresh earth.

It is the opinion of the two physicians who remained in Co during the epidemic that in the majority of the cases the excret not disinfected, but that they were cast upon the ground arou houses. A young man who nursed Mr. Winfrey during his illn formed the writer that the dejections of this case were emptied fr window of the room in which the man was sick into a dirty lane separated the kitchen from the hotel.

By Dr. U. L. Taylor, of Columbia, to whom we are under obli for important aid in the collection of the facts of this demonst we are informed that the treatment consisted of calomel, astringents, and stimulants. Dr. Taylor is of the opinion that use of calomel the only beneficial results that were obtained sho attributed.

On the 27th of October, 1873, the writer visited the Winfrey Hou asked permission to inspect the rooms in which the cholera cas occurred. We found that no effort had been made at cleaning a washing of the bed-clothing and brooming of the floors. Th tresses and other beds remained unchanged, and the stains of the tions were visible. Under the upper portion of the bed upon Winfrey had died a number of soiled rags were found, in all prob just as they were tucked beneath the mattress during its last occu

tance of prompt and immediate cleansing of these rooms, of all soiled articles of property, and a general police of was most earnestly impressed upon the person in charge of , with the only result of eliciting an expression of dis- such interference—a closing demonstration of the same acy that had subjected the town to a fearful epidemic.

N COUNTY.

l, the county-town of Washington County, nine miles north with which town its inhabitants are in daily communica- l almost entirely. A full record of every case in which the ne pronounced has been obtained; and it will be seen that ance the connection is positive between the subject of the either the Marion County fair or the town of Lebanon. nty escaped an epidemic is undoubtedly due to the active infection to which each case was subjected.

, the negro driver of the carriage of Mr. E. D. Davison, r Springfield, returned from the Marion County fair with rrhœa. He was removed to his house on the outskirts of here, at 9 a. m. the next day, he was found fully collapsed, a few hours. The same day a negro man is reported as ed with cholera at Mackville, a small village near the Boyle This man had been attacked with the disease after his the Marion County fair, and recovered after a tedious illness. 1, a young white man, twenty years of age, died of cholera a few miles from Springfield. This case also is referred to County fair.

2, three negroes (two males and one female) living in the n district were taken with cholera, and all died within urs. Each of these individuals had been at Lebanon within their attack. On the same day two cases (a white man and urred at the village of Texas, in the northeastern portion y. The two last mentioned had attended the fair.

3, Dr. Mat. Logan, a physician of much prominence in his had been actively employed in attendance upon the cases Marion as well as Washington Counties, was taken with hœa. Dr. Logan, being a breeder of blooded cattle, had, ily, been in constant attendance upon the Marion County e had exhibited stock. The diarrhœa continued until an the 4th, when cholera was fully developed, and he died -four hours' illness. The same day a negro death near and a white recovery at Texas, are reported. The last was the same family in which it has been recorded that two cases d.

7, Mrs. R., the daughter of Dr. Logan, who resided with sed her father in his illness, was attacked with cholera and nty-two hours. With the other members of the family, this ended the Marion County fair.

day a negro man was found in a field near Springfield, where during the preceding night exposed to a rain-storm. He had alk home from Lebanon, on the road was taken with cholera, shelter in a stable. From this he was driven by the inhu- When found he was fully collapsed, and soon died.

se is reported at Mackville, in the person of a white man en in attendance upon the cases which occurred at that

September 9, Mr. R., the son-in-law of Dr. Logan, was attack cholera and barely escaped with his life after a tedious illnes case was followed by that of Mrs. Logan and the young child of both of whom recovered.

On September 11 and 13 recoveries are reported.

The treatment which was most generally adopted was that of opium, and camphor; morphia hypodermically; stimulants. cases atropia was exhibited, but without beneficial results. He injections seemed to be productive of good in some cases.

Boyle County.

Boyle County, joining Garrard upon the east and Marion u west, was exposed to two distinct lines of cholera infection; ease becoming epidemic in Garrard on the 14th and in Marion 30th of August. So far as can be ascertained, no cases of the were imported from Garrard, while all the cases which were de in Boyle can be distinctly traced to the Marion County fair.

When it was ascertained that cholera had become epidemic caster, the authorites of Danville, the county town of Boyle, extraordinary precautions. The town was thoroughly polic which a rigid house-to-house system of inspection was adopted, having been divided into districts and to each district one me the town trustees and one member of the Boyle County Medical were assigned as inspectors.

The negro inhabitants were compelled to keep their houses and in good sanitary condition. Everything that was detrimenta public health was removed, ponds were drained, *débris* buried or

During the month of June preceding, the embodied circular h issued by the Boyle County Medical Society:

CHOLERA.

FOR THE PUBLIC.

The Boyle County Medical Society having been requested board of trustees, in view of the threatened outbreak of an epi cholera, to recommend to the public such measures as are deem efficient in preventing and controlling the spread of this disea earnestly suggest the following for the careful consideration one:

At once begin a most thorough and painstaking process of cleansing in your houses, your premises, and persons. Be sure t attain to the utmost cleanliness possible in everything, and nev your vigilance and care in this matter. See that in your yards bage from the kitchen is allowed to accumulate. To prevent th it in your gardens two or three feet under the surface, or ob privilege of manuring the country farms with it. The object t tained, it should be borne in mind, is to prevent drainage fr accumulations into springs and wells from which drinking-wa be used, and disposing of it in the way mentioned endangers Precautions of a similar character should be taken with Whether you have a pit or not under them, you should see t there is no danger of surface-drainage in the one case, or it through the wall of intervening earth in the other, into wells or where the water is used for drinking purposes. Well-cemented are free from such dangers, if kept carefully closed at the top.

bens and the contents of privies cannot be kept, however,
a distance even from cisterns; for in many apparently of
ccountable and therefore unsuspected ways, all sources of
er are continually becoming contaminated from such sources.
cautions become many hundred fold more important in
the discharges from the bowels of persons actually attacked

These discharges undoubtedly contain the poison which
y been the cause of propagating the disease by getting into
r drinking purposes. The contents of the privy may be
y pouring daily into every privy-seat a pint of copperas-
by dissolving in a gallon of boiling water about one and
nds of copperas; but this should not forego the necessary
vision of the drainage from it. The same may be said of
on of any mass of filth.

ccumulations of stagnant water about your premises, and
our cellars are always clean and dry.

s, but especially while sleeping, every apartment should be
ghly ventilated.

xcess in eating and drinking, and in your whole course of
-cooked meats and vegetables, and sound, ripe fruit may
r food; but all use of the frying-pan as a cooking-utensil
oandoned. If you cannot roast or broil meats properly,
them. Any kind of food sodden with the fat or grease of
peration is at all times a powerful predisposing cause of
sentery, and cholera morbus. New or unmatured potatoes,
uits, should be studiously avoided. Exposure to sudden
temperature should be shunned, and if accidentally ex-
in, change the wet garments as soon as possible.

d by cholera lie down in bed at once, and with warm wrap-
bricks, and hot bottles, sustain any loss in the tempera-
body. Pass the evacuations in a bed-pan, and don't rise
ontal position for any purpose whatever. If there is a ten-
nit, apply a mustard poultice over the stomach. Have a
ysician in attendance as soon as possible, and swallow no
escribed by any one else—especially avoid patent medi-
ack nostrums. Avoid at all times a panicky state of feel-
holera, and this is best accomplished by keeping the mind
ell employed; but be careful to engage in no exhausting
nental labors, especially avoiding excessive exposure to the
of the sun during the extreme heats of the summer. Co-
ne full extent of your time and ability with the board of
the medical men of the place, all of whom have volun-
services for the town as a sanitary police, and who are ready
erything in their power for the common good, in purifying
nd in making suggestions for individuals and their prem-
so assist them in carrying into efficient and prompt execu-
lth ordinance they may deem proper at any time to enact.

le, your attention is called to the following significant state-
the American Public Health Association, deservedly the
ority in sanitary matters in this country:

at and arrest the progress and prevent the epidemic preva-
scourge of sanitary negligence, it is necessary that the in-
every city and town should promptly resort to the most
rification, and the best known means of disinfection, and
itary cleansing and preparation should as far as possible be
before any cases of cholera occur; and that in the presence

of this disease these sanitary duties should be enforced in ev
hold and throughout the entire district.

* * * * * *

"From being the most feared and destructive pestilence, el
may be controlled and extinguished more quickly and compl
any other epidemic disease."

Perhaps this last statement is a little too strong, yet we th
scarcely urge with too much force the most rigid sanitary p

R. W. DUNLAP, M. D., *P*

G. T. ERWIN, M. D., *Secretary.*

The trustees of the town of Danville cordially recommend
paper from the Boyle County Medical Association, and wou
advise that so long as there is an apprehension of an outbre
fearful epidemic in our midst, the people dispense with all lar
ings within the town or country; especially should they disp
picnics, barbecues, and other gatherings where extensive di
prepared.

Done at a meeting of the board of trustees held this 27th

G. E. WISEMAN, *C*

Attest:

WM. GOODLOE, *Clerk.*

This circular had the desired effect. It tended to remove,
inevitable contact with the disease occurred, the dread whicl
engendered by assertions of individuals in the public press, '
era was a disease of local origin, malarial in its source, agai
disinfectants are unavailing, and that the individual stricke
disease was beyond the aid of human skill."

During the existence of the epidemic in the town of Lanc
rard County, but little communication took place between
and Danville. It has been shown that in Lancaster the disea
cated in the portion of the town that was occupied by the l
of negroes, and that the whites who were attacked were
came directly in contact with the infection in or from that dist
better class of the inhabitants who abandoned the town after
rence of the disease, took refuge at the many watering-pla
State. Some took refuge at isolated positions on the Kentu
others on farms in the county. The negroes scattered th
county, and in large numbers migrated to Lincoln County, wh
been shown that they inaugurated the epidemic. Few, if any,
Boyle County, or into the city of Danville.

The people of Boyle, misled by the circular already refer
stating that no cholera had occurred at Lebanon that season,
the Marion County fair, from the close of which the occurre
disease, as in the other "central counties," dates.

August 30, Mr. B., a farmer in comfortable circumstance
some six miles from Danville, was attacked with the disease,
an illness of ninety-six hours, recovered. This gentleman hav
to exhibit, was anxious to visit Lebanon, but having some m
as to the safety of so doing, consulted his physician, to whom h
ted the "Lebanon circular." The doctor informed him, "From
signed to this, the reports we have heard must be false."
time the doctor and his patient met, the latter was in the sec
of cholera.

August 31, a case occurred near North Fork Station, on the line of the Knoxville branch of the Louisville and Nashville Railroad.

September 1, a young lady, who had with other members of her family left her home in Marion County, on account of the disease, was attacked with cholera and made a slow recovery, and the same day three other cases occurred near North Fork Station.

September 2, the father and brother of the case first recorded on the previous day were attacked; both recovered; and one recovery is reported at North Fork Station.

September 3, a gentleman from Marion County was attacked at Oakland, five miles from Danville, and, after a severe illness, recovered.

In each of these cases the symptoms of the second stage of cholera were fully developed; all received prompt medical treatment; none were collapsed.

September 4, a young man seventeen years of age, a resident of Lebanon, but at this date entered as a student at Center College, Danville, was attacked with cholera while in his class-room. The attack was severe, but did not advance beyond the "blue stage," when reaction was established. In this case the urine was suppressed for forty hours.

September 5, a negro man was attacked with cholera at the house of a friend a few miles from Parksville, and died after an illness of eight hours. This man had been the servant of Colonel Miller, one of the victims of the Winfrey House, Columbia, epidemic. He had nursed his master through his illness, had prepared his body for the grave, and after the funeral had started on foot for the house of his friends in Boyle County. The distance he had walked was over sixty miles. The day after his arrival he was attacked by the same disease.

From the 3d to the 9th of September, five cholera-cases, with one death, are reported as occurring near North Fork.

Each of the cases recorded, with the single exception of the negro who died on the 5th instant, had attended the Marion County fair. Each case had premonitory diarrhœa from one to two days before the development of the disease. The line of treatment reported was morphia, hypodermically; calomel and quinine, exhibited internally; sinapisms and dry heat. Dr. J. D. Jackson reports favorably of the combination of dilute sulphuric acid and morphia. Dr. J. M. Myer enveloped his patients in blankets wrung out of scalding water. Dr. W. B. Harlan used successfully the dilute acid treatment.

In every case the excreta were disinfected and buried, and every effort made to isolate the case.

The only instance in which the attendants of cholera-sick in this county became infected with the disease, occurred in the person of Dr. W. O. Roberts, who reports the cases that occurred near North Fork Station. Dr. Roberts recovered, although he was the subject of a severe attack.

Clinton County.

The history of the epidemic as it occurred in the county of Clinton is of great value, although the epidemic was confined to but two points in the county, and but a small number of individuals were subjected to the disease. At one point it is demonstrated that cholera may at times be introduced with impunity into a healthy community; and by the other the dangers which may arise from such an importation, even at a point upon a mountain well drained and free from all malarial influences.

A Mr. Frank Bryson, who was the proprietor of a store u
River, about eighteen miles from Burksville, Ky., returned to
from a trip to Nashville, where he had been purchasing good
days after his return (early in the month of June) he was atta
cholera and died after a few hours' illness. Although he was su
by his family and friends during his illness, no other case o
ease occurred. Every effort has been made to obtain an offi
of this case, but unsuccessfully.

On the morning of Sunday, August 31, Maj. A. M. Adair,
wealth attorney of the sixth judicial district of Kentucky,
been attending the circuit court at Columbia, Adair County, w
era was developed in that town, started on horseback for
Clinton County, in company with Judge T. T. Alexander, for
pose of opening court at the last-named place.

During the previous night both Judge Alexander and Ma
had remained in the room of a friend who was sick of chole
Winfrey Hotel. At this house both of these gentlemen had
ring the two preceding weeks, and they were present when th
blow struck this locality. On the night preceding the journey
taken turns in nursing their sick friend, one sleeping at a time
remained as long as permitted by their official duties.

When a few miles from Columbia, Major Adair was taken wi
attended with more or less uncomfortable feelings of the
These symptoms became more and more severe until 5 o'cl
when a violent vomiting came on, attended with symptoms of
The party had ridden some fifteen miles since the first sympto
desirous to reach the house of a friend, but Major Adair was no
to dismount and yield to the desire to go to stool, when a violen
began. A pallet was made of the saddle-blankets, and upon t
Adair was placed. Within thirty minutes two teaspoonfuls
num and several teaspoonfuls of the extract of ginger were
him. After some little time, being somewhat relieved, he m
mount his horse with the assistance of Judge Alexander, but
ble to move. Dismounted and laid down again, when the vomi
on again attended with involuntary discharges from the bowe

The case becoming desperate, a place of shelter was obtain
house of a Mr. Kelly living near by, and to this house Ma
was carried and placed in bed. The doses of laudanum an
were repeated, and a horseman was dispatched to Albany, ei
distant, for a physician, who was unable to reach the beds
midnight. Morphia was exhibited hypodermically and free
tinct. opii given internally. The patient retained consciousn
3 o'clock a. m., when he went into a collapse. No reliable in
of the case can now be obtained, until Friday, September 5,
Waggoner, of Bowling Green, a near relative, reached the
took charge of the case. Dr. Waggoner's notes read as follow
piration 12, stertorous; skin moist; pupils very much contract
60, oppressed; miliary eruptions on various parts of the body;
stupor; when partially aroused (could be only partially arous
pick at nose and scratch himself; hiccough; urine suppres
Sunday night, five days and four nights. Was informed by hi
Colonel Adair, who had reached the sick-room on the 3d ins
the patient was taking sulphate of quinine, gr. x, every ten h
a teaspoonful each of fluid extract of buchu, tincture valerian,
ætheris nit. every 'now and then.'"

was at once placed upon the following line of treatment:

℞. Quiniæ sulph., gr. iss.
Camphor. gum, gr. j.
Bismuth subnit., gr. iij.
Potass. nitras, gr. ij.
Ipecac pulv., gr. j.
M. Ft. chart. no. j.
To be repeated every hour for five hours.

k p. m. congestion relieved; hiccough less frequent; and was exhibited:

℞. Quiniæ sulphas, gr. ij.
Bismuthi subnitras, gr. iij.
Potass. nitras, gr. iij.
Ipecac. pulv., gr. j.
M. Ft. chart. no. j.

ted every two hours, while at each alternate hour the fol- dministered:

℞. Tinctura belladonnæ, gtt. xx.
Ext. buchu fluidum, ʒj.
M. For a dose.

k p. m. a hypodermic injection of fluid extract of buchu

p. m. bowels acted well; passed about eighteen ounces cough diminishing; a little brandy given cautiously.
k a. m. pulse 75, respirations 14, temperature normal; dneys acting. The quinine powders continued, and every r the following was given:

℞. Tinct. belladonnæ, gtt. x.
Tinct. valerianæ, ʒi.
Fluid ext. buchu, ʒi.
M. At a dose.

intervals of an hour or two. Calomel, gr. iij, were added wder.
a. m., bowels and kidneys acted; pupils dilated, respira- erature normal; hiccough ceased.
ent, with the exception of diuretics, was continued. Dur- se of treatment flaggelations and occasional cold douches The patient can be roused to semi-consciousness.
randy, and occasional small doses of belladonna were ex- gh the day, with a gradual improvement.
a. m. on the 7th, respiration and temperature normal; idneys acted twice during the night. Strychnine, sulph., iven every three hours during the day.
k m. of the same day passed blood in stool; pulse 116; nplains of pains in lower bowels; had frequent bloody pulse became weak and thready. Refuses injections of and tannin; was placed upon catechu, camphor, and ace- At 2 o'clock p. m. of the 8th the discharges were arrested. his pulse was very weak and irregular; prostration com- given the following every two hours:

℞. Ipecac. pulv., gr. i.
Bismuthi subnit.,
Rhatany ext., āā., gr. v.
M. At a dose.

a continued improvement during the day. Became rational stant, and convalesced to complete recovery. We can only ment, "The forbearance of nature is more than wonderful."

The house at which Major Adair was sick is situated on on spurs of the Cumberland Mountains, twenty-six miles southeas lumbia, which was the nearest point infected with cholera. T tion of this house was so isolated that the owner first learned th era was in the country by the arrival of Major Adair sick w disease. No malaria could be found to produce the disease, but jections of Major Adair were not treated with disinfectants, b thrown out into the privy and upon the ground, with the fo results:

September 8, Mr. Kelly, the owner of the house, was taken with The disease was fully developed, was collapsed for eight hou he reacted. Was treated by Dr. Waggoner by hypodermic in of morphia, and cups over the epigastrium. Hot fomentations men and legs. Later hypodermic injections of quinine. The well until the 12th instant, when the disease was redeveloped, case terminated fatally after a few hours' illness.

September 10, a son of Mr. Kelly, eighteen years of age, was with cholera, but reacted and safely recovered.

September 12, a young daughter of Mr. Kelly was attacked same disease, and died at about the same hour as her father.

It is stated by persons living in the vicinity that a negro man waited upon Major Adair during his illness, died at the same Mr. Kelly and his daughter.

As far as can be ascertained no other cases occurred in the co

Russell County.

The inhabitants of Jamestown, the county-seat of Russell Cou been in constant communication with those of Columbia during demic at the last-named town. The mail-carrier from Columb remained every other night at Jamestown, had suffered severe diarrhœa, and a young man from Lebanon, who had left that to the cholera had become epidemic, was taken with the disea Jamestown, and made a tedious recovery.

September 9, Mrs. James Fields, a lady sixty-two years of ag ing in Jamestown, was attacked with cholera, and died afte hours' illness. In rapid succession, a gentleman who resided in th ing house, a negro woman who had nursed Mrs. Fields, a gentlem was a constant visitor of the Fields family, Mr. Fields, and a negr ten months of age, the last living on the same premises, were a with cholera, and all died. Subsequently five other persons, m of the Fields family, or immediate neighbors, were attacked with ease, but recovered.

October 1, a Mr. Long, who resided on Wolf's Creek, after a Jamestown, was taken with cholera and died.

October 3, Miss Long, who had assiduously nursed her broth of the same disease.

The well from which all the persons who were attacked with c with the exception of Miss Long, had obtained drinking-wat found to be contaminated by drainage from a dirty cellar, wh half full of water, and beneath the house at which the mail-rid Columbia had slept during the period of his diarrhœal sicknes use of this well was prohibited, and the disease disappeared.

Mercer County.

At Harrodsburgh, Mercer County, five cases of cholera are r by Dr. C. H. Spilman. The individuals affected were all negro

hree females. All were adults. But one fatal case occurred,
ember 9.

an states that it is impossible to trace any connection be-
people and the infection; but when the roving character of
taken into consideration, and the fact that they are utterly
their statements as to where they have been, and what
een doing, after their nocturnal excursions, it is not safe to
hese cases *could not* have come in contact with the cholera

CHAPTER XII

OHIO GROUP.

OHIO CONTRIBUTORS.

Dr. J. J. Quinn, health officer, Cincinnati.
Dr. William Clendenin, late health officer, Cincinnati.
Dr. C. L. Armstrong, Hamilton Co.
Dr. J. W. Underhill, Hamilton Co.
Dr. W. Carson, Hamilton County.
Dr. N. Leaman, Hamilton County.
Dr. B. Mosemeir, Hamilton County.
Dr. J. T. Whittaker, Hamilton Co.
Dr. F. Stick, Hamilton County.
Dr. J. P. Walker, Hamilton Co.
Dr. H. Luddington, Hamilton Co.
Dr. C. H. Foertmeyer, Hamilton Co.
Dr. W. T. Brown, Hamilton Co.
Dr. W. B. Kellar, Hamilton Co.
Dr. C. S. Muscraft, Hamilton Co.
Dr. T. Little, Hamilton County.
Dr. La Luerner, Hamilton Co.
Dr. C. D. Fishburn, Hamilton Co.
Dr. C. D. Palmer, Hamilton Co.
Dr. G. M. C. Richards, Hamilton Co.
Dr. W. Stark, Hamilton County.
Dr. F. Richards, Hamilton County.
Dr. T. G. Herron, Hamilton Co.
Dr. G. Bruhl, Hamilton County.
Dr. A. Rosenfelt, Hamilton County.
Dr. A. L. Carrick, Hamilton Co.
Dr. G. Sattlier, Hamilton County.
Dr. J. M. Scudder, Hamilton Co.
Dr. B. L. Lawson, Hamilton Co.
Dr. A. J. Miles, Hamilton County.
Dr. J. H. Tate, Hamilton County.
Dr. H. M. Hittner, Hamilton Co.
Dr. J. Lualone, Hamilton Co.
Dr. W. T. Dunlap, Hamilton Co.
Dr. D. D. Bramble, Hamilton Co.
Dr. G. W. Hail, Hamilton County.
Dr. P. M. Bigney, Hamilton Co.
Dr. F. Langenback, Hamilton Co.
Dr. L. Schwab, Hamilton County.
Dr. J. Trush, Hamilton County.
Dr. J. Marrell, Hamilton County.
Dr. J. J. Jones, Hamilton County.
Dr. G. Saal, Hamilton County.
Dr. S. Nickles, Hamilton County.
Dr. M. Cassat, Hamilton County.
Dr. B. Ehrman, Hamilton County.
Dr. W. P. Thornton, Ham
Dr. A. F. Joseph, Hamilt
Dr. John Davis, Hamilton
Dr. G. K. Taylor, Hamilt
Dr. F. Brunning, Hamilto
Dr. J. C. Cleveland, Ham
Dr. O. E. Davis, Hamilton
Dr. M. L. Amick, Hamilt
Dr. J. L. Cilly, Hamilton
Dr. A. Schwagmeyer, Ham
Dr. W. T. Brown, Hamilt
Dr. D. L. Tidball, Hamilt
Dr. J. M. Tucker, Hamilt
Dr. J. H. Grover, Hamilton
Dr. W. C. Woodward, Ham
Dr. H. Neidemeyer, Ham
Dr. A. Hoeltge, Hamilton
Dr. B. Stanton, Hamilton
Dr. S. W. Craig, Hamilton
Dr. B. P. Good, Hamilton
Dr. V. Fischer, Hamilton
Dr. A. C. Webb, Hamilton
Dr. R. D. Murray, Hamilt
Dr. T. H. Kearney, Hamil
Dr. L. F. Emmert, Hamil
Dr. C. F. Buckner, Hamil
Dr. P. F. Maley, Hamilton
Dr. W. P. Thornton, Ham
Dr. D. Holdt, Hamilton C
Dr. W. H. Bunker, Hamil
Dr. T. L. Neal, Montgome
Dr. E. B. Davis, Montgom
Dr. W. J. Conklin, Montgo
Dr. D. N. Kinsman, Fairfi
Dr. A. E. Jones, Pickaway
Dr. A. A. Jones, Scioto C
Dr. E. M. Buckingham, Cl
Dr. C. W. Dunlap, Clarke
Dr. A. M. Whitehead, Cla
Dr. Isaac Ray, Clarke Cou
Dr. W. G. Bryant, Clarke
Dr. A. Longstreet, Clarke
Dr. D. Halderman, Frankli
Dr. N. Gay, Franklin Cou
Dr. A. Neill, Franklin Cou
Dr. S. M. Smith, Franklin
Dr. W. M. Logan, Hamilt
Dr. J. C. McKenzie, Hami

nderhill, Hamilton Co.
te, Hamilton County.
lkins, Hamilton Co.
s, Hamilton County.
ung, Hamilton Co.
mlinson, Hamilton Co.
rown, Hamilton Co.
rr, Hamilton County.
ggart, Hamilton Co.
ein, Hamilton County.
hardson, Hamilton Co.
IcReynolds, Hamilton

an, Hamilton County.
stein, Hamilton Co.
ng, Hamilton County.
rphy, Hamilton Co.
epard, Hamilton Co.
ter, Hamilton County.
Dawson, Hamilton Co.
ir, Hamilton County.
nan, Hamilton Co.
Allister, Hamilton Co.
nor, Hamilton County.
ter, Hamilton County.
hburn, Hamilton Co.
wis, Franklin County.

Dr. J. K. Flowers, Franklin County.
Dr. John Willoughby, Franklin Co.
Dr. W. H. Drury, Franklin County.
Dr. N. C. Reed, Franklin County.
Dr. J. W. Hamilton, Franklin Co.
Dr. R. Werth, Franklin County.
Dr. J. H. Coulter, Franklin County.
Dr. J. M. Dunham, Franklin Co.
Dr. G. S. Stein, Franklin County.
Dr. Norman, Franklin County.
Dr. C. F. Emrich, Franklin Co.
Dr. Otto Frankenburg, Franklin County.
Dr. R. M. Denig, Franklin County.
Dr. E. B. Fullerton, Franklin Co.
Dr. G. M. White, Franklin County.
Dr. D. R. Kinsell, Franklin Co.
Dr. J. Sadler, Franklin County.
Dr. Z. F. Guerin, Franklin County.
Dr. J. C. Schueller, Franklin Co.
Dr. Butler, Franklin County.
Dr. C. E. Denig, Franklin County.
Dr. J. Lowry, Franklin County.
Dr. John McCarrell, Columbiana County.
Dr. H. W. Kitchen, Cuyahoga Co.

Surgeon John M. Dickson, U. S. A.

DATES OF INITIAL CASES.

unty.....May 27.
County.....June 3.
ty .....July 3.
Franklin County .....July 4.
Scioto County .....July 20.
Fairfield County .....July 31

HAMILTON COUNTY.

In the performance of the duties assigned to us, the task of p
ing a history of the cholera epidemic of 1873, as it affected the
Cincinnati, is attended with greater embarrassment than any o
the series, from the fact that there arose at Cincinnati, early
epidemic, a most acrimonious debate as to the introduction of the
into that city, (*vide* files of the Clinic, 1873,) and it is almost a m
impossibility to prevent even a statement of facts without enteri
certain extent into the merits of this debate. The discussion a
the following form:

Upon one hand it was stated that the disease had reached Cin
through a direct line of connection from the cholera infection, wh
at the time in existence in the city of New Orleans, the South
States, and upon the waters of the Mississippi.

Upon the other hand, this proposition was indignantly repudiat
it was claimed that the disease originated spontaneously in Cin
and without any connection with previously existing cases i
localities.

Upon one side it was stated that the epidemic at Cincinnati pr
the same characteristics of the disease which have always bee
in previous epidemics; and that it once having reached the c
infectious properties of the disease were manifested.

Upon the other side this was utterly denied, and it was assert
the so-called "multiple cases" were but seldom seen; that in no i
did more than two or three individuals contract the disease at th
locality, and that in the vast majority of cases no direct connecti
any infection could be traced.

With an earnest desire to avoid the charge of partisanship
matter, although with no hesitancy to present fully the facts whi
come to our possession, or to express freely the views which we m
formed thereon, we present as the history of the cholera epid
1873 at the city of Cincinnati three distinct papers:

I. By J. J. Quinn, M. D., health officer.
II. By William Clendenin, M. D., late health officer.
III. By C. L. Armstrong, M. D., of Cincinnati.

To which we add the notes of a few facts which have com
knowledge, not embraced in the papers announced.

During the frequent visits of inspection which we made to the
Cincinnati, we were most courteously received by the Health
who spared neither time nor pains in placing before us the view
he held upon the subject of the cholera epidemic, and while we are
to differ from these views, we desire to extend every courtesy to th
efficient officer.

It has been found to be impracticable to reproduce the elaborat
of Dr. Quinn *in extenso*, but we have preserved all facts, and the p
which have been omitted will be found to be, I. Measurements
tances; II. The remarks on "Were any of these cases true cholera
Summary of deaths from acute diarrhœal diseases; IV. Refere
map accompanying report; V. Statistical tables; VI. Remarks
origin and cause of the general epidemic; VII. General remarks
Conclusions.

SPECIAL REPORT.

A.—CHOLERA IN CINCINNATI IN 1873.

By J. J. Quinn, M. D., *Health-Officer.*

SANITARY CONDITION OF THE CITY.

severe winter and backward spring of 1873, and from other, voidable, circumstances, the approach of the warm season ty of Cincinnati, as far as the streets and alleys were con- nat was spoken of by citizens, and at least one medical jour- nfavorable sanitary condition. Changes were being made, pleted, in several departments of the municipal government, ual spring house-to-house examination of dwellings was de- , however, had not lessened the usual efficient action of the fficer, and private nuisances were promptly abated whenever out without the employment of any additional sanitary force raordinary means.

t of warm weather brought with it the energy of a change t-cleaning department. The work of removing public nui- thoroughly cleansing the streets, alleys, and gutters, had enced before the change, and was vigorously prosecuted ot only by the ordinary means, but with the aid of fire- team fire-engines. In the mean time, special attention was sanitary force to the discovery and abatement of private anger to the public health; and the 14th of June, the day the first fatal case of cholera is reported to have occurred, nnati, it is believed, in as favorable sanitary condition as large cities of the country. Nuisances there were in the t had been found impracticable to remove; they were, how- e most part, remote from dwelling-houses, and their per- ct on the public health has not been very clearly demon- ugh there can be little doubt they had an injurious influence.

TALITY OF THE CITY PRECEDING THE EPIDEMIC.

ad made its appearance in New Orleans in the previous nd had been prevailing in different parts of the Southern , although it was not entirely unexpected in Cincinnati, no ount of sickness, nor the prevalence of a particular type of e premonition of its approach. Besides its natural and ordi- n, the population of the city had been increased by the the corporate limits on February 1 over territory containing , by the annexation on March 18 of an additional ward about 5,000, and by the accession on June 9 of territory bout 1,150 inhabitants. Notwithstanding this, there seems n little difference between the mortality immediately preced- earance of cholera and that of the corresponding period of ars; not so much even as often occurred in the respective of particular periods of other years. Without the aid of c influence, great difference in the percentage of mortality d in the corresponding periods of different years. The fol- s the mortality for the month of May:

	1871.
Deaths	319
Still-born	21
Total	340

It is proper to state that a severe small-pox epidemic, which vailed during the winter, still lingered in May, 1872. Making al for the deaths from that disease, and for the natural and unusual i by annexation, of the population in 1873, the ratio of increase i was about the same as in previous years.

During the first three days of June the mortality in the were, in—

	1871.
Deaths	33
Still-born	3
Total	36

There were also in this period for 1872 ten deaths from sm Deducting, however, the deaths from small-pox which occurre of the three years, the mortality from all other causes was 32 37 in 1872, and 35 in 1873.

These statistics show the mortality immediately preceding th ning of my administration as health-officer, June 4, to have be the same as in previous years, making allowance for increase o lation, prevalence of small-pox, and other ordinary circumstan comparison of the first ten days of my term of office, or until pearance of cholera on the 14th of June, with the correspondin the two preceding years, reveals a greater difference in the m but not against the present year. The mortality was, from J June 13, inclusive:

	1871.
Deaths	135
Still-born	6
Total	141

From these facts it must be evident that no unusual number cases of disease gave warning of the advent of cholera. The no record of non-fatal cases of sickness kept in the city, except treated in public institutions and those which occurred among door poor, it is impossible to make a comparison of the whole of sickness prevailing in this period of 1873 with that of previou but, from all the data that can be obtained, it would appear general health of the city was at least as good as in former yea

What was true of fatal cases of disease in general was equ of each particular cause of death. The prevalence of no particu of disease foreshadowed the coming of cholera.

FIRST INFECTED STEAMBOAT FROM A CHOLERA-DISTRIC

Although constant communication by river and railroad h kept up, from the first appearance of cholera in the South, bet fected districts and Cincinnati, the first reported death from th took place, as already stated, on the 14th of June. It is prop back of that date, and inquire whether the disease had been i or developed in the city previous to that time.

The steamboat John Kilgour left New Orleans, where cho prevailing, on May 13, and landed at this city May 23, having h

n cholera on board during the trip. From this it has been
at the cholera of 1873, in Cincinnati, dates with the 23d of
ll therefore confine my present inquiries to the period follow-
te, although my investigations of the subject have extended
t time, with, however, the same result.
nade its appearance on the John Kilgour upon the second
ne left New Orleans. The first victim was Mr. John Schenck,
t citizen of this county, who died about forty miles above
; the second was a deck-passenger, who died about fifty
Cairo, on the Ohio River, and was buried soon after death;
who was also a deck-passenger, died twenty-five to thirty
Evansville, Ind., and was buried at Rome, one hundred
Louisville. The steamer was well washed and scrubbed
es afterward; the state-rooms were thrown and kept open
free ventilation, and the whole boat was thoroughly disin-
rent agents having been obtained at Evansville for that pur-

n had any symptom of cholera on the voyage except those
All the deck-passengers left the boat at Louisville. The
acquainted and subsequently met and conversed with many
-passengers; he knew all the officers and crew; and neither
other officers have heard of a single person on board having
mptom of cholera after the trip.
ains of Mr. Schenck were placed in an air-tight casket at
Tenn., about ninety miles from the place of death, and for-
m Memphis by rail, in charge of Adams Express, to Cincin-
n Cincinnati they were taken to the late residence of the
bout nine miles from the city, thence to the cemetery, one and
distant, without being removed from the hearse, and depos-
ir final resting-place before the performing of the religious
which took place in the adjoining church, after the interment.
was never opened after it had been hermetically sealed at
one thousand miles from Cincinnati. Mr. Schenck left a
ten children. None of the family has since had cholera or
esembling it; neither has any one of over one hundred persons
ed the funeral; nor has there been a death from cholera nearer
age, a village some three or four miles distant, across the
d on a direct road from the city, in a different direction. No
red outside of the city on the road to the residence of the
ver which the funeral cortege passed; and no case occurring
since can be traced to the John Kilgour, to anybody on
anything connected with the vessel.
oat brought the disease to Cincinnati, we might expect to
f the first cases developed in the city among its passengers,
crew; among some of the friends or acquaintances visited by
nong persons having some intercourse with the boat. Or, if
had been at first overlooked as genuine cholera, we might
first fatal cases, pronounced diarrhœal affections, in some
nnected with the boat, or with some article carried by her
fected district. What was the fact?

CHOLERA MORBUS.

death reported from any diarrhœal cause, after the arrival
Kilgour, took place at No. 1327 East Front street, on the
y. This was a case of diarrhœa, in a child four months old,

and will be referred to again. The second occurred in the Ci
Hospital, on May the 27th. The case was reported in the certi
death, by the attending physician, as cholera morbus; duratio
illness, six days. The attack, therefore, commenced two day
the Kilgour arrived at the wharf.

The patient was a stranger in the city, a farmer from the
eastern part of Kentucky, where no cholera had then or has si
vailed; nor did his course to Cincinnati lay through any cholera-
locality. It is not unusual for persons from the country, espe
the early part of the warm season, when the use of new vegeta
just been commenced, to experience, from change of diet, water,
cause, more or less disturbance of the bowels. Soon after his
this visitor was seized with diarrhœa, and taken, May 22, to the
nati Hospital. When admitted, he was, the record says, "
some at the nose. On the 23d, he had light-colored stools; on t
his stools were dark colored; on the 25th, they were tinged gr
the 26th, there was little diarrhœa; on the 27th he was seized w
vulsions, in which he died. The duration of his illness was rec
six days, his residence in the city at one week. His death, as
remarked, was returned to the health-office, with the certificat
physician, as cholera morbus; and certainly the epistaxis and
sions would not point it out as a case of genuine Asiatic choler

The next case reported as cholera morbus, which proved fatal,
in the practice of Dr. George E. Walton, died May 12, also in
sions, and had, besides, sanguineous discharges from the bowe
patient was a child, twenty months old, living with its parents
237 Longworth street, in a high and healthy neighborhood. The
had not been near any person or thing associated with choler
child's illness lasted only twenty hours.

Some physicians might hesitate to pronounce a diagnosis
cholera cases, on account of the doubt and incredulity that migh
tertained by members of the medical profession, until the pre
the disease was well established and generally acknowledged.
be difficult, however, to show that these two, which were the on
reported as cholera morbus until June 16, should have been di
true Asiatic cholera. And if they should be so pronounced,
not be very evident that they were either imported or contract
an imported case.

CHOLERA INFANTUM.

The first death from cholera infantum, after the 23d of May,
May 30, after three days' illness. The patient was a child two
old, living on York street, a distance of 6,650 feet, or more than
one-fourth miles, in a direct line, from the nearest railroad-de
9,800 feet, or nearly two miles, from any steamboat-landing.
same day, at No. 510 West Fifth street, a distance of 6,950 feet,
one third miles from the first case, five squares from the nearest
railroad-depot, and 6,200 feet, or more than a mile, from the w
which the John Kilgour landed, the second death from this dise
place. The patient was a child seven months old, and died a
days' sickness. The third death occurred June 4, at No. 21 Par
four squares from the last case, 5,000 feet, or nearly one mile,
steamboat-landing, and one square from the Ohio and Mississip
road depot. The child was two days old, and two days sick.
same day, after an illness of five days, the fourth fatal case to
at No. 117 Betts street, 2,500 feet, or nearly half a mile, from t

nentioned above, 6,000 feet from the Ohio and Mississippi
8,000 from the public landing. The patient was two months
ifth death from cholera infantum took place at the Burnet
June 6; the child was six months old, one day sick, and only
the city from the South.
the first patient attacked with any diarrhœal disease, who
om a suspected district. No case of cholera, or of any from
disease, occurred subsequently nearer the Burnet House than
e-half squares. That case was one of cholera, and died at
House, nearly a month later; and no connection could be
between it and the Burnet House case of cholera infantum.
fatal case of cholera infantum occurred more than four
the river; death took place June 7; age of the child, seven
n June 8, the seventh case, aged ten months, died on Lib-
after three days' illness. The nearest previous death to
iarrhœal causes, was about ten squares distant. At No. 337
eet, and on June 11, the eighth case died; age, one year;
illness, two days; several squares distant from the last-
case, and 8,500 feet from the river. The ninth case of chol-
n, or the last which terminated fatally, between the 23d of
th of June, died June 13; age, eleven months; duration of
e days; residence, No. 79 Dayton street.
exception of the patient at the Burnet House, these children
tives of the city. The parents of one had no acquaintance
ication with those of any of the others, and their homes were,
st part, at widely-separated points. The two nearest cases
er were the first and last, and they were about two squares

* * * * * *

ACUTE DIARRHŒA.

be difficult to discover anything in the reports of these cases
ey were not what they were represented to be. Nor would
to find any characteristic symptom of cholera in the follow-
l cases of diarrhœa during this period. The first fatal case
, referred to above, occurred on East Front street, 9,000 feet
line (15,000 feet, or nearly three miles, by the line of travel
oad or river) from the public landing, and 6,800 feet in a
e from the nearest railroad-depot, or 11,600 feet by the line
The patient was a child four months old; duration of attack,
hours; date of death, May 26. The second fatal case was
four months old, who died May 31, after ten days' sickness,
st Third street; distant, directly west, from the first case
, or more than two miles, and more than four miles by the
el. The third occurred on Mount Adams, at a point (mid-
n these two cases) 3,500 feet from and 340 feet above the
e Ohio River. This child was nine months old, and three
. The fourth case was three months old, twenty-four hours
lied June 10, on Vine street, above Liberty, formerly the
oundary of the corporation, and still north of the densely-
portion of the city. This case occurred 9,000 feet, or more
nd a half miles, from the river.
al cases of chronic diarrhœa were reported during this time,
f which was an adult. The first was a female, twenty-one
e, who had suffered under the disease four months; another

was a child who had diarrhœa from birth; the third was a chi
months old, the last third of whose life was a prey to the disease.
of these cases were located near any of those mentioned above.
be added that, as in the cases of cholera infantum, none of the
in which death took place from diarrhœa had any acquaintanc
tercourse with the others.

* * * * * *

LATER CASES OF DIARRHŒAL DISEASES.

There were probably cases of cholera occurring at a later period
from the absence of some well-marked symptom or symptoms,
down to kindred diseases. These occurrences, however, took pla
not before, the acknowledged appearance of the epidemic. It
pened that the first fatal cases of true cholera fell into the
physicians who recognized the disease and gave it, in their cer
of death, its true name. From these cases the manner in wh
epidemic entered the city cannot be traced. Had it been po
have obtained a history of all the cases, those that recovered as
those that died, the introduction of the disease might possib
been traced through their history. But even if this could ha
done, it would be difficult to trace the first fatal case to any in
cause; and the mode of propagation afterward would still have r
a mystery. No two cases occurred in the same block or had a
nection with each other, with the exception of a single instance, i
father and child died in the same house upon the same day, u
teen deaths from cholera were reported in widely-separated part
city.

* * * * * *

No cholera-epidemic influence is necessary to explain the diffe
the number of deaths from these causes, in the corresponding
of these different years. The deaths from them were less in 18
in 1871, and the havoc made by small-pox among children in 1
minishing the material for the ordinary summer-complaints of
would account for the difference in that and the present yea
without taking into consideration the difference in population, a
two of the cases actually occurred in the newly-annexed te
Neither in their variety, in the number of cases, ages of the pati
violence of the attacks, were the diarrhœal diseases for three we
ceding the appearance of cholera materially different from othe
What is here said of specific diseases may also be said of dis
general.

The total mortality from May 23 to June 13, inclusive, ex
still-born, was in 1871, 288; 1872, 264; 1873, 261.

FIRST CASES OF CHOLERA.

These facts show pretty clearly that Cincinnati was not only fr
any unusual severity in ordinary diarrhœal affections, but wa
enjoyment of its usual health when the first case of cholera was r
The certificate of death gave the name of Philatine Gundloc
forty-five years; widow; residence, 57 Oliver street; residence
city, twenty years; previous residence, Germany; duration of
ness, twenty hours. Being desirous of tracing the introduction of
into the city, I addressed a note to Dr. N. Leaman, who atten
case, requesting answers to certain questions, and stating as a

st that, as this was the first case reported, it was desirable full a history as possible of the origin of cholera in the city, ntroduction, &c.

quiries were made in the investigation of subsequent cases. ing were the questions:

ere her habits of life?

nd of labor or work was she in the habit of performing?

been recently out of the city; and, if so, when, and to what

person from other localities been visiting her? If so, was om a locality where the cholera was or had been prevailing? recently visited or nursed any sick person having symp- era or cholera morbus; or attended the funeral of any one ymptoms of diarrhœa?

dwelling clean, and what was its situation in relation to ntilation?

ere any filthy gutters, stagnant pools, or other nuisances in hood at or before the time of her attack?

ere the sanitary surroundings of her residence?

, prior to her illness, made any alteration in or departed ustomed diet or drink?

discover any exciting cause; and, if so, what?"

bliged from want of space to omit the details of the four- hich have been reported somewhat in detail by Dr. Quinn; wever, sufficiently noted for all practical purposes in the marks.—McC.]

es occurred during the first six days of the epidemic, and ed somewhat in detail because they were the first fatal ed. None of the parties, except the father and child at 160 ad, had any association with the others; neither had been ty for three months or more; neither had any communica- e steamboat, or with a railroad-depot; and neither, as far certained, had been in contact with persons from cholera- tricts or cholera-patients. The local or proximate cause in e was, in the opinion of the attending physician, the large er-cakes and green vegetables. In the second case, the pa- f attributed his sickness to ice-cream and radishes, eaten e days. The circumstances surrounding the patient, with his of habits, might be sufficient, if the remote cause were account for the development of the disease in the third her the fourth patient had been imprudent in his diet could ed, and whether sewer-gases, from the catch-basin in front residence, had any connection with her attack, may be a eculation. The fifth patient occupied dark, badly-ventilated clean premises, and had used green vegetables for food. The so eaten green vegetables, which, at that time, were consid- t persons, from their own experience alone, very unwhole- seventh had not only eaten unripe vegetables, but also un- t. The eighth had been overheated, and taken an unusual cold beer. The premises where the ninth death occurred sanitary condition, and the patient was in feeble health at the attack. The tenth patient had indulged in the excessive or. Little could be learned, at the time of death, of the d twelfth cases, and as the widow with the surviving child ard returned to Germany, nothing could be learned since. , however, that the father had suffered from diarrhœa for

two weeks before the cholera-symptoms set in, and that thes
lowed the use of sour wine. The habits of the thirteenth pa
lived in a boarding-house with bad sanitary surroundings, co
ascertained. An overcrowded tenement-house was the home
case mentioned. It is not known upon what diet the child ha

These cases, with the exception of the eleventh and twe
place in different and distant parts of the city. They we
10,800 feet, or more than two miles, from west to east, and 1
or nearly three miles, from south to north. The location of the
was 8,750 feet, or more than one and a half miles, from the p
ing, and 7,400 feet, or more than one and a quarter miles, fro
est southern railroad-depot, and not on any line of travel fro
these points to any business part of the city. The second
3,600 feet from the river, 5,000 feet from the nearest southern
depot, and 4,800 feet, or nine-tenths of a mile, from the first
railroad, which makes connection with Louisville, passes the
the third case, but the cars are not stopped to exchange pass
freight nearer than 4,200 feet from the place. Its distance
public landing was 9,150 feet; from the second case, 8,350 fe
than one and a half miles; and from the first, 7,000 feet, or
and a third miles. The fourth death took place at a point nea
of the triangle formed by lines connecting the localities o
three cases, at the distance of 4,350 feet from the first, 3,95
second, and 6,735 from the third case. The patient's own resi
within the triangle, nine squares north of this. Its distance fro
case was six blocks, from the second about 4,000 feet, and from
over 6,000 feet. From the fifth case to the fourth, which was t
reported up to that time, the distance was 4,400 feet. The
was 2,600 feet, the seventh about 900 feet, the eighth 3,000 fe
ninth 2,100 feet from the next nearest cases, respectively.
tenth to the fourth, which was the nearest previous case, the
was 550 feet. From the eleventh and twelfth to the nearest
that had occurred the distance was 2,400 feet. The thirteen
was seized with the disease at the distance of nine squares
nearest previously fatal case of cholera; and the fourte
squares from the nearest death from the same cause.

* * * * * *

It may be remarked that, with comparatively few exception
tion could be traced between cases; and that when an appare
tion existed, it might, in most instances, be fairly attributed
mon proximate cause.

It is also proper to state that in no instance did a death fro
occur at a greater elevation above low-water mark in the O
than 175 feet, and few fatal cases occurred at a higher altitude
feet. Low-water mark in the Ohio River, at Cincinnati, is
above tide-water in the Gulf.

* * * * * *

The total deaths reported from cholera were 207, distribut
lows:

In hospitals, previous histories of patients and places where attacked not k	
In different parts of the city, residences not found	
In hotels	
In private residences	
In tenement and boarding houses	
Total	

e patients who died in hospitals could be traced to their
ne were non-residents, taken from steamboats; some had
permanent homes; and others were boarders in different
city, little of whose histories could be learned. It was as-
wever, that three of them had been in previous ill-health,
ad been imprudent in the use of intoxicating liquors, and
it in diet. In addition to these, two labored under great
ement and dread of the disease, before their attack. It
wn that all were members of different families.
reported on sparsely-built streets, in houses not num-
me were returned with the wrong name of the patient, or
mber of residence. There were eight of these, the sanitary
whose homes and whose habits of life and history of attacks
learned. No two of them, however, belonged to the same
re were also seven other cases, whose residence, though
l included in the following table, cannot be indicated upon
onsequence of its partial boundaries.
ourteen years of age, died in one of our large hotels. He
ending school in the city, though his home was in another
tate, and no exciting cause could be discovered to account
. The hotel was clean, excellent in its appointments, and
No other death from cholera was reported in this or any
the city.

* * * * * *

cult to obtain from surviving relatives an acknowledgment
e in diet, drink, or habits of life. But when reliable histo-
atients could be obtained, a probable exciting cause could
liscovered, either in the habits of the patient, the over-
lition of the dwelling, or the sanitary aspect of the prem-
ndings. The term "exciting cause" is used in the sense in
oisture, heat, and light excite vegetation. On the theory
germs were present, they seemed no more capable of devel-
ut extraneous aid than seeds of grain upon a barren rock.
panic in the city, and few cases could be attributed to
nt proximate cause in the cholera-epidemics of 1849 and

ndred and seventy-six patients whose residences were
-two were members of thirty-one families, occupying an
ng each; two were visiting relatives in a private family
e house; and one hundred and forty-two lived in tenement
houses.

DEATHS IN PRIVATE RESIDENCES.

deaths took place in thirty-two private residences. Thirty
te families had one death each; one had two deaths; and
took place the death of the two visiting relatives.

MULTIPLE CASES IN PRIVATE RESIDENCES.

wo were the first multiple cases in private residences, and
e hundred and thirty-seventh and one hundred and forty-
cases that occurred in the city. One of the patients was a
ewport, Ky., who had merely visited her sister for the pur-
ding the day. She had just recovered from an attack of
r own home, and was laboring under diarrhœa in the fore-

noon of the day of her visit. She ate, however, a hearty dinner
food, was seized with vomiting two hours later, and died next d
9, the duration of the attack being twenty hours. Her son w
pectedly summoned to her bedside, labored under great exc
and became very much exhausted from attendance upon his
His death took place July 10, after twenty-six hours' illness.
tary condition of the premises and surroundings was good. Th
was upon the same block on which case No. 2 occurred, and dist
it about half a square. Some might attribute these cases to t
fact; others would probably regard at least the first of the tw
imported case from Newport.

The other multiple cases in a private residence are 175
those numbers indicating the order of their occurrence. F
tients were children, aged, respectively, four and seven yea
first died August 2 after six, and the second August 3 aft
hours' illness. Nothing which might be considered as the pr
cause of the disease could at first be discovered. The fami
comfortably, in a clean and healthy part of the city; great p
had been exercised in directing and regulating the habits a
of its members; the house itself was well arranged for ven
and in excellent sanitary condition. A closer examination of th
ises showed an unusual construction of the soil-closet, or priv
vault was situated in a wood-shed and arched or covered ove
distance from the shed, toward the center of the yard, was th
house, fitted up with hoppers in water-closet style, but with
traps, water, or water-pipe connections. The hoppers were co
by a downward soil-pipe, with the closed vault in the wood-she
inclination of this pipe was not sufficient to carry downward
the vault, semi-fluid material. Here were a vault and privy
tions, unintentionally arranged for the confinement of noxiou
and for their escape in the most concentrated form, whenever
and agitation from drenching the soil-pipes were brought to bea
took place every day, as the pipe was that often flushed wit
This out-house was used by the children, and around it were
customed haunts.

An occupant of the adjoining building, whose windows ov
the out-house, was also attacked with cholera about the same ti
these children, but recovered.

The thirty private houses, in each of which one death too
contained one hundred and thirty-four rooms, and were occupie
hundred and forty-one persons. The two houses in which
cases occurred contained ten rooms, and were occupied by nine
In twenty-eight, the sanitary condition was good; in the othe
was more or less unfavorable.

DEATHS IN TENEMENT AND BOARDING HOUSES.

One hundred and forty-two persons died of cholera in one
and thirty-one families, who lived in one hundred and thirty-o
ent tenement or boarding houses. The houses contained, in a
hundred and thirty-four families, numbering two thousand nine
and eighteen members. One hundred and twenty-two of the
were members of the same number of families, and lived in h
each of which only one fatal case occurred. These one hund
twenty-two families numbered four hundred and thirty-eight
and occupied two hundred and sixteen rooms. The houses

six hundred and fifty-eight other families, consisting of two
o hundred and ninety-two persons. Forty-nine of these
favorable surroundings; of seventy-three, the vaults were
he premises unclean, or the surroundings bad.

MULTIPLE CASES IN TENEMENTS.

the one hundred and forty-two patients who died in tene-
ding houses were members of nine families, seven families
nd two families having three deaths each. These families
forty-four persons, lived in nine different houses, and occu-
rooms. The same houses were occupied by forty-four
s, consisting of one hundred and eighty-five members,
three families of two hundred and thirty-nine persons in
Five of these houses had clean premises and surround-
mises or surroundings of the other four were in bad sani-
n.

g of the sanitary condition of premises, it is not deemed
refer to that arising from overcrowded buildings, further
the number of members in the families, with the rooms
number of other occupants of the buildings. The char-
enement and boarding houses, in which deaths from chol-
was as follows: fifty-one two-story, sixty three-story, and
, brick; and fourteen one, and two two-story, frame. For
the yards were small, and in many instances so inclosed
houses as to preclude the free circulation of air.

* * * * * *

atients except two were either natives or residents of the
time previous to their attack. None of the families in
ths took place had lived in their respective residences less
r; and none, except that in which cases Nos. 137 and 142
any intercourse with persons from infected districts.
of Nos. 11 and 12, as far as could be learned; Nos. 137
Nos. 175 and 177, has already been given.
, and 27 lived in the upper and rear part of a three-story
second level of the city, in the midst of a densely-inhab-
hood, and surrounded by large tenement-houses. The
sided in the same place for eighteen months. The father
and worked at some distance from his home; the mother
delivered of twins, and the usual care could not be given
n. The first child attacked with the disease was seized
et, while at play, with vomiting, and discharged from the
ge quantity of cherries. To quiet one of the other chil-
taken to a neighboring saloon and fed upon pretzels and
families, of seventeen persons, occupied the house; the
lean and well ventilated; but the vault beneath the win-
partments occupied by the patients was full and foul.
d 29 were children, aged, respectively, twelve and eight
occupied with their parents two rooms on the upper floor
ry brick tenement-house. The house was occupied by five
hirteen persons. The premises were clean, and nothing
be learned of the diet of the children.
, and 32 lived about one square from Nos. 17, 26, and 27.
onsisting of the father, mother, and two children, occupied
n the ground-floor, in a two-story double frame building.
contained four families, and was separated by a joint yard,

about 16 feet wide and 30 feet long, from a three-story brick house, containing eight families of twenty-seven persons. privy, common to the inmates of both tenements, occupied t of the yard. The western part of the yard was occupied stairs, leading to the second story of the frame; porches along building covered the eastern side; and the hydrant, which been running most of the time, to supply so many persons, front, where it was located, continually damp. This yard w structed, on three sides, that no current of air could pass t Little sunlight could enter it at any time, and none for the gr of the forenoon or afternoon.

The father was a musician, and was engaged with a band, o playing in a religious procession. The day was extremely ho children, according to the statement of the mother, became excited and overheated in following the procession. On his the evening, the father found them prostrated with the disea lived until the next day, when he was also attacked; his ca ated fatally on the day following. He had been exposed to during a long walk on the 22d, and became very much agita his children so ill on his return.

Three families, of eleven persons, occupied the house in whi and 60 occurred. The house was a two-story brick, the priv which was in foul condition, though the surface of its conte feet from the ground.

The seventy-eighth and eighty-ninth cases were mother The family consisted of the parents and two children, and two front rooms in the third story of a brick tenement-hous other families, of twenty-nine persons, lived in the same build vault was full and foul. The neighborhood was clean, and, t and sides, occupied with similar tenements. From the rear northward one of the hills which surround the city, and sparsely built upon. Another death from cholera took pla adjoining street almost immediately in the rear of these famil patient had been sick eight days, and died two days previo No. 78.

Cases Nos. 81 and 85 were twins and died upon the same the same duration of illness. The family consisted of nine and occupied two rooms in the rear of the second story. was a two-story double frame, situated in the eastern part of in front of a high hill, and one square north of the Ohio R tween it and the river were no residences or buildings to ob breeze from the water; on the side-hill, to the rear, were houses. The building contained twenty-eight rooms, which pied by thirteen families, of seventy-three persons. Upon the were two vaults, both of which were in a very filthy condition

The building in which cases Nos. 115 and 116 occurred wa story brick, well ventilated, and clean. The entire premises, immediate surroundings were in good sanitary condition. The were brothers—healthy, robust young men. On the 4th of attended a large picnic, given to German societies on a visit f cities, and at which beer and wine were the most prominen ments. Both day and evening, at the picnic and afterward, by these young men socially and convivially. They were sei the next morning with cholera, and died, one after twelve, after eight hours' illness.

No satisfactory history could be obtained of Nos. 202 and

sted of eight persons and lived in a three-story brick house, two other families, of thirteen members. The house, street, rhood were clean, and, with the exception of being situated marshy bottom of Mill Creek, in good sanitary condition.

NON-FATAL CASES.

ve I have only included fatal cases of cholera, but in their every actual, apparent, or probable connection with non- as been duly considered. Non-fatal cases are not included satisfactory reason that full returns of the number which ld not be obtained, and for the additional reason that the nany of the reported cases of recovery were incomplete or sent. Any attempt at a full and complete history of them ore be defective. As I have aimed at definiteness and accu- at what might merely be plausible or possible, I have pre- essay at this time a report which would necessarily have ation only partial returns of numbers and incomplete histo- s. At another time such history may be given of non-fatal ld be warranted by the reports already received and which btained.

ORDINARY DIARRHŒAL DISEASES.

there was no unusual number of deaths from diarrhœal re the appearance of cholera, the mortality reported after- holera morbus, cholera infantum, and acute diarrhœa, was xcess of that from the same causes in previous years. excess was due to the confounding of these diseases with on account of the absence of some prominent symptom, or re were two or more epidemics running parallel with each e determined by each medical reader for himself.

e fatal cases reported as cholera morbus, cholera infantum, iarrhœa, were wanting in one or more of the characteristic Asiatic cholera. In only two of the cases has it been hat rice-water discharges were present. There is reason to they were present in one other case. None of the others, be ascertained, had rice-water evacuations, husky voice, d fingers. In only a few was there suppression of urine, ramps existed they were described as of a much less vio- r than those usually accompanying Asiatic cholera. It is however, that cholera can exist, and even prove fatal, with- ence of rice-water stools, and it may be that the absence ther prominent symptoms, led to errors in diagnosis.

ld not, therefore, seem to be any impropriety in regarding t least, of fatal cases of what was reported as the ordinary iseases of summer as due to the same influence that pro- doubted cases of cholera. For this reason I give the deaths m cholera morbus, cholera infantum, and acute diarrhœa, from June 14 to October 18, together with the total mor- hese causes during the year, and during the years 1870, 72.

* * * * * *

CHARACTER OF THE DISEASE.

holera has been supposed by some not to have been of the atic type. Some have regarded it as Asiatic cholera, but ally characterized by all the prominent symptoms of the

disease, as in former epidemics. If all the cases which were under the names of cholera morbus, cholera infantum, a diarrhœa are to be regarded as typical cases of the cholera there would seem to be grounds for the belief that in Cinc least, some of the hitherto-prominent symptoms of Asiatic cho absent. Whether such was the case in Nashville and elsewhe the epidemic was more devastating in its course, is best know medical profession of those places.

The cases that fell under my own observation, those that r as well as those that died, were as well marked as any encou me in former epidemics of the disease. It is possible for disease to be transplanted, or become naturalized, and yet reta characteristic symptoms and virulence of the original type also undergo some change or modification in its character.

It might be a matter of interest, but can be of little practica tance, to determine whether the late scourge was an indigenou merely resembling in symptoms and violence the cholera of the since it was governed by the same laws in its mode of pro demanded the same treatment, and was attended with the sam as the Asiatic cholera of previous epidemics.

GENERAL SUMMARY.

Cholera was in New Orleans as early as February 9, 1873.

It has been pretty conclusively proven by the health auth New Orleans that the epidemic of 1873 was not imported into by vessel from any European or transatlantic port.

From New Orleans the disease traveled as far north as Lit on the Arkansas; Davenport, on the Mississippi; Yankton Missouri; and Pittsburgh, on the Ohio Rivers; following, ap the larger water-courses, and up the tributaries of the Ohio interior of Tennessee and Kentucky. It also visited interi situated upon small streams of water, and made its appearanc cago and Cleveland, upon the southern borders of our large lak

In its travels northward it frequently avoided one commerc to settle in another and more distant one, although steamb infected districts had landed at, or passed by, the avoided to although communication by other modes of travel was uninte At later periods it broke out at some of the points which had b passed. It was in Louisville eight days before it broke out i ville. It passed Owensborough, Ky., two months before it bro that place. It made its appearance in Burlington, Iowa, on the as in Saint Louis, passing by Hannibal, where it did not app nineteen days afterward. It was in Chicago nearly two mont it was in Cleveland, and one month before it was reported Louis.

The first infected steamboat or vessel on which deaths from had occurred, arriving in Cincinnati from New Orleans du prevalence of the epidemic in the South, brought no case of di the city, neither could any subsequent case be traced to it; no same boat leave the disease at Evansville, where it landed fectants; at Louisville, where it discharged all its deck-pa among whom two deaths had previously occurred; or at oth where it stopped to discharge passengers or disload freight.

Although constant and daily communication was kept up first appearance of cholera in New Orleans between Cincin

e Mississippi and Ohio Rivers where the disease was pre-
first fatal case in Cincinnati occurred on June 14, only two
ne disease broke out in Evansville, three hundred and fifty

earance in Cincinnati the streets and alleys were clean and
erally in a fair sanitary condition. Neither the amount of
the prevalence of any particular type gave premonition of

ction can be established between the first fatal cases of
any steamboat landing, railroad depot, imported cholera
person from a locality where the disease had been prevail-
as also true of the first fatal cases of what were reported as
ous, cholera infantum, and acute diarrhœa, with the single
one case of cholera infantum at the Burnet House, to which
nt case of intestinal disease could be traced.
non-fatal cases occurred in the city before the 14th of June,
e been possible to trace some connection between them and
district, and also between them and some subsequent cases
d fatal. The most careful investigation, however, has failed
the existence of anything like an attack of cholera from
atient recovered before the 14th of June. The first death
reported was the first case of the disease, fatal or non-
as can be ascertained, that actually occurred in the city.
there had been recoveries from cholera in the city before
would not be possible to trace any connection between them
t fatal case that was reported, or between that case and a
ted district. The patient lived a life of almost entire seclu-
n any direct line of travel to or from any steamboat land-
ad depot, and had no intercourse whatever with persons
en affected with any form of diarrhœal trouble.
ries of the first fatal cases were obtained at the time, or
heir attacks; and the fact was well established that the
e unacquainted with each other; resided in different parts
had not visited abroad; received no visitors from places
ra had been prevailing; and associated with no persons who
eal symptoms of any kind. Inquiries into the histories of
ent cases revealed, for the most part, a similar state of

cases of cholera fell under the treatment of physicians who
heir true character, and returned them, in the certificates
nder their proper name. None of the earlier cases were im-
agnosed or falsely reported. In some of the later cases,
ere may have been errors in diagnosis, arising from the ab-
ne prominent symptom, and these may have been returned
ame of cholera morbus or other disease. There was a large
eaths reported from the ordinary diarrhœal affections over
occurring in other years, which might probably be attrib-
lera, or at least to the cholera influence.
fficult to obtain from the surviving relatives any acknowl-
imprudence in diet, drink, or habits of life; but when
be obtained an exciting cause could generally be discovered
n to diet, in the overcrowded condition of the dwelling, in the
rroundings of the patient, or in a violation of some of the
giene. On the theory that cholera germs were present, the
son did not seem sufficient to develop the disease without the
e extraneous agency. Few, if any, persons who were known

to observe regular habits of life, prudence in eating and dri
who lived in clean and comfortable homes, fell victims to the

Except in cases taken from steamboats, after the presence
demic was established, the multiple cases Nos. 137 and 14
person from Pittsburgh, on a boat-race excursion, who spent
time in saloons near the river, no stranger in the city died of
Gardeners and farmers brought their produce to market, co
chants purchased their supply of goods, and citizens visited
business and pleasure; yet none of them were known to c
disease, or convey it in their persons, or on their clothin
places.

In its travelings from Cincinnati, as in its journeyings tow
cholera seems to have followed the direction of the large
water-courses. A case was reported to have occurred at
about June 9, although its prevalence there was not authori
nounced until July 22. It was at Dayton, on the Miami Ri
and at Columbus, on the Scioto, July 5. It did not requir
to three weeks to travel to those cities by railroad lines. Th
in Hamilton, on the Miami River, and also on the line of
tween Cincinnati and Dayton, occurred July 30. Carthage,
suburban village visited by it, is on the waters of Mill Cre
patients there attacked had not been visitors to the city.

* * * * * *

B.—THE INTRODUCTION OF EPIDEMIC CHOLERA I
CITY OF CINCINNATI, OHIO, IN 1873.

By William Clendenin, M. D., *late Health-Officer.*

During the summer of 1873 there were two hundred and se
from cholera reported by the board of health as having o
the city of Cincinnati; the first death from that disease, a
the same report, occurring on the 15th day of June.

At this date, (June 15,) and preceding the time of its rec
istence in the city, the mortality had been about the same as
ing years, and, according to the health-report, "no unusual
fatal cases of disease gave warning of the advent of cholera."
authority further declares that "the prevalence of no particu
disease foreshadowed the coming of cholera."

We have, therefore, the best authority for stating that the
the least indication of the existence of any *so-called* epidemi
or atmospheric condition to which this outbreak of cholera
nati could have been attributed. This is a fact of the great
cance, and one which corroborates the general history of the

How, then, did the cholera originate in Cincinnati in 1873
was the mode of its introduction?

There are but two hypotheses upon which its presence co
plained, viz: It must either have had a spontaneous origin
local conditions at the time existing, or it must have been i
some manner from some place where it was prevailing.

This is a question of the very highest importance to the pu
ally, as it has a distinct and weighty bearing upon the bus
ests of the city, as well as upon the health of the inhabit
cholera has once been generated here, if those conditions u
cholera originates in Hindostan exist in Cincinnati, then is t

e to break out in our midst at any time. Then, the system
e is not only useless, in so far as it affords protection against
tion of cholera from abroad, but it is an embarrassment to
o the merchant, and the traveling public, that should be
once. According to the decisions of the International San-
ence on the origin, endemicity, &c., of Asiatic cholera "this
ever spontaneously developed, and it has never been ob-
endemic, but it has always come from abroad."
earn something definite of the origin and mode of introduc-
holera into this city in 1873 by studying the course of former
nd their mode of introduction. Cholera made its first ap-
the United States in the year 1832. It developed first on
nt at Quebec and Montreal, at which points the first vessel
me to this country with cholera on board landed passen-
the places designated the disease radiated along the lines
all directions. It passed along the Champlain and Erie
nal-boats, and on the lakes in steamboats. It was carried
to the Upper Mississippi by the troops of General Scott's
nd thence to Saint Louis by the steamboat Columbus, and
Louis to Cincinnati on the steamboats William Parsons and
The first cases in Cincinnati occurred on the 9th of October,
having been passengers from Saint Louis on the boats
e epidemic had made its appearance in Cleveland, Ohio,
s earlier, or on the 10th day of July, as it appears from the
cial bulletin from the Cleveland Board of Health:

"BOARD OF HEALTH,
"*Cleveland, July* 10, 1832—*9 o'clock a. m.*

rd of health have the unpleasant duty to report that the
Henry Clay arrived last evening in our piers from Detroit
f her men sick, and, as the board of health have no doubt,
lera. She had been up with soldiers, among whom the dis-
ut, and of whom eleven or twelve died, (of cholera,) with
oat's crew, &c.

"J. MILLS,
"E. W. COWLEY,
"And five other members of the board of health."

mic of 1849 reached Cincinnati by way of New Orleans
e briefly these: The first two cases of cholera occurred in
s December 12, 1848. The patients were a man and a
were taken to the Charity Hospital, in the last stage of the
n the ship Swanton, which had just arrived from Havre.
n's passengers were German immigrants. Seventeen per-
the disease during the passage. The day following, that is,
f October, numerous cases appeared in the houses near the
The disease was carried up the Mississippi River, and ap-
emphis the 22d day of December. The steamboat Peytona
ouisville December 28th from New Orleans, with a passen-
our hundred, and there were fifty deaths from cholera on

ases of this epidemic occurred in this city on the 27th day
, or, to state the facts more correctly, the first cases occurred
f on steamboats just arrived from New Orleans, and were
Cincinnati Hospital for treatment, immediately after which
occurred among the inmates of the hospital. During the

next three weeks a few cases appeared in the vicinity of landing, among persons connected with river pursuits. In t reports of interments for the week ending April 25, nine case are reported, all of whom were boatmen and others taken to t from the wharf.

Prof. George Mendenhall, in a report of this epidemic m American Medical Association, states that "the amount of s Cincinnati) during the months of March, April, and May small, and the proportion of bowel affections not in great than usual. Notwithstanding this, we occasionally had a cas occurring, but they were very few, and confined to the lowe our foreign population, until about the 1st of June." The deaths reported from cholera from the 1st of May to the 30th 1849, was 4,114.

The cholera was carried to Chicago (in 1849) from Saint party of emigrants directly from New Orleans, on a canal-bo through the Illinois and Michigan Canal.

The facts relating to the epidemic of 1866 may be briefly s steamship Virginia left Liverpool on the 4th of April, 1866, v number of German immigrants, and landed at the lower New York, on the 17th. During her passage cholera broke the steerage-passengers, thirty-eight of whom died; and 1 who, after making the usual medical examination, (at the q found twenty-eight of the passengers in the steerage lying si cholera. The disease was communicated to the troops on Island, in New York Harbor, among whom it broke out on th July. A detachment of recruits from Governor's Island w Newport Barracks, where they arrived on the 10th of July death from cholera that occurred in Cincinnati was a Germa the day of the arrival of the troops from New York, had visite and crossed the river on the ferry-boat with them. Late in July 10, she was attacked with diarrhœa, vomiting, and cr next day she became collapsed, with profuse rice-water from the bowels, suppression of urine, &c., and died sixteen the first symptoms appeared.

A part of the same detachment of recruits which carried to Cincinnati were forwarded to Louisville, Ky., where th between the 16th and 19th of July. The first case of cholera i occurred on the 29th day of July, and was one of these re Governor's Island. The disease was carried thence to Bow Ky., and during the last of August and first of Septemb arrived at Nashville, Tenn., from Newport Barracks, Kent first three cases there occurred among these recruits; and, first case at Memphis, Tenn., was a recruit who had arriv before from Nashville.

Recruits from New York Harbor arrived at New Orleans and 16th of July, on the steamer Herman Livingston. pasage two of the recruits died of cholera, and two cases w hospital at Jackson Barracks as soon as the command di From Jackson Barracks the disease was carried into New O thence by boats along the Mississippi River to Cincinnati Louis. Early in the month of August several steamboats ar port of Cincinnati from New Orleans with cholera cases on it was about this date that cholera became epidemic in Cinc

The history of each of the three epidemics thus briefly tr that cholera reached Cincinnati by a different route each

. The facts presented also show most conclusively that in
nic the disease was *carried* to Cincinnati by human beings.
arance of the cholera in Cincinnati does not appear to have
adowed by the prevalence of any particular form of disease in
ie three epidemics, except perhaps by the small-pox, which
been regarded as a forerunner of the epidemic of 1849; but
ot at any time any unusual tendency to disease of the bowels;
y neither of these epidemics could have been of atmospheric
ogical origin, nor in any sense dependent upon local condi-

ases of the cholera epidemic of 1873 occurred in New Orleans
nonths of February. The mortality-reports published in that
by authority of the board of health, showed a number of
this cause during the months of February and March. The
rity admitted the presence of cholera there in April, and in
y-list for the week ending May 11, 1873, there were eleven
stered as having occurred from the same cause.
th or 16th of April the first case of cholera occurred in Mem-
did not become epidemic there until some weeks later.
nboat John Kilgour left New Orleans on the 13th day of May,
ch date cholera was quite prevalent in that city. The Kil-
onsiderable number of deck or steerage passengers on board,
m were flat-boatmen, from different places along the Missis-
Ohio Rivers, who had been down with produce, and were
ome. The cholera broke out on the Kilgour the next day
ft the port. The first victim was Mr. John Schenck, who
t nine miles from Cincinnati. Mr. Schenck died near Vicks-
s body was sent home from Memphis by railroad, in an air-
. Mr. Schenck's baggage was brought to Cincinnati by the
d there delivered to his friends. The body was buried with-
et having been opened or taken into the house. Three of
's deck-passengers died of cholera during this trip; one was
Shawneetown, one near Rome, and one near Evansville.
passengers went ashore at Memphis, and one at Paducah,
ic diarrhœa. When this boat arrived at Mount Vernon,
ble to land at the wharf-boat on account of the low stage of
nd she effected a landing a short distance above the wharf,
f her deck-passengers went on shore sick, as was believed,
oms of cholera, and entered the house of a Mr. Russell, situated
ce of landing. The next day Mrs. Russell was attacked with
died. A number of her relatives, residing in the county a
nce from Mount Vernon, who visited her while sick and
r funeral, subsequently took the disease, and among whom
f deaths ensued at their respective residences.
se cases the disease was carried back again into the town
ernon, and thus originated the fearful epidemic which swept
lace.
Kilgour landed at Cincinnati on the 22d day of May, as re-
he records of the Chamber of Commerce, with a number of
teerage passengers from New Orleans direct.
y stated, the board of health report that the first death from
Cincinnati was on the 15th day of July, *but the records of the*
ospital show that there was a death from cholera in that hos-
27th day of May. The patient was a farmer from Kentucky,
ken from the steamboat-landing to the hospital on the 22d
. Prof. John Davis, a member of the medical staff of the

hospital, who has had large experience in both the epidemics of 1866, treated this case, and pronounced it to be true Asiatic The subjoined history of the case is taken from the record hospital:

"ABRAM RORER was admitted into the hospital on May 22, 1873 Kentucky; states that he was taken sick yesterday with diarrhœa in legs, and vomiting. Stools very thin and frequent. Man of g well-developed, and well nourished. Lies partially comatose; se drowsy when aroused, and has no energy to answer questions of body cool; pulse 114, scarcely perceptible at the wrist; bleeding some at the nose. Temperature 97½° Fahrenheit. beef-essence, with ammonia carb. gr. xx, injected into the rect two hours. Patient vomits everything except the brandy, of had taken ʒss. every two hours since he came in the house.

"May 23. Had two characteristic rice-water discharges la Temperature gradually decreased during the night from 97 o'clock p. m. of the 22d until 4 o'clock a. m. of to-day until it 96° F. By 9 o'clock a. m. the heat was normal, and remained s Pulse 126, barely perceptible. Ordered brandy ʒvj, tinct. ʒij, of which ʒss to be given every two hours.

"May 24. Stopped the above, and ordered the following:

℞. Piperin,
Tannin,
M. Gentian, āā gr. j.
To be given every hour.

"Pulse 105; still weak, but stronger than yesterday; has again to-day. Stools dark-colored and deposit thicker, not so t hands still cold; lies perfectly listless. The temperature remai mal up to the middle of the afternoon, when it again began The following was then given:

℞. Hydrg. sub. mur., grs. x.
Piperin, gr. xx.
Tannin, gr. xx.
M. Ft. chart., No. x.
One to be given every hour.

"This was given until used up; then the same was repeated the hydrg. sub. mur.

"May 25. In *statu quo*. Stools somewhat green. Patient v reduced.

"May 26. Patient much worse; pulseless; limbs cold sunken; not much diarrhœa. Continued the treatment.

"May 27. Died in convulsions; cholera."

Copied from the male medical record of the Cincinnati Hosp 19, page 208, September 7, 1874.

W. R. AMIC
Resident Ph

This case was under the charge of Dr. John Davis, with Neave, resident physician.

W. R. A

On the 26th day of May a child died on East Front street, diarrhœa, after an illness of twenty-four hours. The parent child resided at a considerable distance from the steamboat-lan

o the point where steamboats tie up when not making regular

h of June a child six months old died of cholera infantum
net House, three squares from the public (steamboat) land-
child was sick only twenty-four hours, and had been in the
e day, *from the South.*
A child, aged twenty months, died of cholera morbus; dura-
sickness twenty hours.
ne John Kilgore the following-named steamboats arrived at
rom New Orleans upon the days named: Charles Bodman,
S. Turner, June 6; C. B. Church, June 14, and the Nicho-
rth, on the 23d of June. Each of these boats had cases of
holeraic diarrhœa on board during their passage.
f the line of boats running between Cincinnati and Memphis
on board during their trips made the last of May and the
June.
Rodgers, the Arlington, the Mary Houston, and other boats
on board during their trips up the river. The James D.
several deck-passengers and two or three of her crew by
ing her trip from Memphis to Cincinnati. One of her crew
as buried below Louisville. The family of this man resided
, and his clothing was brought up on the boat. A lady
g the boat at the landing, went on board to make inquiries
the deceased and his effects; the latter were shown to her.
ent from the boat to visit a sister living in Cincinnati. At
was in perfect health, but during the afternoon of the same
s suddenly attacked with cholera, and died the next day,
ess of twenty hours. A son of this lady came to Cincinnati
ng to take his mother home, but finding her seriously ill re-
her all night. Within four hours after the mother's death
similarly attacked, and died of cholera after an illness of
ours. Two other persons, friends of the family, who came
m, were attacked with cholera, but recovered.
of the Parker is reported to have said that all on board
ms of cholera during the trip except the captain and him-

inen used upon the Memphis and Cincinnati boats is usu-
by laundresses on shore, but nothing definite or satisfactory
rtained beyond this mere fact. The Nashville and Saint
generally have their washing done on board, though it is
lone on shore. These facts are certainly possessed of the
tant bearing upon the history of the introduction of the
from them the diffusion of cholera over the city of Cincin-
accounted for.
l, fifth, and seventh cases reported by the health-officer
ar the river. The second case treated at the Cincinnati Hos-
washerwoman, and the third case was taken to the hospital
2 West Front street, near the steamboat-landing.
h case reported by the health-officer was a colored washer-
o died at No. 130 L'Hommedieu alley. She had lived for
rs in Kentucky, a short distance from this city, but at the
death had been a resident of Cincinnati for three months.
made frequent visits across the river to her old home; the
which was three or four days before her death. In crossing
ver, by either the bridge or the ferries, she would have to
mediate vicinity of the steamboat-landing.

The first case reported to the health-officer was a German widow, whose occupation was that of caning chairs. Noth learned of the history of this case, beyond the fact "that sh the lower (toward the river) part of the city to buy her ca patient resided on the south side of Oliver street, more th from the river. Subsequently three other persons died of the north side of Liberty street, (which is the next adjace within one square of the first decedent's place of residence. persons died within the immediate vicinity of the house in second case reported to the health-office had died.

Several instances might be given in which the disease w from infected houses in the city to towns in the vicinity of but the facts already presented afford sufficiently-conclusive that the cholera was *carried* from New Orleans to Cincinnati beings.

The portability of small-pox is recognized by all physician it is often much more difficult to trace the course of that d the connection between cases than may be found in following of either of the epidemics of cholera that have visited the Uni The fact that all the other persons occupying the same hou take cholera from one of the family who may have died of it inexplicable than that only one of a family of six or nine pe small-pox, measles, or scarlet fever.

The facts above adduced are incontrovertible, and every un mind will admit that they prove fully and certainly—

I. That at the time cholera broke out in Cincinnati, in 1873, no unusual tendency to disease of the bowels.

II. That there were no atmospheric or meteorological condi ent which were not common to the locality.

III. That the sanitary condition of the city was fully as goo been at any time previous.

IV. That the first cases of cholera occurred in Cincinnati af rival of the steamboat John Kilgore from New Orleans, whe was prevailing at the time that boat left that port.

V. That the appearance of cholera at Mount Vernon, and ot on the Ohio River, below Cincinnati, occurred after the K landed at those points.

VI. That the first case of the epidemic at Cincinnati occu steamboat-landing.

VII. That other cases occurred in the immediate vicinity o and second cases reported by the health-officer.

VIII. That in each of the epidemics, viz, that of 1832, 184 well as 1873, the disease was carried into Cincinnati, alon routes of travel, by human beings, who had previously been the disease, or in some way directly exposed to its influence.

ISTORY OF A GROUP OF CHOLERA CASES WHICH URRED AT CINCINNATI, OHIO, DURING THE EPI-IC OF 1873.

By C. L. Armstrong, M. D.

CASES.

Irs. Hopper, 66 years of age, residence No. 211 Cutler street.
linnie Pettitt, 6 years of age, residence No. 211 Cutler street.
lichael Smith, 47 years of age, residence No. 70 Rittenhouse street.
. H. Smith, 7 years of age, residence No. 70 Rittenhouse street.
Irs. Dorris, 35 years of age, residence No. 70 Rittenhouse street.
Irs. McCarty, 42 years of age, residence No. 70 Rittenhouse street.
lenry Hoge, sr., 58 years of age, residence No. 72 Rittenhouse street.
nma Kiser, 17 years of age, residence No. 40 Rittenhouse street.
lerman Hoge, 20 years of age, residence No. 72 Rittenhouse street.
lenry Hoge, jr., 23 years of age, residence No. 72 Rittenhouse street.
hristina Hoge, 16 years of age, residence No. 72 Rittenhouse street.
hristina Hoge, 60 years of age, residence No. 72 Rittenhouse street.
linnie Luelf, 1 year of age, residence No. 72 Rittenhouse street.
Irs. George Hoge, 23 years of age, residence No. 258 Baymiller street.
ouisa Westing, 27 years of age, residence No. 258 Baymiller street.
Irs. Niederhelman, 70 years of age, residence No. 258 Baymiller street.
Irs. Niederhelman, 30 years of age, residence No. 408 Baymiller street.
Herman Niederhelman, 7 years of age, residence No. 408 Baymiller street.
Villiam Bromer, 22 years of age, residence No. 74 Rittenhouse street.
Frank Bromer, 18 years of age, residence No. 74 Rittenhouse street.
Irs. Sunderman, 26 years of age, residence No. 70 Rittenhouse street.
George Hoge, 28 years of age, residence No. 258 Baymiller street.

case in this group, Mrs. Hopper, was a professional nurse. een constantly employed prior to her attack, but with what eases cannot now be definitely determined. The symptoms

were severe, strongly marked, and after a collapse of thirty- duration she died. The duration of this illness was about hours. The sanitary condition of the premises was not g house was old. The dejections were not disinfected, but we into a privy in rear of house. The day before this lady died, daughter, Minnie Pettitt, who lived in the same house, was t choleraic diarrhœa, and was seriously ill for a number of day

June 29.—Michael Smith, the second case, was taken sick era, and, after being collapsed for some hours, reacted, and after a tedious convalescence. This man was a cooper by trade at No. 70 Rittenhouse street, but his shop was on the corne and Kossuth streets, and about thirty yards from the privy the excreta of the first cholera case had been thrown.

June 30.—The young son of Smith was taken ill with ch died after an illness of fifteen hours. This child had been in his father's room. The same day a female, who occupied Smith's house, and upon the same floor, was taken with the ease. She recovered after a slow convalescence, during whi fered a threatening relapse.

July 1.—The fourth case occurred in the same house, in the a female occupying a rear room. This case also recovered.

July 3.—Henry Hoge, sr., who lived in the adjoining hou occupied by the preceding cases, was taken with cholera, but The same day a young woman who lived at No. 40 of the s and in the same block of houses, died of cholera, after a few ness. This female had visited frequently the sick-room of boy during his illness, and had frequented the house durin that other persons had the disease.

July 5.—Four cases of cholera occurred at No. 72 Rittenho two of which proved fatal after an illness of from seven to n these are cases Nos. 115 and 116 of the health-officer's re same day, in a small tenement in the rear of this house, an i taken with the same disease.

July 6.—Mrs. George Hoge, the daughter-in-law of the fam 72 Rittenhouse street, who had been constantly with her sick was taken with the same disease at her home at No. 238 Baymi The recovery of this case was much delayed.

July 11.—A young lady, who had been betrothed to Henry and who had assisted in nursing the Hoge family, was taken era at the house of George Hoge.

July 12.—The mother of Mrs. George Hoge, who lived daughter, took cholera; and the same day her daughter-in-la sided at No. 408 Baymiller street, and her young son, were with the same disease.

July 14.—Two young men living at No. 74 Rittenhouse s taken with cholera.

July 16, a lady residing at No. 70 Rittenhouse street ha and the same day George Hoge, who had been constantly wit of his own and his father's family, had the disease.

In this series of cases none were fatal after the cases of Jul cases of recovery were fully marked, but all were placed un ment at the inception of the disease.

The above record is presented as an unusually clear demons the portability of the disease; all the cases, twenty-two in forming a chain of infection from the initial case.

CINCINNATI, OHIO, *December* 28, 1874.

y of the epidemic of cholera at Cincinnati might well be
onstrated by the three articles which we have presented.
would be so submitted, were it not that a few facts, throw-
nt upon the epidemic, have not therein been noted. We
briefly:

the outbreak of the disease at Cincinnati, the epidemic
blished at the following-named points: at Memphis, Tenn.,
ar Cairo, Ill., May 2; Nashville, Tenn., May 11; Saint
ay 11; Paducah, Ky., May 21; and Mount Vernon, Ind.,
th one and all these points Cincinnati is in constant com-
y steamboats and railroad.

reful examination of the records of the health-officer, as
his special report, there is nothing to show that any effort
trace the disease prior to the date of his first fatal case.
nt in paragraph quoted "non-fatal cases," can scarcely be
satisfactory, since the inception of the epidemic was cer-
per time for the investigation, and not a later period, when
the epidemic had been in a measure obliterated by time.
s upon pages 103 and 104 of the health-officer's report, re-
n-fatal cases," are swept away by those upon page 129,
ated "the first death from cholera reported was the first
isease, fatal or non-fatal, as far as can be ascertained, that
rred in the city."

btained from the health-office and the physicians of Cin-
rd of five hundred and three cases of cholera. Of these
ndred and eighty-eight were recoveries. Every effort was
in perfect lists of the cases which occurred, with, however,
ccess, as but a small proportion of the communications ad-
e medical men of the city elicited a reply; but, inaccurate
they still have conveyed significant information. In the
thus obtained, Dr. B. Mosemeier reports, upon June 4, a
that recovered; Dr. J. W. Underhill reports, upon June
case that recovered; Dr. N. Leaman reports, upon June
-case that recovered; Dr. B. Mosemeier reports, upon
olera-case that recovered.

remembered that it has already been recorded that Prof.
tated that the man who died at the Cincinnati Hospital on
lay was a case of epidemic cholera.

for the gentlemen we have named the same honorable
at Dr. Quinn so eloquently demands, upon page 71 of his
ose gentlemen who reported cases of cholera morbus early
nic.

g the epidemic numerous instances occurred demonstrating
sness of the disease. In the city three medical men fell
e of these was a resident physician at the Good Samaritan
this last case it has been contended that the disease was
prudence in diet; but the doctor was not attacked until
-cases had been brought into the hospital, and until after
vith them.

esident physician at the same hospital was attacked on the
e with a painless diarrhœa. He took passage upon the
les for Wheeling, W. Va., where he arrived on the 17th,
ed two house-epidemics of cholera: one at his home, a few
ne city of Wheeling; the other at the house of a blacksmith
d, where he had stopped to rest.

incinnati Hospital one nurse took the disease after many

cholera-cases had been treated, but recovered, although subje serious illness. At the Good Samaritan Hospital a Sister of M of cholera. This sister had not been in robust health for so and had been sent to the Mother-House to recuperate; she ret day that Dr. Quick was attacked, was in his room and that o cholera-subject, and in a few hours was herself attacked. been informed that other cases originated at this hospital, but unable to obtain the particulars.

At the Cincinnati Hospital the excreta of the cholera-pati thrown into the drains that empty into the public sewers. drains are constantly flushed with water, and in them disinfec habitually used. An inspection of the laundry of this most a conducted hospital will demonstrate that in the act of washing conducted, a most efficient disinfection of cholera-soiled clothi be secured.

We are unable to state whether disinfectants were used at Samaritan Hospital or not, being unable to obtain any particu

We are informed that a very active system of disinfection tuted throughout the city, by order of the board of health; th were treated with sulphate of iron; that houses at which cholera were disinfected with carbolic acid; that orders were issue placing of cholera-soiled clothing in strong solutions of sulphat that in two instances, at least, the clothing of cholera-pat burned; that chloride of lime was freely used in yards, and dirty places.

By many medical gentlemen of the city we were informed t cases that occurred under their care the excreta were most disinfected, and that every precaution was adopted to preve fusion of the disease.

Saint Bernard.

Within the limits of Hamilton County cholera was epide villages of Saint Bernard and Carthage.

A careful series of investigations show that these two point fected from entirely different sources, and that the demonstrati point is worthy of careful study. In noting the occurrence c at Carthage, the report of the health-officer of Cincinnati for 1 72,) concludes, "and the persons there attacked had not bee to the city," (Cincinnati.) Our investigations show that in both (Saint Bernard and Carthage) the initial cases *had been* visito cinnati.

The town of Saint Bernard, six miles north of Cincinnati miles south of Carthage, upon the old post-road, was origin ligious settlement, but is now a secluded village of Mill Creek This village, one mile east of the railways, has, with the except canal, no direct communication with the city of Cincinnati or of Carthage, except by private conveyance.

On the 27th of June, 1873, a man named Robert Picket, who day buried his wife, who had died of cholera at Cincinnat with his family of four children at Saint Bernard. A few ho his arrival Picket was attacked with cholera, and almost at hour three of his children were taken with the same disease the children, a female infant, three months old, died after an twelve hours. One child, three years old, died on the fourth,

emaining child, eighteen months old, died on the fifth day of the sickness. July 6, Picket was pronounced to be convalescent.

July 4, a man named Schmidt, who had frequently visited Picket, was taken with cholera and died.

During the illness of the Picket family a Mrs. Norman was constant in her attention to them, and on July 5 this good woman was taken with the same disease and died after an illness of twenty-four hours. This case was followed (July 6) by the attack of a woman named Schulte and two young children, who lived in the same house as Mrs. Norman. Within eighteen hours all three cases terminated fatally.

The Norman family were nursed by a Mr. and Mrs. Luxterman, who remained with them until the termination of the cases, when they returned home. In this family a lady seventy-nine years old, and three children, died of the disease.

A Mrs. Kouniman, who had attended the sick in both the Norman and Luxterman families, was taken with the disease, but recovered. In this family two young children died.

A dairyman named Kizer, living two miles from Saint Bernard, frequently visited the houses at which the disease had occurred. His family remained constantly at home, and only came in contact with the infection through the person of the father. Kizer escaped the disease; but his four children, two males and two females, died of cholera. Three other cases of the disease occurred at Saint Bernard, one of which proved fatal; all of whom resided in close proximity to the infected houses.

CARTHAGE.

Carthage is a small village upon the line of the Cincinnati, Hamilton and Dayton, and the Dayton Short-Line Railways, ten miles north of Cincinnati. The Miami Canal passes along the entire eastern extent of the town. On the southern outskirts is located Longview Insane Asylum. One mile north of town is the Cincinnati Infirmary, a county hospital, and at about the same distance eastward is the Hamilton County Infirmary.

Communication with the city of Cincinnati is constant; many trains each day pass over each railway; boats are constantly passing on the canal, and frequent wagon and carriage journeys are made between the county institutions and the city. North of the town are large beds of sand and gravel, and from these beds the city of Cincinnati obtains her supplies of these materials. This work alone furnishes employment to a large number of laborers, the majority of whom are Germans or Hollanders.

Until the 15th of July, 1873, no cases of cholera had occurred in the town of Carthage, but on that date a child two years of age, named Tent Have, was taken with the disease, and died after an illness of fourteen hours. Every member of the family to whom this child belonged, with but two exceptions, were taken with the disease and died—the father, mother, sister, and five children. These deaths occurred between the 15th and the 23d of July.

From a brother of Tent Have, now living at Carthage, and from a number of papers belonging to the deceased family, access to which we obtained through the kindness of Dr. W. H. Bunker, now the superintendent of Longview Asylum, we are able to trace this family from Holland to Carthage, Ohio. The party, consisting of Tent Have, his wife, five children, and the sister of the wife, with two young men, one of

whom was betrothed to the sister, arrived at New York on
ship City of Limerick from Liverpool, on the 5th day of Jul
shown by the certificate of the commissioners of emigrati
State of New York, which has been obtained through the k
Dr. John C. Peters.

"EMIGRANT-LANDING DEPOT, AND OFFICES OF
THE COMMISSIONERS OF EMIGRATIO
OF THE STATE OF NEW YO
"*Castle Garden, New York, September*

"This is to certify that it appears from the manifest or list
gers of the steamship City of Limerick, William Jamieson, u
rived at the port of New York from Liverpool on the fifth da
one thousand eight hundred and seventy-three, which manifes
file at this office, that Thenhar, Hendk, J. G., Johan, Berdi
Jno., Gerrad, and Maria Have, aged 36, 37, 8, 6, 5, 3, 1, 22, an
natives of Holland, arrived as passengers per said vessel, o
voyage to this port, according to the report of the master afo

[SEAL.] "H. J. JACKSON,
"*Assistant Se*

On the 31st of May, 1873, this party left Tubbergen, Holland
by the passports signed by the burgemeester, now in our
Belonging to a Catholic aid society, this family were shipped
terdam to Liverpool, thence to the United States.

July 6, the Tent Have party left New York for Carthage,
more, Md., and the Baltimore and Ohio Railway. On the 9th
July they arrived at Cincinnati, but, as we are informed by
vors of the party, too late to proceed at once to their destin
they remained in the city over night, sleeping at a station-h
an early train the next day they proceeded to Carthage, and
for by a brother, who, for some time, had resided in the villa

The men, with the characteristic industry of their race, at
employment at the gravel-pits. The women and children rest
ing the arrival of their effects. July 13, the boxes and bales
hold property having arrived, the family took possession o
their effects, which consisted chiefly of bedding and woolen
were unpacked and hung up in and around the house to dry.
long voyage; and it is asserted by the survivors that this had
unpacked since leaving home.

On the 15th of July a male child three years old was atta
cholera. This occurred ten days after landing in New York
days after their arrival at Carthage, and within forty-eight h
the unpacking of the chests and the exposure of their conte
sun and air. The same day, the father, who had been calle
work by the illness of his child, and was directed by Dr. Bu
down and remove some rank weeds growing around the house,
with the same disease, and died within eight hours; and at
same hour that the father was taken sick a second child, fiv
age, was attacked and lived only twenty hours.

The next day (July 16) the mother sickened, and died in twe
The next day (July 17) a third child, seven years old, died af
hours. A lapse of one day, and a fourth child, eight years
after twenty-four hours' illness. July 22 the fifth child, four
died after an illness of twenty-four hours, and the next day

oman died also. The two young men suffered severely with diarrhœa, ıt in neither did the disease advance to the second stage.

Under the direction and personal supervision of Dr. Bunker, the ex-eta of these cases were disinfected with sulphate of iron and buried, ıd all the soiled articles of clothing that could be discovered were ırned. The most active system of disinfection was instituted in the llage, and but one case occurred outside the house occupied by the ent Have family.

July 23, the day of the last Tent Have death, a young woman, married, ıd pregnant with her first child, and who lived in a comfortable house ɔont one hundred yards in the rear of the infected house, was taken ıth diarrhœa; on the 25th, cholera was fully developed, and she died ter forty-eight hours' illness, having aborted a four months' fœtus ɔme twenty hours before death.

It was subsequently ascertained that this lady, although forbidden ɣ her husband to go near the infected house, had prepared articles of iet for the sick, which she each day carried to the fence in the rear of ıe house to which the cholera was confined. Surely, such charity ɔvereth a multitude of sins.

No other cases occurred in the town of Carthage, but on the 21st of ıly, the day upon which it will be remembered the last child of ıe Tent Have family was ill of cholera, the disease suddenly ap-eared at the Longview Asylum, in the negro department, and in the ersɔn of a female who was employed as the cook. The case was iso-ıted; the excreta were disinfected with sulphate of iron. The patient ngered until the 23d, when she died. No other case occurred until ıly 26, when a white patient was attacked, and the same day four ther cases occurred. July 27 two more cases occurred. These eight ases all terminated fatally. July 28 a case occurred, which recovered. ıly 29 a fatal case is reported, with three cases who recovered.

It has been asserted that in no way could a connection be established etween the cases at the asylum and those in the town; that no com-ınunication existed between the asylum and the infected house; therefore he origin in the asylum must be considered as a distinct demonstration f the disease.

Through the indefatigable energy of Dr. William Clendenin, of Cin-ınnati, this point has been cleared up, and it is positively shown that he infection was carried into the negro department of the asylum.

The negro department of Longview Asylum is in a large house sit-ıated at some distance from the main buildings of the asylum. It is a arge brick building upon the western extremity of the asylum grounds. ın front of this building pass the canal and the Dayton Short-line Rail-oad, and in the rear a street to and from the village.

The insane inmates of this house were isolated from contact personally ıith the cholera-sick, but no such restrictions were adopted by the ıttendants, who were allowed all their usual liberty, and, actuated by ıumanity, the physician in charge of the negro division of the asylum ıad visited in consultation with Dr. Bunker the cholera-sick.

The introduction of the disease into the asylum, however, is not to be eft to any conjecture; for it is asserted that Joseph Marshall, the super-ɪisor of attendants in the negro division, frequently went from curiosity ınto the house where the Hollanders were ill of cholera, and that from ɪhis house he time and again returned to the asylum. A morbid curiosity seemed to possess this man; he could not resist the impulse, and as often as he could frame an excuse for leaving the asylum he visited the infected house.

This man, Marshall, who is a negro, passed a portion of e
the asylum-kitchen, and in the company of Delila Pointer,
the asylum-cases. Marshall was at the Tent Have house
last of the family died and as they were all dead he could see
for his not appropriating a curiously-braided coat, which ha
to the dead Tent Have. The negro love for finery overcame a
he may have had; the coat was concealed, and carried to t
when, as it was found to be wet, it was hung up on the bac
dry; while in this position it attracted the attention of a pati
Howard Preston, who, putting on the coat, wore it for a day
in it one night, when it was again taken possession of by Mar
next day Preston and four other inmates of the asylum were
cholera, when Marshall, properly connecting the outbreak of
with the stolen coat, destroyed it at the kitchen-fire. These
obtained by voluntary confession to Dr. Clendenin.

At Longview thirteen cases of cholera occurred, nine of w
nated fatally. Of these cases nine were females, four were
females and three males died. Of the total number of case
whites, seven were negroes. Five whites and four negroes d

The occurrence of white cases at the negro division is acc
from the fact that some time prior to the outbreak of choler
the crowded condition of the wards in the main buildings, a
demented whites had been placed in the negro division,
were mixed with the other inmates.

The main buildings of the asylum were isolated from the
the attendants rigidly respecting the orders issued by the su
ent. The medical gentlemen, who, as in duty bound, met
Dr. Bunker for professional advice, adopted every precautio
the introduction of the disease into the asylum, and successfu
cases occurred in the main buildings, where these gentlemen

At Lockland, some two miles north of Carthage, a single ca
in the person of a lady who had visited the house of the la
Carthage. This case was, however, but mild; the diarrho
tendency to advance beyond the first stage of the disease co
some days, but by absolute rest and the cautious use of
disease was arrested.

MONTGOMERY COUNTY.

Dayton is a city of some 30,000 inhabitants, located on the
of the Great Miami River, at the mouth of Mad River, and
line of the Miami Canal. The city is fifty-two miles northe
cinnati. The city is a railroad-center of considerable import

On the 2d of June, 1873, a man named McManus, who w
mercial traveler, arrived at Dayton, and put up at the Mercha
At the time of his arrival he was suffering with diarrhœa,
himself under the charge of Dr. W. J. Conklin, to whom he
following history:

"That he had come to Dayton directly from Memphis, Tenn
city cholera was epidemic. That a gentleman who traveled
had died at Memphis of cholera the day he left that city. T
leaving Memphis he had been attacked with a diarrhœa,
given him no uneasiness until his arrival at Dayton."

On June 3, Dr. Conklin reports this case as having large
untary rice-water discharges, and as being pulseless and c
treated with morphia, and gradually recovered. The excr

ase and the vault into which they were thrown were disinfected. No ther case occurred in the hotel.

It is not known that any other cases of cholera occurred at Dayton ntil June 29, when a man named Cameron was attacked with cholera, id died after an illness of thirty hours. Cameron was a hard-work-g, industrious man, but given to occasional hard-drinking. His busi-ess took him into all parts of the city, and although no connection can e learned between him and any other cases of disease, he had worked r some days on the new jail-building, which is in the same block as ie Merchants' Hotel. No cases occurred in the house in which Cam-on died, or its immediate vicinity.

July 3, William Wright, a cartman employed in the city street-clean-g, was taken with cholera, and died after an illness of eighteen hours. o cases occurred in his immediate vicinity.

July 14, a fatal case of cholera morbus is reported.

July 19, Martin D. Ward, the driver of a car upon the city-railway, as taken with cholera, and died after an illness of seven hours.

In the house at which Ward died resided his family, eight in num-er, seven of whom were attacked with the same disease, but all re-overed.

July 22, a female named Young, who had assisted in nursing Martin). Ward until his case was pronounced to be cholera, was taken with he disease, and died after an illness of twelve hours.

July 23, John B. Young, living in the same house as the preceding ase, was taken with cholera, and died after an illness of three days.

July 24, Mary Miller, who had been in the house of Ward, (the case f the 19th,) was taken with the disease, and died after an illness of hree days.

July 26, another female member of the Young family died after an lness of twelve hours; and on July 29 a married sister of the same mily, who did not reside in the same house, but who had been with her ther and sisters, died at her home, of cholera, after an illness of two ays.

It will be noted that but at two houses in the city of Dayton did chol-ra become epidemic in 1873. But one group of cases is found, the nitial case of which was Martin D. Ward. In his own family, seven ases of choleraic diarrhœa occurred; Margaret Young, who was in at-endance upon Ward, carried the disease to her own family; two other eaths occurring by Mary Miller, who had also visited the Ward house luring the early stage of the disease; another house was infected, but o other cases occurred. By Mrs. Hackett the disease was carried to a ourth house, but no other person was infected. The houses of the Ward and Young families are upon the same street, (King,) distant one hort square. The house of Mary Miller is on Baxter street, over half a nile from King street, while that of Mrs. Hackett was over two miles listant from King street.

It has been shown that in one instance (case of McManus) cholera ras imported into the city of Dayton; but it will be impossible to stablish any connection from known data between his case and that of Cameron, twenty-seven days later. Nor can any connection be learned etween Cameron and Wright, or between these two men and Ward. But Dayton being a railroad-center, at which not less than eight great ines of railway cross, at which trains of all descriptions are almost iourly arriving, the importation of the infection is more plausible than ny theory of local development which may be advanced.

That this city escaped an epidemic of the disease is due to the ener-

getic action of the health-officer, who promptly adopted all me
his power to confine the disease to the points where it becam
and there to stamp it out. And the solution of the problem
this process of disinfection did not prevent entirely the spre
disease is found in the fact that the early cases of the disea
the hands of irregular practitioners, who did not recognize a
date the gravity of the cases in their hands.

Clarke County.

Springfield, the county-town of Clarke County, is located a
fluence of Lagonda Creek with Mad River, and upon the line
National road, forty-three miles west of the city of Columbus.
field has a population of about thirteen thousand inhabitants
town of extensive manufacturing interests.

On the 3d day of July, 1873, the first case of cholera at
occurred in the person of a man named Patrick Horan, a da
upon the railroad, and who lived upon East Columbia street, a
locality, that receives the drainage of about one-fourth of the
is built upon high ground.

Horan was attended by Dr. E. M. Buckingham, who thus
the case: "Found the patient collapsed. Had been taken th
before with diarrhœa, attended with cramps. Rice-water d
and total suppression of urine rapidly followed. He was d
o'clock a. m. The patient occupied the first story of a fra
which was elevated perhaps one foot above the ground. The
comparatively well-ordered for a common day-laborer, but
filthy neighborhood. The man had been living in the house
than a year, and had been at work the day before his death."

The same day (July 3) Dr. Buckingham was called to see on
Parkes, who lived immediately across the street from the
which Horan had died. Parkes's case presented all the charact
cholera, and at 2 o'clock p. m. he was dead.

The next eight or ten cases that occurred were in the i
vicinity of these two cases. At no time did the disease spread
city, but remained confined to a few blocks and streets in the i
vicinity of the houses in which Hogan and Parkes had died.

A total of twenty-three cases are reported; of these cases e
fatal. This, however, does not embrace a full list of the
occurred, as some of the medical men of Springfield declined
any assistance to the work of collecting the history of the epi

To Drs. A. and C. W. Dunlap we are indebted for much
aid and assistance.

Franklin County.

CHOLERA-EPIDEMIC OF 1873 AT COLUMBUS, O

By D. Halderman, M. D., *Physician to the State Penitentiary.*

The city of Columbus, Ohio, 8,000 feet above the level of
and with a population of about forty-five thousand, is situat
on the east side of the Scioto River; the main part of it up
rising abruptly from the water's edge to an altitude, upon an
of about 65 feet, and extends thence, in the form of a plateau,
to Alum Creek, a tributary of the Scioto, distant, at this point
one-half miles. Toward the northwest this table-land sinks


BOLT WORKS
Ohio Bent Work Co
Schreyer & Smith
Axle Skein Works
C. Ambos & Co's Foundry
COL'S PIPE FOUNDRY
COL'S IRON CO.
Col's Rolling Mill Co
LITTLE MIAMI
& COLUMBUS
& XENIA R R
Glenwood
Asylum
Idiotic
Asylum
MARTIN
Greenlawn
Cemetery
Calvary

ito a somewhat irregular flat, which, as it nears the river above the luff, in turn again drops into low bottom-lands, subject formerly to uccessive inundations, but guarded now by levees. The premises of he Ohio penitentiary are also situated here.

The river at this point makes a series of curves not much unlike the etter "S," with corresponding bottom-lands in each, subject once s the above to overflows, and now in like manner protected by levees; hile, from a convexity looking east, rises the bluff above-named. Directly across from this latter, on the west side of the stream, spreads ut one of those bottoms, relieved only by a sort of table-like eminence, pon which is situated the old town of Franklinton, founded prior to ie settlement of Columbus; while beyond it, this bottom again makes wide sweep, sinking as it recedes to a lower level, till terminated by a econd elevation, the site of some of the public institutions of the State. etween Franklinton and the levee is Middletown, which places jointly ave a population of about eighteen hundred.

East of the river, again below the city, between the former and the anal, is yet a third bottom, over part of which recent portions of the ity extend.

Marshy places in these regions are now in process of being filled in y the rapid growth of the city, the manufacturing interest of which, iz. rolling-mills, founderies, machine and car shops, extends principally i this direction, with a population mostly of the laboring-classes. From is filling in, however, the construction of railroads, the levees, &c., nd the want of due attention to drainage, numerous cess-pools for the efuse and offal of these parts are left.

The Scioto, moreover, at this point corresponding to the length of the ity, is back-water from the dam, as feeder to the canal from this place, nd is about one hundred yards wide, stagnant, and of some depth, afficient for canal-boats, which it freights. Along its shore open the umerous sewers from the city, and with rare exceptions above water, some owing quite a distance down the declivities, which, together with the lth abounding here, set free a very Pandora's box of noisome exhala- ions infesting these parts.

As to the system of sewerage, it needs to be but further observed that i its construction reference seemed solely to have been had to drainage lone, without regard to sanitary purposes. With few exceptions it con- ists of so many subterraneous channels—laboratories, so to speak—for he conversion of the *débris* of the city into noxious gases, to be again isseminated by every wind or breeze; and as these are usually from he west, with the general course of the sewers counter thereto, it follows hat the city, placed to the leeward of their outlets, with corresponding ulets free to the circulation of air through them, must suffer from what- ver evil may come from this direction, as is evident from facts in con- ection with the late epidemic to be given below.

The water-supply of the city, by means of the Holly system of water- orks, is from the Olentaugy River, a tributary of the Scioto, emptying nto the latter just above the city; though for drinking and culinary pur- oses it is used mostly from wells, from which it is naturally of whole- ome quality, but liable to contamination from sinks and privy-vaults, he contiguity of which, and the nature of the soil, but too often excite uspicion, particularly as the custom has been, when filled, to tap these aults into adjacent reservoirs, in which their contents are buried, or o sink new ones and fill in the old, until some back yards are well-nigh ubsoiled with them.

The city, moreover, being without a sanitarium, no measures upon the

approach of the disease were taken against it; nor upon its a
the municipal authorities awakened to the necessity of pr
and sanitary improvements, contrasting in this respect great
prison authorities, who spared no pains in taking every pre
vised by the physician in charge.

So much for its topography, and such the condition of the
the cholera, on the night of the 4th of July, first made its appe
in the penitentiary, however, as is currently alleged, but near
in one of those low places, and within a few steps of the d
below) into the sewers at this place.

The patient, a large, corpulent woman, aged forty years
time of the fatal malady, presided at the bar of the saloon, w
the occasion of the day just ended, held high carnival, exte
into the night; when her illness set in by copious vomiting a
with cramps, the dejections being of the rice-water kind, f
collapse, attended with the icy tongue, chilled breath, an
wrist, as reported by Dr. R. M. Denig, of this city, whose p
standing guarantees the genuineness of the case.

The second case, that of a female taken seventeen hours
squalid tenement-house a square away from the first, was r
the attending physician the same as the above. Both died
hours.

No doubt, then, as to the nature of the malady and of its d
in the city outside the prison. Yet no precautions were take
jections, without disinfection, were disposed of in the usua
the occupancy of the houses, without renovation, continued;
first case, being Irish Catholics, a wake was kept, attended
of festivity, as is their wont.

But the disease paused now until the 10th of the mont
simultaneously appeared in the prison and with renewed vi
place of its first occurrence.

Meantime heavy rains fell, followed by extreme heat; and
fluxes set in which became general and obstinate in charac
disease now, both in the city and prison, progressed, and in
was confined mostly to the course of the river and the line of
known as the infected district, and which extended also over
of the city spoken of as the flats, which, being without sewe
pendent solely upon surface-drainage, is, in consequence, mar
refuse, animal and vegetable, of these parts in process of deca
cess-pools from causes above given, and about which a si
deaths from cholera was had.

Concerning the *locum primum* of the disease, it needs be
served that, from the inclination in this direction of surround
it forms a sort of basin for the surface-drainage of many squa
it, by means of quite a steep fill and a bridge, passes the ra
beneath the latter the street; and where also, within a radi
fourteen yards, five drops open into the great sewers at this
stench-traps guard these openings, and the place is hemme
slaughter-house, the prison-wall, lumber and coal yards. Ou
dozen families, its sole occupants, eleven persons fell victims
ease; which, with some that recovered, and the circumstanc
if any, escaped more or less diarrhœa, lends the suspicion
sewers and their surroundings, together with the dampness i
from the place, had to do with these results. Besides, as bea
the introduction of the disease, the house in which the initi
curred, contiguous to and overlooked by the railroad, must, i

resume, be constantly within the sphere of influence of whatever contagion passing trains may leave.

The whole number of deaths in the city from cholera, not including those in the Ohio penitentiary, was sixty-nine. Twenty-one of these have already been accounted for, and the rest, with few exceptions, were disposed over the region just named, grouped two or more in tenement-houses, a few on canal-boats, &c., and those beyond these limits were also associated generally with insalubrious surroundings of some kind, as in the city prison, the interior of which, through its sinks, in direct communication with sewers beneath; two inmates were simultaneously taken and transferred to the county infirmary, where they died. The rest of the prisoners were at once liberated, and the place being renovated and disinfected, its occupancy was resumed without further molestation. Some were traced to a prior connection with the disease; several persons that visited the first case took it, one of whom, residing in a remote part of the city, recovered, but was followed in a few days by the death of his child, and so others might be cited.

Thus far reference to the mortality only has been had, as an exponent of the prevalence of the disease, and of the kind of places it sought; the discoveries to the number of forty-eight cases as reported by physicians, may be remarked, seemed less observant of the circumstances of place and the conditions in life, than were the deaths.

As to negative results, from the course of the malady, it may be observed that in Franklinton and Middletown, on the west side of the river, to the windward of the latter, the city proper and its sewers, in a population of about eighteen hundred, not a single case occurred. Nothing peculiar about these places, save that Middletown is on a lower level than any other part within the corporate limits, and that neither it nor Franklinton is provided with sewers; otherwise their sanitary condition compares about with that of the rest of the city. Also the extension of the city *below* the *dam* between the river and the canal, entirely escaped. The sewers here open into the latter, and the former is a free flowing stream.

Nor less notable the impunity with which some of the public institutions escaped. The county infirmary, to which the cases referred to in the city prison, with one other, were taken, is situated on the opposite confines of the city from which the disease prevailed. The building itself, antiquated and about to be condemned, is anything but salubrious; but with a strict regard for hygiene and the free use during the epidemic of disinfectants, viz, carbolic acid and sulphate of iron, with which latter its sinks, sewers, &c., were kept constantly saturated, the disease was confined to the cases brought in from the city; cared for, however, in the pest-house, isolated from the rest of the institution, and all of whom died. But it is worthy of note that, near by, the only cholera-deaths, two in number, that occurred in this part of the city succeeded these cases. So also Saint Francis Hospital, containing over one hundred beds, mostly occupied, received from without several fatal cases, and likewise escaped. And the county jail, with about thirty inmates, at the time wholly escaped. Its sanitary condition is all that can be desired; during the cholera, vegetables were discarded from its dietary.

CHOLERA IN THE OHIO PENITENTIARY.

This institution in its construction and surroundings is unfortunate. Situated on the east bank of the Scioto River, only about 16 feet above its level, it is exposed to the opening of the sewers in this vicinity as well

as to the stagnant condition of the stream and the filth along
The sewer, especially, into which the excrement of over a thou
is daily deposited, its inlet and outlet only about one hundred
five yards apart, and alike free to the circulation of air thro
is peculiarly adapted to the generation and dissemination o
morbi.

The building itself, consisting of stone, is arranged in the fo
edifice within another, the inner one containing the cells.
upon an average, is 7 feet long by 3 feet 4 inches wide, and
inches high, making but 157½ cubic feet to the cell, closed in o
by solid masonry, except its entrance, which is closed by an
ing. These cells, numbering in the male department ten hun
fifty, are built in this solid stone structure within the main edif
ing to the ceiling of the latter, and surrounded by corridors
tier of cells; the only space left between it and the outer build
a passage-way 11 feet wide. From this is obvious the defect i
tilation; without an outlet from the cells, save their entrance
the grating (leaving in the aggregate an available air-space
inches square;) this again, for want of due ventilation betwee
edifice and the exterior building, leaves no practicable means
lation within them, to say nothing of their diminutive size.
this the dampness inseparable from the solid stone structure,
with the exhalations and excretions from so large a body of me
for twelve hours in so small a space, and the nature of the
manifest particularly in hot, sultry weather, is comprehende
cell is provided with a night-bucket of sheet-iron, zincked, with
fitting lid, emptied every morning by men detailed for that pu
the sewer aforesaid and thoroughly disinfected.

The female apartment, separate from the rest, is constru
wholly different plan; is well ventilated, and looks out upon
Its inmates, numbering twenty-five, all escaped the disease
asylum for the insane and incorrigible is a separate edifice;
constructed upon a modern plan, are light and airy; but the
cooped in among other buildings, has not the best ventilation
fifteen inmates, one had cholera.

The hospital, in a different wing of the building from that of
on the second floor, is spacious, but had not the best ventilati
the patients, with the necessary corps of nurses and attendan
common, and the latter, during reliefs, also lodge here; and wh
over, the rations for patients and attendants are prepared an

For drinking and culinary purposes the water used, from
well, is pure and of excellent quality.

As already observed, not until the 10th of July, well-nigh
after its appearance in the city, was cholera announced in th
The intestinal fluxes aforesaid were attributed largely to a 4t
repast, in which many of the convicts evidently too freely i
though the same did not follow a similar occasion this year.

On the above date one case only was had, which, after a se
verses, relapse, &c., in a few weeks entirely recovered. Skippi
the second case, that of a frail body, occurred on the 12th of t
and died in fourteen hours. Until the 20th of the month th
daily exacted its victims, as shown by their chronologic order,
tory and results tabulated below. Thus it is seen that, within
of thirty-one days, twenty-seven cases, with twenty-one dea
had, a rate of mortality sadly at variance with that currently
but which may be accounted for by the malign character of th

id by the wretched cachexy of some of these unfortunate beings, en-ndered by a life of vice and dissipation, and by protracted exposure the damp, foul air of the cells, until the *vis conservatrix naturæ* is well-gh spent.

It is further shown that the diarrhœa was had in twenty-three cases, it it does not follow that in the rest it was absent, since its existence the majority was ascertained by inquiry post mortem, through officers id guards, and the recoveries all had it. As to the time of the attack, will be observed that eight of the cases came on between midnight id 6 a. m., ten between this time and 12 m., four between this hour and p. m., five between this latter, again, and midnight; further, that they me together in batches of as many as seven in a day and five in a renoon.

It was striking to note, also, the influence of heat and moisture. A avy rain with a day's hot sun preceded each installment, while the rmer, without or prior to the latter, as invariably checked it. It is fficult to regard this as a mere coincidence; so striking was it that it gan to be a harbinger of evil, seen in the looks of every one. This oleraphobia rose to a morbid condition with some of the prisoners; it, contrary to the popular notion, no harm seemed to come of it—the id were not the ones taken.

That with the majority the disease approached unawares, is evident om the fact that they were apparently in their usual state of health up the last moment; some ate heartily the meal before—in one case but enty or thirty minutes; others were taken while on duty, or asleep in eir cells; two aver they were awakened by it; in one of whom an fort to pass flatus was attended by a profuse watery dejection.

The insidious diarrhœa that preceded was little apt to awaken suspi-on; for notwithstanding the repeated cautions to report for medicine the earliest intimation of illness, but nine of the cases, just one-third, id so. But that they were not wholly without admonition is evident om the circumstance that *tinnitus aurium*, *muscæ volitantes*, vertigo, c., were common, and, though little regarded at the time, subsequently came vividly fixed in the minds of the survivors as signs of the im-ending malady.

Nor was it less severe in its onset than subtile in its approach; facts o to show that men stricken down at their posts, rendered helpless in a w moments, had to be carried into the hospital; that some fell by the ay, and others came in faint.

The course of the disease is well known, and its malignancy here ttested to by its results. With some it seemed mortal from the start, aralyzing sensibility and rendering indifference to life. One poor retch, reduced by a period of solitary confinement, brought in faint and ulseless, expired without apparently a pang or struggle, and without n evacuation until post mortem, when, upon removing the body, the haracteristic fluid escaped. Others, wasting from every pore, tormented y cramps, thirst, &c., and a dread sense of impending dissolution, re-isted to the last the deadly collapse—a sharp rebuke to those given to oubt the Asiatic feature of the disease, or that other than a severe orm of cholera morbus prevaled. And the examples of post-mortem aloric and muscular contractility, characteristic of violent deaths, urther evinced the nature of the malady. In some instances, no sooner ere the bodies carried to the dead-room than the bearers returned in reathless haste, declaring them still alive, and were with difficulty reconciled by an explanation of the harrowing sight.

CASES CONTRACTED IN THE HOSPITAL.

Whether casual, or resultant from the mingling and contac
disease in the hospital, two of its inmates, a patient and an
took it. The first, a feeble and imbecile old man, died, and a p
examination (superintended by the writer) was made of
the second was taken in twenty-four hours thereafter, b
ered. Others present at the examination escaped with
which the nurses and attendants all had, together with mo
gastric disorders. An officer, Captain C., of the night w
included in the table, who, during the cholera, spent most of
superintending the sick, took the disease, and after a protract
recovered.

MANAGEMENT OF THE DISEASE.

The convicts, averaging at the time nine hundred and thi
which number 10 per cent. were blacks, were, when not on
meals, confined to the cells, as is the custom, except in the fo
Sunday, when religious services are held in the chapel; but d
cholera epidemic, to avoid in the afternoon of the same day
air of the cells, they were distributed through the yard and
entertainment suited to the occasion.

All were required to take a full bath once a week.

Few changes were made in the dietary. Corn-bread, part o
ular prison-ration, was discontinued, and wheat-bread alone us
fresh beef and less cured meat, with warm drink, either of tea
for dinner, except when soup was had. No potatoes were
and a scant supply of hominy were continued; also butter an
and tomatoes used to flavor the soup. In hospital, potatoes, co
mutton, milk, tomatoes, animal broths, &c., were had in addit
above, to be used as prescribed.

Upon the approach of the disease, the premises, always we
were renovated throughout and disinfected without stint. Th
used were the chloride of lime, bromo-chloralum, carbolic acid
phate of iron; the first of which in the hospital was soon ab
for the more eligible combination of the two latter, as directe
Parkes, and without which the buckets and bed-pans w
left, unless for a few moments, to inspect the character of
The defect in the sewer referred to, into which the nigh
were emptied, was in part overcome by the free use of dis
and by keeping its inlet, when not in use, closely covered—co
the 18th of July, with the effect, as the table shows, of directl
the disease, and by the 11th of August completely "stampi
in the prison, while it continued increasing in the city, where it
until the 17th of September, which, together with the circum
its inception and subsequent ravages about the drops into t
spoken of, corroborates the suspicion that the latter had to do
tering the malady.

In the use of medicine, those generally approved were ad
Cases that reported before vomiting set in were given, at once,
gr. ¼ alone, or with calomel and bicarb. soda each gr. x.; and, if
followed directly by plumbi-acetas, gr. iii to gr. iv, in solutio
with acetic acid, but was seldom retained long enough to be app
Under these circumstances, or when vomiting had already co
the morphine was administered hypodermically (gr. ½ to gr. ¼
lead solution, as above, the latter to be repeated every half ho

hile purging continued. Large sinapisms were kept to the abdomen long as could well be borne; and as the temperature declined, warmth as applied by means of blankets and fomenters; perspiration kept ied; and for the cramps, friction was used, and, when severe, chloform by inhalation. To whatever due, in the course of from one to ree hours, the evacuations usually abated, and in some ceased; but ey, it soon became evident, were not the burden of the malady. Pendg collapse, but little it seemed could be done— danger rather of tamering than of doing too little; watch was kept not to carry the opiate o far, and the reckless use of the hypodermic syringe by some cannot too much deprecated. The apparent need of stimulants and fluids emed irresistible. Brandy, largely diluted, was given, but with many as distasteful and excited vomiting. Ice-water was taken with avidity, d was allowed freely, as was also ice melted in the mouth, and no rm seemed to come of them. During extreme collapse, when nothing uld be appropriated, or anything borne, the following from Aitken, ed in the British army, in India, was well received by the stomach, d called for by the sufferers, whom it seemed to exhilarate: R. ol. nis, ol. cajeput, ol. juniper, āā3ss., ether, ʒss., liquor acid halleri, 3ss., ct. cinnam, ʒij. M: Dose fifteen drops in water every fifteen minutes.

As a prophylactic rather than to be used in the course of the disease, hot stimulant mixture was resorted to, consisting of tinct. camphor, in. x., tinct. capsicum, min. xv, whisky, ʒss. at a dose; to be given in e event of threatenings in the way of cramps, faintness, vertigo, &c. s an opiate, the tincture or morphine was sometimes added; and it is ifficult to believe, but in some cases it averted the disease. Other edicines were tried, as lime-water, ipecac, subnitrate of bismuth, sul. ther, spts. ammonia aromat., and tannin with brandy by enema, but ere soon abandoned, as were also the calomel and carb. soda, and reance mainly had upon opiates, the lead, and supportants.

Sul. quinine with aromat. sulph. acid, and opiates with vegetable stringents, were given for the diarrhœas.

Nourishment in the way of animal and farinaceous broths, milk, milk-unch, coffee with milk, &c., were taken as soon as tolerated. Solid od was rejected by some for days.

Sour milk was used by some of the attendants; mentioned, inasmuch a writer, recently, in the Nashville Medical Journal, intimated it to e an exciting cause of the malady.

The kidneys and bladder required attention; all that survive d the ollapse except two, had to be catheterized, and from each quite a quanity of urine was taken; but whether it was secreted since or prior to he attack is questioned; its mere presence in the bladder, is not proof f its recent production.

The origin of cholera *de novo*, in Columbus, will scarcely be claimed. hen, whence and how came it? That it commenced at the place, and ith the case named, is well attested. The habitation being one of ublic resort, frequented by classes whose habits and vocations (railoaders, &c.) render them apt bearers of the disease, its introduction by his means, after being heralded for weeks along the line of travel, is hat might, with the present views in regard to the propagation of the isease, have been *a priori* expected; to say nothing of its possible rigin, as intimated, from the contagion brought by passing trains. The entrance of the disease thence into the prison a week later, through he communication kept up by guards, teamsters, &c., was but a natural result. Besides, the husband of the deceased, up to the time of her lness, was employed as night-watch in some of its shops.

Cholera-epidemic of 1873—*Ohio Penitentiary, Columbus, Franklin Coun*

Case.	Age.	Date of attack.	Date of death.	Remarks.
1	29	July 10—11 a. m.....	.....	Recovered; able-bodied; diarrh medicine; vertigo; muscæ volit sense of gastric oppression; col
2	51	July 12—3 a. m.....	July 12—5 p. m.....	Invalid for years; greatly emacia
3	58	July 13—12 m.....	July 14—1.45 a. m...	Debilitated; frail; life-convict; h years.
4	32	July 14—11 a. m.....	.....	Recovered; able-bodied; noted fo pertinacity; had slight diarrhœ borborygmus, followed by pain domea giving way; tinnitus au
5	28	July 14—11 a. m.....	July 17—7.30 a. m...	Robust, but fidgety; diarrhœa; h a few months; syncope; carrie
6	38	July 16—5 a. m.....	July 16—3.30 p. m...	Able-bodied; no characteristic ev post-mortem; medicine.
7	33	July 16—8 a. m.....	July 16—8 p. m.....	Able-bodied; diarrhœa; tinnitu tigo; cramps; vomiting.
8	33	July 16—8.30 a. m...	July 16—6 p. m.....	Able-bodied; diarrhœa; medici hospital.
9	22	July 16—8 30 a. m...	July 16—8.45 p. m...	Able-bodied; diarrhœa; gormand to hospital.
10	42	July 16—12.45 p. m..	July 16—9.45 p. m...	Somewhat feeble; diarrhœa; gas icine.
11	74	July 16—2.30 p. m...	July 16—11 p. m.....	Frail; imbecile; diarrhœa; life-
12	28	July 16—2 p. m.....	July 17—10.40 a. m..	Debilitated; diarrhœa; in dang for incorrigibility; carried to ho
13	45	July 17—1.30 a. m...	July 18—6.30 p. m...	Able-bodied; diarrhœa; had inco dejection.
14	58	July 17—7.30 p. m...	July 18—6.15 a. m ..	Able-bodied; diarrhœa; an effor attended by watery dejections; pital.
15	22	July 17—2 p. m.....	.....	Recovered; vigorous; quick, nerv vertigo; awakened by borbor way to hospital; left with gast
16	34	July 18—2.30 a. m...	July 19—11 a. m.....	Feeble; fidgety; diarrhœa; med
17	44	July 18—4 a. m.....	July 18—10 a. m.....	Able-bodied; diarrhœa; night-b copious rice-water stools; carri
18	59	July 18—1.30 p. m...	July 18—6.30 a. m...	Feeble.
19	28	July 18—10.30 p. m..	July 22—12.50 a. m..	Able-bodied; diarrhœa; medicin Aitken's vomiting of "green-pa ter."
20	28	July 19—12 m.....	July 19—11.15 p. m..	Able-bodied; diarrhœa; came to
21	43	July 19—6 p. m.....	.....	Recovered; lacked in vigor; diar one week; muscæ volitantes;
22	21	July 24—11 a. m.....	July 25—6.30 p. m...	Insane, but able-bodied.
23	63	July 24—9 p. m.....	July 26—3.15 a. m...	Feeble; diarrhœa; medicine; fa
24	37	Aug. 1—4.30 a. m...	Aug. 1—5 p. m.....	Able-bodied; diarrhœa; had cho
25	67	Aug. 6—4 a. m.....	Aug. 8—3.30 a. m...	Frail; imbecile; diarrhœa; life- annuated; was singularly void pain or suffering of any kind.
26	36	Aug. 9—7 a. m.....	.....	Recovered; able-bodied; painle no cramps; medicine; commen ing.
27	27	Aug. 11—12 m.....	.....	Recovered; able-bodied; diarrh tendant; attended post-mortem a cholera-case the day before.

NOTE 1.—The above cases were all white male convicts.

NOTE 2.—Of the six cases marked "Recovered," No. 1 was under treatment about th 4, one week; No. 15, three weeks; No. 21, one week; No. 26, three days, and No. 27 length of time.

NOTE 3.—The remarks refer to the cases prior to or at the onset of the attack, exce being sequelæ.

NOTE 4.—The immediate cause of death in case No. 5 was uræmia.

NOTE 5.—Case No. 25 had atrophy of encephalon, as revealed by post-mortem examin

SCIOTO COUNTY.

Portsmouth, the county-town of Scioto County, is located banks of the Ohio River, above the mouth of the Scioto, and let of the Ohio and Erie Canal, one hundred and fifteen m Cincinnati. This town is also the terminus of the Scioto an Valley Railroad.

On the 20th of July, two men, named Erght and Noel, Portsmouth upon a river steamboat from the city of Cinci both the disease was developed before reaching the city;

minated fatally, that of Erght after five hours' illness, that of Noel er ten hours'. But one other case occurred, that of a little girl seven ars of age, who had been at the house at which one of these men had en cared for. This child was taken on July 26, and died after an ness of ten h ours.

IRFIELD COUNTY.

IOLERA AT LANCASTER, FAIRFIELD COUNTY, OHIO, IN 1873.

By Dr. D. N. Kinsman, *Health-Officer.*

Lancaster is a city of six thousand inhabitants. Along its western d southern borders flows the Hockhocking River, through a marshy il, on a line inside of the river, close to the city; and, indeed, in its nits for more than a mile and a half is the Hocking Canal.

On the north and west of the city is a large extent of land, which has ver been drained; and on the south, although the land is under culture, is often overflowed, and remains damp and swampy during rainy asons.

The geological foundation of this section is the Waverly sandstone, erlaid by a limestone drift. The hills surrounding the city rise to a ight of 300 feet; the banks of the water-courses are abrupt, and the chan-ls are narrow; as a result this section of the country is subject to very dden rises of water. On the 4th of July, 1873, one of the most disas-ous floods ever known in the valley occurred. All the bottoms were over-wed, and thousands of acres were covered with water from one to six et in depth, and upon the subsidence of the waters were covered with getable and animal substances; this matter under the action of the n decomposed, and filled the air of town and country with a stench, hich in some localities was terrible.

In the center of the town is a hill, upon the top and sides of which obably one-fourth of the population resides. The wells on this hill are om 40 to 80 feet in depth; on the low land around the base of the hill ater is reached at a depth of from 12 to 15 feet. The water is strongly mpregnated with lime, and wells are the source of all the potable water xcept in a few families who use filtered rain-water.

The western portion of the town along the canal has been the longest nhabited. The houses are thick, and the soil, from the presence of tables, privies, and out-houses, reeks with filth. The dashing rains of ummer wash the hill-side, carrying all its filth to the base of the hill, here it remains on the level of the greater portion of the town. There s no sewerage in the city, except in the northern portion; all the rest has urface drainage. Hogs are allowed to run at large; although they are o a certain extent scavengers, they are harmful in the total. A few lays after the flood, diarrhœal diseases began to prevail, and from the 5th of July until the 1st of September cholera morbus and cholera in-antum might almost be said to be epidemic. The type of the disease was evere but not fatal.

Six cases were treated, which had all the characteristics of cholera as-phyxia. Four of these occurred in the western part of the town, on the canal ank. Three were in one family, all of whom were seized within twenty-our hours. Another case, living on the same street was sick a few days ater. The fifth case was in the person of the yard-master of the Cin-

cinnati and Muskingum Valley Railroad. The sixth was in of the wife of a beer-saloon keeper. All these cases had dia iting, vox cholerica, and collapse. In two cases the urin pressed. In one delirium lasted for three days after reactio lished.

It was impossible to trace any contact with persons who ease, or those who had come from a distance where the chol vailing. The filthy locality in which the patients lived, th contamination of their drinking-water, heat, and close, ill sleeping-rooms, are accepted as sufficient factors for the dev the disease.

CLEVELAND, OHIO.

It having been noted in the Cleveland Plaindealer that month of July, 1873, two cases of Asiatic cholera had been the health-office, as having occurred on Mulberry street of communication was addressed to the health-officer, which w by the following letter:

"CITY OF CLEVELAND,
"OFFICE OF THE BOARD OF HE
"*Cleveland, July*

"DEAR SIR: Your favor of July 27 at hand. in reply, erferred to our people were fearful that the cholera would re sequently the cases you refer to were hastily reported unde ment as cholera; but upon mature investigation as to the h patients and progress of the disease, it was decided that n died from Asiatic cholera.

"Very respectfully,

"H. W. KITCH

"Dr. ELY MCCLELLAN."

STEUBENVILLE, OHIO.

A dispatch to the Louisville Courier-Journal, June 19, that a man named Stephenson, who arrived at Steubenvil cinnati on the 18th of the month, had been taken sick, and a few hours of cholera.

Upon investigation this report was found to be utterly and to have been circulated for the sake of notoriety. The m son did arrive at the time stated from Cincinnati, where he an excessive debauch. After his arrival at Steubenville he to have eaten immoderately of cherries, and died of acute bus. No other cases of the same or of an assimilating disea in the city.

The above facts are determined upon consultation with who was in 1873 the health-officer of Steubenville, and wit ston, a prominent physician of the city.

CHAPTER XIII.

SDIANA GROUP.

INDIANA CONTRIBUTORS.

r. H. G. Jones, health-officer, Evansville.
r. G. B. Walker, Evansville.
r. B. J. Day, Evansville.
r. J. W. Kyle, Jennings Co.
r. J. A. Scudder, Daviess Co.
r. James Lamb, Dearborn Co.
r. R. C. Bond, Dearborn County.
r. J. W. Culley, Hendricks Co.
r. Morrell, Vigo County.
r. J. B. Armstrong, Vigo County.
Dr. S. H. Pearse, Posey County.
Dr. J. B. Weever, Posey County.
Dr. E. V. Spencer, Posey County.
Dr. M. S. Blount, Posey County.
Dr. W. F. Collins, Marion Co.
Dr. J. M. Darrach, Marion Co.
Dr. S. Record, Marion County.
Dr. T. Parvin, Marion County.
Dr. E. Reed, Vigo County.
Dr. S. J. Young, Vigo County.
Dr. J. W. Thompson, Vigo Co.

Dr. P. H. Bailhache, Surgeon Marine Hospital service.

INITIAL CASES.

lount Vernon, Posey County ..... May 27.
vansville, Vanderburgh County ..... June 5.
ndianapolis, Marion County ..... July 2.
orth Vernon, Jennings County ..... July 10.
erre Haute, Vigo County ..... July 16.
urora, Dearborn County ..... July 27.
izton, Hendricks County ..... August 1.
Vashington, Daviess County ..... August 11.

Posey County.

Mount Vernon, the county town of Posey County, is locate
banks of the Ohio River, about two hundred miles below
Ky. The town has a population of about three thousand i
At this town and in its vicinity the cholera-epidemic o
characterized by its malignancy. The history of this demo
embraced in the following papers:

I.—EPIDEMIC OF CHOLERA AT MOUNT VERNON, 1873.

By S. H. Pearse, M. D.

The subject of cholera has at various times within the la
tury occupied the minds of some of the most eminent phys
various theories have been advocated, and again abandone
ones equally as erroneous as the first. That cholera is a dise
of being carried from place to place, it seems, there is no lon
doubt. The excreta from the body of a cholera patient see
tain some specific poison that can be transported any distan
duce the disease in any given locality, unless everything pe
said patient is most thoroughly disinfected. The beds upo
patient has lain, all the curtains, and everything in and
room, together with the excreta of the body, should be
Taking this view of the subject, we propose to give some of
of cholera in Mount Vernon, Ind., during the epidemic of 187
it came here, and the course pursued by it previous to its br
in an epidemic form.

The location of the town of Mount Vernon is upon a bluff,
highest points on the Ohio River between Louisville and C
town has a population of about four thousand; the river-ba
feet above high-water mark, the ground ascending gradually
the river until in the northern outskirts quite an elevation is

East of the town there is a large extent of level farming-la
a good state of cultivation. This is really a second bottom.
accompanying this paper shows the line of the bluff, and al
of hills, or rolling lands. The river-bottom is shown as
lands, which are extensively cultivated. West of the town,
on the river, there are no overflowed lands, but the lands are
short distance from the river the lands are rolling and v
North of the town the lands are high and rolling, with exten
under good cultivation. South of the town and bordering o
are low lands; this is a large overflowed bottom, reaching se
up and down the river. The natural drainage of the town is
although it has no sewerage. The town being thus situated,
airy, and clean, with natural surface-drainage, leaving no
breeding pestilence, and the general health at that time being
good, there seems to have been no cause for alarm, even when
an established fact that cholera had made its appearance, an
aging towns and cities in our sister State, Kentucky, bor
Ohio River. The sanitary condition of the town was good, a
became known that cholera was approaching, most of our p
exceedingly careful in their diet, and watchful as to cleanlin


Range 14 West
Range 13 West
Town 6 South
Town 7 South
Rolling cultivated lands.
4th Level
Flat
Terrace
Map of
Mt. Vernon, Ind.
and vicinity
Showing the localities
of Cholera cases in the
Epidemic of 1873.
Localities of cases are indicated by
a small square surrounded by a circle
Ohio River
Flat level lands
not subject to overflow.
Comparatively small
drainage area south.

eard of the epidemic now under consideration, prevailing at
nts on the Mississippi River, it being the most violent at
Tenn. One of our citizens fell a victim to it there. His
partner went there to bring the body home. His body was
oard the steamer Pat Rodgers, and brought to Mount Ver-
it arrived on the 26th day of May. It was taken to the
f another brother, Mr. F. C. Decker, who had the casket
then buried on the same day. The night following, the
went to Memphis was taken with a severe diarrhœa, which
nced by the attending physician, Dr. E. V. Spencer, to be

ree days after this event, Mr. F. C. Decker had three chil-
he same character of disease, and but a few days elapsed
ld on the same block, immediately in the rear of Decker's,
nd died.
s after the death of the child just mentioned a second, and
rd, in the same house, took sick and died, each of the same
disease.
e about the 20th day of May (the exact date I am unable to
eamboat, the Eddyville, from Nashville, Tenn., landed to
about three miles above the city. While loading, a family
the landing visited the boat. The landing and the house
amily resided is in section 23, township 7 south, range 13
n on map.) In a day or two the man, Mr. Russel, who had
rd the Eddieville, was taken with a severe diarrhœa, but re-
is wife was taken sick and was moved to her father's, Mr.
s, who lived in section 36, township 6, range 13 west, near
f the section. Mrs. Russel was sick for several days, was
he neighbors, who talked among themselves that "this looks
." Time passed from day to day until the morning of June
Cully, the father, was taken sick, and died the same night.
an by the name of Pickles, who was at work on a farm near
ed there every day to inquire how they were getting along.
been feeling well for two or three days, and on June 7, in
g, he came to Mount Vernon for medicine, was taken ill about
. m., and died at 7 o'clock p. m. of the same day.
hat night and the next day several severe cases of choleraic
ecurred at the hotel where he died, but none fatal. On the
lowing, the mother of the young man had an attack of chol-
ne near dying, but recovered. Following this a German lady,
lm, washed the bedding, &c., for Mrs. Pickles. She took
ed. Mrs. Alsted, who helped to take care of her, was taken
ed.
nel and wife, who were at Alsted's, both died of the disease.
Koonce helped to bury Mr. Himmel and his wife. He was
and died, as did also a daughter of his.
es all occurred in rapid succession, and none but Mr. Koonce
few hours after the attack. From this neighborhood the
taken across the country some twelve miles, where there
l cases. It occurred in this way: When Mrs. Schwalm died,
d's father came over, and to make the children more com-
took the feather-bed upon which Mrs. S. died, put it into a
the children on it, and took them to his house. A few
ing this the children, the old man, and his family were all
with cholera, and nearly all died. In the city, for some days
eath of Pickles, there were no fatal cases; but during this

period fresh poison was constantly being brought to us fro
Nashville, and other points, in the following manner: Ste
our western rivers carry all kinds of freight and a great m
gers. Some of these passengers are in the cabin and some
and the deck-passengers and the deck-hands have their qua
engine-room, where they eat and sleep, and are much of th
around on piles of freight, and frequently on the bare deck.

At that time nearly all the boats on the river had more o
of cholera on board.

On May 26, the steamboat Pat Rodgers, from Memphis, T
at our wharf, having cholera on board. The steamboat Arl
26, landed and discharged a large lot of freight. May 30, th
Mary Houston landed and put off freight; she had choler
On the 26th of May the steamboat R. E. Lee was here, and ag
at our wharf on the 10th of June. The steamboat Henry P
here on the 6th of June. The steamboat James D. Parker
on the 22d of June, all on board sick except the captai
Then there were the regular packets stopping every day,
and coming up the river, with cholera-cases on board most
On the 21st of July the steamboat Camelia brought from
Tenn., a gang of negroes to work at the Grand Chain, (a
work on the Wabash River.) One of those negroes died a
boat of cholera on arrival. A few days afterward another
came over from the Grand Chain, was taken sick, and died
disease. So, from this, it can be readily seen that the s
poison was being constantly supplied from abroad. The dis
veloped gradually, occasional cases occurring from the 7th o
about the 1st of July, when it began to assume an epidemi
very malignant type. There were several cases in rapid
when after about one week there seemed to be a cessat
hoped it had passed by; but we were disappointed.

About the 12th it began to rage in all its fury, very viole
tinued, until the people became panic-stricken, and were th
act upon the advice of some of the physicians, to scatter,
main in the infected district. Had this advice been heed
sooner, without doubt it would have saved the lives of very

About the 18th of July the disease reached its climax,
occurring on that day than on any other; and for some fiv
lowing it gradually decreased in the number of cases.

From the 20th day of July, the city did not contain mor
third the inhabitants that were here previously. They left t
directions, some going but a few miles into the country, w
went to their friends in other States. One of our citize
here on the 18th, was a dairy-man who had visited a
the town twice a day, delivering milk to his customers, fr
mencement of the disease. He started with his family for
Ohio, was taken sick while *en route*, and died just after his a

There were some others who were taken sick after leavin
this was the only death.

The disease prevailed to a great extent in the level parts
where the drainage was the poorest, or, at least, where the
was made by the families to keep their premises clean and

There were a few cases up on the high ground, but they
able, and the first parties attacked came with the cholera fully
The first case on the extreme high part of the city was a yo
the name of Woody. He had been on the river, came hom

n run on for some days, when genuine cholera ensued. He
g at his brother's. His brother's family consisted of him-
ife's sister, and four children, one a babe. The young man
bout forty-eight hours' sickness, and was buried the same
died.
ns attending the funeral from this brother's, together with
an's mother and two sisters, who each lived one mile in the
the high ground, were nearly all taken down with cholera.
day after young Woody died, a young man, who lived in
, and who had assisted in taking care of him, went home
t a few hours, dying of cholera in a malignant form.
after young Woody's death his brother's wife was taken
ed, as also two children, the babe living less than three

e all taken on the morning of July 17, and at noon two were
e wife died about 5 o'clock p. m. On the 18th, the mother
ter, living as before mentioned, were taken, and in a few
her and two other sisters were taken down, and all died,
deaths in this family, which were directly traceable to the
having been taken sick there. Besides these, there were
r other cases that were very bad but recovered.
ne manner some other cases might be traced from some par-
y. But, it seems to me, enough has already been said to
sively that it is communicable from one person to another,
ily to family, as the case may be.
e prevalence of the disease in this locality, the medical pro-
too much occupied to give the subject that close observa-
t demanded, as to its contagious or infectious nature. But
are all agreed in this: that it is communicable from one to
l that very much can be done to check its progress and de-
culiar poisonous properties, whatever they may be.
treatment, we have nothing new to advance, as the treat-
es here was very much the same as advocated by our best
revious epidemics.
e could be summed up as alterative and stimulating.
rhœa was usually treated by giving pill. hydrg. and pulv.
metimes ipecacuanha. After an action of the liver had been
ringents were used.

EMIC OF CHOLERA AT MOUNT VERNON, IND., IN 1873.

By E. V. Spencer, M. D.

he summer and fall of 1872, dysentery prevailed to a consid-
nt. Whe had, also, our average amount of sickness of the
cter, but all cases seemed to have a more irritable condition
ach and bowels than common, and this condition has con-
to this time, slowly and gradually passing away since the
f the cholera. The condition of the air and our physical
eemed ready for an explosion, and all that was necessary
k to ignite it; and this occurred on or about the 20th
73, by the remains of a person who had died of cholera in
Tenn., being brought here for interment; also by persons
infected steamers from Nashville and Memphis, Tenn.
s nothing unusual about the season, except very heavy rains

about the time the disease was introduced among us. was rather cooler than common during the entire prevalen demic. It prevailed in the same localities it had in pre tions—the second bottom, level, with rich, alluvial soil, with subsoil. The inhabitants almost invariably used well-wa wells were nearly full to the surface with a very impure wa cholera broke out, there seemed no appreciable difference epidemic of 1873 and previous visitations of cholera that nessed here, unless in the latter being more general. Th peculiarities of the latter that did not attach with equal former. When it broke out we were having vernal inter usual in this locality, occasionally a case of typhoid fever, elas, diarrhœa, and occasionally a case of mild dysentery. introduction of cholera, fevers diminished in numbers, and at its worst, nothing else seemed to prevail; it absorbed up other complaint, and, as the epidemic abated, the usual turned. The attack was almost invariably preceded by a p rhœa. In some instances obstinate dyspeptic symptoms we Borborygmi preceded the onslaught of the disease in nearly in fact, every one suffered more or less with uneasiness an of the bowels. In a majority of the cases the disease made ance in the latter part of the night, ushered in by nause diarrhœa, labored breathing, cramps, pulse increased in fre weak, great thirst, mind much disturbed, great anxiety; th soon passed away, and if the disease passed on into collapse, manifested a dogged indifference to life. In some cases no isted, the patient passing on to a speedy death, without the muscle. The intellect remained clear to the last, except in where a suppression of urine existed for a considerable time; became comatose. The severe cases were, hoarse talking, a within the chest. The cramps were very painful, making cry out. After the first dejections, which were generally became rice-water in appearance; and after the continuance ease for a brief period, there was no appreciable difference dejections from the stomach and bowels. The urinary secre suspended, as well as that of the liver. In cholerine the poi less force upon the system. Fever light; furred tongue; pa ness of the bowels, nausea, mucus discharges from bowel sionally bloody, but little or no bile discharged. These we cipal symptoms of the disease, which was quite manageable the disease as essentially contagious, as can be clearly p spread during its prevalence among us. It seemed also gated by getting into the water, from the dejections of chol being thrown into privy-vaults, and thus the wells becam nated. It is generally believed here that few had cholera exclusively cistern-water. The treatment I adopted depend upon the stage of the disease.

First. I insisted on the patient going to bed, and permit her under no circumstances to get up. The horizontal essential to a cure. Early in the disease opiates and tants were the remedies. Mustard cataplasms to epigast men, and over kidneys; one-half grain of morphine put upon and allowed to dissolve, or ½ to ⅓ grain hypodermically injec iting existed; or a teaspoonful of a mixture composed of eq tinct. opium, tinct. camphor, and peppermint essence, after tion; bits of ice to hold in the mouth. This treatment con

was relieved, or passed on into collapse. In some instances Nichol's vesicating fluid to epigastrium to check vomiting; as accomplished, if the patient was not in collapse, I gave nuth, morphine, act. plumbi, and hyd. cum creta, and con- with an occasional dose of castor-oil and spirits of turpen- i pulv. in aromat. sirup of rhei, until the secretions were Great care was required in diet. If the case emerged into dicine appeared to have but little influence; friction and ants were used upon the extremities; ice given freely; e stomach would tolerate them; mercurials, and, if neces- gents, to prevent running off. Neither opiates nor alcoholic were prescribed. In my report will be found a Sally Rapier, ed 22. This was the only case of recovery from collapse ng the entire epidemic. I know of no satisfactory treat- is stage of the disease. I may here remark that in every t was possible I caused the dejections to be disinfected. I parties to avoid, as far as consistent, encountering or coming ith the disease, and when it became epidemic in the city, I who could to leave, and am confident that to this more than gency is to be attributed the cessation of the disease. The mmenced the last of May. I labored night and day in it up The hardships attendant upon this protracted epidemic ined my health, so that I was totally disabled; constant nd frequent vomitings, obstinate dyspeptic symptoms, &c., imperative for me to get out of the contaminated atmos- nperate. I left on the 18th of July; after which there were twelve cases in the city.

GH COUNTY.

MIC CHOLERA OF 1873 AT EVANSVILLE, IND.

By H. G. Jones, M. D., *Health Officer.*

e, Ind., is situated on the Ohio River, about two hundred miles uth, and contains a population of about thirty-five thousand

au upon which the city is built is elevated several feet water mark. This plateau extends back several miles, when gradually becomes more elevated and rolling. Immediately about three miles below the corporate limits of the city, the low, and is inundated with every considerable rise of the e low lands are interspersed with numerous bayous and which stands more or less stagnent water during the hot he summer season. The soil is very rich and productive; large crop of vegetation that annually dies and decomposes gnant waters. During the earlier history of these lands -fever prevailed to some considerable extent during the nonths of each year; but recently, since the country has l up and cultivated, (or at least such parts that can be culti- inhabitants are as free from malarial troubles as any country rtility of soil in the world—notwithstanding but little has to drain these sloughs and ponds, which cover nearly as ea as they did a half century ago.

es of the city of Evansville are bounded by running water. system of sewerage has been adopted—emptying for the

most part into the Ohio River—that carries off the rain- surplus water from domestic and manufacturing establis specialty is made of keeping the streets and alleys clea manures, garbage, &c. During the past year, and, indeed years past, the actual mortality of Evansville has been bu one-half, in proportion to its population, that of the great York.

For the past fifteen years no contagious or epidemic di prevailed in the city, save once or twice a few cases of s whooping-cough.

Thus were we situated, with a good system of sewerage and streets in a good condition, the city clean and the healthy, when a New Orleans steamer, the John Kilgore, on the river, left at one of our wharf-boats a deck-hand, in state of cholera. It was stated that the man had had di symptoms of cholera for several days before he was left a boat, and that several cases had occurred on the steamer on Cholera was prevailing at New Orleans at this time. Med called to the man, and every effort made to save him, but he died in a few hours.

In the course of two or three days another deck-hand wa wharf by a New Orleans steamer; he was also in a coll of cholera, and died in a few hours, in despite every effort

These cases called forth redoubled diligence from the boa which was most heartily indorsed by our worthy mayor (But the common-council. Disinfectants were freely used, at and earnest entreaty; every inlet into every sewer was th of considerable quantities of coal-tar or some disinfectant, and sewers were flooded day after day, and every sanita adopted that could be devised to prevent the introduction of cholera. The seed, however, was sown, the disease was i and we battled with it day by day, as best we could, until it out.

These two imported cases referred to occurred about the Before these no cholera or cholera symptoms had been obse of our physicians.

The first case that was reported to occur in the city was day of June. This case proved fatal in twenty-four hours. learn whether any communication had occurred between thi ported case; but he was a drayman, and his business and cal to the river and in and about the wharf-boats, where the im had been landed, and where they remained for some time. to the 12th of the month several cases were reported, mo recovered.

On the 12th, a man in the employ of one of the railroad was attacked with cholera. His boarding-house and place o a mile or more distant from the river and place where the occurred. However, he was a stranger, only a few days in t his family were not here. The probabilities are that he had river and wharf-boat, or may have been brought in contact patients, or patients with cholera symptoms, and he not hav scious of it or cared about it.

The only irregularity that I could hear of was that he had ing water, while at work, that had become stagnant by stand eral days in the tank of an idle locomotive tender. This ca

and proved fatal in eleven hours from the first attack. No
ccurred in the house where this man died.
nother case occurred, in which the patient was collapsed in
half hours and died in nine hours. No other case occurred
.
18th several cases occurred in different parts of the city, but
. On the 18th three cases occurred in one house; the one
d died in thirteen hours; the other two cases recovered.
, one case proved fatal; also, on the 20th one died; on the
and two recovered; on the 23d two died and one recovered;
one recovered; on the 27th two died; on the 28th one died,
0th three died.
cases were reported, both of which recovered; on the 3d
one recovered; on the 7th one died; on the 12th one died;
one died; on the 17th two died; on the 20th three died
vered; on the 22d two died; on the 23d two died and one
n the 28th one recovered; on the 30th two recovered.
one recovered; August 3, one died; August 4, one died
vered.
brief summary of the cases of cholera that occurred in
1873. The greatest amount of mortality occurred in July,
h the disease certainly assumed a malignant type. Four
red, in some cases in from three to six hours. But it must
ed that it was not until several cases had occurred that the
be made to understand the importance of strict sanitary
ing adopted; but as soon as that was acquiesced in and
eaded to the disease disappeared from our midst, notwith-
as raging with such fearful virulence in other places, where
anitary measures had not been adopted.
n the case go to show—first, that the first cases were im-
, secondly, that as soon as proper sanitary measures were
generally employed the disease disappeared.

UNTY.

OLERA EPIDEMIC AT INDIANAPOLIS, IND.

. BAILHACHE, M. D., *Surgeon United States Marine Hospital Service.*

lis, the capital of the State of Indiana, is located upon the
White River, at the crossing of the old National Road.
a population of nearly fifty thousand inhabitants, and is
ost flourishing of the cities of the West.
lis is a railroad-center of great importance; no less than
lines crossing or terminating at this point. A constant
avel, therefore, flows through the limits of the city.
ase in the cholera epidemic of 1873, at this point, which
d, occurred on the 2d day of July in the person of William
Hensley was a bar-keeper in the restaurant of Mr. Samuel
hich is located directly across the street from the Union
ailroad Depot; and this restaurant is much frequented by
sing through the city. Hensley's disease was at first pro-
e cholera morbus; but after a careful examination was diag-
a Asiatica by Dr. Sutcliffe, who had charge of the case.
day (July 3) Mr. Moran, while sitting upon a chair at his

restaurant, suddenly felt himself to be fainting, and fell upo purging and vomiting.

Both of these men recovered after a hard fight and a m convalescence.

Several cases, similar in every respect, occurred in this vici the next few days; and on the 7th day of July a fatal ca within a short distance of the Union depot, that presented a acteristics of epidemic cholera. This was eighteen days pre first case recognized by the board of health. Before these cas at Indianapolis, cholera was epidemic at many places that wer hourly communication with that city, and the disease was n introduced by some traveler or travelers who ate or drank restaurant.

East and south of the Union depot is a flat, that is known ley of Pogue's Creek. This creek serves as a drain for the southern portions of the city. Through this valley the majo railroad lines pass, and to this valley the epidemic was al sively confined.

On the 25th of July, the first case occurred that attra attention. The subject was the son of a man named Bu lived on Pogue Creek flat, at a point on Winston street tha to overflow from the creek and from washings of the surrou ground and streets. The house was a one-story frame, low The well upon the premises had been bricked up, but was no and was invariably filled after rains with surface-washings. who occupied the premises, previous to the Bucksots, h daughter, who empted slops and night-vessels out the back cent to the well, and where a natural declination carried th matter immediately into that reservoir. The well was not cl after the outbreak of cholera.

Directly opposite this house was a railroad round-house, and freight depot.

Bucksot's family belonged to the hard-working class of Ge were ordinarily cleanly about their premises.

The first case proved fatal after an illness of twelve h other cases, all of which proved fatal, occurred in this family next few days, and the disease rapidly spread to other habi is reported that 104 cases of the disease occurred, with forty-e

LOUISVILLE, KY., February 18, 1875.

In the Indiana Journal of Medicine, of June, 1874, the ed M. Stevens, publishes a report made to the board of health apolis, relating to the epidemic, in which he states:

"There is no doubt that the disease, call it by what na would have been more general in its appearance, and mor had not been for the efficient means used by our health-off case as it presented. From personal knowledge, we can te indefatigable exertions of the board of health. The mea were the disinfection of the premises by means of carbolic ac of lime, and a solution of the sulphate of iron. The patien lated, and, where convalescence or death was the result, t together with the bed-clothing, &c., were either destroyed by oughly disinfected. A local quarantine was established abo the infected premises, and in such ways the disease was e stamped out. It is very true that, in some of the cases, mo work could have been done had the health-officers possessed

heir regulations in a manner as they were well aware they been; and especially could there have been better measures vent the further spread of the disease if such power had been em. May the time soon come when to a proper set of health- e shall be given adequate power to enforce any necessary gulations for the prevention of disease."

ianapolis, cholera was conveyed to other portions of Marion most important of which is found to be at Cumberland, a en miles east of the city and upon the line of railroad. The his demonstration will be found embraced in the following ions:

CUMBERLAND, IND., *December* 8, 1874.

rgeon ELY MCCLELLAN, U. S. A.:

cholera made its appearance here about the 8th of August, first case was a German woman, about forty years of age, l having four children. This case was fatal, after an illness ours. The funeral was largely attended.

mic seemed to spread from this case. About five days after tendance upon fifteen cases, all of whom had attended Eight of these cases died. I treated, in all, eighty cases, irty-two were fatal. Ten of the fatal cases could not be ther cases. The epidemic commenced about the 8th day prevailed with severity for about five weeks, when, on the a slight frost, it suddenly subsided. All the cases occurred rea of four miles, comprising a rich, level country, with a ubstrata, and yielding good water. A large proportion of ked were healthy. There were no local influences which avor the spread of the disease. Those who lived twelve an attack generally got well. The treatment adopted was narcotics, and tonics, with hot external applications over rface of the body.

WM. F. COLLINS, M. D.

LAWRENCE, MARION COUNTY, INDIANA.
February 8, 1875.

rgeon ELY MCCLELLAN, U. S. A.:

nswer to your inquiries as to my first case of cholera, I will se as closely as is possible.

artman, a German, came to me on the 17th of August, 1873, for his wife; said she had diarrhœa. I heard no more from until the 20th, a lapse of three days, when I was called in to see her. Arrived at her house about 4 o'clock p. m.; t purging rice-water and vomiting incessantly. Extremities feeble; skin of a leaden color. I thought at first that it of pernicious fever. I made a fruitless attempt to get up d the patient died at 7 o'clock p. m., three hours from the saw her.

onfident that it was a case of cholera that I commenced uiry, and learned that Mrs. Hartman had attended the young child that had been taken from the city of Indianap- he following circumstances: Some time in the month of July,

a family named Bucksot were suddenly attacked with ch
mother and four children died, leaving only one young ch
father of the family alive. The father took this child to t
eight miles east of the city, to the house of a man named
brother of the husband of my first-described patient. This
within a few days of the same disease, and was the case wh
Mrs. Hartman had attended a few days prior to her illness.

On the 24th, four days after Mrs. Hartman's death, I wa
see her two sons, one twelve and the other fifteen years o
them very severely attacked with purging, vomiting, and cr
youngest recovered; the eldest died; the remainder of the
father and an infant, remained well.

At the funeral of Mrs. Hartman there was a general gath
friends of the family. The lid was taken from the coffin
funeral, and two old men, Swear and Wessling, stood by the
coffin for some time. By the next evening they were both
cholera.

The third case after the funeral of Mrs. H. was a Mrs. I
nursed Mrs. H. This case terminated fatally. Before Mr
her daughter was taken with cholera, but recovered. Mr. B.
with cholera at his wife's funeral, and died; and other cases
rapid succession.

In this community forty-four cases of cholera occurred, w
four deaths.

The area of infection covered a space of about from two
to three miles. A thickly-settled country; mostly German
livers; well-to-do farmers. The locality is well drained, and
as any portion of Marion County.

S. RECORD

JENNINGS COUNTY.

North Vernon, the county-town of Jennings County, is loc
Madison and Indianapolis Railroad, at the crossing of the
Mississippi Road. From this point the Louisville division
named railroad branches off to the southwest.

North Vernon has a population of about two thousand in
The town is seventy-three miles southwest of Cincinnati, and
miles northeast of Louisville; with both of these cities it is
communication.

At this town the first case of cholera in the epidemic of 187
on the 10th of July, in the person of a night-watchman at t
ger railroad depot. This case was followed by five other ca
persons of individuals who had been in contact with him
case alone was fatal.

We are informed by Dr. James W. Kyle that, previous to
rence of the disease at North Vernon, several cases of choler
to his notice in persons traveling upon railroad trains as t
through the town.

VIGO COUNTY.

Terre Haute is a flourishing city of about seventeen thousa
ants, located upon the banks of the Wabash River, seventy-
west of Indianapolis. The bluff upon which the city is built
about 60 feet above the river. The soil upon which the city
light, dry sand. The drainage is most admirable. The Terre
Indianapolis; the Terre Haute, Alton and Saint Louis; and

awfordsville Railroads pass through the town. Water-trans-
also furnished by the Wabash and Erie Canal.
en a matter of discussion among the local profession of Terre
o whether, during 1873, any cases of epidemic cholera oc-
at city. At a meeting of the profession, held July, 1873, a
cases were reported that were considered by the physicians
ed them to be cholera. Dr. C. E. Kusler reported that he
about 10 o'clock p. m. July 16, to see a clergyman, sixty-four
e, who had been suddenly taken with diarrhœa some two
ous. The discharges were copious, watery, without fæcal
sterly painless. They were rapidly increasing in frequency.
in bed, much prostrated, pulse very frequent and scarcely
at the wrist. Skin cold and clammy, tongue slightly coated,
ched. Complained of cramps in the extremities; intense
nd the discharges to be rice-water. Morphia exhibited hy-
y, and calomel and opium by the mouth. Was convalescent
.
the case as one of sporadic cholera. Do not know whether
ve come in contact with any person passing through the

en J. Young reported the case of John Reiss, aged forty-six
oyed at a lumber-yard near to the Union railroad depot, who
arly in the morning of July 27 with general malaise. One
ow dejection was followed by large rice-water stools. vomit-
, and collapse, from which he died at 11 o'clock p. m. the

vas called to see a child, three years of age, who presented
ic symptoms of cholera; had been taken suddenly, but re-
his child was a daughter of John Reiss.
ending this child was asked to see an aged man residing in
use, who, after three watery stools, was cramping and vom-
case also yielded to treatment, and he recovered.
, the widow of John Reiss was taken with the same disease,
y collapsed, but reacted. She, however, died of consecutive
he fifth day of her illness.

COUNTY.

ne of the largest towns of Dearborn County, is located upon
the Ohio River, twenty-six miles below Cincinnati. This
market of a rich farming district, inhabited chiefly by Ger-
a considerable trade, and is in daily steamboat-communica-
incinnati.
been unable to elicit full information as to the epidemic at
Seventeen cases are reported, with eleven deaths. We are
at these cases, with but two exceptions, used water from a
in a low, wet bottom on the banks of the Ohio, near the
ogan's Creek, a low, sluggish stream, that at the time of the
ch these cases occurred was nearly dry. Fifteen cases oc-
in an area of four or five hundred yards of this well; *and in*
te vicinity of this well the initial case of the epidemic died on
of July. This case occurred in the person of a white man
er, who contracted the disease at the city of Cincinnati.
cases of choleraic diarrhœa are reported to have occurred
tions of the town.

HENDRICKS COUNTY.

A STATEMENT OF THE EPIDEMIC OF CHOLERA VISITED LIZTON, HENDRICKS COUNTY, IND., SUMMER OF 1873.

BY DR. J. W. CULLEY.

Lizton is a small town situated in Hendricks County, In two miles west of Indianapolis, on the Indianapolis, Bloomi Western Railroad. It contains about three hundred inhabit town is situated on a low, level plane. The surrounding cou in some places marshy and imperfectly drained. There are near, excepting one very small one, which renders the draina

The district is malarious; intermittents and remittents pr the summer and fall months to a great extent. Other disease which prevail generally in other localities. In August, 1873 was visited with an epidemic of cholera which lasted about t and which carried off twenty-two inhabitants.

Causation.—Passing by the special cause, about which I, others, know but little, I shall speak of some local condit may have acted as auxiliary causes. In July, a few weeks the outbreak, heavy rains fell which flooded the place with w of the lots and streets remaining partly covered with wate days. Some of the privies were built without vaults, and t had vaults were filled to overflowing by these rains, by w contents were spread over the ground and left after the w orated, impregnating the air with impure odors.

The wells in this place are shallow, being from 10 to 15 fee in wet seasons were full of water. These same July rains, w flowed the privies, filled many of these wells full of impure pregnated water. Of this many people drank. These rain lowed by hot, sunny days, and by cholera.

The surrounding country has been heavily timbered, but two or three years much of it has been cut down, and a por decay upon the ground. There are in town two saw-mills arc lie large heaps of sawdust, slowly decomposing. Dr. Harve field, thought these decomposing heaps of sawdust sufficient for the disease. For my own part, I am disposed to regard t water and fæcal matter as having much to do with the spr disease.

There is no evidence that the disease was imported. It spring up here, though the special cause may have been impo the cases occurred in town, except four or five. The cases o groups, the members of the family in which the disease occ erally being all attacked. In one family of seven, six died. T was marked by great violence, and in many cases the patien collapse or in a semi-collapse when first seen by the phy death soon followed.

Of the cases reported as cholera, twenty-two out of twenty It is probable, however, that some mild cases which were c rhœa or cholera morbus were in reality cholera-cases which the first stages; and on the other hand, I think it probable or four of the cases reported as cholera were cases of pernic mittent fever, as there was a tendency to call everything cho

fatally. Among those carried away by this epidemic was
Dicks, a physician of more than ordinary ability.
ls treatment, I can say but little of interest. That it was
has already appeared. Why it was unsuccessful, may
ecounted for thus: The attack was generally marked with
ce from the start, the patients often being in a state of col-
irst visited by the physician. But little was done to arrest
except what the physician did himself, who, though not
, was almost required to be so. Vomiting was so excessive
iance could be placed in remedies given *per orem*. The
d purging from the first case in a family was productive of
uness, soiling beds, &c. The neighbors, through fear, with
, rendered no assistance, and in some cases the discharges,
, were left on the floor and in the beds.
g the disease in the first, reliance was placed on opium,
ed in most cases to exert no controlling influence. I gen-
the sulphate of morphia hypodermically, and although I
the system under the influence of the opiate, yet in most
cbarges continued passing, little by little, continually and
r. Malaria being rife, in most cases the sulphate of quinia
metimes in large doses in the first and second stages. The
e of mercury and the subnitrate of bismuth and morphia
ith no apparent benefit. In the collapse, external heat, sin-
, and stimulants of all kinds were employed, but with the
l results.

ND., *November* 26, 1874.

t communication with Dr. Culley elicited the following facts:
son attacked with cholera at Lizton, in 1873, was Allen Davis,
ployed as a section-hand upon the railroad. He had not
rom his work for some time, but was constantly exposed to
railroad-travel. A day or two later, Mrs. Davis, his wife,
d with the same disease. These cases both recovered.
illness they were visited by a relation of the same name,
s taken ill, and died of cholera. A man named Heelmic,
with Davis, and who frequently visited him during his ill-
ken with cholera, and died after a few hours' illness. The
s infant, eighteen months of age, was also attacked and died.
e, a married daughter of Heelmic, who had just been con-
xt attacked, and died; then three sons of Heelmic also died.
t his wife died, Christie was attacked, and died before day.
aining children in the Heelmic family, two died. Dr. Dicks,
ended this family, was taken with the same disease, and died,
already stated. During his illness he was visited by Mr.
o was taken also with cholera, and died. The same day
n took the disease, and she died.
ter of a Mr. Hall visited one of the Mrs. Davis during her
is young lady was taken with cholera and died. Within
er father, mother, and two sisters had the same disease; the
recovered.

UNTY.

on, the county town of Daviess County, is located upon the
ississippi Railroad, one hundred and six miles southwest of
, and three miles west of the Wabash and Erie Canal. We
following

ACCOUNT OF THE EPIDEMIC OF CHOLERA AT W TON IN 1873.

By J. A. Scudder, M. D.

Washington contains from four to five thousand inhabit nated in a rolling valley, surrounded on three sides by hill 200 feet above the general level of the town. The soil is cl natural drainage of the site is good. The sanitary condition liness and the artificial drainage is as good as the avera of its size, and the general health, with the exception of epidemic of 1849 and 1850, and 1873, is considered to be the average for Southern Indiana.

The water used is principally from wells, and contains lime and magnesia, and in the older portions of the town organic matter.

In July and August, 1849, out of a population of less th sand, there were one hundred cholera deaths; and the disea arrested by the absolute dispersion of the people, who directions.

On the 8th day of July, 1850, cholera again attacked the within eight days over forty deaths occurred. The inhabi fled, and there being a decided change in the weather, al the disease was again arrested.

The weather just preceding and during the epidemic of 18 1873, was the same, the temperature varying from 85° to humid atmosphere that seemed not to move at all, but to b with moisture that everything became moldy. The sky was but a haziness was apparent.

The diseases were the same, for a low type of diarrhœa an prevailed through the country during and for some time afte pearance of cholera.

The following cases will show the general character and disease as it appeared in 1873:

Case 1.—Honeycutt, a white man, aged twenty-eight, a labo constitution and robust health. Had eaten of fruit during of green corn for supper; was taken with diarrhœa at 10 o August 11; rice-water discharges resulted; vomiting, cramps and extremities. At 1 o'clock a. m., August 12, was collap suppressed. Died at 4 o'clock a. m.

Case 2.—James Tranter, a white man, forty-four years of gineer employed one mile beyond the town limits, was tak work at 9 o'clock a. m. August 11, with diarrhœa. In two h rice-water discharges, vomiting, and cramps. The cholerai were fully developed, and he died at 1 o'clock p. m. August

No connection is known to have occurred between this case cutt; they lived three-quarters of a mile apart.

Case 3.—Miss H., aged seventeen years, living about thr yards east of the house at which Honeycutt died, was att o'clock p. m., August 12, after eating a hearty supper. C developed; died at 3 o'clock p. m. August 13. On the 20th of this young lady was attacked, but recovered after a c lasted for thirty-six hours.

Four cases occurred in the persons of coal-miners worki town. In another instance, a mother and son living in the

ttacked; making in all, with the father and daughter, eight
es, of whom seven died.
atment adopted an effort was made to restore or maintain
heat of the body by artificial warmth in the shape of hot
ot corn, and blankets, dry or wrung from hot water and
General stimulants with quinine, opium, and calomel in
with astringents.
ted a very noticeable feature in this epidemic; few, if any,
ed in persons of dissolute or dissipated habits, and the ma-
persons of regular habits and the best constitutions.
of importance to state that in no case were any precautions
vent the spread of the contagion. Nor were means used in
more than those employed in ordinary cases of death; and
instance did a family leave the house in which a death
d.
er reports thirteen cases, of which twelve were fatal. He
many cases of diarrhœa occurred, which yielded readily to

on is the county-town of Daviess County, and is located
e of the Ohio and Mississippi Railroad, one hundred and
miles east of Saint Louis, and one hundred and seventy-
f Cincinnati. That the disease traveled along the line of
l has already been demonstrated with sufficient clearness to
of Washington to any claims of a *de novo* development.

CHAPTER XIV.

ALABAMA GROUP.

ALABAMA CONTRIBUTORS.

Dr. L. C. Pynchon, Madison Co.
Dr. A. R. Erskine, Madison Co.
Dr. H. A. Binford, Madison Co.
Dr. H. W. Bassett, Madison Co.
Dr. J. J. Dement, Madison Co.
Dr. A. J. Green, Madison County.
Dr. M. C. Baldridge, Madison Co.
Dr. L. D. Carter, Madison Co.
Dr. A. K. Burnett, Madison Co.
Dr. David Shelby, Madison Co.
Dr. Frank Hudson, Madison Co.
Dr. J. D. Humphrey, Madison Co.
Dr. M. H. Jordan, Jeff
Dr. W. H. Crawford, J
Dr. J. B. Luckie, Jeffe
Dr. J. B. Flonville, Jef
Dr. P. Taylor, Jefferso
Dr. J. W. Sears, Jeffer
Dr. S. H. Day, Jefferso
Dr. W. T. Parker, Jeff
Dr. T. A. Means, Mont
Dr. E. H. C. Bailey, M
Dr. Z. T. Daniel, Barb

Assistant Surgeon Charles R. Greenleaf, U. S. A.
Assistant Surgeon M. K. Taylor, U. S. A.

DATES OF INITIAL CASES.

Huntsville, Madison County .....
Birmingham, Jefferson County .....
Montgomery, Montgomery County .....

Before proceeding with the papers which form the *exposé* era epidemic as it affected the State of Alabama, it is prope that two of the communications presented have already appe transactions of the Alabama State Medical Society for 1874,

I. Epidemic cholera at Huntsville, by J. J. Dement, M. D.

II. Cholera at Birmingham, by M. H. Jordan, M. D.

In regard to these papers we desire to make the following counting for their republication:

I. During a visit to the city of Huntsville, Ala., in the mon 1874, a thorough investigation of the late epidemic was made a consultation with the medical gentlemen of the city, who for the purpose, it was the request of all present that Dr. D pare the history of the epidemic at Huntsville. This paper, properly belongs to this report, although a copy was furnis State Medical Society Publication Committee.

II. The paper of Dr. Jordan was read before the State So annual meeting of 1874. At a visit of inspection which w Birmingham, Dr. Jordan kindly went over the records of th with us, and much new and interesting matter will be fou report which we present.

COUNTY.

RT ON EPIDEMIC CHOLERA AT HUNTSVILLE, ALA.

By M. K. Taylor,

Assistant Surgeon United States Army.

y purpose at the close of last year to embody a brief sketch
emic in my annual sanitary report for the post of Huntsville,
th and a change of station prevented my carrying out my

de notes in a general way of some of the more important
the time, with the intention of filling up the minor details
moments of leisure would permit. Seeing, however, that
e nor circumstances were likely to be of a character to allow
pleting what I had begun, I abandoned the project, and laid
ls aside in the expectation of having no use for them. It
urce of regret that I did so.

ntering upon the special consideration of the epidemic, it
ting to refer to the antecedent circumstances touching the
itary condition of the city, the action of the civil authorities
thereto, and to the public sentiment as to what was ap-
manded. One of the great difficulties to be encountered at
the promotion of sanitary measures is the belief on the part
bitants, as a rule, that their particular locality is the healthiest
e country; and often not until a profound impression is made
verwhelming disaster can public sentiment be sufficiently
o a full realization of the fact that there can be any mistake
ect. This was the case in Huntsville. Until within a short
cholera outbreak there was no board of health; it was not
necessary.

was one of the oldest settled communities in the State, and
d hitherto all the epidemics of cholera and yellow fever
repeatedly visited surrounding cities; particularly Memphis
t, Nashville on the north, Chattanooga on the east, and
y to the southward; with all of which Huntsville had been
nmunication without contamination in times past, and it did
robable that a city so proverbially healthy as that would be
an exception to the apparently established rule.

rtain portions of the city were pointed out as possessing all
ons of unhealthiness, the remark in substance was made not
ly in reply that Huntsville was an exception, and that while
avored cities might have suffered from such causes, no incon-
were felt there. In my annual sanitary report for Thomas
r 1872, I stated that certain portions of the valley in which
is situated were particularly obnoxious to intermittent fevers
arial hematuria type, and more especially so in some of the
d southern parts of the city.

nay be remarked, without attempting to trace any connection
re of the two maladies, it so happened that in those very lo-
ere the malarial fevers were severest in years past, cholera
fatal; thereby showing in a notable manner the general fact
bad sanitary conditions exist, and epidemic influences reach

these places, no matter what may be their characteristics, a corresponding intensity of action and resultant fatality.

In the early part of the season, and before the appearan at Memphis and Nashville, the Madison County Medical measures to impress upon the attention of the city authoriti sity for a registration of deaths, ostensibly with a view comparatively the salubrity of its climate.

The committee appointed consisted of Drs. A. S. Green sett, and M. K. Taylor, United States Army, and upon th tions thus made the ordinance for registration was passed. measure that we are indebted for any exact records as regs tary relations of the epidemic to the various parts of the c

It was the purpose of the medical society, however, so ordinance for registering the mortality of the city was to move for the appointment of a board of health, but a portunity was not presented until the appearance of the Memphis.

Thereupon another committee was selected to confer authorities and urge the necessity for such action at once result of several conferences, a board was appointed, cons members of the board of aldermen and two from the me with the mayor as president.

Work was immediately commenced for the general police Several of the places where there was stagnant water w yards, lanes, back alleys, and streets were policed; an i water-closets, where the circumstances seemed to warrant i and the more dense habitations of the colored population nized, with a view of removing all contaminating influen practicable, in the event of an outbreak of the cholera. Th undoubtedly accomplished much in preventing the subseq of the disease, not only by the removal of offending matt recting the attention of the people to the imperative nece pulous care in all matters pertaining to the hygiene of the localities.

The time intervening, however, before the appearance of was too short to allow of the accomplishment of all that w contemplated by the public authorities; and, besides, some the town can only be put in a healthy condition by an e expensive system of drainage, and the extension of the w all parts where the inhabitants now derive their supplies f wells, all of which will require, not the labor of a few w months and perhaps years, for their full accomplishment.

The city of Huntsville is located about twelve miles south ern boundary of Alabama, in a beautiful valley at the termination of the Cumberland range of mountains; is dist Tennessee River about ten miles to the northward, and with above the sea of about 600 feet.

The geological formations underlying and surrounding the subcarboniferous groups of limestone. These crop ou ern portion of the town, and again on the block west square, in considerable ledges of from 50 to 75 feet in heig

To the eastward of the city, at a distance of a mile a Monte Sano, a mountainous elevation above the valley of feet, and about 1,700 feet above tide-water.

To the south, west, and northwest, at a varying distance ten miles, are the last spurs of the Cumberland range. T

he vicinity are mostly covered with a luxuriant growth of
e the valley is chiefly in a fair state of cultivation. The
age of the valley is in the direction of the Tennessee River,
ally good or can be made so by a reasonable expenditure for
. In high water, however, or after excessively heavy rains,
le portion of the valley between the city and the Tennessee
flooded, but more especially that along the creek leading
ing which issues from the ledges near the public square to
The surfaces within the city-limits are quite diversified.
pring, which is the lowest, as a starting point, and proceed-
terly, we have on the next block the public square, at an
about 60 feet; from thence there is a gradual rise most of
until the hill on which the reservoir is situated, is reached,
ight attains an elevation of about 150 feet. Near the sum-
hill the reservoir is located for the supply of water to the
ons of the town.

irections from the public square the surface slopes off grad-
t at a distance of three or four blocks northward and south-
nging round by the westward, the surface but little exceeds
of 10 or 15 feet above the creek, while to the northeast of
nd other points in the lower portions of the town, there are
sions of the surface that without artificial drainage water
the greater part of the season. * * * *

-supply is derived from three sources, viz, from the large
at famous spring issuing from the ledge west of the public
vater from which is forced up to the reservoir by the water-
which is moderately hard and of excellent quality; from
ace-wells in the lower districts, and in a few instances from

ne well-water has surface-drainage in it, and may be regard-
upplies from such a source, as unwholesome. This latter
f supply in those districts where the epidemic prevailed
t force. So far as cistern-water is concerned in southern
less it is well filtered, I believe, from the casual examination
enabled to make, that it is by no means as wholesome as
se.

ne prevalence of the epidemic I examined the rain-water
precipitated at the garrison on several different occasions,
which the amount of organic matter held in solution ex-
arfold the quantity found in the surface well-water obtained
e Memphis and Charleston Railroad depot. So large, in
amount of organic matters present in the rain-water, at
at after standing closely bottled for a few days it under-
ctive fermentation, and formed black precipitates with most
lic salts to that degree as to render it wholly unserviceable
nsary.

ore, growing out of this condition of the water, the question
ggested itself as to what extent it contributed to the intro-
spread of the epidemic, for it may be observed hereafter
as no traceable connection between the first case occurring
and those who had been exposed in the neighboring cities.
as unable to find but two or three cases of deaths from
re the water from the public works was exclusively used.
ve been only a coincidence, and attributable, perhaps, to the
ary conditions of the town where it was distributed, but I
ot wholly so. Facts of a similar character have been elic-

ited in like investigations of cholera-epidemic in other cit
past, and very intimate relations were established betwee
supply on the one hand and the intensity of the zymotic a
other.

The well-water examined was from a well located nearly d
the depot and near the Meridian pike. Cholera was preva
time in several families which were obtaining their suppl
source for domestic and drinking purposes. Unfortunately
randa are lost or mislaid, and, as a consequence, I am comp
back on my recollections as to the results. I made two ex
the first had not been preceded by recent rain, the second
considerable shower. The first specimen was clear and
wholesome, and moderately hard, but the second quite turb
presence of earthy matters from the surface-drainage. Af
this was tested with a solution of permanganate of potassa
tion with an equal quantity of rain-water caught from the s
at the garrison, when the amount of organic matters held
by the rain-water quadrupled that from the well as before a
amined by the microscope several forms of animalcula we
both specimens of well-water, while in the second, spores of
quite abundant. The water-supply in the southern part o
where Madison street terminates in the Whitesburgh pik
a well scarcely six feet deep, and after the heavier rains the
to within a foot or two of the surrounding surface of the g
the earlier and severer cases of cholera in that neighborho
water from this well. Upon ascertaining these facts the city
forbade the use of water from the well, and arrangements
for a limited supply from the public hydrants by cartage.

The meteorological conditions preceding and during the p
the epidemic were of much interest. * * * *

The month of May was of about the same temperature as
corresponding month in 1872, but the mean relative humidit
one and one-half per cent. higher, or to be exact, 70.0 and 71
respectively. But in June, 1873, and commencing very nea
appearance of the epidemic, the humidity became remarkab
tinued until the latter part of July, when coincident with t
tion very nearly of the normal amount of moisture in the
there was a corresponding abatement and final disappearanc
cases. With only a mean difference in the temperatures in
of June in the two years, of about two degrees, and this diff
due to the lower temperature for that month in 1873, there w
ence in the relative amount of moistures of nearly 10 per
change commenced on the 5th of June, when there was a
rain-fall; cholera had appeared before in a single instance o
other case occurred till the 15th. In all this intervening tim
and indeed during the entire prevalence of the epidemic in
manifestations, the weather had been distressingly close,
oppressive. To that extent was the air saturated with mo
often in the middle of the day the walls of my quarters we
with condensed water, and writing-paper was so damp as t
serviceable. The conditions were so favorable, too, for t
ment of cryptogamic life, that microscopic fungi appeared
almost everywhere and on everything subject to their atta
alike on articles of food and clothing in our dwellings, and o
plants of various kinds either wild or cultivated. Leathern
apparel as well as the leather cases of my instruments would

e mold in a single night, and the same was true of wooden
cently dressed, especially pine lumber, and left unpainted,
ted in close and unventilated places. From the 5th of June
f the month there were fifteen days on which more or less
enerally in the form of light showers in the afternoon. The
precipitation was 5.62 inches, or twice and one-half more
same month in the preceding year, and in excess of the
that month as determined by observations of Dr. Team, of
f an inch.
t of cloudiness was not excessive during the day-time, but in
rning and in the evening there was a thin stratum of bluish
g over the lower portions of the valley, and elevated above
f the earth, at an average, perhaps, of 50 or 60 feet; rarely
gh as the upper portions of the town. As seen from the
an elevation of about 100 feet, this stratum of mist seemed
et in thickness. Its tenuity was such that one underneath
othing of it, and only when in position to see it, as it were
s it observable. Similar conditions were generally witnessed
prevalence of the severer malarial fevers in the summer and
this section, and which, so far as I was enabled to judge
ed there, had a close connection with the intensity in man-
f the paludal poisons. It is true this mist-line may be seen
anging over the lower lands in nearly all sections, but when
ase, it indicates almost complete saturation of the air under-
n condition is generally recognized as particularly favorable
lopment of intense zymotic processes, and an active crypto-
h. In so far as these particular conditions of the under
be atmosphere over the lower portions of the city and valley
d, the meteorological observations in respect to humidity
barracks are not a proper expression; for the difference at
on in the sense of dampness as we passed from the lower
s very remarkable during the time the sun was below the

importance of carefully considering these meteorological
in the selection of locations for private dwellings, public
nd charitable institutions, is beyond the scope of this report;
necessary, when describing the sanitary conditions of cities,
earing on public health in times like these we are now con-
at at least a brief allusion should be made to them, mainly
of calling the attention of the public to their effects at all
nder all circumstances, and of showing that a disregard of
tance will inevitably be followed by severe penalties at one
ther.
case of cholera occurred on the north side of Holmes street,
t of Church, in the instance of a little colored girl, about five
; the attack commencing the evening previous to June 3.
l the facts, she had up to that time been in good health, but
eding afternoon she ate some unripe fruit, apples or peaches,
en about midnight she was taken with vomiting and purging,
into a state of collapse, and died in about twelve hours.
stances under which this case occurred led some of the
hysicians at first view to consider it only a severe form of
bus.
re none of the antecedent bowel diseases prevailing in the
time before this, in a manner so frequently observed preced-

ing the outbreak of cholera; and, from the best obtainable information, this girl had no tendencies that way prior to the attack.

The location of this case will be found on chart No. I, with the date indicated near by. And I may remark here, in passing, that the figures on this chart indicate dates of death for the month of June only, but the marks thereon, as indicated at the bottom, show the location in the city of all recorded deaths from the commencement of its appearance until the close of the epidemic.

I made an effort subsequently, and when the disease became general in the town, to ascertain whether or not this girl had been away from the city, where she would be exposed to any contagious influences; or whether she had seen any one arriving from other places where the epidemic was prevailing; but I could find nothing satisfactory, except that she had not been out of town, nor did it appear probable that she had been subject to any exposure in that direction whatever.

The next case occurred on the same block twelve days thereafter, or on the 15th. This (No. 2 on the list) was a stout, healthy negro in middle life, and who had been employed about the city as a general laborer. He, too, towards night, the day before of his attack, had eaten a quantity of green pears, if I recollect rightly, or some nuripe fruit of like character, when, after a few hours' sleep in the evening, choleraic symptoms supervened, and he sent for medical assistance. I saw him next morning, in consultation, and then it was the unanimous opinion of all the medical gentlemen present that there was no mistaking the nature of the malady, and that the epidemic was fairly in the city. The patient had been in a state of collapse since 2 or 3 o'clock in the morning, and was then quite in a moribund condition. No. 3 in the accompanying list lived beyond the city limits, and I did not obtain any history of her case; but No. 4 lived on the same street with the first two and in the immediate vicinity, and had more or less intimate relations with the families in which deaths from the disease had already occurred. In so far, therefore, as the general principle of contagion is concerned, he would come under the rule.

On the two subsequent days, there was one death each; but on the 24th there were six deaths, of which four were black and two white persons. On the 25th there were two, and on the 26th there were four deaths.

At this time the epidemic had spread over nearly all the lower districts, while the deaths were chiefly confined to the colored population. The white inhabitants, however, were suffering very considerably from a less severe form of the disease, and a feeling of general distress pervaded the community. Many of the cases were of a startling character and well calculated to awaken apprehensions in every one having any tendency to bowel disorders. No. 16 on the list was an example. This was a bright colored lad who had been employed by a grocer as an errand boy during the day. At 5 p. m. he started for home, a distance of three or four blocks, and at the time he left the store of his employer was apparently in good health. When about half-way to his destination, he was stricken down in the street. He was taken home immediately, and as I was passing at the moment, I was called to attend him. He was then in a collapsed state, and although stimulants, frictions, heat, and all the approved means of procuring reaction were employed, they proved of no account, and he died in a few hours. I saw him probably within fifteen minutes after his attack in the street, and his condition then was general lividity of the surface, more especially of the extremities and face; he was pulseless at the wrist; the heart's

action was tumultuous, apparently, but of diminished force; there was stupor and disposition to somnolence, and the extremities shrunken and cold. This boy had also been indulging immoderately in green fruit. During the day he had been seen climbing on the wagons having fruit for sale, and when he started for home he had a green apple in one hand and in the other a quantity of salt, into which he would dip his apple and then eat it. This mode of eating unripe fruit is very common with the negroes, and they use the salt in the belief that it prevents any injurious results from their indulgence of their appetites to any extent. So fixed were they in the habit that no amount of dissuasion would avail anything in checking the practice. When remonstrated with they generally replied that they had always done so, and it had not hurt them before, and they did not think it would do so now. Many were especially obstinate in this respect at first. One colored girl said she would eat what she liked if she knew it would kill her; she indulged her appetite at the time, and was buried the next day at the expense of the city. This unwillingness to restrain their appetites was undoubtedly a potent cause in contributing to the greater mortality of that race; and it was not until near the close of the epidemic, when by many sad demonstrations of the evils arising from the continuance of such a course, would they heed advice in this respect.

About the time of the appearance of the disease in the city, or soon thereafter, cases occurred in various parts of the whole valley, and having, so far as I could learn, no traceable connection. No. 20 on the mortuary list seems to be one of such instances. He had been working on a plantation in the direction of the Tennessee River, several miles from town, and had been in good health until two days before I saw him. During an excessively sultry day he drank freely of water when heated, and partook of a full meal in the evening. The night after, severe diarrhœa set in. He was brought to town, where he had friends, the second day, and I saw him that evening when he was verging on a collapse. He died about daylight the next morning. This man stated that he had not been in the city for two weeks before his attack.

So far as I was able to ascertain the facts, in nearly every case of severe form of the disease, there had been imprudent gratification of the appetite in the after part of the day preceding the cholera symptoms. It mattered not so much whether this indulgence consisted in eating immoderately of the usual articles of food at such hours, or the fresh fruits then coming into market. It was not, however, until the green fruits came into use that the disease broke out.

In this respect, if the newspaper reports were correct in regard to the appearance of cholera at Memphis and Nashville, simultaneously with the arrival of considerable quantities of stale vegetables and fruits from New Orleans, the disease at Huntsville conformed to the general rule that, with the introduction of unripe, immature, or unsound fruits or vegetables as articles of food, did the cholera appear.

The coincidence in this respect was remarkable, I believe, throughout the prevalence of the epidemic, in its ravages over the whole country, judging by the current reports, and certainly no section was apparently healthier than the region about Huntsville prior to June 3, when immature fruits, as affected by the meteorological conditions before alluded to, first appeared on the streets. Many instances might be given in illustration of the influence of the fruits for sale in developing the disease, but one will suffice. A gentleman living on a plantation about twelve miles from the city, and away from any principal thoroughfare, arrived on the cars at 4 o'clock p. m. July 19, in perfect health, appar-

ently. Seeing some fine-looking pears for sale at the depot, s
no food since morning, he purchased two pears and ate the
and in an hour or so partook of a hearty supper. In six h
after, without much premonition, he was seized with vomiting
ing most violently. I saw him in a half-hour thereafter, wh
greatly prostrated and had all the appearance of a very se
of cholera: rice-water discharges, violent retching and vomit
sive abdominal distress, general restlessness, livid and cold e
feeble pulse, the skin on the hands and fingers shrunken,
expression to the face, with all those general symptoms which
the prodromic conditions of collapse. Without timely assi
gentleman would have been past help, undoubtedly, in ano
delay; as it was, with the free administration of morphine
after each effort at vomiting, and stimulants, with hot drinks
applied to the whole abdomen and to the extremities, the c
checked by daylight the next morning, and he finally reco
said, in connection with the attack, that he felt considerable
uneasiness in a short time after eating the fruit, but attri
to the want of his dinner.

The last case of death from the epidemic occurred July 2
may be considered the close. Yet there were many cases o
diarrhœas for two or three weeks thereafter, and which, but f
eral alarm when symptoms of this kind were shown, and whic
the subjects to seek for immediate relief, might have extende
of continuance and number of fatal cases very greatly.

The abatement was as sudden as the onset. On the 24
there were three deaths, and two on the 25th, while the non
were quite as abundant in the city, though of milder type.

The total number of deaths from the epidemic was si
which is included the case of a young woman who left th
Monte Sano when in ill-health, and died three or four days sub
I believe there is no record on the city registry of this case,
fore it is not included in the list hereunto appended. Of the
number, there were twenty whites and forty blacks; and the
respective classes of inhabitants was one death in 127 of t
and one death in 59 of the latter, taking the census of 1870
of calculation.

But it is questionable whither that is fair data upon whic
the deductions, on the ground that, in the opinion of many c
informed people of the place, there has been an actual dim
the population since the census was taken: It is the most re
obtainable, however, and serves the purpose of comparison in
way; but, as applied to the white population only, it is quit
in determining the ratio of deaths for this reason.

Very soon after the disease became well pronounced in the
knowing the fatality of the epidemic in the neighboring citi
gloomy aspect of affairs there, many of the better class of wh
left Huntsville, either for the Northern States and watering
for similar resorts in the country near by; while several f
moved to their plantations, and others made temporary pro
their accommodations in Monte Sano. It is difficult to arriv
proximate estimate of the actual number of persons leaving
this time—some fixing it as high as five hundred, mostly wh
may be safe to safe to say four hundred were absent the grea
the epidemic season.

If this be accepted as near the facts, then the proportion

Showing the location of the fatal cases of Cholera in Huntsville Al

The circle indicates White, and the cross, Colored Persons.

The figures show the dates of deaths for June only.



e population would be one to every one hundred and seven, bout one-half of the colored.

meteorological tables hereunto appended will be observed nths of June and July are divided into three periods each, being made on the 10th, 20th, and last days of the month. these periods the temperature, relative humidity, and mor- ated; and these afford, perhaps, a better idea at a glance of ncement, culmination, and decline of the epidemic in connec- he climatic conditions, than any other form of expression. se statistics are so suggestive that I am not disposed to dwell bject. They speak for themselves.

ribution of the mortality over the city is shown in chart hich the two classes of inhabitants are indicated in connec- e location. This chart in that respect needs no explanation ows that the chief mortality was confined to the low dis- ited largely by negroes, while the higher portions, which are densely populated with whites, escaped almost entirely.

ts are additional elements of error in the ratio of mortality given, and in consideration of which it may be safe to esti- oportion of deaths to the living in the principally infected quite double what has been heretofore stated, and based on statistics of the city.

of recoveries to the whole number attacked is difficult, I possible, to determine, for the reason that it was not practi- ce fine lines of distinction between cases of ordinary diar- the milder choleraic attacks, which latter, and indeed the ell, when allowed to go unchecked, would in time give rise est aspects. If, however, the best statistics obtainable from ns having most to do with the epidemic be taken as a guide, roximate results which can be of some value in determining

wing physicians report their experience as given below:

Name of attending physician.	Number of deaths.	Number of recoveries.	Total.
D.		3	3
M. D	2	3	5
M. D.	3	8	11
D. D	13	20	33
S. A.	4	9	13
M. D	4	(*)	4
	26	43	69

* None reported.

ports of Drs. Dement and Baldridge, their own recoveries are d, as in fact they should be, for both gentlemen were severely he latter being compelled to leave the city as soon as he was r transportation.

other physicians were also affected by the epidemic, but as ailed to report, and declined or neglected to furnish me with ents of their experience, I am compelled to omit them in the imate.

acquaintance with the foregoing gentlemen, and from my of their views as to what should be called cholera, in fact, satisfied that the number of cases given above includes only

such as were well pronounced, and of such a character that be inclined to raise any questions as to the correctness of the

If we allow Dr. Erskine the average number of recoveries omits in his report to state, but to which I believe he is e account would stand four deaths and eight recoveries for his as a total result the proportional death-rate of about 34 per

Again, if we take reports of attending physicians as a bas ther calculation in determining the ratio of the whole numbe attacked to the total population, the statement will be as fo

The sixty-one deaths would give one hundred and eighty- in all, which, from my observation, I believe to be under r over the actual number. This is one case in every twenty-sev ants according to the census of 1870; but, making allowance tees, the rate would be one to every twenty-four and one-l total population. Continuing the calculation, however, on basis for the two races, the results will show that the numb occurring among the whites, also allowing for the absentees, proportion of one to every thirty-four and one-half, and, of the to every nineteen and a small fraction. During the preval epidemic quite a number of cases of cholera-infantum occur what extent it was fatal I have not the data at hand for de Within my own observation there were five cases and two d fatal cases running a very rapid course. Two of those cases from infected cholera districts; one, fatal, from Birmingham one of recovery from Union City, Ky.

Of the treatment, I can say but little that will be new or i In the mortuary tables will be found some general memora course pursued in the several cases therein noted. In regard experience and observations of the course pursued by other the preparations of opium, especially morphine, given in solu podermically in conjunction with the free use of stimulants, alcohols, camphor, ginger, and capsicum, in the earlier st more generally employed. In addition thereto, when astrin acetate of lead, tannin, catechu, &c., failed entirely in the ear and frequently as well in the latter, I found the aromatic sul answer a much better purpose. Also, I found in some cases, opiates seemed to have no effect, given alone, yet combined or g taneously with the elixir vitriol, they became speedily effectiv ing the distressing vomiting and purging. Such, too, was my in treating the epidemic in 1853–'54 and in 1866.

In the later stages of recovery the vegetable or ferruginous were of benefit in giving tone to the intestinal canal and pro gestion and assimilations of the food.

Very few cases recovered when well-marked collapse supe saw none; but Dr. Pynchon reports one recovery, after re this condition for twelve hours, and, with this exception, I de lect of hearing of a case in my intercourse with the other Yet exceptional cases may have occurred, and not come to Several of them ended in a low form of typhoid, and lingered several days; No. 38 was an instance. After the intestinal were arrested, the man seemed to rally for two or three d bowels were disposed to constipation, and mild purgatives mately required to open them; but there was excessive *diur* time; the quantity of urine reaching several pints during t four hours; on the fourth day *sordes* collected on the teeth, became red and dry, the pulse running up to 120 or 130, and t

l the last ranged from 103° to 106°. The more interesting
is case was, that while there was great prostration of the
em, and a comparative arrest of the secretions in most other
he kidneys were unusually active, the urine being of a pale
generally of a low specific gravity, and nearly free from
examined it several times, and could only detect a trace
h was a different result from what I expected.

this report, it is proper to refer to the sanitary measures
t the garrison for the prevention of the epidemic, in case it
that vicinity. After the cholera had appeared at Memphis
general, I suggested to Col. W. F. Drum, the commanding
n all probability the disease would spread in that direction,
cautionary measures should be adopted at once to mitigate,
ot succeed in preventing its introduction among the troops.
he fully coincided, and proceeded to act in accordance there-
hough the garrison was always kept in good order, additional
were given for a more thorough police, not only within the
of the surrounding grounds, which by virtue of the lease
possession was held by the Government, were under con-
ilitary authorities. The men were ordered into another
ents, and the quarters fumigated by burning sulphur in
enty-four hours, then ventilated and whitewashed; the
he men was frequently carefully inspected, while bathing
e introduced to better advantage, and at least one or more
required to be taken weekly by the men. The food was
ended to. In addition to the regular ration there was a
e of fresh vegetables from the post-garden for breakfast
while for the supper the simplest food, chiefly bread and good
ermitted. It has been the habit for those on guard and
es to have a more liberal meal at night, but as I observed
re disposed to overeat at that hour, which, taken in connec-
e sultry weather, produced a tendency to diarrhœas, I ad-
m, also, that this meal be reduced to the simplest form of
vice was based on my observations in regard to overeating at
otent element in the propagation of the epidemic, not only
ce, but in all the other cholera seasons which I have wit-
the fruits of the season were interdicted, unless well cooked,
were specially enjoined against the indulgence in apples,
es, cherries, &c., as they came into market; and it is believed
followed these instructions as faithfully as one could ex-
ermore, they were not allowed to be out after sun-down,
on guard. During the day-time intercourse with the town
ed from the usual practice, except that they should return
retreat; and under this custom probably not less than a
ometimes more, on an average, would go to the city daily.
er of persons of all classes within the garrison, embracing
nd their families and servants, the enlisted men, laundresses
, and several negroes employed in various services, together
ildren, amounted to about one hundred. Of this number there
r persons having any bowel disturbances whatever during
eason. Three of these were enlisted men who had been
ces of hearty food after the day's fatigue, and the other
who had been on furlough for ten days, during which time
ed Nashville and become most thoroughly demoralized by
aspect of that place. He returned claiming that he was
m diarrhœa, but inquiry developed the fact that this con-

sisted in only two evacuations in the twenty-four hours, a
moderate consistency, but he was taken into the hospital for
of quieting his apprehensions. A day or two afterward he h
diarrhœa, which was clearly traceable to his fears, when I ma
prescription of an emulsion of chloroform, camphor, and m
which he took only two or three doses to obtain complete
mentally and bodily. These were the only instances of a
on the part of any inmates of the garrison to diarrhœal at
the cholera was prevalent, not only in the city, but in th
country and over the whole valley, and which approached w
a mile to the westward of the post, where, in a suburba
situated on low ground, there were several cases.

The distance of Thomas barracks from Huntsville is abou
to the northeastward; and, as before stated, it is elevated o
slope about one hundred feet above the lower portions of
The natural drainage is such as to make at all times a very h
but the efficient measures instituted by the commanding offi
out my recommendations contributed very clearly to my n
entire exemption of the troops from the visitation of the epi

In my recommendation to the commanding officer I was a
the belief that quarantine measures are of little account a
spread of cholera, and that unless effective sanitary regulati
in full operation the disease will overleap all such flimsy ba
ravage the country unrestrained; that the best and only effe
to the epidemic is by enforcement of a regular hygiene in a
tains to food, daily exercise, personal cleanliness, and gen
together with a wholesome supply of water.

Originating in filth, the cholera germs can only propagate
when material of like character to its origin is abundantly a
its development and growth, in combination with favora
and meteorological conditions. For its prevention in th
therefore, I consider it of paramount importance to fight th
at our own doors, by instituting such means before its arriv
effectually deprive it of the means of sustenance. The resu
garrison seemed to fully demonstrate the correctness of t
for we had not even the usual number of diarrhœas of the s
absolutely nothing having the semblance of cholera. This
tribute mainly to the regulation of the diet, alike as regarde
quality, and mode of serving. The allowance was not
breakfast or dinner in any manner. The fresh vegetables fro
gardens were gathered early in the morning in quantities su
the day, and distributed immediately. These consisted of p
beets, onions, corn, potatoes, turnips, cabbages, lettuce, cucu
By many the latter article is considered unwholesome durin
alence of cholera, and that it should be wholly interdicted at
yet I have never observed any harm from the vegetable, if
the vines, and eaten in moderation at the proper hours of th
deed, I share very little in the prejudices against green ve
articles of diet during such epidemics, provided they are
from the garden, and served with breakfast and dinner onl
latter term I do not mean a fashionable dinner in the evenin
or 6 o'clock, but the midday meal of the laboring classes and
This gives time for the complete digestion of the food befor
for sleep, while the former custom does not; and the evil
therefrom in cholera seasons are incalculable, when the indul
hearty meal at the latter part of the day is associated with

weather and exhausted nervous energies. Under such cir-
in my judgment, the simple fare of our garrison or some-
is the only correct regimen for the evening repast.
uthorities, however, acting under the advice of the board
ohibited the sale of nearly all green vegetables at the mar-
nd many of the inhabitants found it difficult, as a conse-
btain that variety of food which is clearly necessary to
e functions of digestion in a healthy condition. In my
would have been far better to institute a thorough inspec-
rticles for sale, and to condemn all such as were not unques-
nd and fresh; and to require that the market should be
ese by 7 a. m., at the latest. That this rigid prohibition did
cholera attacks, was demonstrative in several instances
tients had been living on bread and meat almost entirely.
s the lateness of the hour at which the food was served
the chief exciting cause.

of the material in preparing this report, and more especially
ng to the mortuary record, I am indebted to Dr. L. C. Pyn-
retary of the Madison County Medical Society, and to Drs.
resident; J. J. Dement, and Benford, Baldridge, and Er-
es and reports of their cases. To Assistant-Surgeon Chas.
, U. S. A., who relieved me at that station, I am indebted
neteorological records of the post, as well as for other favors
tion.

EXAS, *November*, 1874.

*orological observations made at Thomas Barracks, Huntsville, Ala., for the
ths of May to September, inclusive, for the years* 1872 *and* 1873.

	Mean temperature.				Relative humidity.				Rain-fall, in inches.
	7 a. m.	2 p. m.	9 p. m.	Monthly mean.	7 a. m.	2 p. m.	9 p. m.	Monthly mean.	
.....	68.9	80.1	69.8	72.3	76.3	56.1	77.6	70.0	2.09
.....	75.3	84.3	74.0	77.9	75.5	57.8	73.7	69.0	2.13
.....	77.3	86.6	76.5	80.1	86.8	64.4	81.8	77.6	6.91
.....	76.3	87.1	76.2	80.0	85.0	61.2	80.0	75.4	2.94
.....	65.5	82.2	69.5	72.5	83.3	52.7	70.2	68.7	1.96
an.....	72.6	84.0	73.2	76.6	81.4	58.4	76.7	72.2	15.94
.....	70.2	78.6	68.3	72.4	77.1	61.5	76.2	71.6	3.45
.....	76.5	83.5	73.3	77.8	84.3	67.9	83.4	78.5	5.62
.....	78.9	88.8	77.0	81.6	80.7	59.7	82.5	74.3	3.92
.....	76.5	86.7	75.8	79.6	86.2	60.2	85.5	77.3	3.40
.....	69.9	80.2	67.6	72.7	83.5	62.6	77.7	74.6	3.90
an.....	74.4	83.5	72.4	76.8	82.3	62.3	81.0	75.2	20.29

Meteorological register for the month of June, 1873, transmitted by M. K. Taylor, assistant surgeon, United States Army.

[Station, Thomas Barracks, Huntsville, Ala.; latitude, ——; longitude, ——; altitude of barometer above sea, —— feet.]

Day of month.	Thermometer.				Movements of atmosphere.						Amount of cloudiness.			Rain and melted snow.			Remarks.
					7 a. m.		2 p. m.		9 a. m.								
	7 a. m.	2 p. m.	9 p. m.	Daily mean.	Winds.		Winds.		Winds.		7 a. m.	2 p. m.	9 p. m.	Began.	Ended.	Quantity.	
					D.	F.	D.	F.	D.	F.						*Inches.*	
1	72	85	73	76.66	S.	1	S. E.	0	S.	0	Fair	Fair	Fair				
2	76	88	6	80.00	S. E.	1	N. E.	1	E.	0	Fair	Fair	Fair				
3	76	86	75	79.00	N. E.	2	S.	1	N.	1	Fair	Fair	Fair				
4	75	85	74	78.00	S.	0	W.	2	S.	1	Cloudy	Fair	Fair				
5	85	96	76	85.66	W.	2	W.	3	W.	6	Fair	Fair	Cloudy	Night			Heavy showers during night.
6	73	78	73	74.66	S.	0	E.	0	E.	2	Cloudy	Cloudy	Fair				
7	71	90	75	78.66	S.	0	W.	0	W.	1	Fair	Fair	Fair				Ended early this morning.
8	82	95	78	85.00	W.	1	S. E.	0	N.	5	Fair	Fair	Fair	Night			
9	77	74	70	73.66	W.	2	S.	2	N.	0	Fair	Cloudy	Cloudy	2 p. m.	6 p. m.	0.50	
10	66	68	65	66.33	S. E.	1	S. E.	1	W.	0	Cloudy	Cloudy	Cloudy	7 a. m.	7 p. m.	0.80	Rain all day.
11	72	73	64	69.66	S.	1	S. E.	0	N.	2	Cloudy	Cloudy	Cloudy			1.30	Do.
12	70	82	70	74.00	E.	1	W.	0	N. W.	1	Cloudy	Fair	Fair				
13	74	77	72	75.00	S.	2	S.	0	N.	1	Fair	Fair	Fair	5 p. m.	6½ p. m.	0.60	
14	73	72	65	70.00	W.	0	S.	0	E.	1	Cloudy	Cloudy	Fair			0.40	
15	74	82	75	77.00	N. W.	0	W.	1	E.	0	Fair	Fair	Fair	9 p. m.	Night		
16	74	80	72	75.33	S.	0	S. E.	1	S. W.	3	Cloudy	Cloudy	Cloudy	6 p. m.	Night	0.26	
17	74	86	70	76.66	S. E.	1	S. E.	1	S.	0	Cloudy	Fair	Fair				
18	74	84	74	77.33	S. W.	1	W.	0	S. E.	1	Cloudy	Fair	Fair				
19	74	85	76	78.33	S. W.	0	S. W.	2	S.	0	Cloudy	Fair	Fair	1 p. m.	1½ p. m.	0.05	
20	75	84	74	77.66	W.	0	N. W.	3	S.	3	Fair	Fair	Fair				
21	83	87	78	82.66	W.	0	W.	1	W.	0	Fair	Fair	Fair				
22	88	95	82	88.66	W.	0	W.	0	S.	0	Fair	Fair	Fair				
23	88	80	76	81.33	S.	0	S. W.	3	S. E.	2	Fair	Cloudy	Fair				
24	85	76	70	77.00	S. W.	0	S. W.	0	E.	3	Fair	Cloudy	Fair			0.01	Light showers this p. m.
25	85	91	78	84.66	W.	0	W.	2	N. E.	1	Fair	Fair	Fair			0.01	Do.
26	83	88	76	89.00	S. W.	4	S.	2	E.	2	Fair	Fair	Fair				
27	73	90	75	79.33	S.	3	S. E.	1	N. E.	0	Cloudy	Fair	Fair				

eteorological register for the month of June, 1873, *&c.*—Continued.

Dry and wet bulb thermometer.					Day of month.	Dry and wet bulb thermometer.					
. m.		2 p. m.		9 p. m.		7 a. m.		2 p. m.		9 p. m.	
W. B.	D. B.	W. B.	D. B.	W. B.		D. B.	W. B.	D. B.	W. B.	D. B.	W. B.
66	85	75	73	65	17.....	74	73	86	76	70	71
66	88	75	76	68	18.....	74	80	84	80	74	75
67	86	69	75	70	19.....	74	85	85	85	76	78
72	85	70	74	68	20.....	75	83	84	74	74	73
79	96	72	76	65	21.....	83	80	87	74	78	69
72	78	75	73	69	22.....	88	80	95	80	82	76
71	90	78	75	70	23.....	88	77	80	80	76	73
76	95	84	78	73	24.....	85	70	76	82	70	73
73	74	70	70	69	25.....	85	72	91	77	78	71
65	68	66	65	64	26.....	83	72	88	76	76	70
71	73	64	64	62	27.....	73	71	90	75	75	71
70	82	76	70	65	28.....	75	72	84	77	74	71
71	79	75	72	71	29.....	74	72	81	76	72	70
71	72	68	65	62	30.....	74	71	82	75	73	71
68	82	75	75	70							
72	80	77	72	70	Monthly mean	76.5	72.9	83.5	75.3	73.3	69.5

[These calculations are made from Professor Guyot's tables.]

th.	Relative humidity or per cent. of saturation of the atmosphere at—				Remarks.
	7 a. m.	2 p. m.	9 p. m.	Daily mean.	
	Per cent.	Per cent.	Per cent.		
.....	95.8	60.9	62.9	69.9	
.....	56.3	52.3	64.4	57.7	
.....	66.3	38.7	76.8	58.6	
.....	85.8	44.2	72.0	67.3	
.....	75.6	27.3	52.4	51.8	
.....	93.0	86.3	80.7	87.3	
.....	100.0	56.5	76.8	77.8	Mean temperature for the 10 days, 77.7.
.....	74.7	61.7	77.6	71.3	Mean relative humidity from the 1st to the 10th, 72.
.....	81.7	81.0	94.8	85.8	
.....	94.5	89.5	94.4	92.8	Number of deaths from cholera, 1.
.....	95.0	58.8	88.8	80.9	
.....	100.0	74.7	75.1	83.3	
.....	85.6	82.2	95.0	87.6	
.....	90.2	80.4	83.6	84.7	
.....	72.0	70.8	76.8	73.2	
.....	90.3	86.7	90.0	89.0	
.....	81.2	75.8	89.8	82.3	Mean temperature for the 10 days, 75.1.
.....	90.3	53.5	85.6	76.5	Mean relative humidity from the 11th to the 20th, 82.3.
.....	90.3	68.1	95.2	84.5	
.....	90.4	67.7	85.6	81.2	Number of deaths from cholera, 2.
.....	87.1	69.1	86.3	80.8	
.....	87.8	68.8	82.8	79.8	
.....	80.1	74.1	86.0	80.2	
.....	79.4	90.6	94.8	88.3	
.....	79.4	69.1	90.8	76.8	
.....	75.0	69.1	86.0	76.7	
.....	85.4	69.8	90.4	81.9	Mean temperature for the 10 days, 80.7.
.....	85.8	71.4	85.6	80.9	Mean relative humidity from the 21st to the 30th, 84.1.
.....	90.3	78.4	90.0	86.2	
.....	85.6	70.8	90.2	82.2	Number of deaths from cholera, 29.
mean...	84.3	67.9	83.4	78.5	

Meteorological register for the month of July, 1873, transmitted by M. K. Taylor, assistant surgeon, United States Army.

[Station, Thomas Barracks, Huntsville, Ala.; latitude, ——; longitude, ——; altitude of barometer above sea, —— feet.]

Day of month.	Thermometer.				Movements of atmosphere.						Amount of cloudiness.			Rain and melted snow.			Remarks.
					7 a. m.		2 p. m.		9 a. m.								
	7 a. m.	2 p. m.	9 p. m.	Daily mean.	Winds.		Winds.		Winds.		7 a. m.	2 p. m.	9 p. m.	Began.	Ended.	Quantity.	
					D.	F.	D.	F.	D.	F.						*Inches.*	
1	85	90	80	85.0	W.	0	S.	1	W.	2	Fair	Fair	Fair				
2	80	90	81	83.66	W.	3	S.	1	S.	0	Fair	Fair	Fair				
3	82	94	82	86.00	W.	1	S. W.	2	W.	0	Fair	Fair	Fair				
4	87	95	83	88.33	S. W.	2	W.	3	S. W.	1	Fair	Fair	Fair				
5	84	95	85	88.00	S.	1	W.	5	E.	1	Fair	Fair	Fair				
6	85	96	80	87.00	W.	2	W.	3	N. E.	0	Fair	Fair	Fair				
7	76	91	78	81.66	W.	0	W.	1	N. W.	0	Fair	Fair	Fair				
8	78	85	70	77.66	W.	0	W.	4	N. E.	0	Fair	Fair	Fair			0.01	Light shower during night.
9	73	84	78	78.33	W.	2	W.	2	N. E.	1	Fair	Fair	Fair				
10	75	90	75	80.00	W.	0	W.	1	N. W.	0	Fair	Fair	Fair				
11	83	92	78	84.33	N. W.	0	N. W.	2	N.	1	Fair	Fair	Fair				
12	86	91	79	85.33	N.	0	S.	1	S. W.	0	Fair	Fair	Cloudy				
13	84	92	77	84.33	N. W.	2	S. W.	1	S.	0	Fair	Fair	Fair			0.01	Light shower at 9 p. m.
14	85	94	78	85.66	S.	0	S. E.	1	S. W.	0	Fair	Fair	Fair				
15	86	94	80	86.66	W.	0	W.	0	W.	0	Fair	Fair	Fair				
16	78	80	76	78.00	S.	0	W.	0	S. W.	0	Cloudy	Cloudy	Cloudy	12½	2	0.50	
17	79	95	77	83.66	S.	1	S. W.	0	S.	1	Fair	Fair	Fair				
18	84	89	74	82.33	S. W.	0	W.	4	N.	1	Fair	Cloudy	Cloudy	5	6	0.50	
19	75	85	73	77.66	S.	0	S.	0	N. E.	1	Fair	Cloudy	Fair			0.01	Light shower at 12 m.
20	71	84	68	74.33	E.	0	W.	1	N. E.	0	Cloudy	Fair	Fair				
21	76	82	73	77.00	W.	0	N. E.	0	N. E.	0	Fair	Fair	Fair				
22	71	86	76	77.66	N. E.	0	S. E.	2	S. E.	0	Cloudy	Cloudy	Cloudy			0.23	
23	76	82	78	78.66	E.	0	S.	0	S. W.	0	Cloudy	Cloudy	Fair				
24	77	80	76	77.66	S.	0	W.	0	W.	0	Cloudy	Cloudy	Fair	7	7½	0.24	
25	77	88	70	77.66	S. E.	0	S. W.	2	S.	0	Cloudy	Cloudy	Fair				
26	76	90	75	80.33	S. W.	1	S.	0	S. W.	2	Fair	Fair	Fair				

teorological register for the month of July, 1873, *&c.*—Continued.

y and wet bulb thermometer.					Day of month.	Dry and wet bulb thermometer.					
m.		2 p. m.		9 p. m.		7 a. m.		2 p. m.		9 p. m.	
W. B.	D. B.	W. B.	D. B.	W. B.		D. B.	W. B.	D. B.	W. B.	D. B.	W. B.
85	90	81	80	73	18.....	84	80	89	87	74	72
77	90	80	81	76	19.....	75	75	85	77	73	71
78	94	84	82	77	20.....	71	67	84	68	68	65
81	95	83	83	79	21.....	76	70	82	67	73	65
78	95	81	85	75	22.....	71	67	86	71	76	73
78	96	80	80	76	23.....	76	73	82	76	78	75
72	91	75	78	74	24.....	77	75	80	75	76	70
72	85	75	70	67	25.....	75	73	88	79	70	68
70	84	72	78	74	26.....	76	73	90	80	75	73
72	90	75	75	70	27.....	77	75	94	81	79	75
72	92	76	78	74	28.....	75	73	93	80	79	74
74	91	74	79	76	29.....	76	74	85	78	77	75
76	92	75	77	75	30.....	75	73	84	76	76	73
77	94	80	78	75	31.....	78	75	83	74	77	74
78	94	74	80	74							
75	80	75	76	75							
76	95	86	77	74	Monthly mean	78. 9	74. 4	88. 8	77. 8	77. 0	73. 4

[These calculations are made from Professor Guyot's tables.]

th.	Relative humidity or per cent. of saturation of the atmosphere at—				Remarks.
	7 a. m.	2 p. m.	9 p. m.	Daily mean.	
	Per cent.	Per cent.	Per cent.		
.....	83. 4	66. 3	70. 1	73. 3	
.....	82. 4	100. 0	78. 4	86. 9	
.....	82. 8	64. 4	78. 7	75. 3	
.....	76. 1	58. 6	83. 0	72. 6	
.....	75. 3	52. 7	60. 9	66. 3	
.....	71. 8	45. 7	82. 4	66. 6	
.....	81. 5	44. 8	81. 9	69. 4	Mean temperature for the 10 days, 83.5.
.....	73. 4	86. 3	86. 7	82. 1	Mean relative humidity from the 1st to the 10th, 73.6.
.....	86. 0	53. 5	81. 9	73. 8	
.....	85. 8	47. 2	76. 8	69. 9	Number of deaths from cholera, 14.
.....	56. 4	45. 4	81. 9	61. 2	
.....	54. 5	41. 9	86. 0	60. 8	
.....	67. 7	42. 5	90. 7	66. 9	
.....	71. 8	35. 7	81. 9	63. 1	
.....	64. 8	52. 2	78. 2	65. 2	
.....	86. 3	78. 2	95. 2	86. 6	
.....	86. 5	68. 0	86. 2	80. 2	Mean temperature for the 10 days, 82.2.
.....	83. 2	91. 9	90. 3	88. 5	Mean relative humidity from the 11th to the 20th, 72.7.
.....	100. 0	68. 1	90. 2	86. 1	
.....	80. 2	40. 3	84. 3	68. 3	Number of deaths from cholera, 9.
.....	72. 7	42. 2	62. 9	59. 3	
.....	80. 2	44. 8	86. 0	70. 3	
.....	86. 0	67. 7	86. 3	80. 0	
.....	90. 7	78. 2	72. 7	80. 5	
.....	90. 4	65. 6	89. 8	81. 9	
.....	86. 0	63. 0	90. 4	77. 8	
.....	90. 7	55. 2	82. 2	76. 0	
.....	90. 4	51. 8	77. 9	73. 4	Mean temperature for the 11 days, 79.2.
.....	90. 6	71. 8	90. 7	84. 4	Mean relative humidity from the 21st to the 31st, 76.5.
.....	90. 4	67. 7	86. 0	81. 3	
.....	86. 3	57. 4	86. 2	76. 7	Number of deaths from cholera, 6.
mean...	80. 7	59. 7	82. 5	74. 3	

B.—EPIDEMIC CHOLERA AT HUNTSVILLE, ALA

By J. J. Dement, M. D., *Chairman of the Board of Healt*

Huntsville is situated at the base of the last western Cumberland Mountains, ten miles north of the Tennesse eighteen miles south of the Tennessee and Alabama State an elevation of 692 feet above tide-water at the city of M tude 34° 43′ 44″. In 1870 the city had, according to the census, a population of four thousand nine hundred and se two thousand five hundred and thirty-two were whites, a sand three hundred and seventy-five were colored. Th probably but little change since that time.

The character of the surface upon which a greater porti is built is such as to afford abundant drainage, being natural water-sheds, which prevent the water from coll portion of the city. The surface-soil is a dark, rich loam of pure red clay, resting on a solid limestone base. This city is well supplied with water, mainly from a large spring stone water which bursts from the base of the bluff on wh tion of the city is built. The water is pumped into a res top of the hill, and from thence supplied to the city. Thi ever, is by no means in universal use, as many premises hav yield freestone water after having been dug into the clay from 30 to 50 feet.

Descending gradually about 80 feet from this high and portion of the city in all directions, except easterly in th the mountains, is a low, flat, ill-drained region, in which many years ago a number of ponds and marshes, which hav ally filled by washings from the adjacent elevations, as we *débris* from the older parts of the city which have been ca from time to time. Many of these places still exist, and usually wet season retain water until midsummer, creating orders among the individuals living in their vicinity. T in many places is from 1 to 4 or 5 feet deep, beneath wh places a yellow gravelly subsoil, at others, a white or re which is much more porous than the subsoil of red clay i parts of the city.

In these districts the colored population preponderate. tenement-houses, which are simply wooden huts, not eleva ground. The water in this district is freestone, and o wells which are from 10 to 30 feet in depth. These well spring and early summer of 1873, were filled to the level o with surface-washings.

The Memphis and Charleston Railroad runs along the w of the city, and in close proximity to the portion which made ground. There are upon this road two daily passeng Memphis and Chattanooga, which connect with the train ville, Tenn. At this point are located the railroad-shops fo division of the road, and all passing trains, freight as well change officers and men at Huntsville.

Previous to the outbreak of cholera it was observed that unusual number of intestinal diseases, generally of a mild was also observed that we had much less of those forms of erally regarded as having their origin in malaria.

eral weeks prior to the first death from cholera in our midst, e had been prevailing in Memphis, Nashville, and many of r cities and towns of Western and Middle Tennessee; and direction of the board of health, which had just been organ- uthorities had the city placed in as good hygienic condition sible in so short a space of time.

e center of the low, flat region on the western side of the city, yards from the depot of the Memphis and Charleston Rail- on the main street leading to the business portion of the city, se of cholera occurred in the person of a negro girl, five ge, the child of Toliver Thompson. The family consisted of his wife, and five children; they had lived in the vicinity for s; had no boarders, and received, they state, but few visitors. ation of Thompson was that of cart-driver, and for some time the attack of his child was employed by the city in remov- from the streets.

ately south of Thompson's house was a pond which had been lled, but which yet contained a considerable quantity of dirty most on the brink of this pond was located the well which he water-supply of the family, and which was at the time e brim. On the morning of June 3, the girl was taken with ainless, and odorless diarrhœa. At 10 o'clock a. m. she com- vomit colorless water, and her mother says became very cold, d thirsty. No medical aid was obtained until 5 o'clock p. m., was seen by Drs. Bassett, Buiford, Carter, and the writer. t was *in articulo mortis*, and died almost at the moment of The surface of the body was found shrunken, and the skin ds and feet shriveled. No other case of the disease followed of this child.

, twelve days after the death of the Thompson child, the the Huntsville cases occurred in the person of Joe Smith, a l thirty-five years, who had been for several months a waiter rant in Decatur, Ala., from which town he had arrived some prior to this attack. This man had no home or employment. wherever night overtook him, and ate wherever he could eal. Where he had been or what he had been doing through weeks cannot be determined. Smith during the night of as taken with a diarrhœa, but received no medical aid until . m. the next day, when Dr. Buiford found him in collapse, d during the succeeding night. This case occurred in a house same street, and directly opposite to that occupied by the family.

16th of June, Mrs. Susan Pollard, aged seventy-four, living half miles west of the city, upon the line of the Memphis eston Railroad, was taken with a slight diarrhœa, was worse th, and was in cholera-collapse on the morning of the 18th. uring the succeeding night. This lady had walked to Hunts- ne morning of June 14, and had remained with her children square of the houses occupied by the first and second cases afternoon of the 15th, when she returned home on foot over d-track, and was drenched on the way by a shower of rain.

raham, aged forty-five years, whose residence and store-house diately south of the premises occupied by the first case, was ith cholera on the morning of the 19th of June, and died on Two other members of his family had the disease within a but recovered. Larkin, a negro, aged twenty-six years, who

waited on Mr. Graham, and who assisted in shrouding his
the disease on the night of the 21st of June, and died at 8
of the 22d. The same day (June 21) a negro child living i
in which Joe Smith had died was taken with the disease,
six hours.

From this case it is impossible in this portion of the city
connection of the cases; the disease became epidemic, att
white and black, and extending in all directions. Taking
which Joe Smith died as a center, and describing a circle
dred yards in diameter, we find that fifty cases of cholera
that area within the space of ten days from the developme
ease in the person of Smith.

On the 16th of June, the disease was introduced into
portion of the city through the person of Louis Harris, a
years of age, who was the proprietor of a drinking-saloon,
place of great resort for negroes from all portions of the
was taken with cholera while at his saloon, which was in t
the city, and was immediately removed to his home, whi
locality known as Georgia, inhabited almost entirely by ne

This eastern portion of the city has the same physical ch
as the western portion, the same defective drainage, the sa
of water, and the same kind of ponds and marshes.

Harris was fully collapsed in the afternoon of the 16th
during the night, slowly recovered, and was discharged qu
cent on the fourth day.

June 23, five negroes who lived in the immediate vicin
were taken with cholera, and all died within thirty-six hou
time the use of well-water was forbidden by the board of
portion of the city, and the people were supplied with wa
Great Spring, which was carted in quantities for their us
authorities. This supply of water was furnished for the
week, during which time no new cases of the disease occur
negroes, thinking themselves secure, resumed the use of th
and, within four days, six fatal cases of cholera occurred
vicinity. The use of well-water was again prohibited, an
progress of the disease was arrested.

When it became generally known that cholera was epi
city, many of the citizens removed to the country with th
Among these families six cases of cholera are known to ha
One gentleman sent his family to his plantation, ten miles f
After remaining there for three weeks they returned to H
remained two days, and again went to the country. Thr
their return from the city, a little boy in the family wa
cholera and died in a few hours; the same day a lady, fifty
was attacked, but recovered. The family now returned t
at Huntsville, when all, both white and black, were affec
disease, from which an additional death occurred. None
men or their families on this plantation were affected with

Forty or fifty persons removed from Huntsville during
to Monte Sano, a mountain four miles east of town. Amo
sons there were three cases of cholera, one of whom died
was attacked in two days, one case in fourteen days, and
twenty-three days after they had left Huntsville.

Some persons took refuge at Johnson's Wells, a waterin
miles north of Huntsville. At this time there were nearl

e wells. One case of cholera occurred, and died after an ill-
rty-six hours. No other case occurred.
woman, who lived six miles in the country, came to town to
aughter, who was ill with the cholera. She remained three
eturned to her home. On the sixth day after her return she
with the same disease and died. On the plantation were
persons, but among them no new cases occurred.
and well-drained portions of the city remained almost ex-
the disease, only eight or ten cases having been reported, and
m only two deaths.
he prevalence of the epidemic we had every form of the dis-
slight borborygm, with watery, easy diarrhœa, to that of the
nant type. Under these circumstances it is impossible to give
an approximation to the number of cases. We have, how-
ts of about one hundred and fifty cases so well defined as to
ubt as to their true character. Of the whole number there
ne deaths; of these seventeen were whites and thirty-four
es. Very nearly all the cases which terminated fatally were
state of collapse by the attending physician when first called
. Only four cases are reported as having recovered from
ion. The disease was found to be amenable to treatment,
he early stages. The last case which was reported occurred
of July.

COUNTY.

CHOLERA AT BIRMINGHAM, ALA., IN 1873.

By M. H. JORDAN, M. D., *Member of the Board of Health.*

ing a history of the recent epidemic of cholera as it prevailed
ham, I will not discuss any theories nor indulge in any idle
s, but will confine myself strictly to a simple, concise, narra-
nts.
e city was terribly scourged for long weeks; our citizens
nic-stricken; many left, almost depopulating the town, and
sick and indigent principally in the care of clergymen and
The latter class, however, did not escape the disease, but
r number lay for many days and nights upon the brink of
nd it was only by the intervention of an all-wise Providence
iduous care of their attendants, that they recovered.
am is located in Jones Valley, near the center of Jefferson
th the Red Mountains lying a short distance to the south
nd what is known as Reservoir Ridge to the north and west.
near the surface is blue limestone, covered with a stiff clay
s is usually found in the hilly portions of Central Alabama.
f the valley is formed by the old Silurian limestone, which
as brought to the surface through the superincumbent strata,
d throughout the entire valley, almost on edge, dipping, as
rom the valley, to the northeast and southwest. From this
led to conclude that the only water that appears on the sur-
ound in wells in this valley must be surface-water, for the
mestone are not water-bearing, and only afford such supply
may have filtered through the strata of earth overlying the
is formation during the winter or rainy months, which finds
tlet in a southwest direction along the line of upheaval.
finds numerous outlets at various points in the valley, as is

shown by the location of the springs, to be seen on the accompanying map, all of which, with others northeast and southwest of Birmingham, are situated on the line of upheaval.

Birmingham is a railroad center, having about three thousand inhabitants, a large number of whom live in houses closely crowded together, and in defiance of sanitary laws. Each day four railway-trains pass through this town, making direct connection with Nashville, Chattanooga, and Louisville, in the north, and Montgomery, Mobile, and New Orleans, in the south. In addition, from six to eight freight-trains each day receive and discharge freight. The mineral interests in the neighboring mountains attract to the town many strangers, and during the summer months the transient population is quite large.

The ground upon which the city is located is undulating, with many elevations and depressions, in some places affording fine natural drainage; in others it is low and marshy, and remains damp throughout the entire year.

The inhabitants of Birmingham were in 1873 supplied with water from two sources. A most admirable system of water-supply had been instituted, but the work had only advanced sufficiently to supply a small portion of the city. This supply was obtained from a large creek northeast of the city, distant nearly two miles, and separated from Jones Valley by a high ridge, on the summit of which was located the reservoir, which is over one mile from the center of the city.

The inhabitants who could not yet reach this water-supply, made use of several public wells and springs within the city limits, or were obliged to haul it from springs at the foot of Red Mountains. The public wells and springs referred to were in low, damp places, and so situated that they received the washings from a large surface of ground; and it was only at such points that water could be obtained. For that portion of the city north of the railroad, (see map,) being built over the greatest dip of the limestone rock, water could not be obtained. South of the railroad, where the rock-bed is nearer the surface, water is obtained from private wells. But one house in the city was supplied with a water-cistern.

In the eastern portion of the city there is a pond, (marked A,) from which flows a small branch, which takes a westerly direction, crosses Twentieth street through a culvert, and continues in the same direction to the corner of Seventeenth street and Second avenue, where it unites with two other small branches from the south side of the railroad, (marked B and C.) At their junction these streams spread out and form a low, marshy ravine, overgrown a portion of the year with tall grasses, which continues in the same direction beyond the limits of the corporation. On the northern side of this ravine, (marked E,) from Eleventh to Fourteenth street, which pass along a hill-side, a number of shanties and negro cabins, low, dirty, and ill ventilated, were located, which were known as "Baconsides." (See map.) By each rain-fall the filth of all kinds which covered the ground around these cabins was washed into the ravine, and it was from a low spring and a number of barrels sunk in the marshy bottom of this ravine that the inhabitants of Baconsides and many of the white residents of Birmingham obtained their drinking-water.

Until the alarm of cholera was sounded upon the streets, no effort was made by the city authorities to clean the streets and alleys, to drain and disinfect cess-pools and wet places, nor had cleanliness been demanded in privies and stables.

The first case of cholera that occurred at Birmingham in 1873 was

MAP

OF PART OF THE CITY OF

BIRMINGHAM

ALA.

SHOWING THE LOCATION OF THE CASES OF

CHOLERA

IN

1873.

The cases from 1 to 15 inclusive are designated by figures.

THE SMALL TRIANGLES ☐ SHOW WHERE THE CASES ARE LOCATED.



AN PHOTO-LITHOGRAPHIC BLANK "RESPECTFULLY FURNISHED"

on of a Mr. Y., who was taken sick on the 12th day of June
fter an illness of twenty-four hours. He was an able-bodied
had been in the city about six weeks, and had been perfectly
til the arrival of his bed and bed-clothing, which had been
him from Huntsville, and which were received and used by
days before he was taken with the disease; and it was subse-
termined that these articles had been used in the portion of
Huntsville that was infected with the disease. Y. was taken
ra at the point marked 1 on the map. His physicians had no
that he had cholera at that time, although his symptoms
embled it, as there had been no cases of the disease in this
the State.

was taken to disinfect the discharges, which were thrown on
in the rear of the house, on the slope of the hill, immediately
branch marked D.

cases occurred until June 17, when a young girl named,
d her sister were taken with cholera within a few hours of
, and both died within twenty-four hours. The home of these
ee map 2) was in a miserable little hovel near the edge of a
ch (marked F) which runs through several acres of low,
ound. It was determined that the different members of this
been constantly at the house of Y., the first case, during
The discharges from these patients were not disinfected,
rown into the branch, which flows down to the same marshy
m which the inhabitants of "Baconsides" obtained their
ater.

a man named Bennett, who was a shoemaker, and lived at
arked 4 on the map, was taken with cholera, and died after
f eighteen hours. This man had been absent from home for
ks, and returned, suffering with an acute diarrhœa, from Chat-
e night previous to his attack. The discharges in this case
fected, and the bed and bed-clothing were burned. Under
n which this man died was a damp, filthy cellar, which had
full of water in the early spring.

a comrade of Bennett, who had waited upon him in his illness
rried out the discharges, was taken with cholera, and died in
rs. The excreta were disinfected and buried.

a sister-in-law of Bennett, who was constantly with him
eath, was taken with cholera at her house, (marked 6,) and died
ours. The discharges of this patient were not disinfected,
hrown into the branch in rear of the house.

a negro boy was found in a low, dirty shanty close by the
Alabama and Chattanooga Railroad, (marked 7,) in a state of
nd he died in a few hours. In the evening of the same day a
ed Edwards was taken with the disease at his home on the
he ravine marked C. The disease was fully developed, but
as established, and he recovered.

a negro named Eubank was taken with the disease at the
f a gentleman, (marked 9.) He had copious rice-water dis-
old skin, profuse perspiration, small, frequent pulse, and
he extremities; he responded to the treatment and recovered.
was taken to disinfect and bury the excreta. He was kept as
ted as possible, and no other case was developed on the prem-
he immediate neighborhood.

ame day several cases of cholera occurred at Baconsides, all
rminated fatally within twenty hours. No disinfectants were

used; the excreta were thrown upon the ground; the epider augurated, and deaths occurred in every household. At firs negroes in this portion of the city who took the disease inva within a few hours; but when the violence of the epidemic subside, many recovered.

Along the banks of the branch marked C upon the map ar of cabins, in one of which Edwards, the case of June 22, had and in one of these cabins, on the 24th, Minerva, a negro g nursed Edwards and carried out the dejections, was attacke within ten hours. Before this girl's body was buried, two occurred in the same cabin, which rapidly proved fatal. The in these cases were disinfected and buried, and by order of health the beds and bed-clothing were burned. The occupan cabins upon the line of this branch suffered so severely with that they were abandoned.

June 27, Hughes, the father of the two girls who died upo was taken with cholera, and died on the following day; the in the same house, out of a family of five individuals.

July 1, cholera was declared epidemic over the entire city ham, and it is now impossible to give step by step the prog disease, for the spread of the disease was so rapid and its great that the physicians could take no time to record cases.

July 2, Mr. M., who was a clerk in the city, but who slept at Elyton, distant two miles, was attacked with cholera, and ten hours. The excreta of this case were disinfected with c and buried. No other case of the disease occured in the vi

July 4, an excursion party of about two hundred of the Birmingham visited Blount Springs, some thirty-odd mile the line of the South and North Alabama Railroad. The day in eating, drinking, dancing, &c., and returned to about 8 o'clock in the evening. Before daylight the next d their number had died of cholera.

July 7, a Mrs. H. had slight symptoms of diarrhœa, and to go to the house of her father-in-law, who lived on the to Mountain, distant about eight miles. The next day she wa cholera, and died in twenty-four hours. Her mother-in-law, her carefully until her death, was taken with cholera July 10, twelve hours. The discharges from these cases were re cloths, which were washed out, and the water thrown upon the back-yard, but after the arrival of a physician they were and buried, and the beds and bed-clothing were burned. No of cholera were developed in this family, although several it suffered from diarrhœa.

July 9, was called to see Lee Anderson, the carria Colonel T., who lived in an elevated portion of the city, in had been to this time no cholera, and found him with the the disease strongly defined. This man had remained well visited some of his friends at Baconsides. His system resp remedies exhibited, and late in the evening he had fully rea next morning at an early hour was found fully collapsed. covered that during the night he had several times left had gone to the cistern on the premises for drink, and several dejections in the yard, which were not disinfected. a few hours.

July 10, Colonel T., his wife, and several members of his taken with diarrhœa, which, with the exception of Mrs.

the remedies used. This lady, however, fearing that the ight injure her sucking child, concluded to dose herself with iver regulator, a proprietary medicine much in vogue through- thwest; and the next day an attack of cholera was fully She however reacted, and for several days seemed con- her dejections contained bile; the secretion of urine was ed, but on the fifth day she sank and died. This lady had ed to the disease by assisting in washing and dressing the Mrs. K., who had died of cholera a few days previously in tion of the city.

ises of Colonel T. was one of the few in the city which were ith cisterns of rain-water, and the generous owner, thinking n-water was the safest for drinking purposes, allowed free s water-supply to all in his neighborhood. In this portion no cases of the disease occurred until after the negro Ander- o Baconsides; but after his death the persons who used this er, and the immediate neighborhood of Colonel T.'s property, severely, if not worse, than any other portion of the city.

popular hotel in the city, located close to the line of the rail- nd which the disease prevailed, escaped the disease. This ilt upon pillars several feet above the surface of the ground, ee ventilation. The drainage was admirable, the water- d, and the proprietor spared neither time nor expense in keep- nises clean and disinfected.

served during the course of the epidemic that wind from the east, or that blowing from Baconsides to the more populous the city, increased the violence of the disease and the rate tality, while when it came from the north and west there led moderation in the severity of the symptoms.

hower of rain apparently aggravated the disease. These re unaccompanied with thunder, of short duration, and the heat was intense.

been stated by some physicians of local repute in the State sease which prevailed at Birmingham was not epidemic chol- oper to state that the exhibition of the disease, both in its n, its mode of communicability, and in all its symptoms, fully followed the history of cholera as it is laid down by

e treatment of the premonitory diarrhœa was most success- uted, and the general expression of the profession of this city not a single instance where this stage of the disease was d where the patient followed fully the orders given, did the ance to its second stage; and so marked was this immunity lesired to add to the testimony on record, that by proper pre- nd the observance of hygienic laws, cholera attendants may nost perfect security from the disease.

atment adopted was the opium and mercurial. When the emed so inactive that nothing made any impression upon it, of mustard, salt, ginger, and pepper, suspended in hot water, ases produced a warm glow over the surface of the body in a nts. For the relief of cramps which would not yield to ordi- dies, a number of dry cups applied from the neck to the er the spine, in every case in which they were used furnished d relief. The use of iced water *ad libitum* was found injuri- any instances the unrestrained gratification of the thirst was y a fatal relapse. Ice and ice-water in small quantities and

at short intervals was found most useful. Many of the cases plicated with uræmia, and the majority of these died, although carefully treated. Diuretics produced no good results. No c life, sex, or age escaped. The sucking babe and those of e suffered alike from its ravages.

Before closing this paper, justice demands that we should lude to the heroic and self-sacrificing conduct, during this e that unfortunate class who are known as "women of the tow poor creatures, though outcasts from society, anathemati church, despised by women, and maltreated by men, whe lence swept over the city, came forth from their homes t sick and close the eyes of the dead. It was passing strang would receive no pay, expected no thanks; they only went presence was needed, and never remained longer than they co While we abhor the degradation of these unfortunates, the mous behavior during these fearful days has drawn forth thy and gratitude.

In closing this brief record we desire to state that, in the of our observations, facts will not justify us in believing th conditions of the soil, or peculiarity of climate, or moistu mosphere, or masses of decomposing *débris*, either animal o can in or of themselves produce the specific poison of ch they are the hot-beds in and on which the cholera excreti been placed, the poison is reproduced with fatal rapidity."

BIRMINGHAM, ALA., *August*, 1874.

MONTGOMERY COUNTY.

REPORT OF A CASE OF EPIDEMIC CHOLERA WH CURRED AT MONTGOMERY, ALA., IN 1873

BY T. A. MEANS, M. D., *Health-Officer of that year.*

John Rogers, aged thirty-three years, a negro of intempe left his home at Montgomery to nurse the cholera sick at E some time during the month of June, 1873, and remained un of July, when he returned to his home on the evening of the Meeting his former companions he indulged freely in mixed ate largely of stale vegetables, unripe fruits, &c. After his bauch he returned to his quarters in the southeastern por city, threw himself upon the bare floor without covering soundly until about 4 o'clock a. m., when he was seized w vomiting and purging, the matter cast off being only the the night before. He looked upon this attack as simply ch bus; therefore refused medical aid until 3 p. m., when his wif alarmed, called in Drs. Williams and Michel, who recognized one of cholera, and so informed me. I visited him immed found him presenting the following symptoms:

Skin cold and clammy; pulse at the wrist, small, weak, a ated; tongue cold, moist, and not much coated; stools rem pious, pale, free from odor, and passed without effort, often t in a continuous stream as far as two feet from his person. men was tense and the pulsation of the abdominal aorta dist ble. He seemed depressed and spiritless, with constant tos body from side to side. He made no complaint, either of

t that dependent upon cramps, which seemed only to occur
y preceding a discharge from his bowels. I had him removed
the city hospital, and remained with him until his death,
rred at 9 o'clock and 20 minutes p. m.
'clock p. m. the above symptoms remained unchanged, when
vious features of the stage of collapse came on. The entire
is body became intensely cold; the skin and nails assumed
t, and the skin of the hands and feet wrinkled, sodden, and
o pressure; yet he complained of oppressive heat of body,
constant effort to throw off the covering; the eyes were
p in their orbits; the countenance assumed a cadaverous
rst from the first, with a constant craving for cold drinks.
ue, yet moist, was white and cold; oppressive sense of heat
ed of at the epigastrium; suppression of urine; no bile in
ejected, nor was there seemingly any secretion of saliva.
which from the first was husky and feeble, now became weak,
d hollow; respiration oppressed and slow; breath deficient

ck p. m. the pulse at the wrist became extinct, and could be
th firm pressure over the larger arteries. Coldness of body
the spasms, heretofore violent, now grew less severe, but more
hilst the heat of the head increased quite sensibly.
as it became known that this was a case of cholera, every
e house and left the patient to himself. Upon my arrival I
emises cleansed, and a solution of copperas and crude car-
zeu parts of the former to one of the latter, liberally applied
without the house.
ing the hospital I took the same precautions; isolated the
d had each discharge absorbed with a large sponge saturated
rbolic acid solution, which solution was also freely used in

now recall what remedies were applied by Drs. Williams and
t from his wife I learned that she had given him at his re-
n first attacked, a teaspoonful of laudanum in half a glass of
sides having his feet bathed, and flannels wrung out of hot
applied to the stomach and bowels. I found his stomach
rst too sensitive to retain anything, even cold water; and then
spoonfuls could it be given at a time.
opium, nitrate of potassa, were given, but immediately re-
y-heat frictions with open hands, sinapisms over the stomach
, ankles and wrists, and a free application of lard over the
, constituted the treatment after his arrival in the hospital.
ed himself relieved when the lard was applied, and would
or it.
th day of July, 1873, at the instance of the board of health,
thorities took active measures to have the city cleansed and
disinfected. A quarantine was established against cholera-
stricts. These measures were promptly and faithfully carried
r which we might have had a visitation of cholera equal in
severity to that of our sister city Birmingham. The dread
reak of yellow fever too, at this time prevailing in Pensacola,
lveston, and other points, stimulated the profession as well
icipal authorities to work with all the energy and means at
mand to place our fair city in the best possible sanitary con-

ns and agents employed were the thorough cleansing of privy-

vaults, sinks, and alley-ways; the application of a solut
of iron and crude carbolic acid, ten parts of the first to
lime, coal-tar, and charcoal were also liberally spread up
ities and open surfaces.

It is well to add, perhaps, that the board of health, a
porate body, working under a charter from the State, h
act, being held subordinate to the municipal council. N
all this, co-operation with the board was cordially enter
city authorities.

To the joint efforts of these two bodies, together with
effort of each citizen more than anything else, must be
exemption from an epidemic of cholera in 1873.

MONTGOMERY, ALA., *September* 7, 1874.

BARBOUR COUNTY.

The Eufaula News of July 16, 1873, contains the follow
"The painful bowel-disease, of which we made ment
since, seems to have abated but little. There are now
cases of illness in town."

As Eufaula is an active cotton-market, within the lim
tion of the Chattahoochee River, and is the eastern te
Montgomery and Eufaula and Vicksburgh and Brunswic
well as the western terminus of the Southwestern Railroa
direct communication with cholera-infected districts, a le
formation was forwarded to Dr. Z. T. Daniel, the secreta
bour County Medical Society, in reply to which the follo
been received:

"EUFAULA, ALA., *Aug*

"Dr. ELY MCCLELLAN, *United States Army:*

"MY DEAR DOCTOR: Your communication, with forms
ceived last evening.

* * * * * *

"It becomes me to say, however, that I have never
cholera here, nor has there ever been a case of epidemic or
developed in or brought to this place within the knowledg
physicians. There have been slight choleraic attacks t
summer, but nothing like an epidemic.

"About the time cholera was prevalent in Louisville, Ky.
was an increase of gastro-intestinal complaints, some of
suspicious collapse, but no case was pronounced cholera
doctors. I write this after having consulted all reliab
information.

"Eufaula was quarantined (in 1873) against Montgomery,
place.

"Yours, very respectfully,

"Z. T.

The omitted portions of the above letter refer only to
County Medical Society.

CHAPTER XV.

GINIA GROUP.

WEST VIRGINIA CONTRIBUTORS.

Jepson, Health Officer, Wheeling.
Wall, Huntington.

INITIAL CASE.

Ohio County, June 9.

RA EPIDEMIC OF 1873 AT WHEELING, W. VA.

BY DR. S. L. JEPSON, *Health-Officer.*

A report by me appeared in the Transactions of the American h Association for 1873. *In a few non-essential points that from this. It was written very hurriedly, and I desire this egarded as the correct one.*—S. L. J.]

e of contributing some little aid to the study of epidemic existed in the South and West during the spring, summer, of 1873, I herewith transmit as full and accurate a history f the disease as it occurred in Wheeling, W. Va., of which that time and still am health-officer. I desire in the out- at, as the cholera of 1873 was the first I had ever witnessed, its study with no preconceived theories, and only such as has been derived from the standard medical works of ence my report, with any remarks that may be added, shall ith the sole purpose of relating the facts as they occurred, h such deductions as may be fairly drawn from them. In ore perfect understanding of the facts here given, and as ring upon the sanitary condition of Wheeling, a few words ography of the city may be necessary.

TOPOGRAPHY, ETC.

is situated in latitude 40° 7′ north, by longitude 80° 42′ west, nty, W. Va., on the east bank of the Ohio river. Its aver- is 640 feet above the sea-level. The original town was plateau, elevated some 80 or 90 feet above the level of the is a declivity of some 40 feet in this plateau, to the level of ottom" proper, upon which nearly three-fourths of the city e general level of the "river-bottom" is 40 feet above low- The eastern boundary of the city is flanked by hills, having ude of about 700 feet. * * Its length along the river is iles, with an average breadth of one-fourth mile. The lowest ubject to inundation during high floods of the river. Two occurred in December, 1872, at which times parts of the ighth wards were covered with water. The same was true of

the Seventh ward, which occupies Zane's Island, in the Ohio river, and which, as it contained no case of cholera, we may here dismiss from further notice. The remaining portion of the city is divided into wards, which are numbered from north to south as follows: First, second, third, fourth, fifth, sixth, and eighth, the first being on the highest, and the eighth on the lowest ground. The city is divided between the Fourth and Fifth wards by Wheeling Creek, which is of considerable size, except in the very dry weather of summer, when it becomes low and quite offensive by reason of the waste products of soap-factories, oil-refineries, and slaughter-houses, as well as the sewage from several city sewers emptying into it. This creek is bridged at three points. The Sixth and Eighth wards are separated by a large common, through which a small stream runs. This common is now rapidly filling up with houses, but in 1873 it contained only a few scattered dwellings. A horse-car track extends from about the center of the Eighth ward to the extreme northern end of the city, and the cars are freely patronized by those living in this ward. In 1873 the population of the city was 26,000.

WATER-SUPPLY.

Water is pumped from the Ohio river into a "basin" situated high up on Wheeling Hill, and is thence distributed to all parts of the city through iron pipes. The Eighth ward until recently constituted a separate corporation, and was supplied with water from wells. Quite a number of these wells still remain, and the water from them is used as formerly by those not supplied with water from the basin. No means are provided for filtering or otherwise purifying the water in the basin, and its character is hence much influenced by rains, which cause it to become quite turbid, and after heavy rains a thick sediment of clay will settle in the bottom of the vessel, if water be permitted to stand for any length of time. The summer of 1873 being an unusually wet one, this condition of the water existed very frequently. Mr. Charles E. Dwight, of this city, gives the following as the average quantitive analysis of our water for the month of July and part of August, 1874. The mean temperature was 76° Fahrenheit:

Water	999.14150
Carbonate of lime	.02763
Carbonate of magnesia	.00531
Carbonate of iron	.00725
Sulphate of lime	.01294
Chloride of sodium	.02965
Silica	.01475
Alumina	.01210
Organic matter	.03687
Suspended matter, (clay, silica, lime, and organic matter not in solution)	.71200
	1000.00000

SANITARY ASPECTS.

While few cities are so favorably situated for good drainage as Wheeling, few are possessed of as little improvement looking to the perfection of drainage. The city is very meagerly supplied with sewers, and is likewise but poorly paved. Many of the streets and almost all the alleys south of the creek already referred to are entirely unpaved, while that portion of the city is also most deficient in sewers. The waste-water from hydrants, kitchens, and stables, therefore, finds its way into the alleys and street-gutters, while the solid offal is generously deposited in the same public place, in the confident expectation (by the assessor)

dy removal by some of the innumerable hogs that are per-
roam at will through the city as unpaid, and therefore eco-
nitarians; at least, this is the theory upon which the law is

nsequence of the absence of proper sewerage, the city con-
few water-closets, the out-door privy-vault being used almost
y in their stead. In many parts of the city, indeed in parts
ard except the Seventh, owing to the water-saturated condi-
ground, it is impossible to dig a vault to any considerable
hout a liability of its becoming soon filled with water. In
s this condition exists at a depth of three or four feet, and is
always worse in wet seasons. This is due largely to the fact
former swamps and small water-courses have been filled up
ny previous attempt to drain them; and the very close prox-
e hills, on the sides of which many dwellings are built, doubt-
vates the difficulty, as many springs of water exist in these
he soil is kept constantly wet. As a consequence of all this,
ntains an unusual number of offensive privy-vaults, many re-
aning out every year, and not a few rapidly filling with water
r being cleaned. I think it may with truth be said that this
e most abominable privy-system to be found in the country.
perusal of what has now been written as to the sanitary
Wheeling, one might be pardoned for concluding that it
well nigh impossible to keep the city in first-rate condition.
haps true, unless an unlimited amount of money and labor
ed. But while this is true, it is equally true that the city was
ous to the advent of cholera and during its presence, in very
ion. Laborers, under the control of the street commissioner,
constantly employed in some part of the city cleaning the
l alleys, and at intervals lime was by my order scattered in
offensive localities. When the city was "threatened with
disease," an emergency in the absence of which *the health laws
do not permit the health-officer to employ even a single assistant in
ty*, I employed temporarily a sanitary inspector for each ward,
house-to-house visitations, and who were clothed with full
compel the abatement of all nuisances on private property. In
much good was no doubt accomplished, although the work
tirely completed until a number of cholera-cases had occurred.*
visitation, however, had been made by myself in the early
he worst localities of the city. So that while this city was
ndition, nor ever can be with its present sanitary defects, to
repel an epidemic of cholera, neither was it in a condition to
invite it. The least cleanly parts of it I believe to have been
and Sixth wards. But more on this subject again.

RAILROAD AND RIVER CONNECTIONS.

g, being very largely engaged especially in iron and glass
re, possesses intimate business relations with all prominent
st as well as in many parts of the South. She is in daily com-
n by rail with Columbus, Cincinnati, Cleveland, and inter-

y here, as indicating the ideas of certain city councilmen on the "political
ealth," that when bills for the services of these inspectors were introduced,
ne member of council desired to know by what right the health-officer
d men to do work for which he himself was paid. To the credit of our
s," be it said, the bills were paid by an overwhelming vote.

mediate points, and during the whole of the spring an 1873, the river being unusually high, three boats weekly Cincinnati, two of which were regular Wheeling and Cinci the other a Pittsburgh and Cincinnati boat. In addition t boats occasionally arrived from Cincinnati and points ab which were not making regular trips. The steamboat-lan Second and Third wards. The boats, however, frequentl iron mills, located principally in the Sixth ward; they als land at a wharf in the Eighth ward, the object at these p put off or take on freight. Passengers almost universall off at the wharf in the Third ward.

The Baltimore and Ohio Railroad depot, at which a Columbus, Ohio, and all points south of that city arriv river-bank in the Fourth ward. The track crosses Whee that point, and extends along the river-bank on the weste Fifth and Sixth wards until it reaches Thirty-second st point it crosses the city, forming the division-line between Eighth wards for three-fourths of their width, and thence direction southward and extends entirely through the The trains generally run at so slow a rate through the ci passengers to get off and on the cars.

The machine-shops of this road are located in the low Sixth ward, and give employment to about two hundred

I give the above particulars as having a direct bearing able mode of importation of the disease, upon which poi further remarks until later in my report.

METEOROLOGICAL OBSERVATIONS.

The points embraced in the following table, with note am indebted to Dr. E. A. Hildreth, of this city, may be interest in connection with a study of the origin of chole

Meteorological Observations.—Monthly means.

1873.	Maximum temperature.	Minimum temperature.	Mean temperature.	Rain-fall in inches.	Number of rainy days.	Number of cloudy days.	Number of clear days.	Prevailin		
								Number of		
	°	°	°							
May	86	44	62.66	5.95	10	2	19	5	3	.....
June	92	60	75.33	3.98	10	5	15	5	1	3
July	94	56	75.56	8.72	16	2	13	7	.....	1
August	90	60	69.66	8.55	11	6	14	13	4	.....
September	84	50	65.16	3.08	8	6	16	13	5	.....

Storms, with thunder and lightning, occurred on May 9, 24, 27; July 4, 5, 14, 15, 18, 26, 29; August 25, 27, 28. Sto on August 12. Frosts occurred on May 14, 15, 18, and Light snow on September 13.

NOTES BY DR. H.—"First half of June very dry. O rain-fall in first twenty days; balance of the month wet seen resembling cholera was on the 27th.

"First half of August attended with bad cases of chol and cholera morbus. Typhoid fever and erysipelas the p eases. Typhoid fever became epidemic about the middle and was generally of a mild type."

HISTORY OF CHOLERA CASES.

peaking of the introduction of cholera into Wheeling until
rence to those cases which seem to merit special attention,
uch details as are thought necessary will now be given. It
ble, without a map, to indicate to those unacquainted with
e exact location of the cases. In the hope that at least an
idea may be obtained on this point, I will state that our
ning north and south are named, commencing at the river,
in, Market, Chaplain, Eoff, Jacob, Woods, &c.; those run-
nd west are named from the northern end of the city, First,
ird, &c. The houses on the streets running north and south
ed on a basis of 100 to each square; hence the first house in
uare is numbered 100; in the Twenty-third square, 2,300, &c.
on the cross-streets, east and west, are numbered continu-
the river, commencing with No. 1. In the accompanying
ses, each house in which cholera occurred is numbered.

-The first case presenting the symptoms of cholera did not
knowledge until the end of the month in which it occurred,
death certificate was returned from the cemetery, in which
ostras" was given as the cause of death. The attending
as a very intelligent German, formerly health-officer of this
n him and from a personal visit to the house of the deceased,
ng facts are gathered.

e of attack was June 9, the patient, a German woman aged
the wife of the proprietor of a lager-beer saloon, at No. 2114
t, Fifth ward. This saloon was in the same house as that
the family, who lived in the rooms in the rear of the saloon.
and third stories of the house were rented out to two fami-
ividuals being on the second, and four on the third floor.
f the family on the second floor was a newspaper-carrier;
s employed with his father, and one worked in a cigar-store.
ning children were small, and remained at home. The man
rd floor and his son were laborers, with no regular place of
t.

tary condition of the premises was bad. A privy-vault was
use at this house, and was also used by visitors to the saloon,
much frequented by Germans. The rear wall of the cellar
wall of the privy-vault. This wall was in bad condition,
ted the contents of the vault to ooze through into the cellar
ling-house. On June 9, about 3 o'clock p. m., after her morn-
his woman was suddenly seized with diarrhœa, the discharges
l and copious. Full choleraic symptoms rapidly developed,
out three hours of collapse, she reacted, but died on the sixth
ith cholera typhoid. Thorough disinfection was resorted to,
er case, even of diarrhœa, occurred in the house or neighbor-
s woman was somewhat of an invalid, being subject to attacks
physician calls "catarrh of the stomach and bowels," every
he had not been absent from home, nor had any of the occupants
e, during the spring or summer, nor had any one been visiting
No means of introduction of cholera has been discovered in
with the case. There exists the possible solution that one of
us visitors to the saloon may have been a stranger from an
rt of the country, and in some way bearing the germs of the
t the probabilities are decidedly against this theory, of the
of which there is not the slightest evidence.

In view of this patient's predisposition to diarrhœa; in view of the facts that no other case at all resembling cholera was reported here until June 20; that no case was reported, even as high up the Ohio river as Cincinnati until June 14, and that sporadic cases identical in symptoms, though rare, do occasionally occur in all cities during the summer months,* it might be worth while to inquire whether this case should not be excluded from our list of cholera cases. I throw out the suggestion for the consideration of the reader.

Case 2 occurred on June 20, at No. 3600 Chaplain street, Eighth ward, in a two-story brick tenement-house occupied by four families, and an additional male adult who lived in a room alone. Up-stairs, in the rear wing of the building, lived the family in which this and the next case occurred. This family consisted of husband, wife, and two sons, aged respectively 21 and 26 years. The husband worked at a glass-house in the ward, which employs about two hundred hands. The sons worked at the La Belle iron-mill, in the Sixth ward, which also employs several hundred hands. The other family up-stairs consisted of man, wife, and five small children. The man was a laborer, having no steady employment. Down-stairs was a single man, a shoemaker, who worked and lived in the house; also a family consisting of man, wife, and one child, and another family consisting of a widow-woman and three sons. These males worked at the above-named glass-works and iron-mill.

The premises were in bad sanitary condition. The cellar contained a small quantity of water which had been there so long as to become offensive; an open wooden drain, intended to carry off waste water from the hydrant, was defective and filthy, and the ground near and under it filth-sodden, and at the foot of the yard was an unused privy-vault almost full, and but imperfectly covered.

The first case occurring in this house was that of a male, aged twenty-one years, a boiler in an iron-mill; previous health good; an occasional drinker. Had for several days been suffering with diarrhœa, and was, consequently, unusually prudent in diet; had eaten nothing which would serve as an exciting cause of the symptoms which later presented. He had been so prostrated by a copious diarrhœa that he twice fainted on his way home from his physician's office, a distance of two squares, whither he had gone for medical assistance. On this day, June 20, vomiting and cramps set in, followed by cold surface, shriveled skin, cyanosis of face and fingers, vox cholerica, and all signs of collapse, after the existence of which for some time, reaction set in, and recovery resulted on the 26th. This case was not reported, and I knew nothing of its existence until the occurrence of—

Case 3.—This patient was the mother of the above, aged sixty years, in only moderate health. She had nursed her son during his sickness, and was thus constantly exposed to the poison of the disease. She was attacked suddenly on June 28, having had no premonitory diarrhœa. Vomiting, purging, and cramps occurred, followed by collapse, from which she reacted in a few hours, recovering on the 30th. This case was not so severe as the previous one.

Neither of these patients had been absent from the city, nor do they know that they had been in any way exposed to any case of cholera, or to any person coming from a cholera-infected district.

As soon as this case was reported, which was not until several days after its occurrence, the premises were put in good sanitary condition. No other cases occurred in the house.

* Two such cases, one fatal, were reported to me here during the past summer. I saw one of these, and it presented all the symptoms, in an aggravated form, of the cases witnessed during the epidemic of 1873.

Male, aged thirty years, 3631 Eoff street, one and a half
n Nos. 2 and 3. This patient worked at the La Belle mill,
which case 2 was employed, but in a distant part of it,
men had no acquaintance with each other, nor had their
he home-premises were in good sanitary condition; the
erfect health, until attacked with diarrhœa some days be-
ch he was not kept from work. On the night of July 3 he
vith symptoms of cholera, which were succeeded by collapse
urs, followed by reaction and recovery after four days' ill-

hat this man was employed at the same iron-mill as case 2
ossible that during his premonitory diarrhœa he resorted to
ault. This is not certain, however, as there are several vaults
mill, and one of them is nearer to the point at which case 4
l than is the vault used by case 2.

Male, aged sixty-six years, justice of the peace, residence
in street, nearly a mile from any previous case. Had diar-
arly a week, for which he had received treatment, and the
controlled. A day or two after, which was July 4, he went
several miles in the country. He there doubtless exercised
y, being a man of active habits, but committed no impru-
ting. He, however, drank freely of lemonade made from
ater, to which he was not accustomed, and to this attributed
At 1 o'clock a. m. of July 5 violent purging and vomiting,
s of abdomen and extremities set in, followed by collapse,
came on. All the symptoms were well marked, and the
decidedly rice-water in character. The collapse was long-
and for a time the case was regarded as well-nigh hopeless.
was suppressed for fifty-four hours. Reaction finally came
patient recovered in 7 or 8 days.

ding physician, one of the oldest and most able physicians
with whom I saw this case several times, says the case re-
all respects those witnessed by him in three former cholera
Disinfection was freely employed as soon as the case was
o further cases occurred.

necessary here to give at length the history of every case,
l facts being given in the accompanying table. The cases
ow, however, seem to have some special interest by reason
nection with other cases or with each other, and are there-
omewhat fully. In the cases given above no probable con-
er than stated in the histories recited, either with each other
disease in other places, has been traced. The same is true
s which will not be detailed in this report.

-Male, aged sixty-two years, residence 3834 Eoff street,
night-watchman at Riverside nail-mill, on Main street,
wenty-fourth and Twenty-fifth streets. On duty with this
. Hughes, was another man, Armstrong, who tells me he had
for three days, but still kept at his post, using the vault at
ring the night. He described his diarrhœa as being painless,
e and watery as to necessitate great haste in reaching the
was also so very prostrating as to compel him to lie at home
after it was completely checked, which was done by early
atment. Mr. H. had a similar diarrhœa at the same time,
g some days after its existence, not only remained with Mr. A.
using the same vault, but also visited him at his home after
l up. He was a man of strong constitution and good habits,

and his diarrhœa existed for nearly two weeks before he w
with symptoms of cholera. On the evening of July 9, he st
mill to go on duty, but, when he arrived there, found him
trated that, after resting, he was compelled to return home.
reaching home he was seized with vomiting and purging,
cramps of the extremities and speedy collapse. I saw him
lowing, with his attending physician, when reaction was
After this was established, typhoid symptoms manifested
in almost every case that recovered, and the patient wa
cured on the eighth day. The sanitary surroundings o
promises were excellent.

Cases 10 and 11 were those of a man and wife, aged
seventy-three and seventy years; residence, No. 30 Fifth
sanitary condition excellent, the house being high, and
borhood, as well as the premises themselves, very clean. T
a man vigorous for his years, of perfectly temperate habits
ufacturer, and was in the habit of frequently visiting the
Sixth ward in a business capacity. He was attacked with
July 20, received medical treatment on the 21st, but the di
yield to treatment. On the evening of the 22d the stools w
rice-water in appearance. The next morning collapse ca
reaction afterward manifested, but it was only temporary
occurred on the 24th, at 3 o'clock p. m.; no cramps or pain
The wife was a constant watcher at her husband's bed-side,
in excellent health previously, was worn out with watching
Without any previous diarrhœa, she was attacked suddenly
cholera symptoms at 5 o'clock a. m. on the 25th, and die
at 9 p. m. of the same day. In this case, vomiting, rice-wa
and cramps were all present.

Case 12.—Female, married, aged 48 years; kept a board
No. 1102 Chaplain street; somewhat run down in health
and the cares and trials incident to her occupation. A
source of annoyance, as I learned after the occurrence of t
a large privy-vault in the yard, only 10 or 12 feet from the
This had been cleaned out in May by my order, but had
again, owing to the nature of the ground, and at this time
ingly offensive, and at the side toward the house the liq
sometimes leaked through at one point. Two of the upper
house, also, one of which was occupied as the patient's sl
ment, from some mysterious and still undiscovered cause, e
offensive, indescribable odor. The floor had more than on
tially taken up in the expectation of finding dead rats, o
clue to the mystery; and disinfectants were employed. T
learned after the occurrence of the case. The lady was
health, and rather costive, so that she was sometimes com
main in the privy for some length of time soliciting an op
the night previous to her sickness she had eaten a dish
with a friend in the neighborhood. On the morning of
went to the butcher-shop, one square away, but after her
plained of not feeling well, and about 7 o'clock an exhausti
commenced, the stools being very liquid and passed witho
9 o'clock a. m. all the usual symptoms of genuine cholera
an aggravated form, and speedy collapse came on, termina
at 9 p. m.

I had been boarding at this house for several weeks, and
suffered with a persistent diarrhœa, to get rid of which I

the country on the 23d of July; had also treated a son of
ra patient for a diarrhœa of some days' standing. On my re-
e house, on the 28th, I treated a servant girl, and also a daughter
ceased, both having diarrhœa, loose and painless, and very
g. Both recovered without alarming symptoms. From the
of these cases, I think it quite probable that both would have
d in cholera had early treatment not been employed. Two or
s after the death of the cholera-patient, a boarder was at-
ith what was called cholera morbus, making in all six cases
eal disease that occurred in this one house about the same
imprudence in diet was at the time considered as the cause.
r to this time visited five cholera-patients in my official capac-
ad, as already stated, a persistent diarrhœa for about two
nt I had never used the vault on these premises, nor did
the house, but only took meals there. In addition to this, my
was rather dysenteric in character, and in no respect resem-
rine. The same is true of the son's case above referred to.
—Male, aged 47; artist; health good. From Philadelphia two
vious, on a visit to a brother at No. 59 Twenty-sixth street.
s usual health until the time of attack, which was at 8 p. m.
, two hours after he had eaten his supper. The symptoms
nt, and the patient was in a collapse when the physician ar-
o'clock. Reaction took place, however, and recovery resulted
ek's sickness. The brother with whom this patient was stay-
similar, though less severe, attack a few days before. The
ot reported.
4, 19, 32, 33, 34, and 35 constitute a group of considerable
nd I shall speak of them together. They all occurred in a
-house of two rooms, located in the Fifth ward, on an elevated
looking Wheeling Creek, and about one-third of a mile from any
dence on the same side of the creek. There was no bridge
at distance of the house, and it was hence entirely isolated.
e was occupied by two families, each occupying one room,
tal number of individuals was ten or eleven. These were dirty,
and vile. The husbands were laboring men. Case 14, male,
eight years, occurred on August 29; was comparatively mild,
at the time regarded as cholera morbus, was not reported.
nt, however, did not recover until September 10. Case 19,
ed twenty-eight years, intemperate, occurred on September 2,
nild, the patient recovering on September 6, without the use
an domestic remedies. The other cases occurred, respectively,
ber 14, 19, 24, and 25, were all severe, all received medical
, and all terminated fatally. It was not until September 25
f these cases were reported as cholera. I immediately visited
where I saw one woman lying dead, a child in a dying condi-
another woman in a condition of semi-collapse. From a sober
what intelligent man, not a member of either of these families,
ad nursed the patients, I received a full account of all the
had occurred, as also from two of the patients who had re-
and, after a consultation with the physician who had attended
ase, we had no doubt that all the cases occurring in this house
same disease.
on the premises no privy-vault nor any pretext whatever as
te; and the dejecta of all these patients had been thrown out
ound in the neighborhood of the house. The appearance of
indicated that they had not been scrubbed for weeks. No

attempt had been made at disinfection. Is it any wonder, under all the circumstances, that this fell destroyer found here a congenial home!

I, of course, did all in my power, by enforcing cleanliness and disinfection, to put the premises in good condition. Cholera had disappeared from the city proper on September 7. In this isolated position it lingered until these measures were enforced, after which no other case occurred in any part of the city. That so many cases occurred in this one isolated house *because* of intemperance and filthiness, and the neglect of all hygienic laws, is in accordance with the known nature of this disease. That no case occurred after the adoption of sanitary measures, because of this change in the condition of the premises, is probable, although it is possible that all *susceptible material* was exhausted.

Case 24.—Male, colored, aged sixty-seven, laborer, very intemperate; residence in a private alley near the junction of Tenth and Market streets; sanitary surroundings bad; house low, being situated against a high stone wall, which kept it damp and prevented it from being properly lighted and ventilated. This man had been suffering with a watery diarrhœa for some days, which had very much reduced his strength; no medical treatment had been received. On September 4 at 10 o'clock a. m., he was attacked with cholera, and died at 12 o'clock p. m. of the 4th. Case 31, a daughter of this patient, aged twenty-six years, a prostitute, was attacked with diarrhœa on the day after her father's death, but, like him, neglected it, and on September 7, at 8 p. m. violent cholera-symptoms set in, which terminated her life in six hours.

Case 27.—Female, aged fifty-two years; German; intemperate. Had been in the city about a month, and was engaged in selling pictures &c. from house to house. Was boarding at a German hotel at No. 121 Water street. Had diarrhœa for some days, for which no medical treatment was received. On September 5, at 6 or 7 o'clock in the morning, she was seen vomiting in the back yard by the hotel proprietor. She ate no breakfast. Cholera in its usual form soon after developed; a physician was called, the patient was removed as soon as possible to the hospital, and died there at 9 o'clock p. m. I visited this patient at about 10 o'clock a. m. in conjunction with two other physicians, and by chance noticed that the face of her husband, who sat on another bed in the same room with his wife, presented a pinched and cyanosed appearance. He had made no complaint of being sick, but on examination I found that he too had diarrhœa, and now was suffering with slight cramps in the muscles of the legs. His pulse was feeble, fingers and lips cyanosed, and his surface shriveled and of a death-like coldness. He was immediately put to bed and received a dose of medicine. An hour or two later he was removed to the hospital with his wife, and after a few days of close watching, with constant medical treatment, he recovered. The probabilities are, that had not this man's condition been discovered this early, he would have neglected, like many others, to secure medical assistance, and would have lost his life in consequence. This case is not included in my table, and yet it would be difficult to give a good reason for not placing it there.

I have now given somewhat in detail the histories of a few of the first reported cases of cholera occurring in the city, and also all cases having a connection with one or more other cases; in short, of all groups of cases. I have taken the liberty of including in my table two cases which were called cholera morbus by the attending physician. These are Nos. 14 and 15. The full history of the former has been given above. These cases were called cholera morbus, not because they differed in any respect from the other cases reported as cholera, but because of the pecu-

ar views of the physician in attendance, who did not regard any of ıe cases occurring in this city, or elsewhere in the country, as genuine holera.

Having learned the full particulars from this physician, and also from ıe families in which the cases occurred, I have no doubt whatever that ıey were identical with the other cases, and hence include them. I ould prefer to omit them were I justified in so doing.

Before making any comments on the facts here given, I desire to refer) a very interesting group of cases which occurred in the country, about ur miles away, and between which and the epidemic in the city I have een unable to trace any connection whatever.

Mr. J. T. C., a medical student for some time resident in the Good amaritan Hospital of Cincinnati, and now a resident physician in that ıstitution, took passage for this city on the steamer Andes on June 13. n the 15th he was attacked with a watery diarrhœa, which continued ithout treatment until he reached home. The boat landed at Wheel- ıg on the morning of the 17th, and Mr. C. started immediately for his ome, walking one and a half miles, and riding in a wagon the remain- er of the distance. The diarrhœa continued, and vomiting set in the ext day, (18th.) The dejecta were described to me by Mr. C. as "re- embling water into which a small quantity of milk has been poured." reatment was commenced on the day after Mr. C. reached home, and ıe disease was controlled, but the patient was not well for ten days.

On June 21, four days after Mr. C.'s arrival home, his mother, aged fifty- wo years, in previous good health, was attacked with vomiting, purging, nd cramps, but was promptly placed under treatment by her son, and ecovered in about a week. On June 25 his grandmother, aged seventy- hree years, was similarly attacked, and died in collapse in twelve hours. n June 30, Miss C., a sister of the first patient, aged nine years, healthy, as seized with the same symptoms, and recovered after a week's illness. ll these cases occurred in the same house, which is favorably situated ı the country, and with no sanitary defect. Neither could the cases be raced to any error in diet. On this point I made particular inquiry, nd, as Mr. C. is a personal friend, doubtless received all the facts cor- ectly. The fact also that several days elapsed between the occurrence f the different cases renders this theory improbable. That the disease as genuine cholera as we had it in the city, and that Mr. C. was the arrier thereof to his home, I cannot doubt. This additional fact seems o render positive that which might, in its absence, be received with ome little degree of doubt, viz, the only place between the steamboat nd his home at which Mr. C. left any dejecta was at a blacksmith's, hree and a half miles east of this city. This blacksmith was attacked rith "watery discharges, cramps, and vomiting soon afterward; the xact date I cannot give," writes Mr. C. in a letter to me. I remember his case having been reported in our city papers at the time of its oc- urrence, and it was then regarded as similar to the cases occurring ere; and the fact of a case occurring away in the country was used s an argument to prove that the disease was not imported to the city, y one or two physicians here who regarded the cholera of 1873 as dif- erent in origin and character from that of former epidemics. On the ontrary, in the light of all the facts here given, importation in this in- tance is proved almost to a demonstration.

Unfortunately, the origin of Mr. C.'s case cannot be so satisfactorily ccounted for. It has been noted that he left Cincinnati on June 13. t is worthy of remark that, according to the report of Dr. Quinn, the ealth-officer of that city, the first death from cholera occurred there on

the 14th of June. Nothing at all resembling cholera had occurred a the Good Samaritan Hospital previous to Mr. C.'s departure. Whether he came in contact with any case on the boat, it is impossible to say. He writes: "I know of no one on the boat similarly affected to myself. I was not acquainted with any one, and cannot say positively whether or not there were any."

Since the above was written, I have visited the blacksmith referred to, and from him obtained the following facts: He was attacked, as already stated, several days after Mr. C. had visited his place. Within ten days after this, his mother, wife, and six children, being every occupant of the house, were attacked with diarrhœa, and nearly all of them with both diarrhœa and vomiting. None of the cases, however, were serious. His own was the worst, he being confined to his bed for several days, and not returning to his work for about ten days. I made particular inquiries concerning the diet of this family, but learned nothing that would indicate that these attacks had been caused by imprudence. On the contrary, this blacksmith stated that he at the time of their occurrence thought, and still thinks, that his family "caught the disease from Mr. C." It seems difficult to resist this conclusion, and yet it is strange that none of the cases assumed a serious aspect.

No.	Ward.	Residence.	Sex.	Color.	Age.	Married or single.	Occupation.	Date of attack.	Date of recovery.	Date of death.	Duration of fatal cases.	Local sanitary condition.	Habits and physical condition of patient.	Remarks.
1	5	2114 Main st	F.	W.	50	M.	Housekeeper	June 9		June 15	6 days	Bad	Delicate health	Premon. diarrhœa.
2	8	3600 Chaplain st	M.	W.	22	S.	In iron-mill	20	June 26			Bad	Temperate—healthy	Premon. diarrhœa.
3	8	3600 Chaplain st	F.	W.	60	M.	Housekeeper	28	July 1			Bad	Not very strong	Sudden invasion.
4	8	3631 Eoff st	M.	W.	30	M.	In iron-mill	July 3	6			Good	Healthy—mod. drinker	Premon. diarrhœa.
5	6	2523 Chaplain st	M.	W.	66	M.	Justice of the peace.	5	12			Md'm	Healthy—temperate	Premon. diarrhœa.
6	6	2629 Chaplain st	M.	W.	60	M.	In B. & O. R. R. shop.	6	10			Good	Healthy—temperate	Half day's diarrhœa.
7	8	3624 Eoff st	M.	W.	60	M.	In iron-mill	9	17			Good	Healthy—temperate	Premon. diarrhœa.
8	4	1714 Eoff st	M.	W.	48	M.	Street-paver	16, 4 p. m.		July 17, 5 a. m.	13 hr's	Bad	Intemperate	Premon. diarrhœa.
9	8	3426 Market st	M.	W.	48	M.	Laborer	21, 9 p. m.		23, 6 p. m.	45 hr's	Good	Good health	Premon. diarrhœa.
10	1	30— 5th st	M.	W.	73	M.	Manufacturer	22, 8 p. m.		24, 3 p. m.	43 hr's	Good	Healthy—temperate	Premon. diarrhœa.
11	1	30— 5th st	F.	W.	70	M.	Housekeeper	25, 5 a. m.		25, 9 p. m.	16 hr's	Good	Healthy—temperate	Sudden invasion.
12	2	1102 Chaplain st	F.	W.	48	M.	Housekeeper	25, 9 a. m.		25, 9 p. m.	12 hr's	Bad	Worn down by care	Sudden invasion.
13	6	59— 20th st	M.	W.	49	S.	Artist	29	Aug. 5			Good	Healthy—temperate	Sudden invasion.
14	5	Poverty Point	M.	W.	58	M.	Laborer	Aug. 29	Sept. 10			Bad	Healthy	Premon. diarrhœa.
15	2	1057 Morrow st	M.	W.	59	M.	Cigar-maker	30, 3 p. m.		Aug. 31, 11 a. m.	20 hr's	Good	Very intemperate	Premon. diarrhœa.
16	5	2219 Eoff st	M.	W.	30	S.	In iron-mill	30, 4 p. m.		30, 11½ p. m.	7½ hr's	Md'm	Intemperate	Premon. diarrhœa.
17	8	3722 Eoff st	M.	W.	35	M.	Teamster	31, 3 a. m.		31, 11 a. m.	8 hr's	Good	Intemperate	Premon. diarrhœa.
18	5	2224 Main St	M.	W.	28	S.	In iron-mill	31, 6 p. m.		31, 12 p. m.	6 hr's	Good	Intemperate	Unknown.
19	5	Poverty Point	F.	W.	28	M.	Housekeeper	Sept. 2	Sept. 6			Bad	Intemperate	Premon. diarrhœa.
20	6	2408 Short st	F.	W.	38	M.	Housekeeper	2, 8 a. m.		Sept. 2, 12 p. m.	16 hr's	Md'm	An invalid	Premon. diarrhœa.
21	8	Country Road	M.	W.	32	M.	In iron-mill	2	Sept. 14			Bad	Intemperate	Premon. diarrhœa.
22	6	3013 Market st	F.	W.	48	M.	Housekeeper	2, 12 p. m.		Sept. 9, 10 a. m.	6½ days	Good	Healthy—temperate	Sudden invasion.
23	1	North of 1st, on Main st	M.	W.	40	M.	In iron-mill	3, 10 a. m.		4, 7 a. m.	21 hr's	Md'm	Healthy—temperate	Premon. diarrhœa.
24	2	Near 10th & Market sts	M.	Col.	67	M.	Laborer	3, 10 a. m.		4, 12 p. m.	38 hr's	Bad	Very intemperate	Premon. diarrhœa.
25	6	2407 Alley Court	M.	W.	37	M.	In iron-mill	3, 9 p. m.		4, 12 p. m.	27 hr's	Good	Very intemperate	Premon. diarrhœa.
26	8	3725 Jacob st	M.	W.	48	M.	Shoemaker	3, 12 p. m.		5, 6 a. m.	30 hr's	Good	Very intemperate	Premon. diarrhœa.
27	3	1414 Water st	F.	W.	52	M.	Peddler	5, 7 a. m.		5, 9 p. m.	14 hr's	Good	Intemperate	Premon. diarrhœa.
28	6	2318 Woods st	M.	W.	44	M.	In iron-mill	5	Sept. 10			Good	Healthy	Premon. diarrhœa.
29	8	3638 Eoff st	M.	W.	57	M.	In glass-works	6	14			Good	Not robust, mod. drink'r	Premon. diarrhœa.
30	6	2623 Jacob st	M.	W.	23	M.	In iron-mill	6	11			Good	Healthy—mod. drinker	Premon. diarrhœa.
31	2	Near 10th & Market sts	F.	Col.	26	S.	Washerwoman	7, 8 p. m.		Sept. 8, 2 a. m.	6 hr's	Bad	Healthy—prostitute	Premon. diarrhœa.
32	5	Poverty Point	F.	W.	11	S.	Child	14, 8 a. m.		14, 8 p. m.	12 hr's	Bad	Healthy	Premon. diarrhœa.
33	5	Poverty Point	F.	W.	55	wid.	Housekeeper	19		30	11 days	Bad	Unknown—intemperate	Premon. diarrhœa.
34	5	Poverty Point	F.	W.	41	M.	Housekeeper	24, 10 a. m.		25, 5 p. m.	31 hr's	Bad	Unknown	Unknown.
35	5	Poverty Point	M.	W.	10	S.	Child	25, 9 a. m.		26, 4 a. m.	31 hr's	Bad	Healthy	Unknown.

Having now completed the history of cholera-cases occurring in the city and vicinity during the epidemic of 1873, it is only proper to say that the facts here recorded were received at second-hand in no instance, but directly either from the attending physician or the patient, or the friends present with and nursing the patient; frequently from at least two of these sources. I have visited every house in which cholera occurred, many of these at the time of the occurrence of the case. My aim, as already remarked, has been to arrive at the exact facts, regardless of what theory they may tend to support. In the few remarks I shall now add, the same purpose to develop the truth will be kept in view.

MORTALITY.

By an examination of the table it will be observed that we had two distinct visitations of cholera. One commenced on June 9, or, if we throw out case 1 as having been sporadic, on June 20, and ended on July 29, during which time only thirteen cases occurred, with six deaths, a mortality of 46 per cent. The disease then suddenly disappeared, not a single case occurring until exactly a month later, nor did I during that time hear of any case having occurred that at all resembled cholera. From August 29 until September 7, no less than eighteen cases occurred, when it again disappeared from the city proper; four additional cases occurring, however, between September 14 and 25, in an isolated district. Thus we had in the second epidemic twenty-two cases, with seventeen deaths, a mortality of 73 per cent. During the summer, then, there occurred thirty-five cases and twenty-two deaths, giving a mortality of 63 per cent., which certainly entitles the disease to be called *malignant*, whether it be of *Asiatic* or *American* origin.

DISTRIBUTION OF THE DISEASE.

By a reference to the table it will be seen that the cases were located by wards as follows: In the First, 3; Second, 4; Third, 1; Fourth, 1; Fifth, 9; Sixth, 8; Eighth, 9. Thus the three last-named wards, which are south of the creek, and contiguous to one another, contained twenty-six out of the thirty-five cases. The Seventh ward, situated on Zane's Island, with the main channel of the Ohio river separating it from the other wards, entirely escaped. The one person attacked in the Third ward was not a resident of it, but a peddler temporarily stopping there, and who may have been exposed to the germs of the disease in some of the houses visited by her daily. She was a German, able to converse but little, if at all, in English; the wards south of the creek contain a very large proportion of our German population; facts which render it probable that this woman plied her vocation principally in that part of the city. The man who lived in the Fourth ward was a street-paver, and on the day of his attack, and for some time previously, had been at work in the Fifth ward. One of the three in the First ward—the patient whose wife also died—was in the almost daily habit, in conducting his business, of visiting some of the nail-mills in the lower part of the city. I mention these facts as pointing to a possible mode of origin of some of the cases occurring in the upper wards of the city. It is evident from the facts here given, that the disease was in a great degree localized in the three southern wards of the city, these being separated from the other wards by Wheeling Creek.

LOCAL SANITARY CONDITION, EFFECTS OF.

After a careful study of all the circumstances, I am not convinced at the location of the cases was affected by the comparative uncleanness of the different parts of the city, since there is no great difference in this respect between the different wards. The Third and Seventh are always the cleanest, and these contained but one case; but the Second, which contained four cases, and the Fourth, which contained but one, are both less cleanly than the Eighth, which contained nine cases. The latter, however, as already stated, is the lowest, and next to it the Sixth and Fifth, which likewise are generally in the poorest sanitary condition, being to a very great extent unpaved and unsewered. Thus elevation, rather than cleanliness, seemed to exert a protecting influence, if indeed we are justified in drawing any conclusion where so few cases occurred.

The sanitary surroundings of the houses in which cases occurred certainly did not in many instances exert any great influence. I have endeavored in the table to give some idea of the condition of each house in which cholera occurred, and its surroundings. Of course this can be but imperfectly done without a full description of the premises in each case. By the term *good* I desire to represent those cases in which I detected nothing which would, in my opinion, serve as a predisposing cause of disease; by the term *bad* those cases in which such predisposing cause did exist, and by the term *medium* those cases in which the premises were in fair condition only. The local sanitary condition was regarded as *bad* in fourteen cases, *medium* in four, and *good* in seventeen. Of multiple cases, however, occurred in several houses, which would leave the following as true of each house, viz, sanitary condition *bad* in seven cases, *medium* in four, and *good* in sixteen. In but four or five instances were the sanitary defects so bad as, in my opinion, to serve in any great measure as the predisposing cause of cholera. Certain it is that, with these few exceptions, not a few much worse places entirely escaped, while a number of the houses visited by cholera were very favorably located, and the premises in excellent condition. A second case occurred in but one house whose sanitary condition I have indicated as *good*, while multiple cases occurred in three houses whose sanitary condition was *bad*. In those marked *medium* no second case occurred. In this respect the difference is so small as to warrant no conclusion.

HABITS, ETC., OF THE PERSONS ATTACKED.

I am convinced that in this, as in other epidemics of cholera, the personal habits and mode of life, together with the previous state of health of those attacked with the disease, had much influence not only in inducing the attack, (the presence of the cholera-poison being presumed,) but also in bringing about a fatal termination. It will be seen from the table that twelve of the patients had been "intemperate," four of them "moderate drinkers," five in impaired health, and fourteen, as far as ascertained, in good health, of which last number four were over sixty-five years of age. The "moderate drinkers" were all Germans, who, while seldom becoming intoxicated, yet almost daily consume large quantities of beer. This they consider moderate drinking, and I have so marked it. Others might possibly be added to one or other of the unfavorable classes here named were full data at hand. But even with these partial positively-ascertained facts, we have a total of twenty-five persons who, by reason of either habits of drinking, previous ill-health,

or advanced years, were certainly not in a condition to resist this disease. (I might also add to this list two fatal cases in children aged ten and eleven respectively.) Of the twelve intemperate, no less than ten died, a mortality of 83 per cent.

It will be observed also that ten out of the thirty-five patients were employed in our iron-mills. These iron-mill men are generally of strong constitution, but extremely careless concerning their health and habits of living. Their occupation calls them to labor in an atmosphere whose temperature is excessively high, and very commonly, after finishing a short piece of work, they step to the coolest place they can find, and sit down until their services are again required, often also drinking freely of ice-water, and sometimes having cold water by the bucketful poured over their naked backs, from which the perspiration is streaming. To this I find a number of these men attribute their sickness; and that it had an influence, as in some measure an exciting cause, it is not unreasonable to believe.

MODE OF ATTACK.

It is interesting to note the large number of cases in which premonitory diarrhœa occurred, viz, twenty-seven. The duration of this diarrhœa varied from half a day to over a week. In only a few cases was the disease ushered in suddenly. The diarrhœa was universally watery, painless, and very prostrating. We had during the epidemic an unusual number of cases of diarrhœa in the city in which the stools were very liquid, and often of a light color, being sometimes described as "milky." A few of these cases were accompanied with very feeble cramps of the extremities. Judging from the readiness with which these yielded to treatment—though a few of them were quite rebellious—I cannot doubt but that a number of deaths could have been prevented had the patients given early warning of the existence of a diarrhœa, and at once placed themselves under intelligent medical treatment. This is a point, indeed, already well established by past experience, and one which should be impressed upon the public mind on all proper occasions.

SANITARY TREATMENT.

The health-officer is the sole health authority in Wheeling, save a committee on health of the city council, to whom the health-officer is responsible, who audit his bills, hear cases of appeal when any person feels aggrieved by any order issued by him, but, being unsalaried and not clothed with the powers usually vested in boards of health, do not care to assume any responsibility in the administration of the health laws. The sanitary work, then, must be done solely by the health officer. Our health-laws require physicians to "report promptly to the health officer all cases of Asiatic cholera, &c., which they may attend." Great doubt, however, existed in the minds of physicians, here as elsewhere, as to the exact nature of the disease when it first appeared; and, indeed, two or three still claim that the cases were not genuine cholera. Hence there was at first a hesitancy in announcing a case to be cholera, and hence delay, and in not a few instances entire failure, to report the case. Even late in the epidemic in some instances the first intimation the health-officer received of the existence of a new case was from the local columns of the morning papers, or from rumors heard on the streets. As soon as a case was discovered, however—which was sometimes done by tracing these street rumors and newspaper reports—measures for thorough cleansing and disinfection were at once instituted. In this

ored under very great disadvantage from the limited power conferred the health-ordinance, and the want of assistants upon whom I could y to properly apply disinfectants, and to gratuitously distribute them the infected district, as would have been done had the means for so ing been at my command. In the disinfection of cases, however, was materially aided by the attending physicians, who generally lered disinfectants as soon as called to the cases. This was not ays done, however, nor were the directions always carried out when en. Isolation of the cases was also urged by me, but not enforced, l the advice given was in most instances disregarded. No special caution was enjoined in the preparations for burying the dead, and ne of the funerals of cholera-patients were very largely attended. e houses also were freely visited previous to the funerals by friends the deceased persons. The only precaution taken after death was to ve the clothing of the deceased and the room in which the body lay infected.

Whether any positive good was accomplished by the means employed a question in my mind undetermined. All the facts to be derived from observations as to the benefits of disinfection may perhaps be best iefly expressed as follows:

Case 1 disinfected promptly; no second case.

Case 2 not disinfected; a second case (No. 3) six days later.

Case 3 disinfected; no second case.

Case 4 probably not disinfected; no second case.

Cases 5, 6, 7, 8, and 9 disinfected; no second case.

Case 10 disinfected after active cholera-symptons developed; a second case, (No. 11,) the wife, who died the day following the death of r husband. Thorough disinfection; no further case.

Case 12 disinfected; no second cholera-case; two cases of diarrhœa adults, neither severe, and a case of cholera morbus after disinfection.

Case 13 disinfected; no second case. This case followed three days ter a case of what was called cholera morbus which was not disinfected.

Case 14 not disinfected; five additional cases (Nos. 19, 32, 33, 34, and 5) followed before disinfection, after which no other case occurred.

Cases 15, 16, 17, 18, 20, 21, and 22 disinfected; no second case.

Case 23 disinfected. Two children of this patient were attacked with iarrhœa and vomiting the day following their father's death. The ases were easily controlled by immediate medical treatment.

Case 24 disinfected; a second case, a daughter, (No. 31,) after which o other case.

Cases 25 and 26 disinfected; no second case.

Case 27 disinfected. The husband of this patient had mild cholera-ymptoms at the same time, and probably contracted the disease in the ame way.

Cases 28 and 29 disinfected; no second case.

Case 30 not disinfected at all. A young child of this patient died rith "cholera infantum" ten days after this case occurred. No disinfection after this, and no other cases.

In none of these cases was disinfection resorted to until active cholera-ymptoms set in. An analysis of the facts just given would seem to indicate that disinfection had been productive of good results. The facts may be summarized thus:

Houses disinfected after the occurrence of a cholera-case, in which no second case of any diarrhœal disease occurred, *nineteen*.

Houses disinfected, &c., in which a second case did occur, *four*: in two instances followed by cholera-cases, and in two by cases of diarrhœa.

Houses not disinfected (probably) in which no second case occurred, *one.*

Houses not disinfected in which a second case occurred, *three;* in one instance followed by one "cholera-infantum" case, fatal; in one instance by one and in another by five cholera-cases.

Did the premonitory diarrhœa during this epidemic contain the germs of cholera? This is a question of vital importance in the study of this disease. Accepting the doctrine that the dejecta of cholera-patients are the chief source of infection, the following facts seem to indicate that the excreta of the premonitory diarrhœa were in these cases devoid of cholera-germs, or at least, that these germs were possessed of very feeble reproductive power. It will be seen by the table that at least twenty-seven cases out of thirty-five were preceded by diarrhœa. The diarrhœa existed from one-half day to over a week in the different cases; all this time no disinfection or other precaution against the spread of the disease being resorted to; and yet in but four houses did any second case of *cholera* occur, and in three others, cases of diarrhœal disease other than this. Of these seven houses, three were not disinfected until after the occurrence of the second case.

Again, as noted in the table, eleven of the subjects of cholera were employed in iron-mills and glass-works, five separate establishments employing not less than eight hundred men. So far as I have the facts all of these men suffered with premonitory diarrhœa, and before giving up work used the privy-vaults frequented in common by all the men employed in the mills. In no case was disinfection used in any of these vaults. Why did not cholera prevail extensively among these mill men if this premonitory diarrhœa was capable of propagating the disease? Or is it possible that the germs of cholera could have been destroyed by the disinfectants always present in the atmosphere of iron-mills?

On the other hand, we have the facts related in connection with two cases in the country, viz: Mr. C., while suffering with premonitory diarrhœa, and one day prior to his attack of cholera, used a privy-vault at a house occupied by three adults and six children. Within ten days all of these nine persons were attacked with diarrhœa, or diarrhœa and vomiting, which could not be traced to any other cause.

Thus the question propounded is not answered in a manner altogether satisfactory.

MODE OF INTRODUCTION TO THE CITY.

The consideration of this point I have purposely postponed until now in the hope of gaining some accurate information on the subject. We have in the case of Mr. C. a history of direct importation, and communication of the disease to a number of persons. This seems to me to demonstrate, as well as a hundred cases could do the portability and communicability of the cholera of 1873. But I am satisfied the disease in the city had no connection with this case. Mr. C. did not stop in the city at all, merely passing through it afoot to his home. Besides, our first case occurred eight days before his arrival. And, if we exclude the first case as one of sporadic cholera, the next, which occurred on June 20, three days after Mr. C.'s arrival, was located about two miles from the steamboat-landing. The same is true of the next five cases, while but one case occurred very near to the wharf. Thus far no history of direct importation has been traced in connection with any case

he city. The difficulty of this undertaking is very great, if we grant
t the premonitory diarrhœa may propagate cholera. It is not neces-
y to enlarge on this point.

ll the facts I have been able thus far to collect are briefly these:

n officer of the Andes, a boat plying between Cincinnati and Wheel-
weekly, informed me that during June and July, 1873, they brought
a the former city a large number of persons who suffered on the
e with some form of acute diarrhœal disease. Some of these were
ple diarrhœa, while others were attended with vomiting and severe
n. This officer kept several bottles of "cholera-mixture" on board,
had frequent occasion to employ the medicine. He gave particu-
of three cases that he remembered as being especially severe, but
ld not recall the names of the patients, and the boat being laid up
Cincinnati on account of low water at this time, he has not access to
books. Two of these persons were men, sick with some disease re-
bling cholera, and they suffered so much as to disturb the passengers
their loud cries of pain in the night.

nother was an old lady, who, with her husband and daughter, took
sage at Cincinnati. This was soon after cholera was reported in that
, and the officer thought that they were by its presence induced to
e the place. This lady took sick about Pomeroy, and was exceedingly
vous and apparently alarmed. Some of the cholera-mixture was
ministered, but she grew so much worse that at Parkersburgh a physi-
n was sent for. She improved before reaching Wheeling, but was so
still as to require a carriage to convey her to her residence in this
. We hope yet to obtain the full facts concerning this case.

he porter on the R. R. Hudson, another weekly Cincinnati packet,
orms me that the bar-keeper on that boat experienced a severe attack
what he called cholera on his way up the river, and he also was com-
led to secure a physician at Parkersburgh. The porter described the
reta as being watery and very white. This patient is now in Cin-
nati, and we have been unable to learn where he spent his time
le in this city, where his clothing was washed, and other facts of in-
est connected with the case.

An application to the clerk of the Hudson for further information
ncerning cases occurring on that boat was not responded to, and I
hence unable to give any additional particulars.

Although the facts here given prove nothing conclusively as to the
portation of cholera into this city, yet they indicate a probable mode
introduction, and encourage further investigation in this direction. I
ve said nothing concerning a possible importation of the disease by
road, because I have learned no facts upon which I could rely touch-
this point. It is manifestly more difficult to hunt out cases arriving
rail than those coming by river; but since I have no facts bearing
on the subject, and have no desire to press the question of importa-
n in their absence, I forbear remarking anything further, and here
se my report, believing that all essential facts concerning the cholera-
demic of 1873, as it appeared in Wheeling, W. Va., have been given,
far as it is possible to collect them.

NTINGTON, WEST VIRGINIA.

The following letter has been received in answer to a request for in-
mation as to cases of cholera which were supposed to have occurred
Huntington during the summer of 1873:

"HUNTINGTON, W. VA., *October* 10, 187[illegible]

"Dr. ELY MCCLELLAN,
"*Assistant Surgeon U. S. A.:*

DOCTOR: Your communication of the 3d instant at hand. The circular-letter and blanks to which you refer were handed me some time ago, but not being able to furnish you with any information in regard to the cholera-epidemic of 1873, I delayed writing you longer than I should otherwise have done.

"Diarrhœa and cholera morbus prevailed extensively during the summer of 1873, and during the month of July three deaths occurred which were called cholera, but were not so reported by the physicians. I saw two of the cases in consultation. One was a very feeble old lady: she evidently died from a congestive chill. The second was an aggravated case of cholera morbus brought on by overeating. The third I did not see, but her physicians reported the case cholera morbus.

"Yours, very truly,

"J. V. WALL, M. D."

CHAPTER XVI.

)RGIA GROUP.

GEORGIA CONTRIBUTORS.

Reeves and Malone, Calhoun Co.
J. R. McAfee, Whitfield Co.
G. J. Grimes, Muscogee County.
Dr. J. M. Boring, Fulton County.
Dr. J. B. Baird, Fulton County.
Dr. W. J. Armstrong, Fulton Co.

ssistant Surgeon A. A. Woodhull, U. S. A.

DATES OF CASES.

tlanta, Fulton County, July 2.
alton, Whitfield County, July 3.

uring the epidemic of 1873, in the United States, but two authenti-
d cases of cholera occurred within the limits of the State of Georgia,
ar as can be ascertained.
i both instances the subjects were residents of, and refugees from,
city of Chattanooga, Tenn. In neither instance did the subject
e Chattanooga until after the disease had become epidemic, and
individual at least came from a cholera-infected house.
t the first glance it would seem to be scarcely worth the labor of
ating these cases, in the general history of an extensively-diffused
lemic, but no cases that could be presented are of greater value
illustrating the generally-accepted theory of the infectiousness of,
the means for the prevention of, the disease.
n both instances these cases, as will be shown hereafter, terminated
ılly in communities in which the auxiliaries to the rapid develop-
ıt of a cholera-epidemic were present, the specific causes once having
ı imported; yet, in both instances, by the prompt and energetic
ion of the medical men having the cases in charge, the power of the
ase was confined to the infected individual, and the health of the
idents of the respective houses and of each community were efficiently
ırded.
t has already been demonstrated in the narrative, that throughout
area of infection in the United States during the year 1873, in
great majority of instances the arrival of but a single infected indi-
ual was sufficient to establish a focus from which the cholera-infec-
ı radiated; and that in the few instances in which the arrival of a
)lera-infected individual failed to produce this morbific influence the
ntion of the problem is found to be in the fact that the excreta of the
e were disinfected, or that they were so disposed of as not to gain
rance into the alimentary canal of the healthy residents of the house.
In tracing such cases, the announcement that no disinfectants had
:n used should always be received with caution and hesitancy, until
least the observer has become fully possessed of all the facts of the
se, for a very practical disinfection may have been secured by means
ich were not recognized by the narrator. We instance the cases of
olera that were brought to Paris, Ky., from Millersburgh and Cyn-

thiana. These cases proved fatal, but without infecting other individuals. This was advanced as a proof of the non-infectiousness of cholera. It is stated that disinfectants were not used, but at the same time it is shown that fresh earth was thrown upon the excreta after they had been emptied upon the ground. *Fresh earth is a recognized disinfectant.* When Macnamara wished to test the length of time the specific properties of cholera-dejections could be preserved, he did not select *fresh earth* with which to mix the rice-water discharges, but *fine dry sand.*

Of the two cases to be accredited to the State of Georgia, one occurred at the city of Atlanta, Fulton County. This is one of the most important of the southern cities, having a population of over 22,000 inhabitants, a railroad-center of considerable importance, which brings the city into constant connection with all sections of the country.

On the 2d of July, 1873, Mrs. S., a lady thirty-three years of age, healthy, but never robust, childless, living in easy circumstances, was attacked with cholera, and died, after an illness of about twelve hours, in a healthy location of the city. The case was in the charge of Dr. John M. Boring, and was visited in consultation by Drs. James R. Baird and William S. Armstrong. To these gentlemen, through the kindness of Assistant Surgeon A. A. Woodhull, U. S. A., post-surgeon McPherson barracks, Atlanta, we are indebted for the following history.

Mrs. S. arrived at Atlanta from an infected district of the city of Chattanooga, Tenn., accompanied by her husband, on Sunday afternoon, June 29, and went immediately to the residence of her mother, in a thickly-settled portion of the city. On Monday (the 30th) she was attacked with diarrhœa, which yielded to the administration of some domestic remedy. On Tuesday (July 1st) the diarrhœa returned with greater severity; again domestic aid partially relieved the disorder, but during the succeeding night it returned, and she was obliged to make frequent use of the water-closet. On Wednesday (July 2) Mrs. S. dressed herself and was present with the family at breakfast, but complained of great prostration. During the early hours of the day the diarrhœa had increased in severity, and when first seen by Dr. Boring she was vomiting and cramping violently, and verging on collapse. At 2 o'clock p. m. Dr. Armstrong saw the case in consultation, found the patient in complete collapse, pulseless, skin blue, cold, and shriveled, eyes sunken, voice husky, her mind clear, and intelligence not impaired. At 6 o'clock p. m. Dr. Baird saw the case with Drs. Boring and Armstrong. The collapse deepening. The surface of the body very cold. Thirst was excessive, and the patient complained of great heat, requiring to be constantly fanned, declaring that she was "burning up." The dejections were constant, involuntary, colorless and odorless. The physiognomy was that of an aged woman. The case terminated fatally at 10.30 p. m.

The excreta of this case were carefully disinfected, and although Mrs. S. was surrounded by her family, and by a large number of friends during her illness, no other case occurred in the city.

The treatment adopted was the application of sinapisms and dry heat and the application of camphor, capsicum, laudanum, and tinctura rhei combined. But little opportunity was presented for treatment, the disease being fully developed before the patient was first seen by Dr. Boring.

The second case, to which attention is asked, occurred at the town of Dalton, the county-town of Whitfield County. This town is the southern terminus of the East Tennessee, Virginia and Georgia Railroad, and has a population of about 5,000 inhabitants.

Dr. J. R. McAfee, of Dalton, Georgia, reports the case of Robert nzy, who died at that city of cholera on the 3d day of July, 1873.
On the 2d of July this man arrived at Dalton on the morning train m Chattanooga, Tenn., at which city several members of his imme-ıte family had died of cholera. At 12 o'clock m. of Thursday, July Linzy was attacked with the same disease, and died at 9 o'clock p. m. e same day.
The treatment adopted was the exhibition of stimulants and astrin-nts, but no good results were obtained.
The excreta of this case were carefully disinfected, and agents of that ler were freely used on the premises; and although a number of per-ns were exposed to the disease no other cases occurred.

)LUMBUS:

The Alabama State Journal, (Montgomery,) July 30, 1873, noting a ath from cramp colic at Columbus, Georgia, application for informa-n was made to Dr. George J. Grimes, from whom the following letter s received:

"COLUMBUS, GA., *August* 13, 1874.

"SIR: Your letter of inquiry relative to the number of cases of olera occurring at this place (in 1873) has just been received.
"In reply, I have to say that, not having had any cases myself, I have ade diligent inquiry from all the physicians here, but with a negative sult in each instance, none of them having come in contact with the sease, so far as I can learn, and hence I would infer that cholera had ot made its appearance here for many years.
"Very respectfully,
Your obedient servant,
"GEORGE J. GRIMES, *M. D.*

"ELY MCCLELLAN,
"*Assistant Surgeon U. S. A.*"

CHAPTER XVII.

MINNESOTA GROUP.

MINNESOTA CONTRIBUTORS.

Dr. D. W. Hand, President State Board of Health, Saint Paul, Minn.
Dr. E. S. Frost, Willmar, Kandiyohi County.

INITIAL CASE.

Crow River, Kandiyohi County, July 3.

The history of the cholera-epidemic of 1873, as it affected the State of Minnesota, is strongly corroborative of the third proposition presented in the chapter on the etiology of the epidemic.

Minnesota is one of the Northwestern States of the United States. The State lies between 43° 30′ and 49° north latitude, and between 89° and 97° west longitude; at an elevation of about 2,000 feet above the waters of the Gulf of Mexico; with an area of 81,259 square miles and a population, according to the census of 1870, of 439,706 inhabitants. The area of the State containing 52,005,760 acres, there is an allowance of about one hundred and eighteen acres per individual of its inhabitants.

The geology of the State is described "as drift, lying on crystalline and metamorphic rocks, which occasionally protrude to the surface, that portion of the State east of the Red River of the North. In the southeastern portion of the State, the lower magnesian limestone crops out in the valleys of the Mississippi and Saint Peter's rivers, and the latter river sandstone, and occasionally igneous rocks, are found. In the northeast of the State is a tract of hornblendic and argillaceous slates, with bedded porphyries and intrusions of greenstone and granite."

The meteorological observations made at Fort Snelling, Minnesota, which post is on the same latitude as the locality hereafter to be noted as the point within the confines of the State that became infected with cholera in 1873, are presented as of value.

Mean temperature of 1873 and 1874, 41° 41′.

Maximum temperature, 92°; minimum temperature, 26°.

Amount of rain-fall in same period, 17.26 inches.

Early in the month of July, 1873, a family, named Antonson, arrived at a settlement of Swedes upon Crow river, Kandiyohi county, in Southwestern Minnesota. This family consisted of Errick Antonson, his wife Johanna, four children, who ranged from fourteen to two years of age, and one Christian Oleson, a young man and a family friend.

On the 3d day of July, the day after their arrival, Christian Oleson was attacked with diarrhœa, which lasted for two days, when vomiting and cramping occurred. The patient became collapsed, but reacted, passed into the typhoid stage, and died July 10.

July 6, Bertol Antonson, a lad nine years of age, was attacked with diarrhœa, cramping, and vomiting, became collapsed, and died within forty-eight hours.

July 9, Malina Antonson, a girl of eleven years, was attacked with a similar disease, and died within twenty hours.

July 12, Breta Antonson, an infant of two years, was attacked, and
d after an illness of ten hours, and the same day Errick Errickson,
whose house these people had been taken ill, was attacked and died
thin eight hours.

These five cases were ill, and died without receiving any medical
sistance. On the 12th instant Dr. E. S. Frost, of Willmar, thirty
les distant, was called to the cases, but on his arrival both were dead.
July 13, Johanna Antonson, the mother, was attacked, but under the
re of Dr. Frost recovered.

July 16, the remaining child, a girl of fourteen years of age, was at-
cked, but recovered.

Dr. Frost is decided that the cases which came under his observation
ere cholera, but is unable to trace any connection with the infection in
e United States with this family.

All the inmates of this house suffered with diarrhœa, and three deaths
om cholera are reported among persons living at a distance, but who
d visited the house during the illness of Christian Oleson.

Through an interpreter, Dr. Frost was able to gather the following
utline of the fatal cases:

"Christian Oleson commenced with diarrhœa and vomiting, and on
e second day was stupid and senseless to those around him, yet they
oticed that he had cramps by the twitching of his eye-balls, which
ere retracted. His face was of a black-grayish color, and all who died
oked the same. The vomit was green and yellow at first, but later
othing but water. Their stools were made every minute in bed, and
ere nothing but water. They were very thirsty, and drank much water.
hey did not complain of being cold, but skin was ice. The muscles
ere knots under the skin, and moved from their hips to their feet.
hey cried much with pain, but became still when near death."

This disease was recognized by the people as cholera; the neighbors
oided the house, and even the wind blowing therefrom. Errick Er-
kson had long been a resident in the county. His brother dare not
pproach the house, and his body was cared for by those of the Anton-
ns who were well enough to do so.

The Antonson party left Vük, Alfoden, which is some two hundred
iles north of Bergen, which distance they traveled by steamer. At
ergen they remained for three weeks awaiting the departure of a
eamer, and finally took passage for New York upon the steamer Peter
ipson, Captain Wolf, and arrived at New York on the 26th of June,
73. Upon this vessel were two hundred and ninety-eight passen-
ers, but the quarantine records of New York Harbor show that no
lness had occurred upon the vessel during the voyage.

From New York City the Antonson party were transported to Grand
aven, Mich., remaining but one half hour at Pittsburgh, Pa. At
rand Haven they remained over night, and the next day crossed Lake
lichigan to the city of Milwaukee, Wis., where they remained one half
ay and one night, and thence proceeded direct to Saint Paul, Minn.,
here they rested twenty-four hours; thence to the Crow river settle-
ent via Willmar.

Before leaving Bergen, the effects of this family were packed, except
uch articles as were required for use upon the journey, and which
assed as hand-luggage; but at Willmar, on the 2d day of July, the
runks and boxes (packed at Bergen) were opened, and additional arti-
les of clothing were distributed; *the next day Christian Oleson sickened
ith the diarrhœa.*

Upon the journey from New York City, this family subsisted upon

bread and milk *exclusively;* after they arrived in Minnesota they ha[d] pudding and milk, but no vegetables or fruits.

At our solicitation, Dr. Frost was kind enough to make two dis[tinct] visits to the remaining members of this Antonson family, for the pu[r]pose of testing the information obtained, and, at our suggestion [that] Bergen was the point of infection, directed his inquiries in that dire[c]tion, when from Antonson he learned the facts as now published, [that] prior to their departure cholera had occurred at Bergen, and that sin[ce] their arrival in America they had learned of the death of friends fr[om] that disease.

The above is presented as a distinct, isolated, but positive epidem[ic] of cholera occurring in the United States during the summer of 18[73] produced not by local causes, influenced not by individual indiscretion[s] but by positive importation. When the trunks or chests that had [not] been touched since they were packed at Bergen on the island of Rage[n] a port of the Baltic sea, at which city cholera had been present dur[ing] 1872 and 1873, were opened at Willmar, Kandiyohi county, Minnesot[a] United States, then and there was the person of Christian Oleson in[-] fected with cholera, the material of which had been conveyed from the Baltic in the fabrics of which the articles of clothing were prepar[ed] and from Oleson, the Antonson family, and Errick Erickson, and three other persons who are unknown, were infected.

In the report of the State board of health of Minnesota for 1873 it is erroneously stated that the Antonson family had passed through the city of Chicago, Ill.; it is shown by more careful investigation that not only did they not pass through Chicago, but that they passed through no territory infected with cholera in the United States. The only port through which this family passed, that at any time during the year 1873 became infected with cholera, was the city of Pittsburgh, Pa., and the few cases (four) in that city did not occur until thirty days after the death of Christian Oleson and the Antonsons in Minnesota.

It is most earnestly urged, that had a system of disinfection of the effects of emigrants arriving at the port of New York, from cholera-infected ports of Europe, been in operation during the year 1873, it would have saved to the State of Minnesota the valuable lives of five immigrants and four residents.

CHAPTER XVIII.

ENNSYLVANIA GROUP.

PENNSYLVANIA CONTRIBUTORS.

. W. Snively, Allegheny County, Physician to Board of Health.
r. Crosly Gray, Allegheny County, Health-Officer.
. A. Arthurs, Allegheny County.
r. M. A. Arnholt, Allegheny Co.
Dr. T. P. Graham, Allegheny Co.
Col. Jno. E. Addicks, Philadelphia Health-Officer.
Dr. A. Bournonville, Philadelphia.
Dr. W. H. H. Githens, Philadelphia.

INITIAL CASES.

Pittsburgh, Allegheny County, August 1.

Pittsburgh, a city of nearly one hundred thousand inhabitants, is cated at the confluence of the Alleghany and Monongahela rivers, in 'estern Pennsylvania, three hundred and fifty-seven miles west of the ty of Philadelphia. The population of the towns of Allegheny City id Manchester, at the junction of the Alleghany river with the Ohio, id of Birmingham on the left bank of the Monongahela, should properly) added to that of Pittsburgh, making a total population of two hun-ed thousand people closely connected in all conditions of life.

Pittsburgh is a manufacturing city of immense importance; a shipping ort for vast quantities of coal, oil, &c., and is one of the great railroad-nters of North America.

To Dr. William Snively, the physician to the board of health, we are ndebted for a history of the cases of cholera which occurred at the city f Pittsburgh in 1873.

About the 29th day of July, 1873, Mr. Mooney—who was a railroad ontractor—and his wife returned home from a visit to Cadiz Junction, hio. They resided at a point on the Ohio river about five hundred ards beyond the city line. Directly in front of the house lies the public oad and Ohio river, while a few feet to the rear, and at a considerable levation above the house, are the tracks of the Pittsburgh, Cincinnati nd Saint Louis Railroad.

Two days after their arrival home, August 1, Mrs. Mooney, who was our months and a half advanced in pregnancy, was attacked with ainless diarrhœa, soon succeeded by vomiting, cramps, suppression of rine, rice-water discharges, clammy skin, shriveled extremities, &c., he case terminating in death Monday morning, August 4, at 8 o'clock . m. Dr. Stephenson, who was in charge of the case, reports that Mrs. Mooney, when in the collapse stage, and a short time before death, was aken with labor, and that she was delivered of a fœtus of about the ourth month of gestation. The physicians in attendance, although isposed to consider the case one of Asiatic cholera, did not report it to the board of health, as it occurred beyond the limits of the city.

Monday evening, August 4, Mr. Mooney was suffering from diarrhœa; was prescribed an opiate by his physician. Tuesday morning he felt better, and visited the city for the purpose of making arrangements for

the burial of his wife. While in the city he became very ill, and called on his physician, who prescribed for him, and ordered him to go home and to bed immediately. He did so, continuing to grow worse, suffering from the same train of symptoms described in the previous case. Tuesday night he sank rapidly, and Wednesday morning was in collapse. He died at half past 5 o'clock p. m. During his illness he was visited by a number of physicians, all of whom (skeptical before seeing the case) concurred in pronouncing it Asiatic cholera.

Case 3.—Mary Ward, married, age forty years. Mrs. Ward resided in a small frame house which stands about five yards within the city line, and about five hundred yards from the house where the former cases occurred. Mrs. Ward, who had always enjoyed good health, was with Mrs. Mooney at the time of her death, and assisted in the performance of various duties, remaining in the room probably an hour altogether. This was her only visit to the house.

Two days after, Mrs Ward was attacked with diarrhœa, rapidly succeeded by all the symptoms observed in the two former cases. She died Thursday, August 6, at 8 o'clock p. m.

Case 4.—James Lyons, single, age twenty-five years. He worked in an iron-mill, and had never been sick in his life. He assisted the "sanitary inspectors" to burn the bedding, carpets, &c., at Mr. Mooney's house, on Wednesday evening. He was attacked with painless diarrhœa on Friday, August 8. The preliminary diarrhœa was soon succeeded by violent cramps of the muscles, particularly those of the extremities. Slight vomiting of a clear, watery fluid, containing no bile. Rice-water discharges not so copious as in the former cases. There is suppression of urine, intense thirst, and marked restlessness. Pulse weak, but natural in frequency. Tongue foul, face and extremities cold, breath and tongue warm. Whole surface changing in appearance. Skin from middle joints of fingers to tips inelastic, shriveled, and of a bluish tinge. Intellectual faculties unimpaired. There is slight disposition to stupor, but he is easily aroused, and converses sensibly and intelligently. Temperature in axilla, 99° Fahr.

The vomiting, cramps, and evacuations gradually cease, and the voice begins to get husky; greater tendency to stupor; pulse becomes fluttering, thready, very difficult to count. Whole surface covered with clammy perspiration. Temperature, 99°.

The respiration becomes feebler, the breath and tongue cold, the voice lost, and the pulse imperceptible; only a feeble, oscillatory movement of the heart being perceptible upon auscultation. Temperature, 99⅔°.

He died at 1 o'clock p. m. Sunday, August 10. Temperature of body, two hours after death, 97⅘°.

The duration of the disease in the first case (Mrs. Mooney) was about seventy-two hours; in the second case (Mr. Mooney) about forty-six hours; in the third case (Mrs. Ward) about twenty-four hours; in the fourth case (Mr. Lyons) about forty hours.

These four cases terminating fatally in rapid succession, occurring at this isolated point on the city line, and originally traceable to Mr. and Mrs. Mooney's visit to Cadiz Junction at a time when Asiatic cholera was reported as prevailing there, seems (in the absence of any known cause) sufficient to establish the nature of the disease. That it did not become epidemic is due to several causes: 1. The remoteness of the locality from the populous portions of the city, rendering isolation easy. 2. The immediate disinfection with carbolic acid and sulphate of iron of all the excreta, and the destruction by fire of bedding, carpets, &c.

lothing that had become soiled with the discharges, and which might ave conveyed the infection to others.

Mr. Mooney informed his physician that, prior to his leaving Cadiz unction, Ohio, where he had been superintending some repairs to a ailroad-tunnel, several deaths had occurred within a few hundred ards of the house at which he and his wife were boarding, and that he ad been informed that these persons died of cholera morbus.

We have made every endeavor by communications to obtain informaion from Cadiz, Ohio, as to this occurrence, not having been able to ake a personal inspection of the locality, but have been so unfortunate s to fail to elicit sufficient interest to secure a reply.

Dr. Snively is kind enough to inform us that there has been in Pittsurgh this season (1874) about the usual number of cases of cholera norbus. Fourteen deaths from this cause were reported during the nonths of July, August, and September. The *cause* of this disease was enerally traceable to error in diet, exposure to cold, &c. The cases enerally recovered, unless suffering from some vice of constitution. o particular sanitary precautions were taken with regard to this disase, and in no instance was there any evidence of *contagion*.

HILADELPHIA.

During the summer of 1873 the following dispatch was extensively opied throughout the United States: "There are many cases of what s called by the physicians sporadic cholera in the up-town sections of he city, especially in the densely-populated districts. It is particularly ad in the Eighteenth and Nineteenth wards, and the disease seems on he increase."

A careful investigation, however, demonstrates the erroneousness of his report. By Col. J. E. Addicks, the health-officer, we have been urnished with a copy of the records of all reports made of such cases o the health-office, and from them we find that during the months of June, July, and August, 1873, eight cases of cholera were reported, with wo deaths. The official returns of the physician to the board of health pon these cases is as follows:

June 21.—Case at No. 1118 North Front street; sporadic cholera; leath.

June 24.—Case near Sixth and Pine streets; sporadic cholera; death.

June 28.—Case at No. 2052 Lombard street; cholera morbus; recovery.

June 28.—Case at No. 1732 Lombard street; cholera morbus; recovery.

July 7.—Case at No. 2058 Lombard street; cholera morbus; recovery.

July 9.—Case at No. 612 Peach street; cholera morbus; recovery.

July 20.—Case at No. 120 Cottage street; cholera morbus; recovery.

August 20.—Case at Fourth and Vine streets; sporadic cholera; recovery.

Of the first case we learn that the patient was a female who was taken sick upon a Monday morning with cramps in abdomen and vomiting; that the matter vomited was dark-colored and mixed with food that had been taken; that the dejections were mucous and fœtid. She died the next day with all the symptoms of collapse. The physician in attendance pronounced the case sporadic cholera. The neighborhood in which this case occurred was clean. No other cases occurred. Privy-well disinfected.

Dr. W. H. H. Githens has reported to us that the second case in this series occurred in the person of a shoemaker, in very miserable circumstances, who lived in an overcrowded tenement-house, and who slept upon the floor. The privy-vault was under the house, and the gases escaped into this main room. This case resisted all treatment, and died after a few hours' illness. The locality at which this case occurred was in a very bad sanitary condition. Disinfectants were employed. No other case occurred.

Case 3 was pronounced, upon inspection, simply a case of light cholera morbus in a delicate woman.

Case 4.—A slight attack of cholera morbus in a female who had for years been liable to such attacks after any imprudence in diet.

Case 5.—Was not even cholera morbus; only a slight colic.

Case 6.—A case of cholera morbus after imprudence in diet.

Case 7.—A case of cholera morbus after imprudence in diet.

Case 8.—Dr. A. Bournonville has been kind enough to report this case as having occurred in the person of a confectioner in good circumstances, who was attacked during the night with diarrhœa, vomiting, and cramps. The discharges became rice-water in character, the skin was shriveled, the surface blue, &c. This patient was, however, convalescent in six days. No cause could be assigned for the attack.

As it has been shown that at both New York and New Orleans there arrived during the early months of 1873 the infection of cholera, it is of importance that an exhibit of all arrivals during the same period be made for the port of Philadelphia, a port of entry, and the second city in size and population in the United States.

From statistics furnished by the Health-Officer of Philadelphia we are able to present the following tables:

I.—*Table of number of vessels, with number of passengers and number of crew, that arrived at the port of Philadelphia from ports of Great Britain during the first six months of* 1873.

Port of departure.	Number of vessels.	Number of passengers.	Number of crew.	Total.
London	22	.....	263	263
Liverpool	63	312	1,234	1,546
New Castle	7	.....	91	91
Shields	3	.....	35	35
Falmouth	1	.....	8	8
Ipswich	2	.....	29	29
Harwich	1	.....	10	10
Gloucester	2	.....	25	25
Fowey	1	.....	7	7
Hull	1	.....	13	13
Grimsby	1	.....	15	15
Plymouth	1	.....	11	11
Glasgow	1	.....	14	14
Greenock	1	.....	12	12
Cardiff	1	.....	14	14
Swansea	1	.....	11	11
Dublin	4	1	49	50
Belfast	2	.....	30	30
Londonderry	1	.....	16	16
Aligo	1	.....	12	12
Warren Point	1	.....	12	12
Total	118	313	1,911	2,224

Table of number of vessels, with number of passengers and number of crew, that arrived at the port of Philadelphia from European ports during the first six months of 1873.

Port of departure.	Number of vessels.	Number of passengers.	Number of crew.	Total.
[illegible]dam	6	3	89	92
[illegible]dam	6	.....	89	89
[illegible]rp	20	729	483	1,212
[illegible]lm	3	.....	31	31
[illegible]burg	5	.....	55	55
[illegible]	5	.....	32	32
[illegible]n	1	4	14	18
[illegible]er	1	.....	16	16
[illegible]	10	.....	177	177
[illegible]urg	21	.....	294	294
[illegible]	1	.....	12	12
[illegible]	7	.....	113	113
[illegible]lles	4	.....	49	49
[illegible]	1	.....	11	11
[illegible]pe	1	.....	13	13
[illegible]	1	.....	10	10
[illegible]ante	1	.....	11	11
[illegible]ona	1	.....	9	9
[illegible]	3	8	56	64
[illegible]to	1	.....	11	11
[illegible]	6	.....	82	82
[illegible]rn	4	3	54	57
[illegible]na	18	12	189	201
[illegible]rmo	15	5	167	172
[illegible]a	1	.....	10	10
Total	143	764	2,077	2,841

It is demonstrated by these tables that there arrived at the port of Philadelphia during the first six months of 1873, 261 vessels, with 1,077 passengers, and 3,989 in crew. From the statistics that have been furnished us, we find that during the second six months of 1873 there arrived at the same port 319 vessels, with 3,048 passengers, and 5,895 in crew. Also, that from the same ports there arrived during 1874, 318 vessels, with 10,290 passengers, and 11,884 in crew; while from all ports there arrived at Philadelphia during 1873, 1,176 vessels, with 4,497 passengers, and 15,298 in crew; during 1874, 1,126 vessels, with 10,785 passengers, and 17,089 in crew.

To the small number of passengers who arrived during the first six months of 1873, Philadelphia certainly owes her exemption from the disease.

CHAPTER XIX.

TEXAS GROUP.

TEXAS CONTRIBUTORS.

Dr. James Johnson, Grayson County.
Dr. B. K. Wood, Grayson County.
Dr. A. W. Atcheson, Grayson County.

Surgeon John F. Hammond, U. S. A.,
Medical Director Department of Texas.

INITIAL CASE.

Denison, Grayson County, August 1.

TEXAS.

Having been informed by Dr. C. B. White, the president of the Louisiana State board of health, that early in the year 1873 he received a letter from a medical friend resident at San Antonio, Texas, inquiring as to the existence of cholera in the city of New Orleans, and stating that suspicious diarrhœal cases had occurred at or near San Antonio, addressed Surgeon John F. Hammond, U. S. A., medical director Department of Texas, asking information on this subject, from whom we have received the following letter:

"SAN ANTONIO, TEXAS, *September* 10, 1873.

"Assistant Surgeon ELY MCCLELLAN:

"MY DEAR DOCTOR: On inquiry among the physicians of this place I have ascertained that there were in San Antonio—

"I. An unusual number of cases of diarrhœal diseases in the month of December, 1872, and that during January and the succeeding two months the number of such cases was greater than usual.

"II. Several cases are said to have assimilated cholera. One case, that of the Rev. Mr. Guion, chaplain Tenth United States Cavalry, who was under my care, occurred during the latter part of May or early June. It was a severe attack of cholera morbus. I was struck with a resemblance to cholera. He was decidedly convalescent within thirty-six hours from the commencement of the attack.

"III. All the cases, *so far as my information extends*, except that of Mr. Guion, occurred among Mexicans.

"I see by the monthly reports of sick and wounded on file here, that among the troops stationed here at the time, both white and blacks, there was no unusual occurrence of these diseases.

* * * * * * *

"Truly yours,

"J. F. HAMMOND."

GRAYSON COUNTY.

The only authentic evidence which we have received of the epidemic of 1873 in the State of Texas, is from the town of Denison, in Grayson

orthern county of the State, bordering on the Red river, which sep-
tes it from the Indian Territory.
We present two communications which we have received, and which
of interest as representing the two classes of views held upon the
ntity of the epidemic of 1873.

CHOLERA AT DENISON, TEXAS.

By James Johnston, M. D.

The town of Denison is situated in Grayson County, Texas, and is the
minus of the Missouri, Kansas and Texas, and the Houston and
xas Central Railroads. It was only one year old when the cholera
de its appearance. It contained at the time between three and four
usand inhabitants, who were principally emigrants from the North-
and Eastern States. The first case of cholera that came under my
ice was that of Dr. Moyse, who was attacked on the morning of the
of August, 1873; went into collapse same evening, and died at 3
lock a. m. of the 9th instant.
Having to leave town on business, I did not return until the 19th
ptember, and I learned from other physicians that few cases occurred
ring this interval.
About the 27th September we had some rain, and afterward heat,
en it broke out with greater violence, and for the eight days follow-
, the average deaths numbered seven to eight per day, and from the
ddle to the end of September the average was about four per day.
w cases occurred after this up to the latter part of October, when the
t case came under my observation.
When the disease first made its appearance the town was in a filthy
te. Being a new town, crowded with a floating population, there were
t sufficient improvements in the city, and the people were not so com-
tably fixed as in older towns.
There was diversity of opinion among the physicians with regard to
e nature of the disease, some asserting it was not cholera, and the
ard of health and city council, with a view of preserving the town in
prosperity, published circulars to this effect; and in order to set the
blic right, and establish a correct diagnosis, I wrote a paper on the
bject, which appeared in the Sherman Patriot of November 1, 1873.
copy of the manuscript I herewith inclose.) The medical association
this county have since confirmed my opinion. I return you a list of
e cases that occurred, or as many of them as I could get any account
only a few of which I attended professionally. Some were attended
other physicians, who have since left town, and some died without
edical aid.
In making up the statistical account allowance must be made for
ose that have been attacked and got well without any medical treat-
ent, and that never came under the notice of the physicians, and con-
quently do not appear on the list.
The probable number of deaths during the epidemic amounted to
ghty, and the number of those attacked (giving due allowance for
ose that got well without our knowledge) would be, as near as I can
ess, twice that number. The fatality of the disease seemed to be in
oportion to the amount of filth about the locality in which they lived,
d the habits of the patients, &c., being more fatal to those of dissi-
ated habits and those deprived of their ordinary rest and food, and
ose exposed to excessive fatigue. Grief and fear, on account of the

depressing effects they produce on the nervous system, have a wonderful tendency to induce an attack.

With regard to treatment, my experience has led me to the conclusion that the treatment of cholera, to be comparatively successful, must be commenced early, when the first symptoms of choleraic diarrhœa makes its appearance. I believe that a locality may be almost entirely saved from the scourge by adopting at once proper sanitary and hygienic measures; the treatment must consist more of prophylactic than curative. When the disease first breaks out, all yards should be cleaned, and water-closets disinfected, decaying vegetable substances removed, &c. People should observe regular habits, eat their accustomed food, avoid undue fatigue and excessive impulses of the mind, such as grief and fear, or great anxiety, and see that all the functions of the body are kept in proper order.

On the treatment of well-established cases, or those who have passed into collapse, I have nothing new to say, as volumes have been written on the subject. I will close these few remarks by giving my treatment of one of the worst cases I attended.

Peter Linn, an Irishman, who worked in a brick-yard, was attacked on the 29th October, 1873. I was called to see him about 7 o'clock a. m., and found him in a collapsed condition, perfectly cold, even his tongue and breath, shrunken features, husky voice; he could not speak above a whisper; he had all the symptoms of approaching dissolution. At this advanced stage I did not see any use in giving medicine by the mouth, so I made a solution of one grain of strychnia, and with a hypodermic syringe injected it at different points all over the extremities until almost half of the mixture was used up. I did this in order, if possible, to arouse the action of the nervous system and establish the capillary circulation. I saw him the following morning when the alarming symptoms had passed away; the heat of the body had returned, he took some nourishment and continued to improve, and finally got well. He suffered a little from singultus, from the effect of the large amount of strychnia and the manner in which it was used, as the patient was a very bad cholera subject. He was a man about fifty years of age, with a very feeble constitution and dissipated habits; his digestive organs were very much impaired by drinking bad whisky. I consider the strychnia used in this way at different points all over the extremities much better than giving it by the mouth, as in such cases the stomach and bowels are almost inactive, and very little certainty can be placed on medicines given in that way, and the greater number of points it is inserted the better. In the case mentioned I used the syringe at eight different places, all over the feet and legs, hands and arms.

[From the Sherman (Texas) Weekly Patriot, October 4, 1873.]

"We were in Denison about an hour on Tuesday evening last on our return from Saint Louis, and we were informed by two reliable citizens of that place that on the day and night previous there had been nine or ten deaths from cholera, and that considerable excitement existed. Many were leaving, and business perfectly dead. On Tuesday last and Tuesday following there were seven deaths, as we learn from Mr. Burke, who came down on Wednesday morning. The News of Denison is very silent on the subject; we think this is wrong, as the people should be fully advised. * * * Since the above was penned, we learn from Mr. O'Bannan that there were five deaths on Wednesday, October 8. * * We learn that up to Tuesday last there had been about twenty deaths at Denison from the prevailing disease, which has been on

some doctors cholera, and by others congestion. We learn from Mr. nson, who came down on Monday morning from Denison, that four ths took place there the day and night previous. * * * * We rn that on Wednesday and the night previous there were six or eight ths there. * * * Governor Owings and others of that place in-med us that a large portion of the population had left, probably over housand or fifteen hundred." * * *

THE CHOLERA AT DENISON, TEXAS.

the Editor of the Sherman Patriot:

For some weeks past a disease has visited the thriving town of Deni-, and about sixty deaths during the past three weeks have been the ult of this sad visitation. The inhabitants have been startled, and ny inquiries have been made with regard to what this disease is. ne physicians of good standing pronounce it by one name, and ers another; and the public are puzzled to know what the malady and how it may be averted; and the people very justly look to the dical profession for information. And it has been suggested that if physicians here could not diagnose and treat the disease, that a scription be raised for the purpose of bringing experienced physi-ns from a distance, who were capable of treating such cases success-ly.

Now, for my own part, I cannot see any reason for not coming to the nclusion that the disease with which we have been afflicted is cholera; l those who coincide with me in this conclusion are physicians who re been in practice in the South for a number of years. I may men-n the names of Lipscomb, Field, Cooke, and Harris.

I do not wish to be dogmatical in my assertions, and give due respect those who differ from me. I have no desire to come out in the pub-press on a subject suited for discussion among medical gentlemen, or a medical association; but circulars have been printed and published, d articles have appeared from the press, that the disease with which have been afflicted is not cholera, and is not an epidemic.

* * * * * * *

The absence of malarious influence we have in this locality would not rrant us in coming to the conclusion that these cases are exclusively a malarious character. The number of deaths we have would repre-nt several thousand cases of ordinary remittent and intermittent fever at always, under proper treatment, get well, even in the most malarial-fected localities, and a large number of the very worst cases of this se will yield to treatment.

"Under cinchonism and other proper management not more than one eight probably die." (Hartshorn Essentials, page 323.)

In none of the forms of congestive fever is the first paroxysm apt to of a pernicious character. In the majority of instances the disease gins as an ordinary periodic fever, and it is only in the second or rd paroxysm the alarming symptoms appear. Nor is the first con-stive paroxysm very likely to prove mortal; generally it is not until e second or third that a fatal issue is to be apprehended. (Da Costa Diagnosis, page 725.)

The history of cholera goes to show that it is not confined to any par-cular locality or country. Since 1545 we have accounts of its fre-ently breaking out, from time to time, in different parts of Europe, far north as 64° north latitude, and on this continent we have ac-

counts of its progress since 1832 as far north as Canada, and south to Mexico, the West India Islands, and Central America, and this season we have accounts of it in several parts of Europe, and the eastern cities of this country. I am happy to state that with the change of the season, and the sanitary arrangements that have been adopted, scarcely a trace of it exists at present in this place, and I can state, without fear of contradiction, that the general health of the people of Denison is better, and there is less mortality than there has been for the last eight months.

II.—THE PREVAILING DISEASE AT DENISON, TEXAS DURING THE FALL OF 1873.

By Alex. W. Acheson, M. D.

A disease called cholera visited Denison, Texas, in 1873 and 1874. A few isolated cases were met with during the summer of those years. In 1873, during the month of October, from two to six cases were met almost every day.

Denison is a new town; was born September 23, 1872. When the disease prevailed at its worst the town was but one year old. The inhabitants were all new-comers, therefore unaccustomed to the climate, the water, the food. There were not sufficient conveniences of any kind. Four thousand people lived on six acres. This is denser than New York crowded. Such a state of affairs will intensify any prevailing disease. There was considerable sickness previous to this outbreak. Pneumonia, meningitis, measles, bilious fevers, infantile diarrhœa, and dysentery prevailed. They were unusually severe and fatal.

The majority of the inhabitants were men; railroad-hands, loose in morals, careless in habits, living in and around saloons. The site of Denison is good, high, well-drained, sandy soil, pure water, no pools. The town is three miles south of Red river; the prevailing wind is from the south; no reason why it should be a sickly town. The year just past has been very healthy.

The symptoms presented in this scourge were those usually seen in cholera. There were vomiting, purging, profuses weating, extreme thirst, coldness of surface, loss of elasticity in the skin, washer-woman's fingers, altered respiration, loss of voice, quickened and weak pulse, decreased temperature, cramps in the bowels in the beginning, cramps in the legs towards the close, collapse, &c. We will not describe the symptoms *in extenso*. There were other symptoms present; to these we will refer hereafter.

Popular opinion said this was cholera. Half of the physicians of Denison said so, too. Was it?

What is cholera? A disease originating in India.* It acts by impairing the power of the nerve-centers governing the thoracic and abdominal viscera. Consequent on this defective innervation are vomiting, purging, sighing, respiration, collapse.

To prove this cholera, first, the possibility of importation must be shown; second, the impossibility of other diseases impairing these nervous centers, and giving rise to these symptoms.

First. *Importation.*

Cholera (?) prevailed in Tennessee in the summer of 1873. (Tennessee is five hundred miles from Denison; no direct connection be-

* International Sanitary Conference, Vienna, July, 1874.

two.) It then prevailed in Kentucky; then in Missouri. In Septem-
it was as far west as Boonville, Mo. There was no cholera prevail-
east, south, or west of us. If imported, it came from Boonville,
ch is six hundred miles north of Denison, on the same line of rail-
d. It is claimed that a man from Boonville direct, stopped at the
el in Denison, when the disease appeared in its violence a day or two
r his arrival. Great importance is attached to this. We do not
p to question any link in this chain of importation. Grant that all
rue; then explain the deaths from this disease before this man's
ival.

here was a death from this disease on June 25, 1873. This was three
nths previous to this man's arrival, and previous (we believe) to the
break of cholera at any point in the United States. A second case
urred on August 8, a third on August 12, both previous to the appear-
e of the disease at the point from which it is claimed to have been
ported. Again, not only have many cases occurred before importa-
n was thought of, but cases are met with every year. During the
mer just past (1874) we have encountered thirteen distinctly marked
es of this disease. Ten others have been brought to our knowledge.
ese make twenty-three. As Asiatic cholera was prevailing nowhere,
ould not have been imported. Hence the cause must be indigenous.
indigenous it is not cholera.

SECOND. *The impossibility of other diseases impairing these nervous
ters, and giving rise to these symptoms.*

If we show that other diseases act like cholera, we show the proba-
ity of this having been something else than cholera. Is there any
ease which prevails in the South that presents the symptoms of
olera?

"The skin continues to grow colder, and is bedewed with a cold, un-
tural perspiration. He feels oppressed with excessive heat, calls
ice, and while his skin is cold and wet, wishes to be continually
ned. The skin becomes motley and bluish, its sensibility is im-
ired; the impress of the finger remains some seconds after pressure is
moved; respiration is irregular, with frequent sighing; countenance
ggard. In some cases there is watery purging, resembling Asiatic
olera."—(Congestive intermittent fever. Hunt, 1st ed., vol. I, p. 511.)

"A form called algid is characterized by notable reduction of tem-
rature; the extremities becoming as cold as marble, or the cold-
ss being like that of a cadaver. Profuse sweating characterizes some
ses. Vomiting and purging are not infrequently prominent symptoms,
ding to a state of collapse, like that in cases of epidemic cholera."—
ernicious intermittent fever. Flint, 3d ed., p. 867.)

"Indeed, the analogy between many of the symptoms above described
d those of epidemic cholera is very striking."—(Pernicious intermit-
nt fever. Wood, 6th ed., vol. I, p. 331.)

Dickson says: "The system seems to sink at once prostrate before
e invasion or exacerbation, which can scarcely be called at times fe-
rile. Reaction does not take place. The skin is cold and covered with
clammy sweat, as in the collapse of cholera; the pulse is weak and
ttering, the stomach is very irritable, the countenance is sunken and
le or livid. The phenomena are evidently the result of defective inner-
ation. The propriety of denominating these cases bilious remittent
ver, when they frequently run their course without exhibiting the
ightest sign of febrile reaction, has been doubted by some. They are,
owever, produced by the same cause as bilious fever."—(Bilious remit-
nt fever. Watson, 3d Am. ed. p. 967.)

"In a word, we perceive effects which bear, in the more severe and

malignant forms of the disease especially, a close analogy to those occasioned by other and more tangible toxical agents, like some of these as oxalic acid or nicotine. The malarial and several other zymotic poisons sometimes suddenly prostrate the system to the verge of the grave, or even destroy life in a few hours, and during the first access or, as Dr. Simon says, in the tremendous shock and depression thereby occasioned in the system. So rapidly destructive, indeed, is the effect that were it not for concomitant circumstances, it would often be difficult to form an idea of the real nature of the case."—(La Roche on Pneumonia and Malaria, p. 379.)

The above quotations regarding malarial fevers, which are the prevailing diseases of the section in which Denison is located, show that they may assume the appearance of cholera. Proof to this effect could be multiplied, if necessary. In the absence of positive proof of importation, and in the presence of positive proof that malaria simulates cholera, are we not justified in concluding that this was malaria?

In examining special cases of this disease, we noted a disposition to pass from the ordinary forms of malarial fevers to a malignant type simulating cholera, or to pass back, when proper remedies were used, to arrest it. In several instances patients were seized with well-marked bilious remittent fever; after this had continued some time, the disease assumed all the appearances of cholera. In other instances, where the choleraic symptoms were checked, bilious fever presented itself. In still other cases the choleraic symptoms exhibited periodic movement without fever.

We are aware that these facts have been noted by writers upon cholera, and claimed as illustrations of the erratic manner in which the disease acts. But may they not be examples of the erratic course of malaria? It acts thus, as writers on malarial disorders will testify.

It is claimed that this was cholera, because epidemic; and epidemic because fifty cases occurred in one month.

To this we attach no importance. The summer and early autumn are healthy; after the long-continued heat sickness ensues, but not until the weather breaks. Then fifty cases of pneumonia, bilious fever, congestion, bronchitis, menorrhagia, or leucorrhœa may be encountered. All these cases will be mild or severe according to the condition of the systems attacked.

In claiming that this disease was imported, it is implied that it was contagious. There is not a single fact in the history of the disease pointing toward contagion.

In one house, 14 feet square, where fourteen persons slept, the vomit and the stools were spilled upon the floor, and yet the disease did not spread.

Throughout the continuance of the disease in the city, no effort at disinfection whatever was made, and yet there is not the slightest evidence of the disease being propagated.

In a few well-marked cases, post-mortem examinations were held immediately after death. Inquiry was only made concerning the abdominal viscera. The stomach and bowels were usually empty, and always congested, though generally slightly so. The liver was always bronzed and congested. In one case it was intensely congested, and in another softened. The spleen was always congested, in one instance intensely, in one enlarged, and in one softened. However doubtful the ante-mortem symptoms might be concerning the nature of the disease, the post-mortem symptoms pointed unerringly to malarial poisoning.

DENISON, TEXAS, *November* 17, 1874.

CHAPTER XX

WA GROUP.

IOWA CONTRIBUTORS.

. A. W. Cantwell, Health-Officer, Davenport.
. A. S. Maxwell, Davenport.
. W. F. Peck, Davenport.
. J. F. Baker, Davenport.
. W. W. Grant, Davenport.
. L. French, Davenport.
. J. Bell, Davenport.
Dr. E. H. Hazen, Davenport.
Dr. J. W. W. Baker, Davenport.
Dr. J. J. Tomson, Davenport.
Dr. R. J. Farquharson, Davenport.
Dr. C. H. Preston, Davenport.
Dr. W. D. Middleton, Davenport.
Dr. H. Heed, Chariton.

INITIAL DATE.

avenport, Scott County, August 14.

COTT COUNTY.

Davenport is the county-town of Scott County, located on the west nk of the Mississippi River, three hundred and thirty miles above int Louis, and one hundred and eighty-four miles west of Chicago. he city is laid out at the foot of a bluff which rises gradually from the ver, with a range of rounded hills in the background. Davenport is ie eastern terminus of the Mississippi and Missouri Railroad; the estern terminus of the Chicago and Rock Island Railroad.

The cities of Davenport and Rock Island are connected by a bridge, hich touches Rock Island, upon which is built the United States ord- ance arsenal.

We are indebted to Dr. A. W. Cantwell, Health-Officer of Davenport, r the following outline of the epidemic of 1873:

On the 14th of August, a white man from Saint Louis, who had come) Iowa to obtain work as a harvest-hand, was carried off a steamer om Saint Louis and placed upon the levee at Davenport. The man as found to be ill with cholera. He was cared for, but died in a few ours. No other cases occurred until August 28, when a gentleman rom the northern portion of the State, who had arrived a day or two revious from his home, was taken with diarrhœa at the Burtis House. n a few hours cholera was developed, and he died.

On the same day a young man, one of the telegraph-operators, who oarded at the Burtis House, was seized with the same disease, and ied after a few hours' illness. It was found after his attack that he ad been suffering with diarrhœa during the previous week.

August 30, a white man, living in the interior of the State, was taken rom a train from Chicago in the collapse of cholera, and died after an llness of two days at the Mercy Hospital.

From these cases the disease became epidemic, but was mostly con- ined to the district known as "Flat-iron Square," (see map,) which is ounded by Iowa and Le Clair streets, and extending from the river to Fourth street. At the foot of Iowa street a sewer empties into the river.

This sewer drains the portion of the town in which the cases noted had occurred. The river being very low the mouth of the sewer was exposed and the effluvium was perceptible in the locality.

The disease was chiefly confined to the foreign population, and especially to the Danes. Many of these people were residents of the city, but large numbers were attracted to the city in hopes of obtaining work, as some twenty miles of water and gas pipes were to be laid in the streets of the city.

Disinfectants were freely used, and the city was cleansed as rapidly as possible. The epidemic lasted about ten days, and subsided rapidly upon a change of the weather.

Dr. W. F. Peck reports having treated eleven cases, between the 14th of August and the 25th of September, of whom six died. The duration of the disease was from six to seventy-two hours. These cases were all of the lower classes. They all used impure drinking-water.

Dr. A. S. Maxwell reports having treated thirty cases, between the 18th of August and 20th of September, of whom nineteen were males, eleven were females. Of these cases six died. Twenty-one persons on this list used well-water; eight used river-water; one, cistern. The majority were among the lower classes. In twenty-seven cases there was premonitory diarrhœa. The duration of the disease was from six to forty-eight hours. In ten cases the convalescence was slow. In four, typhoid symptoms were developed; one case relapsed; one case had icterus.

Dr. A. W. Cantwell reports twenty-one cases, with fourteen deaths. Seventeen were males, four were females; all of lower classes; had used impure drinking-water. Treated at cholera-hospital. Seventeen had the premonitory diarrhœa. The disease lasted from three to seventy-two hours.

Dr. J. F. Baker reports five cases—one male, four females; all of the lower class; all had used bad water; four had diarrhœa. The disease lasted from four to sixty hours. Three died.

Dr. W. W. Grant reports nine cases—six males, three females. In all, the surroundings had been bad. Three cases died.

Dr. L. French reports seventeen cases—ten males, seven females; all of lower classes. The disease lasted from six to forty-eight hours. Six of these cases died.

Dr. John Bell reports eight cases—seven males, one female; all in poor condition in life; all used bad water. None died.

Dr. E. H. Hagen reports three cases—two males, one female; all had diarrhœa; all very poor. One case died.

Dr. J. W. W. Baker reports fifteen cases—nine males, six females; all had premonitory diarrhœa; some in good condition of life, but the majority poor. Five deaths occurred.

Dr. J. J. Tomson reports eleven cases—six males, five females. Four of these cases lived in good locality, seven in bad. Two cases died.

Dr. R. J. Farquharson, reports two cases—one male, one female; both in good condition of life. One died.

Dr. C. H. Preston reports one fatal male death.

Dr. W. D. Middleton reports thirteen cases—eight males, five females; all of poor class. Disease lasted from twelve hours to three and a half days. Five cases died.

One hundred and thirty-two cases are reported of whom no particulars can be obtained. Of these, eighty-nine recovered, forty-three died.

The convalescence of the majority of the cases which recovered is re-rted as being slow and complicated.

Additional evidence is offered in the following letter received from . R. J. Farquharson, of Davenport:

"DAVENPORT, IOWA, *December* 23, 1874.

"DEAR SIR: According to promise I send you some facts concerning e origin and progress of the so-called cholera-epidemic of 1873, as it peared in this city.

"The city is divided by an escarpment into two plateaux, the lower ing on an average 30 feet above low-water mark, and is composed of luvial soil, overlying Hamilton limestone, of the Devonian system, nich rock in some places crops out, or comes near the surface, and others is buried many feet. The upper plateau is composed of drift clusively, no rock being found in it but bowlders; it has an average evation of 160 feet above low-water mark. On the upper plateau ere are no sewers, the drainage being on the surface, and taking place wn many ravines, which widen as they join the lower level near the er; near their termination in the lower level their banks are rather nsely inhabited, and here many cases of cholera occurred. On the wer level in 1873, there were but the two main sewers. These sewers ere old, built of stone and mortar, of more than 2 feet diameter, with flat bottom. As they had very slight fall, the flow in them was very uggish, and as they did not reach to the higher ground were never ushed by the rains.

"The upper sewer, or that in Iowa street, during the time of the chol-a-outbreak did not reach the water by the space of 10 feet or more, that here upon the shore its putrid contents were discharged, and a ick draught or reflux of foul air must have taken place from the direc-on of the prevailing wind (southwest) during the months of August nd September, 1874. Most of the deaths took place upon the lower lateau, some of these, as upon the upper one, being really in the ravines unning up from the lower level.

"Two cases with one death, to my knowledge, were remarked, where oth parties, one a bootmaker and the other a founderyman, passed most f their time upon, and drank the water of the lower level. At Mercy lospital eight cases and five deaths occurred, six of which cases were ent from the town, and two were inmates of the institution. Of these ases I shall speak more fully when discussing the subject of the se-uence of cases at the hospital.

Near the railroad is a square bounded by Fourth and Fifth, Perry nd Rock Island streets, occupied by a new passenger-depot and a rge hotel, the Burtis House, then just finished and but recently occu-ied; as will be seen further on, here several deaths occurred. This otel had been but recently connected with the Iowa-street sewer. In lain street, near the river, is the site of the temporary cholera hospital. lere twenty-one cases, with fourteen deaths, occurred. The cases were, owever, brought from other parts of the city, mostly from near the pper sewer; few cases or deaths taking place near the lower sewer, .e., in the vicinity of the temporary hospital.

It may be stated that of the then population of the city, (23,500,) con-iderably more than half was contained in the lower and smaller part. n regard to water-supply, it may be said that both wells and cisterns ere used by those attacked with cholera, yet near the upper sewer ell-water was the prevailing drink, and the water of those wells was ndoubtedly impure from the long-continued drought.

STATISTICS.

Upon the receipt of your letter, I took the report of Dr. Maxwell, and endeavored to make it complete by addressing letters to physicians and others not included in that list; I also visited an apothecary who had attended a number of cases.

I have answers and reports from five physicians, and none from the others addressed. I deem it, therefore, impossible to ever get a perfectly accurate account of the number of cases. As to the number of deaths, the information is fortunately much more reliable, being derived from the undertakers, who keep more trustworthy accounts than the physicians, and are more ready to impart information.

From the books of the three undertakers of the city, it appears that eighty-two persons were buried who died of the cholera, to which number should be added three more, two of whom died at De Witt, and one at Durant, in this State, all having fled from the city, (two from a spot near the upper sewer,) making a grand total of eighty-five deaths. This differs from Dr. Maxwell's report, but is, I think, perfectly reliable. Dr. M., in making up his report, (which was compiled soon after the epidemic in 1873,) gets fifty-seven deaths from physicians' reports, then adds seven deaths in domestic practice, and again thirty-six not reported. Now, taking his fifty-seven deaths as reported by physicians, I am able to add twenty from additional reports, making a total of seventy-seven deaths, leaving only five deaths to be accounted for. Taking as a basis of calculation my reports—two hundred and fifty cases, with seventy-seven deaths, (a mortality of nearly 36 per cent.—eighty-five cases, at the same rate of mortality, would give two hundred and thirty-seven cases, which, I think, may be safely assumed as nearly correct.

NATIONALITY.

Under this head may be mentioned some curious facts. Most of the cases, and a large majority of the deaths of adults at least, were among foreigners; few Americans died, and no negroes died or were attacked, though many lived near the affected spots, and with the usual bad sanitary surroundings.

Of the eighty-five deaths, a large portion, fifteen at least, were Danes. When we consider their small number, (not over two hundred, including children,) this fact is a remarkable one.

Having some acquaintance among the Danes, I have made personal inquiry as to the truth of the above, and also to discover, if possible, some national peculiarity by which to account for their greater liability to this epidemic. As a result of my inquiries, I would state that none of the Danes dead from cholera had been less than one year in the country; indeed, most of them had been here several years. But I discovered that most of them, being day-laborers, partook at a late hour, say 9. p. m., of a peculiar dish called beer-soup, which undoubtedly, in many cases, seemed to be the exciting cause of the attack.

This dish is prepared by boiling stale bread in beer, this often sour, and adding thereto at the time of serving beaten-up eggs.

We come now to the dates and sequence of the early cases in the city and also in Mercy Hospital.

The first case of cholera in Davenport in 1873 was that of Charles Miller, a steamboat deck-hand, a German, and residing in Saint Louis, who was landed very ill on June 27, taken to Mercy Hospital, and died next day. The next case was that of Mr. Bennet, who died at the Ba-

s House July 28. Then Brown died at the Burtis House, August); then Stoeckel, August 30; and lastly, Prettyman, September 3.

Of these cases, Brown and Prettyman resided in the city, and boarded the hotel; the others were strangers stopping for a few days only. ideed, Stoeckel had just come over from Rock Island (where he had en for several days) was taken ill in the street, carried to the Burtis ouse, and died in a few hours.

Coming now to Mercy Hospital and its cases, I may be allowed to ate that I am secretary to the medical board, and also one of the visit- g surgeons, and that I have carefully examined the hospital records, d think the following statements absolutely correct. I would add at I was not on duty at the hospital during the period of cholera, and ly saw one of the cases in the hospital.

The first case of cholera admitted into the hospital was that of Charles iller, mentioned above, who died June 28. No other case is recorded ntil the 27th of August, when Abram Stoner, a man from the interior the State, was taken ill at the depot while waiting for the train, and ut out to the hospital. He died on the 29th of August, and the same ay also died the expressman, Reed, who hauled Stoner to the hospital. eed was a man of feeble health.

It may be here remarked that this was one of those curious coinci- ences which confirm persons in the plausible notion of the direct trans- ission of cholera from person to person. Here we have one man, pparently in good health, taking another writhing with the cramps of holera in his wagon to the hospital. A few hours afterward he is taken ith like symptoms, and actually dies before the first.

On the 5th of September, just a week afterward, a Mrs. Manning and ree children (named Wesson) are brought to the hospital. On the 6th ne of the children, a girl named Johanna Wesson, died; the others re- overed. These all came from the fatal spot near the upper sewer. hese were all the cases of cholera admitted into the hospital from own.

The hospital building is of brick, three stories high, with a large attic; t was built originally for a female school, and is under the charge of the isters of Mercy. The first or ground floor, and also the second, have many rooms for private patients, while the general patients occupy two arge rooms on the third floor, designated the men's and women's wards; bove these again comes the attic, occupied by convalescents, attend- nts, &c. Mr. Stoner died on August 29, in one of the private rooms n the ground floor in the rear of the building. On September 6 the hild died in the women's ward on the third floor.

On September 8 an old man (May) who lived at the hospital and occu- ied the attic, died there.

On September 9 a patient (Holm) who had been recently operated on or fistula in ano died in the men's ward, in a few hours after the first ttack.

This is a full history of the cholera epidemic in Mercy Hospital, to hich I may add that at no time were any means used to disinfect the ischarges, or any attempts made at isolation of the affected persons. The drainage of the house was good; the water used was from a well, and quite hard. You will observe that, excluding the case in June, five ases were introduced, and two cases occurred among the inmates, both being fatal.

Having thus given you as correct and as detailed an account of the cholera here as was in my power, I should, perhaps, refrain from any

deductions or comments. But everyone has a theory and likes to state it, so that I shall presume to give mine, which is as follows:

I regard the nature of the epidemic as malarial; that, though it took the form of Asiatic cholera, it was of a different nature and origin; that it began at New Orleans and advanced up the Mississippi Valley with the increasing temperature; and that it suddenly disappeared everywhere upon the appearance of frost.

An exactly parallel case, I think, is that of the "cholera" which arose at Estero Bellaco in 1866, '67, and '68, progressed southward one thousand miles (along the Parana and La Plata rivers) to the cities of Montevideo and Buenos Ayres, at the mouth of La Plata river, ceasing in each instance upon the approach of winter. In regard to the symptoms, I would state that while living on the Arkansas river, in 1866, I saw among negroes lately brought into that region, several cases with almost exactly the same symptoms as those observed here last summer; not so sudden in its onset, nor so rapidly fatal, however. But enough of theory. This bit of it you may consider the price or penalty of this communication.

Very respectfully,
Your obedient servant,

R. J. FARQUHARSON.

Dr. ELY MCCLELLAN,
Assistant Surgeon U. S. A.

DES MOINES COUNTY.

The only information that we have been able to obtain as to the epidemic of 1873 at Burlington, Iowa, is conveyed in a note from Dr. G. R. Henry, who reports one cholera death at that city on the 12th day of August. We quote the note:

"This was the only case of genuine cholera which I saw, although during the months of August and September I lost five patients from cholera morbus, which prevailed in a very malignant form, but was confined to one locality, where the people drank water contaminated by drainage, and about all the population were ignorant Swedes, who neither knew nor cared to take care of the sick. During the year 1873 we had less disease of the bowels than usual."

In the narrative of the Illinois group, it has been demonstrated that, at two points at least, the initial cases contracted the infection at the city of Burlington.

LUCAS COUNTY.

From Chariton the following letter has been received:

"CHARITON, IOWA, *October* 28, 1874.

"DEAR SIR: Your circular letter came duly to hand. In answer, have to say that we had no epidemic cholera at this point in 1873. We had several cases of sporadic cholera, or bad cholera morbus, nothing more.

"Very respectfully,

"H. STEED, M. D.

"ELY MCCLELLAN,
"*Assistant Surgeon U. S. A.*"

TAH.

At Kelton, Box Elder County, a small town of about four hundred and ty inhabitants, in the extreme northwestern portion of the Territory of tah, and located upon the line of the Union Pacific Railroad, a local- ed epidemic of cholera occurred on the 18th of August, 1873, and sulted in four deaths.

The location of this town is almost in the heart, or rather upon the mmit, of the Sierra Nevadas, and therefore remote from ordinary alarial causes.

The outbreak occurred in a family who had recently removed from e State of Missouri. The clew to the absolute point of infection is st. Dr. B. M. Mallory, who has kindly noted the fact, is rather inclined attribute the outbreak to atmospheric influences. Of the cases at are reported, all are whites; all males. The ages ranged from neteen months to forty-five years. Two of the cases occurred in lults, two in infants. Two of the cases occurred in one family. The hers lived within two hundred yards. It cannot be learned whether not there had been any communication between the houses at which e disease occurred. No emigrants had arrived in the town prior to e outbreak.

CHAPTER XXI.

DAKOTA GROUP.

DAKOTA CONTRIBUTORS.

Dr. J. B. Van Velsor, Yankton County.
Dr. R. J. Thomas, Yankton County.
Dr. G. E. Moon, Yankton County.

INITIAL CASE.

Yankton, Yankton County, August 25.

TERRITORY OF DAKOTA.

Dakota is a Territory of the United States, adjoining the British possessions and the States of Minnesota, Iowa, Nebraska, Montana and Utah. The western portion of this Territory is mountainous, the peaks ranging from 8,000 to 13,000 feet above sea-level. The eastern portions are more nearly level, but they represent a level of 1,500 feet above tide-water.

The Territory is drained by the Missouri, the Red River of the North, the North Fork of the Platte, the Big Horn, the Yellowstone, and Powder rivers. The meteorological observations made at Fort Randall present a fair indication to the climate of this Territory:

Mean temperature during 1873 and 1874, 49.90°; maximum temperature, 103°; minimum temperature, 28°.

Rain-fall during the same period, 14.69 inches.

Yankton, the capital city of Dakota, is located upon the north bank of the Missouri, about seven miles above the mouth of the Dakota river. The last-named stream is also known as the James river. In 1870 Yankton had a population of about fourteen hundred inhabitants.

The history of the cholera epidemic at this point is of value, as it demonstrates that the infection did not reach Yankton from any point within the United States, but that it was developed at that point only after the arrival of certain bands of Russian emigrants, who undoubtedly conveyed the specific infection in their personal effects from cholera-infected districts of Russia.

EPIDEMIC CHOLERA AT YANKTON, DAKOTA, IN 1873.

BY J. B. VAN VELSOR, M. D., *City Physician.*

During the month of August, 1873, the first bands of Russian emigrants reached the Territory of Dakota, and were lodged in unoccupied buildings throughout the city of Yankton. It is estimated that during the season at least two thousand five hundred of these individuals reached this Territory. They arrived in companies, which consisted of from ten to twenty families, each family having an average of four children. The majority of these people came from the Odessa and Crimea districts of Russia; the majority had arrived directly from the

rt of entrance into the United States; each band was a community ıded by one man selected to assume the responsibilities of his party. Some few of these emigrants were persons of wealth and respectaity, but the large majority were of the lower classes, filthy in their ·sons and habits.

Each family brought with them boxes and bales of their personal ·cts, which consisted of articles of clothing, bed-furniture, and cook- ; utensils. In the boxes which contained the articles for use upon the ırney, articles of clothing and those of food were generally to be ınd in an undivided chest.

Upon their arrival at Yankton, these people were cared for by the izens of the city. They were given quarters in unoccupied buildings, ıplied with food, and every effort was made to render them comfortable, til such time as they could be located upon the farms in the territory ıt had been selected for them. It was observed that in the majority instances it was impossible to compel them to adopt any sanitary preıtions in their lives; the utmost repugnance was shown to the use privies, both sexes preferring to urinate and defecate immediately ɔund the building in which they were located.

On the 25th of August, immediately upon the arrival of a party of ·se Russians, who had reached Yankton immediately from New York, o cases of cholera occurred in the persons of children, who with their rents and several other families were lodged in an unoccupied schoolıse. These cases terminated fatally after a few hours' illness. The xt day five other cases occurred in the same room, and nine others in adjoining room. Of these fourteen cases but two recovered. From ·se cases the disease spread, and the epidemic continued in force til about the 15th day of September, when its epidemic influence ·appeared. From August 25 to September 15, forty-two cases of olera occurred among the bands of emigrants; of these, twenty-nine ·re fatal. The large majority occurred among children of less than tteen years of age. Comparatively but few deaths occurred among e adults. In this connection, it must be borne in mind that over twoirds of the entire body of emigrants were minors.

After the development of this disease among the Russians, a few well-fined cases of cholera occurred among the residents of Yankton, while the same time diarrhœal diseases were unusually frequent. Early September a lot at the corner of Third street and Broadway was ·ared for the purpose of erecting a block of buildings. The dirt and *bris* that were removed from this site were used to fill some inequalities ı Third street. Among other refuse removed was the contents of an d privy, which had been used by some Russians who had been quartered an adjoining building. This privy-soil was scattered over the street ı secure its rapid oxidization, but in so doing the stench was unenırable.

September 5, a Mr. M., whose business called him many times each ıy to pass over this ground, was attacked with cholera, and died after few hours' illness. The next day his wife was attacked with the same isease, but recovered after a severe illness. In these cases a thorough ıstem of disinfection was instituted; the bed, bedding, and soiled clothıg were burned.

September 6, a man named McUmber, who was working upon some ew buildings in the vicinity of the point on Third street, upon which ıe *débris* from the privy-vault had been scattered, was taken with holera and died after a few hours' illness. The same active system of ısinfection was instituted. The same day an Indian, who had pitched

his tent immediately adjoining the house in which McUmber was [illegible] was attacked, but recovered after a serious illness.

September 7, a man named Faust, who lived fourteen miles north of Yankton, and who had been in the city on the previous day, was taken with cholera, and died after an illness of about ten hours. This man was attended by some friends who had been through the cholera-epidemic of 1866 and 1867. By them everything was carefully disinfected. The wife of Faust and his child were removed from the house before his death. After death sulphate of iron in quantity was placed in the coffin under the body. His bed, bedding, and clothing were destroyed with fire.

September 9, a Mr. Presho, who lived in close proximity to the polluted point upon Third street, was taken with cholera, but ultimately recovered. September 14, a little girl, whose family resided in the district in which the Russians were lodged, and directly opposite to a house occupied by a number who were intensely filthy in their habits, was taken with cholera, and died after an illness of six hours. The next day a second child in the same family was attacked, but recovered. These cases were followed by six well-marked cholera-cases in the city, all of whom recovered; a total of twelve cases, with four deaths.

After the removal of the Russians from the city to the farms in the counties of Yankton, Bonhomme, Hutchinson, and Turner, no account can be obtained. That fatal cases of the disease still occurred there is no doubt; but as no American physician was called in, it is impossible to bring them to light.

YANKTON, D. T., *November*, 1874.

During the month of November, 1874, an inspection of the cholera-infected districts of 1873, in Dakota Territory, was made by the writer. A most careful and patient research among the emigrants failed to elicit any new information. By some of intelligence, it was admitted that the districts of Russia from which they had departed were cholera-infected, and many instances corroborative of published reports as to the prevalence of this disease in the southern provinces of Russia were obtained. One man of much intelligence and refinement recounted interestingly the frequent arrivals of the disease at the city of Odessa, and another man from the vicinity of the city of Taganrog confirmed the cholera-reports published from the Crimea during the past few years. But one and all were interested in concealing the events among them, as far as the influence of cholera was concerned, after their arrival in the United States. Had it not been that the physicians of the city were active in their observation of the disease, an extended outbreak would have occurred.

A personal inspection of these people will demonstrate that they are peculiarly liable to become the porters of disease. In their persons and in their habits they are filthy. The use of water is almost unknown among them, and when personally used is in the majority of instances perverted. A gentleman of Yankton, who was much interested in the study of these people, informs us that upon one occasion he observed a female wash her hands, head, feet, and other portions of her person in a pan of water. Her ablutions having been accomplished, she proceeded to wash a cooking-utensil in the same water, and finally, before it was discharged from use, some meat and potatoes, upon which in a short time the noon-day meal of her family was made.

The clothing of these people consists of heavy, coarse, woolen fabrics. Their beds are generally of feathers, their blankets thick and heavy. The men wear a great-coat of the shape and size of an Ulster, made [illegible]

ssed sheepskins with the wool retained. Their persons are unkempt, ir hair and beards long. The adult male is the only individual of family of importance. The children, alive or dead, are noticed but the mother, who, besides her household duties, performs the labor of eld-hand.

At a meeting of the physicians of Yankton, held on the night of Nober 14, 1874, the history, as given by Dr. Van Velsor, was corroboed; and it was given as the unanimous opinion of the gentlemen sent that during the summer of 1874 a modified demonstration of same disease occurred, during which but one American family was acked, one member of which died; but among the Russians a number fatal cases occurred.

A great diversity of opinion was found among the citizens of the city Yankton as to the disease of 1873. While the physicians of the city unanimous in pronouncing it to be cholera, many prominent citizens sistently deny that the disease ever occurred in the Territory; while ny others who have had experience in former epidemics of the disse fully corroborate the opinion expressed by the profession.

It is respectfully submitted that a disinfection at quarantine-grounds material from cholera-infected districts of Russia, during the year 73, would have prevented this outbreak of the disease.

CHAPTER XXII.

CHOLERA AT NEW YORK QUARANTINE.

NEW YORK CONTRIBUTORS.

Dr. S. O. Vanderpoel, Health-Officer of the Port.
Dr. Walter DeF. Day, Sanitary Superintendent.
Dr. Elisha Harris, Registrar of Vital Statistics.
Dr. John C. Peters, of New York City.
Dr. A. B. Judson, of New York City.
Dr. Samuel McClellan, of New York City.

NEW YORK CITY AND HARBOR.

During the year 1873 the city of New York was free from epidemic cholera, as shown by the following letter:

"HEALTH DEPARTMENT,
"*No.* 301 *Mott Street, New York, June* 27, 1874

"MY DEAR DOCTOR: It gives me pleasure to inform you that we had no cases of cholera in this city last summer. There was the usual number of cholera-morbus cases, but nothing more.

* * * * * * *

"WALTER DEF. DAY.

"Dr. ELY MCCLELLAN."

At the quarantine of New York Harbor, however, one of the most instructive lessons of the epidemic is to be found, the facts of which have been furnished through the courtesy of Dr. S. O. Vanderpoel, health-officer of the port.

During the months of September and October, 1873, four steamships arrived at quarantine-grounds upon which cases of epidemic cholera had occurred.

I. The steamship Westphalia arrived September 10 from Hamburg, which port she had left on the 27th of August, touching at South Hampton August 30. Upon this vessel a cholera death occurred September 1, and upon the 3d a second death was recorded. Upon arrival at quarantine station September 10, nine cases of cholera were sent to hospital on Dix Island. Of these cases one died; the others recovered.

All of these cases had occurred in the persons of members of the German families, and it was most satisfactorily determined that they had been infected before coming upon the vessel.

The cases had been most rigidly sequestrated; all excreta had been disinfected. The soiled clothing had been destroyed by fire. No other cases occurred upon the steamer or at the hospital.

II. The steamship Ville du Havre arrived at quarantine September 24, from Havre and Brest. She had started upon her voyage September 12. On the 16th a gentleman of New York City was attacked with cholera. The disease was at once detected by the surgeon. Absolute isolation was enforced. The passengers in the neighboring state rooms were removed. The dejections were disinfected as soon as voided.

l soiled linen was burned. The case terminated fatally, and was ried in the ocean the same night.

The state-room was scrupulously cleansed and was disinfected daily. o other case of the disease occurred upon the vessel.

III. The steamship Washington arrived at quarantine October 26, ving left Stettin October 6, and London October 14, with two hun-ed ninety-eight passengers. Upon the 21st of October three fatal ses of cholera occurred. Every precaution had been adopted to pre-nt the spread of the disease. The means adopted were successful, no other cases occurred.

IV. The steamship Holland arrived at quarantine October 28, having iled from London September 18, and from Havre September 20.

Upon this vessel one fatal case of cholera occurred ten days prior to r arrival. This was in the person of a steerage passenger, and occurred suddenly that the surgeon was not informed until the patient was in collapse. Upon inquiry it was found that no dejections had taken ace except at the water-closet into the sea, and none occurred after e collapse. The clothing was at the time carefully examined. Upon e occurrence of death the body was at once thrown overboard, and e effects were destroyed. No other cases occurred.

We quote from a letter of Dr. Vanderpoel, dated September 27, 1874: "In all these cases satisfactory evidence was furnished on board the ips that strict sanitary isolation and regulations had been adopted in ticipation of the rigid requirements of our quarantine. The vessels ere detained sufficiently long to become conversant with all the cir-mstances of the outbreak, and of the precautionary measures adopted prevent the spread of the contagion. Satisfied, after rigid inquiry, at the medical officers of the vessels had taken prompt and full meas-es to prevent others being attacked; that the cases in question had doubtedly contracted the disease before coming on board the ship; at the dejections had been promptly removed, the linen destroyed, d that a full period of incubation had passed without the appearance new cases, the vessels were allowed pratique.

"In the cases removed a rigid isolation and sequestration had been aintained on the vessel, in connection with all the precautions of eanliness, so that in this case also detention was only for twenty-four ours. There were no cases occurring from the vessels after being per-itted to pass quarantine, and no cases occurred among passengers after nding."

These cases are of great value, as demonstrating the efficacy of disin-ction in stamping out cholera, and the institution of a new era in uarantine history.

Under the present enlightened management of the quarantine of the ort of New York, to which reference is made elsewhere, the medical ficers of vessels which may become infected with disease, knowing ill well that their efforts to arrest the disease will be fully recognized d sanctioned, are incited to the utmost exertions; and thus the ad-ance is a triumph of science, and not a result of a pecuniary dread of tention. It is safe to predict that never again in New York Harbor ill the tragedy as enacted in 1866 on the Virginia and the England e repeated.

Three distinct outbreaks of cholera occurred in the United States dur-g 1873 among emigrants, and within a period ranging from seven to ten ays after they had landed at the port of New York. These individu-ls, in one instance at least, passed through no infected districts in the nited States. In each instance the disease occurred among them at

localities at which they formed the initial cases; and in all the evidence is strong that the disease developed only after the trunks, boxes, &c., were opened that contained property packed in Europe.

The very valuable paper which Dr. Peters has contributed exhibits the location of cholera in Europe during 1872 and 1873. We have extracted from the annual report of the commissioners of emigration of the State of New York for the year ending December 31, 1873 tables which show the number of cabin and steerage passengers that arrived at New York upon vessels employed in carrying emigrants and the ports from whence they came during 1873; also, a table of the nationality of said passengers. These tables show that during 1873 the large number of three hundred and sixteen thousand nine hundred and fifty-six passengers arrived at the port of New York, exclusive of the officers and crews of the vessels; that of this number, two hundred and sixty-eight thousand two hundred and eighty-eight individuals were of the class coming directly under the control of the emigration commissioners; that of the last class one hundred and fifty-two thousand one hundred and thirty-five were from the districts of Europe infected with cholera.

The emigrants bring with them effects of all kinds. The commissioners' report shows that about fifteen thousand packages of all kinds pass yearly through the United States Customs Bureau established at Castle Garden. Although no authority is exerted to cause the speedy removal of emigrants from the emigrant establishment, yet arrangements are perfected by which they leave rapidly for their inland destination. "Thousands arrive and depart the same day," carrying with them all that they brought from their distant homes.

The vast majority of these emigrants are of the class among whom contagious diseases find their most numerous victims. A large proportion of those who arrived at the port of New York in the year 1873 were from districts of known contagion in Europe, or who had sailed from infected ports. These people arrive at American seaports en masse, but they gather at the ports of embarkation in small bands. At such points they remain until arrangements are effected, or until the day of departure arrives, and generally they are deprived of almost all the comforts of life. During an extended cholera epidemic, the emigrant may leave a healthy locality to become infected in the mass congregated for departure; and upon arriving at their destination, they may establish an epidemic of the disease in communities as healthy as those they originally left.

It is earnestly suggested that infected fabrics are only too often the cause of cholera outbreaks, and that one great lesson taught by the cholera epidemic of 1873 is that the quarantine of individuals alone will not exclude contagious diseases of exotic origin; but that during the prevalence of any contagious disease, cholera in particular, upon a continent from which emigrants or travelers are to arrive, a thorough and absolute disinfection of all effects which may arrive from infected districts should be accomplished.

It is respectfully suggested that this duty devolves upon the General Government, and that it may be so conducted as not to add additional weighty expense to the emigrant. By such means a national *cordon de sante*, such as has heretofore existed but in dreams, may be realized and made effective.

From the statistics furnished in the report of the commissioners of emigration of the State of New York we have formed the following tables:

—*Statement of the number of vessels, with the number of their crew, and the number of passengers who arrived at the port of New York during* 1873 *from English, European and South American ports.*

Ports of departure.	No. of vessels.	No. of cabin-passengers.	No. of steerage-passengers.	Total No. of passengers.
erpool and Queenstown	299	18, 049	143, 570	161, 619
don and Havre	32	330	9, 280	9, 610
nden	2	12	53	65
stol	19	153	1, 778	1, 931
sgow and Londonderry	104	2, 929	21, 294	24, 223
rdiff	9	275	772	1, 047
nen	123	6, 780	43, 022	49, 802
mburg	64	6, 064	32, 275	38, 359
ttin	16	376	6, 472	6, 848
twerp	8	34	1, 481	1, 515
terdam	16	164	2, 855	3, 019
rgen	15	152	3, 308	3, 460
rseilles	3	.....	92	92
vre and Brest	26	3, 331	541	3, 872
vre	2	15	264	279
ssina	3	.....	142	142
rme	14	.....	563	563
ue	1	.....	7	7
braltar	1	135	49	184
bon	1	.....	50	50
lifax	1	.....	423	423
Janeiro	1	.....	40	40
ntevideo	1	.....	7	7
Total	760	38, 869	268, 285	307, 157

I.—*Table showing the nativity of Emigrants who arrived at the port of New York during the year* 1873.

rope	152, 135	East Indies	17
eat Britain	113, 920	Isle of Man	160
rmenia	14	Malta	13
sia	1	Mexico	6
stralia	5	Nova Scotia	21
frica	9	New Brunswick	52
nada	55	South America	11
ina	4	United States	1, 839
gypt	2	West Indies	24

NOTE.—The steamers of the Cunard and General Transatlantic Companies that carry only cabin-passengers do not land at Castle Garden; during the year, nine thousand seven hundred and ninety-nine passengers arrived upon these vessels, and are not included in the tables. The grand total of passengers arrived at the port of New York from foreign ports during the year 1873 was three hundred and sixteen thousand nine hundred and fifty-six individuals.

CHAPTER XXIII.

CHOLERA-EPIDEMIC OF 1873 IN THE UNITED STATES ARMY.

The cholera-epidemic of 1866 having been diffused throughout the Southern and Western States by the movements of troops, it has been thought advisable to present the facts of the epidemic of 1873, as they relate to the Army of the United States, in a distinct chapter.

The experience of the majority of the officers of the United States Army is strongly in favor of the establishment of a *cordon de santé*, having been demonstrated that, so far at least as military posts are concerned, they are effectual in excluding the infection of cholera. The experience of the cholera epidemic of 1873 adds weight to the experience gained in former epidemics.

It is undoubtedly to be found that whenever the disease has invaded a post so secluded, the cordon has not been rigidly enforced, and that individual violations will always be found to account for the outbreak. In opposition to such measures there has been noted during the present year the instance of a supposed *de novo* development of cholera at Mussoorie, of the Himalayas, in 1872. At that time cholera was epidemic at the villages on the plains, some six miles distant from the sanitarium, and between these villages and Mussoorie a *cordon de santé* had been established. In spite of these precautions a cow-feeder, who lived in the center of the station, died of cholera, and it was asserted that he had never been without the lines.

Dr. Pringle, however, found "that this man had gone to his village on the plains when cholera was present, with some cows that had gone out of milk, to be replaced by others in full milk, without, however, remaining overnight." Within three days he was seized with cholera and died.

DEPARTMENT OF THE EAST.

The cholera-epidemic of 1873 having been announced, extraordinary precautions were adopted by the officers of the United States Army to prevent the introduction of the disease into any of the military posts of New York Harbor. The following circular was issued by the medical director, Department of the East:

"HEADQUARTERS DEPARTMENT OF THE EAST,
"MEDICAL DIRECTOR'S OFFICE,
Circular. "*New York City, July* 19, 1873.

"As the cholera is in the country, and may at any time make its appearance among us, medical officers serving in this Department will look well to the sanitary condition of their stations, and use all the means at their command to prevent, as far as possible, the disease getting among the troops. Timely advice and directions to the officers and soldiers will put them on their guard should the disease appear in their vicinity.

"The attention of all medical officers is called to circular No. 4,

rgeon-General's Office, 1868, the requirements of which will be omptly complied with, in the event of the disease breaking out in any ilitary station in the Department.'

"JOHN M. CUYLER,
"*Surgeon, United States Army,*
"*Medical Director.*"

By the post-surgeon of Fort Columbus, New York Harbor, the follow-g letter was addressed to the post-adjutant. It will be remembered at it was from this post in 1866 that the disease was carried to other sts in the harbor, and also widely distributed over the country.

"POST-HOSPITAL, FORT COLUMBUS,
"*New York Harbor, July* 9, 1873.

"SIR: Health-officers and sanitary superintendents officially report at cholera is prevalent in certain cities in the West and Southwest, id its appearance may be looked for at any time in the different cities st of the Alleghanies. During the epidemic of 1866, cholera was troduced into this post by a recruit, who arrived, three days before ing taken sick, from the rendezvous at Minneapolis, Minn. In 1867 e cholera was again introduced by a recruit who arrived, the night fore being taken ill, direct from Saint Louis, Mo.

"Notwithstanding the timely recommendations and warnings of the edical officer, recruits had been allowed to accumulate at this depot, id the disease on its arrival on the island found a large number of re-uits collected together, ready to fall an easy prey to its ravages. etachments of recruits sent off from here to posts in different parts of e country carried with them to their destination the cholera, to spread r and wide with very disastrous results.

"The experience of these epidemics has made it patent that a very *grave* ror was committed in thus allowing recruits to accumulate at the depot the face of an approaching epidemic, and it is to be sincerely hoped at the lesson taught by the fatal consequences of this error will pre-nt its repetition. It is with this view, therefore, that I respectfully bmit the following suggestions for the serious consideration of the mmanding officer, and of the superintendent of the general recruiting rvice, viz:

"To prevent the introduction of cholera on this island by recruits id others, I would respectfully recommend that each recruiting-officer e ordered to stop sending to this depot recruits and parties as soon as e disease declares itself at all prevalent in the city where his rendez-ous may be located.

"I would further recommend that all recruiting-officers be cautioned gainst taking men coming from infected localities.

"Although the strictest sanitary measures be enforced, and all reason-ble precautions be taken, this command cannot expect an entire immu-ity should cholera become epidemic in the immediate vicinity; still its avages may be limited, and the danger of spreading it much dimin-shed by retaining on the island the smallest number possible of recruits r distribution, and I would strongly recommend that they be dis-ributed as promptly as possible, and in small detachments of less than fty men, because a small detachment is more easily managed than a rger one, the men can be more readily accommodated, their comfort nd welfare better secured, while excesses in eating and drinking can e more effectually checked. Diseases are less liable to break out in a

small command, and when a disease does show itself the number of ca will not be so large but that all can receive proper care and attention.

"A medical officer should accompany each detachment. In case sion, I would respectfully recommend that the distribution of recru cease the moment cholera appears at this depot.

"Very respectfully, your obedient servant,

"JOHN J. MILHAU,
"*Surgeon, U. S. Army,*
"*Post-Surgeon.*

"To the POST-ADJUTANT,
"*Fort Columbus.*"

The representations of Surgeon Milhau, United States Army, in the foregoing letter, led to the issuance of the following order:

"HEADQUARTERS GENERAL RECRUITING SERVICE,
"UNITED STATES ARMY,
Circular No. 6. "*New York City, July* 16, 1873.

"Whenever cholera is declared prevalent at any city or town, where a rendezvous is established, the officer in charge of the rendezvous will at once discontinue the enlistment of recruits, and forward no more to the depots.

"No enlistment will be made when it is ascertained that the applicant has come from an infected district.

"By command of Col. John Gibbon.

"LOUIS R. STILLE,
"*First Lieutenant Twenty-third Infantry,*
"*Acting Assistant Adjutant-General.*"

DEPARTMENT OF THE GULF.

In reply to a communication addressed to Col. James Simons, U. S. A., medical director Department of the Gulf, asking information as to the epidemic of cholera as it affected the military posts of that Department, the following answer has been received:

"OFFICE OF THE MEDICAL DIRECTOR,
"HEADQUARTERS DEPARTMENT OF THE GULF,
"*December* 12, 1873.

"SIR: In reply to your letter of the 17th of October, asking what precautionary measures were adopted to prevent the introduction of Asiatic cholera in the military posts of this department, and requesting me to give any facts personally known as regards the epidemic of 1873, I have to say that the first cases of cholera that appeared in the United States doubtless occurred in this city, but as the disease was not suspected, the first cases were reported as cholera morbus; nor were all of the cases which occurred in the three or four following weeks reported as Asiatic cholera.

"As far as I am able to ascertain, there is no evidence of a case having been introduced into this city from abroad. It has been suggested as probable that the disease may have been brought in the cargo of some ship, or in the baggage of immigrant passengers.

"No precautionary measures were taken to prevent its introduction the military posts in this department, nor was it practicable to carry any orders in regard to a sanitary cordon.

"The only posts at which the appearance of the disease was apprehended was at Jackson barracks, in this city, and at the post of Jack-

ss. No cases occurred among the troops at either of these places. th of these posts were in excellent sanitary condition when person- inspected by me.

In the last of May, 1873, a case of cholera was reported among the ops at Monroe, La., and in June another case was reported at the ne place; both of these cases terminated fatally. An additional dical officer was immediately ordered to Monroe, and the detachment s withdrawn as soon as possible.

No other cases were reported at any of the military posts in this partment. I am informed there were many cases among the negroes different points in the State, but nothing as regards its history or pro- ss has reached me in a reliable form.

"Very respectfully, your obedient servant,

"JAMES SIMONS,
"*Surgeon, U. S. Army,*
"*Medical Director.*

'Assistant Surgeon ELY MCCLELLAN, *U. S. A.*"

II. A communication from Assistant Surgeon Van Buren Hubbard, S. A.:

"JACKSON BARRACKS, LOUISIANA,
December 14, 1874.

"DEAR DOCTOR: In compliance with your verbal request made to e a few days since, that I would furnish you with a statement in writ- g of the precautionary measures, if any, which were adopted at this st during the months of February, March, April, May, and June, 1873, ith the view to secure immunity from 'epidemic cholera,' said to be evailing in this city during these months, I cheerfully place the follow- g at your disposal.

"There were no extra precautionary measures adopted whatever. ndeed, the sanitary condition of the post was such as scarcely to admit improvement, and that, too, when the existence of an epidemic was ot suspected. There were no orders, instructions, circulars, or letters ceived from the medical director of the department, or from any other uthoritative source, warning me, as medical officer of the post, of the robable approach or actual presence of an epidemic of cholera. In ruth, I suspect it was not until the epidemic had abated, and all danger rom it had passed, that it became settled in the minds of medical men this city that we had suffered from a visitation of 'epidemic chol- ra;' though there had been much discussion as to the real nature and rue character of the disease, with no little diversity of opinion on the ubject, which diversity of opinion has not been entirely reconciled, ven at this date.

"During the period mentioned, or the greater portion of it, Dr. R. S. Vickery, U. S. A., was on duty at the barracks, while I was on duty with troops stationed in the more central portions of the city, viz: the rtillery in the Mechanics' Institute, in Dryades street, between Canal and Common streets, and the infantry and cavalry in Magazine street, between Julia and Saint Joseph streets.

"I would respectfully invite your attention to the tabular state- ment given below, showing the number of troops serving in the city of New Orleans during the first half of the year 1873, and the number of cases of bowel complaints for each month, embracing diarrhœa, acute and chronic, and acute dysentery.

"The percentage of bowel complaints to mean strength of the com- mand for each month is also given. There is not reported in the hos-

pital records for that period, nor was there, a single case of cholera morbus or epidemic cholera among the troops.

"During the same period there were three deaths, two in the month of March; one from pneumonia, and one from chronic diarrhœa; and one in the month of May, from chronic bronchitis.

Tabular Statement.

Month.	Diarrhœa, acute.	Diarrhœa, chronic.	Dysentery, acute.	Strength of the command.	Percentage of the command sick from bowel complaints.	Remarks.
1873.						
January	29	.....	.....	542	5.35	There were no cases of "epidemic cholera" or cholera morbus among the troops during the periods specified.
February	12	.....	1	428	3.03	
March	7	1	1	442	1.80	
April	10	.....	.....	363	2.70	
May	6	.....	.....	168	3.57	
June	5	.....	.....	261	1.91	

"Deducting from these figures the percentage of cases of bowel complaint in the command for the whole period of five months, commencing with February and ending with June, it will be found to be 2.46. The month of January is omitted in this calculation, as the first authentic case of cholera did not occur until the 9th of February. No mention is made of any period subsequent to June, as the epidemic terminated quite abruptly with that month.

"Here is, in my opinion, a very important fact, which should arrest attention. That there should be an epidemic disease, and that disease cholera, prevailing in a large city, to an extent in point of severity to sweep off ninety victims in the month of April, and one hundred and twenty-five in the month of May, (*vide* Annual Report of the Board of Health, city of New Orleans, for 1873,) and that troops stationed in the city to the number shown in the above table should possess entire immunity from the disease, presents a problem worthy of consideration. Moreover, the percentage of bowel complaints during the period, as shown in the table, was small. The hygienic conditions and surroundings of the troops, though the best probably that could be provided in the emergency and under the circumstances, were, nevertheless, very far from what they should have been. Nor is any special credit to be given to the medical officers on duty with the troops for this happy event, as neither of them knew nor suspected the existence at the time of epidemic cholera. It establishes beyond controversy, one would say, the fact that the epidemic tendency or influence or atmospheric conditions could have been neither strong nor favorable to the rapid spread of the contagion; and, further, that the material upon which the disease fed was speedily consumed.

"I did not see a case of the disease.

"Very respectfully, your obedient servant,

"V. B. HUBBARD,
"*Assistant Surgeon U. S. Army,*
"*Post-Surgeon.*

"Assistant Surgeon ELY MCCLELLAN,
"*United States Army.*"

II. A note from Acting Assistant Surgeon William R. Manderville, S. A., in relation to the epidemic as it occurred at Monroe, La.:

Monroe is located upon the Ouachita River, about eighty miles from e city of Vicksburgh. The town has a population of about two thou-nd inhabitants. In the spring and early summer of 1873 the sanitary ndition of this town was good.

Company H, Sixteenth United States Infantry, arrived at Monroe, m Jackson, Miss., on the 23d of April, and immediately went into mp two miles below the town. The camp was about twenty-five or rty yards from the bank of the river, having on one side and in the ar a small lagoon of still water, formed by backed water from the er.

During the first four weeks of the occupancy of this camp there were ily deluging rains.

About two weeks after the arrival of these troops, diarrhœas became ry prevalent among them; this, in the first instance, was attributed the impure water which they drank and the fish-diet in which they d been indulging.

Having heard of several cases of cholera among the negroes of the wn and its vicinity, the men were prohibited from eating fish, and re well-water was provided for them. The men were ordered to re-rt at the hospital-tent on the first symptom of diarrhœa; to all who reported, small doses of calomel and opium were administered in oken doses, and with good result.

The first case of cholera occurred May 11; the patient was attacked 4 o'clock a. m. and died that night at 11 o'clock p. m.

No more cases occurred until June 5; this patient was taken at 5 clock in the morning and died that day at 3 o'clock p. m.

Three other cases occurred, but none of them proved fatal, (myself nstituting one of the cases that recovered.) During the month of ay twenty-two cases of diarrhœa and cholerine occurred, and for the nth of June nine cases of diarrhœa and four of cholera morbus.

The command numbered forty-eight men.

Those who were attacked with the disease were isolated as much as ssible, and the hospital-tent thoroughly disinfected from the very art; the camp was placed in a state of cleanliness as far as practica-e. The sink for the men was removed to a considerable distance from e camp, and covered with fresh earth every night; the discharges om the cholera-patients were quickly removed, mixed with carbolic id, (it doubtless being the best antiseptic known,) and buried. The dding and clothes used by the cholera-patients were immediately de-royed by fire. The hygiene of the men was placed in as favorable a ndition as possible.

The cholera was undoubtedly brought to Monroe by way of the rail-ad; the first case appearing at Vicksburgh, then at Delta, a small town pposite, and so on along the line of the road.

EPARTMENT OF THE SOUTH.

The epidemic of cholera having been announced in the Gulf States, nd the fact having been ascertained that the disease had been carried s far north as the city of Memphis, General William J. Sloan, U. S. A., edical Director of the Department of the South, called the attention f all medical officers of the Army serving in the department to the llowing circular order of the Surgeon-General of the Army:

WAR DEPARTMENT,
SURGEON-GENERAL'S OFFICE,
Circular No. 2. *Washington, D. C., June* 12, 1866

Hereafter, on the appearance of the first recognized case of cholera, yellow fever, or of any other epidemic disease, at any military post or station, whether among the officers and men or among citizens in the vicinity, the medical officer in charge will at once address a letter to the medical director of the department announcing the fact, and forward a duplicate copy direct to the Surgeon-General.

Besides the usual reports of sick and wounded, every medical officer in charge of cholera or yellow-fever patients will forward to the Surgeon-General, at the close of each month, list of patients in the following form:

List of patients suffering from epidemic ——— *at* ———. *Month of* ———, 186-.

Name.	Nativity.	Age.	Rank.	Regiment.	Company.	Length of service in months.	Length of time at station in months.	Date of attack.	Date of recovery.	Date of death.	Remarks.

This report will embrace all cases of officers and enlisted men so far as known, and will be made in duplicate, one copy to be forwarded to the Medical Director, and one direct to the Surgeon-General. Blanks for the report can be obtained of the Medical Director, who will receive them from the Surgeon-General.

At the close of the epidemic, or of his term of service, the medical officer in charge will also forward, with as little delay as practicable, a *history of the epidemic*, setting forth, so far as known to him, the facts connected with its origin or importation, its progress, and decline, together with an account of the methods of treatment or prevention employed, and their results, and of the results of autopsies.

This report will be written on one side of foolscap paper, with a margin of one inch on the left-hand side, and will be sent through the Medical Director; a letter will be sent on the same day to the Surgeon-General direct, informing him that such a report has been forwarded.

These reports are required in connection with all cases of cholera or yellow fever occurring among officers or men. In the case of other epidemic diseases, only when specially ordered by the Medical Director or the Surgeon-General.

J. K. BARNES,
Surgeon-General.

I. The earliest intimation of the near approach of cholera to the stations of the United States troops in the Department of the South is found in a telegram which was received at department headquarters on the 9th of June, from Lieut. Col. James Van Voast, commanding the Sixteenth Regiment of United States Infantry and the post of Nas-

le, Tenn., which states "that it is quite certain that cholera to some ent prevails in the city of Nashville. Upon consultation with the geon of the post, we are both of opinion that it may be prudent to ve the troops of this post into some healthy camp about ten miles m the barracks; this movement to be made in case the disease be- nes epidemic in the city."

The recommendation of the medical director of the department upon telegram was as follows:

"Respectfully returned with the remark that although it is doubtful ether the cholera can be prevented among the troops at Nashville by ir removal to *a temporary camp ten miles distant*, yet every measure precaution should be adopted. I therefore recommend that the mat- be left to the best judgment of the commanding officer and surgeon charge, in the event of a probable epidemic."

In accordance with the recommendation of the medical director, the lowing telegraphic order was issued to the commanding officer of the ited States barracks at Nashville:

"LOUISVILLE, KY., *June* 9, 1873.

"The general commanding thinks, with the medical director, that it doubtful if the movement from barracks to camp will prevent the pearance of the disease. If it does appear, you would have exchanged comfort and resources of a good permanent hospital for a poor tem- rary one at camp. Still the general gives you and the medical officer sent the discretionary authority you ask for, as, being on the spot, u may have better means than himself of judging as to the best course follow. Whatever you do, the officers, except the post-quartermaster, ist go with the command, leaving the post under a small guard of a n-commissioned officer and six men."

It being strongly the opinion of the commanding officer and post- rgeon that the troops in garrison could only be preserved from the fluences of the epidemic by removal to an uninfected district, on the th day of June the command was removed to camp at White Creek prings, ten miles northwest of the city. This camp was at an isolated sition off the lines of travel, and was supplied with an abundance of re freestone water. Assistant Surgeon D. G. Caldwell, U. S. A., the rgeon of the post, insisting, if any removal of the command was to be ade, that it be accomplished before any men had become infected, and at if the disease should be developed in camp, then, if necessary, the turn to barracks could be effected without any increase of danger.

The command having reached camp, a *cordon de santé* was established d maintained as rigidly as was possible. The diet and general health f the command were held under close surveillance. *No cases of the isease occurred.*

The non-commissioned officer and the enlisted men who were left nder the command of Maj. W. V. Richards, regimental quartermaster, n experienced officer, were especially selected for this duty as being ber, steady, and reliable men. One officer of the command, being of ne opinion that his family would be in reality more isolated from the pidemic at the barracks, the troops having been removed, obtained per- ission for his family to remain in their quarters.

June 13, the non-commissioned officer who had been left in barracks as attacked with cholera, but recovered. In the family that elected o remain at the barracks a fatal case occurred June 25.

The special report of Assistant Surgeon D. G. Caldwell, United States Army, to the Surgeon-General of the Army, is herewith presented *in extenso:*

"ASH BARRACKS, NASHVILLE, TENN.,
"*July* 30, 1873.

"GENERAL: I have the honor to submit the following brief history of epidemic cholera as it appeared in the city of Nashville, Tenn., during the months of May, June, and July, 1873.

"The first case occurred in Nashville in the latter part of May, but the disease was not recognized as epidemic cholera until about the 10th of June, and no mortuary record was kept until June 7.

"From June 7 until July 10 the undertakers' report for Nashville and vicinity was six hundred and ninety-seven deaths; in many instances persons were buried by others than the regular undertakers, adding these to the list, and then add those that died prior to June 7 and since July 10, it would be safe to say that fully one thousand have died since the appearance of cholera in Nashville.

"Comparatively few deaths occurred in the highest and best-drained and cleanest portions of the city. The disease was almost exclusively confined to the outer limits and low portions of the city, along the foul streams known as Wilson's Spring Run and Lick Branch, which almost encircle the city. On the low ground in the vicinity of these streams are settlements made up of small shanties, occupied by negroes, each shanty being considered large enough for from five to fifteen inmates.

"In the town of Edgefield, on the opposite side of the river from Nashville, where the streets are wide, good surface-drainage, and an abundant supply of cistern-water, there were only twenty deaths out of a population of five thousand.

"The precise manner in which the disease was imported to Nashville would be difficult to determine. It made its appearance in the latter part of May, and was founded upon such a malarial condition of the atmosphere and the people that almost all of the physicians in Nashville doubted its true character. Even the large number of cases occurring so rapidly failed to satisfy them of its true epidemic nature. The localizing cause of the cholera was so extended and apparent that no importation of the disease was looked for, or generally believed in.

"Recent investigation has developed the following facts in regard to the importation of the epidemic: Some negroes came up from New Orleans, where the disease was supposed to be prevailing, in the latter part of May, a part of whom died suddenly in Memphis, Tenn., and the rest came to Nashville, since which time their whereabouts cannot be traced.

"Another supposed origin of the disease is based upon a report that there were a number of convicts working on a railroad twenty miles east of Memphis; the cholera made its appearance among them; several of them died, and the camp was then broken up, and the convicts were brought to Nashville and returned to the penitentiary, from whence a few were soon after discharged, and came into the city. The warden of the penitentiary informs me that one of the convicts died with a disease resembling cholera a few days after returning from Memphis, but thinks those discharged were in good health, and that no cases of cholera occurred among the convicts until after the disease had become epidemic in the city.

"In favor of the local origin of the disease much has been urged. That the essentials for its development and propagation (except the specific germ) existed at Nashville, there can be no doubt. An incredible amount of filth had collected in and around the city; the sewers leading into the city empty their loathsome tides upon the surface of the ground.

hin the corporate limits, and small wooden drains, leading from bath-
ms, wash-rooms, or sinks, emptying through the curbing into the
eet-gutters are found, even in the best portions of the city.

"The city receives its supply of water from the Cumberland River,
: many of the poor whites and negroes, unable to pay water-tax, have
ourse to the public springs. These springs are situated on low ground,
l the water is more or less contaminated with the products of the
omposition of animal and vegetable matter.

"As the disease was progressing rapidly, and no efforts were being
de by the city authorities to check or control it, the post-commander
l myself deemed it prudent to remove the troops from Ash barracks
o camp farther away from the infected city. Permission was obtained
m the department commander June 10, 1873, and on the following
y the troops were moved into camp at White Creek Springs, twelve
les from the city.

"The site selected for the camp was an elevated ridge, with sufficient
el surface on its crest to accommodate two rows of tents, the decline
either side affording good surface-drainage.

"An excellent quality of water was obtained from springs located at
e base of the ridge, some distance from the camp.

"On arrival in camp the post-commander issued orders stopping all
mmunication between the camp and the city, except by permission
one teamster to haul bread from Ash barracks to the command.
is order was strictly enforced until the command returned to Ash
rracks.

"The epidemic having entirely abated on the 10th of July, the troops
re ordered to return to Ash barracks on the 22d of July, 1873, and
cases of cholera or cholera morbus occurred among the troops while
camp or since their return.

"A detachment, composed of one commissioned officer and eight en-
ted men, was left at Ash barracks to take charge of the Government
operty, and the post-commander authorized to make a contract with
r. Stoute to take charge of the sick of the detachment.

"Dr. Stoute reported to me for the month of June, as shown in
onthly report of sick and wounded for that month, one case of chol-
a and three cases of cholera morbus. All of these cases recovered.
e only fatal case reported by Dr. Stoute at Ash Barracks was that
Archibald Clapp, aged eight years, son of First Lieut. W. H. Clapp,
xteenth Infantry, and regimental adjutant. He was taken with a
ight diarrhœa on the 24th of June, which was partially controlled by
e or two doses of Squibb's mixture. On the next day, at about 6 o'clock,
olent vomiting and purging supervened, and he died at 9 oclock a. m.,
a state of collapse.

"As I was on duty with the troops in camp, while the epidemic pre-
ailed in Nashville, I am obliged to depend greatly for information
pon the statements of physicians practicing in the city. They inform
e that the clinical history of the disease did not differ materially from
at noticed in previous epidemics, and that recent experience has failed
throw any new light on the treatment of the disease.

"To Lieutenant-Colonel Van Voast, Sixteenth Infantry, post-com-
ander, much credit is due in preventing the spread of the disease
mong the troops. His promptness in having all of my recommenda-
ions fully complied with, making many daily inspections of the men,
ausing the grounds in and around the camp to be kept clean, sinks to
e inspected and filled up when required, and his vigilance in watching

and correcting lack of personal cleanliness in the men, produced good results.

"I have the honor to be,

"Very respectfully,

"Your obedient servant,

"D. G. CALDWELL,

"*Assistant Surgeon U. S. A.*"

All military posts in the Department of the South were placed in the most rigid sanitary police. Disinfectants were freely used at all points that might become infected by individuals or fabrics from infected localities. The officers of the Medical Department watched carefully for any development of the disease at or in the vicinity of their respective posts.

II. On the 24th of June the commanding officer at Chattanooga, Tenn. reported, by telegram to headquarters Department of the South, that cholera had suddenly broken out in that city, and asked authority to transfer his command to a camp upon Lookout Mountain. The authority thus asked was immediately granted. It having been found impossible to obtain a suitable camp at the point indicated, upon the recommendation of the post-surgeon, that the *morale* and hygienic condition of the command could be better preserved in the barracks than at an exposed camp, it was determined to remain in garrison. Every sanitary precaution was adopted to prevent the introduction of the disease into the garrison. One fatal case of cholera occurred, which is reported in full elsewhere.

The report of Assistant Surgeon Charles Styer, U. S. A., post-surgeon of the post of Chattanooga, to the Surgeon-General of the Army, is herewith presented.

"The record of the medical history of the post" indicates the active and efficient manner in which Dr. Styer discharged his duties of sanitary officer.

"CHATTANOOGA, TENN., *August* 8, 1873.

"SIR: I have the honor to report that I have applied verbally and in writing to the principal physicians of Chattanooga, and have tried every practicable way to trace the history of the first cases of cholera in the late epidemic, but with unsatisfactory results.

"Hearing that Dr. Price, a homœopath, attended the first case, I questioned him, and learned that the first case he saw was a Swedish woman in poor circumstances, on June 21, 1873. When first seen, she was in a state of collapse, with rice-water discharges, &c. This was in the morning, and she died during the day. The same evening he was called to see a negro living opposite, on the same street, with cholera-symptoms. The man had just arrived from Nashville, where cholera was prevalent, and had mild diarrhœa and vomiting for two days. This man recovered. Although he was the second case seen by Dr. Price, he may have been the first taken ill. On this point I could get no definite information. There was no known communication between the two families, and they did not use the same water-closet.

"Subsequently, the disease was most general and most fatal in the same portion of the city; but this would be expected, as it is the dirtiest part and inhabited by the poorest classes, who are badly housed, badly fed, and live in filth, making the locality a natural hot-bed for the development and spread of any epidemic.

"The physicians generally describe the disease as genuine epidemic

olera, with all the usually-described symptoms. At the same time ey attribute to it a malarial character, and almost universally state at quinine influenced its progress, and acted more satisfactorily than y other remedy. They used opium and calomel to combat symptoms, t quinine was their chief reliance. I have not heard of any autopsies ng made. I regret that I omitted it in my case, but my steward was . I was fatigued myself, and the commanding officer was desirous of king a prompt interment.

"No other case appeared in the garrison. There was some increase in e morning sick-report from diarrhœa, but this could be attributed to ght on the part of the men.

"At this date cholera is again reported in Chattanooga. The mayor s re-issued his proclamation, prohibiting the sale of vegetables and its, which had been rescinded July 21.

"During the epidemic, so far as my recommendations went, the soldiers d officers and their families used such mature vegetables and fruits could be obtained and properly prepared for the table, in liberal ough not excessive quantity. I set the example in my own house d in the hospital, and recommended a similar mode of living to others, d the result was satisfactory.

"Certain officers who could not free themselves from the influence of rmer teachings, confined their diet to ham and eggs, coffee, bread, dding, &c., and before the cholera-scare had subsided, had considerle trouble, chiefly diarrhœa, in different members of their families.

"So far as the disease now prevailing (since August 6) is concerned, believe it to be almost entirely caused by excess in eating water-mels, which are raised in great numbers, are very cheap, and are voured by the negroes almost without limit as to quantity.

"Very respectfully,

Your obedient servant,

"CHARLES STYER,

"*Assistant Surgeon U. S. A.*

"The SURGEON-GENERAL OF THE ARMY."

III. The commanding officer of the post of Lancaster, Ky., reported the headquarters Department of the South that several cases of olera had occurred at that town in the following telegram:

"LANCASTER, KY., *August* 19, 1873.

ASSISTANT ADJUTANT-GENERAL,

"*Department of the South:*

"Cholera is prevalent in the town; no case in garrison, but Dr. G. is infirm that I do not think (in which he coincides) that he will be able attend to cases, should there be any. I therefore urgently request at another medical officer be sent here at once. Cannot Dr. McClellan ordered up on first train to examine and report as to cholera in town, ndition of garrison, and Dr. G.?

"J. S. FLETCHER, JR.,

"*Captain Sixteenth Infantry, Commanding.*"

Upon receipt of which communication the following telegraphic order as issued:

"LOUISVILLE, KY., *August* 19, 1873.

Dr. ELY MCCLELLAN, U. S. A.,

"*Lebanon, Ky.:*

"Proceed to Lancaster, by the first train, and confer with Captain letcher with reference to the cholera there. Report by telegraph;

and before returning contract with a physician, if one can be obtained and if advisable. Acknowledge receipt.

"W. J. SLOAN,
"*Medical Director.*"

Authority was given for the purchase of such stores as might be required for immediate use. Hospital-beds with their furniture were sent to Lancaster from the post of Lebanon, with a full supply of hospital stores.

On the 24th the following telegram was received by the Adjutant-General, Department of the South:

"LANCASTER, KY., *August* 24, 1873.

"ASSISTANT ADJUTANT-GENERAL,
"*Department of the South:*

"Cholera has appeared in garrison; one man and one woman past recovery. Please send another physician; also a hospital-steward.

* * * * * * *

"It may be advisable to move; shall decide in the morning, and if cases are fatal shall go at once. Will advise you as to my decision.

"J. S. FLETCHER, JR.,
"*Captain Sixteenth Infantry, Commanding.*"

[Telegram.]

"LANCASTER, KY., *August* 26, 1873.

"ASSISTANT ADJUTANT-GENERAL,
"*Department of the South:*

"No more cases of cholera in camp. The two reported died Sunday. No more cases of actual cholera in town; considerable cholerine, however, among the men and the citizens.

* * * * * * *

"J. S. FLETCHER,
"*Captain Sixteenth Infantry, Commanding.*"

[Telegram.]

"LANCASTER, KY., *August* 31, 1873.

"ASSISTANT ADJUTANT-GENERAL,
"*Department of the South:*

"Two deaths from cholera in town yesterday, and two in garrison. Total deaths in garrison, four. Have gone into camp about two miles from town; good water, healthy locality.

"J. S. FLETCHER,
"*Captain Sixteenth Infantry, Commanding.*"

"LANCASTER, KY., *September* 5, 1873.

"MEDICAL DIRECTOR,
Department of the South:

"SIR: I have the honor to inform you that no cases of cholera have appeared in garrison since Saturday; and as I have moved the troops into camp to a fine, healthy locality about two miles from town, I am encouraged to hope that we shall have no more cases, although there is an unusual number of men on the sick-report.

* * * * * * *

"Very respectfully, your obedient servant,

"J. S. FLETCHER,
"*Captain Sixteenth Infantry, Commanding.*"

"LANCASTER, KY., *September* 15, 1873.

ASSISTANT ADJUTANT-GENERAL,
"*Department of the South:*

"SIR: I have the honor to report that I broke camp on the 13th inant, and marched the command into the garrison.
"There is little or no sickness at the post, and the health of the town good.
"Very respectfully, your obedient servant,
"J. S. FLETCHER,
"*Captain Sixteenth Infantry, Commanding.*"

When it had been definitely ascertained that cases of epidemic chola had occurred in the town of Lancaster, with the view of establishg a *cordon de santé*, the following orders were issued:

ompany order.] "POST OF LANCASTER, KY., *August* 19, 1873.
"From and after this day no enlisted man will be allowed to leave e garrison without a written pass signed by the post-commander.
"All men absenting themselves from the post without such pass will confined, and charges will be preferred against them, with a view to eir being brought before a court-martial for trial.
"J. S. FLETCHER,
"*Captain Sixteenth Infantry, Commanding.*"

ircular.] "HEADQUARTERS, POST OF LANCASTER, KY.,
"*Lancaster, Ky., August* 20, 1873.
"From and after this date, until further orders, no citizens will be lmitted within the grounds of this garrison.
"The guard on duty at this post will take particular care to see that is order is strictly carried out.
"By order of Captain Fletcher.
"W. C. McFARLAND,
"*Second Lieutenant, Post-Adjutant.*"

The narrative of the epidemic demonstrates the way in which the rdon *de santé* thus instituted was evaded.
The special reports of Assistant Surgeon McClellan and of Acting ssistant Surgeons Warren and Smith are presented.

Special report of Assistant Surgeon Ely McClellan, U. S. A.

LEBANON, KY., *August* 24, 1873.

o the MEDICAL DIRECTOR,
Department of the South:

SIR: I have the honor to report that, in obedience to your telegraphic der of the 20th instant, I proceeded to Lancaster, Ky. Upon my rival upon the ground I was soon satisfied that cholera was indeed idemic in that town. The town was nearly deserted, all the houses d stores were closed, business was entirely suspended. The cases hich had occurred up to that date were, with but a single exception, nfined to the blacks.
In company with Captain Fletcher I at once made an inspection of

the camp, which I found in most admirable order and police. After a most critical inspection I could find nothing to suggest beyond the removal of a mass of rank vegetation from a field adjoining the camp grounds, to which some of the company women had been removed from the town.

* * * * * * *

All the physicians of the town, and the gentlemen who still remained, having assembled at the National Bank for the purpose of consulting with me, I joined them, and, by inviting a narrative from each individual, I was enabled to obtain all the facts of the outbreak.

* * * * * * *

No organized effort had been made by citizens or physicians to suppress the disease. At the camp alone had disinfectants been used and other sanitary measures instituted. Earnestly I impressed the necessity of general police and disinfection, and secured a pledge from every person present that sulphate of iron, carbolic acid, and lime should be freely used by them, and that the work of general disinfection should be commenced at once.

* * * * * * *

Up to my departure at 8 o'clock a. m. on the 23d, there had been twenty-one cases of cholera in the town, with nineteen deaths; of the deaths two were white females who had fled into the country. Two cases were still alive. The president of the board of trustees authorized me to procure for the town the services of doctors and nurses from Louisville. Upon my arrival at this post I forwarded such medicines and hospital stores as to my knowledge were deficient in the hospital at Lancaster.

* * * * * * *

Having obeyed to the utmost your orders, I returned to my station, feeling that, from the rapid progress of the disease, my services were demanded by the troops and families of that command.

Very respectfully, your obedient servant,

E. McCLELLAN,
Assistant Surgeon U. S. A.

Special report of Acting Assistant Surgeon J. S. Warren, U. S. A.

POST OF LANCASTER, KY., *August* 28, 1873.

To the MEDICAL DIRECTOR,
Department of the South:

SIR: I have the honor to report that on August 22, 1873, I was contracted with by Dr. E. McClellan, Assistant Surgeon United States Army, to take charge of the post hospital at Lancaster, Ky. I reported immediately, and upon my arrival inspected the garrison, finding everything in a good sanitary condition, so far as cleanliness goes.

The garrison is located in the eastern portion of the town, just outside the town limits. It is upon a high elevation, much higher than any other point about the town. The natural drainage is excellent. The cholera seems to have been confined to certain localities along a ditch which bounds the garrison-grounds on the west. About the head of this drain is a well, which furnished water to the majority of the persons who have died of cholera. * * *

August 23, while sitting in Colonel Fletcher's quarters, at about 4 o'clock p. m., Drummer Rushbrook came in and told me he did not feel well. I examined and prescribed for him. At that time he did not

y symptoms of cholera. 'About 11 o'clock p. m. his wife came and ked me to visit him; she said that his bowels had moved several mes, and that he had also been vomiting. I found that what she told e was true; he had all the symptoms of cholera. I immediately insti- ted what I thought to be the proper treatment by hypodermic injec- ons of atropia, but nothing seemed to do him any good. About an ur after he was taken, his wife, who had been well all day, and even to the time she sent for me, was taken with cholera. The same treat- ent was adopted with the same result. The man was dead in twelve urs after being attacked; the woman in eleven.

Very respectfully, &c.,

J. S. WARREN.

POST OF LANCASTER,
Lancaster, Ky., November, 1873.

the SURGEON-GENERAL OF THE ARMY,
Washington, D. C.:

GENERAL: I have the honor to report for your information the llowing circumstances connected with the outbreak of cholera at this st during the months of August and September last.

Although epidemic cholera had appeared during the summer at shville and other places in the valley of the Mississippi, the authori- es of Lancaster neglected to adopt precautionary measures to prevent outbreak. In consequence, the sanitary condition of the town at the me of the recent epidemic was deplorable. The streets and alleys had t been cleaned for years, and contained the refuse of kitchens and e contents of stables and overflowed water-closets.

The character of the ground upon which the town is built is of such nature as to carry the sewage into the adjacent ravines. The prin- pal drainage is toward the east into a hollow where the poorer class of e population, mostly composed of negroes, reside in huts and shanties dly ventilated and extremely filthy. Through this hollow runs a nall stream, having its source at the base of Cemetery Hill, and after ssing through a meadow overgrown with rank vegetation, it becomes e main sewer for the neighborhood. On the bank of this stream, at e foot of the hill on Richmond street, was a public well—marked Tate's" on the map—so situated that it must inevitably receive the ntents of the stream, with the washings from the adjacent hill-sides. supplied a large part of the population with water. The post, located n an elevation near by, and garrisoned by Company E, Sixteenth fantry, Capt. J. S. Fletcher, jr., commanding, obtained water from a ne spring on the premises, exempt from surface-drainage. The bar- icks and outbuildings were neatly whitewashed, and the camp policed.

Such, briefly, was the sanitary condition of the town on Sunday, ugust 10, when a farmer named Bewley, aged thirty-five, residing near ussellville, East Tennessee, arrived on horseback, and remained at the ouse of one named Tate. The country in the neighborhood of his ome at the time was afflicted with epidemic cholera. He was attacked, hile traveling, with diarrhœa, and compelled to remain over one day t Loudon. After his arrival here he was prostrated with symptoms esembling typhoid fever, accompanied with vomiting and excessive in- oluntary rice-water discharges, which resulted in death the twelfth ay.

No endeavor was made to disinfect or bury the dejections. They were

carelessly thrown on the hill-side at the foot of the lot, immediately above the public well on Richmond street, into which, it is presumed, they were carried by the first rain. The water of this well, although possessing an unpleasant odor and disagreeable taste, was in constant use by the families living convenient, many of whom were attacked and died of cholera.

It was undoubtedly the contamination of this water by the discharges of Bewley that occasioned the outbreak of the disease in the community, although other causes exerted an influence in promoting its distribution.

The first case of cholera occurred August 15, five days after the arrival of Bewley. A negro man living on the same square, and reported to have used water from the Richmond-street well, was attacked with cholera and died in twelve hours. He was accustomed to work about the depot, and at the time was employed opposite the house in which Bewley was sick. The evening before he had washed a buggy in a stagnant pond, and committed some excess in diet. The same day the father-in-law of Bewley, in whose employ was the above-mentioned negro, and who had nursed and staid in the same room with his son-in-law, was taken violently ill on his way home, in the country, and died in eight hours.

On Sunday, August 17, a negro woman, occupying a low, damp, and filthy hovel with her daughter, was stricken with the disease, and died in twenty-two hours. The following Thursday the daughter, also, fell a victim to the epidemic.

Tuesday, the 19th of August, there were four cases of cholera and four deaths, among the colored people, of six, seven, six, and ten hours duration.

The announcement of the result in these cases occasioned intense excitement. The presence of cholera in the community could no longer be denied, and the citizens generally sought safety in flight. The trustees of the town, and the resident physicians, with two exceptions, accompanying the fugitives. In a few hours the population of the town was less than two hundred. Those who remained to face the disease engaged vigorously in the work of disinfection. Lard and sulphur were burned in the streets, and solutions of carbolic acid and sulphate of iron thrown profusely into the sinks, and scattered about the premises. The use of water from the Richmond-street well was interdicted, and the people urged to exercise the utmost caution in their diet. The chairman of the board of town trustees directed the only remaining druggist to dispense medicine to all who applied, at the expense of the town. He organized a corps of nurses for night and day work among the poorer class of the population, who appeared to suffer most from the epidemic.

The commanding officer of the post, Capt. J. S. Fletcher, jr., attended personally to the disinfection of the garrison-grounds. The sinks were carefully watched, and the men directed to report immediately any case of diarrhœa or sickness. The company-table was limited to such articles as did not affect the bowels, and only water from a neighboring spring directed to be used.

There were no deaths from cholera until Wednesday, when a negro man, living in the ravine on the Sugar Creek pike, was attacked with the disease and died in six hours. The same day a lady, who had left town to escape the ravages of the epidemic, was taken suddenly ill and died in sixteen hours.

On Thursday, the 21st, there were five cases and five deaths among the negroes; the first used water from the Richmond-street well, and died in six hours. The discharges were not disinfected, but thrown

privy used by the family, two of whom died the next day. The second e was the daughter of the woman who died the 17th. She was sick een hours. The third case left town on Tuesday and died at Camp lson after an illness of twelve hours. A row of houses near by were upied by fifteen persons, who were supplied with water from the well Richmond street; of this number, one died of cholera and four were cked with cholerine; and another, living on the opposite side of the n, died of choleraphobia. He ran home, jumped into bed, and could be persuaded otherwise. There was no vomiting, cramps, involuntary charges, or premonitory symptoms of the prevailing epidemic. The h case was the husband of the woman who died on Tuesday. He d in the same room and died in ten hours. The house contained e rooms, and was occupied by eight persons, three of whom suffered m cholerine, while two died of cholera.

The surgeon of the post being sick and of advanced age, it was med best to relieve him. Assistant Surgeon E. McClellan, United tes Army, stationed at Lebanon, was sent here to confer with the Comnding officer upon all matters connected with the cholera outbreak. obtained the services of J. S. Warren, M. D., of Crab Orchard, and rned to his station. The next day, Friday, there were three deaths. e first was a lady who had left town with her family, but who was en sick and died at the mouth of Hickman Creek. The next was the e and nurse of a negro who died the preceding day, and whose disrges were thrown into a privy. She was taken sick and died in elve hours at her father's house, in a hollow on the other side of the n. The discharges, as before, were thrown into a privy used by two nilies. The result was that a sister who had nursed the case, returned her husband's house, and soon after was taken violently ill with the ease and died in twenty hours. The discharges were carefully disected and buried, and no other case occurred in the family. On turday, a drunken miller, who boarded near the depot, was stricken h the disease and died in ten hours. The discharges were buried. ere were eight or ten occupants in the house at the time, but no other e occurred. One of the number suffered for several days with vomit; and diarrhœa.

Thesa me day a negro, who had used the privy into which the discharges m the colored woman dying the day before were thrown, was taken in an unfinished building, and died in twenty hours. A workman this building, boarding at the hotel, where little attention was given disinfection, died in Lincoln County, of cholera, after an illness of ght hours. Up to this date there had been no evidence of the disease camp, and it was thought the garrison would escape its ravages; but out 9 o'clock p. m. a soldier, Samuel B. Rushbrook, musician, Comny E, Sixteenth Infantry, living outside of the grounds, in the quars of the commanding officer, which were neat and well policed, was cked with premonitory symptoms, and died at 8.30 o'clock a. m.

On Monday, August 25, in accordance with the requirements of Spel Order No. 150, Headquarters Department of the South, Louisville, ., dated August 25, 1873, I reported for duty to the commanding icer of this post, and immediately inspected its sanitary condition. e garrison grounds were found to be in admirable order, and the most nicety to prevail in regard to cleanliness. The police regulations ere perfect; the barracks and tents well ventilated, clean, and comtable. The sinks and privies were daily disinfected, and the refuse om the kitchen buried. The water for the garrison had been brought om a spring on the premises, but fearing it might become contam-

inated, its use was prohibited, and rain-water from an inclosed cistern substituted. The men generally were complaining of diarrhœa, but its progress was carefully watched and checked by the administration of an opiate combined with astringents.

An allowance of whisky and quinine was issued twice a day, and such other precautions adopted as were thought advisable. The same day a lady who had visited Tate's house died in the country of cholera.

On Wednesday, August 27, an old negro man who had nursed some of the cases was taken with violent purging, cramps, and vomiting. He had been complaining several days, but refused to take medicine. I saw him with Dr. Wilson at midnight, when the pulse was almost imperceptible, and he was fast passing into a state of collapse. The temperature was 97° in the axilla, under the tongue 96.6°, and in the rectum 102°. A solution of morphine and atropia was given hypodermically. The catheter was introduced and no urine found in the bladder. Involuntary discharges were constantly occurring. The patient lingered until 8.30 o'clock a. m., and died from exhaustion.

The evening of the same day, Thursday, a lady who had been living in town died in the country of cholera. The rest of the family in the same house had used water from the Richmond-street well, and were attacked with premonitory symptoms of cholera, but recovered. Early Friday morning, August 29, private Eugene Hasbrouck, Company F, Sixteenth Infantry, who occupied a tent with others on the garrison grounds, was admitted to the post hospital, complaining of vomiting and diarrhœa. At 6.30 o'clock a. m., when first seen, he was very much debilitated from the excessive discharges. The temperature in the axilla was 97½°, and under the tongue 98°. I introduced hypodermically one sixtieth of a grain of atropiæ sulph., and ordered sinapisms to be applied to the stomach and abdomen, and prescribed as follows: R. Inf. opii, gr. iv; pulv. camphoræ, gr. viii; hyd. chlor. mite, gr. viii: M. et chart. No. iv; one to be given every third hour. The first dose was immediately vomited, the others retained. At 8 o'clock a. m. there was an action of the bowels in a bed-pan; the discharge was watery, rice-colored and slightly flocculent; it was immediately disinfected and buried. The temperature at this hour was 96°. I again introduced hypodermically one-sixtieth of a grain of atropiæ sulph., and by advice of Dr. Wilson ordered an administration of five grains of hyd. chlor. mite to be given dry on the tongue every hour and a half. The extremities becoming cold, I ordered bottles of hot water to be applied, and the patient wrapped in blankets. At 9.30 o'clock a. m. the temperature had increased to 97⅖°, when the following was ordered: R. Albumen ovi recentis, No. 1; sodæ chlor., gr. x; spts. frumenti, ℥ss. To be given as required. A catheter being introduced, and the bladder being found void of urine, a flaxseed poultice moistened with ext. digitalis fld. was ordered applied to the small of the back, over the region of the kidneys, and R. Tinct. digitalis, gtt. xv; spts. æth. nitrosi, ℥i, to be given at once, and as often as required. At 10 o'clock a. m. the temperature was 98°. The patient complained of pain in the chest; was restless and perspiring freely. I gave hypodermically one-fourth of a grain of morphine, which relieved the distress and enabled him to sleep. At 11 o'clock a. m. the temperature was normal, and the patient sleeping soundly. At 12 o'clock m. the temperature was 98⅘°; at 2 o'clock p. m. 102⅘°. At 3 o'clock p. m. the symptoms changed; the surface became cold and livid; the skin shrivelled and clammy; the breathing short and labored. A catheter was introduced and not a drop of urine found in the bladder. The patient continued in this condition until death occurred, at 5 o'clock p. m.

During the last hours of Hasbrouck's illness, Private Hermann thjin, Company E, Sixteenth Infantry, who had occupied the same t and bunk, was admitted to the hospital suffering from diarrhœa. had been to the rear four times since morning. He reported at sick- l at 7.25 o'clock a. m., when Acting Assistant Surgeon Warren pre- ibed the following: R. Quiniæ sulph., gr. xxiv; pulvis opii, gr. viii; lrarg chlor. mite, gr. iv; bismuthi subnitras, 3ij. Mix in eight ders; one to be taken three times a day. When brought into the spital his temperature was 99°, and he was complaining of cramps in extremities. There had been no vomiting. Acting Assistant rgeon Warren ordered one drachm of Squibb's mixture to be given occasion required. A wall-tent was erected, and the patient removed m the neighborhood of the hospital where Hasbrouck was dying. 4 o'clock p. m. he had a thin and slightly flocculent discharge. It was infected with carbolic acid and buried. At 5 o'clock the temperature axilla was 99°. He was restless and complaining. The bowels ved again; the second time since the patient was admitted. The charge was excessive in quantity, and wet the bed. I introduced podermically one-sixtieth of a grain of atropia and one-fourth of a in of morphine, with evident relief. At 6 o'clock p. m. the patient was good spirits; so much so that when asked as to his condition, he lied, "Bully; I never felt better in my life." At 7 o'clock p. m. his feat- s had undergone a great change; the face emaciated; the orbits ken; hands shriveled; nails blue; upper extremities cold and pulse- s: lower extremities, body, and face warm. At 8 o'clock p. m. the sur- e was cold and clammy, and the patient comatose. I introduced the theter, and found the bladder empty. At 10 o'clock p. m. the tempera- re was 99°, and the pulse still imperceptible. At 10.30 o'clock p. m. I dered mustard bandages applied to the extremities, when the patient ghtly reacted. At 1 o'clock a. m., August 30, he was moribund. The theter was again introduced, but no urine found in the bladder. At o'clock a. m. his condition was the same; still sinking, with lower ex- mities slightly warm; 7 o'clock a. m. the same. At 7.30 o'clock a. m. e patient died.

In tracing the origin of this and the preceding case, I learned that ivate Rathjin had nursed Musician Rushbrook and wife during their ness, and that Private Hasbrouck had passed several times through e room. Both, however, are reported to have visited certain aban- ed negro shanties, where cases of cholera had occurred, and it is sup- ed that they contracted the disease in that way. The day these two ldiers died the command moved two miles to a new camp, where there s a fine spring of water, and remained there until the disappearance the disease in town. The troops while encamped enjoyed excellent alth. The same day, Saturday, the 30th, a feeble old negro died of e cholera in a law-office in town, after an illness of sixty hours, and e child of a negro who had nursed nearly all the cases was taken ill ith the symptoms of cholera, and died in six hours. The discharges re at first thrown on the ground, but afterward disinfected and ried.

The following Tuesday, September 2, a colored woman who had nursed e last case was attacked with vomiting and diarrhœa, which soon came rice-water in character. Atropine, opium, quinine, and calomel re prescribed without effect; the temperature in the axilla being °, and the patient rapidly sinking. Drs. Wilson and Berry, the attend- g physicians, determined at 10 o'clock p. m. to resort to the transfusion f milk. The following is their report of their experiment:

"Having to improvise an apparatus, the necessary preparations were not completed until 11.30 o'clock p. m., at which time the patient was pulseless, could only speak in a husky whisper, and was so weak as to be unable to raise her head. It being impossible, because of her dark color and the lateness of the hour, to find the cephalic vein, the median cephalic was exposed, the tube inserted, and milk fresh from the cow, and heated at the temperature of 100°, was slowly passed into the vein. In fifteen minutes six or seven ounces had been transfused, when the pulse became moderately strong, the voice returned, so that she could be heard in the adjoining room, and her strength was increased, so that she partially raised up in bed and turned over on her side. The movement of the arm threw the tube out of the vein, when we determined to let her rest for an hour, and then procure more fresh milk with which to repeat the injection. At the end of half an hour she was found sinking rapidly, and before the preparation could be made she was dead."

The same day a lady, who had left town, died in the country of cholera.

On Thursday, September 4, a colored woman, who had been ill some time, was attacked and died of the disease in twelve hours.

At the same time the wife of a negro preacher was taken sick and died in twenty-three hours. These cases for a time were supposed to terminate the disease; and those citizens who had been absent since the first appearance returned to their homes. Among the number returning was a lady who stopped at Tate's house, and occupied the same room in which Bewley died. She had been there but a few days when she was attacked with a severe diarrhœa, that rapidly culminated in cholera. She died Sunday, September 21. This case terminated the disease.

I have enumerated, in the foregoing report, only those cases that resulted in death. There were several cases pronounced cholera that recovered. The first case was a stout, healthy young colored woman living in the rear of Tate's house, who had unmistakable symptoms of the disease. She used water from the Richmond-street well.

The next was a consumptive, the undertaker of the town, who used a privy in common with persons nursing cholera-patients, some of whom afterward were attacked and died of the disease. He had quite a number of thin rice-water discharges, accompanied with vomiting and cramps and entire suppression of urine. The symptoms readily yielded to treatment, and the patient rapidly convalesced.

The third recovery was a young man living opposite the Richmond-street well, who was taken sick in the country with violent vomiting, diarrhœa, and cramps. He was greatly prostrated, and had complete suppression of urine for two days.

The fourth was a colored woman, the mother of the child that died on the 29th. The discharges in this case were very copious, and resembled soap-suds, but afterward became rice-water in character. There was vomiting and cramps, with partial suppression of urine. The treatment, as in the former cases, consisted in the hypodermic injection of atropia with morphine, and the administration of ten grains of dry calomel on the tongue every hour. The patient speedily recovered.

The fifth case was Private William Graff, Company E, Sixteenth Infantry, who was severely prostrated by an acute attack of vomiting, purging, and cramps. His symptoms were carefully watched by Acting Assistant Surgeon Warren, and counteracted by the administration of dry calomel on the tongue, and the injection hypodermically of one sixtieth of a grain of atropia and one-fourth of a grain of morphine. The patient slowly convalesced.

he sixth and last case of recovery occurred at a hotel in town which
in an extremely filthy condition. The cook, a colored woman, was
en with a profuse diarrhœa, which speedily became choleraic. The
ıit was thin and watery; the patient complained of excessive thirst,
of severe cramps in the extremities; the voice became husky; the
its sunken; the skin shriveled, and the surface cold and clammy.
bowels moved involuntarily, the patient's expression being, "it's
the time running from me;" but there was no suppression of urine.
troduced hypodermically a solution of atropia and morphia, with the
ct of controlling the cramps and pain and quieting the stomach. I
ı ordered five grains of dry calomel to be given every hour until the
harges became tinged with bile. The involuntary movements of
bowels ceased, and the patient rested comfortably. The next day I
cted fifteen or twenty drops of aromatic sulphuric acid to be given
ry four hours, and the patient to be well nourished. Secondary fever
n afterward occurred, and the recovery was protracted.
luring the prevalence of the epidemic almost every remedy was pre-
bed, but nothing found so beneficial as the hypodermic use of atropia
morphia in controlling the cramps and vomiting. It was not an
ommon occurrence to give ten grains of dry calomel on the tongue
ry hour until the discharges were distinctly tinged with bile.
he tongue usually indicated a malarial influence, in which case
nine was prescribed. It was noticed during the epidemic that a
ıpathetic diarrhœa prevailed among the citizens, and that in many
es it was accompanied with a partial suppression of urine.
ut of the thirty-four cases of cholera that occurred, only six of them
pened on the west side of town, while the greater number are located
he immediate neighborhood of the Richmond-street well, or in the
ine in which it is situated.
ix cases of cholera are reported from Tate's house, in which Bewley
l, and where undoubtedly originated the outbreak. The largest
ıber of cases occurred Thursday, August 21.
he following is an exhibit of the number of white and colored, male
female, cases that occurred during August and September:

Months.	White.		Colored.		Total.
	Male.	Female.	Male.	Female.	
ust	6	5	11	7	29
ember	.....	2	.....	3	5
Total	6	7	11	10	34

The following table shows the duration of illness, the complexion, and sex:

Hours.	White.		Colored.		Total No. of cases.
	Male.	Female.	Male.	Female.	
6			4	1	5
7			1		1
8	2		1		3
10	2	1	2	2	7
12	1		1	3	5
15				1	1
16	1	1			2
20			1	1	2
22				1	1
23				1	1
60			1		1
Unknown					5

Very respectfully,
Your obedient servant,

SAML. L. S. SMITH,
Acting Assistant Surgeon
United States Army.

IV.—LEBANON, KY.

On the 31st of August, an explosion of epidemic cholera occurred at the town of Lebanon, Marion County, Kentucky.

The command in garrison at the United States barracks upon the northern outskirts of the town, was in most admirable condition, with almost a clean sick-report.

Extraordinary precautions were adopted to discover any case of cholera (should it occur among the troops) at its inception. A guard was kept over the camp-privy, and any individual having two actions of his bowels within twenty-four hours was at once reported, and was required to use at the next dejection an earth-closed commode, that its character might be inspected.

The official history of this post during the epidemic is presented in a series of official telegrams, letters, and reports.

HEADQUARTERS DEPARTMENT OF THE SOUTH,
Louisville, Ky., September 3, 1873.

COMMANDING OFFICER,
Lebanon, Ky.:

SIR: I am instructed by the department commander to direct that, in case the cholera makes its appearance among your command, it be removed to a camp to be selected by yourself and the medical officer of the post.

Very respectfully,
Your obedient servant,

J. H. TAYLOR,
Assistant Adjutant-General.

HEADQUARTERS POST OF LEBANON,
Lebanon, Ky., September 8, 1873.

Assistant Surgeon ELY MCCLELLAN,
Post-Surgeon, Lebanon, Ky.:

SIR: Inclosed herewith please find a copy of letter from headquarters Department of the South, directing, in case "cholera" appears

ng this command, that it be removed to a camp to be selected by commanding officer of the post and yourself. In view of your exive knowledge of the surrounding country, the commanding officer ld be pleased to hear from you of a locality suitable for a camping-nd.

Very respectfully,
Your obedient servant,
W. W. BARRETT,
First Lieutenant Sixteenth Infantry, U. S. A.,
Post-Adjutant.

"LEBANON, KY., *September* 8, 1873.

SIR: I have the honor to acknowledge the receipt of your communi-on of this date, relating to the removal of the command from the acks in case cholera should appear among the troops.

It is impossible for me to designate any locality in this vicinity which ld be suitable for a camping-ground.

In the entire country around Lebanon cholera is or seems to be epi-ic, and the cases attacked have all gone rapidly to a fatal termi-on.

The present indication seems to be that the disease is arrested in the n, and for the present, in my opinion, the barracks are the safest t at which the troops could be placed.

Should a removal become imperative, I would suggest that the camp cted should be in a portion of the country uninfected, and that would uire a considerable distance to be placed between the camp and rion County.

"Very respectfully, your obedient servant,
"ELY MCCLELLAN,
"*Assistant Surgeon U. S. A.,*
Post Surgeon.

Lieut. W. W. BARRETT,
"*Sixteenth Infantry,*
Post-Adjutant, Lebanon, Ky."

"HEADQUARTERS, POST OF LEBANON,
"*Lebanon, Ky., September* 9, 1873.

SIR: I have the honor to submit herewith report of Assistant Sur-on Ely McClellan, U. S. A., post-surgeon, upon the question of moving troops in case cholera should make its appearance among the com-nd.

Upon receipt of the letter containing the order above referred to, Dr. Clellan and myself made an extended tour of observation of the ntry adjacent to the town of Lebanon, the result of which satisfied r minds that cholera was raging to a much greater extent and with re virulence in the country, say within twelve or fourteen miles of e post, than within the limits of the town of Lebanon, (and where olera is not prevailing, flux is.) In interviews with members of the dical profession, who have every opportunity to know the condition the health of the county, I find, without exception, that they indorse my inion. Under such circumstances, and in view of the facts that the oops are comfortably quartered; that they are accustomed to the water the post; that the post is in very good sanitary condition, (as the edical Director of the Department can testify,) and that if the troops ere moved it would almost be impossible to proceed to any point that

is uninfected within two days' march of the post, and then it would be very doubtful if a building could be obtained to quarter the troops; that if they had to live under canvas at this late period of the year, with warm days and cold nights, it would probably induce diseases similar to those prevailing through the country; that the health of the command is very good—(out of a total of nearly eighty persons only persons are sick)—and that in making the move the regular routine duty at this post would be broken into and the command would be more or less alarmed, I have the honor to respectfully ask that the order referred to be so amended as to leave it within the discretion of the Post-Commander and Medical Officer if the move be made and should they decide so to do, that the command may be permitted to move by rail to such a point as in their judgment may seem best.

"Very respectfully,
Your obedient servant,

"CHAS. E. MORSE,
"*Captain Sixteenth Infantry U. S. A.,*
Commanding Post.

"ASSISTANT ADJUTANT-GENERAL,
"*Headquarters Department of the South,*
Louisville, Ky."

"HEADQUARTERS DEPARTMENT OF THE SOUTH.
"*Louisville, Ky., September* 12, 1873.

"SIR: I am instructed by the department commander to say that the question of removing the troops from Lebanon, in the event of the cholera appearing among them, is left to the judgment of the Post-Commander and Medical Officer.

"Very respectfully,
Your most obedient servant,

"J. H. TAYLOR,
"*Assistant Adjutant-General.*

"COMMANDING OFFICER,
Lebanon, Ky."

The special report of Assistant Surgeon Ely McClellan to the Surgeon-General of the Army is herewith submitted:

"SEPTEMBER 30, 1873.

"To the SURGEON-GENERAL U. S. A.

"SIR: I have the honor to forward herewith the report of the epidemic of cholera which occurred in the vicinity of this post during the months of August and September of this year. As soon as the presence of cholera was announced in New Orleans in May last, I succeeded in forming among the medical men of this town a sanitary association. The co-operation of the town trustees was secured, an inspector was appointed, and every effort was made to place the town and its surroundings in as perfect a state of sanitary police as possible. Under the able administration of Capt. C. E. Morse, Sixteenth Infantry, commanding the post of Lebanon, Ky., the garrison was placed in the most admirable police; drains were cleared and disinfected; the *débris* was collected and burned; a careful supervision was kept over the diet and personal cleanliness of the men of the command. Special means were adopted to secure the well from which the drinking-water was procured from all surface

nage. I have no hesitation in stating that the sanitary condition admirable and could not have been improved.*

* * * * * * *

During the epidemic the medical gentlemen of this town were con- ıtly engaged in the country, and for the majority of the hours after outbreak of the disease until September 2, when Acting Assistant geon R. G. Redd, U. S. A., who had been ordered to report to me, ved, I was the only physician in the town.

The commanding officer wisely maintained all camp regulations; duty ıt on as usual; no unusual restrictions were employed, but a constant ilance was maintained.

Impressed with the value of prophylactics, or rather internal disin- ion, sulph. of iron and sulphuric acid were exhibited in all cases, and a ture containing quinine, sulph. of iron, and sulphuric acid largely ıted, was kept upon the hospital-table, and all the command were en- raged to use it. The officers and their families were requested to asionally use a pill of iron, gentian, and nux vomica. With the ex- tion of two cases of diarrhœa threatening to terminate in dysentery he families of two of the officers, that portion of the command re- ıed healthy. Laundresses and their families were subjected to the ie regulations as enlisted men, except that the supervision was with m, if possible, more exacting."

PARTMENT OF TEXAS.

To the courtesy of the Medical Director, Department of Texas, we are ebted for the following information:

"SAN ANTONIO, TEXAS, *November* 4, 1874.

"DOCTOR: The epidemic of cholera of 1873 was heard very little of re. In May of that year I learned, indirectly, from private sources, it the cholera was at that time prevalent and very fatal in New Or- ns; and as there was then a military post here, with a garrison of o companies of infantry, I addressed a communication in relation to to the mayor of this place. (See inclosure.)

"The report was corrected very soon afterward, and nothing more was ard here of the epidemic until September, when it was rumored that th cholera and yellow fever were at one or two points on the Houston d Texas Central Railroad, at Denison and below; but it was not finitely understood that it was truly cholera until subsequently.

"There was but one case reported among the troops in this department 1873. It occurred in a soldier, Private William J. Carson, Company , Eleventh Infantry, while on detached service, on escort duty from ort Griffin, Texas. He died at Denison, Texas, of cholera, at 4 o'clock m. the 14th of October of that year. The report was received at this fice the 13th of December. The case was reported by Acting Assistant rgeon J. S. Cooper, U. S. A., then acting as post-surgeon at Fort riffin, who states in his report, "I am informed that the disease was pidemic in Denison at the time, and the mortality ranged from nine fourteen persons daily."

"I was on a tour of inspection at the time, and heard nothing of this

* The omitted portions of this report refer only to events which have already been ated at length in the narrative of the Kentucky group.

case, and very little about the existence of cholera anywhere; and there were no steps taken to prevent its introduction.

"Very respectfully,

"Your obedient servant,

"J. F. HAMMOND,

"*Surgeon U. S. A.*

Dr. ELY MCCLELLAN,

"*Assistant Surgeon U. S. A.*

"HEADQUARTERS DEPARTMENT OF TEXAS,

"MEDICAL DIRECTOR'S OFFICE,

"*San Antonio, May* 23, 1873.

"To Hon. F. GIRANDL,

"*Mayor San Antonio, Texas:*

"SIR: I have the honor to call your attention to the fact that an epidemic of cholera is said to be prevailing largely in New Orleans, and the mortality great. As the quarantine-laws are not in force along the coast of this State, the disease may make its appearance by any arrival of the stage from Austin or Columbus. I would respectfully suggest that you take, as early as practicable, such measures as the law allows to have and to keep the city thoroughly policed and disinfected, and to have inspected the markets, with the view to excluding all unsound meats, fish, and vegetables.

"Very respectfully,

"Your obedient servant,

"J. F. HAMMOND,

"*Surgeon U. S. A.,*

"*Medical Director Department of Texas.*"

INDEPENDENT POSTS.

"SAINT LOUIS BARRACKS, MO.,

"*October* 15, 1873.

"SIR: I have the honor, in compliance with your request, to furnish you with the following account of the occurrence of cholera at this post in 1873, and of the measures adopted to prevent its spread.

"The only case of cholera that occurred during the year 1873 was in the person of private John T. Morton. This man was a new recruit, large frame and healthy constitution. He reported sick about 10 o'clock a. m. on the 14th of July, 1873, and stated that he began to have diarrhœa at daylight that morning, and that he did not report at sick-call, as he thought it would soon pass off.

"On admission to hospital he had all the characteristic symptoms of cholera. He rapidly became worse, and died at 9 o'clock p. m. the same day, having retained his consciousness and exhibited the most striking indifference to his approaching death. No autopsy was made. Careful inquiry elicited nothing of importance in regard to the source of his disease. He had not been drinking, and had always slept in the quarters of his troop.

"In June cholera prevailed extremely in the adjacent city of Saint Louis, and in July diarrhœa prevailed in the command to the extent of 55.6 per cent. of the whole number taken sick.

"On the 30th of July, in addition to urging in writing that the guard-house be more thoroughly ventilated by suitable openings, I made the following recommendations, which were at once carried into effect:

"I. The old sinks in the rear of the quartermaster's and commissary's storehouses should be filled with dry earth, and no more refuse thrown in.

II. The two main sinks on the north and west sides of the post uld be flushed daily, and all others that do not communicate with sewers should be disinfected daily. Attention should be particu- given to the daily emptying and cleansing of the earth-closets l at the married soldiers' quarters.

III. The back yards of all married soldiers' quarters should be oughly policed and inspected twice a week.

IV. Prisoners should be required to bathe every other day ordina- and every day in hot weather.

Attention to the foregoing measures should be given persistently continuously, spasmodic efforts in such matters being of little il.

* * * * * * *

The floor of the wood-shed ought to be scraped and sprinkled with

A nuisance is committed at the rear of the quartermaster's store- se by men urinating there.

"B. A. CLEMENTS,
"*Surgeon U. S. A.*"

Dr. ELY MCCLELLAN, U. S. A.,
Lebanon, Ky.

gave daily personal attention to the police of the post, and especially he flushing and disinfection of the sinks.

n July 1, I addressed the following letter to the superintendent:

"CAVALRY DEPOT, SAINT LOUIS, MO.,
"*July* 1, 1873.

GENERAL: In view of the prevalence of a form of cholera in a num- of cities bordering the Mississippi and its tributaries, and of its alence in this city to the extent of twenty-five deaths in adults ng the week just passed, I have the honor, in accordance with your est, to suggest the advisability of detaining recruits at this depot for the shortest length of time that the interest of the service will it of.

"Very respectfully,
"Your obedient servant,

"B. A. CLEMENTS,
"*Surgeon U. S. A.*

General B. H. GRIERSON, U. S. A.,
"*Superintendent G. M. R. S.*"

n July 15, as the occurrence of diarrhœa was becoming more preva- , I addressed the following letter to the superintendent, and an order ibstantial conformity therewith was at once issued and caused to crupulously observed:

"CAVALRY DEPOT, SAINT LOUIS, MO.,
"*July* 15, 1873.

GENERAL: A marked tendency to the occurrence of choleraic diar- a having manifested itself among the command, I deem it proper ectfully to recommend that troop-commanders be advised and in- cted to forbid the use in their troop mess-rooms of the following etables, which are believed to be hurtful, viz, cabbage, corn, string- ns, turnips, cucumbers.

The following vegetables afford sufficient variety for a wholesome

diet, and are deemed not to be injurious, viz, potatoes, beets, tomatoes, squash, okra, onions.

"I also recommend that the men be advised and ordered to report to the hospital without delay, and without regard to hours, whenever they become affected with diarrhœa.

"Very respectfully,
"Your obedient servant,

"B. A. CLEMENTS.
"*Surgeon U. S. A.*

"General B. H. GRIERSON, U. S. A.,
"*Superintendent G. M. R. S.*"

On the 21st July means were taken on my written representation to diminish the overcrowding of the guard-house.

During all this period the cholera, and diseases resulting in death called in the official reports cholera morbus, prevailed very extensively in the city of Saint Louis, and but one case occurred here.

In view of the known predisposition of recruits to the attacks of cholera, in consequence of the change in their accustomed diet, and their imprudences, it seems probable that the measures adopted assisted in preventing the further occurrence and spread of the disease at the post.

Very respectfully,
Your obedient servant,

B. A. CLEMENTS,
Surgeon U. S. A.

APPENDIX.

ETEOROLOGICAL RECORDS FROM DECEMBER, 1872, TO NOVEMBER, 1873, IN THE UNITED STATES.

While engaged in collecting the facts upon which the narrative of the olera-epidemic of 1873 is based, we were frequently urged to present th the report a complete history of the meteorological conditions ich may have been recorded during the months in which the epi- mic influences were observed.

Through the courtesy of the Chief Signal-Officer of the Army, we e able to present extracts from the monthly weather review from cember, 1872, to November, 1873.

MONTHLY WEATHER-REVIEW, DECEMBER, 1872.

STORMS.

During this month no less than twenty-seven storm-centers have been traced in their gress over various parts of the country upon the War Department weather-maps, nal Service, United States Army. Two of these storms have apparently traveled tirely across the country from the Pacific coast, but the paths of the remainder are rly confined to the country east of the Rocky Mountains, and are about equally ded between the two favorite winter-routes of these disturbances, the one from the thwest eastward over the lake region and northern New England to the eastern tish provinces, and the other from the southwest northeastward to the Middle tes and New England, or eastward along the Gulf coast, thence following the trend the Atlantic coast northeastward toward Nova Scotia.

RAIN-FALL.

The returns from the signal-service stations show that an excess of rain, amounting from 2 to 5 inches above the mean rain-falls for December, has, during the month, len in Texas, Louisiana, and Western Mississippi. A surplus, varying from 1.12 hes to 2.69 inches, has also fallen in Southern Virginia, North Carolina, Eastern nessee, interior portions of South Carolina and Georgia, and in Northeastern rida. In all other sections east of the Rocky Mountains (excepting at New London, chester, Leavenworth, and Breckenridge, which exhibit amounts slightly above the an) the figures show that the fall of rain and snow has been less than the average December. This deficiency is comparatively small for New England, the Middle tes, and lower lake region, but is large in Western Tennessee, the Ohio and Upper sissippi Valleys, and over the country adjacent to Lakes Michigan and Superior, the cipitation having been scarcely one-fourth as much as the average for the month at ny stations in these sections.

TEMPERATURE.

The mean temperatures for the month at the signal-service stations compared with e mean temperatures for December, as ascertained by a long series of observations, ow that the month has been much colder than usual everywhere east of the Rocky ountains. This excess of cold amounts to from 5° to 7° at stations in all parts of the untry, and at Chicago, Milwaukee, Leavenworth, Breckenridge, and Rochester, it mounts to over 8°. Much colder weather has prevailed than in December, 1871, in all tions east of the Territories, except from Virginia to Southern New Jersey, and from braska to Northern Illinois, where the temperatures have been about the same. This nually severe weather may be attributed to the large number of areas of high barom- r, or high atmospheric waves, which, with their attending low temperatures, have lled across the country from west to east. No less than fifteen of these areas of high ssure have been traced upon the weather-maps for this month, while during the cor- sponding month last year only nine made their appearance.

MONTHLY WEATHER-REVIEW, JANUARY, 1873.

STORMS.

During the past month the progress of twelve storm-centers has been traced on the weather-maps of the signal-service. Of these, three have crossed the country in a northeastward direction from Texas to New England and the British provinces; two have moved from the extreme northwest eastward over the lakes into Canada or New England; one from Manitoba over Lake Superior into Canada; two northeastward the Atlantic coast to the Eastern States and Nova Scotia or Canada; and one has progressed eastward through the Gulf States, and thence northeastward up the coast.

Of these storms the most severe have been that of the 7th and 8th in the northwest and that which from the 21st to the 24th crossed the country from Texas to Nova Scotia. The westerly winds closely following the center of the former increased to storm gales, which, with heavy snow and temperatures far below zero, served to render one of the most terrific which has visited that section for many years. The latter (that of the 21st) was very extensive in its effects, as during its course nearly the whole country east of the Rocky Mountains was reached by its rain or snow belts. Its northeasterly gales were felt with most severity from Lake Michigan to Lake Erie, and heavy snows fell from Kansas and Missouri northeastward to Canada.

RAIN-FALL.

The monthly rain-fall returns for January from the signal-service stations show that there has been in general a deficiency on the Pacific coast; but east of the Rocky Mountains an excess of rain and snow. This latter excess is most decided in Missouri, New Jersey, and Connecticut. A small region of deficiency also appears to extend over Kentucky, Tennessee, Mississippi, and Alabama.

TEMPERATURE.

The mean temperatures for January, as given by the signal-service reports, show that over the country east of the Rocky Mountains the weather has been generally colder than usual. This difference is greatest in the northwestern section, being in Michigan and Northern Ohio about 6° below the mean temperature for the month, and from Wisconsin and Minnesota to Kansas ranging from 7° to 12° lower than usual. In the Upper Mississippi Valley, and also Northwestern New York, the average temperatures have been from 5° to 6° lower than might have been anticipated, while this difference in New England and throughout the Middle States generally has been from 2° to 4°. In the South Atlantic States about the mean temperatures have prevailed, except in Northern Florida, where they are shown to be somewhat lower, as also in the Gulf States.

MONTHLY WEATHER-REVIEW, FEBRUARY, 1873.

STORMS.

During this month ten different storms have crossed portions of the country east the Rocky Mountains. The paths of their centers have, approximately, been traced upon the War Department weather-maps, Signal Service, United States Army.

That of February 3d and 4th passed over Nebraska, Iowa, Wisconsin, and Michigan into Canada, accompanied by rain, at places heavy, from Texas to Iowa and eastward to the middle Atlantic coast, but by generally light snow or rain, thence northward over New England and the lakes, and by brisk and high winds over the lake region, westerly winds being most severe; thunder-storm reported from Knoxville, 4th.

February 5, 6, 7, and 8.—Over Gulf and South Atlantic States and thence northward off the middle and east Atlantic coasts and over Nova Scotia, accompanied by heavy rain to Massachusetts, and by fresh and brisk winds over Gulf coast, and brisk and high over Atlantic coast, easterly to northerly winds most severe.

February 6 and 7.—Eastward over Northern Minnesota and Lake Superior into Canada accompanied by areas of very light snow and brisk and high winds over the lake region, southwesterly to northwesterly being most severe.

February 9, 10, and 11.—Eastward from Dakota over Minnesota, Wisconsin, and Michigan into Canada, accompanied by generally light rain or snow from Missouri, Tennessee, and Virginia northward and northeastward, and by brisk and high winds southeasterly to southwesterly being most severe.

February 11 and 12.—Northeastward over Southern States and beyond middle Atlantic coast, accompanied by heavy rain from Kentucky to Southern New Jersey and southward to Gulf, but snow from Ohio to lower lakes and Connecticut, and by brisk and high southerly to westerly winds over western Gulf coast, brisk and high southwesterly over South Atlantic States, and brisk and high easterly to northerly from Virginia

Massachusetts; thunder-storm reported from Knoxville, 12th; storm very severe m Cape Cod southward.

February 15, 16, and 17.—Northeastward from Texas over the Ohio Valley; thence tward over and beyond middle Atlantic coast, accompanied by rain, generally heavy, m Iowa to Connecticut and southward to Gulf, but areas of light rain and snow nce northward to Maine and the lakes, and by brisk and high winds over western if and Atlantic coasts; severe thunder-storm reported from Memphis on 15th.

February 17 and 18.—Northeastward from Dakota over Minnesota and Lake Superior o Canada, accompanied by light rain and snow and by brisk and high winds, fol- ed by low temperature.

February 20 and 21.—One over the Southern States, and thence northeast along the st, with fresh and brisk southerly winds over west Gulf, veering to high northerly; sk southerly over south Atlantic coast, and brisk and high northeasterly to north- sterly over middle and east Atlantic coasts; other northeastward over Missouri, nois, and Michigan into Canada with brisk and high winds; the two accompanied heavy rain over the country east of the Rocky Mountains, except snow from Iowa l Minnesota eastward over the lake region and Northern New England.

February 26 and 27.—From Nebraska and Missouri northeastward over Michigan into nada, accompanied by brisk and high winds; at the same time a diminished pres- e from Texas eastward over Gulf and South Atlantic States, and thence northeast middle and east Atlantic coasts with brisk and high winds; the two accompanied rain from Missouri to Northern Louisiana and eastward to Virginia and south At- tic coast, but by snow thence northward over northwest lakes and Southern New gland.

RAIN-FALL.

ls compared with the means of a number of years for the month, the rain-fall returns m the signal-service stations show a deficiency over the lake region, Northwest, ulf States, Southern Georgia, and South Carolina, New York, and Northern New Eng- nd, but an excess from the northern portions of Alabama, Georgia, and South Caro- a to Tennessee, Southern Indiana and Ohio, Pennsylvania, and Southern New Jersey, ing most marked over Tennessee; also an excess over Rhode Island and Eastern Mas- chusetts and Connecticut.

TEMPERATURE.

From the mean temperature for the month, taken from the signal-service reports d compared with that for a number of years at the same stations, or close by, it is served that the former has been somewhat higher over the Gulf States, eastern por- ns of Kentucky and Tennessee, and southern portions of Ohio and Indiana, by from to 4°, but otherwise east of the Rocky Mountains lower by from 1° to 8°, being ncipally over New York, Michigan, Wisconsin, and Minnesota.

MONTHLY WEATHER-REVIEW, MARCH, 1873.

STORMS.

During this month eleven storms have crossed portions of the country east of the cky Mountains. The paths of their centers have approximately been traced upon e War Department weather-maps, Signal-Service, United States Army.

The center of that of March 1, 2, 3, and 4, passed from Texas over the Gulf States as diminished pressure on the 1st and 2d, accompanied by heavy rains and brisk winds, ich increased to high northerly along the Texas coast on the 1st and 2d; thence rtheastward along the Atlantic coast, followed by brisk and high northerly to west- ly winds over South Atlantic and Middle States, but brisk and high northeasterly, cking to northwesterly, over east Atlantic coast, and accompanied by heavy rain er the South Atlantic States, but by generally light snow over the Middle and East- n States; this was followed on the 2d and 3d by very cold weather and brisk and gh northwesterly winds from the northwest and upper lakes to the Gulf, which, on e 3d and 4th, extended eastward over the Atlantic coast; on the 3d, thermometer adings from 15 to 36 degrees below zero were reported from Minnesota.

March 6, 7, and 8.—Nearly due east over Dakota, Minnesota, and Upper Michigan to Canada, preceded by rain and brisk to high easterly and southerly winds from the pper Mississippi Valley and Tennessee to the lakes and northern portions of the Mid- le and Eastern States, followed by occasional snow over the lakes and Minnesota, nd by brisk and high westerly winds from the Missouri Valley eastward over the Mid- le and Eastern States, increasing to gales over the lakes.

March 8, 9, and 10.—From Southern Dakota, a little south of east over Iowa, Illinois and Indiana, as a diminished pressure, accompanied by fresh and brisk winds; but thence east over Ohio, Pennsylvania, and beyond Cape Cod increasing in severity with brisk and high winds and generally light rain or snow from Tennessee and South Carolina to Ohio, and thence to Maine.

March 10 and 11.—From Dakota over Minnesota and Lake Superior into Canada, continuing north of the Saint Lawrence Valley; preceded by brisk and high easterly to southerly winds, and followed by brisk and high westerly to northerly winds, accompanied by areas of light rain or snow from Missouri to Minnesota and Lake Superior and Huron, but thence eastward over the Middle and Eastern States heavy in general and at places heavy.

March 14, 15, and 16.—Eastward from Nebraska and Southern Dakota over the Lake region and apparently the eastern British provinces, accompanied by rain from Southern Louisiana to New England and north of this line to the lakes and northwest; preceded by brisk to high easterly and southerly winds, and followed by brisk and high northerly to westerly, increasing at places to gales.

March 17 and 18.—Eastward over Wisconsin, the lakes, New York and New England, accompanied by brisk winds and rain, generally light, from Tennessee and Virginia, northwest, north, and northeastward.

March 18, 19, 20, and 21.—Eastward over Dakotah to lower Michigan, apparently as a diminished pressure, but then developing into two; one passing over Virginia and thence northeastward along the coast; the other north of the lower lakes and over northern portion of New England, accompanied by rain and snow over the entire country east of the Rocky Mountains, also by brisk and high winds, the easterly having probably been the most severe, increasing to gales.

March 22 and 23.—From Dakota over the upper lakes into Canada, and thence over Northern Maine, accompanied by occasionally light snow and brisk winds which at places increased to northeast gales.

March 23, 24, 25, 26, and 27.—Northeastward over the Ohio Valley, and developing into two; one over the lower lakes, down the Saint Lawrence Valley, the other over the middle and east Atlantic coasts and New Brunswick, accompanied by heavy rain over the entire country east of the Rocky Mountains, except that from Northern New England westward over the lakes to the northwest it was snow, and by brisk and high winds, which at places increased to gales, the north and west having been most severe except at Quebec, where a very severe northeast gale prevailed on the afternoon of the 26th; this storm was followed by a severe "norther" in Texas on the 25th.

March 28, 29, and 30.—From Southern Dakota eastward over the lakes, New York and New England, accompanied by areas of light rain or snow over the northwest and upper lakes, but by rain, generally very heavy, from the Lower Mississippi and Ohio Valleys and lower lakes to the Atlantic coast, also by brisk and high winds; in its passage over the Middle and Eastern States it increased in severity, and the winds to southerly gales on the coast, shifting later to northwest; it has undoubtedly been the most severe storm of the month, and the barometric depression most remarkable, the lowest reading having been 28.80 inches at Burlington, Vt., 11 p. m. on the 29th.

March 30 and 31.—Over the northwest lakes and New England, accompanied by generally very light rain or snow from the northwest eastward over the lake region, Ohio Valley, and Middle and New England States, and by brisk winds, increasing occasionally to high.

RAIN-FALL.

As compared with the means of a number of years for the month, the rain-fall returns from the signal-service stations show a general deficiency at the stations east of the Rocky Mountains and at San Francisco, from 0.05 to 4.00 inches, except over the southern portion of New England, northern and western portions of the Middle States, Southeastern Louisiana, Jacksonville, Florida, and Eastern Tennessee and Kansas, where the excess varies from 0.10 to 4.86 inches.

TEMPERATURE.

The mean temperature for the month, as taken from the signal-service reports at stations east of the Rocky Mountains is higher, from 1° to 10°, than the same for last year, except for Jacksonville and Key West, Fla., which is slightly lower, at latter 5'. By comparing same of this year with that for a number of years at the same stations or at others close by, it is observed that the former is from 1° to 5° lower in the Southern, Middle, and New England States, Ohio and southern portions of Michigan, Illinois, and Missouri, but northwest of this region to Minnesota, Iowa, and Nebraska, it varies from 4° above to 5° below. During the month the weather has therefore been generally colder than usual, but warmer than March of last year, except in Utah, where it has been somewhat colder this than last, and at San Francisco, where there has apparently not been any change.

MONTHLY WEATHER-REVIEW, APRIL, 1873.

STORMS.

uring this month seven storms have been felt over a portion, or nearly the whole, he country east of the Rocky Mountains. The paths of their centers have, approxi-ely, been traced upon the War Department weather-maps, Signal Service, United es Army.

he center of that of April 1 and 2 passed over Missouri, Illinois, and Michigan into ada, sending out a minor disturbance over the middle Atlantic coast, accompanied risk to high winds and heavy rain in all the States east of the Rocky Mountains, pt that it was partly snow and sleet over northern New England, the lake region, the northwest; it was felt as a very severe storm from northern Texas to the s and northwest.

pril 3, 4, 5, 6, and 7.—Over Nebraska, Iowa, Missouri, Illinois, and lower Michigan Canada, accompanied by brisk and occasionally high winds, and sending out several or disturbances to the eastward; also by rain-areas, generally light, from the Mis-i and Ohio Valleys and east and middle Atlantic coasts to the lakes and Saint rence Valley, except over the lake region, where it was partly snow.

pril 7, 8, 9, and 10.—Over Texas, Arkansas, Illinois, and Lake Michigan into Canada, ling out a branch over the Ohio Valley, middle Atlantic coast and to the south of England, both accompanied by brisk and high winds; also by rain, generally ry. from Texas to Minnesota and eastward to the Atlantic coast, except that it was tly snow over the upper lakes and northwest; it was followed by a severe "norther" Texas on the 8th.

pril 10, 11, 12, and 13.—Over the northwest, and developed into two; one passing r the lower lakes into Canada, accompanied by brisk and occasionally high winds by rain or snow from Missouri and Kentucky to the lakes; the other over the Ohio ley and Middle Atlantic coast, and thence slowly northeastward, preceded by severe theasterly gales, rains, sleet, and snow from Chesapeake Bay to Nova Scotia, New nswick, and the lower Saint Lawrence Valley.

pril 13, 14, 15, 16, 17, 18, and 19.—Eastward over Wyoming, Nebraska, and Kansas Iowa and Missouri; then diminishing in intensity and breaking up into, and ding out to the eastward over the lower lakes, several minor disturbances, and ther to the middle Atlantic coast, moving thence very slowly on the 17th, 18th, and h, along the New England coast to Nova Scotia and New Brunswick as quite a severe rm; it was accompanied by rain, generally heavy, over the entire country east of Rocky Mountains, except that it was partly snow over northern New England, the e region and the northwest; on the 12th, 13th, 14th, and 15th it was felt as a very ere storm of rain, sleet, and snow in Wyoming, Dakota, Nebraska, and Minnesota, on afternoon and night of the 14th and morning of the 15th as a very severe "norther" Texas; east of the Mississippi numerous minor disturbances were left, producing light n or snow.

pril 21, 22, and 23.—Southeastward over Dakota, the Lower Missouri and Lower io Valleys, and beyond the Carolinas, attended by fresh to very brisk winds, and by as of generally light rain or snow from Missouri, Tennessee, and North Carolina to nnesota, the lakes, and Massachusetts, and followed by a severe "norther" in Indian rritory on the 22d, and in Texas on the 23d and 24th.

pril 27, 28, and 29.—Over Indian Territory to Kentucky, then apparently develop-; into and disappearing to the eastward as several minor disturbances, accom-nied by fresh and brisk winds and rain from the interior of the Gulf States to the tes and Massachusetts, which was generally heavy over the interior and along the lantic coast.

RAIN-FALL.

The returns for the month from the signal-service stations show that there has been excess of rain and snow over southern New England, the lower lake region, from diana and Southern Michigan to Kansas, Iowa, and Southern Minnesota, and over ntral Alabama and Southeastern Georgia, varying from 0.65 inch to 3.06 inches, being eatest in Illinois and Missouri. Elsewhere east of the Rocky Mountains there has en a deficiency of from 0.07 inch to 3.87 inches, being most marked in the western ulf States.

TEMPERATURE.

During the month the weather has been generally colder than usual east of the cky Mountains, and colder than April of last year at the Rocky Mountain stations d eastward. The mean temperature for the month, taken from the signal-service ports, and compared with that for a number of years at the same stations, or others ose by, is lower from Kansas and Missouri to Minnesota, 3° to 8°; in the Middle tates and lake region, 0°.5 to 5°.7; in New England and from Kentucky to the Gulf, .5 to 3°; while in the South Atlantic States it varies a little above and below.

The same compared with that of last year is lower at the Rocky Mountain stations, ' to 6°; thence eastward, 0°.5 to 8°; the difference being greatest over the Northwest nd the Middle States.

MONTHLY WEATHER-REVIEW, MAY, 1873.

STORMS.

During this month ten storms have traversed the country east of the Rocky Mountains.

I. *May* 1, 2, and 3—Apparently originating on the last day of April in the Rocky Mountains, the center of this storm progressed eastward over Kansas, Missouri, Southern Indiana, Southern Michigan, and Lake Erie, moving thence southeastward over Pennsylvania and Maryland to the Atlantic, sending out a branch on the 3d over Virginia, Chesapeake Bay, and thence off the coast. Its passage was attended by heavy rains and brisk and high winds from the Mississippi to the Atlantic, sleet and snow falling in New England.

II. *May* 4 to 8—Appearing first in Southern Texas, this storm moved slowly northeastward over Arkansas, Missouri, Illinois, Southern Michigan, and Lake Huron. The highest winds during its passage were experienced on the coast of Texas, the lower lakes, and the middle Atlantic coast.

III. *May* 8 and 9—Developed among the mountains of North Carolina and moved northeastward along the middle Atlantic coast, accompanied by heavy rains and brisk winds.

IV. *May* 8, 9, and 10—Appeared first in Kansas, and moved eastward over Missouri and thence rapidly northeastward over Illinois, Indiana, Michigan, and southern Lake Huron into Canada. Heavy rains fell in Northern Illinois and Eastern Iowa and a belt of lighter rains and brisk winds, from four hundred miles to eight hundred miles in width, attended its progress.

V. *May* 10, 11, and 12.—Like III, this storm seemed to develop among the mountains of North Carolina, passing northeastward over Virginia, eastward over Chesapeake Bay, and again northeastward along the coast to New Brunswick.

VI. *May* 12 and 13.—Traveled from Minnesota very rapidly eastward over the Saint Lawrence Valley and northern New England to Nova Scotia, causing light rain and high winds throughout its course.

VII. *May* 13, 14, and 15.—From the plains of Kansas and Indian Territory this storm-center moved eastward over Southern Missouri, southeastward into Alabama, and thence again eastward off the coast, rapidly diminishing in intensity after crossing the Mississippi. Considerable rain fell in all the Southern States, except Texas, but no dangerous winds were reported.

VII. *May* 18, 19, and 20.—Developing in the southwestern plains, this depression traveled rather slowly northeastward from the Indian Territory over Lakes Michigan and Huron into Canada, attended by rain-belts and fresh to brisk winds throughout the lake region and western and northwestern sections of the country.

IX. *May* 21 to 24.—From Montana this disturbance moved slowly eastward over Dakota, crossing, with somewhat increased velocity, Minnesota, the upper lakes, the Saint Lawrence Valley, Maine, and Nova Scotia, causing, by its slow progress, several days of cloudy and rainy weather over the entire northern portion of the country. It was during its passage over the Northwest that the terrible and destructive storm swept through Iowa.

X. Two depressions, one slowly descending from the Upper Missouri Valley, the other moving northward over Kansas and Nebraska, seemed to unite in Southern Dakota to form this storm-center. From Dakota it moved southeastward into Iowa, northeastward to Lake Superior, and thence nearly due east over the Saint Lawrence Valley, Maine, and New Brunswick. Its rain-belts reached nearly the whole country east of the Mississippi, and brisk winds, increasing occasionally to high, were experienced throughout the northern sections.

TEMPERATURE.

The temperatures for the last month were generally lower than for May, 1872, the chief exceptions being Key West, Oswego, and Grand Haven. As compared with the mean May temperatures of a series of years, the thermometric figures for May 1873 show excess of warmth over northern Lake Michigan, Northern Michigan, Lake Huron, Southern Ohio, Kentucky, Tennessee, and Eastern Massachusetts, but a deficiency of temperature in Kansas, Missouri, Iowa, Minnesota, Wisconsin, Indiana, Illinois, the Gulf States, Florida, and Southeastern Georgia, and generally throughout the Atlantic States and the lower lake region. The regions of minimum rain-fall and thermometric maxima nearly correspond.

RAIN-FALL.

As compared with the mean May rain-falls, the rain-fall returns of last May show deficiencies in the northern and western parts of Lake Superior, Lake Michigan, and in the entire country stretching from the Saint Lawrence Valley to Maine, and thence over the lower lakes, Western New York, and Western Pennsylvania, West Virginia

io, Central Indiana, and Southeastern Illinois. Excess of rain occurred in Iowa, Mis-ri, Eastern Kansas, East Tennessee, and also along the Atlantic seaboard, except r Portland, Me., and Savannah, Ga., and a very great excess, from 2.00 to 14.58 hes, over the Gulf States.

RIVERS.

he river reports for the month show a slight decline in the Red and Missouri Rivers m the beginning to the middle of the month, after which a decided rise occurs until end. The Arkansas rose slowly at Little Rock until the 23d, after which it subsided wly. The Mississippi has alternately risen and fallen; at Saint Paul the water was et lower on the 19th than on the 31st, at which dates, respectively, it was lowest highest; at Saint Louis the lowest and highest extremes occurred, respectively, the 3d and 31st, the difference being 6 feet and 3 inches. At Cairo the river lowest on the 28th and highest on the 16th, the extremes being about 13 feet. Memphis the difference between the highest and lowest water for the month has n about 9 feet, having been highest on the 22d and lowest on the 28th. A very id rise occurred on the Cumberland at Nashville from the 1st to the 4th, after which water gradually subsided until the 21st, rising again until the 27th, and then again ing until the 31st.

he Ohio was affected by a great swell which traveled from Pittsburgh on the 4th Evansville on the 14th; since then it has fallen almost uninterruptedly. The differ-e between the highest and lowest water has been 15 feet at Pittsburgh, 19 feet at rietta, 23 at Cincinnati, 7½ at Louisville, and 16½ at Evansville.

he indications are that the Missouri and its tributaries will continue to rise.

MONTHLY WEATHER-REVIEW, JUNE, 1873.

STORMS.

During this month ten disturbances have crossed portions of the country east of the cky Mountains.

The center of that of June 1 and 2 moved over Eastern Florida into Southern rgia and disappeared, producing heavy rains and brisk winds.

June 3 and 4.—From Dakota over Iowa, Lake Michigan, lower lakes, New York, and w England, accompanied by fresh and brisk winds over the Northwest, lakes, and antic States, and by rain, at places heavy, east of the Rocky Mountains, except on Gulf coast.

June 7, 8, 9, 10, and 11.—From Dakota over Minnesota, the lake region, and northern w England; with rain, generally heavy, fresh and brisk winds, and occasionally ere thunder-storms, over the northern portion of the country.

June 12, 13, 14, and 15.—One southeastward over Minnesota to Lake Erie, and thence theast into Canada, causing thunder-storms, with rain-areas, generally light, and sh and occasionally brisk winds from the Ohio Valley to the lakes; a second, appa-ntly developing in the Southern States, thence eastward to the coast and northeast-rd over probably Nova Scotia, with fresh and brisk winds and rain-areas on the coast.

June 14, 15, 16, and 17.—Over Dakota, Lake Superior, and thence probably over Maine, ducing areas of light rain and fresh and brisk winds over the northern portion of Middle States and the lake region.

June 18, 19, and 20.—Over Northern Minnesota, Lake Superior, and thence over Maine d Nova Scotia, attended by occasional rain-areas and brisk and high winds over Northwest, lake region, and New England.

June 21, 22, 23, and 24.—From Dakota over Southern Minnesota to Iowa, then break-g up into and sending out to the eastward several minor disturbances, producing ere thunder-storms of short duration from Missouri and the Ohio Valley northward.

June 25, 26, 27, and 28.—Eastward over Northern Dakota, Minnesota, Lake Superior, d northern New England, sending a branch over Iowa, with severe thunder-storms n Tennessee to the Northwest, lakes, and New England.

June 28, 29, and 30.—Over Minnesota and the upper lakes into Canada, accompanied severe thunder-storms north and west of the Ohio Valley, brisk winds over the rthwest, lake region, and Atlantic States, and rain, often quite heavy, from the wer Mississippi, Northwest and lakes to the Atlantic coast.

TEMPERATURE.

The mean temperature for June, 1873, is higher than the mean for the month, except r the vicinity of Lake Superior, where it is lower by 0°.7 to 1°.8; in the South lantic States it varies from 1°.6 below to 1°.0 above, and from New Jersey and East-n Pennsylvania to Maine, 1°.2 below to 1°.1 above. The excess is greatest in North-stern Virginia, 4°.5; Northern New York, 1°.1 to 4°.7; Kentucky, Ohio, Indiana, and uthern Michigan, 1°.7 to 6°.5; Southern Alabama, 4°.9; Illinois, Southern Wisconsin,

and Eastern Iowa and Missouri, 0°.5 to 2°.1; Eastern Kansas, 4°.2; Southern and Western Minnesota, 4°.8 to 6°.7; Fort Sully, Dakota, 8°.0, (?) and Cheyenne, 4°.4.

The mean for June, 1873, is lower than that for June, 1872, at San Francisco, 1 [illegible] the Gulf States, 0°.4 to 1°.6; in the South Atlantic States, 0°.3 to 2°.9; in the region of Lake Superior, 0°.4 to 1°.6. It varies in the Middle, Atlantic, and New England States from 1°.1 above to 3°.9 below. The former is the higher in Iowa and Southern and Western Minnesota, 4°.5 to 5°.5; in the Ohio Valley, 1°.0 to 4°.7; over the lake region, 1°.1 to 2°.7.

Mean Temperature.

Signal-service stations.	1871.			1872.			1873.		
	April.	May.	June.	April.	May.	June.	April.	May.	June.
	°	°	°	°	°	°	°	°	°
Washington	57.6	64.0	73.2	56.2	67.8	76.0	53.3	63.6	[illegible]
New York	54.2	58.6	69.0	49.7	61.9	72.8	46.3	57.6	[illegible]
Boston	46.7	57.4	66.2	46.3	57.2	67.6	44.6	56.[illegible]	[illegible]
Chicago	51.2	56.7	66.8	47.9	56.1	69.5	42.3	53.9	[illegible]
Saint Louis	60.3	69.1	79.0	57.5	67.4	76.9	51.2	65.1	[illegible]
New Orleans	70.8	76.0	82.5	70.4	75.8	80.5	66.9	73.7	[illegible]

RAIN-FALL.

The returns for the month from the signal-service stations show that there has been an excess of rain over the mean from Florida to Western Tennessee, and westward to Arkansas and Eastern Texas, varying from 6.50 inches to 0.86 inch, from Eastern North Carolina to Southern Virginia 1.29 inches to 0.60 inch, from Central Indiana to Southeastern Missouri 1.42 inches to 0.68 inch, over Northeastern Ohio 1.23 inches, and from Eastern Nebraska northeastward to Eastern Minnesota and Northern Wisconsin and over Northern Michigan 4.34 inches to 0.45 inch.

There has been a deficiency in New England varying from 1.79 to 4.00 inches, the Middle States, except Southern Virginia, 0.44 to 3.26 inches, from northern portion of Georgia and South Carolina to the Ohio Valley 0.35 to 2.03 inches, from Northeastern Kansas to Southern Wisconsin and Northern Illinois 1.67 to 3.90 inches, over Northwestern Ohio and Southeastern Michigan 0.29 to 1.23 inches, and over Western Minnesota 0.98 inch.

RIVERS.

The Red River rose steadily at Shreveport during the first week, after which it remained nearly stationary until the 28th, when it began to fall slowly.

The Arkansas fell and rose alternately during the first twenty days, then fell steadily, having been eight and a half feet lower on the 30th than on the 1st.

The Missouri at Fort Benton rose steadily until the 19th. Throughout the upper portion of the river an almost continuous rise occurred, although a slight fall was observed between Kansas City and Brunswick after the 26th.

The Mississippi fell slowly at Saint Paul and between Cairo and New Orleans, (showing some slight oscillations,) the difference between highest and lowest water for the month being at Saint Paul nearly five feet, between Cairo and Vicksburgh nearly [illegible] feet, and at New Orleans eleven inches; between Le Claire and Warsaw a gradual fall occurred from the 4th until the middle of the month, after which a steady fall was observed; at Saint Louis the water rose slightly between the 3d and 11th, falling slowly after that date.

The Cumberland at Nashville fell from the 1st to the 9th, then rose until the 15th, fell again until the 27th, rose until the 29th, but on the 30th it began again to fall, the difference between highest water (19th) and lowest water (9th) being six feet.

The Ohio, at Marietta and above, as well as its tributaries, has changed comparatively little; from Cincinnati to Evansville it has fallen almost continuously, the difference between highest and lowest water being nearly nine feet at Cincinnati and Evansville and three at Louisville; at Paducah the water fell from the 1st to the 11th, rose until the 21st, falling again from that date until the 30th.

MONTHLY WEATHER-REVIEW, JULY, 1873.

STORMS.

During the month of July, 1873, thirteen areas of low barometer have been reported on the daily weather-maps of the Signal Office; they have in general passed eastward over the extreme northern limit of the United States. This feature has indeed been

rear rather more noticeable than in former years, as is seen from the following ment:

1871. The mean latitude of the tracks of 15 centers of low barometer was 45°.
1872. The mean latitude of the tracks of 14 centers of low barometer was 44°.
1873. The mean latitude of the tracks of 13 centers of low barometer was 47°.

in former years during this month, so in the present year, with scarcely an excep- the areas of low pressure first became apparent in or beyond Dakota and Mani-

On most occasions the appearance of a low barometer in the Northwest has preceded by slight barometric depressions on the coasts of Oregon and California, t has been impossible to decide whether the disturbances have passed from the ic Ocean eastward or have originated in the Rocky Mountains of British America. e numerous local storms that are experienced during the summer months have a in relation to the large areas of high and low barometer, to the topography of the try, the position of the ocean and other bodies of water, &c. The local storms ch are almost invariably attended with lightning, &c.) have been most numerous orida, on the west and southwest side of the area of high barometer that prevails g July on the Atlantic between the latitudes of 12° and 30° north. The region xt greatest frequency is in Ohio and Western Pennsylvania, where the south and west winds attending the areas of low pressure rise up over the high country of States. The storm-frequency diminishes as we proceed from the Gulf coast ward over the low, flat country, and northwestward toward the high arid plains; other hand, it increases as we proceed from the middle and east Atlantic coasts ward up a rapid slope to the summit of the Appalachian range. The local storms east frequent on the dry plains west of the valley of the Mississippi River, and are indications of a region of diminished frequency in the northern part of the ince of Ontario, though this may possibly be due to the scarcity of our stations at region.

WINDS.

winds of special severity have been reported during this month, except the tor- of July 3, at Indianapolis. The winds have reached the limit of *high* (a velocity irty miles an hour) only twice in the Middle Atlantic States, and thrice in Dakota Northern Minnesota. In general it may be stated that south and southeast winds prevailed in the Gulf States, Iowa, and Minnesota, but elsewhere over the country of the Rocky Mountains the prevailing winds have been from the south, southwest, west.

RAIN-FALL.

e total amount of rain during the month appears to have been in excess in Indi- Illinois, and Michigan, and on the southern border of Lakes Superior, Erie, and ario, as also in New England. The reports from the summit of Mount Washington a rain-fall of 13.5 inches, as contrasted with only 3.5 inches in July, 1872. On the r hand, the rain-fall of June was 3.5 inches, while in June, 1872, 18.5 inches were rted. By combining the two, we obtain for June and July together, in 1872, 22 es, and in 1873, 17 inches. A deficiency of rain is apparent in the province of ario, on the Middle Atlantic coast, over the Lower Mississippi valley, and in the thwest. The details of the rain-fall are given for each geographical subdivision in accompanying table.

Table showing the Rain-fall and Temperature for July, 1873.

District.	Average rain-fall.	Average temperature.
	Inches.	*Degrees.*
w England	3.5 or an excess	70 or an excess.
ddle Atlantic States	3.5 or a deficiency	77 or an excess.
wer lake region	5.0 or an excess	71 or normal.
per lake region	4.5 or an excess	66 or normal.
ith Atlantic States	5.5 or normal	81 or a deficiency.
tern Gulf States	5.0 or normal	82 or an excess.
stern Gulf States	5.0 or normal	82 or a deficiency.
io Valley	4.5 or a deficiency	77 or an excess.
wer Mississippi Valley	2.0 or a deficiency	80 or normal.
per Mississippi Valley	4.0 or a deficiency	75 or a deficiency.
wer Missouri Valley	2.0 or a deficiency	75 or an excess.
e Northwest	3.0 or a deficiency	75 or normal.

TEMPERATURE.

The temperature has very generally averaged one or two degrees lower than the corresponding month of 1872, which latter was indeed in many places one of the warmest on record. Compared with the average of many years, the past month would have been from one to four degrees warmer than the normal temperature over the Middle Atlantic and the Eastern Gulf States. In general, however, over the region the country east of the Rocky Mountains the temperature has been slightly below the average, the deficiency amounting to one or two degrees in the valley of the Mississippi River.

The accompanying table shows for each geographical subdivision the general mean temperature, as observed and as compared with normal values resulting from many years of observation.

The monthly range of temperature, or the difference between the highest and lowest temperatures that have occurred during the month, is given by the lines of the monthly range on map No. 4. It will be seen that the range is greatest in the dry localities, and least in low and damp regions. The range also increases decidedly with the latitude, even on the Atlantic coast; a phenomenon doubtless due to the greater changes in cloudiness and humidity.

RIVER-OBSERVATIONS.

The Red River fell steadily during the entire month. The Missouri fell continuously, except at Leavenworth, where it rose during the first week of the month. The Upper Mississippi declined somewhat; the middle portion of the river was at first stationary or slightly rising, and then began to fall steadily; the lower portion of the river, after falling and rising, has again begun to fall. The Cumberland has experienced three sudden rises and subsequent falls, attending three periods of rain. Similar oscillations have occurred in the Ohio, a specially large wave having moved from Pittsburgh to Louisville between the 6th and the 10th of the month.

MONTHLY WEATHER-REVIEW, AUGUST, 1873.

STORMS.

The areas of low barometer were accompanied with slight disturbance while in the western portion of the United States, but no marked change in the weather occurred until the 11th of the month, when the area of low barometer was first observed in Kansas.

This storm moved slowly to the eastward, with cloudy weather, rain, and light fresh winds, the winds increasing in force as the center approached the Atlantic coast, and finally producing the northeasterly gale which occurred on the Middle Atlantic and New England coast on the 14th and 15th.

The second storm was by far the most severe one that has occurred since the establishment of the signal-service. Although this storm did not occur within the limits of our stations, there were indications of some atmospheric disturbance off the Middle Atlantic coast on the 23d, which warranted the prediction made in the Probabilities given from the afternoon report of that date, viz, "For the New England and Middle Atlantic coast, threatening weather," and from the midnight report of the same date, "For the New England and Middle Atlantic coast, stormy weather."

This storm, in consequence of its severity, is one of unusual interest, and the degree marked for it may vary from the actual, which cannot be determined until additional data have been obtained, when a complete and accurate description will be published by this office.

The third decided storm of the month was first observed as an area of low barometer in the western portion of Kansas on the 29th at 11 p. m. This area moved to the northward over the lake region without any marked disturbance until the night of the 31st, when brisk and high winds, with areas of rain, were reported. On the morning of the 1st of September it had become unusually well defined in the lower lake region, from which it passed over northern New England and off the Atlantic coast with increased force, finally producing a violent storm since reported from vessels which were in the North Atlantic on the 2d and 3d of September.

WINDS.

Apart from the storms above referred to, no winds of special severity have been reported, except from Dubuque, Iowa. At this station a violent tornado occurred on the 7th, which, although entirely local in its nature, developed an unusual force in

ed great destruction of property. Owing to the carrying away and destruction of anemometer at this station no recorded velocity of this wind has been obtained. e unusual velocity of one hundred miles per hour was reported from Mount Washon, N. H., during the storm of the 16th. The force developed by this wind has not n equaled at any other station since the establishment of the signal-service. e direction of the prevailing winds of the several stations is indicated, and in paring these directions with the isobarometric lines, it will be observed that they ne toward the area of mean low barometer.

RAIN-FALL.

the Middle Atlantic States and in Minnesota there has been a decided excess over mean rain-fall as calculated from observations of previous years; while there has about the usual amount in the South Atlantic and Eastern Gulf States; in the ining districts there has been a deficiency. In the table referred to the quantity in given has been deduced by taking the general average of the reported rain-fall the several stations in each district.

TEMPERATURE.

Table showing the Rain-fall and Temperature for August, 1873.

District.	Average rain-fall.	Average temperature.
	Inches.	*Degrees.*
t Lawrence Valley	1.5 or a deficiency	
England	4.0 or a deficiency	67 or a deficiency.
lle Atlantic	8.0 or an excess	70 or a deficiency.
h Atlantic	6.0 or a deficiency	79 or a normal.
ern Gulf	6.5 or a normal	80 or a deficiency.
tern Gulf	1.5 or a deficiency	82.5 or a normal.
er Lakes	2.0 or a deficiency	68.5 or a deficiency.
er Lakes	1.5 or a deficiency	67 or an excess.
Valley and Tennessee	3.0 or a deficiency	75.5 or a normal.
er Mississippi	1.0 or a deficiency	75 or an excess.
er Missouri	1.0 or a deficiency	77 or an excess.
nesota	4.0 or an excess	67 or an excess.

New England, the Middle States and thence westward over the lower lake region adjoining States, the mean temperature has been from two to five degrees below normal, and about three degrees above the normal in the upper lake region, the er Mississippi and Lower Missouri Valleys, but in the districts last named the temture has been lower than reported for August, 1872. The results of the observa for the month are given in the accompanying table, in which is noted the comon of the temperature of the several districts, with the mean temperature deduced observations of previous years. The isothermal lines for the month indicate general distribution of temperature throughout the United States.

RIVER-OBSERVATIONS.

general these observations show that the rivers draining the eastern slope of the ky Mountains were steadily falling during the entire month; and that those drainthe western slope of the Appalachian range experienced fluctuations attending rains of these districts.

MONTHLY WEATHER-REVIEW, SEPTEMBER, 1873.

STORMS.

uring this month eleven low barometers have crossed the country east of the Rocky ntains. The paths of their centers have passed over the lake region in a northward or eastward course, excepting the two on the South Atlantic coast. eral of them were remarkably severe over the upper lakes, and destructive to ship-

hat of August 30, 31, and September 1, was accompanied by occasional rain and k winds over the Northwest, Ohio Valley, lake region, Middle States, and New

England, the winds increasing to high from Michigan eastward over the lower lake and Saint Lawrence Valley.

September 2, 3, 4, and 5, by brisk and occasionally high winds and rain from the Northwest eastward over the lake region, Ohio Valley, Middle States and New England. A hurricane was reported as having lasted about one hour on Lake Michigan; tornadoes in Massachusetts on the 4th; very severe thunder-storms with high winds in Eastern Tennessee on the 3d, and Southeastern North Carolina on the 5th.

September 11, 12, and 13, by rain at nearly all of the stations east of the Rocky Mountains; brisk and high winds over the Northwest and upper lakes; severe "northers" in Texas on the 13th; heavy snow on Mount Washington on the night of the 12th.

September 14, 15, and 16, by high south and west winds over the Northwest and upper lakes; occasional rain over Minnesota, the lake region, and New England.

September 17, 18, and 19, by high winds over the Northwest, lakes, and Saint Lawrence Valley; by rain from the Northwest eastward over the lakes, Ohio, and Saint Lawrence Valleys, Middle States, and New England.

September 18, 19, and 20, by brisk and high winds and heavy rain from Florida to Southeastern Virginia, having been very severe on the coast.

September 22 and 23, by brisk winds and heavy rains on the South Atlantic coast.

September 23 and 24, by high winds over the Northwest and lakes; rains from the Missouri and Ohio Valleys to the lakes and Middle and East Atlantic coast. This was the severest storm of the month, especially on the upper lakes, whence very high gales were reported.

September 25 and 26, by high winds over the Northwest and upper lakes and occasional rain; light snow in Montana on the 26th; heavy gales on the upper lakes.

September 27, 28 and 29, by high winds on Lake Ontario and the lower Saint Lawrence Valley; rain in all sections east of the Rocky Mountains, except the east Gulf States; followed by a severe "norther" in Texas during the night of the 29th and morning of the 30th, and by light snow from Northern Minnesota and Dakota eastward.

On the 7th, 8th, and 9th, an area of high barometer extended itself eastward from the Northwest, lake region, Ohio Valley, Middle States, and New England, with falling temperature, and with light frost over the Northwest and upper lake region.

13, 14, and 15.—A second, over the same region with quite heavy frost, which was very severe on the morning of the 13th over Dakota, Minnesota, and the northern portion of the upper lake region.

16 and 17.—A third, over the Northwest, lakes, Middle States, and New England, with frosts over the northern portions of these sections.

September 19, 20, and 21.—A fourth, from the Northwest, over the lakes, Ohio Valley, Middle States, and New England, with frost, except probably on the immediate coast.

September 29 and 30.—A fifth, from the Northwest south and east over the eastern country, with low temperature, producing frost over the northern sections.

TEMPERATURE.

Average Mean Temperatures for September, 1873.

District.	Average.	Compared with the for the month
New England	59°.5	Normal.
Middle Atlantic States	67°.6	Slightly above.
South Atlantic States	76°.	Normal.
Eastern Gulf States	77°.5	Slightly above.
Western Gulf States	78°.5	Slightly above.
Lower lake region	61°.5	Slightly above.
Upper lake region	55°.7	Below.
Ohio Valley and Tennessee	68°.4	Normal.
Upper Mississippi Valley	50°.7	Below.
Lower Missouri Valley	63°.2	Below.
Minnesota	51°.3	Below.

For New England, the South Atlantic States, the Ohio Valley, and Tennessee it is the same as that for many years. For the Middle Atlantic and Gulf States, the lower lake region, the former is the greater, from 0°.4 to 0°.6. For the upper lake region, Minnesota, and Upper Mississippi and Lower Missouri Valleys it is less, from 1°.2 to 2°.5. Compared with the average for the same month of last

e former is the lower for the stations in all of the districts, except the South At-ıtic States, Tennessee, and the Ohio Valley, where it varies slightly above and low the latter.

RIVERS.

The observations show that the Missouri, Red, Mississippi, and Ohio Rivers fell quite adily during the month, excepting slight oscillations in the head-waters of the two ter produced by rains. The Cumberland fluctuated more or less, having been lower tober 1 than September 1.

MONTHLY WEATHER REVIEW, OCTOBER, 1873.

STORMS.

During this month fourteen well-defined areas of low barometer have been indicated the tri-daily weather-maps of the Signal Service, some of which have, however, ved over the extreme limits of the territory covered by our stations. Besides these, re have been several indefinite barometric depressions, accompanied by rain and ud. In detail the storms have been as follows:

No. I. *October* 3, 4, 5, 6, 7, and 8.—This was a severe cyclone that was first recognized existing some distance southwest of Cuba; it passed over Florida on the 6th, and ntinued its course northeastward parallel to the Atlantic sea-board. Numerous dis-ers were caused by it at sea, and the settlement of Punta Rassa, Florida, was entirely stroyed, a hurricane velocity of ninety miles having been recorded at that place. It ıck Lake City very suddenly October 6, at 6.10 p. m. Reports of damages have en received from Jacksonville, Saint Augustine, and Charleston. The wind was not rerely felt at Savannah. Destructive gales were also felt off Cape Henry. A severe rther was induced by the extensive area of low pressure, and was felt along the tire coast of Texas and Louisiana, as far as Mobile. This cyclone appears to have ved over the Shetland Islands on the 10th and 11th.

No. II. *October* 3, 4, and 5.—Produced a very general rain in the lake region.

No. II.* *October* 4 and 5.—This kept to the north of the lake region, and on the 5th parently united with No. II as the latter passed down the Saint Lawrence Valley. e barometer fell with unusual rapidity at Eastport, where the wind-velocity rose to irty-two miles on the 5th.

No. III. *October* 6 and 7.—This may be regarded as a disturbance subsidiary to Nos. II, and III. It arose in the Middle Atlantic States, and as it slowly moved north-stward was accompanied by heavy rains on the Atlantic coast. Violent lightning as reported at New Haven on the 6th, and a heavy blow, with rain, at Cape May.

No. IV. *October* 6 and 7.—This storm-center kept so far to the northward that it only oduced strong southwest winds and cloudy weather on Lake Superior.

No. V. *October* 5, 6, 7, 8, 9, 10, 11, and 12.—The rains and barometric depression pre-iling over the Californian coast on the 4th, 5th, and sixth of the month reappeared the 7th as an incipient storm-center in Utah, which, after extending northeast-rd over Dakota and Manitoba, turned to the east and southeast into Minnesota and e upper lake region; it then disappeared in Canada, but reappeared after inducing mall center of disturbance, No. V*, on the Lower Lakes, which latter moved east-rd over New England, joining No. V in Nova Scotia. Violent thunder-storms were ported at Indianapolis and La Crosse.

No. VI. *October* 12.—This was but a slight barometric depression moving northeast-rd across Minnesota. High winds prevailed at Yankton.

No. VII. *October* 14 and 15.—This disturbance appears first in Kansas, although there reason to suspect its existence two days earlier in Northern Arizona. In its passage ward Lake Superior it seems to have lost most of its intensity, a change due possibly the presence of the more extensive disturbance. No. VIII, far to the north and rtheastward.

No. VIII. *October* 16 and 17.—This barometric depression became first recognizable such in the valley of the Saginaw, having probably pursued its previous course far the northward. On the 16th it moved rapidly southeastward over Nova Scotia, and en turned to the east. Brisk winds prevailed over Massachusetts and the Bay of undy.

No. IX. *October* 16, 17, and 18.—This storm originated as a general rain on the morn-ıg of the 16th, extending from Northern Texas to Nebraska, and was probably pro-uced by the cooling of the mass of air that was then being forced from the Gulf of lexico and the Mississippi Valley northwestward up the slopes of the western plains. he consequent area of low pressure gradually closed in on all sides, losing its very xtended elliptical form, until on the afternoon of the 17th; its center appeared as a mall oval in Minnesota, attended by high winds and an extended area of rain. A evere gale was reported at Breckenridge on the 17th, and high winds at Saint Paul.

The storm-center moved northeastward, and the gale of the night of the 17th and 18th on Lakes Superior and Michigan was, according to the reports from Milwaukee, one of the severest on record, while Alpena reports a gale of forty-four miles per hour from the south. The barometer at Marquette fell to 28.59 inches. Brisk southwest winds and rain prevailed on the lower lakes on the 18th and 19th.

No. X. *October* 18, 19, 20, 21, and 22.—This began as a slight depression in the Western Gulf States and moving eastward, was followed by a severe norther on the Texas coast, while itself increasing in intensity; on reaching the Atlantic coast the depression turned its course to the northeast and developed into a severe storm in the Middle Atlantic States on the 19th and 20th. It then turned to the northwest and held this extraordinary course until the 21st at midnight, when it had reached the Straits of Mackinaw, being recorded as the severest storm since 1859 on Lakes Huron, Erie, and Ontario, and continuing for forty-eight hours at most places. Its severity is especially commented upon in reports from Cleveland, Oswego, and Buffalo, while the winds of the 20th at Portland, Me., and Saint John's, New Brunswick, were the severest of the month.

No. XI. *October* 20.—This depression was attended by a gale in Manitoba, but passed so far to the northward as not to seriously affect the upper lakes. Reports from Fort Benton, when they come to hand, will probably throw some light on its previous course.

No. XII. *October* 25, 26, and 27.—This storm may probably be traced in Northern Texas on the 24th, but came within the cognizance of our stations on the 25th, when it was apparently central in Indian Territory. At that time snow was falling throughout the northwest and extreme northwest, being very heavy, with high winds at Yankton. The barometric disturbance was of minor importance, until the 26th, when the snow and rain were increasing in amount; on the latter day the storm-center passed over the lower lakes, and heavy lightning was seen to the northwest of Pittsburgh in the evening. On the night of the 27th and 28th the storm was central in New Brunswick, while a southeasterly gale prevailed on the coast of Maine. This was reported as the heaviest storm of the season at Eastport, Portland, Me., Wood's Hole, and New Haven.

No. XIII. *October* 27, 28, and 29.—This low barometer was formed over the Upper Lakes, following closely in the wake of No. XII, and in some sense connected with it. The snow and fog that prevailed on the lakes, united with the high wind, made the night of the 28th and 29th one of the wildest description, and numerous disasters were reported from Milwaukee. A southeast gale of forty-four miles velocity prevailed at Alpena. The disturbance disappeared over New Brunswick.

No. XIV. *October* 28, 29, 30, and 31.—This storm, after passing slowly eastward, turned southeast to Lake Huron and the Lower Lakes, accompanied by snow and followed by brisk northwest winds. On the afternoon of the 31st a westerly gale prevailed at Buffalo.

TEMPERATURE.

Average Temperatures for October, 1873.

District.	Average temperature.	In comparison with the mean of many years.
New England	51.3	1°.3, above.
Middle States	55.1	—1°.1, slightly below.
South Atlantic States	63.5	—2°.3, below.
Eastern Gulf States	65.9	—0°.7, slightly below.
Western Gulf States	67.	—2°.3, below.
Lower Lake region	49.7	—1°.3, slightly below.
Upper Lake region	44.6	—2°.4, below.
Ohio Valley	53.8	0°.1, normal.
Upper Mississippi Valley	46.3	—5°.0, below.
Lower Mississippi Valley	61.6	—0°.8, slightly below.
Lower Missouri Valley	50.5	—0°.3, normal.
Minnesota	41.	—4°.5, below.

For the Middle States, the Eastern Gulf States, the Lower Lake region, the Lower Mississippi Valley, the Ohio Valley, and the Lower Missouri Valley, it will be seen that the temperature averages about the same as for many years past.

The average temperature for New England is about the normal value; while for the South Atlantic States, the Western Gulf States, the Upper Lake region, the Upper

ississippi Valley, and Minnesota, the temperature during the past month, especially he latter sections, is decidedly below the average of previous years.

Average Rain-fall for October, 1873.

District.	Amount. Inches.	In comparison with the average for October.
t Lawrence Valley	6.0	or an excess.
r England	6.0	or an excess.
ldle States	6.25	or an excess.
th Atlantic States	2.0	or a deficiency.
tern Gulf States	0.75	or a deficiency.
stern Gulf States	2.25	or a deficiency.
rer Lake region	5.5	or an excess.
per Lake region	2.5	or a normal.
o Valley	3.75	or a slight excess.
per Mississippi Valley	2.75	or a normal.
rer Mississippi Valley	2.5	or a normal.
rer Missouri Valley	1.5	or a slight deficiency.
nnesota	1.3	or a deficiency.

he table shows the excess or deficiency for the various geographical subdivisions. t will be seen that the region of heaviest rain was over the northern and eastern tions of the country, the quantity diminishing very regularly as we proceed thence ith and west. Droughts are reported from Denver, Lake City, and Savannah.

EARLY FROSTS.

The first frosts of the season were reported at the following stations:
October 1.—Lexington, slight; Wytheville, light; Oswego, light. 6. Toledo, heavy; troit, heavy; Saint Paul, severe; Leavenworth, heavy. 7. Saint Louis, heavy; cinnati, heavy; Lexington, heavy; Milwaukee, heavy; Detroit, heavy; Vicksrgh, light. 8. Charleston, heavy; Vicksburgh, light. 13. Wytheville, heavy. 19. lwaukee; Duluth, heavy. 20. Milwaukee, Lake City, Heavy; Vicksburgh, heavy. Baltimore, light; Jacksonville, light; La Crosse, heavy; Nashville, heavy. 24. uisville, heavy. 26. Buffalo, heavy. 29. Baltimore, heavy; Jacksonville, slight; lwaukee, light; Mobile, light; Knoxville, heavy; Nashville, heavy; Vicksburgh, avy. 30. Mobile, heavy. 31. Mobile, heavy; Nashville, heavy.

PART SECOND.

A HISTORY

OF THE

TRAVELS OF ASIATIC CHOLERA.

IN ASIA AND EUROPE:

By JOHN C. PETERS, M. D., of New York City.

IN NORTH AMERICA:

By ELY McCLELLAN, M. D.,

Assistant Surgeon, United States Army.

TABLE OF CONTENTS.

APTER I.—History of Epidemic Cholera up to A. D. 1817.
II.—Epidemic of 1817 in India, which reached China to the east in 1820, and Russia in the west in 1823.
III.—Epidemic of 1826 and 1827, in India, which reached Russia in 1829, and England in 1831.
IV.—Epidemic of 1832, 1833, and 1834, in North America.
V.—Epidemic of 1841 to 1850, Asia, Europe, and North America.
VI.—Epidemic of 1847 to 1854, Asia, Europe, and North America.
VII.—Epidemic of 1864 to 1867, Asia, Europe, and North America.
VIII.—Cholera in India.



Cholera direction.

CHAPTER I.

TORY OF EPIDEMIC CHOLERA UP TO A. D. 1817.

gree with Macpherson* that cholera is one of the most ancient
of which distinct descriptions exist, and that there are few
s respecting which such an uninterrupted chain of evidence has
eserved. The following summary of what is known of the his-
cholera from the earliest historic times to A. D. 1500 is derived
most part from his elaborate and scholarly researches, and from
f Drasche and Macnamara.

dic or spasmodic cholera was common enough in the days of
rates, (B. C. 460–370,) especially in the summer months; and he
ost of the symptoms, including suppression of urine and severe
of the limbs.

rveda of Suçruta, in Sanscrit, describes a fatal disease, called
ika, some of the striking symptoms of which were diarrhœa, vom-
lividity, retraction of the abdomen, hollowness of the eyes, and
voice.

A. D. 7, Celsus gave a clear account of very decided cholera.

tæus, of Cappadocia, A. D. 50, as quoted by Dr. Cragie,† describes,
the name of cholera, a most acute disease, in which the juices
whole frame were supposed to be carried by a retrograde motion
he œsophagus, stomach, and bowels; in which the vomited mat-
ere watery, ejected with great force, and the intestinal discharges,
h sometimes feculent, were fluid and mucous; and in which, as the
e proceeded, the muscles of the arms and legs were cramped, the
s becoming incurvated, the nails blue, the extremities cold, and the
body stiff and covered with sweat; in which urine was not secreted,
se the fluids were diverted into the intestines; the voice was lost, and
ulse became very small and frequent, as in syncope; and in which,
continued ineffectual efforts to vomit, and calls to stool without
arging anything, death took place by convulsion, suffocation, and
ing.

len, about A. D. 131, gives a description of a disease which presents
y great similarity to Indian cholera. ‡

elius Aurelianus, about A. D. 151, described serous cholera, noticed
kness of the countenance, sharpening of the features, discharge of
watery fluid, and used the very phrase, "consecutive fever," now so
h employed. At that early date Heraclitus used opium and hen-
e for it. Aurelianus gave directions how to prevent relapses, and was
te aware of the gravity and antiquity of the disease, for he says the
ients knew that it was very acute and swift, being but rarely pro-
cted to the second day.

Oribasius, of Pergamos, A. D. 230, speaks,§ if not connectedly, still
y accurately, of cholera.

Annals of Cholera from the Earliest Periods to the year 1817, by John Macpherson, D., London, 1872.

Remarks on the History and Etiology of Cholera, by David Cragie, M. D., Edinburgh ical and Surgical Journal, April, 1833.

Die epidemische Cholera, Anton Drasche, M. D., Vienna, 1860.

Drasche, *op. cit.*

Aëtius, about A. D. 360, puts the theory of the evacuation of morbid matter (in modern phrase, the eliminating treatment of the disease) in a strong point of view.

Alexander, of Tralles, about A. D. 460, stated that the evacuations were often serous and not at all bilious, and insisted on the importance of seeing the patient early in the attack.

Paulus Ægineta, about A. D. 700, gives a full account of the disease.

Serapion, about A. D. 890, mentions all the essential features of the disease.* He describes the nausea, the watery discharges, the shrunken body and features, the coldness, the cold sweat, the cramps, and the speedy death.

Rhazes, of Bagdad, A. D. 900, described the diarrhœa, failure of pulse, oppression of breathing, sharpening of features, discoloration of the skin like that of the dead, coldness of the limbs, cold perspiration, spasms in hands, feet, and legs, urgent thirst, with vomiting of all that was drunk, and the collapse.

Avicenna, a century afterwards, made remarks on the greater prevalence of the disease during the Ramazan, a fasting period of the Mohammedans, and described the discharges as milky or rice-water like.

Drasche,† quoting from Deguigne's History of the Huns, speaks of an epidemic of cholera in A. D. 1031, which proceeded from India through the provinces of Ghiznee and Khorassan, extended through Armenia and Syria, and even ravaged Constantinople.

Bernard Gordon, of Montpellier, John of Gadesden, of England, and Gilbertus Anglicus, in the beginning of the fourteenth century, describe the disease. The latter wrote of collerica, or collerides, and describes the cramps and collapse with fatal result in the course of a day, in acute cases.

In certain historical data of Arabian origin, Drasche finds a reference to an epidemic of cholera in 1347 and 1349, which, proceeding from India through Egypt, Nubia, and Abyssinia, was lost in the deserts of Africa. And in the Persian records of Aby Ben Hussein there are suggestive hints of a disease similar to cholera, which extended, in the years 1375 and 1376, far beyond the boundaries of Hindostan.

According to Rigler‡ there are historical proofs that cholera prevailed several times, especially after the capture of Constantinople by Sultan Mohammed the Second, in the year 1453; and also at later periods in Syria, Arabia, and Egypt.

Thus almost every known writer in medicine, up to the close of the year 1500, has described a disease attended with violent vomiting and purging, serous evacuations, suppression of urine, lividity of skin, collapse, and death either after a brief interval, or protracted convalescence with secondary fever. A large proportion of these attacks were sporadic, but a few were epidemic and pestilential. In the earliest writers the communicable and migratory characteristics of the disease entirely escaped observation and record; but it is not surprising that the writings of the ancients contain no trace of these features of a pestilence which, without reasonable doubt, seems to have swept at times over the continents of Europe and Asia. Exact knowledge was then rare in any of the branches of medicine, and the received opinions in regard to epidemics were, from the nature of the subject, founded on imagination and superstition. Information passed from country to country only by the

* Cragie, *op. cit.* † *Op. cit.* ‡ Drasche, *op. cit.*

ıe progress of the caravan, or the slow march of an army, or by oft-arrested voyages of small and imperfectly equipped coasting-sels. In many cases, as in modern times, it was doubtless considered essary, by commercial communities, to conceal all knowledge of the tilences from which they suffered. Thus cholera, or any other of the ases now considered migratory, might have gained a foot-hold in a mmunity before a knowledge of its approach was obtained. In the state of medical knowledge, such a visitation, coming without ning or apparent cause, and disappearing in the same mysterious nner, would be soon forgotten, or remembered by the superstitious an exceptional instance of divine displeasure. It is only by such nsiderations as these that we can explain the failure of ancient writers d-tect and describe the migratory nature of a disease, the other tures of which they have recorded in such vivid and unmistakable ms. That cholera might have been imported from India into Persia, abia, Egypt, Turkey, Greece, and Italy, traveling, for centuries be-e the Christian era, over the same highways along which it has been ed in later times by modern exactness of observation and improved ans of communication, is evident from a brief survey of ancient and dieval history.

The intercourse between different countries in the East was carried at first entirely by land. Merchants could often undertake long and some journeys with the aid of the camel, whose persevering strength, deration in the use of food, and ability to lay in a stock of water for eral days, put it in their power to convey bulky commodities through se deserts which must be traversed by all who travel from any of countries west of the Euphrates toward India. Trade was carried in this manner, by the nations near the Red Sea, from the earliest iods to which historical information reaches. Numerous bodies of rchants assembled at stated times, and, forming a caravan, performed rneys of such extent and duration as appear astonishing to nations t accustomed to this mode of carrying on trade.

Again, navigation made its first efforts on the Mediterranean and Red as, and in these waters the earliest active operations of commerce were ried on. The Egyptians and the Phœnicians of Sidon and Tyre are most ancient navigators mentioned in history.

Sesostris was able to fit out a fleet of four hundred ships in the Red a, and subdue all the countries stretching along the Indian Ocean India. At the same time his army, led by himself, marched through ia, and conquered successive countries as far as the Ganges.

The commerce of the Phœnicians was adventurous, and their trade th India was considerable and lucrative. They took possession of inocolura, the Mediterranean port nearest to the Red Sea, and seized mmodious harbors in the Red Sea, with India on the one hand and the stern coast of Africa on the other. The Jews under King Solomon ted out fleets which, under Phœnician pilots, went down the Red Sea Golden Sofala, and to Tarshish and Ophir, on the African coast, op-osite Madagascar and near Zanzibar.

Next, Darius, son of Hystaspes, sent an expedition through Persia nd Central Asia down to the mouth of the River Indus; and about ne hundred and sixty years afterward, Alexander the Great made his ell-known excursion in the same direction. In no place in the earth is ne line of approach better marked and defined more conspicuously than n the northern frontier of India, insomuch that the five great invaders of hat country, Queen Semiramis, Darius, Alexander, Tamerlane, and adir Shah, in different ages and with views and talents extremely dis-

cordant, advanced by the same route, with hardly any deviation: and cholera follows the same roads to the present day. Alexander penetrated India as far as Lahore. Seleucus reached Allahabad. Ptolemy Lagus and Philadelphus also carried out the designs of Alexander the Great.

The Greeks traded to the Black Sea and the Danube. Abaris, the Scythian, visited Delphi, and put a stop to an epidemic.*

Anacharsis, a not less famous Scythian, traveled into Greece in the time of Solon. He taught his followers how to heal acute diseases and to stop pestilences.

The ancient Indian trade of Persia was carried on by caravans from the banks of the Indus to those of the Oxus, down that stream to the Caspian Sea, and from thence to the different countries on the Black Sea, especially to Constantinople.

The Romans under Augustus secured the control of the Red Sea. They were thus enabled by commerce with India to amass such enormous wealth, as to produce an alteration in the value of property and the style of manners in Rome itself. Besides receiving Indian commodities by the Red Sea, the Romans also traded by way of Aleppo and Beirut in a straight line to Damascus, Bagdad, Palmyra, the Euphrates, and the Persian Gulf. Palmyra, situated on an oasis only four miles in extent, achieved a great measure of her grandeur and opulence by an active trade with India. Hippalus, commanding a Roman ship engaged in the Indian trade, was carried by the western monsoon directly to the Malabar coast near Goa, and returned with a cargo of spices, pearls, jewels and silks. The Romans also traded to Tatta, at the mouth of the Indus, and to Baroch, on the sacred river Nerbudda. The elder Pliny describes the course of navigation from the Red Sea to the Malabar coast and Ceylon. Ptolemy described the river Cauveri, Masulipatam, Arcot, and the Coromandel coast.

At the time of Justinian, Persian traders frequented all the principal ports of Western India, and by means of the Persian Gulf and the great rivers Euphrates and Tigris distributed Indian goods through every province of their empire.

Eighty years after the death of Justinian, Mohammed published his new religion, and his followers commenced a course of conquest which reached from the frontiers of China to the shores of the Atlantic in Africa and Spain. Egypt was one of the earliest of their conquests: and they soon excluded the Greeks from all intercourse with Alexandria. Next the Caliph Omar, a few years after the Mohammedan conquest of Persia, founded the City of Bassora, at the head of the Persian Gulf, in order to control the trade from India to the Tigris and Euphrates. Europe was in consequence almost excluded from the East. The great port of Alexandria was shut, and the caliphs, the new lords of the Persian Gulf, neglected to send goods to the Mediterranean. The citizens of Constantinople were thus forced to encourage the caravan-trade which came from Chersi, (?) the westernmost province of China, a march of from eighty to one hundred days to the banks of the Oxus, from thence down to the Caspian, across to the river Cyrus or Kur, and from thence to the Phasis, which empties into the Black Sea near the modern city of Poti, and thence by an easy and well-known course to Constantinople. The commodities of Hindostan were also carried from the banks of the Indus to those of the Oxus, and then followed the above-mentioned route.

The Huns, or Oriental Mongols, came in the fifth century from the

* Dunglison's History of Medicine, p. 81 to 83.

ions watered by the Oxus, crossed the Don and the Dneieper, pushed
en into Turkey and Greece, and thence into Hungary, Lombardy, and
ly. The Alans also came from Asia, A. D. 280 to 375, and passed
ough Germany, and France, down to Spain; while the Saracens from
abia pushed along the whole northern coast of Africa and crossed
o Spain. (See map.)

The crusaders swept up to Constantinople, Syria, and Palestine, fol-
ed by Genoese and Venetian traders, to Tyre and Antioch. The
netians finally concluded a treaty with the Sultan of Egypt, by which
y re-opened the trade with Damascus and Alexandria, and soon con-
lled all the Indian trade to Europe by way of the Persian Gulf and
d Sea.

n the thirteenth century the people around the Baltic united in the
nseatic League, with the center of their trade at Bruges, in Belgium.
ither the merchants of Venice and the Mediterranean resorted with
nmodities of the East in exchange for naval stores and other products
the North. This continued till near the close of the fifteenth century,
en the discovery of America, and the opening of a direct course of
vigation to Hindostan by way of the Cape of Good Hope proved fatal
the power and opulence of Venice. Vasco de Gama sailed from
rtugal around Africa, and landed at Calicut A. D. 1498, ten months
er his departure from Lisbon. The Venetians, foreseeing the ruin of
e lucrative Indian branch of their commerce, incited the Sultan of
ypt to fit out a fleet on the Red Sea, supplied him with timber from
lmatia, built twelve ships of war at Suez, which were destroyed after
veral conflicts by the Portuguese; who then seized the island of Ormuz,
the mouth of the Persian Gulf, and thus secured to Portugal the benefit
that extensive trade with the East which the Persians had been carry-
g on for several centuries. It would have been strange, indeed, if
olera had not reached Europe by some of these expeditions and routes.
According to Robertson, Nolan, and others, previous to the discov-
es of the Portuguese the only commercial route between Hindostan
d Europe was by way of the Red Sea and the Persian Gulf. The
ves of Amboyna; the nutmegs, camphor, and mace of Borneo; the
ndal of Timor; the spices, gums, perfumes, and curiosities of China,
am, Java, and other kingdoms, were first conveyed to Malacca, and
ence to Ceylon and India. Precious stones and spices from Pegu and
ylon, the diamonds of Golconda, Dacca stuffs from Bengal, and spices
om the Coromandel and Malabar coasts, were brought to Calicut, Goa,
rat, and Cambay, on their way to golden Ormuz, at the foot of the
rsian Gulf; thence to Bassora, at the mouth of the Euphrates; whence
ey were distributed by caravans through Armenia to Trebizond, on
e Black Sea, and through Aleppo and Damascus to Beirut, on the
editerranean. From these depots the Venetians, Genoese, and Cata-
nians distributed them throughout Europe. That portion of this rich
ade which was diverted to the Red Sea touched at Aden or Mocha, and
ssed thence to Suez, reaching Cairo by caravan and Alexandria by
e river Nile, to be shipped to Europe.

When this magnificent traffic was broken up by the discovery, by the
ortuguese, of a practicable route to India by way of the Cape of Good
ope, the more civilized nations of Europe were placed in direct com-
unication with Hindostan, and we began at once to have clear records
Asiatic cholera. In A. D. 1500, cholera was found to have been pres-
nt in every place in the west coast of India where Europeans had an
pportunity of observing the diseases of the country. Six distinct ac-
ounts of it came from Calicut, Goa, and Surat. Again, the native

name for cholera, mordshee or mordexin, is a Mahratta word; and as these people had come from the interior to Goa and Calicut, it was probable that they brought the disease with them, as they had been in possession of the great shrines at Bejapore, below Bombay, and of Bisnaginugger, near Bellary, where cholera always prevails.

The following history of cholera from A. D. 1500 to the beginning of the present century, is also derived in a great measure from Macpherson's Drasche, Macnamara, and other annals:

Vasca de Gama first reached the southwest coast of India in 14[illegible]. The Portuguese took Calicut, on the same coast, in the year 150[illegible] and noticed a great outbreak of cholera in 1503. They took Goa, higher up, in 1510; and in 1543 an epidemic of frightful intensity was observed there. The child at the breast, the aged man, the sound as well as the feeble, fell victims, with vomiting, excessive thirst, cramps in the legs and feet, while the nails of the hands and feet became black and curved. Scarcely 10 per cent. of those attacked escaped alive. The church-bells of the Portuguese tolled all day, and there were from twelve to twenty burials of Europeans a day. Garcia D'Orta described another epidemic in 1563. Some of the attacks were cholera morbus, produced by eating cucumbers and shell-fish, especially in those weakened by fatigue and debauchery. In others, bilious vomiting lasted from four to ten days. In others, after the patient had vomited and purged for several hours, at last he only discharged water with no acid or bitter taste. The pulse was weak, with great coldness, and cold prespiration, while the sufferer complained that he was burning; and cramps succeeded. D'Orta distinctly pointed out the varied forms of the disease. He mentions a case of partial convalescence from rice-water discharges, which ended fatally after many days of bilious vomiting.

General Beaulien met with the pestilence in Sumatra in 1620. It destroyed a great many Europeans, especially Frenchmen, who accused the Dutch and English of having poisoned them; although Beaulien himself attributed the disease to indulgence in copious draughts of water and sleeping afterward in the open air with the abdomen exposed, as is not uncommonly done in hot climates. Anderson wrote about cholera in Java and Sumatra, between 1644 and 1650, under the name of bilious diarrhœa.

Bontius, in 1629, called cholera mordeshi, and as the Dutch had been preceded by the Portuguese in Java, there is every probability that it was an imported disease. Bontius states that the hot, bilious, and white and watery, matter irritated the stomach and intestines and was incessantly and copiously discharged by the mouth and anus. It was a disorder of the most acute kind, the principal cause of which, next to the hot and moist disposition of the air, was an intemperate indulgence in eating fruits, which, as they are generally green and obnoxious to fermentation and putrefaction, irritate and oppress the stomach by their superfluous acidity and humidity, and produce an æruginous and cupery tasting but white bile. The discharges might with some degree of reason be reckoned a salutary excretion, but the purgations were excessive that the strength was soon exhausted, and those who were seized with it generally died within twenty-four hours. He says the disease was attended with a weak pulse, difficult respiration, coldness of the extremities, great internal heat, insatiable thirst, restless and incessant tossing of the body, followed at times by convulsions; and if a cold and fetid sweat break out, certain that death was at hand. Bontius saw another epidemic of the same kind twelve years later, in 1641 and 1642, having previously lost his wife by the same disease in 1631.

Zacutus Lusitanus, a celebrated Jewish physician, banished from Lis-
n by Philip IV, retired to Amsterdam, and had opportunities of com-
nicating, first with Portuguese, and afterward with Dutch navigators.
ters addressed to him from Goa and other places in the East, show
t he was in close communication with India. In 1632, he wrote that
Arabs suffered from cholera, and had a tradition that it had traveled
r Persia, Syria, and Egypt, and finally disappeared in the African
ert.
holera is said to have again prevailed in Goa in 1638.
landelsloe in 1639, and Baldaeus in 1641, make allusions to mordexin
India and Ceylon.
olonel Tod gives an account of cholera in the provinces of Mewar in
1, and Marwar in 1681, both near Cambay and Surat, on the west
st of India. Also, in the camp before Goa in 1684, when as many as
hundred men perished daily.
ir John Malcolm says, in 1621, that cholera always exists in the pro-
ce of Malwah, on the sacred river Nerbudda, just above Surat.
e Thevenot found cholera in Boorhampore, near Nagpore, in Middle
lia, in 1666, and described four varieties: first, the dry, with great
e; second, the diarrhœal; third, with both vomiting and diarrhœa;
fourth, with all the above and cramps.
leyer noticed cholera in China in 1669, imported perhaps from Ma-
ra.
r. Fryer, who gives the best statement by an English observer, saw
gain in Surat in 1674, (one hundred and seventy-miles north of Bom-
.) This is a large and very dirty city. Its commerce was extensive,
the moral condition of its inhabitants deplorable. Six miles from
city there was, and is, a noted place for religious ablutions and for
eral pyres; their sacred groves and temples were crowded with de-
ees.
n 1679 Then Rhyne alludes to cholera in Java, and the chemist Hom-
g in 1689; while Kaempher states that it was frequent and fatal in
an.
mperfect accounts are given of a severe pestilence at Masulipatam,
ween Madras and Juggernaut, in 1687, by Forbin.
A carelessly-described pestilence appeared at the holy city Beejapore,
ow Bombay, in 1689; while a similar pestilence raged at Surat from
4 to 1690; and a sweeping epidemic at Balsora, between Juggernaut
l Calcutta, in 1691. Carreri noticed cholera at Damaun, near Bombay,
1695.

CHOLERA IN EUROPE IN THE SEVENTEENTH CENTURY.

In 1610, yellow cholera and bilious fluxes were common in England.
1617, 1623, and 1626, white fluxes, possibly of a choleraic character,
re again noticed in England, Germany, and France.
In 1643 Van Der Heydon, of Belgium, described the furious onset of
mse galant, which so altered the appearance of the patients in a few
ars that their best friends might not recognize them.
In 1649 Riverius gives a full account of sporadic cholera of consider-
le intensity, sometimes followed by secondary fever, expulsion of enor-
ous quantities of fluid by vomiting and purging, and sudden death;
less the attack was produced by something which was eaten, when
overy was probable. But the more severe the convulsions and cold-
ss of the extremities, the more fatal the attack. Riverius believed

in the existence of contagious and pestilent epidemics of diarrhœa c. cholera, as did Piso in 1638.

In 1665 cholera of some kind was epidemic in Ghent, Belgium.

We now come to the English epidemics described by Short, Sydenham, Willis, and Morton. According to Short, owing to the great heat in 1669, came cholera morbus, which reigned till 1672.

In 1676 the convulsions were more violent and continued than Sydenham had ever seen there before. He regarded the autumn cholera as very different from the ordinary cholera induced by indigestible food. Willis has not omitted the leading symptom of white or watery evacuations. He says the disease invaded suddenly, and frequently without any manifest occasion, and did reduce those laboring with it by great vomiting and frequent and watery stools quickly to a very great debility, with weak, small pulse, cold sweats, and short and quick breath. Very few had bloody stools, and not many bilious; but very many had vomiting and plentiful watery, almost clear stools. It raged in London; but did not extend three miles beyond the city, nor seem to be propagated by contagion. The main cause of the disease he thought to be an evil influence of the air, (or water,) which was increased by errors of living; but he could not connect the disease with overeating of fruit.

The celebrated Morton speaks of great epidemic diarrhœas, accompanied by awful twitching cramps, as prevailing annually from 1669 to 1672 in London to such an extent as to occasion a weekly mortality of from three to five hundred. The discharges consisted of a copious pouring of colliquative white, but apparently virulent, serum. In the year immediately preceding the great fire in London, and when the sanitary condition of the city was horrible, this "plague in the guts" caused thousands of deaths.

Ettmüller, in 1685, regarded cholera as only an expanded and unusually malignant form of diarrhœa. He believed it to arise from a ferment, either inspired with the air or taken in with the food, (or drink,) arising from the excreta of the sick, and which multiplied itself after being introduced into the body. It became more or less epidemic, and was at such periods apparently contagious. He repeats, that the disease was caused by the air, by bad water, and by bad fruit. The contagion of epidemic diarrhœa, but especially of dysentery, he supposed to be propagated by latrines, and sometimes even by injection-syringes. Riverius had previously pointed out that in contagious dysentery a (or many) members of a family got it from the use of common latrines or privies.

Pechlin, about this time, describes a cholera which he calls serosa, without bile.

In 1689 there was cholera and dysentery in Europe, in Nuremberg in 1691 in London; in 1695 in Ulm; in 1696 in Switzerland.

Hoffman, about this time, compared cholera to the effects of arse-

CHOLERA IN INDIA IN THE EIGHTEENTH CENTURY.

To return to India. A French Jesuit, Pere Martin, met with cholera in extreme Southern India, between Madura and Trichinopoly, in 1700.

The Sieur Suillier found it in Hooghly, below Calcutta, in 1703, as did Frère Papin, in 1709.

In 1733 Dr. Arbuthnot described cholera as common at Madras from April to August.

In 1736 Paxman said it was frequent in India.

n 1739 it attacked Nadir Shah's invading army, probably near Delhi, he north of India.

'he year 1756 marks the commencement of periodically-returning lemics, the first occurring in 1756 and 1757; the next in 1768 and 9; and the third in 1780 and 1781, with recurrences in 1783 and 1787.

n 1756 the disease was peculiarly severe in Arcot, city and province, ut sixty-four miles southwest of Madras; which included Tripetty, most celebrated Hindoo temple south of the Kistna River. Tripetty ituated in an inclosed plain, entirely encircled by hills, and into which s said no Mohammedan or Christian has ever entered. Every year, n 1758 to 1811, the Brahmins are reported to have paid from $100,000 $150,000 to their conquerors for the privileges of this reservation. st numbers of pilgrims visit it from every part of India, bringing offer- s of every conceivable character, from horses, elephants, gold, jewels, l silk, down to fruits and grain. Several thousand priests are here ported in luxury and idleness.

n 1766 J. H. Grove said cholera was common on the Malabar or west st of India, below Bombay, but had been scarcely seen in that city a long time; showing that it had periods of increase and decrease.

1756 Johnson, of Chester, saw it on board an English fleet in lia. After 1756, when the disease scourged Arcot, it persisted at Vel- e, near by the valley of Ambore or Amburpet, for a series of years. me says it caused great and sudden mortality in Southern India in 7.

Niebuhr says it was seen in Arabia from 1761 to 1763.

Gentil alludes to it in 1761 and 1769 in the Coromandel, or east coast India, near Pondicherry. Shortly after this it was present in China well as in India.*

Sonnerat's travels extended from 1774 to 1781, but his allusions to olera probably include the epidemics about Pondicherry in 1768 and 9. Père Martin had already corrupted the Mahratta word *mordeshi* o *mort de chien*, and this name was now popularized by Sonnerat.

It prevailed at Paliconda, in the Amboor Valley, and at Arcot from 9 to 1771. It was frequent in Bombay in 1772 and at Madras in 1774, d in 1775 was carried down to the Isles of France and Madagascar.

Sonnerat once considered it as of a catarrhal or rheumatic nature, for says it never appeared except in the cold weather of India. Some re attacked after having passed the night in the open air, others from ving eaten cold rice and curds, but the greater number from eating t after they had washed and bathed in cold water. He says there was eat reason to imagine that the perspiration, thus being stopped, reflowed to the mass of the blood, and, finding its way to the stomach and bowels, used a watery flux, accompanied by vomiting, universal spasms, vio- nt pains, extreme faintness, burning thirst, oppression of chest, sup- ression of urine, and death after twenty-four hours or less. At first, is epidemical disease happened near Madras, during the northeasterly nds in December, January, and February only; and when they ceased disappeared. But the epidemic which followed two years after was e more dreadful, and did not proceed from the same causes, as it began July and August. It first showed itself by a watery flux, which me in an instant, followed by twenty or thirty evacuations in five or x hours, which reduced the patients to such a state of weakness that ey could neither speak nor move. They were often without pulse; e hands and ears were cold, the face shrunken, and the eyes sunk in

* Voyage aux Indes orientale, Paris, 1772.

their sockets. They had neither pains in the stomach, colics, nor gr[illegible]ings, like the first class of cases; but their greatest torment was a burning thirst. Death often ensued in less than twenty-four hours. The first form was probably bilious cholera, for it selected debauchees and those suffering from indigestion; the latter was Asiatic.

The chief epidemic described by Sonnerat probably occurred from 1776 to 1778 on the Coromandel, or east coast of India. It was supposed to have been epidemic in the Bundelcund below Allahabad in 1779. It was at Tanquebar, below Madras, in 1780.

From this time on, Macpherson thinks, the English records in the Bengal, Bombay, and Madras reports contain all that is known about the subsequent history of the disease.

For ten years previous to 1781 there is almost constant notice of the prevalence of the disease along the Madras coast and in southern India, and it seems nearly inconceivable to Macpherson how the outbreak in Colonel Pearse's troops at Ganjam, below Juggernaut, in 1781, should have caused so much astonishment, and how this wonder could have been repeated at the next great outbreak in 1817. He says it shows that very little was known in those days of what was going on in different parts of India.

From 1781 to 1783 numerous and severe outbreaks of cholera occurred in different parts of India. On the 22d of March, 1781, at Ganjam, far from the great temple of Juggernaut, it assailed Colonel Pearse's division of Bengal troops, of about five thousand men, with almost inconceivable fury. Men in perfect health dropped down by dozens and were dead or past recovery within an hour. About five hundred men were admitted into the hospital on that day, and within three days half of the army was sick. The celerity and fury of this attack is suggestive of the probability of its origin in the use by the troops of contaminated water. It was subsequently discovered that the disease had been prevalent among the natives and pilgrims in that part of the country before the arrival of the soldiers. In the next month it appeared in Calcutta, about two hundred and fifty miles northeast from Ganjam, and made alarming havoc for about ten days.

In the following year, 1782, cholera was largely diffused in Southern India.

In the next year, 1783, it appeared at Hurdwar, during the fes[illegible] and killed twenty thousand people; and the Madras reports describe the malady as epidemic along the whole east coast.

In 1782 Konig, the botanist, had a narrow escape from death by cholera at Tanquebar, below Madras; followed a long convalescence, probably from consecutive fever.

The epidemics of 1781 to 1783 were observed and described by several English physicians. Dr. Davis, of the hospital board at Madras, was deputed to investigate the disease at Arcot. He found many cases of true destructive rice-water cholera, many cases of simple cholera morbus with colic and spasms, and much bilious cholera with copious discharges of yellow, green, or dark-colored bile from the stomach and bowels. In the latter cases the mortality was only two or three out of sixty.

Its appearance at Madras in 1782 is described by Girdlestone, who states that, among the troops which had just arrived from England with Sir John Burgoyne, more than fifty men perished within three days after landing, and in less than a month upward of a thousand had suffered from the disease. It attacked Sir Edward Hughes's squadron at Madras early in 1782, and was probably carried over to Trincomalee in Ceylon, which was and is the first and last stopping-place for all vessels going

nd from Madras and Bengal. This Ceylon epidemic is described by
rs, who had seen the disease in the Madras fleet and in the Madras
spitals. He says that attacks of watery purging generally came on
ight or in the early morning, and were followed after some hours by
ps and great weakness and sinking, with coldness of the extremi-
and lividity of the countenance. The vomiting brought up nothing
us; the patient complained much of the cramps, and wanted to be
ed hard; the eyes were sunken, hollow and surrounded by a livid
e; pulse feeble, and often absent at the wrist; great thirst and de-
for cold drinks were present; profuse clammy sweat; the finger-
became livid and bent in, while the skin of the palms was white,
rched, and wrinkled up in folds, as if long soaked in water; the counte-
ce and limbs were livid; finally the spasms abated and the patient
in perfect possession of his faculties; being able to speak calmly,
ough the body was cold and the pulse had ceased.

he Rev. Father Sangermano, who was sent to Rangoon, in July, 1783,
that a malady of a malignant nature, and not confined to the Bur-
e Empire, but spread over all India, is that called by the Portu-
e *mordazzino*, consisting of a violent indigestion, which causes
t the physicians call cholera. The continual evacuations, both by
it and stool, will reduce a man in a few hours to such a state of ex-
stion, that he is scarcely to be recognized as the same person. To
e evacuations succeed a cold sweat, hiccough, faintness, and death.
metimes the disease had a totally different effect, which is to make
stomach incapable of expelling the contained matter, and in these
s the convulsions of the patient are indescribable. This species of
era, to which the name of dry *mordazzino* was given, was supposed
e more dangerous than the other variety.

1788 cholera prevailed epidemically at Bellary, and it was in Bata-
in 1789.

acpherson says: Singularly enough another Bengal army was attacked
790, much in the same way as that of Colonel Pearse, in 1781, in the
e country, Ganjam, near Juggernaut, and at the same season in
ch and April, viz, at the time of the pilgrimages.

nkes says it was prevalent in the Mahratta country, in Central India,
794, and reached Tannah, on the west coast, near Bombay.

1797 it was prevalent at Backergunge, near Calcutta, although
n it reappeared there, twenty years later, the great majority of the
opean observers regarded it as an unknown pestilence. As European
in Bengal was then rated at two monsoons, it might easily have been
nown to new-comers.

CHAPTER II.

HISTORY OF EPIDEMIC CHOLERA FROM A. D. 1800 to 1[illegible]

Dr. James Johnson,* in his work on the diseases of tropical climates, alludes to the prevalence of cholera near Trincomalee, on the east coast of Ceylon, in 1804.

In 1808, according to the Bengal reports, quoted by Macnamara,† a few cases occurred among the English troops at Merut, just below Hurdwar, above Delhi; in Delhi; at Muttra, below Delhi; and at Cawnpore.

In 1809, '11, '12, and '13 many cases occurred at Chunar, a military post, just above the holy city of Benares.

In 1814 cases occurred at Cawnpore, above the holy city of Allahabad; at Nagpore, in Central India, on the road from Allahabad to Bombay; at the holy city of Benares; again at Meerut, below sacred Hurdwar; and at Dinapore, near Patna; and at the holy city of Gaya, just below Patna.

In 1814 it also appeared in a crowded barrack in Fort William, near Calcutta, in the east, among recruits just arrived from England: and it was epidemic in Jaulnah, toward Bombay, in the west. As regards the outbreak at Jaulnah in 1814, Dr. Cruikshanks entered the cases in the hospital-returns as bowel-complaints, because the matters ejected by vomit and stool were watery or mucilaginous, containing no bile. Dr. Scott, guided by an accidental remark of Dr. Duncan, was enabled to refer to Dr. Cruikshanks and develop this point, and then remark: Although cholera very rarely appears in the sick-returns of former years, it is by no means to be inferred that it did not then prevail from time to time among the troops as well as the natives.

In 1815 and 1816 no cases were reported among the white troops; in 1817 only two cases occurred among the garrison at Benares, although the disease was raging throughout the whole of Bengal; showing that statistics, drawn from Europeans only, cannot be relied upon as a criterion of the prevalence of the cholera in India. (See map.)

The English population of Hindostan is, and always has been, very much smaller than is generally supposed. In 1874 there were only one hundred and sixty thousand, in all, scattered among two hundred and forty millions of natives. Before the rebellion of 1857 we find there more than thirty thousand English troops in India at one time, but even now there are only about seventy thousand. As late as 1847 there were more than six hundred thousand natives in Calcutta, and only about two thousand Europeans, apart from the troops. Benares, with three hundred thousand inhabitants, had scarcely one hundred and fifty foreign residents. In Delhi, of half a million inhabitants, only one hundred were English. Bombay, with two hundred and fifty thousand, had only several hundred resident Europeans.

To account for the origin of cholera in 1817, it is claimed that the rainy season of 1815 was excessive, while the hot season of 1816 was distinguished for drought and intense heat. Throughout India fevers predominated, and Bengal was visited by various pestilential diseases, especially by malignant sore-throat, a contagious disease previously unknown, according to the Bengal report, except by name.

* The Influence of Tropical Climates on European Constitutions. Philadelphia, 1[illegible]

† A Treatise on Asiatic Cholera. London, 1870.

portion of the globe. In the upper provinces bilious remittent r raged epidemically, and occasioned a mortality which surpassed hing on record in the medical annals of Bengal. The military ions wore a gloom hardly to be imagined. In many of the native ges the whole population was ill, and numerous shops were closed; banks of the rivers were crowded by the dead and dying, and many es were left unburied. The cattle were diseased and their carcasses wn in vast numbers in the pastures.

1817 it rained much in February and March, and on March 30 a of cholera, fatal in thirty-six hours, occurred in an English soldier e Fifty-ninth regiment, at Fort Williams, Calcutta. The regular rains menced May 25, fifteen or twenty days earlier than usual, and poured st incessantly during June and July, putting a stop to cholera, l the dry season in August. This year, 1817, was also the year for the t twelfth yearly festivals or pilgrimages. These festivals are held y year in all parts of India, and increase in sanctity every third, h, and ninth year, and still more every twelfth and sixtieth year. will account far better than the monsoon theory for the greater alence of cholera in India every third or fourth year, and its immense ad every twelfth year.

he cholera of 1817, according to the Bengal report, evidently arose it May or June, after seasons remarkable for their irregularity and inguished for epidemic sickness and mortality; and also after the t pilgrimages in March and April. It did not spring up in Jessore originate in any one town alone; but seemed to arise simultaneously, ifferent districts, and then diverged in all directions. It prevailed he province of Nuddea and other districts, to the north of Calcutta west of Jessore, as early as May and June, 1817. In the middle of , it commenced in the province of Bahar, near Patna, and in the ed city of Gaya; and was also in the great city of Dacca, on the hmapootra, northeast of Jessore and Calcutta. It is distinctly d to have broken out in Patna, three hundred miles northwest of utta, on July 11, from whence it extended a little north of Dina- and to the adjacent villages early in August.

May and June it was in Kishnagur, north of Jessore, and in the pro- e of Mymensing, north of Dacca. In July it was in eight divisions of province of Kishnagur, and also at Sunergong, in the Dacca district, and the mouth of the Brahmapootra. It was at Sylhet, far above ore and Dacca, to the northeast, by the 17th of August. Another unt says it appeared in July at Sunergong, on the great river Megna, ch joins the Ganges and Brahmapootra, and thence proceeded up the r, visiting the ghauts, public ferries, and grain-markets, up to Dacca its neighborhood. It was also at Backergunge, at the mouth of the Ganges and Bramapootra, at a very early period; and was even ied over to Chittagong, on the east coast of the Bay of Bengal, be- it appeared in Jessore. It was also in Calcutta in the first week in gust, before it broke out in Jessore. In Calcutta, where all the fa- ies for information were comparatively abundant, it was long sup- sed that the cholera of 1817 was brought down from Jessore; but sequent investigation proved that there was very little doubt it had ted some spots in the so-called Black Town, or suburbs of Calcutta, arly as the beginning of August; that it daily gained ground, and ore the end of the month had widely spread its ravages in a manner eatening to sweep off a large portion of the native population; and t, in the early part of September, even the English portion of the com-

munity was no longer secure from the concentrated activity of the p
as thirty-six thousand native cases had occurred in three months
quite as likely as not that the disease was brought to Calcutta fro
gernaut, and that the outbreak was delayed by the excessive rain
recommenced, as is usual, in the dry and hot season; or that it
menced in the neighborhood of Patna; or that it came to Calcutta
Dacca, which has always had a great celebrity, not less than that
cutta, for the origin of cholera. Nothing is more certain than that
vailed to the north, south, east, and west of Jessore, for hundred
miles in each direction, before it appeared in Jessore. Dr. James
son* says: "It is clear to demonstration that it did not originate in
sore; on the contrary, there is better reason to suppose that it was
ried to Jessore than that it first broke out there. The Bengal re
says it is certain that nothing can be more erroneous than the notio
the local origin of the epidemic at Jessore, for there are facts
than sufficient to shown the fallacy of every theory which attem
derive the disease from any one spot as the only center from wh
was emitted to the surrounding countries. The facts prove, without
possibility of dispute, that it broke out in remote places at such
intervals of time that its general diffusion must be referable to
known causes of more general operation than infection or contag
proceeding from one spot alone." From March to August probably
lions of pilgrims were traveling to and from Juggernaut, the most
the Ganges and Brahmapootra, from Gaya, Benares, Dacca, and
holy places, and thus distributed the disorder.

Macnamara* says, (page 12:) "Early in September Balasore and
tack, near Juggernaut, and Ganjam, were affected." On page 2
the district of Ganjam, near Juggernaut, cholera, *as usual*, appea
with renewed energy during the months of March and April
spread southward" and doubtless northward toward Calcutta
page 79: "The civil surgeon at Gaya reports that cholera had, as
re-appeared at that station, confirming Dr. Woodburn's statement
to the disease being *endemic* in those parts; a fact to which
surgeons, marching along the trunk road from Calcutta to Be
in charge of troops, will bear witness; for it is hardly possi
pass through this part of the country without some of the men
seized with the disease," (cholera.) However this may be, the
clear accounts of cholera came from Jessore. Dr. Tytler was
to a case there on August 19, 1817, and soon saw many others
the disease was spreading rapidly, the natives fled from the town.
judge closed his court and reported at Calcutta. The medical boa
Calcutta declared the pestilence to be the usual epidemic of this
of the year, aggravated by the peculiarities of the season and
local causes. It was understood that, in certain quarters of Calcu
similar epidemic was also prevailing with more than ordinary fa
So distinct was the European part of Calcutta from the native
and so rare was cholera among the foreign residents, that neither
physicians who had been connected, one for five and the other
years, with the general hospital for Europeans had seen a case pre
to this outbreak.

Dr. Barnes, resident at Jessore from 1810 to 1823, who had
familiar with ordinary Indian cholera for all that period, said the
of the disease were too extensive to be brought under human
Putrid exhalations from the constant and rapid decomposition of
and vegetable matter, and *the use of unwholesome water*, were the

*Op. cit..

es. In two months it swept off ten thousand of the inhabitants of ore, which has since been erroneously styled the "cradle" of cholera. province of Jessore is situated in the center of the Delta of the ges, surrounded by the districts of Backergunge on the south, Dacca e northeast, Rajeshahye in the northwest, Calcutta on the southwest, Purneah on the north. All these districts were affected nearly si-aneously, and most of them before Jessore. But it is also rightly ed that the inhabitants of Jessore, astonished and terrified at the l-nce, fled in crowds to the country, and spread it rapidly through djoining villages. It has been supposed that Jessore was more and unhealthy than other towns. This is not the case, although seated on an almost stagnant arm of the river, which is often formed into a fetid swamp, along which are rows of low, mean huts, ounded by many trees which afford shade but obstruct ventilation. lcutta stands upon an almost perfect level of alluvial and marshy nd, which was formerly covered with stagnant pools. About four a half miles east of the city is a large but shallow lagoon of salt r, from which a canal is cut pretty nearly to the town, and toward h all the drainings of the city flow. Many of the natives cannot oach the "bad water" without attacks of nausea and headache. English portion of the town is a city of palaces, but the Black Town led with wretched houses and miserable huts, which are clustered nd large and filthy tanks, in irregular groups, and are connected narrow, winding, unpaved streets. The air of the Black Town is sive to the smell from the presence of decomposing refuse and filthy r. And as if it were not bad enough the Brahmins are often stopped e common people, and asked to bless their supply of drinking-water ipping their feet in it.

e story of the spread of cholera in and from Bengal in 1817, has told so often that it may be given very succinctly here; and will be y understood by reference to the map. It extended up the Ganges hwest as far as Allahabad; up the Brahmapootra River from Dacca heast to Ringpore, and the borders of Thibet and Southwestern a; around the Bay of Bengal to Burmah and Siam; and down from tta and Juggernaut toward Madras.

arly in 1818 it progressed up the Ganges and Jumna Rivers to Cawn-, Agra, and Delhi, toward holy Hurdwar; from which a new stream he disease was coming down. Jameson traced it to Shahjehanpore, twenty miles from Hurdwar, where it appeared in July, and is rted to have killed five thousand persons. It was also carried still her to the northwest. On July 23, a body of European and native ps marched from Delhi through Meerut to Hansi, cholera being at its height in Delhi. On the 31st, the epidemic appeared among e soldiers, and on August 6 they joined the forces at Hansi, when ost immediately afterward the disease broke out among the entire ade, and accompanied it farther north toward Lahore. It was the eral belief among the medical officers that the troops from Delhi ught the cholera with them, and then distributed it farther north. er similar instances are noted. In May, 1820, Moorcraft incidentally ntions the existence of cholera to the northwest of Lahore; and Sir hard Temple affirms that the Punjaub, toward Peshawur, the extreme thwest border-town, was visited severely by the disease in 1820. But have no accounts that it reached Persia from this direction, as it did 1827, 1828, and 1829.

Early in November, 1817, the disease broke out in Mirzapore, just ow Allahabad. Macnamara (page 296) says that he will have several

occasions to record the progress of cholera during one season as far the west and northwest as Allahabad and Cawnpore; while subsequ the whole of the northwest and the Punjaub came under its influe It seems to him that these facts are best explained as follows: W the monsoon sets in over Bengal, the river Ganges becomes the g high-road of traffic between the home of epidemic cholera and the re western provinces. In April and May large fleets of native boats on their journey from Calcutta, Dacca, and other centers of trad Patna, Benares, Allahabad, Mirzapore, and Cawnpore; which la place they reach about August. A few of these boats sail up the r Jumna as far as Agra and Delhi, bringing a few scattering cas cholera along with them. They return to Lower Bengal before Ganges subsides in September. The influence of the pilgrimage Gaya, Patna, Benares, and Allahabad in increasing and spreading c era up and down the Ganges is well known; but Mirzapore is regar as probably second in importance to no place in India, being the r commercial depot for merchandise passing to and from Bengal, and from Central India and the northwest provinces. It is to Mirz that the majority of the country boats from Dacca and Calcutta in south proceed. Here they disembark their cargoes and the goo carried all over the neighboring districts. The merchants flock to zapore in large numbers, and from thence scatter themselves al India.

In subsequent years numerous outbreaks of cholera occurred in t of country boats, and stuck to them for long journeys, viz, from cutta up stream to Patna; and from Cawnpore down river to Cal Macnamara thinks "if we could trace their history, this must frequ be the case with a great number of the large fleets of country tra vessels proceeding up the Ganges and Jumna Rivers every year. believe that it is by this means and also by the land journey that c era has been carried up to Mirzapore and the intermediate countr so many occasions." It was supposed that in three months from commencement of the great outbreak in 1817, nearly the whole dency of Bengal, including some one hundred and ninety-six thous square miles, was overrun with the disease. But there were sev markable exceptions to this rule, as, for instance, in the great c Moorshedabad, half way between Calcutta and Patna, which w tirely free from the disease during the year 1817, although ch prevailed in many directions around it. This is easily explained situation; for it is placed eight miles west of the Ganges, so that in boats do not stop there; at the same time the great trunk road Calcutta to Benares passes far to the west of it, and thus trade travel sweep by the ancient and almost deserted capital of Benga

In the autumn of 1817, the Marquis of Hastings, with ten thou white troops and eighty thousand natives, was in the Bundlecund vince, just below Allahabad, the force being in three divisions, a towns of Saugor, Jubbelpore, and Mundlah, just below the infected of Benares, Allahabad, and Mirzapore. After creeping about for time among the lower classes of camp-followers, it suddenly burst with irresistible violence in every direction. The natives deserte great numbers, and the highways and the fields for many miles a were strewn with their bodies. The line of march of the white t soon presented a most deplorable spectacle. The greater part of sick were left behind, although the baggage and ammunition were tak away, and the carts taken to swell the number of ambulances. M who left the carts, pressed by the sudden calls of the disease, were

to rise again, and were necessarily abandoned. Hundreds dropped
n in every day's advance and more were left behind at every
ht's halt. The roads were covered with the dead and dying. The
es of encampment and the lines of march presented the appearance
a battle-field and the track of an army retreating under every cir-
nstance of defeat and discomfiture. In less than two weeks nine
usand men had succumbed to the pestilence. The Marquis, appre-
sive of the disastrous effect of his own possible death upon his troops,
e instructions, should this occur, that his body should be secretly
ied in his own tent. But the army was moved from its previous posi-
n on low and marshy ground, into the streams of which the natives
l thrown their dead, so long as they were able to carry them there,
November 19, to the high and rocky place of Gwalior, to the north-
t, from which time the disease became less virulent, and speedily dis-
eared. Macnamara suggests (page 429) "that the water on the low
und, from repeated contamination, kept the disease in constant
ivity, but, by moving away from the infected locality, getting rid of
camp-followers, and encamping on the banks of another and more
id river, the health of the troops rapidly improved." The sudden
ck of Colonel Pearse's army, in 1781, near Juggernaut, and of Col-
l Crockett's force, near the same place, in 1790, have been explained
he same way.

t will be noticed on the map that Gwalior and the River Sinde are
th of the Vindhya or central range of mountains; hence, the epi-
ic traveled west to Jeypore and Ajmere, and southwest to Kotah
Oodipoor, and south to Saugor, Bhopal, Oojein, Indore, and to the
at military station of Mhow, twelve miles south of Indore, and to
oda on the west coast, all north of the Vindhya Mountains. It
progressed to the west, but south of the mountains, by way of
vah, Pannah, Jubbelpore, and Mundlah down to Nagpore, in the
t central part of India. It will also be noticed that the great sandy
ert to the west of Ajmere was left free; also, the district between
Bay of Bengal on the east and Nagpore in the center of India.
latter, although sparsely inhabited, is not a desert, but its rivers
but little navigated, and there are few or no roads; hence, cholera
anced slowly, or not at all, across it. If blown by the winds, it would
e reached Nagpore very rapidly from Juggernaut and the Bay of
ngal.

From Nagpore, the great high-road southwest to Bombay by way of
r. Jaulnah, Aurungabad, Ahmednugger, and Poonah was soon in-
ved, in spite of a strong southwest monsoon which was blowing from
Indian Ocean. From Poonah it spread south to Punderpoor, at the
e of the great festival there, and was carried at once in all directions
the pilgrims; the number of deaths in a few days being estimated at
ee thousand. From there it went down the west coast to Kolapoor,
apoor, Goa, Mysore, Calicut, Cochin, and Quilon, towards Cape
morin, at the extreme southern end of Hindostan.

From the central point, Nagpore, it was also carried due south toward
derabad. A considerable body of Bengal and Madras troops had
n engaged throughout the early part of the year 1818 in the siege of
ndiah, seventy miles south of Nagpore. They escaped cholera, not-
thstanding the excessive heat, many privations, and the fatigue at-
ding their arduous operations. But when Chundah was taken
y marched for Nagpore, and when nine miles below it, they had scarce-
learned that the epidemic was in their vicinity, when many were at-
ked while loitering for water on the neighboring rivulets. Of sev-
ty cases admitted the first day, about twenty died the first night.

Jaulnah, near Nair, southwest of Nagpore, became affected. About one thousand men arrived at Jaulnah on July 4, 1818, in good health, but before they arrived at Aurungabad, toward Bombay, many were seized, and it began to prevail in Aurungabad soon after their arrival. Then the Russell brigade left Jaulnah for Hyderabad on July 5, and a few days after it attacked them and produced great mortality. It broke out at Hyderabad toward the end of July, was carried due south to Gooty, and to Bellary, just above the holy city of Bijjinugger, and to Banglore. In November it was at Seringapatam, that sink of nastiness, and so down to the southern end of Hindostan, through Central India.

In March, 1818, it was generated, as usual, at Ganjam, on the east coast, near Juggernaut; in May, it was at Vizagapatam; in July, at Masulipatam, at the mouth of the river Godavery; in August, at Nellore; in October at Madras. From Madras it went south to Pondicherry, Tanjore, Madura, Tinevelly, and Palmacottah, near Cape Comorin. It was also at the holy island of Ramwieseram, between India and Ceylon, and was carried over to Ceylon.

One of the modes of conveyance of the disease to the island of Ceylon is well told by Dr. Knot, of the Sixth Dragoons. He says the cholera of 1817 traveled down the east coast of India, frequently in opposition to a strong current of wind, in the track of human footsteps and commercial intercourse, till in the beginning of the year 1819, when it reached that part of the Coramandel, or east coast, which is opposite Ceylon, whence it was conveyed across to the island; possibly also by pilgrims to and fro from the holy island of Ramwieseram, situated in the strait between Hindostan and Ceylon. It made its appearance at Jaffna, the nearest town to the coast of Hindostan, and the capital of a large and thickly-inhabited commercial district. From Jaffna it spread southward to Colombo, the present capital; where it was at its height in April, 1819. From Colombo it went eastward to Kandy, the old capital of Ceylon, showing itself only where human intercourse was constant and frequent. From Jaffna it was also carried across to Trincomalee, about the same time that it arrived there by sea, with the ships Leander and Topaze.

Its introduction into the Mauritius from Ceylon is described by Surgeon James Foy, of the frigate Topaze. The Topaze arrived at Trincomalee, Ceylon, on September 5, 1819, with seventy-two sick, most of dysentery. A sail-maker died on board, of cholera, on the 16th, and a marine and a seaman on the 20th; others recovered. The Topaze sailed for the island of Mauritius toward Africa October 9, and soon after cholera broke out again, with seventeen cases, and four deaths. She arrived at the Mauritius October 29. Six out of fifteen cases sent to the military hospital died; among them, four of the sequelæ of cholera, and four more who were sent to Tonnelier Island; all of them having only partially recovered from cholera and subsequent dysentery. Six more cases convalescent from cholera were landed. The first fatal case was in the hospital, and the second did not occur till November 1, and then in the person of a negro employed on the quay. In about three weeks after the arrival of the Topaze fifty or sixty deaths were occurring daily, and soon afterward it appeared in other parts of the island with equal fury. It was said that no case occurred on board the Topaze after her arrival at Mauritius, although almost all the merchant ships in the harbor lost some of their men; but a visiting physician saw one, and others may have been overlooked. The larger portion of the French physicians and the inhabitants thought the disease interior and introduced by the Topaze, while the English authorities were unanimous in the opinion that it was not. The governor of the neighbor-

nd of Bourbon, under the strong conviction that the affection was
municable in some unknown way, forbade all intercourse between
two islands; but notwithstanding two small slave-vessels, in Decem-
, slipped in with the disease on board, and after the usual interval the
9. pestilence broke out in such a manner as to leave no doubt of an infec-
n traceable to the slaves; as the first eight victims were slaves who had
ived in her. The governor, with great promptitude and energy, insti-
ed a thorough police-cordon against the town of Saint Denis, where
vessel had landed, conveyed all the sick to the hospital, and stamped
the disease, with less than two hundred deaths. In the Mauritius,
ere these precautions were neglected, it spread to a calamitous degree,
sing seven thousand deaths.

From the Mauritius cholera was carried to Madagascar, and thence,
ording to Haeser and Drasche, to the east coast of Africa, especially
Zanzibar; from whence it was also taken up to Muscat, at the foot
the Persian Gulf.

As this epidemic originated on the east coast of Hindostan, and the
mmerce with China and the immediate countries and islands was very
at, it was natural, if the disease was at all transportable, that it
uld be carried East toward China. It was at Arracan, coming proba-
both by sea and land, in 1818, and raged severely. The Burmese
r carried English troops and cholera into Burmah. In July, 1819, it
s at Bankok, the capital of Siam, having been introduced by English
ips, and ultimately caused forty thousand deaths.

In October, 1820, it reached Canton and Whampoa, in China, and
netrated into the interior of China. It visited Ningpo and Nankin,
d passed along the Yangtse-Kiang River into Central China. In 1821
was at Pekin, where it was reproduced in 1822 and 1823, and formed
focus of the disease in Northern Asia. According to Livingstone
d Drasche, it penetrated Chinese Tartary from Pekin, and traveled
rthward from Chinese Tartary and was then lost to sight.

From Arracan it is also said to have spread to Pegu, Rangoon, and
ngapore in 1819. At the city of Malacca four hundred died in a few
ys. It appeared at the island of Penang and at Atcheen, in Sumatra,
1819.

In Java, the first cases were noticed at Samarang in April, 1819, from
ence it seems to have spread south to Japara, and north to Batavia, in
ay. It reached its height in Java in 1820 and 1821, and one hundred
d fifty thousand persons died of it. In Java it first appeared after the
rival of trading-junks at Samarang.

It arrived in Borneo in 1820, and reached the Celebes Islands, and
e Moluccas, and Amboina in latitude 5° south and longitude 130° east
om Greenwich. The Moluccas suffered after infected Dutch vessels
om Calcutta had arrived. The Philippine Islands were reached in
20. (especially Manilla on October 5, 1820,) by vessels from Bengal.
t Manilla it is said to have appeared after the arrival of vessels from
fected places, and many ship-captains preserved their crews by forbid-
ing all intercourse with the land. From Manilla it is reported to have
en carried over to Canton and China.

At Bankok it was supposed that cholera arose from an evil spirit in
e shape of a huge fish which had entered the Gulf of Siam; for the
isease seemed to come both by ships from the sea and vessels down the
eat river Memam. A great religious solemnity was held on the coast
exorcise this devil, but the disease broke out with redoubled fury
mong the credulous masses, and killed seven thousand persons in a
hort time.

In the island of Sumatra the epidemic was so violent at the capital,

Atcheen, that the King went into camp at the mouth of the river: but it followed or accompanied them, and soon numbered its victims at the rate of sixty per day.

At Manilla the springs and fountains were supposed to have been poisoned, and the terror and rage of the populace were so great that an insurrection was caused in which many Europeans and a great number of natives were killed. At Pekin the pestilence was imagined to arise with a great yellow fog from the Yellow Sea.

We have already had hints how cholera arrived at Bombay on August 10, 1818. We will now trace it back to Nagpore, in Central India, more carefully. The first case in Bombay came from Panwell, half-way between Poonah and Bombay, where it was prevailing. The progress of the pestilence from Nagpore, in Central India, down to Bombay, has been carefully watched, and they were enabled to trace it from city to city, and creeping along from village to village, by the arrival of persons from places where it was known to prevail; some places escaping for months where this sort of communication did not take place. It seemed capable of transportation from place to place. (See Report of Bombay Medical Board.)

In the European barracks in Bombay nine cases occurred in six days in one ward, which was badly ventilated and too much crowded with men. This was immediately emptied, scoured, and fumigated, and no more cases occurred.

In some instances it was confined to particular houses or isolated spots, affecting whole families; in others only one case occurred.

In Bombay it was almost restricted to the poorer classes; not many of the higher orders suffered and very few Europeans were attacked.

Of the native troops, newly raised corps, which were more drilled and possessed fewer comforts than the old Sepoys, suffered most, especially if deficient in clothing to protect themselves against rain and cold. None of Ogilvey's hospital attendants were attacked.

Dr. Taylor's (president of the Bombay Medical Board) first case was a man who had just returned from Poonah, where the disease was prevailing, through Panwell, where it also existed. His wife was the next victim, and then the wife of a neighbor; then it spread through the lane where they dwelt.

The next fatal case was near the jail, in a populous district, and soon after numbers were attacked, but only a few died; and a distinction began to be made between fatal and non-fatal cases. In the end it is supposed that only twenty-five hundred persons died out of nearly nine thousand attacked.

Dr. Taylor was in doubt whether it was contagious, but fully believes that it was portable; for it traveled against the powerful monsoon winds, and was traced moving along the high road, from place to place. He repeats that its introduction into Bombay was clearly proved. He often saw three or four of a family sick at once, but only three of the forty-four assistants suffered, owing, perhaps, to their better food, accommodations, good ventilation, and cleanliness. The poorest classes suffered most, those who inhabited wretched huts, and slept, without a bed, on the mud-floor, with scarcely a cloth to spread under them.

It will be noticed that the road from Bombay first runs southeast to Poonah, in order to get through the western hills or ghauts, and then it turns sharply to the northeast. At Seroor, just above Poonah, Dr. Burrel had almost every one of his thirty attendants in hospital affected in six days. There was, doubtless, some defect in the arrangements.

Dr. Jukes repeats that cholera traveled along the high road from N[illegible]

e to Bombay, and that he had not heard of any village near Bombay t received the disease without previous intercourse with affected ces.

The first case in Poonah was a soldier belonging to a detachment ich left Seroor while the disease was very general there. Several sol- rs fell ill on the march, and were sent into Poonah. The same troops nt on to Panwell and Bombay. Neither Dr. Jukes, his assistants, or spital attendants were attacked. Nor did it run through many Euro- n families. Although it seemed portable, it did not act like a com- n contagion. It crept from village to village, prevailed for a time, from two to six weeks, and then declined.

Surgeon Coats went with twelve hundred men from Poonah, in June, Ahmednugger, and to Toka, twenty-five miles southwest, a place ch resorted to by pilgrims, where he learned that cholera was pre- ling at Aurungabad, to which it had been brought from Nagpore and alnah; for its progress through the villages, and along the post-road m Nagpore, could be distinctly traced. He found cholera in Colonel Dowell's camp, into which it had been introduced from Jaulnah. om there he fell back to Nassick, where cholera was also raging se- ely, three hundred having already died, and was informed that the ase had been brought by some individuals from Ahmednugger. out one in forty of his men were attacked on their various marches. was led to consider it infectious, but only under some peculiarities constitution. If it was occasioned by some general distemperature the air, he thought it would have spread over the country with more gularity, but it seemed only to travel over the roads; and where the pulation was scanty, and the intercourse slight, its progress was slow.

Surgeon Daw, of Aurungabad, says: "Bowel complaints were much ser in number, and cholera took their place. In a body of troops who termined to live temperately, and avoid the night air, only one in a ndred were affected. A reckless part of the same regiment lost one- nth of their whole number."

Surgeon Wylie, of Nagpore, says: "It commenced there in May, 1818, ming from the northeast, and advancing gradually in a southwestern rection to Nagpore, committing terrible ravages; it seemed limited to rtain tracts, and did not spread by any general atmospheric cause." At Kandeish, many families of Sepoys on their road from Jaulnah ed of cholera, and those who arrived were the first that suffered.

In other places persons going over the ground of these marches found olera prevailing in every village; having commenced soon after the ssage of the affected troops, and the inhabitants were sure they had got from these afflicted detachments.

Surgeon Kellies, of Jaulnah, says cholera prevailed in Nagpore during ay; when they heard of the march of Captain Doveton, from Nagpore, ith a detachment in which the disease existed, they were curious to e it the sick men would bring it with them. He says the troops ar- ed toward the end of June, and cholera commenced among us on ly 3.

Palmer's party of twelve hundred men arrived at Jaulnah on July 4, d marched on the 6th, without sickness; but before they reached urungabad many of them were attacked. The disease began in urungabad soon after their arrival.

Jaulnah is between Aurungabad and Nagpore, and has a fort and antonment for English troops. Surgeon Kellie had hospital patients ized with cholera after some sick with the disease had been admitted. he Sepoy attendants were attacked, and others had to be forced to their

duty. When a family was invaded, several others were apt to be attacked. He regarded the affection as a specific morbid poison, which was reproduced in the body and given to others in some way unknown, but usually by apparently direct contagion.

We have been thus particular in describing the conveyance of cholera from the banks of the Ganges through Nagpore to Bombay, in order to elucidate some of the peculiarities of the disease. Sometimes it seemed infectious, at others not. Sir Gilbert Blaine summed up the whole difficulty admirably, when he stated "that it was capable of being transported from one place to another; and to possess the power of propagating itself, by the acquisition of fresh material with which to assimilate, but subject to particular laws, with which we might never become acquainted." In Bengal the advance of the disease seemed very irregular and incomprehensible. Its mode of falling upon a place and its career in particular districts being singularly capricious. Sometimes it would make a complete circuit around a village, and, leaving it untouched, pass on. Then, after the lapse of days or weeks, it would suddenly return and, scarcely reappearing in the towns which had already undergone its ravages, as if they had been rendered pestilence-proof by one attack, would nearly depopulate the spot that had so lately congratulated itself on its escape. Sometimes, after running a long course on one side of a river, it would take a rapid sweep across it, and lay waste the opposite bank. This very capriciousness of its march was easily accounted for on the supposition that it was communicated by human intercourse; for nothing is more complex, varied, and uncertain than human travel. The persons who quit an infected spot go where they please; may not remain at the nearest village, but often journey to a distant one. Some travelers go from place to place, how and when they like, and as fast or slowly as suits their convenience. Their steps are unfettered and the modes of transport are ever at hand, and thus often sow a scattering fire of the disease in various directions. The pace comes the slow, steady transport of commerce, with an average daily progress by water, by boats or ships; or by land, with horse, camel, or bullock. The eccentricity is followed by a slow, relentless progress along highways. Although it skips about, at first, like fleas or skirmishers, it finally stalks from district to district, and from kingdom to kingdom with the regularity of mail-service. It may be assumed that not more than one case in three or four of cholera is fatal, and not more than the same proportionate number are productive of other cases. Hence the fatal attacks will be separated by several which are overlooked, and by as many more which seem barren.

The presidency of Bengal contains much more than half of the population of the whole of India; and far more than the presidencies of Madras and Bombay. The valley of the Ganges is the most populous perhaps in the world, with a greater number of cities, large towns and villages, than any other, except China. The pilgrimages to many of its distant parts of it are numerous and almost incessant. Hence the progress of cholera along it seemed confused and undeterminate. But as soon as the disease reached Central India, where the population was sparser and the roads fewer, and every objective point was watched by intelligent and responsible army surgeons, the regular and progressive advance of the disease was at once noted. The reason why some places escaped and others were attacked became clear, and a better knowledge of the travels of the pestilence was obtained than in after years, when the novelty of the examination had worn off and carelessness of observation prevailed.

Numberless instances, like that of the frigate Topaze, have since

ered, in which the disease died out at sea; but convalescent patients, ded clothing, and perhaps contaminated bilge-water, introduced the order into other cities and harbors.

ARABIA AND PERSIA.

In 1821, cholera first extended to the WEST beyond the confines of ndostan, viz, to the islands of Kishme and Ormuz and to the city of uscat, on the Arabian side of the foot of the Persian Gulf. It was id to have been brought to Kishme by a convoy of English troops om Bombay to Muscat, both by slave-ships from Zanzibar and vessels om Bombay.

Cholera recurred in the Bombay Presidency and City in 1819, 1820, nd 1821, over one hundred and fifty thousand country and town people ving died of it. Whole villages were depopulated, and the terror was great in Bombay that the crews of many vessels loaded with cotton serted and fled in the night. Cannons were fired to shock away the pposed aerial pestilence, although the southwest monsoon had been owing against the disease for months from the Indian Ocean and rabian Sea. Tar and sulphur were burnt in the streets, in place of orough cleansing, ventilation, and disinfection of persons, clothing, d houses.

Then in 1821 eight hundred British troops, under Captain Thompson, ent to the island of Kishme, at the entrance of the Persian Gulf, and om there were sent to the north and rear of Muscat to co-operate with e Iman of that place against the Wahabees from Central Arabia. ext, three thousand more troops were forwarded from Bombay, under r Lionel Smith, to the island of Ormuz, near Kishme, and cholera oke out on both islands before June, 1821, having first appeared in e English garrison. Slave-ships from Zanzibar, which had lost many cholera, now began to arrive at Muscat, just below the Persian Gulf. The usual disputes about the origin of the disease of course occurred, though cholera had been raging in Bombay from September, 1820, to ay, 1821. In February, 1821, it was prevailing at Surat and along the rders of the river Indus, and about one hundred and twenty British ips and seven hundred and thirty country vessels were going annually om the infected ports to Muscat; so that opportunities for the convey- ce of the disease existed in such abundance that, if transportable at l, it had to arrive *per force* at Muscat. And it is distinctly stated that July, 1821, through the intercourse maintained by ships trading be- ween Bombay and Muscat, the infection was transported to the latter. esides, the harbor of Muscat is so completely inclosed by rocks and ountains that persons unacquainted with its location may easily sail y it, without ever suspecting its existence; so that it is very difficult r the winds to blow cholera into the harbor. By July 8, 1821, the pidemic had cost the Iman of Muscat at least ten thousand of his sub- cts; and Muscat had by no means suffered the most, as it had ex- ended over the great part of the Arabian province of Oman, and had tterly destroyed several tribes and races of Arabs toward the interior. n July it was raging at the island of Kishme, and Mr. Fraser's party nd many of the inhabitants fled to Gomberoon and to Menab, just be- w it, to find the disease still fiercer in those localities. By this time t was at Bunder Abbassee, on the north side of the Persian Gulf, and ahrein, on the south side, where thousands of pearl-fishers congre- ate. On August 20, 1821, it prevailed in Bushire, the only Per- an port of any importance on the Persian Gulf. Bushire, in addition o being very dirty, has many low wells along its streets and suburbs,

so that it is difficult to avoid them when riding at all quickly on horseback. By the 29th it was in Kazeroon, on the caravan route to Shiraz. From the frequent communication between these places it was said by many writers to have been transported by travelers. At Shiraz it raged with great violence. The Prince Royal lost many of his family, including both his mother and son, and it is supposed that six thousand died out of a population ofthirty-five thousand, the rest having fled.

Ispahan refused to admit caravans and travelers from Shiraz, and escaped the disease this year. These were forced to go east to Yezd, where the pestilence broke out in September, died out in the winter, and went on next spring by caravans to Nain, Kashan, and Koom.

In the mean time the epidemic had also broken out in Bassorah, at the head of the Persian Gulf, distinctly stated to have been brought up by English ships. This town has much trade with India, especially with Bombay and Surat. Eighteen thousand are said to have died in this dirty and unhealthy town. From there it went up the river Euphrates to Hillah, and to the two great holy towns, Meschid Ali and Meschid Hossein, near by. Also up the Tigris by boats to Bagdad which became infected together with the surrounding country. At this time a Persian army menaced Bagdad and defeated the Turkish force collected before it for its defense. But a few days after the Prince Royal of Persia saw his troops devastated by this new enemy and recoiled from it. After he had lost two thousand men by cholera, he fell back to Hamadan, losing from thirty to forty men per day, and did not stop his retreat until he reached Tabriz or Tauris, to which another column of the infection was coming up by way of Kasbin, Zengan, and Maraga. From these towns it was carried to Reshdt, the principal port, at the foot of the Caspian Sea; and from there back east to Balfrush toward Astrabad.

From Bagdad and Hillah it was carried up, by pilgrims and travelers from Meschid Hossein and Ali, to Mosul, Diarbekir, Orfu, to Aleppo, and to Antioch and Alexandretta or Iskanderoon on the Mediterranean Sea, and from there down to Tripoli, toward Damascus, where it broke out in 1823. We have the authority of the French consul (the celebrated Lesseps) that the irruption of cholera was coincident with the arrival of the Bagdad caravans at Aleppo, and that the intermediate towns of Merdin, Mosul, Diarbekir, Orfu, Bir, and Arbil had already been infected by them.

From Tabriz or Tauris, where forty-eight hundred persons are said to have died in twenty-five days, it was carried west to Erzeroum, near the Black Sea, and north to Tiflis and Astrakan in September, 1823. There it also died out in 1823, in the winter, not to re-appear for six years. In 1829 it was again brought up by the same route in 1829.

There is but one pass through the Caucasus Mountains above Tiflis, and it was particularly noted that it crossed this defile with great numbers merchants and travelers. They were contagionists in Astrakan in 1823, and the disease was stamped out. They were not in 1829, when the infection again arrived, and it not only became epidemic, but was carried up into Russia. All along the borders of the Mediterranean, the most vigorous measures against contagion and infection were taken in 1823, and the disease was prevented from reaching Europe in that direction. The French government was particularly active in recommending this course.

We have thus minutely described the progress of cholera along the PERSIAN GULF ROUTE, because many succeeding epidemics followed the same course, affected the same places, and, with greater facilities of travel, and larger numbers of travelers and pilgrims, have often reached Russia and Europe.

CHAPTER III.

IE EPIDEMIC OF 1826 AND 1827 IN INDIA, WHICH REACHED RUSSIA IN 1829, ENGLAND IN 1831, AND THE UNITED STATES IN 1832.

The epidemic which reached Orenburg and Astrakan in Russia, in 9, was of course preceded by repeated outbreaks in India.

According to Scott's Madras Reports, "the year 1822 was marked by almost absolute rest from cholera in India. The great epidemic ich had arisen in 1817, and well-nigh covered Asia during the next six rs, had now subsided."

It had been present in June, 1821, at Juggernaut to such an extent it the car of the idols could not be dragged about. In 1823 Cuttack d Balasore, near Juggernaut, suffered severely again. In 1824 it was in ntral India, especially at the cantonment of Mhow, near the crowded l filthy cities of Oojein and Indore. During the early months of 1825 have a repetition of the old story. "The pilgrims at Juggernaut fering severely; cholera again at Calcutta; also it is again at ow; the rest of India comparatively free." Early in 1826, it s evidently on the increase throughout the whole of the lower Ben- . By May 13 two or three hundred cases a day were carried off in the y city of Benares, half way up the Ganges. In November, 1826, it was h up the rivers Ganges and Jumna, at the large cities of Delhi, Mut- , and Agra. In May, 1827, it prevailed in an epidemic form in all the lages for miles around Agra, and an immense number fell victims. June it was again in and around Delhi to an epidemic extent. It was n found to have been present at Hurdwar in the spring. In June it was Nahin, in the Himalayas, 3,000 feet above the sea; and at Sabathoo, o in the mountains, by the 18th. It was prevalent through the whole njaub, or extreme northwest province of India, in 1827; especially at hore, northwest of Hurdwar. Suddenly it was heard of at Teheran, ar the Caspian Sea, in 1829. The Government Calcutta Gazette says: "We regret to state that the greatest consternation prevails at Teheran, capital of Persia, in consequence of the appearance of cholera, ich has gradually advanced from Herat in the east, through the vince of Khorassan to Teheran, the Persian capital," "only seventy les south of the Caspian Sea." At Herat, King Mahomed and Prince ursan, the last member of the royal family in Affghanistan, have len victims. His Majesty, the Shah of Persia, has left Teheran and ired to the mountains. The princes and nobles are following his ex- ple; the lower orders are flying to escape the pestilence." There is doubt that the pestilence was in Herat in 1828 and 1829, for Lieuten- t Connolly, in his Journey to the North of India, from England, ough Russia, Persia, and Affghanistan, in 1830, vol. 2, p. 5, says: The year before our coming to Herat, (*i. e.*, in 1829,) cholera had swept ay many thousands of persons from the city and provinces around." asche, p. 19, says, "In 1827, cholera was in Lahore, Cabul, and even Cashgar, in Central Asia. In 1828, it was at Herat and Bokhara, d is even said to have reached Khiva, at the foot of the Sea of Aral." While this was going on it was again carried east from India to China, pecially to Pekin, in 1826. By December, 1826, it had crossed the

Chinese wall and was spreading through Mongolia to the west. It reached Kiachta—50° north latitude and 110° east longitude—to which all the great Russian caravans come for tea and Chinese goods, and then return by way of Irkutsk, Tomsk, and Omsk to Orenburg and Moscow in Russia, but especially to the great fairs at Nijni-Novgorod. Hence Russia was threatened in three directions, viz, by way of China, Central Asia, and Persia.

On August 26, 1829, the first fatal case occurred in Orenburg, but it was not until the 10th of September that its true nature was discovered, the usual disputes of course arose about its origin. The question was for a long time a difficult one. Orenburg lies high, on a dry, sandy loam; there are no woods, marshes, or putrid water about it; the streets are straight, and rather broad and cleanly; all the necessaries of life, as wheat, fish, and meat, were cheap; and there was nothing peculiar in the weather. But it must have had some sanitary defect, as it was subject to epidemics among the cattle, which annually destroyed a great number. The stables, barn-yards, and, doubtless, privies may have been very foul. Six thousand of its inhabitants were soldiers, a large portion of whom spent their lives on outpost duty, toward Central Asia. It was next learned that the Khan of Khiva had commenced a campaign on the frontiers of the Persian province of Khorassan, and had been compelled to retire on account of a virulent outbreak of cholera, which swept away a large portion of his army. He set out in May and was driven back before the Bokhara caravan arrived. Next Major-General Danilevski, then in Persia, sent intelligence to St. Petersburg that cholera had repeatedly made its appearance in Persia, especially in Khorassan. Then the Kirghis tribes, which live due southeast of Orenburg, toward Khiva, reluctantly supplied clear and convincing evidence of cholera having shown itself among some of their hordes on the rivers Ilek and Embo. The former river empties into the Ural, just below Orenburg; and the latter into the Caspian Sea, east of the mouth of the Ural: both of them lie southeast of Orenburg, in a direct line to Khiva. The constant distrust of the Russians by the Kirghises, and their jealous reserve, greatly impeded the procuring of distinct proof for a long time, although they carried on a continual barter along the whole line of the province of Orenburg, especially in the summer and harvest, for sheep, camels, felt, skins, &c.

For a long time the exemption of the fortresses of Orsk and Troitsk was regarded as sufficient evidence that cholera was not introduced by the caravans; but both of these places lie to the northeast of Orenburg, toward Siberia, and cholera was brought from the southeast, in the direction of the Sea of Aral.

The first victim in Orenburg was a soldier; the second, the wife of a military officer; the third fatal case, a week after, was a carpenter, a serf of the military governor; the fourth, on the next day, viz, September 11, 1829, a soldier from the same battalion as the first victim. The outbreak now commenced causing seven hundred and forty-seven deaths by the 1st of October, or nearly one-fifteenth of the whole population. It was proved that the first fatal case occurred thirty-five days after the arrival of the caravan that came by way of Troitsk and Orsk, and this is doubtless correct. But six or eight caravans arrive every spring and summer from Bokhara, some of them going north of the sea of Aral, and others south; yet these southern caravans were overlooked, except one from Khiva, which arrived seventy five days before. When there was but little fruit cholera prevailed with violence; when unripe or spoiled water-melons were freely used, it did not appear at all. The rye-crop was spoiled, and the

ars, who used it, were among the first attacked. At first it was sup-
d not to be infectious; but it was soon noticed that it was inclined
read in families; that it frequently broke out in various towns
e a single person sick with cholera arrived, or died; that in many
s close to where it was prevailing, it did not appear, because no
had arrived in them affected with it. Few whole familes were ex-
inated. Generally in a family of ten individuals only one, two, or
were attacked. It usually seized one or two persons in a house,
ing successively to others, with intervals between each; but never
any or all at one time. This is explained by the fact that there
no chance for general water-poisoning, for all used the bright,
. clear, and pure waters of the large, broad, and rapid river
l. The only wells were those belonging to the hospital, engineers,
artillery. On October 10th, a month after the commencement of the
ise, and when it had begun to break out in neighboring villages, a
ary cordon was established around Orenburg and its suburbs, and
avelers were detained seven days. But it was found that some were
ked fourteen days after exposure. By the middle of October, the
cal board of Orenburg obtained information from travelers, and offi-
from the government, that cholera had been and was still prevail-
the central regions of Asia, especially at Khiva and Bokhara, with
h Orenburg has commercial intercourse every summer; and that the
spreading of the disease did not occur till after the renewal of this inter-
e, both with their nearest neighbors, the Kirghises, and with other
nt fixed tribes of Southeastern Asia. Finally, it was concluded that
ode in which the disease most probably spread was by the arrival
uninfected place of a person who had contracted a tendency to
disorder in the place where it was prevailing—then becoming ill and
municating in some way a diseased condition to the atmosphere of
ew residence. Then it seemed to increase and spread, seizing those
who were predisposed to it. Eight instances of direct conveyance
ascertained judicially by magistrates and physicians who were
bing the course of the epidemic. The extension of the affection
Orenburg was also decided to have depended on the migration of
nhabitants from infected to healthy places, which often happened
e it was detected in the former and before the enactments of the
l relative to quarantine were or could be put in force. According to
bservations first made in Orenburg, it was inferred that it did not
municate itself by direct intercourse with the sick; but in the sub-
nt progress of the epidemic the magistrates and physicians be-
convinced that it really passed from one person to another in
obscure way, and was thus conveyed from place to place. Its infec-
seemed peculiar. It was not as unequivocal as in the most infectious
ses, and its power did not develop itself in all who were in direct
course with the sick, especially at the beginning of the epidemic.
was it communicated by the winds, for it appeared now here, now
, skipping over many villages, and leaving large tracts of country
ached. It followed the highways, attacking in its course along
those towns first which, though more distant than others, were,
count of their size or commerce, more likely to be the resting-places
avelers; then returning, as it were, on its path to villages previ-
passed over; going from them to other neighboring villages not
e great highways, and remaining generally longest in the most
lous towns. In this way, in the course of six weeks it was traced
ree several directions along the great highways on which there
most travel, viz, towards Uralsk, in the northeast, Ufa, in the

north, and Kazan, in the northwest. Thus at Sterlitanaka, on the [illegible] road, one hundred and fifty miles north of Orenburg, during the annual fair of the town in October, many Tartars arrived from Kargala, where the cholera was raging with fury, and before it had been put under quarantine. The Tartars of the town were the first victims. The first suspected case was admitted into the hospital, but was dismissed in twenty-four hours, as it did not seem to be cholera; but in four days more it was brought back with a fully-developed attack, and three days after others were brought from the same house. The importation of the disease into Iletsk, forty-three miles southwest of Orenburg, was also [illegible] proven.

By July 21, 1829, the Russian authorities had news of the previous of cholera in Cabul, Bucharia, Tashkent, and latterly in Khiva. It was carefully stated that the caravans which arrived at Orsk, due west and north of Orenburg, were healthy; but those which came from the southeast, direct from Khiva, were not examined. The clothing and baggage of the travelers were not looked into, but the Russian authorities ordered the Buchareans to take out some cotton from the middle of every bale and chew it, and to pass it from one to another for that purpose. The Tartars, laughing at the fears of the Russians, pulled out the cotton indiscriminately, without precaution, chewing it readily and tossing it to one another. Hence it was concluded that merchandise did not convey cholera; but clothing and baggage were allowed to pass into Orenburg. Only October 23 were they satisfied from private letters that cholera had broken out that year in Bokhara, and that it had been rapid in its effects and spread. Although some of the Orenburg caravans arrived healthy, others did not.

The first case in Orenburg was reported late in August; but in fact a tradesman went with his brother to barter with the Bucharean merchants of another caravan. After being a whole day with these people he was seized with violent vomiting and diarrhœa. In reply to inquiries whether any of the Buchareans were ill of a similar complaint, it was asserted that some of them certainly were. The disease was not checked in Orenburg till prohibition of intercourse between the diseased and healthy houses, separation of the sick from the sound, institution of cholera-hospitals, and, finally, complete purification of the places which had been attacked, had been enforced.

In a Mohammedan village near Orenburg it raged for sometime before the government was informed, as the inhabitants endeavored to conceal it; but one of their people, going to a neighboring village, died of the disease, followed by forty-one others. At the first intelligence of the arrival of the pestilence at the above place, the Russian peasants of a hamlet only eighty yards distant shut off all communication and entirely escaped. It was carried to one village eighty miles from Orenburg by October 14, and to still another, eighty miles farther, by November 7, then turned back and attacked a third, thirty miles north of Orenburg on December 5. The first place affected from Orenburg was on September 28, at the Fortress Rasypna, sixty-six miles to the northwest, to which the Tenth Cossack Horse Artillery was sent. A tavern servant also died there the day after his arrival from Orenburg. Of the other cases could be traced directly to the latter. It seemed rather unaccountable that places near Orenburg, and in constant communication with it, continued completely healthy. In the middle of October it appeared at two fortresses between Rasypna; while another, only two miles from the city, remained free till January 19, 1830. October 7 reached Iletsk, a fort forty miles southwest of Orenburg. October

N
JUTLAND
P
H
T U R

a village twelve miles from Orenburg, on the high road to
ing over Berdsk, seven miles nearer, until the 18th. On the
as heard of in places sixty and one hundred and twenty miles
ward Kazan, on the River Volga; while it did not appear
eal later in four or five small towns, on the same highway,
or thirty miles from Orenburg. By the beginning of No-
s two hundred miles northwest on its way to Kazan, with a
its from Orenburg, at the same time that it had reached towns
one hundred and twenty miles due north, toward Ufa and
is an important point, as a great dispute arose subse-
nt the origin of cholera in Perm. Two persons were the
d in one town, after they had undergone fourteen days
this side of Ufa. It was afterward proved by other cases
on for fourteen days was not a sufficient interval between
d seizure in every instance. But it was nowhere proved
lera passed directly from the introducing parties to the first
were in communication with them immediately on their
ere appeared to be some intermediate process required in
ces, as some persons seemed to have no predisposition for
other cases, it tended to spread in families. In eight or ten
illages the first persons attacked had just come from Oren-
thers no connection could easily be traced by the superficial
ns which were then, and are still, made.
been thus circumstantial about the origin of cholera in
in order to save repetition, as similar difficulties and obscuri-
met with in many, if not in most, large towns in which the
sequently occurred.
st appearance, the Orenburg physicians, although warned of
ly infectious nature, by a proclamation from the supreme
St. Petersburg, universally believed it, from their first ex-
o be incapable of communicating itself, either directly or in-
om person to person. But ere long a considerable majority
o change their opinion. While they were looking for the dis-
the northeast, it slipped in from the southeast. The lowest
rticularly those residing in damp, confined, and dirty apart-
e most subject to the disease, and did not come early under
vation of physicians or magistrates. In the majority of in-
ly one fatal case occurred in a family, and the non-fatal ones
looked; although in not a few instances after attacking one
sons in a house, particularly the servants, it passed succes-
others, with intervals between each, showing that it was re-
in some way in the affected dwellings. The deaths among the
people were not the first which attracted attention, and the
did not always tell the truth promptly and frankly, nor did the
lcers. The first fatal cases were few and far between, and did
directly connected with each other by an unbroken line of lethal
Debility and strength appeared to have less to do with the
dition to the complaint than some obscure exposure, or unknown
the system; for the propagation of the disease by the stools
cted water was unsuspected.
this was going on in the north at Orenburg, Astrakan, at the
he Caspian Sea, became affected for the second time; having
since 1823. The teachings of that epidemic had been forgotten,
ories about spontaneous origin and latent germs began to prevail.
It had been noticed to have proceeded regularly and steadily
ard from Persia toward the Caspian and Black Seas. It then first

reached Reshd, a large and populous place, and the principal pl... commercial intercourse between the Persian Gulf and Caspian Sea. ... was next very prevalent and fatal, successively, at Enzellee, Kisliar, ... Lenkoran, on the west coast of the Caspian Sea. Then at Salian, at ... mouth of the river Kur, going up its southern branch, the Aras River. Khor, Erivan, and Kars, to which places it was also coming by land fr... Tabreez. Then up the northern branch of the river Kur to Elizabeth... and Tiflis; to which cities it was also coming by land. Tabreez suf... very much in 1823, again in 1828 and 1829, and afterward in 1830, ... it lost five thousand of its inhabitants. Erivan, which is large and p... lous, but very dirty, suffered in 1822 and 1823, and again in 182... 1829. In Tiflis it prevailed in a frightful degree in 1822 and 182... was brought to it again on August 8, 1830.

Above Lenkoran, on the Caspian Sea, Baku, the chief port on the ... coast, had the disease in 1822 and 1829. North of Baku, Derbent ... severely affected in 1822, and more so in 1829. Then comes Astrakan, ... the mouth of the Volga, the chief commercial emporium between A... and Europe, and between Persia and Russia. In 1823 it was beli... to have been imported into Astrakan from Baku, Salian, and Lenkor... where it was then prevailing. For thirty-four vessels arrived at As... kan from these infected ports, and on one of them eight persons ... died of cholera, to which the civil authorities paid no regard, in the ... fortunate belief that cholera could not be imported. An infected ... of-war, the Baku, from Baku, was detained at the quarantine, sixty ... below Astrakan, in 1829, by the military authorities, on July 15, ... restrictions were placed upon merchant-vessels. All was tranquil till A... gust 1, the disease being confined to the quarantine station. But Dra... p. 20, says isolated cases had occurred in Astrakan in the previous ... and winter. Then four persons sickened in Astrakan close to one ... outlets of the Volga, and from there spread imperceptibly through ... city. It increased slowly, appearing during the first days in a ... number of persons only, and was concealed. Then it was proven ... cases had occurred before August 1, but of which the magistrate ... not been made aware. It was only when a person who had been ... overseer of a cholera-hospital in 1823 was attacked, and had his case ... ported to the police, that the town was awakened. It was then found ... a man had died in the same quarter the evening before and been inter... privately. In all there were twelve hundred and twenty-nine att... and about five hundred deaths in Astrakan, including the chief ma... trate and many of the police. By August 8, villages from two to ... miles distant began to be involved, to which many families had ... from the city. By the 10th it was on the high road overland to Mosc... in the persons of those who sickened on the road and perished, after ha... ing over the disease to others. Many gardens and farms near Astrak... which had cut off all intercourse, remained exempt, also many villag... while the disease raged all around. The Tartars immediately ab... doned those attacked and sought other encampments, but still car... the disease with them in the form of diarrhœal cases. Dr. Rehman ... ferred that it was infectious, because it did not spread regularly ... masses, but by leaps, sparing places where it was to be expected, ... came by the atmosphere, and attacking others in which its arrival co... only be explained by the coming of infected persons. Still, the m... ity of the physicians regarded it as void of contagion. At Krasn... which lies to the east of Astrakan, the wind blew directly from the ... east and southeast all the time; while only westerly winds could br... it. But on August 6, an infected soldier and girl arrived from As...

n, and the outbreak commenced. Comparisons were instituted be-
een the infectiousness of plague and cholera, in which it was assumed
at five out of ten exposed to the former disease might take it,
ile of cholera only two out of ten might contract it, unless under
nditions peculiarly favorable. Thus in places where multitudes lived
remely compacted, in miserable abodes, the infection and malignity
the disease obtained its highest degree; while in other places, with
rer persons in more spacious dwellings, it seemed scarcely to make
adway. The bed and body clothes of the sick and dying were ob-
rved to spread the disorder at times, clean merchandise did not. It
owed itself in no person from the quarantine-ground, but in remote
abitants of the town. Also it appeared severely in various districts of
e city in persons who had no acknowledged intercourse with each
her. No tainted persons could be traced to the ship of war Baku,
t the crews of thirty vessels, all from infected ports, and some with
olera on board, had been let loose all over the city. At first, phy-
ians and hospital attendants escaped, but finally three doctors died,
ne hospital attendants, and a majority of the female nurses; doubt-
s because the privies and the ventilation were not well attended to.
nally 8,000 out of 60,000 inhabitants died in Astrakan. Then it went
p by step up the river Volga to Zaritzyn, August 16, and Saratov on
e 18th. By August 12, one hundred persons were attacked daily in
strakan, and 3,000 died in Saratov. On September 8, it was at
mbirsk. On the 27th at Kazan, near the junction of the Kama
er with the Volga, to which it had come both from Orenburg and
strakan, both by land and water, with 2,000 cases. From Saratov it
so struck overland to Penza, toward Moscow, by August 29.

Toward the end of August it was at the great fair at Nijni Novgorod,
ong the boatmen employed on the Volga; but as the market merely
sts during July and August, only one thousand and sixty-eight per-
ns were attacked up to October 15.

By August 23 the Emperor of Russia, through his medical advisers,
d announced his fullest conviction of the propagation of cholera by
species of infection, then first called contingent contagion, and had
dered isolation of infected persons and places, and a quarantine of
urteen days against persons proceeding from infected towns; and that
eir clothes should be washed with chlorine or other disinfectants, but
ods and merchandise could pass free.

From Kazan it was carried far to the northeast, to Perm, by a party
prisoners assembled there from different parts of the empire. They
ere conveyed to the jail beyond the town by a detour so as not to pass
rough the city of Perm at all. A few days after the cholera broke
t among them and spread to other prisoners, fifteen of whom died,
d two soldiers. It is supposed that it was also brought up from Oren-
urg by way of Oufa, and this accounted for some of the mystery
hich at one time attended the outbreak.

From Penza it was carried overland northwest to Riazan, toward
oscow. But long before this, near Taritzin on the Volga, it turned off
ward the river Don, which is there quite near, and traveled down
ward the Sea of Azof and the Black Sea, attacking Rostoff, near
herkask, by September 10, 1830; and Taganrog and the town of Azof
on after. From thence it went to the Crimea, especially to Kertch and
bastopol by ships, some of which were also attacked on the open sea,
d carried the disorder over to Odessa by the middle of October, just
fter all quarantine regulations had been abolished, as the season seemed
o far advanced for the pestilence to arrive. It is also authoritatively

stated that Sebastopol and Odessa became infected shortly after the arrival of Russian ships of war, which had touched at Kertch, near the straits of Kertch and other infected ports.

In the mean time cholera had been traveling up the river Don, as well as down it, and again toward Moscow, by way of Voronetz and Toula. It also traveled up the river Donetz, which empties low down into the Don, and went on to Moscow by way of Kharkof and Koursk. Then it was carried by land across the top of the Sea of Azof and Black Sea, reaching Ekaterinoslav, on the Dnieper, Cherson at its mouth, and Odessa on the Dniester. It will be noticed that it reached Odessa both by sea and land.

By this time Moscow had become completely surrounded by the epidemic, for cholera had reached the province of Tver, to the northwest; those of Vladimir, Jaroslav, and Kostroma, to the northeast; of Nijni Novgorod, to the east; of Penza and Riazan, to the southeast; and finally of Kalouga and Koursk, to the south. If the province of Smolensk on the west had been involved, Moscow would have been surrounded by the pestilence on every side; for the province of Moscow is impacted between those of Tver, Vladimir, Riazan, Toula, Kalouga and Smolensk.

Many preparations were made in Moscow. Twenty cholera hospitals were provided, viz, one for each district of the city; and police inspectors and district physicians, with a magistrate and spiritual overseer for each section. The disease could steal in, in so many ways that no exact information was ever obtained of the precise period at which it first appeared in Moscow. It was never known which were the first cases, or in what part of the city they occurred; which proves that no very keen or intelligent watch had been kept by the twenty magistrates, or twenty sets of police-officers and district physicians, and that no accurate or trustworthy reports were made. By the 18th of September it had already commenced its ravages. From the 24th to the 28th it was called sporadic; and after the pestilence had fairly formed a lodgment in the city, then all the means of preventing its entrance were immediately put in the most rigorous execution. The city was surrounded by a sanitary cordon. All the public establishments were shut. The markets and all places of business and amusement were closed. The twenty different districts were separated from each other by barriers and strong military posts. Up to the middle of September the health of the city was so favorable that the mortality was smaller than it used to be at this period. But as soon as the first cases were reported an inexpressible panic ensued; and in order to shut the wolf up in the sheepfold, all high-roads and by-roads were obstructed, vehicles were destroyed, and the bridges carried away. The military posts around the city were doubled, with loaded cannon everywhere, and no one was allowed to enter Moscow without undergoing fourteen days' quarantine. No attempt was made to stamp out the infection which had already gained headway, but all eyes were turned toward preventing persons absolutely sick with the disease from entering. Of course these violent and inconsiderate measures did not prevent the outbreak. Drasche (p. 21) says: "It was first introduced from the (makorjewschen) fairs of Nijni Novgorod, Moghilev, and Voronetz. At first almost all the Moscow physicians were contagionists; but when chlorine and chloride of lime failed utterly as a means of disinfection, their belief was shaken, and free ventilation, which would give ready access to the air-borne poison (if there were any such,) and washings, and sprinklings with vinegar and other acids, were found more efficient. Some little approach to estimating the power or weakness of the infection was made. In the

trict, in one hundred and one houses, only one case each occurred; in
rty-three houses, two cases each; in fifteen houses, three cases each;
ine houses, four cases each; in six houses, five cases each; in the dis-
t hospital, six attendants; in one house each there were seven, eight,
, ten, thirteen, twenty-one, and twenty-two cases; and in the police
sion twenty-eight cases, including the district medical officer, and
nty-seven policemen and soldiers. The greatest mortality took place
onfined apartments in which were lodged twenty-five or thirty ser-
ts, addicted to debauchery of every kind, drunkenness, and filth.
t as these places were generally located in low, wet, dirty, and marshy
ts, the greater prevalence of the disease was attributed to marsh
sm, aided by getting drunk, and eating pears, cabbage, cucumbers.
umerous instances had been adduced in which the disease had
med to be induced by soiled clothing and bedding; but in Dr. Zoub-
's hospital the man who received the clothes of the cholera patients
en they were admitted, another who distributed them to the laun-
sses, and the doctor who counted the pieces still soiled with choleraic
charges, all escaped with severe diarrhœas without dying. An enor-
us amount of exposure seemed not to cause the disease, but Dr.
bker and his assistant washed their faces and hands frequently
h vinegar, rinsed their mouth with vinegar; were careful not to
allow their saliva, and breathed through sponges soaked with vine-
in the vicinity of bad or dying patents. He also placed much stress
the fact that his clothes sometimes touched the beds of the sick and
ng; that his cloak was occasionally taken away by the same soldiers
o had carried the sick and dying, or was left in an ante-room; and
t the nurses and assistant surgeon sometimes touched him.

The outbreak of cholera caused such an alarm that fifty thousand
rkmen and many of the better classes fled the city before any sani-
y measures were adopted. The disease continued to appear till
rch, 1831, when 8,576 cases had occurred, more than half of which had
d. On October 11th, the Emperor himself repaired to Moscow, to
that everything was being done that could be done, and, on his re-
n to St. Petersburg, subjected himself to fourteen days' quaran-
e. This distinguised example elevated the spirits of the inhabitants
l led to numerous instances of generous and fatal devotion. Moscow
s now perfectly secluded, and St. Petersburg was protected by a
able military cordon.

No account of the number of doctors who died was given, but ninety-
ee of the clergy fell victims, being a much larger proportion than
ght to have been. This was explained by the fact that no Russian
s without the services of a clergyman.

The progress of the disease toward St. Petersburg, according to
s. Russell and Bury, is as follows. It first showed itself in several
uses and villages high up the Volga, above Moscow and Tver. All
pplies of provisions and goods from the interior being brought by wa-
, short inspections were established at these places and subsequently
Novgorod. Crews and passengers were supposed to be slightly
migated; but it soon become known that this trifling precaution was
en omitted or evaded, as it had been kept up for a long time and
false security was established. But in the mean time the cholera
s slipping along from Jaroslav by water to Tischwin, which is at the
ad of navigation of one of the streams leading to the east side of Lake
doga, to which place the confluents from Lake Ilma in the south
d Lake Onega in the northeast also lead, and to which all the boats
ngregate near St. Petersburg. Lake Onega is in the rear of St. Peters-

burg, and a merchant who came per boat from Wytegra on that lake was the first case recognized, on June 26, 1831, in St. Petersburg. The next two cases were residents near the boats. The fourth case was a man from Jaroslav. Of course no direct personal communication could be traced between any two of the first five or six fatal cases. Next, many were taken ill on board the boats, both coming from Novgorod to the south and from Lake Onega on the northeast.* By July 6, six hundred and fifteen cases and three hundred and eighty-seven deaths had occurred, and all St. Petersburg was in the midst of a solemn fast, with great religious and some riotous gatherings and processions. The churches were filled all day. By July 16, it was spreading with considerable rapidity, but not with the violence described in other cities, in which the origin of the outbreak had been less carefully watched. Three-grain doses of bismuth and rubbings with aromatic ammonia was the favorite treatment. Violent excitement arose against all foreigners, especially physicians, who were accused of having poisoned the food and water, and of giving poisonous medicines. In two days one German physician was killed; two narrowly escaped the same fate; and six others were severely beaten. This outbreak was only suppressed by the personal appearance and harangues of the Emperor. Fifteen hospital-physicians were attacked, and six died very early in the epidemic. In some hospitals none were attacked, and in others many probably in proportion to the amount of cleanliness and ventilation. Twenty thousand serfs broke the quarantine, and spread over the country. They beat the physicians and police at the barriers, and were aided by the neighboring villagers, who believed that attempts were being made to shut up and poison them. The epidemic soon broke out in the villages. In the mean time the pestilence was also being brought up from Riga, in the north west where it had previously occurred, toward St. Petersburg; and Narva and Cronstadt, between the two places, became affected by arrivals from both. It was generally admitted that its appearance was usually, if not always, preceded by the coming of persons or things or vessels, or all, from infected places. Some instances of long incubation of five seven to twelve days were noticed. Also that typhoid cases were common after reaction, with greenish, dark, and bilious passages, which did on occasion typhoid fever in the attendants, but genuine, cold, blue cholera, and the fear was expressed that persons apparently suffering with fever, but who were really and truly cases of cholera, would be landed in England and other places. In the majority of prisons and asylums the introduction of the disease was traced; in others it could not. The conveyance down to Cronstadt from St. Petersburg was clearly made out. Ships with the disease from Dantzic also began to arrive at Cronstadt. In the naval hospital, with two hundred and eighty cases, all the attendants, forty-two in number, escaped; and in the general military hospital, with two thousand cases, the same was noted, while in many instances only one case occurred in a large family. The grave-diggers escaped and ten men employed in carrying the dead. English and American ships were attacked on their arrival at Cronstadt, but it was noticed as curious, that of those seamen who had passed the summer there and become habituated to the disorder, none were attacked anew.

The Russian Baltic provinces of Courland, Riga, Livonia, and Esthonia up to the Bay of Finland, toward Cronstadt and St. Petersburg, became affected, in the west as early as March, 1831, before it broke out in St. Petersburg; so that, when it appeared in that city on June

* "There is complete water communication from Jaroslav to Lake Onega, and from Novgorod and St. Petersburg. Hundreds of market and other boats were passing

ıad long been closely surrounded by the disease in the east, south, l west. The Emperor and household, ten thousand in number, retreated Peterhoff and Zarskoeselo, on the Moscow road, shut themselves up h strict quarantine, and turned all the travel to the east and west of m, and all escaped, while the new roads of approach to St. Peters- g became affected.

While this was going on in the north, the disease had been pro- ssing up the river Dnieper to the holy city of Khiev. From Cherson, the river Bog toward Poland; and from Odessa, up the Dniester,) toward Poland. Also overland from Odessa, due west to Jassy, ard Vienna; and from Odessa down to Galatz, at the mouth of the nube; and by ships with cholera cases on board down to Constanti- ple.

n the mean time the Polish revolution of November, 1830, had broken in Warsaw, and masses of Russian troops were sent from Moscow, ere the disease lingered till March, 1831; and from the infected vinces of Novgorod, Tver, Smolensk, and Kalouga, (lying to the th and west of Moscow,) to the provinces of Mohilev, Minsk, Grodno, l Wilna, to the north and east of Warsaw. The provinces of Podolia l Volhynia, to the south and east, also furnished their quotas of in- ted troops. Thus Poland was surrounded by cholera in every Rus- n province on its borders. Battles took place at the towns of Ostro- ka in the north; Bialystok in the northwest; Siedlec and Iganie the east of Warsaw. The Poles were generally successful, and often upied the grounds previously held by the Russians; took many soners, and captured their arms and clothing which they wore. The ttle of Iganie took place on the 10th of April, and by the 12th the les commenced to be affected, as supposed, from drinking water fouled the sick Russians. This transference of the disease from the Rus- n to the Polish soldiers took place at least three times. Then the les fell back toward Warsaw, and cholera obtained a lodgment in aga, on the right bank of the Vistula, which is connected with War- w by bridges. The crowds of persons passing over these, aided by e evacuation of Praga, where the disease was already prevailing, in- duced it into Warsaw by the 19th of April, 1831. By a strange tality the Austrian cordon of troops, toward Poland, was withdrawn fore the evacuation of Warsaw, and large bodies of the Polish troops treated into Austria, where they laid down their arms; and cholera on broke out with extraordinary intensity in Galicia; so that al- ough the Austrian government had now been led to regard cholera a purely epidemic disease, it felt obliged to restore the quarantine ter the mischief was done. (Drasche, p. 25.)

From Warsaw it was sent down to Cracow, to which it was also already proaching by way of Lemberg in the southeast. It also went directly st to Posen, the border town of Prussia, by the 16th of July, and it d previously been noticed at Plock and Thorn, on the Vistula, toward antzic and Konigsberg. Brierre de Boismont, sent by the Academy of edicine in Paris, in March, 1831, to observe cholera in Poland, passed rough Posen across hedges of Prussian bayonets which extended for ght hundred miles from the northernmost point of East Prussia, from lemel on the Baltic to the southernmost end of Silesia. Travelers ere stopped every instant; the most active watch was kept, and Poles ere hunted back to their own country like wild beasts; but all without vail, for fugitives and smugglers were crossing all the time, not only y stealth, but openly by day. All night the soldiers were heard firing t the smugglers, who never ceased to cross in defiance of the sanitary

lines; and very few were shot or captured. De Boismont says the Prussian cordon was not established till the disease had been three weeks on the frontiers of Poland, and above ten days in Warsaw. Cholera showed its wonted capriciousness. In the old and filthy part of Warsaw it seemed to be contagious, or at least infectious; the sick became foci of emanation, infectious even to the robust. While nearly fifty hundred of the poorer people died, very few of the better classes were attacked. De Boismont and other physicians lived at the Hotel de l'Europe, frequented by hundreds of people, without changing his clothes in which he visited the hospitals; yet neither he nor any of his friends contracted the disorder. Drs. Janechen, Foy, Pinel, and Verat, of Paris, inoculated themselves with the blood, and tasted the discharges of cholera-patients, yet none suffered any inconvenience. Physicians and hospital-attendants were rarely attacked; so that in another large class of cases it did not seem infectious at all. But the physicians soon found out that they would rather live and sleep in a well-ventilated and clean hospital, than stay a few hours in dirty and crowded cholera-houses.

The disease had also slipped up the river Vistula in May, to Dantzic, and after it had already commenced there, it was hoped that its progress might be stayed by the establishment of a new double cordon of troops to keep it out, when it was already in. By June 28, 1831, it became epidemic in Dantzic, and by the 22d in Konigsberg on the Baltic.

From Thorn, on the Vistula, it was carried west to Bromberg, and a canal over to the river Oder, after which it soon appeared at Stettin, its mouth.

From Warsaw it was carried due west to Posen and Kalisch, by retreating Polish troops, who took refuge in Posen and Silesia. From Posen it also dropped down the river Wartha to the Oder, into which it empties. From Kalisch it was also carried to Breslau, high up on the Oder, and commenced to drop down that river to Frankfort on the Oder, near which there is another canal, connecting it with the river Spree, and thus it reached Berlin, while it was also coming overland from Posen. The first case in Berlin occurred August 29, 1831, in a man on a turf-boat. The epidemic lasted twenty-two weeks, with two thousand three hundred cases and one thousand four hundred deaths. From Berlin it dropped down the Spree to the Elbe, into which it empties, and appeared at Hamburg, at its mouth, on October 6th, having already been carried west to Magdeburg, on the Elbe, from which the infection had already been conveyed down to Hamburg and from there to Altona.

From Dr. Hamett's official report, (see Edinburgh Medical and Surgical Journal, vol. 39, 1833, p. 443,) we read, notwithstanding the watch that was apparently kept, "it is entirely unknown by what means cholera arose in Dantzic. The first cases appeared May 27, 1831, among the laborers in the mud-barges in the harbor of Dantzic," as if it had floated or been carried down the river Oder. But some light is thrown upon the manner in which it was conveyed to distant places, as the first case was taken to his home, fourteen miles away; the second, third and fourth cases, from four to eleven miles. The fifth case was a driver of horses to the mud-barges, who was carried to his home in town. Other cases occurred on these barges in June, when work was stopped. On May 30 the ship Monna, direct from Riga, arrived with cholera on board, and on the same day other cases occurred in town and in a suburb. It spread irregularly, without any marked order, especially among the poor, and finally extended to the villages, ravines, and valleys in and near Dantzic. The higher and middle classes generally escaped. From

28 to July 23, eight hundred and thirty-five cases occurred, of
h one hundred and ninety-five recovered. During these eight
s two thousand people were shut up in the dwellings of the sick,
well supplied with food and medical attendance. One hundred and
ty-nine persons fell sick in eighty-two of these houses, only fifty-
of whom had been in direct contact with the disease. In sixty-
houses there were more than one case. The whole mortality was
d at one thousand and twenty-eight out of one thousand three
lred and eighty-seven cases, but not all the attacks were reported.
rty-six houses, one case each occurred. In fifty houses, two cases
. In ten houses, three cases each. Four cases in two, and five
s in one. Dr. Hamett counted double and triple cases occur-
at the same time as single attacks, strangely enough. He thought
ven hundred and seventy-six cases no evidence of infection could be
d, and that fewer attacks occurred in those thus shut up and well
lied with food, than among the poor outside of them, who had bad
and hard living, with but little medical attendance.

ie comparatively slight effects of the Dantzic confinement system
reversed at Opatow, just above Cracow, where cholera commenced
30, 1831, with peculiar fury and unusual virulence. The whole ad-
nt country had risen up in arms to prevent intercourse with the
. No one was allowed to go in or out; all communication was for-
en, and all supplies of food interrupted. In the towns the shops
shut; a fearful silence prevailed everywhere. There was scarcely
use without sick, dead, or dying, and the horrors of famine were
g added. A commission from Warsaw boldly declared that the dis-
was not contagious, and only infectious in some peculiar way. Con-
ce was restored, the markets supplied, and a remarkable abate-
t of the epidemic soon occurred. In Dantzic food was furnished,
medical and police attendance enforced cleanliness and order; the
-up people were living in ease and comfort, with no anxieties except
e consequent upon the disease; while the Opatow populace were de-
ed of all comforts and assistance.

ENGLAND AND IRELAND, 1831.

has generally been assumed that Asiatic cholera made its first ap-
ance in England in October, 1831, at Sunderland, near Newcastle.
in the Edinburgh Medical and Surgical Journal, vol. 37, 1832, p. 295,
nd an account of an outbreak on board the ships of war lying in
nary on the river Medway, below London, during the summer and
mn of 1831, by Dr. James Hall, R. N. Nearly seven hundred per-
of all ages and sexes were on board these vessels; but owing to clean-
ss and excellent ventilation, there was but little sickness until an un-
al epidemic suddenly broke out, coincident with the arrival of vessels
n places where Asiatic cholera was prevailing. "In a creek of the
lway, ships from infected foreign ports performed quarantine. In the
ith of June, 1831, numerous vessels arrived from Riga, where cholera
then raging." Early in July two cases occurred on board the English
-of-war. Then again in August a woman and her infant, and soon
r the husband, were attacked. The ships that had arrived were said to
e no sickness on board, although several of them had suffered by it
Riga. Hence the first five cases were regarded as bowel complaints.
next day several other cases showed themselves. In all, the attacks
e sudden, with watery evacuations, cramps, cold sweats, and suppres-
n of urine. Some had the signs of fatal blue cholera. It next became

epidemic on board various ships, attacking infants, children, and adults of every age and rank, and at all hours, by day and night. Sometimes whole families were involved, in others several members in succession. Persons who arrived in perfect health from distant places were attacked in from sixteen hours to two days or one week. From the 7th to the 9th of August thirty sudden cases of cholera occurred, and from the 1st October one hundred and twenty persons were seized. From October to the middle of January several more cases of cholera occurred at intervals. No similar disease had been noticed in the Medway at this season before. No case occurred on board the ships of war until full three weeks after the merchant-vessels from Riga, had arrived in the river and been put in quarantine. Hence Dr. Hall concluded that it was more than probable that "the cause was a miasm radiating from the ships that had been affected with cholera; for the most violently affected ships of war were those that lay nearest to these vessels." Confinement to bed, with emetics of ipecac., hot oatmeal porridge, with opium, are said to have acted like a charm. Calomel was not given, nor the lancet used. The vessels involved were His Majesty's ships Temeraire, Æolus, Foxhound, Devonshire, Russell, Clyde, and Redoubtable. In Sheerness, near Chatham, and Chatham, and other ports, there were only a few sporadic cases. Dr. Hall had seen cholera in India in 1804 and 1805, and again in 1817, when he used venesection; opium, and calomel, and would have shuddered with horror at the bare mention of employing an emetic in this disease. But as he now regarded the evacuations made by the stomach and bowels as attempts of nature to free the system from an offending cause, he gave ipecac. to produce free and full vomiting, so as to discharge the vitiated secretions, and mild rhubarb cathartics for the same reason: and opium to remove spasms, &c.

Sunderland, it is generally claimed, was the first place in the British Isles in which malignant cholera seemed to appear in an epidemic form. Like Jessore in 1817, it made most noise, and was credited with being the cradle of cholera in England. It had about twenty thousand inhabitants, and its staple of commerce was coal; it is twelve miles below Newcastle, and then employed seven hundred ships of from two to four hundred tons each, with five thousand three hundred sailors. The previous season was healthy, the summer more than usually mild and genial; the only peculiarity being immense flocks of young toads. Dr. Snow before October (Ed. Med. Surg. Journal, vol. 38, 1832, p. 96) seven cases had taken place sporadically, to which every one that saw them agreed in assigning true choleraic characters. Dr. Dixon saw one on August 5; Dr. Brown another nearly two miles up the river above Sunderland; the third case was a pilot on August 13, in Sunderland; the fourth a shipwright on August 27. Then several more cases of extraordinary severity occurred before September and continued to appear during the month, with rapid sinking, coldness, severe vomiting, purging and blueness. Nevertheless it was generally maintained that these were merely aggravated cases of indigenous disease or common cholera. The first case that made an effectual impression occurred October 5; the second October 17, in a girl aged twelve years, in a respectable and much frequented public house on the river. The next three cases were a father, son, and daughter living near the first case, workers on keel-boats, which bring down coal. The next was a nurse in the infirmary to which the son had been taken, and who laid out his body. The next was a sail-maker; the next another keel-boat man. By November 1, five cases only had been publicly reported. Then much lightning took place, not followed by any new cases for two days. On November 6, there were

ew cases; on the 7th, two; on the 8th, none; on the 9th, seven
, and then the disease became epidemic. Some days ten, eleven,
hirteen cases were reported; then only six or eight. It was extinct
nuary 22. The weather had no influence, but nineteen deaths in
lay was the highest mortality. The disease lingered particularly in
in streets and lanes. It was not decided whether it arose spontane-
or was introduced. It was claimed truly that none of the seamen of
Hamburg vessels which had arrived in October had been affected.
nly mode in which, if susceptible of importation, the disease could
been introduced was by the crews of vessels which trade to the
c. (p. 105,) and return in August or September, when the seamen
aid off and their clothes and bedding brought ashore. As cholera
ared fatally on board several English vessels at St. Petersburg,
stadt, Riga, Archangel, and other places, Drs. Hazlewood,
lly, and Clanny thought this mode of introduction probable, from
dmitted inadequacy of the quarantine at Sunderland. The current
servation and opinion seemed at first rather to have been not in
r of contagion. In twenty-one cases out of the first fifty-four, no
ection could be traced. But in one instance a man not only fell into
filthy dock, but was taken into the nearest house, in which a
n had died of cholera two days before. In ten other cases, the
se attacked persons residing in the same house with others pre-
sly invaded. In six more it occurred in persons who had frequent
munication with the sick; one of them residing far off, in a healthy
ition. One surgeon and the wife of another died. The mother of
rgeon, who was in constant attendance on cholera cases, and who
r went out, took the disease (from her son, who remained well) and
. The person who washed the clothes of this case (p. 113) also took
disease. The principal nurse of the hospital died in eight hours,
another nurse and the porter were attacked. Of fifty-four cases,
first three were boatmen and relatives; one recovered. The sixth
was a cholera-nurse; the seventh case was the wife of a cholera-sur-
; the eighth case, a cholera-surgeon; the eleventh and twelfth, a
r and his wife; the thirteenth, a fish-woman; the fourteenth was
ly drowned and taken into the house of No. 7, who was a sailor;
sixteenth was the grand-daughter of No. 5; the seventeenth, the
of No. 7; the eighteenth, the daughter of No. 5 and aunt of No. 16,
had attended her father, case No. 5, a boatman. The twentieth
the wife of a custom-house officer. Numbers 15 and 21 were sailor's
stitutes from Sailor's alley; No. 22, a prostitute. No. 23 was the
of a cholera-surgeon. No. 24 laid out body of No. 15 and died; her
children were attacked, but recovered; No. 25, a sailor's prostitute,
had been with No. 21; No. 26 sat up with No. 22; No. 28, a pilot, re-
ng with No. 26; No. 29, a prostitute in Sailor's alley, with No. 21; No. 30
ed No. 27; No. 31's house communicated with Nos. 21 and 29 of Sail-
alley. No. 32 was a sailor and a lodger going from Edinburgh to
nchester, who put up in a lodging-house in which some persons had
viously died. Five persons in Sunderland poor-house, who used the
an on which cholera-patients were carried, with four deaths, was
nted as No. 33. No. 34 were two children and an aunt of No. 5, and
ated to Nos. 16 and 18; all three died. No. 35 a Sailor's alley keelman,
brother of No. 34; No. 36 a lodger in same house as No. 32. No. 37 was
ated to and communicated with Nos. 26 and 28. No. 38 washed the
thes of No. 23. No. 39 was father to No. 37 and related to Nos. 26 and
. No. 40 was the brother-in-law of No. 39 and visited him. No. 41 was
fe of No. 19, and laid out the body of another case. No. 42 assisted

No. 35. No. 43 was husband of No. 38. No. 44 nursed No. 41. No. was head nurse of hospital. No. 46 lived in the house of No. 39 and was mother of No. 28. No. 47 was a pilot in same house as Nos. 39 and No. 49 was a daughter of No. 51. No. 50 was a son of No. 51. No. was the husband of No. 48 and father of Nos. 49 and 50. No. sister of No. 52. No. 54 was father of Nos. 52 and 53.

Dr. Gibson, who gives the above cases, had had several years' experience in India, and never saw there any proof of contagion, but many the contrary. He changed his views in Sunderland. The surgeon whose wife and mother died, did not have the disease in any marked reported form themselves. Taking cholera from washing clothes was considered incredible, as washing was regarded as the grand preventive against contagion; while the humid air, exposure to cold, laborious exertion, scanty fare, abuse of liquors, and living in small, coal apartments, were regarded as the causes of washerwoman's cholera. Of the cases, some of the earliest, were pilots, sailors, and coal-boat men; five were Sailor's alley prostitutes, and four others had been with them.

It was not until October 26, after a good deal of paper conflict, that cholera was acknowledged to be in Sunderland. A large body of medical men raised a violent opposition to the idea that the new disease was malignant cholera, or was imported from abroad. The coal-owners, coal-merchants and other traders declared aloud that the physicians, some of whom had seen the disease in India, had formed a rash and erroneous judgment; that the first five cases were severe common cholera, and denied that it was by any chance imported. Singularly enough, none of the crews on vessels died; but doubtless some who had come ashore with their bedding and baggage. A committee of eighteen Sunderland physicians (Ed. Medical and Surgical Journal, vol. 37, p. 215) delivered their unanimous opinion that it was not the Indian disease. "The strong private interest of their wealthier patients warped their better judgments, and it required stronger nerves and more independence than most persons possess to act unbiased." The Marquis of Londonderry led the Sunderland merchants and coal-owners in their protests, ignorant that at almost every place on the Continent where it successively broke out, it followed exactly the same course pursued at Sunderland and Newcastle, viz, that an interval of four, seven, ten, or fourteen days always elapsed between the first fatal cases and its subsequent steady progress.

Sunderland was in constant intercourse with Hamburg and the Baltic, where cholera prevailed. The quarantine regulations were violated in the most flagrant manner, (p. 215.) The quarantine station was even placed so that suspected vessels had to pass through others lying in the harbor in order to reach it. The first reported cases occurred in the person and family of a keel-boat man, but at least one case of malignant cholera occurred days before in a person from Russia, without being reported to the authorities, although it was attended by a medical man. At the first breaking out of the epidemic no judicial investigation was made of its origin, and subsequent inquiry could scarcely lead to trustworthy results, as the victims were of the lowest class, boatmen, masters and crews of vessels, who had subjected themselves to penalty for violation of the laws, or were traders determined to pervert or conceal the truth, (p. 216.) But it was found that at the end of August, a captain of a ship had come to Newcastle from Riga, and by coach to Sunderland, where he had the disease, and was taken to Dr. Watson's office, who only reported the case long afterwards. In consequence of the dispute among the doctors, the first cases were reported

rhœa, common cholera, and, finally, as malignant cholera; but, after a weeks, diarrhœa was left out, and a few days later common cholera fell from the reports.

reville, secretary of the privy council of England, in his Memoirs, . 2, p. 25,) says: "Dr. Russell, who was in St. Petersburg, was down to Sunderland from London to get information, which it is difficult to procure." "The medical men" (p. 26) "and higher ses of Sunderland are split into parties, quarreling about the nature he disease and perverting and concealing facts which militate against ir respective theories. The people are taught to think there is no lera at all, and that those who say so intend to plunder them. Dr. ner complains of the medical men who would send him no return of ir cases. The consequence is that the government have put forward rong order to compel medical men to give information." The Edinburgh Medical and Surgical Journal (vol. 37, 1832, p. 195) says: "For ng time the truth in Sunderland was quite unattainable. Falsehood propagated with such zeal in every quarter that the daily and medpress were almost universally imposed upon."

ome of the physicians were undoubtedly sincere, and the whole tory of cholera bears them out in part. Dr. Fyfe, of Gateshead, near nderland, saw sixty-seven cases in Gateshead, of which forty-four re single instances in families of various sizes, and only in a few exples did it attack in succession other inmates. He found it very frently to invade only one person in a family, and, when several were ed, it was generally simultaneously, or in quick succession. When ltiple cases happened in one family there was usually want of ntilation, filth, and absence of proper food. Thus, two Taylors died a small, dirty, badly-ventilated house; two Wilsons in an ill-ventild upper room; three Robsons in a low, crowded room, with windows ver opened, and with a number of dogs, ferrets, &c., in it, and rarely aned. Three Coopers recovered in a large family room; and two allaces died in a very small, damp apartment. In short, cholera, with its virulence, always has a strong tendency to die out or be safely uted by a large quantity of fresh air, unless water-poisoning also be sociated with it. In Gateshead there was water-poisoning. There had en but a few cases in the dark alleys or closes, in which the pumps e liable to contamination, and were proven to be impure; when, on ristmas, December 25, 1831, the inhabitants fell asleep in perfect curity, void of panic, but before the sun rose on the 26th, fifty-five rsons had been seized, thirty-two of whom were destined not to see set. This was then supposed to be atmospherical; but fatal cases of olera had occurred, and even the streets and alleys of these filthy ople showed that choleraic diarrhœa was becoming very frequent. The ells and pumps were so placed in the streets that this filth not only uld, but did get into them. The water had been noticed to become ddenly impure and foul.

Finally long after, in 1832, (see Med. Chir. Rev., April, 1832, p. 534,) e truth came out. Dr. Ogden, of Sunderland, writes: "There had en great intercourse between Sunderland and Riga, St. Petersburg, d Archangel during the existence of cholera at these places, and it as the mortality among the British sailors, several of whom were from nderland, which occasioned the institution, in Sunderland, of the first oard of health in England. When the foreign voyages are over, the nderland ships return to the coasting trade, and there was a concenration or reunion in Sunderland of a great number of persons who had en at some period of the summer in unhealthy towns on the continent.

Every sailor brings home his chest of clothes for repairs and preservation; some of these chests belonged to persons who had died abroad (of cholera,) and which had not been opened since the clothes of the deceased had been placed in them. Robert Henry, pilot, died August 1; his cousin Margaret sickened and died December 11–15. John Parkins, a cousin, sickened December 12; Margaret Henry, a daughter, died December 13; Mrs. Parkins, a sister, died December 16–18; William Henry, alias Thompson, illegitimate son of Margaret, became ill December 17. Mrs. Parkins was in constant attendance on Margaret until John required attention. They were all related, and all with each other, and may have given it one to the other. Again, James Ellmore died November 6; Elizabeth Hopper, an elder sister, died November 17; Jane Johnson, another sister, died November 28; Thos. Ellmore, a brother, on December 25; and Ann, wife of Thomas, died December 27. To show how the disease springs up in distant and various places, it is only necessary to say that the first four all lived in separate houses, from one hundred yards to half a mile apart, and died in succession, after the usual intercourse which sick relatives have with each other.

A month after its appearance in Sunderland, on November 26, cases occurred in Newcastle, and the mayor reported them to the town council. The same hue and cry was raised in Newcastle by the merchants; but a physician experienced in cholera recommended a period of suspension of opinion for ten or fourteen days, which interval he had noticed had commonly been necessary for the epidemic to take a fair start after its first appearance. Accordingly, on the tenth day fresh cases occurred, and the disease was confessedly advancing, (p. 219.) By December 15, there had been fifteen new cases and ten deaths; and from November 26, sixty-one cases and twenty-three deaths. In North Shields, not far from Sunderland, and several villages around it and Newcastle, cases commenced to appear.

From Newcastle the disease was carried up to Edinburgh; from there by the well-known canal, over to Glasgow, on the west coast of Scotland; from there, down and over to Belfast and Dublin, on the east coast of Ireland; and from these places and Cork and others over to Canada. It was in London before February, 1832. In November, 1831, one ninety-seven fatal cases had been reported in all England; in December, two hundred and eighty-two; in January, 1832, 614; in February, 1,119; in March, 1,519; and in April, 1,401. So that the disease persisted through the winter, and doubtless not one-half of the cases were made known.

The outbreak in the villages of Scotswood, three and a half miles above Newcastle, Leamington, a mile farther up, and Newburn, a mile higher still, are well detailed by Dr. David Craigie, a decided non-contagionist. A man died in Newcastle December 13; his widow went to his father's in Leamington, and died December 22; then the father died December 28. The cases which afterward occurred were all in the vicinity of the house of the father. Choleraic diarrhœa commenced to prevail, and assumed the appearance of common cholera, and finally of malignant cholera. Next, three in one family died; then thirteen new cases happened in one day, with three deaths; then several single deaths, and three persons in one family; then more single fatal cases, and some doublets and triplets; then a widow who had nursed several; then a son of one who had died; then the son of another fatal case; then another child of a family in which three had already died; then a daughter of a fatal case; then two in one family. In Newburn, in one hundred and thirteen houses with one hundred and forty-four families, and five hundred and fifty-

tants in all, forty-six persons had been attacked, and twenty-three in ten days, with eight more in a dangerous condition. Then single, ble, and triple cases were seen in some houses. The thirtieth case the daughter of the first fatal case; the thirty-third case was the and of the fourth case; the thirty-fourth case was the wife and ner of two fatal cases. Then a father, mother, and young daughter. thirty-eighth and thirty-ninth cases were the father and mother of eventh case. The forty-first case was the sister of the ninth case. a man and wife; then a brother and sister; then four in one fam- then three in one family; then two in another; the fifty-seventh was the grandmother of the seventh and the mother of the thirty- th and thirty-ninth; the fifty-eighth and fifty-ninth cases were son wife of one who had died in Newcastle eleven days before; the eth case was the son of one who died of cholera; then two s in one family; the sixty-second case belonged to a family includ- the nineteenth, twenty-fourth, twenty-fifth, twenty-sixth, twenty- nth, and twenty-eighth fatal cases; then two cases in one house. Of -five cases, fifty-five had had communication one with another, but in a continuous line; nineteen houses had multiple cases, from two ve. On January 16 there were fifty new cases, of which thirteen confirmed cholera, and the rest choleraic diarrhœa. There were ty-two cases and twenty-nine deaths in seven days. Many stout ons of both sexes were carried off. The inhabitants of Newburn all the necessaries and comforts of life, were well clothed and fed, most, if not all, the houses had earthen floors, which retained moist- from the discharges, although all had fires, with large chimneys. e of the fatal cases had been preceded by diarrhœa for a week, and thus have infected several or many places. In all, three hundred thirty persons were attacked out of five hundred and fifty, two hun- l having choleraic diarrhœa, and fifty-five died. On one night sixteen ons were attacked, twelve of whom were dead in thirty hours, prob- from water-poisoning. There was no malaria at Newburn. It fol- d up the north side of the river Tyne, while the south side was vely affected at first. The fact that cholera is apt to vanish as rap- and suddenly as it appears was noticed. In Gateshead the whole demic was over in three weeks; in Newburn in fifteen days. On Jan- 18th it was scarcely noticed in Musselburgh, near Edinburgh. On 19th it was apparent in various parts of the town and vicinity, and dly attained great virulence, especially in Fisherow, in houses in ch there (p. 338) "were no windows or chimneys, and from which smoke issued and the light and air were admitted by one and the e aperture in the roof. The floors were all earthen, wet and filthy n extreme degree; a state of things which can hardly be credited hin ten miles of Edinburgh."

inally Dr. Craigie had to admit that cholera did run through some- ilies, two, three, or four of which were often attacked, (p. 379, Ed. l. Surg. Journal, vol. 37, 1832.) But he also noticed many instances hich the closest contact and the freest intercourse for some time was followed by any outbreak. The medical men and nurses were gener- exempt, only one of the former being seized. The wife and sister of apothecary were first taken, and then he died. But Craigie noticed eral cases in which nursing-infants were attacked after their mother ened or died. Still Dr. Craigie's notions of contagion or infection re very peculiar. He notices the case of Mary Newton, the forty-first e, who attended her sister, Mrs. Veitch and her child, the ninth and th fatal cases. She was twenty-two years old, in the vigor of youth

and health, and attended her sister and child, who died. She was in i
tress and anxiety; the next day she was wan and blanched, skin
pulse gone; but was up and had made no complaint, although
with diarrhœa the previous afternoon, which continued through the
and morning, with cramps in her legs. She went home to her father's
died the following day. None of her father's family took the di
Hence Dr. C. thinks it originated entirely in the epidemic constitu
of the air hanging over the village, aided powerfully by her deep af
tion at the death of her sister and a little niece of whom she had
charge. And all this in a village in which he says there was no ma
But on page 382, he concludes, though cholera is not a disease orig
contagious, he will not venture to say what may take place in a
liarly dense, unclean, and indigent population. There is nothing
possible, he says, in supposing that a disease, not originally capa
producing its generative principles, may, in the crowded and filthy
tations of a very impoverished, relaxed, and immoral population.
a disorder similar to itself, and become capable of spreading fr
person to another. But if we admit malaria when it does not ex
thinks we need not take refuge in this modified opinion.

CHAPTER IV.

CHOLERA EPIDEMIC OF 1832, 1833, AND 1834, IN NORTH AMERICA.

In the majority of the published accounts of the cholera epidemic of 1832 in North America, the arrival of the ship Carricks at the Grosse Isle quarantine station on the Saint Lawrence upon the 3d day of June, has been taken as the date of the original arrival of epidemic cholera upon this continent.

It seems, however, to be pretty clearly demonstrated that the Carricks was but one of the first arrivals of infected vessels. It has been stated that the quarantine records show that on the 28th of April, the ship Constantia, from Limerick, arrived at Grosse Isle with one hundred and seventy emigrants, among whom twenty-nine cholera deaths had occurred during the voyage; that on the 14th of May the ship Robert, from Cork, arrived, having had ten cholera deaths on board; that on the 28th of May, the ship Elizabeth, from Dublin, arrived with two hundred emigrants, having lost twenty from cholera.

The brig Carricks, from Dublin, arrived at Grosse Isle on the 3d of June with one hundred and forty-five emigrants, among whom forty-two cholera-deaths had occurred.

It is thus shown that, prior to June 3, there had arrived four vessels, carrying at least three hundred and seventy emigrants, among whom fifty-nine cholera-deaths had occurred. This fact is established in the face of the many reports from committees composed of medical men from several States, who were especially sent to investigate the arrival of the dread disease.

Dr. Marsden further states that there existed at the time no proper system of quarantine; that no segregation of individuals from cholera-infected ships was attempted; that the only separation consisted in removing those who were actually sick from among those who continued apparently well, the latter being at once sent upon their journey. At the same time constant and uninterrupted intercourse was permitted between the quarantine station and the city by boats and steamers, and passenger-steamers were even permitted to proceed to Grosse Isle and take passengers direct to Quebec and Montreal. So rapidly was this transfer accomplished, that between the second and fifth days of June, seven thousand one hundred and fifty-one emigrants had arrived in the city of Quebec from the quarantine station.

It is thus shown that, prior to any known outbreak of cholera in Canada, during the year 1832, a large number of emigrants from cholera-infected quarters had arrived upon the Saint Lawrence, and had been distributed throughout the province. The Canadian government having offered extraordinary inducements to emigrants, nearly thirty thousand individuals arrived during the spring and early summer months. These emigrants were for the most part Irish, and arrived from the ports which have already been noted.

It is only practicable, at this late day, to commence a history of this epidemic from the arrival of the cases which caused the outbreak at the city of Quebec.

On the 7th day of June, the steamboat Voyageur, of Montreal, left the

quarantine station, with a large number of emigrants, for the city of Montreal. She touched at Quebec, and then proceeded upon her voyage; but, after making a few miles, was obliged, on account of a violent rain-storm and her overcrowded condition, to return to Quebec, where she landed a portion of her passengers, and then proceeded on her trip. The disembarked passengers, wet and exhausted, took refuge at emigrant lodging-houses, and quite a number went to the house of Roache, on Champlain street. At an early hour of the next day a case of cholera occurred at this house in the person of one of the emigrants landed from the Voyageur. On the afternoon of the 31st a second case occurred in an emigrant from the same boat, who had obtained employment upon the wharf, and the same evening six more cases occurred at Roache's house. By 3 o'clock p. m. the next day fifteen cases had occurred, with fourteen deaths. From these cases the disease spread in Quebec, and during the first two weeks one thousand deaths are reported, fifty-six of which occurred at the Roache house.

At Quebec the disease lasted until September 2. A total of three thousand two hundred and eighteen deaths is reported.

June 12.—Cholera appeared at Point Levi, on the opposite bank of the Saint Lawrence; also at Beauport and Little River. At each of these points the disease only appeared after the arrival of emigrants.

Dr. Marsden states that "at the time it was reported that there had been several dead bodies thrown overbord from the Voyageur before she arrived at Montreal, but that the report lacked confirmation."

It is, however, recorded that before she (the Voyageur) reached Three Rivers, an emigrant named Kerr was taken with cholera, and on the evening of the same day (June 9) a man named McKee, also an emigrant, was attacked with the same disease.

As the vessel (the Voyageur) was passing Sorel, a bed belonging to a cholera patient was thrown overboard, and having been picked up by a man named Latour, was taken home as a prize. In twelve hours the man was dead from cholera, and in a few succeeding hours his entire family died.

MONTREAL.

June 9.—The Voyageur reached Montreal. Kerr, the emigrant who had been taken with cholera on the boat, was dead, and the second case, McKee, was in a state of profound collapse. McKee was carried to a tavern on the wharf, where in a few hours he died. All that night and all the succeeding day, the body of this man was exposed to the gaze of the public, and, actuated by motives of curiosity, many persons visited it. The same night (June 9) several other cases of the disease occurred in different portions of the city. Upon this point great stress has been laid, that the outbreak was not confined to any one locality, but it has been conclusively shown that a vast number of individuals from cholera-infected localities had been landed in that city, no part of which could have been preserved from their presence. During the first two weeks eight hundred deaths occurred, and the epidemic lasted until September 1, with a total of one thousand eight hundred and forty-three deaths.

Among the persons who visited McKee before his death was a soldier of the Fifteenth Regiment of the line, then in garrison at Montreal. This soldier assisted in rubbing McKee. After the death of the patient the soldier returned to the barracks, where, in a few hours, he was taken ill with cholera, died, and the disease spread among the command. By the 19th forty-six men had died in garrison of cholera. The command

d was then encamped on the island of Saint Helen's, a *cordon de santé* established, and no other cases occurred, "although steamers hted with dead and dying daily passed close to the island."

ie Voyageur made the trip from Quebec to Montreal without stop- at any point upon the river; consequently, upon this trip, she did spread the infection between the two cities; but Dr. Nelson states a feather-bed which belonged to a cholera-infected emigrant was wn overboard after the boat had passed Sorel; that this bed was n by a farmer named Latour and carried to his house, when both the Latour and his wife died of cholera.

r. Marsden notes that the town of Three Rivers, equidistant be- n Quebec and Montreal, where steamers touched daily from both s, escaped the disease entirely in 1832. An absolute system of intercourse was adopted, and no passenger was permitted to land the boats during the epidemic.

he same author relates an instance of a poor fisherman, who lived at village of Contrecœur, a little below Montreal, who was out fishing in canoe when a raft came floating past. The captain of the raft d the old man to take one of his men ashore, who had died, and y him. The fisherman had not heard of the cholera, took the body re and buried it. During the same night he took ill and died. wife also took the disease, and people passing the house on Sunday ning, seeing it shut up, mentioned the fact to a nephew, whom met at the parish church. This man went to the house, found his le dead and his aunt dying. After doing his duty to his relations, went to his home, where he also died.

t both Quebec and Montreal numerous instances are recorded dem- trating the portability and infectiousness of the disease.

plasterer left Quebec on account of cholera, went to Leeds, to work an unfinished house. He was taken with cholera and died. The man who nursed him next died, and last the husband. The people the town then burned down the house, and no other cases occurred.

poor wanderer, sick with cholera, was taken into the house of a son named Mathieu at Ange Gardieu. During the night he died. wife of Mathieu, then Mathieu himself, and, lastly, a neighbor o had coffined the bodies, died of the disease.

drover left William Henry, where a few cases of cholera had oc- red, to go to the eastern townships. His way led through unsettled sts of many miles. In the center of this forest was a tavern, the y house in the region. The drover arrived at midnight, rested, and k some refreshment, and in a short time left. The next day the man the house and his wife both took cholera and died.

t was demonstrated by Dr. Marsden that those places, intermediate ween Quebec and Montreal, where no passengers were permitted to d, were not attacked by the disease.

From Quebec and Montreal the epidemic spread, and followed closely line of the great rivers, for they were the routes of transportation en to the thirty thousand and forty-nine emigrants who arrived on Saint Lawrence between the 2d and 23d of June.

June 11.—At Lachine, cholera appeared among emigrants on their y to Upper Canada. The same day it broke out at La Prairie, also ong emigrants. At this point twenty-four deaths occurred.

June 12.—The first case occurred at Saint John's, also in the person an emigrant, and eleven deaths occurred.

June 13.—Three emigrants died of cholera at Fort Miller; they had ft Quebec on the 8th, Montreal on the 9th; they were traveling on a

CHAPTER IV.

PIDEMIC OF 1832, 1833, AND 1834, IN NORTH AMERICA.

ly of the published accounts of the cholera epidemic of America, the arrival of the ship Carricks at the Grosse station on the Saint Lawrence upon the 3d day of taken as the date of the original arrival of epidemic his continent.

wever, to be pretty clearly demonstrated that the Carricks the first arrivals of infected vessels. It has been stated ntine records show that on the 28th of April, the ship m Limerick, arrived at Grosse Isle with one hundred migrants, among whom twenty-nine cholera deaths had g the voyage; that on the 14th of May the ship Robert, ived, having had ten cholera deaths on board; that on ay, the ship Elizabeth, from Dublin, arrived with two ants, having lost twenty from cholera.

rricks, from Dublin, arrived at Grosse Isle on the 3d of hundred and forty-five emigrants, among whom forty- eaths had occurred.

hown that, prior to June 3, there had arrived four vessels, ast three hundred and seventy emigrants, among whom lera-deaths had occurred. This fact is established in the any reports from committees composed of medical men States, who were especially sent to investigate the arrival disease.

n further states that there existed at the time no proper arantine; that no segregation of individuals from cholera- s was attempted; that the only separation consisted in se who were actually sick from among those who con- ntly well, the latter being at once sent upon their journey. me constant and uninterrupted intercourse was permitted quarantine station and the city by boats and steamers, and amers were even permitted to proceed to Grosse Isle and ers direct to Quebec and Montreal. So rapidly was this mplished, that between the second and fifth days of June, nd one hundred and fifty-one emigrants had arrived in the ec from the quarantine station.

shown that, prior to any known outbreak of cholera in ing the year 1832, a large number of emigrants from cholera- rters had arrived upon the Saint Lawrence, and had been dis- roughout the province. The Canadian government having ordinary inducements to emigrants, nearly thirty thousand arrived during the spring and early summer months. These were for the most part Irish, and arrived from the ports already been noted.

practicable, at this late day, to commence a history of this m the arrival of the cases which caused the outbreak at Quebec.

h day of June, the steamboat Voyageur, of Montreal, left the

of his honor Mayor Wickham, we obtained access to a vast mass of early health-records of the city of New York, and many days were spent in a most laborious investigation of them, with but this result: *while for preceding and for succeeding years the records are almost perfect, nothing could be found that related in any way to the months of the year in which cholera could have been imported by ships into New York harbor.* A circumstance which is pregnant with thought. The fact that cholera did arrive at New York in 1832, was suppressed so effectually that no records of arrivals at quarantine during the months of April, May, and June, 1832, can be found; while the records of preceding and succeeding months are perfect.

Cholera was undoubtedly imported into the city of New York early in the spring of 1832. The emigrants who were well enough to travel were dispatched rapidly upon their journey from that city, and upon the rapid diffusion of the disease over the Atlantic and Western States a new light is thrown.

At Albany the first cholera-record that can be obtained is on June 9. Two men, one of whom lived at Fish Slip and the other on South Market street, near the watering place, died of cholera; both were men of intemperate habits, and their homes were dirty and neglected. From these cases the disease spread. One thousand one hundred and seven cases with three hundred and eighty-nine deaths are reported.

At Greenbush, opposite to Albany, cases occurred July 7. The first case was in the person of a canal-boat man.

July 12, an individual who had left Albany the day before died of cholera at Schenectady.

At Rochester two cases occurred July 12. They were both from New York City, both arrived sick, and both died.

July 15, cholera occurred at Buffalo. The first case was in the person of a boatman on the canal who had been engaged in rafting lumber for three days previous. Up to July 30 no cases occurred among emigrants.

July 17, cholera occurred among the convicts at Sing Sing; although the authorities denied that there had been any intercourse with points of infection, it has been shown that vessels from New York were constantly being loaded with marble at the prison; that upon one of these vessels, prior to the outbreak at the prison, a man had died of cholera. It was further stated that prior to July 17 a man had sickened and died of cholera at the prison, who, a few days before his attack, had been in New York City. It was also ascertained that convicts had been admitted from points at which the disease was epidemic.

July 17, cholera appeared at Syracuse in the person of a laboring man.

July 18, nine cases of cholera are reported at Brooklyn in persons from New York City.

July 19, cholera appeared in a family at Lockport, Niagara County.

July 22, cholera broke out on the canal-boat Western Barge, at Frankfort, eight miles east of Utica. The boat had left Albany on the 20th of July with fifty-six passengers, all emigrants. The first person attacked was the captain, who died; at Rochester, after their arrival, several other deaths occurred. The following instances of the portability of cholera are recorded by Dr. J. B. Elwood: A man who had nursed a cholera-sick at Rochester went home to Mendon, where he died of the disease the same night. Of six persons who attended him all had cho-

and four died; and this was followed by thirteen deaths in a popu-
on of one hundred and fifty.
lady arrived from New York during the epidemic at that city. She
the disease within five days of her leaving New York and died.
sister, who nursed her, died of same disease two days thereafter.
Oneida County some Indians, who had been employed to bury a per-
who had died of cholera on a canal-boat from New York, took the
ase and six died.
t Ancram, a woman from New York died of cholera, and four of
e who nursed her took the disease and died.
he town of Nyack remained healthy until toward the last of July,
n a Mrs. Leydecker arrived there from New York, and died of chol-
the same night of her arrival. Immediately after her death her
er-in-law took the disease and died. Mr., Mrs., and Miss Graham
t fell victims in quick succession, and the disease spread rapidly.
r. Henry Bronson, of Albany, related the following circumstances:
Stephen Miller, of Sand Lake, a town twelve miles east from Albany,
e to Greenbush, opposite this city, on Sunday, the 5th of August.
cholera was then prevailing in Greenbush. Mr. Miller visited some
is friends who were ill of the disease, and returned home the same
. On Tuesday morning following he was taken down with cholera,
died in the afternoon. On Tuesday morning a negro who worked
Miller, and who had been about him during his illness, sickened in a
ilar way and died before night. On the same day the father-in-law
a daughter-in-law of Miller, living in the same house, were attacked.
former died the day following, and the latter recovered. On Sunday
ıt succeeding, a son of Miller and a boy who lived with him were
en with the disease, but their cases were mild and they both
vered. The next day a man who worked for Miller at the time of
sickness and death, and had been with him, but who had fled from
ht, was seized with the malady, and died in thirty hours."
r. Bronson remarks: "These facts show most conclusively that
lera *may* be contagious, in the ordinary acceptation of that word."

OLERA AMONG THE UNITED STATES TROOPS.

While cholera was creeping along the routes of travel in New York
te, and before the disease had advanced beyond the line of the North
er, a body of troops, destined for the Black Hawk war, had been
ed upon a steamboat at Buffalo, N. Y. Unfortunately, this boat had
n engaged in the transportation of emigrants prior to her being
rtered by the United States.
hrough the kindness of the Adjutant-General of the Army we have
n permitted access to the original reports of General Scott, com-
ding the Army of the Northwest, and from them are able to abstract
mplete history of the distribution of cholera during the year through-
the northwestern portion of the United States.
ıly 1, the battalions of Lieut.-Col. D. E. Twiggs and Major Payne,
sisting of three companies of artillery and four of recruits for the
ırth United States Infantry, embarked at Buffalo, N. Y., on the
amboat Henry Clay. This command had left New York City on the
l of June, had passed through Albany on the 24th, and had continued
journey at once for Buffalo. The boat was, however, detained at
ffalo by unfavorable winds until the morning of the 3d, when she
eeded upon the voyage. The next day cholera occurred among the
ops, and upon arrival in the Detroit River two fatal cases had occurred,

The authorities of Detroit ordered the steamer to proceed two miles up the river and to anchor off Hog Island. July 5, General Scott reports that he had ordered Surgeon Everett, with full supplies, to the aid of Assistant Surgeon Kerr, who had been, until then, the only medical officer on board the Henry Clay. The troops then on the Sheldon Thompson were General Scott and staff, six companies of artillery from Fortress Monroe, and two companies of the Second Infantry, commanded by Colonels Eustis, Crane, and Worth.

July 7, Colonel Twiggs reports that, on this the third day of the epidemic, he had lost four men; that eight were in a dying state, and that the disease, in a most malignant type, was spreading rapidly; that he had landed his command within a mile of Fort Gratiot, and that every effort was being made to prevent the disease from spreading.

July 8, Colonel Twiggs reports that the steamer Henry Clay had left that morning; *the crew refusing to do anything but to take the boat back.* "The deaths up to this time are nine, including two of the steamboat men. Without some great change, this command, or a great portion of it, must be sacrificed."

July 9, Colonel Twiggs reports that nine fatal cases had occurred since his report the previous day, including the first officer who had been attacked, Lieutenant Clay, Fourth United States Infantry, and that Dr. Everett is now sick with cholera.

"When I landed here I had with me four companies of the finest looking recruits I have seen for many years. The panic is so great among them that the desertions have reduced the number to sixty-six. It is reported that many of them (deserters) are dying on the roads." On the same date General Twiggs reports that he had ordered sixteen cadets, who were with his command, to leave camp and to report at West Point on the 1st of September next; thus affording an opportunity to these gentlemen of spending nearly two months at their home.

These gentlemen, members of the class of 1832, at the Military Academy, were *five* from Pennsylvania; four from New York; two from Tennessee; two from Ohio; one from Kentucky; one from Virginia; one from North Carolina, and one from New Hampshire; none of them died of cholera; but there is no record to show that they did or did not suffer from the disease.

A few hours after signing the order quoted above, Colonel Twiggs was himself attaked with cholera, and the command devolved upon Maj. M. M. Payne, Fourth Artillery.

July 12, Major Payne reports Colonel Twiggs as convalescent, and that Dr. Everett had been violently attacked, and was not expected to recover; that the steamboat Superior had arrived and transferred the passengers to the William Penn; the latter steamer starting at once for Chicago. "A schooner, loaded with ordnance and ordnance stores, is in the stream opposite the camp, with the captain dead of cholera and three of the crew dangerously ill. Of the two hundred and odd recruits for the Fourth Infantry, one hundred and thirty deserted, and of them a large number have died in the country."

July 16, Major Payne reports the death of Dr. Everett of cholera. This gentleman was medical director of General Scott's army. At this date thirty-nine cholera deaths had occurred.

The records of the Surgeon-General's Office contain two letters of Surgeon Everett. In the first, under date of July 7, he reports the fact of having been ordered on board of the Henry Clay, and that, by medical advice, Colonel Twiggs had landed his command near Fort Gratiot. We quote the following:

The troops and baggage, being landed in haste, were scarcely on ground when one of the most appalling storms arose I have ever nessed, which left neither person nor baggage dry in any part. The were left on board the boat, and their number has been much reased from the camp. The whole number of cases is fourteen; r deaths; no convalescents yet."

July 8, Dr. Everett writes: "There have been eleven cases since my t, and three deaths. Three cases, are, I think, convalescent."

A few hours later Dr. Everett was himself attacked.

July 9, Major A. W. Thompson, Second United States Infantry, comnding Fort Gratiot, reports that he had moved his command from fort on account of the near proximity of General Twiggs's comnd, and had gone into camp on the Saint Clair, some thirteen miles low the fort. This command consisted of two companies of the Secd Infantry, and two companies of artillery, the whole under orders join General Scott at Chicago, by troop-ships, which were now rly expected.

Upon the evening of the same day a passing steamer landed the garon of Fort Niagara, under Lieutenant Colonel Cummings, and took board the two companies of artillery.

The command of Colonel Cummings was prostrated with cholera, d Major Thompson used every effort to avoid communication with is camp, and endeavored, unsuccessfully, to obtain transportation to able him to march overland for Chicago.

July 11, Major Thompson reports no sickness in his command.

The artillery companies composing the garrison of Fort Niagara, der the command of Lieutenant-Colonel Cummings, arrived at Detroit the 30th of June, and were quartered in the city awaiting transrtation. No cholera had occurred at Niagara before their departure. aving reached Detroit, this command was inspected, and no man was on the sick-list. The men were quartered in an old brick building on e banks of the river, in the most filthy part of the town, and surunded by grop-shops. Assistant-Surgeon Stevenson, with the comand, asserts that on the 4th day of July there were not ten sober en in the command.

July 6, two men who had been employed to communicate with the eamer Henry Clay were taken with cholera in Detroit and died quite ne to the building occupied as the barracks. To the 20th of July Dr. evenson reports, in the command of seventy-eight men, forty-seven olera cases, with twenty-one deaths. The town authorities having come alarmed, asked the removal of the command, and Colonel Cumings, taking the steamer William Penn, arrived at camp below Gratiot condition previously reported.

A letter from Assistant Surgeon H. Stevenson, addressed to the Surgeon General of the Army, dated Fort Niagara, August 1, 1832, vividly escribes the condition of affairs at Detroit upon the explosion of the isease:

"On the morning of July 6 a case of Asiatic cholera occurred in our etachment, (garrison of Fort Niagara,) which terminated fatally in omething less than six hours. During that day four additional cases ccurred, and in the course of twenty-four hours eleven cases and four eaths marked the progress of that dreadful epidemic among us, which s malignancy and violence of attack no other epidemic which had itherto come under my observation was in any respect to be compared ith.

"The occurrence of this disease in the center of the city of Detroit (our

troops having been quartered in a large public store-house, immedia[te]ly in the vicinity of the arsenal) soon attracted the attention of the ci[vil] authorities of the place. The panic and alarm which it created is beyo[nd] conception. A meeting of the city councils was immediately held, wh[en] it was determined that the troops should (*nolens volens* on the part [of] the command) be removed from this location as soon as was practicab[le]. This information having been communicated to Colonel Cummings, [he] advised with me as to the propriety of an immediate removal, when [it] was determined to proceed to Fort Gratiot, or its vicinity, and there await the arrival of the vessel that was to convey us to Chicago."

Assistant Surgeon R. E. Kerr communicates to the honorable the Secretary of War the following, under date of July 16, 1832, from Fort Gratiot:

"On the afternoon of July 4 the first case (cholera) presented itself in one of seven companies of United States troops, under the charge of Colonel Twiggs, while on board the transport-steamer Henry Clay, between Buffalo and Detroit, and near the latter place. It was looked upon with suspicion, but there was great reluctance to consider it the Asiatic cholera. Every effort had been made to preserve health, and chloride of lime had been liberally used; but the boat was very inconveniently crowded, and the men were necessarily exposed to the heat of the day and the dews at night. A great portion of them were obliged to sleep on the upper and uncovered deck, there not being room elsewhere. Until then the troops were in fine health and condition, and a violent case of the disease, especially in a section of country where the cholera was known to be, was well calculated to arouse apprehension.

"In this condition we arrived at Detroit and anchored off the city. Colonel Twiggs acquainted General Scott, who was then there, with the situation of things on board. Dr. Everett was ordered to the boat immediately, and while there, the second case occurred, which removed all doubt, and confirmed the suspicion of its being Asiatic cholera. The first case died that night, and in the morning General Scott directed the command to proceed onward, and, if necessary, to disembark on Bois Blanc, an island near Mackinaw. We proceeded immediately, with Dr. Everett with us; but the cases multiplied with such rapidity and severity, and the alarm on board was so great, that Colonel Twiggs directed as early a disembarkation as practicable, and the bluff of land immediately below Fort Gratiot was selected for the encampment. There is but little question that a longer continuance on board would have but added to our calamitous situation. For two or three days we had the most unfavorable weather. A daily and drenching rain brought the men down with awful rapidity. A large barn, an appendage to Fort Gratiot, was then selected as a hospital, and there was a general manifestation of zealous efforts and unremitting exertions to contribute to the comforts of the sick. Lieutenant Clay was taken down on the morning of the 8th, and died about 1 o'clock the next morning. Dr. Everett was severely attacked on the morning of the 9th, and died on the morning of the 14th. Colonel Twiggs has had the disease, but is now recovering. The number of deaths to this day is thirty-four. During the panic, which was so excessive that attendants could with the greatest difficulty be procured for the sick, many deserted to escape the disease. A detail for that duty was sure to occasion several to go off. The attempt to escape the disease, however, by that means, in a number of cases that came to our ears, proved futile, for they are reported to have died on the road."

RT MACKINAW.

The only record of the epidemic at this point which can be found is ntained in a letter of Assistant Surgeon R. McMillan, dated July 24, 2, which reads as follows:

"On the evening of the 7th instant General Scott arrived here, on way to Chicago. Four of the enlisted men of the detachment who e with him were brought into this hospital about 9 o'clock p. m. the e day. Three of them were violent, marked cases of spasmodic lera; all of them died. The fourth case, being less violent, and un- r control of medicine, recovered. Some of the soldiers of this gar- on were slightly attacked with cholera, but by timely application of dicines the disease was arrested. One of the command only died. veral cases of cholera and some deaths have occurred in the village."

From Chicago, Ill., under date of July 11 and 12, General Scott re- rts to the Secretary of War:

"I. That at the solicitation of the master of the steamer S. Thompson, relieve the overcrowded condition of the boat, it being comparatively small one, he had left two companies of artillery at Fort Gratiot, th orders to proceed upon the next boat.

"II. That before leaving Mackinaw four cases of sickness occurred on e Thompson, which resembled cholera, but as at the end of twenty- ur hours they had not become serious, the hope was entertained that and the sickness on the Henry Clay was not cholera. They were erefore landed at Fort Mackinaw, and orders were left for the com- nder of the troops on board the Henry Clay to leave his sick at the ne point.

"July 8, the steamer S. Thompson, with General Scott and staff, with e four companies of artillery, left Mackinaw, all in high health and irits. At daylight on the 9th six cases of cholera were reported on e Thompson; during the day fifteen other cases occurred; and by July there had been a total of seventy-seven cholera-sick, and nineteen aths. The Thompson reached Chicago during the night of July 10. e next morning the troops were landed, and Fort Dearborn was con- rted into a hospital, the garrison, under Major Whistler, having arched to camp two miles distant.

"July 12, General Scott reports that among the four companies of tillery there are not more men than are required to attend the sick d bury the dead. Assistant Surgeons De Camp and Macomb have splayed great zeal in their attendance upon the sick, and all the well ficers and soldiers, from the first, have displayed the most admirable mness, and have been unceasing in their attentions to the sick.

"The disease was not confined to the enlisted men; in proportion, the ficers suffered the most severely, although to this date none had died. he night of arrival at Chicago six enlisted men died."

July 19, General Scott writes from Chicago:

"Major Whisler reports to-day sixty-three bayonets for duty; the attalion of artillery in the fort or hospital, eighty-one. Colonel Eus- s hands me this paragraph: 'The health of the battalion of artillery is idently improving, and the progress of the cholera is checked. In he last four days there have occurred eleven new cases and ten deaths. he sick report is reduced from seventy to fifty, of whom twenty-eight re decidedly convalescent. The new cases are more mild than those of revious occurrence. The four companies on leaving Detroit counted ne hundred and ninety enlisted men; fifty-nine have died, four were

left sick at Mackinaw, fifty remain sick, and eighty-six enlisted men are on duty.'

"August 1, Colonel Eustis reports that cholera is subsiding at Chicago. No deaths had occurred in the last sixty hours and very few new cases.

"August 2, the Fort Niagara garrison and a number of the deserters from General Twiggs's command arrived at Chicago in command of Lieutenant and Adjutant Clitz; Colonel Cummings having been left sick fifty miles from Detroit."

The communication of Major-General Scott to the honorable the Secretary of War, under date of September 1, contains information so valuable in its character, that it is reproduced *in extenso*.

"HEADQUARTERS NORTHWESTERN ARMY,
"*Rock Island, September* 1, 1832.

"SIR: The great calamity of the times has come upon the troops on this island. The cholera has raged among them. Since the 26th ultimo one hundred and forty-six individuals have taken the infection, twenty-six have already died, twenty-two are convalescent, six have been cured, and ninety-two remain sick. Of the latter, more than sixty are slight cases. From a personal inspection of every individual who has been in hospital from the beginning down to sunset to-day, I am happy to say that the disease is evidently checked and mitigated. We shall probably lose twenty more. Among the deaths is that of Second Lieutenant Samuel Torrence, of the Fourth Infantry, a young officer of much merit.

"The foregoing only includes the sick and the dead in Fort Armstrong, garrisoned by two companies of the First Infantry, and the adjoining camp of the Fourth and Sixth Regiments of Infantry, making a total of four hundred and three enlisted men on the island. I shall, in the sequel, speak of the troops encamped in the neighborhood.

"The *manner* of the introduction of this disease among the troops which had been serving under the immediate orders of Brigadier-General Atkinson is to me an affecting speculation.

"I cannot doubt from much personal observation that spasmodic cholera is partly epidemic and partly contagious. The atmosphere prepares the human system for its reception, and then it is readily generated by intemperance or extraordinary exposure; and, when once generated, it readily propagates from individual to individual, whose systems are more or less prepared for its reception. From all that I can learn, the population below as well as the troops in this quarter were many weeks since so prepared. To the systems so prepared, premature and fatal action has been given, I believe, by importation from Chicago.

"I have already reported many of the measures adopted by me to prevent the spread of the disease from that place among the inhabitants of the country, volunteers, and United States Rangers; but I have not reported half of my care and solicitude on the subject, nor is it possible for me to do much more on the present occasion. I left Chicago on the morning of the 29th of July. The disease among the troops there, as we all thought, had nearly exhausted itself. In the forty minutes before mounting my horse, I had the honor to receive your letter of the 24th of the same month, and I hastily addressed a letter of instructions to Colonel Eustis, second in command, of which the following are extracts:

"'From a letter just received from the Secretary of War, I find that his opinion, on account of cholera, that the movements of detachments

pected with that disease should not be precipitated. You are fully aware of my own policy to guard against the spread of the calamity. I shall therefore leave you the same discretion (to march or not to march) which I have heretofore exercised myself on that critical subject; but I see by the arrival of Lieutenant-Colonel Cummings's small detachment, that not before, it may be deemed safe, in respect to humanity and the good of the service, for you to take up the line of march.

"'You will, as long as new cases of cholera shall happen to occur here on the march, take all proper measures to avoid a junction with Rangers or volunteers, but long before you reach the Mississippi I trust your battalion will cease to be suspected of cholera.

"'I have kept you up to this time so fully acquainted with my correspondence and views, with all authorities and on all subjects, and my confidence in your intelligence, zeal, and abilities is so great, that I deem it superfluous to say more to you at present. I know well that I leave your public interests in safe and able hands.'

"This was not an idle compliment. In merit it would be difficult to find a superior to Colonel Eustis in any service; and if he has erred in respect to cholera, it is because he has been from the first, personally, absolutely indifferent to it, and because he has been animated with an extreme desire to bring his fine troops in immediate contact with the enemy.

"By the misconduct of two express-riders (one of whom lost his dispatches) I did not hear from Colonel Eustis, after he left Turtle River, till the night of the 21st ultimo, when a part of his troops in boats were actually at the mouth of Rock River, three miles below. His letter was dated the 16th of that month, at Dixon's Ferry. He arrived himself by land, near the mouth of Rock River, the same night (with the remainder of his troops) that I received his letter. On the morning of that day I stated to you that 'a few old and lingering cases of cholera were on the boats.'

"This was founded on rumor, and was a mistake. On visiting his camp, on the 22d, I had the happiness to learn that there had not been a new or old case of cholera among his troops, after his passage of Turtle River on the 13th ultimo, one hundred and thirty or one hundred and forty miles from this. I, nevertheless, by order, confined his troops to an island in Rock River, and interdicted all communication, except by my special permission, between his camp and the other troops, or inhabitants of the neighborhood; that is, one family a mile above him, on another island, and one family on this side of Rock River. Neither of these families, as far as I have heard, has been infected, nor was there a single case of cholera in his camp down to last evening. Myself, an aid-de-camp, and one other officer were the only persons who had visited that camp from this island, and neither of us have been infected.

"On the 12th ultimo I caused a letter to be addressed to Colonel Eustis, (which he acknowledged at Dixon's Ferry on the 16th,) of which the following is an extract:

"'The general is very desirous that you should take great pains to avoid all communication, either with the inhabitants of the country or with other troops, should any new case of cholera have occurred on the march.'

"This was written when I knew that the volunteer militia would be returning home by Dixon's Ferry, and that certain companies of the United States Rangers might be expected there on their way to join me. I believe the volunteers returning home had all passed to the east before Colonel Eustis arrived, but he met or found there Captain Ford's com-

pany of United States Rangers, and it is known that some communication personally took place between the *officers* of the two bodies, if not between their *men*, as well while near Dixon's as afterward, on the march hither, Captain Ford following the trail of Colonel Eustis at a distance generally of eight or ten miles till the latter encamped on an island in Rock River, and then the former crossed a half mile above. These facts are by others deemed important as to the introduction of cholera here, but not by me, though they certainly show a neglect of my repeated instructions. Colonel Eustis, always a non-contagionist, had, on reaching the ferry, (Dixon's,) been three or four days without a case of the disease, either new or old, and, therefore, became too confident that his officers and men could not impart it to others.

"But Captain Ford's company, which has clearly infected this island, and through it will, I fear, infect the whole valley of the Mississippi, in all probability imbibed the contagion at Chicago. At that place, and on my way westward, I had filled the whole country, south and east, through newspapers, by innumerable letters, (four of which were to the four captains of Rangers on this side of the Mississippi,) through discharged volunteers on the Illinois and Rock Island Rivers, and other means, with admonitions to Rangers not to approach Chicago. I also sent the arms of the four companies to Danville and Dixon's Ferry, the same view, and informed each captain where to find his own, and to give like information, if he could, to the three others. These letters were all left unsealed, and indorsed with my rank and name to excite curiosity, and to induce postmasters and others to read them and add publicity to my admonitions. In short, I had erected a paper barrier around Chicago, which no company of Rangers, though ordered to report to me there, could ignorantly pass. In the mean time, and down to the arrival of Captains Boon and Ford here, I had not received a line for either of the captains, except Brown, who was recruiting at Danville.

"Captain Ford, on his march from the Ohio River, did not ignorantly pass the barrier I have mentioned. On his arrival at Captain Boon's camp on Hickory Creek, thirty-five miles from Chicago, he learned from the latter (an excellent officer) my solicitude on the subject of cholera. He had seen one of my published letters to the same effect. Nevertheless, with fourteen of his men, he went up to Chicago for provisions, and suffered himself, with some of his men, to be coaxed into Fort Dearborn. This was about the 10th ultimo. Twelve days after Captain Ford's company arrived here, and on the night of the 25th ultimo sent a sick man (Johnson) across into Fort Armstrong, who has proved to be a case of cholera, and is the first on this island. This man was one of those who went up to Chicago, and, if not into Fort Dearborn, was certainly at the entrance of the cholera hospital, then reeking with recent disease.

"The second case and first death was another man (Hall) of the same company. He was brought into the hospital here and died on the 28th.

"Here again I have had all my care and sagacity singularly defeated by accident or ignorance. I had visited Captain Ford's company camp, and, on seeing two of his men sick of fever, directed that cases requiring care in the treatment should be sent to the hospital in Fort Armstrong. I was then ignorant that any part of the company had been near Chicago or had any intercourse with Colonel Eustis's command at Dixon's Ferry. The day that Johnson was sent over to this island, Captain Ford told me that he had a third man sick of *common cholera*, whom I

hed to send to the hospital. Being about to leave the fort for Colo- Eustis's camp, I directed one of the surgeons here to keep watch for t man at the water's edge, in order to see if the case were not one of emodic cholera, and, if so, not to permit him to be landed. Dr. man had never before seen a case of that sort, and received John- through a very natural ignorance. The disease not being early de- oped, I myself, on repeated inspections, doubted its character until er I had the honor of addressing you on the morning of the 26th, I therefore did not mention it. So afterwards, on the 26th, another ger (Hall) was introduced. He was received by the other surgeon, Smith, after a similar caution from me, and died in a few hours cholera. We had but one case, a man of the Fourth Infantry, on the h, who lay in the hospital (a case of debility) with Johnson on the ht of the 25th. On the 30th the disease began to rage among all troops on this island. Strange to say, that not another case oc- red in the camp of rangers (on the west side of the Mississippi) from 26th down to this morning. Two more are now reported, and I fear t the usual havoc will follow among the drunken and feeble. I must logize for these tedious and distressing details. I am fully aware of heavy responsibility that rests upon me for the spread of a dread- malady among the troops under my orders, and through them pre- turely among the population of this immense valley. I have never arded myself as having been born to be a curse to my country. On contrary, it has always been the first wish of my heart to serve her riously, but my care and foresight, amidst recent events, have been nally defeated. I have, without getting into battle myself, brought ease and death upon those who vanquished the public enemy. To new danger I have freely and fearlessly exposed myself without lity. My heart is deeply humbled and afflicted. But if I cannot w that I have employed extraordinary care, and exercised even more n common sagacity to prevent the evils which I lament, I ask to subjected to universal execration.

"SEPTEMBER 2.

"During the panic on the night of the 30th, seventeen men of the Sixth antry, who mostly have families at Jefferson Barracks, stole a boat l deserted. It is supposed they have gone thither. *Many of them l probably perish by the way and the remainder infect the barracks and nt Louis.* On the morning of the 29th, at daylight, I sent off by water, ler guard, seven prisoners, five of whom were principal chiefs or war- rs of Black Hawk's band, to be confined as hostages at Jefferson Bar- ks during the pleasure of the President of the United States. This asure was taken on the night of the 28th, after consulting Governor ynolds, (who was present,) and with his concurrence. I at the same ie delivered up to Ke-o-kuck and other friendly chiefs then here all old men, the women, and children who were under guard as prison- of war, and sent the whole away.

"These precautions were taken in haste, before the cholera had spread ond the third case, which happened on the 27th, and when we hoped t neither the guard of the hostages nor any Indian sent away had bibed the disease. The rapid spread which commenced on the night the 29th has given us great uneasiness on this point. We had re- ining the three murderers of the Menomonees, the murderer of one of r citizens near the Yellow Banks, and some young men whose quality had not ascertained. Two other warriors were brought up from the endly villages below, on the 29th, after the hostages were gone. Of

these Indians, four were already reported as dead of the epidemic, and several others were sick.

* * * * * * *

"Boon and Ford's companies are in camp to get disinfected, as they might otherwise spread the infection through the whole line of their march through Illinois and Missouri to the Arkansas. Bracken, Henry, and Brown's companies have not approached the infected region. In the twenty-four hours ending at meridian to day, there were but five new cases on this island. Surgeon Coleman is one of them, and there is but little hope of his recovery. I have just learned that there have been no new cases in Colonel Eustis's camp. Possibly it may not be re-infected as communications between it and the fort are interdicted. I am just from the hospital. Death has greatly thinned the wards. A few have recovered since yesterday, and many others will survive. The whole number sick at 12 o'clock, including slight cases, was seventy-two. I have just heard that Surgeon Coleman is dead. At any time this loss would be great; it is particularly so at this moment. We have now on Surgeon Finley and Assistant Surgeon Smith on this island, and Assistant Surgeon Macomb in Colonel Eustis's camp.

"I have the honor to be, sir, with great respect,

"Your most obedient servant,

"WINFIELD SCOTT

"Hon. LEWIS CASS,

"*Secretary of War.*

"SEPTEMBER —

"P. S.—There have been but few deaths since the morning of the — and no officers have died. Lieutenant Royster, of the Sixth, cannot — many hours."

On the night of August 31 a guard, under Second Lieutenant Gale of the First Infantry, came down to Rock River with twelve prisoners from Black Hawk's band, who had been delivered up at Dixon's Ferry by the Rock River Winnebagoes. Colonel Eustis, happening to see the canoes, took them to his camp, on account of the illness of Lieutenant Gale. That fine young officer expired of cholera the next morning. Only one other case followed in that camp. The man was sent up to the fort for bread, and took the disease here.

Under date of September 9, General Scott reports the subsidence of the cholera upon Rock Island; total deaths, four officers and fifty-six enlisted men. The disease had again broken out in the camps of the rangers, on the west side of the Mississippi River. In a postscript dated September 10 the General states: "I learn by return of express that the Sacs and Foxes have not had the cholera, though many of them left this on the morning of the 29th ultimo."

September 16, General Scott reports that cholera has entirely disappeared from the troops in the vicinity of Rock Island, and that it was fast subsiding in the camps of rangers.

JEFFERSON BARRACKS, MO.

"JEFFERSON BARRACKS, MO.

"*September* 6, 18—

"SIR: Lieutenant Cross, of the First Infantry, arrived this evening from Rock Island with a small guard, in charge of seven of the principal Hawk prisoners, whom he has delivered to me by order of Major General Scott.

"Lieutenant Cross brings the disagreeable intelligence that the malig-nt cholera has made its appearance among the troops composing neral Atkinson's command at Rock Island. Lieutenant Cross buried e of his command on their passage down, who died of the disease, t who were apparently in good health when they left Rock Island. e of the Indian prisoners is ill, and doubtless past recovery.

"Fifteen men of General Atkinson's command surrendered themselves me at this post on the 4th instant as deserters, alleging that they d run from the *cholera* alone without any intention of quitting the vice. They left Rock Island the day after Lieutenant Cross left there, d informed me that on that day eleven men were buried and a great ny more were sick. Some cases of that disease have occurred in this rrison, but I trust rigid attention to police and good medical attend-ce will divest the disease of much of its fatal character.

"I have the honor to be, your obedient servant,

"H. SMITH,

"*Captain Sixth Regiment, Commanding.*

"The ADJUTANT-GENERAL OF THE ARMY."

Under date of September 10, 1832, Surgeon J. P. C. McMahon reports the Surgeon-General of the Army "that cholera had become epidemic Jefferson Barracks, Missouri." "Deserters are arriving here in boats d canoes from time to time. One of them was brought ashore the ght before last in the last stage of collapse. He was sick before and his comrades deserted from Rock Island. His is the only death ave as yet had occasion to record. The Sixth Regiment, or that por-n of it that remains from death and desertions at Rock Island, is hourly pected here."

TON ROUGE.

Lieutenant-Colonel Foster reports, November 8, that cholera is upon l sides of Baton Rouge, and upon every boat which passes up and wn the river.

November 18, reports the arrival of the New Orleans command, driven t by cholera.

EW ORLEANS.

Surgeon Thomas Lawson, late Surgeon-General United States Army, ports that cholera appeared at New Orleans near the close of October, he city being the first point attacked, and the last position maintained the enemy. Without pretending to determine the cause of this mys-rious disease, or its mode of propagation, one fact is certain, viz, that case of the disease manifested itself among us until after the arrival port of the steamer Constitution, which had several cases on board, number of her passengers having already fallen victims to the disease. fearfully rapid was the pestilence in its progress, that in less than rty-eight hours it reached the lowest plantation on the Mississippi, solating almost every spot inhabited by man.

"One of its peculiarities observed both above the city and in the lower untry is, that it frequently passes over a village or plantation, while e destruction around is terrible; and this, too, without any manifest use, either as regards the local circumstances or the habits and con-tion of the people. On the east bank of the Mississippi it advanced, er scourging New Orleans and the lower country, to within a few miles Baton Rouge, and on the west side, some distance above that point.

"In New Orleans the effects of the epidemic were first manifested among the dissolute and the intemperate; those who were necessarily or accidentally exposed to the inclemency of the weather; those who were without the means of providing themselves with wholesome food and raiment, and the miserable occupants of the damp, filthy, and crowded hovels of the upper Fauxburg. It having desolated the suburbs, the disease invaded the heart of the city, striking down men, women, and children indiscriminately. Here again the disease exhibited some of its eccentricities, for in many instances a house was wholly exempt from its ravages, while those on every side were places of mourning and distress."

During the epidemic Surgeon Lawson and all the attendants of the post hospital were taken down with the disease. Six thousand deaths are said to have occurred at New Orleans.

Having traced the disease from the Saint Lawrence River to New Orleans, we will take up the consideration of the lines of infection, which radiated from the city of New York.

RHODE ISLAND.

Newport.—On the 17th of July the packet Hero left New York City for Newport, R. I., with a list of thirty-seven passengers. Arriving at Newport on the 18th, the vessel was quarantined by the city authorities and all the passengers, with the exception of three ladies and one gentleman, were lodged at the United States barracks on Rose Island.

At sunrise on the 25th the quarantine was raised, and the passengers were allowed to proceed to the city. During the night of the 24th Miss D., one of the two ladies who had remained on the Hero, had been taken with cholera, but as her case was not reported to the authorities, she was carried to her home in the city, where she died after a few hours. On the 25th Miss P., the second lady, took cholera, and died the next day. At almost the same hour that Miss P. was attacked, the third lady, Miss C., and the gentleman who had remained with them on the Hero, also sickened, and both died.

July 30, a man who had assisted at the funeral of two of these ladies was attacked with *bilious colic*, from which he eventually recovered, but his wife and three children took the disease, from which the wife and two of the children died. The last cases occurred at the hospital early in August, and were followed by the death of two attendants.

Providence.—July 25, a Mr. J. Thurber, who had left New York City on the 11th with his family, was taken with cholera, from which he reacted, but relapsed and died. His wife was taken with the same disease July 31, and died the next day.

July 31, a young girl living in the same house as the Thurbers was taken with colera and died.

August 1, a sister of preceding case also died.

During August and September thirty-six cases of cholera occurred at Providence, of whom twenty-five died.

CONNECTICUT.

July 14, a Mrs. N. and her son arrived at New Haven from New York City. They both had diarrhœa when they arrived; in both the cholera developed, and both died. Within a few days the father and mother of Mrs. N., at whose house the preceding cases had occurred, both took the disease and died. July 18, a young child from New York

ty died of cholera at same house. Twenty-seven cases are reported, ith fourteen deaths.

Hartford.—July 19 and 20 two fatal cases of cholera occurred at artford, in the persons of refugees for New York City. Four other ses followed, of whom three died. The case of the 20th of July, a gro man, was taken with cholera, but recovered. His parents, how- er, (said to have been intemperate persons,) took the disease and died. The Boston Medical and Surgical Journal, vol. VII, contains accounts many house epidemics instituted in this State by refugees from New rk City.

ASSACHUSETTS.

July 20, a fatal case of cholera occurred at North Brookfield, in the rson of a gentleman who had just arrived from New York City, where had had an attack of the disease, but from which he supposed him- lf recovered; but on reaching his home he relapsed and died. No her cases occurred.

Andover.—On August 18, an aged lady, after some imprudence in diet, ed of cholera, after seventy-two hours' illness. Several other cases curred, but none were fatal.

Haverhill.—August 25, a Mr. C. who had been in New York City, d who had visited Lowell during the time that he was suffering with iarrhœa, was taken with cholera, but recovered.

Dr. C. A. Lee reports the case of a gentleman who had been exposed cholera in Buffalo, and returned to his home at Mount Washington, ass., fifteen hundred feet above the sea, and there died of cholera. Of ght friends who nursed him, six were attacked with the disease and ur died.

Boston.—On Sunday, August 5, about thirty convicts at the State ison in Charlestown were suddenly attacked, at an early hour of the orning, with violent diarrhœa; and before the evening of the 6th, one undred and eighteen cases had occurred. No cause for the attack uld be traced to food. All these cases were promptly treated, and one were fatal.

On Sunday, August 5, at about 2 o'clock a. m., a number of the in- ates of House of Industry, South Boston, were taken with diarrhœa nd vomiting, and during the next twelve hours fifteen other cases urred; none were fatal. On the succeeding day cases of a similar ature occurred in Charlestown and in Boston, but were not malignant character.

August 15, Miss. E. L., aged twenty-five years, who had been attend- g sick friends who suffered from the prevailing disorder, died of cholera; nd the same day, Mrs. F., a lady thirty-five years of age, who had been, ith Miss L., taking care of several sick persons, also was attacked, and ied.

Twenty-nine fatal cases are reported as having occurred.

The Boston Medical and Surgical Journal for July 25, 1832, reports: 'A man died last week, after an illness of a few hours, on his passage rom New York to Boston, on board the new steamboat Chelsea. It as supposed to be a case of cholera. There were only five or six per- ons on board, and as yet no other case has appeared among them, lthough they are all detained at quarantine and the boat has been umigated."

An interesting incident is recorded as having occurred in the State of Maine.

During December, 1832, a chest of clothing that had belonged to a

sailor, who had died of cholera at a Baltic port, arrived at his home in a small village near Bangor, Me. The chest was opened, the clothing was distributed to his friends, and all who received the garments were taken with cholera and died.

NEW JERSEY.

July 7 a lady died at Newark. She was from New York, where she resided in an infected locality, but did not leave her home until she was herself taken sick, when she took refuge at Newark. Following this case nine deaths occurred.

Dr. Stevens states that during the epidemic at Newark an aged man went from that city to Hanover, fourteen miles distant and across a range of mountains, where he had cholera, but, reacting, was sent to his son's house, at Morristown. The son would not receive him, and the patient was carried to the county poor-house, where he relapsed and died. Within forty-eight hours, the man at whose house he first stopped died of cholera, and four other cases followed in the same house. On the road, and within less than a mile, there were over twenty cases and ten deaths.

The brother of the first case at Hanover came from his home at Chatham to attend the funeral, and, returning home, died.

At New Brunswick fatal cases occurred July 14, and cases are reported about the same time at Elizabethtown, Trenton, Paterson, Princeton, Burlington, and Camden, but Jersey City was not infected until July 26.

At Plainfield a sick stranger was taken into the house of a gentleman, and died of cholera. Four members of this family died of the same disease, and all the others were seriously ill.

On the New Jersey Canal, at section 40, seven miles from Princeton, an epidemic of cholera was caused, on the 26th of July, by the arrival of a peddler from New York City, who died of cholera. Fourteen cases, with thirteen deaths, occurred.

PHILADELPHIA.

According to the late Prof. Samuel Jackson, the first case of cholera in the city of Philadelphia, in the epidemic of 1832, occurred July 5, in an individual who resided in the western part of the city, near the Schuylkill. "No possible circumstances to account for the disease by communication existed. The second case took place in the Northern Liberties, distant from the location of the first at least a mile and a half, on the 9th of July. The next cases were on the 14th of July, two in the Northern Liberties and one in Kensington, the first distant from the second case about a mile; the last about two miles. A few other scattered cases presented themselves at intervals, all in remote unconnected points, until the 27th and 28th of July, when the epidemic influence acquired its full sway, and cases were daily developed. The epidemic attained its acme on the 5th, 6th, and 7th of August, from which time it rapidly declined."

No other records treating of the introduction of the epidemic of 1832 into the city of Philadelphia can be discovered. The theory of the local or malarial development of the disease, having been determined upon, seems to have been almost universally assented to, and the attention of the medical men was turned exclusively to the consideration of the pathology and treatment of the disease.

Philadelphia, however, is a port of entry; emigrants arrived during the spring and summer months, and they belonged to the same classes as have been shown to have arrived cholera-infected at other ports

e rapid scattering of individuals at New-York from cholera-infected sels undoubtedly had its influence in the development of the disease other cities; and it is submitted that the early cases in Philadelphia urred in the localities that would be frequented by such persons, ecially those who might have made the trip overland from New York. n the early part of August, a laborer who had been discharged from prison at Philadelphia, made his appearance at Plymouth Locks in st of work. Shortly after his arrival, he was seized with cholera, l died in a few hours. Among twenty laborers at these locks, fifteen es of cholera, with nine deaths, occurred.

LAWARE.

During the latter part of July two or three cases of cholera were ded at New Castle, Del., from vessels on the Delaware River. The t case among the inhabitants occurred August 6. The disease con- ued, with an intermission of from August 17 to 29, until September 5. Prior to the outbreak an oyster-boat arrived with the dead body of a n who had died of cholera. All who ate the oysters had the disease. fteen deaths occurred.

In August a lady left Philadelphia to escape the disease, and went the farm of her father-in-law, in a secluded portion of the State of laware. The day she arrived she was taken with cholera, and died. ny other fatal cases followed at this place.

ARYLAND.

During the spring of 1832 it was every now and then rumored that ses of cholera had occurred in the city of Baltimore. Of them, how- er, no cognizance had been taken by the health department.

On the 7th of June the ship Brenda arrived from Liverpool with e hundred and twenty-three emigrants on board. The captain re- rted that during the voyage nineteen deaths had occurred, fourteen which he admitted had been cholera, but the disease had disappeared fore the arrival of the vessel.

What became of the passengers of this ship Brenda, the record left Dr. Jameson does not show; but we are informed that Baltimore gilantly and faithfully enforced quarantine regulations against cholera, *hen the mayor, board of health, health-officer, and consulting physician ere decidedly non-contagionists.*

The record of cases, however, begins on the 4th of August, although is more than probable that the record should have commenced at a uch earlier date.

On the 30th of July cholera was announced at Annapolis.

At Hagerstown, Port Tobacco, Govanstown, the importation of the isease is clearly proven by Dr. B. M. Byrne, United States Army.

During the month of August a Captain Dodson returned from Balti- ore to his home at Saint Michael's, a small town on the eastern shore f Maryland, and died of cholera. From this case twenty cases ccurred, half of whom terminated fatally.

DISTRICT OF COLUMBIA.

From Dr. J. M. Toner, of Washington, who has placed at our disposal cholera note-book, containing clippings from the National Intelligencer, e are able to present the following outline of the cholera-outbreak at Washington City in 1832:

"Several thousand laborers were employed during July and August,

1832, in macamadizing Pennsylvania avenue, and upon the improvement and extension of the canal. These laborers were mostly emigrants for a short time in the country, and were so miserably provided for that the Intelligencer of August 8 calls upon the city council to exercise some supervision over them.

"August 8, a colored female servant of Mr. Amos Kendall, living on Twelfth street, between G and H, was suddenly attacked with what was called "malignant typhus fever," from which she died on the 10th.

"August 9, a colored female servant of Postmaster-General Barry, who resided on Eleventh street, between F and G, was attacked with "malignant typhus fever," from which she died on the 11th. The same day a negro man, also a servant of Mr. Barry, and husband of the last-named woman, took the same disease, but on the 14th was reported to be out of danger.

"August 12, an intemperate white man, twenty-one years old, who had suffered from a diarrhœa of some weeks' standing, was suddenly taken ill and died in five hours. This case was pronounced to be cholera."

We copy from the Intelligencer of September 12:

"The epidemic broke out August 8, and continued very nearly until October 8. The physicians who were here through the period of the malady, and are still surviving in this city, all concur in fixing the number of cases at a thousand, of which five hundred were fatal. It raged with great fury early in September, was at the height of its intensity toward the middle, and began to assuage its violence in the latter half of the month. The population of Washington at this time was in round numbers 24,000."

Dr. Thomas Sewell, of Washington, in a letter to Dr. F. B. Page, of Louisiana, reported, October 24, 1832: "That the cholera was most prevalent among the hundreds of laborers engaged upon the public works, of whom a large proportion were foreigners recently arrived in the country, neither speaking our language nor accustomed to our habits and mode of living; many were intemperate, extremely unclean, and messed together in the rudest manner. The disease prevailed with great severity also among the colored population."

From Washington the disease was carried to the neighboring towns of Georgetown and Alexandria, and into the adjacent country districts.

VIRGINIA.

Norfolk.—Tuesday, July 24, cases of cholera are reported.

Richmond.—The epidemic reached this point July 6.

Cholera was introduced into Charles County, in the person of a man named Gibson, who was the captain of a vessel from Georgetown. He landed at the plantation of Mr. Philip Stewart, where he died of cholera. From this case a number of others occurred, the majority of which were fatal.

At Colchester, the disease was introduced by a man from Georgetown, and many fatal cases occurred.

SOUTH CAROLINA.

From an article from the pen of the late Professor Warren Stone we learn of the introduction of cholera in 1832 into the city of Charleston, S. C.:

I left Troy for New York, and in the latter part of October em-
ked for New Orleans in the brig Amelia. The vessel was over-
ded with passengers, and there were a few cases of cholera in New
k when the ship sailed. For the first four days there was a calm,
everything was healthy; but a terrible storm came, and it was found
ssary to fasten down the hatches, and stifle over a hundred human
gs in the space between a small ship's decks. They were all at-
ed, of course, with sickness; and their excrements, together with the
ying provisions and heated air, were enough to destroy life without
assistance of an epidemic poison.. I expected serious consequences.
captain, who was willing to do whatever was proper, said that the
hes could not be raised without imminent danger of sinking the ship—
et which was subsequently verified. On the third day of the storm
re was a cry that there was a dead man below. The weather having
lerated a little, the captain ordered the hatch to be raised, and I
t below, where I found a deplorable state of things. All seemed
pified from foul air, and about twenty-five seemed to be in the second
ge of cholera. Eight bodies were thrown overboard on the first day,
every one that had strength was sent on deck, and the disease soon
sided, leaving no case of cholera except convalescents.

"At this period in our voyage the brig was run on Folly Island in dis-
s. There had been no cholera in South Carolina, and, I think, none
er in Georgia or North Carolina; neither was the disease prevalent for
years afterward. A sea-island planter, who had suffered with
t is called the country fever, was on the island, but as soon as he
ned that cholera had existed aboard the ship, he fled to Charleston,
.. leaving behind two superannuated negroes and two young ones.
e city authorities at once ordered down an ample guard to prevent the
rance of any one into the city, but at the same time provided boun-
lly for all the wants of the passengers. The value of the cargo was
siderable, and quite a company of wreckers came down for the pur-
e of securing it, and the city guard joined with them. Within three
s fourteen of them died; whereupon the city authorities ordered the
p and everything belonging to it to be burned. The fact is, the stench
gendered in the vessel below deck by all the causes combined was un-
rable, and the wreckers cut a hole through the ship's side, but this
not exempt them from the effects of the poison. The boats being
t, the surviving passengers had to be taken ashore through the surf,
consequently were wet. Exposure at this time to a cold northeast
d caused a few new cases, and many of the passengers, visiting the
hy ship for liquor and plunder, renewed to some extent the disease;
t as soon as the ship was destroyed and the passengers were made
nfortable, the disease disappeared, showing that it could not be per-
tuated in a pure atmosphere. The two old and the two young negroes
re constantly among the crew and passengers for the purpose of sell-
g vegetables, and from their well-known cupidity, it is presumed that
y managed to get to the ship. However, three of them died one night.
passing their tent one morning, I observed one of the young ne-
es sitting in the doorway crying, and on inquiring the cause, I received
reply the answer that 'they would not get up to get his breakfast.'
ooked into the hut, and saw on the floor the three dead bodies, pre-
nting all the marks of cholera. The survivor had strong premonitions
the disease, but with care they soon subsided, and he was sent to the
y. These are substantial facts, entirely distinct from coincidences.

"One of the party of wreckers returned to Charleston, and died at his
me, on Elliot street, of cholera. A few days later the nurse who at-

tended this man died of the same disease. As an instance of the ... spirit of exaggeration that possessed the non-contagionists of the ... it is stated that the case on Elliot street '*was visited by hundreds of ... ple, none of whom took the disease,*' and yet the attendant died of ch... No other cases occurred in the city."

Having traced the disease along the Atlantic coast, it is prop... take up the lines of infection as they advanced to the headwaters ... Ohio River.

PENNSYLVANIA.

On the 26th of June a woman died at Erie of cholera. She had ... arrived from Quebec. This woman was an emigrant, whose hus... had died of cholera on the passage to this country. She arrived at E... on the 22d; on the 23d she washed the clothing of her dead husb... on the 25th she was taken with cholera, and died on the 26th.

July 2, cholera was reported at Pittsburgh. The first case wa... the person of an Irish woman, who lived at a house frequented ... emigrants. Subsequently cases occurred among emigrants who arr... from New York.

OHIO.

The following announcement was made by the Cleveland Boar... Health:

"CLEVELAND, OHIO, *July* 10, 1832—9 o'clock a. ...

"The board of health have the unpleasant duty to report that ... steamboat Henry Clay arrived last evening in our piers from De... with three of her men sick, and, as the board of health have no d... with the cholera. * * * Two of the crew died of cholera above ... troit."

After much opposition on the part of the citizens of Cleveland, ... crew of the Henry Clay were allowed to land upon a point of land, wh... they were placed in close quarantine. Several of the men died of ch... era at that point, but the disease did not spread.

July 22, a woman was landed at Cleveland from a passing boat. S... was suffering from diarrhœa when she arrived; cholera was soon de... oped, and she died. From this case the disease spread and became ... demic.

Cincinnati.—October 9. The steamboat Sylph arrived at Cinc... with a passenger on board sick with cholera. He was an emigrant ... had left Kingston, Upper Canada, nine days before, crossed the ... of Ohio from Cleveland to Portsmouth, one hundred and twenty ... above Cincinnati. At Portsmouth he took the steamer Sylph for ... cinnati. After the arrival of this man and his death, the disease be... epidemic in the city.

Up to this time the existence of the disease at Cincinnati had ... denied by the board of health; but it is shown by Dr. Drake that two ... one fatal cases had already occurred, the first on the 30th of Septem...

The first case, that of September 30, was the driver of an express wa... who was employed wherever he could obtain work, and who was ... tacked after exposure to a violent storm of rain. The same night a ... whose occupation is not given, but who lived within but three bl... the river, died after a few hours' illness.

The same day the cook of the steamboat Huntsman was take... and died, collapsed, October 1. This boat was a regular packet bet...

·innati and Louisville. No cholera had occurred at the latter city, from the nature of his employment he was thrown in contact with from other river-steamers, and those employed on the levee of Cin-.ati.)

·ptember 30. A negro woman, living quite close to the second case, taken with cholera and died in twelve hours; and in the same house,)ctober 2, the fifth case occurred, which was also fatal.

·tober 1. In a house almost adjoining that at which the two last died ırred the sixth fatal case.

·tober 4. A man died of cholera at his home some ten miles from ington, Ky. He had spent the four previous days in Cincinnati.

·tober 5. A negro laborer died of cholera; the record does not show exact employment, or whether he had been in contact with the pre-is negro cases. But his home was within the square from their point eath.

·tober 5. A negro deck-hand of a river-steamboat died at the house)ne Anderson, of cholera. Anderson lived *near to* the first case of date. It is recorded that this second case, George Price, had been at house at which he died two days before he was taken with the ase.

wo other cases occurred in the same portion of the city, that termi-ed fatally on the 5th.

)ctober 6. A negro man, occupation not given, died of cholera near center of the city. The same day a gentleman died of the disease at ·ington. He had been in Cincinnati the previous day, and became with rain as he returned home.

)ctober 7. Five cases occurred in the portion of the city infected; all e fatal.

)ctober 9. The first steamboat *known to be infected* arrived at the city. The steamboat referred to as conveying cholera-patients to Cincinnati s the William Parsons, from Saint Louis, Mo.

During the prevalence of cholera at Cincinnati, a party of twenty-four rman emigrants arrived at Dayton, Ohio, (June 23.) When they ded, one of their number was dead with cholera, and eight were ngerously ill; of the latter, seven died. The remaining sixteen were attacked, but recovered with the exception of one infant. Two of nurses employed to care for these people died of the disease. One s ill but recovered; there was no extension of the epidemic.

:NTUCKY.

The report of Dr. Drake shows that, on the 4th of October, a man died cholera at his home some ten or twelve miles south of Covington, ving contracted the disease in Cincinnati; and that, on the 6th, a gen-man died of the same disease in the city of Covington, having con-acted the disease also in Cincinnati.

The importation of the disease into the State is thus established, hough the records in the Transylvania Journal of 1832 and 1833 are nfined almost exclusively to the establishment of the malarial theory. On or about the 4th day of October, cholera appeared at Louisville, y., five days later than we are informed by Dr. Drake that Cincinnati s infected. At this point, the disease was confined to the banks of e Ohio and to Beargrass Creek, which empties into the Ohio at that oint. The mortality never became great; seven deaths per day was e average reported while the disease was at its height.

Lexington.—November 6. A negro died of cholera at Lexington, and ring the next forty-eight hours five deaths occurred. All the cases

occurred in one quarter of the city near to the margin of a small [illegible] which runs through the city, into which all the sewers empty, and [illegible] which the railroad runs. Two of the cases reported were railroad employés—one an engineer.

It will be noted that the first case did not occur until thirty-two [illegible] after the cholera-death recorded by Dr. Drake as having occurred [illegible] or twelve miles south of Covington. We have been informed by [illegible] residents of the State that the disease advanced gradually along the line of public travel, which was at the time slow and tedious.

Frankfort.—November 6. Cholera appeared at Frankfort, which was connected with Lexington by a railroad, and during the first days five deaths occurred, when the disease abated.

It has been most conclusively shown that the cholera-epidemic of 1832 reached North America, not upon any atmospheric wave that was wafted from cholera-infected Europe, but by means of vessels [illegible] with cholera-infected emigrants, who landed upon the Saint Lawrence at New York, Baltimore, and perhaps Philadelphia; that from the Grosse Isle quarantine-station the infection spread along the chain of the lakes carried in infected boats, until the city of Chicago was reached; that from Chicago it was conveyed across the State of Illinois to Rock Island upon the Mississippi River, from which point the entire valley, as far south as New Orleans, received the infection; and that by means of infected steamboats the infection was carried up the Ohio River to Louisville and to intensify the same infection that was being conveyed down the stream.

It has been shown that the infection was carried from the Saint Lawrence, along the routes of travel, into New York State, to meet the line of infection advancing northward from New York City. It has been shown that the infection was carried from the Saint Lawrence into the States of Pennsylvania and Ohio, in which States it was carried southward to join the line of travel along the Ohio.

From New York City, it has been shown that the disease was carried into adjoining towns and States.

Although the exhibit has not been as full as it was hoped, when the task was contemplated, yet sufficient has been shown to prove that epidemic cholera of 1832 was a portable disease; and, in the face of the facts that have been presented, it is impossible, with any reason, to doubt the method of its diffusion over the United States.

In 1833, cholera reached the United States by an entirely different route. The general course of the epidemic of 1832 was reversed: while in that year the disease had been carried down the waters of the Mississippi, in this the disease was conveyed northward, over the same great highway of travel.

In February, 1833, cholera was carried into the island of Cuba, and became epidemic at the cities of Havana and Matanzas, and for several months the disease raged with intense severity; the deaths at Havana being over ten thousand in a population of less than one hundred thousand. During the months of April, May, June, and July, the disease was carried in all directions from Cuba. A fatal case of sporadic cholera occurred during April at New Orleans. During the month of June the disease became epidemic at Tampico, Campeachy, and Vera Cruz. In August, it reached the city of Mexico. At Tampico, it is stated that nearly one-half of the inhabitants perished of the disease—nine hundred died in seventeen days. In May, Surgeon McMahon of the Army reported that cholera was epidemic at New Orleans, and at that city

se was most disastrous. About the same time it appeared at le, Apalachicola, and at Amelia Island on the coast of Florida.
e steamboats in the Mississippi trade were again infected, and the se was carried northward.
w Orleans, Vicksburgh, Memphis, Saint Louis, Quincy, Louisville, nnati, Maysville, Wheeling, and Pittsburgh, all in order suffered, ach in turn became points from which the disease radiated from iver, while the interior cities, receiving the infection, in turn im- d it to their dependencies.
is a point of singular interest to know that a map of the cholera- mic of 1833 in the United States is almost identical with the map e epidemic of 1873.
om the line of the Ohio River, the States of Illinois, Indiana, and were devastated upon the north, while upon the south the State of ucky was overrun with the disease, whose lines of infection extended the State of Tennessee, met the lines of infection from the Mississippi, culminated in the explosion at Nashville. Upon the east, the of Virginia was infected from the Ohio, Wheeling receiving the blow, and in turn transmitting the disease to Shepherdstown, Fred- sburgh, and Charlestown. Lastly, Pittsburgh was infected, and Alle- y, Brownsville, and Claysville followed.
e medical journals of 1832 and 1833, although filled with cholera- s, contain surprisingly few attempts to trace the disease. It seemed almost universally accepted that the diffusion through the United es was influenced by atmospheric causes; and beyond the paper of Beck, which has already been noted, no attempt seems to have been e to note the travels of the disease, with the incidents attending its sion. At a later date, Dr. Marsden collected many facts of value.
e journals of these years abound in articles upon pathology and tment of the disease, but very little can be found which throws any t upon the travels.
rom Dr. Elsworth Eliot, of New York, we have received several clip- gs from various publications of the years in question, some of which rly show the mode of introduction of the disease. The instances dem- rating the portability of cholera are fragmentary, and from necessity t be presented in a disconnected shape. A New Haven paper repub- s the report of the Cincinnati board of health for July 19: "It was overed that the cholera was indeed in the midst of us; two individuals this day and one the day following. We deem it proper to say, of the individuals above named one had just entered the institution, e Seminary,) having recently arrived from Natchez, and that he for twenty-four hours neglected the premonitory symptoms. Another been for several years an invalid, whose constitution was impaired chronic affection. He came here for the benefit which he hoped to ve from associating manual labor with study, and was known among s a feeble man. Concerning the other, we are sorry to say that his th is chargeable to his own presumption. Notwithstanding the reit- ed request and entreaty of the board, he neglected a diarrhœa till ate a stage of the disease that no remedies could avail."
During the epidemic, the inhabitants of the State of Kentucky suffered t severely. Lexington was again attacked after the disease had ap- ed at Maysville, Flemingsburgh, Georgetown, Cynthiana, Millers- gh, and Paris. From Lexington, the disease was distributed to Ver- les, Lawrenceburgh, Frankfort, Lancaster, Danville, and towns of er note, and from each of the localities named the lines of infection

radiated, until nearly the entire area of Eastern and Middle K[illegible] became infected.

It was reported that up to the 12th day of July, over four hu[illegible] deaths had occurred at Lexington; that the mortality was increa[illegible] and that it was difficult to get rough boxes made fast enough to [illegible] dead away.

In the elaborate papers of Drs. L. P. Yandell, sr., Benj. W. Du[illegible] and John E. Cooke, upon the epidemic at Lexington, Ky., a total a[illegible] sence of all attempts to trace the cause of the epidemic and its prog[illegible] is most strikingly evident. It seems to have been accepted as an u[illegible] swerable fact "*that cholera arises in the very same circumstances in w[illegible] fever and dysentery arise,*" and no note is made of the connection be[illegible] cases, which must have occurred.

That cholera was distributed from Lexington to the surroun[illegible] country is shown by the following incidents:

On the 18th day of June, 1833, late in the evening, a wagon laden [illegible] merchandise for the store of William Cooke, who was at that tim[illegible] principal merchant of the place, arrived at Lancaster. These goo[illegible] been loaded upon the wagon at Lexington, which was unloaded the [illegible] ing of its arrival, and the goods unpacked and placed upon the sh[illegible] in Mr. Cooke's store. Before noon the next day, Mr. Cooke, two o[illegible] men who had assisted in handling the goods, and the wagoner w[illegible] dead from cholera; and from the 19th of June to the 8th of Ju[illegible] hundred and sixteen deaths occurred. From Lancaster the disea[illegible] carried to the surrounding country.

We have been informed by our friend Dr. J. D. Jackson, of Da[illegible] Ky., that the first cases of cholera that occurred in Boyle Coun[illegible] 1833, were in the persons of five negroes, employed as teamste[illegible] transporting goods from Louisville and Lexington to that town.

By Dr. W. M. Tomilson, of Mercer County, we are informed tha[illegible] first case of the disease at or near Harrodsburgh was in the person [illegible] man just returned from Lexington.

At Lebanon, Ky., a stranger arrived from Lexington during the e[illegible] demic at that city. He put up at the hotel, and during the nigh[illegible] was taken with cholera and died the next day. The negro who wa[illegible] upon him was next attacked, and from him the disease spread to [illegible] fellow-servants. These cases occurred in the practice of Dr. M. J. Sa[illegible] who is still a practitioner of Marion County.

From Lebanon the disease was carried into the surrounding co[illegible] The first case that occurred at the town of Springfield was in the p[illegible] of a man from Lebanon, and the same thing may be said of other [illegible]

A Mrs. H. died at Maysville of cholera. Her body was take[illegible] Flemingsburgh, where it remained unburied one day. The next da[illegible] deaths occurred among those who had visited the corpse, and the di[illegible] spread rapidly.

At Summerset, a village of about 1,200 inhabitants, in Pulask[illegible] ty, Ky., cholera first occurred in the person of a refugee from Lanca[illegible] and in seven days thirty-four deaths occurred.

At Maysville, Ky., the city is represented as having exhibited a [illegible] that finds no parallel in its previous history. The disease occurre[illegible] the 3d of July, and up to the 12th forty-one deaths occurred.

We have been informed by Judge R. Hawes, of Paris, Ky., th[illegible] Dr. J. D. Jackson, of Danville, that the first cholera-deaths in Bou[illegible] County, during this epidemic, occurred in the persons of two men, [illegible] Johnson and Kennardy, who arrived at their homes from May[illegible] during the epidemic at that city.

r. Z. T. Robards recorded in the Transylvania Journal of Medicine, July, August, and September, 1834, that during the epidemic of , a young man arrived at Shepherdsville from Louisville, and pro- ed to the house of his father, two miles east of the town; that he had diarrhœa for some time before his arrival. The evening of his al he was taken with cholera, and died after ten hours; all the in- s of his house had diarrhœa; in two, cholera was fully developed; case died.

ie sister-in-law of the first case and her husband, living at a differ- location, took the disease and died.

uring the same epidemic, a negro woman, from an infected locality, rned to her master's house at Shepherdsville. She was taken with era, but recovered. Her mistress, who cared for her most attent- , took the disease and died. The brother of this lady lost his ghter, six years old, and a number of his negroes.

r. Robards relates three other instances of the portability of the dis- , and offers the following remark: "Those who argue it is not con- ous or communicable in any way from one to another, use an argument ivor of their position which are not deemed just, that persons go re the disease is without taking it. Because a man may go into le and return without being shot, is it fair to say that there is no ger in bullets?"

o this record the following note is appended, which is reproduced ffording an exact index to the professional mind of the period: ie very fact, however, of the appearance of cholera at those places ridence of insalubrity. We think it is easy to account for all the s contained in the above history without a resort to the doctrine of tagion, which the vast body of evidence presented by the progress holera has, in our view, forever overthrown.—ED."

r. Robards wrote the only account of the epidemic of 1833 in Ken- ky in which facts were given; while his professional brethren would rwhelm him with theories and no facts, he alone attempted to give ain history of the early cases that occurred.

rom the New Haven paper before noted we read, that early in July, of a party of German emigrants *upon the Mississippi River*, on their to Saint Louis, sixteen out of a company of one hundred and fifty, died of cholera.

arly in July the disease was reported at Palmyra, Mo., and before clock p. m. of the day of explosion ten deaths occurred.

he instances given by Dr. M. H. Houston as having occurred during epidemic of 1833 at Wheeling, Va., are certainly strong evidence in or of the infectiousness of cholera. The village of Bridgeport, now art of the city of Wheeling, is located upon a small island in the o, but half a mile from the city of Wheeling. The village was in lthy condition, and contained two or three hundred inhabitants. olera was epidemic at Wheeling on the 15th of May, but the disease not occur in Bridgeport until the last week in June. The village near enough to the city to be subjected to the same atmospheric uences, if cholera is originated by them; was dirty enough to have lera, if filth generates the disease; but more than a month passed, the village escaped. But when it did occur, within the first thirty- hours twenty-two of the inhabitants died. The solution of this blem is most easy. Although communication between Bridgeport Wheeling was of necessity kept up, *it was very much restricted through r of cholera.* No person infected with the disease arrived on the nd until late in June; but the infection once arriving, its reproduction

was rapidly advanced by the filth of the village, and when the cholera explosion did occur its consequences were frightful. Dr. Hume makes no note of special cases. The initial case was unnoticed. The same argument accounts for the isolated outbreak that Dr. Hume notes as having occurred five miles from Wheeling.

In 1834, epidemic cholera again appeared in North America, and the second time its advent was upon Grosse Isle, on the Saint Lawrence. Dr. Marsden records that, on the 4th day of July, 1834, the John, from Dublin, arrived at the quarantine-station with two hundred and sixteen emigrants on board, having lost a large number from cholera on the passage out. On the 6th day of July, the John arrived at the port of Quebec (having passed quarantine without opposition) and landed her passengers. The next day cases of cholera were reported in the city. Four days after the outbreak a public excursion was organized to visit *the quarantine-station*. The commander-in-chief and his staff, a large number of ladies and gentlemen, and a few strangers, with the band of the thirty-second regiment, participated. Dr. Marsden remarks: *Quem Deus vult perdere prius dementat.* The disease spread rapidly from that time, and again advanced along the line of the Saint Lawrence.

As a case strongly illustrating the infectiousness of cholera Dr. Marsden relates the instance of three gentlemen who had gone to Beauport, some twelve miles from Quebec, on a shooting party. After returned to town they called at the house of a farmer to rest, and were shown into a room which, until the moment of their entering, was occupied. While in his room the party drank some brandy and started to continue their walk to the city. Within two days two of these gentlemen were dead from cholera; the third had the disease, but recovered. It was subsequently ascertained that the wife of the farmer had died of cholera in the room occupied by these gentlemen, and that the room had not been entered since her dead body had been removed.

It will be remembered that the town of Three Rivers, situated midway between Quebec and Montreal, had established a *cordon de troupes* in 1832, and thus escaped the disease; but in 1834, influenced no doubt by the theory of non-contagion that had rapidly gained notoriety during the two preceding years, this precaution *was not adopted*, passengers from Quebec were permitted to land, and a devastating pestilence ensued.

Montreal was again infected from Quebec, and from that city the disease spread into Upper Canada and the United States.

During the epidemic of 1832, Nova Scotia had entirely escaped the disease, but in this year cholera was carried into the port of Halifax, spread through the province, and extended to Saint John's.

Dr. Vaché states that the village of Galt, in Upper Canada, was almost depopulated.

Following largely the route of the former epidemic, the towns and villages upon the lakes were infected.

From the lakes, by means of Lake Champlain and the North River, the State of New York was again infected, the disease reaching New York City on the 9th of August.

The query now becomes pertinent: Was not New York City primarily infected in the same way that she was infected in 1832?

Dr. C. A. Lee stated that about the 1st of July bowel-complaints began to prevail very extensively, especially among the poor residing in crowded, ill-ventilated apartments, and occasionally a case occurred with the same symptoms as attended the cholera of 1832. "On the 14th of July, a few days after its appearance in Canada, I attended a pa-

) had been employed in rafting and had been much exposed to wet fatigue; an intemperate man, and living in a filthy habitation. I nd him with violent cramps, cold, shriveled skin, rice-water dejections, almost imperceptible pulse, and the other symptoms characterizing stage of cholera. He recovered."

1 New York City, the total deaths from cholera during this epidemic e eight hundred and twenty-seven to September 20, when the dis-) disappeared.

ew Jersey, Pennsylvania, Maryland, the District of Columbia, Vir- a, Georgia, Florida, and Texas, upon the sea-coast; and Ohio, Michi- , Kentucky, Tennessee, and Mississppi, in the interior became in- ed with the disease.

was admitted universally that Pensacola was infected with the dis- after the arrival of the United States ship Falmouth with cases of era on board.

1 1835, cholera was again introduced into the United States from a, where the disease was especially virulent at Santa Iago, Havana, the south side of the island.

ew Orleans and Charleston, the latter city, for the first time, espe- ly, suffered from the disease.

n unanswerable argument against the theory of the atmospheric or ıric origin of cholera is found in the facts demonstrated by the epi- ics of 1832, 1833, 1834, and 1835, that cholera was developed upon North American continent:

After the disease had become epidemic in foreign territory with ch the North American continent was in constant communication.

. That epidemic cholera occurred in North America only after the val of vessels from such infected countries, and after the arrival of els that, during the voyage to American ports, had become infected the disease, in the persons of passengers.

I. That in no instance during either epidemic did the disease ap- r in the interior of the continent until a sufficient time had elapsed the conveyance of the infection from the foci established upon the oard, in the persons of individuals.

CHAPTER V.

EPIDEMIC WHICH REACHED THE UNITED STATES I

Resuming, now, (says Macnamara, p. 77,) the history of cholera dia, we find that the outbreak in 1826 and 1827 had almost s in 1829. In 1830, there was but little cholera in India. In 1831 a it raged principally near the holy city of Gaya, near Patna, a peared at Patna, Purneah, and other places near by, just as it di breaking out at Jessore in 1817. In 1833, it was farther up the Ga Allahabad; and in 1834, the lower northwest provinces were a der the influence of invading cholera. In 1833 and 1834, it was vere at Bellary, in the Madras presidency, coming, doubtless, f holy city of Bigginuggar, which now began to attract attention, high table-lands near it, although 1,600 feet above the sea, wer to be the home of cholera to a greater extent than any other po Madras. The central provinces, from Nagpore along the whol of the river Nerbudda, almost to Surat on the Arabian Sea, w suffering from a wide-spread epidemic. The river Nerbudda is r by the pilgrims almost as holy as the Ganges.

In Bombay, on the west coast, among the European troops, the only thirty-five deaths in 1831, one hundred and thirteen in 1 two hundred and sixty-three in 1834. This epidemic reached and the basin of the Mediterranean in 1836 and 1837, and was a the remains there of the outbreak of 1831 and 1832.

In 1835, cholera was at a very low ebb throughout Bengal; a was another year of rest. In 1837, it was very prevalent, and it to be assumed that there might be a repetition of the same phen which had occurred in 1817, 1826, and 1833, viz, a vast outburst disease occurring throughout the whole of Bengal in the east, gr advancing to the west and northwest as far as 78° east longitude; halting for the cold season, but throwing forward its feelers in provinces beyond the invaded area. (*Ibid.*, p. 89.)

In 1839, it had got over the borders of India into Cabul, toward sia. The British troops entered Affghanistan in 1838, and found c era raging near Cabul, but did not then seem to spread into Persia.

In 1840, the government of India dispatched a combined Eu p and native army to China in the interests of the opium-trade. It c cholera with it, which not only reached Pekin a second time in the of China, but probably followed the route of the caravans as far Russian station of Kiachtha, from whence it is known that it afte passed west through Siberia toward Russia. Cholera was also sent ward from the neighborhood of Canton in the south of China, reached the north of Burmah in 1842; and is supposed to have c tinued through Thibet to Cabul. In 1841, 1842, and 1843, the e seaboard and much of the interior of China was under the influe cholera, from whence it was spreading westward towards Central A

In 1841, it was again prevalent at Juggernaut; also in 1842. It i it was fearfully epidemic at Agra, above Allahabad. In 1844, again shrunk back to its epidemic area in Lower Bengal, when suddenly reported as breaking out in Cabul. The governor-g agent announced that it had advanced steadily from Bokh

ıtral Asia, southward to Cabul, and from there down to Peshawur, northwest border town of India. The singular spectacle was now sented of India being invaded by cholera from Central Asia, to which s supposed to have come from China. Thus, Dr. Arnott, inspector- ieral, reported that at the end of the hot season of 1844 Balk and khara, in Central Asia, lost upward of 25,000 of their inhabitants; narcand and Koondooz, not far off, also suffered to a frightful ex- t. Traveling south and west, it reached Cabul in the middle of ober. By November 8, it was lower down at Jellalabad, and, at the of the month, at Peshawur. In May, 1845, it was at Lahore, where arried off twenty-two thousand people, and continued its course down ard Central India. It also went down the river Indus to Tatta and rrachee, near its mouth, and escaped out towards the Persian Gulf. cnamara, p. 107, says:

"From a careful study of these facts, we can arrive at no other con- sion than that this outbreak was a continuation of the epidemic ich had been carried east by British troops to China in 1840; that hen traveled west through that populous country, reaching Burmah 1842. If it continued its course north of the Himalaya Mountains he usual rate of progress, it would have reached Bokhara in the very ter of Asia in 1844; from whence it thrust down its branches into ghanistan and Northern India, while other offshoots spread to the t, so that it appeared in the holy city of Meshed in the northeast 'ersia toward the close of 1845, brought there by pilgrims coming n Cabul and Herat. It burst forth in Meshed again with renewed ence in June, 1846, quickly extending to Teheran near the foot of the pian Sea, killing nine thousand persons in four months. Before the of 1846 it had advanced by land from Teheran to Tabreez, where two hundred to four hundred persons died per day; and was again ts way into Russia. It had also been carried from Reshdt, by water, ar north as Derbent on the west coast of the Caspian Sea, having iously appeared at Salian, Leukoran, and Baku. In April, 1847, it ppeared at Derbent, and was transmitted to Kizliar by a detach- t of invalid Russian troops, and spread over the Steppes as far as Volga, reaching Astrakan for the third time on July 30, 1847.

rom Teheran and Tabreez it had also reached Tiflis, and spread from e due west, via Gori, to Poti on the Black Sea. From Teheran and reez it was also carried along the regular caravan route through Erze- a to Trebizonde on the Black Sea by September, 1847. Drasche, p. laces great stress upon the presence of a very large Russian army ie Caucasus, as spreading the disease. A great military road had made from Moscow directly down to Tiflis, and cholera followed new path, crossing the Caucasus Mountains to a height of six thou- feet, and affecting villages at the foot of the mountains on both along this only available pathway. This point had again been par- arly watched, in order to see whether the disease was brought by le or blown by the winds. There was no doubt that it was conveyed d carried over the mountains by soldiers. The great road ran from north to Staropol, Taganrog, Vorenetz, and Toula to Moscow; and ese places became involved in succession.

om Astrakan it ascended the river Volga, as in 1830, affecting the places, but again avoiding Sarepta, where a strict quarantine, isolation and great cleanliness, was enforced by the Moravians. n it reached Saratov, Pensa, Simbirsk, and Kazan, high up on the a, it turned east to Orenburg, which it reached in October, 1847,

and towards which another column of the disease was advancing from China, through Southern Siberia, by way of Tobolsk.

From Kazan it also went west to Nijni Novgorod, threatening Moscow from the east as well as the south, and finally arrived at it on September 18, 1847.

In the mean time, cholera had been carried from Trebizond on the southeast coast of the Black Sea to Constantinople, from where it was sent down to Smyrna, and back into Asia Minor toward Persia. It had also been carried from Taganrog and Azof westward to Odessa and then advanced up the river Dnieper toward the holy city of Kiev, in the direction of Poland.

It broke out in Constantinople on October 24, 1847, and early in the next spring was carried both from there and Odessa to the mouth of the Danube and up into Austria, to which it was also moving overland from Odessa to Jassy towards Pesth. It attacked a Russian army heavily that had advanced into Moldavia, and also a Turkish force on the banks of the Danube. It re-appeared in tremendous force early in 1848, when the Kossuth war broke out, and large Hungarian, Russian and Austrian armies, amounting to at least 800,000 men, marched into the field. It followed them in all their marches, involving Hungary and Austria very severely and extensively. It was also carried over into Italy by Austrian troops during the disturbances of 1848.

It had advanced upon Poland and the Baltic provinces both from St. Petersburg and Moscow; from the latter place by way of Smolensk and Minsk; while it had also been coming from the south, viz, from Odessa and Kiev to Lemberg and Lublin, just southeast of Warsaw.

It was at Riga, on the Baltic, in the winter of 1847, and passed from Poland into Silesia and Posen west toward Berlin, and also west along the Vistula to Königsberg and Dantzic, and up the Oder to Stettin. It was in Breslau early in 1848; in Berlin in July, 1848, where the epidemic lasted eighteen weeks, with two thousand four hundred cases. The greatest number of attacks as usual were among the boatmen and in the streets near the river Spree. It was carried along the Elbe to Hamburg by September 1, 1848, and was in Bremen on September 3, and appeared in London in the beginning of October.

The celebrated Dr. Parkes was selected to inquire into the origin of the cases that occurred in London. The first fatal case was a man named Harnold, who arrived on the 18th of September in a steamer from Hamburg; the next was a man who slept in the same room with Harnold. The second engineer died from cholera on the passage, and M'Namara says, "It was known that the disease was prevalent at Hamburg some time before the vessel started."

It was brought to Edinburgh from Cronstadt, and to Hull and Sunderland from Hamburg.

The first instance reported in Ireland was in a man who arrived at Belfast on December 2 from Edinburgh, which was already infected. He was sent to the workhouse and died there. Cholera soon spread to the inmates and from thence to the town.

It did not reach Paris till March, 1849; but by the end of June there had been over thirty-three thousand cases.

During this epidemic the belief in the absolute and unconditional contagion of cholera had faded almost away; but its portability was very generally admitted. Its regeneration and communicability in some way, in connection with its diarrhœal commencement and spread, was beginning to gain believers. The celebrated Drs. Simpson,

istison, of Edinburgh; Von Gietl, of Munich; Kirk, of Greenock, tland, and Professor William Wagner, of Berlin,* were particularly ve in propagating this theory. Dr. White, of Gateshead, noticed rever cholera occurred that premonitory symptoms would frently arise among those engaged about the patient, or in their imme-e neighborhood. He often witnessed a diarrhœa with dark-brown blackish stools, gradually becoming less feculent for several days, il they assumed the appearance of dirty water; all attended with ht cramps, giddiness, and nausea. At the end of six days the patient ild sometimes recover spontaneously, or with little aid from treat-nt, but might suddenly go into collapse; or some of his friends and tives would contract cholera in a mysterious way. Dr. McIntyre, of rcastle, thought the infective diarrhœa continued from one to seven s, (and in the mean time many persons might be involved in strange icks.) Drs. Frost and Clark, of Newcastle, noticed a preceding rrhœa of from one to twelve days' duration, in nearly five hundred es; and in some few instances beyond this period, (during all which e the patients were doubtless sowing the disease broadcast.) Dr. wson, of Newcastle, noticed that diarrhœa generally preceded spas-lic cholera for some days. Dr. Brady, of Gateshead, found a fore-ng diarrhœa lasting from one to six days; Dr. Knaggs, from one to ten s. Professor John Lizars, of Edinburgh, was particularly enthusi-ic and earnest in adopting this view. Dr. Cunningham, of Tranent, tland, found the antecedent diarrhœa continued from a few hours to en or eight days; Dr. Campbell, of Edinburgh, from one to ten s; Dr. Steele, for fourteen days, before serious symptoms came on; Dunbar, of Musselburgh, noticed previous diarrhœa for several s, or even weeks. Finally, Dr. John Fyfe, of Newcastle, distinctly forth the propositions that the period of the incubation of the mor-c germ of cholera seemed to vary from four hours to eight days; and t the effluvia from the excretions of an individual having diarrhœa-oleraica might communicate to another predisposed individual the st fully-developed form of the disease.†

Thus, instead of looking to a general distemperature of the air for the se of cholera, a large class of astute and painstaking physicians an to watch for a local regeneration and multiplication of the dis-ler proceeding in some way from the bodies or evacuations of the k. But the subject was fraught with many contradictions and diffi-ties; and Dr. Fyfe could not fully grasp the importance of his own servations, although Drs. Simpson, Wagner, and Von Gietl did. He s much perplexed when he found in sixty-seven cases that forty-four re single individuals, in families varying from three to eight persons, ny of them sleeping in the same bed with the infected, and among om there was unlimited intercourse; for it was impossible to separate diseased from the healthy. He also noticed that when several mem-rs of a family suffered, they were often attacked simultaneously, or such quick succession as to apparently preclude the possibility of eir being affected by contagion or infection.

It struck attention that those who lived in houses secluded from the ht, and colliers who were exposed to the influence of cholera evac-tions down in the close mines, were very subject to attacks. The scharges seemed to receive a peculiar potency in these confined and dly-ventilated places; or the drinking-water in the mines may have

* The Extension of Cholera in Prussia, Berlin. 1832, p. 145.
† Practical Observations on Cholera Asphyxia, by James B. Kirk, M. D., of Greenock, 32, p. 72.

become contamined. Then it began to be noticed that successive attacks were apt to recur in the same houses at long intervals, as if the dried excretæ were more dangerous than the fresh moist ones. It also became apparent that if all the causes of ordinary summer, or autumn diarrhœa, had prevailed in a place for weeks or months before the advent of cholera, the epidemic was apt to prove very decided and virulent. Likewise it began to be suspected that the dried or moist excretions might be conveyed into the systems of others in some way, either by inhalation, which seemed rarely to take place, or by swallowing particles of them in food or drink; the former being soiled by the unwashed hands of the patients or their attendants, and the latter fouled by the carelessness with which the discharges were thrown out of doors, near wells and pumps. At St. Petersburg, the people, almost wiser than some of their doctors, ascribed the appalling number of deaths that occurred in every part of the city to a poisoning of the water not from their own filth and carelessness, but by some concealed enemies.

It was also noticed that the disease did not die out entirely in some places. At Moscow, in 1847, as winter approached, the number of attacks became so small that hopes were entertained that it was altogether subsiding. A very significant fact, however, was stated by Dr. Alex. Crawford, viz, that occasional cases continued to occur throughout the winter, affording too much ground for apprehension that the malady was only suspended by the cold, dry state of the atmosphere, and that it would break out again in the spring,* redeveloped and swarming from the cases that had lingered over; just as plants and insects start out in the early months of the year.

In England, most unfortunately, not one case in ten was reported to the boards of health, (*Ibid.*, p. 10,) so that a close watch over the rise and progress of the disease could not be kept. During the winter of 1848, in London, although the deaths never exceeded five per week, and sometimes sunk so low as *one*, the disease never entirely disappeared. There was no single week without at least one death; a most significant fact when taken in connection with what had been previously observed during the suspension of the epidemic in Moscow. In the month of May, 1849, the total number of deaths from cholera in London did not exceed thirteen; but by the last week in June there had been one hundred and twenty-four. From that period the pestilence went on rapidly and uninterruptedly increasing. (*Ibid.*, p. 12.)

A succession of new cases, both of diarrhœa and cholera, soon developed out of those which had wintered over. Another very important fact was acknowledged, viz, that the epidemics never broke out suddenly, but that single cases of the disease occurred a considerable time before the actual presence of the pestilence was admitted. The earliest cases were either overlooked, concealed, or recorded under an erroneous or false name, on the ground that they were doubtful, and that at all events it was unwise to excite alarm. It was finally found that cases of cholera had been imported, not only into London, but into Hull by vessels direct from Hamburg, and also into Edinburgh. In London, Hull, Edinburgh, Glasgow, Plymouth, Manchester, Dundee, Bristol, Liverpool and every town in Great Britain in which the initial cases were actually detected, its invasion was similar. There was a slow uprising of the pestilence by means of isolated attacks, occurring at considerable distances as to place, and intervals as to time, which must be regarded as one of the laws of the disease. The popular notion that cholera is sudden in its invasion of a place or district proved to be as unfounded as the former

* Report of the General Board of Health of England for 1848 and 1849, p. 7.

valent opinion that it is always sudden in its attack of the individual son. Experience refuted both of these suppositions and established very opposite, viz, that cholera is gradual and even slow in its de-opment in every place and person, (*ibid.*, p. 17,) unless water-contami-ion quickly occurs. "These isolated cases began to be regarded as nings not to be mistaken, and often as unequivocal and certain signs t an outbreak was impending. They generally demanded the imme-te and energetic adoption of preventive measures," because from them r cases, both diarrhœal and choleraic, were sure to arise. The den outbreak in Paris, March, 1832, was now discredited. That city l been in communication with Germany, Holland, and England, in ich the disease was prevailing for more than a year. Then, according M. Gendrin, on the third day after the first case was publicly reported, received sufferers from every district of Paris into the Hôtel Dieu. The ients' distant residences and opposite professions seemed to preclude probability of their having derived their complaint from human con-t alone. Within a week after the first alarm the mortality reached hundred per diem, and the cases four times that number. In eighteen s no less than seven thousand persons had died. It may safely be umed that all the first steps and initial cases in this tremendous out-ak were overlooked in Paris. The water-supply was notoriously bad ore the great artesian wells were completed in 1841, and the privy-angements were worse, so that a quick outburst might be expected. The theory of the long dormancy of germs now began to arise. As s anticipated and predicted, cholera in 1848 returned to the same dirty es and towns, and in a few instances to the same streets, houses, and n filthy rooms, which it had ravaged in 1832. In very rare cases it appeared on the very spot in which it first broke out sixteen years ore. The first case that occurred in Leith, in 1848, took place in the ne house, and within a few feet of the very spot from whence the epi-mic of 1832 commenced its course. On its re-appearance in Pollock-aws, it snatched its first victim from the same room and the very same l bed in which it broke out in 1832. Its first appearance in Bermond-s was close to the same ditch near which the earliest fatal cases oc-red in 1832. At Oxford, in 1849, as in 1832, the initial case occurred the county jail. At Groningen, in Holland, the outbreak in 1832 at-ked only two dwellings in the better part of the city, and the epi-mic in that part of the town commenced in these two identical houses the visitation of 1848, (p. 18.) Some of these cases, if true, are hard to plain; but they are so few compared to the millions of opposing facts at they are mere curiosities of experience. Others are easily brought out by drain-connections, underground water-courses, &c.

It was also found that the seats of cholera had often been the usual unts of other epidemics, especially of typhus and typhoid fevers. In notorious fever-haunt in Old Nichols street, London, in twenty-three uses fifty persons were attacked with cholera, of whom thirty-three d, besides developing nine cases approaching to cholera, and one hun-ed and ninety-seven cases of choleraic diarrhœa. Hence, two hundred d six cases were left alive to spread the disorder. New Nichols street sely adjoins it, and there twenty-one persons perished of cholera; irty more were attacked, but recovered, besides two cases approaching cholera, and one hundred and thirty-five cases of diarrhœa; leaving e hundred and sixty-seven persons to scatter abroad the complaint. Swineburne's Yard, containing eleven houses and thirty-five inhabit-ts, and but one privy for the accommodation of all, fifteen died of olera, (p. 21,) leaving twenty to infect others.

In England, during 1848 and 1849, cholera often attacked definite spots in the district which it invaded, confining its ravages to particular streets, the adjoining ones escaping; or even to one side of a street, scarcely a single case occurring on the opposite border; as if the cause had been dropped like tares, by an enemy in the night, or by wandering diarrhœal cases.

At Rotherhithe, in a street where numerous deaths occurred, the attacks were almost entirely confined to one side of the street, occupied by respectable private families, and appeared in only one house on the other side. At Bedford, two streets are named as having each suffered on one side severely, the other nearly escaping. At Bristol, and in several other towns, the same curious fact was observed, and it had also been noticed in St. Petersburg and some other foreign cities. In this respect cholera was supposed to bear a marked resemblance to typhus, yellow fever, and plague, (p. 23.) We may infer that the house-drains were continuous on the affected side of the street, but did not extend to the other; or that the water-supply was divided, and different pumps were used; or that old underground streams carried on the products of the disorder. In other cases "the pestilence passed right through and across several streets like a cannon-ball," following perhaps the course of foul drains and old water-courses. But the observers of these facts contented themselves with wondering over them, or attributing them to malaria.

Sometimes places were attacked in groups; that is, it seized on a certain number of courts, alleys, or streets, decimated their inhabitants, then ceased, and again broke out in a similar manner, often at the opposite extremity of the town. In this way six, eight, or even more deaths not uncommonly occurred in one house, (p. 23.) In all these instances it had doubtless been introduced by diarrhœal cases.

It had been noticed in several countries that it did not, as usual, advance by a strictly progressive and uninterrupted pathway, but that, at one time, it sprang at a single bound over a large tract of land or sea, while, at another season, it absolutely turned back on its steps in a retrograde direction, just as travelers take long journeys in varied and opposite directions. Its progress through a city was similar, there being in general no regular continuity in its course, for its advance was made up of a succession of local and often distant outbreaks, best explained by the moving to and fro of infected people, and clothes, and the contamination of particular water-sources, drains, or privies by ambulating and unsuspected diarrhœal cases; or by the arrival of the latter in overcrowded and filthy places. The mysterious, tremendous, and so-called sudden outbreak in Kurrachee on June 14, 1846, near the mouth of the Indus, was now satisfactorily explained. In that year three European regiments were stationed there. Cholera commenced in November, 1845, with several isolated cases in the camp, town, and vicinity during the cold, hot, and dry seasons. What was wanting for a great explosion was supplied about the beginning of June, 1846, when the southwest monsoon commenced and the air was not only laden with moisture, but the streams began to overflow. Then an appalling tropical storm occurred. The tents were blown down, the men were exposed, the streams were defiled, and four hundred and ten cases and two hundred and thirty-eight deaths took place, in the three regiments, between the 11th and 25th of June, and over eight hundred cases in a few days more.

The partisans of the many hypotheses, or rather notions, as to the

se and progress of cholera were in constant collision with each
er and with facts.
be first supposition, that it advanced like a great morbific wave,
ing slowly and steadily westward, enveloping place after place, and
ntry after country, with a certain, steady progress, at nearly regular
rvals, was fast losing ground, for it notoriously had advanced east-
d, northward, and southward, as well as westward.
s it often seemed to come with ships, and the commerce of the world
then carried on by sailing-vessels, it was next supposed to be
ru about by the winds; and that the same gales that brought the
t also wafted the disease to and fro in every direction. This view
strongly supported by the fact that the first reported fatal cases did
always happen among new arrivals, but often in old residents. But
l-travelers frequently brought the pestilence in spite of and in the
and teeth of the winds. Then the ships were supposed to bring it
their holds, and well travelers in their soiled clothes, especially in
se which had been boxed up.
ome believed that a great and almost universal epidemic distemper-
re of the surface of the earth and of the air, like that which seems
cause malarial diseases, cholera infantum, summer diarrhœa, and
entery, prevailed in every country and caused a disorder like the
atic pestilence, powerfully aided by the heat of summer, filth, over-
wding, bad food, and worse water.
he adventurous person, at least, firmly believed that cholera was
sed by great subterranean vapors, which burst forth like volcanoes,
erever they got access to the surface; this was only a little more
urd than the malarial and ground-water hypotheses.
t was very long before it was seen that there was a better theory
the outbreaks of Asiatic cholera: one founded on the arrival of the
ction of the disease, either in the confined air or bilge-water of
sels, or in the persons and soiled clothing of those suffering either
h the diarrhœal or fully developed form of the complaint, and the
lition thereof to any or all the causes which produce similar disor-
s in the country to which it was brought, especially to filth, over-
wding, bad ventilation, miserable drainage, poor water, indigestible
soiled food, and bad habits of all kinds. Thus could be explained
march along the great traveled roads; its keeping time with the
vements of travel and never outstepping them; its following the lines
commerce, and bringing the disorder in tarnished clothing, when it
not come visibly in sick persons; its attaching itself to armies,
following them over large districts of country, attacking certain
ns and villages and avoiding others; also, to caravans of pilgrims
merchants; its never being found outside the lines of travel and
mmerce; and in no instance of supposed spontaneous origin bearing
test of close examination, but always and everywhere commencing
er the arrival of persons or things from previously affected places.
ll the direct sequence of these events could not always be made out
thout some trouble and much previous knowledge.
These differences of opinion arose mainly from the conflicting and con-
dictory behavior of the disorder, not always from want of earnest-
ss or intelligence in the investigation. As the real causes could not
ariably be detected and grasped, the accessory agents and exciting
uses were carefully studied, and often seemed to outweigh in impor-
nce the actual infection of the disorder. These were supposed to
alize and precipitate, if not generate it. In order to determine its
ecipitation upon and development in any given place, the localizing

conditions and predisposing causes of cholera received great attention in 1848. Among these, overcrowding was considered the principal. No health and strength cannot be maintained in a breathing-space of less than 700 or 800 cubic feet, and to live and sleep in a measure of less than 400 or 500 cubic feet is not compatible with safety to life during the prevalence of an epidemic on the spot. A certain large amount of animal matter of a highly putrescent nature always passes from the lungs, is deposited on the walls of living and sleeping rooms, and clings to articles of clothing, bedding, and other furniture, and causes no disease, while it is the source of the nauseous smell perceived on entering dirty and crowded dormitories, living-rooms, school-houses, &c. In June, 1849, a sudden and violent outbreak of cholera befell the workhouse of the town of Taunton. The ceilings were less than 9 feet high, and the ventilation extremely defective. In the girls' room sixty-seven children had only 68 cubic feet of air each. Within forty-eight hours from the first attack forty-two cases and nineteen deaths had taken place; and in one week sixty of the inmates had been swept away. The boys suffered less, because they could not be kept from breaking the windows; while the girls never shattered one. Doubtless the water-supply, privy-arrangements, and drains were in the same state of neglect. Still the chaplain stated his firm belief that it was to the better ventilation which the broken windows maintained, that the boys, in some measure, owed their lives, (p. 38.)

At Maidstone, fourteen hop-pickers slept in a room containing 700 cubic feet of air; each person having only 50 cubic feet, and one thousand more were accommodated in a similar way. Within four days there were ninety-seven cases of developed cholera, forty-seven deaths, and two hundred cases of diarrhœa. As the importation of the disease could not be traced without more trouble than can usually be taken in such outbreaks, we conclude it was probably introduced by an ambulant diarrhœal case. Among the pauper children at Tooting, each boy had 150 cubic feet of air, and each girl only 133. The windows in the girls' dormitory were small and few, being closed at night, while the doors were also shut, and the chimney-places boarded up. Out of one thousand inmates, three hundred were seized with cholera, and one hundred and eighty died, (p. 38.) The water, food, drains, privies, &c. were doubtless managed in the same nefarious manner. These children were dispersed in various directions, and carried the pestilence to several places. Finally Mr. Grainger stated as a general result of many examinations, that the force of the disease was in the ratio of the overcrowding, all other circumstances being equal; showing that cholera was produced in some way by the persons who conveyed it into the overcrowded places. If it were an air-borne disorder, free ventilation, instead of being the best, would be the most dangerous expedient: for it would be continually letting in the disease.

Foul-air diarrhœa received much attention in 1848. A manufactory of artificial manure at Spitalfields, in which bullocks' blood and night-soil were desiccated by the heat of the sun, and by the dry heat of a kiln, caused a most powerful stench. In December, 1848, sixty children out of four hundred, in the workhouse, only a few yards off, were suddenly seized with violent diarrhœa; the establishment was closed and the children regained their ordinary health. As cholera had not been introduced into the building, none was produced, and no one died. Five months after, the works were recommenced, and on the night following, forty-five of the boys, whose dormitories directly faced the factory, were again suddenly seized with severe bowel-complaint, with

girls, whose sleeping-rooms were in a more distant part and faced nother direction, escaped. The factory was again closed, and there no return of the diarrhœa, yet no cholera was produced. A similar ory in St. George, Southwark, produced the same effects, but no era. Diarrhœa and dysentery were traced by Dr. Baly in the Mill- s penitentiary to noxious animal effluvia wafted across the Thames i bone-boiling establishments, but no cholera, showing that an ad- nal cause is required to produce the latter disease.

t the prison in Brest, France, however, the water-closets communi- d with a drain which opened into the harbor. At low water, the hwest winds blowing up the unguarded drain forced back the me- ic vapors into the wards. After cholera was introduced, one hun- l and eighty-nine cases happened among the prisoners; while only e cases occurred in parts of the building exempt from this nuisance. ough it was assumed that malaria was driven up the drains, it was btless the noxious exhalations from cholera evacuations which were rn back, for the same had occurred in 1832, but not afterwards until ; while malaria should have operated choleraically at every conjunc- of low tides with southwest winds. The mud in the bottom of a canal : Cardiff, Wales, seemed to originate cholera. The water had been rn off, leaving a large surface of black, putrescent, and very offensive ment. Nineteen houses near by were affected, and only four escaped. ne hundred and seventeen persons living in them, forty-three had rhœa; and thirty-three developed cholera, with thirteen deaths. lera evacuations had doubtless got into the mud, if this was the only se of the disease; for it was recollected that at Dantzic, in 1831, y-one vessels from Riga were lying in the port, and that the men king in the mud-scows were among the first victims. Still other l cases had occurred previously, but were not reported till long after- d. Dantzic was then a base of supplies for the Russian armies oper- g against Poland, which accounted for the large number of ships hat nation which congregated there, notwithstanding the rigid land rantine which was enforced against Russia and Poland.

t Hamburg, in those streets which immediately faced the spot where numerous canals that have traversed the city, and become loaded h the excreta of one hundred and seventy-five thousand people, con- trate to pour their foul contents into the Elbe, the cholera raged ently. The accumulated poison from all the town cases was flooded rn there. The same happened in Berlin, where the numerous branches the river Spree unite loaded with all the filth from the drains and ris of the houses; so that the Spree is said to enter Berlin pure as wan and to leave it as foul as a hog. But these causes never produce lera until it is abroad in the land, or else it would recur every year. s always introduced into these places in some way either manifest or ult.

Dr. Sutherland called attention to the fact that the higher stories flats of the houses in the larger towns of Scotland were the most healthy. A great deal of epidemic and choleraic disease prevailed the upper stories of the loftiest tenement-houses, where a compara- ely pure atmosphere should surround the dwellings. Houses with ht or ten successive nests of families piled one above another, in as ny stories, are by no means uncommon in Edinburgh and Glasgow. ny of the stairs and passages or entries which branch off from the ferent stories, or flats are dark and noisome; and from the absence all water-supply, water-closets and domestic conveniences, they be- ne the depositories of much filth of the most disgusting kind. The air

in them was most impure and extremely offensive. The absence of out-door privies and conveniences led to a most abominable condition of the closes or court-yards and alleys. There were no means provided by which the solid and fluid excreta of the households could be removed, except by the laborious process of carrying them down. There were neither closets, sinks, nor dust-shoots, so that all the offensive refuse had to be retained within the inhabited rooms and in immediate proximity to the scanty water-supply; whereby the water was rendered unwholesome by absorbing foul exhalations. The practical result was that the house refuse was thrown out of the windows into the alleys below, where the pumps were often situated. When a case of cholera was introduced into the top stories of such houses, the result may easily be imagined.

In a court-yard in Bristol forty-four deaths from cholera occurred. The drains were lower than the sewers; the privies became choked; there was not a drop of water on the premises fit to drink, that supplied by the only pump being wholly unsuitable from its privy-tainted nature.

A Bristol burying-ground, eighty feet long and fifty broad, was surrounded by houses in which forty-seven cases and thirty-three deaths from cholera occurred; among them a most distinguished surgeon, M. Key, whose valuable life fell a sacrifice. His back windows looked directly into the grave-yard. He had complained several times, shortly before his attack, of the offensive smell proceeding from the burial-ground, in which some cholera corpses had been interred. In one house there were eleven cases, and in several from five to six each, (p. 59.)

Dr. Sutherland reported that during the epidemic of 1848 and 1849 much additional evidence was elicited, proving the influence of *impure water* in predisposing to cholera. "There has scarcely been a town in the British Kingdom, in which cholera prevailed, that did not afford an instance of it; and where the water was contaminated by the contents of the sewers or privies, or by drainage of grave-yards, the seizures have been more sudden and violent, and the proportion of deaths to attacks greater even than from overcrowding." At Hackney a cess-pool was placed within one yard of the only well that supplied water to twelve houses with eighty-five inhabitants. Of these, twenty-two did not use the water and remained healthy; of the remaining sixty-three, forty-six were attacked with severe diarrhœa and cholera. In five houses in Windmill Square, with twenty-two people, supplied by a well into which refuse and the contents of cess-pools percolated, eleven, or one-half of the whole number, died of cholera, (p. 60.) In Manchester, a sudden and violent outburst of cholera supervened in Hope street. The people used water from a pump-well near which a sewer passed within nine inches. The sewer became choked and leaked into the well, and in thirty houses there were nineteen attacks of diarrhœa and twenty-six cases of cholera, with twenty-five deaths. The inhabitants of sixty houses in the immediate neighborhood, who used other water, had eleven cases of diarrhœa, but no cholera, and no death, (p. 62.) Thus is explained, perhaps, the apparently marvelous class of cases in which certain rows of houses or parts of streets are affected and others are not.

A cargo of plums from Hamburg was declared to have spread the disease in Hull. The fruit had not only been exposed to the epidemic influence, but was probably handled by persons sick with choleraic diarrhœa; or it had been stored in foul places. It now began to be suspected that dried fish, pork, bacon, vegetables, and fruits handled by dirty, contaminated people, were more active in causing cholera than fresh, ripe, clean fruits and vegetables, or nicely-kept salted or smoked meats.

any deaths occurred in England in 1848 among nurses, medical men, clergymen, zealously devoted to their arduous duties, and who lost r lives from continuing their labors too unremittingly, (p. 66.) But as fatigue, not the infection of cholera, which was said to have troyed them.

the Metropolitan buildings, with five hundred inmates, well drained, n, with an abundant and constant supply of pure water, with water-ets, and a dust-shaft for the immediate removal of refuse, no case holera occurred. In a row of houses a few yards off, without these antages, the disease was very prevalent and mortal; diarrhœa was severe and common, and twenty fatal cases of cholera showed them-es in a space 200 feet in length, (p. 70.)

n board the ship American Eagle, from Liverpool, with two hundred fifty steerage-passengers, a large proportion were attacked with rrhœa, and twenty-one with developed cholera, causing thirteen ths. In the large, commodious, clean, and well-ventilated cabins re was not even a case of diarrhœa, (p. 70.)

aint Bartholomew's Hospital expended $10,000 in improving its inage and water-supply. It admitted four hundred and ninety-eight es of cholera in detached wards. The average number of other ients was five hundred, with one hundred nurses. In this multitude a single case of cholera occurred, (p. 73.)

The premonitory diarrhœa received great attention. Over the whole Europe, and in every town and village in England, wherever cholera ke out, it was often accompanied by an enormous amount of diarrhœa. Sutherland says: "Diarrhœa often suddenly swept over the entire a of a city or district. At times in the depth of winter, when diarrhœa usually extremely rare, it was preceded and accompanied by fatal l violent outbursts of cholera;" and asks, "If the diarrhœa be not a t of the epidemic, what is it?" (P. 91.) Yet in counting up the fatal es, because each could not be directly connected with another calam-us death, but only with cases of cholerine or diarrhœa, the whole dis-e was often pronounced not infectious or communicable, nor even table and reproductive. The complaint always commenced with ious or feculent diarrhœa, and the rice-water discharges followed in ew days or hours. In forty-nine cases of bilious purging, without niting or cramps, there were no deaths. In forty-three cases of bil-s vomiting and purging, with cramps, there were three deaths. In o hundred and eighty cases with watery stools, without vomiting or mps, there were twelve deaths. In one hundred and eight cases th rice-water stools, and vomiting, there were forty-two deaths. In o hundred and eighty-one cases with rice-water discharges and cramps, ere were one hundred and forty-nine deaths. Thus the unity of the ease and its progressive danger was considered proven. If we admit ie, then, in the above seven hundred and sixty-one cases, there were ly two hundred and six deaths. Yet Dr. Sutherland denied the in-tiousness of the disease, because many fatal cases could not be traced rectly to another death from the same cause. The lethal attacks were nerally linked together by three or four non-fatal cases.

House-to-house visitation by medical officers was established through-t England, in order to discover and check incipient cases. The neral and uniform results of this investigation were:

I. The discovery of a number of bodies of persons dead of cholera thout having received any medical assistance whatever.

II. The finding of many cases of cholera, in various stages of de-lopment, proceeding with different degrees of rapidity to a fatal ter-

mination, not only without having been reported, as by law direc[illegible]. and lacking medical assistance, but also without the slightest appreh[illegible]sion of any danger on the part either of the sufferers or their friend[illegible]

III. The detection of a large number of cases of premonitory di[illegible]rhœa, some of them exhibiting the first stage of cholera; others alre[illegible] with rice-water purging; some advanced to the further stage of ser[illegible]. discharges, without any care on the part of the patients, or alterat[illegible]: in diet, or thought of sickness, much less any apprehension of the [illegible]. tual commencement of a mortal ailment; all without any medicine h[illegible]ing been taken or any physician consulted, (p. 102.)

It began to be suspected that the earliest diarrhœal stage, when [illegible]curring in those with foul breaths, and an offensive condition of the [illegible] digestive organs, either from bad food or drink, was more infectiv[illegible] than the clear rice-water and serous discharges; as were also the co[illegible] and offensive evacuations in the later typhoid stage.

The epidemic was thought to have been stamped out in Dumfrie[illegible] nine days by house-to-house visitation, the early detection and tre[illegible]ment of every diarrhœal case, and by thorough cleansing and disi[illegible]tion. In Paisley twenty-three deaths were occurring daily, but in [illegible]: days after this system was put in operation the deaths fell to three [illegible] day, and in a short time the pestilence ceased.

In Glasgow, thirteen thousand cases of so-called premonitory diarr[illegible] were brought under observation, of which nearly one thousand [illegible]: advanced to the rice-water stage; yet the disorder was stamped [illegible] a few days.

In Dundee, ten thousand seven hundred and ninety-two hypothe[illegible] premonitory cases were detected, of which seven hundred and five [illegible] thought to be on the verge of cholera.

In Manchester, three thousand eight hundred foreshadowing ca[illegible] were brought to light by the visitors, of which two hundred and [illegible] one were nearly developed cholera.

Hull had been lulled into a false security, and as its emigrant [illegible] was large, the deplorable consequences of the neglect of the auth[illegible]ties in delaying the adoption of preventive measures soon became pa[illegible]fully evident. At first there was an enormous preponderance of assu[illegible] premonitory over the developed cases; when the regulations came [illegible] operation, the melancholy spectacle was seen of the better classes [illegible] industrious artisans who were in the receipt of good wages, perish[illegible] in large numbers, while the very poorest people, to whom only the [illegible]ors went, were placed by preventive measures in comparative secu[illegible]

In London, in August, 1849, eleven months after the appearance [illegible] cholera, when one thousand two hundred deaths were occurring week[illegible] house-to-house visitation was finally adopted. Forty-three thousa[illegible] cases of simple and possibly premonitory diarrhœa were detected, [illegible] seven hundred and eighty cases of developed cholera, and nine hundr[illegible] and seventy-eight verging toward it; none of which had yet been [illegible]ported.

The cases of premonitory diarrhœa were estimated to be to those [illegible] developed cholera nearly as sixty to one. Twenty-seven cholera-corp[illegible] were discovered on the first visitation, in which death had taken pla[illegible] without any medical attendance whatever; and fifty-two cases, [illegible] quickly passed into cholera.

In fifteen towns, one hundred and thirty thousand non-positive [illegible] monitory cases were discovered, of which six thousand were pass[illegible] into developed cholera, (p. 118.)

In twelve places in England the cholera widows and orphans [illegible]

ılated to have added £121,576 to the poor-rates, most of which ıt have been saved by house-to-house visitation, at an expense of a few thousand dollars.

ıis epidemic was destined to throw a flood of light, also of con- ɒn, upon the conveyance of cholera. In the words of Professor ızo Clark, "England is separated from the continent by waters too d to permit the winds to carry the poisonous principle from shore ıore. As a matter of fact, (it had passed by Denmark, which was ected by a most careful quarantine,) and was brought by trading- els from Riga and Hamburg to Sunderland, Hull, and Edinburgh, re the North Sea is of the greatest width." The points where it had et made its attack in every epidemic in England had been on the ern coast, and in each instance the first cases occurred after the al of infected vessels. The same is true of its appearance in Bel- and Dublin, in Ireland. The ship Swanton left Havre on October 848, for New Orleans, with German emigrants. Havre was declared ıat time free from cholera, and the Swanton sailed with a clean bill ealth; but a portion of her passengers had left infected places in many, some of them from as far off as Pesth, in Hungary. The nton had been at sea twenty-seven days, when the first case occurred he 26th of November. Previous to the outbreak, it was visited by a hot southeast wind, such as the captain had rarely felt before, and passengers overhauled their baggage for suitable clothing. "It would waste of breath to express the idea that any animal poison can erse the ocean for more than a thousand miles upon the wind." It ned to Dr. Clark far more probable that the poison was lurking he baggage of these passengers, and that the emergency which re- ed the opening of unventilated trunks and packages let loose the ıs brought from the infected regions of Germany. In this way portability and communicability, the rapid regeneration, and im- ıse multiplication of the disorder was easily and correctly explained. assumption that some of the epidemic air of Prague was shut up hese trunks and infolded in the clothing, as believed in by Dr. Nott others, is not as satisfactory as the more natural and plausible opin- that some of the clothing was absolutely soiled by cholera-dis- rges, especially as the latter is a fact supported by many other well- henticated instances.

ıfter the cholera-visitations of 1832, 1833, 1834, and 1835, America ɔyed a cholera immunity of nearly thirteen years, during which the ious portions of the continent were subjected to the same malarial uences that it had been during all preceding years. Cholera did not ear in America, from the simple reasons that those nations with ɒn the inhabitants of North America had commercial intercourse had cholera to transmit. These years of exemption from cholera are, vever, not without their lesson to the nation. During the epidemic 1832, 1833, and 1834, the advocates of the malarial origin of the ease widely disseminated their doctrines. The medical journals m with cholera-literature of the period, but the vast majority are labored attempts to prove that malaria, improper food, excessive ercrowding in badly-ventilated apartments during warm weather, ı and do produce the disease known as Asiatic cholera.

During these years of cholera-peace, war was declared between the ıited States and Mexico. Large bodies of unacclimated troops were ıidly hurried into the malarial regions of Louisiana, Texas, and Mexico. ese troops advanced upon the city of Mexico, over the lines that in 32 and 1833 had been traversed by cholera. The city of Mexico

was captured, and undoubtedly instances of the grossest individual imprudence were committed, but yet no cases of epidemic cholera occurred. The troops returning from Mexico were attacked with yellow fever but not with cholera, for the simple reason that to propagate cholera you must have cholera. Malaria and any attending circumstances will not suffice alone; but bring the specific poison of cholera into such a region, then disease and death run riot. How different was the case of the armies in the Crimea Dr. Peters has shown.

In 1848, however, cholera had advanced to the western shores of Europe, and on the 2d day of December of that year the disease arrived at the port of New York.

The history of this importation, by Professor Alonzo Clark, in his exhaustive series of lectures delivered in 1866, could not be improved. "Two ships left Havre, one on the 31st of October, the other on the 9th of November, 1848. The latter ship, the New York, was bound for the city of New York. The former, the Swanton, was bound for New Orleans. The passengers of these two ships were of the same character, mostly German emigrants; they had been taken up in both instances at Havre, which port was at that time said to be free from cholera. They had come to Havre for the purpose of finding a ship for this country. One report states that a portion of them had left infected places in Germany. The ships came out with a clean bill of health. The New York had been at sea sixteen days when cholera appeared, that is on the 25th of November. The Swanton had been at sea twenty-seven days when the first case occurred, it being on the 26th of November. They were one thousand miles apart. They were both off the coast of the United States, one in latitude 25° 47′, and the other in the parallel of 42°.

"The outbreak on the New York is by the captain of the vessel ascribed to the following fact: A very cold, chilly wind came up on the 24th, and the passengers found themselves in want of warm garments; in his own phrase, 'there was a general overhauling of baggage for warm clothing.' Then the next day became exceedingly hot, and on that day the first case of cholera occurred. It has been found, that on board the ship New York there was an emigrant who had clothing that had belonged to an individual who had died in Germany of cholera. During the day of intense cold, some articles of this clothing were taken from the chest and were worn by several of the passengers, and these passengers were the first taken on the ship. On board the Swanton this cold day was not experienced; but, says the captain, "previous to the sickness, for twenty-four hours, we were visited by a very hot southeast wind; such a one as I had never felt before; indeed, it was more like artificially heated air than anything else." Now, the question comes, where was the poison that produced this disease? Was there a layer of cholera air stretching up and down the ocean, into which the vessels sailed at the same time? Such a supposition is unsupported by any other fact in the history of cholera, and is therefore in the highest degree impossible. The wind could have no agency in the transporting of poison, for during the interval of twenty-four hours which elapsed between the occurrence of the first case on board the New York and the commencement of the sickness on board the Swanton, the wind was blowing from the southeast, or nearly in an opposite direction. Then it would be a waste of breath to express the idea that any animal poison could traverse a thousand miles upon wind.

"It seems to me far more probable that the poison was lurking in the baggage of these passengers, and that the emergencies which required

pening of unventilated trunks and packages let loose in each of ships that poison brought from the infected regions of Germany. s, however, another explanation which is urged by those who paid much attention to the researches of Pettenkofer and the Bava- ommission. It is found in the period of incubation. This period, sserted, is long enough to admit the supposition that a person t receive the infection in Germany, then travel to Havre, embark, e at sea sixteen days, and after that have disease declare itself in This would imply an incubation of above eighteen days, and it is ed that it may be twenty-one or twenty-five. But even this max- requires a little extension to meet the Swanton. Twenty-seven at sea and two from Germany would make an incubation of twenty- days, a period longer than has yet been claimed.

The two ships go on their voyage. One arrives in the harbor of New in the 1st of December, six days after the outbreak, having lost of her passengers. The other goes into the Mississippi River and New Orleans, having lost several of her passengers, reaching the December 11."

om this point the history of the two vessels should be separated. e New York upon her arrival at quarantine sent eleven cholera nts to the quarantine hospital. The next day the number was in- ed to twenty, with eight deaths, and a local epidemic was insti- l. Dr. Clark states that the first person not attached to the ship was attacked was a man who went on board the New York, and in twenty-four hours was seized with cholera and died the next

e passengers from the New York were brought to the public dock houses, and when it was found that the disease was spreading, all alescents at the quarantine hospital were discharged. One of the r was taken with cholera at his lodgings on Wellington street in the This man, it is stated, was sent back to quarantine. His room-mate also attacked with the same disease, and both died. How long the engers of the New York were detained at quarantine is not stated. New York carried a large number of these emigrants; the exact ber is not recorded. These emigrants were scattered over the city ew York and over the United States, carrying with them in all ctions the infection of cholera.

p to the 28th of December, about one hundred cases had occurred he quarantine, fifty of which were fatal. Other than the two cases d, the disease did not spread in the city. Dr. Clark states that disease seemed to have been checked by the severe cold on the 1st anuary, when it ceased.

The Swanton reached the city of New Orleans on the 11th day of ember, having lost, according to Dr. Marsden, thirteen passengers n cholera. She had been detained by no quarantine, but went at e to her wharf and proceeded to discharge her passengers and cargo. the day of her arrival, one cholera case was sent to the charity pital. The other passengers, of whom there was a large number, re lodged in the city. Two days after the arrival of the Swanton, first case in the city was announced; this was also an emigrant from Swanton, and the next day eight cases of the disease were admitted the hospital from houses on the levee. During the month of Decem- , four hundred cholera deaths were reported at New Orleans; in nuary, six hundred were reported, and the number increased each nth until June, when the epidemic culminated in two thousand five ndred and odd deaths.

This is the generally-received report of the introduction of the cholera into the United States in 1848; but a doubt has always been thrown upon the origin of the disease by the opponents of its infectiousness or portability, in the statement of Dr. Fenner, that he had met with cases of the disease several days before the Swanton reached New Orleans.

Dr. Fenner, however, states the following facts in the Southern Medical Reports, volume 1:

I. That on December 6 the ship Gutenberg, from Hamburg, with one hundred and fifty emigrants, arrived, after a passage of fifty-five days, upon which six or seven cholera deaths had occurred. One of the earliest cases at New Orleans was a man from this vessel.

II. That on December 8 the bark Callao, from Bremen, with one hundred and fifty-two German emigrants arrived, after a passage of forty-eight days, during which she lost eighteen emigrants from cholera. The Callao was kept at Slaughter-house Point, opposite to New Orleans until January 4, when she was brought over to the city and unloaded.

It will thus be seen that prior to the arrival of the Swanton two vessels, the Gutenberg, from Hamburg, and the Callao, from Bremen, had arrived at New Orleans with an aggregate of four hundred and two emigrants, who had lost twenty-five of their comrades on the voyage.

Prior to the departure of these vessels Hamburg and Bremen were infected with cholera, and the majority of the emigrants came from localities previously involved in the epidemic, and yet almost universally the outbreak at New Orleans in December, 1848, has been ascribed to the arrival of the Swanton, and it has been denied that importation had anything to do with the outbreak, from the fact that the first case in the city occurred the first or second day after her arrival.

December 20, the steamboat Convoy, from New Orleans, arrived at Memphis, Tenn., after a trip of four days, with two or three cases of cholera among the deck-passengers and crew. For several days previous boats going up the river had reported deaths from cholera before they reached Memphis, but none had landed at the city.

Previous to December 22, Dr. Shanks states that there had been a *tendency to bowel affections;* but on that day a boy who frequented the wharf where boats landed took the disease and died. No other cases occurred until the 26th, when a man and his wife living on a flat-boat took the disease. Both died.

For the first twenty days the disease was confined to the landing and to persons communicating with infected vessels; after that it began to spread to other portions of the city.

On the 27th of December, the steamer Caroline Watkins, from New Orleans, arrived at Nashville, Tenn., with one dead body from cholera on board. During the voyage, which occupied a period of about seven days, she had lost eight others from the same disease. Dr. A. Hamilton Buchanan reports "that these deaths occurred among deck-passengers and firemen, most of whom were foreigners, and, as represented, very imprudent under treatment. One or two of the deaths were among cabin persons."

No cases of the disease, however, occurred at Nashville until the 4th of January, twenty-five days after the arrival of the Watkins, and several days after the arrival of other boats, on board of which there was cholera, the first case occurred. The next day, a second case occurred in the same house; the third case occurred in the same house; all three cases died. The house at which these cases occurred was in a

rable condition, and was nearly surrounded with water. From these s the epidemic originated.
ecember 22, the steamboat Peytona arrived at Louisville, Ky., from Orleans, with a list of four hundred passengers, having had upon voyage fifty deaths on board from cholera. A number of these engers died subsequently of cholera at the marine hospital.
ecember 24, the steamboat Savannah arrived at Louisville, Ky., from Orleans, with three cases of cholera on board, having lost four of passengers from the same disease upon the trip. From these arri- a mild epidemic affected the city.
n the 25th of December, a case of cholera was admitted to the Cin- ati hospital from a steamboat just arrived from New Orleans. His was soon followed by others from the same source, and in a few s cases occurred among the other inmates of the hospital. Within ort time cases of the disease occurred in the city among persons ing connection with the shipping.
n the 18th of May a man from Cincinnati, Ohio, put up at the mers and Mechanics' Hotel at Dayton, Ohio. That night he died of lera, and the disease spread in the hotel. A gentleman from an ad- ing town, while the body of the first case was in the house, ate his ner at the hotel; he died at his home from cholera within twenty-four rs, and from his case the disease spread.
y steamboats the disease was carried to Wheeling, W. Va., and sburgh, Pa., and it is recorded that deaths occurred among emigrants eling on foot upon the national road beyond Wheeling.
ecember 27, boats arrived at Saint Louis with cholera on board. On 28th the Amaranth, with thirty cases on board. The editor of the st Louis Medical Journal states: "Of the cases that occurred at st Louis, at least one-half were persons who contracted the disease in v Orleans, or on their way from that city, *and were landed here in an ost dying condition*. In one of the earliest instances, five deaths oc- red in one family."
n face of such facts, the late Dr. Condie, in his report to the Ameri- Medical Association, after admitting the introduction of the dis- e to various cities by infected steamboats, with a strange inconsist- y notes of Saint Louis, "The disease is said to have been of local gin."
he cholera at the quarantine of New York Harbor, which had abated the 1st of January, 1849, did not re-appear until in the first week of ril.
rior to its re-appearance, several ships having cholera on board had e into the harbor, and their sick had been transferred to the hos- al.
On the 11th of May, the first case of the season occurred in New York y at a lodging-house on Orange street. Six other cases occurred in same house, and the disease spread rapidly, and continued until the t of September, with a total of five thousand and seventeen deaths. According to Dr. Sayre, the first cases were emigrants who had escaped m quarantine.
Dr. Vaché remarks: "The nearest vicinity of the pestilence was the arantine, between which and the city there was constant intercourse the residents of each place; and, in most instances, the passengers m sickly vessels were permitted to disembark at the wharves with ir unventilated baggage. If the infection was not ascribable to se causes, it could not be traced to any other."

At Brooklyn, the disease occurred May 26, and at Williamsburg the 29th, at Jamaica June 4, and about the same date at Newark, N.

Dr. Auerbach states: "The first cholera case at Rockaway, L. I., occurred August 30, in the person of the captain of a small vessel that plied between that town and New York City. He brought to Rockaway household-furniture belonging to a man *whose wife had died* shortly before in New York, and the body was brought to the same place for interment. Other cases then followed.

May 22, eight cases occurred at Philadelphia. Three of these persons were upon a very dirty canal-boat just arrived. Another case was in the person of an Irish emigrant who had been in the city but a few days. The same day, May 22, three cases of cholera occurred at Baltimore.

It is shown in the report of Dr. James Wynne of the cholera outbreak at the Baltimore almshouse in 1849, of which so much has been made by those favoring the malaria theory of the origin of cholera, that the first death at that institution was a man who took the disease in the city; the second case was a man who slept in the attic, but who had been exposed to *malaria, i. e., a foul overflowed privy and drainage from wash-house and dead-house.*

Professor N. R. Smith stated that a poor English traveler, Alexander West, called at his office for medical aid. He seemed extremely ill, threw himself or fell upon a lounge in the office and vomited rice-water like stuff. Dr. Smith believed he was in the collapse of cholera, and had him removed to the almshouse, where he died two days afterward, on July 7. The whole house and grounds, with nearly seven hundred inmates, seemed in splendid condition. On July 7 an old man was attacked by cholera and died. On the 11th a woman on the female side of the house followed. On the 17th there was one case on the male and another on the female side, which were separated by a central building 200 feet long. On the 13th another man was attacked and died. On the 14th the outbreak commenced with ten cases in the men's ward and three in the women's. After July 18 the cholera-patients were assigned to the upper story of the black people's hospital. On the 19th Dr. Buckler, finding no local cause within the walls of the inclosure, for the first time surveyed the premises outside the *north* wall. The main building was 800 feet long, and looked to the south. The east wing was occupied by male paupers and the west by the female, while the central building on the middle was the dwelling of the officers and attendants. An inclosure of four and a half acres, surrounded by a wall, adjoined the building on its north side. Within this inclosure, on the female side, there was a building running north and south for 70 feet, and three stories high. The basement and second story were occupied by lunatics, the third story by foundlings and nurses, and the fourth by aged females. Each of these stories had windows looking out to the east and west. In the lower story a door opened to the north, but all the upper stories had neither door nor window to the north. In close proximity to this north door was the cess-pool for this building. Along the north wall, starting from this point, was the wash-house, where a large amount of dirty linen was washed; next, the dead-house and the men's privy. All this is called pure and simple malaria by Drs. Wynne, Buckler, and Bell. Also, a large pig-pen and a cess-pool adjoining the east wall, in the rear of the men's wing, where the black people's hospital was placed; also a ravine in the rear of the north wall, which was the outlet for the waste water and filth of the whole establishment. Dr. Buckler discovered the source of the pure and simple malaria, which caused the cholera, in the cess-pool connected with the black people's hospital, etc.

lowed and was in a very filthy condition. Near it the drainage the extensive pig-sty also covered a large surface of rank grass rotten weeds, and then found its way to a filthy pool, the con- of which seemed to be in a state of actual fermentation. Yet all regarded as pure and simple malaria. The next object which met Buckler's attention was a large surface covered with the overflowing nts of the men's privy, and a short distance from this a similar one eater depth, containing the washings of the dead-house, and still er on, a much larger place, 30 feet wide and 3 feet deep, leading the wash-house, and communicating with a similar one charged the contents of the cess-pool attached to the ward for insane fe- s. In short, the whole space included between the ravine and the upon its north side, was one putrid and pestilential mass, capable nerating, under the ardent rays of a midsummer sun, the most poi- us and deadly exhalations. It doubtless had caused many an ob- e case of typhoid fever, which was mistaken for malarious bilious ttent, and many cases of diarrhœa and dysentery; but it had never ed cholera until a case or cases were introduced into the almshouse ne or July, 1849. Then, of 632 inmates, 53 were discharged; 62 d; 99 died of cholera; 13 died of other diseases, and 405 were left. e weather was remarkably fine and seasonable, but a gentle breeze the north swept over the whole mass of filth, which was now also ed with cholera-discharges, and carrying the poisonous, so-called rious exhalations up the drains, and through the doors and win- s over the house. In the lower story, in which a door opened upon ilth, there were seventeen lunatics, exposed to the exhalations every this door was opened, and all were attacked and all died of cholera. he three upper stories there was neither door nor window looking to north, and all the inmates escaped. The female wing was protected the north by three rows of trees, and, although the women out- bered the men, the number of attacks was considerably less, which also supposed to prove the pure vegeto-malarial, not the animal or ic malarial origin of the most of the cases.

he first case of cholera was that of an old man, who slept in the , but spent most of his day in the yard; the manager, who slept in third story, looking to the north, suffered; but his family, whose ms were not thus exposed, escaped. Of eight medical students g in the second story of the main building, four living in the north ns were attacked, and the rest, sleeping in south rooms, escaped. se paupers who slept in places exposed then to the north wind were erally seized. After the removal of the cholera-patients to the ward the black hospital, where the influence of exhalations from pig- s and privies, which is termed simple miasm, was entirely unob- cted, the severity of the attacks increased, and the chances of cure inished.

n July 23 the foul pools were drained into the ravine, into which a stream was turned; then the bottoms were covered with lime, and r that a deep layer of clean earth was placed. The men who drained pools were attacked with choleraic diarrhœa, but recovered, and did spread the disease in the town, proving, doubtless, that the disease caused by the patients in the building in some way, and that the outdoor exhalations only intensified real attacks and caused Theal attacks only.

is claimed that those who fled, or were removed from the alms- se, did not carry the disease to others, although attacked them-

selves. But as none of them died outside of the almshouse, perh... they only had septic or fœcal diarrhœa, not real cholera.

As the foulness outside of the house was regarded as sufficie... account for all the disease inside of it, no inquiry was made as t... the disease was handed from one case to another, and persons wh... mistake the exhalations from privies, dead and wash houses for ... vegetable malaria might not carry on a very rigid investigation.

May 30 the disease was reported at Norfolk, Va., and the same da... Richmond, Va.

June 4 three cases are reported at Boston, two of them on the ... Argyle, just arrived from Scotland, and the disease spread to other N... England towns and villages. Providence, Woonsocket, Pawtucket ... other towns of Rhode Island suffered from cholera.

From New York City the disease was carried to the towns of the N... River and to Albany and Troy, and along the line of the Erie Ca...

At Albany the first case occurred in the person of a stranger ... Northern Hotel, but its subject was the second death, the first bei... a man who lived within thirty feet of the person first sick with ch... symptoms.

Buffalo, N. Y., was, however, infected from another direction. ... first case of cholera occurred May 30 in the person of a traveler on ... boat from Chicago. This case was taken to a hotel in the city.

June 1 the second case occurred, in a man from Cincinnati who ... by steamboat from Sandusky.

June 4 the third case occurred, in a female, having no connection ... either of the preceding cases. The same day another steamboat br... an infected female from Chicago. Eight hundred and fifty-eight c... occurred from May 30 to September 7.

The first case of the disease occurred in Canada this year at Kin... in the person of an individual from New York City, who arrived ... 28 or 29 via the New York Central Railroad.

The disease, however, did not reach Montreal until the 15th of ... Quebec until the 4th of July; Hamilton until the 18th of July; ... Lachine on the 28th of the same month.

Dr. Marsden states that the first case at Quebec occurred in the p... of a man named McGill, "whose business was chiefly among stra... lumbermen, and travelers. He died after a few hours' illness, ... which he was visited by one of the water-police, a friend of his ... went home, took the disease, and died the next day."

To Dr. Marsden we are further indebted for an account of the c... occurrences at Quebec in 1849. July 6, a vocalist of some celeb... rived at Quebec from New York City. At the time of his arrival h... suffering from a diarrhœa, which, however, did not prevent his j... fishing-excursion on the 8th, from which, however, he was obliged ... turn, and at 1 o'clock a. m. of the 9th he was dead from cholera.

"The proprietor of the hotel at which this gentleman died was a... to destroy all the clothing both of the patient and of the bed upon ... he had died. The clothing was given to a hotel-waiter named Ro... destroy, but he, from motives of cupidity, carried them to the jail, ... his son was a turnkey, and hung them up to dry in a large room, ... was in the use of the officers of the jail and their families. The ... day Roberts had a diarrhœa, but thinking nothing of it, he vis... friend; on his return to the jail he was taken with cholera, and d... night. His death was followed by the death of the man whom h... visited, the wife of the man, and many cases at the jail. The mattress ... which the first death had occurred was not destroyed, but was ...

ly given to a man to clean, but who died of cholera in the attempt
ng the same epidemic a man was employed by the board of health
uebec to destroy some cholera-infected clothing. Among the articles
und a coat too good to destroy; he put it on, went home in it, and
soon after of cholera.
A lady died during this epidemic at Quebec from cholera; the bed
which she died, with its clothing, and the clothing that had been
her person, were thrown into an unoccupied lot, and a number of
ren belonging to poor persons were seen playing upon and with the
les, when they were driven away; within thirty hours four of these
lren were dead of cholera."
s if to make the warning more impressive, these were not solitary
nces, but during the same epidemic each of those which have been
ated were duplicated.
e return to the epidemic in the South and West. It has been shown
cholera was epidemic in New Orleans in December, 1848, and in
uary, February, and the succeeding months of 1849.
rly in the epidemic the disease spread to the plantations of Louis-
, in the majority of which the conveyance of the infection could be
ctly traced. A plantation in the Bayou Tèche became infected in
uary, and the disease spread to the adjoining localities. Saint Mary's
La Fourche suffered severely.
January, 1849, the disease was carried to Mobile, and until June
sted with but one hundred and twenty-nine deaths. Mobile un-
btedly enjoys her immunity from cholera from the pure drinking-water
which the city is supplied.
n the 1st o December, the Eighth United States Infantry arrived
New Orleans, on its way to Texas. The regiment was placed in the
racks, four miles below the city, and there remained until the 12th,
n they embarked upon the steamers Telegraph and New Orleans.
the 18th they reached Port Lavacca, but the men were not landed
il the 20th. On the night of the 21st a case of cholera occurred in
p, when one battalion, under Major Gates, marched twelve miles into
country. The other battalion, under Major Morrison, remained in
aca; during the night a cold storm came on, and by daylight there
e four deaths from cholera among the troops in town, and many new
es. The same night the disease broke out in Major Gates's camp, and
ing the epidemic one hundred and twenty-eight men of the regiment
d of the disease. Many women and children belonging to the regi-
nt died of the disease.
These were not unacclimated troops. The regiment had served during
Mexican war; had reached Saint Louis on its way to New Mexico,
en, from unexpected orders, its route was changed, and it again de-
nded the Mississippi. For these facts we are indebted to General T.
Pitcher, United States Army, then the regimental adjutant.
The above is the only recorded account of the importation of the dis-
e into the State of Texas. Dr. Fenner states that the epidemic pre-
led to a considerable extent at Houston, while Galveston escaped.
e Eighth Infantry undoubtedly were efficient agents in the introduc
n of the disease into the State.
In a report of Surgeon J. J. B. Wright, United States Army, in Fen-
's, Medical Reports, it is stated that "The disease made its entry
San Antonio about the middle of April, approaching from an east-
y direction, by the Lavacca road. Its advent was heralded by its
tims among the California emigrants on their way to join the Govern-
nt train, which was expected to leave for El Paso del Norte." Dr.

Wright's report is one of the most valuable accounts of the epidemic that has been published.

We append a letter from this gentleman, now the senior surgeon of the Army.

"SAN ANTONIO, *May* 7, 1849.

"DOCTOR: I have to announce what will be most painful intelligence to you, the death of General Worth. He died to-day of spasmodic cholera.

"The general's health has been deranged for several weeks, though not to an extent which precluded attention to his official duties. He arrived last Tuesday from New Orleans, whither he had gone to meet his family. The disease of which he died developed itself about two o'clock yesterday evening, and hastened to a fatal termination, unaided *by medication.*

"I have had a very considerable experience in the treatment of this epidemic, and feel deep humiliation in saying that no plan of treatment, much less any individual article of medicine, has commended itself to my confidence, or even to my preference. When fully formed, sometimes even in its initiative stage, it bids defiance to the *armamentarium* of physic.

"This town suffered in an extraordinary degree from the cholera which prevailed in 1833. Its ravages are fresh in the recollection of the Mexican portion of the population, a great majority of whom fled from the place at its approach. A large proportion of those whose courage permitted them to remain, or whose inability prevented their leaving, soon become victims of the epidemic.

"The disease has been prevailing in this place and vicinity since the middle of April, but no case had occurred in the military encampments in the neighborhood of San Antonio until the 4th instant, when it made its appearance in Camp Salado, the station of the Third Infantry. Some fifteen cases have occurred, of which six have been fatal; the remainder are pending.

"I am, sir, very respectfully, your obedient servant,

"J. J. B. WRIGHT.
"*Surgeon United States Army.*

"TH. LAWSON, M. D.,
"*Bvt. Brigadier-General and Surgeon-General of the Army.*

"P. S. *May* 11, *evening.*—The express left me unexpectedly on the afternoon of the 7th, and I failed to procure admission for this letter. The disease continues to prevail, and many of the cases are more rapidly fatal than those preceding them. The Third Infantry has lost twenty men, while the epidemic is still progressive in the camp. The Eighth Infantry and the squadron of dragoons, three miles from town, remain in excellent health up to this date."

A report of the late Surgeon N. S. Jarvis, United States Army, published also in Fenner's Medical Reports for 1849, demonstrates that cholera was diffused through Texas by the movements of troops and emigrants, and into Mexico by the arrival of refugees from Texas.

From New Orleans the cholera was carried by emigrants to California and to Panama, and the steam-transportation on the Pacific thus became infected.

As the epidemic became pronounced in New Orleans, the steamboats leaving that city were crowded with emigrants and passengers of all classes, flying from the disease. Every steamboat upon the river became a moving pest-house, and during the early months of 1849 the disease had been universally diffused over the valley of the Mississippi.

ugh the city of Saint Louis was considered free from cholera during
ruary, 1849, still, as the spring advanced, constant arrivals took
e. As an instance of the mortality upon the river steamboats, it is
orded that before reaching Cairo, on March 22, seven cholera-deaths
urred upon the *Bride* and three on the *Uncle Sam*. On the 23d,
t cases had occurred on the *Belle Key;* the *General Washington*,
death and several cases; the *Seraph*, eight cases and two deaths;
Gladiator, eight cases and three deaths. On the 24th, the *Tennes-*
three cases; and on the *Yorktown*, ten deaths.

t Saint Louis, early in April, the disease was again epidemic, and
ing May and June the mortality was excessive. Seventeen physi-
ns died.

n the 21st of April, the steamer Sacramento arrived at St. Joseph,
souri, with a large number of California emigrants, who were then
dezvousing at that city preparatory to the march across the plains.
the Sacramento, before her arrival, one cholera-death had occurred.
er infected steamboats followed; on one of which, the Mary, over
deaths had occurred. By these emigrants cholera was carried
tward over the Platte route, and being taken up by succeeding
igrants, the disease reached Sacramento in October, 1850, at almost
same time that it was brought into San Francisco by the steamer
olina from Panama.

n the 7th of September it was reported at Saint Louis; but cholera
s raging among the northwestern Indians to an alarming extent. It
l disappeared from among the southern tribes and those on the South
kansas River. The Indians along the Missouri River continued
atly incensed against the whites for introducing the epidemic among
m, and committed daily murders upon the unoffending inhabitants out
revenge.

From Saint Louis this disease was carried to the headwaters of the
ssissippi and Missouri Rivers. At Galena, the first cases occurred
out the middle of April, in a family from Saint Louis, and four cases
re fatal.

On the 20th of April the Illinois and Michigan Canal was opened, so
t boats could pass through, and the line of water-communication was
nplete between Saint Louis and Chicago. On the 29th of April, the
igrant canal-boat John Drew arrived at Chicago from Saint Louis
th a number of passengers, who were emigrants, and direct from
w Orleans. A few hours after her arrival her captain died of cholera,
d soon after some of the passengers. The epidemic prevailed until
gust 28, with three hundred and fourteen deaths.

About the 5th of July, thirteen emigrants from Sweden, direct from
w York, via Buffalo, arrived at Chicago, and went to the house of a
n named Arns. On their arrival they unpacked their chests of
thing. On the 7th one died of cholera, when the rest of the emi-
ants were turned out of the house. Four cases occurred in Arns's
nily, with two deaths; and from this house the disease spread.

Dr. Evans relates that at Summit, twelve miles southwest of Chi-
go, on the 17th of June, a man from Chicago arrived, to remain a few
ys upon business, but was taken with cholera at the house of a Mr.
eacock, and died the next day. The next day Mrs. Heacock, her son,
d a servant girl died. Two other members of this family had the
sease, but recovered. A Mr. Webster, who lived with a Mr. Brown,
sisted in nursing the Heacock family, and was taken with cholera on
e 20th, and died. The next day Mr. Brown took the disease, and died
the 28th. The next day Mrs. Brown, who had gone to Chicago, as

soon as her husband died, was taken at the house of her father, Mr. Guthrie, with cholera, and died. Mr. Guthrie and a friend took Mr. Brown's body back to Summit. On the road they were taken with cholera; one died, the other recovered. Four other deaths occurred among persons who had been in contact with this group.

At Aurora, forty miles west of Chicago, the first case occurred in the person of a peddler who was direct from Chicago. He stopped at the house of a Mr. Sanfords, about five miles from Aurora, and died of cholera. The next day Mr. S. took the disease, but recovered. July 2, a farmer, living three miles north of Aurora, returned home from Chicago, and died of cholera the same night. His wife died of the disease in eighteen hours. One other case occurred.

July 24, a Mr. Leech returned to his home, five miles from Aurora, after a visit to Chicago, and died the same day.

At Flagg's Creek, twenty miles from Chicago, a lady from Chicago died of cholera; five cases of the disease followed, with two recoveries.

At Doty's Tavern, Buck Horn, Naperville, Cazenovia, the Pre-emption House, and other localities, the disease occurred. At all, the infection was caused by the arrival of sick from Chicago.

On September 24, a fresh arrival of cholera-infected emigrants caused another epidemic, which continued until late into October, the total cholera deaths being six hundred and seventy-eight.

At Chicago, the steam-transporation upon the lakes became infected, and points as far east as Buffalo, N. Y., felt the effects of the epidemic.

By infected steamboats the disease was constantly carried up the waters of the Ohio. Louisville, Cincinnati, Wheeling, and all other towns upon the river became infected.

At Louisville, on the 2d of May, three deaths occurred from cholera on Fifth street, between Main and Water, and one in the alley in the vicinity. May 4, several new cases were reported in the same locality. From the 4th of May to the 7th, four deaths occurred, one a gentleman from St. Louis, who arrived with the premonitory symptoms of the disease. The explosion of the disease occurred in a dirty, overcrowded tenement-house, in a low, damp location on the Bear Grass Creek. The house was frequented by emigrants. The disease spread to other localities, but at no time did the city suffer as severely as other towns in the Ohio Valley. When the occupants were removed from this house in which the disease originally broke out, the epidemic at that point subsided. Dr. Bell states that the survivors were taken to a new house containing two rooms 12 by 14 feet in size. A woman died at this house of cholera the day of arrival, and the eight other members of the party slept in the room adjoining to that which contained the dead body. Seven of these people were dead of cholera by the second day; the survivor had the disease, but was removed to hospital, where he recovered.

On the 23d of July the disease broke out on Market street, between Tenth and Eleventh streets, in a row of tenement-houses in a miserable portion of the city, and fifty cases, with thirty deaths, occurred in a few hours. The survivors were removed, premises disinfected, and no more cases occurred. Many persons from this block died of cholera in different portions of the city.

From Louisville the disease was carried into the interior of the State. A man from that city died among the mountains of Rockcastle County of cholera, and nine deaths occurred among those who were with him during his last moments.

A man from Louisville died at a village hotel in Lincoln County

olera. The negroes who waited on him took the disease, and, transtting it to their wives, an epidemic ensued.

At the city of New Orleans the epidemic subsided during July, and August but four deaths were reported. September had but one case, t in October the epidemic was revived in the following manner:

October 15, the ship Cromwell arrived at New Orleans, having sailed m Havre on the 10th of September with two hundred and four steere passengers. Cholera was prevailing at Havre when she left, but the ssengers had been inspected by a physician before starting and prouunced healthy. The first day out a fatal case of cholera occurred. relve deaths took place from the disease during the voyage. The pasngers remained at New Orleans a few days, and *then went on up the er.*

The same day, October 15, the steamboat General Lane arrived from e Upper Mississippi and Ohio, having lost three or four passengers m cholera. One case occurred after the boat reached New Orleans. October 23 the ship Berlin, from Liverpool, arrived with two hundred d six emigrants, mostly English and Scotch. There was cholera reorted at Liverpool when she left. On the tenth day of the voyage olera broke out, and forty-one deaths occurred. *The vessel was ordered the other side of the river, where the emigrants remained on board a day two and then went up the river to the western country.*

During the month of November the epidemic prevailed to an alarmg extent. On the 26th the ship Gipsey, from Liverpool, arrived with ree hundred and nine emigrants, having lost nineteen from cholera. n the 27th the ship Fingal, from Liverpool, arrived with three hundred d twenty-two emigrants, having lost thirty-seven cases of cholera. hese six hundred and thirty-one emigrants went to swell the sum of olera-infected individuals. The disease remained in the city during e succeeding months.

During the months from January to July, 1850, cholera existed in ew Orleans, fed by constant arrivals, but in none of these months did assume the proportions of an epidemic. On the 24th of Septemer the steamship Falcon arrived from Chagres and Havana, having st twenty-five passengers from cholera, the disease being epidemic at oth ports touched by the steamer. During October the disease inreased in the city, one hundred and seven deaths occurring. During December the disease disappeared.

During 1850 cholera was confined to localities situated on or near the Mississippi and Ohio Rivers, the steamboats to and from New Orleans till being infected, and still being engaged in carrying the infection to and from that city. East of the Alleghany Mountains the disease did not extend.

At Saint Louis, according to Dr. W. M. McPheeters, prior to May, 850, the causes of cholera were not of local origin, but from May to August the disease settled in certain localities of that city. The total deaths were nine hundred and fifty-three.

At Cincinnati, the disease, according to Dr. George Mendenhall, was chiefly among the floating population and emigrants, the first cases again occurring in persons from New Orleans. One thousand four hundred cholera deaths occurred.

At Sandusky, the disease appeared July 8, in the persons of emigrants, and eighteen per cent. of the inhabitants died.

At Columbus, Ohio; Louisville, Ky.; Burlington and Keokuk, Iowa; Chicago, Ill.; Kalamazoo, Mich.; Buffalo, N. Y., the disease occurred during the year.

In 1849, by emigrant trains from both Texas and Missouri, cholera was carried out upon the plains, then known as the great American desert. So great was the mortality that whole parties were decimated. The property of the dead, infected by their discharges, was abandoned upon the roadside, to impart the infection to other travelers upon the highways.

From New Orleans the disease had been carried to Cuba, and to the isthmus of Panama. Chagres upon the east and Panama upon the west, as also Acapulco in Mexico, were infected by the disease. The steamships upon both the Atlantic and Pacific were overcrowded with passengers, and made stops at each of the points named; but it was not until the last of September, or about the first of October, that the disease arrived at San Francisco on board the steamer Carolina. Following the arrival of this vessel a few cases occurred in the city; but it was not until the first week in November that the explosion occurred, and this only after fresh arrivals from Panama. The epidemic lasted until about Christmas, when it disappeared. The total number of deaths was about two hundred and fifty.

In November cholera was carried from San Francisco to San Jose, fifty miles to the southeast, where its ravages were confined to the natives.

About the time that the Carolina arrived at San Francisco, reports reached that city that cholera had broken out at Carson Valley, some hundred miles distant in the interior, where it occurred in the persons of overland emigrants.

On the 18th of October the disease appeared at Sacramento, in the persons of overland emigrants, and rapidly spread. Consternation seized the inhabitants, and all who could do so fled from the city. Out of a population of eight thousand less than four thousand remained, and of these before December, when the disease subsided, over one thousand had died.

During 1850 no other portion of the country was infected.

In the conclusion of the most interesting report of James Wynne, M. D., on epidemic cholera, as it prevailed in the United States in 1849 and 1850, Appendix C to the Report of the General Board of Health on Epidemic Cholera of 1848 and 1849, London, 1852, it is stated: "It appears therefore, upon a careful and minute examination of all the circumstances connected with the spread of cholera from place to place, that in no single instance is there any evidence furnished by first cases, where the disease could be most easily traced, to show its introduction by direct contagion or personal communication; but, on the contrary, all these circumstances tend to establish the existence of some other and more potent morbific agency."

The report referred to has probably done more toward misleading and establishing erroneous theories upon this all-important subject than any other effort that has appeared in the English language; the reasons given are so conclusive, the facts advanced so seemingly uncontrovertible, that it served to clinch the malarial chain; but a careful reading of the report will convince even a prejudiced observer that the evidence upon which the assertion quoted is based, is deficient in two essential points.

I. No account is taken of the extensive scattering of emigrants from infected districts of Europe over the entire North American continent.

II. At each point of infection the history of the outbreak commences with the first fatal case, and no attempt was made to trace any cases that might have been instrumental in the introduction of the disease.

hough their cases may not have terminated until many days after the
st fatal case had occurred.
It is also a point of the utmost significance that at each of the malarial
alities that produced the disease in North America, according to Dr.
ynne, at none was this malarial influence exercised or apparent until
er the arrival of individuals from districts previously infected by
olera.

CHAPTER VI.

THE EPIDEMIC WHICH REACHED NORTH AMERICA IN 1854.

The origin of this epidemic had been very clear for years, wh... Tholozan nearly threw all its records into confusion in 1871, in a pa... let entitled "*Origine nouvelle du choléra asiatique, ou debut et dév... ment en Europe d'une grande épidémie cholérique.*" He assumes ... arose spontaneously in Poland in 1851, and spread from thence, ... ing to the usual way of cholera, in every direction, north, south ... and west, especially down through Russia, by way of the holy ... Kiev, to the Black Sea, and from there east to Persia, and b... Arabia and India. But, according to Drasche and all the other ... historians of cholera, the epidemic of 1830 lasted eight years in ... parts of Europe and America; that of 1847 for twelve years, ... fresh importations from India, Persia, and Arabia, and we may ad... the decreasing belief in its infectiousness and the resultant carele... about importation. From 1847 to 1859 it was always present in ... portions of Europe, both in winter and summer. The great do... of the portability and consequent communicability in some way, a... necessity for stamping out the pestilence in its incipiency by disinf... did not fully arise till 1854. The increased facilities of travel ser... spread it, and Denmark, Switzerland, and Greece, which had pre... protected themselves for over twenty years by quarantine, were ov... by the disease.

In 1850 it had almost died out in Europe, but wintered over at ... berstadt, twenty-nine miles southwest of Magdeburg. It com... again in both these cities in February, 1851; and reached Berlin, ... had twelve hundred cases. It was carried to Hamburg; obtained ... ing in Denmark; also in Stettin, and other Baltic cities; and fou... way to Coblentz, on the Rhine, in the west, and to Posen, towards P... in the east. It had, besides, wintered over in Prague, with one thou... five hundred and sixty cases; was at Vienna in June, 1851, with one ... sand nine hundred and eighty cases; crossed the Soemmering Alps ... tacking six hundred out of eight thousand railroad laborers, and ef... a lodgment in Northern Italy. It broke out in Pesth, Hungary ... Trieste; was at Marseilles and Malta, with two thousand one hundred ... fifty-eight cases; and was coming up from Egypt for the third time, ... two thousand five hundred cases at Cairo. It had also been at Mec... Medina, brought up from Bombay, where there had been two thou... three hundred deaths in 1849, four thousand eight hundred in 185... four thousand and twenty in 1851. Macnamara, page 137, says ... northwest provinces of India had also been affected, and the disease ... traveling on toward Meshed and the Caspian Sea, (by the North Per... route.) It went up the Persian Gulf to Bassora and Bagdad in ... and reached Tabreez and the Caucasus, toward Southern Russia, in ...

In 1851 it wintered in Bohemia, attacking Prague for the fifth ... the course of two and a half years; entered Silesia in August; ... rest of Germany, together with Belgium, Holland, and France, were ... from it. It persisted in various parts of Russia from 1847 to 185...

esh importations from Poland. There were over eleven thousand
s in Warsaw, from whence it again spread north, along the river
ala, with Polish raftsmen, to the Baltic; was carried back west again
erlin, and southwest to Breslau and other places, so that Prussia
sixty-eight thousand five hundred cases from July 3, 1852, to April
853. Importation of the disorder was recognized everywhere and
st every time.

1853 there was a tremendous outbreak in Russia, of which St.
rsburg seemed the center. Moscow was infected from St. Petersburg,
the disease traveled east towards Orenburg and Central Asia. War-
was again attacked and helped to infect Russia southward towards
and down towards Odessa, to which it was also coming by way of
Black Sea. Again it was conveyed west to Prussia from Poland by
old, often-traveled routes of the rivers Vistula and Oder, both of
h are connected by canals with the Dnieper, upon which Kiev is
ed. Memel, Dantzic, Stettin, and Konigsberg were once more
lved. It broke out anew in Berlin August 7, with fourteen hun-
l cases in six weeks; and was carried up the Elbe to Hamburg and
nen by emigrants. Holland, Belgium, and France were now drawn
the vortex. From Hamburg it was carried to Havre, and from there
'aris. In 1853 there were nine hundred and sixty-two cases in Paris,
re it persisted slightly during the winter, to erupt severely in 1854.
land was invaded toward the end of 1853 by arrivals from Germany,
den, and Norway. From July 7, 1853, to December there were one
sand two hundred and sixty-five cases in London. Manchester,
nburgh, and Liverpool were attacked severely, and it lingered in all
hem during the winter. Copenhagen was affected in June, 1853,
seventy-two hundred cases before the epidemic ceased, and formed
nter from which cholera was sent in various directions; not only
r Denmark, but also again to Sweden; where, however, only five
tors died out of three hundred; and one hundred and twenty-seven
ses out of three thousand. Twenty-eight infected vessels sailed for
United States from England, Holland, France, Hamburg, and
men with one thousand one hundred and forty-one deaths on their
ages.

t re-appeared in Persia in May and June, 1853, and lingered through
winter, with fifteen thousand deaths at Teheran. Paris was again
ted in the spring of 1853, and it spread over France with one hun-
d and twenty-five thousand seven hundred and twenty-five deaths in
rteen months. It arose in Spain and Italy by importation and mul-
ication; with five thousand three hundred and eighteen cases in
ioa, forty-five thousand attacks in Sardinia, twelve thousand six
ndred in Naples, and twenty thousand in Messina. It again appeared
Malta, probably coming both from Egypt and Europe. In Venice it
ed from the fall through the winter, to April, 1855. Switzerland was
r attacked for the first time. It reached Munich at the time of the
at exposition, and continued from July, 1854, through the winter to
ril, 1855, with four thousand eight hundred cases. Munich was the
r center from which it spread in all directions over Bavaria, with six-
n thousand eight hundred cases. Forty-eight Bavarian physicians
; of seventy-six thought it arose from miasmatic infection, twenty-
ht were contagionists, while sixty-six were convinced that it was
h imported and portable and communicable in some way. It ap-
ared again in Vienna with a few attacks in June; more, but scattered
es in July; and then it progressed so slowly that it was not acknowl-

edged by the government until September; after which it lasted up to February, 1855, with five thousand two hundred cases.

It was carried east to the Crimea by the French armies and fleets in 1854, as the whole of France and Algeria, from whence the troops came, was infected. Also it was taken by the British fleet to the Baltic, which helped to spread it again into Russia. London had three thousand deaths from diarrhœa and ten thousand seven hundred and eighty-five from cholera in 1854.

Persia was again the abode of Asiatic cholera in 1854, the mortality at Teheran being very great.

In 1855 it obtained a still greater extension in Italy, especially at Genoa, Nice, Turin, and in Sardinia; while Parma and Piacenza had thirteen thousand five hundred cases; Florence, five thousand. From Venice it spread up into the Tyrol, and eastwards to the coast of the Adriatic, towards Turkey.

In 1855 cases occurred through the whole winter in Prague, Pesth, Galicia, and Venice; and by May, Bohemia, Moravia, Galicia, and Hungary were again involved. In Venitia there were seventy-two thousand cases; in Lombardy, sixty-four thousand; in Vienna, six thousand six hundred and eighty-five; in Bohemia, fifteen thousand; Galicia, one hundred and twenty-eight thousand; and in Pesth, thirty-seven thousand. In the whole of Austria, two hundred and seventy thousand nine hundred. From Austria once more it spread north toward Prussia, and came out again from Poland down the river Vistula, to Dantzic, Konigsberg, and other Baltic towns. It reached Berlin in July, with two thousand one hundred and seventy-two cases in all. In Paris the first case occurred in February, and there were only sixty reported in August, when another outburst commenced. It re-appeared in Marseilles, Holland, Spain, Portugal, and Turkey. Sweden had one thousand three hundred cases, and Russia three hundred and twenty-four thousand; while Poland, Africa, Egypt, Asia Minor, Syria, Arabia, and Mecca were all again afflicted. Europe was the great acknowledged seat of cholera from 1852 to 1855, probably because other places, especially Persia, could not make their distresses known. But nothing is farther from the truth than the assumption of Tholozan that it arose spontaneously anywhere.

In 1856 Spain, Portugal, Russia, Sweden, and North Germany had cholera. It showed itself in Lubeck for the seventh time. In 1857 it had almost disappeared, except in Sweden, from whence it was again carried over to North Germany, especially to Altona, Hamburg, Konigsberg, and Dantzic. It broke out afresh in Persia, particularly at Meshed. In 1858 there were sixteen thousand deaths among sixty thousand pilgrims at Mecca. During 1859 it again raised its head in Russia, at Astrakan, Moscow, and Saint Petersburg, from whence it was conveyed to Rostock in Prussia by steamboats. Dantzic had a fresh outbreak. Hamburg had two thousand four hundred cases, and forwarded it to Denmark and Holland. It again appeared at Mecca and Damascus. Macnamara, p. 182, says: "Cholera again showed itself in the northeast of Persia, in connection with the extension of the pestilence over the northwest of India and the Punjaub in 1856, and from 1851 until 1861 it reappeared in Persia year after year in various localities. It was on the Persian Gulf and at Bagdad in 1851; at Teheran and the shores of the Caspian Sea, and simultaneously in the principal towns on the Persian Gulf in 1853. In 1855 the north of Persia was again under the influence of invading cholera. The Persian caravan going down to Mecca was also attacked. In 1856 the north of Persia and the

re course of the river Euphrates were infected. In 1857 there was a h outburst in the northeast of Persia, and also in the south at Ker-, Bagdad, Meshed Ali, Bassora, and other places on or near the ian Gulf. In the Persian province of Fars, the outbreak in 1857 the most virulent that had happened in twenty years; and not only inhabitants of the Gulf coast, but those of the interior of Persia, e under its influence. In 1860 and 1861 it again invaded Persia; but 1861 to 1865 there was no further epidemics in that country." (*Ibid.*, 8.) "The great twelve-year pilgrimages of 1865 and 1867 in India about to take place, previous to which the ordinary annual gather- sink to the lowest numbers, often leading to the innocent belief the interest in these religious dissipations is dying out. Hence lera seems to sink down everywhere just previous to its greatest reaks."

he principal facts which seemed proved during this epidemic were:

The capability for the disease to linger along, with a few cases, all ter.

. The renewed outbursts from these hibernating cases during the warm season.

I. The conveyance of the disorder in every direction, north, east, h, and west; just as the pressure of commerce, travel, or war pro- ed it.

. The involvement of Denmark, Switzerland, and Greece, always iously protected by quarantines, which were now forced or aban- ed. Greece was attacked for the first time, during the Crimean war, n both Odessa and the countries near the mouth of the Danube had infected from Poland and Russia. Early in 1854 it attacked the sian and Turkish forces on either bank of the Danube; but it did reach Greece from that direction.

the early part of June, vessels from Marseilles, bringing French ps from infected places and with deaths on the voyages, landed the se at Varna. From the time these troops landed, cholera spread pro- sively through the town and allied forces, attacking the French and ks almost simultaneously and afterward the English soldiers. The ps in the Piræus, Greece, were all perfectly healthy until the early of July, 1854, when a French steamer arrived from Marseilles with era on board; cases were carried to the hospital; cholera appeared and ad rapidly, and the disease began to crop out in various parts of the n. Greece, from her peculiar situation, relations, and small commerce, been able to isolate herself from the rest of the world in the epi- ics of 1832 and 1849, and had always been absolutely free from era; for no winds from Egypt, Malta, Italy, Asia Minor, or Turkey ever blown it to her. In 1854, being occupied by foreign forces, which she had no control, the disease effected an entrance into the ntry, by well-known importation, in many troop-ships. In 1865, g again her own mistress, she entirely protected herself, while the dis- was raging all around her. (*Ibid.*, p. 147.) It was introduced into Gal- li also by a French troop-vessel from Marseilles, and in nine days it hed the British hospital, in the direct track of communication between French camp and the town. A distant hospital entirely escaped. Marroin, chief physician of the French fleet, stated that cholera was ed into the Black Sea with the French ships Primaugult and Magel- from Marseilles and Gallipoli. When free communication was opened ween the fleet and General Bosquet's division the disease broke out extreme violence. In the English fleet it first appeared in the Dia- d, ten days after the arrival, near her, of a French steamer from

Toulon, with cholera on board. Of twelve thousand five hundred and seventy-two British sailors, seven hundred and ten were attacked. . . per cent. of whom were supplied with water from springs at Balt. . where French troops had not only been quartered while suffering . cholera, but had covered the ground for a great distance with . excreta, and washed their foul clothes at the springs. The English . sels which were supplied with distilled water had not a case. At a . period the Baltchick water seemed to cause severe diarrhœa only.

By strict quarantine Denmark was saved from cholera until 18[illegible]; although Russia, Prussia, Sweden, Norway, England, and Holland . been affected repeatedly and severely all around it. Then there . slight outbreak of twenty-eight cases and fifteen deaths from a La . vessel, which had slipped in with a clean bill of health. In 1852, . the example of England, all quarantine restrictions were removed; a . in 1853, the first great Danish epidemic commenced at Copenha . which culminated in seven thousand cases and four thousand seven . dred and thirty-seven deaths. The first case was a ship's carp . the next a ship's laborer. They were taken to the marine ho; where an epidemic soon occurred. Hamburg, Lubeck, St. Peters . and various Finnish ports were affected, and ships from them with . era on board were then lying in the harbor of Copenhagen. A . days after three cholera-patients were taken to a civic hospital, w . another outbreak took place. From Copenhagen the disorder s . all over Denmark, and the authorities were reconverted to their . views about contagion. Denmark was again protected until 1857, w . cholera was re-introduced. The most energetic measures were ins . taken to stamp it out, and only two hundred and eighty-six deat . curred. In 1859 there was a small outbreak with one hundred and . deaths in all Denmark. It has remained free till the present time. . Danish physicians all now are contagionists. (See Küchenmeis . Zeitshrcft für Epidemiologie vol. 2, p. 70, report of Dr. Schless . delegate to the cholera conference, for Denmark.)

In England Dr. R. Dundas Thomson found many vibrios in the a . phere of wards filled with cholera-patients, fewer in wards one-half f . and none in empty wards; also in the air of sewers, which was als . The greatest mortality often happened in houses near offensive g . gratings. In three hundred and seventy-three cases, nine deaths . curred on the kitchen floor, sixty on the ground floor, one hundre . the first floor, one hundred and fourteen on the second floor, and . enty-three on the third floor. Ninety-six houses had one death . forty-six had two each, twenty-two had three, seven had four, eight . five, two had six, three had eight, and one house eleven deaths. T . were no less than twenty-one instances of husband and wife dying . a few days of each other. Vibriones were noticed in great abundan . in the rice-water discharges; and in the drinking-water of affected p . also in the blood of cholera-patients. Although occasionally found . other disorders, they were vastly more frequent and abundant in cho . Hassall found that three circumstances were necessary to the develop . of vibriones, viz:

I. An alkaline fluid;

II. Organic matter in a state of decomposition; and,

III. Warmth.

He also discovered that when once introduced into the alimen . canal of cholera-patients, vibriones are brought into relation with . ditions highly favorable to their development. Their multiplication . place with almost inconceivable rapidity in twenty-five cases, seem . because the rice-water discharges are always alkaline, offensive, a . .

els warm. In other diseases he found few vibriones, but as he found
e, he did not draw the broad conclusions he might have done. He
ught their occurrence in such vast numbers, in the rice-water dis-
rges, of interest, if not importance; and turned marked attention to
fact that the fluid thrown out into the intestinal canal in cholera, is
re than usually prone to decomposition, and is more than commonly
aline. He even went so far as to suggest that the existence of these
ge numbers of vibriones in the evacuations might explain, in some
ree, the success of sulphuric acid in checking the diarrhœa; for
d and other acids, when freely administered, destroy the conditions
ential to the development of vibriones, and thus annihilate the
riones themselves. It checks the tendency to decomposition and
tralizes the alkalinity of the fluid. Vibrios were also found in the
ne; and on the soiled clothing of cholera-subjects they abounded
l were alive and active. Hassall again mildly drew the conclusion
t, if these vibriones possess any influence in the production of
lera, washing soiled clothes might in some cases give rise to the
ase. He repeats, "the only organic productions met with in the ex-
uation of cholera-linen are vibriones." To test the matter still fur-
r, several cholera-patients were made to breathe repeatedly into a
ll's apparatus charged with recently-distilled water, when numerous
rules of fungi and vibriones were seen by the third day. Hassell
eated the experiment on himself for three days, but no fungi or
riones were found. The fluid part of the mucus in the bronchial tubes
holera-patients abounded in vibriones, and the rice-water discharges,
n when still retained in the small intestines, swarmed with them.
e conclusions became irresistible that these bodies were more abun-
nt in cholera than most other diseases, and might become injurious
m their very numbers; or at least they mark a peculiar state of the
ly, which allows them to multiply with excessive rapidity, or, as
skell cautiously says, although they may not be the cause, they may
l have some influence in explaining and aggravating the symptoms.
t has been suggested and almost proven that the wet discharges are
as dangerous as the dried. Hassall unwittingly threw some light
this point also. He found that vibriones did not escape from fluids
ring their evaporation. By carefully distilling, at a low temperature,
ortion of rice-water discharge, which absolutely seemed alive with
riones, and which was opaque from the numbers present in it, he
nd that the distilled fluid came off as clear and transparent as water;
l no vibriones were discovered in it on the strictest scrutiny with the
roscope. But when the discharges become dry, vibriones may be
wn about by draughts of air, or in sweeping, dusting, &c. It seems
urd to assume because a few vibriones are not harmful that many
y not prove so. A few drops of laudanum or any other poison may
no harm, but many assuredly will. (See appendix to Report to the
dical Council of England, of the Committee for Scientific Inquiries
Relation to the Cholera Epidemic of 1854.)

In the same report some light is thrown on the origin of cholera in
wcastle and other places. The tide of the river Tyne carries up the
vage of Newcastle as far as Elswick. During a drought the water-
mpany supplying Newcastle pumped directly from the river at
swick, so that the inhabitants of Newcastle began to drink water
ntaminated with the filth of their own dirty city, at a time when
arly two-thirds of the population were without privies, and the human
h accumulated in their streets was washed into the river by every
n. This impure water was consumed from May to the end of August,

1854, without causing cholera, although diarrhœa, typhoid fever, and dysentery abounded. As soon as the first cases of cholera occurred the authorities of Newcastle betook themselves vigorously to washing out and flushing all the drains and dirty holes in the place. On August 29th a woman came by steamer to Newcastle with cholera. On September 1 three sudden deaths occurred, and by the 9th the disease was declared epidemic; for on the 12th there were fifty-nine deaths, and on the 15th no less than one hundred and forty. The scandalous proceedings of the water-company were discovered and stopped on the 17th. On the 25th the deaths had fallen to seventy-five a day, and on the 30th to sixteen, after which not more than four deaths occurred in any one day.*

Something, doubtless, of this kind, happened in Paris in 1832, when in that year cholera upheaved very slowly in Newcastle, and consisted a succession of local outbreaks proceeding from individual cases, or the contamination of isolated pumps and wells.

In 1854, the well-known splendid investigations of Drs. Snow and Budd cleared up many of the mysteries connected with the spread of cholera and typhoid fever by contaminated water, and led to the most important and beneficent sanitary reforms. The water-supply of almost every city, town, and many villages in England, was examined chemically and microscopically; drainage and cleansing were studied more particularly and carefully, and the endeavor was made to make every living being and place cleaner and sweeter savored; the air and soil of the whole land purer; the food and clothing more wholesome and fresh. Every cellar, sink, drain, gully, gutter, privy, alley, street, and court was to be cleansed and brightened; every nuisance was to be abated; every house rendered fragrant by fresh air, pure water, and prompt removal of all offense and refuse; in short, as pure as snow.

At the same time Pettenkoffer, in Munich, began to look from forty-fifty feet under the surface of the earth for underground water, which he supposed had first to be efficiently infected by the cholera-evacuations before food, clothing, beds, floors, hands, plates, cups, glasses, sinks, privies, gutters, and drains could become actively contaminated by them. From personal observation in 1842 and 1857, the writer can corroborate the following account: "From time immemorial, Munich had had the reputation of being an exceptionally unhealthy place; and stories of an ignorant defiance of sanitary laws are especially numerous in its records. It should be free from cholera and typhoid fever. It stands upon a high, barren plain, 1,600 feet above the level of the sea, open to the purifying effects of the full power of the sun in summer, while its atmosphere is swept the whole year by storms that accumulate upon the neighboring mountains. Its soil consists of loose gravel to the depth of many feet, allowing all the fluid refuse deposited on the surface to leach away, and the Iser, "rolling rapidly," furnishes a convenient water-way for the removal of sewage. But the introduction of sewers is very recent, even in the best and broadest streets; and, owing to a want of knowledge in their construction, there is not sufficient declivity given to them to carry away their contents. Nor is there any system of water-flushing to drive out the foul sediments and cleanse the pipes. Of the 75,000 tons of refuse matter furnished by the inhabitants, about one-third is carried out of the city by the market-gardeners who spread it upon the neighboring fields, to send back polluted smells with every wind that blows. There is a disagreeable

*Report on the Epidemic Cholera of 1866, in England, p. 32.

ending at all times from the sewer and gully gratings in the streets. ny of the privies in private dwellings extend like huge chimney- fts from the tops of the houses with openings on every floor down) the cellars where they end, without any sewer-connection or ter-flushing. The air of the houses is always bad, especially at night, l when the discharges from typhoid fever, cholera, or other infectious ease get into the privies disaster is almost sure to follow, especially the Munichers, with great dread of colds and catarrhs, make all close en they go to bed. The ground below Munich is full of springs; re is a well in the court-yard of almost every house, in close prox- ty to the outdoor vaults, refuse-pits and drains, and of course is filled m that bugbear of the Munich theorists, "the ground-water." The st ignorant citizen knows that the well-water, owing to the mistakes of s, is not fit to drink, and avoids it as a beverage when he can; augers are warned against using it; and in numerous instances bowel nplaints and typhoid fever have been directly traced to its poison. ithin a few years spring-water from Thalkirchen, a few miles out of e city, has been supplied to about one-third of the inhabitants; and in last outbreak of cholera, 28 per cent. only of those attacked, while ing it, died; while 72 per cent. of those relying upon other fouler water ccumbed. Small shops are kept on the ground-floors of many dwell- g-houses, and the dairy-woman keeps her milk in the cellar; the green- ocer makes the air of his underground shop damp and bitter with aps of neglected vegetables; the butcher has the right to keep living lves, pigs, and sheep in his, and slaughter them there. The streets ve long reached up to the old cemetery, and the new one laid out only few years ago was placed within one block of the nearest houses. hole generations of families have been buried in graves, deep at first; it coffin has been placed on top of coffin, till the last one has often me within a few feet of the surface. The air of the vicinity is laden th the smell of death; and the underground water is polluted. One of e favorite myths of Munich is that "an enormous dragon, which lived the ground beneath the city, poisoned all the wells with his venomous eath, until, being at last lured to the surface by seeing his reflection a mirror held above a certain spring, a brave knight slew him, and ved the people from further destruction."

Pettenkofer has been looking deep under ground for the mythical agon, which lay right under his eyes and nose. What Munich eeded was pure water for the people to drink, and cook with; plenty of ater for them to wash and bathe in; sewer connection with their vaults d drains, and water to cleanse them; and an abundance of water for constant daily flushing of the sewers. As far back as 1822, an inex- austible source was pointed out from which water could be obtained, suffi- ent to obviate the necessity of any hydraulic works for its elevation. Not r away in the mountains is a lake of remarkably pure water, situated bove the level of the tops of the highest houses. The estimated cost of inging this water to the city was only two million of dollars; but the incipal scientific medical object has seemed to be not to supply Munich ith abundance of pure water, or to sewer or cleanse it, but to substan- iate the useless proposition that the variations in the sanitary condition f the city might or might not be closely connected with the rising and alling of the underground water. The broadest and most beautiful treets have been laid out, but no sewers put in them. Magnificent uildings for religious purposes and those of art have been erected; ut the surface-filth has not been properly removed.

The few physicians who declared that bad water and bad drainage

are the principal causes of its everlasting typhus and its frequ- epidemics, were denounced as the enemies of the fair fame and prosper- of a beautiful-looking pest-city and its dirty inhabitants. Mar- has always been a religious place, but it has never learned that cle- ness always comes next to godliness, and, in times of pestilence, bet- it. Those who defy pestilence, by excess in eating and drinking and riotous living, are scarcely less severely punished than those who ex- the first symptoms of the disease, to the cold, damp churches, and w- in prayer the few precious hours, which, spent in a warm, clean bed a room, might have insured the preservation of their temporal life- perhaps the better salvation of their souls. Such are the results w- exist to this day, after a twenty years' search for the underground wa- dragon of pestilence. The English plan was to stop all importa- cholera; to cleanse every place and body; to furnish good food a- pure water to every one; and thus remove the distemperature of the a- and noxious quality of the underground water, which are thus brou- entirely under human control; for surface and local filth are the pr- causes of both.

Pettenkofer rendered immense services to more practical me- proving the frequency of occult importations of cholera, the le- period of incubation that it might occasionally sustain, and by his e- deavors, according to the plan of Von Gietl, to destroy and disinfect t- cholera-discharges before they could get into the dangerous underg- water. But he led the more dreamy part of scientific men into geolo- and hydrographical studies, rather than toward plain sanitary exer-

In 1854, also, Thiersch made his first well-known experiments i- reproduction of cholera on mice, and laid the foundation of the prev- doctrine of infection.

All the difficulties and ordinary results of an investigation into t- causes and course of an outbreak of cholera in a large city are well p- trayed in the celebrated Dr. H. W. Acland's memoir on the cholera Oxford, England, in 1854, (London, 1856, 4th,) p. 172.

Three hundred and seventeen cases of cholera and choleraic diarrhœa with one hundred and ninety-four deaths, occurred from August 6 October 30, 1854. The first reported cases were among residents: and t earliest deaths among butchers' wives and cartmen's daughters. T- localities of the first thirty fatal cases are given unfortunately with- omission of the choleraic cases, and an attempt was made to show t- there was not always direct communication or connection in all the fa- tal attacks. The first deadly case occurred at the north end of the to- the second to the twelfth attacks happened on one block in Gas stree- close contact with each other, almost at the extreme southern end of t- city; but in the mean time the disease had commenced in the county j- The thirteenth case was at the extreme east of the town; the sixteen- close to cases Nos. 9 and 12; the seventeenth, in the great group in Gas street; the eighteenth, in the highest and most central part of the pl- the nineteenth was a countryman, who had been about the city near t- eighteenth case; the twentieth, a surgeon, who had visited cases t- twenty-second, also in the block on Gas street; the twenty-third was th- first which occurred near the initial case; the twenty-fourth, twenty-s- enth, twenty-eighth; and thirtieth were grouped together; and the twe- sixth and twenty-ninth were near the great focus in Gas street. Be- the scattered cases were few. There were only three deaths in the fi- fifteen cases, and among the first thirty cases there were no less th- fifteen recoveries. Of course the first fifteen deaths were separated the fifteen recoveries, and there was no perfectly visible connec-

he fatal cases. The thirtieth death was in reality the forty-sixth
, and twenty-three localities had already become affected instead of
as we are led to suppose. The first and ninth cases were in a butch-
wife and daughter, occurring in the first and second affected locali-
, at great distances from each other. The first and fifteenth cases
e charwomen in different places; the third, fifth, eighth, and
ty-second cases were prisoners in the county jail; the fourth and
nth were a carter's son and daughter; the sixth, twenty-eighth, and
nty ninth were tailors; the eleventh, sixteenth, and thirty-eighth
e laborers; the fourteenth, thirty-third, thirty-fifth, thirty-seventh,
forty-sixth were laborers' wives and daughters; the twelfth, a rail-
porter; the thirteenth was a shoemaker's son; the nineteenth and
nty first, a shoemaker and daughter; the thirty-first and thirty-sixth
e washerwomen; and the thirtieth a laundress's son. Then there
e grooms, fishmongers, milkmen, carpenters, boatmen, policemen and
ir wives, coal merchants, and waiters. All these were among a class
people who moved about in every direction, often with diarrhœa upon
m, and cholera had been in England for many months. Dr. Acland's
position, p. 21, that cholera arose in many of these persons without
mmunication on the part of those attacked is very far from proven,
hough it seemed so on casual examination; while his admission that
lid spread under some circumstances and in some localities from per-
to person is fully corroborated. In the first three weeks only three
es of cholera were recognized; in the second period of three weeks
re were eighty-three. In the first four weeks only the north and south
es of the town were touched; but in the fifth week the north, south,
t, west, center, and outskirts were involved. Hence it arose very slowly
l seemed to spread from infected localities and persons rather than
m a general atmospheric distemperature. Besides, the population
s twenty-six thousand five hundred, and only three hundred and
renteen actual cases occurred; showing that the disorder attacked a
r people rather than the whole inhabitants. One medical man died,
e was in danger, and several had choleraic diarrhœa. The nurses
re tolerably exempt, (only three being affected:) the washerwomen
ffered much, (eighteen of them.) There were no cases in the city
l, near by the county jail, where the highest proportional number
cases and deaths occurred in the whole city. No cases were returned
cholera in which the evacuations were bilious, although many of
em were severe, and attended with cramps, vomitings, and more or less
llapse. Still, these diarrhœal cases appeared generally in the same
calities, times, and intensity as the genuine cholera. In the first
riod of three weeks no record of the diarrhœal cases was kept, so
at all clews were lost.

In the second period of three weeks there were one thousand three
ndred and thirteen cases of diarrhœa; in the third, two thousand six
ndred and three; in the fourth, when cholera was ceasing, there were
ly five hundred and twenty-seven. In all, at least six thousand and
ree hundred cases of diarrhœa were enumerated. In addition, during
e first three weeks, one hundred and twenty-three cases of choleraic
iarrhœa were reported, and it was stated as known that many more
curred; in the second period of three weeks, one hundred and sixty-
ve; in the third, sixty-one; with 11 per cent. of deaths. Hence, in
cing the connection of the fatal cases, at least three hundred and fifty
ts were omitted, and, perhaps, six thousand six hundred and fifty.
n ten places around Oxford the importation of the disease was not
aced; in nine villages it was; and the proof had to be very clear and

simple to be admitted at all. A few plain occurrences were thought afford excellent illustrations of cholera originating, to all appearance spontaneously and then spreading by infection to persons in immediate contact with the first attacked. But when all the diarrhœal and cholaic cases are overlooked the transportation of the disease, of course, is often escape notice. Still some cases were very clear and striking. Garsington, the man Ruffle, who was first attacked, had not been in Oxford, but had received into his house a person who had tended cholera cases, and his son, who had just partially recovered in Oxford. The latter, who was still weak, occupied his father's bed by day. As his father died; next his wife died; and a grandson was attacked but recovered. The Ruffle's house was half of a double cottage with five dwellings under the same roof; in it eleven cases of cholera, with four deaths, and many cases of bad diarrhœa occurred. Of thirteen neighbors and friends engaged about Ruffle and his wife, eleven contracted the disorder, and two out of the four nurses who carried Ruffle and his wife to their graves were affected. A chaff bed, occupied by two persons, reproduced the disease. Cholera clothes and bedding taken from Oxford started an epidemic in New Hinxton and produced eight cases. Density of population alone did not produce this cholera, but increased it when introduced. Imperfect drainage (p. 50) unaided was not the cause, although the ground in some places was saturated with liquid ordure to an amount scarcely to be estimated. The wells were more or less impure; and the better class of people would not live in the worst places. The water-supply of Oxford was decided to be one mode, but not the only one, of conveying cholera. The city jail had escaped and the county jail was attacked in 1832, 1849, and 1854. The cause was in the water-supply. Many cases of choleraic diarrhœa and some of common cholera of special severity occurred early in the outbreak, in the latter building. The third reported case in the whole city happened in the county jail. Finally, thirty-seven out of ninety-five inmates were attacked, and four of the officers. The county jail was supplied with water by a stream running through one of the worst diarrhœal and cholera districts, Saint Thomas. The stream was low; the water was ponded; the pool not only contained garbage but a drain from the prison flowed into it; and within ten feet of the mouth of this running drain, the supply-pipe from the jail sucked the contents of the polluted pool for the prison use. From this source the kitchen-coppers were supplied, and from this repulsive source the soup and gruel of the establishment was made. It need excite no surprise that the first fatal case had been in the prison for a month and the third for several months. There had been three severe choleraic attacks and recoveries, and much diarrhœa in the county jail before the first fatal case in Saint Thomas district, from which the water-supply came. The earliest death in Saint Thomas parish occurred on September 6; the first in the jail on September 19. The water originally caused diarrhœa, then cholera. The foul supply-pipes were cut off, after thirty cases of choleraic diarrhœa and five of fatal cholera had occurred, and only five more new cases supervened. The disease was not blown from India to Oxford, for the winds were generally north and west. It was not caused by deficiency of ozone, as there was an excess of it when cholera was at its height. The weather was unusually fine, dry, and clear, (p. 66;) and the air was not stagnant, for hospital tents were blown down by gales when the disease was at its acme.

Dr. Acland's final conclusions were: First. Diarrhœa always occurs with cholera. Second. Cholera may arise without the suspicion of

ion. (especially when it is not carefully sought for;) although it may ainly be conveyed from place to place by human agency. Third. It scarcely be doubted that cholera evacuations are capable of communi-ng the disease; but it is quite certain that in the majority of cases y remain innoxious. Fourth. It is quite certain that productive lera may be imported; and it is equally certain that it is often not pagated in some localities apparently exceedingly prone to the devel-ment of the disease. Dr. Acland continues, p. 76: "No one doubts t in a cholera period: First. Persons die of diarrhœa and choleraic rrhœa, without passing into true cholera. Second, such cases do ntimes pass into cholera. The two diseases, diarrhœa and cholera, ch seem so widely apart in their appearances and danger, so unlike heir relation to treatment, yet do at times pass one into the other."

Acland assumes, very incorrectly, that all diarrhœas and choleraic rrhœas are produced by atmospheric influence; but we know that y are often caused by bad food, polluted water, and foul exhalations, from the general atmosphere, but from offensive privies, drains, sew-, and a tainted state of dwellings, kitchens, cellars, and of the surface he earth aronnd them, from the careless disposal of refuse, garbage, l filth of all kinds. He thinks diarrhœal and choleraic diarrhœal dis-rges are innoxious at first, but may become so altered in or outside he human body as to develop a new specific poison which will act upon er persons, and thus produce cholera spontaneously. The only solu-n of this question lies in a simple statement of all the facts, viz, first, t there are numberless cases of diarrhœa, both in ordinary and cholera sons, which have nothing whatever to do with infectious cholera; ond, that there are also many cases of common diarrhœa so severe as rely to be distinguished from the milder cases of true cholera; third, t there are instances of cholera-morbus occurring every year from ac-ntal causes, which closely resemble true cholera, but are not infec-us; fourth, there are developments of true cholera, of so mild a type t they may easily be mistaken for mild or more severe diarrhœa, but ich are infectious, like the milder cases of scarlatina; and, fifth, severe es of cholera which are deadly and can be mistaken for no other dis-e, but which are so little infectious that they produce no multiple es unless their products get into the drinking-water, milk, or food of neighbors, visitors, or relatives. There will always be debatable cases l many intermediate occurrences, which are readily capable of differ-t explanations, and which may perhaps never be distinguished from ch other by any except the most widely read and experienced men. long as different diseases act so similarly, there must always be ersity of opinions among the varied classes of learned and unlearned ysicians, all appealing to apparently reliable facts. Dr. Acland, how-er, infers, p. 77, "that it is important beyond all power of expression destroy with chemical agents the organic combination of all diarrhœa d cholera evacuations immediately after they have been passed, and apply the same precaution to all evacuations in any way resembling em.

It is a matter of much doubt whether North America was ever free m cholera at any period from December, 1848, until after the sub-lence of the epidemic of 1854.

Dr. Peters has shown that Asiatic cholera existed continuously in Eu pe from 1847 until 1859, and it seems pretty clearly indicated that the idemic of 1848 in the United States received continual re-enforce-nts, if not of cholera-infected individuals, by cholera-infected fab-s. Dr. Fenner writes: "Cholera seems still to linger about New

Orleans and along the Mississippi River, occasionally amounting to a moderate epidemic in the city and on some of the plantations along the coast." Dr. Marsden records an epidemic at Quebec in 1851, the first case of which occurred on the person of a German recently arrived in the United States. This man was attacked with cholera while at a boarding-house and died. The man who nursed this case was sent to order a coffin, but, on his way, stopped to see his wife, who lived upon a small street called Ancien Chantier. This woman died of cholera in two days. From these cases the disease spread, and two hundred and eighty-one deaths occurred.

Dr. Marsden also records an epidemic at Quebec in 1852, which occurred on the 25th of September, the initial case being in a man named McKnight, who had been working upon the ship Advance, from New York, upon which vessel a case of cholera had occurred on the voyage to Quebec. The disease communicated rapidly to six other persons who lived in the same lodging-house, among whom were two sailors of the Advance. Of these seven cases, five died. The last case occurred November 9, there having been one hundred and forty-five deaths.

During 1851 one case of cholera was reported at Boston, Mass. During the same year the disease occurred at Saint Louis, Mo., among European immigrants who arrived directly from New Orleans. A considerable number arrived on the steamer Latona, from New Orleans, April 11.

About July 5, 1852, a woman arrived at Dayton, Ohio, from Sandusky, where cholera was said to be epidemic. When she arrived she had every symptom of the disease. She was taken to an Irish boarding-house, where, after a severe illness, she recovered. Six other cases occurred at this house; all died. The disease spread and about [illegible] deaths occurred.

In 1852, during the month of August, cholera appeared among the laborers, many of whom were emigrants, on the Bellefontaine and Indiana Railroad. The majority of those attacked died. Very few citizens took the disease, with but one death.

In 1852 a slight epidemic occurred at Gilboa, Ohio. Thirteen deaths occurred.

In 1852, on the 12th day of July, cholera appeared at Chicago. Four hundred and thirty deaths are reported. During the year, reports from Michigan note the occurrence of isolated cases.

In 1852, cholera appeared at Saint Louis, again among emigrants and the lower German population, and spread to other counties of the State.

Enough has been shown to demonstrate that the disease was in the United States during 1852, and the same story might be told of the earlier months of 1853, as has been acknowledged of the latter months.

We quote again from Dr. A. Clark:

"In the autumn of 1853, ships from infected ports arrived in great numbers in the harbor of New York, bringing emigrants infected with the disease. Indeed, it is reported for this port alone, that on board twenty-eight ships arriving in the month of November, one thousand one hundred and forty-one persons had died of cholera. In fact, ships bringing this unwelcome freight continued to arrive during the winter and spring. But the first appearance of cholera in the northern division of the United States was not in New York; it was not even on Staten Island, but it was in Chicago, in the latter part of April, 1854. It broke out there among the recently-arrived emigrants, continued to be severe until June, when it was declared epidemic. On the 16th of May, same class of persons, recently-arrived emigrants, were seized with

ase in Detroit; and still it was not in New York. During the whole
ıth of May of this year, there was but one death from cholera in this
. The epidemic of that year dates from the 14th of June. Then, in
cago and in Detroit the outbreak of the disease preceded its out-
ak here; and why? Those places are in the principal line of emi-
nt travel; the emigrants passed through New York, to be sure, but
y were in good health at that time. They passed on to those cities,
were there seized with the disease, although cholera had not visited
er of the cities since 1849. Why should emigrants coming from the
cted ports of Europe, in infected vessels, be attacked to the exclu-
ı of other persons? Plainly, to my mind, because they carried about
ı them, in clothing or baggage, a poison capable of regenerating
lf and spreading abroad an influence that in the warm months pro-
ed a general epidemic."

ut these were not alone the arrivals that produced the epidemic of
4 in North America; for we find recorded by Dr. Marsden: "The ship
nmanna, from Liverpool, arrived at the quarantine station below Que-
on the 15th of June, having thrown forty-five passengers overboard
he voyage, who had died of Asiatic cholera. The John Howell, another
senger vessel from Liverpool, arrived at the station on the same day,
ing had no cholera on board. The passengers from the two vessels
e landed at the same moment of time, in fact together; and being
stly Germans, Prussians, &c., they intermingled freely, and enjoyed
nterrupted intercourse with each other. During their stay at the
rantine station, one of the passengers of the Glenmanna died of
lera, and yet the passengers of both these vessels were discharged
m quarantine, and allowed to proceed to Quebec without further de-
tion. In five days after the landing of the passengers from the
lera-ship at the quarantine station, the first case of Asiatic cholera
Canada, in 1854, broke out at Quebec in the person of Lang Lorts, a
rman, who had been a passenger in the Glenmanna cholera-ship. He
s removed to the marine and emigrant hospital, and on the same day,
20th of June, nine other cases were admitted to the same establish-
nt, all belonging to the ill-fated ship John Howell, which had crossed
ocean and arrived at the quarantine station in perfect health, there
e infected and scourged by the pestilence. Of these ten cases, the
t ten admitted to hospital, or known to exist, eight died in periods
rying from ten hours to thirteen days."

In Quebec the disease spread among the citizens, became epidemic,
d the history of the former epidemics was repeated. These emigrants
ried the disease along the water-courses. Dr. Rowand, of Quebec, on
urning from a visit to the distant Red River country, reported that
en far beyond the limits of civilization, where habitations were few
d far between, where the stage-coach or wagon was the only means
transportation, he found the emigrants from these ill-fated ships
ffering from cholera.

In December, 1853, a few cases of cholera occurred at the quarantine
tions on the Mississippi below Saint Louis, but in January and Feb-
ary, 1854, when crowds of emigrants began to pour into the city, the
ease became epidemic and continued during the year. The mortality
ong the emigrants again was excessive, and was most severe during
e months of April and June. In this epidemic Saint Louis suffered
re severely than any other city in the United States. The river
eamboats becoming again infected, the disease was carried to the head-
ters of the Mississippi, Missouri, and Ohio. From Saint Louis the
ease was carried into Saint Charles, Gasconade, Boone, Cooper,

Chariton, Lafayette, Cape Girardeau, Washington, and Saint Genev... counties.

In April cholera occurred among emigrants at Chicago, and the ... demic lasted through November, with a total of fourteen hundred a... twenty-four deaths.

May 19, 1854, cholera occurred at Detroit among newly-arrived e... grants, the majority of whom had recently arrived from Holland. T... total deaths amounted to about one thousand.

About the last of June, four emigrants were put off an emigra... train at Ann Arbor, Mich., sick with cholera; three of the four d... Two men, one from New York, the other from Chicago, and a you... lady from Chicago died of the disease at this town; five deaths occur... among residents of the town.

It is well known that ships arrived at New Orleans, having lost pa... sengers from cholera on the voyage, during the last months of 185... early in 1854, but the disease did not assume an epidemic form ... the latter part of May, when, during the first week of the epidemi... two hundred cholera deaths occurred. Cholera remained in N... Orleans until all records were lost in the epidemic of yellow fev... that year.

On the 3d of June the disease was reported on a plantation n... Memphis.

On the 20th of June, Nashville was infected. In April the dise... occurred at New Albany, Ind., among persons recently arrived f... Saint Louis; several of the attendants took the disease, but it did ... spread.

On the 29th of May cholera appeared in New York. An editoria... the New York Journal of Medicine states: "Within the last few w... there have arrived at quarantine, Staten Island, three ships, ea... which lost passengers at sea, with a disease resembling, in all its ... acteristics, cholera. The first was the ship North America, tw... seven days from Liverpool, with seven hundred and sixty-eight pas... gers, arrived the 16th of May. This ship lost seventeen pass... during the voyage, and on arrival at quarantine several others w... sick. The sick were at once admitted into the hospital, and the ... were bestowed in the United States store-house, their persons clea... their clothing dried, and all supplied with good, nutritious food. T... period required for quarantine of passengers in good health is forty... hours. Within this period of detention cholera broke out among ... passengers, and out of about one hundred and twenty or over, that ... attacked, about seventy died. The second was the ship Progress ... seven hundred and fifteen passengers, thirty-two days from Liv... arrived the 18th day of May. She lost forty-four from the same ... but her passengers were all healthy on arrival at quarantine. The ... was the ship Charles Crocker, thirty days from Liverpool, wit... hundred and fifteen passengers, arrived June 3, and lost thir... from the same cause. Her passengers were all subjected, after ar... to the same sanitary treatment, but no case of cholera occurred a... them while at quarantine."

"In regard to the appearance of the disease in the city, it is be... that about one-half of the one hundred and twenty-eight deaths ... occurred during the four weeks commencing May 27 and ... June 24, have been among recently-arrived emigrants, who, regar... of all sanitary or hygienic regulations, have taken up their abo... filthy, ill-ventilated, and already-crowded courts, alleys, or tene...

r. H. E. Bartlett, health-officer of the port, referring to the arrival holera-infected ships, states:

About the same time the ships *Chas. Hill*, *Plymouth*, *Robt. ker*, *G. I. Patten*, and some others, arrived from Havre, all having rge number of cases of small-pox of a very malignant type. These e all placed in the small-pox hospital, situated in the northeast le of the quarantine grounds, at least eighty rods from the hospital grounds, where the sick and well from the cholera-ships were placed.

* * No cases of cholera were subsequently traced to them, the convalescent patients in the shanty buildings began to die of era, and, in less than a week, 75 *per cent. of the patients in the small-hospital died of cholera.*

On the 21st of May the *Dirigo* arrived from Glasgow with a small ber of emigrants. On her passage she took from the wreck of a el from Liverpool about thirty passengers. There had been no era on the wrecked vessel, and the persons taken from her saved the clothing upon their persons. The vessel, being healthy, all e allowed to go up to the city. Some of the first cases of cholera occurred in the city were traced to these emigrants."

une 2, the disease broke out at Buffalo, N. Y., and again its oc-rence can be traced to the arrival of emigrants. During this epi-ic the county poor-house became infected, and a frightful mortal-ensued. July 18, the disease occurred at the Suspension bridge, r Niagara Falls, where it was confined exclusively to a large number emigrants engaged in the excavations and public works.

rom New York City the disease was carried to New Haven, Conn., vidence, R. I., and Portland, Me., upon the east; to Albany, Troy, Syracuse, on the north. It reached Philadelphia about the 17th of e, but at this city, during the two months of its presence, but eighty-t deaths are recorded. The disease occurred in the lower portion he city, and in tenement-houses occupied by emigrants and sailors. During this year the disease was carried into Baltimore, Washington, some points farther south.

Dr. Atlee, of Lancaster, Pa., records that a car-load of emigrants e from Philadelphia to Columbia, Pa. Two or three of these grants, who were ill of cholera, were put out on the platform at the road-station; some gentlemen, seeing them at the point of death, ried them to a shed and waited upon them; in forty-eight hours the grants and these gentlemen were dead, and the disease spread in the n.

holera was carried into Lancaster by an emigrant, and several deaths urred. The train that left the cholera-cases at Columbia went on h the remainder of the emigrants to Pittsburgh, and from them cases urred at the last-named city.

Dr. A. C. Smith, of Columbia, states, in relation to the early cases at umbia, Pa.: "Among those who fell under my care, I recognized by whom I had noticed in the room with the German emigrants ing their illness."

Dr. J. H. Jackson states that a gentleman of Bainbridge visited Co-bia during the epidemic; on his return home he died of cholera. family fled; a friend, who took care of him, contracted the disease, did another who assisted at his burial. Neither of these two had n at Columbia or any other place where cholera was prevailing.

At Pittsburgh, early in July, a lady, who had just returned from a stern journey, took cholera and died. Several members of the same ily took the disease, and some died. From this time until Septem-

ber, occasional cases occurred among persons who had contracted disease *down the river*. September 12, after a violent rain-storm, era became epidemic. Those who most suffered were Irish emi- who had recently arrived in the country. The report of Drs. G Pollock, and Draine is most exhaustive, and contains much illustra matter.

Dr. C. H. Ohr reports that at Cumberland, Md., "the first ca in the person of a canal-boatman on the Chesapeake and Ohio about the middle of July. He had come from Williamsport, whe cholera was raging with considerable violence. He lay out o "green," and died the next morning. The next case occurred abo weeks later, also imported. The subject was a boatman from W port. He lay sick in a green grocery, kept by a man named H recovered. On the 6th of August, six or seven days from the this boatman's arrival, a little girl living with Hall died. Hall d the 7th. On the same day a boat-builder named Cooter was take the disease, and died in nine hours. He had been at Hall's the fore. Meantime several deaths had occurred in the immediate borhood of Hall's grocery. On the 8th Kennedy and several o ily were attacked. They lived fifty yards from Hall's, and there. On the night of the 8th, Hazel Beall, a watchman, was He had been at Hall's. On the 12th, Mrs. Beall was attacked. house was about a mile from Hall's, and near Cooter's. Four of children were attacked successively.

"Some of the children were taken to Mrs. Simpkins's, an adjoining Mrs. Simpkins and her child died. On the 10th or 11th Mrs. Beall went to the house of Hazel Beall, who was still living assisted in nursing. She was attacked, went home, and died 13th. Her husband and two children were attacked, and died 19th. Nelson Beall lived about a mile southeast of Hazel Be out of town. No person in the neighborhood of Nelson Beall's his house, and none suffered from the disease. On the 18th was attacked. He had been a day and night at Hazel Beall's lived three-quarters of a mile east of Hall's, and a greater distance east from Beall's. His mother and three children of his brothe attacked successively. No other persons in that neighborhood h disease except two mulatto girls named Cole, who had assisted in care of this family. From the 6th to the 18th a number of occurred along Green street, in which was Hall's grocery; some different parts of Mechanic street, in which Cooter and Haz lived; some in other places, said to have been from cholera mor the 19th there were thirteen victims. The town became alarmed (three thousand) fled; and it became impossible to trace the cu cable features of the disease further. Hall's grocery was a lo old one-story frame building, the base about three feet below th ment. It was kept for the retail of cakes, candy, liquors, potato bage, cod-fish, &c. Much of the cod-fish was rotten. It was a boatmen, loafers, white and black—of strong odors. It stood corner of Green street, where Will's Creek joins the Potomac favorable a place for the incubation of pestilence as could be de The place had been healthy till the 1st of August, though the been dry, hot, and stagnant."

The epidemic of 1854 was not confined to the North American tinent, for we find it recorded that, from May 14 to June 14, tw sand eight hundred and seven cholera deaths occurred on the of Barbados.

1 June it was reported that cholera was raging to a fearful extent
he island of Jamaica, and that the epidemic had reached the city of
ico, there being at that city, in one day, over two hundred deaths,
ng others the celebrated prima donna, Madame Sontag.
r. Stephen Smith, in the editorial to which we have already referred,
arks: "Along all the great routes of travel, it (the cholera) appeared
ng the summer-months, but without any definite law of progres-
, being governed apparently by the temperature of the weather,
ourse of emigrants, and the condition of towns where they took up
r residence.
From the large cities, located upon the great thoroughfares, the
emic spread widely in every direction, but it principally followed in
train of emigration, and thus reached the most remote settlements
ie West."

CHAPTER VII.

EPIDEMIC WHICH REACHED NORTH AMERICA IN 18[illegible] 1866.

This epidemic came out from India by way of the Red Sea to th[illegible] iterranean; and we have purposely delayed consideration of the *[illegible] route*, in order to give all its peculiarities in one view. The time [illegible] feast of sacrifices at Mecca varies by eleven days each year, as [illegible] hammedan months are lunar, of twenty-eight days each; so tha[illegible] course of fifteen years the festival will have happened in every [illegible] in the year, and every season, viz, spring, summer, fall, and winte[illegible] the Mecca festivals always occurred simultaneously with or short[illegible] the Hindoo fairs, cholera would be conveyed to Europe by way [illegible] Red Sea almost every year. As it is, the disease is carried to Me[illegible] occasionally, while it never breaks out there spontaneously. In [illegible] showed itself in a few cases in the early days of the assemblag[illegible] was declared by the Arabs to have been brought by pilgrims fro[illegible] dia; but it was not until the whole multitude had gathered [illegible] reached its height. Its virulence became at length so great tha[illegible] numbers computed to have fallen victims were many thousands. [illegible] governors of Mecca and Jedda, the pasha who accompanied the [illegible] caravan, and many other people of distinction, were swept away. [illegible] dead were buried in trenches or left without sepulcher. The d[illegible] followed the returning pilgrims up the Red Sea to Suez, and from th[illegible] Cairo and Alexandria. When it was carried into the Mediterranea[illegible] results became so mixed up with those of the epidemic which had a[illegible] by way of Russia, that its course has never been properly traced. [illegible] tenant Wellstadt, (see *Travels in Arabia: London*, 1838,) who spe[illegible] years in the Red Sea, about this time, in English government surv[illegible] ships, found the stopping-places of the pilgrim-boats covered w[illegible] bodies and graves.

The following sketch is condensed from his work:

"Jedda is the port of Mecca, and all the pilgrims who come by [illegible] land there. Its streets are crowded with Turks, Egyptians, A[illegible] Persians, Affghans, Algerines, people from Tunis and Tripoli, H[illegible] Nubians, Abyssinians, and negroes of every shade. Crowds o[illegible] Hindoos litter the streets like dogs; they have performed their p[illegible] age to Mecca, but are destitute of means to return home. The l[illegible] consul is often obliged to give six thousand free passages on m[illegible] vessels which sail for Bombay every autumn. Yet hundreds an[illegible] sands of families live in the streets until they can obtain pass[illegible] although small brigs of only 200 tons have carried as many as t[illegible] dred and seventy persons. In 1831, Jedda had 10,000 tons of sh[illegible] and as much more in large boats, engaged in this pilgrim trade, an[illegible] collected together a more motley assemblage of human beings tha[illegible] be found on any other spot on the globe. Twenty thousand cam[illegible] Egypt alone; one hundred and twenty boats were employed in co[illegible] those from Turkey and the Barbary States, through Suez to Jedd[illegible] pilgrims from Abyssinia, Nubia, and the interior of Africa cross[illegible] Red Sea, from the ports of Cossier, Suakin, and Massuah; four t[illegible] sand came from the Persian Gulf, principally from Muscat, Bush[illegible]

(ASIA.)

MAP by J. C. PETERS of the Red Sea Route, followed in several epidemics.


PIRE
BERIA
CHINESE
EMPIRE
TIBET
BURMAH
SIAM
Bay of
Bengal
Ceylon
Singapore


PIRE
BERIA
CHINESE
EMPIRE
TIBET
BURMAH
Bay of
Bengal
SIAM

orah; two thousand came from Malay; three thousand from Mocha Southern Arabia. Besides all these, six great caravans arrived: from Cairo and Suez; another from Damascus, Syria, and Asia r; a third from Bassorah; a fourth from Bushire, across the Per- Gulf to Bahrein, and thence through Central Arabia; a fifth from at; and the sixth from Yemen. The cholera of 1829 was rightly osed by the Arabs of Jedda to have been brought up by the Hin- from India; but it was not until the whole multitude had assembled ecca that it reached its utmost violence. Over sixty thousand pil- s died, and among them the governors of Mecca and Jedda, the a of the Persian caravan, and many people of distinction. The were thrown by hundreds into large pits, and the road from Mecca dda was strewn with the dead and dying for weeks. The disease wed the pilgrims in their return passage up and down the Red Sea, notably so to Yembo, Suez, and Cairo, which were attacked succes- y, as the pilgrims arrived at them."

regard to the next epidemic, Macnamara, p. 10, quotes Rigler, who s that in May, 1846, cholera (which was carried over from Bombay) ed itself at Aden and Mocha, near the mouth of the Red Sea, and dda which is the port of Mecca. Fortunately the celebration of the ban Bairan did not then take place, or there can be little doubt that era would have at once spread to Mecca, as it did later in the year, n the devotees crowded there in November. Dr. Verollet states it was also brought down from Persia in 1847 by the great Damas- car avan, which picked up the disease at Meshed Hossein and Meshed He also assures us that it had been carried south from Bolkhara entral Asia to Great Meshed by pilgrims, and from there to Teheran, ascus, Meshed Hossein and Ali, down to Mecca, occupying ten ths in the trip. Fifteen thousand pilgrims died at Mecca in 1847. appeared in Mecca and Medina in April, 1848, and was carried by returning pilgrims to Egypt, and reached the fair at Tantah between and Alexandria, quickly destroying three thousand there, besides mitting great ravages over the whole country.

Olympe Audouards, "*Les Mysteres de l'Egypte Devoiles*," 12th ion, Paris, 1866, p. 251, will be found a description of the most hor- of all festivals, which takes place at Tantah in June every year, e tomb of Said el Bedoui, who had a great reputation for the cure terility. All barren women have the privilege of going to this as- blage, where from two to six hundred thousand persons are said to gregate. The scenes of licentiousness exceed all ordinary credence; the cures effected are stated to be numberless. All the most obscene tices of the ancient heathen worship are there rivaled. The re- s of this outbreak of cholera were also united on the Mediterranean those which had come by way of Russia, Turkey, and Germany, in

1850 cholera again broke out in Egypt and along the whole Afri- coast of the Mediterranean. In 1852, Egypt, Malta, and the Ionian nds were once more under its influence. In 1855 it was in Asia or and Egypt, carried down there from the west by the outbreak in Crimea and other places, and the Damascus caravan was attacked on way to Mecca. During 1858 many towns along the coast of the Red were again subjected to the scourge. It also prevailed at Mecca, ea, Hodeida, Mocha, and Aden, and at or near the mouth of the Red , to which it was continually brought by pilgrims. From these places as, as usual, carried down the east coast of Africa to Zanzibar, from nce place pilgrims and slave-traders also came to Mecca. It also

crossed the Red Sea into Abyssinia, and was carried down to C... Africa by slave-traders and others. In 1859 it was reproduced at M... and the havoc in the returning Damascus caravan was again very ... From 1851 to 1861, inclusive, there were twenty-one thousand ack... edged deaths from cholera in Bombay. Of these, four thousa... curred in 1851; three thousand three hundred in 1854; two thou... one hundred in 1856; two thousand three hundred in 1859; and ... other years had from one thousand one hundred to one thousand ... hundred each, except 1858, in which only one hundred and five ... recorded. Macnamara says, p. 185, "We find in the history of th... ease in Bombay evidence of a source quite sufficient to reproduce ... those places which are in constant communication with it." Fre... it was carried unobtrusively by the native boats and sailing-vessels ... which nobody cared, and rarely by the large well-equipped steam... except at the time of the Mecca festivals. Hence Bombay long ... the suspicion of exporting the disease.

In 1864, it appeared at Punderpoor, below Bombay, among th... grims, and at the fair in Kandeish, above it, and soon became ep... among the native population in Bombay. The year 1865 was a ... twelfth-year festival period, and eighty-four thousand died of c... in the Bombay presidency alone. Macnamara says, (p. 203.) "w... evidence of the disease quickly extending its influence from Bo... the Red Sea. Early in 1865 it was at Makalla, on the South A... coast; at Aden, near the mouth of the Red Sea; and at Mocha, ... side and above it." From Dr. Buez's account—see *Mission au li* (the province of Arabia in which Mecca and Jeddah are situated. ... 1873, p. 74—cholera was at Makalla as early as February, 1865. A ... sel stopped there and sailed with four hundred pilgrims; on the ... day out cholera appeared, with five or six deaths at first, and th... deaths in two days; but none for three days before arrival at Je... from whence the rest of the pilgrims departed quickly for Mecca. ... steamers Persia and North Wind, which stopped at Makalla, l... hundred and forty-three pilgrims and sailors by cholera before th... rived at Jeddah. Another vessel from India lost twenty-nine; a... twenty; the Ruby, from Singapore, lost ninety out of five hundre... grims. In all, forty-one vessels arrived at Jeddah from infected p... some with cholera on board.

Dr. Said Bukt, of India, and a member of the local council of M... in 1865, shrewdly says: "The disease may have come first w... Persia and North Wind, but who can say positively, when thos... are coming and going?"

Jeddah is largely concerned in the slave-trade, mainly with Abys... but somewhat with Muscat and Zanzibar. The slaves have to be ... at night to escape the observation of the foreign consuls, and ... thorities and ship-captains are familiar with every device for ... inquisitive inquirers. It is estimated that thirty thousand pilg... victims to cholera at Jeddah and Mecca in May, 1865. From M... to June 10, fifteen thousand pilgrims arrived at Suez in ten ... from Jeddah and Mecca. It was officially declared that the he... the passengers was perfect, and that only six or eight had died ... non-contagious diseases, on board of each vessel; and free pratiq... allowed; but it afterward came out that the Sidney, an English ste... had lost more than one hundred out of two thousand pass... (Buez, p. 72.) On May 23, one of M. Lesseps's physicians observed ... in a convoy of pilgrims from Suez to Alexandria. By the ... May, fifteen thousand pilgrims were encamped near Alexandr...

English Government Map

Showing the Seaports in the Mediterranean Basin Affected by Cholera *in 1865 as well as the course of the disease from Mecca to Alexandria and its radiation thence.*



neighboring Arabs fraternized with them and contracted cholera. June 1, the first case in Alexandria was reported, in the per- of one who had lived in communication with the pilgrims. If any ths occurred among the pilgrims they were concealed. From the 5th he 11th of June the disease became decided, always among those had been in contact with the pilgrims; but the physicians of sanitary corps pronounced all the cases to be pernicious algid fever ed with cholerine and sporadic cholera, (p. 73.) It was not until e 11 that the health-bills of vessels from Alexandria contained the that cholera was present there. In the course of two months estroyed four thousand in Alexandria; and up to July 23, sixty sand died in Egypt. A panic ensued in Alexandria, and thirty-five sand persons fled from it to Beyrout, Cyprus, Malta, Smyrna, Con- tinople, Trieste, Ancona, and Marseilles. The first infected vessel for thampton, England, left Alexandria before cholera was acknowledged re, and it was not until after the lapse of seven years that Dr. Nettin leliff obtained indubitable evidence of its presence. It was claimed t it had been blown to Southampton by the winds, or sprang up from ie occult epidemic influence before it broke out in Alexandria.

We have seen how cholera is brought to Alexandria from Mecca, in East; we will now show how it is distributed along the Mediterra- n to the West. Almost all the English, French, Austrian, and Ital- steamships which sail on the Mediterranean carry pilgrims to Al- ndria from Morocco, Algiers, Tunis, Tripoli, Malta, Turkey, South- Russia, Asia Minor, &c., in time to partake in the festivities of the *rban Bairam* at Mecca; for this trade yields considerable profit at le cost. In 1863, as many as ten thousand pilgrims were conveyed British ships alone between Alexandria and one or the other ports Southern and Western Africa. We will record the experience of one amer stopping at Tangier, opposite Gibraltar: "Crowds of the ky tents of the Hadji, or pilgrims, were seen upon the beach. The t day, from dawn to sunset, large boat-loads were poured on board, h their bags of millet, cracked wheat, little cooking-stoves, charcoal, l their water-bags, to the number of two thousand persons. The ht came on boisterously; the skies poured down torrents of rain; burdened vessel plunged among the waves, shipping many heavy s, until all were drenched and soaked, and their provisions damaged. ove the howlings of the storm arose the piteous cries of the pilgrims, the great seas broke over them.

"It is a point of religion for these devotees to carry no change of rai- nt with them, and besides the filth of their wet and unchanged gar- nts, there was soon added the ordure of two thousand men, women, d children kept closely packed together on deck for a fortnight, with thing provided for their relief but an extemporized stage of planks jecting from the vessel's side, upon which few landsmen could ven- e, even in moderately calm weather. The constant wash of the rain d sea alone carried away much of the filth, which otherwise would ve been unbearable. Small-pox broke out, and several deaths oc- rred before arrival at Malta, but passengers and sailors combined to ceive the captain, from fear that he would report it and have his ship arantined. The deaths are comparatively few on the voyage east, but the return-passage, when all are exhausted and worn out, as many one-third have been known to die. Then their companions push em into the sea the moment they cease to breathe, if they can do so observed; or else cover over their bodies and sit upon them, like gs, until a convenient opportunity occurs.

"Every evening, when the weather permitted, prayers were s... short passages from the Koran recited. First, the pilgrims s... shod, bowing together, then dropping upon their knees, pressed ... foreheads upon the deck in such lowly attitudes that it was diffi... resist the impression that every creature of them was most revere... humbling himself in the dust before his Creator. Finally, one eve... when the sun was set, every face was found intently turned in one ... rection, and the heavens were searched by keenly peering eyes: ... a slight thread-like arc of faintest silvery light marked the appeara... of the new moon, with the arrival of which the '*Kurban Bairam*,' *feast of sacrifices*, begins. Shouts, clapping of hands, and the gleam... brightness of every eye announced that all had seen the sight, w... marks the anniversary of the time when Abraham attempted to ... up Isaac, or, as the Mahomedans believe, his first-born, Ishmael, ... great progenitor; and when a ram was miraculously supplied and ... rificed in his stead. It is the commemoration of this event which dr... such crowds to Mecca every year, and notably every twelfth year; for ... Mecca is situated the well Zem Zem, which Hagar and Ishmael fo... when fainting with thirst in the wilderness, and thus saved the lives of ... founders of the Arab and Mahomedan races. Abraham, it is ... claimed, paid annual visits to Hagar at Mecca, on this anniversary, ... to the time of her death, notwithstanding the reluctance and jeal... of Sarah."

Cholera was brought to Marseilles about June 11, 1865, by some of t... pilgrim-steamers, and acknowledged in Paris, with sixteen deaths in J... thirty in July, one hundred and twenty-five in August, two hundred ... September, four thousand four hundred and sixty-six in October, one t... sand two hundred and eighteen in November, and seven hundred and s... eight in December, 1865. The Atalanta steamed from Havre on O... ber 12, with fifty-two cabin and five hundred and fifty-two steerage pa... sengers, all of whom had been in Paris, where cholera prevailed. S... cases had also occurred at the Havre emigrant-hotels, but were c... unknown or suppressed by the authorities. The Atalanta had one h... dred and two cases and twenty-three deaths before arrival at New Y... and the Herrman arrived November 16, with several cases. From t... quarantine-ship Falcon it was carried up to Ward's Island by a nur... and in eleven days thirty-one attacks and eighteen deaths occur... Thus by steamer and rail cholera was carried from Bombay to Ward's Island within nine months by an unbroken chain of connection.

Singularly enough, strong corroboration of the correctness of the ab... account is supplied by Dr. John Parkin in his work on Epidemics (London, 1873,) the whole of which seems to have been written for ... express purpose of disproving it. On page 187 we read: "That ch... was not imported into Mecca, but arose there spontaneously, may ... inferred from the following facts: The ceremonies do not last ... (eight) days; and the principal one, the Kurban Bairam, or feast of sa... rifice, took place on the 4th of May." But the cholera had appeared ... early as February and March at Makalla, a port, not on the Red S... but on the south coast of Arabia, from whence it could not only ... but actually was carried up to Jeddah and Mecca by many vessels.

"It was here (Makalla) that some pilgrims from Singapore were a... tacked on their arrival in two sailing [steam] vessels, the Persia and N... Wind." But Buez (p. 75) writes: "The consul-general of Holland ... Singapore says cholera raged at Java and Singapore in 1864. ... Moeris and Ruby from Singapore (p. 70) arrived at Makalla bef... the Persia and North Wind, the first having lost twenty-nine, the ...

city, by cholera on the trips. Of course we can believe (Parkin, p.) "that the disease broke out on the Persia and North Wind after ching at Makalla. The disease was prevailing at the same time at deida, another port in the Red Sea," but not on the Arabian Sea, Makalla. Dr. Parkin seems to have known nothing then of the hty-four thousand deaths in the presidency of Bombay, nor of the ival of vessels at Makalla from Bombay, as well as Singapore, with lera before the arrival of the Persia and North Wind, but triumph-ly, although erroneously, asserts: "We thus have proof that the cause ductive of the epidemic cholera was in operation in this part of the rld before the arrival of any pilgrims. That cause was in operation other and adjacent towns, and the probability is that Mecca was ught under the influence of the same malign agency, although it ght not manifest" [which it did not until there was an abundance of e and opportunity for it to be conveyed there] "its effects until a r period. If so, there can be no difficulty in accounting for the out-ak" at [Mecca.] "The disease arose there spontaneously, [?] the same in other places, and the pilgrims were attacked in common with the er inhabitants, possibly before, being more predisposed than the lat-for a variety of reasons. The pilgrims fled when the disease oke out, (at Mecca,) and, as a matter of course, many of them took e seeds [!] of it with them. The mortality was great among the pilgrims the road from Mecca to Jeddah. The survivors arrived at Jeddah May 10, but the epidemic was already prevailing there, many of the ropean sailors and lascars having died previously, and also some of e Turkish soldiers in garrison. The disease, consequently, was not car-d into Jeddah by the pilgrims [from Mecca, simply because they had ought it there before they went to Mecca.] "The same result, no doubt, curred on other roads taken by the pilgrims, but no account has en transmitted to us (Dr. Parkin) of these occurrences." [But every her student of the conveyance of cholera is familiar with them.] The first ship, with one thousand five hundred passengers, arrived Suez on May 19. The Egyptian government had taken the precau-n (p. 189) to send medical men to Suez to examine the pilgrims on eir arrival, and they reported that no indications of cholera existed nong them. Some deaths had occurred on board during the voyage, but e cause was not known, [or rather was concealed.] "We (Dr. Parkin) ly learned that the captain and his wife were both attacked, and died cholera, [and these cases could not be denied.] After this, we (Dr. arkin) hear nothing more of the pilgrims, not a single case having en reported among the thousands that arrived in Egypt. Had there en any, we (Dr. Parkin) would most assuredly have been informed of e fact. [?] On June 2 there was a (fatal) case of cholera in a resi-nt of Alexandria. By the end of the month (June) nearly all the wns in the delta of the Nile, [upon which twelve thousand pilgrims om Mecca had been precipitated,] had been attacked, viz, Cairo, setta, Damietta, &c. As the epidemic thus broke out in Egypt *so* on after the arrival of the pilgrims, the contagionists of course affirmed hat the germs of the disease were brought there by them."

But Dr. Parkin forgets that he has already proved that the pestilence as at Jeddah, Hodeida, Mocha, Aden, Loheia, and other places on the ed Sea, before the return of the pilgrims from Mecca; brought there, ot only by the steamships, (not sailing-vessels,) Persia and North Wind, ut by forty other boats. Hence it could have been conveyed from Jeddah nd these other and many more places, on the route from Bombay upward o Suez, before the return of the pilgrims; for the ordinary commerce of

the world did not stop, but was rather increased in consequence of the wants and tastes of the pilgrims. Many traders and idlers besides slave-merchants go no farther than Jeddah, and the nearest market for their wares. They go for lucre and pleasure, and care little for the mummeries of the Mahomedan zealots. Dr. Parkin does not allude to the conveyance of cholera from Persia in various other ways. The so-called Syrian caravan starts from Constantinople, passes down the Asia Minor to Damascus, and from there to Medina and Mecca. The principal Persian caravan comes from Teheran, Koom, &c., to Bagdad Hillah, and thence also down to Medina and Mecca. While only a few thousand come by boats and the sea, nearly one hundred and fifty thousand come by land to Mecca, with the Egyptian, Syrian, Bagdad, and other caravans. On page 191 he says: "The epidemic has pursued in 1865 the route it has invariably followed, namely, from south to north. We (Dr. Parkin) never hear of its following the opposite course!" It would be impossible to express a more erroneous view of the travels of cholera than is conveyed in these few words. Dr. P. continues: "Malta was attacked June 20, quarantine having been established on the 14th." But he has admitted that the first cases occurred in Alexandria on the 2d; and adds, "Previously to this, however, between June 1 and 14, thirteen steamships arrived at Malta from Alexandria, the majority laden with pilgrims for other places while a certain small number landed at Malta;" showing that the disease was imported before quarantine was established. P. 192: "The epidemic commenced at Marseilles in the beginning of June, and was ascribed to the arrival of the Stella, with sixty-five pilgrims bound for Algiers. The infected" (p. 193,) therefore, could not have been conveyed to Marseilles by the pilgrims!! It spread through the south of France, and was acknowledged at Paris October 13," *i. e.*, several months after its actual outbreak.

P. 194: The first place attacked in Spain was Valencia, July 3, on the east coast; "which town could have had no direct communication with Alexandria, or other infected port!" But Macnamara (p. 212) and Constantinople report say: "The first case was a Frenchman, who arrived at Valencia from Alexandria via Marseilles. It next spread to the inmates of the house in which he died; and, from this and other cases, did not cease until eleven thousand inhabitants were attacked, of whom five thousand one hundred died." Dr. P. also says "it could not have been conveyed to Toulon," although so near Marseilles; but the first case was in an arrival from that place.

Dr. Parkin's account of the outbreak in Southampton is equally erroneous. On page 196 he says: "There were no cases of cholera on board the regular steamers at the time of their arrival at Southampton; and it does not appear that any one landed suffering from diarrhœa." Dr. Wiblin, the health-officer, was deceived, and asserted, "from the most careful inquiries, he was unable to ascertain that any cases of cholera or diarrhœa were landed at the port of Southampton." However, Professor Parkes, who was sent by the English government, says "that, during June, July, August, and September, there can be no doubt that steamers ran into Southampton after having had cases of cholera on two occasions, and of diarrhœa in three, on board during the voyage from Alexandria. The crews of these vessels dispersed over Southampton and its neghborhood. Dr. Miller, the surgeon of the Ellora, had thirty-one cases of acknowledged choleraic diarrhœa on board; and as many more were afterward found to have concealed their condition in order to escape detention at quarantine. One of the crew died of cholera in his own house in Southampton, but only after

e son, to whom he had given it, had succumbed. Hence, although disease was imported, the first fatal case occurred in a resident. third fatal case was a laborer employed on the mud-engine, but who d in a house with three sets of lodgers; the only privy being also mon to seamen, the frequenters of the theatre and brothels only a yards off. Choleraic diarrhœa prevailed largely in Southampton, several of the earliest cases of fatal cholera were in the wives of men who had worked in the repair-yard where ele ven Alexandria sels, among them the Ellora, had been overhauled July 11th. There also an outbreak of severe diarrhœa at this yard, which lasted till middle of October. No such extended outburst had ever before been wn during the seventeen years that the yard had been open. (Mr. on's report for 1865, p. 428.) In Southampton the fatal cases were y distantly connected together by long lines of choleraic diarrhœa. ne time afterward it was discovered that the ship Poonah had arrived, e 10, having lost a man from cholera the previous day. As the ase was not yet reported at Alexandria, the crew and passengers e landed without detention. It is stated that twenty-three Alexria vessels arrived before cholera fairly broke out in Southampton. Much light was thrown on choleraic diarrhœa at Malta during the demic of 1865 by Drs. Adams and Welch, (*British Army Medical orts, vol.* 6.) There had been no prevalence of bowel-complaints till er the arrival of the pilgrim-ships from Alexandria. Then three ms commenced to prevail:

st. What appeared to be the common, ordinary summer diarrhœa, rked by pains in the bowels, foul tongue, and numerous bilious stools. is seemed to be caused by the hot weather, imprudence in diet, spoiled it, and bad habits, but was easily controlled.

d. A new form of diarrhœa, with painless, watery purging and vomg with exhaustion. It occurred in every form of intensity, and when ere was clearly choleraic diarrhœa. It could not be checked by atment, but never passed a certain point, or became fatal or malig-nt.

d. There was another form, which merely seemed an intensification the second variety, but so completely intractable that in sixty-one es where every possible attempt was made to check it, in none did succeed. It was invariably followed by the full development of olera.

The second variety showed no tendency to run into fatal cholera, with lapse, while the third form could not be prevented from so doing. s. Adams and Welch say it may be fairly questioned whether a single e of it was prevented from developing itself into cholera by treatnt.

Dr. Parkin says: "With the exception of Paris and Southampton, this ms to have been the boundary of cholera northwards in 1865, with e reservation. The disease broke out at Altenburg, about twenty-ir miles from Leipsic, but did not extend beyond. (!) Perhaps the ntagionists will be kind enough to inform us [Dr. Parkin] why so inious a disease was confined to this single spot, the inhabitants not ving been placed in quarantine, and no wall having been built around e town." The answer is very easy. It did extend beyond Altenburg, d very promptly; and formed a zone of cholera through which the ussian armies had to pass the next year on their way down towards ustria, with the most disastrous consequences; for the disease folwed them into Bohemia and Bavaria, and returned with them, after eir wonderful six-weeks' campaign, into Northern Germany, to which

it had also come, over the well-known and oft-traveled route from Odessa to Kief, and Poland, and along the Vistula and Oder to the Baltic. The whole story is a thrice-told tale, but has to be repeated for the sake, not only of Dr. Parkin, but of many other polemists. On June 28, 1865, when neither cholera nor premonitory diarrhœa existed at Constantinople, an Ottoman frigate, the *Muchbiri Surur*, arrived in that port, having left Alexandria on the 21st. She landed twenty-one men suffering from cholera, and the outbreak soon commenced. From Constantinople it was carried due east across the Black Sea to Trebizond, in the southeast corner, down to Erzeroum, by a party of laborers arriving from Constantinople, and then was impelled towards Persia, in the line of the pilgrims to Damascus, Bagdad, and Mecca.

No cholera existed in Odessa before the middle of July, when cases were taken into the lazaretto from the ship Concentrino and* vessels arriving from Constantinople, and its development was observed with great exactness, which had not often been previously the case at Odessa. A custom-house agent, Gonline, serving in the lazaretto was attacked, carried home, and from there to the hospital, where he died. His wife, son, and servant were next attacked. A similar train of consequences followed in another case. The wife of a German workman left Odessa on August 16 for Altenburg, in Saxony, with her child suffering from diarrhœa. In nine days the child became worse; the mother being in perfect health on the 27th, when she was attacked, and died on the 29th. Next the child died, and a sister-in-law on the 30th. Then an epidemic commenced, which killed 2 per cent. of the Altenburgers. The family of a workman, who had died at Altenburg on September 13, imported the disease into Werdau, and an outburst commenced in the heart of Europe. We believe we are in possession of a large majority of all the official reports which have been published on the epidemics of 1865, 1866, and 1867 in Germany. From Gunther's report (Leipsic, 1866,) we learn that cholera broke out in twenty-six places in Saxony in 1865. His conclusions are that cholera was first imported into Altenburg from Odessa, and that in the majority of towns in which the disease subsequently occurred, a communication between the initial cases and infected places and persons was proved. From L. Pfeiffer's reports, (Weimar, Munich, and Jena, 1868 and 1871,) we learn that in 1865 importation was proved in 60 per cent. of all the cases. In 1866, when cholera had been spread silently during the winter, it could only be traced in 36 per cent.; but that accounted for eighty-four towns and villages, and the individual cases amounted to hundreds. At the outbreak of the Austro-Prussian war, no cases of cholera had been reported in the Prussian army in Saxony up to June 4, 1866. The Saxons, with true patriotism, attributed their cholera, which had been in existence for nearly a year, from the Odessa-Altenburg importation in 1865, to the Prussians who came in 1866; declaring that the Prussians brought it down from Konigsberg, Stettin, and other places on the Baltic. But all accounts agree that the Prussian army became affected in Saxony, and carried the infection down into Bohemia and Bavaria, where they handed it over to the Austrians and Bavarians. It returned over the same infected places at the end of the short war, and then the disease assumed its largest proportions; extending from the borders of Russia to the Rhine, surging up to the Baltic again, involving Holland, and spreading to England. From Liverpool it was carried over to Dublin in such a visible way, and all the points in the chain of connec-

* Dr. Fr. Ilisch's Untersuchungen über Entstehung und Verbüttung der Cholera. St. Petersburg, 1866.

were so clear back to India, that Dr. Houghton was obliged to ex-
n, "If we possessed the requisite knowledge, the disease could always
raced backwards in lineal descent to its origin in some poor Hindoo
he banks of the Ganges, as certainly as the pedigree of a horse or
of repute can be followed to his remote ancestors."

ODESSA-ALTENBURG EPIDEMIC OF 1865.

his small epidemic, which was destined to bear such terrible fruits
866, was confined to a space of thirty-eight square miles, in the most
ely populated province of Saxony, near Leipsic. According to
ther's official report, (Leipsic, 1866,) one death occurred in August,
in September, one hundred and seventy-five in October, one hundred
sixty-eight in November, and eighty-four in December, when winter
ked the outbreak. All the streams in the infected neighborhood
lly empty in the river Elbe. The drinking-water of Altenburg was
good; it often became turbid, and was loaded with lime-salts. The
n had thirteen hundred and fifty houses and eighteen thousand in-
itants. The dwellings of the poorer classes had small court-yards,
large dung-heaps, and the drainage from them generally ran under
houses. The privies were usually small boxes placed over one edge of
dung-heaps. The little creek which runs through the town was
led with offensive impurities.

he first death in Altenburg was a woman who had traveled nine
s and nights from Odessa, on August 29. The little creek, be-
spoken of, ran just before her house. The second case was in a
bbing-woman living some distance off, on the bank of this offen-
stream; the third, was a woman in the same house, whose two
dren were sent to a sister's at some distance, where one of them
sickened and died. Then one of the sister's children was seized
died; next the sister and her husband, who both recovered. Then
more cases took place in the second infected house, but recovered.
succeeding two cases occurred near the railroad-bridge under which
foul creek flowed. Next, three cases were brought to the hospital
n another house similarly situated. Finally there were seventy
ths in forty-five houses, viz, one each in twenty-eight houses, two each
ight houses, three in four, four in one, and five deaths each in
e houses. At the end of the outbreak, twenty-nine cases and sixteen
ths also occurred in the almshouse. Soon after the commencement
he epidemic a very large number of mild diarrhœas were noticed, as
e lateness of the season, or other causes, or the small quantity of
poison which had been imported merely sufficed to produce chol-
c diarrhœa, and only occasionally fully developed cholera. The
t affected village, Rasephas, was near by, and the disease was intro-
ed by a market-woman from Altenburg, who died September 13. In
e days her husband was attacked and recovered; in six days more
daughter died in fourteen hours; two days after, the mother-in-law;
n a son was seized and recovered; a daughter who had been sent
y for safety was attacked and sent to the hospital, where she died
the 26th; on the 27th the woman who washed the bodies; on the
e day, the nurse, who also acted as washerwoman; and on the 28th,
cowherd of the family. Six houses, out of the thirty in the village,
e involved, with one death each; two in two, and five in one house.
next place where it appeared was Werdau, with seven hundred and
enty-four houses, and ten thousand five hundred inhabitants. The
ial case, on September 17, was the infant of a man who had died of

cholera on September 12, in Altenburg. The second case was the washerwoman, living three doors off, who washed the soiled clothes of the dead man, which the widow had brought with her. The next two deaths occurred in a house to which other children of the widow were sent; and the following three were children of her sister-in-law. The next two cases could not be traced to exposure to the disease, but, as some of the fatal cases had succumbed without any medical help or report to the authorities, the disease may have been silently diffused in various ways. From the first three infected houses the disorder spread, until one hundred and fifty houses, with two hundred and sixty deaths, were involved, viz: one death each in ninety-six houses, two in twenty-five, three in eighteen, four in four, five in three, seven in two, and eight in one house only. Here in the heart of civilized Saxony, in a town with over ten thousand inhabitants, we find the widow of a man, lately dead of cholera, coming from Altenburg with her deceased husband's soiled clothing, which she hands over to a washerwoman, who dies; her one infant quickly succumbs without medical assistance or the knowledge of the authorities; her other infected children are sent to her neighbor's and sister's houses and there start epidemics. Seven deaths are immediately traced to this careless widow, yet she had not a vestige of the disease that was reported. At the next town, Zwickau, with one thousand two hundred houses and twenty-two thousand five hundred inhabitants, the so-called first case occurred in the person of a laborer's daughter, aged twelve years, on the outskirts of the town, near the railroad station, where no importation could be traced without more trouble and intelligence than was expended upon the matter. But it was soon discovered that her younger brother had died five days before of the same affection. The house was light, dry, and airy; the privy was a primitive board affair over the cattle dung-heap; but the most careful investigation elicited no exposure, except, doubtless, at the railroad, and no imprudence in diet or conduct was discovered. These cases were supposed to be, undoubtedly, spontaneous in their origin. In fact, the origin of none of the cases in the town was discovered; for, singularly enough, the initial cases all happened among children from nine to eleven years of age and upward, while their mothers and fathers became afterward affected. In the fifth place attacked, Marienthal, with one hundred and forty-six houses and one thousand and seven hundred inhabitants, near Zwickau and Werdau and in constant communication with them, the importation of the disease was not detected; but there were only five fatal cases, each in a separate house. The sixth town in order, Glauchau, with one thousand three hundred and seventy-five houses and nineteen thousand two hundred and ninety-six inhabitants, six miles from Zwickau, and ten from Altenburg, cholerine commenced in September, and was benign and tractable in October and November, but gradually increased in severity, until the first fatal case occurred, on November 27. Some weeks previously the sister of this patient had come sick from Altenburg, and had cholerine for two and a half days, when she went on to Dresden; and six days before his death he was also visited by a friend from infected Werdau. During the next three days three new cases occurred in distant parts of the town, not traced to importation. At this late period of the year, only twenty-seven infected houses, with thirty-two deaths, were recognized, among which there was one death each in twenty-two houses, and two in five houses. The seventh important place which was involved was Elsterberg, on the River Elster, which runs down to Leipzig. It had three hundred and five houses and three thousand five hundred and fifty-seven inhabitants. Cholerine, typhoid fever, and dysentery were preva-

up to November 25, when the first fatal case of cholera occurred; ch could not be traced to importation. A woman living in the same se sent one of her children to a distant relative, where it also died; moved herself with two more children to another distant house, where hree died. The corpse-washer who attended to them also died. Then rooms in the poor-house were set aside for cholera-patients and the hes of all were cleansed and disinfected there. The succeeding cases irred in an adjoining house below it, followed by other cases in the inally affected dwellings. But the disease gained a footing in thir- houses only, with twenty-eight deaths; with one death in each of houses, two in six houses, five in one house, and six in another.

rom these seven towns the disease spread to eighteen small villages. he first, the only fatal case occurred on the banks of a little stream ning down from Altenburg. In the second, it was imported n Altenburg, where a daughter had been attacked but recovered. mother, to whom she brought it, died. In the third village a little had been sent from Altenburg to her grandmother's, from a house hich six had died of cholera. She was attacked on October 3, re- ed home, and recovered; but her grandmother, to whom she had n sent, died. In the fourth hamlet the initial case was one from Al- burg. The fifth place was Leipzig, with eighty-five thousand inhab- its, in which the initial case was a washerwoman; but no connection h any other was traced. In the sixth village the first fatal case was wife of a pack-carrier; but no importation was discovered. In the enth village the first attacked was a railroad-laborer from Altenburg. wife and two children sickened and recovered; while her babe was not cted. In the eighth hamlet the first fatal case was a girl from Wer- , followed by her mother. In the ninth village two fatal cases were orted from Werdau, and the corpse-woman who washed their bodies, the first victim. The second case had shared the bed of a cholera- ient in Werdau until death. In the tenth village importation could not proven. In the eleventh village a woman and her child came from a lera-house in Werdau. They were both attacked and sent back; but ir visit was followed by six cases in their house and the next one. In twelfth village the initial case ate meat from an infected house in rdau, and the corpse-woman also died. In the thirteenth village five es occurred in the poor-house, in which refugees were received. The ther of three of the children who died, recovered. Importation was proven; neither was it in the fourteenth village. In the fifteenth vil- e the outbreak was preceded by cholerine, but the first fatal case was orted from Glauchau; in the sixteenth, from Elsterberg. In the sev- enth no connection was discovered. In the eighteenth there was portation from Glauchau. These were the twenty-three towns and vil- es near or through which the Prussian army had to pass next year, er cholera had recommenced in Altenburg, Zeitz, Weissenfels, Merse- rg, Leipzig, and Halle; all in the immediate neighborhood of Leip- . According to Pfeiffer's official report, (Jena, 1871,) in Halle, which he nearest city to Prussia, there was diarrhœa during the winter, with oleraic diarrhœa and mild cholera. In May there were two deaths. June and July there were sporadic cases in isolated parts of the y, and in August, over the whole town. But Halle attributed her olera to the Prussians, who brought back many sick and wounded th them from Bohemia, among whom diarrhœa and cholerine were mmon. The number of medical men and nurses who were attacked Halle was remarkable, as well as in the stationary Prussian garrison; ile the wounded and returning troops suffered much less. Buildings

with bad privy-arrangements suffered most; next, badly-ventilated houses, and those which were new and damp. Halle is on the river Saale below Merseburg and Leipzig, and seems to have been more affected than either of these cities, from which it receives much drainage, as well as from all the previously-mentioned places; so that water-poisoning seems to have occurred. Three deaths occurred in sixty-six houses, each, four in thirty-eight, five in eighteen, six in nine, eight in four, nine in two, and thirteen and sixteen fatal cases each in one house. The Halle prison had always suffered severely in every epidemic. The cholera-wards were over the privies, and after the first imported case occurred, the second, third, and fourth attacks happened among prisoners; the fifth, sixth, seventh, eighth, and ninth cases were in women who washed the soiled clothes; the tenth was the overseer of the laundry. Finally all discharges and clothes were disinfected and no more cases occurred in the wash-house. All the prison officials escaped. In September, when the disease had almost disappeared, the privies were emptied, and a new outbreak ensued. The water-closets of the officers were separate from those of the prisoners. One of the city sewers passed under the prison, and all the kitchen and privy drains emptied into it, so that the house was often filled with sewer odors. In the lunatic asylum the male wards were affected, but not the female; in 1850 the opposite had been the case. The drainage of the latter had been improved, and better drinking-water had been introduced. The orphan asylum again escaped, as it had in every previous epidemic. It is seated on a hill, all the privies are outside the building. The water is the best in Halle, and imported cases were not present. The contagiousness of the Halle cholera of 1866 is said to have been decided; eight physicians out of sixty-one were affected; three died. The nurses were attacked in numbers. The importation of the disease was accomplished by persons and clothes, especially when the latter had been laid aside for a few days. In Querfurt, near by, there were one hundred and sixteen deaths from cholera. In Naumburg, where the privies and dung-heaps were offensive, and the pump-water bad, the disease spread readily all over the town. The best houses were spared. Disinfection was carried out in the most thorough manner, but did not seem to neutralize the filth and bad water. In the whole of Saxony in 1866, there were six thousand seven hundred and twenty-four deaths from cholera, in three hundred and twenty-nine different places. In Leipzig there were twelve or fifteen massive importations of cholera before a decided outbreak occurred. On June 24 a Prussian troop came from Stettin on the Baltic, with cholera, and put forty sick with it into the hospital. Only one washerwoman and one tavern servant were affected, and then the disease ceased among the troops. The second importation came with Prussian soldiers from Stralsund and Kustrin, near the Elbe. Many were put into the hospital, but only a few cases occurred among the towns-people. Several other times was it brought in July and August, but it was only in the middle of the latter month that the pestilence gained headway. Then, as all the well-appointed barracks were occupied, a regiment of black hussars had to be quartered in dirty parts of the city. Several cases soon occurred among the hussars in one house, from which the disease seemed to spread. The effects of subsequent importations could not be traced among the inhabitants. From June 29 to November 21, one thousand seven hundred and eight deaths occurred. Of these, twenty lived in cellars; two hundred and forty-three on the first floor; eight hundred and fifty-six on the second floor; three hundred and twenty-seven on the third; two hundred and eighty-one on the fourth;

hundred and fifty-eight on the fifth; and fifteen on the sixth story. ight hundred and fifty infected houses, four hundred and ninety-four only one death, one hundred and ninety-five had two each, thirty-eight four, twenty-two had five, two had six, five had seven, three had nine, e had ten, two had eleven, two had fourteen, and one house each had ve, fourteen, sixteen, eighteen, and twenty-eight deaths. One hun- l and forty-six families had three hundred and forty-six deaths, or e than two each. Leipzig had generally escaped cholera; previously disease had only reached it in 1849 and 1850, with three hundred six, and three hundred and twenty deaths respectively. In 1866 era was exported from Leipzig to sixteen towns and villages; and y-one districts out of one hundred and four finally became involved. outbreaks were often traced to diarrhœal cases which did not die. resden had always escaped cholera, but in 1866 it was said by the ens to have been imported by fort laborers from Berlin, and troops n Prussian Pomerania, and again, and more severely, on the return hese troops from Bohemia and Moravia. Notwithstanding the enor- us masses of imported disease, no great outbreak occurred, and only seven deaths. In eight other towns single cases only happened; in e, none, although large numbers of affected troops marched through quartered in them.

rfurt, to the west, with forty thousand inhabitants, had had five lemics, viz, in 1832, 1849, 1850, 1855, and 1357. In 1866 it had two usand six hundred cases. The Erfurters claimed that the city was cted from Berlin and Leipzig, and also seventy-two places in the ghborhood. The first fatal case in Erfurt was a lady from a cholera- se in Berlin. The woman who waited on her died, and the servant helped the latter. Narrow, dirty streets with many privies suf- d most.

otha, like Weimar and Appolda, were attacked in 1866 for the first e. It was imported into Gotha from Erfurt. To Weimar it was ught from Berlin and Leipzig; but among fourteen thousand inhab- its there were only seventy-three deaths. In Appolda, with eight usand inhabitants, two hundred deaths. On page 115, Pfeiffer gives st of cases produced by soiled clothes in various places. In Leipzig y-two laundresses were attacked and twenty died. At various nts in Saxony one thousand two hundred and three died on Sundays, thousand three hundred and thirty-eight on Mondays, one thousand hundred and sixty-seven on Tuesdays, one thousand two hundred l fifty-nine on Wednesdays, one thousand one hundred and ninety- ee on Thursdays, one thousand two hundred and thirty-three on Fri- s, and one thousand one hundred and thirty-six on Saturdays. Sep- ber was the most fatal month.

his dispute between the Prussians and Saxons will doubtless never be tled. In the official report of Dr. Delbrück (Halle, 1867) we learn that re were choleraic diarrhœas for weeks and months before the Prussians ched Halle, and one fatal case in town and another in the prison in y. In July it was well established, and persisted until September 21, en it seemed about to cease, but again broke out and continued up to vember. In July there were twelve deaths; in August, one thousand d eighteen; in September, three hundred and forty-six; in October, e hundred and eighteen, and in November, eleven. In the prison, ong seven hundred persons, there were three hundred and thirty-three es of diarrhœa, seventy-one of violent cholerine, eighty-nine of cholera, d thirty-three deaths. Dr. Delbrüch thinks that the disease was in- sified by the Prussians, but not caused by them alone. On their first

march through they had no cholera, but on their return from Bo[illegible] they had much diarrhœa, and some cholera. The returning troops [illegible] to be saturated; and proof against the infection, while the stay[illegible] garrison and the whole of the medical staff and nurses of the hos[illegible] were heavily attacked. The garrison did guard-duty at the hou[illegible] and prisons, and seemed to convey the disease from one to the [illegible] and to infect the privies of both. Ground-water had no influence. [illegible] the parts of the city supplied with water from the river Saale, [illegible] was much polluted by drainage from the town, suffered most. [illegible] district had separate and better water, and almost escaped until [illegible] ber, when the pipes burst and water was supplied from the filthy [illegible] in consequence of which a severe outbreak occurred. The [illegible] asylum had its own pure water, and escaped as it had in five pre[illegible] epidemics. Men working in mud-scows near the foul water-works [illegible] fered heavily and continuously. One-twentieth of all the houses [illegible] eight-twentieths of all the deaths. In one hundred and thirty[illegible] houses there were five hundred and ten deaths; sixty-six houses [illegible] three deaths each, thirty-eight had four, nine had six, three had [illegible] one had eight, two had nine, one had thirteen, and one had six[illegible] deaths; the rest had two and one death each.

Stettin has been charged with sending cholera down with Prus[illegible] troops into Saxony, and in reality we find from Dr. Goeden's [illegible] report (Stettin, 1867) that the first fatal cases occurred on May 19, [illegible] person of a railroad laborer and his daughter. Next, three soldiers [illegible] attacked. Up to October 9 there were two thousand three hundred [illegible] seventeen cases and one thousand six hundred and eleven deaths [illegible] sixty-five thousand civilians; and by November three hundred and [illegible] seven cases and one hundred and forty-one deaths among the troops, [illegible] bering five thousand. In the suburbs, seven hundred and thirteen [illegible] and four hundred and eighty-four deaths. Laborers and servants [illegible] nineteen hundred cases; hotel and liquor-shop people, forty-one; [illegible] thirty-eight; butchers, eighteen; coachmen, thirty-nine; officials [illegible] policemen, one hundred and fifty-five; sailors, one hundred and [illegible] four; leather-workers, one hundred; tailors, sixty-seven; and men [illegible] seventy-seven. These suffered most heavily. Up to 1866 Stettin [illegible] twelve epidemics of cholera, and less information is afforded by [illegible] any other city except Hamburg. Taking cold was regarded as the [illegible] cipal cause. The first epidemic commenced August 23, 1831, and [illegible] sixteen weeks, with three hundred and ninety-two cases and two hu[illegible] and seventy-five deaths. That of 1832 lasted from September 25 [illegible] vember 10, with one hundred and fifteen deaths. That of 1837 com[illegible] August 10 and lasted ten weeks, with three hundred and fifty d[illegible] That of 1848 lasted twelve weeks, from August 8, with one thousan[illegible] hundred and twenty-two cases and five hundred and ninety-five d[illegible] In 1849 there were one thousand one hundred and sixty-two cases, [illegible] hundred and forty-three deaths, from June 14 to September 27. I[illegible] there were sixty-nine cases in ten weeks, from August 30; in 18[illegible] hundred and eighteen cases in nine weeks, from September 12; in [illegible] one thousand two hundred and fifty-one cases and nine hundre[illegible] forty-nine deaths, from July 13 to October 31; in 1855, in fourteen [illegible] from July 21 to October 30, eight hundred and one cases and fou[illegible] dred and seventy-eight deaths; in 1857 a few cases; in 185[illegible] October 19 to February 15, 1859, fifty-eight cases; in the secon[illegible] break in 1858, from August 20 to February 15, 1859, two hundre[illegible] seventy-three cases. In these thirty-five years there were [illegible] epidemics in this dirty town, with nine thousand cases and six the[illegible]

ths. As the authorities had not the slightest idea of infection or nfection, or water-pollution, the disease had its own way. The outaks of 1831, 1832, and 1837 were traced to importation; also those of 3, 1858, and 1859. Those of 1855 and 1866 were supposed to have en spontaneously. Among the proofs of spontaneous origin the folng instances are given, (p. 39:) "When there was no cholera in ttin, a lady came from a neighboring place to her sister's house to uit from the bodily and mental distress occasioned by witnessing deaths, and nursing two of her sisters who had died of cholera. Five s after her arrival her sister was attacked; two days after, the ant-girl who waited upon her, and finally the refugee herself. All e died." Dr. Goeden believed that the disease originated with the er living in Stettin; that next her maid developed it; and finally the er who had come from nursing two fatal cases of cholera. Again, a herd came to Stettin from a place where cholera was prevailing. sickened in three days, and asked to go back home, where he soon l of cholera. Three days after his departure, three persons who had t in the same room with him in Stettin became ill, and all died of lera. Dr. Goeden believes that the cowherd, coming from an infected e, contracted the disease spontaneously in Stettin, and his three m and bed-fellows also. Stettin will probably be affected to the end time. It is sufficient to add that Stettin is situated at the mouth of river Oder, to which the disease is flooded down from Poland; and t it is easily imported from Russia, Norway, Sweden, Denmark, all Baltic towns, Hamburg, and Berlin, and other places.

Berlin was also charged with having sent down cholera into Saxony 866, when we have seen that it had been present in the latter since gust, 1865. There had been no cholera in Berlin since 1855, (see ial report by Dr. E. H. Müller, Berlin, 1867,) except eighteen cases 857, and seventy-two in 1859. There was one suspicious, though fatal, case on May 7, 1866, but there had been numerous attacks in the ghboring province of Pomerania, (in which Stettin is situated,) on the er Oder, and on the Finow Canal, which connects the Oder with the er Ravel, which joins the river Spree at Berlin. Attacks and deaths gan to prevail more and more upon the boats and barges arriving at lin. The first fatal case in Berlin occurred June 7, in a sailor ing from Oderburg, on the Oder, but it was not reported for some e. On June 14 there were two more deaths; then it gradually reased to July 18, when there were two hundred and fifty-one attacks ne day; and then slowly subsided to November 17, when the last case s reported. The first cases were generally, but not exclusively, imted ones. The second and third cases could not be traced to infection; third was a child two and a half years old, on board an Oder boat; fourth, the owner of another boat; the fifth was the father of the rd case; the seventh a boatwoman; the eighth a lad working at the p-yard; the ninth and tenth were boatmen. But a connection beeen these fatal cases, one with another, could not be traced, especially the most of them were new importations.

There were eight thousand one hundred and eighty-six cases in 1866 in rlin. One thousand one hundred and one took place on Sundays, one usand two hundred and three on Mondays, one thousand one hundred l thirty-eight on Tuesdays, one thousand two hundred and forty on dnesdays, one thousand two hundred and eighteen on Thursdays, e thousand one hundred and forty on Fridays, and one thousand one ndred and forty-six on Saturdays. Dr. Müller thinks that the excess cases on Mondays arose from the fact that the Sunday-cases are not

reported promptly, and not from Sunday dissipations. In three th... five hundred and thirty-nine cholera-houses, only one death eac... place in one thousand seven hundred and eighty-four houses... seven hundred and ninety, three in three hundred and ninety-... four in two hundred and thirteen, five in one hundred and forty-... six in seventy, seven in forty-two, eight in twenty-seven, nine in ... six, ten in seventeen, eleven in nine, twelve in six, thirteen in ... fourteen in four, fifteen in two, sixteen, seventeen, eighteen, nin... twenty-one, twenty-eight, thirty-two, forty-three, and fifty-four ... each in one house. Seven per cent. of the deaths took place in c... 22 per cent. on the ground-floors, 28 per cent. in the second stor... per cent. on the third floor, 15 per cent. on the fourth, and 4 per ce... in garrets, owing to the smaller or larger number of inhabitants on ... floor.

Königsberg and other Baltic towns were also charged with sen... cholera down to Saxony. There had been no cholera in Königs... since 1860. Saxony, France, Belgium, and Holland were infected in ... and the whole south of Russia. The first death in Stettin was on ... 19; in Berlin and in Breslau on the Oder on June 14, in Leipsi... June 29. In Königsberg on June 22 the first case was in the pers... a Polish Jew, and the third, also, on the 28th. The soldiers and Aus... prisoners were not attacked until July 4. Danzig was not involved ... fore July 8. Of the first twenty-five cases, seventeen were fatal. ... October 21, five thousand five hundred and forty-three cases and two th... sand six hundred and seventy-one deaths occurred. On Mondays th... were nine hundred and four *attacks*; on Wednesdays, eight hun... and fourteen; on Sundays, eight hundred and three; on Saturdays, se... hundred and eighty-six; on Tuesdays, seven hundred and seventy-... on Fridays, seven hundred and forty-three; and on Thursdays, se... hundred and seventeen. On Tuesdays there were four hundred a... thirty-seven *deaths*; on Sundays, three hundred and ninety; on M... days, three hundred and eighty-eight; on Thursdays, three hundred a... seventy-three; on Fridays, three hundred and seventy-two; on Wed... days, three hundred and seventy-one; on Saturdays, three hundred a... forty. Königsberg had had twelve epidemics of the disease, viz: in 1... 1837, 1838, 1849, 1852, 1853, 1854, 1855, 1856, 1857, and 1859. In the ... break of 1866 they finally discovered that high parts of the town, sup... with pure water, had generally escaped, while all the streets and p... most frequently and severely attacked had a very impure supply. ... place with the best water had one hundred and twenty-two attacks in ev... ten thousand inhabitants; that with the worst had seven hundred a... seventy-seven. There were only two parts of the city with less than ... hundred and fifty, three more with less than four hundred, two ... under six hundred, three with less than seven hundred, and seven ... over 700 cases in each 10,000 inhabitants. The foul water of the ... Pregel and of the surface-wells was credited with the majority of d... Königsberg has generally succeeded in tracing her epidemics to imp... tions from Poland, along the Vistula, and from Russia, both by land ... sea. Still some of them, as usual in all large cities, were involved ... security. The first detected victims at times were residents, not strang... but they had come in contact with choleraic diarrhœa in some form. ... William Budd threw much light upon this point and upon the capric... ness of outbreaks in hospitals. *

A work-house in an open country, on high ground, contained seven ...

* Asiatic Cholera in Bristol in 1866. By William Budd, M. D.;

and fifty paupers. A woman brought cholera to it from the city,) miles distant, where the disease was rife. She had choleraic diar- , on her admission, and died on the second day. The next day cases n to follow one after another, until, in little more than a week, there over fifty patients on hand at one time. Within five weeks one red and forty-four had died of cholera. The disease was propa- l mainly through the agency of ill-constructed privies, which be- contaminated by the discharges from the sick, while they were resorted to by the healthy. A narrow passage separated two wards, occupied by thirteen men. In one ward there were seven cases of ra and six deaths; in the other there was only one case. The men the same food and water, and breathed the same air, but the in- s of the stricken ward were healthy men, who frequented the ed privy, while in the other, all were sick and confined to bed ex- one; the only one who was able to go to the privy was the only one developed cholera. Early in the outbreak a room, with six sick en in it, was made a cholera-ward. Cholera was thus brought to the six en, and they all died of it. Of two hundred and forty-four women children who used one privy, many fled; and of the rest, eighty-one, or than one in three, had cholera, and seventy-four died. In a female ical ward of nineteen women, six had cholera, and four died; four, were confined to their beds, escaped; of the fifteen who were able to o the privy, six took cholera. This seems to explain the curious fact cholera cases are often strangely scattered over sick wards; those lying t to the sick escaping, while those in distant beds may suffer. In y room, in this work-house, a large proportion of the inmates took the ase; in many wards one-half were affected; in one all died. Now, in a few paces of the spot where the appalling mortality was occur- there were sixteen persons housed in a separate building, who all ped. They were fed with the same food and drank the same water heir neighbors, who were dying by the score, yet not one had even rhœa. They had contagious forms of skin-disease; were closely ined to their rooms; and, in particular, were strictly debarred from rting to the common privy. There was also almost complete ex- tion of sixty-six children who lived in another isolated building. y had a separate privy, devoted to their sole use, and which ned into a cess-pool which had no connection with the common nage of the place; only one case occurred, which was quickly de- ed and promptly removed; yet their building was very near an- r, where out of one hundred and twenty inmates, twenty-eight died, only six were not attacked. The disease was introduced from with- ; was reproduced by the discharges of the sick; and the rapidity extent of its spread was due to the fact that so large a proportion he inmates were brought in close relation with the poisoned air he privies, which had become the receptacles of the choleraic dis- rges. If all the circumstances of every outbreak of cholera were in- tigated with the same untiring energy and sagacity as were displayed Dr. Budd in this most interesting inquiry, we should soon cease to r of outbursts of the disease being so mysterious and inexplicable to justify the Dundreary lament, "that no fellow can understand m."* If we take into consideration that every case of cholera com- nces as an infectious diarrhœa, which may persist for two or three s, or even as many weeks, we can readily understand how the germs

* Brit. and For. Med. Chir. Rev., July, 1872.

of the disease are spread in various secret and widely-distant p... before a fatal case may occur.

To complete the chain by which this cholera reached the United Sta... we have only to add, that early in 1866 cholera was reproduced in ... all the localities (Macnamara, p. 223) it had visited during the pre... year, extending northward as far as St. Petersburg; appearing ... several places in Bavaria, Saxony, and Prussia, as well as in Belg... and Holland. It also persisted, during the winter in Paris, extend... to the northwest of France, about Brest and Caen. The movement... large masses of troops by Prussia, Austria, and Italy contributed ... diffuse the disease, which told terribly on these armies during the ... mer campaign. We have all the official accounts, some of which ... most curious, subtile, and occult distributions of the disease; but ... omit them here. The first case reported in Great Britain, in 186... curred at Bristol, in a sailor from Rotterdam. Next, two more ... were reported in Liverpool among emigrants just arrived from Rot... dam via Hull. On the same day, (May 2,) the Helvetia sailed, with ... hundred and twenty-five steerage-passengers, among whom cholera ... out so severely, that she had to put back. From May 2, cases of ch... were of constant occurrence in Liverpool, but they were called spora... and it was not until July 22 that it became epidemic among the citi... but up to the end of November it carried off one thousand seven hun... and ninety-two victims. The first cases in London occurred June 3, ... a family at Bromley. Mr. Radcliffe traced their and other cholera ... charges into the river Lea, near the open reservoirs which distrib... drinking-water to London; and seventy-two out of every ten thou... who drank of it were carried off by cholera, while only eight in ... ten thousand suffered who had better water.

From 1854 until 1866, North America enjoyed a remarkable exe... tion from Asiatic cholera. Twelve years of security from this sca... was passed, but they were years of value to the cholera-student. I... erence has already been made to the various theories which called ... queries of Dr. Wynne in relation to the epidemics of 1848 and 1... and which are equally applicable to all other epidemics of the sa... ease. We quote from page 77: "Shall we consider the disease as ... nently contagious, and as having been brought into the ports of N... York and New Orleans by the emigrant-ships New York and Sva... and from thence disseminated by the same agency along the grea... of travel through the length and breadth of the North American ... tinent? Or shall we suppose that in its inscrutable progress fro... east to the west it was wafted by the atmosphere over the wa... panse of water which separates the eastern from the western ... nent, and arrived at New York and New Orleans simultaneously ... the two vessels leaving the same port under a remarkable identity o... dition? Or shall we look upon it as a disease of indigenous or... every place where it appears, and dependent upon a combinati... circumstances connected with the localities which it desolates ... we can at least partly explain and almost entirely prevent?" ... upon page 92, after summing up the evidence in favor of the ma... origin of cholera, Dr. Wynne remarks: "In all these circumst... the adjuncts in the production of cholera are found to maintain a ... ing resemblance to those which produce malarial diseases. If the ... tion were propounded to me, after the collection of all these facts, ... you tell what is the nature of the cause that produces cholera? I ... unhesitatingly reply that *I could not*. But I should give the sa... swer if I were interrogated concerning the nature of autumna...

i true, I might reply, in regard to fever, that it depended upon the ience of malaria. But what is malaria? It is the decomposition, er certain known circumstances, of vegetable matter. These cir- stances are the presence of air, heat, and moisture. Whenever ie elements unite in due proportion, fever is produced; but if either ranting, malaria is not generated. Hence, during the cold of winter the dryness of midsummer, we have no fever, but with the decom- ed vegetation of autumn, united with the heat and moisture of that ion of the year, fevers prevail. Heat and moisture cannot produce r. It requires decomposed matter, uncleanliness, and filth. These precisely the circumstances under which cholera makes its appear- e, and the reader will have had frequent occasion to observe how h it is under the conjoined influence of elevated temperature and sture, and how steadily it dwells among filth and uncleanliness."

n the early spring of 1861 the American civil war was inaugurated, the United States was hurriedly converted into a vast military en- ipment. In all the cities that had been favorite haunts of cholera in ner years, from the Penobscot to the Rio Grande, and from the Mis- ri to the Atlantic Ocean, troops were collected, and vast armies were centrated in the worst malarial regions of the United States, the val- s of the Potomac, Ohio, and Mississippi rivers.

t is estimated that during the years of this war the United States my had in the field an aggregate of 2,335,942 men, or that the mean ength of the armies was about 783,906 men. These troops were in up, constantly exposed to all the vicissitudes of the campaigns, or re in hospitals where, in spite of the lavish precautions which were pted, not infrequently all the disadvantages of overcrowding and icient food were present. Vast numbers of men were transported to l from the scene of active operations upon steam-transports. A very all percentage of the troops were in permanent fortifications. Vast son-pens were formed, in which overcrowding, bad ventilation, in- erent police, and unsuitable food were present to co-operate with al malarial influences upon the unfortunate prisoners.

The record of the medical history of the war demonstrates that there urred in the Army of the United States, of diseases of malarial ori- , 1,468,410 cases, with 46,310 deaths; of intestinal diseases, 1,765,501 es, with 44,863 deaths. Among the first are included typhoid, typhus, amon continued, typho-malarial, yellow, remittent, the intermittents, l congestive intermittent fevers. Among the second are included rrhœas, dysenteries, and cholera morbus. Of the latter, during the ire war, there were reported but three hundred and five deaths.

t must be borne in mind that these figures represent but one arm of United States service. When to these already large figures the tistics of the United States Navy are added, and to this combination added the statistics of the confederate armies, the mass of circum- ntial evidence is overwhelming.

In the very region where it is claimed that every epidemic of Asiatic olera that has visited the United States from 1832 to 1873 originated *le novo*," these immense bodies of men were congregated, and the eeding mortalities occurred; yet, during all those years of blood- ed and suffering, *not one case of epidemic cholera occurred.* Why? *cause there was none of the specific poison of cholera, which is alone olera, from which the disease might be reproduced.*

If cholera originated spontaneously among the troops that formed e armies during the Crimean war; if among them there were to be und causes sufficiently potent to cause an explosion of the disease,

why did it not originate among the armies engaged in the interna American war? It certainly cannot be said that any powerful loca fluences were present in one case that were absent in the other. Chol existed and committed the greatest ravages among the Crimean troo because, in a perfectly legitimate way, in a manner perfectly in keep with the history of the disease, it was carried into their camps fr previously infected localities; and it did not exist in the Americ armies during the civil war, because it was not then in existence at point from which it could be conveyed to them.

The theory of spontaneous origin during the Paraguayan war deser no further notice, as the light which Dr. Rego threw upon it has yet been obscured.

The American war was concluded, the armies were withdrawn fr the field of operations, and, to the admiration of the world, the m whom they had been composed, returned without confusion or disor to the walks of private life.

The disbandment of these armies had scarcely been accompli when cholera appeared in emigrant vessels upon the Atlantic coas the United States, and the narrative of the epidemic will demonstra how rapidly and fatally the disease was diffused over the United Sta by recruits which were forwarded from New York Harbor to that re nant of the grand army, the regular army of the United States.

The introduction of epidemic cholera into North America in years 1865 and 1866 is surrounded with no mystery or uncertainty. Peters has shown in the preceding portions of this chapter the a vance of this dread disease through Europe.

In the annual report of the Health-Officer of the port of New Yo dated December 30, 1865, we find the following: "Up to this d thirty-six vessels from European ports, at or adjacent to which cho was known or reported to prevail, have been detained in quarantine observation, fumigation, and purification. Strict surveillance h been kept upon vessels arriving from suspected or infected port some time before any case of cholera was by us discovered. In no c has the disease been detected in vessels from any other port ex Havre."

The first vessel upon which cholera was detected was the Eng iron mail-steamer Atalanta. This vessel had three separate commod steerages. She left London October 10, with twenty-eight cabin twelve steerage passengers, and a full cargo. On the 11th she rea Havre, where she remained one day, and received five hundred a forty steerage passengers, all of whom were from or had passed thr cholera-infected districts. Among these emigrants were two Ger families who had rested one day at the hotel "City of New York Paris, and five days at the Weissen Lomni and Stuttgarder H Havre. While at these hotels emigrants had been sent from them to hospital. October 12, the Atalanta left Havre. October 13, a ch death occurred in the party from the Weissen Lomni. By the 2 the month five cholera deaths occurred among the family fro Stuttgarder Hof.

The same day a fatal case occurred in the second steerage. O 28th, cases occurred in the third steerage, and by the time that t alanta reached New York, November 2, sixty cases of cholera fifteen deaths, had occurred. Forty-two cases were admitted t quarantine hospital-ship, eight of which were fatal.

November 26, the Hermani arrived at quarantine, and reported deaths upon the voyage. The first of these deaths occurred in a

had lost one of their number from cholera at the Stuttgarder Hof, at re, prior to the sailing of the Atalanta.

ovember 20, the steamer Cella arrived from Havre, with three hun- l and sixty emigrants of the same nationalities as those already noted, no sickness was noted as having occurred on the voyage.

ecember 12, the Mary Ann arrived from Havre. The captain reports deaths from cholera on the voyage, *but for thirty days prior to arrival ases had occurred.* (*!*)

; has been noted as a significant fact that the Atalanta, Mary Ann, mani, and Harpsvill had each names on the passenger list which e not among the passengers, but who were reported to have been ; to hospital by the local authorities at Havre.

holera existed on the Atalanta for two weeks after her arrival at t. The baggage of the passengers was aired and fumigated in cool mbers, and ten days after the last case occurred they were allowed tique, and passed up to the city.

here is, however, nothing to show that any precautions were adopted egards the passengers of the Hermani, Cella, Mary Ann, or Harps-

.

Ve, however, learn from the report of the sanitary committee of the tropolitan Board of Health that, "owing to the coldness of the ather, the disease did not extend" beyond the hospital on Ward's and, where, at one hospital, twenty-four deaths occurred among con- escents from fever; and from Appendix M to the annual report of Metropolitan Board of Health we quote the following: "Diarrhœa l dysentery were much more prevalent than in former years, but did appear of an epidemic or fatal character until the rainy period, which urred in November, 1865, when it assumed an epidemic or choleraic e. On the 22d of November the first fatal case was recorded, fol- ed daily by others, until the middle of December, when it mitigated, ing, probably, to the favorable change which had previously taken ce in the weather, and the sanitary measures then adopted to arrest Still it continued in the same building in which it commenced up to 20th of December, when it entirely ceased." Dr. Ford says: "It s my opinion at the time that these cases were Asiatic cholera; *it is opinion still*, and their history corresponds with my observation in past epidemics of this disease which I have witnessed."

t is well to remember that the above was written of the State emi- nt hospital, and that the disease occurred in the building devoted to men and children.

The cholera-epidemic of 1866 in North America opened with the arrival the harbor of Halifax of the steamship England. Upon this vessel y fatal cholera-cases had occurred prior to her arrival, and she put o Halifax to obtain additional medical aid. The instance of cholera on the England having been used by the opponents of quarantine as strative of the barbarities arising from the employment of that means defense against contagious diseases, it is well to reproduce the story.

The steamship England left Liverpool for New York on the 28th of rch, with eleven hundred and eighty-five German and Irish emigrants, enteen saloon-passengers, and a crew of one hundred and twenty- o officers and men. On the 1st of April, a German boy died of chol- . On the 3d of April, the ship experienced heavy weather, and the tches were battened down for two nights. When the hatches were ened, it was found that another cholera-death had occurred; and when e put into Halifax on the 9th, the surgeon reported one hundred and ty cholera-cases, with forty-six deaths.

On the 11th, the sick were placed in the Pyramus, that had been converted into a hospital-ship; and the well were landed and placed in tents. On the 13th, it was reported that the deaths were twenty-two a day. The crew and saloon-passengers remained on the England without sickness among the latter, and none among the crew after reaching Halifax.

On the 18th the England, *having been scraped, scrubbed, and fumigated*, left for New York with eight hundred and seventy-five steerage, sixty saloon-passengers, and a crew of one hundred and sixteen officers and men. One saloon-passenger died of apoplexy.

A pilot who spoke the England on her arrival, but who would not board her on account of the cholera, but was towed after her, died on the 11th, of cholera, at his home near Halifax; his five children all had the disease, and two of them died.

Seventeen men were sent down from Halifax to clean the England. On the 13th one of these men died of cholera. Dr. Slayter, the health-officer who boarded the England, died of cholera on the 17th. The only cases that occurred in Halifax among persons that had not been in intercourse with the England were one family who had made use of clothing of some material picked up on the shore; in this family four deaths occurred. For the above facts we are indebted to the British Medical and Surgical Journal.

April 18, the first vessel having cholera on board arrived at New York quarantine; this was the steamship Virginia, from Liverpool, with four cabin and one thousand and twenty-nine steerage-passengers. On the passage thirty-six of the steerage-passengers and two of the crew had died from cholera, and forty-six were ill on arrival; they were transferred to the hospital-ship as rapidly as possible. The subsequent cholera arrivals are exhibited in tabular form:

Date of arrival.	Name of vessel.	Port of departure.	Total passengers and crew
April 18	Virginia	Liverpool	1,135
April 20	England	do.	[illegible]
May 29	Union	do.	[illegible]
May 30	Peruvian	do.	[illegible]
August 15	Bavaria	Hamburg	[illegible]
August 16	Johan Martin	Antwerp	[illegible]
September 6	Gettysburgh	Havre	[illegible]
September 26	Bellona	London	[illegible]
October 8	Helvetia	Liverpool	[illegible]
October 25	Isaac Webb	do.	[illegible]
October 31	Herschel	Hamburg	[illegible]
November 7	Yorktown	London	[illegible]
November 7	John Bertram	Hamburg	[illegible]
November 7	Floride	Havre	[illegible]
November 8	Mozart	Bremen	[illegible]
November 12	Washington	Hamburg	[illegible]
November 21	Mercury	Havre	[illegible]
November 28	Jessie	Hamburg	[illegible]
Total			[illegible]

In the report of the health-officer of the port for the year 1866, it was stated that in every instance the passengers were detained twenty-two days after the occurrence of the last case. This, with the exception of the case of four vessels, would have been most difficult to accomplish, and even in the case of the passengers of the vessels excepted would have demanded the detention from April 18 until June 21, which undoubtedly was not done; therefore, even with the precautions adopted, persons exposed to the infection of cholera, and therefore capable of conveying it, must have come up to the city of New York.

The first cholera death in New York City occurred May 2, at a tenement-house in Ninety-third street, near Third avenue. The second case occurred May 2, in a tenement-house on Mulberry street. The third case was at No. 303 Broome street, in a private, well-kept house. The fourth case washed the soiled clothing of the third case. The fifth case was in a tenement-house on West Twentieth street. The sixth case worked on East River, and lived on Hester street. The seventh case spent a portion of the day before attack in the vicinity of Pitt and Willett streets. The eighth case was an Irishman on Cherry street. The ninth case was a farmer who ate breakfast near Greenwich and Liberty streets before his attack. The elaborate and complete report of Dr. Elisha Harris, to whose indefatigable exertions the United States owes many sanitary reforms in past years, fails to determine any connection between any of these cases, except the third and fourth cases. But it must be remembered that prior to the occurrence of either of these cases, at least two thousand and ninety-four individuals who had been directly exposed to the infection of cholera at Liverpool, on shipboard and at quarantine, had arrived in New York City; further, that each of these cases occurred in the very portions of the city of New York that are frequented by the classes of the community to whom these emigrants belong. Dr. John Swinburne, who was at the time health-officer of the port, makes a suggestion that throws light upon this subject. We quote from his report: "The question may then be asked, if not traceable to quarantine, from what source did the infection in New York emanate? The answer is simple. Prior to the appearance of cholera in the city, all persons exposed to the disease, either on the passage or in this port, were, as I have already stated, detained during a period of twenty-two days, while others, among whom there had been no appearance of cholera during the voyage, but who came from European ports, where the disease is known to have prevailed, were mingling with their friends in New York in the course of from ten to fourteen days from the date of their probable exposure to cholera."

And this is the probable solution of the problem. The tenement-houses of New York were probably full of cholera-infected individuals and clothing, and but for the prompt and efficient management of the Metropolitan Board of Health; but for the almost universal system of disinfection which was adopted in 1865, and scrupulously continued, the city of New York would, in all probability, have witnessed a most disastrous explosion of the disease.

From the report of Dr. Harris we learn that up to July 8 twenty-one deaths from cholera had occurred in New York City, and that while none were directly exposed to persons or things from quarantine or from the emigrant landing, yet all resided in localities that were frequented by freshly-landed emigrants.

The first case occurred in Brooklyn in the first week in July, and in a locality inhabited entirely by foreigners. This case established the focus of an intense local epidemic.

On the 14th of July the first cases occurred at the emigrant hospital on Ward's Island, and became epidemic.

On the 3d of July the first fatal case occurred among the garrison of Fort Columbus, on Governor's Island, the general recruiting-depot of the United States Army. As from this point the disease was extensively diffused over the United States, we present *in extenso* the report of Assistant Surgeon J. J. Woodward, U. S. A., which is a most elaborate *exposé* of the diffusion of the disease of that year. This report is extracted from Circular No. 5, Surgeon-General's Office, May, 1867.

REPORT ON EPIDEMIC CHOLERA IN THE ARMY OF THE UNITED STATES DURING THE YEAR 1866.

By J. J. Woodward, M. D.,
Assistant Surgeon United States Army.

* * * * * * *

The first reported case of cholera in the Army during 1866 occurred at Fort Columbus, Governor's Island, New York Harbor, on the evening of July 3. The patient was a recruit from the recruiting rendezvous, Minneapolis, Minn., of whose previous history and exposure nothing is known. He had been but three days at the post. About an hour after his admission into hospital another case occurred, also a recruit of unknown previous history. Cholera was at this time prevailing in New York City.

Recruits from Governor's Island carried cholera to Hart's Island, where the first case occurred on the 8th of July. The epidemic becoming severe among the troops at this post, they were moved, on the 30th, to David's Island, where the disease subsequently prevailed to a limited extent among the troops thus transferred. These cases are reported from the De Camp Hospital, David's Island, where they were sent for treatment. A single case also occurred at Fort Schuyler, New York Harbor. The patient was a lieutenant of the First United States Artillery, who had slept on board the steamboat used the day before in transporting the infected troops from Hart's Island to David's Island. Six cases occurred in the garrisons of Forts Hamilton, Lafayette, and Wadsworth, the fort at Sandy Hook, Madison Barracks, or Willet's Point, New York Harbor. Moreover, there were none among the officers and men on detached duty in New York City, Jersey City, and Williamsburgh. The total number of cases reported among the troops in New York Harbor was one hundred and eighty-one, with seventy-six deaths.

On the 19th of July, a soldier died of cholera at the Soldier's Rest, Boston, Mass. This man arrived in Boston, on the morning of the 19th, from Hart's Island, where he had been on duty as a ward-master in the cholera-hospital. No further military cases occurred in Boston.

On the 14th of July, the steamship San Salvador left New York with seventy or eighty cabin-passengers, and sixty in the crew and steerage. She touched at Governor's Island and took on board four hundred and seventy-six recruits for the Seventh United States Infantry. The troops were lodged between decks, and were greatly overcrowded. On the second day out cholera appeared among the recruits, and when the vessel arrived at quarantine, near Savannah, Ga., three deaths had occurred, and there were twenty-five ill of the disease. The troops were landed on Tybee Island and a hospital extemporized. Cholera continued to prevail on the island during July and the first few days of August. Altogether there were two hundred and two cases and one hundred and sixteen deaths, including eighteen deserters, reported as having died in the woods of Tybee Island, and one who escaped from the island and died in Whitemarsh quarantine hospital. The cabin-passengers and crew of the San Salvador appear to have escaped, but of the ten white citizens residing on Tybee Island, nine were seized with cholera shortly after the arrival of the infected ship and five died. The tenth fled from the island, and is reported to have died of cholera somewhere in the

or of Georgia. No cases of cholera occurred among the troops sta-
ıed in Savannah.
ecruits from New York Harbor arrived in New Orleans on the 8th and
ı of July, others from Carlisle Barracks, by way of New York Har-
, on the 23d. One of these detachments, on the steamship Herman
ingston, brought recruits from Hart's Island, which she left on the

ın the 8th a case of cholera occurred which proved fatal the next day.
reek subsequently another fatal case occurred. The vessel arrived
quarantine in the Mississippi River on the 15th and put off two re-
its said to have diarrhœa. On the 16th the command disembarked
Jackson Barracks, six miles below New Orleans, where two recruits
e sent to hospital with choleraic diarrhœa. The command remained
ee days in New Orleans, and on the 19th of July embarked on the
amship Texas for Galveston. The first case reported among the
ops at New Orleans was on the 22d of July in Company G, Sixth
ited States Cavalry, stationed at Holmes's Foundery. The patient
s a recruit recently enlisted in New Orleans. It is not known whether
had been in communication with the New York recruits. On the
h of July, a case occurred at Jackson Barracks, six miles below New
leans. The patient was one of the recruits recently arrived from
w York Harbor on the Herman Livingston. A number of cases sub-
quently occurred among the troops at this post, and in company G of
e Sixth United States Cavalry. On the 25th of July, also, a soldier
the Eighty-first United States Colored Infantry, at the Louisiana
tton-press in the first district of New Orleans, was seized with symp-
ns of cholera, and sent to hospital; he died on the 26th. On the
th another man of the same regiment, who had been on guard duty
Bull's Head stables, near the levee in the fourth district, was brought
o camp with cholera, and died the same day. The disease spread
pidly through the regiment. Cholera already existed among the citi-
ns of New Orleans, and a number of the early victims among the
ops were out of camp when attacked, many of them being brought
a state of collapse from hovels in the city. The health-ordinance in
ew Orleans did not become a law until after cholera had manifested
elf, and it is difficult, therefore, to tell when the first cases among the
izens occurred.
In the Seventh, Ninth, Thirty-ninth, and One hundred and sixteenth
olored Regiments, the disease had appeared while on duty in Texas;
e large majority of the cases reported in New Orleans, however, oc-
urred in company G, Sixth United States Cavalry, and in the Eighty-
st United States Colored Infantry. Altogether ninety-three cases and
enty-four deaths were reported among the white troops at New
rleans, and two hundred and fifty-four cases and one hundred and
rty-nine deaths among the colored troops.
The disease was carried to the colored troops at Forts St. Philip and
ckson, below New Orleans, on the Mississippi River, by detachments
turning to those places after having been on duty in New Orleans
uring the riot. The first case appeared on the 10th of August, and
uring the rest of the month and September there were seventeen cases
nd eleven deaths.
At Ship Island, Miss., the first case occurred September 8. There
as one fatal case among the colored troops during September, and
thers among the hired men, convicts, &c. On the 17th of August the
rst case was reported at Baton Rouge, La., in the Sixty-fifth United
tates Colored Troops. During August, September, and October, there

were sixty-nine cases and forty-three deaths. There was also a late case in August, and one during October, in the detachment of ordnance (white) stationed at the post.

The reports do not indicate the mode in which cholera arrived at Hart's Island or Baton Rouge.

The first case at Shreveport, La., on the Red River, occurred September 22, in the Eighteenth United States Colored Troops; for nearly a month previously cholera had been reported on the plantations below, and in the city of Shreveport just above the post. During September and October there were eleven cases and four deaths in the command. The steamship Texas, with recruits from Hart's Island, for the Seventeenth United States Infantry, left New Orleans, as already stated, July 19, and arrived at Galveston, Tex., on the 22d. The day after their arrival one of the recruits was attacked with cholera, and died in thirty-six hours. In the outbreak which followed, forty-four cases and twenty-four deaths are reported among the white troops at Galveston, and one fatal case of a colored soldier in the post hospital during August. The subsequent progress of the epidemic in Texas was as follows:

The first fatal case among the colored troops at Brazos Santiago occurred August 21; in all, ninety cases and forty-seven deaths were reported.

Among the colored troops at White's Ranch, the first fatal case was on the 13th of August, ninety-eight cases and thirty-seven deaths being reported during the month.

Among the colored troops at Brownsville, the first case was on the 20th of August, and proved fatal the same day. In all there were ninety-nine cases and fifty-seven deaths reported during August and September. Among the white troops at the same post, the disease also appeared in the latter part of August. The first death was on the 1st of September; twenty-four cases and eight deaths are reported.

Among the colored troops at Indianola, the disease appeared in the latter part of August. The first fatal case was on the 6th of September; thirty-nine cases and seven deaths are reported. At San Antonio, the first case occurred on the 10th of September, in the Fourth United States Cavalry, (white.) The regiment was moving at the time, part of it being in San Antonio, and part in camp on the Medina River, about fifteen miles distant. In the latter detachment three cases appeared from the 7th to the 10th; in the former, two cases on the 11th. The first death occurred September 10. Cholera was prevailing among the citizens of San Antonio at the time, the first case having occurred September 1, at San Juan Mission, about six miles distant; the patient had just arrived from the Rio Grande, where the disease was epidemic. A detachment of the Seventeenth United States Infantry at San Antonio escaped until after it was moved from town, September 16, to camp on the Medina near the cavalry camp. Cholera appeared in this detachment a few days afterward, however, having apparently been introduced by two Mexican teamsters who came from San Antonio, stopped for the night near the camp, and died of the disease. The total number of cases reported among the white troops at and near San Antonio during September, was three hundred and eighty-seven, with sixty-four deaths.

Among the white troops at Austin, to which place the disease was carried by recruits who arrived by way of Indianola, the first death was the 18th of September. During September and November twelve fatal cases are reported.

At Richmond, Va., the first case occurred at Camp Grant, on the 1st of August. Recruits had been received during July and August [illegible]

r York Harbor and Newport Barracks. It appears, however, that earliest cases were not among those recruits, but among soldiers had been at Richmond the entire summer. Cholera appeared in city of Richmond about the same time. The total number of cases two hundred and seventy-one, with one hundred and three deaths, white.

n the 21st of August, the third battalion of the Eleventh United tes Infantry was sent from Camp Grant to Norfolk, Fortress Monroe, Yorktown. Four cases and two deaths occurred during September October, among the companies thus removed to Norfolk.

ugust 12, a death from cholera occurred at Carlisle Barracks, and ther on the 20th. Both were Swiss recruits from Philadelphia, where lera was prevailing to a moderate extent. One of the attendants on se men was attacked, but recovered. These men were attacked imliately after return from Jefferson Barracks, Missouri, where cholera s prevailing. On the 17th of October a cavalry recruit was attacked l died in thirty-six hours. He had arrived the day before his attack n Chicago, Ill., where cholera was then prevailing. No other case urred at this post.

A detachment of recruits from Governor's Island, New York Harbor, ived at Newport Barracks, Kentucky, July 12; recruits were also re-ved during the latter part of July and first of August from Saint uis, Mo., and Cincinnati, Ohio; from the latter place almost daily er July 13. The first case of cholera at this post occurred August 12. e patient was a recruit who had been doing duty as a teamster, and iting Cincinnati daily. From this time to the close of November, there re nine cases and five deaths of cholera reported at the station.

During September cholera also appeared at Atlanta and Augusta, Ga., ong recruits who went from Newport Barracks by way of Nashville. e disease was limited to the recruits. The first fatal case at Atlanta s on the 9th of September, and nineteen cases with seven deaths, oc-rred during the month. At Augusta the first fatal cases were also the 9th, and the total number during the month was eight cases, of om seven died.

At Louisville, Ky., the first case July 29. The patient was a recruit m Governor's Island, New York Harbor; three hundred and sixty-ir recruits from Governor's Island arrived at Taylor Barracks, Louis-lle, between the 16th and 19th of the month. Cases of cholera occurred st among these recruits, but subsequently among the rest of the gar-on. The first case in the garrison (excluding New York recruits) oc-rred August 18. The total number of cases at Louisville was thirty-t, with twenty-three deaths.

On the 21st of August, company E, Second United States Infantry, as ordered from Taylor Barracks to Bowling Green, Ky. Six cases of olera occurred in this company during the remaining days of August d two in September. None were fatal.

During the last days of August and the first of September, squads of cruits, numbering ninety each, arrived at Nashville, Tenn., from ewport Barracks, Kentucky, and were quartered for quarantine pur-oses in the immediate vicinity of the post hospital. The first three ses occurred among these recruits—the first fatal case being on Sep-mber 2. About this time, also, cholera began to prevail among the itizens of Nashville, and it would appear probable that it was from this urce that the disease was introduced into the detachment at Sibley arracks, as the first two cases at this post were men who had been on debauch in the town. Altogether, there were seventy-two cases and

thirty-nine deaths among the white troops. Two deaths of colored soldiers also occurred in September, in the Nashville post hospital.

The first case among the white troops at Memphis, Tenn., occurred September 6, and died the next day. The patient was a recruit who had arrived, the day before the attack, from Nashville. Altogether, there were twenty-one cases and sixteen deaths during September among the white troops at Memphis. On the 15th of August, however, a fatal case had occurred in the post hospital at Memphis. The patient was a soldier of the Fifty-sixth United States Colored Troops, who was taken sick on board the steamer Continental, passing up the river from Helena, Ark.

The first case among the white troops at Vicksburg, Miss., occurred on the 22d of August, on which day two soldiers were attacked. The colored barber had died of the disease the day before. There were in all fifty-nine cases and twenty-five deaths in Vicksburg. A detachment of one hundred and forty-five recruits had been received July 1 from Fort Columbus, New York Harbor. Cholera also appeared in a detached company (E) of the Fifteenth United States Infantry, stationed at Jackson, Miss., where, during August and September, there were eight cases and six deaths. A detachment of fifty-one recruits had been received at Jackson, July 17, from Fort Columbus, New York Harbor.

The Fifty-sixth Colored Infantry left Helena, Ark., in two detachments—the first on the steamer Continental, August 9; the second on the Platte Valley, August 10. A death, probably of cholera, occurred on the Platte Valley about twenty-four hours after starting, and another while between Cairo and Saint Louis. The disease, however, was not recognized until the morning of the 14th at Saint Louis, when the vessel was ordered to the quarantine-grounds at Jefferson Barracks. Cholera broke out on the Continental shortly after leaving Helena. A case was put on shore at Memphis, and died in the post hospital. This vessel also went into quarantine at Jefferson Barracks, where she arrived before the Platte Valley. During August and September, two hundred and fifty-six cases and one hundred and thirty-four deaths were reported in this regiment; this number, however, does not include those who died on the river before reaching Jefferson Barracks. The disease spread to but a limited extent among the white troops at Jefferson Barracks. The first fatal case was August 15, several days after the arrival of the Fifty-sixth United States Colored Infantry. Altogether there were eight cases and seven deaths. Four cases and three deaths also occurred during August and September in the ordnance detachment at Saint Louis Arsenal, the first fatal case dying on the 17th of August.

On the 25th of August three hundred and eighty-four cavalry recruits (white,) from Carlisle Barracks, Pennsylvania, by way of Saint Louis, arrived at Fort Riley, Kansas. One of them died of cholera August 31. From this time to October 16, fifty-nine cases and twenty-seven deaths occurred, all among the recruits, the rest of the garrison escaping.

At Fort Leavenworth, Kansas, (white troops,) the first case occurred September 18; the patient died next day. Altogether there were seven cases and five deaths at this post. A few days before the appearance of cholera, about twenty cases were reported among the citizens of Leavenworth City, two miles south of the garrison. Intercourse between the city and the post was unrestricted. One case, not fatal, was reported at Albuquerque, N. Mex., in October; particulars not known.

At Helena, Ark., the first fatal case (white troops) occurred August 30, and during August and September there were ten cases and six deaths. A detachment of twenty-eight recruits was received at

August 3, supposed to be a portion of a detachment of recruits ch left Newport Barracks, Kentucky, for Little Rock, Ark., July 28. t Little Rock, Ark., the first case occurred September 12. Altogether e were one hundred and thirty-one cases and sixty-four deaths among white troops. A company of the Fifty-fourth United States Colored ntry, stationed at the same post, had three cases and one death in tember, and four cases and one death in October, the first fatal case ng them being September 27. Nine recruits of the Thirteenth United tes Infantry arrived at Little Rock, August 10, from Newport Barks, Kentucky. It does not, however, appear probable that cholera imported into Little Rock by this detachment of recruits. The ort of Bvt. Lieut. Col. J. R. Smith, Surgeon United States Army Medical Director, would rather seem to show that it was carried re by steamboats coming up the river from infected points. Surn Smith says: "From time to time, during the month of August, amboats arrived both at Little Rock, on the Arkansas, and Duvall's ff, on White River, on which rumor said that cases of cholera either sted or had occurred. Examination made by other physicians here l at Duvall's Bluff, as well as by myself, failed to confirm the report the present existence of cholera on board these boats, *although I was isfied, in several instances, from the histories related to me, that fatal es of cholera had occurred during their trip from Memphis to Little ck.*"

At Huntersville, a suburb of Little Rock, Ark., there were twenty-one ses and nine deaths during September, in the Fifty-fourth Colored fantry, the first case occurring September 15, and proving fatal the xt day.

At Fort Smith, Ark., there were two cases in September, and six ses and two deaths in October, among the white troops. Four cases d two deaths among the colored troops for the same time. The disse was carried to Fort Smith on a steamer from Little Rock.

Three cases and two deaths occurred at Fort Gibson, Cherokee Nan, during October; the first case occurred October 15. Two of these ses were soldiers belonging to Company F, Nineteenth Infantry, which rived at Fort Gibson, October 12, from Fort Smith, Arkansas. The ird had attended them during their illness. One fatal case occurred ring November.

Finally the latest appearance of cholera during the year was in a rty of recruits who left New York for San Francisco, November 20. n the 16th of December cholera appeared, the vessel then being on the an Juan River. On the 20th the command reached La Virgin, on Lake icaragua, about twelve miles from the Pacific; went into camp and tablished a hospital. Altogether there were fifty-four cases and twenty-ven deaths during the month.

The epidemic appears from the record to have radiated distinctly from o chief centers.

* * * * * * *

Originating in the overcrowded barracks of Governor's Island, New ork Harbor, in the immediate vicinity of an infected city, through hich recruits passed with more or less delay before arrival, the infecon spread by readily traceable steps to Hart's Island and other posts the harbor, to Tybee Island, Georgia; to Louisiana, by way of New rleans; to Texas, by way of Galveston; to Louisville, Ky.; to Richmond, Va., and to La Virgin, Nicaragua Bay. From Richmond it was arried to Norfolk, Va.; from Louisville to Bowling Green, Ky. The robabilities appear to be that the disease was carried from New Or-

leans up the Mississippi River to various points on that stream, and o- of it, and though the whole chain of evidence is not complete, yet there are a sufficient number of known cases of the transfer of the epide- from one post to another in this region to put this view of the line movement beyond reasonable doubt.

The other principal center appears to have been Newport Barra- Kentucky, where the disease was plainly introduced from the infec- city of Cincinnati, on the opposite side of the Ohio River. Altho- it did not prevail to any great extent at this post, yet it is in evide- that it was carried thence to Augusta and Atlanta, Ga., to Nash- and Memphis, Tenn.

At several points, as, for example, at Augusta and Atlanta, Ga., e- epidemic did not extend beyond the infected recruits by whom it w- reported. In many cases, however, it involved the rest of the comma- and it is highly probable that this would have been the case far m- generally but for the stringent hygienic precautions adopted.

* * * * * * *

The following medical officers died of cholera while engaged in t- active performance of their duties in connection with the epidemic:

1st. Brevet Major J. T. Calhoun, Assistant Surgeon United St- Army, died of cholera, July 20, 1866, at Hart's Island, New Y- Harbor.

2d. John E. McDonald, Assistant Surgeon United States Army, d- of cholera September 10, 1866, at Saint Louis, Mo.

3d. Acting Assistant Surgeon J. F. Burdett died of cholera Aug- 6, 1866, at Tybee Island, Georgia.

4th. Acting Assistant Surgeon Samuel Catlin died of cholera Nove- ber 27, 1866, at New Orleans, La.

5th. Benjamin Hobbs, Surgeon of the One hundred and sixtie- United States Colored Troops, died of gastro-enteritis (?) August 1866, after rising from a sick-bed to attend cholera-cases in his regim- at White's Ranch, Texas. * * * * * * *

The report of Dr. Woodward is of great value, as it demonstrates t- distribution of the disease throughout the United States by the m- ments of recruits for the United States Army; and were it possible trace as accurately the progress of emigrants, the history of the e- demic would admit of no misconception. The table which we have p- sented shows that from April 18 to November 28, 1866, seven thousa- six hundred and nineteen individuals, from vessels known to have be- infected with cholera, were landed at the port of New York alone: b- no record can be obtained of the number of emigrants who arri- upon vessels that did not become infected with the disease upon th- voyages, although the port from which they sailed was infected w- the disease, and the large majority of the emigrants were from cholera- infected countries. Neither can it be determined how many emigra- arrived at other ports, *i. e.*, Boston, Philadelphia, Baltimore, and N- Orleans; but it is known positively that at the points of greatest pre- lence during this epidemic, viz, New Orleans, Memphis, Saint Lo- Cincinnati, and Chicago, the epidemic was largely fed by these infec- nates.

On the 24th of April, two cases of cholera occurred at Portland, M- one of whom was an escaped emigrant from the quarantine at McN- Island, Nova Scotia. This man was one of the Virginia's passengers.

On the 29th of May, three cholera-deaths occurred among the child- of an emigrant party which arrived at Detroit by way of the G- Western Railway from New York City.

On the 16th of June, a man, who had contracted cholera at New York
y, died at an infirmary in Baltimore, Md.
On the 11th of July, a German woman died of cholera in a filthy
ement at Cincinnati, Ohio. This woman had gone to Newport, Ky.,
h a party of recruits from Governor's Island the day before she was
icked.
During the last week of July, cholera occurred in Philadelphia, and
of the first victims, a negro in a miserable tenement-house, was left
days unburied.
On the 21st of July, the first case occurred at Chicago, in the person
an emigrant.
On the 27th of July, two cholera-deaths occurred at Saint Louis, Mo.
ese cases occurred in that portion of the city most frequented by emi-
nts.
On the 13th of August, a party of emigrants camped on the outskirts
Kansas City, Mo.; nine of this party died of cholera, and the disease
read to the city.
In the Medical Record for September 1, 1866, under the caption of
ogress of the cholera, we read: "The deaths in Cincinnati, Ohio, have
reased from an aggregate of six hundred and ten, in twelve days, to
laily average of nearly eighty, and this in spite of vigorous sanitary
asures, the gratuitous issue to the poor of remedies intended to con-
l the precursory diarrhœa, and a re-enforced corps of district physi-
ans. Newport Barracks, on the opposite shore, lost a recruit on the
th ultimo, and the Louisville, Ky., Board of Health reports a few
aths. with the explanation that the cases were mostly imported. In
int Louis, Mo., a city of imperfect drainage, the visitation as yet
hibits no prospect of a decline; the record of a single day sums up
e hundred and forty-one cases, and fifty-two deaths. The steamer
ontinental also arrived at Saint Louis on the 13th ultimo, with a de-
chment of the Sixteenth United States Colored Infantry, of whom
ty-one died during the passage from Cairo, Ill., and twenty-six re-
ained under treatment. From Saint Louis, Mo., the disease has been
rried by the Canada, of the Northern Packet Line, to La Crosse, Wis.;
hile from Chicago, Ill., where the river has become substantially a
agnant bayou, we have advices indicating not only an invasion on
e part of the pestilence, but the inauguration of what promises to be
very active campaign. From Saint Paul, Minn., we hear that two
en have died of cholera, and that a quarantine is established at
aposia, three miles above the city, where steamers will put off any
olera-patients that may be on board. New Orleans reports an in-
easing mortality, at the rate of 10 per cent., but the infected district
elongs to the lower portions of the city, and the victims are to be found
mong the blacks; and Galveston, Tex., still suffers in the persons of
s garrison. Approaching the interior, we find that Memphis, Tenn.,
as been visited, but not severely, although its physicians, evidently on
he alert, have appointed a committee to confer with the governor of
he State regarding the establishment of a river quarantine."
In the Medical Record of September 15, we read: "Turning to the
Mississippi Valley, we find that Saint Louis has been the heaviest
oser in the Southwest, having already published a death-list approach-
ng, in round numbers, nearly two thousand five hundred, as the result of
a month's prevalence of the epidemic in a very virulent form. The de-
crease in Cincinnati and New Orleans is counterbalanced by a fresh
mpetus to its force at Memphis, and an importation at Leavenworth,
Kans. In Louisville, Ky., the disease just now seems keeping within

bounds; while into Mobile, despite the establishment of a fifteen-day quarantine on all New Orleans vessels, the scourge has somehow been smuggled."

September 26, one death from cholera occurred at Louisville, Ky. The same day there were twenty-six deaths in Nashville, and many in Memphis, Tenn.

September 27, Nashville had twenty-two fatal cases, and Memphis twenty-four.

October 2, a gentleman from Richmond, Va., died at Washington City from cholera, and several fatal cases followed.

During the epidemic, Saint Louis lost eight thousand five hundred cases, Cincinnati one thousand four hundred and six, and Chicago one hundred and ninety.

It was the fate of the writer, during the epidemic of 1866, to witness a demonstration of the efficacy of stringent hygienic precautions in protecting small communities from the inroads of cholera, as well as the portability of the disease by means of cholera-infected clothing.

During the war, the Pea-Patch Island, at the head of Delaware Bay, upon which is located Fort Delaware, had been used as a prison for confederate soldiers, of whom many thousands during the war had been confined at that point. All the available space outside the fortification had been covered by the buildings occupied as prisons and hospitals, and from necessity, after the large rate of occupancy, the island at the close of the war was in a most unsatisfactory sanitary condition. During the fall of 1865 and the winter of 1865–'66, all unnecessary buildings were removed from the island, the ditches which traversed the island (the surface of which was below high-water mark) were drained and dredged. *Débris* of all kinds was collected and burned, and the island, at a very considerable pecuniary outlay on the part of the General Government, was placed in a most perfect sanitary condition. In the latter part of August, 1866, a case of cholera occurred at Delaware City, the eastern terminus of the Delaware and Chesapeake Canal, distant from Fort Delaware one and a quarter miles, from which town the garrison obtained its mail and supplies of all characters. The first case occurred in the person of a canal-boatman, and spread to the inhabitants of the town, and an epidemic was instituted. Shortly afterward the town of New Castle, Del., Salem and Bridgeton, N. J., were infected with the disease, thus completely encircling the post within lines of cholera-infection. By my advice the commanding officer at the post instituted a rigid system of isolation. But one boat, with a picked crew, were allowed to leave the island each day; and of this crew but one man, the cockswain, a most reliable and intelligent man, was permitted to enter the town. By this man the mail and all necessary supplies were obtained, and by this boat were conveyed to the island. The commissary department having been most liberally supplied, no stores in large bulk were required to be transported to the island. Although the epidemic during the season was so often carried into the towns that have been named in the vicinity of Fort Delaware, as to institute two distinct epidemics, no case of cholera, or of any disease assimilating it, occurred upon the island, beyond the ordinary diarrhœa of the season, with but a single exception which can be most satisfactorily accounted for. The isolation of the post which had been instituted had been most rigidly maintained. And with the exception of the cockswain of the boat's crew already mentioned, no person but the post-surgeon had been allowed to leave the island. As post-surgeon, my services had frequently been asked during the prevalence

epidemic; and the precaution always had been adopted of changing clothing in an isolated shed upon one of the wharfs every time and returned to the island. Convinced of the non-infectiousness disease by some instances which seemed to me to be inexplicable, evening, on returning to the island weary and exhausted by a fatiguday's work, I went, in the clothes in which I had been working a cholera-patient in Delaware City, to my quarters, undressed, retired in the same room with my wife, at that time in extremely ate health, and the clothing remained in the room throughout the t. The next day my wife had a diarrhœa which she allowed to con- for two days without calling my attention to it; upon the third cholera was suddenly developed at an early hour in the morning; became fully collapsed, and reacted only after the most severe ggle. Disinfectants were freely used, every means of isolation employed, and no other cases occurred.

June, 1857, cholera re-appeared at the city of New Orleans, and lly spread through the Lower Mississippi Valley. During that h the disease was carried to towns upon the Mississippi, Arkansas, Missouri Rivers. We reproduce so much of the second report of stant Surgeon J. J. Woodward, United States Army, Circular No. me 10, 1868, Surgeon General's Office, as relates to the diffusion of lisease by the movements of troops:

PORT ON EPIDEMIC CHOLERA IN THE ARMY OF THE UNITED STATES DURING THE YEAR 1867.

By J. J. Woodward, M. D., *Assistant Surgeon United States Army.*

* * * * * * *

is well known that cholera prevailed extensively in the Army dur- the year 1866, causing over twelve hundred deaths among officers men. Circular No. 5, of 1867, giving a detailed account of the emic of 1866, was sent to each medical officer, in anticipation of possible return of the disease in 1867. It will be seen by consult- that document that cholera spread over the country during the 1866, extending as far westward as Forts Leavenworth, Riley, and son, and in the Southwest as far as Texas. In its progress the ase followed the lines of travel rather than any general westward se, and in the case of the Army it especially followed the move- ts of bodies of recruits, which were the most important movements infected points during the year. The compiler of Circular No. 5 hence an argument in favor of quarantine, and the Surgeon-Gen- in Circular No. 3, instructed medical officers to endeavor, as far as sible, to protect any threatened command by a proper quarantine. measures thus adopted, in conjunction with the hygienic precau- s directed in the same circular, undoubtedly saved many lives in Army, for the total number of deaths from cholera during 1867 s but two hundred and thirty, and it cannot be claimed that the ase in itself was less virulent during 1867, for the proportion of ths to the total number of cases was 1 death to 2.19 cases, while ing 1866 it was 1 to 2.22.

n a general way, it may here be said that the experience of the Army ing 1867 confirms the views in favor of quarantine, formed during 6, and especially confirms the opinions formed with regard to the ger of distributing recruits or other bodies of troops from an in-

fected point to other garrisons. An additional point, however, is suggested by the experience of 1867, namely, the possibility of disease re-appearing in the following year at places visited by it during an epidemic, if the most stringent hygienic precautions are not adopted.

* * * * * * *

Had the cases thus originating been the only ones, the mortality from the disease would have been comparatively small; but the unfortunate movement of infected troops and trains during July carried the pestilence across the plains to every post on the Arkansas R. and the Smoky Hill Fork, and three other notable instances of transplantation of the disease occurred: one on the route between Fort Gibson and Arbuckle, one in the case of the posts in New York Harbor, the third in that of certain recruits distributed from New York by way of New Orleans, through Texas.

At New Orleans, where cholera had prevailed extensively during 1866, among both citizens and troops, continuing during the summer and fall until January, 1867, it re-appeared among the citizens in June. The reports of the board of health record four cases during June, five hundred and seventy-one during the following six months. During the same period only six cases and three deaths were reported among the white troops, and but four cases and two deaths among the colored troops. The first of these cases occurred at Jackson barracks on the 4th August, and recovered; the second case, at the same barracks, on the 1st September, also recovered. After this no cases occurred until November. During November and December there were a few cases both at Jackson barracks and at Greenville, making, in all, but ten cases and five deaths during the six months in a garrison of over a thousand men. Besides these, one case, which recovered, was reported at Jackson barracks during January, 1868, and two cases of cholera and one of choleraic diarrhœa during the same month in Company A, Third U. S. Infantry, which had just arrived from Georgia.

In view of the prevalence of the disease among the citizens of New Orleans, this comparative immunity of the troops must be attributed to a great extent, to the stringent hygienic measures adopted in view of the approach of yellow fever. These measures are fully recorded in the reports on the yellow-fever epidemic.

At Fort Jackson, Miss., below New Orleans, one case, a colored soldier, who recovered, is reported during September. No particulars have been received.

During the month of June cholera also appeared among the freedmen on various plantations in the vicinity of Vidalia, La. The troops, however, escaped until October. During this month eight cases and three deaths are reported out of a strength of sixty-one officers and men.

At Vicksburgh, Miss., where cholera had prevailed among the troops during 1866, it re-appeared among the citizens during the month of June. The first case among the troops occurred on the 29th of the month, and died the same day. There were eight cases and two deaths among the troops during July; one fatal case during September; and in October two cases, which recovered; in all, eleven cases and four deaths, not including the fatal case during June. The average strength of the command during the six months was two hundred and seventy-seven officers and men.

At Madison, Ark., cholera appears to have been introduced by the body of a citizen dead of cholera, who was brought from Lindenburg for burial. Shortly afterward the disease appeared among the troops. Eight cases and three deaths are reported during July; two cases

death during August; in all, ten cases and four deaths; the average
ngth for the two months being seventy-five officers and men.
t Newport barracks, Ky., where cases had occurred during 1866,
mild cases are reported during June, both of which recovered.
re was also one fatal case during August. The average strength
he command during the six months was five hundred and nine.
es are said to have occurred in both Cincinnati, Ohio, and Coving-
, Ky., a few days before the first of these cases.
t Paducah, Ky., four cases and two deaths are reported during
gust out of a strength of one hundred and eight. No particulars
e been received.
t Saint Louis, Mo., where cholera had prevailed during 1866, it re-
eared among the citizens during the month of June, 1867. Cases
tinued to occur with increasing frequency during the summer and
. Only one case, however, is reported at the Saint Louis arsenal
of an average strength of one hundred and twenty-five. This case
urred during October; the man recovered.
t Jefferson barracks, near Saint Louis, where cholera had prevailed
nsively among the Fifty-sixth United States Colored Infantry dur-
the previous summer, two hundred and fifty-six cases and one hun-
d and thirty-four deaths having been reported, one case of cholera
six of cholera morbus occurred during July, all of which recovered.
eral fatal cases of cholera were reported, however, among Govern-
nt employés.
t may here also be mentioned that, during June, prior to their move-
nt from the post, a considerable number of cases of diarrhœa occur-
among the soldiers of the Thirty-eighth United States Colored In-
try at Jefferson Barracks. To the story of these troops we shall
ur.
On the 26th of October Companies G and H, One hundred and twenty-
h Colored Volunteers, arrived at Jefferson barracks for muster-out.
y had marched from Fort Bliss, Tex., across the plains to Fort Har-
, and thence been brought by railroad to Saint Louis, where cholera
s then prevailing. Two days after their arrival at Jefferson barracks,
lera appeared among them, thirteen cases and five deaths occurring
re the close of the month, and two cases and one death during No-
nber.
t Fort Riley, Kansas, where there had been fifty-nine cases and twenty-
en deaths of cholera, and six hundred and forty-one cases of diar-
ea and dysentery among the troops during 1866, a quartermaster's
ployé was attacked June 22, 1867, and died the same day. Company
of the Thirty-eighth Infantry, which left Jefferson Barracks June 9,
l reached Fort Riley June 12, had moved for Fort Harker on the 19th,
l Companies D and F, which left Jefferson Barracks on the 19th for
rt Riley, also left that place for Fort Harker on the 22d, arriving on
25th. All these troops were suffering much from diarrhœa, and
mpanies D and F left behind them when they moved a number of
n sick with diarrhœa. After this, however, no cases of cholera oc-
red at Fort Riley, where the most stringent hygienic means appeared
have been adopted, until July 11, when an employé of the Pacific
ilroad was attacked, and died the same day. He had just arrived
m the vicinity of Fort Harker, where cholera was then prevailing.
other cases occurred until November, when two colored recruits for
e Tenth Cavalry were attacked; one of them recovered; the other
d December 1. Of these men the first had arrived two days before
attack from Saint Louis, Mo., where he had been taken sick with

diarrhœa. No particulars have been received with regard to his ... rade. The regular garrison of Fort Riley, averaging for the six ... twenty-six white and one hundred and ninety-seven colored ... wholly escaped. At Fort Harker, Kansas, the disease appeared ... after the arrival of Companies K, D, F, and H of the Thirty-eigh... fantry. There were three cases and one death among the colored ... in June, fifteen cases and ten deaths during July and August. A... the white troops twenty-eight cases and twenty deaths are reported ... ing July and August. The average strength of the command ... and August was eighty-four white and one hundred and nine... colored troops. There were, also, at the post over four hundred ... master's employés, among whom were many deaths. The hygien... dition of the fort and its vicinity is reported to have been very ... the date of the outbreak of the epidemic.

Company K of the Thirty-eighth Infantry reached Fort Harker ... 22; Companies D and F arrived on the 25th; Company H, on the ... Companies A and B had been stationed there since May 16; and ... pany G, since May 17.

The first case among the troops at Fort Harker was a soldi... Company H, who was taken sick June 28, and sent to the post ho... On the same day, but a little earlier in the day, a citizen in the ... of the beef-contractor was attacked. He lived in a dug-out on the ... of the river, near the slaughter-pen, a mile and a half from the for... half a mile from the camp of the detachment of the Thirty-eighth. S... has been laid on this case in some of the appended reports, as sho... that cholera was not introduced into Fort Harker by the Thirty-e... Infantry; but the dates of the arrivals of Companies D, F, H, a... above given, perfectly accord with the theory that the detachme... the Thirty-eighth Infantry brought the germs of the disease with ... from Jefferson Barracks; and it has not been shown that the be... tractor's employé, living so near their camp, did not communicate ... with the newly arrived troops. At all events, the first cases amo... troops at Fort Harker were soldiers of the Thirty-eighth Infantry, ... were carried from their camp to the post hospital; and it was no... number of these cases had occurred that the disease began to spr... among the garrison of the post.

But whatever question may be raised as to the introduction of ch... at Fort Harker by the Thirty-eighth Infantry, there is no doubt ... mode in which the pestilence, once established at that post, was ... tunately, carried thence across the plains.

On the 28th of June, the same day on which the cholera appear... Fort Harker, a detachment of the Thirty-eighth Infantry, consis... Companies D and F, Bvt. Lieut. Col. H. C. Merriam in comman... Bvt. Lieut. Col. George H. McGill, assistant surgeon United S... Army, in medical charge, left Fort Harker to march by the Ark... River route to New Mexico.

At the close of the first day's march they reached Plum Creek, ... shortly after going into camp a case of cholera occurred among th... The command marched next day, but cases continued to occur ... until it reached Fort Lyon, Colorado Territory.

The posts visited on this route were Fort Zarah, Fort Larned, ... Fort Dodge, and the arrival of the detachment at each of these ... was promptly followed by the appearance of cholera. The death ... McGill, July 20, has prevented the receipt of the usual monthly ... of sick and wounded for this detachment, but it appears from the ... of Colonel Merriam that twenty-nine enlisted men were attacke...

died, out of a mean strength of two hundred and thirty-two enlisted
. With the exception of Dr. McGill and his wife, the officers and
r families escaped.

he headquarters of the Thirty-eighth Infantry, with Companies A,
nd K, remained at Fort Harker until the 20th of July. The first
of cholera among the troops at Fort Harker, already mentioned as
rring June 28, was a soldier of Company H. On the 29th another
occurred in the same company. On the 30th, another. July 1, five
s were reported; July 2, three. * * * July 4 there were two
s; July 5 and 7 each one case. After this no more cases occurred
his command for some days, although the disease still prevailed
ng other troops at Fort Harker, and among the quartermaster's
loyés and other citizens. July 20, headquarters, with Compa-
A and K, started across the plains with twelve officers, two hun-
l and twenty men, forty-four quartermaster's employés, and thirty-
n ladies, children, and servants. After crossing the Smoky Hill
k they were joined by the sutler of Fort Sumner, with a family of
persons, making in all three hundred and twenty-four souls. July 21,
he march, a soldier was attacked with cholera, and cases continued
ccur until July 30, when the command had reached a camp a few
s west of Fort Dodge, after which no more cases occurred among
troops. Up to this time there had been forty-six cases and seven-
deaths, all enlisted men. The rest of the party escaped, with the
ption of the wife of one of the officers, who was taken sick after
command reached Fort Lyon and recovered. The case reported
ng August was a man who had been detached with the mail between
s Larned and Harker, and who was brought sick to camp. In mak-
this march the command avoided communication with the posts
g the route, and, after the 25th of July, avoided the route taken
Colonel Merriam's detachment. Two detachments of the Thirty-
th Infantry are thus shown to have carried cholera with them
ss the plains by the Arkansas River route. It was by the first of
e that it was distributed to the military stations on the way.

n the 1st of July Colonel Merriam's detachment of the Thirty-
th Infantry arrived at Fort Zarah, and, on July 2 or 3, at Fort Lar-
, going into camp, within five hundred yards of the fort, and remain-
there for forty-eight hours. July 6 the first case occurred in the
rison at Fort Larned, and subsequently cases occurred at both this
and Fort Zarah.

ort Zarah being occupied as a picket post of Fort Larned, the cases
oth posts are included in the monthly reports of sick and wounded
Fort Larned. In all there were five cases and four deaths of white
ps during July; of colored troops, one fatal case during July and
during August. There were quite a number of cases among the
rtermaster's employés.

According to Brevet Major C. S. De Graw, assistant surgeon United
tes Army, Colonel Merriam's command arrived at Fort Dodge on the
noon of July 7 and went into camp a mile from the post, remaining
y-eight hours. An unsuccessful attempt was made to isolate the
mand when it was understood that cholera was prevailing in it.

During the evening of July 11, a Government employé, living about
e hundred yards from the garrison, was attacked; and on the 14th
ther; and diarrhœa became very prevalent among the citizens about
post. On the 18th several trains arrived from Fort Harker with
plies for the post, and a man accompanying one of these trains was
nd to have cholera. On the 21st a soldier of the garrison was attacked

while on guard duty some distance from the post and brought to the hospital. This was followed by other cases, and during the rest of July and the early part of August, twenty-five cases and fourteen deaths occurred among the troops. The mean strength for the two months was two hundred and twenty-six officers and men. There were also a number of cases among the citizens. The pestilence did not extend on its route to posts west of Fort Dodge.

Returning now to the neighborhood of Fort Harker, we find that Company G, Tenth Colored Cavalry, moved from Fort Harker July 5, leaving behind three or four men sick of choleraic diarrhœa; they went into camp at Wilson's Creek, about fifteen miles from Harker, where during the rest of the month they had fifteen cases of cholera, eight of which died during July and one in August. The command subsequently went to Fort Hays and became a part of the garrison of that post.

Company F, Third Infantry, in camp near Cow Creek, Kansas, at the terminus of the Pacific Railroad, not far from Fort Harker, reports seven cases and four deaths during July and one case during August, with a strength of sixty-eight officers and men; the disease was brought from Fort Harker. Company C, Tenth Colored Cavalry, at Camp Grierson, Kansas, on the Little Arkansas River, reports seven cases and three deaths during July, and ten cases and four deaths during August, the mean strength for the two months being seventy-eight men: the officers escaped. The disease is reported to have been brought to the camp by one of the messengers from Fort Harker.

Leaving, now, the vicinity of Fort Harker, we find cholera reported along the route of the Smoky Hill Fork, toward Denver, as far west as Fort Wallace. The posts on this route are Fort Hays, Downer's Station, Monument Station, and Fort Wallace. The first case at Fort Hays was a citizen who had just arrived from Salina, whither the cholera had extended from Fort Harker. On the same day, July 11, a colored soldier of the garrison was taken sick, and died the next day. During July, August, and September, thirty-three cases and twenty-three deaths are reported among the colored troops, whose mean strength during the three months was two hundred and fifteen men. September 1, a white soldier was attacked but recovered; the rest of the white troops, averaging, during the three months, thirty-four in number, escaped. Free communication had existed with Fort Harker previous to the appearance of the first cases, and trains with escorts of troops were continually passing from Fort Harker, by way of Fort Hays and the other posts on this route, to Fort Wallace and back again.

Notwithstanding the free passage of such trains, however, the detachment at Downer's Station, Kansas, escaped until August 9, when a supply-train *en route* from Fort Harker to Fort Wallace, accompanied by a detachment of Company B, Thirty-eighth United States Infantry, camped at Grinnell Springs, a small stage station about twenty miles from Downer's, and guarded by a party from that post. The day after the arrival of the train, two of the men at the stage station were taken sick, and were sent to the hospital at Downer's Station for treatment. One of them recovered, the other died. The mean strength of the command at Downer's Station during August was ninety-one officers and men, but no other cases occurred.

Company I, Thirty-eighth Infantry, which had been stationed at Fort Hays since May 25, left that place June 24, and established a post at Monument Station, Kansas. During July three cases and one death from cholera are reported in this detachment, the strength being reported one hundred and fifteen men. No particulars have been received.

une 1, 1867, a detachment of the Seventh United States Cavalry left
t Hays on an expedition to the Platte River, and after marching
r seven hundred miles, subjected to great hardships, went into camp
y 13, near Fort Wallace. A second detachment of the Seventh left
t Hays on the 12th of July, the day after the first cases of cholera
l appeared at that post, and, marching directly to Fort Wallace, went
) camp, July 18, with the first detachment. July 22 the first case of
lera occurred, and was rapidly followed by others, seventeen cases
l eleven deaths being reported during July and August, besides a
nber among the citizen employés. The mean strength of this detach-
nt during July and August was two hundred and twenty officers and
n. It is reported that most of the cases occurred among the soldiers
l employés who were debilitated and exhausted by the exposure of
: Platte River expedition. Notwithstanding the proximity of the
np of the Seventh United States Infantry to Fort Wallace, the gar-
on of the latter place wholly escaped, intercourse being restricted,
ugh not wholly prevented.

On the 8th of August, a detachment of the Fifth United States In-
ntry arrived at Fort Wallace from New Mexico, and encamped
out a mile west of the fort. The command is said to have been
althy on the road, with the exception of diarrhœa, after leaving the
Kansas; seven days before reaching Fort Wallace they passed, with-
t halting, a camp of colored troops, among whom cholera was pre-
iling. On the day of their arrival at Fort Wallace a case occurred,
lowed by others, making in all twenty-five cases and eleven deaths
ring the month. A quarantine hospital was established on the 10th,
which all the cases were treated. These cases were wholly confined
the detachment of the Fifth United States Infantry, which, at the
ne of its arrival, numbered about three hundred and forty-three
icers and men. None of the original garrison of Fort Wallace were
tacked.

* * * * * * *

Turning, now, from the plains to the route into Indian Territory, the
cord will be found equally instructive. One fatal case of cholera was
orted at Little Rock, Ark., during July. The patient had been in-
xicated, and the case is admitted to have been a doubtful one.

* * * * * * *

At Fort Smith, Arkansas, where cholera had occurred during 1866, it
appeared among the citizens August 28, 1867. The precautions
ken to prevent the disease from extending to a company of troops
re so effectual that but two cases occurred; the first September 16,
e second September 21; both proved fatal.

At Fort Gibson, Indian Territory, where cholera also prevailed dur-
g 1866, it re-appeared toward the close of June, 1867, among the In-
ans and negroes. These people, who were surrounded by the worst
gienic conditions, suffered severely till the close of July, when a nest
negro huts, where the disease had been most virulent, was burned,
d the survivors removed to a camp in the open prairie, after which
e disease abated. The troops, encamped in wall-tents on elevated
ound near the fort, escaped, having but two cases; one, a negro
ldier, attacked July 18, died July 23, and the other, a white soldier,
tacked August 18, died next day. The mean strength of the com-
and at Fort Gibson, during the six months, was one hundred and
fty-nine white and eighty colored troops.

Toward the close of June, just after the appearance of cholera among
e Indians and negroes, near the post, Company D, Tenth United

States Cavalry, left Fort Gibson for Fort Arbuckle; had much diarrhœa on the road, and one man died July 1, with symptoms of cholera. The company, bringing with them the dead body of their comrade for interment, arrived at Fort Arbuckle July 2. Immediately after their arrival three cases of cholera occurred in this company, and these cases and four deaths followed, during July, among the white troops stationed at Fort Arbuckle, one hundred and sixty-six in number.

On the 11th of June two companies of the Sixth United States Infantry left South Carolina for Indian Territory, and, going by way of Memphis and Fort Smith, set out to march from the latter post to Fort Arbuckle. On the 8th of July a messenger from Fort Arbuckle passed their camp, who reported the existence of cholera at Forts Gibson and Arbuckle. They prevented his intercourse with the detachment. They unfortunately, followed the road just passed over by Company D, of the Tenth United States Cavalry, and did not avoid their camps. July 15 cholera appeared among them in their camp on Sandy Creek, and before the close of the month forty cases and sixteen deaths occurred out of a command of one hundred and twenty-nine officers and men.

At Fort Columbus, New York Harbor, there were thirty-five cases of cholera and eighteen deaths during August and September. The first case occurred on the 21st of August. The patient was a recruit who had arrived the evening previous with a detachment of recruits from Saint Louis, Mo., where cholera was prevailing. One man had died on the road with symptoms similar to cholera, and the man attacked on arriving at Fort Columbus had been in attendance upon him.

Another recruit, who had also been in attendance upon the first patient, was sent to Fort Wood, Bedloe's Island, and was attacked with cholera shortly after his arrival there.

No additional cases occurred at Fort Columbus until the 31st of August, an interval of ten days, when ten new cases were admitted to the hospital, four of these cases occurring among a fresh detachment of recruits who had arrived on the 28th of August, three days previous.

At Fort Wood, Bedloe's Island, New York Harbor, there were three cases of cholera and four deaths during August and September. The first case occurred August 25; the last, September 24. Of these cases six were recruits, two belonged to the permanent party of the post, and two to the band. The first case was the recruit from Saint Louis, already mentioned.

One fatal case is reported at the Plattsburgh barracks, New York. The patient had just returned from Governor's Island, where he had been sent for trial by court-martial. He was attacked the night of his return, August 31, and died September 2.

On the 23d of November a detachment of several hundred recruits left New York Harbor, by steamer, for Texas. On the 30th another large detachment sailed.

The first detachment went on the steamer Raleigh, and reached New Orleans December 2 without sickness. Here one hundred and ten men were disembarked, but the detachment for Texas was kept on board, and, learning that cholera was prevailing among the citizens of New Orleans, an attempt was made to keep them isolated. December 3 the detachment was transferred to the steamer W. G. Hewes, and sailed for Galveston. During the 4th a number of cases of diarrhœa with watery discharges were observed, and in one case there were cramps and collapse, but none died. December 6 the vessel arrived at Galveston, the men were disembarked and placed in tents, but after three days, on account of bad weather, were transferred to the barracks of the Sis-

th Infantry at that post. December 11 the second detachment of nits which had left New York November 30 arrived at Galveston, after remaining a day, sailed for Indianola. This detachment had stopped a day at New Orleans, and after leaving that place cholera ared among them. One death had already occurred. This detach- t left at Galveston a number of sick with choleraic diarrhœa or al cholera. Altogether, twenty-two cases of cholera and eighteen of eraic diarrhœa were admitted to the post-hospital at Galveston from e detachments; five of the cases of cholera died. Three men of the nteenth Infantry, into whose barracks the first party of recruits received, were also attacked, but all recovered.

n the 13th of December a party of the recruits from Galveston arrived Iempstead, Texas, where fifteen cases of cholera appeared among n, with, however, but one death. The detachment that went to anola reports thirteen cases and two deaths of cholera at that post, the disease did not extend to the garrison. Finally, a party of these e recruits were quartered at Onion Creek, near Austin, December where nine cases and one death are reported during December, and fatal case during January in the same detachment, then at Indian- on their way to Brownsville, Tex. The extreme mildness of the s among these recruits cannot escape attention; there were among n, in all, sixty-three cases, and but nine deaths. This happy result, ch is attributed by the medical officer at Galveston to the use of nin in large doses, was observed also at Hempstead, where reliance ears to have been placed on camphor and opium pills; and at Onion ek, where calomel was employed in large doses.

he foregoing brief statement will serve to indicate the movements of lera in the Army during 1867. * * * * *

he total number of cases among the white troops during the year, nding the month of June, was three hundred and seventeen, of whom hundred and thirty-nine died; among the colored troops one hun- l and eighty-seven cases and ninety-one deaths. The mortality was, refore, 1 to every 2.28 cases for white; 1 for every 2.05 for colored ops. A comparison with the data of Circular No. 5 shows that the tality during 1866 was 1 to every 2.5 cases for white; 1 to every 1.9 es for colored troops. The proportion of deaths to cases during 1867 , therefore, rather larger for white and rather smaller for colored ops than during 1866.

he following medical officers fell victims to cholera during the year: vet Lt.-Colonel George McGill, Asst. Surgeon U. S A., died July 20, 7, near old Fort Lyon, Colorado Territory; Act. Asst. Surgeon Al- non M. Squire died July 29, 1867, near Fort Larned, Kansas.

* * * * * * * *

rom the report of the health-officer of the port of New York we learn t during the year three vessels arrived at that port upon which well- rked cases of Asiatic cholera had occurred on the passage from Eu- e, and one or two others had cases in many respects resembling that ease. After the arrival of these vessels there had been at quarantine hundred cases of cholera with one hundred and thirty-three deaths. n the 15th of November the steamship City of Cork arrived from twerp with ten cabin and three hundred and ninety-five steerage ssengers. On her arrival fourteen cholera deaths had occurred, and iety-two individuals were suffering from the disease. The first cases urred among Swiss passengers.

November 25, the steamship City of Washington arrived from Liver- ol with seventy-four cabin and five hundred and thirty-eight steerage

passengers. Seven cholera deaths had occurred, the first in an emigrant from Holland.

December 6 the ship Lord Brougham arrived from Hamburg with three hundred and eighty-three passengers, having lost seventy-two from cholera on the voyage.

During 1867, cholera having become epidemic on the island of Cuba, the United States ship of war Potomac became infected, the first death occurring October 19. By the Potomac the disease was carried to the Philadelphia naval rendezvous, but did not spread to the city.

After the subsidence of the epidemic of 1866 and 1867, North America enjoyed a cholera immunity of six years, when the disease was again brought to the Atlantic coast by ships.

CHAPTER VIII.

CHOLERA IN INDIA.

ie festivals and pilgrimages which are so frequent in India have been charged with regenerating and distributing cholera, as the h of armies is well known to do. From W. W. Hunter's Orissa we that twenty-four high festivals take place every year at Jugger-, below Calcutta. At one of them, about Easter, forty thousand lge in hemp and hasheesh to a degree that shocks the observers. " car festival" takes place in June or July. For weeks before the pil-s come trooping in by thousands every day. These are fed by the le-cooks to the number of ninety thousand; and over one hundred sand men and women, many of them unaccustomed to exposure or l labor, tug and strain at the car till they drop exhausted and k up the roads with their prostrate bodies. Day and night, ugh every month in the year, troops of devotees pour along the t Orissa road, from Calcutta, and for three hundred miles every ge has its pilgrim encampment. The parties consist of from ty to three hundred persons, and at the time of the great festivals e bands follow so closely as to touch each other. At least five-sixths females. Ninety-five out of every hundred are on foot, but occa-ally some great nabob and his ladies sweep past with forty or fifty nkeens, three hundred bearers, and fifty luggage-carriers; or a big h with his caravans of elephants, camels, horses, and swordsmen, l the indescribable confusion, dirt, and noise of Indian royalty. s of this great spiritual army march hundreds and sometimes sands of miles. They are drummed up from every town and vil-by about three thousand emissaries of the temple, who visit every ince and district in India in search of dupes. They often travel one sand to one thousand four hundred miles by rail, but generally have alk from three hundred to six hundred miles, and are always forced o doing a full day's journey. Many a sickly girl and feeble man dies on road, and all arrive lame, with their feet bound up in rags, plastered dirt and blood. They rush into the sacred tanks and into the and come out to dress in clean garments. They bathe every day, at the great festival as many as forty thousand run together into surf. The dead are buried in the sands, and the hillocks are cov-l with bones and skulls washed bare by the tropical rains. Disease death make havoc of the pilgrims, for they are badly lodged and rly fed. The temple kitchen has secured the monopoly of cooking the multitude; and the food is always presented before Jugger-h, and thus becomes holy food. When fresh, it is not unwholesome; it is too sacred for the least part to be thrown away. Large quantities n undergo putrefactive fermentation, and in forty-eight hours much t is a loathsome mass, utterly unfit for human use. It is then dan-ous even to a man in robust health, and deadly to the way-worn rims, half of whom reach the temple with some form or other of el-complaint. This food forms the chief subsistence of the pil-ms, and the sole nourishment of the beggars, who flock in thousands. s consumed by some one to the very last morsel. The natural drain-of the place is checked by sandy ridges, and the city is a very dirty . Each house is built upon a mud platform about four feet high, in

the center of which is a hole which receives the filth of the hou... The wretched inmates eat and sleep around this perennial source of ... These platforms are covered with rooms without windows or ro... lation; and into these caves of disease the pilgrims are mas... gether, at a temperature of 85° to 105° for seven months. Th... of agony and suffocation that take place in these putrid de... description. In some of the best of them, 13 feet long, 10½ feet ... and 6½ feet high, with but one entrance and no escape for the ... air, eighty persons pass the night. The stench is overpowerin... the heat like an oven. The head clerk of the district says that ... hundred thousand visited Puri, the city of Juggernaut, during th... son; and ninety thousand are often packed together for a week. ... thousand of these model lodging-houses. But in certain seasons ... can sleep out-doors. In the streets of Puri the spiritual army ... times slumber in regiments and battalions, covered only by th... cotton garment that clothes them by day. The soaking dews ar... wholesome enough; but the car-festival falls at the beginning ... rains, when the water pours down almost in solid sheets. Every ... and alley then becomes a torrent, or a stinking canal; and the wr... pilgrims are driven into the foul lodging-houses. Cholera (says Hu... p. 152) invariably breaks out. The living and dead are huddled ... gether, with a leaky roof above, a foul cess-pool below, and with ... just as much space as they can cover lying down. There are al... called corpse-fields around the town on which forty or fifty bodies ... often seen at a time. Carnivorous birds were found sitting around ... and wild dogs lounged about full of the flesh of man. The streets ... lanes presented many scenes of the most appalling misery and hum... tion. In one sudden storm the bodies of poor deserted women f... a dam to the insufferable filthiness from a thousand bodies whic... being washed down by the sudden shower. They were too weak ... and lay throwing their arms about in agony to the heedless passe... Some of them had been rolled about by the torrent till they had ... all their clothing, which is always mere wraps. Others lay quiet en... having apparently died without much struggling. The horrors ... the bishop of Calcutta, are unutterable.

But on the return journey the misery of the pilgrims reaches ... max. They have been plundered by priests and landlords, and ... along under their burdens of holy food, wrapped up in dirty cl... packed in heavy baskets or earthen pots. Every stream is flooded ... they often have to sit for days in the rain on the banks of rivers be... boat will venture to cross. Then their corpses lie thick around. ... accounts for much of the cholera about brooks, streams, and ... An English traveler counted forty festering bodies at one spot ... banks of one river. Some drag their weary limbs along till they ... from sheer fatigue; others crowd into the villages and halting-p... along the road, blocking up the streets, after the available sh... places are crammed to overflowing; and every night thousands ... no shelter from the pouring rain. Miserable groups huddle und... trees; long lines lie among the carts and bullocks on the mud... their hair mixing with the mud in which they lie; the bridges ar... ered with the sodden bodies; hundreds sit on the wet grass, not ... to lie down, and rock themselves to a monotonous chant throu... long, dismal night. It is impossible to compute the numbers tha... perish. Bishop Wilson thought fifty thousand succumbed; and H... that from one in eight to one in five died. Every year six times ... die there than fell at Waterloo.

is description will answer for all the great pilgrimages, especially to
isseram, opposite Ceylon; to Bigginnugar, near Bellary, in Southern
a; to Conjeiveram, near Madras; to Gaya, near Patna, on the Ganges;
e holy cities of Benares and Allahabad, farther up the river;
to Hurdwar, at its source. Also to the holy places along the river
ndda, which runs from Central India to the Arabian Sea, north of
bay; and to Punderpoor, below Bombay; and to hundreds of other
r shrines all over the country. So that cholera has abundant op-
unities for spreading over the whole of India every year, by many
armies of filthy pilgrims.

e customs of the Hindoos are very peculiar in some respects. It is
lated that one hundred and fifty millions of them always defecate on
ground; they have no privies or latrines, and even the native sol-
under British rule will not use them. A mutiny greater than that
57 might be produced if this necessary hygienic rule were rigidly
ced. Many thousands of tons of human excrement have thus been
deposited upon the open ground for some thousands of years. Out-
of the large cities of India, the bulk of the people always dwell in
ges of from two thousand to ten thousand inhabitants, and from five
s than twenty miles apart. The result has been the accumulation
normous amounts of fæcal matter, with a corresponding degree of
ration of the soil, and the consequent extensive pollution of water
very direction. The disinfection of India can only be a remote pos-
ity, and Europe must make up its mind to be scourged by cholera
that prolific source for many years to come, unless she protects her-
by quarantine and disinfection.

s regards the spread of cholera among the villages in India, Dr.
te, of Assam, a devout believer in and follower of Bryden, is forced
dmit (see "Sixth Annual Report of the Sanitary Commissioner with
Government of India," p. 8) that "the history of the outbreaks of
era is the same in every case. A case of sporadic cholera occurs in
indoo village; the patient is placed in the *smallest and closest apart-
t* of the house; a *large fire is lighted*, and as many people, friends
relatives of the sufferer, as the room will hold, assemble and squat
nd him solely for the purpose of praying, as there is seldom, if ever,
attempt to administer remedies. The patient during this time is
iting, defecating, &c., and *the fomites of the disease must necessarily
arried* off by the visitors to the crowded rooms and huts. After
e or four days, five or six new cases occur, and so on daily, until it
s through the whole village or villages to which the persons first in-
d belonged. Its further progress is limited or circumscribed by the
e system of quarantine maintained by the natives. As soon as it is
wn that any considerable number of fatal cases have occurred in any
ticular village, all the other places in the neighborhood cut off every
ercourse with it. Although they may have very dear relatives living
re, they will not go near, nor allow any person from the infected vil-
e to enter their own; and so rigidly is this precaution enforced, that
ny instances are known in which persons approaching a healthy abode
n one where cholera existed, have been violently assaulted."

Thus it will be seen that heat, filth, carelessness, and overcrowding
capable of making a non-contagious disease at least infectious. For
pherson says, (p. 20:) "While admitting that it is impossible to
st the evidence that cholera is contagious at certain times, I must
l assert that it is pestilent in a very slight degree in the better houses
l general hospitals of Bengal." Again, ordinary dysentery is not
ntagious; but Professor McLean (see Reynold's "System of Medicine,"

p. 627) asserts: "Dysentery, once established as an epidemic, is propagated by the effluvia from the evacuations of those affected in crowded hospitals. In most of the Hindostan barracks, the latrines were badly constructed, so injudiciously placed, and so illy kept as to materially in propagating both dysentery and cholera, by exposing healthy to the effluvia arising from the evacuations of the diseased. He has seen these disorders propagated in hospitals by the practice of preserving the evacuations of large numbers of patients for inspection by the medical officers at their morning and evening visits. No sanitary measure of a preventive kind yet tried has exercised a more beneficial effect on the health of troops in India than the improvement which has been introduced in the position, construction, and care of barrack-hospital latrines."*

The filthy habits of the Hindoos have carried cholera to the "Sanitaria" of Hindostan. Dr. Macnamara (see "Treatise on Cholera," p. 262) says: "Simla is the most beautiful hill sanitarium in the east. It is placed seven thousand feet up the Himalaya Mountains, near Hurdwar. Scarcely a year now passes without deaths from cholera occurring at Simla, and in 1866–'67 and 1868 it appeared in a decided form. Nor can we wonder at this, when, as late as 1865, the sanitary commissioners inform us that the "sides of the hills were everywhere studded with human excrement, and the smells which arose in every direction were a disgrace to a place which professes to be an asylum for the sick. The water was contaminated. In summer the dry beds of the mountain-torrents are places of convenience and filth. The edge of a hill at a few yards distance from the public road was lined with fæces, and evidently the resort of the numerous native servants of the location; and at some distance lower down the slope is the spring from which the water-supply of the summer residence of Her Majesty's viceroy. . . . many of the largest and best English houses in the vicinity is drawn. What must occur after every fall of rain is too obvious. Dr. Macrae has made an elaborate series of analyses of the waters of Simla which are naturally the purest he has found in India; but, as they reach the consumer, they are the most impure he has ever analyzed. The amount of nitrates in them is something appalling."

In no other country in the world are the pilgrimages so vast and numerous; and if cholera be portable at all, it must be carried far by the thousands and millions of pilgrims who annually traverse Hindostan in every direction.

In spite of all this, the transportation of cholera in Bengal is generally denied; but if the diarrhœal cases were tracked down as they have been in Europe and America, this point would be cleared up. Until very lately the English had no correct idea of the population of India, the highest estimate being two hundred millions, while it has now been proved to be over two hundred and forty millions. So that the movements of forty millions were unknown. The highest estimate of the population of Nuddea was five hundred and seventy thousand; it was found to be one million eight hundred thousand. That of Cuttack, near Jagernaut, was said to be two hundred and sixteen thousand; while it proved is one million five hundred thousand. All these uncounted millions escaped taxation and sanitary control. (See *official statement of condition of India during the year* 1871–'72.)

*According to Inspector-General John Murray, (See *Observations on the Pathology and Treatment of Cholera*, 1874, p. 56:) "Out of two hundred and ninety-one cases treated in the civil hospitals in Paris, from September 16 to November 10, 1873, one hundred and four, equal to thirty-five per cent. originated in the hospitals in patients under treatment for other diseases." There was probably less ventilation than in warmer weather.

ıe opening of the Suez Canal has caused the gradual rise of trade ·een Bombay and Trieste, Genoa, Constantinople, and Odessa, which not exist previous to 1869. (Ibid., p. 93.) Perhaps cholera has ed or may slip into Europe this way.

addition to the sea-borne commerce of India, there is the land-traffic Western India and the Punjaub to Afghanistan, Turkestan, and ia. The Afghan traders, called Provindahs, number twelve thou- fighting men with sixty thousand camels. If the route was safe, could make four trips a year instead of one, as they could proceed pendently, instead of being obliged to collect in strong caravans. y move toward the plains of India in October, and find their way to chief marts of India, down to Delhi, Benares, and even to Calcutta. traffic has existed from time immemorial, [and must often have to the importation of cholera into Persia by land.] The numerous held all over India, generally on the occasion of pilgrimages, are ıulants to trade. At the Delhi fairs fifty thousand people assemble; ımbala, two hundred thousand. There are one hundred and twenty- ın other fairs in the Punjaub alone, at which the assemblies number thousand and upward. In the Bombay presidency the fairs are l all over the country. (Ibid., p. 96.) "Much of the disease in India ne to bad water and bad drainage; and the mortality is fearfully ravated by the passion of the people for pilgrimages. Dr. Hunter's at work on Orissa has made an awful disclosure." (Ibid., p. 103.)

he marked resemblance between the progress of the great epidemic 1841 to 1849, and that of 1867 to 1873, has impressed many. The ge twelfth-year Juggernaut pilgrimage of 1841, in India, was supple- ıted by an equally great Hurdwar festival in 1843. According to Pro- ıor Dickson,* in 1844 cholera was known to have made an encroach- ıt upon Afghanistan, where its ravages were considerable. In May 5, it was at Kandahar, carrying off three hundred victims a day. In ıe, at Cabul; in July, at Herat. Some pilgrims going to Meschid, car- l it to that city in February, 1846. From Meschid it traversed Persia ın east to west, following the great roads, reaching Astrabad in May, 6, and Teheran in June, 1846; carrying off seven thousand persons seventy days. It is significant that, in 1846 and in 1831, cholera ap- ıred at the precise time when the pilgrims were flocking in from all es. At the same time, following the west coast of the Caspian Sea, November, 1846, it invaded the Russian provinces, attacking the same ıns as in 1823 and 1831. Here it stopped at the end of the year 46, and took up its winter-quarters upon the frontiers of Europe. For ·eral months nothing was heard from it; there were, indeed, some ıments of hope that it had disappeared entirely. But this illusion did t last. At the end of March, 1847, it started from its short sleep, and ıppeared on the shores of the Caspian; in May, 1847, it was among e Kossacks; in July, at Astracan; on July 21, at Taganrog, on the Sea Azof; at Kherson, at the mouth of the Dnieper; then at Kiev; and ın there went north to the Baltic. It arrived at Hamburg in August d September, 1848; and at New Orleans by three ships from Ham- ırg and Bremen, in December, 1848.

In the "Bavarian Official Report," p. 14, it is stated that in two hun- ed and fourteen towns and villages importation of the disease could proved, and that in eighty-one it was not. It is highly probable that telligent and industrious investigators will find importation in almost l instances.

* See *New York Journal of Medicine*, January, 1849, p. 9.

In the Madras, Bombay, and central provinces the course of ch... has generally been traced; in Bengal it has not, owing to its ... population, the enormous number of pilgrims who are passing in ... direction, the absence of a proper census until 1872, (when it was ... that there were forty millions more of people than had been supp... the utter untruthfulness of the Hindoos, and the entire neglect of ... sanitary authorities to track down the diarrhœal cases, and their ... less endeavor to connect merely the fatal cases with each other. ... fatal cases only of scarlet or typhoid fever were counted, no p... relation between them could be found. The reporters to the Sa... Commissioner of India in 1872 seemed so determined to prov... cholera is not portable and communicable in any way, that we re... page 33 of the Ninth Annual Report, Calcutta, 1873, "the l... contagion is not the law which governs the spread of small-pox an... than it is of cholera." In India, in the camps and jails, sanitary ... is forced to its utmost perfection; disinfection and cleanliness are p... to their most wholesome extremes. As soon as one or two ca... cholera occur in a barrack or prison, it is at once evacuated; the ... or prisoners are moved from camp to camp, at greater or lesser ... tances, as fast as fresh cases occur. If surgeons and hospital... ards in sufficient numbers could be left behind to supply pr... medical care to all the diarrhœal sick, the main body would s... freed from pestilence. Various places in India, especially thos... Moultan, near the great deserts, or high up on the mountains, have ... found nearly always to escape cholera, unless it is brought to the... large quantities; and to these exempt places it is contemplated to ... infected troops. The report attempts to draw positive conclusions a... the portability of cholera from necessarily imperfect materials. ... p. 2, report of 1872, we read: "The mortuary registration among ... natives is still confessedly imperfect; at the best it shows on... deaths from cholera and not the number attacked, and even the n... of deaths cannot be relied upon. No doubt, as a rule, they are ... underrated, for the fear of quarantine and other measures has pro... the people to conceal the disease altogether, or return it under an... name." On page 14 it begs the question about travelers and pi... when it says, "It must be remembered that hungry, weary, very ... and crowded together, as they often are, they are in the very cir... stances calculated to render them susceptible to cholera, if cholera ... about." On page 18, in answer to the not very infrequent repo... attacks among hospital-attendants, we are simply informed that "atte... ance on a cholera-case cannot confer immunity from the epidemic." ... inability to find water-pollution in India shows scarcely less pre... than prevailed in Munich up to a very late date. On page 27 we are ... that "even in a cantonment anything approaching to a strict quara... is simply impossible. Hundreds of grass-cutters and other servants ... go out and in daily. Supplies must come from without. Many ... military stations lie directly on the great high-road of communi... The mails must pass; all travelers cannot be stopped; nor can ord... traffic be arrested without interfering with the whole trade of ... country. In addition to those who must not be stopped, there are ... who cannot be stopped, and natives who desire to go in and out ca... little difficulty in doing so. A small bribe to the native police is ... sufficient to insure the breaking of the quarantine. In every ca... ment in which it was attempted there was a general admission ... was not strict, and that it was impossible to make it so." The entire ... sence of all allusion to the mendacity of the Hindoos, and of the ...

soldiers, who for purposes of licentiousness break the lines every
, and of all reference to the filthy domestic habits of the natives,
s that almost all the great causes of the propagation and transporta-
of cholera have been overlooked. All these criminal people, viz,
intine-breakers, faithless police-officers, and jolly soldiers, would
r die than admit the truth.

the northwest provinces, the sanitary commissioner, Dr. De Renzy, is
fectionist. In 1861, out of fifteen thousand prisoners, there were
undred and twenty-four deaths from cholera; in 1863, among fifteen
and five hundred and twenty, there were only one hundred and
six; in 1867, amidst fifteen thousand one hundred, only thirty-
in 1869, out of eighteen thousand five hundred, only eighty-eight;
72, out of sixteen thousand seven hundred, only forty-three deaths
cholera. "A striking example of the efficacy of sanitary measures,"
: "In Madras, from 1861 to 1866, from fifteen to thirty per thousand
of cholera; from 1867 to 1871, from less than one, to only four per
and died. It is justly said that such marked diminution in the
s from cholera in conjunction with great sanitary improvements
mere coincidence." Bengal, with her retrograde views, cannot put
lf in very favorable comparison with these results. In Bengal, p. 8,
were nearly nine attacks per thousand. On p. 11 we are told that
nost of the places where cholera was severe, cases of diarrhœa
frequent; and there can be little doubt that diarrhœa often
sents merely a mild form of cholera." Yet, if every one of these
t detected, no one can say where or how the fatal cases arise. We
re to assert, if medical officers were specially detailed to hunt up the
nce of events, and were possessed of the patience, fairness,
ity and knowledge of the one who has now unraveled most of the
ries of the epidemic of 1873 in this country, the views in Ben-
ould rapidly undergo a great change. As it is, we may soon
to prepare for another outbreak in Russia. In 1872 another epi-
of cholera swept over Northern India. There were one hundred
ixty-five thousand four hundred and fifty-eight deaths from it in all
ostan, eighty-five thousand of which were in the north. On p. 5
ad: "From Meshed, the capital of Persian Khorassan, the agent
s, on September 8: 'It is about a month since the cholera appeared
and more than two hundred persons die from it daily.' Astrabad,
lies to the west of Meshed, at the southeast corner of the Caspian
was also attacked. The disease was said to have been brought by
van of pilgrims who had lately arrived from Meshed." Hence
estilence seems again to have passed over the north Persian route,
tands in the same places which led to the outbreak in Russia in
and 1870. The great Juggernaut twelve-year pilgrimages will take
in 1877, and those of Hurdwar in 1879. At the former date, 1877,
ay expect an outbreak like that of 1865, coming out by way of
bay; and in 1879, another Hurdwar outbreak, which may reach
ia in 1881 or 1882.

CHOLERA IN CEYLON.

is island lies so near to Hindostan that the introduction of cholera
it has been studied with great care. From the official report
mbo, 1867] of the cholera-commission appointed by the governor of
on to inquire into the causes which led to the outbreak in 1866, soon
the twelfh-year festivals in India, we learn that the first cases were
rted from India to a village called Katys; that the outbreak com-

menced soon after, aided by other importations. There were eight deaths in July, thirty-one in August, one hundred and thirty-eight September, one thousand three hundred and four in Novemb thousand two hundred and seventy-one in December, three thousand hundred and eighty-seven in January, one thousand seven hundred sixty-seven in February, and seven hundred and seventy-five in M There were sixteen thousand two hundred and ninety-eight cases a thousand two hundred and seven deaths, in a population of three dred and fifteen thousand.

Of two hundred and twenty-six villages, only sixty-two escaped almost every village the disease was introduced from the centra or from an infected village. The whole evidence renders it quite that cholera was imported into Ceylon in 1866 from India. The mittee consisted of the treasurer, surgeon-general, chief govern agent, chief medical officer, and chief of police. They visited infected place, and got answers from the head-men of villages, pr medical men, old residents, and native doctors. The latter recog three forms of cholera—1. The patient vomits and purges, is q seized with cramps and collapse, and dies. Medicines are of no a 2. There is free vomiting and purging, but cramps and collapse on slowly, or not at all, and the patient may be saved. 3. vomiting and purging are not severe, and there are neither cramps collapse; the patients may recover without medicine. Diarrhœa dysentery prevailed during the epidemic of cholera, and made a p it. In the jail, where disinfectants were freely used, only nine occurred. Five of them recovered. The natives rarely take rem for they believe that cholera is a visitation of the goddess Amal anger is so excited that she will kill ten for every one who takes me The houses are surrounded by high hedges and fences, through it is almost impossible for the air to circulate. The compound grounds are approached by narrow, tortuous lanes. The houses co of rooms and verandas, looking toward a small space or yard center. The men and children sleep on the verandas, and the wom rooms with only one door and no windows; so that the ventilat very bad. Most compounds have a well, the walls of which are and broken as to give an easy access to filth and water from the clothes which are always washed near them. The inhabitants are industrious, but poor. Their breakfast is cold and often spoile left from the previous evening's meal. They have curry and r dinner and supper. The calls of nature are responded to by the and children on the surface of the ground, near the houses, which erally emits an offensive odor. The men go to the fields or othe habited places. They all wash every day, or second and third day richer classes often rub themselves with oil and lime-juice. There system of sewerage. The burying-grounds are frequently quite n villages. The bodies are, as a rule, put in graves only two or feet deep, which not only emit offensive smells, but are ofte up by dogs and jackals. In 1866 there had been no rain for and the soil was saturated with decomposed animal and vegetable ter, as none of the human ordure, &c., had been washed away fr unswept compounds. The epidemic lasted long because the were overcrowded and badly ventilated, the compounds dirty, and ered with human ordure near the fences. The air was generally and stagnant from the height of these hedges and fences. The evacuations and vomits were generally thrown out on the ground clothes of the sick were invariably washed at the wells in the

nds, and the water must have become contaminated. Then when a
: appeared in any house, there was every chance of the other occu-
ts contracting the disease. Most of the bodies were buried hur-
ly and at insufficient depths. Some graves in almost all burial-
unds were opened by dogs and jackals, so that bones, skulls, flesh,
s, cloths, &c., were often found scattered over the ground. The
doo priests refused to perform religious ceremonies over the dead,
hence many were exhumed and buried from fourteen to thirty days
r interment, when the anger of Amal was supposed to be appeased.
buyers and sellers performed the calls of nature near the fish and
:etable markets; and even in the European parts of the towns the
ies were often in close proximity to the wells. The evacuations and
iit of the sick were generally thrown into the former, and the epi-
ic spread rapidly by means of infection from the privies and foul
unds. From one privy belonging to a nunnery thus contaminated six-
i cases and fifteen deaths arose, because the evacuations of one girl
ing from an infected district, with diarrhœa, which soon turned
cholera, were thrown into it. She, however, finally recovered,
le fifteen of her companions died. If this first non-fatal case had
been detected the whole outbreak would have been an impenetrable
stery. It was calculated that the excrement of one hundred thou-
d people, left upon the ground, would impregnate the soil with an
ount of putrescible matter equal to the decomposition of fifty thou-
d corpses disposed of in the same way. It was concluded that hygi-
sts and sanitarians were wanted more than medical men and mis-
aries, unless the latter could also perform the duties of all. The
ed clothes of cholera-patients were usually cleansed at the wells of
houses of patients, but sometimes were given to the laundresses,
) washed them at the public tanks. In 1866, sixty-two infected ves-
arrived at Ceylon, having had twenty-four deaths on board and
lve after landing. Seventy-one thousand six hundred and eighty-
en emigrant-coolies arrived from India, and had eight hundred and
enty-one cases of cholera and six hundred and thirty-six deaths.
hundred and eighty-five deaths occurred among them along the
st-road, and three hundred and fifty-five along the central road.
re are cooly-sheds every mile along these highways, and deaths oc-
red at the second, eighth, fourteenth, eighteenth, twenty-third, thirty-
th, forty-third, fifty-second, one hundred and fifth, one hundred and
lfth, one hundred and seventeenth, one hundred and nineteenth, one
dred and twenty-eighth, one hundred and thirty-sixth, and one hun-
d and forty-sixth mile-sheds. Dead bodies were also found along
roads. The principal importation took place at Manaar, which is
ectly opposite Ramisseram, to which a great Hindoo pilgrimage in
uthern India takes place. Year after year sickness has been intro-
ed by emigrant coolies, and whole villages where they stopped
e been swept away. Many of these villages were very small, having
y thirty inhabitants; and in some of them only two or three people
nained alive.

THE INTRODUCTION OF ASIATIC CHOLERA INTO LARGE CITIES.

The discovery of the steps by which this takes place is often a
y difficult task indeed, and must always remain so. When it hap-
ns by means of diarrhœal cases these generally go long undetected,
l the majority of the non-fatal cases will always remain undiscovered.

In the last outbreak in Munich, in 1873 and 1874, the facts were as follows: The disease had commenced in May, 1873, in Vienna, before the opening of the great exhibition there. In June it was present in Rus as it had been for years, and in Bohemia, Galicia, Hungary, in the Ger man provinces of Bromberg, Marienwerder, and Danzig; also in Saxo in boats on the Elbe, and in two villages near Dresden. Hence the da ger of importation into Munich was great and increasing. On June 25 a American clergyman, Cliny Wood, came from Vienna, put up at the H Reinischen Hofe, with fully developed cholera, but was removed to t hospital, without being allowed to use the privy, and died in the af noon. On June 29, another person came from Vienna by way of Nur berg and died. Both he and Wood had lived at the Hotel Donau in Vie in which the well-known great outbreak occurred. A third person fr the Hotel Donau died June 24 at Neveto, Italy. The room occu by Mr. Wood and the railroad-car in which he traveled were clean and disinfected. No other fatal case occurred for twenty-one days, w on July 16, another case from Vienna, by way of Darmstadt, was ported into another hotel, and was quickly removed to the hospital, w he recovered. The third case was a street-sweeper in a distant pa the town. The fourth was an infant four months old, July 19; and fifth its mother, July 21, who had received a visit from an apparen healthy professor from Vienna. The house was washed and puri The sixth was a railroad-laborer, who sickened July 17 and died o 22d. The seventh, July 22, was a laborer, who recovered. T eighth case was a body-servant of Prince Leopold, who came with diarrhœa from Vienna on July 19, staid at the palace and th went on to Lindau, where he died on the 23d. His bed at the pa was burned, and disinfection and fumigation were carried out in t most thorough manner. The ninth case, July 27, was a locksmith wo ing at the central works of the state railroad. He had had diarrh for four days at home, and was then taken to the hospital, where he d on the 29th. There was no prevalence as yet of diarrhœa in Mun The sister of the last case, who had been with him during his sickne but lived at a distant house, took some of his soiled clothes to wa (although she denied it stoutly,) and had a severe diarrhœa for th days. In the same house a fatal case soon occurred, quickly follo by another. These three were the first fatal cases which could be trac to each other. The thirteenth case was fatal, in a cook in a distant ho and the cause of her attack could not be traced. The fourteenth c came from Papau, where no cholera was acknowledged; put up house where suspicious cases of diarrhœa had occurred, and died removal to the hospital. Her child, who slept with her, remained w The fifteenth case, August 2, occurred in the barracks of the cadet co in a servant, the origin of which could not be traced, but was follo by two other cases on the 10th and 11th of August. The first case the right side of the river Isar seemed sporadic, and did not prove pr ductive. Those on the left side spread gradually to others, and fin over the whole city. Such was the commencement of an epidemic wh culminated in three thousand and forty cases, of which one thousa nine hundred and twenty-three were called cholera, with one thous one hundred and fifty-five deaths, and seven hundred and sixty-t recoveries; and one thousand one hundred and seventeen were repo as cholerine, with three hundred and five deaths and eight hund and twelve recoveries. Two hundred and twenty-four house epidem were noticed with one thousand and eight cases, five hundred a eighty-one deaths, and five hundred and twenty-seven recoveries.

ıdred and fourteen houses had three cases each; forty-eight had r; twenty-seven, five; sixteen, six; four, seven; three, eight; three, e; two, ten; two, thirteen; and one house each had sixteen, twenty-en, thirty, thirty-one, fifty, and sixty-eight cases. In all there were) thousand and seventy affected houses with three thousand and forty es. Six hundred and twenty cases occurred on the north side of ıses, seven hundred and fifty-five on the east, eight hundred and ınty-six on the south, and five hundred and ninety-two on the west. ere were seventeen cases in cellars, six hundred and sixty-seven on ground-floors, eight hundred and sixty-seven in the second stories, hundred and thirty-nine in the third stories, three hundred and ninety-ht in the fourth, one hundred and sixty-three in the fifth, and nine-n in the sixth. The number of cases in the different stories depended irely upon the number of dwellers and their sanitary relations. There re one hundred and three epidemics confined to single stories of ıses, with one hundred and ninety-nine deaths and one hundred and hty-three recoveries. There were twenty epidemics confined to sin-rooms. The state of the ground-water was in opposition to the Pet-kofer theory. The drinking-water was found for the first time in ıich to have exerted an influence upon the spread of the disease. ıy cases proved that the disease was infectious at times, at others . The portability of the disease was often proved, but it was impos-le to connect all the fatal cases together. Some of the imported cases ·ed to produce no further result than the one death. Only ten sherwomen out of one hundred and two were affected, but disinfect-ts were generally used. Taking cold seemed to bring on attacks in) hundred and forty cases; mistakes in diet in two hundred and fifty-; the use of bad cheese and sausage in forty-seven; bad beer and ne in thirty-eight; poor vegetables in forty-two; and exposure to other es in two hundred and fifteen. Preceding diarrhœa was noticed) thousand and eighty-seven times. (See M. Frank's official report of) cholera-epidemic in Munich in 1873 and 1874.)

Hundreds of travelers must have come from Vienna to Munich, but ne of the diarrhœal cases were detected; and only a few of well-pro-ınced cholera. These travelers must have distributed themselves er many and distant parts of Munich. Soon diarrhœa, which had t previously existed, began to prevail, with here and there a severe fatal case of cholera in widely-separated houses. In order to have ıdied the outbreak thoroughly, every arrival from Vienna should have en watched, his place of residence become known to the health-offi-rs, and his wanderings to and fro recorded, and the results obtained. is is, of course, a very difficult matter in large cities, but it is not im-acticable; and one epidemic thus studied would doubtless clear up the obscure points about every outbreak of the disease. Until this done, nothing absolutely satisfactory will ever be known; and it will time and money well spent to do it.

In further illustration of this subject see British and Foreign Medico-ırurgical Review of July, 1872, for Dr. Parkes's account of the intro-ction of cholera in Southampton in 1865. On June 10 the steamship ıonah arrived from Alexandria, Malta, and Gibraltar. The crew and ssengers had perfect health until two days before arriving at South-ıpton, when several men became ill with severe diarrhœa, and one died cholera. This outbreak was attributed to foul water taken in at Gibral-r. The water had a disagreeable smell and taste. The firemen alone ank of it, and they alone suffered from decided choleraic disease. On ıne 8 one fireman drank a large quantity of this water, and early next orning was seized with vomiting, purging, and cramps. He became cold

and pulseless, and died in nine hours. On the same day six or seven other firemen, and on the following day three or four more, were affected with violent purging and some with vomiting. None of these men reported themselves to the medical officer, as they were afraid of being detained on board, and they all landed at Southampton and dispersed themselves over the town on the 10th and 11th of June. They were then seen by several medical men, who diagnosed the disease as the severest choleraic diarrhœa. Edward Palmer, one of the firemen in the same watch as the man who died on board, was attacked at his clean and pleasant home, on June 11, with diarrhœa, which was very severe for three days. He slept in an airy room with his wife and child, generally going to the closet outside, and occasionally using a chamber-vessel in the room. On June 13, his boy, aged three years, was suddenly seized, and died of cholera in six hours. The next day Palmer himself became worse, and died on the 15th. His wife escaped. There can be no doubt that the dejecta of cholera in large quantities must have passed from thirty or more persons into the sewers of the town; and in this way cholera was doubtless introduced into Southampton. Four cases, which could not be traced directly to the Poonah, occurred, and then the outbreak commenced, three weeks after the arrival of the vessel. The disease was not confined to the low and unhealthy parts of the town. Except the Poonah there was no traceable mode of importation. Except Palmer's child did not spread at first to others in close proximity. The water of Southampton was good, and the poison was probably disseminated through the sewers. At the lower part of the town the sewage accumulates, and gases are often forced back into the houses. Just before the outbreak the pumping of sewage had been discontinued while the sewers were being cleansed. The pumping was resumed just before the outbreak, and several tons of offensive fluid were daily poured down an open conduit into the outlet-sewer. The odor was overpowering, and several cases of diarrhœa and cholera occurred near the pumping-station, for which no other cause could be discovered than the effluvia from the sewage. The conduit was covered, and carbolic acid was largely introduced into the sewer. The cases, which had been very numerous, then lessened, and in six days the worst was over. Dr. Parkes expressed the belief that the outbreak was mainly caused by the fæcal effluvia from the sewers, into which cholera-dejecta had been largely introduced. It was also suggested that some cases were caused by the escape of poisonous gases into the houses through insufficient traps, and thus occasioned a few scattered cases.

Among the numberless instances in which cholera was brought into South Germany, in 1866, by the Prussian soldiers, after their march through Saxony, we select the following, (see Vogt and Smidt's Official Report, Munich, 1868, p. 14.) The last battle between the Prussians and South German troops took place at Waldbrunn, four miles southwest of Würzburg, on July 26. By August 4, about seventeen hundred Prussians had occupied the little town, but left it the same day, as they could get no supplies of food, or even of water. No deaths occurred among the Prussians while in the place, but many had diarrhœa and cholera. From house No. 2 a Prussian, suffering with vomiting and diarrhœa, was carried away. The first cases occurred near this spot. In house No. 21 about fifteen soldiers were quartered; some of them had diarrhœa and vomiting, and lay down on the beds of the house-people. Almost all this family sickened. In No. 28, they occupied a room which was subsequently used by the housewife. She became sick, and soon after, the rest of the occupants. In No. 46 a Prussian suffered with diarrhœa, and was taken to the hospital; the proprietor died on August 7. From No. 51 two Prus-

s were carried away sick with cholerine. In No. 65 a woman waited
a diarrhœal Prussian, who lay in the bed of her husband, who was
:ked soon after. The woman, who would not allow her bed to be
, escaped. In No. 72 the Prussians said the disease prevailed in their
es, and that they were glad to be away; two of them had diar-
a. In consequence of these occurrences, there was a sudden out-
k of cholera in various parts of the town. It seemed as if the
ase had assumed a mild, almost diarrhœal form among the Prus-
s, but that they gave off a material which was capable of pro-
ng fully developed cholera in other predisposed persons. On
unt of their painlessness, and the slight sickness which these ap-
ntly slight cholerines or premonitory diarrhœas produce, it is often
difficult to follow up the trail of importation. And from the occa-
al long incubation of the disease quarantine and isolation often fail
rther prevent the introduction and progress of the disease. When
Prussians marched away, the health of Waldbrunn was good; but
wo days cholera broke out in the severest manner. On August 6
lve persons were attacked in various parts of the town, all of whom
l. One strong, healthy man went out to his fields in the morning quite
l, and was suddenly attacked with great exhaustion; but diarrhœa
not come on until after his return home. He died the same evening,
noon a large, powerful female was attacked, and died in seven hours.
was nursed by her sister, a healthy, blooming woman, who died the
t day. In house No. 59, a strong peasant woman, who had worked in
fields in the evening, was dead at 7 a. m., and six out of seven of
family died in succession. On August 10 eighteen persons were
d in full collapse, and many with diarrhœa, which they were neglect-
and overlooking in the general consternation. The period of incu-
ion varied from two to eight days. Of five hundred inhabitants, one
dred and eighteen were attacked and forty-one died in fifteen days.
all of fifty-seven cases of fully-developed cholera, forty-two died and
een recovered. Of the forty-two deaths, one-fourth happened within
nty-four hours, another quarter the fourth day, and the other half
m the fourth to the twelfth days; but two cases lingered for three
eks. In ninety houses there were multiple cases in thirty-one. The
lage lay high, the dwellings were large, the streets were broad, the cel-
s were dry, the people were not poor, but the water-supply was very
nty. There was only one spring in the place, and that may have become
llied by the soldiers, who drew it dry in one day. In order to prevent the
rapid use of the water, no facilities for drawing it were allowed, but
ch villager had to bring his own well rope and bucket. Many of these
re soiled in some way, for the water soon acquired a suspicious look
d taste. There was no ground-water about the place, for water could
ly be reached at a depth of eighty feet. The houses were all scattered,
d separated from each other by yards and gardens. Although the center
the town seemed to be affected first, cholera quickly appeared in every
ok and corner of the place. There seemed not to be the slightest reg-
arity in the attacks as regards the running number or position of
e houses. But a connection of the cases could be traced easily, and in
other way, by the visits of soldiers, and of friends and relatives.
hus Goezner, of house No. 2, who had attended his brother on August
at house No. 72, was attacked on the 9th. These houses were situated
r apart. As before said, not a single Prussian soldier died in the vil-
ge during their short stay. The disease had a strictly diarrhœal origin.
all travelers could be as easily recognized as uniformed soldiers,
ere would be but little difficulty in tracing the importation of cholera
to towns and houses.

INDEX.

lieville, Ill., epidemic in, 234.
amson, Dr. M. F., report of cases, 279.
air County, Ky., epidemic in, 314.
ds in treatment, 6, 7, 17, 25, 26, 27, 28, 9, 30, 31, 32.
ds, as prophylactic, 6, 32.
beson, Dr. A. W., report from, 452.
tins, account of cholera, 520.
ents in diffusion of cholera, 42.
en, Dr. S., report of epidemic, 119.
giers, cholera at, 112.
xander County, Ill., epidemic in, 212.
abama group, 388. Contributors, 388. Initial cases, 388.
xander of Tralles, account of cholera, 520.
derson, Turner, M. D., cases reported by, 20.
natomy, morbid, of cholera, 36.
derson, Dr. S. M., report of epidemic, 170.
derson County, Tenn., epidemic in, 200.
derson, Dr. R. S., report on epidemic, 245.
derson, Dr. T., report of cholera group, 267.
phonia, 3, 4.
ea of infection in the United States during 1873, 91.
rkansas group, 126. Contributors, 126. Initial cases, 126.
rmstrong, Dr. C. L., report of cases, 351.
strakan, cholera at, 547.
terial cramping, 4.
tropia, 6, 8, 9, 17, 18, 19, 27.
ttendants upon cholera sick, 72.
tlanta, Ga., case at, 438.
tlee, Dr., of Lancaster, epidemic, 1854, 636.
uxiliaries to cholera attacks, 47.
urora, Ind., epidemic in, 383.
vritt, B. E., M. D., case reported by, 11, 12.
venues of infection, 57.

all on the communicability of cholera, 58.
ailey, Dr. P. F., statement by, 123.
ailey, Dr. F. K., report of epidemic, 188.
arrett, Dr. Wm. L., report of epidemic, 240.
ailhache, Dr. P. H., report of epidemic, 274, 293, 379.
allard County, Ky., epidemic in, 278.
arren County, Ky., epidemic in, 295.
ardstown, Ky., epidemic at, 311.
arbour County, Ala., 416.
altimore alms-house, epidemic of 1849, 612.
Baton Rouge Parish, epidemic in, 117. Epidemic of 1832, 579.
Benares, cholera at, 543.
Beaulieu, account of cholera in 1620, 524.
Bedford County, Tenn., epidemic in, 163.
Bemiss, Prof. S. M., editorial on cholera in New Orleans, 102, 103, 104.
Berry, W., Dr., cases reported by, 17, 365.
Birmingham, Ala., epidemic at, 409.
Black, Dr. J. E., report on epidemic, 137.
Bluffs, Ill., epidemic in, 231.
Boone, Dr. Jno., death of, 257.
Bowling Green, Ky., epidemic at, 264.
Boxville, Ky., epidemic at, 274.
Bourbon County, Ky., epidemic in, 284.
Boston, Ky., epidemic at, 310.
Boyle County, Ky., epidemic in, 318.
Bontius, account of cholera, 524.
Bombay, cholera carried to, 538.
Booth, Dr. D. W., report on epidemic, 121.
Boeltzer, method of producing ozone, 71.
Bruberger, examinations of cholera-dejecta, 43, 44.
Brown, report on quarantines on Gulf coast, 63.
Bryden, on cholera of 1869, 77, 79, 90.
Bromine as a disinfectant, 71.
Breysacher, Dr. A. L., report on epidemic, 133.
Bryant, Dr. J., report of epidemic, 170.
Breyles, Dr. J. F., report of epidemic, 210.
Buchanan, Dr. J. R., letter from, 252.
Butler County, Mo., epidemic in, 253.
Burial cities, 76, 77.
Burdon-Sanderson, experiments with cholera-dejecta, 44.
Bushire, cholera at, 541.
Bunker, Dr. W. H., report of epidemic, 355.
Buckingham, Dr. E. M., report of cases, 360.

Calomel, treatment by, 6, 7, 8, 10, 13, 14, 16, 17, 22, 25, 26, 27, 28, 29, 30, 31.
Carrollton, 112.
Carroll Parish, La., epidemic in, 117.
Capers, Dr. L. G. G., report on epidemic, 122.
Carroll, Dr. J. H., (deceased,) 132.
Carter County, Tenn., epidemic in, 209.
Cairo, Ill., epidemic at, 212.
Caseyville, Ill., epidemic in, 224.
Carmi, Ill., epidemic in, 227.
Carver, Dr. W. C., report on epidemic, 229.
Cadiz, Ky., epidemic at, 272.
Caseyville, Ky., epidemic at, 272.
Carter County, Ky., epidemic in, 274.
Caldwell County, Ky., epidemic in, 276.
Campbellsville, Ky., cases at, 294.

Carroll County, Ky., epidemic in, 295.
Cane Valley, Ky., cases at, 315.
Carthage, Ohio, cases at, 355.
Cantwell, Dr. A. W., health report, 455.
Caldwell, Assistant Surgeon, report of, 478.
Calcutta, 531, 533.
California, cholera in, 620.
Centerville, La., epidemic at, 118.
Celsus, account of cholera, 519.
Ceylon, cholera carried to, 536.
Cholera in children, 2.
Cholera at Halifax in 1872, 109; at Chezetcook, 109; at Jamaica in 1872, 110, 111.
Cholera on steamer John Kilgore, 121.
Cholera, history up to 1817, 519.
Cholera in Europe in 16th century, 525.
Cholera in India in 18th century, 526.
Cholera, history to 1823, 530.
Cholera carried into China, 537.
Cholera in Arabia and Persia, 541.
Cholera in North America in 1832, 563.
Chicago, cholera at, in 1832, 573.
Cholera, epidemic of 1833, 588; of 1848, 608.
Cholera in Cuba in 1833, 588.
Cholera of 1848 in Eighth United States Infantry, 615.
Cholera epidemic of 1853 and 1854, 634.
Crimean war, introduction of cholera, 624.
Cholera in India, 75, 79, 85, 521, 523, 526, 528, 530–534, 536–538, 594, 624, 641, 683, 689.
Cholera in Persia, 75, 78, 522, 541, 594, 595, 622, 624.
Cholera in Arabia, 527, 541, 624, 641.
Cholera in Egypt, 75, 521, 624, 643.
Cholera in Palestine, 522, 624.
Cholera in China, 527, 543, 594.
Cholera on islands, 524, 525, 527, 536, 537, 689–691.
Cholera in Europe, 77, 83, 84, 86, 87, 88, 89, 522, 525, 596, 597, 599, 603, 622, 624, 626, 629, 644, 646, 649.
Cholera in Russia, 80–83, 90, 543, 544–555, 595, 622, 624, 648.
Cholera in England and Ireland, 555–562, 596, 598, 600, 602, 604, 605, 606, 627, 630, 646, 657.
Cholera in North America, 563–593, 607–621, 638–639, 658–682.
Cholera in the Crimea, 624, 625.
Cholera in large cities, introduction, 691–695.
Chandler, S. T., Dr., case reported by, 16.
Charcoal as a disinfectant, 69.
Chicot County, Ark., epidemic in, 128.
Chattanooga, Tenn., epidemic in, 173.
Chicago, Ill., epidemic at, 213.
Chandler, Dr. W. T., note of cases, 294.
Chandler, Dr. S. Y., report of acid treatment, 295.
Christian County, Ky., epidemic in, 295.
Chattanooga, Tenn., garrison of, 480.
Cincinnati, Ohio, epidemic at, 329; early cases in, 353.
Clinical history of epidemic of 1873, 1.
Cleaver, W. W., M. D., cases reported by, 10, 11, 13.
Cleanliness, personal, in preventing cholera, 66.
Clarksville, Tenn., epidemic in, 170.
Clinton, Tenn., epidemic at, 200.
Clarksville, Mo., epidemic at, 252.
Clinton County, Ky., epidemic in, 2[illegible]
Clendenin, Dr. W., report of, 344.
Clark County, Ohio, epidemic in, 36[illegible]
Cleveland, Ohio, 370.
Clements, Surgeon B. A., letter from, [illegible]
Clark, Prof. Alonzo, 607–609, 633.
Cook County Hospital, cases at, 24
Common carriers, agency in diffu[illegible] cholera, 49, 50, 51, 52, 53.
Counties never visited by cholera, [illegible]
Communicability of cholera, mean[illegible] 58.
Columbia, Ky., cholera-infected p[illegible]
Cordon de santé, Austrian, 60.
Conservative disinfectants, 67.
Coprology of Hindoo and Persians [illegible]
Cordes, privies at Lubeck, 86.
Concordia Parish, La., epidemic in, [illegible]
Compton, Dr., statement of Nashv[illegible] demic, 151–154.
Connell, Dr., statement as to Nashv[illegible] demic, 153.
Cook, Dr., statement as to Nashv[illegible] demic, 155.
Cook County, Ill., epidemic in, 21[illegible]
Cole County, Mo., epidemic in, 254.
Collins, Dr. J. D., report of case, 27[illegible]
Cook, Dr. J. L., 272.
Covington, Ky., epidemic at, 27[illegible]
Columbia, Ky., epidemic at, 314.
Conklin, Dr. W. J., case, 358.
Columbus, Ohio, epidemic at, 36[illegible]
Collins, Dr. Wm. F., letter from, [illegible]
Columbus, Ga., letter from, 439.
Cœlius Aurelianus's account of cholera
Connecticut, epidemic of 1[illegible]
Columbia, District, epidemic of 1[illegible]
Creosote, treatment by, 26.
Craig, S. P., M. D., cases reported by
Craig, B. F., Dr., on disinfectants, [illegible] fication of water, 69.
Crooks, purification of drinking-wat[illegible]
Crute, Dr. H. P., report on epidem[illegible]
Cronchwait, Dr. G. D., report on epid[illegible] 168.
Craig, Dr. S. P., report on epidem[illegible]
Cunningham and Lewis, microscopic [illegible] physiological researches, 46.
Cunningham, Dr. R. F., report [illegible] demic, 222.
Cumberland, Ind., epidemic at, 3[illegible]
Culley, Dr. J. W., report from, 38[illegible]
Cuyler, Surgeon J. M., medical d[illegible] circular of, 470.

Danforth, Dr. J. N., microscopic exam[illegible] tions, 37–41.
Dale, Dr. I. R., report on epidemic, 1[illegible]
Davidson County, Tenn., epidemic [illegible]
Davis, Dr. J. W., report on epidem[illegible]
Day, Dr. E., letters on epidemic, 29[illegible]
Daviess County, Ky., epidemic in, 3[illegible]
Danville, Ky., case at, 390.
Dayton, Ohio, epidemic at, 358.
Daviess County, Ind., 385.
Daniels, Dr. Z. T., letter from, 41[illegible]
Dalton, Ga., case at, 439.
Davenport, Iowa, epidemic at, 45[illegible]

ota group, contributor's initial case, 2.
tzic, cholera at, 554.
ructive disinfectants, 67, 69.
ii, epidemic originating at a funeral ast, 85.
ctions, infectiousness of, 42.
Poorter, Dr. L., epidemic near Convent O., 113.
a, La., epidemic at, 115.
Creek, Miss., epidemic at, 123.
ii, Ill., epidemic in, 226.
rborn County, epidemic in, 383.
ent, Dr. J. J., report from, 406.
son, Texas, epidemic at, 449.
Moines County, Iowa, 460.
artment of the East, 470; of the Gulf, 2; of the South, 475; of Texas, 495.
boismont, account of cholera in Poland, 3.
roit, cholera of 1832 at, 571.
ware, epidemic of 1832, 583.
mark, cholera of 1850, 625.
nfectants, use of, 6, 66–68, 72, 114, 9, 131, 132.
usion of cholera-infection, 60, 61.
ntection by hot-air closet, 65.
during a cholera-epidemic, 73.
inage, 60, 65.
s during epidemic of cholera. 73.
che, account of cholera, 519, 520, 543, 0.
ke, Dr. D., cholera in Cincinnati, 586.
ation of cholera-infection, instance of, .
te, Dr. J. M., remarks on epidemic, 279.
lap, Drs. A. and C. W., reports by, 360
lin, cholera at, 560.

th, value as a disinfectant, 70.
stein, experiments on disinfectants, 70.
ar, W. S., M. D., case reported by, 23.
ar, Dr. W. S., cholera at Saint Louis, 7.
nburgh, cholera at, 560.
m, Dr. T. J., report one pidemic, 168.
rabethtown, Tenn., epidemic at, 209.
rabethtown, Ky., epidemic at, 283.
igrants, influence of, in diffusing chol-ra, 63.
igrants, arrival at New Orleans, 109.
igrants, agency in importing cholera New Orleans, 110.
glish authorities, action regarding chol-ra, 89.
gland, cholera in 1831, 543, 555.
demic which reached North America 1854, 621.
demic which reached North America 1848, 594.
demic which reached North America 1665, 639.
demic which reached North America 1854, 622.
ithelium, destruction of intestinal, 36.
ithelium, nasal passages, mouth, 36.
ithelium, pharynx and œsophagus, 36.
ithelium, villi of small intestines, 36.
ithelium, villi of large intestines, 36.
ithelium, urinary tracts, &c., 36.
Epithelium, pleura, abdominal cavity, choroidal plexuses, 36.
Epithelium, nerve tubes, ganglionic cells, gray matter, 36.
Epperson Springs, Tenn., cases at, 161.
Erskine, Dr. I. H., report on epidemic, 137.
Erskine, Dr. A., report of case, 138.
Erin, Tenn., epidemic at, 186.
Estrazulas, cholera during Paraguayan war, 56.
Etiology of the cholera-epidemic of 1873, 36.
Ettmüller, account of cholera, 526.
Evansville, Ind., epidemic at, 377.
Everett, Surgeon, death of, 570.
Everett, Surgeon, letters of, 571.
Ewen, Dr. C., report of epidemic, 117.
Exeter, Ill., epidemic in, 229.

Fabrics infected with cholera, 41.
Factors of cholera, 56, 57.
Farmington, Tenn., epidemic in, 171.
Fayette, Mo., epidemic at, 257.
Fairfield County, Ohio, epidemic in, 369.
Farquharson, Dr. R. J., letter from, 457.
Fenners, southern medical reports, 610.
Filtration of water, 68.
Filters, 68.
Fire as a disinfectant, 72.
Fifte, Dr. J. L., report on epidemic, 169.
Flies as porters of cholera, 71.
Flauvel, cholera in Russia, 80.
Flint, compulsory removals from infected districts, 73.
Fœti, effect upon, 5.
Foss, S. A., Dr., cases reported by, 21.
Formulæ, 6, 7, 10, 19, 23, 26, 29, 31, 158, 159, 167, 204, 323, 348.
Fort William, outbreak at, 530.
Friar's Point, Miss., epidemic at, 124.
Frazer, Dr. J. R., report of case, 137.
Franklin County, Kentucky, epidemic at, 265.
Franklin County, Ohio, epidemic in, 360.
Fryer, cholera in Surat, 525.
Frankfort, Ky., epidemic of 1832, 588.
Fyke, Dr. J. J., report on epidemic, 222.

Gastric juice, action on molicular matter, 45.
Gates, Dr. A. S., report on epidemic, 118.
Gallatin, Tenn., epidemic at, 159.
Galesburgh, Ill., epidemic in, 236.
Galt, Dr. T., report of epidemic, 236.
Garrard County, Ky., epidemic in, 300.
Galen, account of cholera, 519.
Germany, privies in, 85.
Georgia group, contributors, dates of cases, 437.
Glasgow, Ky., cases at, 296.
Glasgow, cholera at, 560.
Goa, cholera at, 524.
Goodletsville, Tenn., epidemic at, 157.
Goodell, on faulty privy accommodations, 70.
Goose Island, Ill., epidemic at, 212.
Grand Lower, Ill., epidemic at, 219.
Green County, Ill., epidemic in, 221.
Grafton, Ill., epidemic in, 225.
Greene County, Tenn., epidemic in, 181.
Greeneville, Tenn., epidemic at, 181, 210.

Gray, Dr. Chas., death of, 113.
Greer, Dr. J. A., report of epidemic, 253.
Grayson, Ky., epidemic near, 274.
Griffin Springs, Ky., cases at, 315.
Gratiot, Fort, cholera at, in 1832, 571.

Harlan, W. B., Dr., case reported by, 7.
Hayem, record of post mortems, 37.
Habits, individual, during cholera-epidemic, 73.
Hamburg, concealment of epidemic, in 1872, 87.
Hamilton, Dr. S. W., 115.
Harrington, Dr. J. F., (deceased,) letter from, 122.
Happy Hollow, Memphis, Tenn., 139.
Haines, Dr. R. B., report on epidemic, 168.
Hamilton County, Tenn., epidemic in, 173.
Hamblen County, Tenn., epidemic in, 202.
Hawkins County, Tenn., epidemic in, 209.
Hannibal, Mo., epidemic at, 251.
Hanna, Dr. W. M., report of case, 269.
Hazelwood, Ky., epidemic near, 273.
Hardin County, Ky., epidemic in, 282.
Harrodsburgh, Ky., cases at, 324.
Hamilton County, Ohio, epidemic in, 328.
Halderman, Dr. D., paper by, 360.
Hammond, Dr. J. F., letters from, 448–496.
Hastings, Marquis of, cholera in army of, 534.
Helena, Ark., epidemic at, 133.
Hemorrhage of bowels, 5.
Henry, Dr. S. L., cholera at Carrollton, 112.
Henry, Dr. George P., report on epidemic, 147. Statement as to epidemic, 151, 152, 153, 154.
Herriot, Dr. E. L., letter on epidemic, 226.
Henderson County, Ky., epidemic in, 268.
Henry County, Ky., epidemic in, 280.
Hendricks County, Ind., epidemic in, 384.
Henry Clay, steamboat, cholera on, 569.
Hinds County, Miss., epidemic in, 122.
Hickman, Dr. J. F., notes of cases, 312.
Hippocrates, account of cholera, 519.
Himalayas, cholera in the, 543.
Hour of attack, 3.
Högyes, experiments with cholera-discharges, 45, 46.
Hospital cholera, 66.
House epidemic at Calcutta, 85.
Hotel Donau, epidemic at, 86.
Houses, number infected in Berlin in 1873, 88.
Hogs, as scavengers, 65.
Hot-beds for cholera, 69.
Holly Springs, Miss., 124.
Holcombe, Dr. J. M., report on epidemic, 130.
Hooper, Dr. P. O., report on epidemic, 133.
Houston County, Tenn., epidemic in, 186.
Hollingsworth, Dr. H. M., report on epidemic, 201.
Howard County, Mo., epidemic in, 257.
Hodge, Dr. J. A., report of case, 269.
Hopkinsville, Ky., cases at, 295.
Hopkins County, Ky., epidemic in, 299.
Hollanders at Carthage, Ohio, 355.
Houston, Dr. M. H., epidemic of 1833, 591.
Hurdwar, the great nursery of cholera, 55, 528.
Hurdwar, fair of 1867, 55, 77.
Hubbard, Dr., notes on cholera at New Orleans, 104.
Hunt, Dr. J. M., report on epidemic, 121.
Hughes, Dr., statement as to Nashville epidemic, 154.
Huntington, W. V., letter from, 436.
Hubbard, Assistant Surgeon, letter from, 474.
Hygienic condition of locality, influence on epidemic, 59.

Ice, 68.
Illinois Group, contributors, initial cases, 212.
Importation of cholera-infected fabrics, 48, 63, 549.
Importation of cholera from Holland, 48, 356.
Importation of cholera from Sweden, 48.
Importation of cholera from Russia, 48.
Importation of cholera, 62, 63.
Impure water, test for, 67.
Impure water, effects of, 69.
Infectiousness of cholera, 36.
International sanitary conference, 47, 49, 54.
Inspectors, sanitary, 65.
Initial cases, dates of, in the United States for 1873, 91.
Initial cases at New Orleans, 93–97; remarks on, 97, 104, 105, 106.
Infection of food, 89; of cooking-utensils, 89.
Individuals from infected localities, care to be exercised by, 65.
India, early commerce with, 522.
Infectiousness of cholera announced by Emperor of Russia, 549.
Indiana Group, contributors, initial cases, 371.
Indianapolis, Ind., epidemic at, 379.
Johnston, Dr. Jas., report from, 449.
Iowa Group, contributors, initial date, 455.
Iron, sulphate of, as a prophylactic, 32.
Iron, sulphate, as a disinfectant, 69.
Italy, privies in, 85.

Jackson, John D., Dr., case reported by, 5, 321, 590.
Jaccond, observations, 5.
Jackson, Miss., epidemic in, 122.
Jefferson County, Ark., epidemic in, 130.
James County, Tenn., epidemic in, 180.
Jackson County, Ill., epidemic in, 219.
Java, cholera carried to, 537.
Jefferson Parish, 112.
Jennings, Dr. R. G., report on vital statistics, 130.
Jersey County, Ill., epidemic in, 225.
Jefferson City, Mo., epidemic at, 254.
Jefferson County, Ky., epidemic in, 267.
Jefferson, Dr. T. B., death of, 272.
Jennings County, Ind., epidemic in, 332.
Jepson, Dr. S. L., report from, 417.
Jessore, cholera at, 531, 533.
Jefferson Barracks, Mo., cholera at, in 1832, 578.
Jonesborough, Tenn., epidemic at, 202.
Johnson, Hon. A., case of, 210.

, Dr. Wm. A., report of epidemic, 273.
, Dr. H. G., report as health-officer,
.
an, Dr. M. H., report from, 409.
ernaut pilgrimages, influence of, 75.
ernaut, cholera at, 543.
liyohi County, Minn., epidemic in,
).
acky Group, contributors, 258; ini-
l cases, 259.
on County, Ky., epidemic in, 275.
r, Dr. D., paper on cholera, 284.
, Dr. R. E., report of cholera in 1832,
2.
ucky, epidemic of 1832, 587.
, 80, 81.
patrick, Dr. J. R., report on epidemic,
7.
man, Dr. D. N., report as health-officer,
9.
hen, Dr. H. W., letter from, 370.
ht, Dr. L. W., report on epidemic, 168.
x County, Tenn., epidemic in, 188.
xville, Tenn., epidemic at, 188.
x County, Ill., epidemic in, 236.
ler, Dr. C. E., report of case, 383.
e, Dr. J. W., report from, 382.
ourche Parish, epidemic in, 116.
e Providence, La., cholera at, 122.
rence, Dr. Thos., report of epidemic,
12.
range, Ky., epidemic at, 281.
caster, Ky., epidemic at, 300.
caster, Ohio, epidemic at, 369.
caster, Ky., garrison of, 481.
ke, N. G., M. D., cases reported by, 15,
6.
sis & Cunningham, microscopical and
hysiological researches, 46.
anon, Ill., epidemic in, 222.
anon, Ky., epidemic at, 305.
anon, Ky., garrison of, 492.
anon, Ky., instance of cholera-infected
ater, 59.
anon, Tenn., epidemic at, 169.
ow, Dr. J. H., report on epidemic, 132.
is, Dr. E. T., report on epidemic, 187.
is, Dr., death from cholera, 209.
is, Dr. N. B., report of cases, 295.
ke, Dr. N. G., notes of epidemic, 316.
mington, Dr. Cragie on cholera at, 560.
ington, Ky., epidemic of 1832, 587;
pidemic of 1833, 589.
ert, influence of local conditions, 59.
ert, immunity to disease after one
ttack of cholera, 61.
ne as a disinfectant, 69, 70.
tle Rock, Ark., epidemic at, 130.
thicum, Dr. D. A., report on epidemic,
23.
scomb, Dr. Thos., epidemic at Shelby-
ille, 165.
tle York, Ill., epidemic at, 237.
coln County, Mo., epidemic in, 255.
dsay, Dr. L., report of epidemic, 272.
coln County, Ky., epidemic in, 312.
ton, Ind., 384.
isiana Group, contributors, initial
ases, dates, 92.
Louisiana, Mo., epidemic at, 251.
Louisville, Ky., epidemic at, 267.
Logan, Dr. M., death of, 317.
Longview Insane Asylum, epidemic at, 357.
Lockland, Ohio, cases at, 358.
Lucy Depot, Tenn., epidemic at, 136.
Lucket, Dr. E. H., history of epidemic, 297.
Lucas County, Iowa, 460.
Lusitanus, account of cholera, 525.
Lytle, Dr. F. W., report on epidemic, 224.

Marshall County, Tenn., epidemic in, 171.
Marion County, Ill., epidemic in, 222.
Marion County, Mo., epidemic in, 250.
Marion County, Ky., epidemic in, 305.
Marion County (Ky.) Fair, 58, 59, 307.
Marion County, Ind., epidemic in, 379.
Macnamara, summary of morbid anatomy of cholera, 36.
Macnamara, observations on rice-water discharges, 42, 43, 70.
Macnamara, instance of drinking cholera-infected water, 44.
Macnamara, experiment for the preservation of cholera poison, 47.
Macnamara, on the diffusion of cholera, 54.
Macnamara, cholera diffused by drinking-water, 56, 535.
Macnamara, molecular matter in cholera-discharges, 42.
Macnamara, alkalinity of cholera-discharges, 42.
Macnamara, history of cholera, 77, 519, 530, 532, 533, 535, 621, 594, 640.
Murry, Hardwar festival of 1867, 55, 77.
Murry, communicability of cholera, 56.
Management of a cholera-infected house, 72.
Malarial origin and non-infectiousness of cholera, instances claimed, 1, 46, 98, 101, 104, 114, 116, 117, 129, 150, 172, 198, 217, 219, 220, 225, 229, 240, 252, 253, 255, 256, 273, 282, 284-292, 296, 311, 329-334, 350 386, 452, 460, 590.
Madison Parish, 114.
Mason County, Ky., epidemic in, 278.
Management of a cholera corpse, 72.
Mackville, Ky., epidemic at, 317.
Madison County, Ala., epidemic in, 380.
Manderville, Dr. W. R., note of, 475.
Madagascar, cholera conveyed to, 537.
Marsden, cholera in Canada, 563, 592, 614, 609, 633, 634.
Mackinaw, Fort, cholera at, in 1832, 573.
Maryland, epidemic of 1832, 583.
Massachusetts, epidemic of 1832, 581.
Maine, incident of the epidemic of 1832, 581.
Mauritius, cholera conveyed to, 536.
McMurray, Dr., statement as to Nashville epidemic, 154.
McCracken County, Ky., epidemic in, 260.
McMurtry, L. S., Dr., case reported by, 7, 305.
McCreary, Dr. I. R., letter from, 280.
Meridian, Miss., 124.
Memphis, Tenn., epidemic at, 137.
Memphis and Paducah Railroad, epidemic on, 137.

Menees, Dr. Thomas, statement of Nashville epidemic, 151, 154.
Metcalf, J. L., M. D., case reported by, 19.
Mecca, a distributing point, 75.
Meade County, Ky., epidemic in, 300.
Mercer County, Ky., epidemic in, 324.
Means, Dr. T. A., report of case, 414.
Mississippi group; contributors, initial cases, 120.
Mitchell, Dr. T. J., statement by, 123.
Mississippi County, Arkansas, epidemic in, 127.
Minutes of meeting at Nashville, 150.
Miller, Dr. B. C., report on epidemic, 213.
Miller, Dr. L. T., report of epidemic, 224.
Missouri group; contributors, 238; initial cases, 239.
Milk, infected with cholera, 85.
Millersburgh, Ky., epidemic at, 284.
Minnesota group; contributors, initial case, 440.
Milhau, Surgeon J. J., letter from, 471.
Millspring, Mo., epidemic at, 253.
Morrison, Dr. S. J., report of case, 137.
Morton, Dr., statement as to Nashville epidemic, 152.
Montgomery County, Tennessee, epidemic in, 170.
Monmouth, Ill., epidemic at, 237.
Moore, Dr. Isaac, letter from, 256.
Morgan County, Missouri, epidemic in, 257.
Mortality under various treatments, 31.
Morphia in treatment, 6, 7, 8, 9, 19, 20, 25, 27, 30.
Montgomery, cholera causes, 57.
Monall on sanitary condition of St. Petersburg, 85.
Monroe, La., epidemic at, 116.
Montgomery County, Ohio, epidemic in, 358.
Mount Vernon, Ind., epidemic at, 372.
Montgomery County, Alabama, epidemic in, 414.
Morton, account of cholera, 526.
Montreal, cholera at, 563.
Moscow, cholera at, 550.
Murfreesborough, Tenn., epidemic at, 165.
Murfrees, Dr. J. B., report of epidemic, 165.
Muir, Dr. James, letter from, 312.
Munich, epidemic at, in 1854, 622.

National Sanitary Bureau, necessity for, 64.
Narrative of cholera epidemic of 1873, 91.
Natchez, Miss., 124.
Nashville, Tenn., epidemic at, 141.
Nashville, Tenn., garrison of, 477.
Nedswetzky, experiments of, 32, 33, 90.
New York, epidemic of 1833, 60; epidemic of 1873, 62.
Nelson County, Ky., epidemic in, 310.
New Haven, Ky., epidemic at, 310.
Neal, Dr. Thomas J., health-officer, Dayton, O., 359.
New York quarantine, cases at, 466.
New York City, cholera at, in 1832, 567; epidemic of 1848, 611.
New Orleans, epidemic of 1832, 579; epidemic of 1833, 588.
New Jersey, epidemic of 1842, 582.
New Orleans, epidemic of 1848, 609.
Nijni Novgorod, cholera at fair at, 549.
Niemeyer, communicability of cholera, 58.
Nidus of cholera infection, 69.
Nitrous acid as a disinfectant, 71.
North Fork, Ky., cases at, 321.
North Vernon, Ind., epidemic in, 382.
Nurses upon cholera-sick, liability of, 46.

Obermeir, death of, 90.
Obion County, Tenn., epidemic at, 200.
Odin, Ill., epidemic at, 222.
Ohio group; contributors, 326; initial cases, 327.
Ohio, epidemic of 1832, 586.
Ohr, Dr. C. H., epidemic of 1854, 637.
Okawville, Ill., epidemic in, 233.
Oldham County, Ky., epidemic in, 281.
Ooltewah, Tenn., epidemic at, 180.
Opium, treatment by, 8, 9, 10, 11, 12, 13, 14, 22, 23, 25, 28, 29, 30, 31.
Opium, injudicious use, 26.
Origin of the epidemic that attacked America in 1873, 55.
Origin of cholera, 53.
Oribasius, account of cholera, 519.
Orenburg, cholera at, 544.
Osceola, Ark., epidemic at, 127.
Ouachita Parish, epidemic in, 116.
Owensborough, Ky., epidemic at, 297.
Owens, Dr. Henry, death of, 315.
Oxford, epidemic of 1854, 629.
Ozone, 70, 71; artificial production of, 71; test for, 71.

Palmyra, Tenn., epidemic in, 171.
Paducah, Ky., epidemic at, 260.
Paint Lick, epidemic at, 305.
Paschal, F., Dr., case reported by, 18; record of respiration in fatal case, 4.
Palmer, report on epidemic, 127.
Paulus Ægineta, account of cholera, 520.
Perkins's plantation, Ark., epidemic at, 133.
Penitentiary, Tennessee State, 142-147.
Penitentiary, Missouri State, 255.
Penitentiary, Ohio State, 363-368.
Peyton, Dr. Thos., report on epidemic, 140.
Pearse, Dr. S. H., report from, 372.
Pennsylvania group; contributors; initial case, 443.
Pelikan, cholera epidemic in Russia, 54.
Petlenkofer, communicability of cholera, 58-89.
Peters, J. C., Dr., factors of cholera, 56; water filter, 68.
Peters, J. C., Dr., article on origin of the epidemic of 1867-1873, 75.
Perry, Dr. A.W., on Mississippi quarantine, 107.
Persian caravanseries, 85.
Penitentiary, Arkansas State, 132.
Persian Gulf route, 542.
Pearse, Colonel, troops under, 528.
Pennsylvania, epidemic of, 1832, 586.
Pettenkofer, subsoil water, 628.
Philadelphia, 445.
Philadelphia, epidemic of 1832, 582.
Physicians, liability to cholera, 46.
Pierce, Dr. W. M., report of epidemic, 233.
Pike County, Missouri, epidemic in, 251.
Pittsburgh, epidemic at, 443.

grims' (Indian and Persian) influence in diffusion, 76, 79.
ie Bluff, Ark., epidemic at, 130.
inket, Dr. J. O., Nashville board of health, 150; statement Nashville epidemic, 153.
sasant Run, Ky., epidemic on, 317.
plar Bluff, epidemic at, 353.
rtage des Sioux, Mo., epidemic in, 256.
rtsmouth, Ohio, epidemic at, 368.
ey County, Indiana, epidemic in, 372.
lin, D. O., Dr., case reported by, 17.
rtability of cholera without infection of porter, 7.
tash permanganate, test of impure water, 67.
ison, specific, of cholera, 74.
rtuguese at Calicut, 524.
land, cholera in, 553.
rtability of cholera, instances of, 48, 55, 56, 58, 59, 62, 81, 82, 84, 85, 86, 99, 109, 110, 115, 117, 119, 121, 123, 127, 130, 131, 132, 137, 140, 147, 157, 159, 161, 163, 165, 166, 168, 169, 170, 172, 174, 180, 181, 186, 190, 196, 197, 200, 201, 209, 212, 213, 214, 215, 221, 222, 223, 224, 227, 228, 231, 232, 233, 234, 235, 236, 237, 238, 241, 244, 245, 251, 253, 254, 255, 257, 260, 261, 263, 264, 265, 266, 268, 270, 271, 273, 274, 275, 276, 277, 278, 279, 281, 283, 292, 293, 394, 295, 297, 299, 300, 301, 302, 303, 304, 305, 307, 308, 310, 311, 312, 313, 314, 315, 316, 317, 320, 321, 322, 324, 333, 345, 346, 349, 352, 354, 355, 358, 359, 360, 373, 378, 381, 382, 383, 385, 407, 408, 411, 412, 414, 427, 435, 438, 439, 440, 443, 444, 455, 461, 463, 466, 467, 485, 486, 495, 538, 539, 541, 542, 544, 545, 547, 548, 549, 551, 553, 554, 555, 556, 557, 564, 565, 566, 568, 569, 576, 577, 579, 580, 581, 582, 583, 584, 585, 586, 587, 589, 590, 591, 592, 608. 610, 611, 614, 615, 616, 617, 618, 619, 620, 633, 635, 636, 637.
rewitt, Dr. F. F., cholera at Saint Louis Hospital, 250.
richard, Dr. L., report on epidemic, 275.
rinceton, Ky., epidemic at, 276.
richett, Dr. J. W., note of epidemic, 299.
regnancy, effect upon, 5, 16, 25, 232.
revention of cholera, 62, 64.
rophylactics, 72.
rout, explorations of Caspian Sea, 78.
ringle, comparative mortality, 59.
usey, Dr. H. R., remarks on epidemic, 284, 300.
uerperal state, result of attack in, 5.
urification of water, 68.
ulaski County, Arkansas, epidemic in, 130.

Quinine as a prophylactic, 28.
Quarantine, 48, 62, 63.
Quarantine on Mississippi River, 106, 107, 111, 112.
Quimby, Dr. S. J., remarks on cases, 139.
Quinn, Dr. J. J., report as health-officer, 329.
Quebec, cholera at, 563.

Ratio of mortality of epidemic, 32.
Registrar-general of Great Britain, 47.
Rego, cholera in Brazil, 57.
Removal of individuals from cholera districts, 73.
Renzy, travels of cholera, 78.
Rainey, Dr., statement as to Nashville epidemic, 155.
Reiss, Dr. Charles, report of cholera cases, 245.
Records, Dr. S., letter from, 382.
Red Sea route, 639.
Rhazes of Bagdad, account of cholera, 526.
Rhode Island, epidemic of 1832, 580.
Rice-water discharges, constituents of, 42.
Riley, Dr. W. H., cholera at Algiers, 112.
Riverius, account of cholera, 525.
Routes of cholera, 75.
Robinson, Dr. G. L., report of epidemic, 170.
Roddy, Dr. T. H., report on epidemic, 180.
Rogersville, Tenn., epidemic at, 209.
Rock Island County, Illinois, epidemic in, 236.
Rock Island, Ill., cholera at, in 1832, 574.
Royster, Dr. C. G., report of epidemic, 263.
Round Hollow, Ky., epidemic at, 283.
Routh, on Russian epidemics in winter, 58.
Robards, Dr. Z. T., report of epidemic of 1833, 591.
Russia, privies in, 85.
Rutherford County, Tenn., epidemic in, 165.
Rucker, Dr. J. J., report on epidemic, 168.
Russellville, Tenn., epidemic at, 202.
Russell County, Kentucky, epidemic in, 324.
Russian emigrants, cholera among, 462.
Russia, cholera in, in 1829, 543.

Sawdust as a disinfecting agent, 72.
Salt as a condiment and disinfectant, 74.
Saint James Parish, Louisiana, epidemic in, 113.
Saint Mary's Parish, Louisiana, epidemic in, 118.
Saint Clair County, Illinois, epidemic in, 222.
Saint Louis County, Illinois, epidemic in, 240.
Saint Charles County, Missouri, epidemic in, 256.
Saint Bernard, Ohio, 354.
San Antonio, Texas, letter from, 448.
Saint Louis Barracks, Missouri, 496.
Saint Petersburg, cholera at, 551.
Sanscrit account of cholera, 519.
Sangermano, cholera at Rangoon, 529.
Saunders, Dr. H. J., report of epidemic, 148.
Saunders, Dr. D. D., report of case, 137.
Schiff, Dr., statement as to Nashville epidemic, 155.
Schell, Dr. H. A., report on epidemic, 159.
Scott County, Illinois, epidemic in, 229.
Scioto County, epidemic in, 368.
Scudder, Dr. J. A., report from, 386.
Scott County, Iowa, epidemic in, 455.
Scott, General, reports of cholera in 1832, 570, 573, 574, 575. 576, 577.
Sequelæ of cholera, 5.
Sevier, Dr. W. R., report on epidemic, 202.
Shelby County, Tennessee, epidemic in, 137.

Shelbyville, Tenn., epidemic at, 163.
Shop Springs, Tenn., cholera at, 170.
Shackelford, Dr., report of group, 279.
Shackelford, Dr. John, death of, 300.
Simpson County, Kentucky, epidemic in, 265.
Simons, Surgeon James, letter from, 473.
Sloan, Surgeon W. J., 475.
Smith, S. L. S., Dr., record of temperature, 3, 303, 485.
Smith, Dr. Alfred, notes on epidemic, 311.
Smith, Dr. Stephen, 635, 638.
Snow, on drinking-water, 58.
Soda, chlorinated, as a disinfectant, 72.
Soil polluted by excrement, 84.
South Carolina, epidemic of 1832, 584.
Sonnerat, account of cholera, 527.
Spencer, Dr. L. H., report on epidemic, 221.
Springfield, Ky., cases at, 317.
Springfield, Ohio, epidemic at, 360.
Spencer, Dr. E. V., report from, 375.
Styer, Chas., Dr., case reported by, 22.
Strychnia in treatment, 25.
Statistical tables, 34, 35.
Stimulants, effects of, in treatment, 73.
Statistics of arrivals at New Orleans prior to epidemic, 107, 108.
Statistics of emigration to New Orleans, 108.
Strother, Dr. R. C., 117.
Stanford, Ky., epidemic at, 312.
Steubenville, Ohio, 370.
Styer, Charles, assistant surgeon, report of, 481.
Stevenson, Dr. H., on cholera in 1832, 571.
Stone, Dr. Warren, cholera on Folly Island, 585.
Sulphurous acid as a disinfectant, 71.
Sumner County, Tennessee, epidemic in, 159.
Suddeth, Dr., death of, 266.
Supervising Surgeon Marine Hospital Service, 110–177, 240–274.
Serapion, account of cholera, 529.
Sumatra, cholera carried to, 537.
Sunderland, cholera at, 556.
Swedish emigrants, 440, 441.
Symptoms of cholera, 2, 3, 4.

Tadlock, Dr. A. B., epidemic at Greenville, 182.
Taylor County, Kentucky, epidemic in, 293.
Taylor, Dr. M. K., report from, 389.
Taylor, Dr., epidemic in China, 68.
Temperature, 3, 4.
Tepid stage, 4.
Tests for ozone, 71.
Tests for impurity of water, 68.
Tennessee group, contributors, 135; initial cases, 136.
Terre Haute, Ind., 382.
Texas group, 448.
Teheran, cholera at, 543.
Texas, epidemic of 1848, 616.
Thiersch, experiments with cholera dejecta, 44.
Tholozan, physician to Shah, 75, 79.
Thudicum, constituents of rice-water discharges, 42.
Thibodeaux, epidemic at, 116.
Thornton, Dr. G. B., report of [illegible] cases, 138.
Thomas, Dr. E., report on epidemic, [illegible]
Thompson, Dr. C. A., report on epidemic, 254.
Thomas, Dr. J. L., letter from, 256
Thompson, Dr., report of case, 269.
Tillman, Dr. J. A., report of epidemic [illegible]
Tollulah, epidemic at, 114.
Topaze, frigate, infected with cholera
Toner, Dr. J. M., notes on the epidemic 1832, 583.
Transmissibility of cholera, 47.
Travels of cholera, 75.
Trezevant, Dr. George T., 114.
Troy, Mo., epidemic at, 255.
Trigg County, Kentucky, epidemic in [illegible]
Treatment of cholera, 6, 7, 8, 9, 10, 11, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, [illegible] 25, 26, 27, 28, 29, 30, 31, 32, 101, 10[illegible] 114, 118, 128, 129, 149, 152, 158, 159, [illegible] 165, 167, 168, 169, 188, 190, 191, 192, [illegible] 196, 201, 203, 204, 210, 216, 222, 226, [illegible] 246, 255, 256, 264, 267, 269, 274, 2[illegible] 290, 295, 296, 309, 311, 314, 316, 31[illegible] 348, 360, 367, 375, 383, 385, 387, 41[illegible] 438, 441, 481, 488, 489, 490, 495.
Turner, Dr. R. J., report on epidemic
Tucker, Dr. G. B., death of, 226.
Typhoid stage of cholera, 4.

Union City, Tenn., epidemic at, 2[illegible]
Union County, Tennessee, epidemic 208.
Union County, Kentucky, epidemic
United States Army, epidemic of 1[illegible] 470.
United States Army, epidemic of 1[illegible]
Uræmia, 5.
Uterine complications, 5.
Utah Territory, cases in, 461.

Vanderpoel, Dr. S. O., New York Quarantine under, 63, 467, 468.
Vanderpoel, Dr. S. O., letters from
Von Gietl, observations of cholera epidemics, 89.
Vandeman, Dr. J. H., report of epidemic 173.
Vanderbergh County, Indiana, epidemic in, 377.
Van der Heyden, account of cholera
Vegetables, use of, during epidemic
Versailles, Mo., epidemic at, 257.
Vibriones, 67.
Vinegar as a disinfectant, 72.
Vienna Exposition of 1873, cholera epidemic, 87.
Vidalia, epidemic at, 117.
Vicksburgh, epidemic at, 121.
Villa Ridge, Ill., epidemic at, 257
Vigo County, Ind., epidemic in, 382
Virginia, epidemic of 1832, 584.

Washers of cholera-infected clothes, 48, 89, 232.
Washington County, Miss., epidemic 123.

hington County, Tenn., epidemic in, 2.
hington County, Ill., epidemic in, 3.
hington County, Ky., epidemic in, 7.
hington, Ind., 385.
trace, Tenn., epidemic at, 165.
lace Cross-Roads, Tenn., epidemic at, 1.
ker, Dr. J. R., report on epidemic, 0.
dner, Dr. H., report on epidemic, 213, 8.
ne County, Mo., epidemic in, 253.
ren County, Ill., epidemic in, 237.
d, Dr. J. A., report of epidemic, 255.
ren County, Miss., epidemic in, 121.
ren County, Ky., epidemic in, 264.
ren, Dr. J. P., death of, 268.
ren, J. S., M. D., cases reported by, 8, 6, 484.
naw, cholera at, 553.
ter, agency in diffusion of cholera, 1, 67, 85, 87, 134, 140, 147, 172, 185, 187, 16, 283, 303, 308, 324, 384, 408, 412.
ter from wells, 67, 218.
ter from cisterns, 67, 279.
ter, rain, impurities of, 68.
ter, snow, impurities of, 68.
ter of rivers, marshes, &c., 68, 114, 185.
ter, spring, impurities, 68, 209, 285.
ter for domestic use, 49, 74.
ter, effects of, works on Calcutta, 85.
ter-supply of Nashville, Tenn., 143, 144, 45, 154.
lls, management of, during an epidemic, 5.
bster County, Ky., epidemic in, 300.
st Virginia group, contributors, initial ase, 417.
White, Dr. C. B., report on cholera of 1873, 93, 98, 102.
Whitehead, Dr. C. R., report, 117.
Whitehead, Dr. P. F., report on epidemic, 122.
White Hall, Ill., epidemic at, 221.
White County, Ill., epidemic in, 227.
Wheeling, W. Va., epidemic at, 417.
Winsett, Dr., statement as to Nashville epidemic, 153.
Wilson County, Tenn., epidemic in, 169.
Williams, Dr. E. R., death of, 296.
Winston, Dr. G. B., note in treatment, 30.
Wilson, Dr. F. C., 305.
Wight, Dr. E. M., report on epidemic, 177.
Wright, Surgeon J. J. B., letter of, 616.
Winfrey House epidemic, 314.
Wright, Dr. W. M., report on cholera among convicts, 147.
Wood, Dr. H. C., on disinfectants, 70.
Wood, Dr. M. W., cholera autopsies, 37.
Wynne, Dr. James, report on epidemic of 1848–'49, 620.
Wood, Dr. M. W., letter on causes of epidemic at Chicago, 217.
Woodville, Ky., epidemic at, 263.
Woodburn, Ky., epidemic at, 265.
Worthville, Ky., epidemic at, 295.
Woods, Dr. J. D., letter from, 296.
Worth, General, death of, from cholera, 616.
Woodward, Dr. J. J., report on cholera in United States Army in 1866, 664.
Woodward, Dr. J. J., report on cholera in United States Army in 1867, 673.

Yankton, Dak., epidemic at, 462.
Young, Dr. R. E., report of epidemic, 254.

Zinc, sulphate of, as a disinfectant, 72.

C.

BIBLIOGRAPHY OF CHOLERA.

BY

JOHN S. BILLINGS, M. D.,
ASSISTANT SURGEON, U. S. A.

SURGEON-GENERAL'S OFFICE,
Washington, D. C., April 1, 1875.

ENERAL: I have the honor to submit the following list of books, and nal and periodical articles, relating to cholera, compiled in accord- with your directions on a request to that effect made by Assistant geon Ely McClellan, United States Army, in July, 1874. This list, ough by no means complete, is believed to be sufficiently extensive eet the wants of the great majority of inquirers.

he library of the Surgeon-General's Office at Washington is compar- ely rich in the literature of this subject, a good foundation having n laid several years ago by the purchase of the collection of works ting to epidemic diseases made by the late Professor Baart de la lle, of Groningen, and the majority of recent treatises on the subject e since been added as they appeared. The files of medical journals he library which have been examined for this purpose comprise a le over 8,000 volumes, being about 75 per cent. of all which have been olished, and the majority of those still wanting were either published r to 1830 or are of minor importance.

As a rule, titles are given only of works which relate mainly or entirely cholera. Hardly a treatise on epidemics, public hygiene, the practice medicine, or the diseases of India, has been published since 1832 that s not contain more or less with regard to this subject, but it would useless to attempt to give this class of references in a compilation of s character.

As it is, the majority of readers will probably think that the magnitude the work is much greater than its importance; but it must be remem- ed that no two men would agree as to what should be omitted, nor ve I had either the time or the material to make a careful selection. hile hundreds of editorial notes, cholera-news items, extracts, &c., ich are scattered through the medical journals of 1831–'34, 1848–'50, 4–'57, 1865–'67, and 1873–'74, have been omitted, I have retained ne which, although of little interest in themselves, may serve to give lew to an inquirer, especially as regards the geographical distribution cholera.

As is well known, there are two distinct diseases which have been lled cholera, or cholera morbus; and while the classification can in st cases be made from the title and date alone, this is by no means ays the case, and I am sure that some of the following titles relate the sporadic and non-epidemic disease rather than to the true Asi- ic pest. The titles given under the heading "Cholera prior to 1817" late almost entirely to the sporadic form of the disease. The classifi- tion made use of is but a rough one, but will, I think, be found actically convenient, at least for verifying the titles of books, and om the collector's and librarian's point of view; and, as one object this list is for use as a means of completing the collection of this rary on this subject, it was considered advisable to bring it into ok-sellers' form as much as possible, while affording enough classifica- on to facilitate the work of literary investigators. No one of the latter ass would find any classification made by another person suited to his ants, and I do not flatter myself that I have hit the golden mean, pecially as I have been compelled to make my classification largely

from the data furnished by the titles themselves, on account of lack of time and opportunity to examine the original documents.

The classification made use of is as follows:

I. History, statistics, and bibliography.
   A. Works published prior to 1817, mostly relating to sporadic cholera morbus or cholera nostras.
   B. Periodicals.
   C. History and statistics, general treatises, and essays.
   D. Accounts of cholera, in particular localities.
II. General treatises on cholera.
III. Causes and prevention.
   A. Causes, theories of causation, and contagion.
   B. Hygiene and methods of prevention.
IV. Pathology and pathological anatomy.
V. Complications, sequelæ, and cases.
VI. Treatment.
   A. General.
   B. Special.

All the periodicals and transactions referred to are in the library of the Surgeon-General's Office at Washington.

With regard to books and pamphlets, the letters following titles have the following meanings:

L. in Library Surgeon-General's Office.

C. in same library as a special deposit from the Congressional Library.

C.L. in the Library of Congress.

An asterisk (*) prefixed signifies that the work is an inaugural thesis or dissertation.

I am indebted to Dr. Salvatore Caro, of New York, for some Italian titles, which are indicated by the letters S. C.

In each subdivision except I. D. (accounts of cholera in particular localities) and VI. B. (special treatment) the titles are arranged alphabetically under the name of the author, anonymous works being placed separate under the first word of the title excepting the article.

Any one noting errors of omission or commission will confer a favor by pointing them out to the compiler.

Very respectfully, your obedient servant,

JOHN S. BILLINGS.
Assistant Surgeon, United States Army.

Gen. J. K. BARNES,
Surgeon-General U. S. A.

I.—HISTORY, STATISTICS, AND BIBLIOGRAPHY.

A.—WORKS PUBLISHED PRIOR TO 1817.

olphi. *De passione cholerica. *Lipsiae*, 710.

aeldung (J. H.) *De cholera. *Jenæ*, 697.

ıpuhn. *De cholera humida. *Göttin-*, 1760.

ıbar (P. A.) *Dissertation sur le choléra norbus. 4°. *Paris*, 1815. L.

ncel (G. C.) *Sur le choléra-morbus. 8°. *Strasbourg*, 1816. L.

ıuer d'Adelsbach (J. J. H.) *De cho-era. 4°. *Altdorfii*, 1751.

ckwith (S.) *De cholera. 8°. *Edin-burgi*, 1797. L.

ılius (J. T.) *De cholera humida. 4°. *Göttingae* [1747.] L.

[Quoted as by BOHN.]

ohn (J.) *De cholera. 4°. *Lipsiae* (1666). L.

ontius (J.) De medicina Indorum. 4°. *Lugd. Bat.*, 1718. L.

[De cholera, pp. 69–71.]

ovy (J. J.) *De cholera morbo. 4°. *Parisiis*, 1808. L.

uisson (F.) *Dissertation sur le choléra-morbus. 4°. *Paris*, 1813. L.

arter (A.) *De cholera. *Edinburgi*, 1794.

hevans (J.) *Propositions médicales sur la coquelluche et le choléra-morbus. 4°. *Paris*, 1806. L.

urtis (C.) An account of the diseases of India, as they appeared in the English fleet, and in the naval hospital at Madras in 1782 and 1783. 8°. *Edin-burgh*, 1807. L.

[Contains a copy of a letter of J. Paisley on the cholera, dated Fort St. George, Feby. 12, 1774.]

Deroissart (P. J.) *Dissertation sur le choléra-morbus ou cholérrhagie. 4°. *Paris*, 1814. L.

Deys (G.) *Dissertation sur le choléra. 4°. *Paris*, 1812. L.

Dickson (P.) *De cholera. 4°. *Edin-burgi* [1750]. L.

Diemer (van). *De cholera. *Lugd. Bat.*, 1670.

Douglass (C. A.) Cur der Gallenruhr (Cholera).

[Der Arzt, Hamburg, 1764, XII, pp. 358–361.]

Drechsler (C. H.) *De cholera. 4°. *Vit-tembergae* [1802]. L.

Duerr (F. G.) *De cholera. 4°. *Jenae*, 1760. L.

Dufau (J. J. F.) *De cholera morbo. 4°. —, 1774.

Dummett (E. J.) *De cholera. 8°. *Edin-burgi*, 1799. L.

Eichler (J. M.) *De cholera. 4°. *Jenae*, 1735. L.

Engelmann. *De cholera. *Basileae*, 1662.

Esménard (P. M.) *Dissertation sur le choléra morbus. 4°. *Paris*, 1808. L.

Fabricius. *De cholera. *Rostochii*, 1628.

Farraguth. *De cholera humida. 4°. *Jenae*, 1675. L.

Fasch. *De cholera humida. *Jenae*, 1675.

Fickius (J. J.) *De cholera illegitima. 4°. *Jenae*, 1721. L.

[Quoted as by SLEVOGT (J. A.)]

Francus de Franckenau. *De cholera. *Hafniae*, 1707.

Gallereux. Observations de choléra-mor-bus ou trousse-galant, et indication d'une potion qu'on peut regarder comme spécifique dans le traitement de cette maladie.

[Jour. génl. de méd., de chir. et de pharm., Paris, 1816, LV, pp. 158–165.]

Gigas. *De cholera. *Jenae*, 1662.

Gigougeux (F.) *Dissertation sur le choléra-morbus. 4°. *Paris*, 1816. L.

Gillet (P. B.) *Thèse sur le choléra-mor-bus, suivie de quelques propositions sur la dysenterie. 4°. *Paris*, 1812. L.

Giraud (S. B.) *Dissertation sur le cho-léra-morbus. 4°. *Paris*, 1812. L.

Girdlestone (T.) Essays on the hepatitis and spasmodic affections in India, found-ed on observations made, whilst on ser-vice with his majesty's troops, in differ-ent parts of that country. 8°. *London*, 1787. L.

Goltz (J. G.) *De cholera. 4°. *Koenigs-berg*, 1691.

Harkan (P.) *De cholera. 8°. *Edinburgi*, 1801. L.

Harper (R. W.) *An inaugural dissertation on cholera. 8°. *Baltimore*, 1815. L.

Hein. *De cholera. *Erfordiae*, 1745.

Henricus (H.) *et* **Messer** (F.) *De cholera morbo. *Halae*, 1710. L.
[HALLER, Disp. ad morb., III.]

Hermann (F. C. J.) * De cholera morbo. 4°. 1816.

Hermann (J. A.) * De cholera humida. 4°. [*Erfordiae*], 1670. L.
[Quoted as by LEICHNER (E.)]

Hermans (J.) * De cholera morbo. 4°. *Lugd. Bat.*, 1816.

Heyden (G. de). Discours et advis sur le flux de ventre douloureux soit qu'il y ait du sang ou point; sur le trousse-galant, dit choléra-morbus; . . . [etc.] 4°. *Gand*, 1643.

——— The same. 1645.

Heyderus (S. A.) * De cholera. 4°. *Wittenbergae*, 1699. L.

Hofmann. * De cholera morbo. *Viennae*, 1767.

Hoffmann (A.) * De cholera. 4°. *Lipsiae*, 1698. L.

Hoppestein. * De cholera. *Leidae*, 1673.

Isenbern. * De cholera. *Lubeo*, 1759.

Janellii (à). * De cholera. *Pragae*, 1779.

Kaltschmid. * De cholera. *Jenae*, 1760.

Keeren (van). * De cholera. *Lugd. Bat.*, 1658.

Kentmann. * De cholera. *Basileae*, 1579.

Kischius (D. J.) * De cholera. 4°. *Halae Magdeb.* [1771]. L.

Kissel. * De cholera. *Giessae*, 1780.

Koch. * De cholera. *Leidae*, 1704.

Körber (H. F.) * De cholera. 4°. *Jenae*, 1653. L.

Lagasquie (J. F.) * Essai sur le choléra-morbus. 4°. *Paris*, 1816. L.

Lane. * De cholera morbo. *Lugd. Bat.*, 1664.

Leman (J.) * De cholera. 8°. *Edinburgi*, 1778. L.

Lentilius (R.) Eteodromus medico-practicus. 4°. *Stuttg.*, 1711.

Liesdorff. * De cholera. *Lugd. Bat.*, 1704.

Lodberg. * De cholera. 4°. *Hafniae*, 1707.

Lothus. * De cholera. *Regiomonti*, 1649.

Lyons (J.) * De cholera. 8°. *Edinburgi*, 1785. C. L.

Mayenschein. * De cholera morbo. *Basileae*, 1583.

Mayer (H.) * De cholera humida. *Giessae*, 1751.

Mead (H.) * An inaugural dissertation on the cholera morbus. 12°. *New York*, 1794. L.

Menjot. * De cholera in diss. pa[illegible] *ris*, 1662.

Messer (J. F.) * De cholera mor[illegible] *Halae Magdeburgicae* (1710).

Michaelis. * De cholera. *Lipsiae*.

Moeller. * De cholera. *Basileae*.

Moeller. * De cholera passione *monti*, 1644.

Ness (J. van). * De cholera. 4°. *ad Rhenum*, 1709.

Noirot. * De cholera morbo. *Lugd.* 1667.

Parent (A. J. B.) Essai sur le ch[illegible] morbus. 4°. *Paris*, 1814.

Pauli. * De cholera. *Rostock*, 1[illegible]

Penada (G.) Saggio d'osservazion[illegible] morie. 4°. *Padua*, 1793.

Peyron (L. J.) * Dissertation sur l[illegible] léra morbus. 4°. *Paris*, 1806.

Philipson. * De cholera. *Londini*.

Planer. * De cholera. *Tubingae*, 1[illegible]

Plowden (G.) * De cholera morbo. 1784. L.
[LOUVAIN diss., III.]

Renard. Observation sur un ch[illegible] morbus, appelé vulgairement tr[illegible] galant.
[JOUR. de méd., chir. et pharm., Paris, 17[illegible] pp. 119–124.]

Rivinus. * De cholera. *Lipsiae*, 16[illegible]

Rolfinck. * De cholera ventriculi. *Jenae* 1637.

Rossum (van). * De cholera morbo. L[illegible] van, 1784.

Ruuk (O. de). * De cholera humida. *Lugduni Batavorum*, 1778.

Salberg (J.) * De cholera. 4°. *Upsaliae* 1768.

Schaller. * De cholera. *Wittebergae*.

Schat. * De cholera. *Leidae*, 1691.

Schenk. * De cholera. *Jenae*, 165[illegible]

Schober. * De cholera. *Ultraj.*, 1[illegible]

Sengensse (J. S.) * Dissertation [illegible] choléra-morbus. 8°. *Paris*, an [illegible] (1803).

Sereul (L. L. M.) * Dissertatio de c[illegible] rhagia seu cholera-morbo. 4°. [illegible] 1811.

Sidren. * De cholera. *Upsaliae*, 17[illegible]

Slevogt. * De cholera humida, siccâ [illegible] cipiente, ejusque curatione in viro[illegible] nae, 1704.

Sloane (H.) Voyage to the Madera[illegible] 2 v. fol. *London*, 1707–25.

Sperling. * De cholera. *Vitebergae*[illegible]

hl. * De febre letifera Hippocratis. *ilae*, 1711.

hl. * De cholera. *Erfordiae*, 1733.

rk. * De cholera humida. *Leidae*, 1654.

rutas. Áyurvédas. Id est medicinae stema, III, pp. 110–112. 8°. *Erlan-e*, 1850. L.

mann (M.) De cholera. 8°. *Viennae*, 81.

— * De cholera. *Viennae*, 1789.

chmeyer (G. F.) * De cholera. 4°. *Je-e*, 1735.

besius. * De cholera. *Ultraj.*, 1685.

mas. Observation sur un choléra-orbus sec.

[Jr. génl. de méd., de chir. et de pharm., Paris, 1805, XXII, pp. 419–424.]

lcke (L. B.) * De cholera. 4°. *Lun-e* (1791). L.

lles (B. L.) Historia cholerae atrocis-imae quam sustinuit ipse. 8°. *Vratis-riae*, 1753. L.

llan. * De cholera. *Jenae*, 1679.

ter. * De atrocissima & acutissima

Vater—continued.

cholerica passione rite judicanda & curanda. *Wittebergae*, 1720.

Vater (A.) * De cholera humidâ. 4°. *Wittenberg.*, 1732.

Verniers (C.) * De cholera. sm. 4°. *Lugduni Batavorum*, 1743. L.

Vetter (J. C.) * De cholera. 8°. *Trajecti ad Viadrum*, 1797. L.

Waenman (C. H.) Morbi nautarum Indiae. *Upsal.*, 1768. L.

[LINNAEUS, Amoenitates, vol. 8.]

Wedel. * De cholera. *Jenae*, 1797.

Weiss (J. F.) * De cholera. *Altdorfii*, 1628.

Wilson (R.) * De cholera. 8°. *Edinburgi*, 1794. L.

Zaentus (L.) Operum tomus secundus. Praxis historiarum. fol. *Lugduni*, 1649. L.

Zollikover. * De cholera. *Argentorati*, 1663.

Hvilke sygdomme herske for naervaerende tid ? (cholera.)

[SUNDH.-JOURNAL, Copenhagen, 1794, I, pp. 193–194.]

B.—PERIODICALS.

inalen (bayerischen). Ausserordentliche Beylage zu den . . . *See* **Cholera** in Germany. "Berichte bayerischer Aerzte über Cholera morbus."

olera-Archiv, mit Benutzung amtlicher Quellen. Herausgegeben von J. C. Albers, F. D. Barry, etc. 3 v. 8°. *Berlin. T. C. F. Enslin*, 1832–33. L.

[No more published.]

olera-Blatt. Als Beilage zu den Schlesischen Blättern, von F. Mehwald. 1 Band. sm. 8°. *Breslau, Aderholz*, 1831.

olera (The) Gazette. Weekly. Nos. 1–16, vol. 1, July 11 to Nov. 21, 1832. 8°. *Philadelphia.* L.

[Completed.]

olera (The) Gazette, consisting of documents communicated by the central board of health, with intelligence relative to the disease, etc. Nos. 1–6, Jan. 14 to April 7, 1832. 8°. *London*, 1832. L.

—— The same. 2d ed. *London* [*n. d.*]

holera orientalis. Extrablatt zum Allgemeinen Repertorium der gesammten deutschen medicinisch-chirurgischen Journalistik. Herausgegeben von C. F. Kleinert. Nos. 1–80. 4 Hefte in 2 v. 8°. *Leipzig*, 1831–32. L.

[Completed.]

Cholera-Zeitung. Herausgegeben von den Aerzten Königsbergs. 2te Auflage. 4°. *Königsberg*, 1832. L.

Cholera-Zeitung. Herausgegeben von Dr. Zitterland. 2 v. 4°. *Leipzig und Aachen*, 1831.

Cholera-Zeitung (Allgemeine). Mittheilungen des Neuesten und Wissenswürdigsten über die asiatische Cholera. In Verbindung mit mehreren in- und ausländischen Gelehrten herausgegeben von J. Radius. Aug. 26, 1831–Nov. 28, 1832. 5 Bände in 1 v. 4°. *Leipzig.* L.

[Want Nos. 97–105.]

Cholera-Zeitung (Berliner). Materialien zur Geschichte und Behandlung der asiatischen Cholera, etc. Herausgegeben von Dr. J. L. Casper. Nos. 1–36, Sept. 24 to Dec. 27, 1831. 4°. *Berlin*, 1831. L.

[Completed.]

Cholera-Zeitung (Schlesische). Herausgegeben von dem ärztlichen Comité für Schlesien. (Desinficirt.) Nos. 1–12, Oct. 8, 1831–Feb. 18, 1832. Nebst Supplementbogen, Register und 2 Steinzeichnungen. 4°. *Breslau*, 1831–32. L.

[All published.]

Henricus (H.) *et* **Messer** (F.) * De cholera morbo. *Halae*, 1710. L.
[HALLER, Disp. ad morb., III.]

Hermann (F. C. J.) * De cholera morbo. 4°. 1816.

Hermann (J. A.) * De cholera humida. 4°. [*Erfordiae*], 1670. L.
[Quoted as by LEICHNER (E.)]

Hermans (J.) * De cholera morbo. 4°. *Lugd. Bat.*, 1816.

Heyden (G. de). Discours et advis sur le flux de ventre douloureux soit qu'il y ait du sang ou point; sur le trousse-galant, dit choléra-morbus; . . . [etc.] 4°. *Gand*, 1643.

——— The same. 1645.

Heyderus (S. A.) * De cholera. 4°. *Wittenbergae*, 1699. L.

Hofmann. * De cholera morbo. *Viennae*, 1767.

Hoffmann (A.) * De cholera. 4°. *Lipsiae*, 1698. L.

Hoppestein. * De cholera. *Leidae*, 1673.

Isenbern. * De cholera. *Lubec*, 1759.

Janellii (à). * De cholera. *Pragae*, 1779.

Kaltschmid. * De cholera. *Jenae*, 1760.

Keeren (van). * De cholera. *Lugd. Bat.*, 1658.

Kentmann. * De cholera. *Basileae*, 1579.

Kischius (D. J.) * De cholera. 4°. *Halae Magdeb.* [1771]. L.

Kissel. * De cholera. *Giessae*, 1780.

Koch. * De cholera. *Leidae*, 1704.

Körber (H. F.) * De cholera. 4°. *Jenae*, 1653. L.

Lagasquie (J. F.) * Essai sur le choléra-morbus. 4°. *Paris*, 1816. L.

Lane. * De cholera morbo. *Lugd. Bat.*, 1664.

Leman (J.) * De cholera. 8°. *Edinburgi*, 1778. L.

Lentilius (R.) Eteodromus medico-practicus. 4°. *Stuttg.*, 1711.

Liesdorff. * De cholera. *Lugd. Bat.*, 1704.

Lodberg. * De cholera. 4°. *Hafniae*, 1707.

Lothus. * De cholera. *Regiomonti*, 1649.

Lyons (J.) * De cholera. 8°. *Edinburgi*, 1785. C. L.

Mayenschein. * De cholera morbo. *Basileae*, 1583.

Mayer (H.) * De cholera humida. *Giessae*, 1751.

Mead (H.) * An inaugural dissertation on the cholera morbus. 12°. *New York*, 1794. L.

Menjot. * De cholera in diss. pathol. *Paris*, 1662.

Messer (J. F.) * De cholera morbo. 4°. *Halae Magdeburgicae* (1710). L.

Michaelis. * De cholera. *Lipsiae*, 1641.

Moeller. * De cholera. *Basileae*, 1594.

Moeller. * De cholera passione. *Regiomonti*, 1644.

Ness (J. van). * De cholera. 4°. *Trajecti ad Rhenum*, 1709. L.

Noirot. * De cholera morbo. *Lugd. Bat.*, 1667.

Parent (A. J. B.) Essai sur le choléra-morbus. 4°. *Paris*, 1814. L.

Pauli. * De cholera. *Rostock*, 1601.

Penada (G.) Saggio d'osservazioni e memorie. 4°. *Padua*, 1793.

Peyron (L. J.) * Dissertation sur le choléra morbus. 4°. *Paris*, 1806. L.

Philipson. * De cholera. *Lundae*, 1791.

Planer. * De cholera. *Tubingae*, 1588.

Plowden (G.) * De cholera morbo. 8°. 1784. L.
[LOUVAIN diss., III.]

Renard. Observation sur un choléra-morbus, appelé vulgairement trousse-galant.
[JOUR. de méd., chir. et pharm., Paris, 1764, XXI, pp. 119–124.]

Rivinus. * De cholera. *Lipsiae*, 1698.

Rolfinck. * De cholera ventriculi. *Jenae*, 1637.

Rossum (van). * De cholera morbo. *Levan*, 1784.

Ruuk (O. de). * De cholera humida. 8°. *Lugduni Batavorum*, 1778. L.

Salberg (J.) * De cholera. 4°. *Upsaliae*, 1768.

Schaller. * De cholera. *Wittebergae*, 1620.

Schat. * De cholera. *Leidae*, 1691.

Schenk. * De cholera. *Jenae*, 1653.

Schober. * De cholera. *Ultraj.*, 1646.

Sengensse (J. S.) * Dissertation sur le choléra-morbus. 8°. *Paris*, an XII (1803). L.

Sereul (L. L. M.) * Dissertatio de cholerrhagia seu cholera-morbo. 4°. *Paris*, 1811. L.

Sidren. * De cholera. *Upsaliae*, 1768.

Slevogt. * De cholera humida, siccam excipiente, ejusque curatione in viro. *Jenae*, 1704.

Sloane (H.) Voyage to the Madeira, etc. 2 v. fol. *London*, 1707–25. C. L.

Sperling. * De cholera. *Vitebergae*, 1699.

rchardt (I. S.) Kurze Darstellung der holera und unfehlbare Heilmethode erselben. Nach den Grundsätzen des halmud bearbeitet. 8°. *Berlin*, 1831.

ndin (A. V.) Del colera morbo asiatico, en Polonia, en Alemania, en Francia en Paris, durante las epidemias de 31 y 1832; con un analysis critico y razonado de los diversos metodos curativos puestos en practica en la India, en Russia, etc. 8°. *Paris*, 1832. L.

igham (A.) A treatise on epidemic cholera, including an historical account of its origin and progress to the present period. Compiled from the most authentic sources. 8°. *Hartford*, 1832. L.

iquet. Rapport sur les épidémies de choléra-morbus qui ont régné de 1817 à 1850.

[Mem. Acad. imp. de méd., Paris, 1867-68, XXVIII, pp. 56-271.]

uet (J. A.) Histoire générale du choléra-morbus depuis 1817 jusqu'en août 1831. 8°. *Paris*, 1831.

urdach (K. F.) Historisch-statistische Studien über die Choleraepidemie. 8°. *Königsberg*, 1832.

ushnan (J. S.) Cholera and its cures: an historical sketch. 8°. *London*, 1850. L.

ampbell (F. W.) The present epidemic of cholera, its origin and progress.

[Canada Med. Jour., Montreal, 1866, II, pp. 202-212.]

hatto (J.) Report on the recent progress of cholera.

[Assn. Med. Jour., London, 1854, II, pp. 620-624.]

lendenin (W.) Some facts in the history of Asiatic cholera.

[Cinc. Lancet and Obs., 1874, XVII, pp. 1-5, 72-77.]

lot-Bey. Quelques mots sur le choléra à l'Institut et à l'Académie de médecine de Paris; suivis d'une réponse à la Gazette de France et à M. Grimaud de Caux et d'une relation de l'épidémie de choléra qui a régné, en 1831, en Arabie et en Egypte. 8°. *Paris* [*n. d.*]

——— The same. 2e éd. *Paris* [*n. d.*]

ollins (G. T.) The cholera: a familiar treatise on its history. Also . . . a history of the epidemics of the middle ages. 12°. *New York and Cincinnati*, 1866. L.

Cox (W. J.) On the statistics of cholera. [A tabular report.]

[Lancet, London, 1850, I, n. s., pp. 112-113.]

Dechambre (A.) Tableau abrégé du choléra de 1853.

[Gaz. hebd. de méd. et de chir., Paris, 1853-54, I, pp. 197-201, 229-232, 245-249.]

——— Le choléra en Europe.

[Gaz. hebd. de méd. et de chir., Paris, 1855, II, pp. 533-535.]

Dellon. Relation d'un voyage des Indes-Orientales. *Paris*, 1685.

Deran (C.) Diss. historiam cholerae morbi sistens. 8°. *Pesthi*, 1832.

D'Espine. Esquisse géographique des invasions du choléra en Europe; rôle joué par la Suisse en particulier, et théorie de la propagation du choléra.

[Arch. gén. de méd., Paris, 1857, I, pp. 641-649. Also reprinted in 8°, Geneva, 1857.]

Dowler (B.) Historical and statistical observations on cholera.

[N. Orleans Med. and Surg. Journ., 1857, XIV, pp. 1-22.]

Drasche. Geographisch-statistischer Bericht über die diesjährige Cholera-Epidemie.

[Wien. Med. Wochenschr., 1865, XV, pp. 1201-1204, 1236-1238, 1273-1275, 1301-1311, 1344-1346, 1384-1387, 1415-1487.]

Dubouchet. Observations sur le choléra-morbus . .·. séjour en Angleterre, en Ecosse et à Paris. 8°. *Paris*, 1832.

Dührssen (H. C.) Vergleichung der epidemischen Cholera mit der europäischen Küsten-Epidemie der Jahre 1826, 1827, 1828 und 1829.

[Mag. d. ausländ. Liter. d. ges. Heilk., Hamburg, 1831, XXII, pp. 193-221.]

Edwards. On cholera in Europe.

[St. Louis Med. Jour., 1850, VIII, pp. 120-125.]

Faber. Die epidemische Cholera in den Jahren 1845-47.

[Med. Corresp.-Bl. d. Württem. aerztl. Vereins, 1847, XVII, pp. 299-303.]

Fabre (A.) *et* **Chailau** (F.) Histoire du choléra-morbus asiatique depuis son départ des bords du Gange, en 1817, jusqu'à l'invasion du midi de la France en 1835; accompagnée de tableaux statistiques dressés d'après des documents officiels. 8°. *Marseille*, 1835.

——— The same. 2d ed. *Marseille*, 1836.

Farr. Formel zur Berechnung der Choleramortalität aus der Elevation in London.

[Zeitschr. f. Biologie, München, 1865, I, pp. 378-380.]

Fauvel. Note sur le choléra. [Its progress in 1871.]

[Bulletin de l'Acad. de méd., Paris, 1871, xxxvi, pp. 599, 983; 1872, i, 2e s., pp. 574–588; 1873. ii, 2e s., p. 1133.]

——— Marche du choléra.

[Revue de thérap. méd.-chirurg., Paris, 1872, xx, pp. 5–9.]

Foderé (F. E.) Recherches historiques et critiques sur la nature, les causes et le traitement du choléra-morbus d'Europe, de l'Inde, . . . spécialement appliquées à l'hygiène publique. 8°. *Paris*, 1831.

Foissac. Considérations sur la mortalité du choléra.

[L'Union méd., Paris, 1865, xxviii, 2e sér., pp. 116–121.]

Fox (T.) The cholera in the east.

[Lancet, London, 1865, ii, pp. 274–275.]

Foy. Histoire médicale du choléra-morbus. 8°. *Paris*, 1832.

Frankl (L. A.) Hippokrates und die Cholera. Trimeter und Knittelvers. 3te Auflage. 8°. *Wien*, 1855.

Gaskoin (G.) Contributions to the current literature of cholera.

[Brit. and For. Med.-Chir. Review, 1867, xl, pp. 217–232.]

Gaudet (A. M.) Recherches sur le choléra de 1833 comparé au choléra épidémique de 1832.

[Gaz. méd. de Paris, 1834, ii, pp. 113–117.]

Gentz (J.) Beitrag zur Geschichte der Cholera. 8°. *Berlin*, 1831.

Gibbs (O. C.) A report on epidemics and endemics. Cholera. [Read before Med. Soc. Southwestern N. Y., 1848.]

[North Am. Med.-Chir. Rev., Phila., 1861, v, pp. 469–486.]

——— The same. 8°. *Philadelphia*, 1861. L.

Giusti (L.) Sur les dernières attaques de choléra dans l'orient.

[Gaz. des hôp. Paris, 1848, p. 178.]

Gooday (A. F.) The Royal College of Physicians and the cholera.

[Lancet, London, 1853, ii, pp. 513–514.]

Graves (R. J.) Sketch of the origin and progress of Asiatic cholera. 8°. *Philadelphia*, 1841. L.

——— On the progress of Asiatic cholera.

[Dublin Quar. Jour. of Med. Science, 1848, vi, pp. 289–316.]

[**Gray** (W. H. C.)] Dysenteria serosa, or convulsive nervous "cholera" of Hindostan. An essay containing a short statement of its progress from Asia, in 1817, to its suspected appearance in England, in 1831; wherein a new view of the essential principles, symptoms, and

[**Gray** (W. H. C.)]—continued. operation of that disease is shown; a practical, easy, and efficacious . . . illustrated. By Philanthropos. *don*, 1832.

Gregory (G.) Mortality from ch[olera]

[London Med. Gaz., 1832, x, pp. 69–72.]

——— Statistics of cholera.

[London Med. Gaz., 1833, xi, pp. 11–14.]

Griffin (W.) On the application of . . . merical method to the study of . . .

[Dublin Med. Press, 1841, vi, pp. 314–316.]

Gross (W.) On the etymology of "cholera."

[Lancet, London, 1839–33, i, pp. 625.]

Haeser (H.) Addimenta ad bibl[iothecam] epidemiographicam. Collegit atque edidit J. T. Thierfelder. 8°. Lips. 1843.

——— Bibliotheca epidemiographica . . . catalogus librorum de historia . . . borum epidemicorum tam generatim . . . speciali conscriptorum. 8°. Jenæ, 1843.

——— Lehrbuch der Geschichte der Medicin und Volkskrankheiten. *Jena*.

——— Geschichte der epidemischen Krankheiten. 2. Aufl. 8°. *Jena*.

Hall (J. C.) Some remarks on the progress of the cholera.

[Jour. Pub. Health, London, 1848, 33, 72.]

Heine (J. G.) Historie über den Verlauf der asiatischen Cholera-Krankheit in den Jahren 1836-1838. Erterte Gruende, welche Dr. H[eine] 's Gravenhage bestimmten, seine raschriften zuerst unterm 29. Ju[ly] 1836 an das königl. Bayer. Medicinal Collegium zu München, mit einer schrift, die desfallsigen Gründe, Weise und Art der Abfassung . . . allgemeinen Verbreitung der . . . gleitet, direct einzuschicken, genannte Denkschrift allen . . . schriften beigefügt wurde. den Copien von Antwort und A[n]nungsschreiben vorgesetzt . . . [*n. p., n. d.*]

Henriques (A.) Etiological, p[a]thological and therapeutical remarks on Asiatic cholera, as observed in Asia Minor and Egypt. . . . *don*, 1848.

Hirsch. Handbuch der historisch-graphischen Pathologie. *Erlan*[gen]

rch (A.) Rückblick auf die Erfahrungen und Leistungen im Gebiete der Cholera während der letzten Jahre.

[Schmidt's Jahrbücher, Leipzig, 1854, LXXXIV, pp. 82–114; 1855, LXXXVIII, pp. 233–277; 1856, XCII, pp. 233–272.]

ümann (H.) Bemerkungen zur Geschichte der Cholera orientalis. [Mit einem "Zusatz" von Hohnbaum.]

[Med. Convers.-Bl., Hildburghausen, 1831, pp. 403–413.]

feland (C. W.) Schluss-Resultat über die Cholera, eine neue, ausländische, aus Asien nach Europa verpflanzte, ansteckende, aber nicht sperrbare Krankheit; ihr Keim immer derselbe, ihre Ursache immer Uebertragung, aber nicht bloss persönliche.

[Berlin Med. Central-Zeitg., 1832, I, pp. 225–228.]

nsee (A.) Generalcharte der geographischen Verbreitung und des Ganges der Cholera vom Ende des Jahres 1816 bis zum Anfange des Jahres 1836. fol. *Berlin*, 1837.

— The same. 3. Aufl. *Berlin*, 1837.

ncowich (A.) Die epidemische Cholera in den Jahren 1817–1832. 8°. *Ofen*, 1832.

hnson (H. A.) The cholera in Europe.

[North-West. Med. and Surg. Jour., Chicago and Indianapolis, 1854, XI, pp. 302–310.]

nnedy (J.) The history of the contagious cholera, with facts explanatory of its origin, and laws for its rational method of cure. 8°. *London*, 1831. L.

— The same. 3d ed. 1832.

inberg (H.) *og* **Esbenson.** Cholera i London, Dublin og Paris.

[Bibl. for Laeger, Copenhagen, 1832, XVII, 169–249.]

nigsfeld (G. A.) Kurze Darstellung des Weltganges der Cholera vom August 1817 bis zum Januar 1837 und der gegen dieselbe durch die Erfahrung am meisten erprobten Schutzmaassregeln. Nebst kurzem Hinblick auf ihre neuesten Wanderungen und Fortschritte. Für Ärzte und Nichtärzte. 8°. *Aachen*, 1848. L.

rave (L.) Le choléra en Europe.

[Gaz. hebd. de med. et de chir., Paris, 1873 x, 2e s., pp. 553–555.]

wrie (J. A.) On the cholera morbus.

[Glasgow Med. Jour., 1831, IV, pp. 383–406.]

ach (H.) The cholera in eastern Europe.

[Lancet, London, 1865, II, p. 350.]

Lemasson (T.) Aperçu historique et médicale sur le choléra-morbus.

[Trans. méd., Journ. de méd. prat., Paris, 1831, IV, pp. 404–431. Also reprinted in 8°, Paris, 1831.]

Lippich (F. W.) Was verstand Aretäus unter dem Fluchtergreifen der Aerzte vor der Cholera?

[Med. Jahrbüch. des K. K. oesterr. Staates, Wien, 1838, XV, n. f., pp. 546–555.]

Lombard (H. C.) Notes historiques sur le choléra-morbus, et sur les principales épidémies de cette maladie depuis 1817 jusqu'au mois d'octobre 1831. 8°. *Genève*, 1832. L.

Longueville (P. F. T.) *See* **Thomas-Longueville** (P. F.)

Macpherson (J.) The early seats of cholera in India and in the east, with reference to the past and present.

[Med. Times and Gaz., London, 1867, I, p. 510.]

——— Annals of cholera from the earliest periods to the year 1817. 8°. *London*, 1872. L.

——— Early notice of cholera in India.

[Med. Times and Gaz., London, 1874, II, p. 592.]

Mahlmann (H.) Statistisches aus der neuesten Cholera-Literatur.

[Deutsche Klinik, Berlin, 1857, IX, pp. 9–14.]

Mansa. Die Cholera und der schwarze Tod, eine medicinisch-historische Parallele. Aus dem Dänischen von Dr. Nevermann.

[Wissenschaftl. Ann. der ges. Heilk., Berlin, 1834, XXX pp. 397–415.]

——— Sammenstilling af den epidemiske Cholera og den frygtelige Sygdom, den Sorte död kaltet, der i det 14 de Aarhundrede, fra 1346 til 1350, ödelagde den störste Deel af den paa hiin Tide bekjindte verden.

[Jour. for Med. og Chir., Copenhagen, 1834, IV, pp. 193–221.]

Maragliano. Cronaca del cholera.

[Gaz. Med. Ital.-Lombard., 1874, XXXIV, p. 88.]

Mareschal. Tableau par régions des décédés cholériques de 1849, accompagné de quelques remarques.

[Journ. sect. de méd. soc. acad. dépt. Loire-inf., 1851, XXVII, pp. 219–234; 1 tab.]

Marin-Desbrosses (J. C. M.) Histoire de l'épidémie de choléra-morbus. 8°. *Paris*, 1832.

Martin (A.) Die Cholera vom September 1845 bis zum September 1847.

[Neue Med.-Chir. Zeitung, München, 1847, IV, pp. 33–41.]

Fauvel. Note sur le choléra. [Its progress in 1871.]

[Bulletin de l'Acad. de méd., Paris, 1871, xxxvi, pp. 599, 983; 1872, i, 2e s., pp. 574–588; 1873, ii, 2e s., p. 1133.]

——— Marche du choléra.

[Revue de thérap. méd.-chirurg., Paris, 1872, xx, pp. 5–9.]

Foderé (F. E.) Recherches historiques et critiques sur la nature, les causes et le traitement du choléra-morbus d'Europe, de l'Inde, . . . spécialement appliquées à l'hygiène publique. 8°. *Paris*, 1831.

Foissac. Considérations sur la mortalité du choléra.

[L'Union méd., Paris, 1865, xxviii, 2e sér., pp. 116–121.]

Fox (T.) The cholera in the east.

[Lancet, London, 1865, ii, pp. 274–275.]

Foy. Histoire médicale du choléra-morbus. 8°. *Paris*, 1832.

Frankl (L. A.) Hippokrates und die Cholera. Trimeter und Knittelvers. 3te Auflage. 8°. *Wien*, 1855.

Gaskoin (G.) Contributions to the current literature of cholera.

[Brit. and For. Med.-Chir. Review, 1867, xl, pp. 217–232.]

Gaudet (A. M.) Recherches sur le choléra de 1833 comparé au choléra épidémique de 1832.

[Gaz. méd. de Paris, 1834, ii, pp. 113–117.]

Gentz (J.) Beitrag zur Geschichte der Cholera. 8°. *Berlin*, 1831.

Gibbs (O. C.) A report on epidemics and endemics. Cholera. [Read before Med. Soc. Southwestern N. Y., 1848.]

[North Am. Med.-Chir. Rev., Phila., 1861, v, pp. 469–486.]

——— The same. 8°. *Philadelphia*, 1861. L.

Giusti (L.) Sur les dernières attaques de choléra dans l'orient.

[Gaz. des hôp. Paris, 1848, p. 178.]

Gooday (A. F.) The Royal College of Physicians and the cholera.

[Lancet, London, 1853, ii, pp. 513–514.]

Graves (R. J.) Sketch of the origin and progress of Asiatic cholera. 8°. *Philadelphia*, 1841. L.

——— On the progress of Asiatic cholera.

[Dublin Quar. Jour. of Med. Science, 1848, vi, pp. 289–316.]

[Gray (W. H. C.)] Dysenteria serosa, or convulsive nervous "cholera" of Hindostan. An essay containing a short statement of its progress from Asia, in 1817, to its suspected appearance in England, in 1831; wherein a new view of the essential principles, symptoms, and operation of that disease is shewn; and a practical, easy, and efficacious remedy illustrated. By Philanthropos. 8°. *London*, 1832. L.

Gregory (G.) Mortality from cholera.

[London Med. Gaz., 1832, x, pp. 608–609.]

——— Statistics of cholera.

[London Med. Gaz., 1833, xi, pp. 11–12.]

Griffin (W.) On the application of the numerical method to the study of cholera.

[Dublin Med. Press, 1841, vi, pp. 314–318.]

Gross (W.) On the etymology of "cholera."

[Lancet, London, 1839–33, i, pp. 809–810.]

Haeser (H.) Addimenta ad bibliothecam epidemiographicam. Collegit atque edidit J. T. Thierfelder. 8°. *Misenae*, 1843. L.

——— Bibliotheca epidemiographica sive catalogus librorum de historia morborum epidemicorum tam generali quam speciali conscriptorum. 8°. *Jenae*, 1843. L.

——— Lehrbuch der Geschichte der Medicin und Volkskrankheiten. *Jena*, 1845.

——— Geschichte der epidemischen Krankheiten. 2. Aufl. 8°. *Jena*, 1865.

Hall (J. C.) Some remarks on the progress of the cholera.

[Jour. Pub. Health, London, 1848, i, pp. 32–33, 72.]

Heine (J. G.) Historie über den letzten Verlauf der asiatischen Cholerakrankheit in den Jahren 1836–1838. Erweiterte Gruende, welche Dr. Heine zu 's Gravenhage bestimmten, seine Choleraschriften zuerst unterm 29. Dezember 1836 an das königl. Bayer. Medizinal-Collegium zu München, mit einer Denkschrift, die desfallsigen Gründe, für die Weise und Art der Abfassung und der allgemeinen Verbreitung derselben begleitet, direct einzuschicken, sowie genannte Denkschrift allen Choleraschriften beigefügt wurde, und auch den Copien von Antwort und Anerkennungsschreiben vorgesetzt ist. 4°. [*n. p., n. d.*] L.

Henriques (A.) Etiological, pathological and therapeutical reflections on Asiatic cholera, as observed in Europe, Asia Minor and Egypt. . . . 8°. *London*, 1848.

Hirsch. Handbuch der historisch-geographischen Pathologie. *Erlangen*, 1859.

ns (J.C.)—continued.

Canada and the United States Indian rritory in 1832. 8°. L.

— On the conveyance of Asiatic olera from Northern Hindoostan to ntral Asia. 8°. [*n. p.*] L.

om LEAVENWORTH Med. Herald, April, 1868.]

— On the conveyance of cholera from ndostan through Asia to Europe and nerica.

ANS. Americ. Med. Assoc., 1868, XIX, pp. 309–17, 4 maps.]

— The same. 8°. [*n. p.*] L.

— On the conveyance of cholera from dia through Persia, Armenia and Geora, to Russia and the rest of Europe.

HICAGO Med. Examiner, 1868. IX, pp. 513–526.]

— The same. 8°. [*n. p., n. d.*] L.

— On the origin of cholera in Hinstan, and its conveyance to Europe.

HICAGO Med. Examiner, 1868, IX, pp. 385–[illegible]

— The same. 8°. [*n. p., n. d.*] L.

— The homes and travels of Asiatic olera.

ERD. Gaz. New York, 1869, III, pp. 25–27, 39–[illegible]

— On the origin and travels of Asiatic olera. 8°. *New York*, 1871. L.

rom N. Y. Med. Journal.]

— The history of cholera.

LINC. Cinc., O., 1874, VII, pp. 59, 82.]

— On cholera.

ASHVILLE Jour. of Med. and Surg., 1874, XXXV, pp. 128–133.]

llips (P. L.) Cholera not a new disse.

ONDON Med. Gaz., 1832, IX, pp. 594–596.]

ra-Santa (P. de.) Documents pour rvir à l'histoire du choléra-morbus.

AZ. hebd. de méd. et de chirurg., Paris, 53–54, I, pp. 147–148.]

gge (T.) Zur Geschichte der Cholera.

ERTZL. Intell.-Bl., München, 1858, V, pp. 200–01.]

ys Van Der Hoeven (C.) Historische essen over de Cholera. 8°. *Leiden*, 32. L.

dcliffe (J. W.) Report on the sources nd development of the present diffuion of cholera in Europe.

RIV. Priv. Counc., 1865, [app.], pp. 306–391.]

n (C. F. v.) Geschichte der Verbreiung der Cholera und ihrer Verheerunen in Asien, Afrika und Europa, vom ahre 1817 bis zum Ende des Jahres 31. 8°. *Berlin*, 1832.

Rehmann (J.) Die Ankunft der orientalischen Cholera am mittelländischen und kaspischen Meere.

[HUFELAND'S Journ. der prakt. Heilk., 1824, LVIII, pp. 3–16; LIX, pp. 3–13.]

Reis (P.) Notice historique et pratique sur le choléra-morbus, et particulièrement sur l'épidémie de 1849. 8°. *Paris*, 1849.

Rendu (A.) Remarques sur l'épidémie de choléra de 1849. 8°. *Compiègne*, 1849.

Richardson (F. W.) The Royal College of Physicians and the cholera.

[LANCET, London, 1853, II, p. 422.]

Richter (G. A.) Die orientalische Cholera, nach fremden und eigenen Ansichten und Erfahrungen Nach dem Tode des Verfassers von Dr. H. Stannius herausgegeben. Erste Abtheilung. Enthaltend: Geschichte der Cholera bis zu ihrem ersten Auftreten in Frankreich. 8°. *Berlin*, 1836. L.

Rigler. Beitrag zur Geschichte der Cholera.

[WIEN. med. Wochenschr., 1855, pp. 161–177.]

Rittmann (A.) Sydenham's Cholera vom Jahre 1669. Ein Beitrag zur Geschichte der Volkskrankheiten.

[ALLG. Wien. med. Zeitg., 1866, XI, pp. 373–374.]

Rogers (C.) A chapter in the history of cholera.

[MED. Times and Gaz., London, 1872, I, pp. 608–609.]

Rosenberger. Officieller Bericht über den Gang und die Verbreitung der diesjährigen Cholera.

[ST. PETERSBURG med. Zeitsch., 1866, X, pp. 43–48, 354–355.]

Roux. Contributions à l'histoire du choléra-morbus [1865–1866].

[GAZ. des hôp. Paris, 1866, pp. 431–432.]

[**Sander** (G. C. H.)] Tabulae chronologicae hydrodromicam pestis gangeticae dissipationem explicantes. Accedit tabula geographica. fol. *Braunschweig*, 1832.

——— Die zweite Wanderung der asiatischen Cholera oder der gangetischen Pest nach Europa.

[HANNOVER. Ann. f. d. ges. Heilk., 1847, XII, pp. 516–540.]

Schilling. Uebersichts-Karte des Verheerungszuges der Cholera morbus, etc. fol. *Breslau*, 1831.

Schnurrer (F.) Charte der Krankheiten, über deren geographischen Ausbreitung,

Prias (R.) Cenni sul cholera morbus sviluppatosi in Alessandria 1831. 8°. *Lucca*, 1832.

Grassi. Relazione e riflessioni sopra il cholera indiano che ha regnato in Egitto l'anno 1848.

[OMODEI, Ann. un. di med., 1848, CXXVIII, pp. 18–43.]

Griesinger (W.) Klinische und anatomische Beobachtungen über die Krankheiten von Egypten. [Cholera.]

[ARCH. f. physiol. Heilk., Stuttgart, 1853, pp. 375–376.]

Grimsud (M. G.) Du choléra en Égypte dans ses rapports avec l'épidémie de Marseille en 1865.

[GAZ. méd. de Paris, 1866, XXI, pp. 316–317.]

Maruchi. Statistischer Bericht über die Cholera-Epidemie zu Aegypten im Sommer 1855.

[ARZTL. Intell.-Bl., 1856, III, p. 648.]

Mimaut. Choléra en Égypte.

[ANN. d'hygiène, Paris, 1831, VI, pp. 476–480.]

Nizzoli. Cenno sul cholera-morbus divampato in Alessandria d'Egitto.

[OMODEI, Ann. un. di med., 1832, LXI, pp.146–151.]

Patterson (J.) On the late pestilence in Cairo, Egypt.

[MED. Times & Gaz., 1865, II, pp. 545–547.]

Zagiell (J.) Choléra-morbus d'Égypte.

[GAZ. des hôp., 1865, pp. 474–475. Reprinted at Marseilles in 8°, 1865.]

Cholera (The) in Egypt.

[MED. Times, London, 1848, XVIII, pp. 246, 281, 298.]

Cholera prodoljaiet sia v Ehiptie.

[MEDYTZYNSKIY viestnik, iejemiedelna gazeta, St. Petersburg, 1865, p. 300.]

Fogo (*Island of*).

Leaõ (José Fernandez da Silva.) On the cholera epidemy at the island of Fogo, in the Cape de Verds, in 1855. [Translated from the Portuguese by Geo. Miller and J. O. McWilliam.]

[TRANS. of the Epid. Soc., 1857 (appended to the Jour. of Pub. Health, 1857, vol. 3), pp. 41–62.]

Cholera (The) epidemy at the island of Fogo, in the Cape de Verds.

[MED. Times & Gaz., London, 1857, XV, n. s., pp. 46–47.]

Gambia.

Papers relating to the outbreak of cholera at the Gambia. Plans. 1869.

Saint Jago (*Island of*).

Hopffers. Notes on the epidemic of cholera morbus at the island of St. Iago, Cape de Verds, in 1856.

[MED. Times & Gaz., 1860, II, pp. 645–646.]

Tunis.

Ferrini (G.) Intorno al cholera di Tunisi dell'anno 1867. *Milano*, 1867.

[*Also*, in GAZ. med. italiana Lombardia, Milano, 1868, XXVIII, pp. 226–230, 234–239, 273–279, 283–287, 293–295.]

Guyon. Lettre sur l'état du choléra dans la régence de Tunis.

[GAZ. méd. de Paris, 1850, V, pp. 401–402.]

Lumbroso (A.) Cenni storico-scientifici sul cholera-morbus asiatico che invase la reggenza di Tunis nel 1849–1850 . . . 8°. *Marsiglia*, 1850.

Moriggia. Rapporto sulla memoria del dott. G. Ferrini sul cholera di Tunisi dell'anno 1867.

[GIORN. d. r. Acad. di med. di Torino, 1870, IX, 2a ser., pp. 21–23.]

Nunes Vias (G. A.) Del cholera a Tunisi

[L'IMPARZIALE, 1867, VII, pp. 566–567.]

——— Osservazioni e considerazioni cliniche sul cholera tratte dall'ultima epidemia di Tunisi.

[L'IMPARZIALE, 1868, VIII, pp. 37–47, 74–87, 99–109, 131–136. Reprinted at Firenze, 1868.]

Zanzibar (*Island of*).

Memorandum by the army sanitary commission on communication from Dr. Bryden regarding cholera at Zanzibar.

[REPORT on measures adopted for the sanitary improvement in India from June, 1870, to June, 1871, London, 1871, pp. 216–217.]

NORTH AMERICA AND WEST INDIES.

BRITISH AMERICA.

Goldstone (Geo.) The cholera in Cobourg, C. W.

[BRIT. AM. Jour. of Med. & Phys. Science, 1849, V, pp. 177.]

Henry (W.) Report on malignant cholera amongst the troops in Canada, in the summer of 1854.

[MED. Chron., Montreal, 1854, II, pp. 213–230.]

Lloyd (S. McV.) Report of an outbreak of cholera in Chezetcook and Halifax, N. S., originating in an infected emigrant ship, in November, 1871.

[LANCET, London, 1871, pp. 296–297.]

Mountain (G. B.) Recollections of the cholera.

[JOUR. of health, Phila., 1832, IV, pp. 312–316; *also in* WESTERN Med. Gaz., Cincinnati, 1833, I, pp. 265–268.]

Paine (Martyn). History of the cholera at Montreal.

[BOSTON Med. & Surg. Jour., 1833, VIII, pp. 53–66.]

——— History of the cholera at Montreal.

[BRIT. Amer. Jour., 1851, II, pp. 69–86, 104–109.]

ıtter (C. M.) * Itinerarium der indischen Cholera-Epidemie in chronologischen Tabellen von ihrem Ausbruche in dien im Jahre 1817 bis zu ihrem jüngsten Auftreten innerhalb der Gränzen seres Vaterlandes. 8°. *Würzburg*, 37. L.

ide (P. G. B. de.) * Diss. med. continens epidemiae cholerae asiaticae historiam. 8°. *Lugd. Bat.*, 1834.

tzer. Die asiatische Cholera, 1847 in ıropa angelangt.

[HEIN. Monatsschr. f. prakt. Aerzte, Köln, 1847, , pp. 637–638.]

ount (An) of the rise and progress of e Indian or spasmodic cholera. With particular description of the symptoms tending the disease. Illustrated by a ap, showing the route and progress of ie disease from Jessore, near the anges, in 1817, to Great Britain in 1831. . *New Haven*, 1832. L.

vance of the cholera.

[Quart. of Publ. Health and Mo. Rec. of San. Impr., London, 1848, I, p. 332.]

latic cholera again in Europe.

[Eighth Rept. Med. Off. Privy Couns., 1865, London, pp. 27–30.]

latic cholera: its symptoms, remedies, nd preventives: containing particular structions in reference to the different ages of the disease; accompanied by a istory of the progress of this dreadful isease. 8°. *New York*, 1848. L.

thorities on cholera.

[Brit. and For. Med.-Chirurg. Rev., London, 1866, XXXVIII, pp. 130–161, 417–438; 1867, XL, pp. 1–40.]

lletin du choléra.

[Gaz. d. Connaiss., Paris, 1849, XVI, pp. 168–174.—Arch. méd. belges, Bruxelles, 1866, IV 2e s., pp. 62–64.]

olera.

[Bibl. for Laeger, Copenhagen, 1847, II, pp. 457–461; 1848, IV, pp. 217–225, 427–433; 1849, V, pp. 406–419; 1849, VI, pp. 129–194, 388–406; 1850, VII, pp. 304–335; 1850, VIII, pp. 385–389.]

olera (The).

[Lancet, London, 1866, II, pp. 54–55, 114, 242–243, 374–375.]

olera.

[Hosak. for Laeger, Copenhagen, 1867, IV, pp. 274, 319, 337–338, 353, 394, 459, 471.]

olera. [A general review of cholera om 1832 to 1849.]

[Nieuws. Courant, Tiel, 1848, Nos. 38–41.]

olére (Le) à Paris et à Londres.

[Gaz. méd. de Paris, 1846, I, 3e s., pp. 653–654.]

olera (The) epidemic of 1866.

[Brit. Med. Jour., London, 1866, II, p. 169.]

Cholera (The) in St. Petersburg, Cronstadt, Prussia, Persia, south-eastern ports, Cardiff and London.

[Lancet, London, 1871, II, p. 275.]

Choléra, invasion en Holland, en Belgique, en Angleterre, en France. Moyens préventifs.

[Journ. de méd. et de chirurg. prat., 1853, XXIV, 2e sér., pp. 529–534.]

Cholera on the continent.

[Lancet, London, 1866, II, pp. 706–708.]

Cholera u innych Krajach. [Cholera in foreign countries.]

[Przeglad Lekarski, Krakow, 1871, X, pp. 24, 56, 87, 255, 280, 304, 312, 336, 344, 352.]

Choleraens Vandring.

[Hosp. Tidende, Kjöbenhavn, 1865, VIII, pp. 174–175.]

Cholera-Chronik.

[Allg. Wien. Med. Zeitg., 1866, XI, pp. 265–267, 274–275, 291–292, 297–299, 306, 314–315, 329–331, 338, 347, 355, 362, 370–371, 378; 1871, XVI, pp. 546–547, 563–564, 581, 597, 613; 1873, XVIII, pp. 502–503, 511, 519–520, 531, 539, 547–548.]

Cholera morbus (Die), oder kurze Geschichte des Ursprunges und Verlaufes der indischen epidemischen Brechruhr, wie sie seit dem Jahre 1817 geherrscht hat, nebst ihrer Heilart und den gegen sie schützenden Vorsichtsmassregeln für Gebildete aller Stände dargestellt von einem praktischen Arzte. 12°. *Leipsig*, 1831. L.

Choléra-morbus (Le), ou caractère et progrès de cette maladie, depuis son invasion, jusqu'en 1831. 16°. *Bruxelles*, 1831. L.

Cholera-morbus (De) door de Jezuiten naar Europa overgebragt, en tot Bereiking van Hun doel in de XIX^e^ Eeuw aangewend. 8°. *Amsterdam*, 1854. [Is met geringe Wijziging het zelfde als het vorige No., andermaal opgedischt.]

Chronique du choléra asiatique.

[Arch. belg. méd. mil., Bruxelles, 1848, I, pp. 74–78, 131–137.]

Colera (Il) dell'anno 1855.

[La med. comun. Seregno, 1865, III, pp. 173–183.]

Comparative mortality of cholera.

[London Med. Gaz., 1832, IX, pp. 720–721.]

Coup d'œil sur la marche et les progrès du choléra-morbus.

[Archiv. gén. de méd., Paris, 1848, III, pp. 371–373.]

Derivation of the term "cholera."

[Lancet, London, 1833, II, pp. 227–228.]

Diffusion (The) of cholera in Europe.

[Med. Times and Gaz., London, 1872, I, pp. 736–737.]

Schnurrer (F.)—continued.
mit einem Supplement-Kärtchen der Verbreitung der Cholera morbus von August 1817 bis Ende Julius 1831. fol. *München*, 1831.

Schuette (J. A. V.) *De cholera veterum. 8°. *Casselis*, 1832. L.

Scoutetten (H.) Histoire médicale et topographique du choléra-morbus. 8°. *Metz*, 1831.

——— A medical and topographical history of the cholera morbus, including the mode of prevention and treatment. With a report read at the Royal Academy of Medicine Sept. 17th, 1831. Translated from the French by A. S. Doane. 8°. *Boston*, 1832. L.

——— Histoire chronologique, topographique et étymologique du choléra, depuis la haute antiquité jusqu'à son invasion en France en 1832.

[Gaz. hebd. de méd. et de chirurg., Paris, 1869, VI, 2e sér., pp. 435-436, 451-454, 482-486, 563-567, 577-580, 674-677, 721-724, 773-776, 801-804, 834-840.]

——— The same. 8°. *Paris*, 1869. L.

Simon *jun.* Name und eigentliche Bedeutung des Wortes χολέρα [cholera]; missbräuchlicher Ausdruck Cholera morbus.

[Med. Convers.-Bl., Hildburghausen, 1831, pp. 110-112.]

Simon (J.) The recent diffusion of cholera in Europe.

[Brit. Med. Jour., London, 1872, I, pp. 695-696.]

Smith (D. B.) Early records of cholera.

[Indian Ann. of Med. Science, Calcutta, 1870, XXVI, pp. 166-218.]

[Smith (E. H.)] *Discours académique sur le mot choléra. 8°. [*Paris*, 1832.]

Smith (H. L.) Cholera Assurance Society.

[Provinc. Med. and Surg. Jour., 1849, pp. 82-83.]

Smith (S.) Report on the progress of epidemic cholera, made to the Society of Statistical Medicine, New York, Oct., 1854.

[N. Y. Journ. of Med., 1854, XIII, n. s., pp. 368-377.]

Sobernheim. Zur Cholera-Literatur dieses Jahres.

[Berlin Med. Central-Zeitg., 1832, I, pp. 39-44.]

Sonnerat. Voyage aux Indes-Orientales et à la Chine. 8°. *Paris*, 1782.

[Tom. I, pp. 200-204.]

Sonty (J. J. A.) Rapport sur le choléra-morbus observé dans l'Inde en 1829 et 1830, et comparé à la maladie qui a régné en Europe. 8°. *Paris*, 1832.

Sovet. Discussion du rapport sur un tableau statistique de l'épidémie de choléra qui a régné en 1866.

[Bull. de l'Acad. roy. de méd. de Belg., 1867, I, pp. 862-880.]

Tholozan. De la marche de deux grandes épidémies actuellement regnantes, le choléra et la fièvre jaune.

[Gaz. méd. de Paris, 1853, VIII, 3e s., pp. 555-556, 597-598.]

——— Marche du choléra en 1855.

[Gaz. méd. de Paris, 1855, X, pp. 435-436.]

Tholozan (J. D.) Observations sur le choléra. Ie mémoire. De l'antiquité du choléra dans l'Inde. 2e mémoire. Du choléra dans l'Inde depuis le seizième jusqu'à la fin du dix-huitième siècle. 8°. *Paris*, 1868. L.

——— Durée du choléra asiatique en Europe et en Amérique, ou persistance des causes productrices des épidémies cholériques hors de l'Inde.

[Gaz. hebd. de méd. et de chirurg., Paris, 1871, VIII, 2e sér., pp. 671-674, 706-710, 717-719, 751-754; 1872, IX, 2e sér., pp. 68-72, 100-105, 147-152.]

Thomas-Longueville (P. F.) Recherches sur le choléra asiatique observé en Amérique et en Europe. 8°. *Paris*, 1857. L.

Toner (J. M.) A catalogue of medical works on cholera, in the library of . . . 8°. *Washington*, 1865. L.

Vacher. Statistique du choléra de 1865 à 1867 en Europe. roy. 8°. *Strasbourg*, 1868. L.

Veit (A.) Ueber die Cholera im Oriente.

[Arch. f. physiol. Heilk., Stuttgart, 1850, pp. 485-492.]

Walser (T.) Cholera. Reviewing its history and considering quarantine regulations.

[Trans. N. Y. Acad. of Med., 1874, I, 2d ser., pp. 155-156.]

Wawruch (A. I.) Disquisitio medica cholerae cujus mentio in Sacris Bibliis occurrit [Numeri cap. xi.] 4°. *Vindobonae*, 1832. L.

Weiland (C. F.) Cholera-Karte, oder Uebersicht der progressiven Verbreitung der Cholera seit ihrer Erscheinung im Jahre 1817 über Asien, Europa, Afrika, etc. imp. fol. *Weimar*, 1832.

Werres. Ein Beitrag zur Naturgeschichte der Cholera unter Benutzung der ältern Schriftsteller.

[Hufeland's Journ. der prakt. Heilkunde, 1832, LXXIV, pp. 31-61.]

xions sur quelques mots de la Bi- au sujet du choléra. 8°. *Marseille*, 5.

rts on epidemic cholera drawn up at desire of the cholera committee of Royal College of Physicians by Will- Baly, and W. W. Gull. 8°. *Lon-*, 1854. L.

lts of the cholera epidemic, 1854.

rn. Times and Gaz., London, 1855, x, n. s., pp. 1-74, 650-652.]

ance of cholera.

NDON Med. Gaz., 1833, XI, pp. 87-88.]

imen of the weekly cholera returns der the regulations of the privy coun-

P. Priv. Counc., 1866 [append.], pp. 239-241.]

istics of cholera.

NCET, London, 1855, I, n. s., p. 90.]

istik der Cholera-Erkrankungen in n Garnisonen des 1. Armeecorps im hre 1871.

LLG. med. Central-Zeitg., Berlin, 1871, XL, p. 1211.]

tistique du choléra dans l'armée elge] pendant l'épidémie de 1849.

RCH. belg. de méd. mil., Bruxelles, 1850, VI, p. 134.]

Statistique du choléra en Europe.

[GAZ. hebd. de méd. et de chirurg., Paris, 1867, IV, 2e s., pp. 15-16.]

Sur le choléra de 1865.

[GAZ. des hôp. Paris, 1866, pp. 313-314.]

Table for the uniform medical registration of cases of cholera, issued by the Western Medical and Surgical Society of London.

Tableau proportionnel de la mortalité et des guérisons obtenues dans les hôpitaux de Paris depuis l'invasion de l'épidémie jusqu'au 30 avril inclusivement.

[GAZ. méd. de Paris, 1832, III, pp. 333-335.]

Value of medical services in the treatment of cholera. Action against a board of guardians.

[LONDON Med. Gaz., 1849, XLIII, pp. 781-782.]

Versteckte (Eine) Cholera-Epidemie.

[MITTHEILGN. d. bad. ärztl. Vereins, Karlsruhe, 1867, XXI, pp. 130-132.]

Was malignant cholera known in England before 1831-32?

[LONDON Med. Gaz., 1849, XLIV, pp. 545-550.]

Zur Cholera-Statistik.

[ALLG. med. Central-Zeitg., Berlin, 1849, XVIII, pp. 795-796.]

D.—ACCOUNTS OF CHOLERA IN PARTICULAR LOCALITIES.

ON SHIPBOARD.

dington. On cholera which visited r majesty's Black Sea fleet in the au- mn of 1854.

ED. Times & Gaz., 1856, XIII, n. s., pp. 223-225.]

row. Narrative of the late outbreak Asiatic cholera on board the steam- ip "England."

ARMY Stat. San & Med. Repts., London, 1864, VI, pp. 363-367.]

ssaing. Cholera-morbus am Bord der orvette "Adria."

MILITÄRÄRZTL. Zeit., 1863, IV, pp. 77-78, 81-82.]

mett (W.) Extracts from a report on he cholera which attacked the fleet in he Black Sea in August, 1854.

MED. Times & Gaz., 1855, X, n. s., pp. 27-28, 53-54, 80-81, 107-108, 130-131.]

salas. Relazione dell'epidemia colérо- a da cui fu colpita la prima divisione ell'armata di Levante nella Dobrut- cha nel luglio e agosto del 1854. Se- uita da brevi considerazioni del dott. . Fallani.

GAZ. med. ital. Tosc., Firenze, 1855, I, 3a ser., pp. 389-393, 397-400, 405-410, 417-423.]

Celarier (C.) Rapport médical sur les deux épidémies de choléra qui ont sévi à bord des navires à émigrants Clotilde et Peter Hattrick en sept. et oct. 1854.

[ARCH. belge de méd. mil., 1855, XVI, pp. 15-23.]

Collins (J.) Notes and observations on the loss of lives from cholera on board the ship "Brutus" [etc.]

[LONDON Med. Gaz., 1832, X, pp. 412-415.]

Heath (N. W. J.) Asiatic cholera, as it appeared on the steamship "England," in April, 1866.

[BULL. N. Y. Acad. of Med., 1866, III, pp. 131-139.]

Henderson (A.) The cholera on board H. C. ship Berwickshire in Bombay harbour.

[TRANS. Med. & Phys. Soc. of Calcutta, 1831, V, pp. 311-324.]

Hitchcock (W.) Account of the cholera on board the H. C. ship Abercrombie Robinson.

[TRANS. Med. & Phys. Soc. of Calcutta, 1831 V, pp. 165-187.]

Hutchison (A. C.) Cholera—the Topaze frigate.

[LONDON Med. Gaz., 1832, IX, p. 297.]

Kupfer (O.) Ueber eine Cholera-Epidemie an Bord des Auswandererschiffes Franziska.

[Vierteljahresschrift f. gerichtl. Med., 1873, xviii, n. f., pp. 75, 85, 92.]

Lawrason (S. C.) Notes of the epidemic cholera, on board the U. S. frigate Constellation, in the harbor of Mahon, in September, 1834.

[Maryland Med. & Surg. Jour., 1840, i, pp. 281–285.]

Lawson. Extract regarding the outbreak of cholera in the ship "Renown," on passage from Gibraltar to the Cape of Good Hope.

[Army Stat. San. & Med. Repts., London, 1864, vi, pp. 359–363.]

Lawson (R.) Observations on outbreaks of cholera in ships at sea.

[Med. Times & Gaz., 1871, ii, pp. 152–156; *also in* Trans. Epid. Soc., London, 1871, iii, pp. 288–309.]

Macpherson (J.) Cholera at St. Kilda, and on board an East Indiaman; its propagation at sea.

[Med. Times & Gaz., 1867, i, p. 454.]

——— On cholera as carried by ships, with reference to some modern theories.

[Med. Times & Gaz., London, 1867, ii, pp. 32–34.]

Pettenkofer (M. v.) Ueber Cholera auf Schiffen und den Zweck der Quarantänen.

[Ztschr. f. Biologie, 1872, viii, pp. 1–70, 294–295; 1 pl.]

Porteous (W.) Treatment of cholera on board of the Circassian convict ship.

[Lancet, London, 1851-52, ii, pp. 718–719.]

Ridreau. Notes pour servir à l'histoire du choléra. [Sur la Salamandre en 1854.]

[Gaz. des hôp., 1867, pp. 488–489.]

Robson (W.) History of epidemic cholera as it appeared on board his majesty's ship Malabar, on its passage from Bombay to the equator.

[Edinb. Med. & Surg. Jour., 1833, xix, pp. 507–513.]

Rossi (F.) Se il cholera orientale si asi sviluppato l'anno 1821 nella i. r. corvetta in mezzo all'Oceano.

[Giorn. p. serv. ai progr. d. patolog., Venezia, 1836, v, pp. 156–363.]

Smart (W. R. E.) An account of a cholera epidemic which affected the crew of her majesty's ship Queen, in the summer of 1850.

[Med. Times & Gaz., 1854, ix, n. s., pp. 409–411, 435–436.]

Sutherland (J.) On cholera [illegible] at sea.

[Madras Quar. Med. Jour., 1839, i, pp. [illegible]

Veitch (J. T.) Cholera in the Black Sea fleet.

[Med. Times & Gaz., 1854, ix, n. s., pp. 350–351.]

Vetter. Ueber den Ausbruch der C[illegible] auf der königlich-schwedischen [illegible] gatte Chapman. Ein wichtiger [illegible] zu den Forschungen über die Pathog[illegible] der Cholera.

[Journ. der prakt. Heilk., 1832, lxxv, pp. 100.]

Walser (T.) History of the cholera [illegible] the Atalanta.

[Med. & Surg. Reporter, Phila., 1871, [illegible] 373.]

Outbreak of cholera on emigrant [illegible] England.

[Lancet, London, 1866, i, pp. 482–484.]

AFRICA.

Audouard (F. M.) Histoire du [illegible] morbus qui à régné dans l'Armée [illegible] çaise au nord de l'Afrique, et par[illegible] autres habitants de cette contr[illegible] 1834 et en 1835. 8°. *Paris*, 1836.

Beaumier (A.) Le choléra au Mara[illegible] marche au Sahara jusqu'au Senega[illegible] 1868. 8°. *Paris*, 1872.

Christie (J.) Notes on the cholera [illegible] demics in East-Africa.

[Trans. Epid. Soc., Lond., iii, 1871, pp. 25–[illegible] *also, in* Lancet, 1871, i, pp. 113–[illegible] additional notes, ibid., 1873, i, pp. 257–[illegible]

Clot. Relation des épidémies de c[illegible] morbus qui ont régné à l'Hedjaz [illegible] Suez et en Égypte.

[Ann. de la Med. Phys., xxix, pp. 21–[illegible] printed at Marseilles in 8°, 1834.]

Hamont. Lettres adressés à M. L[illegible] sur le choléra-morbus d'Afrique.

[Annales d'hygiène, 1838, vii, pp. 28–[illegible]

Smart. On the distribution of cholera in Africa.

[Trans. Epid. Soc., Lond., 1872, iii, pp. 2[illegible]

Cholera (The) in West Africa.

[Lancet, London, 1869, ii, pp. 282–[illegible]

Algeria.

Audouard. De l'exportation du morbus de Marseille à Paradis [illegible] en 1837.

[Revue méd., Paris, 1838, ii, pp. 76–[illegible]

Barnier (J. B.) Note sur l'ép[illegible] choléra qui a sévi dans l'île de [illegible]

ler (J. B.)—continued.

dant les mois de septembre, octobre novembre 1870.

HIV. de méd. navale, XVI, 1871, pp. 190–198.— AZ. hebd., 1871, pp. 559–561.]

ard. Notice sur l'épidémie de choléra qui a régné à Constantine pendant les s d'août, septembre et octobre, 1854.

C. de mém. de méd. mil., 1858, XVI, 2e sér., pp. 7–229.]

set (P.) *Étude sur le choléra épidémique de 1865, 1866, 1867, observées à Alger. *Paris*, 1870. L.

C.) *Remarques sur le choléra épidémique observé en Algérie. 4°. *Paris*, 1. L.

tier de Clanbry. Sur l'épidémie lérique d'Alger.

UR. hebd. des progrès des sc. et inst. méd., 5, III, pp. 259–266; IV, pp. 19–22.]

on. Note sur la marche suivie, dans traitement du choléra-morbus d'Alger.

L. méd de Paris, 1836, IV, pp. 76–77.]

— Détails intéressants sur le choléra i vient de régner parmi les troupes de province de Constantine.

TEN. des connaiss., Paris, 1838, V, pp. 106–2*.]

r (J.) Rapport sur l'épidémie de léra de 1865 dans la province d'Alger. er, 1866.

ppe. Épidémie de choléra et de res cholériques qui a régné pendant 6 de 1854 [at Batna, province of nstantine].

L. des hôp. Paris, 1856, pp. 94–96.]

rançon (F. S. J.) **Relation, sous le nt de vue de l'hygiène publique, de la rche du choléra dans la subdivision Mostaganem, province d'Oran . . . uis son invasion jusqu'à sa terminai- en 1851, accompagnée de notes relas à la mortalité dans l'armée . . . *Paris*, 1862.**

rulleau. Rapport sur l'épidémie de léra qui a régné à Constantine en llet, août et septembre 1867. *Constantine*, 1869.

ingier. Notes sur le choléra-morbus démique de Tanger en 1856.

C. de mém. de méd. mil., 1856, XVIII, 2e sér., p. 175–188.]

ttetten. Rapport adressé à monsieur ministre de la guerre par le dr. Scoutten, . . . envoyé en mission à Alger, r ordre du 31 août 1835, avec le titre

Scoutetten—continued.

de méd. ordinaire, pour y observer et aider à combattre le choléra.

[REC. de mém. de méd. mil., 1836, XXXIX, 1e sér. pp. 21–60.]

Tassard (A.) Choléra en Algérie.

[GAZ. des hôp., 1851, p. 552.]

Vignes (P.) Histoire du choléra-morbus qui a régné épidémiquement à Oran (Afrique) pendant les mois d'octobre, de novembre 1834, et de janvier 1835. 8°. *Paris et Metz*, 1836. L.

Vincent (M. A.) *et* **Collardot** (V.) Le choléra d'après les neuf épidémies qui ont régné à Alger depuis 1835 jusqu'en 1865. 8°. *Paris*, 1867. L.

Bellinghausen (Island of).

Moorss. Die Cholera in Bellinghausen (Kreis Essen) im Sommer 1868.

[VIERTELJAHRSSCHRIFT für gerichtl. und öffentl. Med., 1870, XIII, neue Folge, pp. 177–186.]

Canary Islands.

Houghton (H.) The cholera in the Canary islands.

[LONDON Med. Gaz., 1851, XLVIII, pp. 130–131.]

Egypt.

Abbate (O.) Sul cholera-morbus nel 1848. 8°. *Cairo*, 1848.

Angelin (J. P.) *Du choléra en Égypte: observations faites sur cette maladie et sur son traitement pendant l'expédition du Luxor, 1831. 4°. *Paris*, 1834. L.

Aubert-Roche. Rapport sur le choléra dans l'isthme de Suez en juin et juillet 1865. . . . 8°. *Paris*, 1865.

Broussais (F. J. V.) Quelques notes sur l'épidémie du choléra-morbus observée en Égypte au mois d'août 1831.

[ANN. de la méd. phys., XXII, pp. 150–164.]

Colucci-Bey (J.) Quelques notes sur le choléra qui sévit au Caire en 1850 et 1855 . . . 4°. *Paris* [1862].

——— Le choléra en Égypte . . . 8°. *Paris*, 1866.

De Castro (S. V.) Del cholera morbus in Alessandria d'Egitto.

[L'IMPARZIALE, 1865, V, pp. 557–563, 581–586.]

Dumesthe. Un mot sur le choléra d'Alexandrie . . . 8°. *Alexandrie*, 1865.

Du Vivier (E.) Égypte et choléra . . 8°. *Paris*, 1866. L.

Fox (T.) Cholera in Egypt.

[BRIT. Med. Jour., 1865, II, pp. 667–670.]

Frias (R.) Cenni sul cholera morbus sviluppatosi in Alessandria 1831. 8°. *Lucca*, 1832.

Grassi. Relazione e riflessioni sopra il cholera indiano che ha regnato in Egitto l'anno 1848.
[OMODEI, Ann. un. di med., 1848, CXXVIII, pp. 18–43.]

Griesinger (W.) Klinische und anatomische Beobachtungen über die Krankheiten von Egypten. [Cholera.]
[ARCH. f. physiol. Heilk., Stuttgart, 1853, pp. 375–376.]

Grimsud (M. G.) Du choléra en Égypte dans ses rapports avec l'épidémie de Marseille en 1865.
[GAZ. méd. de Paris, 1866, XXI, pp. 316–317.]

Maruchi. Statistischer Bericht über die Cholera-Epidemie zu Aegypten im Sommer 1855.
[AERZTL. Intell.-Bl., 1856, III, p. 648.]

Mimaut. Choléra en Égypte.
[ANN. d'hygiène, Paris, 1831, VI, pp. 476–480.]

Nizzoli. Cenno sul cholera-morbus divampato in Alessandria d'Egitto.
[OMODEI, Ann. un. di med., 1839, LXI, pp.146–151.]

Patterson (J.) On the late pestilence in Cairo, Egypt.
[MED. Times & Gaz., 1865, II, pp. 545–547.]

Zagiell (J.) Choléra-morbus d'Égypte.
[GAZ. des hôp., 1865, pp. 474–475. Reprinted at Marseilles in 8°, 1865.]

Cholera (The) in Egypt.
[MED. Times, London, 1848, XVIII, pp. 246, 281, 298.]

Cholera prodoljaiet sia v Ehiptie.
[MEDITZYNSKIY viestnik, iejeniedelna gazeta, St. Petersburg, 1865, p. 300.]

Fogo (*Island of*).

Leaõ (José Fernandez da Silva.) On the cholera epidemy at the island of Fogo, in the Cape de Verds, in 1855. [Translated from the Portuguese by Geo. Miller and J. O. McWilliam.]
[TRANS. of the Epid. Soc., 1857 (appended to the Jour. of Pub. Health, 1857, vol. 3), pp. 41–62.]

Cholera (The) epidemy at the island of Fogo, in the Cape de Verds.
[MED. Times & Gaz., London, 1857, XV, n. s., pp. 46–47.]

Gambia.

Papers relating to the outbreak of cholera at the Gambia. Plans. 1869.

Saint Jago (*Island of*).

Hopffers. Notes on the epidemic of cholera morbus at the island of St. Iago, Cape de Verds, in 1856.
[MED. Times & Gaz., 1860, II, pp. 645–646.]

Tunis.

Ferrini (G.) Intorno al cholera di T— dell'anno 1867. *Milano*, 1867.
[*Also, in* GAZ. med. italiana Lombardia, V. a 1868, XXVIII, pp. 225–230, 234–239, 273–[illegible] 287, 293–295.]

Guyon. Lettre sur l'état du cholera [illegible] la régence de Tunis.
[GAZ. méd. de Paris, 1850, V, pp. 481–48[illegible].

Lumbroso (A.) Cenni storico-scientifici sul cholera-morbus asiatico che [illegible] la reggenza di Tunis nel 1849-[illegible] 8°. *Marsiglia*, 1850.

Moriggia. Rapporto sulla memoria del dott. G. Ferrini sul cholera di Tunis l'anno 1867.
[GIORN. d. r. Acad. di med. di Torino, 1[illegible] ser., pp. 21–23.]

Nunes Vias (G. A.) Del cholera a [illegible]
[L'IMPARZIALE, 1867, VII, pp. 305–307.]

——— Osservazioni e considerazioni [illegible] iche sul cholera tratte dall'altre[illegible] demia di Tunisi.
[L'IMPARZIALE, 1868, VIII, pp. 37–47, 73–[illegible] 109, 131–136. Reprinted at Firenze 18[illegible]

Zanzibar (*Island of*).

Memorandum by the army [illegible] commission on communication from [illegible] Bryden regarding cholera at Zanzibar
[REPORT on measures adopted for the [illegible] improvement in India from June [illegible] June, 1871, London, 1871, pp. 216–217.]

NORTH AMERICA AND WEST IN[illegible]

BRITISH AMERICA.

Goldstone (Geo.) The cholera [illegible] bourg, C. W.
[BRIT. AM. Jour. of Med. & Phys. Sc[illegible] V, pp. 177.]

Henry (W.) Report on malignant [illegible] era amongst the troops in Canada the summer of 1854.
[MED. Chron., Montreal, 1854, II, pp. 21[illegible]

Lloyd (S. McV.) Report of an [illegible] of cholera in Chezzetcook and Ha[illegible] N. S., originating in an infected [illegible] ship, in November, 1871.
[LANCET, London, 1871, pp. 226–227.]

Mountain (G. B.) Recollections [illegible] cholera.
[JOUR. of health, Phila., 1858, IV, pp. 225–[illegible] in WESTERN Med. Gaz., Cincinnati, 18[illegible] 265–268.]

Paine (Martyn). History of the [illegible] at Montreal.
[BOSTON Med. & Surg. Jour., 1832, VI[illegible] 66.]

——— History of the cholera at Mon[illegible]
[BRIT. Amer. Jour., 1861, II, pp. 65–[illegible]

ıs (Horatio). The appearance of the ılera in Kingston.
[Amer. Jour. of Med. & Phys. Science, 842, v, pp. 89–90.]

era at Quebec.
[Boston Med. & Surg. Jour., 1832, vi, pp. 379–82.]

era (The) in Canada.
[Am. Amer. Jour. of Med. & Phys. Science, 849, v, pp. 107–108.]

lene and cholera.
[Can. Chron., Montreal, 1855, ii, pp. 163–165.]

ress (The) of the cholera in Canada.
[Am. Am. Jour. of Med. & Phys. Science, 1849, , pp. 135–137.]

ınt (The) outbreak of cholera near lifax, N. S.
[Lancet, London, 1871, ii, p. 896.]

ort of the commission appointed by e sanitary board of the city councils, visit Canada, for the investigation of e epidemic cholera prevailing in Mont- al and Quebec. 8°. *Phil.*, 1832. L.

ort of the commissioners employed to vestigate the origin and nature of the idemic cholera of Canada. Published y order of the board of health. 8°. *ew York*, 1832. L.

ort on the cholera in Quebec.
[Lancet (London), 1833, i, pp. 473–475.]

UNITED STATES.

k (L. C.) Report on cholera in the nited States.
[Edinburgh Med. & Surg. Jour., 1833, xxxix, pp. 235–248.]

wling (W. K.) The cholera on its late ampage.
[Nashville Jour. of Med. & Surg., 1873, xii, pp. 65–114.]

kson (S. H.) On the progress of siatic cholera during the years 1844–5–46–47 and 48.
[N. Y. Jour. of Med., 1849, ii, pp. 9–20; 1 map.]

chassaing. De la route suivie par le holéra-morbus dans l'Amérique, et de a nature transportable de cette mala- lie.
[Gaz. méd. de Paris, 1851, vi, pp. 115–116.]

tt (G.) On the cholera of North Amer- ca.
[Med. Gaz., London, 1836, xvii, pp. 43–49.]

nter (H. M.) Facts confirmatory of he contagion of cholera. [Among In- liana.]
[New Orleans Med. & Surg. Jour., 1849–50, vi, pp. 740–741.]

dson (A. B.) Report upon the course of cholera through two hundred towns and cities in the Mississippi Valley in 1873.
[Amer. Public Health Assn. reports, N. Y., 1875, i, pp. 224–252; 1 map.]

Judson (A. B.)—continued.

Peters (J. C.) Conveyance of cholera from Ireland to Canada and the United States Indian Territory in 1832.
[Galveston Med. Jour., 1867, ii, pp. 938–940.]

——— Epidemic cholera routes, means of travel, and prevalence in the South.
[Med. Investigator, Chicago, 1873, x, pp. 511–514.]

——— Facts and theories about the recent outbreak of Asiatic cholera.
[N. Y. Med. Jour., 1873, xviii, pp. 472–478.]

——— The introduction of the cholera.
[Med. & Surg. Reporter, 1873, xxix, pp. 357–358.]

——— On the outbreak of Asiatic cholera, 1873.
[Sanitarian, 1873–74, i, pp. 466–469.]

——— Notes on cholera.
[Nashville Jour. of Med. & Surg., 1874, xiv, n. s., pp. 129–133.]

——— The south western cholera of 1873.
[Sanitarian, 1873–74, i, pp. 277–282, 313–319.]

——— The same. 8°. [*n. p., n. d.*] L.

——— The south-western epidemic of 1873.
[Clinic, Cin., O., 1874, v, pp. 277–281.]

Quinn (J. J.) The south-western cholera of 1873.
[Clinic, Cin., O., 1874, v, pp. 133, 136, 247, 249.]

Smith (E.) The cholera in America.
[Med. Times, London, 1849, xx, pp. 226–227.]

Vaché (A. F.) A brief historical sketch of the rise and progress of cholera to the present time, &c., &c.
[N. Y. Jour. of Med., 1850, iv, pp. 301–314.]

Warren (E.) Sketch of the progress of the malignant or epidemic cholera, from its arrival in America. With tables illustrative of its progress in the principal cities it has visited. 8°. *Boston*, 1832. L.

Woodward (J. J.) *See* Report on epidemic cholera in the army of the United States [etc.]

Wynne (J.) Abstract of report on epidemic cholera, as it prevailed in the United States in 1849 and 1850. Appendix (C) to the report of the general board of health on the epidemic cholera of 1848 and 1849. Presented to both houses of parliament. 8°. *London*, 1852. L.

Yates. Recherches historiques sur le choléra asiatique et sur son apparition dans l'Amérique du nord.
[Gaz. méd. de Paris, 1835, iii, p. 234.]

Cholera (The) Gazette. Weekly. Nos. 1–16, v. 1, July 11 to Nov. 21, 1832. 8°. *Philadelphia.* L.

Cholera in the United States in 1873. [Printed for the use of the American Public Health Association, at its conference in New York, Nov. 11, 1873.] 8°. [*n. p.*, 1873.] L.

Cholera (The) in the west.
[Boston Med. & Surg. Jour., 1834, IX, pp. 44–48.]

Report of the committee on foreign affairs on a memorial of the board of health of the city of New York on the subject of the disease known as Indian or Asiatic cholera. (With accompanying documents.) 22d Congress 1st session, Ho. of Reps. 8°. *Washington, D.C.*, 1832. L.

Report on epidemic cholera in the army of the United States, during the year 1866. [With appendix containing statistical tables and extracts from official reports.] Army medical department, U. S., circular No. 5, May 4, 1867. By J. J. Woodward. 4°. *Washington*, 1867. L.

Report on epidemic cholera and yellow fever in the army of the United States during the year 1867. [With appendix containing statistical tables and extracts from official reports.] Army medical department, U. S., circular No. 1, June 10, 1868. By J. J. Woodward. 4°. *Washington*, 1868. L.

Alabama.

Dement (J. J.) Cholera in Huntsville, 1873.
[Trans. Med. Assn. Ala., 1874, pp. 198–204.]

Jordan (M. H.) Cholera in Birmingham, Alabama, 1873.
[Trans. Med. Assn. Ala., 1874, pp. 188–197.]

Arkansas.

Cholera in Little Rock, Arkansas. Report by the board of health.
[Amer. Publ. Health Assn. reports, N. Y., 1875, I, pp. 257–260.]

California.

Gibbons (H.) Malignant cholera in California.
[Pacific Med. & Surg. Jour., 1865–66, VIII, pp. 191–197.]

Logan (T. M.) A history of the epidemic cholera that prevailed in Sacramento city in the autumn of 1850.
[Fenner's South. Med. Repts., 1850, II, pp. 463–468.]

Logan (T. M.)—continued.

——— Report of the cholera at Sacramento in 1852. Its analogy if not identity with malignant congestive intermittent—[illegible] attendant meteorological phenomena—[illegible] history, pathology and treatment of the disease.
[New Orleans Med. & Surg. Jour., 1852–3, pp. 488–503.]

Taylor (W.) Cholera as it appeared in California.
[New Orleans Med. & Surg. Jour., 1852–3, pp. 53–56.]

Report of the cholera at Sacramento 1852. 8°. L.

Georgia.

Harris (S. N.) Report of the treatment of some cases of cholera occurring on Savannah river.
[Charleston Med. Jour., 1849, IV, pp. 5[illegible]

Kollock (P. M.) An account of cholera as it prevailed in the city of Savannah and its vicinity, in the fall of 1854.
[Southern Med. & Surg. Jour., 1857, [illegible] 335.]

Illinois.

Bevan (T.) The recent epidemic of cholera at the county hospital, Chicago.
[Chicago Med. Jour., 1866, XXIII, pp. [illegible]

Davis (N. S.) How far do the facts accompanying the prevalence of epidemic cholera in Chicago, during the summer and autumn of 1866, throw light on the etiology of that disease? 8°. Chicago, 1867. L.

Hall (G. W.) An account of the epidemic cholera as it prevailed in the town of Carthage, Ill., in the summer of 1854.
[Boston Med. & Surg. Jour., 1855, LII, pp. 159.]

Marsh (W. R.) Report on cholera in Chicago in 1866.
[Trans. Ill. State Med. Soc., 1867, pp. 9–[illegible] *also in* Chicago Med. Jour., 1867, XI, 289–296.]

Miller (B. C.) Cholera as it prevailed in Chicago, Ill., in 1873.
[Amer. Pub. Health Assn. repts., 1875, I, pp. 261–264.]

Spading (J. W.) History of cholera in the vicinity of Victoria, Knox co. L.
[North-Western Med. & Surg. Jour., VII, pp. 430–440.]

Winans (N. T.) Cholera in Illinois.
[Eclectic Med. Jour., Cin., O., 1850, [illegible] 393.]

Cholera (The).
[North-Western Med. & Surg. Jour. go and Indianapolis, 1849–50, [illegible] pp.

lera in Chicago.
ESTERN Jour. of Med., Detroit, 1854-55, II, pp. 136-141.]

gress of cholera in Chicago.
ORTH-WESTERN Med. & Surg. Jour., Chicago and Indianapolis, 1854, XI, pp. 327-336.]

ana.

nett (W. T. S.) Brief remarks on idemic cholera as it appeared in Vernes, Ind., and its vicinity, in the summer of 1833.
ESTERN Jour. Med. & Phys. Sciences, Cin., O., 1835, VIII, pp. 9-13.]

ld (N.) Cholera.
RANS. Ind. State Med. Soc., 1868, pp. 114-119.]

y (Ch.) An account of the cholera as appeared in Salem, Indiana, during the mmer of 1833.
RANSYLV. Jour. of Med., 1834, VII, pp. 42-53.]

nczynski (A. de). Report on Asiatic holera, as it appeared in New Albany, ndiana, in the year 1852.
WEST. Jour. of Med. & Surg., 1852, II, pp. 389-393.]

vens (T. M.) Cholera as appearing in ndianapolis during the summer of 1873.
INDIANA Jour. of Med., 1874, V, pp. 49-61.]

tton (G.) A report on Asiatic cholera, s it prevailed in this state in 1849-50-1-52.
TRANS. Ind. State Med. Soc., 1853, pp. 109-175.]

— The same. [Reprint.] With observations on the laws which govern its rogress. 8°. *Indianapolis*, 1854. L.

atts (J. S.) Cholera in Indiana.
ECLECTIC Med. Jour., Cin., O., 1849, I, n. s., pp. 352-353.]

ns.

rnsworth (P. J.) Some remarks on the holera as it appeared in Clinton, Iowa.
MED. & Surg. Rep., 1867, XV, pp. 429-430.]

NAS.

gley (W. H.) Observations on cholera in military practice.
MED. Exam., Phil., 1852, VIII, n. s., pp. 504-514.]

ntucky.

ll (Th. S.) Remarks on spasmodic cholera as it appeared in Louisville in October, 1832.
TRANSYLV. Jour. of Med., 1832, V, pp. 534-549.]

— A notice of cholera as it appeared in Louisville in May, 1849.
WESTERN Jour. of Med. & Surg., 1849, III, 3d ser., pp. 519-520.]

Bell (Th. S.)—continued.

— Brief notes on cholera in Louisville, in 1850.
[WEST. Jour. of Med. & Surg., 1850, II, pp. 99-104.]

Berry (W.) *and* Wilson (F. C.) History of cholera at Lancaster in 1873.
[AM. Pract., 1873, VIII, pp. 193-204.]

— The same. [Reprint.] 8°. *Louisville*, 1873. L.

Cooke (J. E.) Remarks on cholera, as it appeared in Lexington, in June, 1833.
[TRANSYLV. Jour. of Med., 1833, VI, pp. 309-356.]

— Brief remarks on a late review of his paper on cholera as it appeared in Lexington in June, 1833.
[TRANSYLV. Jour. of Med., 1834, VII, pp. 55-100.]

— The same. [Reprint.] 8°. [*n. p., n. d.*] L.

Dills (M.) The cholera in Kentucky.
[CLINIC, Cin., O., 1874, V, p. 198.]

Drake (D. P.) Cholera in Lexington, Kentucky.
[TRANS. Ky. State Med. Soc., 1852, pp. 321-336.]

Dudley (B. W.) Observations on epidemic cholera.
[TRANSYLV. Jour. of Med., 1833, VI, pp. 322-332.]

Edwards (C. H.) The cholera in Kentucky.
[MED. & Surg. Reporter, 1873, XXIX, p. 71.]

McClellan (E.) An account of the epidemic of cholera, during the summer of 1873, in eighteen counties of the state of Kentucky. 8°. *Cambridge*, 1874. L.
[*Also, in* AMER. Public Health Assn. repts. and papers, N. Y., 1875, I, pp. 200-223.]

Yandell (L. P.) An account of spasmodic cholera, as it appeared in the city of Lexington, in June, 1833.
[TRANSYLV. Jour. of Med., 1833, VI, pp. 197-228.]

— The same. [Reprint.] 8°. *n. p.* L.

— Cholera in Louisville.
[WESTERN Jour. of Med. & Surg., 1851, VIII, 3d s., pp. 269-272.]

Louisiana.

Allen (S.) [History of the first twenty cases of cholera and cholera morbus in the United States.]
[ANN. report bd. of health of Louisiana, New Orleans, 1874, pp. 23-46.]

Bemiss (S. M.) Cholera.
[NEW ORLEANS Jour. of Med., 1868, XXI, pp. 510-514.]

Booth (W. A.) On the cholera of Lafourche Interior.
[FENNER'S South. Med. Repts., 1849, I, pp. 196-235.]

Calhoun (J. W.) A short sketch of the cholera as it prevailed in Trinity, La.,

Elkinton (J. A.)—continued.
pitals in New York, taken on the 24th to 27th of July, 1832; with some facts and observations of a practical nature. 1832. 8°. L.

Elmendorf (J. L. H.) Cholera in Brooklyn, Long Island, during the past summer.
[St. Louis Med. Reporter, 1866-67, I, pp. 433-437.]

Ferris (F. T.) A treatise on epidemic cholera, as observed in the Duane street cholera hospital, New York, during its prevalence there in 1834. 8°. *New York*, 1835. L.

Francis (J. W.) Letter on the cholera asphyxia, now prevailing in the city of New York; addressed to J. B. Read, chairman of the medical board, Savannah. 8°. *New York*, 1832. L.

Garnier (P.) Importation du choléra de France à New-York en 1865.
[L'Union méd., Paris, 1866, XXIX, 2e s., pp. 592-594.]

Hamilton (F. H.) Vegetable malaria one of the exciting causes of Asiatic cholera; being a report on the immediate or exciting cause of the Asiatic cholera which appeared in Buffalo, N. Y., 1852. Also the report of a committee appointed to investigate the relation of upturning of the soil to the causation of the cholera. 8°. *Buffalo*, 1852. L.

Hutchison (J. C.) History and observations on Asiatic cholera in Brooklyn, N. Y., in 1854.
[N. Y. Jour. of Med., 1855, XIV, n. s., pp. 46-70.]

——— The same. [Reprint.] 8°. *s. p.* L.

Page (F. B.) Cholera in New York.
[Boston Med. & Surg. Jour., 1849, XL, pp. 479-484.]

Paine (M.) Cholera at New York.
[Boston Med. & Surg. Jour., 1832, VI, pp. 353-356.]

——— Letters on the cholera asphyxia as it has appeared in the city of New York: addressed to J. C. Warren, of Boston and originally published in that city. Together with other letters, not before published. 8°. *New York*, 1832. L.

Reese (D. M.) A plain and practical treatise on the epidemic cholera, as it prevailed in the city of New York in the summer of 1832; including its nature, causes, treatment and prevention. Designed for popular instruction. . . . 8°. *New York*, 1833. L.

Reese (D. M.)—continued.
——— Cholera at Bellevue hospital, New York.
[Amer. Jour. Med. Sci., 1859, XIX, pp. 162-163.]

Sherrill (H.) An essay on epidemics, as they appeared in Dutchess county from 1809 to 1825; . . . With an appendix containing an account of the epidemic cholera, as it appeared in Poughkeepsie in 1832. 4°. *New York*, 1832. L.

Smith (O. H.) The epidemic cholera of 1849 and 1854.
[N. Y. Med. Jour., 1865, II, pp. 215-219.]

Sterling (J. W.) History of the Asiatic cholera at quarantine, Staten Island, N. Y., in December, 1848, and Jan., 1849.
[N. Y. Jour. of Med., 1849, III, pp. 9-29; 3 tables.]

Swinburne (J.) Report of cholera at quarantine, port of New York, for the year ending December 31, 1865, and December 31, 1866.
[Trans. N. Y. Med. Soc., 1867, pp. 249-290.]

Thayer (W. H.) Epidemic cholera in Brooklyn, New York.
[New York Med. Jour., 1866-67, IV, pp. 161-183.]

Vanderveer (J. H.) Epidemic cholera as it appeared at the Franklin st. hospital, during the summer of 1854.
[N. Y. Jour. of Med., 1855, XV, n. s., pp. 201-223.]

Whiting (A. B.) Report on the origin and progress of the cholera at quarantine, Staten Island, N. Y.
[Buffalo Med. Jour., 1848-49, IV, pp. 561-567.]

Woodward (A. T.) Asiatic cholera,—its prevalence as an epidemic at Whitehall, N. Y., in 1849; observations on its pathology,—successful results from the opium-plan of treatment.
[Vt. Med. Jour., 1874, I, pp. 57-63.]

Yale (L. M.) Report of the epidemic cholera occurring on Blackwell's island, New York, in the summer 1866. 8°. *New York*, 1867. L.

Yates (C. C.) Observations on the epidemic now prevailing in the city of New York, called the Asiatic or spasmodic cholera; with advice to the planters of the south, for the medical treatment of their slaves. 8°. *New York*, 1832. L.

Zabriskie (J. B.) Remarks on cholera as it appeared in the alms-house of King's county, New York.
[Amer. Jour. of Med. Sciences, 1832, XI, pp. 355-368.]

Cholera at the military posts in the harbor of New York in the summer of 1867. 8°. *New York*, 1868. L.

olera at Ward's island, 1866. Report of the sanitary committee.
[Repts. Met. Bd. of Health, New-York, 1866. pp. 424–427.]

olera in New York, and its progress in the United States.
[N. Y. Jour. of Med., 1849, III, n. s., pp. 96–100.]

urse (The) of the epidemic in New York and its institutions, 1866. Diagram showing the range of total mortality, and the course of cholera diarrhœa, cholera infantum, and the sum of zymotic deaths, week by week. 4°. *New York*, [*n.d.*] L.

ocuments and papers explanatory of the progress of cholera, in the Auburn and Sing Sing state prisons, during 1832.
[Trans. N. Y. Med. Soc., 1834–35, pp. 79–94.]

ecords of cholera upon the islands of the East river.
[Repts. Met. Bd. of Health, New York, 1866, pp. 251–301.]

emarks on the cholera, embracing facts and observations collected at New York, during a visit to the city expressly for that purpose. [Signed J. Maurin, Thomas H. Webb, Sam'l Boyd Tobey.] 3d ed. 12°. *Providence*, 1832. L.

eport of the majority of the committee on medical societies and colleges on so much of the governor's message as relates to the cholera. State of New York, No. 98. In senate, March 25, 1850. 8°. [1850.] L.

eport of the proceedings of the sanatory committee of the board of health in relation to cholera, as it prevailed in New York in 1849. 8°. *New York*, 1849. L.

eport of the standing sanatory committee of the board of health of the city of New York, on the subject of Asiatic cholera at present prevailing at the quarantine establishment of New York, at Staten Island. 8°. *New York*, 1848. L.

eport of the board of health, on cholera, as it appeared in Rochester, New York, in 1852. Published by order of the board. 8°. *Rochester*, 1852. L.

Report to the board of health of the city of Albany, N. Y., on the bills of mortality from June 23d to July 17th, 1832.] fol. [*n. p., n. d.*] L.

eport on the epidemic cholera at Buffalo in 1849.
Buffalo Med. Jour., 1849–50, V, pp. 313–333.]

Ohio.

Awl (W. M.) A brief history of the epidemic cholera as it appeared in the town of Columbus, and the penitentiary of Ohio, in the summer of 1833.
[Western Jour. Med. & Phys. Sci., 1834, VII, pp. 341–349.]

Carroll (T.) Observations on the Asiatic cholera, as it appeared in Cincinnati during the years of 1849 and 1850.
[Western Lancet, Cin., O., 1854, XV, pp. 321–354, 385–405, 449–470.]

——— The same. [Reprint.] 8°. [*n.p.*] L.

Drake (D.) An account of the third visitation of epidemic cholera, in connexion with dysentery, at Cincinnati, in the summer of 1834. Historical and ætiological remarks.
[Western Jour. of Med. & Phys. Sc., 1835, VIII, pp. 109–193.]

——— Epidemic cholera in Cincinnati.
[Western Jour. of Med. & Phys. Sci., 1832–33, VI, pp. 321–364.]

——— The same. [Reprint.] 8°. *Cincinnati*, 1832, L.

——— Miscellaneous observations—historical, statistical, ætiological and therapeutic, on the prevailing epidemic.
[Western. Jour. of Med. & Phys. Sci., 1834, VII, pp. 161–181.]

Edwards. Report on cholera and ship or typhoid fever.
[Trans. Ohio State Med. Soc., 1852, pp. 99–45.]

Freeman (Z.) Cholera report.
[Eclectic Med. Jour., Cin., O., 1857, XXVII, pp. 65–70.]

Halderman. Cholera in the Ohio penitentiary.
[Clinic, Cin., O., 1874, V, pp. 169, 172, 181, 184; 1 tab.]

Henry (J. F.) A letter, to Dr. Short, on the cholera as it occurred in Cincinnati, Ohio, in the month of October, 1832.
[Transylv. Jour. of Med., 1833, V, pp. 507–533.]

——— The same. [Reprint.] 8°. [*n. p., n. d.*] L.

Jordon (J. H.) Report of . . ., as attending physician of the Cincinnati cholera hospital to the board of health.
[Ecl. Med. Jour., Cincinnati, 1849, I, n. s., pp. 410–414.]

Latta (S. A.) The cholera in Cincinnati; or a connected view of the controversy between the homœopathists and the Methodist Expositor; also, a review of the report read before the Homœopathic Association. 8°. *Cincinnati*, 1850. L.

Mendenhall (G.) An account of cholera as it appeared in Cincinnati during the year 1850.
[Trans. Am. Med. Assoc., 1851, IV, pp. 181-200; 1 map.]

Miller (A.) Review of Dr. S. A. Latta's pamphlet, entitled "The cholera in Cincinnati, or a connected view of the controversy between the homœopathists and the Methodist Expositor; also, a review of the report read before the Homœopathic Association." 8°. *Cincinnati*, 1850. L.

Newton (O. E.) An essay on Asiatic cholera, as it appeared in Cincinnati, O., in the years 1849, 1850, and 1866, with remarks upon its treatment, and a tabulated statement of 117 cases treated. 8°. *New York and Cincinnati*, 1867. L.

Peters (J. C.) The Cincinnati cholera.
[Clinic, Cin., O., 1874, V, pp. 164-165, 212-213, 223-224, 236-238.]

Quinn (J. J.) Cholera in Cincinnati, Ohio.
[Amer. Public Health Assn. repts. & papers, N. Y., 1875, I, pp. 290-302.]

——— The cholera in Cincinnati.
[Clinic, Cin., O., 1874, V, pp. 121-123.]

Richey (C. D.) [Cholera.]
[New Orleans Med. & Surg. Jour., 1873-74, I, n. s., pp. 442-444.]

Walker (E.) Cholera in Sandusky.
[Ecl. Med. Jour., Cincinnati, 1849, I, n. s., pp. 552-553.]

Cholera.
[Trans. Clarke Co. (Ohio) Med. Soc., Cincinnati Lanc. & Observer, 1873, XVI, pp. 606-609.]

Cholera in Cincinnati—triumph of liberal principles.
[Eclectic Med. Jour., Cin., O., 1849, n. s., I, pp. 284-288.]

Pennsylvania.

Gilbert. Cholera on vessels at Philadelphia.
[Trans. College of Phys. of Phila., II, n. s., 1856, pp. 279-283; discussion on ibid., pp. 295-299.]

Jackson (T. H.) Account of the Asiatic cholera, as it prevailed in Columbia, Lancaster co., Pa., in the autumn of 1854.
[Am. Jour. of Med. Sci., 1855, XXIX, n. s., pp. 336-346.]

Jackson (S.) Personal observations and experience of epidemic or malignant cholera, in the city of Philadelphia.
[Amer. Jour. of Med. Sciences, 1832, XI, pp. 289-346; 1833, XII, pp. 76-120.]

Jewell (W.) Statistics of cholera with the sanitary measures adopted by the board of health prior to, and during the prevalence of the epidemic in Philadelphia, in the summer of 1849, chronologically arranged. 8°. *Philadelphia*, 1849. L.

Lowber (W.) The cholera at the Philadelphia navy-yard, in July, 1866.
[Med. & Surg. Reporter, 1866, XVII, pp. 6-

Snively (W.) Report on Asiatic cholera [in Pittsburgh].
[Amer. Public Health Association reports & papers, N. Y., 1875, I, pp. 303-305.]

Stillé (M.) *and* **Mayer** (E. R.) History of the epidemic cholera, at the Philadelphia almshouse, Blockley, in the summer of 1849.
[Med. Exam., Phila., 1849, V, n. s., pp. 69-

Cases of cholera noticed in counties Pennsylvania in the years 1850-51 and previous years.
[Transact. Med. Soc. of Penna., Phila. 1851, I, p. 74; II, pp. 69-84, 91, 93; V, pp. 31, 34, 77, 79-81, 93, 101-102, 125, 128; n. s., pp. 98-99, 151; 1866-67, II, pp. 97, 289 [etc.

Cholera in Philadelphia.
[Transact. Med. Soc. of Penna., Phila. 1851, n. s., pt. I, pp. 181-182.]

Observations on a letter from Dr. N. Chapman, of Philadelphia, to Dr. W. Tyler, of Frederick (Md.), on the nature of cholera, as appearing in Philadelphia—August, 1832. 8°. [n. p.], 1832. L.

Report of the College of Physicians Philadelphia to the board of health epidemic cholera. 8°. *Philadelphia*, 1832. L.

Report of the committee of the Philadelphia Medical Society on epidemic cholera. 8°. *Philadelphia*, 1832.

Statistics of cholera: with the sanitary measures adoted by the board of health prior to, and during the prevalence of the epidemic in Philadelphia, in the summer of 1849, chronologically arranged. 8°. *Philadelphia*, 1849.

Rhode Island.

Parsons (U.) Cholera in Rhode Island.
[Boston Med. & Surg. Jour., 1850, XLII, pp. 3-

Snow (E. M.) History of the late cholera in Providence. 8°. [n. p.].
[From Providence Jour., 1832.]

Turner (W.) Account of the first case of cholera at Newport.
[Boston Med. & Surg. Jour., 1832, VI, pp. 3-

atistics and causes of Asiatic cholera, as it prevailed in Providence, in the summer of 1854. Being a letter addressed to the mayor of Providence. 8°. *Providence*, 1855. L.

Tennessee.

filey (F. K.) Cholera in Knoxville, Tenn., and vicinity in 1873.

[Amer. Publ. Health Assn. repts. and papers, N. Y., 1875, I, pp. 282–289.]

owling (W. K.) Cholera, as it appeared in Nashville in 1849, 1850, 1854, and 1866. 8°. *Nashville (Tenn.)*, 1866. L.

—— An account of the cholera, as it appeared at Nashville, in the year 1873. 8°. *Nashville*, 1873. L.

—— Cholera notes.

[Nashville Jour. of Med. & Surg., 1874, XIV, n. s., pp. 13–38, 101–105.]

uchanan (A. H.) Cholera as it appeared in Nashville.

[West. Jour. of Med. & Surg., 1849, I, pp. 369–376.]

coombs (S. W.) The cholera at Bowling Green.

[Nash. Jour. of Med. & Surg., 1873, XII, pp. 143–147.]

ake (J. P.) Cholera in Nashville.

[Med. Investigator, 1873, X, pp. 506–511.—Am. Homœop. Obs., 1873, X, pp. 477–484.]

ite (J. L.) Cholera in Lebanon and vicinity.

[Nash. Jour. of Med. & Surg., 1873, XII, pp. 210–214.]

askins (E. B.) Cholera, as it appeared in Clarksville, Tennessee; with reflections.

[West. Jour. of Med. & Surg., 1849, II, pp. 1–15.]

eckeley (E. C.) An endeavor to show that the cholera, which existed on Folly island, near Charleston, neither arose from nor was propagated by means of contagion.

[Am. Jour. of Med. Sci., 1834, XIV, pp. 377–382.]

ong. Cholera in East Tennessee.

[Nashville Jour. Med. & Surg., 1854, VIII, pp. 273–277.]

eters (J. C.) "Cholera in Nashville."

[N. Y. Med. Record, 1873, VIII, p. 517.]

eynor (J. S.) Observations on cholera as it appeared in Nashville in 1873.

[Nash. Jour. of Med. & Surg., 1873, XII, pp. 129–137.]

evier (W. R.) Report upon epidemic cholera as it appeared at Jonesborough, Tenn.

Amer. Publ. Health Assn. repts. & papers, N. Y., 1875, I, 279–281.]

Shanks (L.) A brief account of the origin, progress, symptoms, mortality, and treatment of pestilential cholera, as it occurred in the Mississippi valley, especially in the city of Memphis.

[Amer. Jour. of Med. Sci., 1849, XVIII, n. s., pp. 13–34.]

—— Report of the commencement, prevalence, fatality, treatment, &c., of pestilential cholera, in Memphis and its vicinity; with the prominent facts bearing upon the unsettled question of its imported or domestic origin.

[Fenner's South. Med. Repts., 1849, I, pp. 382–397.]

Tuck (W. J.) A brief account of the Asiatic cholera, as it occurred on the plantation of Jno. Trigg, esq., some twenty miles above Memphis, on the Mississippi river.

[New Orleans Med. & Surg. Jour., 1851–52, VIII, pp. 329–337.]

Van Deman (J. H.) Cholera in Chattanooga, Tenn., and cities south of Nashville, during the summer of 1873.

[Amer. Publ. Health Assn. repts. and papers, N. Y., 1875, I, pp. 253–256.]

Warne (W.) Cholera in Nashville.

[Eclectic Med. Jour., Cin., O., 1849, I, n. s., pp. 350–351.]

Wight (E. M.) Cholera at Chattanooga.

[Nash. Jour. of Med. & Surg., 1873, XII, pp. 193–199.]

Yandell (H.) An account of spasmodic cholera, as it appeared in Shelbyville, Tennessee, in the summer of 1833.

[Transylv. Jour. of Med., 1834, VII, pp. 37–39.]

Cholera.

[Nashville Jour. of Med. & Surg., 1851, I, pp. 126–127.]

Texas.

Jarvis (N. S.) Report on the rise, progress and decline of epidemic cholera in the valley of the Rio Grande.

[Fenner's South. Med. Repts., 1849, I, pp. 436–448.]

Massie (J. C.) Remarks on the treatment of cholera in Houston, Texas.

[Eclectic Med. Jour., Cin., O., 1849, I, n. s., pp. 153–155.]

Rösch. Aerztlicher Bericht über meine Reise nach Texas. Die Cholera.

[Med. Correspbl. des Würtemberg. aerztl. Vereins, 1855, XXV, pp. 37–40.]

Wright (J. J. B.) Report on the topography of San Antonio, and the epidemic cholera that prevailed there in the spring of 1849.

[Fenner's South. Med. Repts., 1849, I, pp. 415–435.]

West Virginia.

Jepson (S. L.) Cholera in Wheeling, West Va., in 1873.
[Amer. Publ. Health Assn. Repts. and papers, N. Y., 1875, I, pp. 267-278.]

MEXICO.

Chaniac (E. de). Remarques et observations sur le choléra-morbus au Mexique en 1833, et sur l'emploi du guaco.
[Gaz. Med. de Paris, 1835, III, pp. 452-453.]

WEST INDIES.

Candido (F. de P.) Relatorio ácerca do cholera-morbus precedido de considerações sanitarias aos portos do imperio. . . . 4°. *Rio de Janeiro*, 1855.

Guyon. Note sur le choléra de la Soufrière, petite population de Sainte-Lucie, l'une des Antilles.
[Gaz. méd. de Paris, 1866, XXI, pp. 445-446.]

Cholera paa St. Thomas og St. Jan.
[Supplement. til Bibl. for Laeger, 1854, pp. 41-52.]

Dansk-vestindiske (De) Oer. (St. Croix, St. Thomas, St. Jan.) (Cholera.)
[Supplement. til Bibl. for Laeger, 1869, pp. 453-457.]

Treatment of cholera in the West Indies—appointment of medical officers of health by government.
[London Med. Gaz., 1851, XLVII, p. 48.]

Bahamas.

Farre (F. J.) Cholera in the Bahamas.
[Med. Times & Gaz., London, 1853, VI, pp. 300-301.]

Barbadoes.

Cholera in Barbadoes.
[Lancet, London, 1854, II, n. s., p. 93.]

Cuba.

Babé (J.) Relacion de la marcha que ha seguido en el hospital civil el cólera morbo, presentado epidémicamente el dia 15 de Junio de 1870.
[Anal. Acad. de cienc. de la Habana, 1870, VII, pp. 90-95.]

Dupierris (M.) Sur le choléra; relation des faits observés à la Havane en 1850. Rapport de M. Tallois.
[Bull. de l'Acad. roy. de méd. de Belgique, 1855-56, XV, pp. 963-970.]

La Sagra (R. de). Tablas necrológicas del cólera-morbus en la ciudad de la Habana y sus arrabales formadas á escitacion del escmo. señor intendente de ejército conde de Villanueva. 4°. *Habana*, 1833.

La Sagra (R. de)—continued.
Cholera in Havana.
[Med. Mag., Boston, 1833, I, pp. 668-674.]

Documentos relativos al cólera en la Habana [1867-68].
[Anal. Acad. de cienc. de la Habana, 1867, IV, pp. 291-302, 337-351; 1868, V, pp. 87-90, 110-113, 161-165, 193-196.]

Estadística de la epidemía del cólera, llevada por distritos, barrios, partidos ruralés y hospitales, desde que recrudeció el 20 de Junio hasta su declinacion favorable el 31 de Julio próximo pasado.
[Anal. Acad. de cienc. de la Habana, 1868, V, pp. 163-165.]

Guadeloupe.

Cuzent (G.) Épidémie de la Guadeloupe (1865-66). . . . 8°. *Paris*, 1867.

Lignières (H.-V.-A.) Relation d'un épidémie de choléra à la Guadeloupe, 1865-1866. 4°. *Montpellier*, 1867. C.

Pellarin (A.) Considérations sur la topographie médicale de la Guadeloupe pour servir à l'histoire de l'épidémie de choléra qui a éclaté dans cette île en 1865.
[Arch. de méd. nav., 1868, IX, pp. 417-430; X, pp. 5-18.]

——— Hygiène des pays chauds. Contagion du choléra demontrée par l'épidémie de la Guadeloupe. 8°. *Paris*, 1872. L.

Jamaica.

Bowerbank (L. Q.) Lessons from the cholera at Jamaica.
[Med. Times & Gaz., London, 1866, I, pp. 389-401.]

M'Ilree (J. D.) Extracts from a report on epidemic cholera in Newcastle, Jamaica.
[Med. Times & Gaz., London, 1850, VII, n. s., pp. 572-573.]

Melville (H.) Some reflections on the nature and curability of cholera Asiatica, the result of careful observations of the epidemy during the years 1850 and 1851, and the experimental application of a peculiar method of treatment.
[Amer. Med. Monthly, N. Y., 1853, III, pp. 358-368.]

Milroy (G.) Report made . . . to the colonial office on the cholera epidemic in Jamaica 1850-51. . . . fol. *London*. 1854. L.

ales (C. M.) Fatal case of cholera at rt-Royal.
[AMAICA Phys. Jour., 1834, I, pp. 50-51.]

kin (J.) Statistical report of the epimic cholera in Jamaica. 8°. *London*, 32. L.

J. S.) **A brief inquiry into some of** e causes of the virulence and malignity the cholera in the island of Jamaica.
[J. Med. Reporter, 1851, IV, pp. 197-207.]

mpson (J. B.) Cholera in Jamaica.
[ST. London, 1851, I, n. s., pp. 532-533.]

tson (J.) Cholera in Jamaica. An count of the first outbreak of the disse in that island in 1850.
[ST, London, 1851, I, n. s., pp. 40-41.]

lera at Jamaica.
[ES. Times, London, 1850, I, n. s., p. 550.]

lera (The) in Jamaica.
[ONDON Med. Gaz., 1851, XLVII, pp. 173-174.]

lera (Jamaica). Return to an address f the house of commons, dated 17 Feb., 51;—for, "copies or extracts of despatches and other documents relating the outbreak of the cholera in the land of Jamaica, and respecting any pplications made to her majesty's government for the adoption of measures to ect the difficulties thus brought upon e colony." (Ordered, by the house of mmons, to be printed, 10 Mar., 1851.) l. [*n. p., n. d.*] L.

lera. Epidemic of cholera in Jamaica.
[ES. Times, Lond., 1851, II, n. s., p. 25.]

vages (The) of cholera at Kingston in amaica.
[LONDON Med. Gaz., 1850, XLVI, pp. 1109-1110.]

is.

olera in the island of Nevis, West Indies [Report on]. (From the Antigua Observer of April 6, 1854.)
[ASS. Med. Jour., 1854, p. 394.]

CENTRAL AMERICA.

lendorf (F.) Die Cholera in Costa Rica nd Nicaragua.
[Allg. med. Centr.-Zeit., Berlin, 1859, XXVIII, pp. 238-239.]

rrine (H.) An account of the epidemic cholera, in Campeche, and other parts of Yucatan.
[WESTERN Jour. Med. & Phys. Sci., 1834, VII, pp. 321-341.]

SOUTH AMERICA.

Estrazulas (E. M.) Epidemic cholera in South America.
[AMER. Jour. Med. Sci., Phila., 1873, LXVI, pp. 74-84.]

Valdes (J. M.) Memoria sobre el cólera-morbus, escrita de órden del supremo gobierno. . . . 8°. *Lima*, 1838.

Expedição (A) de Matto Grosso e a cholera morbus.
[GAZ. med. da Bahia, 1867-68, II, p. 36.]

Mappa geeneral dos cholericos tratados no hospital do Saladero desde 30 de Março até 6 de Maio de 1868.
[GAZ. med. da Bahia, 1868, III, p. 7.]

Relatorio (O) do presidente da junta central de hygiene publica.
[GAZ. med. da Bahia, 1866, I, pp. 277-281.]

Brazil.

Asschenfeldt (F.) Die Cholera in Maroim, Brasilien, während der Monate März und April 1863.
[VIRCHOW's Archiv, 1863, XXVIII, pp. 414-421.]

Mendonça (J. J. de) Boletim do expediente do presidente da provincia de Sergipe contendo medidas e providencias em soccorro da população da mesma provincia affectada do cholera morbus desde 1862 até 1863. 4°. *Sergipe*, 1863. L.

Rego (J. P.) Memoria historica das epidemias de febre amarella e cholera-morbo que têm reinado no Brazil. 8°. *Rio de Janeiro*, 1873.

Cholera (Die) und ihre Verbreitung in Brasilien.
[ALLG. med. Centr.-Zeit., Berlin, 1856, XXV, pp. 429-431.]

Epidemic (The) cholera, as it appeared in Rio de Janeiro during 1855.
[Med. Times & Gaz., London, 1857, XV, p. 62.]

Buenos Ayres.

Cholera (De) te Buenos-Ayres.
[GENEESK. Courant, Tiel, 1867, No. 24.]

Contribucion al estudio del cólera en 1874.
[REVISTA med.-quirúrg., Buenos Aires, 1874, X, pp. 393-398; XI, pp. 11-13.]

Estado sanitario: la epidemia del cólera morbus en Buenos Aires, 1874.
[REVISTA med.-quirúrg., Buenos Aires, 1874, X, pp. 341-342, 373.]

ASIA AND EAST INDIES.

Karbinsky (D.) Amtlicher Bericht abgestattet seiner Eminenz dem Erzbisch

Karbinsky (D.)—continued.

Narses, von * * . Anweisung zur Heilung der Cholera, einer Krankheit, die nicht vor langer Zeit in Indien ausgebrochen ist, und sich in verschiedenen Gegenden gezeigt hat. (Aus dem Armenischen.) *Tyflis*, 1823.

[JOUR. der prakt. Heilk., 1824, LIX, pp. 33–39.]

Michell (W. D.) The progress and geographical extension of cholera in the Khanates, Central Asia, in 1872.

[LANCET, London, 1872, II, p. 690.]

Cholera in the east.

[LANCET, London, 1872, II, p. 498.]

Progress of the Asiatic cholera in the east.

[DUBLIN Med. Press, 1846, XVI, p. 382.]

Afghanistan.

Cholera in Afghanistan.

[MED. Gaz., N. Y., 1869, III, p. 55.]

Bokhara.

Burnes (A.) Cholera [in Bokhara].

[TRANS. Med. & Phys. Soc., Calcutta, 1835, VII, 2d part, pp. 460–461.]

Arabia.

Buez (A.) Une mission au Hedjaz (Arabie). Contributions à l'histoire du choléra. La pèlerinage de la Mecque, les services sanitaires et les institutions quarantenaires de la Mer Rouge; les épidémies de choléra de 1865 et de 1871–1872 au Hedjaz; le commerce des esclaves dans la Mer Rouge; ethnologie; géographie de la peninsula arabique. 8°. *Paris*, 1873.

L.

Darcet (F.) Note sur le choléra-morbus de la Mecque; extrait d'une lettre du consul général de France en Égypte, communiquée à l'Académie des sciences.

[GAZ. méd. de Paris, 1831, II, pp. 319–320.]

Dechambre (A.) Le choléra. La Mecque et le Gange. Moyens sanitaires.

[GAZ. hebd. de méd. et de chirurg., Paris, 1865, II, 2e s., pp. 641–643.]

Mahmoud (H. E.) Communications sur le choléra. Le choléra et le haddj (pèlerinage de la Mecque).

[L'UNION méd., 1865, XXVIII, 2e s., pp. 260–264.]

Polak (E.) Die Mekkapilger und die Cholera.

[MED. Presse, Wien, 1872, XIII, pp. 641–642.]

Cholera in the Hedjaz.

[LANCET, London, 1872, II, pp. 530–531.]

China.

Home. Report on the sanitary c... of Shanghai, and on the epidemic o... era, which visited that station in ...

[ARMY Stat., San., & Med. Repts., Lond... V, pp. 359–360; 1 map.]

Livingstone (J.) Observations o... epidemic cholera as it appeared in C...

[TRANS. Med. & Phys. Soc. of Calcutta ... pp. 204–210.]

Thin (G.) On cholera at Shangha...

[EDINB. Med. Jour., 1869, XIV, pp. ...–...]

Ullersperger (J. B.) Die Cholera-E... mie zu Macaú im Jahre 1862.

[AERZTL. Intell.-Bl., München, 1864, X... 536.]

Cochin-China.

Armand (A.) Du choléra observé ... chinchine et de son traitement.

[GAZ. hebd. de méd. et de chirurg. Par... 2e s., pp. 614–616, 646–649, 661–663, 747–749. Also reprint in 8°, Paris, 1...

——— Mémoire sur le choléra obser... Cochinchine.

[REC. de mém. de méd. mil., Paris, 1... s., pp. 143–149.]

Poujade (A.) * Du choléra da... chinchine française. 4°. *Paris*, 1...

India.

Anderson (W. S.) An account of ... epidemic in India, in 1817 and 1...

[EDINB. Med. & Surg. Jour., 1819, ... 372.]

Annesley (J.) Sketches of the m... valent diseases of India: compr... treatise on the epidemic cholera ... east [etc.] 8°. *London*, 1...

Baleguer (F.) History of Asiatic ... morbus; its courses, symptoms, ... prognosis, termination and treat... . . . . being a result of seventee... observation in the presidency ... dras. . . . 8°. *Agra* [n. d.]

Balfour (E. G.), **Sutlefe** (R. S. M... **Taviah** (A. C.), *and* **Griffith** H... port on the recent epidemic outb... cholera at Thayetmyoo.

[MADRAS Quar. Jour. of Med Sc., ... 305–345.]

Barry (J. H.) On the epidemic cho... Assam in 1853.

[INDIAN Ann. of Med. Sci., Calcutta ... 441–456.]

Beatson (*Dr.*) Report on the epi... cholera in Bengal in 1867.

[ARMY Stat., San., & Med. Repts. ... pp. 335–359; 1 chart.]

her (J. W.) Outbreak of cholera at roda, in the B battery, 18th brigade al artillery, June, 1865.

[MY Stat., San., & Med. Repts., London, 1864, I. pp. 435–440.]

· J.) Contributions to the pathology cholera, embracing its history, modi-ations, stages and treatment, as the ease appeared in the Bombay presi-ncy from 1818 to 1842. . . . . 8°. *ndon*, 1849.

vn (T.) On cholera, more especially it has occurred during late years in tish India, a letter addressed to Sir McGrigor. 8°. *Edinburgh*, 1824. L.

len (J. L.) Memorandum on the chol-epidemic of 1872 in Northern India. *Simla*, 1872. L.

— Report on the general aspects of olera in 1869; a sequel to the history epidemic cholera in the Bengal presi-ncy in 1866–68.

[VIII Ann. Rept. San. Commr. with the Govt. of India, 1869, app. B, pp. 181–239.]

— Vital statistics of the Bengal presi-ncy. Cholera epidemics of recent ars viewed in relation to former epi-mics: a record of cholera in the Ben-l presidency from 1817 to 1872. fol. *lcutta, office of the supt. of govt. print-g*, 1874. L.

CONTENTS.

A report on the cholera of 1866–68, and its relations to the cholera of previous epidemics. With an appendix of tables showing the admissions and deaths from cholera in the European and native armies during the twenty-seven years from 1826 to 1853. *Calcutta*, 1869.

Report on the general aspects of epidemic cholera in 1869: a sequel to a report on the cholera of 1866–68. *Calcutta*, 1870.

Report on the general aspects of epidemic cholera in 1872, with appendix. *Calcutta*, 1874.

Note on the epidemic connection of the cholera of Madras and Bombay with the cholera epidemics of the Bengal presidency. *Calcutta*, 1871.

alas. "Le choléra dans l'Inde." 8°. *ris*, 1873.

pman (E.) Remarques générales sur pidémie de choléra dans l'Inde. Ex-ait du grand rapport fait en 1824, par s médecins de Madras, sur cette mala-e, traduit par M. Blin.

[. sect. de méd. soc. acad. dépt. Loire-inf., 1-52, VIII, pp. 92–104.]

pperfield (W. N.) Report on the cases epidemic cholera treated in the gen-al hospital, Madras, from July 4 to Oc-ber 31, 1866.

[Madras Quar. Jour. of Med. Sci., 1867, XI, pp. 2-71, 9 tables.]

Chipperfield (W. N.)—continued.

——— Report on the cases of Asiatic cholera treated at the general hospital, Madras, during the second outbreak in 1866.

[Madras Quar. Jour. of Med. Sci., 1867, XI, pp. 265–277.]

Clark (G. B.) Cholera in India.

[London Med. Gaz., 1843–44, XXXIV, pp. 17–18.]

Corbyn (F.) Sur le choléra spasmodique et épidémique de l'Inde. Tiré de la bibliothèque universelle. Août 1831. 8°. L.

——— A treatise on the epidemic cholera, as it has prevailed in India; together with the reports of the medical officers, made to the medical boards of the presidencies of Bengal, Madras, and Bombay, for the purpose of ascertaining a successful mode of treating that destructive disease; and a critical examination of all the works which have hitherto appeared on the subject. 8°. *Philadelphia*, 1832. L.

Cornish (W. R.) Cholera in Southern India. A record of the progress of cholera in 1870. *Madras*, 1871.

——— An inquiry into the circumstances attending an outbreak of cholera in H. M.'s 18th hussars, Secunderabad, in the month of May, 1871.

[Rept. San. Commissioner for Madras, 1871, app. III, pp. xviii–lii; 3 maps.]

——— Memorandum on the movement of cholera in Southern India, 1869–72.

[Rept. San. Commissioner for Madras, 1871, app. I, pp. i–xi; 7 maps.]

——— On the seasonal prevalence of cholera in Madras.

[Med. Times & Gazette, London, 1868, I, pp. 312–313, 338–339.]

Cowen (H. L.) *and* **Scott** (J. B.) Report on an epidemic of cholera in her majesty's 18th hussars, Secunderabad, during the months of May and June, 1871.

[Rept. San. Commissioner for Madras, 1871, app. IV & V, pp. liv–lxx.]

Cunningham (D. D.) A report on cholera.

[Seventh annual rept. of the San. Com. with the government of India, 1870, appendix B, pp. 141–234; 11 plates.]

Cunningham (J. M.) Report on the cholera epidemic of 1872 in Northern India. fol. *Calcutta*, 1873. L.

——— Recent experience of cholera in India.

[Lancet, London, 1874, I, pp. 477–479.]

Day (F.) On cholera in Kurnool.
[MADRAS Quar. Jour. of Med. Sci., 1866, x, pp. 338–357.]

Deane (F. M. R.) Cholera in the Bunnoo district in October, 1867.
[INDIAN Med. Gaz., 1868, III, pp. 80–83; 1 table.]

Delioux de Savignac (A.) "Étude comparative du choléra épidémique observé dans l'Inde, en 1845 et en 1846, en Europe, en 1849. 4°. *Paris*, 1855. L.

Deville (J.-J.) Mémoire et observations sur l'épidémie de choléra morbus, qui a régné au Bengale pendant l'été de 1818. 8°. *Paris*, 1819. L.

Deville (J.-J.-L.-A.) Dissertation sur le choléra-morbus du Bengale. 4°. *Paris*, 1828. L.

Donaldson (J.) Some account of the cholera epidemic of 1861, as it appeared at Vizagapatam, Madras presidency, East Indies.
[EDINB. Med. Jour., 1863, IX, pp. 507–523.]

Doyle (W.) Report on the cholera epidemic as it appeared in the Cuddalore jail in Dec., 1863.
[MADRAS Quar. Jour. of Med. Sci., 1865, VIII, pp. 110–115; 1 table.]

Fairweather. The outbreak of cholera at Delhi.
[LANCET, London, 1872, I, p. 452.]

Fitzgerald (P. G.) Report on the cases of epidemic cholera treated in the Royapettah dispensary, Madras, from 8th July to 1st Nov., 1866.
[MADRAS Quar. Jour. of Med. Sci., 1867, XI, pp. 21–24.]

——— Supplementary report on cholera at the Royapettah dispensary.
[MADRAS Quar. Jour. of Med. Sci., 1867, XI, pp. 278–279.]

French (J.) Account of cholera as it appeared in H. M.'s 49th regiment, at Hazareebaugh, in 1835.
[MADRAS Quar. Med. Jour., 1840, II, pp. 436–443.]

Geddes (J. L.) Observations on cholera, as it appeared in an epidemic form in the 2nd Madras European light infantry regiment.
[MADRAS Quar. Med. Jour., 1841, III, pp. 296–305.]

Gibson (J.) Account of an epidemic attack of Indian cholera of spontaneous origin.
[EDINBURGH Med. & Surg. Jour., 1832, XXXVIII, pp. 289–301.]

Gorno (P.) Memoria sopra un'epidemia di cholera. [Estratto dai commentari

Gorno (P.)—continued.
dell'Ateneo di Brescia per l'a[illegible] demico MDCCCXXX.]
[OMODEI, Ann. Un. di Med., 1831, LX, pp. [illegible]

Graham (J.) Cholera in India.
[LANCET, London, 1862, II, [illegible]

Hachard (V.-N.) "Description [illegible] léra-morbus qui a régné épidémiquement à Calcutta pendant l'été de [illegible] suivie de quelques observations [illegible] nature de cette maladie. 4. [illegible] 1820.

Hall (T. M.) Remarks on the morbus of Calcutta.
[AMERICAN Med. Recorder, Phila. [illegible] 162–166.]

Harris (W. H.) Report on two epi[illegible] of cholera in the Madras pe[illegible] during the year 1866.
[MADRAS Quar. Jour. of Med. Sci. [illegible] 256–264.]

Hungerford (R.) *and* **Robertson** Reports on cholera in H. M.'s [illegible] ment and F battery 20th brigade [illegible] at Thayetmyo.
[REPORT San. Com. for Madras, 1[illegible] 1874, app. 2, pp. 1–42.]

——— The same. Reprint. fol. [illegible] 1874.

Hunter (R. A. H.) Report on cho[illegible] Particularly as it occurred, in the [illegible] wing of the queen's royals, in the [illegible] barracks of Bombay, in Aug.[illegible]
[INDIA Jour. of Med. Sci., Calcutta [illegible] 169–173.]

Innes (J. H. K.) Report on cholera [illegible] Oude division and Rohilcund dur[illegible] 1867.
[ARMY Stat., San. & Med. Repts. Lo[illegible] pp. 372–379.]

Jameson (J.) *See* **Report** on [illegible] demick cholera-morbus . . . [illegible] [etc.]; *and* **Bericht** über die [illegible] Seuche [etc.]

Johnson (G.) The theory and trea[illegible] of cholera in India.
[MED. Times & Gaz., London, 1869 [illegible]

Keraudren (P. F.) Du choléra de [illegible] fol. 1825.

——— Memoir on the cholera [illegible] India. Translated from the Fren[illegible] *London*, 1831.
[*With* CHOLERA Gazette.]

Lamare-Picquot. Observat[illegible] sur le choléra-morbus dans l[illegible] Bengale et à l'Île-de-France. [illegible] *Paris*, 1831.

wrence (J.) Observations on cholera, ·eing extracts from the half yearly med·al report of the 34th regiment of na·ive infantry for the year 1837.
[MADRAS Quar. Med. Jour., 1840, II, pp. 158–172.]

›big (G. v.) Eine briefliche Mittheilung ›ber die Cholera in Indien
[ARCH. f. wissenschftl. Hlkde., Göttingen, 1836, ·1. pp. 31–35.]

rimer (A.) Observations on epidemic holera; being extracts from the half early report of sick in the 24th regi·ent N. I., during its march from Secun·erabad to Palaveram in March and ›pril 1838.
[MADRAS Quar. Med. Jour., 1839, I, pp. 27–46.]

—— Report on the epidemic cholera as t has appeared amongst the native roops of the Madras army. *Madras,* ·46.

on (R. T.) An account of cholera in he [right] Chittagong column of the Looshai expeditionary force. *Calcutta,* ·72.

'Coah (J.) Cholera in the Chooar cam·›ign.
[INDIA Jour. of Med. Sci., 1834, I, pp. 439–442.]

acGrigor (J.) Special report on cholera, ›s it affected her majesty's 39th regiment ›t Bellary, during the months of March, ›pril, and May, 1839.
[MADRAS Quar. Med. Jour., 1840, II, pp. 99–107, 172–205.]

acloughlin (D.) The cholera in India.
[LANCET, London, 1862, I, n. s., pp. 187–188, 691.]

acpherson (J.) Cholera in its home. With a sketch of the pathology and reament of the disease. 8°. *London,* ·866. L.

—— De Cholera in hare Bakermat. Met ›ene korte Beschrijving van de Patholo·gie en de Behandeling der Ziekte. Uit ›et Engelsch vertaald door Doctor G. Vrolik. 8°. *Rotterdam,* 1866. L.

—— Die Cholera in ihrer Heimath, mit ›iner Skizze ihrer Pathologie und Thera·pie. Ins Deutsche übersetzt von Dr. R. Volten. Einzige vom Verfasser authori·sirte und durch Zusätze vermehrte deut·sche Ausgabe. 8°. *Erlangen,* 1867. L.

—— Die Cholera in Indien.
[ÄRZTL. Intell.-Bl., München, 1867, XIV, pp. 271–272.]

—— On the prevalence of cholera in India, according to season, and on some points in its etiology.
[MED. Times & Gaz., London, 1867, II, pp. 561–563; 2 tables; 590–593.]

Macpherson (J.)—continued.

—— Early notice of cholera in India.
[MED. Times & Gaz., London, 1874, II, p. 522.]

Martin (W. T.) Report upon the station and vicinity of Neemuch, with reference to the recent outbreaks of cholera which occurred in the left wing of H. M.'s 45th foot, from May to October, 1865, the means adopted to check its spread, and a short notice of the mode of treatment adopted.
[ARMY Stat. San. & Med. Reports, London, 1866, VI, pp. 367–382.]

Massy (H. H.) Remarks from memory upon an epidemic of cholera, that raged through most parts of the north-western provinces of India, during the months of July, Aug. and part of Sept. in the year 1845.
[LONDON Med. Gaz., 1848, XLI, pp. 144–150.]

Maunsell (S. E.) On the treatment of cholera in India.
[LANCET, London, 1861, II, n. s., p. 605.]

Montgomery (H. B.) The treatment of cholera in India.
[MED. Times & Gaz., London, 1866, I, pp. 262–264, 294.]

Moodelly (V. R.) Report on the treatment adopted in the recent epidemic of cholera at Pollachy.
[MADRAS Quar. Jour. of Med. Sci., 1867, XI, pp. 24–25.]

Mouat (J.) On cholera morbus, in his majesty's 14th regt. Berhampore.
[TRANS. Med. & Phys. Soc. of Calcutta, 1829, IV, pp. 265–307.]

—— Report on cholera, as it appeared in H. M. 13th light dragroons on the march from Bangalore to Madras, between the 20th December 1839 and 20th January 1840.
[MADRAS Quar. Med. Jour., 1840, II, pp. 443–450.]

Mouat (T.) Cholera at Bangalore. (Tables.)
[TRANS. Med. & Phys. Soc., Calcutta, 1835, VII, 2d ser., pp. 310–343.]

Munro (W.) Report on the epidemic visitation of cholera in the 93rd Sutherland Highlanders in 1862.
[ARMY Stat., San., & Med. Repts., London, 1862, IV, pp. 406–424.]

—— Report on the epidemic of cholera in the Sirhind division during the season of 1867.
[ARMY Stat., San., & Med. Repts., London, 1866, pp. 360–371.]

Murray (J.) Report on the attack of cholera in the central prison at Agra, in 1856.
[MONTH. Hom. Rev., London, 1857, I, pp. 469–482.]

Murray (J.)—continued.

——— Report on the Hurdwar cholera of 1867.
[EDINB. Med. Jour., 1868, XIV, pp. 303–311.]

——— Review of Dr. Cuningham's report of the epidemic cholera of 1872.
[BRIT. Med. Jour., 1874, I, pp. 71–74.]

Murray (T.) A brief report of the outbreak of cholera at Ajmeer during the rainy season of 1867.
[INDIAN Med. Gaz., Calcutta, 1868, III, p. 75.]

Orton (R.) An essay on the epidemic cholera of India. 8°. *Madras*, 1820.

——— The same. 2d ed. With a supplement. 8°. *London*, 1831. L.

Oxley (T.) Historical sketch of the general state of the public health in the settlement of Malacca for the year 1840. With detailed account of an epidemic cholera: and the value of the saline treatment.
[TRANS. Med. & Phys. Soc., Calcutta, 1842, VIII, pp. 328–349.]

Pearse (R. E.) Report on an outbreak of cholera occurring amongst the prisoners in Calicut jail, in March 1863.
[MADRAS Quar. Jour. of Med. Sci., 1863, VII, pp. 75–81; 2 tables.]

Pettenkofer (M. v.) Verbreitungsart der Cholera in Indien. 8°. *Braunschweig*, 1871. L.

——— Der neueste Bericht des Sanitary Commissioner Dr. J. M. Cuningham über die Cholera 1872 in Indien.
[ZTSCHR. f. Biologie, München, 1873, IX, pp. 411–431.]

Pillay (S. A.) On the relation existing between atmospheric vicissitudes, and epidemic cholera, at Mundium, in 1861.
[MADRAS Quar. Jour. of Med. Sci., 1865, VIII, pp. 406–408.]

Renzy (A. C. C. de). Cholera in India.
[LANCET, London, 1872, II, p. 623.]

——— The late outbreak of cholera at Secunderabad.
[LANCET, London, 1871, II, p. 623.]

Rogers (S.) Reports on Asiatic cholera in regiments of the Madras army, from 1828 to 1844, with introductory remarks on its modes of diffusion and prevention, and summary of the general method of treatment in India. 8°. *London*, 1848. L.

Scot (W.) Report on the epidemic cholera as it has appeared in the territories subject to the presidency of Fort St.

Scot (W.)—continued.
George. Drawn up by order of the government, under the superintendence the medical board. Appendix containing the sick returns of the army of St. George, from the year 1815 to ... inclusive, also diurnal tables of progress of cholera [etc.] 4°. Mad. 1824.

——— The same. Abridged from the original report printed at Madras ... with introductory remarks, by the author. 8°. *London*, 1849.

——— Traité complet du choléra de l'Inde, ou rapport sur le choléra démique tel qu'il s'est montré dans territoires soumis à la présidence Fort Saint Georges. Traduit par Blin. 8°. *Nantes*, 1831.

Shaw (J.) Cholera in the Calicut Salem jails.
[MADRAS Quar. Jour. of Med. Sci., ... 231–233.]

Shortt (J.) An account of the ... of cholera in the jail of Chingleput ... ing the month of March, 1863.
[MADRAS Quar. Jour. of Med. Sci., 18... 426–439.]

Someren (W. J. van). Report ... cases of cholera treated at the ... firmary, Madras, from July to ...
[MADRAS Quar. Jour. of Med. Sci., 18... 19–20.]

Stuart. An account of an outbreak cholera, in Kurrachee, Scinde. ...
[IRISH Hosp. Gaz., Dublin, 1853, I, pp. ...

Sutherland. Report of epidemic ... in 1867, in the Punjaub, north-west and central provinces of India.
[ARMY Stat., San., & Med. Repts., Lon... pp. 360–382; 1 map.]

Switzer (B. W.) Narrative of the outbreak of epidemic cholera in the ... son and district of Kohat, 1867.
[INDIAN Med. Gaz., 1868, III, pp. 25–...

Tholozan (J. D.) De l'antiquité ... léra dans l'Inde.
[GAZ. méd. de Paris, 1868, XXIII, pp. ... 437, 487–491, 579–585, 631–633, 679–...

——— Le choléra dans l'Inde. (Fait à la Société médicale d'émulation Paris, par M. Cazalas.)
[L'UNION méd. de Paris, 1873, XV, ... 65–72.]

Thom (A.) Notes on cholera in ...
[MED. Times & Gaz., 1853, VI, pp. 15...

——— Account of the cholera wh...

om (A.)—continued.
ailed in the 86th regiment, stationed at Kurrachee during April and May 1846.
Med. Times, London, 1847, XVI, pp. 151-152; 1848, XVII, pp. 326-329, 374-376, 388-390; XVIII, pp. 51-54, 67-69, 84-86, 102-105.]

omson (W. A.) Report on an epidemic of cholera at Thayetmo, British Burmah, in 1869.
Army Stat., San. & Med. Repts, London, 1871, pp. 393-422; 1 map.]

orn (A.) Report on the causes, character, and treatment of spasmodic cholera in H. M. 86th regiment at Kurrachee in June, 1846. Ordered by the house of commons to be printed. *London*, 1848.

wnshend (S. C.) Report on the cholera (epidemic of 1868 in the central provinces of India). fol. 1869.

s (J. R.) Vom Ursprunge, dem Vorrufe, den Symptomen und der Heilung der Cholera morbus, wie sie sich seit dem Jahre 1817 in Bengalen gezeigt hat. Aus dem Holländischen übersetzt von C. H. Ebermaier.
Hufel. Mag. f. d. gesammt. Heilk., 1827, XXIV, pp. 97-135.]

oodburn (D.) Account of two reports on cholera.
Trans. Med. & Phys. Soc., Calcutta, 1835, VII, pp. 422-464.]

richt über die Cholera-Seuche, welche im Gebiet der Präsidentschaft von Bengalen in den Jahren 1817, 1818 und 1819 heimgesucht hat. Auf Befehl der Regierung, unter der Aufsicht der Medicinal-Behörde aufgesetzt von Jacob Jameson. See **Cholera**: General. Sammlungen der wichtigsten Abhandlungen über die jetzt herrschende Cholera-Seuche.

holera as it appeared in the central provinces [India] during the year 1872.]
Annual Rept. of the San. Commissioner for the Central Provinces for the year 1872, pp. 16-75; 11 tables.]

olera (The) epidemic [of India. History and preventive measures].
XVIII Ann. Rept. San. Comm. with the Govt. of India, 1869, pp. 1-75.]

holera in Britisch Indie.)
Nederl. Tijdschr. v. Geneesk., Amsterd., 1862, p. 143.]

olera as it appeared in the Bombay presidency.
Report of the San. Commissioner for Bombay, 1871 sec. II, pp. 2-14, 1 map; 1872, sec. II, pp. 2-17, 1 map.]

holera (The) at Kurrachee, Scinde.
Lancet, London, 1847, I, p. 132.]

Cholera (The) at Secunderabad in May, 1871.
[Med. Times & Gaz., London, 1871, II, pp. 590-592.]

Cholera in India.
[Brit. & For. Med.-Chir. Rev., London, 1870, XLVI, pp. 100-124.]

Cholera (The) in Scinde — treatment adopted by the natives.
[London Med. Gaz., 1846, XXXVIII, n. s., pp. 510-511.]

Cholera in Southern India. A record of the progress of cholera in 1870, and résumé of the records of former epidemic invasions of the Madras presidency. fol. *Madras*, 1871. L.

Epidemic cholera in the Bengal presidency. Note on the epidemic connection of the cholera of Madras and Bombay with the cholera epidemic of the Bengal presidency. fol. *Calcutta*, 1871. L.

Epidemic cholera in Madras.
[Madras Quar. Jour. of Med. Sci., 1860, I, pp. 498-500.]

Excessive (The) cholera mortality in India.
[Brit. Med. Jour., London, 1872, II, pp. 584-585.]

Fourth (The) annual report of the sanitary commissioner with the government of Bengal for 1867. [History of the cholera epidemic of Northern India.]
[Med. Times & Gaz., London, 1869, I, pp. 283-284.]

History of the chief diseases causing mortality [in India]. Cholera.
[Rept. San. Com. for Madras, 1871, pp. 118-192.]

Inquiry (An) into the circumstances attending the outbreak of cholera in H. M.'s 18th hussars at Secunderabad in the month of May 1871. fol. *Madras* ? [*n. d.*] L.

Late (The) outbreak of cholera at Secunderabad.
[Lancet, London, 1871, II, p. 546; 1872, II, p. 680.]

Map showing the mortality from cholera in the districts of the Bombay presidency in the year 1868.
[Rept. on measures adopted for san. imp. in India from June, 1869 to June 1870, London, 1870, at p. 143.]

Map showing the mortality from cholera in the districts of the Bombay presidency in the year 1869.
[Rept. of San. Commissioner for Bombay, 1869, at p. 200; *also in* Rept. on measures adopted for san. imp. in India, from June 1870 to June 1871, London, 1871, at p. 157.]

Map to illustrate the mortality from cholera in the Madras presidency during the year 1871.

[REPT. on measures adopted for san. imp. in India, from June 1872 to June 1873, London, 1873, at p. 111.]

Nachrichten über die Cholera-Seuche, wie sie in Hindostan und in der indischen Halbinsel in den Jahren 1817, 1818 und 1819 geherrscht hat. Gesammelt und auf Verordnung der Regierung herausgegeben von der Medicinalbehörde in Bombay. *See* **Cholera**: General. Sammlungen der wichtigsten Abhandlungen über die jetzt herrschende Cholera-Seuche.

On cholera in 1873 in central provinces of India.

[REPORT of San. Commissioner for the Centr. Prov., 1873, fol., Nagpur, 1874, pp. 14-31.]

Report of the Madras medical board on epidemic cholera. Drawn up by order of government. 8°. [*n. p.*], 1824.

Report on the cholera epidemic of 1872 in Northern India.

[NINTH ann. rept. San. Commissioner with the govt. of India, 1872, pp. 1-150. *Also in* REPT. on meas. adopted for san. imp. in India, from June 1873 to June 1874, London, 1874, pp. 67-197; 1 map.]

Report on cholera in Southern India for the year 1869, with map illustrative of the disease. fol. *Madras*, 1870. L.

Report on the epidemick cholera morbus as it visited the territories subject to the presidency of Bengal, in the years 1817, 1818, and 1819. Drawn up by order of the government, under the superintendence of the medical board, by James Jameson. 8°. *Calcutta*, 1820. L.

Reports on Asiatic cholera in regiments of the Madras army from 1828 to 1844 [etc.] *See* **Rogers** (S.)

Reports on the epidemic cholera which has raged throughout Hindostan and the peninsula of India, since August 1817. Published under the authority of government. 8°. *Bombay*, 1819. L.

Sketch map to illustrate the distribution of and comparative mortality from cholera in the different circles of mortuary registration of the presidency [Bombay] during the year 1871.

[REPT. on meas. adopted for san. imp. in India from June 1872 to June 1873, London, 1873, at p. 159.]

Studien über die Cholera in Indien.

[ALLG. med. Centr.-Zeitg., Berlin, 1874, XLIII, pp. 105-107. 117-119, 129-131.]

Two cases of cholera in the [illegible] on its march from Chittore and [illegible] in the early part of 1838.

[MADRAS Quar. Med. Jour., 1839 [illegible]

Persia.

Bell (C. W.) Report on the [illegible] ague or "fainting fever" of [illegible] species of cholera occurring in [illegible] in the autumn of the year 1842

[BRIT. & For. Med. Rev., London, [illegible] 558-566.]

Cloquet (E.) Sur le choléra en Pe[illegible]

[BULL. de l'Acad. nat. de med., Par[illegible] XVIII, pp. 1190-1192.]

Cormick (J.) On the occurrence [illegible] sia of the epidemic cholera of [illegible]

[MED.-CHIRURG. Trans., London [illegible] 359-365.]

Dickson (E. D.) On cholera in [illegible] 1866-68.

[TRANS. Epid.Soc., London, 1867, III, p[illegible]

Guettet. Note sur ce qui a le [illegible] ussi en Perse contre le choléra.

[GAZ. méd. de Paris, 1850, V, p. 90.]

Hübenthal (C. P. W. von). D[illegible] und Behandlung der orientali[illegible] lera, von der persischen Gr[illegible] theilt.

[JOUR. d. prakt. Heilk., 1831, LXXII, [illegible]

Polak (J. E.) Die Cholera in Pe[illegible] die Landquarantäne.

[WIEN. med. Wochenschr., 1869, pp. [illegible]

Tholozan. Note sur le choléra [illegible] et sur la valeur des quarante [illegible] voie de terre.

[GAZ. hebd. de méd. et de chirurg. 2e sér., VI, pp. 643-644.]

Tholozan (J. D.) Prophylaxie [illegible] ra en orient. L'hygiène et la [illegible] sanitaire en Perse . . . [illegible]. P.

Cholera (The) in Persia.

[BRIT. Med. Jour., London, 1871, II, p. [illegible]

Syria.

Barker (J.) Mode of curing [illegible] Syria.

[LANCET, London, 1848, II, p. 515.]

Hirsch (A.) Bericht über die C[illegible] Beirut vom 1. Juli bis 15. Septe[illegible] vom Arzte des Johannes-H[illegible] selbst, Dr. R. Lange.

[BERLIN. klin. Wochensch., 1[illegible] 458-460.]

Tilt (E. T.) The cholera in D[illegible]

[LANCET, London, 1849, II, p. 372.]

EAST INDIES.

ne (G.) On the cholera of the East
ndies.
[Edinb. Med. & Surg. Jour., 1825, xxiv, pp. 60–64.]

rincent (P.-M.) *Considérations sur
choléra épidémique, et sur celui des
ndes orientales en particulier. 4°.
Paris, 1829. L.

reau de Jonnes (A.) Notice sur la
aladie pestilentielle importée aux isles
France et de Bourbon et désignée sous
nom de choléra morbus de l'Inde. 8°.
Paris, 1821.

ıken (J.) Observations on the epi-
emic cholera morbus of the East Indies.
[Edinb. Med. & Surg. Jour., 1823, xix, pp. 1–13.]

ssink (G.) Algemeen Rapport der
de 1ste Militaire Afdeeling voorge-
omen Cholera Lijders in het Jaar 1851.
[Nederl. Tijdschr. voor Neederl. Indië, Batavia, 1854, III, pp. 1–126.]

the mordixim or cholera of Java and
Malabar.
[London Med. Gaz., 1833, XII, pp. 535–536.]

lon

wne (A.) Notice of cholera as it ap-
eared at Colombo in 1817.
[Med. Times, London, 1848, XVII, pp. 32–34.]

ry (J.) Report on cholera, as it oc-
urred in Ceylon in 1819.
[Med. Times, London, 1850, I, n. s., pp. 224–226.]

gusson (A.) Extracts from reports
the cholera and small pox in the
land of Ceylon in 1852.
[Lond. Times & Gaz., 1853, VII, n. s., p. 495.]

s.

ıen (A.) De Cholera-Epidemie te Ba-
via, in 1864.
[Nederl. Tijdschr. v. Geneesk., 1865, I, pp. 225–255.]

ıneider (F.) Cholera in Soerabaya auf
va. 8°. *Berlin*, 1871. L.

tge. Beschreibung der asiatischen
olera, sowie sie auf der holländ-
sch-ostindischen Insel Java, in Asien
legen [etc.] 8°. *Neuhaldensleben*
:31]. L.

lera-Epidemie te Batavia.
[Nederl. Tijdschr. v. Geneesk., 1864, VIII, p. 542.]

lera (De) op Java.
[Nederl. Tijdschr. .v. Geneesk., 1864, VIII, pp. 1865, I, pp. 93, 175.]

Madagascar.

Barnier (I. B.) Note sur l'épidémie de choléra qui a sévi dans l'île de Nossi-Bé, pendant les mois de septembre, octobre et novembre 1870.
[Gaz. hebdom., Paris, 1871, VIII, 2e sér., pp. 559–561.]

Mauritius.

Collas. Le choléra à l'île Maurice.
[L'Union méd., 1854, VIII, p. 440.]

Hardie (G. K.) Cholera.—Illustration of the doctrine of contagion in cholera, drawn from the epidemics of 1854 and 1856, at Mauritius.
[Trans. Cork Med. & Surg. Soc., 1866–67, pp. 52–68.]

Hutchison (A. C.) Importation of cholera into the Mauritius.
[London Med. Gaz., 1832, IX, p. 352.]

Kinnis (J.) Observations on cholera-morbus and other diseases, which prevailed epidemically among the soldiers of the 56th regiment, stationed at Port Louis, Mauritius, in the end of the year 1819, and beginning of 1820.
[Edinb. Med. & Surg. Jour., 1821, XVII, pp. 1–29.]

Lamare (P.) Observations faites sur le choléra-morbus dans l'Inde, au Bengale et à l'île de France. Son invasion dans cette colonie; ravages qu'il y produisit; essais multipliés pour combattre son intensité, des résultats heureux obtenus par des médecins distingués de cette île, et des moyens hygiéniques proposés pour éviter l'infection. 8°. *Paris*, 1831. L.

Quesnel (F.) *Essai sur l'épidémie de choléra-morbus qui à désolé l'Île-de-France en 1819. 4°. *Paris*, 1823. L.

Telfair (C.) Account of the epidemic cholera, as it occurred at Mauritius.
[Edinb. Med. & Surg. Jour., 1821, XVII, pp. 517–526.]

Cholera-Epidemie in Mauritius.
[Nederl. Tijdschr. v. Geneesk., 1868, I, p. 414.]

Cholera (Die) morbus auf Isle de France. 8°. *Leipzig*, 1831. L.

Importation of cholera into the Mauritius.
[Med. Gaz., London, 1832, IX, pp. 526–527.]

Réunion.

Petit (L. A.) Mémoire sur l'épidémie de choléra-morbus qui a régné à la Réunion en 1859. . . . 8°. *Paris*, 1862.

EUROPE.

Althaus (J.) Cholera in Germany and Russia.

[MED. Times & Gaz., London, 1865, II, pp. 562–563.]

Bremer. Geschichtliche Nachrichten über die Verbreitung der asiatischen Cholera in Russland [und Oesterreich].

[JOUR. der prakt. Heilk., 1830, LXXI, V Stück, pp. 122–130; VI, Stück, pp. 86–107; 1831, LXXII, II Stück, pp. 105–136; III Stück, pp. 97–114.

——— The same. 12°. [*n. p., n. d.*] L.

Drasche. Ueber den gegenwärtigen Stand der Cholera.

[WIEN. med. Wochenschr., 1866, pp. 1001–1005; 1867, XVII, pp. 561–565, 1011–1013, 1028–1029, 1201–1203, 1217–1219, 1265–1268, 1281–1283.]

Gerardin (A.) *and* **Gaimard** (P.) Du choléra-morbus en Russie, en Prusse et en Autriche, pendant les années 1831 et 1832. 8°. *Paris*, 1832. L.

——— The same. 2e éd. *Paris*, 1832. L.

[Cover marked "Troisième éd. 1833."]

Gosse (L. A.) Rapport sur l'épidémie de choléra, en Prusse, en Russie, et en Pologne. . . . 8°. *Genève*, 1833.

Guyon. Des moyens préservatifs et curatifs du choléra, d'après une expérience acquise en Pologne et en Autriche. Ouvrage particulièrement destiné aux gens du monde. 8°. *Paris*, 1832. L.

Heyfelder (J. F.) Beobachtungen über die Cholera asiatica auf einer in Folge höhern Auftrags in die von jener Krankheit heimgesuchten Gegenden unternommenen Reise und während eines mehrmonatlichen Aufenthalts in Berlin und Magdeburg, sowie im Cüstrin'schen, Königsberg'schen und Oberbarnim-'schen Kreise gesammelt. 2 v. 8°. *Bonn*, 1832. L.

Sandras (C. M. S.) Du choléra épidémique observé en Pologne, en Allemagne, et en France. 8°. *Paris*, 1832. L.

Sophianopoulo (D. M.) Relation des épidémies du choléra morbus observées en Hongrie, Moldavie, Gallicie, et à Vienne en Autriche, dans les années 1831 et 1832; avec une histoire générale de cette maladie, et son traitement préservatif et curatif; avec des notes du professeur Broussais. 8°. *Paris*, 1832. L.

——— The same. [In Italian.] 8°. *Paris*, 1832.

Triberti (A.) Altri pensamenti sulla natura della malattia del cholera che epidemicamente va manifestando . . . Europa, e quali sarebbero le disposanitarie da adottarsi per far . . . giare la medicina su questa . . . ma malattia, se mai in Lomb . . . manifestasse.

[OMODEI, Ann. un. di med., 1832 . . . 374.]

Analyse de quelques ouvrages . . . publiés sur le choléra-morbus . . . que observé en France, en R . . . Autriche et en Prusse. 8°. *Pa* . . .

Beiträge zur Geschichte der . . . Cholera im südlichen Frankr . . . J. J. 1834 bis 1835, in Ober- and M . . . italien in den J. J. 1835 bis . . . der Schweiz im J. 1836.

[SCHWEIZ. Zeitschr. f. Nat. u. Heilk . . . 92–113, 277–292, 356–384.]

Cholera. [Statistics of, in Russ . . . and other countries.]

[DEUTSCHE Klinik, Berlin, 1853 . . . etc.; 1855, VII, pp. 363–364, etc. . . . GLAD Lekarski, Krakow, 1866, V, pp. . . . 1867, VI, pp. 16, 32, etc.]

Cholera-Epidemie (De) in ver . . . Landen van Europa.

[GENEESK. Courant, Tiel, 1866, No. . . .

AUSTRIA.

Ballin (S. J.) Observationes . . . asiatica, Cracoviae, Vienn . . . aliésque in locis institutae. . . . *niae*, 1832.

Carrière (E.) Le choléra en A . . .

[L'UNION méd., Paris, 1855, IX, pp. . . . 538.]

Elsässer (C. L.) Die epidemi . . . nach eigenen aus Auftrag der . . . würtembergischen Regierung . . . ten Beobachtungen in Wien . . . ren, besonders Brünn. . . . 1832.

Knolz (J. J.) Die Cholera-E . . . Niederoesterreich im Jahre 1 . . .

[MED. Jahrb. des k. k. oesterr. St . . . XIX, n. F., pp. 74–84, 212–221, 434–441.]

Krauss (A.) Die Cholera-Epid . . . eigenen in Wien und in Mähren . . . trag der königlich würtemb . . . Regierung angestellten Beob . . . 8°. *Stuttgart*, 1832.

Kroczak (A.) Die Cholera-Epid . . . Jahres 1836–1837 in der Prov . . . und Schlesien.

[MED. Jahrb. d. k. k. oesterr. Staa . . . n. F., pp. 536–539.]

…born. Rapport de la commission re…atifs au choléra et à la peste bovine, …ignant dans la monarchie austro-hon…groise.

[…L. Ac. roy. de méd., Belgique, 1873, VII, 3e s., pp. 71, 209–216.]

…ltz (B.) Beiträge zur Choleraepidemie im Semmering im Jahre 1850.

[WIEN. med. Wochenschr., 1854, IV, pp. 581–583.]

…iss (K.) Erfahrungen während der Cholera-Epidemie im Jahre 1873.

[WIEN. med. Presse, 1873, XIV, pp. 973–976.]

…une. Ueber die Brechruhr in Prag und Wien.

[…d. ausländ. Lit. d. gesammt. Heilk., 1832, …III, pp. 377–387.]

…itlacil (A.) Beobachtungen aus der Cholera-Epidemie des Jahres 1866 in den Vororten Neulerchenfeld, Hernals und Währing.

[WIEN. med. Wochenschr., 1867, XVII, pp. 323–…341–343, 356–357, 371–373, 388–390, 406–408, …424.]

…r Cholerastatistik in Oesterreich.

[…r. med. Presse, 1866, VII, pp. 904, 951–952, …1120–1121.]

…e.

…arex (F.) Cenni su'l coléra nella città' …l isola di Arbe in Dalmazia nell'estate del 1855.

[…az. med. ital.-lomb., 1857, II, 4th s., pp. 104–…107, 123–125.]

…rberg.

…ittmann (D. J.) Skizze über die Brechruhr-Epidemie im illyrischen Bezirke Luersperg im Jahre 1836.

[MED. Jahrb. d. k. k. oesterr. Staates, 1838, XV, n. F., pp. 54–68.]

…hemia.

…ulich (J.) Die Cholera in Böhmen in den Jahren 1866 und 1872–73.

[VIERTELJAHRSCHR. f. d. prakt. Heilk., 1875, …XXV, pp. 119–142; CXXVI, pp. 95–110, 2 maps.]

…ratmann (F. O.) *Observationes de Cholera asiatica per Borussorum exercitus in Bohemia bellum gerentes vagata. *Berolini*, [1866]. L.

…ün.

…16. Bild und Behandlung der Cholera asiatica zu Brünn in Mähren im Jahre …36.

[MED. Jahrb. d. k. k. oesterr. Staates, 1837, XIII, n. F., pp. 305–347.]

…er. Die Cholera in Brünn im Jahre …36.

[… Wien. med. Zeitg., 1866, XI, pp. 335–336, …343–344.]

Buda.

Hoffer (S.) Die Choleraepidemie zu Ofen in den Monaten October und November 1854.

[ZEITSCHR. f. Natur- u. Heilk. in Ungarn, 1855, V, pp. 275–277.]

Carniola.

Melzer (R.) Die epidemische Brechruhr in Krain im J. 1849.

[VIERTELJAHRSCHR. f. d. prakt. Heilk., 1851, III, pp. 118–146.]

Pettenkofer (M. v.) Die Cholera und die Bodenbeschaffenheit in der k. k. oesterreichischen Provinz Krain. Mit besonderer Rücksicht auf die Angaben hierüber in Dr. Drasche's monographischer Arbeit: "Die epidemische Cholera."

[ÄRZTL. Intell.-Bl., 1861, VIII, pp. 89–95, 103–109, 113–119. Also in 4°, München, 1861.]

Cracow.

Jakubowski (J.) De cholera ind. in Cracoviae observata. 8°. *Cracov.*, 1834.

Daka.

Beschrijving der Cholera te Daka in Hongarije, en de Wijze waarop dezelve aldaar door den Graaf Nadaskij behandeld is, van den 17 Sept. . . . 1831. 8°. *Amsterdam*, 1832.

Dalmatia.

Herrmann. Erlebnisse eines Wiener Arztes während der heurigen Cholera-Epidemie in Dalmatien.

[ALLG. Wien. Med.-Zeitg., 1867, XII, pp. 381–382.]

Eisnern.

Kainzlsberger. Die seröse Brechruhr-Epidemie in Eisnern im Laibacher Kreise der Provinz Illyrien im Jahre 1836.

[MED. Jahrb. des oesterr. Staates, 1837, XIII, n. F., pp. 416–426.]

Galicia.

Flechner (A. E.) Bemerkungen über die Cholera nach eigenen Erfahrungen in den Jahren 1831, 1832 und 1836 in Galizien.

[MED. Jahrb. des k. k. österr. Staat., 1848, IV, pp. 257–276.]

Prchal (J. M.) Die Cholera beobachtet in Galizien im Jahre 1831. 8°. *Prag*, 1831. L.

——— Ueber die im Zaleschcziker Kreise in k. k. Galizien um sich greifende Brech-

Prchal (J. M.)—continued.
ruhr. Aus den diessfälligen Kranken-Beobachtungen.
[MED. Jahrb. des k. k. oesterr. Staates, 1832, II, n. F., pp. 372–391.]

Riedel (J.) Die asiatische Brechruhr nach den in Galizien gemachten Erfahrungen und Beobachtungen. 8°. *Prag*, 1832. L.

Schnitzer (A.) Die Cholera contagiosa beobachtet auf einer in Folge höheren Auftrages in Galizien während der Monate Mai, Juni und Juli, und im Beuthner Kreise in Oberschlesien im August gemachten Reise. 8°. *Breslau*, 1831. L.

Tomada (V.) *e* **Fassetta** (V.) Ragguaglio d'uffizio intorno al cholera-morbus regnante nella Gallizia.
[OMODEI, Ann. un. di med., 1831, LX, pp. 252–276.]

Trapp (E. C.) Die Cholera. Beobachtungen gesammelt auf einer in allerhöchsten Auftrage unternommenen Reise in Galizien, Schlesien Mähren, Ungarn und Wien in den Monaten Aug., Sept., Oct., Nov., und Dec. 1831. 8°. *Giessen*, 1832. L.

Cholera n Galicyi.
[PRZEGLAD Lekarski, Krakow, 1871, X, pp. 8, 344, 367, 376, 392, 407.]

Cholera (Die) in Galizien.
[WIEN. med. Presse, 1866, VII, pp. 949–950.]

Hungary.

Grosz. Die Cholera-Epidemie in Ungarn 1872–73. Besprochen von Dr. Josef Schrank.
[ALLG. Wien. med. Zeitg., 1874, XIX, pp. 277–278, 286.]

Kuthy (L.) Ein Wort über die Cholera-Epidemie auf dem Lande.
[ZEITSCHR. f. Natur- u. Heilk. in Ungarn, 1855, VI, pp. 193–196.]

Lenhossék (M.) Animadversiones circa curandum choleram orientalem et alios epidemicos morbos, in regno Hungariæ nunc vigentes, secundum captas hactenus observationes exaratae. 8°. *Budæ*, 1831. L.

Löwy (L.) Ueber die Cholera in Ungarn.
[WIEN. med. Presse, 1873, XIV, p. 738.]

Cholera (Die) in Pest and Ungarn.
[ALLG. Wien. med. Zeitg., 1873, XVIII, pp. 600–601.]

Illyria.

Schneditz (J.) Die Cholera-Epidemie in Illyrien im Jahre 1836.
[MED. Jahrb. des k. k. oesterr. Staates, 1839, XX, n. F., pp. 339–342.]

Inzersdorf.

Hermann. Die Cholera-Epidemie zu Inzersdorf am Wienerberge.
[WIEN. med. Wochenschr., 1853, p. [illegible]

Lemberg.

Berres (C. J.) Praktische Erfahrungen über die Natur der Cholera in Lemberg und Behandlung derselben. [illegible] berg, 1831.

Rohrer (M.) Die epidemische Cholera zu Lemberg, beobachtet und [illegible] ben. 8°. *Brünn*, 1831.

Slawikowski (A.) Die Cholera-Epidemie in Lemberg und im Lemberger Kreise im Jahre 1831.
[MED. Jahrb. des k. k. oesterr. Staates, n. F., pp. 552–580.]

Liptau.

Flittner (J. C.) Nachrichten und Erfahrungen über die Cholera; gesammelt in dem Liptauer Comitate im Jahre [illegible]
[MED. Jahrb. des k. k. oesterr. Staates, n. F., pp. 222–243.]

Moravia.

Wolfstein (G. C.) Tratato sulla [illegible] dietro ad osservazioni fatte in [illegible] e particolarmente in Moravia [illegible] 1831 e 1832. . . . 8°. Vien[illegible]

Olmütz.

Pissling (W. F.) Die Cholera-Epidemie in Olmütz.
[WIEN. med. Wochenschr., 1854, pp. 1385–1388, 1401–1403; 1 table.]

Pápa.

Pserhofer. Die Cholera in Papa, Anders im J. 1855, mit gleichzeitiger Berücksichtigung der medicinisch-topographischen Verhältnisse dieses [illegible]
[ZEITSCHR. f. Natur- u. Heilk. in Ungarn, VIII, pp. 265–268, 273–277, 289–291, 303–307, 345–347, 362–365, 369–373.]

Pesth.

Eckstein (F.) Die epidemische Cholera beobachtet in Pesth in den Monaten Juli, August, September 1831. Nebst einem Anhange über die Nicht-Contagiosität dieser Krankheit und die Anwendung zur kalten und warmen Behandlung derselben. 8°. *Pesth und Leipzig.* [illegible]

Pólya (J.) *and* **Grünhut** (J. C.) Specimen observationum quas de cholera [illegible] anni MDCCCXXXI in libera [illegible]

Kuborn. Rapport de la commission relatifs au choléra et à la peste bovine, régnant dans la monarchie austro-hongroise.

[BULL. Ac. roy. de méd., Belgique, 1873, VII, 3e s., pp. 71, 209–216.]

Piltz (B.) Beiträge zur Choleraepidemie am Semmering im Jahre 1850.

[WIEN. med. Wochenschr., 1854, IV, pp. 581–583.]

Reiss (K.) Erfahrungen während der Cholera-Epidemie im Jahre 1873.

[WIEN. med. Presse, 1873, XIV, pp. 973–976.]

Thune. Ueber die Brechruhr in Prag und Wien.

[MAG. d. ausländ. Lit. d. gesammt. Heilk., 1832, XXIII, pp. 377–387.]

Witlacil (A.) Beobachtungen aus der Cholera-Epidemie des Jahres 1866 in den Vororten Neulerchenfeld, Hernals und Ottakring.

[WIEN. med. Wochenschr., 1867, XVII, pp. 323–325, 341–343, 356–357, 371–373, 388–390, 406–408, 422–424.]

Zur Cholerastatistik in Oesterreich.

[WIEN. med. Presse, 1866, VII, pp. 904, 951–952, 1026, 1120–1121.]

Arbe.

Marez (F.) Cenni su'l coléra nella città ed isola di Arbe in Dalmazia nell'estate del 1855.

[GAZ. med. ital.-lomb., 1857, II, 4th s., pp. 104–107, 123–125.]

Auersberg.

Wittmann (D. J.) Skizze über die Brechruhr-Epidemie im illyrischen Bezirke Auersperg im Jahre 1836.

[MED. Jahrb. d. k. k. oesterr. Staates, 1838, XV, n. F., pp. 54–68.]

Bohemia.

Kaulich (J.) Die Cholera in Böhmen in den Jahren 1866 und 1872–73.

[VIERTELJAHRSCHR. f. d. prakt. Heilk., 1875, CXXV, pp. 119–142; CXXVI, pp. 95–110, 2 maps.]

Stratmann (F. Q.) *Observationes de cholera asiatica per Borussorum exercitus in Bohemia bellum gerentes vagata. 8°. *Berolini*, [1866]. L.

Brunn.

Allé. Bild und Behandlung der Cholera asiatica zu Brünn in Mähren im Jahre 1836.

[MED. Jahrb. d. k. k. oesterr. Staates, 1837, XIII, n. F., pp. 305–337.]

Beer. Die Cholera in Brünn im Jahre 1866.

[ALLG. Wien. med. Zeitg., 1866, XI, pp. 335–336, 343–344.]

Buda.

Hoffer (S.) Die Choleraepidemie zu Ofen in den Monaten October und November 1854.

[ZEITSCHR. f. Natur- u. Heilk. in Ungarn, 1855, V, pp. 275–277.]

Carniola.

Melzer (R.) Die epidemische Brechruhr in Krain im J. 1849.

[VIERTELJAHRSCHR. f. d. prakt. Heilk., 1851, III, pp. 118–146.]

Pettenkofer (M. v.) Die Cholera und die Bodenbeschaffenheit in der k. k. oesterreichischen Provinz Krain. Mit besonderer Rücksicht auf die Angaben hierüber in Dr. Drasche's monographischer Arbeit: "Die epidemische Cholera."

[ÄRZTL. Intell.-Bl., 1861, VIII, pp. 89–95, 103–109, 113–119. Also in 4°, München, 1861.]

Cracow.

Jakubowski (J.) De cholera ind. in Cracoviae observata. 8°. *Cracov.*, 1834.

Daka.

Beschrijving der Cholera te Daka in Hongarije, en de Wijze waarop dezelve aldaar door den Graaf Nadaskij behandeld is, van den 17 Sept. . . . 1831. 8°. *Amsterdam*, 1832.

Dalmatia.

Herrmann. Erlebnisse eines Wiener Arztes während der heurigen Cholera-Epidemie in Dalmatien.

[ALLG. Wien. Med.-Zeitg., 1867, XII, pp. 381–382.]

Eisnern.

Kainzlsberger. Die seröse Brechruhr-Epidemie in Eisnern im Laibacher Kreise der Provinz Illyrien im Jahre 1836.

[MED. Jahrb. des oesterr. Staates, 1837, XIII, n. F., pp. 416–426.]

Galicia.

Flechner (A. E.) Bemerkungen über die Cholera nach eigenen Erfahrungen in den Jahren 1831, 1832 und 1836 in Galizien.

[MED. Jahrb. des k. k. österr. Staat., 1848, IV, pp. 257–276.]

Prchal (J. M.) Die Cholera beobachtet in Galizien im Jahre 1831. 8°. *Prag*, 1831. L.

——— Ueber die im Zaleschcziker Kreise in k. k. Galizien um sich greifende Brech-

Prchal (J. M.)—continued.
ruhr. Aus den diessfälligen Kranken-Beobachtungen.
[MED. Jahrb. des k. k. oesterr. Staates, 1832, II, n. F., pp. 372–391.]

Riedel (J.) Die asiatische Brechruhr nach den in Galizien gemachten Erfahrungen und Beobachtungen. 8°. *Prag*, 1832. L.

Schnitzer (A.) Die Cholera contagiosa beobachtet auf einer in Folge höheren Auftrages in Galizien während der Monate Mai, Juni und Juli, und im Beuthner Kreise in Oberschlesien im August gemachten Reise. 8°. *Breslau*, 1831. L.

Tomada (V.) *e* **Fassetta** (V.) Ragguaglio d'uffizio intorno al cholera-morbus regnante nella Gallizia.
[OMODEI, Ann. un. di med., 1831, LX, pp. 252–276.]

Trapp (E. C.) Die Cholera. Beobachtungen gesammelt auf einer in allerhöchsten Auftrage unternommenen Reise in Galizien, Schlesien Mähren, Ungarn und Wien in den Monaten Aug., Sept., Oct., Nov., und Dec. 1831. 8°. *Giessen*, 1832. L.

Cholera n Galicyi.
[PRZEGLAD Lekarski, Krakow, 1871, X, pp. 8, 344, 367, 376, 392, 407.]

Cholera (Die) in Galizien.
[WIEN. med. Presse, 1866, VII, pp. 949–950.]

Hungary.

Grosz. Die Cholera-Epidemie in Ungarn 1872–73. Besprochen von Dr. Josef Schrank.
[ALLG. Wien. med. Zeitg., 1874, XIX, pp. 277–278, 286.]

Kuthy (L.) Ein Wort über die Cholera-Epidemie auf dem Lande.
[ZEITSCHR. f. Natur- u. Heilk. in Ungarn, 1855, VI, pp. 193–196.]

Lenhossék (M.) Animadversiones circa curandum choleram orientalem et alios epidemicos morbos, in regno Hungariæ nunc vigentes, secundum captas hactenus observationes exaratae. 8°. *Budæ*, 1831. L.

Löwy (L.) Ueber die Cholera in Ungarn.
[WIEN. med. Presse, 1873, XIV, p. 738.]

Cholera (Die) in Pest and Ungarn.
[ALLG. Wien. med. Zeitg., 1873, XVIII, pp. 600–601.]

Illyria.

Schneditz (J.) Die Cholera-Epidemie in Illyrien im Jahre 1836.
[MED. Jahrb. des k. k. oesterr. Staates, 1839, XX, n. F., pp. 339–342.]

Inzersdorf.

Hermann. Die Cholera-Epidemie zu Inzersdorf am Wienerberge.
[WIEN. med. Wochenschr., 1855, p. 807.]

Lemberg.

Berres (C. J.) Praktische Erfahrungen über die Natur der Cholera in Lemberg und Behandlung derselben. 8°. *Lemberg*, 1831.

Rohrer (M.) Die epidemische Brechruhr zu Lemberg, beobachtet und beschrieben. 8°. *Brünn*, 1831.

Slawikowski (A.) Die Cholera-Epidemie in Lemberg und im Lemberger Kreise im Jahre 1831.
[MED. Jahrb. des k. k. oesterr. Staates, 1831, n. F., pp. 552–580.]

Liptau.

Flittner (J. C.) Nachrichten und Erfahrungen über die Cholera; gesammelt in dem Liptauer Comitate im Jahre 1831.
[MED. Jahrb. des k. k. oesterr. Staates, 1831, n. F., pp. 222–243.]

Moravia.

Wolfstein (G. C.) Tratato sul cholera dietro ad osservazioni fatte in generale, e particolarmente in Moravia, negli anni 1831 e 1832. . . . 8°. *Vienna* [*n. d.*]

Olmütz.

Pissling (W. F.) Die Cholera-Epidemie in Olmütz.
[WIEN. med. Wochenschr., 1866, pp. 1372–1373, 1385–1388, 1401–1403; 1 table.]

Pápa.

Pserhofer. Die Cholera in Pápa, besonders im J. 1855, mit gleichzeitiger Berücksichtigung der medicinisch-topographischen Verhältnisse dieses Ortes.
[ZEITSCHR. f. Natur- u. Heilk. in Ungarn, 1857, VIII, pp. 265–268, 273–277, 289–291, 297–303, 305–307, 345–347, 362–365, 369–373.]

Pesth.

Eckstein (F.) Die epidemische Cholera beobachtet in Pesth in den Monaten Juli, August, September 1831. Nebst einem Anhange über die Nicht-Contagiosität dieser Krankheit und die Anzeigen zur kalten und warmen Behandlung derselben. 8°. *Pesth und Leipzig*, 1832. L.

Pólya (J.) *and* **Grünhut** (J. C.) Summa observationum quas de cholera orientali anni MDCCCXXXI in liberae regiaeque

(C.) Auszug eines Schreibens des an Prof. Jäger in Stuttgart. Vom ind 19. Juni 1832. [Cholera in Vi-

. Corrspdzbl. d. Württ. aerztl. Ver., Stutt-rt, 1832, I, pp. 145–147.]

Darstellung der Cholera-Epidemie . k. Waisenhause im Herbste des res 1854.

rs. HRIFT der k. k. Ges. der Aerzte zu Wien, 4, pp. 244–249.]

t (J. J.) Ueber die Cholera zu Wien. [CHIR. Zeitung, Innspruck, 1831, IV, pp. 1–256.]

· Darstellung der Brechruhr-Epide-in der k. k. Haupt- und Residenz-t Wien, wie auch auf dem flachen de in Oesterreich unter der Enns in Jahren 1831 und 1832, nebst den da-en getroffenen sanitäts-polizeylichen kehrungen. 8°. *Wien*, 1834.

ar. Beobachtungen auf der Cholera-heilung des Primar. Dr. Löbel im . Rudolfspitale.

[NER med. Wochenschr., 1867, XVII, pp. 195–7, 213–216, 230–232, 247–249, 261–263, 277–279.]

tbel (*Le baron de*). Lettre sur le léra de Vienne en Autriche. Avec notes, par M. Guyon. 8°. *Paris*, 2. L.

ier. Kurzer übersichtlicher Schluss-icht über die diesjährige Cholera-idemie [Wien, 1866].

[TERR. Zeitschr. f. prakt. Heilk., Wien, 1866, II, pp. 911–916.]

– und **Innhauser** (—). Amtsbericht Stadtphysikates über die Cholera-demie in Wien im Jahre 1873.

[Wien. med. Zeitg., 1874, XIX, pp. 67–68, 3–163, 173–174.]

es (A.) Die Choleraepidemie des hres 1873 unter den Garnisonstruppen r Stadt Wien.

[ER med. Wochenschr., 1874, XXIV, pp. 28–30, 5–47, 72–74, 88–91.]

ler (J. A. E. v.) Die Cholera zu Wien. n Sendschreiben an C. F. v. Gräfe. is dem XVI Bde. 3ten Hefte v. Gräfe's d v. Walther's Journ. f. Chirurgie. *Berlin*, 1831. L.

iel. Du choléra-morbus de Vienne. [. des hôp. Paris, 1831, V, pp. 230–231, 246; –42, VI, pp. 29–34.]

k. Bericht über die vom 18. Oktober s 17. November letzten Jahres unter n Truppen der hiesigen Garnison be-andenen Cholera-Epidemie.

[16. militärärztl. Ztg., 1865, VI, pp. 393–395, 401–403, 409–411.]

Vest (v.) Noch Etwas über die asiatische Cholera, und insbesondere über das Verhalten dieser Krankheit in Wien.

[MED.-CHIR. Zeitung, Innspruck, 1832, I, pp. 122–128, 139–144.]

Wisgrill (J.) Resultat der pathologischen und therapeutischen Erfahrungen über den epidemischen Brechdurchfall, gesammelt in dem Filial-Cholera-Krankenhause Nro. 5 in Wien.

[MED. Jahrb. des k. k. oesterr. Staates, 1832, III, n. F., pp. 105–133, 202–243.]

——— Reminiscenzen practischen Inhaltes aus der jüngsten Brechdurchfall-Epidemie in Wien im Jahre 1836.

[MED. Jahr. des k. k. oesterr. Staates, 1837, XIII, n. F., pp. 126–154.]

Zink (A.) Geschichtliche Bemerkungen über die epidemische Cholera während ihres Eintrittes und Herrschens in Wien, nebst einem Versuche das aetiologische Verhältniss derselben aufzuklären. 8°. *Wien*, 1832. L.

Zsigmondy (A.) Die Cholera-Epidemie im k. k. n. ö. Provinzial-Strafhause vom 18 August–6 October 1855.

[ZEITSCHRIFT der k. k. Ges. der Aerzte zu Wien, 1856, pp. 654–664.]

Zuber (J.) Bemerkungen für Ärzte über die Cholera in Wien. . . . 8°. *Mülhausen*, 1832.

Aus einem Schreiben eines Arztes aus Wien vom 28. September 1831, über die Cholera daselbst.

[MED.-CHIR. Zeitung, Innspruck, 1831, IV, pp. 142–144, 156–158.]

Aus einem Schreiben eines Wiener Arztes über die Cholera-Epidemie zu Wien im Jahre 1832.

[MED.-CHIR. Zeitung, Innspruck, 1832, IV, pp. 395–400.]

Auszüge brieflicher Mittheilungen aus Wien, der asiatischen Cholera betreffend. 8°. [*Leipzig*], 1832.

Rückblicke auf die Cholera-Epidemie.

[WIEN. med. Wochenschr., 1874, XXIV, pp. 15–18.]

Stand der Cholera in Wien [1866].

[OESTERR. Zeitschr. f. prakt. Heilk., Wien, 1866, XII, pp. 696–698, 713, 783, 807, 828, 844, 860, 876.]

Verhalten der Cholera-Epidemie in der Reichs-Hauptstadt Wien. Meteorologische Beobachtungen.

[OESTERR. Zeitschr. f. pract. Heilk., 1855, I, p. 2.]

Warasdin.

Mlinarić. Auszug aus dem Schluss-Berichte über die Cholera-Epidemie des Jahres 1855 im Warasdiner Comitate.

[OESTERR. Zeitschr. f. pract. Heilk., 1856, II, pp. 193–202.]

BELGIUM.

Saunier (J. J. D.) Extrait de l'enquête sur le choléra de 1866, dans les cantons de Contich et de Wilryck.

[Ann. Soc. de méd. d'Anvers, 1874, xxxv, pp. 506–539, 585–632; 1875, xxxvi, pp. 5–36.]

Segers. Quelques remarques sur le choléra régnant.

[Bull. de l'Acad. roy. de méd. de Belgique, 1866, ix, pp. 925–927.]

Suerman (A. C. G.) *Specimen historico-medicum de choleræ asiaticæ itinere per Belgium septentrionale. 8°. *Trajecti ad Rhenum*, 1835. L.

Van Kempen. Rapport sur les mémoires relatifs à l'épidémie de choléra qui a sévi en Belgique pendant l'année 1866.

[Bull. de l'Acad. roy. de méd. de Belgique, 1869, iii, pp. 867–893.]

Discussion sur l'épidémie de choléra de 1866.

[Bull. de l'Acad. roy. de méd. de Belgique, Bruxelles, 1871, v, pp. 1290–1354; 1872, vi, pp. 25–27, 102–146, 257–281, 353–359, 453–466, 548–576, 618–669, 757–789, 812–859; 1873, vii, pp. 25–43.]

Antwerp.

Broeckx (C.) Note sur le choléra-morbus asiatique qui a régné épidémiquement à Anvers, pendant les mois de juillet, août, septembre et octobre 1859. 8°. *Anvers*, 1859.

Desguin. Apparition du choléra à Anvers et marche de la maladie.

[Arch. méd. belges, 1873, iv, pp. 361–372; *also in* Bull. Acad. roy. de méd. Belgique, 1873, vii, 3e s., pp. 775–788, 884–888.]

Gouzée. De l'épidémie de choléra qui a régné dans la garnison d'Anvers. (June–Sept. 1849.)

[Arch. belg. de méd. mil., 1849, iv, pp. 241–253.]

Bruges.

Van Dromme. Note sur le traitement curatif et préventif du choléra asiatique, à propos d'une épidémie de cette affection qui a régné à Bruges en 1859. Rapport de M. Van Coetsem.

[Bull. de l'Acad. roy. de méd. de Belgique, 1861, iv, pp. 237–245.]

Wemaer. Note sur le choléra-morbus épidémique de Bruges (Belgique), pendant l'été de 1832.

[Gaz. méd. de Paris, 1832, iii, pp. 776–777.]

Brussels.

Statistique et traitement du choléra à l'hôpital militaire de Bruxelles.

[Arch. belg. de méd. mil., 1849, iv, pp. 377–385.]

Châtelet.

Gallez. Des affections miasmat... Châtelet et dans les environs ... spécialement de l'épidémie de 18... léra et suette. Rapport de M. ... mont.

[Bull. de l'Acad. roy. de méd. de Bel... ii, pp. 502–511; suppl., pp. 5–283.]

Conie.

Raimbert (L. A.) Relation de ... de choléra qui a régné dans le ... Conie en 1865.

[Jour. de méd., de chir., et de pharm... xelles, 1866, xliii, pp. 3–12.]

Hensies.

Devos. Rapport sur l'épidémie ... léra dans la commune d'Hensies.

[Jour. de méd. de chir. et de pharm... pp. 3–11.]

Herenthals.

Loneaux (P. L.) Notes et observ... sur l'épidémie de choléra qui a ... Herenthals en 1859.

[Jour. de méd., de chir., et de pharmac... xelles, 1860, xxx, pp. 429–457.]

Liége.

Lombard. Communication sur ... mie du choléra asiatique qui a ... ge depuis le 11 décembre 184...

[Bull. de l'Acad. roy. de méd. de Bel... 49, viii, pp. 373–422.]

Midavaine (I.) Rapport adr... l'inspecteur général du service ... de l'armée, sur le choléra qui a ... dans la garnison de Liége 184...

[Arch. belg. de méd. mil., 1849, iv, pp. ...]

Rapport sur le mouvement des ... du choléra à Liége, et sur les ... traitement qui y ont été employ...

[Bull. de l'Acad. roy. de méd. de Bel... 49, viii, pp. 765–786.]

Mechlin.

Dechange. Épidémies du choléra ... lines.

[Arch. méd. belges, 1866, iv, 2e s., p. ...]

Mons.

Bouvier. Considérations sur ... épidémique qui a régné à Mons ... l'année 1859.

[Arch. belg. de méd. mil., 1860, xiv, pp. ...]

Broeck (Van den). Histoire ... épidémique qui a régné en 18... garnison de Mons.

[Arch. belg. de méd. mil., 1855, xv, p. ...]

lième. Quelques faits et considéra-ons relatifs à l'épidémie de choléra, qui égné à Mons, du 13 juin au 15 octo-e 1866.
[ULL. de l'Acad. roy. de méd. de Belgique, 1870, v. pp. 383–389.]

ur.

l (A.) Histoire de l'épidémie de cho-a à Namur en 1866. 8°. *Bruxelles*, 74. L.

ide.

umné. Mémoire sur le choléra qui a gné à Ostende en 1854. Rapport de Van Coetsem.
[ULL. de l'Acad. roy. de méd. de Belgique, 1855-6, XV, pp. 151–152.]

haegha. Notice sur l'apparition et la arche du choléra à Ostende en 1854.
[EV. de la Soc. méd. chir. de Bruges, 1855, III, e s., pp. 9–19.]

léra. [Épidémie d'Ostende.—Rap-rt du 2e sémestre 1854.]
[ERN. belg. de méd. mil., 1856, XVII, pp. 149–156.]

ine-en-Haye.

acken. Notice sur l'épidémie de Ve-ine-en-Haye, juin–juillet 1832. 8°. ancy [*n. d.*]

mes.

dam (L. J.) Rapport sur l'épidémie choléra dans la commune de Wasmes.
[CH. belg. de méd. mil., 1849, III, pp. 398–412.]

DENMARK.

lin. Statistike Opgivelser om Chole-Hospitalet i Frue Arbeidshuus.
[BL. for Laeger, 1853, III, pp. 371–374.]

ska (T.) Cholera-Epidemien i Konge-et Danmark i Aaret 1853. 8°. *Copen-gen*, 1855.

— The same. [Translation and re-ew.]
[BIT. & For. Med. & Chir. Rev., London, 1860, XXV, pp. 145–160.]

ch. Mittheilungen über die Cholera-pidemie in Dänemark 1853. 8°. *Ber-n*, 1853.

din (L. A.) Gesteldheid van den Bo-em en Cholera. Twee Hoofdstukken t de Geschiedenis van de jongste Cho-ra-Epidemie te Kopenhagen.
[ERKL. Tijdschr. v. Geneesk., 1858, II, pp. 161–196.]

ding (A.) *og* **Thomsen** (J.) Om de ind-sulige Aarsager til Choleraens ulige Styrke i de forskjellige Dele af Kjö-

Colding *og* **Thomsen**—continued.
benhavn, og om midlerne Til i Fremti-den at formindske Sygdommens Styrke.
[UGESKR. for Laeger, 1854, XX, pp. 161–198.]

Fenger. En Udsigt over de Choleratil-faelde som i Aar ere forekomme paa Frederiks Hospital.
[BIBL. for Laeger, 1853, III, pp. 356–363.]

——— Prof. Fenger's Beobachtungen über die asiatische Cholera, in dem königl. Friedrichs-Hospitale zu Kopenhagen 1853. Mitgetheilt von Dr. Möller in Altona.
[ALLG. med. Centr.-Zeitg., 1854, XXIII, pp. 41–44, 50–52.]

Holst (E.) Nogle Bemaerkninger i Anled-ning af Choleraepidemien i Korsör.
[UGESKR. for Laeger, 1857, XXVII, pp. 289–299, 333–335.]

——— Meddelelser om Koleraepidemien i Korsör i 1857, isaer i hygienisk og statis-tik Henseende.
[HOSP. Tidende, 1859, II, pp. 94–96.]

Hüberts (J. R.) Beretning om Cholera-Epidemien i Kjöbenhavn, 12 Juni–1 Oc-tober 1853, udarbeidet og udgiven for den overordentlige Sundhedscommission for Kjöbenhavn. . . 8°. *Kjöbenhavn*, 1855.

——— Rapport sur l'épidémie de choléra qui a régné à Copenhague en 1853. Rap-port de M. Fallois.
[BULL. de l'Acad. roy. de méd. de Belgique, 1856–57, XVI, pp. 75–78.]

Hummel (G.) En Bemaerkning i An-ledning af Beretningen om den Kjöben-havnske Koleraepidemie.
[UGESKR. for Laeger, 1855, XXIII, pp. 97–106.]

Knudsen (P.) Beretning fra Hospitalet i Barakkerne. (Cholerahospitalet.)
[UGESKR. for Laeger, 1857, XXVII, pp. 267–271.]

Krebs. Koleraepidemien i Skjelskör Laegedistrikt i Efteraaret 1857.
[UGESKR. for Laeger, 1858, XXVIII, pp. 73–87.]

Panum (P.) Om Cholera-Epidemien i Bandholm, 1850. *Kjöbenhavn* [*n. d.*]

Poulsen (I. P.) *og* **Wilster** (F.) Om Cho-leraen i Korsör i symptomatologisk og therapeutisk Henseende.
[UGESKR. for Laeger, 1857, XXVII, pp. 337–351.]

Schleisaner (P. A.) The cholera in Co-penhagen in 1866, the precautions there taken against the spread of the disease, and the frequency of diarrhœal com-plaints in Denmark.
[BRIT. & For. Med.-Chir. Rev., 1871, XLVIII, pp. 462–476.]

——— Cholerabericht. Das Auftreten der Cholera in Dänemark seit ihrer ersten

Schleissner (P. A.)—continued.
europäischen Invasion, verglichen mit dem Auftreten dieser Krankheit in den angränzenden Ländern und den benachbarten Hafenstädten. [Eingereicht an die internationale sanitäre Conferenz in Wien.]
[Allg. Zeitschr. f. Epidemiol., Stuttgart, 1875, II, pp. 70–86; 2 tables.]

Sommer. Om Cholera's Udbredelsesmaade i Kongeriget Danmark (med Undtagelse af Kjöbenhavn), i Aaret 1853.
[Bibl. for Laeger, 1854, V, pp. 286–377.]

Zachariae. Den i dette Aar truende Cholera-Epidemis Forhold til Kjöbenhavn. Smedeliniens Lazareth.
[Ugeskr. for Laeger, 1866, II, pp. 393–405.]

Beretning om Udbredelsen af Cholera her i Landet i August og Sept. 1859.
[Ugeskr. for Laeger, 1859, XXXI, pp. 380–382.]

Cholera-Epidemien i Kongeriget Danmark i 1853, efter de til Sundhedskollegiet indsendte Laegeberetninger.
[Suppl. til Bibl. for Laeger, 1853, pp. 1–258 (med 5 Kort).]

Choleratilfaelde paa Christianshavn.
[Ugeskr. for Laeger, 1866, II, p. 279.]

Om den orientalske Cholera, dens Natur og Behandling, og Hvorvidt vi have dens Udbredelse til Danmark at Befrygte.
[Bibl. for Laeger, 1831, XIV, pp. 128–198.]

[**Statistics** of cholera in Denmark.]
[Suppl. til Bibl. for Laeger, 1851, pp. 25–35; 1853, III, p. 328; 1855, pp. 44–50; 1856, pp. 51–62; 1857, pp. 292–293; 1858, pp. 384–395; 1859, pp. 406–408; 1860, pp. 363–367; 1872, pp. 463–467.]

FRANCE.

Armieux. Répartition du choléra en France.
[Rev. méd. Toulouse, 1867, I, pp. 9–21.]

——— Le choléra en France: répartition des 4 épidémies sur les 86 départements [carte].
[Gaz. hebd. de méd. et de chirurg., Paris, 1869, 2e sér., VI, p. 848².]

Barrier (F.) *et* **Garin** (J.) L'épidémie cholérique [1854].
[Gaz. méd. de Lyon, 1854, VI, pp. 217–222, 249–255.]

Barth. Rapport sur les épidémies du choléra-morbus qui ont régné en France pendant les années 1854 et 1865.
[Mem. de l'Acad. de méd., Paris, 1871–73, XXX, pp. 297–424, 1 pl.; *also in* 4°, Paris, n. d.]

——— Résumé des rapports sur les épidémies de choléra-morbus des années 1854 et 1865.
[Gaz. hebd. de méd. et de chirurg., Paris, 1869, 2e sér., VI, pp. 390–393, 418–424; *also in* 8°, Paris, 1869.]

Barth—continued.

——— Résumé of the report on epidemics of cholera in France in 1854, 1854 and 1865.
[Brit. & For. Med.-Chirurg. Review, 1874, II, pp. 193–209.]

——— Résumé du rapport sur les épidémies de choléra qui ont régné en France en 1856, 1865 et 1866.
[Bull. de l'Acad. imp. de méd., Paris, XXXIV, pp. 271–308.]

Besnier (E.) Contribution à l'étude des épidémies cholériques, 1866–73. Leçons faites à la Société médicale des hôpitaux.
[L'Union méd., 1873, XVI, 3e ser., pp. [illegible] etc.]

——— The same. 8°. *Paris*, 1874.

Besuchet (J. C.) Le choléra, ses caractères, ses progrès, son traitement appuyés sur des faits nombreux observés en France et en Belgique, pendant l'épidémie de 1832. . . . 8°. *Paris*, 1837.

Billot. Rapport à l'Académie de médecine sur l'épidémie du choléra qui a régné, depuis le 20 juillet jusqu'au 15 octobre 1854, dans les communes de Dôle, Authume, Jouhe, Rochefort, Chamblanois, Amange, arrondissement de Dôle, Pont-du-Navoy, Monnet-la-Ville, Montigny Le Pasquier, Ney, arrondissement de Poligny. 8°. *Poligny*, 1854.

Bompard. Première lettre à un médecin sur l'épidémie régnante. 8°. *Paris*, 1832.]

Bourgogne, *fils.* Épidémie cholérique observée dans les communes de Corbeil, Vieux-Condé, Fresnes et Estrampes pendant l'année 1866. Le choléra considéré et traité comme une fièvre pernicieuse pédéenne épidémique très-pernicieuse de l'Inde orientale, . . .
[Journ. de méd., de chir., et de pharmacie de Bruxelles, 1869, XLVIII, pp. 13–22, etc.; LI, 1870, 34, etc.; 1870, L, pp. 36–44, etc., LII, pp. [illegible] etc.; 1871, LII, pp. 36–43.]

——— The same. 8°. *Bruxelles*, 1871.

Brouardel. Comparaison entre les épidémies du choléra de 1853–54, 1865–66 et 1873.
[L'Union méd., 1873, XVI, 3e s., pp. [illegible]]

Cazenave (J. S.) Rapport sur la constitution miliaire et le choléra, présenté à la Société de Landes. 8°. *Bayonne*, 1854.

Champouillon. Le choléra et [illegible]. Étiologie et prophylaxie.
[Gaz. des Hôp., 1865, pp. 509–512.]

tard. Rapport sur le choléra, lu à la ciété . . . de médecine de Bordeaux . 16 juillet 1866. . . . 8°. *Bordeaux* . d.]

nu. Rapport sur le choléra-morbus, ressé à m. le colonel baron de l'E- ng. 8°. *Perpignan*, 1835.

hambre (A.) Coup d'œil sur le cho- ra des départements en 1854.

AZ. hebd. de méd. et de chir., Paris, 1853–54, . pp. 1052–1080, 1109–1112; 1855, II, pp. 26–31, 114–119.]

pech de Frayssinet. Mémoire sur le oléra-morbus, pour servir à l'histoire cette maladie sur le territoire fran- . 8°. *Lyon*, 1833.

reuil *et* **Rech.** Rapport sur le cho- ra-morbus asiatique, qui a régné dans midi de la France en 1835. 8°. *Mont- llier*, 1836. L.

in (C.) Comparative statistics of aths from cholera in France, in 1832 d 1849.

ED. Times & Gazette, 1852, IV, n. s., p. 194.]

rcault. Influence des conditions géo- giques et hydrologiques sur la marche choléra en France.

AZ. méd. de Paris, 1849, IV, pp. 338–340, 357–60.]

— Influence des lieux, des eaux et des bitations sur le développement du oléra qui a régné, en 1834 et 1835, ns le midi de la France.

AZ. méd. de Paris, 1850, V, pp. 373–377, 411–14.

ter. Lettre sur les choléras dans le idi de la France.

AZ. méd. de Paris, 1849, IV, pp. 678–679.]

nier-Léteurrie (T.) Lettre sur le oléra-morbus, relative aux conditions pographiques et hygiéniques du can- n de Passais et de Domfront. 8°. *Ver- illes*, 1849.

idichon. Lettre du . . . à ses clients, r le choléra-morbus (31 mars 1832), re- ie, annotée et publiée en 1849; par hibault. 8°. *Versailles*, 1849.

e ed. 1832.]

thier (W.) Rapport sur le cholera orbus. 8°. *Lyon*, 1831.

sain (P. A.) *Étude sur le choléra rticulièrement au point de vue de pidémie de 1873. 4°. *Paris*, 1874. L.

frin (J.) Réapparition du choléra.

AZ. méd. de Paris, 1854, IX, 3e s., pp. 143–144.]

Hergt (F. C.) Geschichte der beiden Cholera-Epidemien des südlichen Frankreichs in den Jahren 1834 und 1835. 12°. *Coblenz*, 1838.

Heyfelder (J. F.) Die Cholera in Frankreich, besonders im Mosel-, Maas-, Marne-, Seine- und Marne-Seine und Oise und Oise Departement, sowie in Paris, in Folge höhern Auftrags. *See* CHOLERA IN EUROPE. **Heyfelder** (J. F.) Beobachtungen über die Cholera asiatica [etc.]

——— Fragmente aus einem Berichte über die Cholera in einigen französischen Departements während des Sommers 1833.

[MED. Annalen, Heidelberg, 1836, II, pp. 105–129.]

Houlès (B.) Étude médicale sur la dernière épidémie de choléra dans le midi de la France.

[REV. méd., Paris, 1855, II, pp. 199–214, 257–259.]

Jacquemond. Le choléra. Préservation, traitement, causes. Choléra des Alpes. 8°. *Moutiers*, 1867.

Langenhagen (O. de). Le choléra, son mode de développement et de propagation, épidémie de 1865, traitement. 12°. *Paris*, 1866.

Larrey (D. J., *le baron*). Notice sur l'épidémie du choléra-morbus indien qui a régné dans les ports méridionaux de la Méditerranée et dans toute la Provence, pendant les mois de juillet et d'août 1835. 4°. *Paris*, 1835. L.

Lasèque (C.) Le choléra en 1852.

[ARCH. gén. de méd., 1852, III, pp. 118–190.]

——— Étude clinique sur l'épidémie actuelle de choléra asiatique.

[ARCH. gén. de méd., 1865, II, pp. 513–531.]

——— The same. Reprint. 8°. *s. p.* L.

Lauvergne. Choléra-morbus en Provence. . . . Suivi de la biographie du docteur Fleury, . . . 8°. *Toulon*, 1836.

Lélut. Quelques traits de l'histoire du choléra en province.

[GAZ. méd. de Paris, 1855, X, pp. 115–121.]

Le Roy. Épidémie de choléra-morbus de 1865–1866. Réponse . . . à M. le dr. Denis. 8°. *Caen*, 1868.

Lutaud. Le choléra à Rouen et au Havre.

[GAZ. hebd. de méd. et chir., Paris, 1873, X, 2e s., pp. 561–570, 586.]

Menard (A.) Lettre sur les choléras dans le midi de la France.

[GAZ. méd de Paris, 1849, IV, pp. 802–804.]

Moreau de Jonnes. Statistical remarks on the effects of cholera in France, during the epidemic of 1832.

[LONDON Med. Gaz., 1833, XI, pp. 629–633; *also in* LANCET, 1833, I, p. 689.]

Paillard (H.) Histoire statistique du choléra-morbus qui a régné en France en 1832. 8°. *Paris*, 1832. L.

Pietra Santa (P. de). Épidémie cholérique de 1865. Rapport lu à la Société médico-chirurgicale de Paris et publié par décision de la société. 8°. *Paris*, 1866. L.

Raspail (F. V.) Le choléra en 1865. . . . 8°. *Paris*, 1865.

[2e éd., Le choléra en 1865 et 1866, 8°, 1866; 3e éd., 8°, same year.]

Robbe (L.-A.) Du choléra épidémique. Épidémies de 1865–66. Essai sur les formes cliniques et les indications thérapeutiques suivi des considérations sur le choléra morbus, à l'occasion de ces deux épidémies, par J. Bouley. 4°. *Paris*, 1871. L.

Rousseau-Saint-Philippe. Le choléra en France.

[GAZ. méd. de Bordeaux, 1873, II, pp. 481–483.]

Solari (L. J. M.) Choléra de 1865. Sa marche, son mode de transmission. Moyens de le faire disparaître ou d'en arrêter la propagation. 8°. *Paris*, 1865. L.

Tholozan. Bulletin du choléra.

[GAZ. méd. de Paris, 1853, VIII, 3e s., pp. 779–780; 1854, IX, pp. 227–228, etc.]

——— Le choléra dans le midi de la France. —Des localités atteintes et des localités préservées.—Influence de la dissémination de la population.

[GAZ. méd. de Paris, 1854, IX, pp. 473–474, 487–488.]

Thomas (J. F. R.) Quelques observations de choléra-morbus, recueillies dans le service du docteur Cauvière, et suivies de quelques propositions sur cette maladie. 8°. *Marseille*, 1835.

Toussaint (F.) Description du choléra-morbus épidémique qui s'est manifesté dans les villes de Saint-Nicolas et de Rosières, et dans les communes de Tonnoy, Burthecourt, Lupcourt, Gerardcourt, Dombasle, Art-sur-Meurthe, Bosserville, Harancourt, Lenoncourt et Laneuveville. Suivie de considérations topographiques sur ces communes. 8°. *St. Nicolas*, 1855.

Documents statistiques et administratifs concernant l'épidémie de choléra de 1854, comparée aux précédentes épidémies cholériques qui ont sévi en France, publiés par ordre de s. exc. le ministre de l'agriculture. . . . 4°. *Paris*, [illegible].

Épidémie régnante, marche du choléra-diarrhée prémonitoire.

[JOUR. de méd. et de chir. prat., Paris, 1854, 2e s., pp. 6–13.]

Gazette médicale de Paris, journal spécial du choléra-morbus. 4°. *Paris*, 1854.

[This title was assumed by the GAZETTE MÉDICALE in No. 14 of tome 3, April 1, 1854, and was continued to No. 26, Oct. 11, 1854.]

Marche du choléra.—Nouvelles sanitaires.

[GAZ. méd. de Paris, 1849, IV, pp. 1–2, 2–4, 61–62, 75–76, 95–96, 215–216.]

Note sur la situation actuelle par rapport au choléra.

[GAZ. des hôp. Paris, 1873, XLV, pp. 613–615.]

Rapport sur le choléra épidémique.

[BULL. de l'Acad. de méd., Paris, 1873, [illegible], pp. 73–96.]

Rapport sur les épidémies de choléra-morbus qui ont régné de 1817 à 1850: fait au nom d'une commission composée de MM. Bouillaud, Barth, Davenne, de Kergaradec, J. Guérin, Jolly, Mélier, Rochoux, Trousseau, Briquet, par M. Briquet. Extrait des Mémoires de l'Académie impériale de médécine, tome XXVIII. 4°. *Paris*, 1867.

Abbeville.

Vésignié (J. B.) Documents sur le choléra-morbus asiatique considéré comme maladie contagieuse ou communicable recueillis dans l'arrondissement d'Abbeville en 1832 et 1833. 8°. *Abbeville*, [illegible].

Aigues-Mortes.

Schillizzi. Exposé pratique sur l'épidémie du choléra-morbus qui a régné à Aigues-Mortes du 6 juillet au 14 septembre 1854. 8°. *Montpellier*, 1855.

Aix.

Bourguet. Étude sur la marche et le mode de propagation du choléra dans l'arrondissement d'Aix en 1865. 8°. *Aix*, 1867.

Amiens.

Barbier. Lettres sur le choléra-morbus d'Amiens.

[GAZ. méd. de Paris, 1832, III, pp. 257–259, 273–276.]

Petit (J.) Histoire du choléra-morbus asiatique, avec les mesures administratives

it (J.)—continued.
ves auxquelles il donna lieu en 1832, à miens et dans . . . . la somme, etc. . *Amiens*, 1833.
it (A) to Amiens to see the cholera.
MED. Times & Gaz., London, 1866, II, pp. 39–43.]

ibes.

phel. Réflexions sur le choléra qui gné à Antibes. Avis aux Antibois, lativement à cette épidémie. 12°. rasse, 1835.

ége (Department of the).

ert (A.) Dissertation sur le choléra siatique en Europe, à propos de l'épiémie de l'Ariége [1854]. 8°. *Paris*, 855. L.

es.

cros. Rapport sur le choléra-morbus l'Arles [Bouches-du-Rhône].
GAZ. des hôp., 1832, VI, pp. 405–408.]

artin (F.) Du choléra épidémique, dit siatique, observé dans la ville d'Arles, n Provence, en 1832, 1835, 1837 et 1849, avec des observations cliniques importantes, . . . suivies d'un court traité de principes d'hygiène privée. 8°. *Arles* [1850]. L.

eissonnier (C.) Considérations sur le choléra d'Arles, adressées à m. le maréchal ministre de la guerre et à mm. les inspecteurs du conseil de santé des armées. 8°. *Avignon*, 1855.

mentières.

ire. Rapport sur le choléra dans la ville d'Armentières en 1866, lu au Conseil central d'hygiène. . . . 8°. *Lille*, 1867.
2e ed. same year.]

teuil.

echelle (P.) L'épidémie d'Auteuil [près Paris].
GAZ des hôp., 1832, VI, pp. 122–123, 136.]

vignon.

hauffard. Choléra-morbus observé à l'hôpital d'Avignon.
GAZ. des hôp., 1831, V, p. 368.]

lérard (F.) Notice sur le choléra-morbus observé à Avignon pendant les mois de juillet, août et septembre 1835. 8°. *Avignon*, 1835.

'amard. Sur le choléra à Avignon.
BULL. de l'Acad. nat. de méd., 1849–50, XV pp. 6–10.]

Bar-le-Duc.

Baillot. Quelques réflexions sur l'épidémie cholérique de 1854 dans la ville de Bar-le-Duc. 8°. *Bar-le-Duc*, 1855.

Bar sur-Seine.

Douat (J.-P.-B.-A.) *Quelques considérations sur le choléra-morbus épidémique, observé dans l'arrondissement de Bar-sur-Seine (Aube), pendant les mois de juillet, d'août et de septembre 1854. 4°. *Paris*, 1856. L.

Bayonne.

Bossoutrot (J.-B.-S.) *Du choléra épidémique qui a régné dans l'arrondissement de Bayonne (année 1855). 4°. *Paris*, 1858. L.

Beaucaire.

Blaud (P.) Histoire du choléra épidémique qui a régné à Beaucaire pendant le mois de juillet, août, septembre, octobre et novembre 1835.
[REVUE méd. franç. et étrang., Paris, 1836, I, pp. 320–352; 1836, III, pp. 201–243.]

——— Sur le choléra à Beaucaire.
[BULL. de l'Acad. nat. de méd., 1849–50, XV, pp. 82–85.]

Beaujeu.

Diday (P.) Documents sur l'origine et la propagation du choléra à Beaujeu.
[GAZ. med. de Lyon, 1854, VI, pp. 273–278.]

Beaune.

Billardet. Sur le choléra à Beaune.
[BULL. de l'Acad. nat. de méd., 1848–49, XIV, pp. 1069–1074.]

Beauvais.

Choléra-morbus (Le) observé à l'Hôtel-Dieu de Beauvais [Oise].
[GAZ. des hôp., 1832, VI, pp. 142–143, etc.]

Bercy.

Lanessan (de). Rapport statistique sur le choléra épidémique à Bercy, pendant les mois de mars, avril, mai, juin et juillet 1849. 8°. *Paris* [n. d.]

Bernay.

Neuville. Relation sur le choléra-morbus observé à Paris, dans le mois d'avril 1832, suivie d'un rapport sur l'épidémie cholérique, qui a régné dans l'arrondissement de Bernay (Eure) depuis le 29 avril jusqu'au 27 septembre 1832. 8°. *Paris*, 1832. L.

Bicêtre.

Rochoux (J. A.) Notice sur le choléra-morbus en général, et en particulier sur celui de Bicêtre. 8°. *Paris*, 1833. L.
[Ext. en partie des Arch. génl. de méd.]

Bordeaux.

Lande (P. L.) Le choléra et les commissions sanitaires à Bordeaux.
[Gaz. méd. de Bordeaux, 1873, II, pp. 433–435.]

Mabit (J.) Rapport sur le choléra-morbus asiatique qui à été observé à Bordeaux depuis le 4 août 1832 jusqu'à ce jour, et sur la nécessité du complet assainissement de la ville [etc.] 8°. *Bordeaux*, 1832. L.

Boulogne (Seine).

Lefebure. Le choléra-morbus de Boulogne, près Paris.
[Gaz. des hôp., 1832, VI, pp. 138, 170–171.]

Brest.

Caradec (T.) Le choléra de Brest en 1866. *Paris*, 1866.

Duval (M.) Mémoire sur le choléra-morbus asiatique. Description du bagne de Brest, avec plan ou tracé ; relation d'une épidémie de choléra, qui a régné en 1849 dans cet établissement; comparaison avec d'autres épidémies de même nature qui ont sévi en France, soit en 1832, soit en 1849 (Salpétrière, Val-de-Grâce, Charité) ;—tableaux relatifs, à l'anatomie pathologique du choléra, à la durée de la maladie, aux âges, aux professions et au régime alimentaire des forçats. 8°. *Brest*, 1853. L.

Guépratte (A.) Choléra mitigé observé à Brest en février et mars 1844.
[Gaz. des hôp., 1844, pp. 426–427.]

Broglie.

Note sur le choléra-morbus de la commune de Broglie (Eure).
[Gaz. méd. de Paris, 1832, III, pp. 552–553.]

Caen.

Denis-Dumont. Simple rectification à propos de l'épidémie cholérique de Caen en 1865–66. Réponse à M. le Dr. Le Roy. 8°. *Caen*, 1868.

Le Roy. Rapport sur l'épidémie le choléra-morbus qui a régné à Caen, en 1865–66, fait à la Société de médecine de Caen. 8°. *Caen*, 1868.

Calais.

Baudens. Le choléra-morbus de Calais.
[Gaz. des hôp., 1832, VI, p. 73.]

Gasté (L. F.) Notice historique et statistique sur le choléra-morbus épidémique de Calais, depuis la fin de mars jusqu'en juillet suivant.
[Ann. de la méd. phys., Paris, 1832, XV, pp. 72–73 ; *also*, reprint in 8°, Paris, 1832.

——— Réflexions et observations nouvelles sur le choléra-morbus épidémique de Calais et des environs.
[Ann. de la méd. phys., Paris, 1833, XXIII, pp. 197–213.]

Choléra-morbus : observations sur le lazaret de Calais.
[Gaz. des hôp., 1832, VI, pp. 20, 43–44.]

Calvados (Department of).

Denis-Dumont. Le choléra dans le département du Calvados en 1865 et 1866. Rapport présenté à M. le préfet. 8°. *Caen*, 1867.

Camaret.

Delioux de Savignac (O. C. A.) Sur une épidémie de choléra à Camaret, en Languedoc. 4°. *Montpellier*, 1837.

Chambéry.

Grandclément (J. E.) Quelques remarques sur une épidémie de choléra asiatique observée à Chambéry [etc.] en septembre 1867. 4°. *Paris*, 1867.

Charente (Department of the).

Chapelle (A.) De l'épidémie de choléra qui a régné dans le département de la Charente, pendant l'année 1854. 8°. *Paris*, 1856.

Charenton.

Ramon (L. J.) Description du choléra-morbus qui a régné épidémiquement dans les communes de Charenton et de Charenton-Saint-Maurice en 1832 ; réflexions sur cette maladie. 8°. *Paris*, 1833.

Château-Chinon.

Valat. Relation de l'épidémie de choléra-morbus asiatique à Château-Chinon (Nièvre), en juin 1849.
[Bull. de l'Acad. nat. de méd., 1849–50, XIV, pp. 1006–1024.]

Château-Voué.

Ancelon (E. A.) Le choléra-morbus épidémique, à Château-Voué. 8°. 1850.

…enois.

…tler. Note sur le choléra de Chatenois.
[…az. méd. de Strasbourg, 1854, XIV, pp. 358–361.]

…minon.

…rvillion (O.) Le choléra à Cheminon, … 1854. 8°. *Paris*, 1854.

…mont-Ferrand.

…ret. Documents sur les épidémies qui …nt régné dans l'arrondissement de Cler…ont-Ferrand, de 1849–64. *Paris*, 1865.

…lichy-la-Garonne.

…pport du Dr. Souchal, de la faculté …e Paris [sur le choléra épidémique, à …lichy-la-Garonne], au conseil munici…al, en son assemblée du 13 mai 1832. …. *Paris*, 1832. L.

…mmercy.

…dson (A.) Le choléra en 1854 dans l'ar…rondissement de Commercy. 8°. *Com…mercy*, 1855.

…émoire de la Société médicale de Com…mercy sur le choléra et la suette de 1854. Rapport du Dr. Dechilly à la société, lu …t adopté dans sa séance du 22 novem…bre 1855. 8°. *Commercy* [*n. d.*]

…mpiègne.

…rvivier *et* Villette. Choléra-morbus …observé à Compiègne, et spécialement à l'Hôtel-Dieu de cette ville. Compte ren…du. . . . 8°. *Compiègne*, 1832.

…rbeil.

…lalle. Le choléra-morbus à Corbeil et dans la banlieue. 8°. *Corbeil*. L.

…écy.

…drien (A.) Choléra-morbus. Relation historique et médicale de l'épidémie de Crécy et des villages circonvoisins. 8°. *Paris*, 1832.

…ieppe.

…audet. Histoire d'une épidémie chole…riforme observée à Dieppe pendant l'été de 1834.
[…AL. méd. de Paris, 1835, III, pp. 33–40.]

…inan.

…lotice sur le choléra qui s'est manifesté à …Saint-Cast, arrondissement de Dinan. …. *Dinan*, 1832.

Étain.

Gérard. Choléra morbus d'Étain (Meuse). Faits en faveur de la contagion de cette maladie.
[BULL. gén. de thérap. méd. et chir., 1832, II, pp. 391–393.]

Étampes.

Bourgeois. Coup d'œil sur les deux épidémies de choléra asiatique qui ont sévi à Étampes et dans son arrondissement pendant les années 1832 et 1849. 8°. *Puy*, 1850.

Martin (C.) *Considérations sur le choléra-morbus épidémique, observé à Étampes (Seine-et-Oise) pendant le printemps et l'été de l'année 1832. 4°. *Paris*, 1833. L.

Eure-et-Loir.

Rapport fait à la commission centrale de salubrité . . . d'Eure-et-Loir, par MM. Durand, Grealou et Maumoury, sur le choléra-morbus et son traitement. 4°. *Chartres* [*n. d.*]

Flayosc.

Giraud. Relation d'une épidémie de choléra à Flayosc [Var].
[LA FRANCE méd. et pharm., Paris, 1855, II, pp. 5–8, 21–23, 37–39.]

Gerzat.

Coste (É.) *Sur le choléra épidémique de 1849 à Gerzat (Puy-de-Dôme). 4°. *Paris*, 1852. L.

Giromagny.

Benoit (H.) Du choléra dans la vallée de Giromagny et des moyens qui ont réussi à arrêter les progrès de l'épidémie en 1854. 8°. *Strasbourg*, 1855.

Gironde (Department of).

Levieux (C.) Rapport fait au conseil central d'hygiène et de salubrité publique . . . de la Gironde, sur l'épidémie cholérique qui a régné dans ce département pendant l'année 1849. 8°. *Bordeaux*, 1852.

Givet.

Pellarin. Nouvelle communication sur le choléra de Givet, et documents relatifs à cette épidémie.
[COMPTES-RENDUS hebd. des séances de l'Acad. des sci., Paris, 1849, XXIX, p. 483.]

Gorze.

Petitgand (A.) Rapport sur l'épidémie de choléra qui a éclaté dans le canton de Gorze en 1849. 8°. *Metz*, 1850.

Gray.

Paris. Note sur le choléra à Gray et son traitement.
[BULL. gén. de thérap. méd. et chir., 1856, L, pp. 506–510.]

Grenelle.

Marie (J.-L.) * Esquisse du choléra-morbus de Grenelle. 4°. *Paris*, 1832. L.

Choléra-morbus (Le) de Grenelle.
[GAZ. des hôp., 1832, VI, pp. 242–243.]

Gy.

Niobey (P. A.) Histoire médicale du choléra-morbus épidémique qui a régné en 1854 dans la ville de Gy (Haute Saône) suivie de tableaux statistiques [etc.] 8°. *Paris*, 1858. L.

Havre.

Beauregard (F. V.) Recherches sur la nature et le traitement du choléra épidémique. (Observations recueillies au Havre-Graville), 1848–49, 1853. 8°. *Havre*, 1854. L.

Lecadre (A.) Le choléra-morbus au Havre en 1832. . . . 8°. *Havre*, 1862.

——— Histoire des trois invasions épidémiques de choléra-morbus au Havre en 1832, 1848 et 1849, 1853 et 1854. 8°. *Paris*, 1863.

——— Le choléra-morbus épidémique au Havre et dans l'arrondissement en 1865–66. . . . 8°. *Paris*, 1867. L.

Irancy.

Moret (S.) Note sur le choléra-morbus de la commune d'Irancy (Yonne).
[GAZ. méd. de Paris, 1832, III, pp. 397–399.]

Isère (Department of).

Duboulox. Note sur le mode de propagation du choléra asiatique dans la vallée de l'Isère pendant l'année 1854.
[GAZ. méd. de Lyon, 1855, VII, p. 374.]

Is-sur-Tille.

Beulet. Note sur la marche et le traitement du choléra d'Is-sur-Tille. 8°. *Dijon* [1854].

Joigny.

Roussel (A.-N.) *Quelques mots sur l'épidémie de choléra asiatique qui a régné en Joigny en juillet et août 1854, précédés de considérations générales sur le choléra. 4°. *Paris*, 1854. L.

Jura (Department of).

Germain. Mémoire sur le choléra [illegible] dans le Jura salinois. . . . [illegible] *le-Saulnier*, 1855.

La Calmette.

Roux (J.) Relation d'une épidémie [illegible] lérique qui a régné à La Calmette pendant les mois de septembre, [illegible] et novembre 1855. 8°. Nîmes [illegible].

Lacaune.

Moximan. Observations pratiques [illegible] choléra-morbus qui s'est développé dans le mois de juillet de l'année [illegible] dans quelques communes du canton de Lacaune. 8°. [*Castres*], 1856.

Laigle.

Emangard (F. P.) Relation de l'épidémie de choléra-morbus qui a régné à Laigle (Orne).
[ANN. de la méd. phys., 1832, XXII, pp. 97–[illegible]]

Lanvéoc.

Guillemart (J. B.) *Du choléra épidémique observé à Lanvéoc, canton de Crozon (Finistère). 4°. *Morlaix*, 1868.

La Rochelle.

Godelier. Sur le choléra à la Rochelle.
[BULL. de l'Acad. nat. de méd., 1848–49, XIV, 1059–1060.]

La Seyne.

Prat. La Seyne et son épidémie [illegible] lérique en 1865. . . . 8°. *Toulon*.

La Villette.

Cornin. Choléra-morbus observé à la Villette. Réflexions sur l'influence de la constitution atmosphérique.
[GAZ. des hôp., 1835, IX, p. 394.]

Le Mans.

Barbier. Du choléra épidémique [illegible] au Mans, année 1849. (Lectures faites à la Société d'agriculture, sciences et arts de la Sarthe.) 1°. Aperçu de l'épidémie de choléra épidémique au Mans: par [illegible] teur Barbier, secrétaire. 2°. Recherches analytiques sur la rue Basse, communiquées par M. Ed. Guerangue. 3°. Observation de choléra mortel, avec hémorrhagie intestinale. par MM. [illegible] ton Vallée et Barbier. 8°. *Le Mans* 1850.

r.

get (A.) Le choléra de Levier [1855]. *Poligny*, 1872. L.
XT du Bull. de la société d'agriculture, sciences et arts de Poligny.]

y. Sur le choléra à Lille.
TLL. de l'Acad. nat. de méd., 1848-49, XIV, pp. 364-369, 374-379.]

llot. Recherches sur le choléra observé dans la garnison de la ville de lle pendant l'épidémie 1848-49.
'UNION méd., Paris, 1849, III, pp. 117-119.]

risson. Compte rendu des cholériques trés à l'hôpital Saint-Roch [Lille] du juillet au 21 octobre 1866.
AZ. hebd. de méd. et de chirurg., 1867, IV, 2e s., pp. 225-229, 261-263, 276-279.]

at. Choléra de 1866. Rapport sur le oléra qui a régné à Lille et dans le épartement. . . . 8°. *Lille*, 1867.

pport général sur l'épidémie du choera qui a régné à Lille en 1832. (Fait u conseil central de salubrité du département du Nord par une commission ormée de MM. Dourlen, Trachez, Brigandat, Bailly et Lestibondois, rapporteurs.) 8°. *Lille* [1833?] L.

lebonne.

chaptois (D.) Notice sur le choléra à Lillebonne [1849]. 8°. *Fécamp*, 1850.

ches.

ntaine (P. A.) *Du choléra-morbus épidémique observé dans la commune de Loches (Aube), pendant les mois d'août et septembre 1854. 4°. *Paris*, 1855. L.

ir-et-Cher (Department of).

arin-Desbrosses (J. C. M.) Histoire de l'épidémie de choléra-morbus dans le département de Loir-et-Cher pendant l'année 1832. 8°. *Paris*, 1833.

unéville.

ancerotte. Sur le choléra à Lunéville.
[BULL. de l'Acad. nat. de méd., 1849-50, XV, pp. 50-53.]

yons.

ally. Lyon, à l'occasion de la maladie asiatique.
[GAZ. des hôp., 1850, pp. 550-552, 562-563, 590; also, reprint in 8°, Paris, 1850.]

uménil (C.) Rapport sur le choléra-morbus de Lyon et principalement de l'hôpital militaire. 8°. *Lyon*, 1850.

Garin *et* Rambaud. De l'épidémie cholérique qui a régné à Lyon en 1854.
[ANN. de la soc. de méd. de Lyon, 1854, II, pp. 419-442.]

Gauthier (L. P. A.) Rapport sur le choléra morbus fait à la Société de Lyon. 8°. *Lyon*, 1831.

Épidémie (De l') cholérique qui a régné à Lyon pendant les mois de juillet, août et septembre 1854. [Extr. des procès-verbaux de la Société de médecine de Lyon.]
GAZ. méd. de Lyon, 1854, VI, pp. 311-319.]

Vérité (La) sur le choléra à Lyon, avertissements et conseils; par M. T., ex chirurgien de la marine. 8°. *Lyon*, 1849.

Manosque (Canton of).

Mallez (F.) Rapport sur une épidémie de choléra, qui a régné dans le canton de Manosque . . . en septembre et octobre 1855, à M. le sous-préfet de l'arrondissement de Ruffec. 4°. *Paris* [1856.]

Marne, Haute (Department of the).

Daviot (L.) *De la marche du choléra dans diverses communes du département de la Haute-Marne. Quelques considérations sur la suette. 4°. *Paris*, 1854. L.

Marseilles.

André *fils.* Rapport sur l'état sanitaire de la caserne des douanes de la rue Paradis pendant l'épidémie cholérique qui a régné à Marseille en juin, juillet et août 1854, présenté à M. Marcotte, directeur des douanes. 8°. *Marseille*, 1854.

Barthélemy. Coup d'œil sur la seconde invasion du choléra à Marseille, notice lue en séance de la Société de statistique. 8°. *Marseille* [1835].

Bertin (E.) Le choléra de Marseille en 1865 et les travaux de M. le Dr. Seux. . . . 8°. *Montpellier*, 1867.

Desalle (E.) Note sur la dernière épidémie cholérique de Marseille.
[GAZ. méd. de Paris, 1837, V, pp. 657-659.]

Didiot. Réponse à la note de M. Grimand de Caux intitulée : Sur les cas de choléra qui se seraient produits à Marseille avant l'arrivée des pèlerins de la Mecque en 1865.
[GAZ. méd. de Paris, 1866, XXI, pp. 736-737.]

Didiot (A.) Le choléra à Marseille en 1865. Des causes essentielles qui ont

Didiot (A.)—continued.
présidé à son développement à l'état épidémique.
[Rec. de mém. de méd. mil., 1866, XVI. 3e s., pp. 109–142; *also*, reprint in 8°, Paris, 1866.]

Didiot (P. A.) *and* Guès (C.) Choléra épidémique de 1865. Rapport sur l'origine du choléra à Marseille, en 1865. 8°. *Marseille*, 1866.

Ducros, *aîné*. Quelques considérations topographiques et médicales sur le choléra de Marseille en 1837. . . . 8°. *Marseille*, 1837.

Fraisse, Ramadier *et* Boyron. Du choléra-morbus de Marseille. 8°. *Paris*, 1835.

Franc (J.) *et* Méry (L.) Le choléra à Marseille. Seconde invasion, 1835, pour faire suite au choléra à Marseille, première invasion, 1834–35. 8°. *Marseille*, 1836.

Grimaud [de Caux] (G.) Études sur le choléra faites à Marseille en septembre et octobre 1865.
[Gaz. des hôp., Paris, 1865, pp. 487, 502–503, 511; *also*, reprint in 4°, Paris, 1865.]

Jobert (A.) Notice sur l'épidémie cholérique de 1865, contenant: 1° la pathogénie du choléra; 2° le tableau météorologique du déclin de l'épidémie à Marseille. . . . 8°. *Paris*, 1866.

Laugier *et* Ollive. Étude sur le choléra de Marseille en 1865. . . . 8°. *Marseille*, 1865.

Lisle (E.) Le choléra de 1865 à l'asile public d'aliénés de Marseille. Traitement par le sulfate de cuivre. Rapport à M. le sénateur. 8°. *Marseille*, 1866. L.

Maurin (S.-E.) Caractères du choléra de Marseille en 1865.
[Gaz. des hôp., 1865, p. 457.]

Méli (H.) Du choléra asiatique dans la ville de Marseille, en 1849. Rapport fait à la Société nationale de médecine de Marseille. 8°. *Marseille*, 1850. L.

Mélier. Le choléra de Marseille.
[L'Union méd., Paris, 1850, IV, p. 445.]

Menecier (C.) Historique de l'épidémie de choléra à Marseille, 1865. 8°. *Paris et Marseille*, 1866. L.
[Ext. des actes du comité méd. des Bouches-du-Rhône (année 1865).]

Pirondi *and* Rasori (G.) Memoria sul metodo curativo del cholera-morbus asiatico osservato a Marsiglia. 8°. *Milano*, 1836. L.

Rivière (E.) Rapport sur le service des femmes cholériques pendant l'année 1855, adressé à l'administrateur des hospices de Marseille. 8°. Marseille, 1855.

Robert. Lettres sur le choléra de Marseille.
[Bull. Acad. de méd., Paris, 1837–38, II, pp. 25, 40, 54.]

Robert (L. J. M.) Mémoire sur le choléra de Marseille en 1834–1835, et en particulier sur l'emploi des frictions mercurielles à haute dose dans le traitement de cette épidémie.
[Gaz. méd. de Paris, 1835, III, pp. 417–68.]

Roux de Brignolle. Lettre sur le choléra de Marseille.
[Bull. Acad. de méd., Paris, 1837–38, II, p. —.]

Seux (V.) Le choléra dans les hôpitaux civils de Marseille pendant l'épidémie de 1865. . . . 8°. *Paris*, 1866.

Sirus-Pirondi. Des maladies qui ont régné à Marseille depuis 1er décembre 1852 jusqu'au 30 novembre 1853. Rapport présenté à la Société impériale de médecine le 18 décembre 1853. 8°. Marseille, 1854.

——— Relation historique et médicale de l'épidémie cholérique qui a régné à Marseille pendant l'année 1854. 8°. Paris, 1859.

——— Remarques sur le choléra de Marseille en 1855, adressées à M. L. Serre, rédacteur en chef de la "Revue thérapeutique du Midi, gazette médicale de Montpellier" (N°. du 15 sept. 1855). *Marseille* [1855.]

——— *et* **Fabre (A.)** À propos de l'origine du choléra de Marseille en 1865.
[Gaz. hebd. de méd. et de chirurg., 1866, III, p. 297.]

Sue (G. A. T.) Relation de l'épidémie de choléra-morbus qui a régné à Marseille pendant l'hiver de 1834 à 1835. 8°. Marseille, 1835.

Villard (A.) Le choléra, et M. le Dr. Aronssohn dans les hôpitaux de Marseille. 8°. *Marseille*, 1865.

Histoire du choléra asiatique à Marseille pendant les mois de juillet, août 1835, par les vingt et un membres de la commission lyonnaise. 8°. 1835.

Memoir on the cholera of Marseilles.
[Lancet, London, 1834–35, II, pp. 29–32.]

uguio.

urrigat (A.) Relation de l'épidémie holérique qui a régné à Mauguio en septembre et octobre 1865. . . . 8°. *Montellier*, 1865.

zamet.

oazis (P.) Quelques réflexions sur épidémie cholérique qui a régné à Mamet dans le courant de l'année 1854. . *Castres*, 1855.

rville.

lson. Relation d'une épidémie de choéra, observée dans la commune de Merille, en 1873.

[Revue méd. de l'Est, 1874, I, pp. 384–389; 1 map; pp. 421–426, 456–463.]

ntargis.

uette. Recherches sur l'importation, la ransmission et la propagation du choléra en province par les nourrissons de Paris et sur les moyens propres à empêcher la transmission. (Observations recueillies dans l'arrondissement de Montargis, en 1854, 1865–66.) 8°. *Montargis*, 1867. L.

ntbeliard.

uffard *fils.* Mémoire sur l'épidémie de choléra et de suette qui a régné dans l'arrondissement de Montbéliard, depuis le mois d'août jusqu'à celui de novembre 1854. 8°. *Montbéliard* [*n.d.*]

ntbrehain.

uel (B.) Relation complète de l'épidémie cholérique de Montbrehain (Aisne). 8°. *Saint Quentin*, 1854. L.

selle (*Department of the*).

ussaint. Rapport sur l'épidémie cholérique qui a régné en 1866 dans le département de la Moselle. . . . 8°. *Metz*, 1867.

arin. Rapport sur le choléra de 1854 dans le département, lu et adopté dans la séance du 12 juin 1855. . . . 8°. *Metz*, 1855.

ncy.

atelain. Notice sur le choléra qui a régné dans la garnison de Nancy pendant le mois d'octobre 1855.

[Rec. de mém. de méd. . . . mil., 1856, XVIII, 2e s., pp. 213–222.]

Leuret. Choléra de Nancy.

[Gaz. méd. de Paris, 1832, III, p. 598.]

Simonin. Sur le choléra à Nancy.

[Bull. de l'Acad. nat. de méd., 1848–49, XIV, pp. 1133–1139.]

Nantes.

Aublanc. Résumé des observations faites pendant les épidémies de choléra qui ont régné à Nantes, en 1832 et 1834.

[Jour. Sect. de méd. soc. acad. dépt. Loire-Inf., 1834, X, pp. 150–152.]

Bally. Exploration scientifique de la ville de Nantes pendant l'épidémie cholérique.

[Gaz. des hôp., 1849, pp. 512–513.]

Bonamy (E.) Rapport sur l'épidémie de choléra-morbus asiatique, observée à Nantes et dans diverses parties du département de la Loire-Inférieure en 1849.

[Jour. Sect. de méd. soc. acad. dépt. Loire-Inf., 1850, XXVI, pp. 67–165.]

——— The same. 8°. *Nantes*, 1850. L.

Leray. Variété du choléra-morbus distingué dans les Indes par quelques auteurs anglais sous le nom de choléra spasmodica, observé à Nantes dans les mois de juillet, août et octobre 1824.

[Jour. Sect. de méd. soc. acad. du dépt. de la Loire-Inférieure, 1825, I, pp. 118–127.]

Priou. Réflexions sur le choléra-morbus de l'Asie, épidémique à Nantes, en 1832.

[Journ. Sect. de méd. soc. acad. dépt. Loire-Inf., 1833, IX, pp. 16–48; *also*, reprint in 8°, Nantes, 1833.]

Vaugiraud. Aperçu historique sur les malades atteints du choléra, traités à l'Hôtel-Dieu de Nantes, pendant les six mois d'avril, mai, juin, juillet, août et septembre 1832.

[Journ. Sect. de méd. soc. acad. dépt. Loire-Inf., 1832, VIII, pp. 130–156.]

Nanteuil.

Coussot (L.) Aperçu sur l'épidémie de choléra observée à Nanteuil (Charente), pendant les mois d'octobre, novembre et décembre de l'année 1855. 4°. *Paris*, 1856. L.

Narbonne.

Labadié. Lettre sur le choléra-morbus épidémique observé à Narbonne en 1854. 8°. *Narbonne*, 1854.

Py (P.) Note sur la maladie qui règne à Narbonne depuis la fin du mois d'août 1837, et qui a déjà présenté, en septem-

Py (P.)—continued.
bre, l'intercurrence de plusieurs cas de choléra asiatique.
[Gaz. méd. de Paris, 1837, v, pp. 648–649.]

Neuilly.

Destouches *et* **Godier.** Rapport sur la marche et les modifications qui le choléra a présentées à Neuilly, pendant l'épidémie.
[Gaz. des hôp., Paris, 1832, vi, p. 353.]

Cholera-morbus (Le) et l'hôpital temporaire de Neuilly fondé par le Roi pour le traitement des cholériques.
[Gaz. des hôp., 1832, vi, pp. 133–134, 353.]

Nîmes.

Deloche. Étude sur le choléra. Théorie sur la manière dont ce fléau distribue ses coups dans les localités qu'il ravage. Application de cette théorie à la mortalité cholérique due aux quatre épidémies que la ville de Nîmes a subies. . . . 8°. *Paris*, 1867.

Girard (F.) *et* **Fontaines** (C.) Rapport sur l'épidémie de choléra-morbus, qui a régné à Nîmes, pendant les mois d'août et de septembre 1835. . . . 4°. *Nîmes*, 1835.

Maxel (E.) Rapport sur le dernier choléra, lu à la Société de médecine de Nîmes, le 27 décembre 1865. . . . 12°. *Nîmes*, 1866.

Tribes (E.) Rapport sur l'épidémie de choléra-morbus qui a régné à Nîmes pendant les mois de septembre, d'octobre et de novembre 1849. . . . 4°. *Nîmes*, 1850.

——— Rapport historique et statistique sur les épidémies de choléra-morbus, qui ont régné à Nîmes pendant les années de 1854 et de 1865. . . . 4°. *Nîmes*, 1866.

Nogent-le-Rotrou.

Brochard. Du mode de propagation du choléra et de la nature contagieuse de cette maladie. Relation médicale de l'épidémie de choléra qui a régné pendant l'année 1849 à Nogent-le-Rotrou. . . . . Mémoire présenté à l'Académie . . . de méd., 1850. 8°. *Paris*, 1851.

Nord (*Department of*).

Legros (F.) Sur le choléra-morbus du département du Nord.
[Gaz. des hôp., 1832, vi, pp. 486–487.]

Norrois.

Relation d'un cas de choléra observé à Norrois; rapport lu à la commission sanitaire, le 23 avril dernier, par P. D. M. 8°. *Vitry-le-François*, 1832.

Paris.

Achard (F.) * Coup d'œil rétrospectif sur le choléra-morbus observé à l'hôtel-Dieu de Paris en 1832, propositions de médecine et de chirurgie. 4°. *Paris*, 1835. L.

Aclocque (*Mme.* E.) Nous n'aurons point le choléra! ! 12°. *Paris*, 1848.

Aran (F. A.) Note sur l'épidémie actuelle de choléra-morbus et sur son traitement.
[L'Union méd., 1853, vii, pp. 602–603, 609–611.]

Barth (J. B.) Du choléra-morbus épidémique observé à la Salpêtrière pendant les mois de mars et avril 1849.
[Arch. gén. de méd., Paris, 1849, xxi, 4e s., pp 1–43.]

——— Histoire médicale du choléra-morbus épidémique observé à l'hospice de la Salpêtrière. 8°. *Paris*, 1849.
[Reprint of the preceding.]

Berthelot (J.) Observations de médecine pratique sur le choléra-morbus de Paris en 1832 et 1833. 8°. *Paris*, 1835.

Besnier (E.) Terminaison de l'épidémie cholérique. Statistique des décès cholériques à Paris (ville et hôpitaux), pendant les mois de septembre, octobre et novembre 1873.
[L'Union méd., 1874, xxviii, pp. 5–7.]

Blondel. Rapport sur les épidémies cholériques de 1832 et 1849 dans les hôpitaux et hospices de Paris.
[Revue méd.-chirurg. de Paris, 1850, viii, pp. 321–329; *also*, reprint in 4°, Paris, 1850.]

Bompard. Sur le choléra régnant.
[Gaz. des hôp., 1832, vi, pp. 166–168.]

Bordier (A.) Épidémie cholérique de 1866, à l'hôpital Beaujon.
[Archiv. gén. de méd., 1867, i, pp. 176–193.]

Bouillaud (J.) Choléra-morbus de Paris.
[Jour. univ. et hebd. de méd. et de chir. prat. 1832, vii, pp. 5–8, 29–31, 79–81, 85–125.]

——— Traité pratique, théorique et statistique du choléra-morbus de Paris, appuyé sur un grand nombre d'observations recueillies à l'hôpital de La Pitié. 8°. *Paris*, 1832. L.

Boulay de la Meurthe (H.) Histoire du choléra morbus dans le quartier du Luxembourg, ou précis des travaux de la commission sanitaire et du bureau de

Boulay de la Meurthe (H.)—continued. secours de ce quartier; suivi de documents statistiques sur les ravages que le choléra y a exercés. 8°. *Paris*, 1832. L.

Bourneville. Le choléra à l'hôpital Cochin (1865). Étude clinique. 8°. *Paris*, 1873. L.

Bouvier. Mémoire sur la mortalité comparée des quartiers de Paris dans l'épidémie de choléra de 1849.
[Mém. Acad. imp. de méd., 1853, XVII, pp. 335–385; 2 maps.]

Bricheteau. Note sur la récrudescence de l'épidémie de choléra-morbus.
[Gaz. des hôp., 1832, VI, p. 281.]

Bricheteau (F.) Sur l'épidémie de choléra.
[Bull. gén. de thérap. méd. et chir., 1865, LXIX, pp. 289–293.]

Brismontier (G. L.) Moyens efficaces de guérison du choléra-morbus sans médecin. Instruction populaire . . . accompagnée d'un tableau de Paris pendant les plus grands sévices de le maladie, et terminée par un aperçu statistique et exact du nombre des décès à Paris, etc. 12°. *Paris*, 1832.

Brouardel. Comparaison entre les épidémies du choléra de 1853–54, 1865–66 et 1873.
[Bull. et mém. Soc. méd. des hôp., 1873, X, 2e s., p. 287.]

Burkart (E.) * Die Cholera in Paris, ihr Entstehen, ihre Verbreitung, Ursachen und Behandlung. 8°. *Konstanz*, 1835. L.

Caffe. Notice statistique pour servir à l'histoire du choléra-morbus de Paris.
[Jour. univ. et hebd. de méd. et de chir. prat., 1832, VII, pp. 157–164, 205–217, 317–334.]

Caffe (P.) Considérations sur l'histoire médicale et statistique du choléra-morbus de Paris. 8°. *Paris*, 1832. L.

Candy. Rapport sur le choléra-morbus de Paris, présenté à M. le maire et au conseil municipal de Lyon, au nom d'une commission médicale. . . . Épidémie de 1849. 8°. *Lyon*, 1849.

Canstatt (C., *jun.*) Die Cholera in Paris. Auszüge aus Briefen über Entstehung, Verlauf und Behandlung der Cholera in Paris. 8°. *Regensburg*, 1832. L.

Capello (A.) *e* **Lupi** (A.) Storia medica del cholèra indiano osservato a Parigi anno 1832. 8°. *Roma*, 1833. L.

Cartaux *et* **Masse.** Compte rendu de l'ambulance établie dans les bâtiments

Cartaux *et* **Masse**—continued. de l'ancien trésor, et destinée au traitement des cholériques.
[Jour. de méd. et de chir. prat., 1832, III, pp. 177–197.]

Cauvière, Rey *et* **Rousset.** Rapport de la commission médicale envoyée à Paris par l'administration municipale de Marseille pour étudier le choléra-morbus. . . . 8°. *Marseille*, 1832.

Chaudé. Observations sur l'épidémie de choléra-morbus dans le quartier de la Sorbonne (XI^e^ arrondissement).
[Jour. univ. et hebd. de méd. et de chir. prat., 1832, VIII, pp. 5–16.]

Dauvergne (A.) Recueil d'observations sur le choléra-morbus, faites à l'hôpital St. Louis de Paris, enrichi de quelques documents précieux puisés dans la clinique de M. le baron Alibert. 8°. *Marseille*, 1832.

Dechambre (A.) Coup d'œil sur la constitution médicale et l'épidémie de choléra à Paris.
[Gaz. hebd. de méd. et de chir., 1853–54, I, pp. 917–920, 953–956.]

——— Quelques remarques sur certaines manifestations de l'épidémie actuelle.
[Gaz. hebd. de méd. et de chir., 1853–54, I, pp. 501–504.]

Decori (C.) * Relation de l'épidémie de choléra de 1865, à l'hôpital St. Antoine. 4°. *Paris*, 1866. L.
[*Also*, reprint in 8°, Paris, 1866.]

Després (H.) Relevé statistique de l'hôpital temporaire de la Reservé, durant la première invasion du choléra.
[Ann. de la méd. phys., 1832, XXI, pp. 611–612.]

[Deville (J. J.)] Compte-rendu des travaux de la commission sanitaire du quartier de l'Hôtel-de-Ville, depuis son institution jusqu'à l'invasion de choléra-morbus, et depuis cette époque jusqu'au 30 septembre 1832.
[Trans. méd., Jour. de méd. prat., Paris, 1832, X, pp. 36–74; *also*, reprint in 8°, Paris, 1832.]

——— Histoire médicale du choléra-morbus dans le quartier de l'Hôtel-de-Ville, suivie d'un aperçu de cette même maladie observée au Bengale et comparée à l'épidémie de Paris.
[Trans. méd., Jour. de méd. prat., Paris, 1833, XIV, pp. 3–60, 141–166; *also*, reprint in 8°, Paris, 1833.]

Dubost (G.) * Essai sur le choléra-morbus épidémique observé à Paris en 1832. 4°. *Paris*, 1832. L.

Dubourg. Note sur les cholériques traités à l'hôpital de la charité depuis le commencement de l'épidémie.
[Journ. univ. et hebd. de méd. et de chir. prat., 1832, VII, pp. 15–17, 39–41.]

Duchesne (E. A.) Histoire statistique du choléra-morbus dans le XI^me^ arrondissement de Paris pendant l'épidémie de 1849. 8°. *Paris*, 1851. L.

Dudon. Recherches sur le siége, les causes et le traitement du choléra-morbus épidémique, observé à Paris en avril et mai 1832. 8°. *Paris*, 1832. L.

Dupont (J. B.) Tableau synoptique du choléra asiatique observé à Paris et dans les départements du Nord et du Pas-de-Calais. fol. *Lille* [1832].

Edwards. [Observations on the cholera in Paris.]
[St. Louis Med. & Surg. Jour., 1850, VIII, pp. 25–30.]

Ély (C.) Tableaux statistiques de l'épidémie cholérique à Paris, pendant les mois de septembre, octobre, novembre et décembre 1865.
[Gaz. hebd. de méd. et de chir., 1672, 2e s., IX, pp. 817–820.]

Euvrard (A. P. M.) *Du choléra morbus épidémique observé à Paris et dans le département de l'Oise en 1849; à Gray et aux environs (Haute-Saone), à Montbéliard et aux environs (Doubs) en 1854. 4°. *Strasbourg*, 1860. L.

Fabre (A.) Du choléra-morbus de Paris, ou guide des praticiens dans la connaissance et le traitement de cette maladie: contenant l'histoire abrégée de l'épidémie, la symptomatologie, l'exposé des lésions cadavériques, et les diverses méthodes de traitement adoptées par les médecins des hôpitaux de Paris, et les principaux médecins français et étrangers. 12°. *Paris*, 1832. L.

Filhos. Observations et relevé statistique sur les malades atteintes du choléra dans le service de M. Martin-Solon, hôpital Beaujon.
[Gaz. des hôp., 1832, VI, pp. 341–342.]

Fleury *et* Peghoux. Rapport sur le choléra-morbus de Paris, fait à la commission sanitaire. . . . 8°. *Clermont-Ferrand*, 1832.

Foy (F.) Histoire médicale de choléra-[illegible]us de Paris, et des moyens théra-[illegible]ics et hygiéniques sur cette épi-[illegible] appuyés sur des observations

Foy (F.)—continued. recueillies à Paris, en Pologne et en Angleterre. 8°. *Paris*, 1832.

Franck (C.) Bulletin du choléra.
[La France méd. et pharm., Paris, 1854, [illegible] 117–118, 135, 150.]

Fuster. Coup d'œil sur la constitution médicale qui a précédé et accompagné l'invasion du choléra-morbus à Paris.
[Bull. gén. de thér. méd. et chir., 1[illegible] [illegible] 229–235.]

Gasc (J. C.) Compte-rendu des cholériques observés à l'hôpital militaire Val-de-Grâce . . . pendant le mois d'avril dernier et jusqu'à la fin de mai.
[Ann. de la méd. phys., 1832, XII, pp. [illegible] *also in* Trans. méd., Jour. de méd. prat., 1832, VIII, pp. 309–312.]

Gendrin (A. N.) Mémoire monographique sur le choléra-morbus de l'Asie, épidémique à Paris.
[Trans. méd., Jour. de méd. prat., Paris, VIII, pp. 73–155, 333–436.]

——— Monographie du choléra-morbus épidémique de Paris, rédigée spécialement sur les observations cliniques de l'auteur à l'Hôtel-Dieu de Paris. *Paris*, 1832. L.

Gibert. Note sur l'épidémie cholérique de 1849 observée à l'Hôpital Saint-Louis.
[Revue méd., Paris, 1849, I, pp. 481–495.]

Gouraud (H.) Du choléra morbus et de la médecine à Paris.
[Revue méd. franç. et étrang., 1832, II, pp. 289–318.]

——— Note sur le choléra observé à la maison d'accouchement.
[Bull. gén. de thérap. méd. et chir., 1832, I, pp. 420–424.]

——— Traitement du choléra-morbus asiatique à l'hôpital militaire de la rue Blanche.
[Bull. gén. de thérap. méd. et chir., 1832, II, pp. 113–119.]

Guérard (A.) Sur l'épidémie du choléra qui sévit en ce moment à Paris.
[Ann. d'hyg. publ., 1854, I, 2e s., pp. 79–[illegible]

Guérin. Le choléra-morbus.—Le [illegible] de l'administration.—La réunion des cholériques des hôpitaux dans des salles spéciales.
[Gaz. méd. de Paris, 1866, XXI, pp. 497–[illegible]

Guichard (J.) Relation statistique et [illegible] thologique du choléra-morbus dans le quartier des Invalides. [illegible] 1832. L.

Guyot (J.) Une visite à l'*Hôtel-Dieu* et à l'hôpital Lariboisière, résultats du traitement du choléra.
[L'Union méd., 1865, XXVIII, 2e s., pp. [illegible]

nes. A review of the statistics of aths in the hospitals during the months October, November, and December.
[Louis Med. & Surg. Jour., 1866, III, pp. 405–10.]

ıel (L.-J.) *Symptomatologie du cho-a épidémique observé à Paris, en 1849, l'hôpital militaire du Val-de-Grâce. *Paris*, 1851. L.

ıson (J., *jr.*) Cases of cholera col-:ted at Paris in the month of April, :32, in the wards of MM. Andral and)uis, at the hospital La Pitié. 8°. *Bos-*, 1832. L.

ach (A.) Le choléra au Val-de-Grâce 1:73; étudié surtout au point de vue) l'anatomie pathologique.
[Recueil des mém. de méd., de chirurg. et de pharm. mil., 1874, XXX, pp. 193–221.]

ol (J. A.) Iets over de aziatische Cho-:ra te Parijs. 8°. *Amsterdam*, 1832. L.

berge (L.) Du choléra-morbus qui :gne épidémiquement à Paris.
[Jour. univ. et hebd. de méd. et de chir. prat., 1832, VII, pp. 31–39, 125–130.]

ngronne (É.-A.) *Du choléra épidémi-ue de 1865, observé à l'hôpital Laribois-ière. 4°. *Paris*, 1866. L.

sèque (C.) Le choléra à Paris en 1849.
Archiv. gén. de méd., Paris, 1849, I, pp. 493–505; II, pp. 123–123, 372–374; III, pp. 123–123, 501–502.]

grand (A.) Choléra-morbus. Histoire lu malade de la rue des Lombards. 8°. *Paris*, 1832. L.

) Masson (P.) *Propositions sur le cho-léra-morbus épidémique observé à Pa-ris, au printemps de 1832. 4°. *Paris*, 1832. L.

rebouillet (A.) *Considérations pra-tiques sur le choléra-morbus, observé à Paris et dans le département de la Meuse pendant l'année 1832. 4°. *Strasbourg*, 1832. L.

lgnerolles. Épidémie cholérique à l'hô-pital Saint-Louis.
[Gaz. des hôp., 1866, pp. 393–394.]

ynch (J. R.) Sketch of the origin, pro-gress, cause, symptoms, treatment, and post-mortem appearances, of the cholera in Paris.
[Lancet, 1831–32, II, pp. 268–270.]

lagne (R.) *Essai sur le choléra-morbus observé à Paris, 4°. *Paris*, 1832. L.

Malgaigne. Le choléra à Paris en 1849.
[Revue méd.-chirurg. de Paris, 1849, V, pp. 193–200.]

Marrotte. Compte rendu des cholériques entrés dans la salle Saint-Benjamin (service spécial), à l'hôpital de La Pitié, du 17 juillet au 21 août 1866 exclusive-ment.
[Bull. et mém. soc. méd. des hôp. de Paris, 1867, III, pp. 208–221.]

Meli. Risultamenti degli studii fatti a Parigi sul cholera-morbus per ordine di sua Santita Papa Gregorio XVI, 1832. 8°. *Roma*, 1833. L.

Mesnet (E.) Choléra, 1865, hôpital St.-Antoine (service des hommes).
[Archiv. gén. de méd., 1866, I, pp. 129–151, 292–302.]

Métral (A.) Description naturelle, mo-rale et politique du choléra-morbus à Paris. 12°. *Paris*, 1833. L.

Mons (C. J. van) *et* Maroq (P. A.) Rap-port sur le choléra-morbus, adressé au conseil supérieur de santé de la Belgi-que. 8°. *Bruxelles*, 1832. L.

Montault (J. *J.* H.) Choléra-morbus de Paris.
[Jour. univ. et hebd. de méd. et de chir. prat., 1832, VII, pp. 53–67.]

——— Recherches pour servir à l'histoire du choléra-morbus observé à l'Hôtel-Dieu de Paris.
[*Ibid.*, pp. 238–247.]

Moreau (F. M.) Histoire statistique du choléra-morbus dans le quartier du fau-bourg Saint-Denis . . . pendant les mois d'avril, mai, juin, juillet, août et septem-bre. 8°. *Paris*, 1833.

——— Histoire statistique du choléra asia-tique de 1849 dans le V^e^ arrondissement municipal de Paris. 8°. *Paris*, 1850. L.

Moulin (E.) Hygiène et traitement du choléra-morbus. Coup d'œil historique sur l'épidémie de Paris de 1832. 8°. *Pa-ris*, 1832. L.

Moure. Réflexions sur le mode de traite-ment du choléra du Val-de-Grâce et des Invalides.
[Jour. univ. et hebd. de méd. et de chir. prat., 1832, VII, pp. 181–188.]

Mousset. Choléra asiatique observé à Paris en septembre 1847.
[Gaz. des hôp., 1847, p. 550.]

Panvini (P.) Osservazioni cliniche sul cholera morbus fatte all'Hôtel-Dieu di Parigi. 8°. *Napoli*, 1834. L.

Parrot. Note sur les cas de choléra ob-servés à l'hôpital de La Charité.
[Gaz. hebd. de méd. et de chirurg., 1865, II, 2e s., pp. 775–779.]

Patrix (E. G.) Lettres sur le choléra-morbus, observé à Paris, au faubourg Saint-Antoine. Lettres 1–10. 8°. *Paris*, 1832. L.

Pennock (C. W.) *and* **Gerhard** (W. W.) Observations on the cholera of Paris.
[Am. Jour. of the Med. Sci., 1832, x, pp. 319–390.]

——— The same. 8°. *Philadelphia*, 1832. L.

Perdrix. Rapport sur le choléra-morbus observé dans le 4e arrondissement de Paris, adressé à M. le comte de Bondy. 8°. *Paris*, 1832.

Petit (C. F.) Rapport sur le choléra-morbus observé à Paris. 8°. *Avallon*, 1832.

Petit-Cuenot (C.-A.) * Dissertation sur le choléra-morbus asiatique qui a régné à Paris en 1832. 4°. *Paris*, 1832. L.

Pierson (L. F.) Quelques réflexions sur le choléra observé à Paris en mars et avril 1832. 8°. *Nevers*, 1832.

Piorry. Note sur les cas d'épidémie de choléra qui a régné dans les salles Saint-Charles et Sainte-Anne à La Charité en 1854.
[Gaz. des hôp., 1854, pp. 179, 182–183; *also, in* Bull. de l'Acad. imp. de méd, Paris, 1853–54, xix, pp. 537–551.]

Piorry (P. A.) Mémoire sur l'épidémie de choléra observée à Paris en 1832.
[Jour. univ. et hebd. de méd. et de chir. prat., 1832, ix, pp. 145–160, 177–204.]

——— The same. 8°. [*n. p., n. d.*] L.

Prevost (L. C.) Tableau graphique, états, notice et observations concernant les ravages occasionnés par le choléra-morbus dans le huitième arrondissement de Paris, pendant la durée de cette épidémie en 1832. 4°. *Paris*, 1833. L.

Récamier. Choléra-morbus à Paris. Premier supplément aux recherches sur le traitement du choléra.
[Rev. méd. franç. et étrang., 1832, II, pp. 137–158.]

Ripault (H.) Quelques réflexions sur le choléra-morbus observé à l'Hôtel-Dieu de Paris dans le service médical de M. Bally. 8°. *Paris*, 1832. L.

Robinson (C.) Considérations sur le choléra-morbus observé à Paris et à Crécy, arrondissement de Meaux. 8°. *Paris*, 1833.

Roche (L. C.) Mémoire sur le choléra-morbus épidémique observé à Paris.
[Jour. univ. et hebd. de méd. et de chir. prat., 1831, vii, pp. 437–464; *also*, reprint in 8°, Paris, 1832.]

Rullier. Remarques sur le choléra-morbus épidémique de Paris, pour servir à l'histoire de cette maladie.
[Bull. gén. de thérap. méd., 1832, III, pp. 80–89.]

Sales-Girons. Du prétendu retour de l'épidémie de choléra à Paris, et de ce qu'il faut penser des cas qui ont été signalés en ville et dans les hôpitaux.
[Rev. méd., Paris, 1854, I, pp. 321–357.]

——— Les épidémistes et les endémistes, ou les deux interprétations de la dernière recrudescence du choléra à Paris.
[*Ibid.*, pp. 513–521.]

——— Le choléra à Paris; ses chiffres, et son traitement par la diète et par la thérapeutique respiratoire.
[Rev. méd., Paris, 1865, II, pp. 449–459, 513–519.]

Salgues. Deux leçons du professeur Broussais sur le choléra-morbus, faites au Val-de-Grâce les 18 et 19 avril 1832: suivies d'une notice hygiénique sur les moyens préservatifs de ce fléau. 8°. *Dijon*, 1832.

Smith (A.) The cholera spasmodica, as observed in Paris 1832. 8°. *New York*, 1832.

Souza Vaz (F.-d'A.) Relação historica, statistica e medica da cholera-morbus em Paris, precedida da topographia desta capital. . . . 8°. *Paris*, 1833.

Stouffiet (F.-L.) * Le choléra à l'hôpital Lariboisière en 1865, du 17 septembre 1865 au 9 janvier 1866. 4°. *Paris*, 1866. L.

Tacheron [C. F.] Statistique médicale de la mortalité du choléra-morbus dans le XIe arrondissement de Paris, pendant les mois d'avril, mai, juin, juillet et août 1852; ou documents et observations hygiéniques devant servir à l'étude de cette épidémie.
[Gaz. des hôp., Paris, 1832, VI, pp. 389–394.]

——— The same. 8°. *Paris*, 1832. L.

Thomson (A.) Blue, or Asiatic cholera. Cases taken at La Pitié.
[London Med. & Surg. Jour., 1833, II, pp. 489–495.]

Treille. Conversations sur le choléra-morbus observé à Paris en 1831 et 1832. 8°. *Paris*, 1832.

Villermé (L. R.) Notes sur les ravages du choléra-morbus dans les maisons garnies de Paris, depuis le 29 mars jusqu'au 1er août 1832, et sur les causes qui paraissent avoir favorisé le développement

ermé (L. R.)—continued.
la maladie dans un grand nombre maisons.
...v. d'hyg. pub. et de méd. lég., Paris, 1834, XI, pp. 385–409.]

sin [J. C.] Mémoire sur le choléra-orbus observé à l'hôpital Saint-Louis.
...R. univ. et hebd. de mé l. et de chir. prat., 1832, VII, pp. 349–363, 381–403; VIII, pp. 33–48.]

— The same. 8°. *Paris*, 1832. L.

hu. Remarques sur le choléra épidémique qui a sévi à Paris en 1849.
[L'UNION méd., Paris, 1849, III, pp. 302–303.]

section de forme cholérique grave observée à la clinique de ville.
[GAZ. des hôp., 1831, V, pp. 449–450.]

oléra (Le) à Paris en 1847; sa marche actuelle en Europe, ses préservatifs et ses remèdes infaillibles. 12°. *Paris*, 847.

oléra (Le) asiatique n'a jamais existé dans Paris, ou un mot sur l'épidémie régnante; par F. J. D. . . . 8°. *Paris*, 1849.

oléra (Le) aux portes de Paris.
[GAZ. des hôp., Paris, 1851, p. 304.]

holera in Paris.]
[LONDON Med. & Surg. Jour., 1832, pp. 322–323, 354–355, 418–419.—BOSTON Med. & Surg. Jour., 1832, VI, pp. 279–284, 302–306.—PROV. Med. & Surg. Jour., 1849, pp. 360–361.—ARCH. gén. de méd., Paris, 1854, I, pp. 106–110; II, pp. 243–246; 1855, II, pp. 504–505; *also, in* GAZ. des hôp., Paris, 1854, pp. 437–438.—COMPTES rend. hebd. des séances de l'Acad. des sci., Paris, 1849, XX, pp. 663–684.—L'UNION méd., Paris, 1849, III, pp. 551–552.—GAZ. méd. de Paris, 1849, IV, 3e s., pp. 195–196; *also, in* REV. méd.-chir. de Paris, 1849, V, pp. 193–200.—JOUR. d. prakt. Heilk., C. W. Hufeland und E. Osann, 1832, LXXIV, pp. 101–116; LXXV, pp. 90–110.]

holéra-morbus (Le) à l'hospice de Bicêtre.
[GAZ. des hôp., Paris, 1832, VI, pp. 113–114, 129–130.]

holéra-morbus (Le) observé à la clinique de ville.
[GAZ. des hôp., Paris, 1831, V, pp. 465–467.]

holéra-morbus. Progrès de l'épidémie de Paris.
[BULL. gén. de thér. méd. et chir., Paris, 1832, II, pp. 209–213.]

ompte rendu de l'ambulance établie dans les bâtiments de l'ancien trésor . . . et destinée au traitement des cholériques. 8°. *Paris*, 1832.

Compte rendu des travaux de la commission sanitaire du quartier de l'hôtel de ville, depuis son institution jusqu'à l'invasion du choléra-morbus, et depuis cette époque jusqu'au 30 septembre 1832, présenté à la commission centrale de salubrité, par la commission sanitaire dudit quartier, composée de MM. Loiseleur, Deslongchamps, Fautrel, ... 8°. *Paris*, 1832.

Considérations pratiques sur le choléra-morbus de Paris, son invasion, sa marche, ses symptômes, [etc.]
[JOUR. de méd. et de chir. prat., 1832, III, pp. 129–149.]

Épidémie (L') de choléra à l'hôpital Saint-Antoine, en novembre et décembre, 1865.
[GAZ. des hôp., 1866, pp. 137.]

Épidémie de choléra; sa décroissance à Paris et dans les départements.
[JOUR. de méd. et de chir. prat., 1873, XLIV, 3e s. pp. 481–485.]

Examen historique de l'épidémie de choléra-morbus qui s'est déclarée à Paris; exposé des traitements divers employés. . . . 8°. *Paris*, 1832.

Faits (Des) de choléra attribués à la contagion. Épidémie de 1865 à l'hôpital Lariboisière.
[GAZ. des hôp., 1866, pp. 385–387.]

Maladies régnantes; rapport de la commission. [Choléra.]
[BULL. et mém. Soc. méd. des hôp. de Paris, 1867, III, pp. 239, 247, 267, 307; 1868, IV, pp. 26, 93, 131, 151, 169, 272.]

Mémoire sur les causes occasionnelles qui ont spécialement agi dans l'épidémie de choléra observée à Paris en 1832, et principalement à l'hospice de la Saltpêtrière. 8°. [*n. p., n. d.*] L.

Note sur la recrudescence du choléra-morbus à Paris dans le mois de juillet.
[BULL. gén. de thérap. méd. et chir., 1832, III, pp. 54–58.]

Note sur la seconde invasion du choléra-morbus de Paris, sur sa marche, sa prétendue contagion, et quelques médications proposées.
[JOUR. de méd. et de chir. prat., 1832, III, pp. 241–245.]

Préfecture du département de la Seine. Tableaux statistiques de l'épidémie cholérique à Paris pendant les mois de septembre, octobre, novembre et décembre 1865. 4°. *Paris*, 1872.

Progress of the cholera in Paris.
[LONDON Med. Gaz., 1832, X, pp. 56–59.]

Quelques (Des) cas de choléra que l'on observe en ce moment dans les hôpitaux de Paris.
[GAZ. des hôp., Paris, 1853, pp. 555–556, 559–560.]

Rapport sur la marche et les effets du choléra-morbus dans Paris et les communes rurales du département de la Seine, par la commission nommée par MM. les préfets de la Seine et de police. Année, 1832. 4°. *Paris*, 1834. L.

Rapport sur le choléra-morbus de Paris, présenté à M. le maire et au conseil municipal de Lyon, par MM. Trolliet, Polinière et Bottex, formant la commission envoyée à Paris par la ville de Lyon. 8°. *Lyon*, 1832. L.

Rapport sur les cholériques admis à l'hôpital des enfans, pendant le mois d'avril, adressé au conseil général d'administration des hôpitaux. (Extrait de la Revue médicale, No. de mai, 1832.) 8°. [*n. p.*] L.

Réapparition du choléra-morbus à Paris.

[Rev. méd. franç. et étrang., 1833, IV, pp. 146–151.]

Relation médicale de la commission envoyée à Paris par la chambre de commerce et par l'intendance sanitaire de Marseille pour observer le choléra-morbus, par MM. les docteurs Ducros, Giraud, Martin et P. M. Roux. 8°. *Marseille*, 1832. L.

Report of the cholera in Paris. Published by authority of the French government. Translated from the original and printed by recommendation of the Board of Health and the Academy of Medicine of the city of New York. 8°. *New York*, 1849. L.

Revue clinique du choléra.

[Gaz. méd. de Paris, 1849, IV, 3e s., pp. 202–208, 221–227, 240–247, 258–269, 282–288, 301–307, 340–348.]

Salpêtrière (La.) Bicêtre et l'épidémie régnante. . . . 8°. *Paris*, 1849.

Statistics of the cholera in Paris.

[Lond. Med. and Surg. Jour, 1835, VI, pp. 408–410.

Statistique du choléra. Sur le movement général de l'épidémie dans les hôpitaux de Paris, depuis le 26 mars jusqu'au 30 avril inclusivement.

[Gaz. méd. de Paris, 1832, III, pp. 297–299.]

Sur le choléra-morbus qui règne actuellement à Paris, comparé au choléra épidémique de l'année 1832.

[Gaz. méd. de Paris, 1833, I, pp. 697–700.]

Sur l'invasion du choléra-morbus à Paris.

[Gaz méd. de Paris, 1832, III, pp. 137–138.]

Pas.

Bidart (A.) Observations pratiques . . . le choléra-morbus épidémique . . . a régné en 1832 à Pas. . . . [*n. d.*]

Pyrénées, Basses.

Cazaux (J. B.) Notice sur le choléra . . . Basses-Pyrénées en 1855. 8°. *Pau.*

Épidémie cholérique du département . . . Basses-Pyrénées.

[Gaz. des hôp., 1855, p. 479.]

Pyrénées-Orientales.

Bocamy (J.) Rapport sur le choléra démique qui a sévi dans les Pyré . . . Orientales pendant les mois de j . . . août, septembre, octobre et nove . . . 1854; précédé de la relation somma . . . des épidémies du choléra qui ont . . . dans le département des Pyrénées-Or entales en 1835 et 1837. 8°. *Perpign.* 1856.

Puy-de-Dome.

Nivet (V.) *et* **Aguilhon** (H.) Notice . . . l'épidémie de choléra-morbus qui a . . . vagé le département du Puy-de-Dôme en 1849, adressée à M. le ministre . . . l'agriculture et du commerce. 8°. *Paris*, 1851.

Revel.

Piccioni (A.) Mémoire relatif à l'épi . . . mie cholérique observée dans le can . . . de Revel . . . . . pendant les mois de septembre et octobre 1854. 4°. *Paris*, 1854.

Riom.

Aguilhon (J. J. H.) Considérations . . . la nature du choléra observé en 1 . . . dans l'arrondissement de Riom (Puy-de-Dome), suivi d'une relation d'une . . . mie dysenterique qui a régné dans la commune de Teilhede. 8°. *Clermont* 1850.

Rive-de-Gier.

Kosciakiewicz. Mémoire sur l'épi . . . du choléra-morbus asiatique qui a . . . en 1854 dans le canton et la . . . Rive-de-Gier. 8°. *Paris*, 1855.

Rochefort (*Charante-Inférieure*).

Laurencin. Lettre sur le choléra-m . . . de Rochefort.

[Trans. méd., Jour. de méd. prat., 1832, I, pp. 141–146.]

efèvre (A.) Recherches sur la marche et les effets du choléra asiatique à Rochefort, pendant les différentes épidémies dont cette ville a été le théâtre en 1832, 1834 et particulièrement en 1849. Mémoire remis au conseil d'hygiène de l'arrondissement. 8°. *Rochefort*, 1850.

Rouen.

Iellis. Souvenirs du choléra à Rouen en 1832. 8°. *Paris et Rouen*, 1833.

eudet. Note sur le choléra observé à l'Hôtel-Dieu de Rouen dans la division de clinique médicale.
[Bull. de l'Acad. imp. de méd., 1866-67, xxxii, pp. 73-77.]

—— Le choléra à Rouen en 1832, 1849, 1854, 1866 et 1873.
[L'Union méd., 1874, xxviii, pp. 795-796.]

Quentin (A.) Étude sur le choléra, observé à l'Hôtel-Dieu de Rouen en 1865-1866. 4°. *Paris*, 1867. L.

Saint-Bonnet-de-Mûre.

Prestier (L.) Choléra-morbus épidémique de St.-Bonnet-de-Mûre.
[Gaz. méd. de Lyon, 1855, vii, pp. 385-389.]

—— Note sur l'épidémie cholérique qui a régné à Saint-Bonnet-de-Mûre (Isère) en septembre 1855. 8°. *Lyon* [*n. d.*]

Saint-Brevin.

Drouet. Observations faites en 1826 à Saint-Brévin . . . sur le choléra-morbus. 8°. *Le Mans*, 1832.

Sainte-Menehould.

Normand (C.) Sur le choléra-morbus de Sainte-Menehould (Marne).
[Gaz. méd. de Paris, 1833, i, pp. 137-138.]

Saint-Julien-du-Sault.

Hatin (J.) Relation historique sur le choléra-morbus épidémique qui a ravagé la ville de Saint-Julien-du-Sault (Yonne) en mai et juin 1832; précédée de la topographie médicale du pays. 8°. *Paris*, 1832.

Saint-Laurent-d'Aizouze.

Palot (R.) Observations on the choleraic epidemic that prevailed during 1854 at St. Laurent d'Aizouze, and its environs. [Translated from the French and communicated to the Epidemiological Society by W. Campa.]
[Med. Times & Gaz., London, 1856, xii, n. s., pp. 172-173.]

Saint-Pierre-aux-Bois.

Mistler. Rapports sur le choléra-morbus qui règne épidémiquement à Saint-Pierre-aux-Bois, canton de Villé.
[Gaz. méd. de Strasbourg, 1849, ix, pp. 245-248.]

Saint-Rémy-en-Bouzemont.

Seure. Note sur le choléra-morbus de la commune de Saint-Rémy-en-Bouzemont (Marne).
[Gaz. méd. de Paris, 1832, iii, pp. 636-637.]

Sarthe (*Department of*).

Etoc-Demazy (F.) Du choléra-morbus et de ce qu'on a fait dans . . . . la Sarthe pour se préserver de cette maladie. 8°. *Le Mans*, 1833.

Savoy.

Rapport de la Société médicale de Chambéry pour résumer l'histoire de choléra en Savoie en 1854. 8°. *Chambéry*, 1858.

Seine (*Department of the*).

Duchesne. Rapport au conseil d'hygiène du département de la Seine, sur le choléra de 1853-1854. 1864.

Seine-Inférieure.

Vingtrinier. De l'état sanitaire du département de la Seine-Inférieure en 1866, et particulièrement de l'épidémie du choléra. Rapport présenté à M. le préfet . . . 8°. *Rouen*, 1867.

Senlis.

Dubois. Note sur le mode d'invasion et la marche du choléra-morbus dans quelques communes de l'arrondissement de Senlis.
[Revue méd., Paris, 1832, iii, pp. 29-39.]

Sèvres.

Lesage. Le choléra-morbus de Sèvres.
[Gaz. des hôp., 1832, vi, pp. 126-127, 177, 178.]

Soissons.

Godelle. Notes sur le choléra qui a régné dans l'arrondissement de Soissons pendant le printemps et l'été de 1832.
[Revue méd., Paris, 1832, iv, pp 337-370.]

Toulon.

Ackerman (P.) Mémoire et observations sur le choléra observé à l'hôpital de Saint-Mandrier, de Toulon, du 23 juin au 25 août 1835. . . . 2e ed. 8°. *Paris*, 1843.
[1st ed. appeared in the "Archives médicales de Strasbourg."]

Dominique (A.) Étude historique et statistique sur le choléra de 1865 à Toulon, à la Seyne, et à Solliès-Pont. . . . 8°. *Toulon* [*n. d.*]

Haspel (A.) Lettre sur la marche du choléra à Toulon.
[Gaz. méd. de Paris, 1849, IV, pp. 753–759.]

Lauvergne (H.) Histoire du choléra de 1854, dans l'hôpital principal de la marine de Toulon.
[L'Union méd., 1855, IX, pp. 230–231, 234–235, 250–251, 263–263.]

Layet. Aperçu historique et médical sur le choléra-morbus à Toulon. 8°. *Toulon*, 1836.

Martinenq (L. L. J. F.) Choléra de Toulon. Appréciation des causes qui le rendirent si terrible, et moyens d'en atténuer les funestes effets en cas de réapparition. 8°. *Toulon et Paris*, 1848. L.

——— Additions au choléra de Toulon de 1835, qui a été imprimé en entier dans les bulletins de l'académie en août 1848. 8°. *Grasse*, 1865. L.

——— Supplément au choléra de Toulon de 1835. À propos de l'épidémie de Marseille de 1865. 8°. *Grasse*, 1865. L.

——— Appendice au choléra de Toulon de 1835. À propos de l'épidémie de Marseille de 1865. 8°. *Grasse*, 1866. L.

Merlin (L.-B.) *Considérations sur le choléra épidémique qui a sévi au bagne de Toulon en 1853. 4°. *Montpellier*, 1866. C.

Reynaud. Mémoire sur le choléra-morbus asiatique qui a régné à Toulon pendant l'année 1835. . . . 8°. *Paris*, 1838.

Taxil. Le choléra de Toulon [en 1835].
[Journ. des connaiss., 1836–37, V, pp. 194–196.]

Turrel. Compte rendu de notre pratique pendant le choléra de Toulon, en 1849. 8°. *Paris*, 1852.

Aperçu historique sur l'invasion, la marche, et les effets du choléra à Toulon. Résumé de la correspondance d'un ex-administrateur du bureau central de secours, du 20 juin au 31 août 1835. 8°. *Toulon*, 1835.

Tours.

Charcellay. Histoire médicale topographique des épidémies de choléra, qui ont régné en 1832, 1849, et 1854, dans la ville de Tours et le département d'Indre-et-Loire. 8°. *Tours* [1854]. L.

Haime. Sur le choléra à Tours.
[Bull. de l'Acad. nat. de méd., 1848–49, XIV, pp. 1106–1110.]

Huot (P.) Le choléra au pénitencier de Tours [juillet 1849].
[Revue méd., Paris, 1849, III, pp. 339–412 and reprint in 8°, Paris, 1849.]

Troyes.

Blampignon (J. N. A.) Mémoire sur le choléra-morbus épidémique de Troyes en 1832. 8°. *Troyes* [1835].

Versailles.

Clairin (C. A.) *Sur le choléra de 1849 à l'hôpital militaire de Versailles. 4°. *Paris*, 1849. L.

Gemin (J.) *Le choléra à Versailles. 4°. *Paris*, 1866. L.

Voncq.

Brébant (L.) De l'épidémie cholérique de 1854, à Voncq, canton d'Attigny . . . [Ardennes]. 8°. *Vouziers*, 1855.

Vosges.

Liégey. Note sur la constitution médicale du mois de juillet 1857 (tendance des maladies à revêtir la forme cholérique) dans une contrée des Vosges.
[Journ. de méd., de chir. et de pharmacol. Bruxelles, 1857, XXV, pp. 206–212.]

Yonne.

Duché (E.) Lettre sur le choléra à l'Yonne.
[Gaz. des hôp., 1857, pp. 197–198.]

GERMANY.

Anné (F.) Die Cholera-Epidemie in den grossherzoglich badischen Ortschaften Schönfeld, Ilmspan und Gerchsheim im Spätsommer 1866 mit besonderer Rücksichtigung auf die Behandlung dieser gefürchteten Krankheit. 8°. *Würzburg*, 1867.

Barrie (C.) Wodurch kann die Weiterverbreitung der Cholera in Deutschland verhindert und der Stoff zu dieser Krankheit in der Wurzel vernichtet werden? 8°. *Leipsig*, 1831. L.

Behr (O.) Die Cholera in Deutschland. Populaire Belehrungen über das Auftreten und die Bekämpfung dieser Seuche. 8°. *Leipsig*, 1848. L.

Busch (v. d.) Ueber die Cholera in Magdeburg und Hamburg.
[Med.-chir. Zeitg., Innspruck, 1832, I, pp. 73–86, 89–96, 110–112.]

Ebermaier (C. H.) Bericht über die während eines mehrwöchentlichen Aufenthalts in Berlin und Magdeburg gesammelten Beobachtungen und Erfahrungen in Betreff der asiatischen Cholera. Mit Abbildungen. 8°. *Düsseldorf*, 1832.

Franz (K.) Beobachtungen während der vorjährigen Choleraepidemie.
[Allg. Wien. med. Zeitg., 1867, xii, pp. 67–68, 74–75.]

Fuchs (G.) * Ueber das Auftreten der Cholera in Miltenberg, Rothenfels und die Immunität Würzburgs im Jahre 1866. 8°. *Würzburg*, 1870. L.

Furbach. Wie weit wird die Cholera in Deutschland vordringen? und was haben die angrenzenden Staaten davon zu befürchten? 8°. *Stettin*, 1831.

Gieseler (R.) Die Cholera-Epidemie zu Spanbeck und Sudershausen.
[Deutsche Klinik, 1850, ii, pp. 517–519.]

Gietl (F. X. v.) Gedrängte Uebersicht meiner Beobachtungen über die Cholera vom Jahre 1831–1873. 8°. *München*, 1873.

Günsburg (F.) Mittheilungen über die gegenwärtige Epidemie der asiatischen Cholera. 8°. *Breslau*, 1848. L.

Heidenhain. Einige Mittheilungen über die Cholera, mit besonderer Beziehung auf die letzte Epidemie (1852).
[Deutsche Klinik, 1853, v, pp. 73–77, 85–88, 97–102.]

Hergt (F.) *und* **Sommerschu** (K.) Berichte über Cholera-morbus. 8°. *Karlsruhe*, 1831. L.

Höring. Die Cholera in Heilbronn a. N. und Frankenbach.
[Med. Correspbl. d württemb. ärztl. Ver., 1874, xliv, pp. 33–38, 41–48.]

Köhler. Bemerkungen über die asiatische Cholera und deren Behandlung. Nach Beobachtungen während der 1854er Epidemien zu München, Augsburg, Cannstadt, Zwiefalten, Zwiefaltendorf und Ulm abgefasst.
[Med. Correspbl. d. württemb. ärztl. Ver., 1855, xxv, pp. 225–230, 233–238, 241–246.]

Lichtenstein (E.) Zur dermaligen Cholera-Epidemie.
[Deutsche Klinik, 1873, xxv, pp. 337–338.]

Löbel (G.) *und* **Klob** (J.) Bericht über die diessjährige Cholera-Epidemie.
[Bericht d. k. k. Krankenanstalt Rudolph-Stiftung, Wien, 1867, pp. 251–288.]

Poppelauer. Die Cholera-Epidemie des Jahres 1866. Statistische, ätiologische und therapeutische Beobachtungen.
[Berl. klin. Wochenschr., 1867, iv, pp. 136, 146, 162.]

Röser (B.) *und* **Urban** (A.) *See* **Berichte** bayerischer Aerzte über Cholera morbus.

Röttger (J. C.) Kritik der Cholera nach physikalischen Gründen ermessen aus dem plebejischen Gange, den dieselbe durch die bei Magdeburg gelegenen fünf Dörfern: Oesterweddingen, Stemmern, Bahrendorf, Sülldorf und Altenweddingen genommen hat, und wo sie zuletzt wegen Mangel an genugsamer Verblendung über sie wirklich gestorben ist. Ferner: Ueber die trügerischen Umtriebe der Cholera im Reiche der Lust. 8°. *Halle*, 1832. L.

Rosenbaum (A.) Resultate meiner Beobachtungen während der Cholera-Epidemie in Landsberg und Kreuzburg. 8°. *Ratibor*, 1853. L.

Rosenberg. Erfahrungen über die Cholera im Jahre 1855.
[Wien. med. Presse, 1865, vi, pp. 810–813, 831–833, 858–861.]

Schäffer (v.) Beschreibung der Brechruhrepidemie, welche in den Monaten September und Oktober 1854 in der k. Pflegeanstalt Zwiefalten geherrscht hat.
[Med. Correspbl. d. württemb. ärztl. Ver., 1855, xxv, pp. 209–216.]

Sinogowitz (H. S.) De cholera epidemica, M.D.CCCXXXI anno Dantisci et Berolini observata, tractatus pathol.-therap. 8°. *Danzig*, 1831.

Vogt *und* **Schmidt.** Amtlicher Bericht über Epidemien der asiatischen Cholera des Jahres 1866, in den Regierungsbezirken Unterfranken und Aschaffenburg, Schwaben und Neuburg. 8°. *München*, 1860. L.

Wachsmuth (A.) Die Cholera in Gieboldenhausen im Juli und August 1850. Nebst einigen nachträglichen Notizen über die Cholera in Eisdorf und im Göttinger academischen Hospitale sowie über die Behandlung der Cholera im Allgemeinen. 8°. *Göttingen*, 1851. L.

Wallichs. Choleraberichte. [In Altona und Ottensen.]
[Allg. Zeitschr. f. Epidem., Erlangen, 1874, i, pp. 451–459.]

Wintrich (M.) Die Cholera, beobachtet in der Neuzeit in Berlin, Leipzig, und nordwärts. Nebst einem Anhang über galvanische Bäder in der Epidemie. 8°. *Augsburg*, 1850. L.

Zeller (C.) Die epidemische Cholera, beobachtet in Wien und Brünn im Herbste 1831. 8°. *Tübingen*, 1832. L.

Zeroni (H.) Das Auftreten der Cholera in den Provinzen Posen und Preussen im Jahre 1873. Eine Besprechung des Reiseberichts des Herrn Prof. Dr. A. Hirsch über diese Epidemie. 8°. *Mannheim*, 1874.

Beobachtungen bayerischer Aerzte über Cholera morbus. Beobachtungen jener Aerzte, welche auf allerhöchsten Befehl nach Berlin gereist waren: Dr. Gietl, Kaltenbrunner, Pfeufer, Roeser, und Urban welcher aus Polen dorthin zurückkehrte. 8°. *München*, 1832. L.

CONTENTS.

1stes Heft. Die Beobachtungen und Krankengeschichten von X. Gietl.
2tes Heft. Ueber die Verbreitung der Cholera morbus und den Erfolg der dagegen in den k. preussischen und k. k. österreichischen Staaten ergriffenen Massregeln von G. Kaltenbrunner.
3tes Heft. Die asiatische Cholera in Wien beobachtet von W. Sander.

Berichte bayerischer Aerzte über Cholera morbus. Auf allerhöchsten Befehl ausgezogen und redigirt von Dr. B. Röser und Dr. Aloys Urban. 1ste und 2te Abtheilung. 4°. *München*, 1831–33. L.

[This is a collection of the "AUSSERORDENTLICHE Beylage zu den bayerischen Annalen", Nos. 1–27.]

Cholera-Archiv, mit Benutzung amtlicher Quellen. Herausgegeben von J. C. Albers, F. D. Barry, etc. 3 v. 8°. *Berlin*, 1832–33. L.

Cholera-Blatt. Als Beilage zu den Schlesischen Blättern, von Friedr. Mehwald. 1 Band à 30 Nummern. sm. 8°. *Breslau*, 1831.

Cholera-Nachrichten.

[WIEN. med. Presse, 1866, VII, pp. 753 et seq.]

Cholera orientalis. Extrablatt zum allgemeinen Repertorium der gesammten deutschen medicinisch - chirurgischen Journalistik. Herausgegeben von Carl Ferdinand Kleinert. 2 v. 8°. *Leipzig*, 1831–32. L.

Cholera-Zeitung (Allgemeine). Mittheilungen des Neuesten und Wissenswürdigsten über die asiatische Cholera. In Verbindung mit mehreren in- und ausländischen Gelehrten herausgegeben von J. Radius. Aug. 26, 1831–Nov. 28, 1832. 4°. *Leipzig*. L.

Cholera-Zeitung (Berliner). Materialien zur Geschichte und Behandlung der

Cholera-Zeitung, etc.—continued

asiatischen Cholera, etc. Herausgegeben von Dr. J. L. Casper. Nos. 1–18 Sept. 24 to Dec. 27, 1831. 4°. *Berlin*, 1831. L.

Cholera-Zeitung. Herausgegeben von Dr. Zitterland. 2 Quartale à 26 Nummern. 4°. *Leipzig und Aachen*, 1831. L.

Cholera-Zeitung. Herausgegeben von den Aerzten Königsbergs. 2te Aufl. 4°. *Königsberg*, 1832. L.

Cholera-Zeitung (Schlesische). Herausgegeben von dem ärztlichen Comité in Schlesien. (Desinficirt.) Nos. 1–[illegible] 8, 1831, to Feb. 18, 1832. Nebst Supplementbogen, Register und 2 Steindruckungen. 4°. *Breslau*, 1831–32. L.

Notizen und Cholera-Chronik.

[WIEN. med. Wochenschr., 1866, pp. [illegible] et seq.]

Notizenblatt (Wiener medicinisches) enthaltend Mittheilungen über das Verhalten bei Cholera-Epidemien und die Heilart. Herausgegeben von dem Doctoren-Collegium der medicinischen Facultät in Wien. Hauptredakteur Dr. Joh. Knolz. 1ste Abtheilung. 12 Nummern. 4°. *Wien*, 1854.

Report on the progress and character of the epidemic cholera prevailing in Germany in 1852. 8°. *London*, 1852. L.

Tabellen die Cholera-Epidemie des Jahres 1866 betreffend.

[1. JAHRESBERICHT des Landes-Medicinalcollegiums über das Med.-Wesen im Königr. Sachsen. Dresden, 1869, pp. 44, 146–168.]

Zur Cholera-Statistik. Tabelle der im Jahre 1849, 1850, 1859, im Kreise Elberfeld an der Cholera erkrankten, genesenen und gestorbenen Personen

[DEUTSCHE Klinik, Beilage, 1861, XIII, pp. [illegible]

Aix-la-Chapelle.

Hartung (J.) Die Cholera-Epidemie in Aachen in Folge höh. Auftrages beschrieben. 8°. *Aachen*, 1833.

Kremers (C.) Die asiatische Cholera in der Bürgermeisterei Würselen, Landkreises Aachen. Ein von der hiesigen Regierung zu Aachen zum Druck beförderten Bericht. 8°. *Aachen*, 1832.

Neumann (K. G.) Mittheilungen über Aachen.

[BERLINER med. Central Zeitung, 1832, [illegible] 22, 36–39, 53–55.]

Altona.

Gaskoin (J. S.) Cholera at Altona

[LONDON Med. Gaz., 1832, IX, pp. [illegible]

agel (C. F.) Ueber die Cholera in Altona.

[Mag. d. ausländ. Lit. d. ges. Heilk., v. 23, 1832, pp. 279–294.]

teinheim. Analecten zur Geschichte der Cholera-Epidemie in Altona.

[Wissenschaftl. Ann. der ges. Heilk., 1834, xxx, pp. 129–154.]

nklam.

irschstein (J.) Der Genius Epidemicus und die Cholera zu Anklam im Jahre 1853.

[Med. Zeitung, Berlin, 1853, pp. 233–234.]

rnswald.

Wolff. Einiges über die Arnswalder Cholera-Epidemie im Jahre 1866.

[Berlin klin. Wochenschr., 1867, iv, p. 422.]

ugsburg.

ikentscher (L.) Die Cholera asiatica zu Augsburg 1873-74 vom sanitätspolizeilichen Standpunkte aus geschildert. 8°. *Augsburg*, 1875.

Baden.

Volz (R.) Die Cholera auf dem badischen Kriegsschauplatze im Sommer 1866. Amtlicher Bericht an das grossherzoglich-badische Ministerium des Innern. 8°. *Karlsruhe*, 1867. L.

Bavaria.

Lautenbacher (L.) Summarischer Ausweis über den Stand der Cholera in Bayern bis zum 4. September 1854.

[Aerztl. Intell.-Bl., München, 1854, i, pp. 304–306.]

Martin (A.) Hauptbericht über die Cholera-Epidemie Jahres 1854 im Königreiche Baie

[Aerztl. Intell.-Bl., München, 1857, iv, p. 170.]

—— The same. 8°. *München*, 1857. L.

—— Schluss-Folgerungen aus dem amtlichen Hauptbericht über die Cholera-Epidemie des Jahres 1854 im Königreich Baiern.

[Aerztl. Intell.-Bl., München, 1857, iv, p. 467.]

—— Die Cholera in Bayern während des diesjährigen Sommers (und Herbstes).

[Aerztl. Intell.-Bl., München, 1866, xiii, pp. 556–558, 577–586, 610–612, 641, 673, 727–730.]

Plagge. Hauptbericht über die Cholera-Epidemien des Jahres 1854 im Königreich Baiern.

[Aerztl. Intell.-Bl., München, 1858, v, p. 52.]

Bemerkungen (Einige) zu dem "Hauptbericht über die Cholera-Epidemie des Jahres 1854 im Königreich Bayern."

[Deutsche Klinik, Beilage, 1859, xi, pp. 53–60.]

Hauptbericht über die Cholera-Epidemie 1854 im Königreiche Bayern. *München*, 1857.

Schlussfolgerungen aus dem amtlichen Hauptberichte über die Cholera-Epidemie des Jahres 1854 im Königreiche Bayern.

[Med. Corspdzbl. d. württemb. aerzt. Vereins, Stuttgart, 1857, xxvii, pp. 261–264, 270–272, 278–279.]

Summarischer Ausweis über den Stand der Cholera in Bayern bis zum 12. September 1854.

[Aerztl. Intell.-Bl., München, 1854, i, pp. 313–316, 325–328.]

Verzeichniss über die Cholera-Vorkommnisse in Oberbayern im Jahre 1873. [Nach amtlichen Mittheilungen.]

[Aerztl. Intell.-Bl., München, 1873, xx, pp. 581–583.]

Berlin.

Baltz (T. F.) Über die diesjährige Brechruhr- (Cholera-) Epidemie in Berlin. Eine Neujahrsgabe zum Besten der Klein-Kinderbewahranstalten und zur Beruhigung Aller, welche noch an Ansteckung der genannten Krankheit glauben. 8°. *Berlin*, 1853. L.

Becker (F. W.) Account of the cholera at Berlin.

[London Med. Gaz., 1832, ix, pp. 204–206.]

Breyer. Die Cholera-Epidemie zu Berlin, in kurzgefasster Darstellung.

[Jour. der prakt. Heilk., 1832, lxxiv, pp. 7–32.]

Bruck (M. M.) Rationelle Behandlung der Cholera und Widerlegung der herrschend gewordenen falschen Ansichten über die Natur und Heilung derselben, nebst ein Anhang über den Character, mit welchem sie in Berlin auftritt. 8°. *Berlin*, 1831.

Burghardt (C.) Bericht über die in Berlin herrschende Cholera-Seuche. 4°. *Erfurt*, 1831.

Casper. Der Ausbruch der zweiten Cholera-Epidemie in Berlin im Jahre 1832. Nebst einer Nachschrift von Hufeland.

[Jour. der prakt. Heilk., 1832, lxxv, pp. 107–126.]

—— Statistische Uebersicht über die Berliner Cholera-Epidemie von 1837.

[Wochenschr. f. d. ges. Heilk., 1838, pp. 92–94.]

Casper (J. L.) Differenzen der zweiten Berliner Cholera-Epidemie im Jahre 1832 von der ersten des Jahres 1831.
[WOCHENSCHR. f. d. ges. Heilk., 1833, II, pp. 633–644.]

De Greck (P.) Über die asiatische Cholera in Berlin. Reisebericht an die königl. hochlöbl. Regierung zu Köln, als Resultat seiner Beobachtungen. 8°. *Köln*, 1832.

Froriep (R.) Symptome der asiatischen Cholera. In Nov. und Dec. 1831 zu Berlin abgebildet. 4°. *Weimar*, 1832. L.

Goldbaum (M.) Bericht über die städtische Cholera-Heilanstalt No. III. zu Berlin während der Epidemie des Jahres 1866.
[VIRCHOW'S Archiv, 1867, XXXVIII, pp. 245–296.]

Gosse *und* **Volmar.** Ueber die Behandlung der Cholera in Berlin; aus einem Berichte der abgeordneten Schweizer Aerzte Dr. Gosse und Dr. Volmar aus Berlin vom 17. Wintermonath 1831.
[MED.-CHIR. Zeitung, Innspruck, 1832, I, pp. 153–160, 161–176.]

——— De Behandeling van den aziatischen Braakloop in de Ziekenhuizen te Berlijn. Uit het Hoogd. vert. (d. C. v. Eldik). 8°. *Nijmegen*, 1832.

Güterbock (L.) Bericht über das Cholera-Lazareth an der Waisenbrücke. [*Berlin*], 1852.
[DEUTSCHE Klinik, 1853, V, pp. 121–126, 133–137, 145–149.]

Heilbronn (D.) Mittheilungen über die Cholera-Epidemie in Berlin. Aus Berichten an die königliche Regierung zu Minden. 8°. *Minden*, 1831.

Horn. De la propagation et de la marche du choléra dans Berlin.
[ANN. d'hyg. pub., 1831, VI, pp. 473–476.]

Horn (E.) De Cholera, zoo als dezelve te Berlijn is waargenomen. Uit het Hoogduitsch door Th. Davids. 8°. *Amsterdam*, 1831. L.

Joël (S.) Bericht über die Cholera des Jahres 1831 in Berlin.
[MAG. f. d. ges. Heilk., 1834, XLII, pp. 63–141.]

Lamprey (J.) Remarks and observations on the cholera at present epidemic in Berlin. 12°. *London*, 1848.

Lessing (M. B.) Medicinisch-polizeiliche Erinnerungen aus der Zeit der Cholera-Epidemie zu Berlin.
[MED. Argos, Leipzig, 1839, I, pp. 311–319.]

Leubuscher (R.) Die Cholera in Berlin.
[MED. Reform, Berlin, 1848, pp. 162–164.]

Leubuscher (R.)—continued.

——— Mittheilungen aus dem [illegible] Spital II.
[MED. Zeitung, Berlin, 1849, pp. 202–204 [illegible]

——— Bericht über die Cholera-Heilanstalt in Berlin im Jahre 1850.
[DEUTSCHE Klinik, 1851, III, pp. 6–9, 13–21

Lewin (L.) Bericht über die Erkrankungen an der asiatischen Cholera in Berlin im Jahre 1871.
[DEUTSCHE Klinik, 1871, XXIII, pp. 411–4[illegible]

Lichtenstein (E.) Das locale [illegible] phärische Verhalten zur Zeit der Berliner Cholera-Epidemie im Jahre 1866.
[DEUTSCHE Klinik, Beilage, 1867, XII; [illegible]

Lieber (G.) Die Cholera im neuen Hospitale zu Berlin. 8°. *Berlin*, 1832.

Mädler (J. H.) Ist aus dem Verlauf der Cholera in Berlin ein Zusammenhang derselben mit der Witterung nachbar?
[BERLINER med. Centr.-Zeitg., 1832, I, pp. [illegible]

Mahlmann (H.) Die Cholera zu Berlin in den zehn Jahren 1831, 32, 37, 48, 50, 52, 53, 54 und 55, mit besonderer Rücksicht auf ihre räumliche Verbreitung.
[DEUTSCHE Klinik, Beilage, 1856, VIII, pp. [illegible] 20–28 (1 Karte).]

Meyer (J.) Bericht über die Cholera-Epidemie des Jahres 1855, aus der Abtheilung für Cholerakranke der Charité.
[ANN. d. Charité-Krank. zu Berlin, 1856, [illegible] 1–27.]

Müller. Amtlicher Bericht über die Cholera-Epidemie zu Berlin, 1[illegible]
[DEUTSCHE Klinik, 1853, V, pp. 153–17[illegible]

——— A history of epidemic cholera in Berlin in the year 1853. Translated from the German by R. U. West, [illegible]
[JOUR. of Pub. Health, 1855, I, pp. 23[illegible]

Müller (E.) Bericht über die im Jahre 1854 zu Berlin vorgekommenen Cholera-Fälle.
[MED. Zeitung, Berlin, 1854, pp. 365–36[illegible]

——— Die Cholera-Epidemie zu Berlin im Jahre 1855.
[ANN. d. Charité-Krankenhauses zu Berlin, [illegible] VII, pp. 1–96.]

——— The same. 8°. *Berlin*, 1856.

Müller (E. H.) Die Cholera-Epidemie zu Berlin im Jahre 1866. Amtlicher Bericht erstattet im Auftrage der Königlichen Sanitäts-Commission. [illegible] *lin*, 1867.

——— Die Cholera-Erkrankungen zu Berlin im Jahre 1871.
[VIERTELJ. f. gerichtl. Med. u. öffentl. [illegible] 1872, XVII, n. F., pp. 116–122.]

iller (E. H.)—continued.

— Die Cholera-Epidemie zu Berlin im ahre 1873. Amtlicher Bericht. 4°. *Ber-*
n, 1874. L.

olai (A.) Die Cholera-Epidemie in erlin im Jahre 1837.

[Jahrb. d. ges. Staatsarz., Frankfurt a. M., 1838, IV. pp. 377-411.]

iff (F.) Untersuchungen über die Cho-era, mit besonderer Berücksichtigung er Berliner Epidemie. 8°. *Erlangen*, 849. L.

ich (G. C.) Die Cholera in Berlin, mit ndeutungen zu ihrer sichern Abwehr nd Heilung. 8°. *Berlin*, 1831.

edel (T.) Sterblichkeits-Verhältnisse n der jüngsten Berliner Cholera-Epide-ie, nebst einer Uebersicht der einzelnen holera-Sterbefälle nach ihrer räumli-hen Verbreitung. [Separat-Abdruck us dem aerztlichen Volksboten, Band 1., eft 7. und 8.] 4°. *Berlin*, 1856. L.

mberg (M. H.) Erfahrungen über die rientalische Cholera. Ein Bericht über as Cholera-Hospital No. I. zu Berlin, bgestattet von dessen dirigirendem rzte.

[Journ. d. prakt. Heilk., 1832, LXXIV, pp. 3-64.]

— Bemerkungen über die asiatische holera. 8°. *Berlin*, 1832. L.

[Reprint of the preceding.]

— Bericht über die Cholera-Epidemie es Jahres 1837.

[Wochenschrift f. d. gesamm. Heilk., 1838, pp. 33-39, 49-56, 69-76, 86-92.]

— The same. 8°. *Berlin*, 1838. L.

hnitzer. Statistische Bemerkungen über die Choleraepidemie der Jahre 831-32, 1837 und 1848 zu Berlin.

[Allg. med. Central-Zeitung, Berlin, 1848, XVII, p. 815.]

— Statistische Bemerkungen über die Cholera-Epidemie des Jahres 1849 zu Berlin im Vergleiche zu den frühern Epidemien.

[Allg. med. Central-Zeitung, Berlin, 1849, XVIII, p. 811.]

huts (W.) Bericht über die Cholera-Epidemie des Jahres 1848 in Berlin.

[Virchow's Archiv, 1848, II, pp. 379-408.]

— Vergleichende statistische Uebersicht der in Berlin in den vier Epidemien 831, 1832, 1837 und 1848 vorgekommenen Cholerafälle nach den Wohnungen der Erkrankten aus den amtlichen Listen zusammengestellt und erläutert. 8°. *Berlin*, 1849. L.

Scoutetten (H.) Observations de choléra recueillies à Berlin.

[Ann. de la méd. phys., Paris, 1832, XXI, pp. 124-137.]

— Relation historique et médicale de l'épidémie de choléra qui a régné à Berlin en 1831. 2e éd. 8°. *Paris*, 1832. L.

[1st ed. same year.]

Stich. Erfahrungen aus der Berliner Cholera-Epidemie 1849.

[Neue Zeitg. f. Med. u. Med.-Reform, Nordhausen, 1849, I, pp. 771-773, 778-780.]

Thümmel. Bericht über die in der Heilanstalt No. V. zu Berlin vorgekommenen Formen der Cholera und die Behandlung derselben.

[Mag. f. d. ges. Heilk., 1832, XXXVI, pp. 403-431.]

Vocke. Die Cholera in Berlin, 1866.

[Deutsche Klinik, 1867, XIX, pp. 189, 201, 219.]

Weisbach. Beschränkte Cholera-Erkrankungen in der Berliner Charité im Jahre 1871.

[Virchow's Archiv, 1872, LV, pp. 249-251.]

Behandeling (De) van den aziatischen Braakloop in de Ziekenhuizen te Berlijn (uit een Berigt der tot Onderzoek van den aziatischen Braakloop naar Berlijn gezondene Zwitsersche Geneesheeren Gosse en Volmar, gedagteekend: Berlijn, . . . 1831). 8°. *Nijm*, 1832.

Cholera (Die) in Berlin.

[Allg. med. Central-Zeitung, 1848, XVII, pp. 683, 697-698, 707-708.]

Cholera-Contumaz-Anstalt in der Charité.

[Mag. f. d. gesammte Heilk., 1835, XLIII, pp. 290-296.]

Cholera-Erkrankungen (Die) in Berlin im Jahre 1859.

[Med. Zeitg., Berlin, 1860, III, n. F., pp. 52-54.]

Diesjähriger Stand der Cholera in hiesiger Residenz (Berlin).

[Berliner med. Central-Zeitung, 1832, I, pp. 48, 64, 80.]

Mittheilungen über den Stand der Cholera in Berlin und die bisher getroffenen prophylaktischen Massregeln.

[Berl. klin. Wochsch., 1874, XI, pp. 158-159.]

Tagebuch über das Verhalten der bösartigen Cholera in Berlin. Eine Sammlung von Aufsätzen pathologisch-therapeutischen, gesundheits-polizeilichen, und populär-medicinischen Inhalts in Bezug auf den Verlauf der Epidemie im In- und Auslande. Seit dem 14. September bis zum 31. December 1831 herausgegeben von Dr. Albert Sachs. 92 Num. 4°. *Berlin*, 1831. L.

Frankfurt am Main.

Mappes (J. M.) Die Cholera in Frankfurt a. M.
[ARCH. f. physiol. Heilk., 1856, pp. 467–478.]

Neufville (W. de). Ueber das Auftreten der asiatischen Cholera zu Frankfurt a. M. im Jahre 1849.
[ARCH. f. physiol. Heilk., 1850, pp. 455–467.]

Varrentrapp (G.) Cholera in Frankfort-on-the-Main.
[TRANS. of the Epidemiol. Soc., 1856, pp. 66–82.]

——— On cholera in Frankfort on the Main, and other parts of Germany.
[MED. Times & Gaz., London, 1855, XI, n. s., pp. 223–224.]

Frankfurt an der Oder.

Löwenstein (J. S.) Zur Cholera-Epidemie in Frankfurt a. d. O., 1866.
[DEUTSCHE Klinik, 1867, XIX, p. 296.]

Choleraepidemie (Die) in und um Frankfurt an der Oder.
[HEIDELB. klin. Ann., 1832, VIII, pp. 115–151.]

Freudenstadt.

Diez. Bemerkung über die Brechruhr und Ruhr in den Monaten August, September und Oktober 1854 im Oberamtsbezirke Freudenstadt.
[MED. Correspbl. d. württemb. ärztl. Ver., 1856, XXVI, pp. 113–116.]

Greifswald.

Brasch (R.) * Die Cholera in Greifswald. 8°. *Greifswald* [1866]. L.

——— Beobachtungen über die Cholera in Greifswald.
[VIRCHOW's Arch., 1868, XLIII, pp. 353–358.]

Bolle (P. M.) * De cholera orientali, quae anno MDCCCXXXVII Gryphiae erupit, nonnullis quae de eodem morbo lassani observavi adjectis. 8°. *Gryphiae* [1838]. L.

Gumbinnen.

Weiss (A.) Die Cholera-Epidemie des Jahres 1873 im Regierungs-Bezirke Gumbinnen, nach amtlichen Quellen und eigenen Wahrnehmungen dargestellt.
[ALLG. Zeitschr. f. Epidemiol., 1874, I, pp. 241–269, 321–364.]

Halle.

Bresler. Die Cholera zu Halle.
[MED. Conversationsbl., 1832, pp. 265–270.]

Delbrück (E. v.) Bericht über die Cholera-Epidemie des Jahres 1855 in der Strafanstalt zu Halle. 8°. *Halle*, 1856. L.

Delbrück (E. v.)—continued.

——— The same. Des Jahres [illegible] *Halle*, 1867.

——— Mittheilungen über die C[illegible] Halle. Ein Beitrag zur Ch[illegible] logie.
[ZEITSCHR. f. Biologie, 1868, IV, pp. [illegible]]

Heim (E. C. L.) De cholera Ha[illegible] MDCCCXLIX observata. [illegible] *Saxonum*, 1850.

Zuckschwerdt (B.) * Die Typhomie im Waisenhause zu Halle [illegible] Mit Berücksichtigung der Im[illegible] desselben gegen Cholera. [illegible] *S.*, 1872.

Bundestagsbeschlüsse (Die [illegible] nius 1832 und die deutschen [illegible] Ein politischer Tractat für den [illegible] und Landmann. Zum Besten [illegible] lerawaisen in Halle. [illegible] 1832.

Hamburg.

Buchheister (J. C.) *and* Noodt fahrungen über die Cholera [illegible] Hamburg im Herbste 1831. [illegible] 1832.

Erman (F.) Ueber einige [illegible] an den Cholerakranken des [illegible] Krankenhauses zu Hamburg. Beobachtungen.
[VIRCHOW's Arch., 1874, LX, pp. [illegible]]

Fricke (J. C. G.) Geschichte [illegible] lung des Ausbruchs der asiatischen [illegible] lera in Hamburg. Nach [illegible] amtlichen Untersuchungen.
[MAG. d. ausl. Lit. d. gesammt. H[illegible] pp. 386–472.]

——— The same. 8°. *Hamburg*, [illegible]

Hallier (E.) Zur Geschichte des Ausbruchs der Cholera in Ham[illegible]
[ZEITSCHR. f. Parasitenk., Jena, [illegible] 91.]

Koch (C. A. L.) Beobachtungen Cholera asiatica in Hamburg.
[MED. Corresp.-Bl. d. württemb. [illegible] 1, pp. 229–233.]

Mögling. Bericht über den [illegible] asiatischen Cholera in Ham[illegible]
[MED. Corresp.-Bl. d. württemb. [illegible] XIX, pp. 17–19.]

Rothenburg (J. N. C.) Ueber [illegible] Epidemie des Jahres 1832 in H[illegible]
[ZEITSCHR. f. d. gesammte Med. F[illegible] II, pp. 401–449; *also*, reprint [illegible] 1836.]

Schön (M. J. A.) Kurze Be[illegible] über die Cholera in Hamburg
[LITT. Ann. d. gesammt. Heilk. [illegible] 415.]

stt (J.) Extracts from medical re-
ts founded on actual observation and
mmunicated to the government on
cholera-morbus which prevailed at
ıtzig between the end of May and
part of September 1831. 8°. [*Lon-*
n. d.]

- Extracts from reports on the chol-
at Dantzig.

NION Med. Gaz., 1832. IX, pp. 441-445, 473-

- The substance of the official medi-
reports upon the epidemic, called
lera, which prevailed among the poor
Dantzick (in 1831). Published by
authority of the privy council. 8°.
don, 1832. L.

n. Medicinal-Bericht über die Cho-
a-Station des Danziger Garnison-La-
rths vom 22. Sept. bis zum 1. Dec.
57.

ıs. Zeitg., Berlin, 1858, I. n. F., pp. 25-27, 29-
1, 35-37.]

Boutraye (de). Documents sur le
léra-morbus envoyés à l'intendance
itaire . . . de la Gironde; par . . . ,
sul général de France, à Dantzig.
Bordeaux, 1832.

in (A.) Danzig und die Cholera. Ein
tistisch-topographischer Versuch. 4°.
nzig, 1868.

sper. Die Cholera im Regierungs-
zirk Danzig.

[HUFELAND'S Archiv, 1866, XXXVII, pp. 257-272.]

meyer (L.) Skizzen und Bemer-
ngen von einer Reise nach Danzig
d dessen Umgegend im August und
ptember 1831 im Auftrage der königl.
h-hannoveranischen Immediat-Com-
ssion gegen die Cholera unternom-
en. 8°. *Hannover*, 1832. L.

ame aus Danzig über die Cholera.
Danzig, 1831.

hlmen.

ganico. Die Cholera-Epidemie des
erbstes 1837 in Darkehmen, im Regie-
ngs-Bezirk Gumbinnen.

[Ang. f. d. gesammt. Heilk., 1839. LIV, pp. 3-74.]

urg.

ing. Die Cholera-Epidemie in der
trafanstalt zu Dieburg bei Darmstadt
3 Oct. 1854.

[DEUTSCHE Klinik, 1856. VIII, pp. 109-111, 121-123.]

Dresden.

Warnatz (G.) Die asiatische Cholera des Jahres 1866 im k. s. Regierungsbezirke Dresden. Amtlicher Bericht an das k. s. Ministerium des Innern. 8°. *Leipsig*, 1868. L.

Düsseldorf.

Ebermaier. Bericht über das Verhalten der asiatischen Brechruhr im Regierungs-Bezirke Düsseldorf während des Herbstes 1832.

[MAG. f. d. gesammt. Heilk., 1833, XI, pp. 290-348.]

——— Generalbericht über das Verhalten der asiatischen Cholera im Regierungs-Bezirke Düsseldorf während des Jahres 1833.

[MAG. f. d. gesammt. Heilk., 1843, XLIII, pp. 456-490.]

Elberfeld.

Brisken (C. E.) Die Epidemie der asiatischen Cholera im Kreise Elberfeld, im Jahre 1859, nebst tabellarischen Uebersichten über die vorgekommenen Erkrankungen und Sterbefälle in den Jahren 1849, 1850, und 1859, und einem Anhange. 12°. *Elberfeld*, 1860. L.

Pagenstecher (C., *sen.*) Die asiatische Cholera in Elberfeld vom Herbst 1849 bis zum Frühling 1850. 8°. *Elberfeld*, 1851. L.

Elbing.

Auszug aus einem Berichte des Hrn. Dr. Barchewitz über die Cholera zu Elbing. Zunächst zur Beherzigung der Orts-Sanitäts-Commission, im Auftrag der königlichen Regierung zu Köln herausgegeben von D. K. Th. Merrem. 8°. *Köln*, 1831.

Erding.

Beobachtungen beim Ausbruche der Cholera zu Erding (Oberbayern) während des Sommers 1854.

[ÄRZTL. Intell.-Blt., 1854, I, pp. 282-288, 293-296, 302-304.]

Wesen und rationelle Therapie der Cholera geschöpft aus Beobachtungen ihres Ausbruches zu Erding von F. G. K. roy. 8°. 1854. L.

Erfurt.

Pettenkofer (M. v.) Über Ursachen und Gegenwirkungen von Cholera-Epidemien in Erfurt. 8°. *Erfurt*, 1867.

Frankfurt am Main.

Mappes (J. M.) Die Cholera in Frankfurt a. M.
[Arch. f. physiol. Heilk., 1856, pp. 467–478.]

Neufville (W. de). Ueber das Auftreten der asiatischen Cholera zu Frankfurt a. M. im Jahre 1849.
[Arch. f. physiol. Heilk., 1850, pp. 455–467.]

Varrentrapp (G.) Cholera in Frankfort-on-the-Main.
[Trans. of the Epidemiol. Soc., 1856, pp. 66–82.]

——— On cholera in Frankfort on the Main, and other parts of Germany.
[Med. Times & Gaz., London, 1855, xi, n. s., pp. 223–224.]

Frankfurt an der Oder.

Löwenstein (J. S.) Zur Cholera-Epidemie in Frankfurt a. d. O., 1866.
[Deutsche Klinik, 1867, xix, p. 296.]

Choleraepidemie (Die) in und um Frankfurt an der Oder.
[Heidelb. klin. Ann., 1832, viii, pp. 115–151.]

Freudenstadt.

Diez. Bemerkung über die Brechruhr und Ruhr in den Monaten August, September und Oktober 1854 im Oberamtsbezirke Freudenstadt.
[Med. Correspbl. d. württemb. ärztl. Ver., 1856, xxvi, pp. 113–116.]

Greifswald.

Brasch (R.) * Die Cholera in Greifswald. 8°. *Greifswald* [1866]. L.

——— Beobachtungen über die Cholera in Greifswald.
[Virchow's Arch., 1868, xliii, pp. 353–358.]

Bolle (P. M.) * De cholera orientali, quae anno MDCCCXXXVII Gryphiae erupit, nonnullis quae de eodem morbo lassani observavi adjectis. 8°. *Gryphiae* [1838]. L.

Gumbinnen.

Weiss (A.) Die Cholera-Epidemie des Jahres 1873 im Regierungs-Bezirke Gumbinnen, nach amtlichen Quellen und eigenen Wahrnehmungen dargestellt.
[Allg. Zeitschr. f. Epidemiol., 1874, i, pp. 241–269, 321–364.]

Halle.

Bresler. Die Cholera zu Halle.
[Med. Conversationsbl., 1832, pp. 265–270.]

Delbrück (E. v.) Bericht über die Cholera-Epidemie des Jahres 1855 in der Strafanstalt zu Halle. 8°. *Halle*, 1856. L.

Delbrück (E. v.)—continued.

——— The same. Des Jahres 1866. 8°. *Halle*, 1867. L.

——— Mittheilungen über die Cholera in Halle. Ein Beitrag zur Cholera-Aetiologie.
[Zeitschr. f. Biologie, 1868, iv, pp. 231–345.]

Heim (E. C. L.) De cholera Halis anno MDCCCXLIX observata. 12°. *Halis Saxonum*, 1850. L.

Zuckschwerdt (B.) * Die Typhusepidemie im Waisenhause zu Halle a. S., 1871. Mit Berücksichtigung der Immunität desselben gegen Cholera. 8°. *Halle a. S.*, 1872. L.

Bundestagsbeschlüsse (Die) vom 28. Januius 1832 und die deutschen Demagogen. Ein politischer Tractat für den Bürger und Landmann. Zum Besten der Cholerawaisen in Halle. 12°. *Merseburg*, 1832. L.

Hamburg.

Buchheister (J. C.) *und* **Noodt** (C.) Erfahrungen über die Cholera asiatica in Hamburg im Herbste 1831. 8°. *Hamburg*, 1832.

Erman (F.) Ueber einige im Jahre 1831 an den Cholerakranken des allgemeinen Krankenhauses zu Hamburg gemachte Beobachtungen.
[Virchow's Arch., 1874, lx, pp. 46–66.]

Fricke (J. C. G.) Geschichtliche Darstellung des Ausbruchs der asiatischen Cholera in Hamburg. Nach Akten und amtlichen Untersuchungen.
[Mag. d. ausl. Lit. d. gesammt. Heilk., 1831, lii, pp. 386–472.]

——— The same. 8°. *Hamburg*, 1831. L.

Hallier (E.) Zur Geschichte des ersten Ausbruchs der Cholera in Hamburg.
[Zeitschr. f. Parasitenk., Jena, 1870, ii, pp. 1–91.]

Koch (C. A. L.) Beobachtungen über die Cholera asiatica in Hamburg.
[Med. Corresp.-Bl. d. württemb. ärztl. Ver., 1832, i, pp. 229–233.]

Mögling. Bericht über den Verlauf der asiatischen Cholera in Hamburg.
[Med. Corresp.-Bl. d. württemb. ärztl. Ver., 1850, xix, pp. 17–19.]

Rothenburg (J. N. C.) Ueber die Cholera-Epidemie des Jahres 1832 in Hamburg.
[Zeitschr. f. d. gesammte Med., Hamburg, 1834, ii, pp. 401–449; *also*, reprint in 8°, Hamburg, 1836.]

Schön (M. J. A.) Kurze Bemerkungen über die Cholera in Hamburg.
[Litt. Ann. d. gesammt. Heilk., 1831, xx, pp. 385–415.]

eraberichte aus den Niederlanden, Sachsen, und aus Magdeburg.
[Virch. Zeitschr. f. Epidemiol., Erlangen, 1874, I, pp. 193–225.]

heim.

s (G.) Cholera in Mannheim.
[Med. Correspbl. d. württemb. ärztl. Ver., 1849, XX, pp. 249–252.]

'. Resultate aus den Choleralisten nnheims.
[Ann. u. f. physiol. Heilk., 1850, pp. 270–294.]

'er. Sanitäts- und Hospitalsbericht r Garnison Mannheim für den Monat ptember 1849.
[Mittth. d. bad. ärztl. Vereins, Karlsruhe, 1849, II, pp. 141–147.]

)ni (H.) Erstes Lehrjahr in der Behandlung der Cholera. Epidemie in annheim im Jahre 1849. 8°. *Mannheim*, 1850. L.

— Zweite Choleraepidemie in Mannheim 1854.
[Mittth. d. bad. ärztl. Vereins, Karlsruhe, 1855, I, pp. 17–40.]

— Ueber die Choleravorgänge im Jahre 1867 in Mannheim.
[Zeitschr. f. Biologie, München, 1868, IV, pp. 480–511; *also*, reprint in 8°.]

— Die Cholera und das Cholera-Gift. in Rückblick auf die Choleravorgänge Mannheim vom Jahre 1848–1873. 8°. *Mannheim*, 1874. L.

rienburg.

g. Die Cholera, eine ansteckende olksseuche, der Import und die Verreitung derselben im Kreise Marienurg vom Jahre 1873. 8°. *Marienburg s. d.*]

rienthal.

w (H.) Rückblick auf die in den Monaten August und September v. J. bestandene Cholera-Epidemie in Marienthal.
[Wien. med. Presse, 1874, XV, pp. 58–60.]

cklenburg.

kermann (T.) Die Cholera-Epidemie des Jahres 1859 im Grossherzogthume Mecklenburg-Schwerin. Nach officiellen Mittheilungen und nach Berichten der Prediger, Ärzte und Physiker des Landes im Auftrage des hohen grossherzoglichen Ministeriums beschrieben. 8°. *Rostock*, 1860.

Sachse. Ueber die Cholera in Mecklenburg.
[Med. Conversationsbl., Hildburghausen, 1832, pp. 325–328.]

Spitta (D. H.) Die asiatische Cholera im Grossherzogthume Mecklenburg-Schwerin im Jahre 1832. 8°. *Rostock und Schwerin*, 1833. L.

Tott (C. A.) Was ist von der amtlichen Angabe zu halten, dass die asiatische Cholera in der hiesigen Stadt und ihrer Umgegend vorgekommen seyn soll? (Mecklenburg-Schwerin).
[Berl. med. Centr.-Zeitg., 1833, II, pp. 213–215.]

Memel.

Arendt (F. A.) Observationes nonnullae de cholera anni 1831, mensibus Julio, Augusto, Septembri, Octobri, Memeliae epidemica grassante. 8°. *Regimontii Prussorum*, 1832. L.

Mergentheim.

Höring. Cholera (in Mergentheim).
[Med. Correspbl. d. württemb. Ärztl. Ver., 1849, XIX, pp. 194–196.]

Metz.

Maréchal (F.) Rapport statistique et médical sur l'épidémie de choléra qui a régné à Metz et dans . . . . la Moselle en 1832. 8°. *Metz*, 1839.

Pascal (J. J.) Mémoire sur le choléra morbus qui a régné épidémiquement à Metz, et lieux circonvoisins, pendant l'année 1832. 8°. *Paris*, 1836. L.

Mittenwald.

Pfeufer (K.) Bericht über die Cholera-Epidemie in Mittenwald. 8°. *München*, 1837. L.

Mühlhausen.

Becker (C. A.) Neue Aufschlüsse über das Wesen und die Behandlung der Cholera, gewonnen in der Epidemie zu Mühlhausen; mit einem Flankenmarsche gegen vermeintliche Homöopathie. 8°. *Mühlhausen*, 1832.

Munich.

Decaisne (E.) Le choléra à Munich.
[L'Union méd., 1874, XXVIII, p. 302.]

Dieterich (G. L.) Beobachtungen und Behandlungen des wandernden Brechdurchfalles in München. 8°. [*Nürnberg*, 1837.

Frank (M.) Die Cholera-Epidemie in München in dem Jahre 1873–74, nach amtlichen Quellen dargestellt. 8°. *München*, 1875.

Gietl (F. X. v.) Die Cholera nach Beobachtungen auf der ersten medicinischen Klinik und Abtheilung im städtischen Hospital zu München. 8°. *München*, 1855. L.

——— Geschichtliches zur Cholera-Epidemie in München im Jahr 1854 als Zusatz zu der Schrift: Die Cholera nach Beobachtungen [etc.] 8°. *München*, 1855. L.

Huberwald (H.) Therapeutische Erfahrungen während der letzten Cholera-Epidemie in München.

[JAHRB. f. Kinderheilk., 1874, VIII, pp. 161–174.]

Kopp (F. X.) Generalbericht über die Cholera-Epidemie in München einschlüssig der Vorstadt Au im Jahre 1836–37. 8°. *München*, 1837. L.

Mahir (O.) Die Cholera in München, 1854. Deren Entstehung, Verbreitung, Verhütung und homöopathische Behandlung. 8°. *München*, 1854. L.

M[artin] (A.) Die diesjährige Cholera-Epidemie in München.

[AERZTL. Intell.-Bl., 1854, I, pp. 288–292; Beilage zu No. 37, pp. 307–312, 316–323, 328–340, 347–349, 357–358, 361–375.]

Oertel. Oeffentliche Beschwerde . . . über die unglückliche Behandlung der Cholera in München. Ende November 1836. 16°. *Nürnberg* [1836]. L.

Pettenkofer (M. v.) On the recent outbreak of cholera in Munich.

[MED. Times & Gaz., London, 1874, I, pp. 569–583.]

Rampold (F.) Die orientalische Brechruhr in München und an andern Orten. 8°. *Stuttgart und Tübingen*, 1838. L.

Romerio. Beobachtungen bei der Cholera in München.

[MED. Corresphl. d. württemberg. aerztl. Vereins, 1837, VII, pp. 25–31.]

Schättle. Beobachtungen bei Brechruhrkranken in München.

[MED. Corresphl. d. württemberg. aerztl. Vereins, 1836, VI, pp. 391–394, 403–405.]

Schlagintweit (W. A. J.) Praktische Erfahrungen und Beobachtungen über die epidemische Brechruhr in München. 8°. *München*, 1837. L.

Schleiss von Löwenfeld (C.) * Cholera asiatica zu und bei uns. 8°. *Mün-*, 1837.

Siebert (A.) Ueber die ärztliche Besuchsanstalten während der Cholera-Epidemie zu München.

[ANNAL. d. Staatsarzneik., Tübingen, 2. R., pp. 250–267.]

Spring (A. F.) Ueber Ursprung, Wesen und Verbreitung der wandernden Cholera. Mit Beziehung auf die Epidemie in München, 1836–37. 8°. *München*, 1837.

Stein (J.) Aerztliche Notizen über die Cholera-Epidemie in München im Jahre 1854. 8°. *Frankfurt am M.*, 1854.

Strüpf [*Dr.*] Tabellarische Uebersicht der Erkrankungen an Cholera und Cholera-verwandten Krankheiten im Bezirksamte München.

[AERZTL. Intelligenz-Blatt, 1874, XXI, p. 2.]

Vogel. Untersuchungen über das Wesen, die Behandlung und die Verbreitung der asiatischen Brechruhr. Nach Beobachtungen in München.

[MED. Annalen, 1838, IV, pp. 161–208, 325–]

Weishaar. Die Cholera in München.

[MED. Corresphl. d. württemberg. aerztl. Vereins, 1837, VII, pp. 409–415.]

Cholera-Bericht (München).

[JAHRB. für Kinderheil. und physische Erziehung, Leipzig, 1874, VIII, pp. 36–51.]

Cholera (Die) in München.

[DEUTSCHE Klinik, 1854, VI, p. 562.]

Plan über die Verbreitung der Cholera in der königlichen Haupt- und Residenz-Stadt München, 1836–37, etc. [*München*, 1838.]

Tags-Rapport über den Stand der Brechruhr-Kranken in der königlichen Haupt- und Residenz-Stadt München und den Vorstädten, vom 25sten October 1836 bis 21sten Januar 1837. fol. *München*.

Nassau.

Pranque (J. B. v.) Die europäische und asiatische Cholera in den Jahren 1855–56.

[MED. Jahrbr. f. Nassau, 1858, pp. 94–125.]

——— Die europäische Cholera in den Jahren 1857–59.

[MED. Jahrbr. f. Nassau, 1863, pp. 137–]

Neudorf.

Robert (A.) Histoire du choléra de Neudorf, 1855. 8°. *Strasbourg*, 1855.

Niederurg.

Pudon. Die Cholera im Kreise Niederung.

[MED. Zeitung, Berlin, 1857, pp. 137–]

mberg.

hner. Ueber das Auftreten der Cho-a im allgemeinen Krankenhause in rnberg.
ERETTL. Intell.-Bl., 1854, I, pp. 353-356, 378-382, 144-448, 449-455.]

riesenthal.

müller (G.) Die Cholera-Epidemie in berwiesenthal im Oktober und Novem-r 1836 beobachtet und beschrieben. *Leipzig*, 1837.

zko.

enemann (H. W.) Genius Epidemicus nd Cholera im Kreise Oletzko (Kreis-adt Marggrabowa) während des Jahres 48.
ALLG. med. Centr.-Zeitg., 1849, XVIII, pp. 33-37.]

aburg.

oop (E.) Die Cholera-Epidemie zu Os-abrück in den Monaten Julius, August, eptember und October 1859. 8°. *Osna-rück*, 1860. L.

—— Bericht über die in den Monaten ugust und September 1866 in der Stadt snabrück vorgekommenen Cholera-älle.
ZEITSCHR. f. pract. Heilk., 1867, IV, pp. 134-147.]

latinate.

rtin (A.) Die diesjährigen Cholera-Epidemieen in der Pfalz.
ERETTL. Intell.-Bl., München, 1867, XIV, pp. 564-566.]

trikof.

'asserfuhr (H.) Bericht über die Lei-stungen des städtischen Cholera-Lazareths zu Petrikof bei Stettin in der Epidemie von 1866.
[BERLIN. klin. Wochenschr., 1867, IV, p. 195.]

sen.

irsch. Mittheilungen über die Cholera-epidemie von 1873 in der Weichselgegend.
[VERHANDL. d. Berlin. med. Gesellsch., 1874, V, pp. 63-66.]

aczorowski (v.) Bericht über die Cholera-Epidemie des Jahres 1866 in Posen.
[BERLIN. klin. Wochenschr., 1872, IX, pp. 15-30.]

ericht über die Cholera in Posen im Jahre 1848, zusammengestellt nach den Erfahrungen der Dr. C. Van Baren, Fliess, [etc.] 8°. *Posen*, 1849.

Prenslow.

Löwenhardt (R.) Mittheilungen über die Cholera-Epidemie in Preuzlau.
[MED. Zeitg., 1853, pp. 131-133, 153-155, 157-159.]

Prussia.

Becker (F. W.) Letter on the cholera in Prussia. 8°. *London*, 1832.

Brauser (H.) Die Cholera-Epidemie des Jahres 1852 in Preussen. Statistische Zusammenstellung aus den Acten des königlichen Ministeriums der geistlichen, Unterrichts- und Medicinal-Angelegenheiten. Mit einem Vorwort von Dr. Barez. Mit einer Karte und zwei Tabellen. 8°. *Berlin*, 1854. L.

—— Statistische Mittheilungen über den Verlauf der Cholera-Epidemieen in Preussen, mit einem Vorwort von Dr. Houselle. 8°. *Berlin*, 1862. L.

Hirsch (A.) Das Auftreten und der Verlauf der Cholera in den preussischen Provinzen Posen und Preussen während der Monate Mai bis September 1873. Reise-Bericht. 8°. *Berlin*, 1874. L.

Hoffmann (J. G.) Die asiatische Cholera im preussischen Staate, 1831.
[BERLIN. Akad. d. Wiss., Abh., 1832, LIV; *also*, reprint in 4°, Berlin, 1833.]

Holscher (G. P.) Mittheilungen über die asiatische Cholera. Ein Auszug aus Berichten über eine im Auftrage der königlich hannoverschen Immediat-Commission gegen die Cholera unternommenen Reise in gesunde und inficirte königlich preussischen Provinzen. 8°. *Hannover*, 1831. L.

Lange. Zur Cholera-Statistik in Preussen.
[ALLG. med. Central-Zeitung, 1858, XXVII, pp. 277-278.]

Schneemann (C.) Beiträge zur Kenntniss und Behandlung der asiatischen Cholera. Gesammelt während einer, auf Veranlassung der königlich hannoverschen Immediat-Commission unternommenen Reise, in die von jener Krankheit heimgesuchten Gegenden Ost-Preussens. 8°. *Hannover*, 1831. L.

Schneller. Einiges über die Cholera-Epidemie an den Weichseldurchbrüchen auf dem Marienburg-Dirschauer Delta.
[DEUTSCHE Klinik, 1856, VIII, pp. 56-59, 65-66.]

Szrant (V.) Die Cholera in ihrer Vertheilung auf die einzelnen Bezirke des

Szrant (V.)—continued.
preussischen Staates, mit Rücksicht auf die Bodenverhältnisse. 8°. *Halle*, 1874.

Wagner (W.) Die Verbreitung der Cholera im preussischen Staate; ein Beweis ihrer Contagiosität. 8°. *Berlin*, 1832. L.
[Map wanting.]

——— Neuere Verbreitung der Cholera im preussischen Staate.
[MED. Zeitung, Berlin, 1832, pp. 5–6, 18, 49, 58, 73; 1833, pp. 32, 80.]

Watson. Alleged outbreak of the cholera in Prussia.
[LONDON Med. Gaz., 1848, XLI, pp. 85–86.]

[Cholera-]Karte vom preussischen Staate. (Mit genauer Bezeichnungen der Gegenden, wo die Cholera geherrscht hat.) imp. fol. *Berlin*, 1827.

Kurze Uebersicht des Seitens des königlich preussischen Staates zur Abwendung der durch die asiatische Cholera drohenden Gefahr erlassenen Verordnungen, nebst einer Anweisung über das diätetische Verhalten und über die unverzüglich zu leistende Selbsthülfe im Falle des Erkrankens. Zunächst für die Bewohner des Grosherzogthums Posen. 8°. *Posen*, 1831. L.
[In German and in Polish text.]

Stand der Cholera in Preussen.
[ALLG. med. Central-Zeitung, 1872, XLI, pp. 1251–1252; 1873, XLII, pp. 714, 737, 761, 810, 834–836, 858–859, 869–870.]

Uebersichts-Karte der Verbreitung der Cholera morbus im preussischen Staate bis zum 1. October 1831. fol. *Dantzig*, 1832.

Quedlinburg.

Wolff. Bericht über die Cholera-Epidemie des Jahres 1866 in Quedlinburg. 8°. *Quedlinburg*, 1867.

Querfurt.

Schraube (O.) Die Choleraepidemie in der Stadt Querfurt und Umgegend während des Sommers 1866.
[DEUTSCHE Klinik, Beilage, 1866, XVIII, pp. 81–86; 1867, XIX, pp. 1–31.]

Rastadt.

Haug. Beiträge zu den geschichtlichen Momenten beim Auftreten der Cholera in Rastatt.
[MITTHEILGN. d. bad. ärztl. Vereins, Karlsruhe, 1854, VIII, pp. 145–149, 161–166.]

Ratisbon.

Cholera (Die) in Regensburg.
[AERZTL. Intllgz.-Bl., München, 1854, I, pp. 419–420.]

Rebdorf.

Lutz. Die Cholera-Epidemie im K. Arbeitshause Rebdorf im Jahre 1874.
[AERZTL. Intell.-Blatt, München, 1874, XXI, pp. 181–185, 191–195.]

——— The same. 8°. *München*, 1875.

Reichshofen.

Kuhn (J.) *et* **Langenhagen** (O. de) Rapport médical sur l'épidémie de choléra qui a régné à Reichshoffen et dans les environs en 1855. 8°. *Strasbourg*, 1856.

Rhin (*Bas-*).

Tourdes (G.) Rapport sur les épidémies qui ont régné en 1866 dans le département du Bas-Rhin.
[GAZ. méd. de Strasbourg, 1867, pp. 2–3.]

Rostock.

Krüger-Hanson (B. C.) Praktische Erfahrungen und Bemerkungen über die Cholera in Rostock. 8°. *Güstrow*, 1831.

Schröder. Bemerkungen über die Verbreitung der Cholera im St. Catharinen-Stifte zu Rostock während der Epidemie von 1859.
[CORRESPONDENZ-BLATT der deutschen Gesellschaft f. Psychiatrie, 1861, pp. 12–13.]

Sandhofen.

Alt. Die Cholera in Sandhofen. Ein Beitrag zur Ansteckungsfähigkeit der Seuche. (Mit einem Ortsplane.
[MITTHEILGN. d. bad. ärztl. Vereins, Karlsruhe, 1868, XXII, pp. 73–75.]

Saxony.

Günther (R.) Die indische Cholera in Sachsen im Jahre 1865. Auf Grund amtlicher Mittheilungen und eigener Wahrnehmungen dargestellt. 8°. Leipzig, 1866.

Pettenkofer (M.) Die sächsischen Cholera-Epidemien des Jahres 1865.
[ZTSCHR. f. Biologie, 1866, II, pp. 75–84.]

Reinhard (H.) Die Verbreitung der Cholera im Königreiche Sachsen und die Erfahrungen der Jahre 1865–66.
[4. JAHRESBERICHT des Landes-Medicinal-Collegiums über das Med.-Wesen im Königreich Sachsen, 1870–71, Dresden, 1874, pp. 14–[illegible] Karte); *also*, reprint in 8°. Dresden, 1874.

Wagner. Nachricht über einige in Zittauer Kreise (des Herzogthums Sachsen) vorgekommene epidemische Cholera.
[LITTER. Ann. d. gesam. Heilk., [illegible] –455.]

ringen.

h. Bericht über die herrschenden nkheiten in meinem Bezirk (Schwengen) während des zweiten Semesters Jahres 1839: Cholera, Gastromalacia.
rn. Correspbl. d. württemberg. aerztl. Vereins, 1840, x. pp. 10–11.]

a.

idt (J.) Ueber die asiatische Cholera ihrem Uebertritte in Schlesiens südliche Gränzen. Ein Sendschreiben seine Amtsgenossen in der Provinz. *Breslau*, 1831. L.

bachtung der Cholera im Steinauer rise in Schlesien.
ED.-CHIR. Zeitung, 1832, III, pp. 14–16, 23–31.]

r.

ie (J.) Die epidemische Cholera in ren elementaren Lebenseigenschaften d in ihrer physiologischen Behandngsmethode, aus der grossen Epidemie n Speyer 1873 dargestellt. 8°. *Würzrg*, 1874. L.

lhäuser (F. A.) Ueber Epidemieen d Cholera, insbesondere über Chora in Speier 1873. 8°. *Mannheim*, 75. L.

in.

den. Bericht über die Cholera-Epiemie in Stettin im Jahre 1866. 8°. ettin, 1867. L.

— Ueber die Cholera des Jahres 1871 Stettin und auf dem Franklin.
ERL. klin. Wochenschr., 1872, IX, p. 396.]

ides (F. G. F.) Beitrag zur Beantworing der Frage: ob die Cholera ansteckend sei? Zu einem Binnen kurzem m Drucke zu übergebenden Gesammterke über die Cholera von einem Vere Stettiner Aerzte, nach den währnd des Verlaufes der Epidemie in Stetn gemachten Erfahrungen. 8°. *Stetn*, 1832. L.

demische (Die) Cholera in Stettin im ahre 1831. Von einem Vereine prakscher Aerzte. 8°. *Stettin*, 1831. L.

teritz.

ze (C. R.) Die Choleraepidemie von 866 in Stötteritz bei Leipzig. 8°. *Leipig*, 1867. L.

lsund.

selberg (E. von). Die asiatische Choera im Regierungsbezirk Stralsund.

Haselberg (E. von)—continued.
Ein Beitrag zur Contagiositätsfrage. 8°. *Stralsund*, 1851.

Strasbourg.

Bissen. Le choléra à Strasbourg en 1854.
[GAZ. méd. de Strasbourg, 1854, XIV, pp. 273–282, 333–338.]

Lereboullet (A.) Lettre sur l'apparition du choléra à Strasbourg.
[GAZ. méd. de Paris, 1849, IV, pp. 699–700.]

Spindler (J. B. A.) *Le choléra à Strasbourg en 1849. Envisagé sous le point de vue de son mode de propagation. 4°. *Strasbourg*, 1850. L.

Stamm. Die Cholera in Strasburg [1849].
[NEUE Zeitg. f. Med. und Med.-Reform, 1849, I, pp. 733–734.]

Stuttgart.

Clesa. [Jahresberichte . . . Katharinenhospitale zu Stuttgart.]
[MED. Correspbl. d. württemb. aerzt. Vereins, 1834, III, p. 291; 1835, IV, p. 104, V, p. 205; 1844, XIV, p. 233; 1854, XXIV, p. 363.]

Köstlin (P.) Die asiatische Cholera zu Stuttgart im Jahre 1854.
[MED. Correspbl. d. württemb. aerztl. Vereins, 1855, XXV, pp. 203–207.]

Thuringia.

Pfeiffer (L.) Die Choleraverhältnisse Thüringens.
[ZTSCHR. f. Biologie, 1867, III, pp. 145–240, 4 maps.]

——— The same. roy. 8°. *München*, 1867. L.

——— Die Cholera in Thüringen und Sachsen während der dritten Cholerainvasion 1865–1867. 8°. *Jena*, 1871. L.

Tiefenthal.

Mittheilungen über Cholera im engeren Verwaltungsbezirke Marktheidenfeld, 1866. Speciell: Cholera-Epidemie zu Tiefenthal. 8°. *Würzburg*, 1867. L.

Torgau.

Riecke. Die Cholera-Epidemie in Norddeutschland 1850, mit besonderer Rücksicht auf die Epidemie zu Torgau. *Nordhausen*, 1850.

Treves.

Neumann (K. G.) Cholera in Trier, 1849.
[RHEINISCHE Monats. f. prakt. Aerzte, 1850, IV, pp. 285–302.]

Ueckermünde.

Patczek (F.) *Observationes de cholera asiatica in epidemia Ueckermuendensi. 8°. *Gryphiae* [1866]. C.

Utzmemmingen.

Klein. Bericht über die Cholera in Utzmemmingen.

[MED. Corresphl. des württemberg aerztl. Vereins, 1866, XXXVI, p. 305.]

Teuffel (J.) Die Choleraepidemie zu Uzmemmingen O. A. Neresheim im Jahre 1866.

[MED. Corresphl. des württemberg. aerztl. Vereins, 1867, XXXVII, pp. 129–132, 141–144, 149–150, 157–160, 165–169, 223–228.]

——— * The same. 4°. *Stuttgart*, 1867. L.

Unterfranken.

Cholera (Die) in Unterfranken während des laufenden Sommers.

[AERZTL. Intell.-Bl., 1866, XIII, pp. 509–511.]

Vaihingen.

Keyler. Bericht über die in den Monaten August und September in Vaihingen a. E. grassirende Brechruhr.

[MED. Corresphl. des württemberg. aerztl. Vereins, 1849, XIX, pp. 210–211.]

Weimar.

Pettenkofer (M. v.) Die Cholera vom Jahre 1866 in Weimar. 8°. *Weimar*, 1867.

Cholera-Epidemie (Die) zu Weimar im Jahre 1866. Bericht der von dem ärztlichen Verein zu Weimar niedergesetzten Cholera-Commission. Im Auftrage des Vereins herausgegeben von L. Pfeiffer. 4°. [*n. p.*,] 1866? L.

Witzenhausen.

Rothamel (G. C. F.) Die Cholera-Epidemie im Physicats-Bezirk Witzenhausen, im Herbst 1850.

[DEUTSCHE Klinik, 1855, VII, pp. 78–79, 88–90, 100–101.]

Würtemberg.

Elsässer. Die asiatische Cholera Württembergs im Jahre 1854.

[MED. Corresphlatt. d. württemberg. aerztl. Vereins, 1855, XXV, pp. 169–173, 177–181, 185–189, 193–198, 201–203.]

Riecke (V. A.) Die Cholera in Würtemberg in den Monaten Juni bis September 1849.

[MED. Corresphlatt. d. württemberg. aerztl. Vereins, 1849, XIX, pp. 216–220.]

Würzburg.

Gock (H.) Die Cholara-Epidemie zu Würzburg, Juli, August und September 1873.

[VERHANDL. der phys.-med. Gesellschaft in Würzburg, 1874, VI, pp. 49–81, 3 Taf.]

Gock (H.)—continued.

——— * The same. 8°. *Würzburg*, 1874. L.

Grashey (H.) * Die Cholera-Epidemie im Juliusspitale zu Würzburg (August-Oktober 1866).

[WÜRZBURGER medicinische Zeitschrift, 1867, VII, pp. 135–167, pl. iii–v.]

——— The same. 8°. *Würzburg*, 1867. L.

Zeitz.

Richter (A.) Choleraepidemie under den Arbeitern der Zeitzer Zuckerfabrik.

[ARCHIV der Heilkunde, 1867, pp. 472–475.]

Zwickau.

Günther (R.) Die indische Cholera im Regierungsbezirke Zwickau im Jahre 1866. 4°. *Leipzig*, 1869. L.

GREAT BRITAIN.

Coste et Lowenhayn. Mémoire sur le traitement du choléra-morbus, observé en Angleterre et en Écosse. 8°. *Paris*, 1832.

Delpech (J.) Étude du choléra-morbus en Angleterre et en Écosse pendant les mois de janvier et février 1832. 8°. *Paris*, 1832. L.

Howison (W.) Remarks on the malignant cholera in Ireland and Scotland.

[LANCET, London, 1832–33, I, pp. 203–207.]

Löwenhayn (H. A. M. J.) Beobachtungen über die Cholera-Asphyxie in England und Schottland. Mit einen Vorworte von F. A. Ritgen. 8°. *Giessen*, 1833.

Analyses of reports on cholera.

[LONDON Med. Gaz., 1833, XI, pp. 50–56, 81–84, 115–119, 149–151.]

Cholera (The) and the government.

[LONDON Med. & Surg. Jour., 1832, I, pp. 833–834.]

Cholera (The) in the United Kingdom in 1854.

[LANCET, 1854, I, n. s., pp. 408–409, 431, 459–461, 505, 557–558.]

History of the progress of the malignant cholera in England and Scotland.

[LANCET, London, 1831–32, I, pp. 669–684.]

Aberdeenshire.

Paterson (J.) Observations on cholera

erson (J.)—continued.
it appeared at Collieston and Footdee, Aberdeenshire.
[Edin. Med. & Surg. Jour., 1838, xlix, pp. 408–412.]

by-de-la-Zouch.

medy (J. M. S.) A lecture on cholera at Ashby-de-la-Zouch. *Ashby*, 1832.

nasloe.

urkey (E.) Brief notes of the epidemic cholera in Ballinasloe.
[Dublin Med. Gaz., 1850, xlvi, pp. 22–24.]

rnsley.

ller (M. T.) Observations on the spread of cholera in Barnsley, during the year 1849.
[Med. Times & Gaz., 1853, vii, n. s., pp. 371–372.]

dford.

ower (W.) Cholera at Bedford.
[Brit. Med. Jour., 1858, p. 729.]

fast.

lcolm. Asiatic cholera. [Analysis of a series of cases admitted into Belfast hospital.]
[Dublin Med. Press, 1849, xxii, pp. 295–296.]

urphy (W.) Asiatic cholera in the Belfast general hospital.
[Med. Times, 1849, xx, pp. 157–159.]

dd (S.) Extract from [a report on cholera] to the board of guardians of the Belfast Union.
[Dublin Med. Press, 1849, xxi, pp. 242–244.]

ompson (T.) Practical remarks on the epidemic cholera in Belfast. 8°. *Belfast*, 1832.

ston.

igh (W.) An authentic narrative of the melancholy occurrences at Bilston, in the county of Stafford, during the awful visitation in that town by cholera in 1832. To which are added the proceedings of the local board of health, etc. 8°. *Wolverhampton*, 1833. L.

idport.

ttard (S. R.) Personal experience of cholera.
[Med. Circular, 1855, vii, pp. 65–67, 84, 114–115, 173–174, 203–204.]

Bristol.

Budd (W.) Asiatic cholera in Bristol in 1866.
[Brit. Med. Jour., 1867, i, p. 413.]

——— The same. 4°. [*s. p.*] L.

Davies (D.) The case of cholera imported from Rotterdam to Bristol.
[Med. Times & Gaz., 1866, i, pp. 467–468.]

Symonds (J. A.) Treatment of malignant cholera at the Bristol cholera hospital.
[Lancet, London, 1832–33, i, pp. 142–144.]

——— Remarks upon the progress and causes of cholera, as it occurred in Bristol, in 1832.
[Trans. Provinc. Med. & Surg. Assoc., 1835, iii, pp. 170–193.]

Cawston.

Cox (W. T.) Cholera at Cawston.
[London Med. Gaz., 1832, x, pp. 356–357.]

Clare.

Williams (R.) Report of the rise, progress, and decline, of the malignant cholera amongst the soldiers of the sixty-eighth regiment, at Clare Castle, Ireland.
[Lancet, 1831–32, ii, pp. 681–684.]

Cork.

Bullen (D. B.) Practical observations on the epidemic cholera at Cork. 8°. *London*, 1832.

Cummins (W. J.) Remarks on cholera.
[Dublin Quar. Jour. of Med. Sci., 1867, xliv, pp. 42–57; *also, in* Trans. Cork Med. & Surg. Soc., 1866–67, pp. 28–43.]

Purcell (F. A.) A report of thirty-eight cases of cholera occurring consecutively in the city of Cork during the outbreak of this year (1866); recording the first case and introduction of the epidemic.
[Trans. Cork Med. & Surg. Soc., 1866–67, pp. 48–52; *also, in* Dublin Quar. Jour. of Med. Sci., 1867, xliv, pp. 253–259.]

Cowes.

Hoffmeister *and* Rickards. Notes on the cholera at Cowes.
[Lancet, 1866, ii, pp. 263–264.]

Jeans (J. H.) Notes on cholera at Cowes, Isle of Wight.
[Lancet, 1866, ii, p. 386.]

Cramond Parish.

Balfour (G. W.) Cholera in Cramond Parish.
[Med. Times, 1849, xx, pp. 214–215.]

Cupar-Fife.

Scott (D.) On the varieties, symptoms, and treatment of epidemic cholera, as it appeared in Cupar-Fife.
[EDINB. Med. & Surg. Jour., 1833, XXXIX, pp. 296–301.]

Dublin.

Hayden *and* **Cruise.** Report on cholera, with remarks.
[DUBLIN Quar. Jour. of Med. Sci., 1867, XLIII, pp. 345–408.]

——— ——— Report on the cholera epidemic of 1866, as treated in the Mater Misericordiæ Hospital, Dublin. 8°. *Dublin*, 1867. L.
[Reprint of the preceding.]

Jackson (G.) Appearance of cholera.
[DUBL. Med. Press, 1841, VI, p. 216.]

McCoy (S.) Notes on malignant cholera, as it appeared in Dublin.
[DUBL. Jour. of Med. Sci., 1833, II, pp. 357–375; III, pp. 1–21.]

Saunders (G.) Epidemic cholera. A sketch of the medical history of the 47th regiment.
[MED. Times, 1849, XIX, pp. 249–250.]

Abstract of reports on the late epidemic of cholera, as it occurred in the hospitals of Dublin.
[DUBL. Med. Press & Circ., 1867, supplement to vol. III.]

Cholera in Dublin.
[LONDON Med. & Surg. Jour., 1832, I, pp. 321–322; 1833, II, pp. 82–83.]

Cholera reports of the Dublin hospitals.
[DUBL. Med. Press & Circ., 1867, III, pp. 321–322.]

Dumfries.

Blacklock (A.) On the origin of cholera in Dumfries.
[MONTHLY Jour. of Med. Sci., 1854, IX, 3d s., pp. 291–292, 480–483; 1854, X, pp. 83–84.]

Grieve (J.) On the cholera at Dumfries.
[MONTHLY Jour. of Med. Sci., 1854, IX, 3d s., pp. 381–383, 568–569.]

Grieve (J. [*and others*]). Practical observations on epidemic cholera, as it appeared in Dumfries in 1832, and in 1848.
[MED. Times, 1849, XIX, pp. 584–586, 630, 647, 668; XX, pp. 167, 187, 207.]

Edinburgh.

Craigie (D.) Observations, pathological and therapeutic, on the epidemic cholera, as it has prevailed in Edinburgh and its vicinity.
[EDINB. Med. & Surg. Jour., 1833, XXIX, pp. 19–70.]

Knapp (J.) Cholera at Edinburgh.
[LONDON Med. Gaz., 1832, IX, pp. 721–722.]

England.

Badeley (J. C.) On the rewards to cholera doctors.
[LANCET, 1849, II, pp. 646–647.]

Bishop (E.) The recent outbreak of cholera.
[PROV. Med. & Surg. Jour., 1851, p. 585.]

Black (J.) Observations on the pestilential cholera of 1832–3.
[PROV. Med. & Surg. Jour., 1848, pp. 29–32.]

Dodd (H. W.) Observations on the malignant cholera in England, and its treatment.
[LANCET, 1831–32, I, pp. 795–798.]

Dubuc (É.) Rapport adressé à l'intendance sanitaire de Rouen, sur le choléra morbus observé à Sunderland, Newcastle et les environs. 8°. *Rouen*, 1832. L.

Farr (W.) *See* **Report** [etc.]

Greenhow (T. M.) Cholera, as it recently appeared in the towns of New Castle and Gateshead; including cases illustrative of its physiology and pathology, with a view to the establishment of sound principles of practice. 8°. *Philadelphia*, 1832. L.
[Originally published, 8°, London, 1832.]

Latour (A.) Organisation, conséquences et resultats des visites médicales préventives contre le choléra épidémique en Angleterre.
[L'UNION méd., 1853, VII, pp. 477–478.]

Maclean (W.) No Asiatic cholera in England. Triumph of truth.
[LOND. Med. & Surg. Jour., 1832, I, pp. 118–119.]

Randell (H. K.) Remarks on the existence of cholera in England, with cases.
[LANCET, 1830–31, II, pp. 811–813.]

Spitta (R. J.) Brief remarks on cholera: being the result of observations during the two last outbreaks of cholera in England, and an attempt to advance the theory of that disease which shall lead to a more consistent method of treatment. To which is added a short table of practical rules for general use during an epidemic. 8°. *London*, 1866. L.

Stodart (E.) Characters which prove the prevailing cholera to be a new disease in England.
[LANCET, 1831–32, I, pp. 867–869.]

atton (T.) History of the epidemic olera in Chatham, Rochester, and trood, in 1849.

[Edinb. Med. & Surg. Jour., 1851, LXXV, pp. 253–284.]

kes (J.) An account of the disease rmed cholera morbus, from its first ppearance at Sunderland to its final eparture from Northumberland and urham, with the daily official reports f its destructive ravages in New Castle nd Gateshead, &c. 8°. *New Castle*, 832.

olozan. Y a-t-il à l'heure actuelle pidémie de choléra en Angleterre?—larche actuelle du choléra.

[Gaz. méd. de Paris, 1853, VIII, 3e s., pp. 619–620.]

illiams (P. H.) Report on cholera.

[Prov. Med. & Surg. Jour., 1850, pp. 505–510.]

olera (The).

[Dublin Med. Press, 1853, XXX, pp. 235–239.]

olera (The) epidemic of 1853–54.

[Registrar-Genl.'s reports, London, 1854, pp. 74–176.]

olera in England.

[Monthly Homœopathic Rev., London, 1866, X, pp. 513–525.]

olera varieties.

[London Med. Gaz., 1832, IX, pp. 833–835.]

rst appearance of the epidemic cholera n the coast of England.

[Lancet, 1832, I, pp. 630–632.]

ficial reports of twelve cases of cholera, ccurring at Sunderland and Newcastle, nd their neighbourhood, in which death as the result. With one case of re-overy.

[Lancet, 1831–32, I, pp. 543–553.]

eport of the commissioners appointed o inquire into the causes which have ed to, or have aggravated the late out-reak of cholera in the towns of New-astle-upon-Tyne, Gateshead, and Tyne-outh. (Presented to both houses of arliament by command of her majesty.) 8°. *London*, 1854. L.

eport of the committee for scientific inquiries in relation to the cholera epi-demic of 1854. 8°. *London*, 1855. L.

—— Appendix to report of the committee for scientific inquiries in relation to the cholera-epidemic of 1854. 8°. *London*, 1855. L.

Report of the general board of health on the epidemic cholera of 1848 and 1849. 8°. *London*, 1851. L.

—— Appendix (A) to the report of the general board of health on the epidemic cholera of 1848 and 1849, by Dr. Sutherland. 8°. *London*, 1851. L.

—— Appendix (B) to the report of the general board of health on the epidemic cholera of 1848 and 1849. 8°. *London*, 1850. L.

—— Appendix (C) to the report of the general board of health on the epidemic cholera of 1848 and 1849. 8°. *London*, 1852. L.

Report of the medical council in relation to the cholera epidemic of 1854. 8°. *London*, 1855. L.

Report on the cholera epidemic of 1866 in England. Supplement to the twenty-ninth annual report of the registrar-general . . . (Presented to both houses of parliament by command of her majesty.) 8°. *London*, 1868. L.

Report on the mortality of cholera in England in 1848–49. By W. Farr. 2 parts. 8°. *London*, 1852. L.

Reports on various outbreaks of cholera, with particular reference to the sanitary circumstances under which they occurred.

[Rep. Priv. Counc., 1866 (appendix), pp. 242–368.]

Exeter.

Shapter (T.) The history of the cholera in Exeter in 1832. 8°. *London*, 1849. L.

Finglass.

Moore (C.) A sketch of the recent outbreak of cholera at Finglass.

[Dublin Quar. Jour. of Med. Science, 1854, XVIII, pp. 330–341; *also*, reprint in 8°, Dublin, 1854.]

Glasgow.

Adams (J. M.) Observations on the epidemic cholera of 1848–9, chiefly as it prevailed in the 13th medical district of the city of Glasgow parish.

[Monthly Jour. of Med. Sci., 1849, III, n. s., pp. 1012–1020, 1 table, 1087–1092, 3 tables.]

Auchincloss (W.) Report of the epidemic cholera, as it appeared in the town's hospital of Glasgow, in February and March, 1832, with cases and observations.

[Glasgow Med. Jour., 1832, V, pp. 113–140.]

Bryce (C.) An examination into the etiology of cholera, founded on the phenomena of the disease, as exhibited during its prevalence in Glasgow and suburbs.
[GLASGOW Med. Jour., 1832, v, pp. 262–298.]

Cleland (J.) Conspectus of cholera in Glasgow, being a table of weekly cholera cases occurring in the whole district.
[EDINB. Med. & Surg. Jour., 1833, XXXIX, pp. 503–506.]

Easton (J. A.) Report of diseases among the poor of Glasgow, during the months of May, June, and July, 1832.
[GLASGOW Med. Jour., 1832, v, pp. 442–452.]

Lawrie (J. A.) Reports of the Albion street cholera hospital.
[GLASGOW Med. Jour., 1832, v, pp. 309–331, 416–429.]

——— The same. 8°. *Glasgow*, 1832. L.

M'Etheran (J.) Report of the epidemic of cholera in the sixteenth district of the city of Glasgow, from December 20th to February 21st, 1848–49.
[MONTH. Jour. of Med. Sci., Edinburgh, 1848–49, IX, pp. 1165–1166.]

M'Gregor (R.) Two clinical lectures delivered upon the cases of cholera treated in the royal infirmary of Glasgow during the late epidemic.
[LONDON Med. Gaz., 1849, XLIV, pp. 141–145.]

Marshall (J.) Observations on cholera, as it appeared at Port Glasgow, during the months of July and August, 1831, illustrated by numerous cases. 8°. *Edinburgh*, 1831. L.

Moore (S. J.) Recent cases of cholera at Ibrox.
[GLASGOW Med. Jour., 1867, I, n. s., pp. 386–403.]

Watt (G.) On the origin and spread of malignant cholera in Glasgow and its neighbourhood.
[GLASGOW Med. Jour., 1832, v, pp. 298–308, 364–394.]

Cholera at port Glasgow (?).
[LONDON Med. Gaz., 1831, VIII, pp. 571–572.]

Statistics of the malignant cholera in Glasgow, 1848–9.
[LONDON Med. Gaz., 1848, XLIII, pp. 611–613.]

Glass Houghton.

Simpson (J. H.) The cholera at Glass Houghton.
[LANCET, 1859, II, n. s., pp. 448–449.]

Ham (West).

Bain (W. P.) The cholera at West Ham.
[LANCET, 1857, II, n. s., p. 476.]

Elliot (W.) The cholera at West Ham.
[LANCET, London, 1857, II, n. s., pp. 442–443, 568–569; 1858, I, p. 100.]

Macloughlin (D.) Cholera at West Ham.
[LANCET, 1857, II, n. s., pp. 638–639, [illegible] 152.]

Snow (J.) On the outbreak of cholera, Abbey-row, West Ham.
[MED. Times & Gaz., 1857, XV, pp. 417–418 *and in* LANCET, 1857, II, n. s., pp. 419–420.]

Huddersfield.

Taylor. Mode of origin and propagation of the epidemic cholera in Huddersfield and the neighbourhood, in the autumn of 1849.
[MED. Times, 1851, II, n. s., pp. 256–258, 399–402; *also*, reprint in 12°, London.]

Hull.

Alderson (J.) A brief outline of the history and progress of cholera at Hull, with some remarks on the pathology and treatment of the disease. 8°. *London*, [illegible].

Hutton.

Keenlyside (R. H.) Cholera at Hutton, its propagation by contagion, &c.
[LONDON MED. Gaz., 1833, XI, pp. 31–[illegible].]

Ireland.

Corrigan (D.) The cholera mania in Ireland: with observations. 8°. [illegible] 1866.

Cranfield (R.) Practical observations on cholera; particularly in reference to the treatment of the disease as it has appeared in Ireland since the year [illegible]. 8°. *Dublin*, 1834.

Green (R.) Cholera in Ireland.
[LANCET, 1836, II, p. 83.]

Jackson (G.) Appearance of cholera [illegible].
[MED. Times, 1841, V, p. 23.]

Kidd. On cholera in Ireland.
[MED. Times, 1849, XX, pp. 25–26.]

Abstract of reports on the late epidemic of cholera.
[DUBLIN Quar. Jour. of Med. Sci., [illegible] 461–522.]

Cholera in Ireland.
[LONDON Med. Gaz., 1832, X, p. 136.]

Cholera [in Ireland]. Abstract [illegible] to an order of the house of commons, dated 2 Feb., 1854;—for a return of reports addressed to the commissioners of poor laws in Ireland, relative to the appearance and spread of cholera in that country, and of all correspondence relating thereon; together with a return of all cases of cholera hitherto reported to the commissioners from each workhouse union in Ireland." (Ordered

olera [in Ireland]—continued.
ouse of commons, to be printed, 16 March, 1854.) fol. [n. p., n. d.] L.

ey (Island of).

ote (J., *jr.*) A slight sketch of the cholera, as it appeared at St. Hilier's, Jersey, in the months of Aug. and Sept. 1832, with a topographical description of the island.
[London Med. & Surg. Jour., 1832, III, pp. 355–364.]

—— Cholera hospital at St. Hilier's.
[London Med. & Surg. Jour., 1833, II, pp. 217–218.]

holera (The) at Jersey.
[Med. Times & Gaz., 1867, I, pp. 203–208.—Dubl. Med. Press & Circ., 1867, III, pp. 253.]

erious outbreak of cholera in Jersey.
[Lancet, 1867, I, pp. 256–257.]

ndal.

roudfoot (T.) Account of the epidemic cholera of Kendal.
[Edinb. Med. & Surg. Jour., 1833, XXXIX, pp. 70–103.]

irkintilloch.

awrie (J. A.) Essay on cholera . . . . containing, in an appendix, the history and treatment of cholera at Kirkintilloch, Scotland. 2d ed. 8°. *Glasgow*, 1832. L.

eeds.

irtwhistle (R.) Treatment of the malignant cholera at Leeds.
[Lancet, 1831–32, II, p. 671.]

imerick.

idd. Outbreak of cholera at Limerick.
[Med. Times, 1849, XIX, pp. 452, 510–511, 584, 619–620.]

isburn.

ampbell (J.) Treatment of cholera at Lisburn.
[Med. Circ., 1854, V, p. 186.]

elso (J. J.) Some remarks on epidemic cholera, as it appeared in and about Lisburn, in 1854.
[Lancet, 1855, II, n. s., pp. 185–196, 222–224.]

tatistics of the cholera at Lisburn—its propagation by contagion.
[London Med. Gaz., 1848, XLIII, pp. 610–611.]

iverpool.

amilton (R.) The epidemics of typhus and cholera in Liverpool.
[Lancet, 1867, II, pp. 608–609, 639–641, 701–702, 731–733.]

M'Cloy (J. W.) Notes on the treatment of 123 cases of cholera in the Liverpool parish infirmary, July and August, 1866.
[Lancet, 1866, II, pp. 178–180.]

Murphy (T. J.) Character and treatment of the malignant cholera at Liverpool. Trial of venous injections.
[Lancet, 1831–32, II, pp. 368–369.]

Nightingale (B.) Treatment of the malignant cholera, at the Liverpool fever hospital.
[Lancet, 1832–33, I, pp. 209–210.]

Weatherhill (T.) Appearance of the cholera in Liverpool.
[Lancet, 1831–32, II, pp. 270–271.]

Cholera (The) at Liverpool.
[Med. Times & Gaz., 1866, I, pp. 527–528, 537, 565, 594; II, pp. 66–67, 125–126.—Lancet, 1866, II, pp. 109, 136.]

Cholera (Die) zu Liverpool im Mai 1866. (Amtlicher Bericht des dortigen bayerischen Consulats an unser Staats-Ministerium des Aeusseren.)
[Aerztl. Intell.-Bl. München, 1866, XIII, pp. 411–412.]

Report from the committee of the Liverpool training school and home for nurses on the cholera outbreak in 1866. 8°. *Liverpool*, 1871. L.

Llanelly.

Brigstocke (C. A.) Notes of a cholera epidemic.
[British Med. Jour., 1872, II, pp. 602–603.]

London.

Badgley (F.) Cholera (?) at Kensington.
[London Med. Gaz., 1832, IX, pp. 862–867.]

Bailey (J. G. [*and others*]). A sketch of the Asiatic cholera, as it broke out at the pauper establishment of Mr. Drouet, Surrey Hall, Tooting.
[Med. Times, London, 1849, XIX, pp. 250–251, 261, 274–275, 279, 354–356.]

Barry (D.) Papers relative to the existence of the malignant cholera in the Cold-Bath-Fields prison.
[Lancet, 1831–32, II, pp. 455–457, 492–493.]

—— Cholera in Cold-Bath-Fields prison (?)—saline treatment.
[London Med. Gaz., 1832, X, pp. 487–490.]

—— Reported cholera in Cold-Bath-Fields-prison.
[London Med. Gaz., 1832, X, pp. 513–514.]

Birtwhistle (J.) Case of malignant cholera in the Mile-End road.
[Lancet, 1832, I, pp. 866–867.]

Blair (C. E.) The cholera.
[Lancet, 1832, I, pp. 765–766.]

Budd (G.) Statistical account of cholera, in the Seaman's Hospital, in 1832.
[MED.-CHIR. Trans., London, 1839, XXII, pp. 110–123.]

Chesterton (G. L.) Cholera in Cold-Bath-Fields prison.
[LONDON Med. Gaz., 1832, X, pp. 548–550.]

Church (W.) Report on the cases of cholera treated in the wards of St. Bartholomew's Hospital during the epidemic of 1866.
[ST. BARTH. Hospl. Repts., 1867, III, pp. 171–212.]

Gane (J.) Remarks on the appearance of cholera in London.
[LANCET, 1831–32, I, pp. 767–768.]

Gaselee (C.) Cholera in Southwark.
[LONDON Med. Gaz., 1832, IX, pp. 762–765.]

Gavin (H.) Cholera and typhus fever. Tables showing the comparative loss entailed on the population of London by the visitation of cholera in 1832 and ordinary typhus fever.
[JOUR. of Pub. Health, 1849, II, pp. 24–26.]

Haller (C.) Die Cholera-Epidemie des Jahres 1854 in London, nach den von dem allgemeinen Gesundheitsrathe (General Board of Health) veröffentlichten und von dem k. k. Ministerium des Innern der k. k. Gesellschaft der Ärzte in Wien mitgetheilten Berichten.
[ZEITSCH. d. k. k. Ges. d. Aerzte, Wien, 1858, pp. 369–376, 388–397, 409–413.]

Halma-Grand. Relation du choléra-morbus épidémique de Londres; accompagnée d'un plan de Londres indiquant la marche de l'épidémie. 8°. *Paris*, 1832.

Hill (J.) The cholera in the Peckham House asylum.
[LANCET, 1848, II, p. 618.]

Hoblyn (F. P.) Cholera at Notting Hill.
[MED. Times, 1846, XIV, pp. 320–321.]

Hodgkin (T.) Hints relating to the cholera in London. 8°. *London*, 1832.

Hope (J.) Supposed cholera in Marylebone infirmary.
[LONDON Med. Gaz., 1832, IX, pp. 893–896.]

Johnson (C.) The cholera at Limehouse.
[LANCET, 1837–38, I, pp. 240–242.]

Kidd (C.) Some notes on cholera in London.
[DUBLIN Quar. Jour. of Med. Science, 1854, XVIII, pp. 341–350.]

King. The epidemic of 1849 illustrated by St. Giles's, and suggestive of the gaseous origin of cholera.
[MED. Times, 1850, I, n. s., pp. 197–200.]

King—continued.

——— The locality of cholera in ... in 1832 and 1849.
[MED. Times, 1850, I, pp. 138–139, 644–6...]

M'William (J. O.) A brief report of cholera and diarrhœa among the ... of the water guard and watch ... partments of the customs in ... during the epidemy of 1854.
[MED. Times & Gaz., 1855, XI, n. s., pp. 33–3...]

Marsden (W.) Malignant cholera at ... hospital in Greenville street, ...
[LANCET, 1832–33, I, pp. 598–599.]

Michele (J. G.) Cases of cholera ... Pancras, with some observations.
[LONDON Med. Gaz., 1832, IX, pp. 857–8...]

Ogle (J. W.) Reminiscences of the ... at St George's hospital in the ... and 1854.
[MED. Times & Gaz., 1865, II, pp. 597–... 704–706; *also*, reprint, London, ...]

Ousby (J.) Cholera in Cold-Bath ...
[LONDON Med. Gaz., 1832, X, p. 712.]

Parkes (E. A.) Report on the ... of cholera in London.
[LONDON Med. Gaz., 1850, XLV, pp. ...]

Popham (W. H.) A brief account ... symptoms presented by cholera ... the pauper children at Drove ... lishment, Tooting.
[LANCET, 1849, I, n. s., p. 153.]

Powell (R. H.) On the climat ... don during the prevalence of ... cholera in August, 1849. ... 1851.

Radcliffe (J. N.) Professor Pet... on the East London cholera ... 1866.
[LANCET, 1874, I, pp. 567–568.]

Ray (C.) Cholera in London. ... of fifty cases.
[LANCET, 1841–42, II, pp. 816–817.]

Reade (W. W.) Notes from the ... hospital, Southampton.
[LANCET, 1866, II, pp. 181–182.]

Richards (C. C.) Remarks on ... the East-End of London.
[DUBL. Med. Press & Circ., 1867, ...]

Robertson (W.) Statistics of the ... hospital in Surgeon Square, ... 28 to Dec. 16.
[MONTHLY Jour. of Med. Sci., 1... 455–460, 5 tables.]

Ross (G.) Observations on the ... epidemic cholera.
[MED. Times, 1849, XX, pp. 33–34; ... XXI, pp. 55–56, 166–167.]

ley (S. W.) Report on the cholera patients admitted into the Middlesex hospital during the year 1854. 8°. *London*, 1855. L.

lith (B.) Statistics of the cholera in the metropolis for 1848, 1849.
[Med. Times, 1849, xx, pp. 355–360.]

lith (E.) On the relations of the mortality from cholera in London, to the general mortality and temperature.
[Med.-Chirurg. Trans., London, 1855, xxxviii, pp. 101–109, 2 tab.]

low (J.) The cholera at Albion Terrace.
[London Med. Gaz., 1849, xliv, pp. 504–505.]

—— The cholera near Golden-square, and at Deptford.
[Med. Times & Gaz., 1854, ix, n. s., pp. 321–322.]

—— Cholera and the water supply in the south districts of London, in 1854. 8°. *London* [1856]. L.

Stevens (W.) On the cholera in Cold-Bath-Fields prison, and on the saline treatment of that disease.
[London Med. Gaz., 1832, x, pp. 455–456, 657–665.]

Stewart (A. P.) Attendance on cholera patients at dispensaries.
[Lancet, 1849, ii, p. 220.]

—— Cholera at the dispensaries,—remuneration of the medical officers.
[Lancet, 1849, ii, pp. 135–136.]

—— Cholera in St. James's.
[Med. Times & Gaz., 1854, ix, n. s., p. 351.]

—— Cholera in the Middlesex hospital.
[Med. Times & Gaz., 1854, ix, n. s., pp. 363–365.]

Sutherland. Report to the general board of health on the sanitary condition of the epidemic districts in Newington Union. [*London*,] 1852.

—— Report on epidemic cholera in the metropolis in 1854 . . . . Presented to parliament 1855. 8°. [*London*, 1855.]

Sutton (H. G.) Report on the clinical characters of the cholera of 1866, as studied in Miss Sellon's East London cholera hospital.
[Rep. Priv. Counc., 1866 (appendix), pp. 369–453.]

Webster (J.) Cholera in St. James's, Westminster.
[Lancet, 1854, ii, n. s., p. 300.]

Account given by the magistrates of the cholera at Cold Bath Fields prison.
[London Med. Gaz., 1832, x, pp. 491–494.]

Appearance of cholera in the metropolis.
[London Med. & Surg. Jour., 1832, i, pp. 80–81.]

Arrival of cholera in London.
[London Med. & Surg. Jour., 1832, i, pp. 88–92.]

Association (The) for the investigation of cholera.
[London Med. & Surg. Jour., 1832, i, pp. 352–354.]

Cholera and the port of London.
[Lancet, 1871, ii, p. 970.]

Cholera (The) at the poor establishment, Tooting.
[London Med. Gaz., 1849, xliii, pp. 59–60.]

Cholera (The) epidemic in London.
[Med. Times & Gaz., 1866, pp. 639–640.]

Cholera (The) in London.
[Dublin Med. Press & Circular, 1866, ii, pp. 159–160, 180.]

Cholera in London.
[Med. Times & Gaz., 1866, ii, p. 197.]

Cholera in London and the vicinity.
[London Med. & Surg. Jour., 1833, ii, pp. 286–287.]

Cholera in London. What has been its effect on the mortality of the year?
[London Med. Gaz., 1833, xi, p. 444.]

Cholera in the London hospitals.
[Med. Times & Gaz., 1866, ii, p. 115.]

Cholera (The) in the metropolitan hospitals.
[Med. Circular, London, 1853, iii, pp. 360–361; 1854, v, pp. 83, 96.]

Cholera (The) Gazette, consisting of documents communicated by the central board of health, with intelligence relative to the disease, etc. Nos. 1–6, January 14 to April 7, 1832. 8°. *London*, 1832. L.

——— The same. 2d ed. *London* [*n. d.*] L.

Data for the history of the present epidemic of cholera in London.
[Lancet, 1866, ii, pp. 242–243.]

Details of cases of cholera in Southwark, Limehouse, and Rotherhithe.
[Lancet, 1831–32, i, pp. 739–741.]

Epidemic of cholera in the East End of London.
[Lancet, 1866, ii, pp. 157–160, 217–219, 273–276.]

Extraordinary outbreak of cholera at Camberwell.
[Med. Times & Gaz., 1866, ii, pp. 586–587.]

Fatality of cholera epidemics in London.
[Lancet, 1867, i, pp. 125–126.]

General report of the sanitary committee of their proceedings under the orders of the privy council of the 21st July last, and the resolutions of the board of the 24th July last, on the outbreak of the cholera in the district. With memoran-

General report, etc.—continued.
dum on the measures proposed by the board of works for the Saint Giles district. 8°. fol. [*Bloomsbury*, 1867.] L.

Letter of the president of the general board of health accompanying a report from Dr. Sutherland on epidemic cholera in the metropolis in 1854, with report. 8°. *London*, 1855. L.

Notes on the cholera epidemic of 1866.
[Clin. Lec. & Rep. of London Hospital, 1866, III, pp. 435–491.]

Progress of cholera in London.
[Med. Times & Gaz., 1866, II, pp. 371–372, 395–396.]

Progress of cholera in the metropolis.
[London Med. Gaz., 1832, IX, pp. 880–882.]

Progress of cholera, Mary-le-bone-job.
[London Med. & Surg. Jour., 1832, I, pp. 180–181.]

Report of cases of epidemic cholera for the last five weeks.
[Med. Times & Gaz., 1853, VII, n. s., pp. 577–578.]

Report on the cholera.
[Med. Times & Gaz., 1854, IX, n. s., pp. 214–215.]

Report (A) on the cholera epidemic of 1866, in the city of London, by H. Letheby, medical officer of health, to the commissioners of sewers of the city of London. 8°. *London*, 1867. L.

Report on the cholera epidemic of 1866 within Hackney district, by John W. Tripe, medical officer of health, (to the sanitary committee of the board of works). 8°. *Hackney*, 1866. L.

Report on the cholera outbreak in the parish of St. James, Westminster, during the autumn of 1854. Presented to the vestry by the cholera inquiry committee, July 1855. 8°. *London*, 1855. L.

Report on the cholera patients admitted into the [Middlesex] hospital during the year 1854. *See* Sibley (S. W.)

Report on the epidemic of cholera in 1866, by John Liddle, medical officer of health to board of works, Whitechapel district, January 21st 1867. 8°. *London*, 1867. L.

Report on the last two cholera-epidemics of London, as affected by the consumption of impure water; addressed to the rt. hon. the president of the general board of health, by the medical officer of the board. 8°. *London*, 1856. L.

Report (A) to the special sanitary committee of the vestry of St. Mary [illegible] ington [on the cholera epidemic of [illegible] by William Tiffin Iliff, medical officer health]. 8°. [*n. p.*, 1866?] L.

Reports on the old cholera haunts and modern fever nests of London.
[Lancet, 1865, II, pp. 523–524, 603–604, 631–6[illegible]

Special report by [Thomas] Orton, medical officer of health, upon the cholera epidemic of 1866, to the board of works for the Limehouse district. 8°. [*n. p.*, 1866?] L.

Special report on cholera [in London] the year 1866 by John S. Bris[illegible] 8°. [*n. p.*, 1867?] L.

Tables illustrating the cholera epidemic of London in 1849 and 1854. [illegible] don, 1856. L.

Manchester.

Gaskell (S.) Remarks on the malignant cholera as it appeared in Manchester.
[Edinb. Med. & Surg. Jour., 1833, XL, pp. 33[illegible]

Gaulter (H.) The origin and progress of the malignant cholera in Manchester, chiefly considered in their bearings on the contagiousness and the secondary causes of the disease. 8°. *London*, 1833. L.

Leigh (J.) *and* Gardiner (N.) History of the cholera in Manchester in 1849. 8°. *London*, 1850.

Ollier (H.) Appearance and progress of cholera in the New Bailey prison, Manchester.
[Lond. Med. & Surg. Jour., 1833, II, pp. 673–[illegible]

Maryport.

Pearson (J.) The history of cholera in Maryport.
[London Med. Gaz., 1850, XLV, pp. 13–16.]

Musselburgh.

Knapp (J.) Cholera at Musselburgh.
[London Med. Gaz., 1832, IX, pp. 628–634.]

Newburn.

Craigie (D.) Account of the epidemic cholera of Newburn in January and February, 1832.
[Edinb. Med. & Surg. Jour., 1832, XXXVII, pp. 377–384; *also*, reprint in 8°. Edinburgh 1832.]

Newcastle-upon-Tyne.

Cobb (F.) Report to the chairman of the house committee, the house commit[illegible]

Cobb (F.)—continued.
and medical officers of the London hospital on the subject of the epidemic now prevailing at Newcastle and its neighbourhood. 8°. *London*, 1832. L.

Gibb (C. J.) Report of the cases of cholera and choleraic diarrhœa, treated at the Newcastle-upon-Tyne infirmary during the present epidemic; with observations thereon.
[MED. Times & Gaz., 1853, VII, n. s., pp. 549–551, 575–576.]

Gibson (G.) Cholera at Newcastle and the board of health.
[LANCET, 1853, I, n. s., pp. 353–354.]

Greenhow (T. M.) Treatment of malignant cholera at Newcastle.
[LANCET, 1832–33, I, pp. 51–53.]

——— Report of the outbreak of cholera in the borough gaol of Newcastle-on-Tyne.
[MED. Times & Gaz., 1853, VII, n. s., pp. 627–628.]

Molison (T.) Remarks on the epidemic disease called cholera, as it occurred in Newcastle. 8°. *Edinburgh*, 1832. L.

Pearse (J. S.) *and* **Marston** (J. A.) Statistics of the cases of the cholera epidemic, 1853, treated at the Newcastle dispensary, with the chemical and microscopical examinations of the excretions, and observations upon the pathology and treatment.
[MED. Times & Gaz., 1854, VIII, pp. 106–108, 129–131, 182–183.]

Robinson (G.) Appearance of cholera in Newcastle.
[LANCET, 1853, I, n. s., p. 254.]

——— A letter to N. G. Lambert on the outbreak of cholera in Newcastle-upon-Tyne. 8°. *Newcastle-upon-Tyne*, 1853. L.

Thacrah (T.) Cholera, its character and treatment, with reference to the disease as now existent at Newcastle. 8°. *Leeds*, 1832.

Cholera in Newcastle-on-Tyne.
[LANCET, 1866, II, pp. 109, 507–508.]

Newport-Pagnell.

Daniell (E.) A succinct history of Asiatic cholera, as it appeared in Newport-Pagnell in August, 1838.
[MED. Times, 1850, XXI, pp. 174–176.]

Oxford.

Acland (H. W.) Memoir on the cholera at Oxford in the year 1854, with considerations suggested by the epidemic. 4°. *London*, 1856. L.

Pill.

Tibbits (R. W.) On the prevention or the spread of the cholera as illustrated by the epidemic at Pill, near Bristol.
[MED. Times & Gaz., 1867, II, pp. 457–458.]

Cholera at Pill, near Bristol.
[MED. Times & Gaz., 1866, II, pp. 559–560.]

Plymouth.

Blackmore (E.) Facts relative to the rise and progress of cholera at Plymouth.
[LONDON Med. Gaz., 1832, X, pp. 473–478, 541–547.]

——— Facts relative to epidemic cholera, detailed from personal observation of the disease, at Plymouth in 1832.
[PROV. Med. & Surg. Jour., 1848, pp. 482–483.]

Hamilton (W.) An attempt to collect the statistics of cholera during its two invasions of 1832, and 1849, in the borough of Plymouth.
[LONDON Med. Gaz., 1849, XLIV, pp. 793–797, 3 tables.]

——— Supplementary statistics of cholera in Plymouth in 1849.
[LONDON Med. Gaz., 1850, XLV, pp. 103–110.]

MacLaren (A. C.) Cholera in Plymouth.
[MED. Times, 1850, I, n. s., p. 415; 1851, II, pp. 159–160.]

Millar (A.) Mr. McClure and the cholera in Plymouth marine barracks.
[MED. Times, 1849, XX, p. 516.]

Roe (E. T.) The cholera in Plymouth and its neighbourhood in 1849.
[MED. Times, 1850, I, n. s., pp. 116–117, 195–197, 453–455, 632–633; 1851, II, pp. 194–197.]

——— The cholera at Noss. [Reply to MacLaren.]
[MED. Times, 1851, II, n. s., pp. 271–272.]

Soltau (W. F.) The cholera in Plymouth.
[LONDON Med. Gaz., 1850, XLV, pp. 49–56, 368–372, 1019–1022, 1060–1064.]

Plymstock.

Bellamy (G.), **Jones** (D.), **Nutt** (J.), *and* **Macleod** (A. W.) Treatment of malignant cholera at Plymstock, Devonshire.
[LANCET, 1832–33, I, p. 19.]

Portsmouth.

Cholera at Portsmouth.
[LONDON Med. & Surg. Jour., 1835, VI, pp. 727–728.]

Rochester.

Vaughan (W.) An account of cholera and cholera fever at Rochester in 1818. 8°. *London*, 1832.

Sandgate.

Blackwell (T. E.) Report on the drainage and water supply of Sandgate in

Blackwell (T. E.)—continued.
connection with the outbreak of cholera in that town. fol. [*n.p.*], 1855. L.

Scotland.

Grieve. Reports on cholera in Scotland, 1848–49.
[Month. Jour. of Med. Sci., Edinburgh, 1848–49, IX, pp. 777–789, 854–859, 940–942, 1009–1012.]

Moir (D. M.) Practical observations on malignant cholera, as that disease is now exhibiting itself in Scotland. 2d ed. 8°. *Edinburgh*, 1832. L.

Shields (North). See *Tynemouth.*

Slateford.

Balfour (J.) Short history of the outbreak of cholera which recently prevailed at Slateford, near Edinburgh.
[Edinb. Med. Jour., 1857, XII, pp. 690–695, 2 pl.]

Southampton.

Cholera (The) at Southampton.
[Med. Times & Gaz., 1866, II, pp. 94, 124–125.—Lancet, 1866, II, pp. 136–137.]

Outbreak of choleraic diarrhœa near Southampton.
[Med. Press & Circ., 1869, VII, pp. 14–15.]

Report by Professor Parkes on the outbreak of cholera in and about Southampton in September and October, 1865.
[Rept. Priv. Counc., 1865 (appendix), pp. 392–438.]

Sunderland.

Ainsworth (W.) Observations on the pestilential cholera (asphyxia pestilenta) as it appeared at Sunderland in the months of November and December, 1831, and on the measures taken for its prevention and cure. 8°. *London*, 1832. L.

Brown (J.) The cholera at Sunderland.
[Midland Med. & Surg. Reporter, 1831–32, III, pp. 220–223.]

Clanny (W. R.) Investigation into the cholera at Sunderland.
[Lancet, 1831–32, I, pp. 633–634, 731.]

——— Historical, pathological and chemical investigation on the nature of the Sunderland cholera. 8°. *London* [1832].

——— Hyperanthraxis; or the cholera of Sunderland. 8°. *London*, 1832. L.

Clanny, Ferguson, *and* Lamotte. Report on the cholera at Monk-Wearmouth colliery.
[Med. Times, 1849, XIX, p. 340.]

Dixon (W.) Cholera at Bishop Wearmouth.
[London Med. Gaz., 1832, IX, pp. 668–671.]

Haslewood (W.) *and* Mordey W[illegible] tory and medical treatment of cholera as it appeared in Sunderland in [illegible] illustrated by numerous cases and dissections. 8°. *London*, 1832. L.

Kell (J. B.) On the appearance of cholera at Sunderland in 1831; with an account of that disease. 8°. *Edinburgh*, 1834. L.

McClure (A.) The cholera at Tapson Devon.
[Med. Times, 1849, XX, pp. 473–476; 529 [illegible] pp. 47–48.]
Chubb (C. W.) [On the same.] pp. 65–66 1850, XXI, p. 68.

Cholera at Sunderland.
[Lancet, 1832, I, pp. 459–460.]

Tynemouth-with-North-Shields.

Greenhow (E.) Cholera at North Shields.
[London Med. Gaz., 1832, IX, pp. 382–384.]

Greenhow (E. H.) Cholera in Tynemouth in 1831–2, 1848–9, and 1853.
[Trans. Epidemiol. Soc., 1854, pp. 25–39 & reprint in 8°, London, 1855.]

Wakefield.

Dunn (H.) The malignant cholera in the house of correction at Wakefield. Admixture of rice with the food.
[Lancet, 1834, I, pp. 687–689.]

Wales.

Cholera in Wales.
[Lancet, 1866, II, p. 556.]

Warrington.

Report of the cholera at Warrington. Superiority of the saline treatment.
[London Med. Gaz., 1832, X, pp. 131–132.]

Whittlesea.

Venables (R.) Cholera at Whittlesea—further evidence of its contagion—with the details of two cases cured by the administration of a saturated solution, followed by the liq. opii sedativus.
[London Med. Gaz., 1832, X, pp. 446–450.]

Wolverhampton.

Ward (T. O.) Observations upon the cholera, as it appeared in Wolverhampton and its neighbourhood, in August, September, and October 1832.
[Trans. Prov. Med. & Surg. Assoc. 1834, II, pp. 368–390.]

rk.

derson (W. C.) Treatment of malig-ant cholera at the cholera hospital, York.
[LANCET, 1832-33, I, pp. 72-74.]

edham (J. P.) Facts and observations elative to the disease commonly called holera, as it has recently prevailed in he city of York. 8°. *London*, 1833. L.

rkshire.

right (T. G.) Reports on the origin nd progress of pestilential cholera in he West-Yorkshire lunatic asylum, uring the autumn of 1849; and on the revious state of the institution. 8°. *London*, 1850. L.

GREECE.

nasi (V.-P.-T.) * Essai sur un choléra épidémique observé en Grèce dans l'année 1831. 4°. *Paris*, 1831. L.

eber die Cholera-Epidemie in Griechen-land und über eine neue Behandlungs-weise gegen dieselbe.
[DEUTSCHE Klinik, 1856, VIII, pp. 339-341, 348-350.]

thens.

holera (Die) zu Athen.
[ÄRZTL. Intell.-Bl., München, 1835, I, p. 106.]

Description of an outbreak of cholera at the Piræus in 1854.]
[LANCET, 1866, II, p. 141.]

ITALY AND THE MEDITERRANEAN.

ndrea (R. D.) Sul cholera, ulteriori osservazioni in appendice al volume primo degli studi medici del dottor ..... (primo lettura) al veneto Ateneo nel di 17. Gennaro 1856. 8°. *Venezia*, 1856. L.

—— Osservazioni sul cholera.
[GIORN. venet. d. sc. med., 1856, VI, 2a s., pp. 481-516.]

acon (G. M.) Cholera in Italy.
[MED Times & Gaz., 1867, I, p. 307.]

ally (V.) Documents et mélanges publiés à l'occasion de la maladie asiatique introduite dans les États Romains et les Alpes Dauphinoises. 8°. *Paris*, 1855. L.

laudin (C.) Extrait d'une lettre de . . . à M. Dupin, sur la manière dont le choléra a sévi à bord de l'escadre française de la Méditerranée.
[COMPTES rendus de l'Acad. des sci., Paris, 1835, I, p. 254-255.]

Berruti *e* **Trompeo.** Rapporto della regia commissione medica piemontese sul cholera-morbus .... 8°. *Torino*, 1832.

Buffini (A.) *e* **Sordelli** (A.) Articoli principali dei rapporti fatti all'I. R. governo di Milano, duranti la loro dimora nei paesi infestati dal cholera-morbus.
[OMODEI, Ann. un. di med., 1831, LX, pp. 496-528, 1 pl.; 1832, LXI, pp. 5-107.]

Calderini (C.) Cenno istorico del cholera-morbus che ha regnato nel 1835 in Nizza, Cuneo, Genova, Torino e altri luoghi dello stato Sardo, dal suo primo aparire fino al 18. Settembre 1835.
[OMODEI, Ann. un. di med., 1835, LXXVI, pp. 401-475.]

Castiglioni (F.) Sulle comunicazioni fatte all'Accademia fisio-medico-statistica, da varii Istituti scientifici d'Italia, risguardanti l'invasione e l'andamento del cholera-morbus nel 1854. L'invasione e l'andamento del cholera asiatico in Sicilia nel 1854, in appoggio alla memoria del prof. S. Cacopardo.
[OMODEI, Ann. un. di med., 1855, CLIII, pp. 37-55; 1855, CLIV, pp. 525-537.]

Centomo (L.) Il cholera quale fu vedute nell'estate del 1855. *Vicenza*, 1857.

Contini (G.) Sulla epidemia colerica del 1866. *Napoli*, 1866.

Coscienza (E.) Il cholera del 1865 in Italia e la rettificazione del prof. Carlo Ghinozzi.
[GAZ. med. ital. prov. Veneto, 1865, VIII, pp. 337-342.]

Curci (L.) Nuove scoverte e mezzi curativi per guarirse dal morbo colera. Memoria medica per l'attuale malattia corrente verminosa velenosa, nella provincia di Bari ed attualmente in Napoli sotto il nome di colera morbo. 8°. *Napoli*, 1837. L.

Da-Camino (F. S.) *e* **Provasi** (C.) Del cholera. Due lettere ed un rapporto sul colera che ha dominato nel comune di Cordenons nell'anno 1855.
[GIORN. venet. d. sc. med., 1856, VII, 2a s., pp. 207-216.]

Fulmiani (J.) Intorno all'epidemia colerosa dominata nei villaggi di Oltre, Pogliana, Sant'Eufemia, e Lucorano degli Scogli di Zaro, dal 3 Luglio al 20 Agosto 1855.
[GAZ. med. it. Lomb., 1856, I, 4a s., pp. 84-85.]

Grandesso-Silvestri (O.) Del cholera [1855].

[Gaz. med. ital. prov. Veneto, 1867, x, pp. 177–179, 185–188, 193–197, 201–204.]

Larrey (D. J., *le baron*). Notice sur l'épidémie du choléra morbus indien qui a régné dans les ports méridionaux de la Méditerranée et dans toute la Provence, pendant les mois de juillet et d'août 1835.

[Comptes rendus de l'Acad. des sci., Paris, 1835, I, pp. 140–144.]

——— The same. 8°. *Paris*, 1835. L.

Monteverdi (A.) Sull'epidemia colerosa dell'anno 1867 nei comuni del due Miglia e del Corpi Santi relazione. 8°. *Cremona*, 1868. L.

Pallavicino (S.) Descrizione del contagio che da Napoli si comunico a Roma nell'anno 1656. E de'saggi provvedimenti ordinati allora. Da Alessandro VII. Estratta dalla Vita del medesimo pontefice che conservasi manuscritta nella biblioteca Albani. Opera inedita. 4°. *Roma*, 1837. S. C.

Peyrani (V.) Relazione dell'epidemia colerosa dominante nei circondari d'Ivrea e d'Aosta.

[Giorn. d. R. accad. di med. di Torino, 1867, IV, 3a s., pp. 54–61.]

Renzi (S. de). Relazione statistica e clinica degl'infermi di choléra morbo, trattati nell'ospedale di Santa Maria di Loreto: contenente la diagnosi, il prognostico, la cura, le note cadaveriche, ec. rilevate in quell'ospedale, e preceduta da un sunto storico dell'epidemia di colera della città di Napoli. 8°. *Napoli*, 1837. L.

Scamoni (C.) Intorno al colera morbus in Motta Baluffi e Solarolo Monestirolo.

[Gaz. med. it. Lomb., 1856, I, 4a s., pp. 93–98.]

Schivardi (P.) Gli studi degli Italiani sul cholera nel 1865–66. 8°. *Torino*, 1866. S. C.

Sonsino (P.) Della statistica d'Italia sul cholera-morbus del 1865. 8°. *Firenze*, 1867. L.

[*Extracted from* L'Imparziale, anno VII, 1867.]

——— Medaglia ai benemeriti della salute pubblica nell'ultima epidemia di cholera in Italia.

[L'Imparziale, Firenze, 1869, IX, pp. 353–356.]

Sormani (N.), **Clerici** (G.), *e* **Alfieri** (C.) Notizie intorno al cholera-morbus che ha regnato nelle città di Cuneo e [illegible] durante il 1835.

[Omodei, Ann. un. di med., 1835, LXIV, pp. 5–367.]

Strambio (G.) Cronaca del cholera diano in Italia durante l'anno 1854. *Milano*, 1854.

——— The same. . . . 1855. [illegible] 1855.

——— Cronaca del cholera.

[Gaz. med. it. Lomb., Milano, 1867, [illegible] 113, 121, 152, 163, 178, 201, 209, 21[illegible] 256, 264, 284, 295, 305, 315, 329, 33[illegible] 382, 394, 460.]

Sutherland (J.) Cholera in the Mediterranean stations.

[Lancet, 1867, II, pp. 380–381.]

Terenzi (A.) Saggio istorico sul [illegible] morbus di Monte Fano e frazione Monte Fiore nel Piceno, espresso in lettera diretta ad un amico in R[illegible] 8°. *Macerata*, 1837.

Tholozan. Développement du [illegible] en Italie; son mode d'extension et propagation.

[Gaz. méd. de Paris, 1855, X, pp. 513–5[illegible]

Vallelunga (G. S. da). Brevi [illegible] occasione del cholera 1866. [illegible] *lermo*, 1866.

Verri (V.) Studi ed osservazioni [illegible] tiche sul cholera desunte dalle [illegible] vasioni occorse in diverse città d'[illegible] dal 1835 al 1865. *Milano*, 1865.

Villani (E.) Relazione igienico statistica sulla epidemia colerica 1873 relazione Vicaria. 8°. *Napoli*, 1874.

Werneck. Sendschreiben an den [illegible] ausgeber über die gewöhnliche Cholera im tiefen Italien, und Versuche mit Zinkblumen und den Wismuth-Präparaten.

[Med.-Chir. Zeitung, Innspruck, 1[illegible] 305–320.]

Cholera in Italy.

[Dublin Med. Press & Circ., 1867, [illegible] 204–205, 305–306.]

Cronaca del cholera.

[Omodei, Ann. un. di med., 1867, CCII, [illegible] 609; CCI, pp. 230–240.]

Discussione in senato della legge per pensioni alle famiglie dei medici morti nell'epidemia colerosa, e un altro per colleghi.

[Gaz. med. ital. prov. Veneto, 1867, X, [illegible] 47.]

Progetto di legge per la pensione alle famiglie dei medici morti combattendo il cholera.

[Gaz. med. ital. prov. Veneto, 1867, X, [illegible]

ıgetto di legge sulle pensioni alle ve- ove ed ai figli dei medici e chirurghi ıorti in servizio dello stato per l'assis- ınza ai colerosi.

HORN. d. R. accad. di med. di Torino, 1867, IV, 3a s., pp. 187–192; 1868, VI, pp. 63–64.]

ıtistica del regno d'Italia. Sanità pub- lica. Il cholera-morbus nel 1865. fol. irenze, 1867. L.

— The same. . . . nel 1866 e 1867. irenze, 1870. S. C.

l colera indico nel 1854, recerche del omitato medico Ligure, collo coopera- ione di altri sanitari. 4°. *Genova*, 556.

ona.

ıncazzi (C.) Intorno al cholera in An- ona.

SPERIMENTALE (Lo), 1865, XVI, pp. 188–191; 1866, XVIII, pp. 111–117.]

azi (S.) Cenni sul cholera morbus e ul metodo di cura osservato in Ancona. . *Loreto*, 1836.

rsonali (E.) Brevi cenni sull'epidemia :holerosa manifestatasi nei militari del presidio di Ancona. *Modena*, 1865.

sta.

soari (F.) Cholera in Aosta nel 1867. *Torino*, 1867.

coli del Piceno.

ıroni (A. *e* C. B.) Sul modo di propa- garsi del cholera e sua irruzione in As- coli del Piceno nel 1855. 8°. *Ascoli*, 1856.

ri.

randonisio (R.) Il cholera-morbus, che nel 1836 e 1837 travaglio Bari ed altri luoghi della provincia, sotto l'impero dell'analisi, colla soluzione di alguni importanti problemi in medicina. 2 v. 8°. *Bari*, 1839, 1844. L.

ssignana.

lcchio (S.) Relazione sul cholera in Bassignana. 4°. *Alessandria*, 1867. S. C.

rgamo.

omotti (G.) Relazione amministrativa sulla invasione del cholera in Bergamo negli anni 1866 e 1867, etc. *Bergamo*, 1868.

Borsani (L.) *e* **Freschi** (F.) Osservazioni intorno al cholera asiatico fatte in Ber- gamo.

[OMODEI, Ann. un. di med., 1836, LXXIX, pp. 114–161.]

Leguini (L.) Del colera-morbus nel- l'ospedale militare di Galgario in Ber- gamo nel 1849.

[GAZ. med. it. Lomb., 1854, V, 3a s., pp. 333–337.]

Movimento del colera nella città di Ber- gamo.

[GAZ. med. it. Lomb., Milano, 1855, VI, 3a s., pp. 266, 289, 298, 305, 315, 321, 330, 338, 357.]

Relazione amministrativa sulla invasione del cholera in Bergamo negli anni 1866 e 1867, pubblicata per cura della giunta municipale. *Bergamo*, 1868.

Bobbio.

Conti (F.) Cenni sul metodo curativo e natura del cholera-morbus, e del cholera artificiale nella città di Bobbio e nel comune di Pregola. 8°. *Torino*, 1855.

Bologna.

Hampeis (K.) Die Cholera-Epidemie zu Bologna im Sommer 1855.

[WIEN. med. Wochenschr., 1855, pp. 691–707.]

Brescia.

Balardini (L.) Invasione del cholera-mor- bus nella provincia di Brescia nell'anno 1849, e fatti occorsi comprovanti sempre più la sua indole contagiosa.

[OMODEI, Ann. un. di med., 1851, CXXXVII, pp. 529–545; *also*, reprint in 8°, Milano, 1851.]

Bargnani (A.) Sulle cause che hanno ultimamente dato origine al chelera- morbus nella Sala delle Pazze in Bre- scia.

[OMODEI, Ann. un. di med., 1836, LXXX, pp. 105–119.]

Benedini (F.) Sul colera di Brescia nel- l'anno 1855. *Brescia*, 1856.

Boschetti (A.) Sul colera del 1855. Cenni pratici in case ai quesiti formulati dalla congregazione municipale di Brescia.

[GAZ. med. it. Lomb., 1856, I, 4a s., pp. 418–420, 429–432.]

Da-Ponte (L.) Il cholera-morbus in Bre- scia nell'anno 1855. 4°. *Brescia*, 1856.

Fornasini (L.) Intorno al colera di Bre- scia.

[OMODEI, Ann. un. di med., 1850, CXXXIV, pp. 225–290.]

Gamba (F.) Osservazioni e cure sul cholera asiatico, fatte nel civico lazzaretto di Brescia.
[OMODEI, Ann. un. di med., 1867, CCII, p. 524.]
——— The same. 8°. *Milano*, 1867. L.

Girelli (F.) Relazione intorno al lazzaretto di Brescia, attivatosi nell'ultima invasione del colera morbus, dei mesi di Giugno, Luglio, Agosto e Settembre del 1855.
[GAZ. med. it. Lomb., 1856, I, 4a s., pp. 11–13.]

Manzini (B.) Cenni storici intorno al cholera-morbus che afflisse Brescia nel Giugno, Luglio ed Agosto 1836. 8°. *Brescia*, 1837.

Menis (G.) Saggio di topografia statistico-medica della provincia di Brescia; aggiuntovi le notizie storico-statistiche sul colera epidemico che la desolò nell'anno 1836. 2 v. 8°. *Brescia*, 1837.

Perolio (C.) Rendiconto statistico clinico del colerosi, curati nel lazzaretto di Brescia, dal 27 Giugno al 15 Settembre 1855.
[GAZ. med. it. Lomb., 1856, I, 4a s., pp. 13–14, 17–23.]

Uberti (G.) Del cholera morbo che disertò le Sale delle Pazze nell'ospitale femminile in Brescia, e della casa di siccorso, o lazzaretto, ivi attivato.
[OMODEI, Ann. un. di med., 1837, LXXXII, pp. 62–93.]

Movimento del colera nella città e provincia di Brescia.
[GAZ. med. it. Lomb., 1855, VI, 3a s., pp. 248, etc.]

Brindisi.

Nesti (L.) e **Pera** (S.) Del cholera morbus in Brindisi.
[SPERIMENTALE (Lo), 1866, XVII, pp. 140–160.]

Cagliari.

Fadda (T.) Relazione sul cholera asiatico che domino nel 1867 nel quartiere di Stampace in Cagliari. 16°. *Cagliari*, 1867. S. C.

Falconi (G.) Sul cholera asiatico che domino in diversi comuni della provincia di Cagliari nel 1867. *Cagliari*, 1868.

Calcinaja.

Martini (A.) Intorno ai casi de cholera morbus osservati e curati in Calcinaja nell'Agosto e Settembre del 1854. 8°. *Pisa*, 1854. L.

Turchetti (O.) Considerazioni etiologiche, nosogeniche e terapeutiche sul cho-

Turchetti (O.)—continued.
lera e visita fatta ai cholero[illegible] naja. 8°. *Firenze*, 1854.

Campi.

Benini, Martinuzzi, e **Ristori** (G.) [illegible] provanti la contagiosità del ch[illegible] bus, osservati nella comunità d[illegible]
[GAZ. med. ital. Tosc., 1856, II, 3a s., pp. [illegible]

Cantu.

Morandi (P.) Sul colera in Ca[illegible]
[GAZ. med. it. Lomb., 1856, I, 4a s., p. [illegible]

Caravaggio.

Fedeli (G.) Cenno sul colera [illegible] vaggio.
[GAZ. med. it. Lomb., 1855, VI, 3a s., pp. [illegible]

Castel S. Nicolo.

Bargi (G.) Il colera asiatico [illegible] munità di Castel S. Nicolo l'an[illegible]
[GAZ. med. ital. Tosc., 1855, II, 3a s., pp. [illegible]

Cephalonia.

Pretenderis Typaldos (C.) De [illegible] épidémique observé à Céphal[illegible] 1850. 8°. *Athènes*, 1851.

Ceprano.

Piazzoli (C.) Sulla costituzione [illegible] co-contagiosa cholerica che ha [illegible] nel comune di Ceprano ne'mes[illegible] glio, Agosto 1837. 8°. *Roma*, [illegible]

Cerda.

Tripi (A. B.) Sull'andamento del [illegible] morbo e suo metodo curativo [illegible] mune di Cerda. Rapporto [illegible] *Palermo*, 1837.

Certaldo.

Masini (G.) Il colera a Certaldo [illegible] te del 1855.
[GAZ. med. ital. Tosc., 1856, II, 3a s., [illegible] 99–103, 111–115.]

Cesenatico.

Fedeli (D. B.) Storia sul cho[illegible] bus indiano sviluppatosi nella [illegible] condario dell'Cesenatico nell'est[illegible] l'anno MDCCCXXXVI. [illegible] 1837.

Chiari.

Fantoni (A. F.) Rapporto statist[illegible] cholera indiana stata in Chia[illegible] 1849.
[OMODEI, Ann. un. di med. [illegible] 321–353.]

ari (F.) Il colera in Como nei mesi Luglio, Agosto, Settembre ed Ottobre 5.
[Az. med. it. Lomb., 1856, I, 4a s., pp. 4–7.]

tti (G.) Sul colera di Camerlata, e di uni paesi limitrofi nella provincia di mo. Osservazioni storico-statistiche.
[Az. med. it. Lomb., 1855, VI, 3a s., pp. 370–371.]

azzoni (I.) Il comitato provinciale beneficenza per gli afflitti dal cholera Como. 16°. *Como*, 1867. S. C.

tti (G.) Sul cholera che l'anno 1867 vase la città e provincia di Como. mo, 1867.

sani (A.) Invasione e modo di diffu- ne del colera asiatico nella provincia Como durante il 1867. *Como*, 1867.

vimento del colera nella città e pro- ncia di Como.
[Az. med. it. Lomb., Milano, 1854, V, 3a s., pp. 324, etc.; 1855, VI, pp. 265, etc.]

c.

colò e **Susini** (C.) Storia del colera ominato in Colle nella estate del 1855.
[Az. med. ital. Tosc., 1856, II, 3a s., pp. 172, 179, 187, 195.]

mona.

bolotti (F.) Del morbo-cholera che a dominato in Cremona negli anni 1836, 54, e 1855. 8°. *Cremona*, 1855.

vimento del colera in Cremona.
[Az. med. it. Lomb., 1855, VI, 3a s., pp. 259, etc.]

nza.

lamini (G.) Considerazioni etiologiche terapeutiche sul cholera epidemico in aenza.
[Az. med. ital. Tosc., 1855, II, 3a s., pp. 54–58.]

glia.

ttai (G.) Intorno al colera dominato a anglia nell'estate dell'anno 1855.
[Az. med. ital. Tosc., 1856, II, 3a s., pp. 243–245, 253–254.]

rrara.

lazione del cholera morbus che dominò nella città e provincia Ferrara nel 1849 [etc.] 4°. *Ferrara*, 1851.

lazione storica del colera-morbus nella provincia Ferrarese, l'anno 1855. 4°. *Ferrara*, 1857.

Forli.

Valentini (D.) Osservazioni sui morbi epidemici e sul colera, desunte dai fatti raccolti nella provincia di Forli. 8°. *Bologna*, 1856. L.

Frosinone.

Ciatti (G.) Sul cholera di Frosinone.
[Omodei, Ann. un. di med., 1856, CLVI, pp. 449–464.]

Genoa.

Balestreri (F. M.) Sesta invasione del cholera in Genova nel 1866. 4°. *Genova*, 1866. S. C.

——— Osservazioni pratiche di un cholera in Genova nel 1873.
[Omodei, Ann. un. di med., 1873, CCXVI, pp 331–355.]

——— The same. 8°. *Milano*, 1873. L.

Borelli (G. B.) Sull'epidemia di cholera morbus dominante in Genova, quattro prime lettere. 8°. *Genova*, 1854.

Brocchini (D.) Il cholera asiatico nel comune di S. M. a Monte nell'anno 1855.
[Gaz. med. ital. Tosc., 1856, II, 3a s., pp. 163–166.]

Chiossone (D.) Il cholera morbus in Genova nell'anno 1867. 8°. *Genova*, 1867. S. C.

De Bernardi (P. N.) Cenno distintivo e statistico degli infermi di cholera asiatico ricoverati nello spedale consorti le temporaneo dell'exconvento di N. S. Del Monte in Bisagno, durante l'epidemia del 1873 in Genova.
[L'Imparziale, 1875, XV, pp. 3–18.]

Du Jardin (G.) Storia della epidemia d cholera patita in Genova nell'anno 1866 *Genova*, 1867.

Freschi (F.) Storia ducumentata della epidemia di cholera-morbus in Genova nel 1854, e delle providenze ordinate da governo e dal municipio a vantaggio della pubblica e privata igiene. 8° *Genova*, 1855.

Granara (R.) Invasione del cholera asiatico in Genova e sua propagazione nell'anno 1854. *Genova*, 1854.

Massone (G. B.) Il cholera-morbus nel porto di Genova durante l'epidemie del 1854. *Genova*, 1855.

Solerio (G.) Sull'invasione del cholera-morbus nella città e ducato di Genova. *Genova*, 1836.

Bollettino del colera in Genova nel 1854.
[Gaz. med. it. Lomb., Milano, 1854, v, 3a s., pp. 291, etc.; 1855, vi, 3a s., pp. 296, etc.]

Relazione intorno all'invasione di colera asiatico in Genova nell'estate ed autunno 1873, fatta dalla commissione municipale di Santa. [Giov. Du Jardin relat.] Le otto epidemie colériche di Genova in rapporto colla meteorologia [anni 1835, 36, 37, 54, 55, 66, 67, 73]. roy. 8°. *Genova*, 1874. L.

Giglio.

Corvetti (G.) Il cholera al castello della Isola del Giglio nell'estate del 1855.
[Gaz. med. ital. Tosc., 1856, ii, 3a s., pp. 134-138, 144-146.]

Goito.

Casnici (L.) Intorno al cholera di Goito. Riferto in risposta all'ordinanza delegatizia 23 Dicembre 1849.
[Omodei, Ann. un. di med., 1850, cxxxvi, pp. 449-503.]

Lamon.

Facen (J.) Rapporti medico-statistico del morbo-cholera che domino nel comune di Lamon nel 1855.
[Giorn. venet. d. sc. med., 1855, v, 2a s., pp. 740-753.]

Leghorn.

Carbonaro (G.) Epitome sul cholera-morbus asiatico, osservato in Livorno nel 1835. 8°. *Napoli*, 1836. L.

Rossini (L.) Osservazioni sul cholera di Livorno e sopra altri mali popolari.
[Gaz. med. ital. Tosc., 1854, iv, 2a s., pp. 376-378, 385-387, 393-395, 401-403, 412-413, 417-419.]

Legnago.

Carazza (A.) Del cholera occorso in S. Pietro di Legnago nel 1867.
[Gaz. med. ital. prov. Venete, 1867, x, pp. 369-372.]

Liguria.

De Vita (A.) *Diss. teorico-pratica sulla colera asiatica occorsa ultimamente nella Liguria, e sul contagio della medesima. 8°. *Genova*, 1855.

Elena (C.) Sul cholera indico nel 1854. Richerche del comitato medico Ligure colla cooperazione di altri sanitarj. *Genova*, 1855.

Cholera (Il) in Liguria.
[Salute (La), 1874, ix, pp. 279-281, 291-293, 323-325, 339-341.]

Lodi.

Movimento del colera nella città di Lodi e Crema.
[Gaz. med. it. Lomb., 1855, vi, 3a s., pp. 290, etc.]

Lombardy.

Gianelli (J.) Die Cholera-Epidemie in der Lombardie im Jahre 1836.
[Med. Jahrb. d. k. k. oesterr. Staates, 1840, xxi, s. F., pp. 180-184.]

Locatelli *e* **Tonini.** Rapporto all'I. R. governo di Lombardia intorno al cholera-morbus.
[Omodei, Ann. un. di med., 1831, lx, pp. 485-496. 1832, lxi, pp. 107-145.]

Maraschini (G. G.) Materiali per la storia del colera-morbus nel regno Lombardo-Veneto durante il 1849.
[Gaz. med. it. Lomb., 1851, ii, 3a s., pp. 181-189.]

Notizie sul cholera in Lombardia.
[Omodei, Ann. un. di med., 1854, cxlix, pp. 444-448, 667-672; 1854, cl, pp. 445-448, 660-662.]

Prospetto de cholerosi della Lombardia durante l'anno 1849.
[Omodei, Ann. un. di med., 1849, cxxix, pp. 671-672.]

Malta (Island of).

Adams (A. L.) Report of the cholera epidemic of 1865 in the Maltese islands: together with an introduction and an epitome of the cholera epidemics that have previously ravaged them.
[Army Stat., San., & Med. Repts., London, 1864, vi. pp. 310-349, 7 ch.]

Butler (E. J.) The epidemic of cholera at Malta in 1865.
[Dublin Quar. Jour. of Med. Sci., 1868, xlvi, pp. 333-339.]

Pettenkofer (M. v.) Die Choleraepidemien auf Malta und Gozo.
[Ztschr. f. Biologie, 1870, vi, pp. 143-202, 1 map.]

Phillips (H. J.) The cholera.
[Med. & Surg. Reporter, Phila., 1865, xiii, p. 3[illegible].]

Pisani (S. L.) Faulty hygiene in connection with the mortality from cholera morbus at Malta, during the epidemics of 1837 and 1850.
[Denkschr. d. Ver. deutsch. Aerzte in Paris, 1874. pp. 57-58.]

Stilon (G.) The cholera at Malta in 1837. From the Italian by S. B. Watson. 12°. *London*, 1848. L.

therland. Report on the sanitary condition of Malta and Gozo with reference to the epidemic cholera in the year 1865. fol. *London*, 1867. L.

olera at Malta.

[MED. Times, 1850, I, n. s., p. 671.—MED. Times & Gaz., 1867, II, pp. 256–257.]

ndsuria.

llegrino (L.) Dei cholera morbus in Ianduria.

[L'IMPARZIALE, 1865, V, pp. 613–620.]

ntua.

ontani. Cenni sul cholera morbus che lominò nella provincia di Montova l'anno 1836.

[GIORN. p. serv. al progr. di patolog., 1837, VII, pp. 21–52.]

ovimento del colera nella città di Mantova.

[GAZ. med. it. Lomb., Milano, 1855, VI, 3a s., pp. 267, etc.]

Messina.

enna (A.) Osservazioni cliniche sul cholera-morbus in Messina. 8°. *Messina*, 1854. L.

egne (I.) Relazione sull'epidemie cholerica che ha dominato nel 10° reggimento di fanteria a Messina nei mesi di Agosto e Settembre 1867. 8°. *Saluzzo*, 1868.

holéra (Le) à Messine.

[GAZ. méd. de Paris, 1855, X, pp. 101–105.]

Milan.

alderini (C.) Rapporto fatto alla direzione dell'ospitale maggiore di Milano sugli ammalati di cholera-morbus asiatico curati nell'ospitale maggiore di Milano dal 17 Aprile fino alli 27 Settembre inclusivi dell'anno 1836.

[OMODEI, Ann. un. di med., 1837, LXXXI, pp. 257–398.]

hiapponi (P.) Il cholera in Milano nell'anno 1867. *Milano*, 1868.

lerici (G.) Rendiconto clinico de'colerosi ricoverati nelle case di siccorso di S. Barnaba e del Gallo, toccante i fatti di osservazione, presentato alla direzione dell'ospedale maggiore di Milano.

[OMODEI, Ann. un. di med., 1837, LXXXIII, pp. 417–547.]

errario (G.) Cenni storico-statistici sul pestilenziale cholera-morbus asiatico negli anni 1837, 1849 e 1854 in Milano e nelle provincie Lombarde. 16°. *Milano*, 1855.

Frua (C.) Del cholera-morbus osservato in Milano nel secondo semestre dell'anno 1854.

[OMODEI, Ann. un. di med., 1855, CLI, pp. 449–519, 2 pl.]

——— The same. 8°. *Milano*, 1855. L.

Manzolini (A.) Rendiconto statistico-clinico-igienico di quanto fu operato nella casa di soccorso pei colerosi "al Gallo" dall'Agosto a tutto Novembre 1854.

[OMODEI, Ann. un. di med., 1855, CLI, pp. 520–549.]

——— The same. 8°. *Milano*, 1855. L.

Monti (G.) Sul cholera nel comune dei Corpi Santi di Milano durante l'anno 1867. *Milano*, 1868.

Scotti (G.) Il cholera in Milano nell'anno 1873.

[GAZ. med. it. Lomb., 1874, XXXIV, pp. 52–53.]

Strambio (G.) e Ambrosoli (G.) Intorno all invasione del cholera-morbus in Milano nell'anno 1849.

[OMODEI, Ann. un. di med., 1849, CXXXII, pp. 243–260.]

Todeschini (C.) L'epidemia colerica di Milano dell'anno 1855, osservata nelle Case di Soccorso pei colerosi.

[OMODEI, Ann. un. di med., 1857, CLIX, pp. 342–431; CLX, pp. 130–162, 325–350, 568–606.]

Trezzi (A.) Annotazioni statistiche sul colera della prov. di Milano nell'epidemia del 1867. *Milano*, 1868.

Cholera-morbus (Il) in Milano nell'anno 1854. Relazione della commissione sanitaria municipale. 4°. *Milano*, 1855.

Colera (Il) in Milano nell'anno 1867. Relazione della commissione straordinaria di sanità. fol. 1868.

Movimento del colera nella città e provincia di Milano.

[GAZ. med. it. Lomb., 1854, V, 3a s., pp. 316, etc.; 1855, VI, 3a s., pp. 8, etc.]

Relazione della commissione sanitaria di Milano sul cholera-morbus nell'anno 1855. 4°. *Milano*, 1856.

Modigliana.

Fabroni (L.) Intorno il colera di Modigliana nell'estate del 1855.

[GAZ. med. ital. Tosc., 1855, I, 3a s., pp. 337–341, 345–348.]

Montagnana.

Berti (A.) Brevi cenni intorno il colera di Montagnana nel Settembre e Ottobre 1849.

[GIORN. veuet. d. sc. med., 1855, V, 2a s., pp 409–430.]

Montajone.

Pandolfi (L.) Sul colera che dominò a Montajone.
[Gaz. med. ital. Tosc., 1856, II, 3a s., pp. 227–230.]

Naples.

Barracano (G.) Osservazioni sul colera morbo asiatico, fatte nel corso delle due invasioni a Napoli negli anni 1836 e 1837. 8°. *Napoli*, 1849. L.

Bidera (G. E.) Gli ultimi novanta giorni del 1836, ossia il colera in Napoli. Racconti . . . 2a ed. 12°. *Napoli*, 1837.

Carbonaro (G.) Intorno al cholera-morbus osservazioni pratiche fatte in Napoli nel 1836 e 1837. 4°. *Napoli*, 1849. L.

Cera (V. L.) Metodo curativo razionale per la colera sviluppatasi in Napoli dalla scorcio di Luglio 1854. 8°. *Napoli*, 1854. L.

De Renzi (S.) *See* **Intorno** al cholera, etc.

Gentile (F.) Sul colera asiatico curato nello spedal militare della cristalliera di Napoli. 8°. *Napoli*, 1837.

Maldacea (G.) Storia del colera della città di Napoli. 8°. *Napoli*, 1839. L.

Margotta (A.) Relazione storico-medico-statistica sul cholera del 1866 nella provincia di Napoli. 8°. *Napoli*, 1866. S. C.

Mariano (—). Relazione medica sull'epidemia del cholera morbus che dominò fra i militari del presidio di Napoli nell'anno 1873.
[Giorn. di med., farm. e veter. mil., 1874, XXII, pp. 19–27.]

Sanctis (T. L. de). Lettera sul colera del 1854 in Napoli. 8°. *Napoli*, 1854. L.

Sterlich (C. de). Quadri storici del cholera di Napoli . . . 16°. *Napoli*, 1837.

Thibault. Observations sur le choléra-morbus de Naples.
[Bull. de l'Acad. de méd., I, 1836, p. 880; 1837–38, II, p. 796.]

Vulpes (B.) Sul cholera asiatico osservato in Napoli nell'autunno dell'anno 1836. 8°. *Napoli*, 1836.
[2d ed. same year.]

Whyte (R.) Cholera in Naples.
[Lancet, 1854, p. 200.]

Zarlnuga (R.), **Carrlizzi**, *und* **De Renzi.** Bemerkungen über die Cholera in Neapel, am Ende des Jahres 1836.
[Mrd. Corspdzbl. d. württ. aerztl. Vereins, 1837, VII, pp. 117–120.]

Chevalley (de Rivaz). Lettre sur la marche du choléra à Naples.
[Bull. de l'Acad. de méd., 1836, I, p. 206.]

Intorno al colera di Napoli dell'anno 1854. Relazione della facoltà medica al soprintendente generale ed al supremo magistrato di salute. Relatore: Salvatore de Renzi. 4°. *Napoli*, 1854. L.

Movimento del colera in Napoli.
[Gaz. med. it. Lomb., 1854, V, 3a s., pp. 332, 37[illegible].]

Nice.

Nicolis (B.) Cenni sul cholera-morbus dominato in Nizza nel 1854. 16°. *Torino*, 1855.

Cronaca del colero. Movimento del colera in Nizza.
[Gaz. med. it. Lomb., 1854, V, 3a s., pp. 299, 302, 3[illegible].]

Norcia.

Barbieré (C.) Pochi cenni sul cholera di Norcia. *Norcia*, 1856.

Novi.

Caielli (N.) Nuovi fatti a conferma del contagio choleroso, ossia Schizzo della cholera asiatica che dominó in una vallata della prov. di Novi nella state del 1836. 8°. *Genova*, 1837.

Oleggio.

Ramini (F.) Il cholera-morbus in Oleggio nell'anno 1854. *Novara*, 1854.

Padua.

Argenti (F.) Il cholera-morbus in Padova negli anni 1854–55. 4°. *Padova*, 1856.

Berselli (G.) Il cholera in Padova nel 1873. 4°. *Padova*, 1874. L.

Noale (A.) Del cholera considerato amministrativamente in alcuni comuni del territorio Padovano.
[Giorn. venet. d. sc. med., 1856, VII, 2a s., pp. 3–17.]

Pinali (V.) Memoria intorno al cholera di Padova.
[Giorn. p. serv. al progr. di patolog., 1837, VII, pp. 241–283, 397–456.]

Zecchinelli (G. M.) Cenni sul cholera che si mostrò in Padova nei mesi di Ottobre, Novembre, Dicembre 1835 e Gennajo 1836.
[Giorn. p. serv. al progr. d. patolog., 1835, III, pp. 322–336; 1836, IV, pp. 146–186.]

Palermo.

Abate (V.) Gli eccitanti sostenuti dalle osservazioni e da'fatti nella cura del colera di Palermo. 8°. *Palermo*, 1837.

ritano (G.) Relazione sul colera di 'alermo nel 1867 fatta dal corpo sanitario centrale, all'illustrissimo signor indaco. 4°. *Palermo*, 1867. S. C.

ıcluso (A.) Sul cholera che domino a 'alermo nell'autunno del 1866. *Palerto*, 1867.

cioppi (A.) Del cholera che invase la narnigione di Palermo nell'està del 837, ... al D. Antonia Alvarez-y-obo. 8°. *Palermo*, 1837.

ndaccio (F.) Sul cholera di Palermo el 1867. *Palermo*, 1867.

ımmasi (C.) Relazione sul cholera di Palermo nel 1866. *Palermo*, 1866.

—— Il cholera di Palermo nel 1866. fol. *Palermo*, 1867.

us dem Cholera-Lazarethe in Palermo.

[Wiener med. Wochenschr., 1865, xv, pp. 1742-1743.]

apporto sul cholera-morbus che regnò in Palermo in Giugno, Luglio ed Agosto del 1837, presentato al governo dalla R. accademia delle scienze mediche. 8°. *Palermo*, 1837.

arma.

elazione della commissione sanitaria sul cholera che dominò nella città di Parma nell'anno 1873.

[Spallanzani (Lo), 1875, xiii, pp. 131-148.]

arona.

'ine (F.) Il cholera in Parona di Lomel-ina.

[Gaz. med. it. Lomb., 1868, xxviii, pp. 265-271.]

ascia.

lovimento del coléra nella provincia di Pavia.

[Gaz. med. it. Lomb., 1854, v, 3a s., pp. 399, 420, 439; 1855, vi, 3a s., pp. 248, etc.]

egognaga.

'olta (F.) Su'l coléra-morbus di Pegognaga.

[Gaz. med. it. Lomb., 1856, i, 4a s., pp. 48, 181, 253.]

erugia.

larroni (G.) Relazione sul cholera a Perugia.

[L'Imparziale, 1867, vii, pp. 564-565.]

escia.

lartolozzi (D.) Osservazioni sul cholera che ha regnato nell'estate del 1855 a Pescia, e cenno delle malattie che l'hanno preceduto da tre anni.

[Gaz. med. it. Tosc., 1856, ii, 3a s., pp. 33-35, 37-42, 45-49.]

Piedmont.

Tarlocco (F. A.) Osservazioni sul colera morbus che imperversò in Piemonte nel 1835 con alcuni suggerimenti per prevenire questa spaventevole malattia o curarla con successo. 8°. *Torino*, 1849. L.

Pisa.

Puccianti (G.) Sul cholera che dominò a Pisa nel 1855.

[Gaz. med. it. Tosc., 1856, ii, 3a s., pp. 203-205, 212-214, 220-222.]

Podenzano.

Daneri (L.) Sulla natura e sul metodo curativo del cholera asiatico e intorno ai contagi, non appendice sul cholera di Podenzano del 1854 ed esito curativo. 8°. *Piacenza*, 1854.

Poggibonsi.

Burresi (P.) Sul coléra epidemico della comunità di Poggibonsi nel 1855.

[Gaz. med. it. Tosc., 1855, i, 3a s., pp. 408-413, 417-422; *also*, reprint in 8°, Firenze, 1855.]

Pomaro Monferrato.

Giorcelli (A.) Sulla epidemia colérosa di Pomaro Monferrato. *Casale*, 1867.

Valerani (F.) Il cholera in Pomaro Monferrato. 8°. *Alessandria*, 1867. L.

Poppi.

Sancasciani (C.) Sull'epidemia colérosa che ha dominato nella comune di Poppi nell'anno 1855, e sui grandi cangiamenti avvenuti nei morbi sporadici.

[Gaz. med. it. Tosc., 1856, ii, 3a s., pp. 320-322, 328-330, 336-340, 347-349, 379-381, 386-388, 398-401, 408-410.]

Porto Ferrajo.

Chiarugi (E.) Il cholera in Portoferrajo.

[Gaz. med. it. Tosc., 1856, ii, 3a s., pp. 119-121.]

Predal.

Torre (G.) Resoconto e relazione medica della commissione di soccorso del sestiere di Predal 27 Luglio al 30 Settembre 1854. 8°. *Genova*, 1854.

Rodi.

Baculo (B.) Il cholera-morbus in Rodi, cenno pronunziato in pubblica adunanza li 4. Dicembre 1836 . . . . 2a ed. 8°. *Foggia*, 1837.

Romagnese.

Arciprete (B. D. P.) Cenni sul colera scoppiato in Romagnese nell'anno 1867. 8°. *Romagnese*, 1867. S. C.

Rome.

Ceccarelli. Notes on cholera at Rome in 1854.

[MED. Times & Gaz., 1862, II, n. s., pp. 31–32.]

Papillon (E.) Note sur un foyer cholérique. Voisinage de la Cloaca Maxima.

[GAZETTE méd. de Strasbourg, 1868, XXVIII, pp. 67–68.]

Ruga (P.) Sul metodo adoperato nella cura del colera asiatico in Roma, nell'anno 1837. 8°. *Roma*, 1838.

Sabbattini (L.) Sul cholera asiatico in Roma. 8°. *Roma*, 1854.

Scalzi (F.) Il cholera in Roma nel 1867. 8°. *Roma*, 1867. S. C.

Toscani (D.) Relazione sul cholera asiatico in Roma nell'anno 1867. *Roma*, 1868.

Trompeo. Rapporto sulla memoria del prof. F. Scalzi intitolata: Il cholera di Roma nel 1867.

[GIORN. d. R. accad. di med. di Torino, 1868, VI, 3a s., pp. 263–266.]

——— Relazione sul colera asiatico in Roma nel 1867.

[GIORN. d. R. accad. di med. di Torino, 1868, VI, 3a s., pp. 137–138.]

Statistica di coloro che furono presi dal cholera asiatico in Roma nell'anno 1837, umiliata alla Santità di nostro signore papa Gregorio XVI dalla commissione straordinaria di pubblica incolumità. 4°. *Roma*, 1838.

San Giovanni.

Pepere (P.) Rapporto sul cholera di S. Giovanni a Teduccio nel 1865 alla commissione medica di vigilanza. *Napoli*, 1865.

San Miniato.

Neri (G.) Il cholera a S. Miniato nell'estate del 1855. *Fano*, 1856.

Pieragnoli (M.) Delle malattie che dominarono in S. Miniato e sue adiacenze negli anni 1854–55 e più particolarmente della choléra.

[GAZ. med. it. Tosc., 1855, I, 3a s., pp. 425–428, 433–435.]

San Pier d'Arena.

Canevari (G. B.) Alcune notizie intorno al comune di S. P. d'Arena ed al choleramorbus che vi ha regnato nel 1855. 8°. *Sanpierdarena*, 1855.

San Severo.

Vera (L.) Il cholera in Sanseverino. 8°. *Napoli*, 1865.

Santo Angelo.

Sandulli (L.) Il cholera del 1837 in Santo Angelo Tremonti (Principato Ulteriore). 8°. *Tremonti*, 1867.

Sardinia.

Du Jardin (G.) Memorie storico-cliniche sul cholera indico osservati in Sassari nell'epidemia del 1855. 16°. Genova, 1856.

Mohaupt (P.) *Observationes de cholera asiatica in epidemia Sedinensi. *Gryphiswaldiae*, 1867.

Timermans (G.) Sulle epidemie cholerose degli stati Sardi relazione alla consulta centrale dell'associazione medica. 8°. *Torino*, 1857.

Sicily.

Linares (A. *e* V.) Biografie e ritratti d'illustri Siciliani morti nel cholera l'anno 1837 . . . 12°. *Palermo*, 1837.

Siciliana.

Bonadonna (F. P.) Relazione medica sull'epidemia del cholera scoppiato in Siciliana letta alla commissione municipale di sanità. 4°. *Corpo* 1867.

Sirta.

Taroni (P.) Il coléra in Sirta nel 1855.

[GAZ. med. it. Lomb., 1855, VI, 3a s., pp. 46–

Sondrio.

Movimento del coléra nella città di Sondrio.

[GAZ. med. it. Lomb., 1855, VI, 3a s., pp. 338, 356.]

Stradella.

Movimento del coléra in Stradella.

[GAZ. med. it. Lomb., 1854, V, 3a s., p. 2

racuse.

overta (La) del cholera in Siracusa, ossia il racconto fedele degli originali fatti ivi avvenuti nel Luglio 1837. Scritto da un Siracusano. 8°. *Palermo*, 1838. L.

egolo.

lpa (L.) Il coléra nella consorziale condutta di Tregolo.
[GAZ. med. it. Lomb., 1855, VI, 3a s., pp. 377, etc.]

eriso.

s-Liberali (P. L.) Relazione storico-statistica dell'ultima invasione del cholera morbus nel comune di Treviso.
[GIORN. venet. d. sc. med., 1856, VIII, 2a s., pp. 183-215.]

artorelli (F.) Sul coléra di Paderno, Merlengo e Ponzano, nella provincia di Treviso. Cenni storico-statistici.
[GAZ. med. it. Lomb., 1855, VI, 3a s., pp. 325-327.]

lota numerica dei casi di coléra verificatisi nella città e provincia di Treviso.
[GAZ. med. it. Lomb., 1855, VI, 3a s., pp. 257, 264, 289, 321, 336, 356.]

risino.

lugna (G.) Sul cholera che fu in Trisino di Vicenza nei mesi di Luglio ed Agosto del 1836.
[OMODEI, Ann. un. di med., 1837, LXXXII, pp. 288-306.]

uria.

onino (G. G.) Il cholera morbus nella città di Torino. 4°. *Torino*, 1855.

lizzetti. Sunto dell'istoria documentata delle epidemie di colera di Torino nel 1565 e 1866.
[GIORN. d. R. accad. di med. di Torino, 1867, IV, 3a s., pp. 385-415.]

lovimento del coléra in Torino.
[GAZ. med. it. Lomb., 1854, V, 3a s., pp. 300, etc.]

uscany.

letti (P.) Dei venti medici morti in Toscana durante l'invasione colerica degli anni 1854-55. Cenni biografici con note . . . . . 8°. *Firenze*, 1856.

—— Documenti annessi alle considerazioni sul cholera che contristo la Toscana negli anni 1835-36-37-49. 8°. *Firenze*, 1856-57.

—— Prima appendice alle considerazioni sul cholera asiatico che contristo la Toscana negli anni 1835-36-37-39, comprendente la invasione colerica del 1854. 8°. *Firenze*, 1856-57.

Betti (P.)—continued.

—— Seconda appendice . . . 2 v. 8°. *Firenze*, 1858.

Gason (J.) Remarks on the cholera which raged in Tuscany in 1855; together with an account of a new mode of treatment.
[MED. Circular, London, 1860, XVII, pp. 421-422.]

Puccinotti (F.) Lettere storiche sul cholera-morbus della Toscana. Dirette al ch. professore cav. Salvatore De Renzi.
[*With* PUCCINOTTI, Opere med., Milano, 1855, I, pp. 917-950.]

Varazze.

Maurizio (A.) Storia del cholera-morbus in Varazze l'anno 1837. 8°. *Genova* [*n. d.*]

Venice.

Asson, Cortesi, Fario, e Pancrazio. Intorno alla prima invasione del cholera-morbus in Venezia.
[OMODEI, Ann. un. di med., 1836, LXXVIII, pp. 417-452; LXXIX, pp. 78-113.]

Berti. Studi sulle relazioni del cholera in Venezia colle vicende meteorologiche e col calendario religioso e civile. *Venezia*, 1859.

Caffi (T.) Cenni sulla irruzione del colera nelle provincie Venete, contegno tenuto dai medici durante il suo domino, e compendio analitico di alcune opere sullo stesso. 8°. *Venezia*, 1837.

Derchich (J.) Die Cholera-Epidemie im venezianischen Gebiethe in den Jahren 1835 und 1836.
[MED. Jahrb. d. k. k. oesterr. Staates, 1839, XX, n. F., pp. 4-7.]

Duodo (G.) Tavole statistiche dell'intero corso del cholera in Venezia.
[GIORN. p. serv. al progr. di patholog., Venezia, 1837, VI, pp. 15-38.]

—— Prospetti dimostranti l'andamento diviso per decadi di tutte le nove epidemie coleriche avutesi in Venezia. 4°. *Venezia*, 1874.

—— Prospetti statistici risguardanti il cholera a Venezia nel 1873.
[GIORN. ven. di sci. med., 1874, XX, pp. 7-27, 4 tab.]

Hildenbrand (F., *Edler von*). Ueber die Cholera in Venedig und im venetianischen Gubernial-Gebiethe.
[MED. Jahrb. d. k. k. oesterr. Staates, 1836, X, n. F., pp. 490-496.]

Namias (G.) Memoria intorno alle malattie che dominarono a Venezia nell'ultimo quadrimestre del 1835.
[GIORN. p. serv. al progr. d. patolog., 1835, III, pp. 259-321.]

Namias (G.)—continued.

——— Intorno alla memoria del cav. professor Speranza sul cholera vagante nelle provincie Venete.

[GIORN. p. serv. al progr. d. patolog., 1836, v, pp. 153–155.]

——— Sul choléra di Venezia dell'anno 1855; cenni della giunta centrale di sanità. 8°. *Venezia*, 1856.

——— Storia naturale e cura del colera, due letture tenute all'ospitale civile di Venezia. 3a ed. 12°. *Milano*, 1873. L.

Speranza (C.) Osservazioni del cholera vagante nelle provincie Venete.

[GIORN. p. serv. al progr. d. patolog., 1836, IV, pp. 433–491; V, pp. 81–153.]

Stéer (M. F.) Cenni intorno lo stato attuale dell'epidemia tellurica dominante [detta cholerica] riguardo all'Italia e soprattutto alle provincie Venete.

[OMODEI, Ann. un. di med., 1832, LXIII, pp. 225–242.]

Turri (R.) Cholera: il primo caso nel Venete [nel 1865].

[GAZ. med. ital. prov. Venete, 1865, VIII, p. 377.]

Ziliotto (P.) Discorso sul colera della provincia di Venezia nel 1855.

[GIORN. venet. d. sc. med., 1857, IX, 2a s., pp. 40–92.]

Cenni della giunta centrale di sanità sul colera di Venezia nell'anno 1855.

[GIORN. venet. d. sc. med., 1857, IX, 2a s., pp. 93–121.]

Vernazza.

Rossi (G.) Del cholera in Vernazza l'autunno del 1855 a consiglio sanitario provinciale. 8°. *Genova*, 1855.

Verona.

Agostini (A.) Resoconto statistico-nosologico per l'anno camerale 1854–55 del circondario di Verona del Consorzio della Cassa di soccorso presso l'I. R. esercizio delle strade ferrate Lombardo-Venete dello stato. [Estratto: Sul cholera.]

[OMODEI, Ann. un. di med., 1856, CLVI, pp. 251–266.]

Versilia.

Galligani (S. G.) Della choléra della Versilia nel 1854 e 1855.

[GAZ. med. ital. Tosc., 1856, II, 3a s., pp. 260, etc.]

Vespolate.

Galli (G. e E.) Del colera e della sua comparsa in Vespolate nella state del 1867. *Milano*, 1867.

Viareggio.

Pieri (A.) Rapporto sulla coléra dominata epidemicamente nell'estate ultima a Viareggio.

[GAZ. med. ital. Tosc., Firenze, 1856, II, 3a s., pp. 89–92.]

Vicenza.

Movimento del coléra in Vicenza.

[GAZ. med. it. Lomb., 1855, VI, 3a s., pp. 238, etc.]

Vico.

Santini (F.) Cenni storico sul colera che domino in Vico nel Settembre 1837. 8°. *Ferentino*, 1838.

Vignola.

Tosi (L.) Osservazioni sopra l'andamento e la cura del cholera che ha regnato a Vignola.

[GAZ. med. ital. Tosc., 1855, I, 3a s., pp. 332–333.]

Villanova.

Contini (V.) Il cholera di Villanova. *Casal Maggiore*, 1868.

THE NETHERLANDS.

Beduin (S.) De Cholera-Sterfte in Nederland in het Jaar 1866, graphisch voorgesteld.

[NEDERL. Tijdschr. v. Geneesk., 1867, II, pp. 337–344.]

Fremerij (P. J. I. de). Verslag uit het Archief voor de Cholera. [*Also,*] Bijvoegselen uit het Archief voor de Cholera. 8°. [*n. p., n. d.*] L.

Godefroi (M. J.) De Cholera en de openbare Gezondheidsregeling in Nederland. 8°. *Hertogenbosch*, 1866. L.

Hanlo (J.) Statistieke Opgaaf van het Beloop der Cholera in de verschillende Gemeenten van ons Koningrijk gedurende 1866 (8 April tot 15 Dec.)

[NEDERL. Tijdschr. v. Geneesk., 1867, II, pp. 130–143.]

——— Statistieke Opgaaf der Cholera-Sterfte in de verschillende Gemeenten gedurende 1867.

[NEDERL. Tijdschr. v. Geneesk., 1868, II, pp. 493–494.]

Jorritsma (T. A.) Een Woord aan mijne Land- en Stadgenooten, vooral ook aan de Gemeente-Besturen in Nederland, bij het Heerschen van den aziatischen Braakloop. 8°. *Horen*, 1832. L.

ıte (J. J. L. ten). De Cholera in Nederland. Zang des Tijds. 8°. *Amsterdam* 1849.

enn (J.)] Over Maatregelen ter Wering en Vermindering der epidemische Cholera in Nederland. 4°. *Amsterdam*, 1853.

unier (J. J. D.) Extrait de l'enquête ur le choléra de 1866, dans les cantons le Contich et de Wilryck.

ANNAL. Soc. de méd. d'Anvers, 1875, XXXV, pp. 36, 129-161.]

eman (J.) Geschiedenis van de Cholera ;edurende 1859 in Nederland.

NEDERL. Tijdschr. v. Geneesk., 1860, IV, pp. 675-718.]

— The same. 4°. [*n. p., n. d.*] L.

gemeen Rapport der Commissie tot het Onderzoeken van den Aard en de meest geschikte Wijze van Behandeling van len aziatischen Braakloop. 8°. *'s Gravenhage*, 1832.

jdragen tot de Kennis en Behandeling van den aziatischen Braakloop in Nederland. [Nos. 1 to 18, August, 1832, to April, 1833. *Also,*] Bijlage. Stand van den aziatischen Braakloop in het Koningrijk der Nederlanden. Door D. J. A. Arntzenius. 8°. *Amsterdam*, 1832-33. L.

ıolera (De), Bijblad tot de geneeskundige Courant voor het Koningrijk der Nederlanden, van Zondag, July 1-Dec. 9, 1849. 8°. *Tiel*, 1849. L.

ıolera-Epidemie (De) in Nederland in 1866 en 1867. 1ste Stuk. Uitgegeven door het Departement van binnenlandsche Zaken. roy. 8°. *Gravenhage*, 1872. L.

[2 Stuck was published in 1873.]

ıolera-Epidemie in Nederland, statistieke Opgaven.

[NEDERL. Tijdschr. v. Geneesk., 1866, I, pp. 208, 223, etc.]

edachten over de Cholera morbus (aziatischen Braakloop) voor mijne Stad- en Landgenooten te Zierikzee. 8°. *Zier*, 1832.

orte Beschrijving van den thans heerschenden aziatischen Braakloop of Cholera en deszelfs Genezing. 16°. *Gravenhage*, 1831. L.

— The same. 8°. [*Also,*] Aanwijzing ter Bewaring van de Gezondheid, en ter Voorbehoeding van de Aansteking van den aziatischen Braakloop of Cholera. 16°. *Gravenhage*, 1831. L.

Medaille in Nederland uitgereikt voor verleenden Bijstand gedurende het Heerschen in 1866.

[NEDERL. Tijdschr. v. Geneesk., 1866, I, p. 44.]

Mededeelingen en Berigten van Cholera.

[NEDERL. Tijdschr. v. Geneesk., 1867, I, pp. 16, 30, etc.]

Opwekking aan mijne Landgenooten bij het Indringen der Cholera in Nederland, 8°. *Leijden*, 1832.

Over Maatregelen ter Wering en Vermindering der epidemische Cholera in Nederland. (Overgedrukt uit het nederlandsch Weekblad voor Geneeskundigen, No. XXXVII, 10 Sept. 1853.) 4°. *Amsterdam*, 1853. L.

Rapport der Commissie van den aziatischen Braakloop. 8°. *Gravenhage* 1832. L.

Amsterdam.

Stokvis (B. J.) De Cholera-Sterfte bij de Israëlieten te Amsterdam.

[NEDERL. Tijdschr. v. Geneesk., 1867, II, pp. 104-110.]

Vrolik (W.) Berigten betreffende de asiatische Cholera te Amsterdam en in andere Deelen des Rijks. Onder Medewerking van G. Vrolik, C. J. Nieuwenhuys, H. Haakman, etc. 2 v. 8°. *Amsterdam*, 1832. L.

Beschrijving van de 24 medicin. Wijken der St. Amsterdam, . . . ten Dienste der Wijk-Kommiss. bij de Verzorg. van Ch.-Lijders. 8°. *Amsterdam*, 1832.

Cholera [Statistics of, in Amsterdam].

[GENEESK. Courant, Tiel, 1848, Nos. 43-49; 1855, Nos. 34-42; 1866, Nos. 29-38.]

Verslag der centrale Cholera-Commissie te Amsterdam, ingediend 13 Febr. 1854. 8°. *Amsterdam*, 1854.

Verslag der plaatselijke geneeskundige Commissie te Amsterdam, over de in 1855 geheerscht hebbende Cholera. 8°. *Amsterdam*, 1856. L.

Arnhem.

Cholera [Statistics of, in Arnhem].

[GENEESK. Courant, Tiel, 1849, Nos. 31-34.]

Charlois.

Groot (H. de). Kort Verslag der Cholera-Epidemie te Charlois.

[GENEESK. Courant, Tiel, 1849, No. 12.]

Delft.

Westerouen van Meeteren (G. N.) Een Woord aan het Publiek, ten Opzigte van het Uitbreken der Cholera asiatica te Delft of 1832. 8°. *Delft*, 1832.

Dort.

Cholera [Statistics of, in Dordrecht].
[GENEESK. Courant, Tiel, 1848, Nos. 49–50; 1849, Nos. 9, 24, 31; 1853, Nos. 42–44; 1854, No. 47; 1866, Nos. 27–34.]

Gelderland.

Kiehl (W. F. P.) Verslag over de Cholera-Epidemie in de Provincie Gelderland in 1866. 8°. [*n. p., n. d.*] L.

Gouda.

Büchner (W. F.) Aanteekeningen en Opmerkingen betrekkelijk den aziatischen Braakloop te Gouda. Met 9 Tab. en platten Grond. 8°. *Amsterdam*, 1833.

Groningen.

Coronel (S.) De Reiniging te Groningen en de Cholera.
[NEDERL. Tijdschr. v. Geneesk., 1867, II, pp. 374–375.]

Eekma (B.) De Circulaire van den 26sten July 1832, bevattende eene Lijst van Geneesmiddelen tegen den aziatischen Braakloop, uitgeschreven door de provinciale Commissie van Onderzoek en Toevoorzigt te Groningen getöstaande Doelmatigheid etc. 8°. *Winschoten*, 1834.

Gerhards (W.) Verslag van de Commissie voor Cholera-Zieken te Groningen, omtrent hare Werkzaamheden gedurende het Heerschen dier Ziekte aldaar, in het Jaar 1849, opgedragen aan allen, die haar op de eene of andere Wijze ondersteunden ter Bereiking van het Doel, dat zij zich voorstelde. 8°. *Groningen*, 1849. L.

——Verslag van de Werkzaamheden der Commissie voor Cholera-Zieken te Groningen in het Jaar 1855. Met een' Brief van den Hoogleeraar J. Baart de la Faille, tot Voorberigt. 8°. *Groningen*, 1855. L.

——The same . . . in het Jaar 1854. Benevens eenige Opmerkingen en Bijzonderheden op deze Epidemie betrekkelijk medegedeeld door Haren Voorzitter. 8°. *Groningen*, 1855. L.

Reilingh (D. DeV.) Eenige Aanteekeningen over het Onstaan en de Verbreiding der Cholera te Groningen, in 1853 en vooral in 1864. (Overgedrukt uit het Reper[illegible], Jaargang viii, Nr. 1.) 8°. L.

Wageningen (S. R. D. van). "De[illegible] ra asiatica quæ annis 1854 et 1[illegible] urbe Groningana sæviit. 8. *Gro.* [1856].

Cholera [Statistics of, in Groningen].
[GENEESK. Courant, Tiel, 1848, Nos. 49–50; 1849, Nos. 23, 25; 1855, Nos. 37–43; 1866, Nos. 27–34.]

Overdenkingen voor alle Chr[illegible] bij de thans heerschende Cholera [illegible] *Groningen.*

Praktische Opmerkingen nopens [illegible]lera-Asiatica, zoo als zij van 1[illegible] tot nu toe, in de Stad Groninge[illegible] schende is.
[PRACT. Tijdschr. voor de Geneesk., [illegible] pp. 7–20.]

Werkzaamheden der Commis[illegible] Cholera-Zieken te Groningen.
[NEDERL. Tijdschr. v. Geneesk., 1[illegible] 31, 48.]

Haarlem.

Cholera [Statistics of, in Haarlem].
[GENEESK. Courant, Tiel, 1849, Nos. [illegible] Nos. 29–34.]

Hague.

Geese (J. P. van). Verslag [illegible] aziatischen Braakloop te H[illegible] redijk, 's Hage. 8°. *Thierrij en M.* 1832.

Cholera [Records of, in Gravenha[illegible]
[GENEESK. Courant, Tiel, 1854, Nos. [illegible] Nos. 40–43; 1863, Nos. 24–34.]

Holland.

Alexander (W.) The cholera in H[illegible] and the sanitary condition of that [illegible] try.
[Jour. of Pub. Health, 1849, II, pp. [illegible] 312–313.]

——Remarks on the cholera, as it ex[illegible] in Holland.
[LANCET, 1849, II, 2. s., pp. 69–70.]

Ballot (A. M.) The water supply [illegible] land, and cholera.
[MED. Times & Gazette, 1869, I, pp. 63–[illegible]

Duilboulin (T.) Lettre sur le C[illegible] en Hollande.
[GAZ. méd. de Paris, 1866, XXI, pp. 462–[illegible]

Heine (J. G.) Auszug aus dem im A[illegible] Juli 1832, bald nach dem Ersch[illegible] der asiatischen Brechruhr in Ha[illegible] in deutscher und holländischer Spra[illegible] [etc.] * * * aus den k. bayer. [illegible] taets Office Anord. 4°. *Bonn*, 18[illegible]

Jacobi (H.) De Cholera in Noord[illegible] land.
[NEDERL. Tijdschr. v. Geneesk., 18[illegible] 117–129.]

oreau de Jonnès (A.) Aperçus statistiques sur l'irruption du choléra oriental en Hollande, pendant 1832.
[Gaz. med. de Paris, 1833, I, pp. 300–302.]

olera.
[Verslag aan den Koning, 's Gravenhage, 1866, pp. 110–113; 1869, pp. 385, 438.]

olera. [Records of cholera in Holland.]
[Geneesk. Courant, Tiel, 1855, Nos. 43, 44, 47.]

uldbetooning aan Geneeskundigen voor, tijdens het Bestaan der Cholera, bewezene Diensten.
Geneesk. Courant, Tiel, 1850, No. 29.]

orte Berigten omtrent de Cholera in ons Land.
Geneesk. Courant, Tiel, 1849, No. 35.]

apport, nopens den Stand der Cholera asiatica in het Ressort, van de provinciale Commissie van geneeskundig Onderzoek en Toevoorzigt in Zuid-Holland, residerende te 's Gravenhage, op den 12 Oct. 1853.
Geneesk. Courant, Tiel, 1853, Nos. 42, 43, 44, 47, 49.]

Kampen.

holera [Records of, in Kampen].
Geneesk. Courant, Tiel, 1866, Nos. 29–34.]

Culenburg.

Alpherts (W. J.) Verslag der Cholera asiatica, zoo als zij van 13 Nov. 1848 tot 1. Januarij 1849, te Culenburg is waargenomen.
Pract. Tijdschr. voor de Geneesk., 1849, XXVIII, pp. 193–199.]

Leeuwarden.

holera [Statistics of, in Leeuwarden].
Geneesk. Courant, Tiel, 1849, Nos. 25, 27, 37; 1855, No. 41.]

Leyden.

Dozy (F.) Verslag van hetgeen. betr. de Cholera asiatica, in het 3e Cholerazieken-huis te Leiden is waargenomen. 8°. [*n. p.*, 1833.]

Hoeven (C. P. van der), Kaathoven (C. W. H. van), *en* Salomon (G.) Geschiedverhaal van de Cholera-Epidemie te Leiden in 1832. 8°. *Leiden*, 1833. L.

Langelaan (J. J.) *Verslag aangaande het Cholera-Hospitaal te Leiden. 8°. *Leiden*, 1866. L.

Cholera [Records of, in Leyden].
Geneesk. Courant, Tiel, 1866, Nos. 24–34.]

Loenen.

Meer Mohr (J. H. van der). Cholera-Epidemie te Loenen.
[Nederl. Tijdschr. v. Geneesk., 1860, IV, pp. 114–115.]

Luxemburg.

Rapport sur les épidémies de choléra et de suette qui ont sévi dans le grand-duché de Luxembourg. Pendant les années 1865 et 1866, fait à la Société des sciences médicales de Luxembourg par la commission nommée par elle dans le but d'étudier ces épidémies et composée de MM. les docteurs Bivort, Feltgen et P. Schmit.
[Bull. de la Soc. des. sci. med. du grand-duché de Luxembourg, 1868, pp. 1–314, 1 map, 10 tables.]

Meppel.

Cholera [Records of, in Meppel].
[Geneesk. Courant, 1854, Nos. 44, 47, 50; 1866, Nos. 30–34.]

Ouderamstel.

Campen (J. E. C. van). De Cholera-Epidemie te Ouderamstel, beschound uit het Oogpunt van de Contagiositeit der Ziekte.
[Pract. Tijdschr. voor de Geneesk., 1855, I, n. s., pp. 667–674.]

Rotterdam.

Ballot (A. M.) Onderzoek naar de Sterfte te Rotterdam en hare Oorzaken.
[Nederl. Tijdschr. v. Geneesk., 1873, II, pp. 113–156.]

Mulder (G. J.) *en* Pant (D. F. van der). De Cholera in Rotterdam. 8°. *Rotterdam*, 1832. L.

Zwaan (H. de). Verslag van het Cholera-Hospitaal te Rotterdam, van het Jaar 1866. (Acad. Proefschr.) 8°. *Gravenhage*, 1867. L.

Algemeen Verslag der Sub-Commissie voor den aziatischen Braakloop geheerscht hebbende te Rotterdam in 1848 en 1849. 8°. 1849. L.

Algemeen Verslag der Sub-Commissie voor de Zaken den aziatischen Braakloop aangaande te Rotterdam: aan de Hoofd-Commissie in de Provincie Holland. Zuidelijk Gedeelte gevestigd te 's Gravenhage. 8°. *Rotterdam*, 1833. L.

Cholera [Statistics of, in Rotterdam].
[Geneesk. Courant, Tiel, 1848, Nos. 46–53; 1849, Nos. 1–7, 14–23, 27–34; 1853, Nos. 37–40; 1854, Nos. 1–9, 51; 1855, No. 46; 1866, Nos. 18–39, 40–42; 1867, Nos. 38–41.]

Verslag van de Commissie ter Zake van de aziatische Cholera te Rotterdam in het Jaar 1866. 8°. [*Rotterdam,*] 1867. L.

Verslag van de speciale Commissie over de Cholera asiatica, geheerscht hebbende te Rotterdam, in de Jaren 1853 en 1854. 8°. [*n. p., n. d.*] L.

Scheveningen.

Arntzenius (J. A.) Brief over de Wijze van Ontstaan van den aziatischen Braakloop te Scheveningen. 8°. *Amsterdam,* 1832. L.

D'Aumerie (J. F.) Herinneringen uit de Cholera-Epidemie te Scheveningen. 8°. *Gravenhage en Amsterdam,* 1833. L.

Heine (J. G.) Circulaire betr. de aziatische Ch., welke den 30 Junij te Scheveningen is uitgebroken. Met Bijvoegsel. 2 Stu. 4°. *'s Gravenhage,* 1832.

——— Copie von dem Briefe über die asiatische Cholera, welchen der Verfasser Anfangs Juli 1832 unmittelbar nach dem Eindringen der Cholera-Krankheit in Holland, in dem Fischerorte Scheveningen, wo das unter demselben Namen bekannte Seebad, und nahe hinter dieser orthopaedischen Seebadanstalt, zuerst ausgebrochen ist, [etc.] 4°. *Bonn,* 1837. L.

Waardenburg (J. G.) Practische Aanteekeningen betreffende de Cholera te Scheveningen. 8°. *Leiden,* 1832. L.

Schiedam.

Hodenpyl (F. M. T. G.) Specimen medico-practicum, exhibens brevem delineationem cholera, quæ in urbe Schiedamensi regnavit. 16°. *Groningæ,* 1833. L.

Kort Verslag der Cholera-Epidemie van 1848 te Schiedam.
[GENEESK. Courant, Tiel, 1849, Nos. 10, 11; 1866, Nos. 27–34.]

Sneek.

Galama (S. J.) Geschiedenis van den aziatischen Braakloop te Sneek. 8°. [*n. p., n. d.*]

Utrecht.

Blom (P. J.) Bijdragen tot de Kennis en Behandeling van de Cholera asiatica, [ui]tleiding van Waarnemingen [ge]de Epidemie] van 1832 te [U]. *Utrecht,* 1833. L.

Fremerij (P. J. L de). Verha[n]. over het Zuiveren van besmette [ka]ren, vooral door hooge Tempera[tu]r benevens Beschrijving van den To[e]hiertoe gebruikt, tijdens het Heers[c]der Cholera te Utrecht. 8°. [U]. 1833.

Goudoever (L. C. van) en Imans [V]rigt over de Cholera, te Utrecht [in] Hospitaal waargenomen.
[NEDERLAND. Lancet, 1848–49, 2e [d.] 641–674; 1849–50, v. pp. 285–304.]

——— The same. 8°. *Utrecht,* 1[8]

Haerten (J. L. H.) Diss. inaug., [de] historiam cholerae asiaticae an[no] et 1849 dum Ultrajecti regnabat. *Utrecht,* 1850.

Kloos (J. P.) De Cholera onder [het] Garnizoen te Utrecht. (Acad. Proefs.) 8°. *Amsterdam,* 1866.

Snellen (H.) Locale Uitbreiding [der] Cholera-Epidemie, Utrecht, 1866.
[VERSL. van de Vereen. tot Verbet. der [Volks]gezondh., Utrecht, 1866, I, pp. 57–79, 1 p.]

Suerman. De Verspreiding van de Cholera asiatica, in de Provincie Utrecht, 1848 en in het Begin van 1849.
[NEDERLAND. Lancet, 1849–50, 2e s., V, pp. 284.]

Vos (F. E.) Onderzoekingen over de Cholera-Epidemie van 1866, in de gemeente Utrecht. (Acad. Proefschr.) *Utrecht,* 1867.

Archief voor den aziatischen Braakloop en al wat daartoe Betrekking heeft in de Stad en Provincie Utrecht. Door J. I. de Fremerij. 8°. *Utrecht,* 1[8]

Cholera [Statistics of, in Utrecht].
[GENEESK. Courant, Tiel, 1848, Nos. 45 & Nos. 90, 94, 29, 32–33; 1854, No. 46, 24–34.]

**Veralagen van de Vereeniging tot V[er]tering der Volksgezondheid, opgerich[t] Utrecht gedurende de Cholera-Epi[de]in 1866. 2 v. 8°. *Utrecht,* 1866–[67]

Valkenburg.

Wilde (P. G. B. de). Diss. inaug. [de] nens historiam epidemiæ cholerae [a]ticæ quæ mensibus Julii et Augusti 1833 in pago Valkenburg regnavit. *Lugduni Batavorum,* 1833.

Wyk.

Verbeek (W. J. L.) Aanteekeningen Opmerkingen betr. de Cholera-Epidemie te Wijk bij Duurstede (in 1848–[49]

land.

»ecke (J. C. van den) *en* **Man** (J. C. de). **le Cholera asiatica in Zeeland, haar lorsprong en hare Verspreiding gedu-ende de Jaren 1832–1833 en 1848–1849.** *Middelburg*, 1850. L.

ıge (B. de). De Cholera asiatica in Zeeland.

[Genees. Courant, Tiel, 1853, Nos. 44, 50.]

rikzee.

ayne (J. K. de). Mededeelingen en)pmerkingen omtrent de Cholera asiatica, waargenomen te Zierikzee in 1855.

[Pract. Tijdschr. voor de Geneesk., 1856, II, n. s., pp. 341–357.—Aanmerkingen door Dr. Goeman, *ib.*, pp. 711–720.]

NORWAY.

rgfeldt (O.) Beretning om Oslo Lazareth under Cholera-Epidemien i Christiania 1853.

[Norsk. Mag. for Laegevid., 1854, VIII, pp. 580–5[illegible].]

»nradi. Cholera i Christiania og dens Omegn i Aaret 1853.

[Norsk. Mag. for Laegevid., 1854, VIII, pp. 433–460.]

ıye (F. C.) Bemaerkninger om Choleras Maade at Opstaae og Forplante sig paa med saerlight Hensyn til Epidemien i Christiania i 1850.

[Norsk. Mag. for Laegevid., 1851, V, pp. 145–165.]

—— Om Cholera i Norge i Aaret 1853 udenfor Christiania og Akers Sogn.

[Norsk. Mag. for Laegevid., 1854, VIII, pp. 625, 689, 769.]

reng (L.) Beretning om Sorgenfri Lazareth under Cholera-Epidemien i Christiania 1853.

[Norsk. Mag. for Laegevid., 1854, VIII, pp. 516–523.]

olst (A.) Beretning om Pipervigens Lazareth under Cholera-Epidemien i Christiania 1853.

[Norsk. Mag. for Laegevid., 1854, VIII, pp. 570–580.]

förbye. Beretning om Ankerlökkens Lazareth under Cholera-Epidemien i Christiania 1853.

[Norsk. Mag. for Laegevid., 1854, VIII, pp. 561–570.]

ierulf (C. T.) Om Cholera i Bergen og naermeste Omegn.

[Norsk. Mag. for Laegevid., 1849, III, pp. 541–554, 561–564.]

söberg (T. J.) Cholera i Bergen.

[Norsk. Mag. for Laegevid., 1849, III, pp. 271–312.]

Steffen (H.), **Lund** (O.), *og* **Lochman.** Cholera i Christiania i 1866. Beretninger til Sundheds-Commissionen. 8°. *Christiania*, 1867. L.

Winge (E.) Beretning om Grönlands Lazareth under Cholera-Epidemien i Christiania 1853.

[Norsk. Mag. for Laegevid., 1854, VIII, pp. 497–516.]

Actstykker angaaende Cholera, navnlig Epidemieen i Christiania i 1850: besörgede ved den kgl. Cholera-Central-Commission. 12°. *Christiania*, 1851.

Actstykker angaaende Cholera-Epidemien i Norge i 1853 besörgede ved Medicinal-Committeen. *Christiania*, 1854.

Behandling af Cholera i Christiania i 1853.

[Norsk. Mag. for Laegevid., 1853, VII, pp. 856, 858, 864; 1854, VIII, pp. 66, 131, 510, 519.]

Cholera-Epidemien i Christiania i 1850.

[Norsk. Mag. for Laegevid., 1851, V, pp. 57, 66, 126, 167, 291.]

Cholera i Bergen. [4 cases.]

[Norsk. Mag. for Laegevid., 1849, III, pp. 208–217.]

Cholera i Christiani i 1866.

[Norsk. Mag. for Laegevid., 1867, XXI, pp. 1–4 (supplement).]

Cholera (The) in Christiania and parish of Aker.

[Med. Circular, Lond., 1853, III, p. 270.]

Cholerine og Cholera i Christiania i Sommeren 1852.

[Norsk. Mag. for Laegevid., 1852, VI, pp. 801–806.]

Epidemiske Cholera i Straffeanstalterne i Norge.

[Norsk. Mag. for Laegevid., 1841, II, pp. 297–298.]

Forhandlinger i det medicinske Selskab i Christiania i 1848.

[Norsk. Mag. for Laegevid., 1849, III, pp. 52–54.]

Forplantelsesmaade, om dens Cholera, forhandlet i det medicinske Selskab i Christiania.

[Norsk. Mag. for Laegevid., 1854, VIII, pp. 597, 609, 664, 685, 764.]

POLAND.

See, also, under Austria, Prussia, *and* Russia.

Bergson (J.) Die diesjährige Cholera in Polen.

[Med. Zeitung, Berlin, 1849, pp. 10–11.]

Brierre-de-Boismont (A.) Relation historique et médicale du choléra-morbus de Pologne, comprenant l'apparition de la maladie, sa marche, ses progrès, ses symptômes, son mode de traitement et

Brierre-de-Boismont (A.)—continued.
les moyens préservatifs. 8°. *Paris*, 1832. L.

——— Quelques mots sur le choléra-morbus de Pologne et sur son traitement.
[BULL. génl. de thérap. méd. et chir., 1832, I, pp. 175–186.]

——— *et* **Le Gallois.** Lettre sur le choléra-morbus de Pologne, adressée à l'Académie des sciences.
[GAZ. méd. de Paris, 1831, II, pp. 235–236.]

Chamberet. Rapport sur le choléra-morbus, observé en Pologne en 1831.
[REC. de mém. de méd. mil., 1832, XXXII, pp. 14–67.]

Chamberet *et* **Trachez.** Du choléra-morbus de Pologne, renseignements sur cette maladie, recueillis par la commission des officiers de santé militaires envoyée à Varsovie par M. le maréchal duc de Dalmatie . . . 8°. *Paris*, 1832.

Eulenberg. Die Cholera im Königreich Polen.
[BERLIN. klin. Wochenschr., 1871, VIII, p. 142.]

Foy (F.) Choléra-morbus de Pologne: description de la maladie et du traitement.
[GAZ. des hôp., 1831, V, pp. 62–63, 211–212.]

——— Cholera-Morbus in Polen. Leichenöffnungen und Behandlung.
[NOTIZEN aus dem Gebiete der Natur- und Heilkunde, 1831, XXXI, pp. 172–176.]

——— Du choléra-morbus de Pologne; ou recherches anatomico-pathologiques, thérapeutiques et hygiéniques sur cette épidémie. 8°. *Paris*, 1832. L.

Gnuschcke (E.) Die Cholera in Polen, auf einer Reise durch einen Theil dieses Landes beobachtet. 8°. *Berlin*, 1831. L.

Jacoby. Bemerkungen über die gegenwärtige Cholera-Epidemie in Polen.
[VERHAND. der physik.-med. Gesel. zu Königsberg über die Cholera, 1832, pp. 92–112.]

Korabiewicz. Notice sur le choléra-morbus et les différents modes de traitement essayés dans le royaume de Pologne. 8°. *Strasbourg*, 1832.

Latour (A.) Le choléra en Pologne.
[L'UNION méd., 1852, VI, p. 525.]

Pinel (S.) Observations sur le choléra-morbus de Pologne.
[GAZ. méd. de Paris, 1832, III, pp. 101–104.]

Pulst. Die asiatische Cholera im Königreich Polen. Ein Versuch ihre Heilung nach rationellen Principien zu begründen. Auf eigene während einer amtlichen Reise in Polen gesammelte Erfahrungen und Ansichten gestützt. 8°. *Breslau*, 1831. L.

Pulst—continued.

Raciborski. Rapport officiel sur les épidémies de choléra asiatique régnant en Pologne en 1836 et 1837. [Extrait.]
[GAZ. des hôp., Paris, 1838, XII, pp. 555–556, 571.]

Sandras. Observations sur le choléra-morbus de Pologne.
[TRANS. méd., Journ. de méd. prat., Paris, 1832, VII, pp. 22–40, 323–362.]

Schnuhr. Bericht über die Verbreitung der Cholera im Königreiche Polen vom 12ten Mai 1831.
[MAG. der ausländ. Lit. der gesamm. Heilk., 1831, XX, pp. 98–117.]

Tschetgrhin. Rapport du choléra épidémique qui a régné en 1852 dans le royaume de Pologne. [Traduit du polonais par J. C. Smith.]
[REVUE de thérap., Paris, 1853, I, pp. 423–428.]

Wernery. Beobachtungen über die Cholera. Mitgetheilt von Prof. Friedreich in Würzburg.
[HEIDELBERGER klinische Annalen, 1831, VII pp. 525–545.]

Cholera i Polen i 1852.
[BIBL. for Laeger, 1853, III, pp. 157–168.]

Cholera. Nachricht über die Cholera, bekannt gemacht von dem Collegium Medikum des Königreichs Polen. Aus dem Polnischen von F. D. 2te Aufl. 12°. *Danzig*, 1831. L.

Cholera-Morbus (Du) de Pologne; renseignemens sur cette maladie, recueillis par la commission des officiers de santé militaires envoyée à Varsovie par M. le maréchal duc de Dalmatie, ministre de guerre. 8°. *Paris*, 1832. L.

Observation de choléra-morbus; description du choléra pestilentiel de Pologne, traitement, contagion, expériences proposées.
[JOUR. de méd. et de chir. prat., 1831, II, pp. 226–230.]

Rapport lu à l'Académie royale de médecine, et remis à M. le ministre du commerce et des travaux publics, en décembre 1831, par MM. C. Allibert, Boudart, etc., membres de la commission envoyée en Pologne pour étudier le choléra-morbus. 8°. *Paris*, 1832.

Sur le choléra épidémique qui sévit en Pologne, par M. Tschetgrhin. (Rapport de M. Gérardin.)
[BULL. de l'Acad. nat. de méd., Paris, 1852–53, XVIII, pp. 193–202.]

PORTUGAL.

urdner (W.) History of the progress of the malignant cholera from Oporto to Lisbon.
[LANCET, 1834–35, I, pp. 314–320.]

oléra (Du) en Portugal.
[L'UNION méd., 1854, VIII, p. 544.]

bon.

varenga (P. F. da Costa). Relatorio sobre a epidemia de cholera morbus no hospital de Sant' Anna em 1856 . . .
. *Lisboa*, 1858.

atistique sur le choléra épidémique à l'hôpital spécial de Lisbonne en 1856.
[GAZ. hebd. de méd. et de chir., 1858, V, pp. 684–695.]

orto.

urdner (W.) The malignant cholera in Oporto in 1833.
LANCET, 1832–33, II, pp. 300–302.]

RUSSIA.

abington (B. G.) Report on cholera in the Black Sea and Baltic fleets in the autumn of 1854.—Black Sea fleet.
[JOUR. of Pub. Health, 1856, London, II, p. 413; *also*, in TRANS. Epidem. Soc., 1856, p. 89.]

acker (L. T.) Choleraepidemien i Russland i 1847.
[NORSK. Mag. for Laegevid., 1849, III, pp. 721–740.]

elgrave (T. B.) The cholera in St. Petersburg and Cronstadt.
[MED. Times & Gaz., 1866, II, pp. 459–460.]

lumenthal (H.) Flüchtiger Schattenriss der sogenannten Cholera indica, wie sie im Jahre 1830 in der östlichen Hälfte des europäischen Russlands epidemisch herrschte.
[MAG. f. d. gesammte Heilk., 1831, XXXIII, pp. 554–581.]

rasche (A.) * Quaedam de cholera epidemia anno 1853. 8°. *Dorpat*, 1854. L.

nek (H. W.) Die bisherige Verbreitung der jetzt besonders in Russland herrschenden Cholera, erläutert durch eine Karte und eine dieselbe erklärende kurze Geschichte dieser Epidemie. 8°. *Hamburg*, 1831. L.

rvellerie (F.) Riflessioni patologiche e pratiche sul colera-morbus di Russia e delle Indie; precedute da un cenno storiografico dell'invasione della malattia dall'Asia nella Russia Europea. . . 8°. *Napoli*, 1835.

Chrichton (*Sir* W.) An account of the introduction and progress of the cholera-morbus in Russia to the end of the year 1830, exhibiting the principal facts which strengthen the belief of its being a contagious disorder . . .
[MED.-CHIR. Rev., 1832, XX, pp. 168–224, 266–283.]

Edmonston (A.) A brief inquiry into the nature and causes of the cholera, which has prevailed and at present prevails in the Russian armies. 8°. *Edinburgh*, 1831. L.

Everard. Un mot sur le choléra qui règne en Russie.
[BULL. de l'Acad. roy. de méd. de Belgique, 1853–54, XIII, pp. 201–220.]

——— Communication sur le choléra qui règne en Russie. 8°. *Bruxelles*, 1854.

Frettenbacher. Note sur la marche de l'épidémie du choléra en Russie en 1847 et 1848.
[GAZ. méd. de Paris, 1849, IV, pp. 23–28.]

Hawkins (B.) History of the epidemic spasmodic cholera of Russia. Illustrated by numerous official and other documents. 8°. *London*, 1831. L.

Hinze (F.) Der Rathgeber in der Cholera. Anweisung des Verhaltens während der Epidemie und bei Erkrankungsfällen. Entworfen nach Beobachtungen und Erfahrungen aus den Epidemien von 1813 und 1848 in Russland. 8°. *Lübeck*, 1848. L.

Jachnichen. Mémoire sur le cholera-morbus qui règne en Russie.
[GAZ. méd. de Paris, 1831, II, pp. 83–88.]

Koeppen (P.) Baktschisaraj, zur Zeit der Cholera 1830. Nebst einem Vorwort von J. R. Lichtenstaedt. 8°. *St. Petersburg*, 1831. L.

Labarraque. Le choléra-morbus dans la Russie.
[GAZ. des hôp., Paris, 1831, IV, pp. 157–158.]

Lanyer. Du cholera-morbus en Russie.
[ANN. de la méd. phys., Paris, 1830, XVIII, pp. 654–669.]

Lasèque (C.) De la marche du choléra dans la Russie méridionale.
[ARCHIV. gén. de méd., 1848, III, pp. 114–119.]

Lichtenstädt (J. R.) Die asiatische Cholera in Russland in den Jahren 1829 und 1830. Nach russischen amtlichen Quellen bearbeitet. 8°. *Berlin*, 1831. L.

——— The same. 2te Aufl. *Berlin*, 1831. L.

Lichtenstädt (J. R.)—continued.

——— The same. In den Jahren 1830 und 1831. Nach russischen Aktenstücken und Berichten so wie nach eignen Erfahrungen. 8°. *Berlin*, 1832. L.

——— Die asiatische Cholera in Russland im Jahre 1847.

[MED. Zeitung, Berlin, 1847, pp. 193–195; 1848, pp. 135–1. 8.]

Mackenzie. Notice of the cholera in Russia in 1848.

[LONDON Med. Gaz., 1848, XLIII, pp. 499–502, 539–542, 587–589, 635–637.]

Margulies (M.) Observations on the Asiatic cholera as it appeared in St. Petersburg in 1848.

[MONTHLY Journal of Med. Sciences, Edinburgh, 1848–49, IX, pp. 620–626.]

Markus (F. C. M.) Notices sur le choléra en Russie. 8°. *St. Pétersbourg*, 1847. L.

Marsicani. Sur le choléra de 1869 en Russie.

[GAZ. méd. de Paris, 1871, pp. 194–196.]

Massaris. Histoire du choléra-morbus qui éclata en Russie, suivi du traitement et du mode de s'en préserver. 8°. *Verceil*, 1835.

Pélican (E.) La marche du choléra en Russie en 1865–6.

[GAZ. méd. de Paris, 1866, XXI, pp. 9–10.]

Russell (W.) *and* **Barry** (D.) Official reports made to government on the disease called cholera spasmodica, as observed by them during their mission to Russia in 1831. With an appendix, and other papers, extracts of letters, reports and communications received from the continent relating to that disease. Published by authority of the lords of H. M.'s most honorable privy council. 8°. *London*, 1832. L.

Spausta, Olexik, *und* **Zhuber.** Amtliche Nachrichten über die Cholera in Russland.

[MED. Jahrb. d. k. k. oesterr. Staates, 1832, II, n. F., pp. 299–312.]

Spiro (A.) Sendschreiben an die k. k. Gesellschaft der Ärzte in Wien über die jetzt in Russland herrschende Cholera-Epidemie.

[ZEITSCHRIFT d. k. k. Ges. der Ärzte zu Wien, 1848, II, pp. 393–397.]

Thomas. Sur la marche du choléra en Russie.

[Bull. de l'Acad. nat. de méd., Paris, 1852–53, XVIII, pp. 1153–1156, 1161–1164, 1178–1179, 1189.]

Varges (A. W.) Ueber die Cholera in Russland.

[ZEITSCHR. d. deutsch. chirurg. Vereins f. Med., Chir. u. Geburtsh., 1848, II, pp. 390–391.]

Zhuber. Vorläufige Nachricht über die Cholera morbus in Russland.

[MED. Jahrb. d. k. k. oesterr. Staates, 1829, I. n. F., pp. 132–138.]

Zimmerman (C.) *Nonnulla de ratione, qua cholera a 1846 in provinciis trans Caucasum sitis primum orta sit et latius serpserit et de epidemiis hujus morbi a 1847. Astrachani et Saratoviae grassatis. 8°. *Dorpat*, 1849. L.

Zschokke (T.) Moskau und Petersburg beim Ausbruch der Cholera morbus. Mit Bemerkungen über die bisher gemachten Erfahrungen von dieser Krankheit. 12°. *Aarau*, 1832. L.

[1st ed. appeared in 1831.]

Choléra en Russie. Sa marche pendant l'année 1848.

[GAZ. des hôp., 1848. p. 421.]

Cholera n Krolestwie Polskiém i n Rosyi.

[PRZEGLAD Lekarski, Krakow, 1871, X, pp. 14, 15, 40, 47, 72, 79, 112, 136, 158, 167, 175, 255, 288, 295, 303, 328, 336, 352, 407.]

Cholera in Russia.

[LANCET, 1870, I, p. 284; 1871, II, p. 29; 1872, II, p. 165.]

Cholera (The) in the Russian empire.

[MED. Times, 1848, XVII, p. 147; XVIII, pp. 181, 197, 260–261, 345.]

Lettre de la commission médicale envoyée en Russie, pour observer le choléra-morbus; adressée à M. le ministre du comm. et des travaux publics, et lue à l'Acad. de médecine.

[GAZ. méd. de Paris, 1831, II, pp. 437–439.]

Morgenländische (Die) **Brechruhr** in Süd-Russland.

[MAG. der ausländ. Lit. der gesammt. Heilk., 1831, XIX, pp. 373–375; 1839, XX, pp. 409–443; 1840, XXI, pp. 1–60.]

Observations sur le choléra-morbus recueillies et publiées par l'ambassade de France en Russie. 8°. *Paris*, 1831. L.

Recueil des faits observés sur le choléra-morbus par les docteurs Hermann, Markus, Jänichen, etc. *Moscou*, 1832.

Ueber die wandernde Cholera in Russland.

[NEUE med.-chir. Zeitung, 1849, II, pp. 1–11.]

[*For statistics of cholera in Russia, see* MED. VESTNIK, St. Petersburg, 1866; *and* MOSKOVSKAIA MED. GAZETU, Moscow, 1866.]

Astrakhan.

Eversmann (E. von). Etwas über die indische Brechruhr, welche sich in d. sem 1830sten Jahre von Astrakan aus über den grössten Theil des europäisch. Russlands verbreitet hat.

[MAG. d. ausländ. Lit. d. gesammt. Heilk., 1831, XXI, pp. 200–243.]

eyerson (M. H.) Die Cholera in Astra-
han.
[Med. Zeitg. Russlands, 1856, pp. 225–231, 233–
238.]
olera in Astrachah.
[Med. Zeitg. Russlands, 1859, p. 350.]

ssarabia.

maiev (V.) Zamietki o cholerie, mej-
iu nijnymi tchynami 129° piechotnaho
Bessarabskaho polka.
[Voienno-medytzynskiy Jurnal, St. Petersburg,
1867, part C', book xi, pp. 195–210.]

ineu.

nkerton (A. W. P.) On the spread of
cholera in the Crimean campaign.
[Edinb. Med. Jour., 1858, III, pp. 867–877.]

rpat.

'eyrieh (v.) Rückblick auf die Chole-
ra-Epidemie zu Dorpat vom Jahre 1871.
[Mit einem Plan der Stadt.]
[Dorpat. med. Zeitschr., 1873, IV, pp. 193–342.]

inaburg.

ichler (E. H.) Heilverfahren gegen die
epidemische Cholera im Dünaburgi-
schen.
[Journ. d. prakt. Heilk., 1832, LXXIV, pp. 105–109.]

lookhov.

raczewsky (J. von). Von der Chole-
ra. Glookhov. Aus dem Polnischen
übersetzt. 8°. *Posen*, 1853. L.

olno.

ishman. Kratkiy otcherk epidemi-
icheskoy cholery, mejdu nijnymo voĭn-
skimi tchynami Grodnienskaho garnizo-
na, s 2° Iulia po 9 Oktiabra 1866. h.
[Voienno-medytzynskiy Jurnal, St. Petersburg,
1867, part C', book xi, pp. 181–193.]
lyltov (A.) V Hrodnie cholera i kakiia
poslvierhlis epidemiu.
[Medytzynskiy Viestnik, St. Petersburg, 1866,
16th year, No. 35, p. 403.]

Helsingfors.

eyfelder (J. F.) Die Cholera im Land-
hospital zu Helsingfors.
[Deutsche Klinik, 1856, VIII, pp. 192–194.]
vist (C.) Om Koleran i Helsingfors 1871
och om föregående Koleraepidemier i Fin-
land. [Ett Bidrag till Landets-Farsots-
Historik.] 8°. *Helsingfors*, 1872. L.

Ismailia.

Companyo (L.) Rapport sur le choléra
à Ismaïlia . . . 8°. *Paris*, 1865.

Kazan.

Kieter (A. v.) Praktische Bemerkungen
über die Cholera zu Kasan im Jahre
1847.
[Med. Zeitg., Berlin, 1848, pp. 127–128.]
Skandowsky (N.) Ueber die Cholera in
Kasan.
[Med. Zeitg., Berlin, 1848, pp. 128–129.]

Kharkov.

Branbeis (H.) Die Cholera-Morbus in
Charkow. Eine den 23. September 1830
gehaltene Vorlesung. Aus dem latein-
ischen Manuscripte. 12°. *Charkow*,
1830. L.

Kherson.

Cholera v Tyraspolskom uiezdie, Cher-
sonskoy hubernii.
[Medytzynskiy Viestnik, St. Petersburg, 1867,
7th year, No. 35, p. 320.]

Kiev.

Hübbenet (C. von). Bericht über die im
Kiew'schen Militärhospitale im Jahre
1848 beobachtete Cholera-Epidemie. 8°.
Riga, 1850. L.
Léveillé. Rapport sur le mémoire du dr.
Hübbenet: Le choléra de 1848 observé à
l'hôpital militaire de Kiew.
[Revue méd., Paris, 1853, II, pp. 257–264.]

Krasnoe-Szelo.

Kozakewiecz (J. de). * Cholerae asia-
ticae in nosocomio militari quod a. 1853
tempore aestivo in vico Krasnoje-Selo
institutum erat decursus et cura. 8°.
Dorpat, 1854. L.

Lithuania.

Burdach (E.) Bericht an die medicinisch-
physikalische Gesellschaft über eine auf
hohen Befehl unternommene Reise nach
dem russischen Lithauen.
[Verh. d. phys.-med. Gesells. zu Königsberg über
d. Cholera, 1832, pp. 113–126.]

Mitau.

Bidder. Erfahrungen über die Brech-
ruhr in Mitau.
[Mag. der ausländ. Lit. der gesammt. Heilk., 1832,
XXIII, pp. 216–238.]

Montenegro.

Cholera v Tchernogoriy.
[MEDYTZYNSKIY Vlestnik, St. Petersburg, 1867, 7th year, No. 32, p. 296.]

Moscow.

Jähnichen. Die Cholera in Moskau, mit kritischen Bemerkungen zu einem Aufsatz vom Herrn Leibmedicus Dr. v. Loder über diese Epidemie.
[LITTERAR. Ann. der gesamm. Heilk., 1831, XIX, pp. 385–450.]

Keir (J.) A treatise on cholera, containing the author's experience of the epidemic known by that name, as it prevailed in the city of Moscow in 1830–31. 8°. *Edinburgh*, 1832. L.

Loder. [Cholera-epidemic in Moscow. Russian text.] *Moscow*, 1831.

Markus (F. C. M.) Rapport sur le choléra-morbus de Moscow. 4°. *Moscow*, 1832. L.

Polunin (A.) Abhandlung über die Cholera, vorzüglich auf Beobachtungen gegründet die in der therapeutischen Hospital-Klinik der kaiserlich-russischen Universität zu Moskau, in den Jahren 1847–48 gemacht wurden. Aus dem Russischen. 8°. *Leipzig*, 1849. L.

Rumiantzev (P.) Nieskolko slov o bolnych choleroiu, byvshych na izletcheniu v Moskovskoy bolnitzie, in 1866.
[MOSKOVSKAIA medytzynskaia gazeta, Moscow, 1867, No. 31, pp. 281–283; No. 32, pp. 293–295; No. 33, pp. 308–310.]

Strumpf. Behandlung der Cholera in der Hospital-Klinik der Universität Moskau.
[MED. Zeitung, Berlin, 1857, p. 78.]

Zoubkoff (B.) Observations faites sur le choléra morbus dans le quartier de la Yakimanka, à Moscou, en 1830. 8°. *Moscou*, 1831. L.

Zukowski. Historiae morbi cholerae indicae apud lectos aegrorum notatae in nosocomiis carcerariis Mosquae ann. 1830 et 1831 epidemice grassatae. 8°. *Moscow*, 1832.

Cholera v Moskvie. [Statistics.]
[MOSKOVSKAIA medytzynskaia gazeta, Moscow, 1866, No. 39, p. 330; No. 41, p. 338; No. 44, p. 369.]

Nizhnee-Novgorod.

Lindgreen (J. G.) Der epidemische Brechdurchfall, beobachtet zu Nishni-Nowgorod. 8°. *Dorpat*, 1831.

Obookhov.

Zorn (H.) *und* **Werther** (L.) Bericht über die Cholera im Obuchow-Hospital im Jahre 1866.
[ST. PETERSB. med. Zeitschr., 1867, XIII, pp. 1–21.]

Odessa.

De Valcourt (T.) Le choléra à Odessa et le système des quarantaines.
[GAZ. méd. Paris, 1872, XXVII, pp. 381, 385.]

Orel.

Guttceit (H. L. von). Die Cholera in Orel im Jahre 1847. Ein Beitrag zur Kenntniss dieser Krankheit. 8°. *Leipzig*, 1848. L.

Orenboorg.

Rang. Ueber die Cholera, die im letzten Herbste und Winter in und um Orenburg herrschte. Die Cholera innerhalb Russland's Gränzen im Jahre 1829–30.
[JOUR. der prakt. Heilk., 1830, LXXI, pp. 86–102.]

Revel.

Lingen. Ueber die Ausbreitung der Cholera in Reval und deren directe Beziehung zu der dortigen Wasserleitung.
[ST. PETERSB. med. Zeitschr., 1872, III. n. s., pp. 180–181.]

Riga.

Baerens (B. F.) Geschichtliches aus der Cholera-Epidemie in Riga im Jahr 1848.
[BEITRÄGE zur Heilkunde, Riga, 1851, I, pp. 107–131.]

Müller. Die Cholera in Riga im Sommer 1858.
[BEITRÄGE zur Heilkunde, Riga, 1857, IV, pp. 87–93.]

Müller (C. J. G.) *See* **Cholera** (Die) in Riga [etc.]

Reyher (C. v.) *Zur Pathologie und Therapie der Cholera in der Rigaer Epidemie von 1871. 8°. *Dorpat*, 1872. L.

Beobachtungen und Erfahrungen der Rigaer Aerzte über die Natur und Behandlung der asiatischen Cholera; herausgegeben von der königl. Schleswig-Holstein-Lauenburg. Central-Commission wegen der Cholera. Mit einem Vorwort des Prof. Lüders in Kiel und über den gegenwärtigen Gesundheitszustand der Herzogthümer, zunächst in Beziehung auf die asiatische Cholera. 8°. *Kiel*, 1831.

Beobachtungen und Erfahrungen über die epidemische Cholera. In Protocoll-Extracten der Versammlungen sämmtlicher Aerzte Riga's zur Zeit der daselbst im Jahre 1831 herrschenden Cholera-Epidemie. 8°. *Riga*, 1831. L.

——— The same. 8°. *Hamburg*, 1831. L.

——— The same. Nebst einem Anhange über die Einrichtung der Hospitäler für Cholera-Kranke. Herausgegeben von L. Dyrsen und B. F. Baerens. 8°. *Riga und Dorpat*, 1831. L.

Cholera (Die) in Riga im Jahr 1848.
[Beiträge zur Heilkunde, Riga, 1851, I, pp. 1–106.]

Cholera (Die) in Riga im Jahre 1848. Collectivarbeit zusammengestellt von Dr. C. J. G. Müller. [Aus den Beiträgen zur Heilkunde.] 8° *Riga*, 1849. L.

Room-Elee.

Balaczeanu (G.) Die Cholera in Rumänien im Jahre 1866. Diss. 8°. *Berlin*, 1870. L.

Saint Petersburg.

Botkin (*Prof.*) Zur Symptomatologie und Therapie der in Petersburg im Frühjahr 1871 beobachteten Cholera.
[Berlin. klin. Wochenschr., 1871, VIII, pp. 389–391, 401–404.]

Crawford (A.) Observations on the Asiatic cholera during a residence in St. Petersburg in 1848. 8°. *London*, 1848. L.

Delpech. Sur le choléra. État statistique de l'épidémie cholérique à Saint-Pétersbourg du 14–26 juillet au 19–31 juillet.
[Bull. de l'Acad. de méd., Paris, 1871, XXXVI, pp. 614–615, 656–657; 1873, II, pp. 1127, 1130.]

Hugenberger (T.) Die diesjährige Choleraepidemie in der Expedition zur Anfertigung von Staatspapieren zu St. Petersburg.
[St. Petersb. med. Zeitschr., 1866, XI, pp. 259–281.]

Lefevre (G. W.) Observations on the nature and treatment of the cholera morbus, now prevailing epidemically at St. Petersburg. 8°. *London*, 1831. L.

Lichtenstädt *und* **Seidlitz.** Mittheilungen über die Cholera-Epidemie zu St. Petersburg im Sommer 1831. 8°. *St. Petersburg*, 1831. L.

Lingen. Bericht über die Cholera dieses Jahres im Marien-Magdalenen-Hospital.
[St. Petersb. med. Zeitschr., 1866, XI, pp. 34–45.]

Maydell. Ueber die diesjährige Cholera-Epidemie in St. Petersburg.
[St. Petersb. med. Zeitschr, 1870, II, n. s., pp. 212–213.]

Mayer (C.) Skizze einiger Erfahrungen und Bemerkungen über die Cholera-Epidemie zu St. Petersburg. Besonderer Abdruck aus den Mittheilungen ueber diese Epidemie, von practischen Aerzten. 8°. *St. Petersburg*, 1832. L.

Müller (E.) Bijdragen tot de Léer en de Behandeling der Cholera. 1e Bijdrage, inhoudende: Rapport over de Cholera te St. Petersburg in 1848. Aan het nederlandsche geneeskundige Publiek medegedeeld, en met Bijvoegselen vermeerderd, door I. van Deen. 8°. *Zwolle*, 1848. L.
[Reprint of the following.]

——— Rapport over de Cholera te St. Petersburg in 1848. Medegedeeld door de Redactie.
[Nieuw Arch. v. bin- en buitenlandsche Geneeskde. te Zwolle, 1848, pp. 255–304.]

Ockel. Observations on the cholera as it was experienced at St. Petersburg [in 1830. Translated from the French].
[London Med. Gaz., 1832, IX, pp. 792–795.]

Pelikan (E.) Note sur le choléra épidémique qui a sévi à Saint-Pétersbourg l'an 1848.
[Gaz. méd. de Paris, 1848, III, 3e s., pp. 1005–1008.]

Schroeder (H.) * Quaedam de cholera orientali, praesertim epidemiae anno 1852 Petropoli grassatae respectu habito. 8°. *Dorpat*, 1856. L.

Snitkin (M.) Nabliudienia nad choleroiu, sdielannyia v cholernom otdieleniy Prof Bessera vo vtorom voiennosucho putnym St. Peterburhskom hospitalie.
[Voienno-medytzynski jurnal, St. Petersburg, 1867, part XCVIII, book I, art. III, pp. 1–81.]

Wolff (H. S.) Erfahrungen und Bemerkungen über die Cholera in Petersburg, ihren Character und beste Behandlung. Nebst einer tabellarischen Uebersicht der in den Hospitälern behandelten Kranken.
[Jour. der prakt. Heilk., 1831, LXXIII, pp. 82–100.]

Auszug aus dem Schreiben eines Ulmers, die Cholera betreffend. Geschrieben aus Petersburg, vom 19. August 1831. 8°. *Ulm*, 1831. L.

Cholera-Epidemie (Die) in St. Petersburg 1848, beobachtet im Obuchowschen Hospital. 8°. *St. Petersburg*, 1849.

Cholera (Die) in Petersburg, von einem Nichtarzte. [*From the* "Preuss. Staatszeitung".]
[JOUR. der prakt. Heilk., 1831, LXXIII, pp. 103–122.]

Choléra-morbus (Le): copie d'une lettre du consul-général de France à St. Pétersbourg.
[GAZ. des hôp., Paris, 1830, IV, pp. 140–141.]

Tabelle über den Gang der Cholera in St. Petersburg. fol. *St. Petersburg*, 1832. L.

Saratov.

Huber. Rettung von der Cholera. Tagebuch aus Saratow vom 10. bis 31. Aug. 1830. 8°. *Dessau*, 1830.

Nachrichten über die Cholera morbus und ihre schrecklichen Verheerungen im Jahr 1830, mitgetheilt von zwey evangelischen Pastoren im russischen Gouvernement Saratow, nebst einem Anhang über die Entstehung und Verbreitung dieser Krankheit, so wie einige Heilmittel gegen dieselbe. sm. 8°. *Basel*, 1831. L.
[Another ed. Strassburg, 1831.]

Tagebuch eines Geistlichen während der Cholera-Pest zu Saratow an der Wolga vom 6. bis 31. Aug. 1830. Eine Beherzigungsschrift für Jedermann in jetziger Zeit. (Abgedruckt aus dem Januarheft der Neuesten Nachrichten von 1831.) 8°. *Erlangen*, 1831.

Staraia-Roossa.

Strumpf. Ueber die Cholera und deren Behandlung in Staraja-Russa vom Jahre 1853.
[MED. Zeitung, Berlin, 1854, pp. 199–200.]

Toola.

Bierfreund (C. A.) Den asiatiske Cholera i Staden Tula og Omegn.
[UGESKR. for Laeger, 1848, IX, pp. 225–250.]

Warsaw.

Antommarchi (F.) Mémoire et observations sur le choléra-morbus régnant à Varsovie. 8°. *Paris*, 1831. L.

Archypoo (A.) Cholera v Varshavie pviavilas.
[MEDITZYNSKIY Vlestnik, St. Petersburg, 1867, 7th year, No. 28, pp. 262–263.]

Binaghi (O. A.) Opinion upon the epidemic cholera morbus observed at Warsaw. Translated from the Italian by W. Sampson. 8°. *New York*, 1832. L.

Hille (K. C.) Beobachtungen üb[er] asiatische Cholera, gesammelt [auf] nach Warschau im Auftrage [der] Landesregierung unternommenen [Reise] 8°. *Leipzig*, 1831.

Köhler (L.) Die Cholera in W[arschau]
[LITTERAR. Ann. der gesammt. H[eilkunde], pp. 385–425.]

Lubelski (G.) Le choléra à Var[sovie] juillet, août et septembre 1[831].
[GAZ. hebdom. med. et chir., Paris, [1]8[3]1, 638, 640, 687, 688; *also*, reprint in [the] [Pa]ris

Oettingen (O. v.) Rückblick [auf] Choleraepidemie in Warschau [vom] fang des July bis zum Ende [Sept.] 1852.
[BEITRÄGE zur Heilkunde, Riga, 18[5]2, [II], 436.]

Pfeiffer (L.) Erfahrungen über [die] mische Cholera, gesammelt in den [Elb]tälern zu Warschau im Sommer [1831] 8°. *Kassel*, 1831.

Rein (J. G. M. von). Die orient[alische] Cholera. Ergebniss einer mit [Unterstützung] der hochfürstlichen Landesregierung zu Schwarzburg-Rudolstadt [im] Monat Juni bis December 1[831] Warschau gemachten Untersuch[ungen]. Mit einer Vorrede von D. G. K[ieser]. 8°. *Jenae*, 1832.

Remer (C. J. W. P.) Beobachtungen [über] die epidemische Cholera gesam[melt] Folge einer in amtlichem Auftrag[e] machten Reise nach Warschau [und] höheren Orts eingeholter Gene[ral]-herausgegeben. 8°. *Breslau*, 1[83]1.

Steinheimer (J. B.) Wenige [Worte] über Cholera morbus während [des] Aufenthaltes in Warschau. [8°.] *berg*, 1832.

Trachez (F. J.) Rapport sur l[e] morbus épidémique, observé à V[arsovie] pendant les mois de juillet et [août]
[REC. de mém. de méd. mil., Par[is], 1[8]3[1], pp. 68–176.]

Cholera at Warsaw.
[LONDON Med. Gaz., 1831, VIII, pp. [5]9[3]–

Cholera w gubernii Warszawsk[iej].
[PRZEGLAD Lekarski, Krakow, 1[8]7[3].]

SPAIN.

Samano (M. G. de). Memoria [so]bre el colera-morbo asiatico en [Es]pa[ña]. 2 v. 8°. *Madrid*, 1[8]5[3].

Ullersperger. Geschichte der C[holera] in Spanien.
[ARETZL. Intell.-Blatt., München, 1[8]6[2], 665–672; 1862, IX, pp. 132–13[5]

holéra (Le) en Espagne.
[L'Union méd., 1860, VIII, 2e s., pp. 79–80.]

holera (The) in Spain.
[London Med. & Surg. Jour., 1834, IV, p. 318.]

rcelona.

lbell. Quelques mots sur le choléra de Barcelone.
[Gaz. hebd. de méd. et de chirurg., 1865, 2e s., II, pp. 732–733.]

lbao.

tutel (J. L.) Le choléra-morbus de Bilbao.
[Gaz. des hôp., 1834, VIII, pp. 513–514, 517.]

ibraltar.

ross (J. E.) Rough notes on the cholera epidemic at the government prison, Gibraltar.
[Med. Times & Gaz., 1865, II, pp. 520–521.]

ettenkofer (M. v.) Die Choleraepidemie des Jahres 1865 in Gibraltar.
Ztschr. f. Biologie, München, 1870, VI, pp. 95–127, 2 maps.]

utherford (W.) General report upon the cholera epidemic in Gibraltar during the summer and autumn of 1865.
[Army Stat., San., & Med. Repts., London, 1862, VI, pp. 350–359, 1 ch.]

utherland. Report on the sanitary condition of Gibraltar with reference to the epidemic cholera in the year 1865. (Presented to both houses of parliament by command of her majesty, August, 1867.) fol. *London*, 1867. L.

holera (The) at Gibraltar.
[Lancet, 1860, II, n. s., pp. 314–315.]

oda.

ambruschini (R.) Il cholera a Roda. Racconto istrutivo. 8°. *Firenze*, 1835. L.

rille.

loreno y Fernandez (J.) Del colera: sus caractéres, origen y desenvolvimiento, causas naturaleza y curacion; historia de esta enfermedad durante la invasion que ha sufrido Sevilla en 1854, con algunas consideraciones generales sobre el mismo padecimiento, tomadas de su estudio en los diferentes pueblos que ha recorrido. 8°. *Sevilla*, 1855. L.

SWEDEN.

Berg (F. T.) Sammandrag af officiella Rapporter om Cholerafarsoten I Sverge År 1850 efter Uppdrag af kongl. majts. Sundhets-Collegium Utarbe tadt af dess Ledamot. 8°. *Stockholm*, 1851. L.

Wistrand. Sundhets-Collegii bera etteise om Kolerasoten I Sverige Aor 1853. 4°. *Stockholm*, 1855.

Angaaende Honorar for private Laeger som Medlemmer af Sundheds-Commissioner mod Cholera.
[Norsk. Mag. for Laegevid., 1859, XIII, pp. 380–381.]

Cholera.
[Norsk. Mag. for Laegevid., 1848, II, pp. 121, 188, 635, 704; 1855, IX, pp. 214, 278; 1856, X, pp. 124, 132; 1858, XII, pp. 60–63.]

Cholera (The) epidemic of 1866 in Sweden. Translated by J. W. Moore.
[Med. Times & Gaz., 1870, I, pp. 519–520.]

Cholera, dens Optraeden i Lund i 1854 og 55.
[Ugeskr. for Laeger, 1855, XXII, pp. 39, 72.]

Cholera i Göteborg 1866.
[Forhandl. vid Svenska Läk.-Sälsk., Stockholm 1867, pp. 56–57.]

Choleratilfaelde i Klaerkegaden.
[Ugeskr. for Laeger, 1855, XXIII, pp. 247–252.]

Constitutio epidemica. Adress till Allmänheten om Choleran.
[Förhandl. vid Svenska Läk.-Sälsk., Stockholm, 1852, pp. 4–38.]

SWITZERLAND.

Hegetschweiler (J.) Ueber den Charakter, die Cur und die Verhütung der ostindischen Brechruhr (Cholera), mit besonderer Berücksichtigung der Verhältnisse der Schweiz. 8°. *Zürich*, 1831.

Jacquemond. Le choléra, preservation—traitement—causes, choléra des Alpes. 8°. *Moutiers*, 1867. L.

Ogden (H.) Papers and correspondence on cholera. Epidemic at Switzerland.
[London Med. Gaz., 1832, IX, pp. 586–590.]

Cholera in Switzerland.
[Dublin Med. Press & Circular, 1867, IV, p 368.]

Cholera (The) in Switzerland.
[Med. Times & Gaz., 1867, II, pp. 326–327.]

Aarau.

Blösch. Einige Mittheilungen über die Choleraepidemie in Aarau im Herbste 1854.
[Schweizerische Zeitschr. f. Med., Chir. und Geburtsh., 1855, pp. 1–16.]

Zschokke. Mittheilungen über die Cholera in Aarau 1854.
[Schweizerische Zeitschr. f. Med., Chir. und Geburtsh., 1854, pp. 359–431.]

Aargau.

Nieriker (P.) Die Cholerafälle im Bezirk Baden (Kanton Aargau) im Jahre 1867. 8°. *Aarau*, 1867. L.

Basel.

Welte (de.) Bericht über den Verlauf der Cholera in Basel 1855. *Basel*, 1856.

Bern.

Levier (E.) Notizen über eine Cholerine-epidemie in Bern, mit leucinhaltigen Darmentleerungen.
[SCHWEIZERISCHE Zeitschr. f. Heilkunde, 1864, III, pp. 140–153.]

Geneva.

D'Espine (M.) Notice statistique sur la première invasion du choléra dans le canton de Genève.
[SCHWEIZERISCHE Zeitschr. f. Med., Chir. und Geburtsh., 1855, pp. 351–360.]

Rilliet (F.) Le choléra à Genève pendant les mois de septembre et d'octobre 1855.
[L'UNION méd., 1856, X, pp. 145–146, 151–152, 157–158; *also*, reprint in 8°, Paris, 1856.]

Mendrisio.

Intorno al coléra morbus asiatico. Rapporto finale della commissione di sanità nel distretto di Mendrisio.
[GAZ. med. it. Lomb., 1855, VI, 3a s., pp. 453–455.]

Ticino.

Minnich *und* **Volmar.** Die indische Cholera im Canton Tessin im J. 1836; nebst Angabe der Schuzmassregeln Graubündtens gegen diese Krankheit in damaliger Zeit. (Aus den Generalberichten der eidgenössischen Sanitäts-Commissarien . . . an den hohen Vorort zu Bern.)
[SCHWEIZ. Zeitsch. für Nat.- u. Heilk., Zürich, 1839, IV, pp. 19–51, 223–251.]

Zürich.

Fischer. Die Cholera in Zürich.
[MITTHEILGN. d. bad. ärztl. Vereins, 1867, XXI, pp. 183–186.]

Lebert (H.) Vorträge über die Cholera gehalten in Zürich am Ende des Sommer-Semesters 1854. 8°. *Erlangen*, 1854. L.

——— Die Cholera in der Schweiz und das über dieselbe im Züricher Kantons-Spital beobachtete. Ein Bericht an die Medicinal-Direktion. 8°. *Frankfurt am Main*, 1856. L.

Pettenkofer (M. v.) Typhus und Cholera und Grundwasser in Zürich.
[ZTSCHR. f. Biologie, München, 1871, VII, pp. 86–103.]

Schrämli. Auszug aus dem bezüglichen Berichte über die Choleraepidemie des Bezirkes Zürich im Jahre 1855.
[SCHWEIZ. Zeitschrift für Med., Chir. u. Geburtsh., 1856, p. 457.]

Vontobel (H.) Ueber Cholera nach Beobachtungen aus der letztjährigen Züricher Epidemie. 8°. *Zürich*, 1866.

Zehnder (C.) Die Cholera, die Art ihrer Verbreitung und Massregeln gegen dieselben. Mit Berücksichtigung der schweizerischen Verhältnisse, insbesondere des Kantons Zürich. 8°. *Zürich*, 1866.

——— Bericht über die Choleraepidemie des Jahres 1867 im Kanton Zürich. *Zürich*, 1871.

——— Bericht über die Cholera-Epidemie des Jahres 1867 im Kanton Zürich.
[WIEN. med. Presse, 1873, XIV, pp. 105–]

Choleraepidemie in Zürich.
[WIEN. med. Wochenschr., 1867, pp. 173–]

Rapport au conseil d'état de la république et canton de Neuchâtel sur les mesures sanitaires prises à Zurich pendant l'épidémie du choléra par A. Guillaume. 8°. [*n. p., n. d.*]

TURKEY.

Bushell (T.) Cholera in Turkey.
[LONDON Med. Gaz., 1832, IX, p. 49.]

Ferro. Histoire médicale de l'épidémie de choléra de Cadi-Keui, du 23 août au 31 décembre 1865.
[GAZ. méd. d'orient, 1865–66, IX, pp. 168–175, 187–192.]

Hodsejeffsky. Die Cholera-Epidemie im activen Corps in der asiatischen Türkei, vom 3. Sept. 1855 bis Ende desselben Jahres.
[MED. Zeitung Russlands, 1857, pp. 129–131.]

Aleppo.

Barozzi. Le choléra à Alep.
[GAZ. méd. d'orient, 1865–66, IX, pp. 1–]

Brusa.

Mordtmann. Quelques notes sur l'épidémie cholérique du Vilay et de Kirvendigniar (Brousse) pendant 1871.
[GAZ. méd. d'orient, 1872, XV, pp. 56–]

Constantinople.

Bechset. Die Cholera-Epidemie in Constantinopel und Verhaltungs-

chzet—continued.
labei. Aus dem Türkischen übersetzt
nd mit Anmerkungen begleitet vom
ürsten Demetrius Maurocordato.
Jour. der prakt. Heilk., 1832, LXXIV, pp. 33–47.]

unetti. Le choléra de Constantinople. Études étiologiques. *Constantinople,* 66.

levras. Quelques observations puisées ans l'hôpital militaire des cholériques Haïdar-Kiosk.
Gaz. méd. d'orient, 1865–66, IX, pp. 115–117.]

on. Lettres à un ami sur le choléra de onstantinople de 1865.
Gaz. méd. d'orient, 1866–67, X, pp. 1–6, 17–21, 33–37.]

val (A.) Lettre sur le choléra qui ègne actuellement à Constantinople.
Gaz. méd. de Paris, 1847, II, pp. 1009–1010.]

Carthy (W.) On the cholera at Constantinople.
London Med. Gaz., 1832, IX, pp. 681–682.]

ngeri. Étude sur l'épidémie de choléra ui a régné à Constantinople.
Gaz. méd. d'orient, 1865–66, IX, pp. 132–137, 149–151, 181–168; 1866–67, X, pp. 6–9, 21–24, 38–42, 55–57, 71–74.]

— Études sur l'épidémie de choléra qui régné à Constantinople en 1865, suivies 'un appendice sur la nature contagieuse du choléra et des devoirs des médecins sanitaires. 8°. *Constantinople,* 66. L.

nneret. Relation du choléra-morbus bservé à Constantinople en 1847 et 48.
Bull. de l'Acad. nat. de méd., 1847–48, XIII, pp. 528–543 (2e partie).]

— The same. 8°. *Paris,* 1848. L.

— History of the cholera observed at onstantinople during the winter of 847–48.
Lond. Times, London, 1848, XVII, pp. 458–459, 480–481.]

hlig. Die Cholera-Epidemie Constantinopels.
Deutsche Klinik, 1865, XVII, pp. 461–464, 471–473, 480–482 (1 Tafel).]

— Cinquième épidémie de choléra-orbus à Constantinople.
Gaz. méd. d'orient, 1872, XV, pp. 81–85.]

ollot. Du choléra-morbus en 1845 46 et 1847, avec deux cartes indiquant marche pendant ces trois années, suivi e l'histoire du choléra-morbus à Constantinople en 1848. 8°. *Constantinole,* 1849.

Nouridjan. Cinquième épidémie de choléra-morbus à Constantinople.
[Gaz. méd. d'orient, 1872, XV, pp. 49–56.]

Parsnicki. Quelques notices sur le choléra épidémique à Constantinople en 1871.
[Gaz. méd. d'orient, 1872, XV, pp. 85–90; 1873, XVI, pp. 4–8, 70–74.]

Rigler. Die Cholera-Epidemie des Jahres 1847–48 in Constantinopel.
[Zeitschr. d. k. k. Ges. der Ärzte zu Wien, 1849, pp. 305–328, 357–371, 436–443.]

Saurel. Du choléra à Constantinople en 1847.
[Jour. Soc. de méd. prat. de Montpellier, 1847, XVI, pp. 158–159.]

Stampa (C.) Rapports circa il cholera che regnò nel terzo circondario di Constantinopoli l'anno 1865, durante tutto il tempo di sua ispezione.
[L'Imparziale, Firenze, 1866, VI, pp. 43–49.]

Tian. Die Cholera zu Konstantinopel im Jahre 1865.
[Aerztl. Intell.-Blatt, 1865, XII, pp. 590–592.]

Verollot. Ueber Cholera. Aus dem Berichte des Dr. Verollot, franz. Gesandtschafts- und Spitalsarzte zu Konstantinopel.
[Wiener med. Wochenschr., 1851, I, pp. 398–400.]

Zennaro (S.) Étude sur le choléra à l'occasion de l'épidémie de Constantinople en 1865.
[Gaz. méd. d'orient, 1868–69, XII, pp. 6–9, 23–28, 39–43, 53–57, 68–71, 85–89, 102–107, 139–142, 152–156; 1869–70, XIII, pp. 6–12, 25–29, 40–41, 54–63, 70–76, 100–104, 122–124, 133–143, 165–170; *also,* reprint in 8°, Constantinople, 1870.]

——— Lecture sur le choléra à Constantinople.
[Gaz. méd. d'orient, Constantinople, 1872, XV, pp. 104–106; 1873, XVI, pp. 53–57.]

Cholera (The) at Constantinople.
[London Med. Gaz., 1848, XLI, pp. 18–22.]

Choléra (Le) à Constantinople en 1865, 1866.
[Gaz. méd. d'orient, 1865–66, IX, pp. 65–71, 81–84, 97–102, 113–115, 177–181; 1866–67, X, pp. 129–131.]

Despatch from her majesty's ambassador at Constantinople, together with documents therein alluded to, regarding the conclusions arrived at by the cholera conference at Constantinople. (Presented to both houses of parliament by command of her majesty, 1868.) fol. *London* [*n. d.*] L.

Fünfte Cholera-Epidemie in Konstantinopel.
[Wien. med. Wochenschr., 1872, XXII, pp. 161–163.]

Devna.

Cholera amongst the troops at Devna.
[LANCET, London, 1854, II, n. s., pp. 160–161.]

Dobrudscha.

Cazalas. Relation de l'épidémie cholérique dont la première division de l'armée d'orient a été frappée dans la Dobrutscha, en juillet et août 1854.
[GAZ. méd. de Paris, 1855, X, 3e s., pp. 527–531, 541–546, 577–587; *also, in* REC. de mém. de méd. mil., Paris, 1855, XV, 2e s., pp. 130–162.]

Salonica.

Borsani (P.) Sull'invasione del cholera morbus asiatico in Salonicchio nel Maggio del 1855.
[GIORN. venet. d. sc. med., 1856, VII, 2a s., pp. 169–207.]

Smyrna.

Burguières (E.) Étude sur le choléra-morbus observé à Smyrne, sa marche, ses causes et son traitement. 8°. *Paris*, 1849. L.

Chasseaud (W.) Invasion et mode de propagation du choléra étudiés à Smyrne.
[GAZ. méd. d'orient, 1870–71, XIV, pp. 4–6, 21–25, 40–41, 55–70, 87–90, 103–127, 137–141, 150–153; *also*, reprint in 8°, Constantinople, 1871.]

Cricca (A.) À propos du choléra: Smyrne, juillet 1865. 8°. *Smyrne*, 1865. L.

——— The same. 2e éd. *Smyrne*, 1865. L.

——— Après le choléra, Smyrne, septembre 1865. 8°. *Smyrne*, 1865(?). L.

——— The same. 2e éd. *Smyrne*, 1865. L.

Cricca (A.)—continued.

——— L'homœopathie en présence du choléra à Smyrne en 1865. Nouvelle. 8°. *Paris*, 1866.

Dethier (A.) Account of the cholera as it appeared at Smyrna.
[LONDON Med. Gaz., 1832, IX, pp. 75–

Varna.

Mackay (G.) Notes on the cholera as it appeared at Varna in 1854.
[EDINB. Med. Jour., 1857, III, pp. 3–8, 240–252.]

——— On the cholera at Varna, and more especially in her Majesty's ship "Agamemnon" in the Black Sea. Between the 1st August, 1854, and 8th September, 1855. 8°. *L.* 1857.

Tellier. Quelques mots sur la récurrence cholérique observée à Varna (Bulgarie).
[REC. de mém. de méd. mil., Paris, 2e s., pp. 189–206.]

Yassy.

Bassereau (A. H.) Mémoire sur l'épidémie de choléra qui a régné à Jassy (Moldavie), pendant les mois de juin et juillet 1848.
[GAZ. méd. de Paris, 1848, III, 3e s., pp. 828–832.]

Landesberg. Die Cholera zu Jassy im Jassyer Kreise in den Monaten August, September und October 1
[ZEITSCHR. f. klin. Med., 1853, VI,

II.—GENERAL TREATISES ON CHOLERA.

Abercrombie (J.) Suggestions submitted to the medical practitioners of Edinburgh on the character and treatment of the malignant cholera. 2d ed. 12°. *Edinburgh*, 1832. L.
[1st ed. same year.]

Adam (J.) On cholera morbus.
[LONDON Med. & Phys. Jour., 1822, XLVIII, pp. 199–211.]

Adde-Margras (J.) De cholera epidemica. 8°. *Jenae*, 1864. C.

[**Agar de Bus** (d').] Causes, action et préservatif du choléra. 8°. *Issoudun* [*n. d.*]

Ainslie (W.) Observations on the cholera-morbus of India. 8°. *London*, 1825. L.

Aladane de Lalibarde. Études sur le choléra épidémique; sa nature et son traitement. 8°. *Paris*, 1851.
[2d ed. same year.]

Albers. Ueber die Cholera.
[MAG. f. d. gesammt. Heilk., 1831, XXXIV, pp. 382–400.]

Alcock (N.) Treatise on cholera. *London*, 1849.

Aldis (C.) On cholera. [etc.] *London*, 1832.

Aldis (C. J. B.) An introductory hospital practice, . . . ; being a report of fever, . . . cholera. *London*, 1835.

Alison (S. S.) Cholera: its management and sanitary requirements. *London*, 1853.

Allen (J.) Cholera and diarrhœa.
[LANCET, 1857, II, n. s., pp. 97–98.]

Allen (J. A.) Remarks on the typical character of the prevailing epidemic cholera and on the therapeutic application to it of remedial agents.
[BOSTON Med. & Surg. Jour., 1833, VI, 213–217.]

Alleyne (J. S. B.) Cholera.
[ST. LOUIS Med. Repr., 1866–67, I,

ison (W.) Diagnosis of English and ndian cholera.
[ROYL. Med. & Surg. Jour., 1843, v, pp. 168–169.]
oncourt (F. d'). Influenza und Cho-ra. 8°. *Lipsiae*, 1831.
mon (F. A. v.) Die Erkenntniss und ie Behandlung der nach Deutschland erschleppten asiatischen Cholera. Mit ücksichtigung der durch Leichenöff-ungen gewonnenen Aufklärungen über ie Natur dieser Krankheit und mit ner Sammlung der bei Behandlung erselben erprobten Heilmittel und Heil-ormeln versehen. 8°. *Dresden*, 1831. L.
— The same. 4te Aufl. 8°. *Dresden*, 31. L.
shoff (G. H.) Eene Bijdrage ter Gene-ing en Afwering van den oost-indischen ranksloop (Cholera indica) voor al en iet Geneeskundigen. 8°. *Koerorden*, 49. L.
derson (T.) Handbook for yellow ver . . . to which is adjoined a brief istory of pestilential cholera and a ethod of cure. 12°. *London*, 1866. L.
derson (W. M.) On the cholera.
[LONDON Med. & Surg. Jour., 1833, II, pp. 45–47.]
dral. Leçon sur le choléra-morbus.
[GAZ. des hôp., 1831, IV, pp. 213–214.]
drea (R. D.) Sul cholera. Ulteriori sservazione in appendice al volume rimo degli studi medici del dottore . . . prima lettura) al veneto Atteneo nel di ennaro 1856. 8°. *Venezia*, 1856. L.
dreae (A.) Die Erkenntniss und Be-andlung der asiatischen Cholera. 8°. *agdeburg*, 1831.
jon (T. P.) *Dissertation sur le choléra-orbus épidémique. 4°. *Paris*, 1832. L.
nesley (J.) A treatise on epidemic olera. 8°. *London*, 1831.
— Ueber die ostindische Cholera, nach ielen eigenen Beobachtungen und eichenöffnungen. Nach der zweiten usgabe von 1829 aus dem Englischen ersetzt von G. Himly. Nebst einem nhange, enthaltend: Instruction der aiserl.-königl. österreichischen Regie-ung für die Sanitäts-Behörden, zum Be-ufe die Gränzen vor dem Einbruche der holera zu sichern, und ihre Verbreitung u hemmen. 8°. *Hannover*, 1831. L.
tholne de Beaucaire. Considéra-ons générales sur le choléra et son raitement.
[Rev. méd., Paris, 1866, II, pp. 458–469, 527–527, et 7, I, pp. 203–212, etc.]

Anton (K. C.) Die bewährtesten Heil-formeln für die epidemische Cholera. Nebst einer ausführlichen pathologisch-therapeutischen Einleitung. 8°. *Leipzig*, 1849. L.
Appel (J.) Über das nächste Causalver-hältniss und die rationelle Behandlungs-weise der orientalischen Brechruhr. 8°. *Würzburg*, 1831. L.
Armstrong (G. A.) Asiatic cholera; its pathology and treatment.
[LANCET, 1848, I, p. 604.]
Arnaud. Note sur le choléra-morbus.
[Rev. méd. franç. et étrang., 1832, I, pp. 395–398.]
Arnaud (J.) Mémoire à consulter sur le choléra-morbus . . . [etc.] 8°. *Paris*, 1831.
Arrambide (J. B.) Explication des symptômes du choléra-morbus, des apparences cadavériques et de ses méthodes curatives, par des données physiologiques. Traduit de l'espagnol. 8°. *Paris*, 1832.
Arztheim (V. E. v.) Beyträge zur Erkenntniss des Wesens und der Heil-methode der gegenwärtig epidemisch herrschenden Brechruhr, und die Schutz-mittel dagegen, [etc.] 8°. *Troppau*, 1831.
Ashton (T.) *De cholera. 8°. *Lugd. Batav.*, 1833. L.
Assing (D. A.) Skizze betreffend: die etwannige Aehnlichkeit der von älteren Aerzten beschriebenen Cholera mit der Cholera orientalis.
[JOUR. d. prak. Heilk., 1831, LXXIII, pp. 79–102.]
Astier (C. B.) Lettre de . . . à la Société royale de médecine de Toulouse, sur le choléra-morbus, [etc.] 8°. *Toulouse*, 1832.
Aubril (J. A.) *Du choléra épidémique. 4°. *Paris*, 1850. L.
Audial (F. A.) Bibliothèque L. Curmer. Enseignement universel. Du choléra-morbus et de son traitement. 32°. *Paris*, 1848.
Austin (J.) Cholera-morbus. A short and faithful account of the history, progress, causes, symptoms, and treatment of the Indian and Russian cholera, taken from various authentic sources [etc.] 8°. *London*, 1831.
Avanzini (C.) Aforismi teorico-pratico intorno al colera asiatico. *Torino*, 1866.
Axmann (C.) Die indische Cholera und das Ganglien-Nervensystem, nebst Bemerkungen über die Verhütung der Cholera. 8°. *Erfurt*, 1867. L.

Ayre (J.) On the pathology and treatment of the malignant cholera.
[LANCET, 1831–32, II, pp. 43–46, 105–106.]

——— Cholera: its nature, symptoms, and treatment. To which is added the sanatory regulations of the boards of health of London, Edinburgh, and Dublin. 8°. *London*, 1849. L.

——— Letter on cholera.
[LANCET, 1854, I, n. s., pp. 536–538, 563–566, 591–593.]

Ayres (P. B.) Asiatic cholera.
[LONDON Med. Gaz., 1842–43, I, n. s., pp. 18–19.]

Azémar. Mes études sur le choléra, ou découverte de tout ce qu'il importe à la science et à l'humanité de connaître sur cette maladie. 8°. *Paris*, 1856. L.

Babington (B. G.) Address at the first meeting of the fifth session of the Epidemiological Society for 1854.
[MED. Times & Gaz., 1854, IX, pp. 511–513.]

Backhausen. Cholera und Influenza.
[MED. Conversbl., 1831, pp. 265–266.]

Baird (D.) Substance of a lecture on cholera, delivered before a meeting of the medical profession at Liverpool, January 1832. 8°. [*n. d.*]

Balardini e Rusca (E.) Rapporto all'I. R. governo della Lombardia intorno il cholera-morbus.
[OMODEI, Ann. un. di med., 1831, LX, pp. 460–485; 1832, LXI, pp. 107–145.]

Ball (B.) Du choléra.
[GAZ. des hôp., 1873, pp. 954, 993.]

Ballot (A. M.) Een goede Raad aan mijne Stadgenooten, bij het Heerschen der Cholera. 8°. *Rotterdam*, 1853. L.

Bally (V.) Études sur la choladrée lymphatique, ou choléra indien, et sur la fièvre jaune. 8°. *Paris*, 1833. L.

——— Note sur l'hydro-choladrée ou choladrée lymphatique (choléra asiatique).
[JOUR. des connaiss., Paris, 1848, XV, pp. 137–140.]

——— Recherches sur les maladies épidémiques et endémiques des bords de la Méditerranée, et notamment sur la choladrée lymphatique.
[MÉM. Acad. roy. de méd., Paris, 1849, XIV, pp. 189–250.]

——— The same. 4°. *Paris*, 1849. L.

Balme (C.) Nouveaux éclaircissemens sur le choléra-morbus. 8°. *Lyon*, 1832. L.

——— Observatiops et annotations pratiques sur le choléra-morbus; ouvrage dans lequel on prouve que le choléra vulgaire n'est point une maladie [etc.] 8°. *Paris*, 1849.

Balme (C.)—continued.

Baltz (T. F.) Meinungen über die Entstehung, das Wesen und die Heilung einer Verhütung der sogenannten Cholera, aus der Natur und Erfahrung genommen und vielleicht zur Beruhigung und zum Nutzen für die Bewohner solcher Gegenden, wo diese [illegible] noch nicht ausgebrochen ist. [illegible] *lin*, 1832.

Bang (O.) Et par Ord om det [illegible] Cholera.
[UGESKR. for Laeger, 1848, IX, pp. [illegible]

Bangold (J. K.) Ueber die Cholera. *Stuttgart und Tübingen*, 1849.

Bankier (J.) Essay on the origin, progress, and treatment of cholera. 8°. *Madras*, 1835.

Barbosa y Vianna. Ensaio sobre a cholera epidemica. *Lisboa*, 1854.

Barchewitz (E.) Anleitungen für Wärter der Cholera-Kranken. [illegible] *zig*, 1832.

——— Über die Cholera, nach [illegible] Beobachtung in Russland und [illegible] 8°. *Danzig*, 1832.

Bard (A.) Idées générales sur le morbus, son traitement préservatif et curatif. 8°. *Paris*, 1832.

Bardet (A., *père*). Notice sur le morbus. 8°. *Bernay*, 1832.

Barham (T. F.) On cholera.
[LONDON Med. Gaz., 1832, IX, pp. [illegible]

Barnes. Cholera and choleroid [illegible]
[LANCET, 1859, II, pp. 137–138.]

Barrant (R. A.) Essai sur la [illegible] traitement du choléra. [illegible] 1863.

Barrie (C.) Die Cholera-Miasma, ihre Entstehung, Ausbildung, [illegible] und Ansteckungs-Fähigkeit. [illegible] *Hamburg*, 1831.

——— Winke über die Natur der Morbus. 8°. *Hamburg*, 1831.

——— Ein Wort zu einer Zeit, oder [illegible] tische Beiträge zu den von mir gegebenen Schriften über die [illegible] Morbus [etc.] 8°. *Hamburg*, 1[illegible]

——— Zusätze über die von mir herausgegebene Schrift: "Winke über [illegible] der Cholera-Morbus", nebst einem Anhange über die Erzeugung der Miasma [Miasma], aus dem Englischen. *Hamburg*, 1831.

rry (J. C.) On a case of malignant holera.

[LANCET, 1855, II, pp. 143-144.]

rtels (E. D. A.) Grundzüge einer speiellen Pathologie und Therapie der rientalischen Cholera; als Leitfaden für raktische Aerzte. 8°. *Berlin, Posen nd Bromberg*, 1832. L.

rth. Leçons sur la choléra, faites à 'Hôtel-Dieu de Paris.

[AZ. hebd. de méd. et de chir., Paris, 1865, 2e s., II, pp. 821-827; III, pp. 3-5, 33-38.]

— The same. 8°. *Paris*, 1866. L.

rth (C.) Practische Reflexionen über as Wesen, die Ursachen, die Prevenivmassregeln resp. über die Desinfecionsmittel, und über die Behandlung ler Cholera asiatica. 12°. *Aachen*, 71. L.

rthet (E. F.) *Du choléra-morbus. 4°. *'aris*, 1849. L.

ruffi. Considerazioni sul cholera asiaico. *Ente*, 1858.

rwell (R.) Asiatic cholera, its symptoms, pathology, and treatment, with which is embodied its morbid anatomy, general and minute; translated from a paper by Reinhardt and Leubuscher. '. *London*, 1853. L.

sie (A.) Instructions sur le mode de prevenir, de traiter et de l'éloigner auant que possible, la fatale maladie choléique. Rapport de M. Raikem. [Discussion.]

[BULL. Acad. roy. de méd. de Belgique, 1849-50, IX, pp. 334-342.]

tchelder (J. P.) Cholera; its causes, ymptoms, and treatment, considered nd explained. 8°. *New York*, 1849. L.

— Suggestions relative to the pathology and treatment of cholera.

[N. Y. Jour. of Med., 1854, XIII, pp. 344-359.]

udrimont (A.) Recherches expérimentales et observations sur le choléra pidémique. [Discussion.]

[CONGRÈS méd. de France, 3e session, à Bordeaux, 1865, Paris, 1866, pp. 484-526, 541.]

yrle (J.) *Die asiatische Cholera. '. *Tübingen*, 1836. C.

al (J. B.) *Du choléra-morbus épilémique. 4°. *Paris*, 1832. L.

auregard (F. V.) Recherches sur la nature et le traitement du choléra épilémique. 8°. *Havre*, 1854. L.

Beckedorff (L. von). Die Cholera, ihre Ursachen, ihre Verbreitung, ihre Abwehr und ihre Heilung. 8°. *Berlin*, 1848. L.

Becker. Ueber das Wesen und die Behandlung der Cholera. 8°. *Muhltruff*, 1832.

— Ueber die Verhütung und Heilung der Cholera, [etc.] 8°. *Berlin* [*n. d.*]

Begbie (J. N.) Facts and opinions in regard to Asiatic cholera.

[EDINB. Med. & Surg. Jour., 1854, LXXXI, pp. 502-523; 1855, LXXXII, pp. 86-107, 250-265.]

Bégin (L. J.) Analyse des rapports adressés au conseil de santé des armées sur le choléra-morbus épidémique.

[REC. de mém. de méd., de chirurg. et de pharm. mil., Paris, 1832, XXXIII, pp. 1-199.]

Behrend (F. J.) Amtlicher Bericht über die epidemische Cholera. Deutsch bearbeitet mit Anmerkungen von Dr. M. H. Romberg. 8°. *Berlin*, 1832. L.

Bek. Einige Worte über die Cholera-Morbus.

[SCHWEIZ. Zeitsch. f. Nat.- u. Heilk., Zürich, 1841, VI, pp. 452-454.]

Bell (C.) On the advance of the Asiatic cholera; with suggestions for its treatment.

[LONDON Med. Gaz., 1847, XL, pp. 797-802; 1848, XLI, pp. 8-13, 52-57.]

— Observations and suggestions in regard to cholera asphyxia.

[LONDON Med. Gaz., 1848, XLII, pp. 752-754.]

— Two lectures on cholera and intermittent fever. 16°. *London*, 1849.

— On cholera; its diagnosis and treatment.

[BRIT. Med. Jour., 1857, I, pp. 85-87, 105-107.]

Bell (G. H.) Treatise on cholera asphyxia, or epidemic cholera, as it appeared in Asia, and more recently in Europe. 8°. *Edinburgh*, 1831. L.

— The same. 2d ed. With practical remarks on the disease in Europe; an appendix of cases; and the reports and regulations of the boards of health of London and Edinburgh. 1832. L.

— The same. 3d ed. 8°. 1848.

Belliol. Choléra-morbus. Rapport . . . sur les moyens de traiter et de prévenir cette maladie, suivi d'un plan-modèle pour la prompte organisation d'un bureau de secours. 8°. *Paris*, 1832.

Belloe (H.) Le choléra, les médecins et le public.

[L'ABEILLE méd., Paris, 1865, XXII, pp. 345-346.]

Belloli (R.) Del colera epidemico. 8°. *Cologna*, 1834.

Bencke (J.) * De cholera asiatica. 8°. *Berolini* [1866]. L.

Benech (L. V.) Du choléra-morbus, de ses causes, de sa nature, de ses moyens préservatifs et de son traitement. 8°. *Paris* [*n. d.*] L.

Benson (C.) [Lecture on cholera-morbus.]

[Dublin Med. Press, 1841, VI, pp. 146–148, 177–181, 209–213, 241–246.]

Berg (F. H. A.) * Nonnulla ad choleræ orientalis nosologiam. 8°. *Berolini* [1832]. L.

Bergson. Die Cholera.

[Med. Reform, Berlin, 1848, pp. 80–82.]

Bergues (L.) Observations et réflexions sur le choléra.

[Jour. univ. et hebd. de méd. et de chir. prat., 1832, VIII, pp. 476–475.]

Berres. Erfahrungen über die Cholera. *Lemberg*, 1831.

Berres (J.) Erfahrungen, gesammelt bey den Sectionen der in den verschiedenen Stadien der Cholera Verstorbenen.

[Med. Jahrb. des oesterr. Staates, 1833, IV, n. F., pp. 111–143.]

Berristi e Trompeo. Rapporto della regia commissione medica Piemontese sul cholera-morbus. 8°. *Torino*, 1832.

Berthold (A. A.) Etwas über das Wesen und die Behandlung der Cholera morbus.

[Med. Conversbl., 1831, pp. 193–197, 315–316.]

[Bertulas (E.)] Réponse d'un ilote de la province à M. André Sanson, l'un des rédacteurs de "La Presse", à propos du choléra. 18°. *Marseille*, 1865.

Bésnier (E.) Épidémie cholérique de 1866. Prophylaxie et thérapeutique.

[Bull. gén. de thérap. méd. et chir., Paris, 1866, LXXI, pp. 385–392, 433–443.]

——— Contributions à l'étude des épidémies cholériques. 1866–73.

[Bull. et mém. Soc. méd. d. hôp. de Paris, 1873, X, 2e s., pp. 235, 246, 270, 289, 310, 339, 349, 381, 398, 422.]

——— The same. 8°. *Paris*, 1874. L.

Besnier (J.) Recherches sur la nosographie et le traitement du choléra épidémique considéré dans ses formes et ses accidents secondaires [épidémie de 1835 et 1836]. 8°. *Paris*, 1867. L.

Besuchet (J. C.) Le choléra, sa marche, ses progrès, son traitement appuyé sur des faits nombreux observés en France et en Belgique, pendant l'épidémie de 1832. 8°. *Paris*, 1837.

Beyer (V.) * De cholera epidemica. *Berolini*, 1850.

Biermann. Ein Wort zur Ausgleichung der verschiedenen Ansichten von der Verbreitung der Cholera.

[Med. Conversbl., 1832, pp. 41–42.]

Billaudelle. Remarques et observations sur le choléra-morbus aqueux [1849]. *Beville* [1849].

Bird (S. D.) On the nature and treatment of epidemic cholera.

[Austral. Med. Jour., Melbourne, 1857, pp. 73–92.]

Bischoff (J. R.) Kurze Belehrung über die Kennzeichen und Verhütung der Cholera. Nebst Angabe der Behandlungsart bis zur Ankunft des Arztes. 12°. *Wien*, 1831.

Blacklock (A.) The leading phenomena of epidemic cholera, with some practical suggestions for its better treatment and prevention. 8°. *Madras*, 1848.

Blanc (H.) Des moyens de prévenir et de traiter le choléra. Étude fondée sur une connaissance des causes et du mode de propagation de cette maladie. *Paris*, 1874.

Blanchard (N.) * Quelques réflexions relatives au choléra-morbus. 4°. *Paris*, 1833.

Bland. Cholera asphyxia.

[St. Louis Med. & Surg. Jour., 1866, pp. 501–511.]

Bland. Nouvelles observations sur la nature et le traitement du cholera-morbus épidémique.

[Revue méd. franç. et étrang., 1832, pp. 41–44.]

Blaustein. Einige Notizen über asiatische Cholera.

[Neue med.-chir. Zeitg., 1847, IV, pp. 369–372.]

Bleeker (P.) De Cholera. 8°. *'s-Gravenhage*, 1866.

Blizard (W.) An address to the gentleman and members of the house committee of the London hospital on the subject of cholera. 8°. *London*, 1831.

Block (J. G. de). Le choléra-morbus. *Gand*, 1849.

Blume (C. L.) Over de asiatische cholera, uit eigene Waarnemingen en Stukken. 8°. *Amsterdam*, 1832.

Bockenheimer (J. A.) Die Cholera in ihren Erscheinungen und in ihrem Wesen populär dargestellt. 8°. *Frankf. a. M.*, 1865.

denhamer (W.) Epidemic cholera.
[Hall's Jour. of Health, N. Y., 1833, II. pp. 212–217.]

din (L.) Précis sur le choléra-morbus et sur la contagion. 8°. *Tours*, 1831. L.

eneck (G. S.) Noch ein Wort über die epidemische Cholera, eine Vertheidigungs- und Widerlegungsschrift. 8°. *Hamburg*, 1831.

ëns. Observations recueillies pendant l'épidémie de choléra en 1848–49, dans le service de M. Lombard. Rapport de M. Lequime.
[Bull. de l'Acad. roy. de méd. de Belg., 1853–56, XV, pp. 16–19.]

— Note sur la symptomatologie, l'étiologie, et le traitement du choléra épidémique.
[Bull. de l'Acad. roy. de méd. de Belg., 1866, IX, pp. 839–847.]

ittger (A. G.) *De cholera orientali. 16°. *Halae*, 1832. L.

loisseau, *aîné*.] Notice sur le choléra, causes, symptômes, traitement, préservatif. 8°. *Paris* [1849].

oisseau (F. G.) Traité de choléra-morbus considéré sous le rapport médical et administratif, ou recherches sur les symptômes, la nature et le traitement de cette maladie, et sur les moyens de l'éviter. 8°. *Paris*, 1831.

— Mémoire sur la cyanose cholérique.
[Journ. univ. et hebd. de méd. et de chir. prat., Paris, 1832, IX, pp. 277–286.]

— Traité du choléra morbus. *Paris*, 1832.

olle (P. M.) De cholera orientali. *Greifswalde*, 1838.

mpard (A.) Du choléra-morbus. Description de la maladie, des moyens hygiéniques et pharmaceutiques qu'il convient de lui opposer. 8°. *Paris*, 1831. L.

njean (J.) Le choléra; moyens de le prévenir, de le combattre à temps et d'en restreindre l'étendue. 16°. *Paris*, 1867.

nnet (A.) De la nature et du siége du choléra-morbus; communication faite à la Société royale de médecine de Bordeaux. 8°. *Bordeaux*, 1832.

onacker (J. J.) *De cholera asiatica. 8°. *Lugd. Bat.*, 1833.

os (F. de). Le choléra asiatique. 32°. *Paris* [1853].

rchardt (J. S.) Anweisung zur Abwehrung und Behandlung der pandemisch-contagiösen Cholera, worin der Ursprung des Namens "Cholera", die

Borchardt (J. S.)—continued.
Gelegenheitsursache, der Sitz, das Wesen, das primäre Leiden und eine sichere Heilmethode derselben nachgewiesen wird. 12°. *Berlin*, 1831. L.

——— Kurze Darstellung der Cholera. 8°. *Berlin*, 1831.

Borelli (G.) Lettere sul cholera morbus. 18°. *Torino*, 1855.

Bories (P.) Du choléra-morbus asiatique, et des moyens de s'en préserver. 8°. *Paris*, 1832. L.

Borivent. Simple mot sur le choléra. 8°. *La Guillotière* [1850].

Bostock (J.) Observations on cholera.
[London Med. Gaz., 1842–43, pp. 870–871.]

Bottani (A.) Riflessioni sopra il colera asiatico.
[Giorn. p. serv. ai progr. d patol., 1836, IV, pp. 371–397.]

Bouchardat (A.) *Sur la nature, le traitement et les préservatifs du choléra-morbus. 4°. *Paris*, 1832. L.

Bouchut. Le choléra et son traitement.
[Gaz. des hôp., 1865, pp. 522–523.]

Bouillaud (J.) Leçons sur le choléra-morbus.
[Gaz. des hôp., 1832 VI, pp. 153–154, 158–159, 162–163, 170–171, 174–175, 181–182, 190–191.]

——— Quelques réflexions sur la nature, etc., du choléra. 8°. *Paris*, 1832.

[**Bourdon** (I.)] Choléra-morbus. 8°. *Paris* [1854].

Bourgogne. Étude sur la cachexie cholérique primitive. Traitement.
[L'Abeille med., Paris, 1865, XXII, pp. 402–404; 1866, XXIII, pp. 3–4.]

Bourgogne, *père*. Traité de la médication complète du choléra asiatique considéré comme une fièvre paludéenne épidémique très-pernicieuse de l'Inde orientale, offrant avec le type continu les formes nerveuse, sudorale et gastro-intestinale, précédé de l'examen des lettres de MM. Boudin, Maillot, F. Jacquot, touchant la non-identité du choléra et des fièvres palustres. 8°. *Paris*, 1859. L.

——— Aperçu sommaire touchant les idées émises dans les différents ouvrages du dr. Bourgogne père, sur la nature, les différentes formes, et le traitement du choléra asiatique considéré comme une

Bourgogne, *père*—continued.
fièvre paludéenne pernicieuse de l'Inde orientale, offrant le type continu.
[Jour. de méd., de chirurg. et de pharm., Bruxelles, 1866, xlii, pp. 32–41.]

——— Lettre à M. Crocq, touchant certaines propositions relatives à la nature et au traitement du choléra indien.
[Jour. de méd., de chirurg. et de pharm., Bruxelles, 1869, xxx, pp. 237–250. 321–333.]

Bourgogne (L. F.) Simple leçon sur le choléra. 12°. *Auzin*, 1849.

Bourrian (A.) *Du choléra. 4°. *Paris*, 1854. L.

Bousquet. Lettre d'un médecin à un magistrat sur le choléra-morbus. 8°. *Paris*, 1831. L.

Bouvier (A.) *Choléra. De la réaction. 4°. *Paris*, 1856. L.

Boyer (P. A.) *Du choléra épidémique. 4°. *Paris*, 1856. L.

Boyle (J.) Epidemic cholera of India. 8°. *London*, 1821.

Bräunlich (F. G.) Cholera asiatica. Deren Wesen und Behandlung. 8°. *Freyberg*, 1831.

Braun. Zu Herrn Dr. Mayer's Quodlibet über die Cholera.
[Med. Conversationsbl., 1832, pp. 401–405.]

Bravard (T.) *et* **Marquet** (E.) Du choléra, de sa véritable cause et de son traitement anthelmintique, d'après les principes de la nouvelle méthode. 18°. *Paris*, 1849.

——— The same. 2e éd. 8°. *Jumeaux-sur-Allier*, 1854.

Brébant (L.) Choléra épidémique considéré comme affection morbide personnelle. Physiologie pathologique et thérapeutique rationnelle. 8°. *Paris*, 1868. L.

Bree (R.) Thoughts on cholera asphyxia. 8°. *London*, 1832. L.

Breggen (F. van der). Bijdragen tot Bevordering van de Kennis aangaande den Aart, de Verschijnsen, de Vóórkoming en de Behandeling van de westelijk Gedeelte van Europa bedreigende Cholera. 8°. *Amsterdam*, 1831. L.

——— Wenken voor he niet geneeskundig Publieck, met Opzigt tot de Cholera. 8°. *Amsterdam*, 1831.

——— Brief aan C. G. Ontjid in Antwoord op zijne hemgeschreven Brieven voorkomende in den algem. Konst- en Letterbode betr. de asiatische Cholera. 8°. *Amsterdam*, 1832.

Breitenbuecher (C. H. T.) Cholerae orient. s. epidem. antidoti, theoria et experim. etc. 8°. *Rostochii*, 1831.

Breuning (G. v.) Der asiatischen Brechruhr Erkenntniss und Heilart. 8°. *Wien*, 1837.

Briand (J.) Du choléra, son origine, ses principaux caractères, son véritable traitement. 12°. *Rennes*, 1849.

Briquet (P.) *et* **Mignot** (A.) Traité pratique et analytique du choléra-morbus: [épidémie de 1849]. 8°. *Paris*, 1850. L.

Brochin. Le choléra.
[Gaz. des hôp., 1865, p. 485.]

Brockmüller (C.) Ansichten über die herrschende Cholera, Vergleiche derselben mit dem Wechselfieber, und Beweise dass dieselbe so wenig ansteckend ist, noch werden kann, als das Wechselfieber [etc.] 8°. *Julich*, 1832. L.

Broelemann (F.) *De cholera asiatica. 8°. *Bonnae*, 1867. C.

Broocks (J. N.) On cholera. *
[Virginia Med. & Surg. Jour., 1854, iii, pp. 314–323.]

Brosch (C. W.) Die epidemische Cholera, ihrem Wesen nach betrachtet. Ein Beitrag zur Diagnostik derselben. 8°. *Prag*, 1832.

Brossard (M.) *Quelques réflexions sur le choléra épidémique. 4°. *Paris*, 1832. L.

Brougham (S.) On cholera. A treatise, practical and theoretical, on the nature of this disease; with an examination of the moral and physical influence of the doctrine of contagion. 8°. *London*, 1834. L.

Broussais (F. J. V.) Leçons sur le choléra.
[Gaz. des hôp., 1832, vi, pp. 95–97, 105–106, 109–111.]

——— Lettre sur le choléra-morbus. 8°. *Lyon* [1832].

——— Lezioni sul cholera-morbus. [*Milan*, 1835.]

——— Le choléra-morbus épidémique, observé et traité selon la méthode physiologique. 8°. *Paris*, 1832.

——— Cholera. Two clinical lectures upon the nature, treatment and symptoms of spasmodic cholera. [Translated by J. S. Bartlett.] 8°. *New York*, 1832. L.

Brown. Cholera.
[Cyc. of Pract. Med., Phila., 1845, i, pp. 399–428.]

ruck (M.) Das Wesen und die Behandlung der asiatischen Cholera, oder wissenschaftliche Lösung der Cholerafrage. 8°. *Berlin*, 1841. L.

ruggemann (A. F.) Ueber die Cholera: einige Worte zur Beruhigung über die Möglichkeit und die Grösse der Gefahr. 12°. *Leipzig*, 1831.

uno (G.) Il colera alla portata di tutti e suo metodo curativo. 2a ed. 4°. *Napoli*, 1855. S. C.

iard (G. A. L.) * Du choléra-morbus épidémique. 4°. *Paris*, 1832. L.

ichanan (A.) Observations on malignant cholera, intended to illustrate the natural course of the disease, the natural processes by which a spontaneous recovery is effected, and the mode of treatment best adapted to second the curative efforts of nature. 8°. *London*, 1848. L.

ichner (J.) Die Cholera. 8°. *München*, 1831. L.

ichner (F. W.) Wenken en Raadgevingen betreffende den aziatischen Braakloop, aan zijne Stadgenooten. 12°. *Gouda* [*n. d.*] L.

dd (G.) A clinical lecture on cholera.
[Med. Times, 1849, xx, pp. 315–317.]

— Cholera.
[Wilson's Sys. of Pract. Med., Philadelphia, 1841, iv, pp. 158–186.]

ttner (C. J.) Die Cholera asiatica, deren Ursachen, Behandlung und Verhütung auf Grund der während der 1866er Epidemie in der Seidau bei Budissin gemachten Erfahrungen. 8°. *Leipzig*, 1866. L.

falini (M.) Pensieri intorno alla colera alle malattie epidemiche e contagiose.
[Giorn. p. serv. al progr. d. patol., 1835, II, pp. 431–442.]

sson. Traité sur le choléra. 8°. *Paris*, 1855.

sson (F.) Traité raisonnée sur le choléra. Moyen de prévenir et de guérir cette maladie. 4°. *Paris*, 1835. L.

ard (A. F.) Nouvelles recherches sur cause, la nature, les moyens préservatifs et le traitement du choléra. 8°. *Paris*, 1833.

dina (M.) Trattato delle varie specie cholera-morbus. 8°. *Turin*, 1831.

eaud-Riofrey (A. M.) Du choléra; moyens préservatifs et curatifs, ou philosophie des grandes épidémies. 8°. *Paris*, 1847. L.

Bureaud-Riofrey (A. M.)—continued.

——— The same. 8°. *Paris*, 1865.

Burrall (F. A.) Asiatic cholera. 12°. *New York*, 1866. L.

Burrough (M.) [On spasmodic cholera, in two letters: I. Letter addressed to D. Hosack, New York, September 15, 1831. II. Letter addressed to the board of health of Philadelphia, September 27, 1831.] 8°. [*Philadelphia*, 1831.] L.

Bushnan (J. S.) Cholera and its cures.
[London Jour. of Med., 1850, II, pp. 966–969.]

Caffe. Notice sur le choléra. 8°. *Paris* [1849].

Caggiati (L.) Lezioni sul cholera. 16°. *Parma*, 1856.

Cahen. Du choléra, sa nature et son traitement. 8°. *Paris*, 1866.

Cajander (H.) Afhandling om Cholerans epidemiska Natur. 12°. *Helsingfors*, 1832. L.

Calamy (E.) Quelques considérations générales sur le choléra dit asiatique. 4°. *Paris*, 1833. L.

Calenda (D.) Preguidizie e verità sul morbo-colera con la cura specifica del polmone. 8°. *Napoli*, 1874. L.

Campi (E.) Memoria critica sul cholera-morbus e sull'uso del salasso nel suo trattamento. 8°. *Cagliari*, 1856.

Camus (P. C. A.) * I. Le diagnostic du choléra-morbus épidémique [etc.] 4°. *Paris*, 1843. L.

Cane (R.) Some practical remarks on cholera.
[Dublin Med. Press., 1848, xx, pp. 100, 117–120.]

Cannon (H. M.) Cholera theories and practice.
[Brit. Med. Jour., 1866, I, p. 494.]

Canstatt (C.) Darstellung der ostindischen Brechruhr. 8°. *Regensburg*, 1831.

——— De oost-indische Braakloop. Uit het Hoogd. vert. door H. H. Hagemann, jr. 8°. *Amsterdam*, 1848.

Capsoni (G.) Breve di una memoria inedita intorno al colera estesa nel 1831.
[Giorn. p. serv. al progr. d. patol., 1835, III, pp. 72–74.]

Caracciolo (G.) Sul cholera morbus. 16°. *Messina*, 1872.

Caraxaimis (E. A.) Du choléra. 4°. *Paris*, 1850. L.

Carbonaro (G.) Osservazioni pratiche sul cholera-morbus. 8°. *Napoli*, 1855.

Carlisle (A.) Letter on cholera-morbus; with notes by Chas. Caldwell.
[MARYLAND Med. Recd., Balto., 1831, II, pp. 570–580.]

——— A lecture on cholera and other pestilential diseases, etc. 8°. *London*, 1832.

Carr (A.) Remarks upon the theory and treatment of Asiatic cholera.
[LANCET, 1848, I, p. 67.]

Carroll (T.) On the symptoms and treatment of Asiatic cholera.
[CINC. Lancet & Observ., 1866, IX, pp. 521–537.]

Carter (W. B.) *De cholera indica vel spasmodica. 8°. *Glasgow*, 1822.

Cartwright (S. A.) Some account of the Asiatic cholera, cholera asphyxia, or pulseless plague; with a sketch of its pathology and treatment, and advice relative to its prevention on plantations, premonitory symptoms and treatment. 8°. *Natchez, Miss.*, 1833. L.

——— The pathology and treatment of cholera; with an appendix containing his latest instructions to planters and heads of families (remote from medical advice) in regard to its prevention and cure. 8°. *New Orleans*, 1849. L.

Casanova (J. N.) General observations respecting cholera morbus. 8°. *Philadelphia*, 1834. L.

Casile (N.) Compendio di osservazioni cliniche sul cholera. *Alessandria*, 1865.

Casilli (N. D.) Istruzioni sommarie sul colera asiatico dirette al suoi alunni. 3a ed. *Napoli*, 1865. L.

Cassaignade (P. J.) Mémoires sur les causes de la vie. Avec un mémoire sur le choléra-morbus asiatique. 8°. *Nismes*, 1835. L.

Cassesse (E.) Brevissima storia del cholera per colore, che non professano medicina, cive per poterlo essi distinguere, preservarsene, e riparare. 8°. *Napoli*, 1836. L.

Cassiano (G.) Idee generiche sul cholera in occasione di alcuni sospetti, che tale malatti a potesse visitare Livorno anche nel 1854.
[GAZ. med. Ital. Tosc., 1854, IV, 2a s., pp. 221–222.]

Cazentre (J. E.) Considérations sur la nature, le siége et le traitement du choléra-morbus épidémique. 4°. *Paris*, 1833. L.

Cerbonney Dubarry (J. M. C.) *Sur le choléra. 4°. *Paris*, 1832. L.

Céré (J. L.) *Dissertation sur le choléra-morbus. 4°. *Paris*, 1833. L.

Ceresa (C. de). Riflessione sulla cholera epidemica. 8°. *Vienna*, 1831.

Chabert (J. X.) Observations on the origin, treatment and cure of Asiatic cholera, and cholera morbus; and the result of an experience of forty-five years during a residence in Asia, Europe, and America. 8°. *New York*, 1852. L.

Chalut (L. P.) Note sur l'épidémie du choléra. 8°. *Sevres*, 1833.

Chambers (W. F.) Three lectures on cholera.
[LONDON Med. Gaz., 1849, XLIII, pp. 244–251, 288–293, 325–330.]

Chaniac (E. de). *Du choléra-morbus. 4°. *Paris*, 1847. L.

Chaperon (L. F.) Essai sur la nature et le traitement du choléra asiatique, basé sur l'autopsie et la clinique.
[CANADA med. jour., 1852, I, pp. 513–536, 577–589.]

Chapman (N.) A letter on cholera, to Dr. Tyler, with remarks.
[TRANSYLV. Jour. of Med., Lexington, 1832, V. pp. 450–457.]

——— Lecture on cholera morbus.
[AM. Jour. of Med. Sci., 1833, XII, pp. 293–306.]

Charnaux (E.) *Étude sur le choléra. 4°. *Paris*, 1858. L.

Charpentier (A. T., *fils*). *Dissertation sur le choléra-morbus. 4°. *Paris*, 1831. L.

Charruau (A.) *Essai sur le choléra-morbus. 4°. *Paris*, 1834. L.

Cheaney (J. P.) Interesting facts connected with cholera.
[RICHMOND & Louisv. Med. Jour., 1869, VIII, pp. 587–589.]

Chevalier (T. W.) On Asiatic cholera, to his patients and acquaintance. 8°. *London*, 1831. L.

Chevreul. Considérations relatives à l'état actuel de nos connaissances sur le choléra.
[GAZ. des hôp., 1865, pp. 542–543.]

Chiari. Riflessioni sul cholera-morbus del 1835 applicabili a quello del 1854. *Firenze*, 1854.

Chilliard (C. J.) *De la cholerrhagie. 4°. *Paris*, 1819. L.

Chomel. Leçons cliniques sur le choléra.
[GAZ. des hôp., 1849, pp. 155–156, 164–165, 176–177, 184–185; *also, in* L'UNION méd., Paris, 1849 III, pp. 142–143, 147–148, 155–156, 159–160.]

Chomet (H.) Le choléra-morbus, ses causes, sa marche, ses symptômes et son traitement, d'après les faits observés en 1832 et 1849. 8°. *Paris*, 1849.

Chrestien (A. T.) Étude du choléra

Chrestien (A. T.)—continued.
morbus à l'usage des gens du monde. 8°. *Montpellier*, 1835.
[3e éd., 18°, 1849; 4e éd., 1855.]

Christie (A. T.) Observations on the nature and treatment of cholera, and on the pathology of mucous membranes. 8°. *Edinburgh*, 1828. L.

—— On the epidemic cholera. 8°. *London*, 1833.

—— A treatise on the epidemic cholera, containing its history, symptoms, autopsy, etiology, causes, and treatment.
[London Med. & Phys. Jour., 1833, LXIX, pp. 265–283, 353–365, 456–473, 1 map.]

—— On the symptoms of epidemic cholera.
[Jamaica Phys. Jour., Kingston, 1834, I, pp. 79–91.]

Chuckerbutty (S. G.) Cholera, its symptoms, clinical history, pathology, diagnosis, prognosis, treatment and prophylaxis.
[Ind. Ann. of Med. Sci., Calcutta, 1867, XXII, pp. 61–236.]

Cigala (J. de). * Ueber die Cholera. 8°. *Syra*, 1868.

Cipolina (C.) Molta luce sul cholera-morbus. 8°. *Genova*, 1874.

Clanny (W. R.) The diagnosis of English and Asiatic cholera.
[Lancet, 1833–34, I, pp. 335–336.]

—— On cholera.
[Med. Times, 1849, XX, pp. 344–345.]

Clark (A.) Lectures on cholera.
[Med. & Surg. Reporter, 1866, XIV, pp. 161–164, etc; *also*, in Med. Record, N. Y., 1866–67, I, pp. 29–32, etc.]

Clark (B.) The cholera unmasked, or its true name, nature and causes pointed out; also a more consistent and successful mode of treating. 4°. *London*, 1833.

—— The same. fol. 1848.

Clark (C.) On cholera, its nature and treatment.
[Lancet, 1846, I, pp. 651–652.]

Clement (A.) Il cholera: la sua origine, il suo sviluppo, e le sue escursioni. 8°. *Napoli*, 1865.

Cloquet (J.) Sur le choléra-morbus.
[Bull. de l'Acad. imp. de méd, Paris, 1865–66, XXXI, pp. 157–161.]

Clutterbuck. Lectures on cholera morbus, diarrhœa and dysentery.
[Lancet, 1826, X, pp. 354–357.]

Cockle (J.) Practical observations upon some forms of epidemic cholera.
[Med. Circular, 1854, V, p. 131.]

Coghlan (J.) Practical observations on the history, nature and treatment of cholera asphyxia. 8°. *Dublin*, 1853.

Cohen (L. A.) Voorafgaande Diarrhœa en Cholera.
[Nederl. Tijdschr. v. Geneesk, 1857, I, pp. 51–54.]

Collins (F.) On cholera.
[Med. Circular, 1854, V, pp. 139–140.]

Colson. Observations sur le choléra et le traitement de cette maladie.
[Gaz. des hôp., 1832, VI, pp. 142–143.]

Comegys (C. G.) Pathology and treatment of Asiatic cholera.
[Cinc. Jour. of Med., 1866, I, pp. 430–436.]

Comet (C. J. B.) Traité sur le choléra-morbus. 8°. *Paris*, 1831.

Comstock (J.) On cholera and typhus fever.
[Boston Med. & Surg. Jour., 1832, VI, pp. 269–271.]

Conant (D. S.) Remarks on the pathology and treatment of cholera.
[Amer. Med. Monthly, 1855, III, pp. 81–96.]

Concata (L.) Parole al popolo sul cholera. *Bologna*, 1865.

Contini (A.) Istruzione al popolo per conoscere e curare il cholera-morbus asiatico. *Chiari*, 1867.

—— Del segno principale per il quale si conosce tosto il cholera-morbus asiatico e sul suo metodo curativo e preservativo appoggiato all'ossido e fiori di zinco. *Chiari*, 1867.

Cooke (J. E.) Remarks on spasmodic cholera.
[Transylv. Jour. of Med., 1832, V, pp. 481–500.]

Cooke (T. W.) A few words on diarrhœa and malignant cholera in a letter to a country patient. 8°. *London*, 1848.

Cooke (W.) A brief sketch of the most striking characteristic appearances, during life and after death, of the continental spasmodic cholera; with practical remarks upon its treatment. 8°. *London*, 1861. L.

Copland (J.) Of pestilential cholera: its nature, prevention, and curative treatment. 8°. *London*, 1832. L.

Coppinger (J. J.) Another word about cholera.
[Med. Times, 1850, I, p. 186.]

Corneliani (J.) Animadversiones in epidemias atque contages ad choleram morbum relatae. 8°. *Papiae*, 1836. L.

Corréger (L.) Ce qu'on pense du choléra dans le monde médical, état actuel de cette question. 8°. *Paris*, 1866. L.

Corriez. Le choléra, sa guérison par ses antidotes naturels; moyen de le prévenir et de se guérir soi-même. [etc.] 12°. *Amiens* [1867].

Couverchel (*jeune*). Théorie du choléra, et des moyens de paralyser sa funeste influence.

[Revue méd. franç. et étrang., 1835, IV, pp. 360–379.]

Coventry (C. B.) Report on epidemic cholera. 8°. *Utica, N. Y.*, 1848. L.

——— Epidemic cholera: its history, causes, pathology, and treatment. 12°. *Buffalo*, 1849. L.

Cowan (C.) Observations on cholera.

[Provinc. Med. & Surg. Jour., 1848, pp. 594–599.]

Cox (A. L.) The pathology and treatment of Asiatic cholera, so-called. 2d ed. 8°. *New York*, 1849. L.

Cox (P.) *Dissertation sur le choléra-morbus observé dans les régions équatoriales. 4°. *Paris*, 1824. L.

Coxe (E. J.) Remarks on cholera, with special reference to the severe and collapsed stages.

[Boston Med. & Surg. Jour., 1855, LI, pp. 169–175.]

Craigie (D.) Observations, pathological and therapeutic, on the epidemic cholera. 8°. *Edinburgh*, 1832.

Cranfield (R.) Practical observations on cholera and on the treatment of the disease. 8°. *Dublin*, 1834.

Crisp (E.) On malignant cholera: its origin, pathology, treatment, and mode of prevention, with the occupations of 5568 males over 20 years of age that died in London in 1849, 1853, 1854, and 1866, [etc.] 8°. *London*, 1866. L.

Croft (J. M.) Asiatic cholera.

[Med. Press & Circ., 1870, pp. 94–95.]

Crookshank. Hints on cholera.

[Western Med. Gaz., 1835, II, pp. 149–152.]

Crosilhes (H.) Du choléra, des moyens de le prévenir et de son traitement. 8°. *Paris*, 1848.

Cross (E.) Cholera and diarrhœa.

[Lancet, 1857, II, pp. 180–181.]

Crousat (E. P. A.) *Étude sur le choléra-morbus épidémique. 4°. *Paris*, 1856. L.

Crummey (L. F.) Observations on cholera.

[Med. Times, 1849, XIX, pp. 197, 321.]

——— Practical observations on cholera.

[Lancet, 1854, II, p. 178.]

Cuvelier (J.) *Dissertation sur le choléra-morbus épidémique. 4°. *Paris*, 1832. L.

Daneri (L.) Esaminazione dell'opuscolo di prof. L. Caggiati: "Lezione sul cholera."

[Omodei, Ann. un. di med., 1857, CLIX, pp. 69–118.]

Danet (G.) Des infiniment petits rencontres chez les cholériques; étiologie, prophylaxie et traitement du choléra. 8°. *Paris*, 1873. L.

Dargin. Nature and treatment of Asiatic cholera.

[Nashville Jour. Med. & Surg., 1854, VII, pp. 481, 495.]

Davis (N. S.) The pathology and treatment of epidemic cholera.

[Chicago Med. Examiner, 1866, VII, pp. 193–198.]

Davreux (M.) Le choléra: considérations cliniques et traitement. 8°. *Paris*, 1874. L.

Debat (P. L.) *Du choléra-morbus épidémique. 4°. *Paris*, 1833. L.

Dechambre (A.) Quelques remarques sur certaines manifestations de l'épidémie actuelle [choléra].

[Gaz. hebd. de méd. et de chirurg., 1853–54, I, pp. 501–504.]

——— Des symptômes prémonitoires du choléra.

[Gaz. hebd. de méd. et de chirurg., 1865, II, 2e s., pp. 673–675, 805–807.]

Dehous. Réplique à la réponse de M. le dr. Bourgogne père . . . . Travail lu à la section des sciences . . . de la Société de Valenciennes. 8°. [*Valenciennes*, 1857.]

Delagrange. Mémoire contre le choléra d'Asie, la peste d'orient, [etc.] *Paris*, 1850.

Delery (C.) Observations on cholera.

[N. O. Med. & Surg. Jour., 1849–50, VI, pp. 127–133, 197–209.]

Della Bella (V.) Il reggente del cholera-morbus. 8°. *Napoli*, 1873.

Delmas (J. F.) *Essai sur le choléra-morbus. 4°. *Paris*, 1835. L.

Delord (P. M. E.) *Du choléra épidémique. 4°. *Paris*, 1853. L.

Delpech (J.) Études sur le choléra-morbus. *Paris*, 1832.

Delthil (J.) *Dissertation sur le choléra-morbus épidémique. 4°. *Paris*, 1832. L.

Denans (F. N.) *Dissertation sur le choléra-morbus, suivie de quelques observations recueillies dans l'Inde. 4°. *Paris*, 1820. L.

Desgenettes (*Le baron*). Lettre sur le choléra-morbus.
[Gaz. des hôp., 1832, VI, pp. 235–236.]

Desruelles (H. M. J.) Précis physiologiques du choléra-morbus. 8°. *Paris*, 1831. L.

De Vine. Colera morbus, sus causas, sintomas, no-contajiosidad, etc.
[Gaceta med., Lima, 1867. XII, pp. 10, 12, 23, 24, 47, 48.]

Dewachter. Mémoire sur le choléra. Rapport de M. Lequime.
[Bull. de l'Acad. roy. de méd. de Belg., 1849–50, IX, pp. 378–380.]

Dexter (R.) Epidemic cholera. A few remarks on its pathology and treatment.
[Chicago Med. Exam., 1866, VII, pp. 577–581.]

Dick (R.) Cholera.
[London Med. Gaz., 1847, XL, pp. 1137–1140.]

Dickson (S.) Memoranda on the epidemic cholera of India.
[Lancet, 1829–30, II, pp. 235–240.]

—— On the epidemic cholera and other prevalent diseases of India. 8°. *Edinburgh*, 1832.

Didiot (P. A.) Étude nouvelle du choléra, historique, dynamique, prophylactique. 8°. *Paris et Marseille*, 1866. L.

Dieffenbach (J. F.) Observations physiologiques et chirurgicales faites sur les cholériques. 8°. *Berlin*, 1835. L.

Dieterich (G. L.) Beobachtung und Behandlung des wandernden Brechdurchfalles, in München dargestellt. 8°. *Nürnberg*, 1837. L.

Dietl. Klinische Vorträge über die Cholera.
[Wien. med. Wochenschr., 1855, pp. 353, 374, et seq.]

—— The same. 8°. *Krakau*, 1855. L.

Dietrich (E. C. V.) Die Influenza [Grippe], Ruhr, epidemische Diarrhöe und asiatische Brechruhr. Cholera in Hinsicht ihrer Geschichte, ihres Verlaufs, ihrer Behandlung und Krankenplege. 8°. *Leipzig*, 1837.

Dixon (J.) A lecture on diarrhœa and cholera, their nature, symptoms, treatment, and prevention. 12°. *London*, 1871. L.

Doden (G.) Ideen über das Wesen der asiatischen Brechruhr und Versuch zur Begründung eines rationellen Vorbauungs- und Heilverfahrens für diese Krankheit. 8°. *Hannover*, 1831. L.

Dole (J. C.) Opuscule sur le choléra-morbus spasmodique et épidémique [etc.] 8°. *Marseille*, 1832.

Doquin de Saint-Preux. Remarques et observations sur le choléra.
[Gaz. méd. de Paris, 1835, III, pp. 510–511.]

Dorris. Cause, prevention and cure of cholera.
[Nashville Jour. Med. & Surg., 1851, I, pp. 174–190.]

Douglas (G.) Asiatic cholera.
[Brit.-Am. Jour. of Med. & Phys. Sci., 1847–48, III, pp. 262–263.]

Dowler (B.) On cholera.
[N. O. Med. & Surg. Jour., 1856–57, XIII, pp. 620–640; 1857, XIV, pp. 171–190, 297–307; 1858, XV, pp. 387–394, 605–617.]

Dowling (F.) Some remarks on cholera.
[Cinc. Lancet & Obs., 1873, XVI, pp. 590–594.]

Drake (D.) A practical treatise on the history, prevention, and treatment of epidemic cholera. 12°. *Cincinnati*, 1832. L.

Drasche (A.) Die epidemische Cholera; eine monographische Arbeit. 8°. *Wien*, 1860. L.

—— Die Cholera und der Krieg.
[Wien. med. Wochenschr., 1870, XX, pp. 933–935.]

Draut. Ueber die Cholera.
[Med.-chirurg. Zeitg., Salzburg, 1832, I, pp. 315–320, 333–336.]

Drescher (H.) * De cholera epidemica. 8°. *Vratislaviæ*, 1848. L.

Duboc (J. A.) Recherches sur le choléra, ses causes . . . . et les moyens curatifs et préservatifs de s'en garantir individuellement. 8°. *Paris* [1833].

Dubois (E. F.) Examen des conclusions du rapport de M. Double sur le choléra-morbus. 8°. *Paris*, 1831. L.

Dubois (H.) Recherches sur l'origine et la nature du choléra d'Asia, et traitement de cette maladie. 8°. *Soissons*, 1832.

Duchassain (E. M. A.) Du choléra pestilentiel, méthode préservative et curative de cette maladie. 8°. *Saint-Quentin*, 1831.

Dugas (*nerveu*). Rapport sur l'invasion du choléra; son origine; sa propagation; ses symptômes; son traitement.
[Gaz. des hôp., 1837, XI, pp. 461, 465–466.]

Duhamel (F., *Le duc.*) Choléra-morbus; méthode pour le reconnaître, s'en préserver et le guérir. 12°. *Montpellier* [1850].

Duhot (F. L.) * De cholera. 4°. *Gand*, 1821.

Dunan (E. J. M.) * Du choléra épidémique. 4°. *Paris*, 1850. L.

Dupuytren. Lettre et leçon . . . sur le siége, la nature et le traitement du choléra-morbus, recueillies et publiées par MM. A. Paillard et Marx. 8°. *Paris*, 1832. L.

——— Lettre sur la nature, le siége et le traitement du choléra-morbus.

[BULL. gén. de thérap., méd. et chirurg., 1832, II, pp. 89–93; *also*, in JOUR. univ. et hebd. de méd. et de chirurg. prat., 1832, VI, pp. 171–176, 212–229.]

Durand (F. A.) De la nature et du traitement du choléra.

[GAZ. méd. de Paris, 1849, IV, pp. 730–733, 755–758.]

Duringe. Observations et notes sur le choléra-morbus oriental. 8°. *Paris*, 1831.

——— Un dernier mot sur le choléra. 8°. *Paris*, 1832.

Duse (A.) Sul cholera morbus. *Chioggia*, 1869.

Duval (C.) Du choléra. 8°. *Alger*, 1854.

Dvorjak (C.) Mémoire sur le développement, les causes et le traitement du choléra. 8°. *St.-Pétersbourg*, 1848. L.

Dyrsen. Kurzgefasste Anweisung, die orientalische Cholera zu verhüten, zu erkennen und zu behandeln. 8°. *Hamburg*, 1831. L.

Ebermaier (C. H.) Erfahrungen und Ansichten über die Erkenntniss und Behandlung des asiatischen Brechdurchfalls. 8°. *Düsseldorf*, 1832. L.

Eissen. Choléra.

[GAZ. méd. de Strasbourg, 1849, IX, pp. 241–245, 281–287, 297–304, 329–332, 361–365, 393–394.]

Elliotson. Epidemic Asiatic cholera.

[DOCTOR, London, 1833–34, II, pp. 29–33, 31, 35–37.]

Elsässer (C. L.) Die epidemische Cholera nach eigenen, aus Auftrag der königlich-würtembergischen Regierung angestellten Beobachtungen in Wien und Mähren, besonders Brunn. 8°. *Stuttgart*, 1832. L.

Elsner (C. J. H.) Ueber die Cholera. Ein Versuch dieselbe zu deuten. 12°. *Königsberg*, 1831. L.

Ely (W. S.) An essay on Asiatic cholera. 8°. *Rochester*, 1872. L.

Emangard (F. P.) *Dissertation sur le choléra. 8°. *L'Aigle*, 1832.

Ennemoser (J.) De aziatische Cholera, hare Kenteekenen, Beloop, Oorzaken, Voorbehoeding en Behandeling. Eene Handleiding voor Niet-Geneeskundigen deze Ziekte te leeren kennen, te voorkomen en te genezen. Naar het Hoogduitsch van Dr. J. Ennemoser en Anderen bewerkt door een practiserend Geneesheer. 8°. *Utrecht en Amsterdam*, 1848. L.

——— Was ist die Cholera, und wie kann man sich vor ihr am sichersten bewahren? Nebst Angabe der bewährtesten Heilung derselben. 2te Aufl. 8°. *Stuttgart und Tübingen*, 1854. L.

——— Che cosa è il cholera e come ci amo garentirci da esso nel modo sicuro? Con l'aggiunta di una descrizione del più sperimentato metodo di cura del dott. Ennemoser; tradotto dal tedesco sulla seconda edizione. Cotta in Stuttgard per cura del dott. Federico Clerpazzo. 8°. Napoli, 1854.

Etienne (J. P.) Mémoire sur le cholera-morbus. 8°. *Metz*, 1835.

Eydoux (C. T.) *Considérations générales sur la nature du choléra asiatique. 4°. *Paris*, 1832.

Fabas (B. X.) Notice sur le choléra asiatique, sur l'identité des symptômes qui le caractérisent, comparés à ceux produits par la morsure de la vipère, et sur son traitement abortif et curatif. 8°. *Tarbes*, 1857.

Faber (W. E.) Ueber die Cholera

[MED. Correspbl. des württemb. ärztl. Vereins, 1832, I, pp. 89–91, 93–95; *also*, reprint, Stuttgardt, 1832.]

Fabre (A. F. H.) Choléra-morbus. Guide du médecin praticien dans la connaissance et le traitement de cette maladie, suivi d'un dictionnaire de thérapeutique appliquée au choléra-morbus et d'un formulaire spécial. 8°. *Paris*, 1854.

Fabre (E.) Mémoire sur le choléra-morbus. 8°. *Marseille*, 1854.

Facini (G.) Cicalata sul cholera e sulle malattie affini. *Padova*, 1851.

Fallot. Note sur le choléra-morbus. [*n. p.*, 1832.]

[EXTR. du Bull. de l'Acad. roy. de méd. de . . . tome VIII, No. 6.]

Fauvel. Sur le choléra.

[BULL. de l'Acad. imp. de méd., Paris, XXXIV, pp. 336–333, 561–564, 1247–1255.]

Favell (C. F.) A treatise on the nature, causes and treatment of spasmodic cholera. 8°. *London*, 1832.

Fawcett (J.) *De cholerae morbo apud incolas Indiae orientalis. 8°. *Edinburgi*, 1822.

ıyolle (J.) *Dissertation sur le choléra-morbus asiatique. 4°. *Paris*, 1835. L.

'echner (G. T.)] Mises. De Cholera verdedigd. Naar het Hoogd. 8°. *Amsterdam*, 1833.

ıichtmann (A.) Ueber Cholera-Asphyctica.

[ZEITSCHR. f. Natur.- u. Heilk. in Ungarn, 1856, VII, pp. 202–203.]

enicia (S.) Dissertazione sul cholera morbus. 2a ed. 8°. *Bari*, 1867. L.

éraud (E.) Le choléra devant l'humanité. 8°. *Marseille*, 1849.

éraud (S.) Idées sur le choléra-morbus. 8°. *Paris*, 1832.

erguson (W.) Letters on cholera morbus; with observations on contagion, quarantine, and disinfection. 8°. *London*, 1832.

errarese (L.) Sul morbo colera asiatico. Riflessioni teoriche e pratiche. 8°. *Napoli*, 1837.

errari (P.) Cenno sul colera.

[GIORN. p. serv. al progr. d. patol., 1836, V, pp. 302–311.]

erro (G.) Riflessioni sul cholera epidemico per servire alla profilassi ed alla cura di questo morbo. *Reggio di Calabria*, 1865.

ielding (G. H.) Cholera.

[LONDON Med. Gaz., 1831, VIII, pp. 816–820.]

iévée de Jeumont. Du choléra asiatique; de ses formes diverses et de son traitement.

[GAZ. méd. de Paris, 1849, IV, pp. 81–84, 100–103.]

ife (G.) Cholera.

[PROVINC. Med. & Surg. Jour., 1843, V, pp. 208–209, 267–268, 466–468, 532; *also, in* MED. Times & Gaz., 1853, VII, n. s., pp. 596–597.]

incham. Cholera.

[MED. Times & Gaz., 1855, X, pp. 270–271.]

inger (J.) Die Cholera epidemica nach Beobachtungen auf der Abtheilung des Dr. Jaksch, im Prager allgemeinen Krankenhause, mit Bemerkungen über Hamernjk's Werk "Cholera epidemica". 8°. *Leipzig*, 1851. L.

inkenstein. Einige Bemerkungen zur Aetiologie und Therapie der Cholera asiatica.

[ALLG. med. Central-Zeitg., Berlin, 1849, XVIII, pp. 601–606.]

—— Bemerkungen über die Cholera bei Kindern.

[ZEITSCHR. f. klin. Med., Breslau, 1852, III, pp. 302–304.]

ischer. Zur Cholerafrage.

[ARZTL. Intell.-Bl., München, 1874, XXI, pp. 49–52.]

Fitzgerald (E. A.) Epidemic cholera. 8°. *London*, 1871. L.

Flamm. Cholera und Vergiftung.

[WIEN. med. Wochenschr., 1855, pp. 623–624, et seq.; *also*, reprint in 4°, Wien, 1856.]

Flandin (C.) *Propositions et questions sur le choléra-morbus épidémique. 4°. *Paris*, 1832. L.

Flechner (A. E.) Diss. med.-pract. de cholera. 8°. *Vindobona*, 1831.

Fleischer (T.) Die Cholera. Ihr eigentliches Wesen, ihre Kennzeichen und die Schutzmittel gegen dieselbe. 8°. *Leipzig*, 1848. L.

—— Die Cholera. Neueste Erfahrungen über das Wesen derselben und ihre zuverlässige Heilung. 2te Aufl. 8°. *Leipzig*, 1850. L.

Fletcher (W. B.) Cholera: its characteristics, history, treatment, geographical distribution of different epidemics, suitable sanitary preventions, etc. 8°. *Cincinnati*, 1866. L.

—— The history of epidemic cholera: its causes, diagnosis, pathology, treatment, and the sanitary measures which may modify the severity of the disease.

[CINC. Jour. of Med., 1866, I, pp. 89–95, 135–151.]

Flygare (L. J.) *Cholerae asiaticae brevis expositio, cujus part. II. 4°. *Lundae*, 1838. L.

Fodéré. Recherches historiques et critiques sur la nature, les causes et le traitement du choléra-morbus. 8°. *Paris*, 1831.

—— Sur le choléra.

[L'ABEILLE méd., 1865, XXII, pp. 329–330.]

Förster. Zur Cholera-Epidemie.

[BERLIN. klin. Wochenschr., 1871, VIII, pp. 446–447.]

Foing (L. A.) *Étude sur le choléra. 4°. *Paris*, 1866. L.

Foissac (P.) Les trois fléaux: le choléra épidémique, la fièvre jaune et la peste. 8°. *Paris*, 1865. L.

Foley (A. E.) *Étude à propos du choléra-morbus. 4°. *Paris*, 1855. L.

—— Deux mots sur le choléra et les premiers soins qu'il reclame. 8°. *Paris* [1866].

Foote (G. H.) Quaedam de cholera indica complecteus; quam annuente summo numine. 8°. *Edinburgi*, 1825. L.

Fornasini (L.) Del cholera e de suoi rimedj.

[OMODEI, Ann. un. di med., 1865, CXCIV, pp. 519–520.]

Fornasini (L.)—continued.

——— Sulla maggiore o minore intensità del cholera. *Brescia-Verona*, 1867.

Forry (S.) Remarks on epidemic cholera, inebriety, etc.

[Am. Jour. Med. Sci., 1842, III, n. s., pp. 307-324.]

Foscarini (G.) Sul cholera morbus. *Padova*, 1868.

Foubert (M.) Choléra-morbus et autres maladies; remèdes indiqués. 8°. *Paris*, 1831.

Fougnot (F.) * Dissertation sur le choléra-morbus épidémique. 4°. *Paris*, 1832. L.

Fourcault. Du choléra épidémique.

[Gaz. méd. de Paris, 1849, pp. 7-10, 157-161, 338-340, 357-360.]

——— The same. 8°. [*n. d.*] L.

Fournié (E.) Nature et traitement du choléra.

[L'Union méd., Paris, 1865, XXVIII, 2e s., pp. 136-138.]

——— Consultation médicale sur le choléra. 8°. *Paris*, 1866. L.

——— Sur le choléra.

[Gaz. des hôp., 1873, pp. 876, 885.]

Fourrier (E. A.) * Du choléra épidémique. 4°. *Paris*, 1855. L.

Foville (A.) *et* **Parchappe** (M.) De la nature, du siége et du traitement du choléra-morbus. 8°. *Rouen*, 1832. L.

Fox (E. L.) On cholera.

[London Med. Gaz., 1831, VIII, pp. 556-557.]

Foy. Choléra-morbus. Premiers secours à donner aux cholériques avant l'arrivée du médecin, précédés d'une indication précise des signes de la maladie et suivis d'un exposé simple et rapide des moyens hygiéniques et prophylactiques qui peuvent empêcher son invasion. 18°. *Paris*, 1849. L.

Fraisse (C.) *et* **François** (F.) Répertoire complet et analyse des diverses méthodes de traitement appliquées au choléra-morbus en France et dans les pays étrangers; avec une description des symptômes, de la marche, des diverses formes de la maladie et des lésions cadavériques qu'elle laisse après elle. 8°. *Paris*, 1832. L.

Frampolesi (A.) Monografia sul cholera-morbus. 8°. *Forlì*, 1873. L.

Francis (C. R.) Cholera.

[Med. Times & Gaz., Lond., 1868, I, pp. 157-159.—Ind. Med. Gaz., Calcutta, 1868, III, p. 182, 1 tab.]

François (F.) * Du choléra-morbus épidémique. 4°. *Paris*, 1832. L.

Franklyn (H. B.) Study of the epidemic cholera and the army medical department.

[Lancet, 1863, II, pp. 201-202, 224.]

Franque (J. B. von). Beobachtungen über die europäische und asiatische Cholera.

[Med. Jahrb. f. Nassau, 1853, pp. 313-[illegible]

Franz (C.) Beobachtungen über die Cholera und ihre Behandlung.

[Memorabilien, Heilbronn, 1874, XIX, p. [illegible]

Freeman (E.) Cholera asiatica. The cholera atmosphere: pathology, symptoms, and treatment of the disease.

[Amer. Eclectic Med. Review, N. Y., 1866, I, pp. 1-13.]

Fremaux. La vérité sur le choléra-morbus et sur sa présence dans les localités où il n'était autrefois ni contagieux ni épidémique. Documents inédits. *Paris*, 1860.

——— Recherches pratiques sur la mortalité prématurée, sous le rapport hygiénique, ou la vérité sur les causes et les désastres du choléra-morbus épidémique et autres maladies en ce qu'il peut y avoir de factice et d'exagéré. Ouvrage orné de planches coloriées en représentant les principaux types. 2 v. [illegible] 1864.

——— Du choléra épidémique. [illegible] *Cloud* [1867].

French (J. C.) The cholera.

[Lancet, 1842, II, pp. 788-789.]

——— Observations on cholera.

[London Med. Gaz., 1846, XXXVIII, p. [illegible]

——— The nature of cholera investigated with a supplement chapter on treatment, addressed to junior practitioners. 2d ed. 8°. *London*, 1854.

Freuler (C.) Ueber die Geschichte, Vorzeichen und Heilart der orientalischen Cholera: eine leicht fassliche Abhandlung aus den besten und neuesten Schriften der russischen, polischen, englischen und österreichischen Aerzte gesammelt von einem Nichtaerzte. 8°. *Schaffhausen*, [illegible]

Frey. Ueber Cholera.

[Arch. f. physiol. Heilk., Stuttgart, 1853, XII, pp. 153-155.]

Friedmann. Zur Cholera-Frage.

[Deutsche Klinik, 1855, VII, pp. 337-[illegible]

Frison (V.) Du choléra épidémique.

[Algér. méd., 1873, I, pp. 98-101.]

Froben (E. F.) Cholera. Ueber Fuselstoffe. 8°. *St. Petersburg*, [illegible]

oriep (L. F. von). Die Cholera und die ebensversicherungs-Gesellschaften.
Notizen aus d. Gebiete d. Natur.- u. Heilk., 1832, xxxv, pp. 153–157.]

oriep (R.) Symptome der asiatischen Cholera. 2te Aufl. 4°. *Weimar*, 1832.

rst. Cholera und Rinderpest vor den Schranken der Humanität.
Ärztl. Intell.-Bl., München, 1867, xiv, pp. 438–440.]

ller (H. W.) Cholera and choleraic diarrhœa.
Med. Times & Gaz., 1853, vii, n. s., pp. 344–346.]

rlonge (J.) Some important facts regarding cholera.
Lancet, 1854, i, n. s., p. 69.]

rlonge (W.) On cholera.
Med. Circular, 1855, vii, p. 206.]

ibb (J.) Cholera.
Med. Times & Gaz., 1866, ii, p. 188.]

rdner (A. K.) Facts and opinions respecting Asiatic cholera.
N. Y. Jour. of Med., 1850, v, n. s., pp. 212–216.]

rdner (J.) Cholera.
Brit. Med. Jour., 1865, ii, pp. 282–284.]

rnier (L. N.) Petit traité pratique du choléra-morbus asiatique, ou résumé de l'expérience dans les épidémies de 1832 et 1854. 12°. *Vitry*, 1861. L.

rnot (P.) * Essai sur le choléra-morbus. 4°. *Paris*, 1822. L.

son (J.) Cholera; its nature and treatment.
Lancet, 1865, ii, pp. 697–698.]

sztowtt (M.) Choléra-morbus asiatique. 8°. *Nevers*, 1849.

yley (J. F.) On cholera asphyxia.
Am. Jour. of Med. Sci., Phila., 1850, xx, n. s., pp. 83–89.]

zagnaire (P. J.) Instruction pratique et populaire sur le choléra-morbus épidémique, son traitement et ses moyens préservatifs. 8°. *Grasse*, 1835.

ary (J. F.) Epidemic cholera; its treatment, prevention, etc. 8°. *San Francisco*, 1866. C. L.

bel (D. A.) Aphorismen über die Brechruhr, nebst Angabe ihrer Heilung, Vorbeugung und sonstigen polizeilichen Maasregeln. 8°. *Liegnitz*, 1831. L.

ndrin. Leçons cliniques sur le choléra.
Gaz. des hôp., 1849, pp. 152–153, 156–157, 160–161; 1853, pp. 587–589, 591–593, 595–596, 599–600.]

ndrin (A. N.) Documents sur le choléra-morbus épidémique. 8°. *Paris*, 1832. L.

Gendron. Mémoire sur le choléra-morbus.
[Jour. des connaiss. méd., 1834–35, ii, pp. 130–141.]

Gérard. Lettre . . . . sur les causes, le mode de propagation et le traitement du choléra-morbus épidémique.
[Trans. méd., Jour. de méd. prat., Paris, 1832, viii, pp. 312–333; *also*, reprint in 8°, Paris, 1832.]

——— Note sur le choléra asiatique.
[Bull. gén. de thérap., méd. et chirurg., 1865, lxix, p. 416.]

Gérard (A.) Lettre sur le choléra asiatique.
[Revue méd., Paris, 1850, ii, pp. 536–545.]

Gescheidt (A.) Beiträge zur Pathologie und Therapie der epidemischen Cholera, nach eigenen Beobachtungen und Untersuchungen geliefert. 8°. *Dresden*, 1832.

Gianelli (G. L.) Sul cholera-morbus nuovamente comparso in Europa. Studj e considerazioni.
[Omodei, Ann. un. di med., 1849, cxxix, pp. 53–131, 345–399.]

——— The same. 8°. *Milano*, 1849. L.

——— Reminiscenze di fatti e di principj medico-politici sul cholera-morbus.
[Gaz. med. it. prov. Venete, 1858, i, pp. 61–63, 69–71, 77–80, 85–90, 129–132, 137–138, 145–147, 153–158, 165–168, 173–175, 181–184, 189–192; *also*, reprint in 8°, Padova, 1858.]

Gibbs (H. L.) Observations on cholera.
[Edinb. Med. & Surg. Jour., 1831, xxxvi, pp. 395–398.]

Gietl (F. X. v.) Die Ergebnisse meiner Beobachtungen über die Cholera vom Jahre 1831–74 in ätiologischer und praktischer Beziehung.
[Allg. Zeitschr. f. Epidem., Erlangen, 1874, i, pp. 388–400; *also*, reprint in 8°, München, 1874.]

Gigault D'Olincourt (F.) Choléra-morbus [25 avril 1832]. 8°. *Bar-le-Duc* [*n. d.*]

Gigot (L.) Instruction sur le choléra-morbus. 18°. *Paris*, 1854.

Giordano (S.) Zolfo e cholera. Consid. pres. R. accad. med. di Torino. *Torino*, 1867.

Giordano (V.) Il cholera in rapporto all'igiene e dalla medicina. 8°. *Salerno*, 1873.

Giradeau de St. Gervais. Choléra-morbus. 8°. *Paris*, 1831.

Girard. Sur le choléra.
[Bull. de l'Acad. nat. de méd., Paris, 1848–49, xiv, pp. 968–972.]

Giraud (A.) Précis historique et guérison du choléra épidémique. 18°. *Paris*, 1855.
[3e éd., 8°, Marseille, 1857; *also*, ed. in 1858.]

Giraud (J.) * Essai sur le choléra-morbus, ou cholerrhagie. 4°. *Paris*, 1822. L.

Girette (J.) La civilisation et le choléra. 8°. *Paris*, 1867.

Girou (P. A.) Étude sur le choléra épidémique. 4°. *Paris*, 1855. L.

Glanau. Le choléra vaincu, ses causes, sa marche, ses symptômes, son traitement; suivis du moyen de s'en préserver, et d'un examen sur l'efficacité du tonisudogène. 8°. *Paris*, 1849.

Glatter. Die Choleragefahr.
[Wien. med. Presse, 1872, xiii, pp. 560–561, 608–609.]

Godefroe (M. J.) Iets over het Standpunt der Cholerakennis in 1873.
[Nederland. Tijdschr. voor Geneesk., 1874, x, 2. Afdeel., pp. 123–127.]

Göppert. Radius Mittheilungen über die asiatische Cholera. *Leipzig*, 1831.

Görz. Die Cholera.
[Zeitschr. d. deutsch. chir. Ver. f. Med., Chir. u. Geburtsh., 1849, iii, pp. 519–530.]

Gonsalez (J.) Du choléra, des causes qui le produisent et du traitement à suivre pour combattre ce fléau. 4°. *Perpignan* [1855].

Good (J. M.) Die ostindische Cholera, aus dem Englischen übersetzt und mit einigen Zusätzen versehen von F. G. Gmelin. 8°. *Tübingen*, 1831. L.
[2d ed., 1832.]

Goodeve (E.) Epidemic cholera.
[Reynold's Syst. of Med., 1866, i, pp. 126–128.]

Gordon (T. W.) Cholera, its causes and treatment.
[Ohio Med. & Surg. Jour., 1853–54, vi, pp. 373–382.]

Goss. Remarks on the malignant or blue cholera, arising from the progress of that disease, and anticipatory of its reaching the metropolis of Ireland. 8°. *Dublin*, 1832. L.

Goss (J.) Practical remarks on the disease called cholera, which now exists on the continent of Europe. 8°. *London*, 1831. L.

Gosse. Diss. sul cholera morbus. [*Milan*, 1835.]

Gosse (L. A.) Dr. Gosse über die Natur und Heilung der sporadischen und epidemischen Cholera. Nach dem Französischen bearbeitet von Dr. A. Clemens. 8°. *Frankfurt a. M.*, 1831. L.

Gosse (W.) Asiatic cholera.
[Lancet, 1840–41, i, pp. 500–501.]

Goupil. Note sur le choléra-morbus observée à un Français habitant la Russie
[Revue méd., Paris, 1831, ii, pp. 3[illegible]–4.]

——— Sur le choléra-morbus.
[Gaz. d. hôp., 1831, iv, pp. 224–225.]

Goupil (A.) Mémoire déposé à l'Académie de France [Académie des sciences] Choléra, propositions physiologiques. 4°. *Paris*, 1854.

Gouttebessis (J. E.) * Essai sur le choléra-morbus. 4°. *Paris*, 1817.

Gouyon. Sur la nature et le traitement du choléra.
[L'Abeille méd., 1859, xvi, p. 39[illegible]]

Gower (J.) Eight weeks of cholera practice.
[Lancet, 1850, i, pp. 117, 143–144.]

Graff. Die asiatische Cholera.
[Heidelb. klin. Ann., 1831, vii, pp. [illegible]]

Graffunder (R. G. I. I.) * De cholera orientali epidemica. 12°. *Halae*, 1831.

Graham (S.) A lecture on epidemic diseases generally, and particularly on spasmodic cholera. 8°. London, 1833.

Granet de Gandolphe. Qu'est-ce que le choléra? Réflexions et conseils. *Espinard*, 1854.

[Granie (J.)] Choléra épidémique: pêchons de mourir. 8°. *Foix* [1854].

Granville (A. B.) A catechism of cholera, or plain and simple rules, respecting the nature, treatment, and prevention of cholera. 16°. *Baltimore*, 1832.

——— Nature, treatment, and prevention of cholera. 24°. *London*, 1832.

Gratiot (L. A.) * Propositions sur le choléra-morbus épidémique suivies de quelques remarques sur la pratique des couchemens et divers points de la physiologie. 4°. *Paris*, 1832.

Gravier. Documens sur le choléra-morbus de l'Inde.
[Ann. de la méd. phys., xi, pp. 257–[illegible]]

Greenhow (T. M.) On cholera.
[Brit. Med. Jour., 1866, ii, pp. 305–307.]

Greenwood (H.) On the natural treatment of cholera in the collapse state.
[Med. Times & Gaz., 1865, i, p. 5[illegible]]

Gregory. Asiatic cholera.
[St. Louis Med. & Surg. Jour., [illegible] 417.]

Greiner (A. M. A.) *De cholera morbo. 8°. *Berolini*, 1823. L.

Gremilly (L. F. A.) De la frayeur cholérique, ou caractère physiologique du choléra, et traitement positif de cette maladie. 8°. *Paris*, 1832. L.

Grenier (M.) Choléra-morbus, asphyxique.
[JOUR. univ. et hebd. de méd. et de chirurg. prat., 1832, VII, pp. 217-221.]

Greve (H. E.) * Einiges über die Aetiologie und die Behandlung der Cholera. 4°. *Kiel*, 1871. L.

Greville (C. C.) The cholera.
[PROVINC. Med. & Surg. Jour., 1848, p. 560.]

Griesinger (W.) Infectious-Krankheiten.
[HANDB. d. spec. Pathol. u. Therap. von Virchow, 2. Bd., 2. Abth., 1857.]

——— Traité des maladies infectieuses: choléra. 8°. *Paris*, 1868. L.

Griffin (G.) Observations on cholera.
[BRIT.-AMER. Jour. of Med. & Phys. Sci., 1848, IV, pp. 266-270, 292-296.]

Griffin (W.) Recollections of cholera; its nature and treatment.
[LONDON Med. Gaz., 1837, XXI, pp. 572-575, etc.; 1837-38, XXII, n. s., pp. 113-118, etc.]

Grimaud de Caux (G.) Du choléra, du moyen de s'en préserver et de son traitement spécifique. 8°. *Paris*, 1866.

Gritzner (R. A.) *De cholera orientali. *Griefswalde*, 1849.

Groh (C. F.) Einige Worte über die gastrischnervöse Epidemie des 19. Jahrh., vulgo Cholera morbus, [etc.] 8°. *Freiberg*, 1831.

Gros (G.) De cholera epidemica epistola. 8°. *Heidelbergae*, 1850. L.

Guastalla. Osservazioni medico-pratiche sul cholera asiatico. *Trieste*, 1849.

Guérin (J.) Examen de la doctrine physiologique, appliqué à l'étude et au traitement du choléra-morbus, suivie de l'histoire de la maladie de M. Casimir Périer. 8°. *Paris*, 1832. L.

——— Discussion sur le choléra.
[BULL. de l'Acad. de méd., Paris, 1874, XXXVIII, pp. 321-340.]

Guérin de Mamers. De la nature, du siége et du traitement du choléra-morbus miasmatique [asiatique].
[BULL. gén. de thérap., méd. et chirurg., 1832, II, pp. 295-303.]

Guggemos (F.) *Cholera-morbus. 8°. *Monachii*, 1837. C.

Guilloux (M.) *Du choléra-morbus. 4°. *Paris*, 1835. L.

Gulli (G.) Osservazioni sul cholera asiatico-europeo. 8°. *Palermo*, 1837.

Habenicht (A.) *De cholera. 8°. *Berolini*, 1849. L.

Hagen (T. A. von). Ueber die Cholera, ihre Heilung und ihre Vorbeugung, nebst beigefügten Arzneivorschriften. 8°. *Heidelberg*, 1832. L.

Hagerschweiler (J.) Ueber die charakteristische Cur und Verhütung der asiatischen Brechruhr. *Zürich*, 1831.

Hahnemann (C. F. S.) Sendschreiben über die Heilung der Cholera und die Sicherung vor Ansteckung am Krankenbette. Nebst einem erläuternden Nachtrage des Verfassers und bestätigenden Mittheilungen des Herausgebers. 8°. *Berlin*, 1831.

——— Diss. sur le choléra-morbus . . . à C. S. Des Guidi. 8°. *Lyon*, 1831.

Haines (J.) Epidemic cholera.
[IOWA Med. Jour., 1854, I, pp. 163-167.]

Haire. Doctrine rationelle du choléra asiatique: prophylaxie et traitement de ce terrible fléau. 8°. *Paris*, 1873.

Halford (H.) Cholera morbus. 8°. *London*, 1831. L.

Hall (A. R.) Thoughts about cholera.
[INDIAN Ann. of Med. Sc., 1870, XXVI, pp. 1-24.]

Hall (W.) On cholera.
[PROVINC. Med. & Surg. Jour., 1849, pp. 625-627.]

——— On cholera, its nature and treatment.
[MED. Times, 1849, XX, pp. 501-502.]

Hamel (J.) *De l'indoloiosie (choléra épidémique). 4°. *Paris*, 1849. L.

Hamernik (J.) Die Cholera epidemica. Mit besonderer Berücksichtigung der allgemeinen pathologischen und allgemeinen therapeutischen Beziehungen bearbeitet. Cholera-Rapport an das hohe Ministerium des Innern und des öffentlichen Unterrichtes. 8°. *Prag*, 1850. L.

Hamilton (W.) Observations on the nature, causes, and treatment of cholera-morbus. 8°. *Edinburgh*, 1832.

Hancock (T.) The laws and progress of the epidemic cholera. 8°. *London*, 1832.

Hanley (W.) On cholera, its nature and treatment.
[NORTH-WEST. Med. & Surg. Jour., 1854, XI, pp. 310-311.]

Hardie (G. K.) Remarks on cholera.
[BRIT. Med. Jour., 1866, II, p. 213.]

Hardwick (A.) Attempt to explain the physiology of the malignant cholera, with deductions indicating its treatment.
[LANCET, 1831-32, I, pp. 918-919.]

Harless. Bruchstück aus einer noch ungedruckten Schrift eines oesterreichischen Arztes über die Ganges-Seuche oder die indische Cholera.
[HEIDELB. klin.-Annalen, 1833, IX, pp. 274-282.]

Harless (C. F.) Die indische Cholera, nach allen ihren Beziehungen, geschichtlich, pathologisch-diagnostisch, therapeutisch und als Gegenstand der Staats- und Sanitäts-Polizei dargestellt. 8°. *Braunschweig*, 1831. L.

Harrison (E.) Observations on cholera.
[LANCET, 1829, II, pp. 257-260.]

Harrison (J. P.) Practical reflections on cholera.
[BALTIMORE Med. & Surg. Jour., 1834, II, pp. 265-296.]

——— Clinical lecture on cholera.
[WEST. Lancet, Cinc., O., 1849, IX, pp. 69-76, 137-142.]

Hartshorne (H.) On the nature and treatment of cholera.
[MED. Examiner, 1855, XI, n. s., pp. 321-324.]

——— Cholera: facts and conclusions as to its nature, prevention, and treatment. 12°. *Philadelphia*, 1866. L.

Harvey (P.) Asiatic cholera: a report on its nature, cause, prevention, and its cure.
[IOWA Med. Jour., 1867-68, V, pp. 52-59.]

Haskins (E. B.) Some remarks on the febrile stage of epidemic cholera; with the suggestion of a new theory of the propagation and spread of cholera.
[WEST. Jour. of Med. & Surg., 1849, I, pp. 379-387.]

Hasper (M.) Die epidemische Cholera, oder die Brechruhr. Ein Vortrag, gehalten in der naturforschenden Gesellschaft zu Leipzig am 14. December 1830. 12°. *Leipzig*, 1831. L.

Hastings (C.) Inquiry on cholera.
[PROVINC. Med. & Surg. Jour., 1849, pp. 522-523.]

Hawkins (F.) On cholera.
[MED. Circul., 1854, V, p. 223.]

Hawthorne (G. S.) The true pathological nature of cholera, and an infallible method of treating it, with an introduction, additions, and emendations; in a series of letters. 8°. *London*, 1848.

——— The same. From 2d Lond. ed. *New York*, 1849. L.

Haynau (L., *baron de*). Le c[illegible] morbus, cause de cette maladie [illegible] de se préserver, de se guérir . . . [illegible] l'extirper des états de l'Europe. *Paris*, 1831.

Hayne (A. P.) Remarks on cholera.
[WEST. Lancet, San Franc., 1873, II, p. [illegible]]

Haynes (R. L.) The pathology and treatment of cholera.
[LANCET, 1849, II, n. s., p. 244.]

Headland (E.) Cholera.
[MED. Times & Gaz., 1854, IX, n. s., pp. [illegible]]

Heard (T. J.) Cholera.
[SOUTH. Jour. of Med. Sci., N. O., La., [illegible] 651-655; *also*, in GALVESTON Med. Jour. I, pp. 323-333.]

Heath (G. Y.) Plague and cholera: [illegible] lectures on some of the epidemic diseases of Europe, etc. *London*, 1855.

Hebert (L.) Quelques considérations [illegible] le traitement et la nature du choléra.
[GAZ. hebd. de méd. et de chirurg., Paris, [illegible] s., III, pp. 119-122.]

Hébert *et* **Burggraeve.** [Deux [illegible] sur le choléra.
[RÉPERT. de méd. docimétr., 1873-74, I, pp. [illegible] 530.]

Heger (A.) Zur Klinik der [illegible] morgenländischen Krankheit, [illegible] tische Resultate gezogen aus den [illegible] rungen der besten, zumahl deutsch[illegible] Aerzte, und mit den Ergebnissen [illegible] rer, nach den Choleragegenden [illegible] nommenen Reisen zusammengest[illegible] sowie die Nosologie und Therapie [illegible] schiedener Formen des gastrisch[illegible] schen Fiebers, als häufigsten Vor[illegible] Nachkrankheiten der Cholera. *Darmstadt*, 1832.

Heidler (C. J.) Die epidemische Cho[illegible] ein neuer Versuch über ihre [illegible] Natur und Behandlung, ihre Schut[illegible] und die Furcht vor derselben. [illegible] *zig*, 1848.

——— Versuch einer neuen empir[illegible] Begründung der Cholera-wissen[illegible] Als Beilage zu der Abhandlung Schutzmittel gegen die Cholera [illegible] Rücksicht auf ein ursächliches Lab[illegible] sorium und dessen nicht-contagiö[illegible] tur." 8°. *Prag*, 1854.

Heinecken (J.) Bemerkungen [illegible] asiatische Cholera. 8°. *Bremen*.

Heinrich (J.) Beitrag zur Kenntn[illegible] Cholera.
[WIEN. med. Presse, 1872, XIII, pp. 1154-[illegible]]

lo (J. M.) Quelques considérations ir le choléra-morbus. 8°. *Brest*, 1833.

npel (C.) Den epidemiske Cholera.
[GERSK. for Laeger, 1848, IX, pp. 1, 33, 65, 81, 97.]

ming (G.) *De cholera sporadica spectu habito cholera asiatico. 8°. *alis Saxonum*, 1846. L.

ariques (A.) The probable cause, nature, and mode of treatment of the prevailing disease termed cholera morbus. 8°. *London*, 1832.

— Etiological, pathological and therapeutical reflexions on Asiatic cholera as observed in Europe, Asia Minor and Egypt. 8°. *London*, 1848.

ary (N.) Le choléra-morbus. 8°. *Paris*, 1832.

rberger (F., *sen.*) Ueber die Cholera, und über die Vortrefflichkeit der Lauchmittel überhaupt insbesondere. 2te Aufl. 8°. *Ulm*, 1832.

rmann (A.) Zur Diagnose der Cholera.
WIEN. med. Wochenschr., 1873, XXIII, pp. 1043–1046, 1065–1068, 1086–1088; *also, in* WIEN. med. Presse, 1873, XIV, pp. 1024–1025.]

rmann (R.) Scheikundig Onderzoek van de uitgebraakte en door Stoelgang ontlaste Stoffen, het Bloed, de Urin en Gal der Cholera-Lijders, met toepasselijke Aanmerkingen, vooral over den eigenlijken Aard dezer Ziekte, onder den Titel van: Over de Veranderingen die de Zaftwerpselen des menschelijken Organismus door de Cholera ondergaan. 8°. *Arnhem*, 1831. L.

rrick (W. B.) Cholera, its cause, pathology and treatment.
WEST. Lancet, Cinc., 1849, X, pp. 111–122; *also, in* NORTHWEST. Med. & Surg. Jour., 1849–50, VI, pp. 181–196.]

rtzka (K.) Zur Pathologie und Therapie der Cholera.
WIEN. med. Presse, 1871, XII, pp. 953–956, 979–981.]

rzog (J. P.) *Cholera. 8°. *München*, 1837. L.

ulhard d'Arcy. Quelques considérations sur le choléra.
L'ABEILLE méd., 1867, XXIV, pp. 265–268, 273–275.]

yfelder. Ueber das gleichzeitige Vorkommen der Cholera mit andern epidemischen Krankheiten.
MED. Correspbl. des württembg. ärztl. Vereins, 1836, III, pp. 402–403.]

jmans (H. S.) Opmerkingen ter Gerustelling tegen de Vrees voor den thans heerschenden Braakloop. 8°. *Rotterdam*, 1832.

Hildenbrand (F., *Edler von*). Ueber das gleichzeitige Erkranken der Thiere und Pflanzen zur Zeit herrschender Epidemien, besonders der epidemischen Cholera.
[MED. Jahrb. d. k. k. oesterr. Staates, 1838, XVII, n. F., pp. 439–448, 606–607; 1839, XVIII, n. F., pp. 83–96, 237–246, 436–444, 590–600.]

Himmelreich (T.) De cholera epidemica. 16°. *Berolini*, 1855. L.

Hinze. Cholera.
[JOUR. d. prakt. Heilk., 1832, LXXV, pp. 121–123.]

Hirsch (R.) *Du choléra. 4°. *Paris*, 1837. L.

Hiraiger. Choléra; notices historiques sur la cause du choléra; observations sur les symptômes de cette maladie; moyens de le guérir et de s'en préserver. 8°. *Paris*, 1868.

Hocke (L.) *De cholera epid. stadio congestivo et typhoso cum adnexa historia synoptica. 8°. *Pragae*, 1839. L.

Hodge (H. L.) On the pathology and therapeutics of cholera maligna.
[AM. Jour. of Med. Sci., 1833, XII, pp. 386–432.]

——— The same. 8°. *Philadelphia*, 1833. L.

Hoeglauer (J. G.) Kurze Winke und Andeutungen zur nähern Ergründung der Natur und Behandlung der orientalischen Cholera. 8°. *Regensburg*, 1831.

Hoffmann (A.) De Cholera en hare Genezing. Uit het Fransch door een Geneeskundige. 8°. *Gravenhage* [*n. d.*]

——— Dernier coup porté au choléra. 8°. *Paris*, 1866.

Hoffmann (J. F.) Ansichten und Bemerkungen über die Brechruhr und deren Behandlung. 8°. *Stuttgart*, 1831. L.

Hoffmann (K. F.) Vollrath, die morgenländische Brechruhr nach ihrem Zuge und ihrer Verbreitung dargestellt. fol. *Stuttgart*, 1832.

Hofmann (J. A.) Unterricht für Cholera-Krankenwärter. 8°. *Leipzig*, 1832.

Hogman (J. P.) Cholera morbus, dest rätta Kännetecken och Behandling. 8°. *Helsingbourg*, 1831.

Hohnbaum. Cholera.
[MED. Conversbl., 1831, pp. 238–240.]

Holt (M.) Remarks on cholera.
[BOSTON Med. & Surg. Jour., 1832, VI, pp. 59–64.]

Holbrook (J.) Nature and treatment of malignant cholera.
[LONDON Med. Gaz., 1832, IX, pp. 499–502.]

Holger (P. A.) Chemische Beiträge zur Erkenntniss der Natur der Cholera, mit Berücksichtigung der Hermann'schen Versuche. 8°. *Wien*, 1832.

Holländer (J.) Ueber die Pflege der Cholera-Kranken.
[ALLG. wien. med. Zeitg., 1874, XIX, p. 405.]

Holland (G. C.) An inquiry into the nature and treatment of cholera. v. 2. *London*, 1838.

Honigberger (J. M.) Cholera, its cause and infallible cure, [etc.] *Calcutta*, 1861.

——— Die Cholera, deren Ursache und unfehlbare Heilung und die Epidemien im Allgemeinen. Dritte Broschüre. Eine Uebersetzung aus dem Englischen, mit einem Zusatze von neueren Erfahrungen. 8°. *Wien*, 1865. L.

Hood (S.) * Dissertation sur le woba, ou cholera indica. 4°. *Paris*, 1821. L.

——— On the nosology and diagnosis of spasmodic cholera; or diarrhœa cephalica.
[LONDON Med. & Surg. Jour., 1832, I, pp. 347–351.]

Hoop (A. van der, *jr.*) De Cholera Graf en Boeteklanken. 8°. *Amsterdam*, 1832.

Hope (T.) Letter on the prevention and cure of cholera morbus.
[DOCTOR, 1833, I, pp. 84–85.]

Hopkinson (J. P.) Remarks on the pathology and treatment of the disease termed malignant cholera.
[AM. Jour. of the Med. Sci., 1832, X, pp. 533–544.]

Horaninoff (P.) Beitrag zur Geschichte und Behandlung der epidemischen Cholera. 8°. *St. Petersburg*, 1832.

Horn (E.) *et* **Wagner** (G.) Instruction sur le choléra-morbus, contenant les moyens de s'en préserver, d'en guérir et d'empêcher sa propagation, traduite et augmentée par M. L. Paris. 8°. *Paris*, 1831. L.

Horsley (W.) On the nature, origin, frequency and fatality of gastro-enteric affection, yclepd Asiatic, Indian, malignant or spasmodic "cholera".
[LONDON Med. & Surg. Jour., 1832, I, pp. 270–272.]

Hosper (M.) Die epidemische Cholera, etc. *Leipzig*, 1831.

Houston (M. M.) Cholera.
[RICHMOND & Louisv. Med. Jour., 1866, I, pp. 91–121.]

Hovasse. Notice sur le choléra morbus. 8°. *Nancy*, 1831.

Howison (W.) Addenda to remarks on the malignant cholera.
[LANCET, 1833, I, pp. 827–828.]

Huber (S.) De evangelische Bediening onder der Verschrikkingen der Cholera, verheerlijkt; gedurende de Cholera, in Augustus, 1830. Eene Handleiding voor Allen, en bepaaldelijk voor Predikanten en Huisvaders, die wenschen om de Cholera, en de beste Handelwijs vóór, bij en in deze Ziekte te leeren kennen; medegedeeld door G. H. van Senden. 8°. *Groningen*, 1831. L.

Huberwald (H.) Diarrhöe und Cholera. 8°. *München*, 1869. L.

Hufeland (C. W.) Fernere Bemerkungen und Nachrichten über die Cholera orientalis.
[JOUR. d. pract. Heilk., 1830, LXXI, pp. 112–115.]

——— Das Schwitzfieber und die orientalische Cholera.
[JOUR. d. pract. Heilk., 1832, LXXV, pp. 118–119.]

——— Schlussresultat: Die Cholera, eine neue, ausländische, aus Asien nach Europa verpflanzte, bedingt ansteckende, aber nicht sperrbare, Krankheit, ihr Keim immer derselbe, ihre Ursache immer Uebertragung, aber nicht bloss persönliche.
[JOUR. d. prakt. Heilk., 1832, LXXIV, pp. 3–10.]

——— Ueber die Verschiedenheit der Erkrankungs- und Mortalitätsverhältnisse bei der orientalischen Cholera, und ihre Ursachen.
[JOUR. d. prakt. Heilk., 1832, LXXV, pp. 66–85.]

Hunt (J. W.) Letter on malignant cholera.
[N. O. Med & Surg. Jour., 1849–50, VI, pp. 821–822.]

Hunt (T.) Inquiry on cholera.
[PROVINC. Med. Jour., 1849, pp. 688–689; 1850 pp. 14–15, 98–101, 155–158, 211–213, 261–269, 435–439.]

Hurt (G.) Epidemic cholera: its causes, pathology, &c., and the best means for its prevention and cure; being a synopsis of cholera literature, embracing in a condensed form the views of the most eminent and scientific authors of Europe and America, with a glossary explaining all technical terms, and adapting it for the non-professional reader. 8°. *St. Louis*, 1867. L.

Hutchison (J. C.) On cholera.
[AMER. Med. Monthly, N. Y., 1855, III, pp. 371–374.]

Ingalls (W.) Spasmodic cholera.
[BOSTON Med. & Surg. Jour., 1849, XXXIX, pp. 78–83.]

amail. Observations sur les cholériques.
[Bull. Acad. roy. de méd., Paris, 1847-48, xiii, pp. 646-653.]

abin (É.) * Dissertation sur le choléra-morbus. 4°. *Paris*, 1831. L.

accoud (S.) Asiatic cholera.
[Richmond & Louisv. Med. Jour., 1873, xvi, pp. 207-215.]

acquement (V.) Lettre sur le choléra; suivie de réflexions.
[Répert. de méd. dosimétr., 1872-73, i, pp. 540-544.]

acquemoud. Le choléra: préservation, traitement, causes. Choléra des Alpes. 8°. *Moutiers*, 1867. L.

acquez (P.) Histoire du choléra, de ses causes, des moyens propres à préserver de cette maladie. 8°. *Vesoul*, 1849.

Jacquin.] Notice sur le choléra-morbus. 8°. *Valence*, 1832.

aenichen (D.) Quelques réflexions sur le choléra-morbus. 8°. *Moscou*, 1831.

—— Sendschreiben des Herrn Dr. Jähnichen in Moskau an den Herausgeber [on cholera].
[Litterar. Ann. d. ges. Heilk., Berlin, 1832, xxiii, pp. 155-165.]

ahn. Andeutungen über die Natur der Cholera.
[Med. Conversatbl., 1831, pp. 393-400, 401-406.]

ameson (H. G.) An epitome of the more important circumstances connected with the epidemic cholera.
[Md. Med. Rec., Balto., 1832, iii, pp. 193-229.]

—— A treatise on epidemic cholera. 8°. *Philadelphia*, 1855. L.

ameson (T. R.) Reply to three queries respecting cholera.
[London Med. Gaz., 1833, xii, p. 614.]

ansen (F.) Anfrage an Naturforscher und Aerzte über die Cholera.
[Magaz. f. d. ges. Heilk., Berlin, 1833, xxxix, pp. 293-296; xl, pp. 387-391.]

anssens (F. X.) Cholerae descriptio in qua ejus definitio, causa proxima et remota, divisio, diagnosis, prognosis, autopsia cadaverum, curatio et regimen prophylacticum therapeutice exarata occurunt. 8°. *Bredae*, 1833.

eanneret (H.) Epidemic cholera, diarrhœa, and dysentery. *London*, 1857.

encken. The cholera.
[Lancet, 1832, i, pp. 216-217.]

encken (F.) Bemerkungen über die Cholera morbus. 8°. *Hamburg*, 1831.

encken (F. E.) The cholera: its origin, idiosyncracy, and treatment. 12°. *London*, 1867. L.

Jennette (M.) Remarks on the symptoms, treatment, and infectious nature of Asiatic cholera.
[London Med. Gaz., 1848, vii, n. s., pp. 487-493.]

Jensen (J.) Zur Cholerafrage.
[Berlin klin. Wochenschr., 1866, iii, p. 467.]

Jewell (J. S.) Cholera.
[Med. Exam., Chicago, 1873, xiv, pp. 157-160.]

Jocootton (B.) * Essai sur le choléra-morbus épidémique. 4°. *Paris*, 1832. L.

Jörg (E.) Anweisung, die Tropenkrankheiten, die asiatische Cholera, und das gelbe Fieber zu verhüten oder sicher zu heilen. Nebst einem kurzen Anhange über die Behandlung der Ruhr, des Gallen- und Wechselfiebers, der Sommerkrankheit und des Croup, besonders für Reisende und Auswanderer in heisse Gegenden gemeinverständlich abgefasst. 8°. *Leipzig*, 1854. L.

—— Die gänzliche Unterdrückung der asiatischen Cholera den europäischen Staatsregierungen als ausführbar dargethan und eine sichere Heilmethode dieser Seuche Aersten und gebildeten Laien anempfohlen. . . . . Mit einem Vorworte von Dr. J. C. G. Jörg. 8°. *Leipzig*, 1855. L.

Johnson (G.) On epidemic diarrhœa and cholera: their pathology and treatment. 8°. *London*, 1855. L.

—— Notes on the pathology and treatment of cholera.
[Brit. Med. Jour., 1865, ii, pp. 251-252, 465-466, 491-494, 519-521, 543-548; 1866, ii, pp. 150-151, 586.]

—— Notes on cholera: its nature and its treatment. 8°. *London*, 1861. L.

—— The same. 16°. 1866. C. L.

—— Clinical lecture on cholera.
[Brit. Med. Jour., 1866, ii, pp. 515-519.]

—— On epidemic diarrhœa and cholera: their nature and treatment. 12°. *London*, 1866. L.

—— On the pathology and treatment of cholera.
[Med.-Chir. Trans., London, 1867, l, pp. 103-127; *also, in* Lancet, 1867, i, pp. 27-28, 157-158, 254-255, 539.]

—— The same. 8°. *London*, 1867. L.

—— On cholera and choleraic diarrhœa: their nature, cause and treatment [etc.] 8°. *London*, 1870. L.

—— The pathology and treatment of cholera.
[Brit. Med. Jour., 1871, ii, pp. 197-198; *also, in* Med. Times & Gaz., 1872, i, pp. 35-37, 125-127.]

Johnson (J. M.) Cause, symptoms, and treatment of cholera.
[Atlanta Med. & Surg. Jour., 1866, VII, pp. 152–161.]

Jolly (P.) Lettre sur le choléra-morbus. 8°. *Paris*, 1832.

Jones (J.) Remarks on spasmodic cholera.
[London Med. & Phys. Jour., 1833, LXIX, pp. 25–34.]

——— The pathology of cholera, and its treatment with purgatives.
[Lancet, 1854, II, pp. 312–314.]

Jubin (H.) Considérations sur le choléra, 1849–1854. 8°. *Niort* [1854].

Judkins (J. P.) On cholera.
[Ohio Med. & Surg. Jour., 1848–49, I, pp. 233–241.]

Julien (L. C.) Considérations sur le choléra asiatique. 8°. *Besançon*, 1854.

Kaan (H.) *Gedanken eines Arztes über die Cholera als Weltseuche. 12°. *Innsbruck*, 1854. L.

Kaernbach (C.) *De cholera asiatica observationes. 8°. *Berolini*, 1838. L.

Kalisch (M.) Zur Lösung der Ansteckungs- und Heilbarkeitsfrage der Cholera. 8°. *Berlin*, 1831. L.

Kaufmann (W. S.) Ueber die indische Brechruhr in praktisch-therapeutischer Beziehung. 12°. *Hamm*, 1831.

Keim (J. W. A.) Kurze Darstellung der Cholera epidemica, ihres Wesens, ihrer Behandlungsweise und Verbreitung. 8°. *München*, 1838. L.

Keir (J.) On cholera. 8°. *Edinburgh*, 1832.

——— Practical observations on the prevailing epidemic called cholera; with advice to the heads of families and others, as to the precautionary and primary domestic treatment to be used in warding off a threatened attack of, and assisting those already affected by, the epidemic. 8°. *Edinburgh*, 1848. L.

Kennard. Cholera; its history, causes, pathology, and treatment.
[St. Louis Med. & Surg. Jour., 1867, IV, pp. 118–133, 219–233.]

Kennedy (J.) The history of the contagious cholera; with facts explanatory of its origin and laws, and of a rational method of cure. 8°. *London*, 1831. L.

——— The same. 3d ed. 8°.

Kennedy (J. M. S.) A lecture on the nature, causes, and prevention of cholera, delivered at the Ivanhoe Baths' Assembly Rooms, Ashby-de-la-Zouch [etc.] 8°. *Ashby-de-la-Zouch*, 1832.

Kennedy (R. H.) Notes on the epidemic cholera of India.
[London Med. Repository, 1827, V, pp. 489–497; *also*, reprint in 8°. Calcutta, 1827.]

——— The same. 2d ed. 8°. *London*, 1846. L.

Keraudren (P. F.) Du choléra-morbus de l'Inde ou mordéchi. 8°. *Paris*, 1824. L.

——— Mémoire sur le choléra-morbus de l'Inde.
[Jour. univ. et hebd. de méd. et de chir., Paris, 1831, II, pp. 155–167, 253–270.]

——— The same. 8°. *Paris*, 1831. L.

Kerckhoffs [*or* **Kirckhoff** *or* **Kerckhove**] (J. R. L.) Considérations sur la nature et le traitement du choléra-morbus, suivies d'une instruction sur les préceptes hygiéniques contre cette maladie. 8°. *Anvers*, 1833. L.

Kidd (C.) On cholera.
[Med. Circular, London, 1854, IV, pp. 225–227.]

Kiehl (W. F. P.) Aanwijzing om de Cholera-Zieken eene dadelijke en doelmatige Hulp te verleenen. 8°. *Graven-hage*, 1831.

——— Over Legersteden en Daar te stellen ten behoeve van Cholera-Lijders. Ten Vervolge en ter nadere Opheldering van de Aanwijzing om aan de Cholera-Zieken eene dadelijke en doelmatige Hulp te verleenen. 8°. *Gravenhage*, 1831.

——— Proeve eener Aanwijzing om de Cholera te beperken en zoo mogelijk mit te roeijen. 8°. *Gravenhage*, 1831.

——— Ueber den Ursprung und die Verhütung der Seuchen. Erläutert durch das Beispiel der ansteckenden Cholera. 8°. *Berlin*, 1865.

Kirchhove (J. R. L. de). *See* **Kerckhoffs**.

Kirk (J. B.) Practical observations on cholera asphyxia [etc.] With an appendix. 8°. *Greenock*, 1832.

Kirschneck (K.) In der Cholera-Noth. Aerztliche Winke. 8°. *Wien*, 1831.

Klementooski (A.) Zamietki o cholere.
[Moskovskaia med. gaz., 1866, No. 34, pp. 289–292–294.]

Klose (C. L.) Asiatische Brechruhr.
[Med. Zeitg., Berlin, 1838, pp. 61–65.]

Knapp (M. L.) On the cause, nature and prevention of epidemic cholera.
[N. Y. Jour. of Med., 1855, III, pp. 268–278.]

napp (M. L.)—continued.

— The same. 8°. *Cincinnati*, 1855. L.

nolz (J.) Beobachtungen der Wiener Aerzte über die epidemische Brechruhr und ihre Heilart. Aus den vorgelegten Berichten derselben zusammengestellt.

[Med. Jahrb. d. k. k. oesterr. Staates, Wien, 1832, III, n. F., pp. 37–82.]

nott (W.) Cholera morbus of India.

[London Med. Gaz., 1832, IX, pp. 293–295.]

nox. On the present state of our knowledge of cholera.

[Dublin Med. Press, 1847, XVIII, pp. 356–361, et seq., 1848, XIX, pp. 52–57, et seq.]

nox (A.) Inquiry into the actual state of our knowledge of cholera, with practical directions regarding its prevention and treatment. 8°. *Dublin*, 1849.

nchlin (J. R.) Ueber die Cholera oder den Brechdurchfall und die dagegen gerichteten Schutz- und Hilfsmittel. 8°. *Zürich*, 1831. L.

nrtüm (A.) *Von der Cholera, ein Votum über ihre Natur und Behandlung. 8°. *Rostock und Schwerin*, [1849]. C.

nstler (A. L.) Aus der Erfahrung geschöpfte Andeutungen zur Erkenntniss und Behandlung der epidemischen Cholera. 12°. *Wien*, 1831. L.

nziel (J. T.) Das Wesen der Cholera.

[Mittheil. d. aerztl. Vereines in Wien, 1874, III, pp. 130–147.]

nanendonk (P. J. van). Bijdrage over de besmettelijkheid van den aziatischen Braakloop. Uit het Hoogduitsch. 8°. *Delft*, 1832. L.

napff [?] (F. G.) Wesen und rationelle Therapie der Cholera, geschöpft aus Beobachtungen ihres Ausbruches zu Erding. 8°. [*n. p.*,] 1854. L.

natzenstein (C. F. W.) Verlauf und Heilung der asiatischen Cholera, für Aerzte und Wundärzte. 8°. *Helmstädt*, 1831.

nauss (A.) Die Cholera-Epidemie. 8°. *Stuttgart*, 1832.

nauss *und* **Pichler.** Aphorismen zum Studium der Pathologie und Therapie der Cholera.

[Allg. wien med. Zeit., 1866, XI, pp. 328–329.]

nonser (V. N.) Studien über die Cholera und die interessantesten Daten der vorzüglichsten und zweckmässigsten Behandlungs-Methoden nach dem neuesten

Kronser (V. N.)—continued.

Standpunkte der medicinischen Wissenschaft. 8°. *Wien*, 1848. L.

Krüger-Hansen. Zu den Curbildern, mit Bezug auf Cholera. 8°. *Rostock und Güstrow*, 1831. L.

Kubyss (F. M.) Cholera oder Brechruhr. 8°. *Berlin*, 1835.

Küchenmeister (F.) Offener Brief an Herrn G. Gross in Petersburg, Verfasser einer lateinischen "Epistola de Cholera epidemica", nebst einigen Worten über Santonin.

[Zeitschr. f. klin. Med., Breslau, 1851, II, pp. 209–226.]

Küchler (R.) Einige Ansichten über die Entstehung der Cholera asiatica. 8°. *Jena*, 1869. L.

Kühne (C.) *Beiträge zur Erklärung der Symptome im Stadium algidum der asiatischen Cholera. 8°. *Halle* [1873]. L.

Küss (H.) Die Cholera, deren Wesen und Behandlung.

[Deutsche Klinik, 1865, XVII, pp. 324–326, 341–344, 362–363.]

Kumpf (J. G.) Ueber das Wesen der asiatischen Cholera und deren Behandlung.

[Med.-chir. Zeitung, Salzburg, 1831, IV, pp. 31–32.]

Kunkler (E. A.) Malignant cholera.

[Pacif. Med. & Surg. Jour., San Francisco, 1866–67, IX, pp. 59–68, 113–121.]

Kurtz (P. T. E.) Maassregeln der Entstehung, der Verbreitung und der Gefährlichkeit der Cholera vorzubeugen. 2te Aufl. 8°. *Dorpat*, 1865.

Kypke (M.) Die Cholera: deren Behandlung und Verhütung auf diätetischem Wege. 12°. *Leipzig*, 1865. L.

Labat (B. *et* L.) Parallèle du choléra-morbus sporadique et du choléra-morbus asiatique.

[Annal. de la méd. phys., 1833, XXIV, pp. 427–451, 724–776.]

——— The same. 8°. [*n. d.*] L.

Labat (L.) Choléra-morbus asiatique.

[Annal. de la méd. phys., 1831, XX, pp. 267–275.]

——— The same. 8°. *Paris*, 1832. L.

La Boutraye (de). Documents sur le choléra-morbus envoyés à l'intendance sanitaire . . . . de la Gironde. 8°. *Bordeaux*, 1832.

Labouverie (C.) Instructions sur le choléra. 12°. *Charleville*, 1865.

Lac de Bosredon (C. J. B.) * Dissertation sur le choléra-morbus. 4°. *Paris*, 1829. L.

Laker (W. A.) On cholera asiatica.

[MED. Times, 1849, XX, pp. 155–160.]

Lamby (A.) Versuch einer Construction der asiatischen Cholera. 8°. *Osnabrück*, 1831. L.

Landousy. Observation de choléra-morbus indien.

[GAZ. des hôp., 1834, VIII, pp. 169–170.]

Langenhagen (O. de). Le choléra sec.

[GAZ. hebd. de méd. et de chirurg., 1866, III, 2e s., p. 60.]

Langlebert (A.) * Du choléra asiatique. 4°. *Paris*, 1858. L.

Lantairés (J.) Coup-d'œil sur les difficultés qui s'opposent à la découverte des causes procathartiques du choléra-morbus, suivi d'une méthode de traitement relative à l'état actuel de nos connaissances. 8°. *Aix*, 1835.

Laplaigne (A. E. L. de). Du choléra. Simple instruction. 8°. *Bordeaux*, 1854.

Largent (J. C.), **Mansa** (F. V.), *og* **Trier** (S. M.)* Simlinger til Kundskab om Cholera, udgivne. *Kjøbenhavn*, 1831.

Larrey (*Le baron*). Mémoire sur le choléra-morbus. 8°. *Paris et Londres*, 1831. L.

——— The same. Translated by H. Paterson. *Dublin.*

Larrue (P.) * I. Du pronostic du choléra-morbus épidémique. II. [etc.] 4°. *Paris*, 1840. L.

Lassis. Motifs de la proposition de l'auteur, d'aller à ses frais et sous les auspices de l'Académie des sciences, sur l'un des principaux points du théâtre de l'épidémie dite choléra-morbus. Nouveaux résultats avantageux obtenus par l'application des principes de ce médecin à Paris et dans plusieurs départements. 8°. *Paris*, 1832. L.

Latière (J. F.) Notice sur le choléra-morbus. 8°. *Toulon*, 1835.

Latour (A.), **Guyot** (J.), **Pellarin** (C.), *et* **Mignot** (A.) Communications sur le choléra.

[L'UNION méd., Paris, 1865, XXVII, 2e s., pp. 612–622.]

Laveran. Un dernier mot sur la discussion académique relative au choléra.

[GAZ. hebd. de méd. et de chirurg., 1874, XI, 2e s., pp. 161–163.]

Laveran (L.) Cholera.

[DICTIONNAIRE encyclopédique des sc. s., VI, 8°, Paris, 1875, L, pp. 758–767.]

Lawrie (J. A.) Essay on cholera, [illegible] on observations of the disease in various parts of India, and in Sunderland, Newcastle, and Gateshead, with notices of the treatment, and of the civil and hospital police adopted in these towns. Containing in an appendix a history and treatment of cholera at Kirkintilloch, Scotland; with cases. [illegible] *gow*, 1832. L.

Lawson (L. M.) The nature and treatment of cholera, including a brief sketch of the disease, the causes which produce it, mode of propagation, [illegible] ology [etc.]

[WEST. Lancet, Cinc., 1848, VIII, pp. 257–354.]

——— The same. 8°. *Cincinnati*, 1849.

Lawton (A. G.) On the epidemic cholera.

[AMER. Med. Monthly, N. Y., 1853, III, p. 187.]

Laycock (T.) A lecture on pestilential cholera.

[LONDON Med. Gaz., 1849, XLIV, pp. 37–

——— Suggestions as to the investigation and discussion of the nature and treatment of cholera.

[LONDON Med. Gaz., 1849, XLIV, pp. [illegible]

Leaman (E.) Cholera asiatica.

[CLINIC, Cinc., 1874, VII, pp. 305–307, 3[illegible]

Lebert. Vorträge über die Cholera. *Erlangen*, 1854.

Lebert (H.) Cholera.

[ZIEMSSEN'S Handb. d. sp. Path. u. Therapeutik, 1874, II, pp. 336–442.]

[Le Bon (G.)] Nouvelles recherches sur le choléra.

[REVUE de thérap. méd.-chirurg., 1866, 8–9.]

Le Borgne (G.) Quelques réflexions sur le choléra-morbus épidémique.

[JOUR. sect. de méd. Soc. acad. dépt. L. 1834, X, pp. 152–171.]

Leboucher. Nouvel abracadabra sur le choléra et les tables tournantes. [illegible] 8°. *Paris* [*n. d.*]

Lecadre (A.) Communications sur le choléra.

[L'UNION méd., 1865, XXVIII, 2e s., pp. [illegible]

Le Cœur (J.) Précis sommaire sur le choléra-morbus épidémique, ses [illegible] symptômes . . . . suivis de [illegible] conseils aux gens du monde. [illegible] 1832.

[2e éd. same year.]

deboer (A. M.) Brief betreffende de cholera. 8°. *Rotterdam*, 1831.

derer. Ueber epidemische Cholera der Kinder im frühesten Lebensalter.

[OESTERR. Zeitschr. f. pract. Heilk., 1855, I, pp. 273–275.]

disinger (J.) Die Cholera; ihr Ursprung, ihr Wesen, ihre Ursachen, ihr Verlauf, nebst Angabe der ersten Vorkehrungsmittel. 8°. *Stuttgart*, 1849. L.

Mercier (A. P.) * Du choléra épidémique. 4°. *Paris*, 1856. L.

Morvan (A.) Traité sur le choléra indien et sur les moyens aussi simples qu'efficaces de le combattre et d'éteindre en quelques jours l'épidémie la plus intense. 8°. *Paris*, 1867. L.

nci (P.) Riflessioni sulla corrente malattia asiatico-colérica e modo sicuro di preservarsene. 8°. *Livorno*, 1835. L.

one (A.) Memoria patologico-clinica sul cholera morbus.

[GIORN. DEI, Ann. un. di med., 1831, LVIII, pp. 17–31.]

epelletier. Principes généraux sur la nature, le traitement préservatif et curatif du choléra-morbus . . . . ; précédés d'une notice sur l'itinéraire de cette maladie, suivis de l'instruction populaire rédigée, par le comité de salubrité publique de Paris. 12°. *Le Mans*, 1832.

[Also same year.]

equine. Rapport sur diverses communications relatives au choléra épidémique, transmises par le gouvernement.

[BULL. de l'Acad. roy. de méd. de Belg., 1849–50, IX, pp. 382–387.]

roy. Sur le choléra-morbus et la gastro-entérite aiguë.

[ANN. de la méd. physiol., 1824, V, pp. 301–305.]

stocquoy (D.) * Du choléra asiatique. 8°. *Paris*, 1850. L.

upoldt (J. M.) Neues über Entstehung, Natur, Verbreitung und Verhütung der sogenannten asiatischen Cholera, als Entwickelungs-Krankheit des heutigen Menschengeschlechts. 8°. *Erlangen*, 1832. L.

uret (F.) Mémoire sur l'épidémie actuelle désignée sous le nom de choléra-morbus de l'Inde, contenant une analyse de tout ce que les auteurs les plus estimés ont écrit sur les causes de cette maladie. Suivi des dispositions législatives concernant les mesures sanitaires.

[ANN. d'hyg. pub. et de méd. leg., Paris, 1831, VI, pp. 382–440; *also*, reprint in 8°, Paris, 1831.]

Levieux (C.) Aperçu clinique sur le choléra. 8°. *Bordeaux*, 1854. L.

Le Viseur. Aphorismen über die Cholera für angehende Practiker am Krankenbette.

[DEUTSCHE Klinik, 1866, XVIII, pp. 445–447, 455–456.]

Leviseur (C. J.) Praktische Mittheilungen zur Diagnose, Prognose und Cur der epidemischen Cholera, nach eigenen Beobachtungen. 8°. *Bromberg*, 1832.

——— Über die Cholera und die erfolgreichste Kur derselben. 8°. *Posen*, 1867. C.

Levrat (E.) Du choléra considéré au point de vue de l'humanité et des premiers soins à donner aux malades. 8°. *Lyon*, 1849.

Lewis (A.) On the nature, cause, and treatment of cholera.

[LANCET, 1854, II, n. s., pp. 258–259.]

Lichtenstädt. Ein Beitrag zu der Lehre von dem Einflusse der asiatischen Cholera auf die Sterblichkeitsverhältnisse.

[LITTERAR. Ann. d. ges. Heilk., Berlin, 1832, XXII, pp. 350–367.]

Lichtenstein (E.) Die Cholera. Das Wissenswertheste über diese Krankheit, nebst den gebräuchlichsten Heilmitteln dagegen, sowie neue Vorschläge zur Verhütung und Heilung derselben. 8°. *Breslau*, 1853. L.

——— Neuer Beitrag zur Cholera. Aetiologisches und Therapeutisches. 8°. *Berlin*, 1860. L.

——— Die Cholera.

[DEUTSCHE Klinik, 1866, XVIII, pp. 321–323, 329–331, 337–340, 365–366, 373–375, 381–383.]

Lichtenthal. Istruzione sulla coléra pei non-medici, e de'rimedi più efficace da applicarsi contro questa malattia sino all'arrivo del medico. *Milano* [1831].

——— Ragguaglio storico terapeutico del coléra-morbo sino alla meta d'Ottobre 1831, etc. *Milano* [1831].

Lieber (J. A.) Esquisse sur le choléra-morbus. 8°. *Paris*, 1831.

Lieblein. Welche ist die naturgemässe Krise der epidemischen Cholera und welchen Einfluss hat dieselbe auf deren Behandlung?

[MED. Conversbl., 1832, pp. 57–64, 65–67.]

Liégard (A.) La période algide du choléra est-elle curable?

[GAZ. des hôp., 1865, p. 489.]

Lincke (C. G.) Versuch, das Wesen der pandemischen Cholera zu erklären. 8°. *Halle*, 1833. L.

Lindsay (L.) Identity of British and Asiatic cholera.
[MED. Times & Gaz., 1857, XV, pp. 448–450.]

Lindsay (W. L.) Clinical notes on cholera.
[ASSN. Med. Jour., 1854, I, pp. 216–222, etc.; II, pp. 670–676, etc.]

Linley ([*Mrs.*] V.) A few remarks on cholera, its symptoms and best mode of treatment. 8°. *London*, 1848.

Lion. Die Cholera und das Proletariat.
[ALLG. med. Central-Zeitg., 1850, XIX, pp. 49–50.]

Lipien (L.) O cholerie.
[VIENNO. med. jur., St. Petersburg, 1867, part c, book X, pp. 211–214.]

Liscovius (A.) Die Cholera. 8°. *Berlin*, 1867.

Littré. Traité du choléra oriental, rédigé principalement d'après les documens publiées par les médecins allemands, contenant la marche géographique du choléra, ses symptômes, l'anatomie pathologique, l'analyse chimique des liquides, la nature de la maladie, ses divers modes de propagation, l'examen de la valeur des mesures sanitaires, l'exposition des diverses méthodes de traitement, etc. 8°. *Paris*, 1832. L.

Lizars (J.) Substance of the investigations regarding cholera asphyxia. 8°. *Edinburgh*, 1832.

Loder (J. C. von). Ueber die Cholera-Krankheit. Ein Sendschreiben. Zusätze zu seiner Schrift "Ueber die Cholera-Krankheit". 12°. *Königsberg*, 1831. L.

Loisel (A.) * Quelques considérations sur le choléra-morbus asiatique. 4°. *Paris*, 1834. L.

Lolli. Sul cholera. Tentativo di nuova spiegazione di alcuni dei fenomeni più gravi del cholera, appoggiato a osservazioni cliniche e ad alcuni esperimenti, etc. *Trieste*, 1866.

Lombard. Rapport sur une communication de M. Grainger, inspecteur du conseil supérieur de santé de Londres, relative au choléra.
[BULL. de l'Acad. roy. de méd. de Belg., 1854–55, XIV, pp. 98–102.]

Lorinser (C. J.) De Cholera geene besmettelijke Ziekte. Een bemoedigend Volks-Woord. 8°. *Nymegen*, 1831. L.

Lownds (T. M.) A few remarks on cholera.
[EDINBURGH Med. Jour., 1856, I, pp. 830–839.]

Lowther (G.) On the pathology and treatment of cholera.
[LANCET, 1849, II, n. s., pp. 503–505.]

Luppi (G.) Sur le choléra-morbus: causes, sa nature, manière de le conserver et son traitement. 2e éd. *Lyon*, 1854.
[1e éd., 1835.]

Lutz *und* **Tuppert** (F.) Zur Frage.
[AERZTL. Intell.-Bl., 1866, XIII, pp. 3–

Luyten (A.) Over Cholera.
[NEDERLAND. Lancet, 1849–50, 3e s., [illegible] 265–272.]

Luzzati. Lettere Tergestine sul [illegible] *Trieste*, 1856.

Lyne (W. H.) Letter on cholera.
[N. O. MED. & Surg. Jour., 1853–54, XI, p. [illegible]

McArthur (E.) Cholera—its causes, thology, and treatment.
[NORTHWEST Med. & Surg. Jour., VI, pp. 230–235; 1852–53, II, pp. [illegible] 355.]

McBride (A.) The cause, treatment cure of cholera. 8°. *Cincinnati*, [illegible]

McCall (A.) Remarks on Asiatic
[WEST. Lancet, Cinc., O., 1849, IX, p. 100.]

——— Observations upon Asiatic
[NASHVILLE Jour. Med. & Surg., 177–185.]

McCartney. Cholera and pe[illegible] ease.
[ST. LOUIS Med. & Surg. Jour., [illegible] 104–119, 301–312.]

McCormac (H.) Observations on modic cholera, its origin, nature, treatment; with remarks on diseases generally. 2d ed., [illegible] tions and alterations. [illegible] 1832.

MacCormack (M. J.) Cholera: its non-contagiousness, prevention treatment; showing the effects tricity on the animal economy ductive of epidemics generally. 8°. *London*, 1872.

McCormick (C.) Epidemic cholera.
[N. O. Med. & Surg. Jour., 1852–53, 196.]

M'Cullough (G.) *and* **Maclaren** The phenomena of pestilential in relation to the grade of [illegible] the treatment; its pathology, spread, and the means of [illegible] 8°. *London*, 1850.

Dermot (J.) Remarks on the progress, causes and treatment of cholera.
[Dublin Med. Press, 1847, xviii, pp. 387–388.]

Mcdermott (R.) Case of Asiatic cholera.
[Dublin Hosp. Gaz., 1857, iv, pp. 260–261.]

Gregor (W. L.) A treatise on the blue epidemic cholera. 8°. *Delhi* [*n. d.*]

Macher. Die Cholera-Frage.
[Berl. med. Wochenschr., 1847, pp. 1515–1519; 1848, pp. 513–517, 548–556.]

Maclean (W. C.) A critical examination of Dr. Monro's views on malarial fevers and cholera.
[Brit. Med. Jour., 1874, ii, pp. 764–766, 806–807.]

Macleod (A. C.) Acholic diseases: jaundice, cholera, etc. 8°. *London*, 1866.

Macloughlin. The cholera.
[N. O. Times & Gaz., 1853, vii, n. s., p. 583.]

Mcloughlin (D.) The study of cholera by military surgeons.
[Lancet, 1863, ii, p. 236.]

Macnamara (C.) On cholera.
[Ind. Med. Gaz., Calcutta, 1868, iii, pp. 121–123, etc.]

—— A treatise on Asiatic cholera. 8°. *London*, 1870. L.

Macpherson (J.) Analogies of cholera nostras and of cholera indica.
[N. O. Times & Gaz., 1870, ii, pp. 723–725.]

—— Cholera.
[Lancet, 1872, ii, p. 67.]

Madin. Considérations sur la nature et le traitement du choléra. 8°. *Verdun*, 1851. L.

—— The same. 3e éd. 1854. L.

Magendie. Leçons sur le choléra.
[Gaz. des hôp., 1832, vi, pp. 123–124, etc.]

Magendie (F.) Leçons sur le choléra-morbus, faites au collége de France, revues par le professeur, recueillies et publiées avec son autorisation par Eugène Cadrés et Hippolyte Prévost. 8°. *Paris*, 1832. L.

—— Vorlesungen über die epidemische Cholera, deren Verlauf, anatomisch-pathologische Erscheinungen und Behandlungen, gehalten am Collége de France. Deutsch bearbeitet von S. Hirsch. 8°. *Leipzig*, 1839. L.

Magistel. Notice sur le choléra-morbus sporadique et pestilentiel. 8°. *Paris*, 1831.

Magnan (de).] Du choléra asiatique, des moyens d'en guérir et d'arrêter le cours de l'épidémie. 12°. *Aix*, 1855.

Mahir (O.) Ueber Natur und Behandlung der Cholera. 8°. *Würzburg*, 1836.

Mailloux. Mémoire sur le choléra-morbus épidémique de l'Inde, etc. *Maurice*, 1864.

Mainwaring (E. V.) Asiatic cholera; its pathology and treatment.
[Lancet, 1848, i, p. 444.]

Maire. Doctrine rationnelle du choléra asiatique. Prophylaxie et traitement de cet terrible fléau. 8°. *Paris*, 1873. L.

[Maizière (A.)] Sur le choléra. Dialogue: le frère et la sœur [1848]. 4°. *Reims* [*n. d.*]

Malcolmson (J. G.) Letter from India on the Asiatic cholera.
[Lancet, 1832–33, i, pp. 231–238.]

Man (J. W. E. de). Een Woord over de Cholera [ook voor Niet-Geneeskundigen]. 8°. *Breda*, 1849. L.

—— Le choléra-morbus. Avec un avant-propos du Dr. Lassalvy. 8°. *Amersfort*, 1850. L.

Mangenot (A. S.) Du choléra épidémique. 4°. *Paris*, 1837. L.

Mangold (L. G.) Guter Rath für seine lieben Freunde und Bekannte wegen der asiatischen Cholera-Krankheit. 8°. *Berlin*, 1831.

Manley (J. R.) Essay on cholera.
[Trans. N. Y. Med. Soc., 1834–35, pp. 241–260.]

—— Memorial on the subject of cholera and the means of mitigating its violence.
[Trans. N. Y. Med. Soc., 1836–37, pp. 167–178.]

Mann (J.) Malignant cholera.
[Lancet, 1836–37, ii, pp. 815–816.]

Marbais (de) *et* **Van Berchem.** Communications sur le choléra épidémique. Rapport de M. Fallot.
[Bull. de l'Acad. roy. de méd. de Belg., 1849–50, ix, pp. 14–23.]

Marbot. Mémoire sur le choléra, principalement sur la marche, les principaux symptômes et le traitement de cette maladie. 8°. *Nevers* [1854].

Marchal. Lettres et propositions sur le choléra. 8°. *Paris*, 1866. L.

Marchand (L.) Essai sur le choléra-morbus. 8°. *Bordeaux*, 1831.

Marchetti (N.) Del colera asiatico. Etiologia, pathogenese, igiene e cura. 8°. *Barri*, 1873.

Mareschal. Remarques sur le choléra-morbus asiatique.
[Jour. sect. de méd. Soc. acad. dépt. Loire-Inf., 1833, ix, pp. 113–133.]

Marinus (J. R.) Notice sur le choléra épidémique.
[Bull. de l'Acad. roy. de méd de Belg., 1849–50, ix, pp. 184–197.]

Marrano (T.) Le mie convinzioni sul cholera morbus colla proposta d'un mezzo curativo. 8°. *Falingo.*

Marsden (W.) Malignant cholera.
[LONDON Med. & Surg. Jour., 1832, I, pp. 830–831.]

——— Symptoms and treatment of malignant diarrhœa, better known by the name of Asiatic or malignant cholera. 8°. *London*, 1834. L.

——— The same. 2d ed. 1848. L.

——— Practical remarks and suggestions on Asiatic cholera.
[MED. Chron., Montreal, 1853–54, I, pp. 355–358.]

——— An essay on the contagion, infection, portability and communicability of the Asiatic cholera, in its relation to quarantine; with a brief history of its origin and course in Canada, from 1832.
[CANADA Med. Jour., 1868, IV, pp. 529–537; 1869, V, pp. 1–7, 49–53, 101–108, 145–151, 196–203, 243–250.]

Martarello (P.) Scienza nuova.—Non più cholera. *Alessandria d'Egitto*, 1866.

Martelli (A.) Instruction sur la maladie appelée choléra-morbus épidémique.
[REVUE méd., 1832, II, pp. 207–252.]

Martin (A.) Die Cholera.
[NEUE med.-chirurg. Zeit., München, 1847, IV, pp. 97–100.]

Martin (A.) Zur Entstehungs- und Verbreitungsweise der epidemischen Cholera.
[WIEN. med. Wochenschr., 1873, XXIII, pp. 869–872.]

Martin (A. E. V.) Réponse à un mot de M. le Dr. Levicaire, sur le choléra. 8°. *Toulon*, 1837.

Martini. Was ist Cholera, und auf welchen Wegen ist ihre Heilung möglich? 8°. *Augsburg*, 1850. L.

Martini (E.) Abschrift eines Briefes . . . Ueber Cholera.
[HEIDELB. klin. Ann., 1832, VIII, pp. 84–114, 1 table.]

Marx (K. F. H.) Die Erkentniss, Verhütung und Heilung der ansteckenden Cholera. 8°. *Carlsruhe und Baden*, 1831. L.

Masson. Étude sur le choléra.
[GAZ. des hôp., 1865, p. 594.]

Masuyer. Observations sur la véritable nature du choléra-morbus, et instructions sur la meilleure méthode de traitement de cette maladie. 8°. *Strasbourg*, 1832.

Matice. Considérations sur la [illegible] sidieuse du choléra, les caractères malignité et quelques indications [illegible] peutiques.
[L'ABEILLE méd., 1849, VI, pp. 257–[illegible]

Matterstock. Ueber Cholerastatistik.
[BERLIN klin. Wochenschr., 1874, XI, pp. [illegible]

Maugenest (L.) *Dissertation [illegible] choléra-morbus. 4°. *Paris*, 1[illegible]

Maurer (O.) *Ueber die asiatische [illegible] lera. 8°. *Würzburg*, 1[illegible]

Maurice (J. J.) Traité complet [illegible] léra-morbus. 8°. *Lyon*, 1[illegible]

Maurienne (A. P. de). Recherches [illegible] causes, la nature et le traitement [illegible] choléra. 8°. *Paris*, 1[illegible]

Mauthner. Zur Cholera-Frage.
[NEUE med.-chirurg. Zeitg., München, pp. 281–283.]

——— Ueber die Cholera bei Kindern.
[DEUTSCHE Klinik, 1850, II, pp. [illegible]

Maxwell (W. G.) Cholera.
[INDIA Med. Jour. of Phys. Sci., [illegible] p. 279.]

——— Cholera, its causes and [illegible]
[MED. Times, 1846, XV, p. 322.]

——— A key to cholera.
[MED. Times, 1848, XVIII, pp. 165–[illegible]

Mayer (M.) Quodlibet über die [illegible]
[MED. Conversbl., 1832, pp. 241–[illegible] 353–357.]

——— Theoretisches und Praktisches [illegible] die Cholera.
[MED. Conversbl., 1832, pp. 209–[illegible]

Mayo (T.) The malignant cholera—or an old disease.
[LONDON Med. Gaz., 1849, XLIII, pp. 34–[illegible]

Mazzinghi (D.) Alcuni studii [illegible] morbus asiatico. *Genova*, 1[illegible]

Meigs (C. D.) Remarks on [illegible] cholera. [Printed, not published.] *Philadelphia*, 1849.

Meissner (P. T.) Beiträge zur K[illegible] der Cholera und zwar Nachweis d[illegible] sache ihres Entstehens, aus den E[illegible] tungen und Erfahrungen der [illegible] 1830 ausgebrochenen, verbr[illegible] Seuche. 8°. *Wien*, 1[illegible]

Melzer. Die asiatische Brech[illegible] Volks-Krankheit, ihre Verbr[illegible] weise, ihre Behandlung und [illegible] hältniss zum Staate.
[ZEITSCHR. d. k. k. Gesellsch. der Aerz[illegible] 1856, pp. 534–616.]

Melzer (R.) Studien über die a[illegible] Brechruhr. 8°. *Erlangen*, 1[illegible]

Ierland (C.) *Dissertation sur le choléra-morbus épidémique. 4°. *Paris*, 1832. L.

Iey (A. de). Quelques lettres sur le choléra-morbus. 8°. *Paris*, 1832.

Iichu (J. L.) Du choléra-morbus, ou discussion sur sa nature, le traitement qu'on doit lui opposer et la manière de s'en preserver. 8°. *Paris*, 1831.

Iiller (J.) Malignant cholera.
[LANCET, 1835–36, II, pp. 759–761.]

Iillet (A.) Du choléra-morbus épidémique. 8°. *Paris*, 1851. L.

Iilligan (G.) *De cholera epidemica. 8°. *Edinburgi*, 1822. L.

Iillingen (J. G.) Observations sur la nature et le traitement du choléra-morbus. 8°. *Paris*, 1831.

Iilner (U. R.) Theory and treatment of cholera.
[N. O. Med. & Surg. Jour., 1868, XXI, pp. 209–220.]

Iilroy (G.) Cholera and dysentery.
[LANCET, 1847, II, pp. 673–677.]

Iiner (T.) Letter on the cholera, addressed to any medical gentleman residing where the cholera is or has been prevailing.
[BOSTON Med. & Surg. Jour., 1832, VI, pp. 375–377.]

——— Remarks on cholera.
[MED. Magazine, Boston, 1833, I, pp. 157–163.]

Iises. [*Pseudonym.*] *See* **Fechner** (G. F.)

Iitchell (T. D.) Lecture on epidemic cholera. 8°. *Philadelphia*, 1849.

Iohl (A. F.) Analogien der asiatischen Cholera mit der blauen Krankheit und daraus entnommene Resultate. 8°. *Halle*, 1831.

Ioir (D. M.) Practical observations on malignant cholera. 8°. *Edinburgh*, 1832.

Ioléon (V. de). Du choléra-morbus. Notice générale sur cette maladie. 8°. *Paris*, 1831.

Ioleschott (J.) Consigli e conforti nei tempi di colera, diretti alle singole persone ed in ispecie ai padri di famiglia. 2a ed. *Torino e Firenze*, 1866.

——— Rath und Trost für Cholerazeiten. 8°. *Giessen*, 1866.

Iolinari (G. B.) Del cholera e de suoi rimedi. Trattato popolare. 8°. *Brescia*, 1873.

Ioll (A.) Beknopte Beschrijving van den aziatischen Braakloop (Cholera asiatica), in deszelfs verschijnselen Kenteekenen, Oorzaken, onderscheidene Vormen en geneeskundige Behandeling; inzonderheid ten Nutte der Heelmeesters ten platten Lande. 8°. *Arnhem*, 1832. L.

Monestrol (M. D. de). Du choléra, de l'action de l'agent cholérique, de l'hygiène en temps d'épidémie, des premiers secours à donner, de l'emploi du camphre et des bains chauds comme curatifs. 12°. *Paris*, 1853.

Mongkut (T. Y. C.) Cholera.
[MED. Examiner, Philadelphia, 1851, VII. n. s., pp. 224–230.]

Monks (E.) On cholera.
[MED. Times, 1846, XIV, p. 482.]

[Monod (G.)] Conseils au sujet du choléra [1849]. 8°. *Paris* [*n. d.*]
[2e et 3e éd., 1865.]

Monteverde (D.) *Du choléra-morbus. 4°. *Paris*, 1833. L.

Montgomery. A few words on cholera.
[ST. LOUIS Med. & Surg. Jour., 1866, III, pp. 502–505.]

——— Observations and suggestions on epidemic cholera.
[ST. LOUIS Med. & Surg. Jour., 1866, III, pp. 97–105; 209–215.]

Montgomery (A.) Some interesting particulars regarding the nature and cure of cholera morbus.
[LONDON Med. Repository, 1826, II, n. s., pp. 432–434.]

Monti (P.) Il cholera morbus studiato alla pietra di paragone a schiarimento e giustificazione del suo proprio opusculo. *Cremona*, 1868.

Moore. Brief notes on the disease, Indian cholera.
[LONDON Med. Gaz., 1850, XLIII, pp 534–540, 709–713, 840–845, 893–897, 982–986, 1069–1074, 1103–1107; XLVI, pp. 182–187, 226–232.]

Moos (J. M.) Ueber das Verfahren und die ersten Hülfsleistungen in der Cholera. fol. *Freiburg* [*n. d.*] L.

Morache (G.) À propos du choléra.
[GAZ. hebd. méd. et chirurg., 1873, X, pp. 633–635, 649–651.]

Moreau (M. F.) Observations et réflexions sur plusieurs maladies prises pour de cas de choléra.
[JOUR. univ. et hebd. de méd. et de chirurg. prat., 1832, IX, pp. 488–494.]

Moreau de Jonnès (A.) Note sur la maladie connue sous le nom de choléra-morbus de l'Inde.
[JOUR. (Nouv.) de méd., chirurg., pharm., Paris, 1821, X, pp. 291–303.]

Moreau de Jonnès (A.)—continued.

——— Rapport au conseil supérieur de santé sur la maladie pestilentielle désignée sous le nom de choléra-morbus de l'Inde et de Syrie. 4°. *Paris*, 1824.

——— Rapport au conseil supérieur de santé sur le choléra-morbus, les caractères et phénomènes pathologiques de cette maladie, les moyens curatifs et hygiéniques qu'on lui oppose, sa mortalité, son mode de propagation et ses irruptions dans l'Indoustan, l'Asie orientale, l'Archipel indien, l'Arabie, la Syrie, la Perse, l'empire Russe et la Pologne. 8°. *Paris*, 1831. L.

Morris (F. W.) Remarks on spasmodic cholera. 8°. *Halifax*, 1832.

Moser (P.) Das Wesen der Cholera. Der wahre Schutz vor derselben. Ihre sicherste und schnellste Heilung. 8°. *Ulm*, 1854. L.

Mosgrove (F. J.) Practical remarks on the predisposing causes and treatment of the Asiatic cholera. 12°. *Bombay*, 1849. L.

Moss (W.) Cholera.

[LANCET, 1839–40, II, p. 817.]

——— Cholera: its nature and treatment.

[MED. Circular, 1853, III, pp. 324–325; *also, in* LANCET, 1853, I, n. s., pp. 536–537.]

Mouchet (W. B.) Cholera: its ætiology, contagiousness, and treatment.

[MED. Press & Circular, 1874, II, 369–371, 455–456, 547–549, 564–565; 1875, I, pp. 4–6, 29–30.]

Moulin (E. J.) * Considérations pratiques sur le choléra morbus des Indes. 4°. *Paris*, 1833. L.

Moura (F. A. de). * Du choléra épidémique. 4°. *Paris*, 1850. L.

Moure. Observations de choléra-morbus.

[JOUR. univ. et hebd. d. méd. et d. chirurg. prat., 1832, VII, pp. 8–12.]

Mozzoni. Che sieno il coléra e le febbri tifoidee? Saggio di fisica sintetica applicata alle malattie ora dominanti e digressione sulla diffusione dei veri memoria di Giuseppe Mozzoni letta ad alcuni amici. 8°. *Milano*, 1855. L.

Müller. Cholera.

[MED. Zeitg., Berlin, 1850, p. 176.]

Müller (C.) Einige Bemerkungen über die asiatische Cholera für Aerzte, nach eigener Erfahrung gesammelt auf einer zur Beobachtung des Uebels unternommenen Reise. 8°. *Hannover*, 1848. L.

Müller (E.) Cholera.

[MED. Zeitg., Berlin, 1855, pp. 188, 192, 196, 200, 206, 210, 214, 220, 230, 242.]

Mueller (J.) * Natura cholerae [illegible]. 8°. *Pestini* [1832].

Müller (J.) Ueber epidemische Krankheiten, insbesondere die asiatische Cholera. 8°. *Würzburg*, 1855.

Mulder (J. G.) De scheikundige Verdelen der nederlandsche Regering de Verspreiding der Cholera. [illegible] *terdam*, 1866.

Muller (F. A. H.) Jets over den [illegible]schen Braakloop.

[NEDERLAND. Lancet, 1848–49, IV, [illegible] 277.]

Mulreany (J.) On Asiatic cholera.

[MED. Circular, 1854, V, pp. 85, 98, 12[illegible]

Mure e Gatti. Il cholera-morbus [illegible] colla scienza. 2a ed. 8°. *Genova*, [illegible]

Murray (J.) Nature and treatment of cholera, new method proposed.

[LONDON Med. & Surg. Jour., 1831, I, pp. 7[illegible]

——— Deductions from experience [illegible] the nature of cholera and other [illegible] demics.

[LANCET, 1848, II, pp. 444–448, 499–501.]

——— Cholera: its diffusion, pro[illegible] symptoms, and treatment.

[BRIT. Med. Jour., 1871, II, pp. 173–17[illegible]

Nagel (A.) * Ueber Cholera. [illegible] *burg*, 1860.

Namias (G.) Riflessioni su le [illegible] de'signori Tommasini e Bronzino il cholera-morbus.

[OMODEI, Ann. un. di med., 1832, LX[illegible] 257.]

——— Memoria seconda sul colera.

[GIORN. p. serv. al progr. di patol., [illegible] 314–333.]

——— Lezioni orali sul colera.

[GIORN. venet. di sci. med., 1865, II[illegible] 464; *also*, reprint in 8°, Venezia, [illegible]

——— Storia naturale e cura del [illegible] *Milano*, 1873.

Naumann (M.) Etwas über die C[illegible] [Als Ergänzung zu S. 363 bis 41[illegible] sten Abtheilung des 3. Bandes Handbuches der medizinischen [illegible] Berlin, 1831.]

[LITTER. Ann. d. ges. Heilk., Berlin, [illegible] pp. 232–252.]

Negni (L.) Sul cholera morbus. [illegible] a Carlo Cioccari. 8°. *Milano*, [illegible]

Netter (A.) Notes sur divers [illegible] l'histoire du choléra [cause, [illegible] traitement].

[REVUE méd. de l'est, Nancy, 1874, I, [illegible]

——— Vues nouvelles sur le [illegible] [cause, nature, et traitement]; [illegible] étude sur les injections faites [illegible] veines. 8°. *Paris* [n. d.]

Neumann. Ueber die Cholera.
[Med. Conversbl., 1831, pp. 377-382.]

Ricaise. Étude sur le choléra.
[Gaz. méd. de Paris, 1868, XXIII, pp. 62-65, 92-94, 113-121, 161-164.]

——— The same. 8°. *Paris*, 1868. L.

Ricolich. Lettere sul choléra asiatico. 8°. *Trieste*, 1866.

Nieuwenhuys (C. J.) Eenige Wenken over de Pathogenie, Pathologie, Therapie en Aetiologie der aziatische Cholera. 8°. *Amsterdam*, 1833.

Nivelet. Propositions médicales et observations relatives au choléra, à la choleïne et à la suette épidémiques. 8°. *Commercy*, 1854.

North (M. L.) Observations on cholera.
[HALL'S Jour. of Health, 1855, II, pp. 191-212.]

——— On epidemic cholera, the phenomena, causes, prevention and treatment . . . [etc.] 8°. *Brooklyn*, 1865. L.
[From TRANS. Med. Assoc. East. Dist. Brooklyn.]

Nourse (W. E. C.) A short and plain history of cholera, its causes and prevention. 8°. *London*, 1857. L.

O'Callaghan (P.) Abstract of a paper on Cholera.
[Brit. Med. Jour., 1865, II, pp. 525-526.]

Oesterlen (J. F.) Auch einige Worte über die ostindische Cholera. 8°. *Stuttgart*, 1831.

Ohr (C. H.) Epidemic cholera; its contagion, pathology, and cure; with an account of the disease as it prevailed in Cumberland, Md., during the past summer.
[Amer. Jour. Med. Sci., 1854, XXVII, n. s., pp. 102-112.]

Olinet (H. G. P. M. A.) Considérations sur le choléra morbus spasmodique. 8°. *Paris*, 1832. L.

O-Neill (C. F.) Dissertation sur le choléra-morbus. 4°. *Paris*, 1821. L.

Ontijd (C. G.) Brieven over de aziatische Cholera voorkomende in de algemeenen Konsten Letterbode, 1832, Nos. 30, 32, 34, 37, 42, 46, 47; en 1833, Nos. 2-5. 8°.

Opdorp (J. H. van). Onderzoekingen over den aziatischen Braakloop, bij eenen Persoon, die zich in den hoogsten Graad van Clairvoyance van het magnetisch Somnambulismus bevond. 8°. *Breda*, 1832.

Oppolzer (J.) Pathologie und Therapie der epidemischen Cholera.
[Wien. med. Wochenschr., 1854, IV, pp. 673-681.]

Oragi (S.) Cenni sul cholera-morbus e sul metodo di cura. 8°. *Loreto*, 1836.

Orton (R.) Observations on the malignant cholera.
[LANCET, 1832-33, I, pp. 43-45.]

Osborne (J.) Observations on cholera.
[LONDON Med. Gaz., 1833, XI, pp. 143-147.]

Ottaviani (V.) Intorno all'origine del cholera indiano ed a varie controversi insorte fra gli scrittori di questa malattia. 8°. *Urbino*, 1832.

Otto (T.) Cholera morbus: eller kort Fremstilling af denne Sygdoms Voesen, Udbredelse, Aarsagerne til dens Oprindelse, Sikkrigsmidler &c. Oversat efter Blätter für Lit. Unterhalt. 8°. *Kjöbenhavn*, 1831.

Owen (A.) Remarks on the cholera.
[LONDON Med. Gaz., 1848, XLII, p. 685.]

Pacini (F.) Della natura del colera asiatico, sua teoria matematica e sua comparazione col cholera europeo e con altri profluvj intestinali. 8°. *Firenze*, 1866. L.

——— Sull'ultimo stadio del colera asiatico o stadio di morte apparente de colerosi e sul modo di farli risorgere. 8°. *Firenze*, 1871. L.

Padioleau. Réflexions sur le choléra asiatique.
[REVUE méd., 1850, II, pp. 174-190.]

Page (F. B.) Remarks on epidemic cholera.
[BOSTON Med. & Surg. Jour., 1849, XL, pp. 429-439.]

Paillard (A.) *et* **Marx.** Lettre et leçon de M. le professeur Dupuytren sur le siége, la nature et le traitement du choléra-morbus. 8°. *Paris*, 1832. L.

Paine (H. M.) Manual of reference on epidemic cholera, its causes, prevention, symptoms and treatment. 8°. *Albany*, 1866. L.

Painter (B. B.) Remarks on the nature and treatment of cholera.
[LANCET, 1866, II, pp. 91-92, 118-119.]

Palmer (A. B.) Observations on the cause, nature and treatment of epidemic cholera.
[PENINS. Jour. of Med., Detroit, 1853-54, I, pp. 337-352, 433-454.]

——— Remarks on epidemic cholera.
[DETROIT Rev. of Med & Pharm., 1866, I, pp. 145-153, 193-210, 241-248; *also*, reprint in 8°, Detroit, 1866.]

Palmer (E. R.) On cholera and cholera infantum.
[AMER. Practitioner, 1873, VIII, pp. 75-79.]

Pancoast (S.) The cholera, its history, cause, symptoms, and treatment. 8°. *Philadelphia* [1873 ?].

Pannetier (J. F. C.) *I. Des symptômes du choléra-morbus épidémique. II. . . . . [etc.] 4°. *Paris*, 1843. L.

Pantaloup (N.) Le dernier mot du choléra. Précédé d'une lettre à M. Bellue. 8°. *Marseille*, 1866.

——— Extrait des mémoires de . . . Commandements du choléra. 18°. *Marseille*, 1866.

Panvini (P.) Riflessioni mediche sul cholera-morbus. 8°. *Parigi*, 1832.

Papillon (F.) Recherches analytiques sur les humeurs de provenance cholérique.

[Jour. de l'anat. et de la physiol., 1866, III, pp. 201–207.]

Pari (A.) Cosa è il cholera e mezzi per combatterlo. *Udine*, 1871.

Park. Asiatic cholera.

[Nashville Jour. Med & Surg., 1854, VII, pp. 211–215.]

Parkes (E. A.) Researches into the pathology and treatment of the Asiatic or algide cholera. 8°. *London*, 1847. L.

[*Review of*, Brit. & For. Med. & Chir. Rev., 1848, I, pp. 236–248.]

Parkin (H. H.) * Inaugural dissertation on spasmodic cholera. 8°. *Edinburgh*, 1834. L.

Parkin (J.) Suggestions respecting the cause, nature, and treatment of cholera.

[London Med. & Surg. Jour., 1833, II, pp. 151–153.]

——— Sobre la fisiologie y el tratamiento del colera morbo en el estado de colapso. 12°. *Valencia*, 1835.

Paterson (J.) Notes on and relating to cholera.

[Med. Times & Gaz., 1866, I, pp. 388–390.]

Patrozek (F.) Observationes de cholera asiatica. *Greifswalde*, 1866.

Pattison (G. S.) Letter on cholera to Dr. Carmichael of Virginia. [Originally published in the Washington Telegraph.] 8°. *Philadelphia*, 1852. L.

Pauli (F., *fils*). Mémoire sur le choléra-morbus.

[Revue méd. franç. et étrang., 1831, IV, pp. 409–428.]

Pauwels (A.) Le choléra-morbus, sa cause, ses effets, son traitement. 8°. *Paris*, 1848.

Pellarin (C.) Le choléra ou typhus indien. Épidémie de 1865. Prophylaxie et traitement. 8°. *Paris*, 1866. L.

Pellarin (C.)—continued.

——— Note complémentaire aux . . nications précédentes sur le ch . . .

[Compt. rend. hebd. des séances Acad . . ces, Paris, 1874, LXXVIII, pp. 533–534

Penneck (H.) An essay on the . . pestilence, etc. 8°. *London*, 1 . . .

——— On the nature and treat . . cholera.

[Lancet, 1831–32, I, pp. 793–799; a . . 8°, London, 1831.]

Pennink (J. J.) Nosologisch th . . tisch Onderzoek naar den O . . den Aard, de Toevallen, Ben . . heid en Behandeling van de . . een Gedeelte van Europa heer . . epidemische Cholera-Morbus, g . . op eene Vergelijking der jongste . . nemingen en Lijkopeningen. . . Aanteekeningen door oudere . . aangaande het Wezen en de B . . ling van soortgelijke Epidem . . *Deventer*, 1831.

Périer (J.) Note sur la sympto . . phie et la thérapeutique du [Extr. du "Bull. clinique".] [*n. d.*]

Perrin-Delatouche (J.) * Étu . . choléra épidémique. 4°. *Paris*, 1 . . .

Perron. On Asiatic or Indian ch . . [Transylv. Jour. of Med., 1832, V, p . . .

Perry (J.) Lettre sur le choléra,— . . au docteur Nunes. 8°. *Paris*, 1 . . .

Person. Brief over den aziatisch . . loop. Uit het Fransch door G. H . . ter. 8°. *Gravenhage*, 1832.

Petel (P.) Quelques réflexion . . choléra.

[L'Union méd., 1865, XXVIII, 3e s., p . . .

Peters (J. C.) Treatise on the on . . ture, prevention and treatment . . atic cholera. 12°. *New York*, 1 . . .

——— The same. 2d ed. 1867.

——— The Asiatic or Bengal cho . . *Cambridge*, 1874.

——— Cholera.

[Amer. Cyclopæd., 1874, IV, p. 30 . . .

Petit (E.) Notice sur le choléra . . 8°. *Paris*, 1831.

Petit (J.) Recherches sur la pro . . les causes, la nature et le traite . . choléra-morbus épidémique, suivi . . statistique de l'épidémie obse . . 1832, dans l'arrondissement de S . . nehould. 8°. *Sainte-Ménehould*, 1 . . .

Petit de Maurienne (A.) Rec . . sur les causes, la nature et le tr . . .

Petit de Maurienne (A.)—continued.
du choléra; moyens d'en empêcher le développement en l'attaquant dans la première période, moyens de s'en garantir lorsqu'il règne d'une manière épidémique. 8°. *Paris*, 1837. L.

Petitmengin (T. L.) * Du choléra épidémique. 4°. *Paris*, 1853. L.

Pettenkofer (M.) Die Immunität von Lyon gegen Cholera und das Vorkommen der Cholera auf Seeschiffen.
[ZEITSCHR. f. Biolog., München, 1868, IV, pp. 400–4[illegible], 2 maps.]

—— Ueber den gegenwärtigen Stand der Cholera-Frage und über die nächsten Aufgaben zur weiteren Ergründung ihrer Ursachen.
[ZEITSCHR. f. Biolog., München, 1872, VIII, pp. 402–566, 1 tab.]

—— The same. 8°. *München*, 1873. L.

Pettigrew (T. J.) Observations on cholera; comprising a description of the epidemic cholera of India, the mode of treatment, and the means of prevention. 8°. *London*, 1831. L.

Pfeufer. Pathologie und Therapie der epidemischen Cholera.
[WIEN. med. Wochenschr., 1854, IV, pp. 689–694.]

Philip (A. P. W.) Observations on the nature of malignant cholera, with a view to establish correct principles of its prevention and treatment. 8°. *London*, 1832. L.

Philippson (P. M.) Anweisung zur Erkenntniss, Verhütung und thätigen Hülfsleistung in Betreff der asiatischen Cholera, für Prediger, Schullehrer, Amtleute und Dorf-Vorsteher. 8°. *Magdeburg*, 1831.

—— Beiträge zu den Untersuchungen über die Cholera-Morbus. 2te Aufl. 8°. *Magdeburg*, 1831.

Philodemus. Hoe men in Canada over de Cholera denkt. Naar het Engelsch. 8°. *Graravenhage*, 1866. L.

Pichon (A.) * Dissertation sur le choléra-morbus épidémique. 4°. *Paris*, 1833. L.

Pietra-Leone (E. de). Trattato pratico sul cholera: lavoro utile a tutti, particolarmente per la parte profilatica e a portata del trattamento curativo che nei casi urgenti potra'servire di guida alle persone che non hanno studiato la medicina pria dell'arrivo del medico. 8°. *Palermo*, 1870. L.

Pigeon-Litan (F.) * Du choléra-morbus épidémique. 4°. *Paris*, 1832. L.

Pigliacelli (L.) Il colera morbo. *Teramo*, 1865.

Pinckard (T. B.) An essay on the cause, treatment and cure of asiatic epidemic cholera.
[N. O. Med & Surg. Jour., 1858, XV, pp. 363–373, 439–447.]

Piorry. Leçons sur le choléra-morbus.
[GAZ. des hôp., 1849, pp. 245–246, 247–248.]

Pitet (P.) Dissertation sur quelques points de philosophie médicale et thérapeutique à propos du choléra. 8°. *Paris*, 1867. L.

Plagge (M. W.) Das Cholera-Fieber, gewöhnlich epidemische, oder asiatische Cholera, auch Cholera morbus, genannt. 8°. *Hannover*, 1832. L.

Plagge (T.) Zur Cholerafrage.
[AERZTL. Intell.-Bl., 1857, IV, p. 14.]

Plosz (L.) A Cholararol. 8°. *Pest*, 1866.

Pocci (J.) Nuove idee sul colera e sua cura. 16°. *Pistoria*, 1874.

Pointe. Sur le choléra.
[BULL. Acad. nat. de méd., Paris, 1849–50, XV, pp. 236, 238.]

Pointmayr (J.) De cholera. 8°. *Monachii*, 1837. L.

Pollak (M.) Bemerkungen über Cholera asiatica.
[VIRCHOW's Archiv, 1856, X, pp. 518–522.]

Pollard (T.) Asiatic cholera and cholera morbus.
[VIRG. Med. Jour., Richmond, 1857, IX, pp. 213–224.]

[Pons.] Plus de choléra! Méthode préservative et curative, confirmée par l'expérience. 16°. *Nice*, 1865.

Porges (G.) * De cholera morbo. 8°. *Pragae*, 1836. L.

Porral (A.) Mémoire sur le choléra-morbus, suivi de l'instruction populaire relative à cette maladie. 8°. *Le Puy*, 1832.

Potter (S. H.) Asiatic cholera.
[WORCEST. Jour. Med., 1832, VII, pp. 349–353.]

Poujol (F. A. A.) Du choléra-morbus. 8°. *Paris*, 1832.

Poumier. Essai sur le choléra asiatique. 8°. *Fontainebleau*, 1832.

Pourret. Instruction populaire sur les moyens préservatifs et curatifs du choléra. 8°. *Marseille*, 1855.

Poznanski (F. X.) De la nature, du traitement et des préservatifs du choléra. 8°. *Saint Pétersbourg*, 1856. L.

Poznanski (F. X.)—continued.

——— The same. 2e éd. *Paris*, 1857. L.

Pracros-Visiniol (J.) *Du choléra-morbus. 4°. *Paris*, 1827. L.

Prater (H.) On the nature and treatment of cholera asphyxia. *London*, 1832.

Pringle (R.) Asiatic cholera.
[EDINB. Med. Jour., 1874, XX, pp. 225-238.]

——— The same. 8°. *Edinburgh*, 1874. L.

Prior (W. S.) A fatal blow to the cholera-morbus: or the opinions of a recovered cholera patient, on the origin, symptoms, and proper treatment, in opposition to the present poisonous mode of treating that malady, with an account of the treatment of a number of cases, together with some advice to the public, on the means of preventing an attack. 8°. *London*, 1832. L.

Prost (P. A.) Sommaire analytique du traité physiologique, anatomico-pathologique, thérapeutique et hygiénique du choléra-morbus. 8°. [*n. p., n. d.*] L.

——— Traité du choléra-morbus considéré sous les rapports physiologique, anatomico-pathologique, thérapeutique et hygiénique, contenant l'analyse critique de tout ce que les auteurs anciens et modernes ont écrit sur le choléra-morbus. 8°. *Paris*, 1832. L.

Pruner-Bey. Die Weltseuche Cholera, oder die Polizei der Natur. 8°. *Erlangen*, 1851. L.

Puccinotti (F.) Annotazioni cliniche sul cholera-morbus e su le malattie epidemiche e contagiose in generale secondo le osservazioni fatte in Firenze ed in Livorno nella epidemia del 1835.
[*With* PUCCINOTTI, Opere med., Milano, 1855, I, pp. 889-913.]

Puhlschneider (W.) Einige Bemerkungen über die Cholera.
[ALLG. med. Central-Zeitg., 1853, XXII, pp. 610-611.]

Pujade. Recherches théoriques et pratiques sur l'affection typhoïde intense, générale, dite choléra épidémique. 4°. *Perpignan* [1855]. L.

Querner (E.) Die Cholera, ihre Anzeichen, Ursachen, Verhütung und Heilung. 8°. *Philadelphia*, 1866.

Quintard (C.) *Du choléra épidémique et de la cause encombrement. 4°. *Paris*, 1849. L.

Rabache (C.) Études, observations et recherches sur le choléra, sa cause et son remède. 8°. *Bordeaux*, 1854. L.

Rae (M. J.) Observations on cholera.
[LANCET, 1854, II, n. s., pp. 187-189, 208-210.]

Raffaele (G.) Trattato del colera asiatico. 8°. *Napoli*, 1837.

Raikem. Rapport verbal sur un ouvrage de M. Gaetano Tardani sur le choléra.
[BULL. Acad. roy. de méd. de Belg., 1853-54, XIII, pp. 92-95.]

Ralph (J.) A plain treatise on cholera intended for the use of private individuals, showing the nature of cholera, its causes, both predisposing and exciting, etc., etc. To which is added Rules for preservation of health in the four seasons. 8°. *New York*, 1849. L.

Ramsey (F. A.) Cholera: a series of letters communicated to "The Standard and Reformer." 8°. *Knoxville, Tenn.*, 1849. L.

——— Observations on sporadic, endemic and epidemic diseases: cholera.
[MED. & Surg. Monthly, Memphis, Tenn., 1866, I, pp. 265-279.]

Ranque. Mémoire sur le choléra-morbus.
[GAZ. des hôp., 1831, V, pp. 6, 26-27, 162.]

Ranson (C. H.) *Dissertation sur la cholerrhagie. 4°. *Paris*, 1818. L.

Rant (L. J.) Proeve eener geneeskundige Verhandeling, over den Aard, de Voorbehoedmiddelen tegen, en de Geneeswijze der Cholera aziatica of Indica. 8°. *Amsterdam*, 1831. L.

Raphaël. Sur la nature et le traitement du choléra.
[GAZ. des hôp., 1850, pp. 187-188, 196.]

Rasis (C.) Cenni sul cholera-morbus asiatico responsivi all'operetta intitolata: Riflessioni sulla corrente malattia asiatico-colerica e modo sicuro di preservarsene. 8°. *Livorno*, 1835. L.

Raspail. Neue Schutz- und Heil-Verfahren gegen die Cholera und die tausendfach erprobte, wahrhaft wunderthätige Wirksamkeit derselben. 12°. *Leipzig*, 1852. L.

Rathke. Ueber die Cholera.
[MAGAZIN f. d. ges. Heilk., 1831, XXXIII, pp. 582-601.]

Ratti (L.) Osservazioni sul cholera-morbus: suggerimenti igienici. 18°. *Torino*, 1872.

Rausche (G. A.) *De cholera epidemica. 8°. *Berolini* [1840]. L.

ausche (G. A.)—continued.

—— A letter to the consulting physicians of Boston [on cholera]. 8°. *Boston*, 1866. L.

écamier (J. C. A.) Recherches pratiques sur la conduite à tenir dans le choléra algide ou asiatique. 8°. *Paris*, 1849. L.

[2d ed. same year.]

echelet (C. C.) *Du choléra-morbus épidémique. 4°. *Strasbourg*, 1855. L.

ecke (W. v. der). Die Cholera, die Ruhr, . . . , auf Grundlage 25-jähriger Erfahrung als verwandte, nach einem und demselben Principe zu behandelnde Krankheiten dargestellt. 8°. *Leipzig und Heidelberg*, 1873. L.

eed (D. McC.) Fever physiologically considered. Considerations on cholera; also, the questions of contagion and the quarantine laws; with an address to the public, &c., on the proper treatment of cholera. 12°. *London*, 1846. L.

eeken (C. G. von). De Cholera. Wat ieder doen moest om haar af te weren. 8°. *Haarlem*, 1866. L.

ees (G.) Lectures on carbon, oxygen and vitality, the three great agents in the physical character of man, with remarks on Asiatic cholera. 8°. *London*, 1832. L.

ees (G. O.) The pathology and treatment of cholera.

[LANCET, 1867, I, pp. 97–98, 224.]

ein (J. G. M. v.) Briefliche Mittheilung über die orientalische Cholera, an und durch Dr. Dietrich Georg Kieser. 8°. *Leipzig* [1831]. L.

einhardt (B.) *und* **Leubuscher** (R.) Beobachtungen über die epidemische Cholera.

[VIRCHOW's Archiv, 1848, II, pp. 409–582.]

eip (A. G. G.) *De cholera asiatica. 8°. *Berolini*, 1866. C.

eiss (K.) Erfahrungen während der Cholera-Epidemie im Jahre 1873.

[WIENER med. Presse, 1873, XIV, pp. 973–975.]

emer *und* **Neugebauer.** Die asiatische Cholera. 8°. *Goerlitz*, 1846.

ennecke (F.) *De cholera asiatica ejusque causis auxiliaribus adjectis observationibus in epidemia megalopolitana A. H. S. LIX. factis. 8°. *Gryphiswaldiae*, 1861. C.

eubel (J.) Vier Vorlesungen über die asiatische epidemische Brechruhr in Europa, enthaltend einen praktischen Unterricht für Nichtaerzte, diese Krankheit im Nothfalle auch ohne Aerzte vollständig zu behandeln und zu heilen; vorgetragen einem zahlreichen aus allen Ständen gemischten Publikum in dem Universitätsgebäude zu München. 12°. *München*, 1831. L.

Reuss (J.) Studien über die Cholera.

[MED. Correspbl. d. württemb. aerztl. Vereins, 1855, XXV, pp. 137–140, 145–149, 153–156.]

Reveillé-Parise. Lettre à un médecin contenant un résumé de ce que l'on sait sur le choléra-morbus.

[GAZ. méd. de Paris, 1832, III, pp. 389–392.]

Rezek. Miszellen aus Erfahrungen über Cholera.

[WIEN. med. Presse, 1873, XIV, pp. 1109–1112, 1133–1137, 1159–1160.]

Richardson (B. W.) On the physiological formula of cholera and the treatment.

[MED. Times & Gaz., 1866, II, pp. 110–113.]

Richardson (C.) The cholera: its cause, prevention and cure. 8°. *New York*, 1849. L.

Richardson (F. W.) The cholera.

[LANCET, 1853, I, n. s., pp. 352–353.]

Richardson (R. S.) Cursory remarks on the nature of the Asiatic cholera, with a summary account of the best mode of prevention and cure. 8°. *London*, 1831. L.

Richter (C. A. W.) *Die asiatische Brechruhr. 8°. *Leipzig*, 1832. L.

—— Die asiatische Cholera ist als Epidemie und als einzelner Krankheitsfall erfolgreich zu bekämpfen. 8°. *Leipzig*, 1872. L.

Ridgway (T.) Some observations on cholera.

[LONDON Med. & Phys. Jour., 1832, LXVIII, pp. 5–8.]

Rieck (C. H. A.) *De cholera asiatica. 12°. *Berolini*, 1855. L.

Riecke. Typhus und Cholera als Gegenstände der Gesundheitspflege in den Kriegsheeren.

[NEUE Zeitg. f. Med. u. med. Reform, Nordhausen, 1849, I, pp. 763–764.]

Riecke (C. T.) Die asiatische Cholera und die Gesundheitspflege. Ein Beitrag zur Erforschung und Bekämpfung dieser neuen Volksseuche. 8°. *Nordhausen*, 1850. L.

Riecke (V. A.) Mittheilungen über die morgenländische Brechruhr. 3 Bd. in 2 v. 8°. *Stuttgart*, 1831–32. L.

Ripoll (A.) Étude sommaire sur le choléra.

[BULL. gén. de thérap., méd. et chirurg., 1866, LXX, pp. 26–35, 71–79.]

Rive (F. G.) * De cholera asiatica. 8°. *Trajecti ad Rhenum*, 1833. L.

Robbe. Sur la nature et le traitement du choléra.

[L'UNION méd., 1873, XVI, 3e s., pp. 480–481.]

Robert (E. F. F. C. W.) Cholerabuch, oder das Buch über die ursprüngliche und fernere Entstehung und Abwendung der bengalischen Brechruhrpest oder Hindupest. Nach zuverlässigen Quellen und nach eigenen Ansichten. 8° *Giessen*, 1832.

Robert (F. J. A.) * Essai sur la nature du choléra-morbus et son traitement. 4°. *Paris*, 1833. L.

Robert (L. J. M.) Conseils aux habitants de Marseille et à ceux de la Provence pour se préserver du choléra . . . . précédés d'un nouvel aperçu sur la cause spéciale et la nature de cette maladie. 32°. *Marseille*, 1832.

Robert (P. H.) Qu'est-ce que le choléra? Quel moyen de le neutraliser à son invasion? 8°. *Paris*, 1855.

Robillard (J. B. P.) Du choléra, de ses causes, effets et traitement curatif. Rapport de . . . . sur le travail de M. L. Lemoine-Moreau, lu . . . 1866. 8°. *Paris*, 1866.

Roche. Cholera.

[DICT. de méd. et de chirurg., Paris, 1830, V, pp. 250–262.]

Roche (L. C.) Lettres à A. Latour sur le choléra. I. Du degré de curabilité du choléra-morbus. II. Les prétendues bizarreries du choléra. III. De la contagion du choléra. IV. Réponse aux objections à l'opinion de la contagion du choléra. V. Sur la contagion du choléra-morbus. VI. Réhabilitation de l'hypothèse. VII. Anatomisme et vitalisme. VIII. Étiologie; miasmes en général; miasme du choléra. IX. Nature des maladies; nature du choléra. X. Encore un mot sur la contagion de cette maladie. XI. Hypothèses. XII. Diagnostic, pronostic, et traitement.

[L'UNION méd., Paris, 1849, III, pp. 318–319, 329–330, 361–362, 365–366, 485–487; 1851, V, pp. 1–2, 5–6, 93–94; 1852, VI, pp. 191–192, 453–454, 461–463, 473–474, 477–479, 485–487, [illegible]–513–514, 521–522; 1853, VII, pp. [illegible]–50, 53–54; 1854, VIII, pp. 585–586, [illegible]–IX, pp. 373–374, 377–379, 381–383, [illegible]–465–467, 477–479, 489–491, 501–503, [illegible]–]

Roche (L. C.)—continued.

——— The same. 8°. *Paris*, 1849–[illegible].

Rochester (T. F.) A few remarks cholera.

[BUFF. Med. & Surg. Jour., 1863–[illegible], I, pp. [illegible]–464; 1866–67, VI, pp. 1–9.]

Rochoux. Notice sur le choléra-[illegible] etc. 1833.

Rodolfi (R.) Sul cholera Indiano [illegible]tera al Gaetano Strambio. [illegible]. M 1873.

——— Sul cholera-morbus. Lettera [illegible] al cav. G. Strambio.

[GAZ. med. it. Lomb., 1874, XXXIV, pp. [illegible] *also*, reprint in 8°, Milano, 1874.]

Rodrigues-Barrant (A.) Essai [illegible] nature et le traitement du choléra. *Maurice*, 1863.

Roe (E. T.) Observations on [illegible].

[PROVINC. Med. & Surg. Jour., London, [illegible] 681–682.]

Röschlaub (A. *und* M. J.) Erk[illegible] über die wandernde Cholera-Krankheit und die gegen dieselbe bei ihrem [illegible]hen, Eintreten und Herrschen [illegible] fenden Vorkehrungen. 8. [illegible] 1831.

Rogers (J.) Reports on Asiatic [illegible] *London*, 1848.

Romberg. Bemerkungen über [illegible] tische Cholera. 8°. *Berlin*, 1[illegible]

Romberg (M. H.) Einige practische [illegible] merkungen über asiatische Cholera.

[WOCHENSCHR. f. d. ges. Heilk., 1[illegible] II 787.]

Romich (J.) Neueste Beobachtungen über die epidemische Cholera. [illegible] 8°. *Wien*, 1866.

Rosenthal (C.) Die Cholera-Epidemie, deren Verlauf, naturgemässe Behandlung und Beurtheilung. 1[illegible] *schweig*, 1850.

Rosenzweig (H. S.) Choleram[illegible] turam medendique rationem. [illegible] tratu invitatus breviter descripsit. *Cracoviae*, 1850.

Roseville (A. de). Choléra: de sa [illegible] et de son traitement. Mémoire [illegible] senté [1866] par J. Cloquet. [illegible] *Germain-en-Laye* [n. d.]

Ross (G.) Lectures on the Asiatic [illegible]

[MED. Times, 1848, XVIII, pp. 386–[illegible] 4–5, etc.]

)sshirt. Wie erkennt man die orienta-...sche Cholera in ihrem ersten Beginnen, ...elches sind die sichersten Vorbauungs-...ittel, und welches ist die beste Be-...handlung? Nebst einem Anhange von ...rzneyformeln. 12°. *Bamberg*, 1831. L.

)stan. Leçons cliniques sur le choléra.

[...z. des hôp., 1849, pp. 204, 215-216, 238, 331-..., et seq.]

— Cholera-morbus: lezioni cliniche. [Versione italiana.]

[...z. med. it. Tosc., Firenze, 1854, IV. 2a s., pp. ...-275, 281-283, 289-290, 317-319, 333-337, 365-..., 381-385, 388-393, 396-400, 417-421.]

)thamel. Andeutungen des Wesens, der Natur und des Charakters der Cholera, nebst Vorschlägen zu einer rationellen Behandlung dieser Krankheit.

[...Conversbl., Hildburghausen, 1831, pp. 321-...]

)tondo (D.) Osservazioni clinico-me...che sul colera-morbo. 8°. *Napoli*, 1837.

)ugedemontant (J. H.) * Du choléra ...atique. 4°. *Paris*, 1849. L.

)usset (C.) Traité du choléra-morbus. ...tenant l'historique, les causes, [etc.]; ...suivi de quelques observations sur ...ssainissement de la ville de Paris. 2e ... °. *Paris*, 1853. L.

1. 1851.]

)vida (C. L.) Osservazioni intorno al ...olera asiatico. 8°. [*Milano*, 1868.] L.

)off (J. F.) Über die Cholera und deren ...pecifische Behandlung. 8°. *Leipzig*, ...8.

)st (J. N.) Einiges über die Cholera. Ein Sendschreiben an Alex. v. Hum...oldt. 8°. *Berlin*, 1832. L.

)mer (J.) Cholera-morbus; its first ...ymptoms clearly pointed out, and its ...angerous effects fully prevented; writ...en with the view to afford immediate ...elief and ultimate cure to those af...fected with this dreadful malady by the ...doption of certain remedies here recom...mended; together with Dr. Sydenham's ...ccount of the cholera-morbus which ...aged in England in the year 1669. 8°. *London*, 1831. L.

)bell (E. W.) Die Cholera. Ihre Entste...hung und Verbreitung, ihr Wesen, ihre ...Verhütung und Heilung. Nach zehnjäh...rigen Beobachtungen und Erfahrungen ...populär und praktisch dargestellt. 8°. *Berlin*, 1871. L.

Sablairoles (J.) Réflexions analytiques et critiques sur le choléra-morbus, contenant l'exposé d'un nouveau moyen thérapeutique contre cette maladie. 8°. *Paris*, 1832.

Sachs (J. J.) Allgemeine Lehren von den epidemischen und ansteckenden Krankheiten, insbesondere der Cholera, und den zu ihrer Hemmung oder Minderung geeigneten Maassregeln. 8°. *Berlin*, 1831.

——— Ueber die Cholera auf deutschem Boden, und ihre bisher bewährteste Präservativ- und Heilmethode. Zunächst als vielseitig gewünschter Nachtrag zu dessen grösserer Schrift. 8°. *Berlin*, 1831.

Sachs (L. W.) Offenes Sendschreiben, die Cholera betreffend. 8°. *Königsberg*, 1831.

Sachse (J. H. L.) * De cholera morbo observationes nonnullae. 8°. *Rostochii*, 1832. L.

Sadler (M. T.) A few thoughts on cholera. 8°. *London*, 1848.

——— On the nature of cholera and the principles of its treatment.

[MED. Times & Gaz., 1854, IX, n. s., pp. 461-463.]

Sainmont. Sur la nature et sur le traitement du choléra.

[GAZ. des hôp, 1872, XLV, pp. 11-30.]

Saint-Amand (E. J. de). * Dissertation sur le choléra-morbus. 4°. *Paris*, 1817. L.

Saintpère (J.) * Dissertation sur le choléra-morbus épidémique. 4°. *Paris*, 1836. L.

Sales-Girons. Réflexions éminemment pratiques sur le choléra.

[REVUE méd., 1853, II, pp. 577-590, 648-656; *also, in* ARCH. belg. de méd. mil., 1854, XIII, pp. 75-87.]

——— Considérations pratiques sur l'épidémie actuelle du choléra.

[REVUE méd., 1854, I, pp. 13-21.]

——— Coup-d'œil sur les ouvrages: La civilisation et le choléra par M. J. Girette.—Exposé des travaux de la conférence sanitaire de Constantinople par M. A. Fauvel.

[REVUE méd., 1869, I, pp. 257-271.]

Sander (W.) Beobachtungen und Ansichten über die Cholera-Morbus. 3 Hefte. 8°. 1832.

Sander (W.)—continued.

——— Lichtfunken in das geheimnissvolle Dunkel der Cholera. 8°. *Kandern*, 1836. L.

Sarazin (J.) Le choléra pestilentiel, ou réponse à une lettre d'un curé de campagne sur ces questions: Le choléra russe est-il une espèce nouvelle, est-il contagieux ou épidémique? Comment doit-il être traité? Peut on s'en garantir? 8°. *Paris*, 1831.

Sardham (B. L.) Remarks on cholera.

[LONDON Med. & Phys. Jour., 1824, LII, pp. 295–298.]

Sasse (A.) De Cholera. Opmerkingen naar Aanleid van G. J. Mulder's de natuurkundige Methode en de Cholera. 8°. *Amsterdam*, 1867.

Satter (J. N.) Die Cholera und ihre Heilung. *Wien*, 1856.

Sauerhering (E.) Was hat man bei dem herrschenden Brechdurchfall oder einem Cholera-Anfalle selbst augenblicklich zu thun, wenn man sich nicht gleich eines Arztes bedienen kann? 12°. *Berlin*, 1837.

Sauveur (D.) Note sur le choléra.

[BULL. de l'Acad. roy. de méd. de Belgique, 1848–49, VIII, pp. 1057–1058.]

Savatier (J. La M.) *Dissertation sur le choléra-morbus. 4°. *Paris*, 1827. L.

Sbarra (J.) Réflexions sur le choléra. 8°. *L'Aigle* [1849].

Schäfer. Bemerkungen über das Wesen und die Behandlung der Cholera.

[MED. Zeitg., Berlin, 1837, pp. 215–217.]

Schäfer (H.) Cholera: das Wesen und die rationelle Behandlung derselben. 8°. *Leipzig*, 1833.

Schärtler (C. F.) Enträthselung der Cholera. 8°. *Olmütz*, 1849. L.

Schärtler (F. C.) Neueste Diagnose und Therapie der Cholera-Morbus. 8°. *Brünn*, 1838.

Scharlau (G. W.) Ueber die Cholera.

[ZEITSCHR. f. klin. Medizin, Breslau, 1850, I, pp. 462–468.]

——— Theoretisch-praktische Abhandlungen über den Typhus, die Cholera, [etc.] 8°. *Stettin*, 1853. L.

——— Précis de la nature et du traitement du choléra asiatique. 8°. *Stettin*, 1854.

Schauenburg (C. H.) Ueber [illegible] und die Principien der Mittel [illegible] Bekämpfung. 8°. *Würzburg*, 1[illegible]

Schenck (W. L.) Asiatic cholera.

[CINC. Lancet & Observer, 1866, II, pp. 2[illegible]

Schimko (J. G.) Pathogenetische [illegible] schreibungen und zweckmässige [illegible] handlungen der asiatischen [illegible] 8°. *Olmütz*, 1837.

Schleiss von Löwenfeld (K.) [illegible] asiatica zu und bei uns. [illegible] 1837.

Schlesinger (M.) De cholera. *Vratislaviae*, 1826.

Schlott (C. H. O.) *De cholera mica. 8°. *Berolini*, 1852.

Schlüter. Einiges über Cholera, deren Behandlung.

[ALLG. med. Central-Zeitg., 1867, XXXVI, 976.]

Schmidt (C.) Beitrag zur Lehre der Cholera. 8°. *Würzburg* [illegible]

——— Charakteristik der epidemischen Cholera gegenüber verwandten Exsudationsanomalien. 8°. *Leipzig, Mitau*, 1850.

Schmidt (C. T.) *De cognoscenda cholera. 8°. *Berolini* [illegible]

Schmidt (H.) Die europäische [illegible]

[MED. Zeitg., Berlin, 1848, pp. 178–17[illegible]

Schmoele (W.) An essay on the diffusion, localisation, prevention and cure of the Asiatic cholera and other epidemics. 8°. *Philadelphia*, [illegible]

Schneemann (M. W.) Was ist Natur? und welches die auf sie gegründete Heilart der asiatischen Cholera? Oder: Aerztliches Parer zu der einstimmenden Kranken-Geschichte und erschöpfenden Sektions-Befund über die an der asiatischen Cholera Erkrankten und Gestorbenen. [illegible] *burg*, 1832.

Schneider (F.) Catechismus over de cholera. 8°. *Rotterdam*, 1873.

Schnizlein (E.) Meine Behandlung der Cholera, ihre Entstehung, Verbreitung, Heilung und Verhütung. 8°. [illegible] 1854.

Schnurrer (F.) Die Cholera-Krankheit, ihre Verbreitung, ihre Zufälle, die gesuchten Heilmethoden, ihre Eigenthümlichkeiten und die im Grossen [illegible] anzuwendenden Mittel. [illegible] *und Tübingen*, 1831.

hoewers (A.) Mémoire sur le choléra épidémique ou recherches sur son principe morbifique et son traitement rationnel. 8°. *Amsterdam*, 1848. L.

houten (H. J.) Brief aan J. Vitringa houlon aangaande deszelfs Betoog over le Noodzakelijkheid enz. 8°. *Amsterdam*, 1832.

—— Ontleed-, natuur- en ziektekundige Onderzoekingen aangaande den Aard en le Geneeswijze van de Cholera morbus n het Algemeen, en van de aziatische n het Bijzondere. 8°. *Amsterdam*, 1832. L.

hraube (O.) Ueber Pathogenese und Therapie der Cholera.

[Deutsche Klinik, 1868, XX, pp. 359–362, et seq.; ibid, XXI, pp. 65–67, et seq.]

hubert (J. A.) Heilung und Verhütung der Cholera-Morbus. 8°. *Lipsiae* [1830]. L.

hultze (C. A.) Ideen über die asiatische Cholera. Ein Beitrag zu ihrer Kenntniss und Heilung für Aerzte, Wundärzte und gebildete Leser. 8°. *Leipsig*, 1831.

chumann (G. A.) Die entdeckte Ursache der Cholera-Epidemie, nebst Bemerkungen über das Wesen, die Heilung und Verhütung der Cholera. 8°. *Quedlinburg*, 1850. L.

chwarz (A. G.) * Cholera asiatica, inflammatio toxica veterum. 8°. *Berolini* [1849]. L.

cot (W.) Amtlicher Bericht über die epidemische Cholera. Deutsch bearbeitet von Dr. F. J. Behrend. Bevorwortet und mit Anmerkungen begleitet von M. H. Romberg. 8°. *Berlin*, 1832. L.

earle (C.) Cholera, its nature, cause, and treatment; &c. 8°. *London*, 1830.

—— Cholera, its nature, cause, treatment, and prevention, clearly and concisely explained. 8°. *London*, 1831. L.

—— The same. 2d ed. With an appendix, containing practical remarks on fever and dysentery, with which cholera is intimately connected, and frequently combined: being the substance of reports made to the late government of Poland. 1831.

—— Ueber die Natur, die Ursachen und die Behandlung der Cholera. Aus dem Englischen herausgegeben und mit einer Vorrede begleitet von C. F. von Graefe. 8°. *Berlin*, 1831.

Searle (C.)—continued.

—— Cholera: its nature, cause, and treatment, simply, scientifically and practically explained. roy. 8°. [*London*, 1866.]

Seaton (E. C.) Plan for the registration of cases of cholera.

[London Med. Gaz., 1848, XL, p. 858.]

Seavy (J.) A treatise on the Asiatic cholera, giving an account of its rise and progress, character and nature, symptoms, prevention, and mode of treatment. 8°. *New York*, 1832. L.

Seghers. Note relative au choléra asiatique. [Discussion.]

[Bull. de l'Acad. roy. de méd. de Belg., 1866, IX, pp. 457–466.]

Selleger (J.) *De cholera vera epidemica. 4°. *Lugdun. Bat.*, 1823.

Selais (P.) Réponse au Dr. A. F. Andrieu. Suivie d'une instruction pour le traitement allopathique du choléra. 8°. *Agen*, 1854.

Sérée (J. F.) Mémoire sur la nature, le siége et le traitement du choléra. 8°. *Pau*, 1860. L.

—— Traité sur la nature, le siége et le traitement du choléra, suivi d'une réfutation des doctrines de l'importation et de la contagion de cette maladie et d'une dissertation sur la formation des miasmes cholériques. 8°. *Pau*, 1865. L.

Serres *et* **Nonat.** Mémoire sur le choléra-morbus.

[Gaz. des hôp., 1832, VI, pp. 103–104.]

Sertürner (F.) Blicke in die Gegenwart und Zukunft, mit Beziehung auf die orientalische Cholera.

[Hufeland's Jour. d. prakt. Heilk., 1831, LXXI, pp. 71–77.]

—— Dringende Aufforderung an das deutsche Vaterland in Beziehung der orientalischen Brechruhr. [Zugabe zur 2. Auflage.] 8°. *Göttingen*, 1831.

Sewall (T.) Letter on epidemic cholera.

[Boston Med. & Surg. Jour., 1859, XLI, pp. 169–173.]

Sexton (R.) Remarks on malignant cholera.

[North-Amer. Arch. of Med. & Surg. Sci., 1835, II, pp. 314–325.]

Sherrill (H.) On the pathology of epidemic cholera, with some preliminary observations on the history of the disease, and the general cause and nature of

Sherrill (H.)—continued.
epidemics: containing an improved plan of treatment, the means of prevention and rules for corporations and individuals to pursue. 8°. *New York*, 1835. L.

Shrimpton (C.) Cholera: its seat, nature and treatment. 8°. *London*, 1866. L.

——— The same [in French]. *Paris* [1866].

Sibson. Asiatic cholera.
[LANCET, 1853, I, pp. 519–520.]

Siebert (A.) Zur Genesis und Therapeutik der epidemischen Cholera, und über deren Verhältniss zum Morbus miliaris, nach eigenen, in Eger und München gesammelten Erfahrungen. 8°. *Bamberg*, 1837. L.

——— Ein Brief an die Redaction über die Cholera-Verhandlungen vom 19. bis 22. September d. J. in der medicinischen Section der XXVI. Versammlung deutscher Naturforscher und Aerzte in Regensburg.
[JENAISCHE Annal. f. Physiol. u. Med., 1850, I, pp. 468–482.]

Siegert (E. M.) *Pathologia et therapia cholerae asiaticae summatim exposita. 8°. *Lipsiae* [1850]. L.

Siegmeyer (J. G.) Betrachtungen über die Natur der Cholera. Mit Hinweisung auf die möglichen Heilmittel nach physischen und chemischen Gründen [etc.] 8°. *Berlin*, 1831. L.

Siemerling (F.) Entschleierung der Cholera. *Hamburg*, 1831.

——— Sendschreiben an Deutschland's Aerzte über die Cholera. 8°. *Rostock*, 1831. L.

Sigriz (A.) *De cholera epidemica dissertationis tentamen. 8°. *Monachii* [*n. d.*] L.

Simon. Cholera.
[LANCET, 1871, II, p. 279.]

Simon (F. A., *jun.*) Die Cholera morbus, Symptome, Wesen und Behandlung. 2te Aufl. 8°. *Hamburg*, 1832.

——— Weg mit den Kordons, quand même .... der epidemisch-miasmatische Charakter der indischen Brechruhr, ein grober Verstoss gegen die Geschichte ihres Zuges von Dschissore in Mittelindien nach dem tiefen Keller in Hamburg, und der gröbste gegen den gesunden Menschenverstand, mit Beziehung auf die von Burdach, Lovinser und C. W. Hufeland in No. 265, 275, 276, 277 und 307 der

Simon (F. A., *jun.*)—continued.
preussischen Staatszeitung [illegible] enthaltenen Artikel. 12°. *Ham.* 1832.

——— Die indische Brechruhr oder Cholera-Morbus. Ihre Symptome, ihr Wesen und ihre Behandlung; sowie [illegible] ursprüngliche und alleinige Verbreitung durch Menschenverkehr sowohl in Asien als in Europa, und die dringende Notwendigkeit der strengsten Quarantaine gegen aus damit behafteten und damit behaftet gewesenen Städten und Ländern den kommende Menschen und Waaren, gegründet auf endliche, natürliche Schlichtung des Streites über Kontagiosität und Nichtkontagiosität der Seuche. 12°. *Hamburg*, 1831.

Simon (M.) Du choléra.
[BULL. gén. de thérap., méd. et chir., XXXV, pp. 193–199.]

Simond (E. A.) Du choléra-morbus. *Paris*, 1824.

Simonson. Noticer over Cholera. 8°. *Kjöbenhavn*, 1831.

Simpson (J.) Observations on the cholera. *London*, 1849.

Singer (L.) *Auch ein Wort über die Cholera. 8°. *München*, 1837.

Sinogowitz. Cholera.
[MED. Zeitg., Berlin, 1850, pp. 164, 17[illegible]

——— Einige Thesen über die asiatische Cholera.
[MED. Zeitg., Berlin, 1853, p. 55.]

Skoda. Pathologie und Therapie der epidemischen Cholera.
[WIEN. med. Wochenschr., 1854, IV, pp. [illegible]

——— Cholera nostras und Cholera epidemica.
[WIEN. med. Presse, 1871, XII, pp. [illegible] 301.]

Smith (F.) Extracts from the introductory part of an address on Asiatic cholera. [TRANS. Med. Soc. of Tenn., 1838, pp. [illegible]

Smith (J. M.) A discourse on the epidemic cholera-morbus of Europe and Asia. 8°. *New York*, 1831.

Socquet (J. M.) Observations pratiques et instructions familières sur la nature et le traitement simple et méthodique du choléra-morbus asiatique, recueillies et rédigées au sein des hôpitaux de *Turin*, 1835.

Solzer (E.) Die Lehre von der asiatischen Cholera, ihrer Entstehung und ihrer Behandlung. 8°. *Nürnberg*, [illegible]

nnet (M.) Traité du choléra, contenant 'explication de ce fléau ... et les moy- ns de s'en préserver et de s'en guérir. 8°. lfoux, 1851.

rmani (N. M.) Problemi patologici illa natura e sul trattamento terapeu- co del cholera-morbus.

OMODEI, Ann. un. di med., 1831, LX, pp. 39-56.]

ubrier (P.) *Symptômes et traitement lu cholera-morbus épidémique. 4°. 'aris, 1849. L.

umain (J. V.) *De cholera asiatica. . Lugdun. Bat., 1849.

uthall (J. H.) Epidemic cholera-mor- ns.

RICHMOND & LOUISV. Med. Jour., 1873, XVI, pp. 31-36.]

ence (J.) Observations on the cholera norbus of India.

LONDON Med. Gaz., 1832, IX, pp. 337-344.]

encer (T.) Annual address. On the nature of the epidemic usually called Asiatic cholera, etc.

TRANS. N. Y. Med. Soc., 1832-33, pp. 217-341.]

—— An essay on the nature of the epi- lemic usually called Asiatic cholera, etc., with the reasons why it should be re- garded as an epidemic diarrhœa serosa, instead of common cholera-morbus; and an attempt to found the treatment upon the pathology of the disease. 8°. *Albany*, 1833. L.

itta. Brief remarks on cholera. *Lon- lon*, 1866.

ague (G.) Remarks upon cholera, ts pathology and treatment.

WESTERN Lancet, Cinc., O., 1852, XIII, pp. 23-31.]

anley (E.) Cholera.

LONDON Med. Gaz., 1832, IX, p. 309.]

arr (T. H.) A discourse on the Asiatic holera and its relations to some other pidemics, including general and special ules for its prevention and treatment. . *London*, 1848. L.

atham (S. F.) A practical sketch of he Asiatic cholera of 1848, its rationale nd [presumed] pathology. Supple- nentary remarks to pamphlet on low nflammations. 8°. *London*, 1852. L.

eele (G.) Some remarks on cholera; vith reminiscences of the epidemic of 832.

EDINB. Med. Jour., 1866, XII, pp. 237-246.]

eifensand. Sur le choléra asiatique. Rapport de M. Fallot.

BULL. de l'Acad. roy. de méd. de Belg., 1848-49, VIII, pp. 456-459.]

Steinheim (S. L.) Bau und Bruchstücke einer künftigen Lehre von den Epide- mieen und ihrer Verbreitung, mit be- sonderer Rücksicht auf die asiatische Brechruhr. [2tes Heft.] 8°. *Altona*, 1831. L.

Stephans. Choléra; son origine, sa mar- che, sa nature, ses causes, moyens pré- servatifs . . . 8°. *Paris*, 1849.

Stephens (H.) Cholera: an analysis of its epidemic, endemic, and contagious character; with original and peculiar views of its mode of propagation and the means of counteracting it. . . . . 2d ed. 8°. *London*, 1849.

[3d ed., 1854.]

Stevens (W.) Treatise on the cholera, extracted from his work entitled "Ob- servations on the healthy and diseased properties of the blood." 8°. *New York*, 1832. L.

—— Observations on the nature and the treatment of Asiatic cholera. 8°. *Lon- don*, 1853. L.

Stieglitz. Unterscheidungs-Merkmale der einheimischen Brechruhr von der asiatischen Cholera.

[HUFELAND'S Jour. d. prakt. Heilk., 1831, LXXII, pp. 129-132.]

Stiemer (G. F.) Die Cholera: ihre Aetio- logie und Pathogenese; ihre Prophylaxe und Therapie, basirt auf den veränder- lichen Ozongehalt der Luft und dessen Einfluss auf die Athmung. 8°. *Königs- berg*, 1853. L.

Stillé (A.) A lecture on epidemic or ma- lignant cholera.

[PHILA. Med. Times, 1873, III, pp. 641-656; *also*, reprint in 12°, Philadelphia.]

Stilon (G. M.) Sul cholera morbus. Avvisi medici. 8°. *Malta*, 1839. L.

Stintzing (J. W.) Beiträge zur Nosolo- gie, Pathologie und Physiasiologie an asiatischer Cholera Leidender. 8°. *Al- tona*, 1833.

Story (W.) Cholera: its pathology, di- agnosis, and treatment. 8°. *London*, 1865. L.

Strahl (M.) Drei Fragen, die asiatische Cholera betreffend: I. Welches ist das Wesen der Cholera? II. Durch welche Mittel ist sie heilbar? III. Giebt es ein Praeservatif, und welches ist es? 12°. *Berlin*, 1837. L.

—— Abhandlung über die Cholera [in 4th ed. of his work "Über die wahren

Strahl (M.)—continued.
Ursachen der habituellen Leibesverstopfung", etc.] 8°. *Berlin*, 1853. L.

——— De Cholera, naar haar Wezen en naar hare Oorzaken wetenschappelijk onderzocht en de Leer daarvan door Ondervindingen gestaafd; benevens Wenken en Raadgevingen ter Afweering dezer Epidemie. 8°. *Emden*, 1857. L.

Strange (R.) Observations on the cholera-morbus of India, drawn from personal experience; with a consideration of the various remedies which have been tried in this disease; remarks on the similarity existing between the cholera and intermittent fever; and a proposal for a new mode of treating the cholera by the administration of oxigen gas.
[LANCET, 1830-31, II, pp. 644-649.]

Strehler (M.) Die morgenländische Brechruhr. Nach eigenen Erfahrungen. 8°. *Hamburg*, 1837. L.

Strickland (A.) Cholera: its symptoms and treatment. 12°. *Cincinnati*, 1866. L.

Stuart (J. H.) Cholera asphyxia.
[N. J. Med. Reporter, 1852, VI, pp. 109-116.]

Stucke (C.) Beitrag zur Erkenntniss der Natur und Heilung der Cholera. Nach eigenen Erfahrungen. 8°. *Cöln*, 1832. L.

Suerman (B. F.) Raadgevingen aan mijne Medeburgers, bij het Naderen der Cholera. 8°. *Utrecht*, 1832. L.

Sundelin (K.) Darstellung einer gründlichen Ansicht von dem Wesen oder der eigentlichen Ursache der Cholera; nebst einer genauen Angabe der Kennzeichen, Erscheinungen, des Verlaufs, der Ausgänge und der entfernteren, die Krankheit erzeugenden Ursachen und Schädlichkeiten derselben. 12°. *Berlin*, 1831. L.

Sutton (T.) Nature and treatment of cholera.
[LONDON Med. Gaz., 1832, IX, pp. 678-680.]

Szymkowicz (J.) Observationes de cholera epidemica. 8°. *Vilnae*, 1833.

Tadini (F.) Instruzioni onde preservare od almeno dimminuire d'assai la propagazione della pestilenza cholerica negli stati e nelle famiglie. 8°. *Parigi*, 1835.

Tallmann (M.) De cholera.
[EREL Diss. Med., II, p. 240.]

Tancrède. Choléra-morbus. 8°. *Mariy* 1849. L.

Tardani (G.) Risoluzione del problema sul choléra-morbus. 8°. *Roma*, 1855. L.

Tardieu (A.) Du choléra épidémique. 8°. *Paris*, 1849. L.

——— Treatise on epidemic cholera: being lectures delivered under the authority of the faculty of medicine of Paris. With an appendix by a fellow of the Massachusetts Medical Society. 8°. *Boston*, 1849. L.

Taussig (G.) Il cholera. Monografia. 8°. *Firenze*, 1854. L.

Taylor (J. T.) Cholera.
[N. O. Med. & Surg. Jour., 1866-67, XIX, pp. 157-173.]

Terlecki (S. H.) * De cholera. 8°. *Cracoviae*, 1833. L.

Terry (C. C.) On cholera: an account of its history, etiology, pathology, prophylaxis, and treatment.
[N. Y. Med. Jour., 1866, III, pp. 113-121, 196-202, 369-382.]

Teschemacher (P. A.) * De cholera asiatica. 8°. *Berolini* [1867]. L.

Tesnières. Note sur le choléra-morbus.
[REC. de Mém. de méd., de chirurg. et de pharm. Paris, 1830, XXIX, pp. 389-393.]

Thackrah (C. T.) Cholera, its character and treatment; with remarks on the identity of the Indian and English cholera. 8°. *Leeds*, 1832.

Théron (J. E.) Étude sur le choléra-morbus épidémique. 4°. *Paris*, 1855. L.

Thielmann. Cholera-Nachrichten.
[ALLG. Med. Central-Zeitg., 1847, XVI, pp. 791-792, etc.; 1848, XVII, pp. 15-16, etc.]

Thienemann (H. W.) Cholera.
[Neue Zeitg. f. Med. & med. Reform. 1849, I, pp. 483-485, 490-493.]

Thirault (J.) * I. Des symptômes de choléra-morbus épidémique. [etc.] 4°. *Paris*, 1840. L.

Thomas (P. F.) Mémoire sur le choléra asiatique. 8°. *Paris*, 1854. L.
[*From* BULL. de l'Acad. imp. de méd., XIX.]

Thommassenà Thuessink (E. J.) Een Woord over de gewigtige Vraag, is de asiatische Braakloop besmettelijk, of niet? 8°. *Groningen*, 1832. L.

Thompson (J. V.) The pestilential cholera unmasked, and its real nature and treatment developed; with proofs of its contagion, &c. *Cork*, 1832.

Thorbock (T. R.) On cholera.
[MED. Circular, 1865, XXVII, pp. 212-213.]

gri. Del cholera-morbus. *Milano*, 1856.

gri (A.) Sul tipo e sulla patologia generale del cholera-morbus.

[Omodei, Ann. un. di med., 1856, clviii, pp. 449-472.]

lesius (W. G. v. T.) Ueber die Cholera und die kräftigsten Mittel dagegen. Nebst Vorschlag eines grossen Ableitungsmittels, um die Krankheit in der Geburt zu ersticken. 8°. *Nürnberg*, 1830. L.

—— Neueste ableitende Behandlungsart der krampfartigen Cholera asiatica. Mit Abbildungen der Instrumenta dissoria der orientalischen Nationen. Nebst einer Abhandlung von J. Monat über die Cholera-Morbus, welche 1828 zu Berhampore in Indien beim 14ten Regimente geherrscht hat. Aus den Calcutta Transactions, v. iv, 1829, übersetzt und mit Anmerkungen begleitet. 8°. *Leipzig*, 1831. L.

—— Over de Cholera en de krachtdadigste Middelen daartegen. Uit het Hoogd. vert. en verm. door I. G. Hodenpyl. 1e Stukje. 8°. *Rotterdam*, 1831.

nn (G.) A practical treatise on cholera, and on muco-enteritis, or the disease misnamed Asiatic, malignant, or epidemic cholera. 8°. *Newcastle upon Tyne*, 1837.

asot (J.) Le choléra, sa nature et sa véritable cause. Moyens de le prévenir et de le guérir. *Paris*, 1850.

bler (T.) Die wandernde Brechruhr.

[Schweiz. Zeitschr. f. Nat. u. Heilk., 1838, iii, pp. 152-158.]

rtis (F.) Trattato clinico sul colera sporadico ed epidemico. 8°. *Napoli*, 1855. L.

urrette. Du traitement curatif du choléra-morbus épidémique, et de sa prophylaxie, suivi de quelques réflexions sur son mode de transmission. 8°. *Paris*, 1853. L.

ravers (J.)] Au peuple, sur le choléra-morbus. 12°. *Saint-Lô*, 1831.

eille. Choléra-morbus. Observations adressées à M. le rédacteur des "Annales de la médecine physiologique". 8°. *Paris*, 1832.

—— Conversations sur le choléra-morbus. 8°. *Paris*, 1832.

—— Quelques cas de choléra-morbus observés en 1831.

[Gaz. des hôp., 1832, vi, pp. 101-102.]

Treyden. Leichtfassliche Anweisung zur Erkenntniss und Behandlung der Cholera, für die Bewohner des platten Landes. 8°. *Königsberg*, 1831. L.

Triberti (A.) Pensamenti sulla malattia del cholera.

[Omodei, Ann. un. di med., 1832, lxii, pp. 353-367.]

[Trifet.] Choléra. Symptômes de la maladie. Premiers soins à donner aux malades. Traitement. [1849.] 4°. *Arcueil* [*n. d.*]

Tripi (B.) Sull'andamento del colera-morbo e suo metodo curativo nella comune di Cerda. 8°. *Palermo*, 1837.

Tristan (J. de, *père*). Études physiques sur le choléra de 1832. 8°. *Orléans*, 1849.

Troschel. Cholera.

[Med. Zeitg., Berlin, 1848, pp. 150, 154, etc.; 1849, pp. 120, 124, etc.; 1850, pp. 160, 180, etc.; 1851, pp. 4, 38, etc.; 1852, pp. 50, 180, etc.; 1853, pp. 172, 178, etc.]

Truckenbrod (J.) * Die Entstehung der neuen Form der Cholera nebst kurzgefasster Darstellung ihrer Verbreitung bis nach Deutschland. 8°. [*München*,] 1837. L.

Tucker. Essay on the nature and treatment of cholera, fever and cattle plague, and on public health. *Dublin*, 1865.

Turchetti (O.) Considerazioni etiologiche, nosogeniche, e therapeutiche sul cholera e visita fatta ai cholerosi di Calcinaja.

[Gaz. med. Ital. Tosc., Firenze, 1854, iv, 2a s., pp. 304-306, 311-312, 325-328, 336-338.]

Turck. De la nature du choléra, et des moyens de l'éteindre à sa source.

[Revue méd. franç. et étrang., 1833, i, pp. 201-206.]

Turinaz (J. J.) Conseils au peuple sur le choléra-morbus oriental. 16°. *Paris* [1832].

Turley (E. A.) Cholera: the nature of the poison, the part of the body first attacked, its development and self-generation in the blood, its first effects on the nervous and vascular systems, and its fatality thence arising, with observations on our means of defense against its infection, and the simple and rational method of treating this Asiatic pestilence, [etc.] 8°. *Worcester*, 1854. L.

Tuschek (M.) Ueber die Cholera. 8°. *Wien*, 1832.

Tyson (J.) A pathological explanation of

Tuson (J.)—continued.
cholera; and its symptoms, method of cure, etc.
[LONDON Med. & Surg. Jour., 1833, II, pp. 569-570.]

Tweedale (J.) Malignant European cholera.
[LONDON Med. Gaz., 1832, IX, pp. 389-391.]

Tweedie (A.) A practical treatise on cholera. 8°. *London*, 1832.

Twining (W.) A practical account of the epidemic cholera, and of the treatment requisite in the various modifications of that disease. 12°. *London*, 1833.

Tytler (R.) The malignant cholera.
[LANCET, 1834, II, pp. 669-670.]

Uffer (G. J.) Versuch einer Darstellung der Cholera-Morbus im Allgemeinen mit besonderer Rücksicht auf ihre im Jahre 1817 aus Bengalen hervorgegangene epidemische Form, die Entstehung, Verbreitung, [etc.] 8°. *Pesth*, 1831. L.

Ullmann (M.) Ueber Cholera.
[ZEITSCHR. f. Natur- u. Heilk. in Ungarn, 1855, VI, pp. 188-189.]

Vaidy (J. V. F.) Note sur le choléra-morbus.
[REVUE méd., 1823, XI, pp. 379-384.]

Valdes (J. M.) Memoria sobre el colera morbus, escrita de órden del supremo gobierno. 8°. *Lima*, 1838.

Valeria. Rapporto sulla memoria del dott. Jacquemono sul cholera.
[GIORN. d. R. accad. di med. di Torino, 1868, VI, 3a s., pp. 67-84; discussione, pp. 193-196.]

Valerius (A.) Quelques nouvelles considérations sur les causes et le traitement du choléra.
[JOUR. de méd., de chirurg. et de pharm., Bruxelles, 1866, XLIII, pp. 337-341.]

Varges (A. W.) Die asiatische Cholera.
[ZEITSCHR. d. deutsch. Chirurg.-Vereins f. Med., Chirurg. u. Geburtsh., Magdeburg, 1849, III, pp. 391-450; 1850, IV, pp. 313-319, etc.; 1852, V, pp. 558-584; 1853, VII, pp. 389-391.]

Varlez. Coup-d'œil sur le choléra-morbus asiatique. Traitement préservatif et curatif de cette maladie. 12°. *Bruxelles*, 1848. L.

Vassal. Considérations physiologiques et cliniques sur le choléra-morbus épidémique. 8°. *Paris*, 1833. L.

Vauréal (de). Genèse et indications du choléra-morbus épidémique. 8°. *Paris*, 1866. L.

Vavasseur (P.) Note sur l'épidémie de choléra-morbus. Extrait du Journal des connaissances nouvelles, mai 1832. 8°. *Paris* [*n. d.*] L.

Velpeau. Remarques sur le c[illegible] morbus.
[GAZ. des hôp., 1832, VI, pp. 253-254]

Venables (R.) The nature and [illegible]ment of the epidemic cholera. *London*, 1832.

——— On Asiatic cholera.
[MED. Times, London, 1848, XVIII, p. 2[illegible]

Verbeek (W. J. L.) Leefregelen [illegible] standhouding van de Gezondh[illegible] ter Voorbehoeding van den aan[illegible] Braakloop of Cholera. Wel[illegible] Raadgevingen voor Armen en L[illegible] 2de Druk. 8°. *Wijk* [1854].

Verdé de Lisle (N. M.) Traité th[illegible] et pratique du choléra-morbus cherches sur la nature, le siége[illegible] tômes et le traitement de cette ma[illegible] ainsi que sur les règles hyg[illegible] observer pour se préserver de [illegible] 8°. *Paris*, 1848.

——— The same. 3e ed. 18[illegible]

Vering. Observations on asiatic [illegible]
[LANCET, 1832-33, I, pp. 297-302.]

Vérollot. Du choléra-morbus [illegible] *Constantinople*, 1848.

Verweij. De Oorzaken en het W[illegible] tusschenpoozende Koorts en d[illegible] lera, benevens een Voorbehoe[illegible] tegen dezelve en eene doelma[illegible] handeling in den Aanvang. [illegible] venhage, 1859.

Vetch (J.) Pathology and tr[illegible] cholera.
[LONDON Med. Gaz., 1832, X, pp. 64-67]

Vetter (A.) Beleuchtung d[illegible] schreibens, die Cholera betreffe[illegible] Dr. Rust an A. von Humbo[illegible] Uebereinstimmung mit mehrere[illegible] tischen Aerzten Berlin's heraus[illegible] 8°. *Berlin*, 1832.

——— Toelichting van den Brief [illegible] besmettelijken Aard aziatische C[illegible] van Dr. Rust aan A. von Hu[illegible] Uit het Hoogduitsch van D. J. A[illegible] zenius. 8°. *Amsterdam*, 1832.

Vialle. Mémoire sur le choléra-[illegible] épidémique.
[ANN. de la méd. phys., 1833, XXIII, pp. [illegible] 1834, XXV, pp. 279-304.]

Vielguth (F.) Beiträge zur [illegible] der Cholera. 8°. *Wels*, 1831.

Vigil y Mora (F.) Mémoire sur [illegible] léra asiatique. 12°. *Bayonne*, [illegible]

Villain (B.) Recherches sur [illegible] choléra-morbus, sur les moyen[illegible]

llain (B.)—continued.
…server et de le traiter. 4°. [*Paris, d.*]

lar. Colera epidémico.
[GACETA med., Lima, 1866, II, pp. 75–77.]

ike. Ein Beitrag zur Cholerafrage.
[DEUTSHE Klinik, 1866, XVIII, pp. 126–127, etc.]

chow (R.) Offenes Schreiben an . . . chönlein [über Cholera].
[DEUTSCHE Klinik, 1855, VII, pp. 37–39.]

sánik (M. von). Die asiatische Cholera nach eigener Erfahrung an mehr als weitausend Cholerakranken, und mit Berücksichtigung aller darüber erschienenen vorzüglichsten Schriften für Aerzte und gebildete Laien. 8°. *Wien*, …56. L.

elkel (H. J. G. F.) *De cholera asiatica. 8°. *Berolini* [1855]. L.

gt (F. A.) Cholera und Rinderpest vor den Schranken der Humanität.
[ALLGEM. Intell.-Bl., München, 1867, XIV, pp. 361–…]

isin (J. C.) Quelques réflexions sur la maladie dite choléra-morbus, des moyens curatifs et préservatifs, du bandage du corps et des chaussettes prophylactiques de cette maladie. 8°. *Vannes*, …32.

izot. Réflexions sur le choléra asiatique, contenant un essai sur la dynamique des épidémies et quelques moyens de les atténuer par la purification de l'air. 8°. *Dijon*, 1855. L.

lpi (P.) Ai medici un pensiero sul holera-morbus. 8°. [*Lucca*, 1837.]

ltolini. Zur Cholera.
[ZEITSCHR. f. klin. Med., Breslau, 1856, VII, pp. 109–…]

agner (J.) *De cholera asiatica. 8°. *Pragae*, 1833. L.

ahu. Choléra.
[L'ABEILLE méd., 1854, XI, pp. 71–74.]

akefield (H.) Cholera.
[LONDON Med. Gaz., 1833, XI, pp. 482–483.]

alford (T. L.) Observations on Asiatic cholera.
[PROVINC. Med. & Surg. Jour., 1849, pp. 208–211.]

alshe (J. N.) Observations on cholera.
[DUBLIN Med. Press, 1849, XXI, pp. 155–156.]

ard (B.) Cholera.
[INDIANA Jour. of Med., 1872–73, III, pp. 199–206.]

asserfuhr (A. F.) Sendschreiben an seine Freunde in Stettin, wie sie sich beim Ausbruche der indischen Cholera zu verhalten haben, und was gegen die Krankheit selbst zu thun ist, bis der Arzt kommt. fol. *Bromberg*, 1831.

Wasserfuhr (A. F.)—continued.

Watkins (R. W.) Notes on cholera.
[BRIT. Med. Jour., 1865, II, pp. 414–416, 445–446.]

Watson (F.) Epidemic cholera.
[LONDON Med. Gaz., 1842, XXX, pp. 115–120.]

——— A lecture on cholera and diarrhœa.
[BRIT. Med. Jour., 1868, II, pp. 49–50.]

——— Lecture on the diffusion, pathology and treatment of Asiatic cholera.
[BRIT. Med. Jour., 1871, II, pp. 141–144.]

Wawruch (A. I.) Disquisito medica cholerae cujus mentio in sacris bibii occurrit. 4°. *Vindobonae* [1832]. L.

Webster (J.) An essay on the epidemic cholera, its contagious character, and treatment. With its mortality in London. 8°. *London*, 1832.

——— A letter to the president of the Westminster Medical Society on cholera. 8°. *London*, 1832.

Wedekind (G. F. von). Einige Bemerkungen über die Cholera.
[MED. Conversbl., 1831, pp. 345–347.]

——— Ueber die Cholera im Allgemeinen und die asiatishe Cholera insbesondere. 8°. *Frankfurt a. M.*, 1831. L.

Wedel (C.) Studien über die Cholera.
[ZEITSCHR. d. k. k. Ges. der Aerzte zu Wien, 1849, pp. 609–642.]

Wegener (H.) *Ueber asiatische Cholera. 8°. *Griefswalde*, 1868. C.

Weisenberg (A.) Auch eine Ansicht über die mögliche Abwehrung und Heilung der asiatischen Cholera. 8°. *Ansbach*, 1831.

Weissbrod. Mémoire sur le choléra. *Munich*, 1852.

Weissbrod (F.) Das Wesen der Cholera, asiatische Brechruhr. 8°. [*Altöt*, 1840?]

Weyland (G.) Traité sur le choléra asiatique. 8°. *Paris*, 1831.

Wheeler. A treatise on Asiatic cholera. 16°. *New York*, 1849. L.

White (W.) The Indian cholera.
[LANCET, 1831, II, p. 478.]

Whitmore (H.) On the pathology and successful treatment of cholera.
[LONDON Med. & Surg. Jour., 1839, I, pp. 404–405.]

Whitney (D. N.) The family physician, ... Together with the history, causes, symptoms and treatment of Asiatic cholera . . . [etc.] 8°. *New York*, 1834. L.

Whitney (E. *and* A. B.) Asiatic cholera: a treatise on its origin, pathology, treatment and cure. 12°. *New York*, 1866. L.

[Wibmer.] Brief in Dichtmaat aan de Cholera morbus. 8°. *Amsterdam*, 1832.

Wiedow (G. W.) * Beobachtungen über die Cholera. 8°. *Rostock*, 1850. C.

Wiewiorowski (A.) * De cholerae asiaticae pathologia et therapia. 8°. *Regimonti Pr.*, 1866. C.

Wilkinson (J.) On cholera. 8°. *Edinburgh*, 1832.

Wilkinson (J. J. G.) War, cholera, and the ministry of health [etc.] [From London ed.] 4°. *Boston*, 1855. L.

Wilks (S.) Observations on cholera.
[Assoc. Med. Jour., 1854, II, pp. 935–940.]

Will. Das Wesen, der Verlauf, die Fortpflanzung und die Behandlung der Cholera. 8°. *Königsberg*, 1850.

Willemin. Considérations sur le mode de propagation du choléra et sur les mesures prophylactiques applicables à cette maladie.
[Gaz. méd. de Strasbourg, 1866, XXVI, pp. 21–28.]

Williams (C. J. B.) Lecture on bilious and malignant cholera.
[Med. Times, 1843, XI, pp. 13–14.]

Wilson (G. A.) Observations on epidemic cholera.
[Stethoscope & Virg. Med. Gaz., 1854, IV, pp. 519–527, 1 table.]

Wilson (J. A.) Opinions on the nature and treatment of the Asiatic cholera, submitted to the "cholera committee" of the College of Physicians.
[Lancet, 1848, II, pp. 501–503.]

Winkler (J. M.) Die orientalische Cholera, ihre Geschichte und Entstehung, und bisherige Verbreitung, Verlaufsweise, Symptomen, ausführliche Vergleichung und Uebereinstimmung mit den vorzüglichen Contagionen, und die hieraus hervorgehende Folgerung ihrer Beschaffenheit und Vorbauungsweise. [1. Theil.] 8°. *Olmütz*, 1831.

Winslow (F.) The cholera, considered psychologically. 8°. *London* 1849. L.

Winslow (G. E.) Essay on the nature, symptoms and treatment of Asiatic cholera. 8°. *New York*, 1832. L.

——— A plain and practical description of Asiatic cholera, containing rules and directions for its prevention and treatment. 12°. *London*, 1848.

Winter. Ueber die Identität. zwischen der Cholera und der Mis der organischen Gewebe, vorzug der Organe des Unterleibes statt als Beitrag zur Aufhellung des Wes der Cholera.
[Med. Conversbl., Hildburghausen, 18 32, 33–35.]

Wise (T. A.) Cholera, its sym causes and remedies. 8°. *Cork*, 1

Witt (G.) * De cholera epidemica L orientalis. 4°. *Lugduni Bat.*, 18

Wolfart (K. C.) Hülfs-Tafeln w indische Cholera. 8°. *Berlin*, 18

Wolfert (A.) Le choléra-morbus. N velles observations sur son ... suivies d'une méthode de guérison. *Berlin*, 1865.

Wood (J.) Remarks on the cholera.
[Boston Med. & Surg. Jour., 1832, VI, pp. 3

Wrgl v. Hubenthal (C. P.) [Ver lung der orientalischen Cholera. *Petersburg*, 1832.

Wright. Cholera in asylums.
[Med. Times, 1852, V, pp. 60–61.]

Wright (N.) Essay on cholera.
[Chicago Med. Examiner, 1867, VIII, pp.

Wright (T.) Observations on the prominent traits of cholera.
[Clin. Lancet & Observer, 1866, II, pp. 25–5

——— The same. 8°. *Cincinnati*, 186

Wright (T. G.) Remarks on the ma nant cholera; its pathology and ... treatment.
[Lancet, 1832–33, I, pp. 625–628.]

Wronski (H.) Spiegazione di ... fenomeni del choléra-morbus, ed cazione dei mezzi per prevenire ... rimedio per combattere questo ter flagello. Traduzione dal Francese Dr. T. [Toffoletto]. 8°. [1a ed. ... *Vicenza*, 1865.

Wysokinski (A.) De cholera ... epidemico Indorum. 8°. *Vilnae* ...

Wyszewski (T.) De morbo chole ejus curandi modo. 8°. *Berolini* ...

Yandell (L. P.) The origin and ... ment of epidemic cholera.
[Amer. Practitioner, Louisville, 1871, IV, 225.]

Young (H.) Remarks on the ... morbus: containing a descriptio disease, its symptoms, causes, and ... ment, together with suggestions ... the best means of guarding ... attack; submitted to the ...

'oung (H.)—continued.
of the medical profession but designed principally for the use of the public in general. 8°. *London*, 1831. L.

'oung (J.) Observations on cholera morbus.
[AMER. Jour. of the Med. Sci., 1832, x, pp. 396–399.]

aiaczkowski (T.) Die epidemische Brechruhr, ihr Verlauf, ihre Verhütung und Behandlung nach eigenen, zahlreichen und neuen Beobachtungen geschildert. 12°. *Zürich*, 1837.

ehdniker (J.) *Nonnullae de asiatica cholera observationes. 8°. *Berolini*, 1832. L.

ehnder (C.) Die Cholera, die Art ihrer Verbreitung und die Maassregeln gegen dieselbe. 8°. *Zürich*, 1866.

eller (C. A.) Die asiatische Krampf-Brechruhr (Cholera). Der Schutz gegen dieselbe und ihre richtige Heilung. 12°. *Heilbronn und Leipzig*, 1854. L.

enker (H. T.) *De cholera. 8°. *Lipsiae*, 1850. L.

erfil (J. S.) Kurzgefasste Darstellung der asiatischen Cholera, ihrer Ausbildung und Fortpflanzung, und der sichersten, bis jetzt bekannten Vorbauungs- und Ableitungsmittel dagegen, damit diese Krankheit in der Geburt erstickt werde; [etc.] 8°. *Grätz*, 1831. L.

lgemeen nuttige Toelichting en Raadgeving betreffende de Cholera. 8°. *Nijm*, 1832.

nalyses of communications relative to the pathology, causes and treatment of cholera.
[LANCET, 1849, II, pp. 149–151, 237.]

nalyses of pamphlets on cholera.
[LANCET, 1849, II, pp. 14–17.]

nsichten und Vorschläge über die Auffindung des die asiatische Cholera insbesondere und andere ansteckenden Krankheiten überhaupt erzeugenden Urstoffes. 8°. *Leipzig*, 1831.

nweisung, wie man bei etwa eintretender asiatischen Cholera seine Gesundheit erhalten, die Krankheit erkennen, und der Ansteckung und Weiterverbreitung vorbeugen kann. Bekannt gemacht durch die oberste Sanitäts-Kommission zu Cassel. 12°. *Cassel*, 1831. L.

nweisung zur Erhaltung der Gesundheit und Verhütung der Ansteckung bei etwa eintretender Cholera-Epidemie.

Anweisung, *etc.*—continued.
Neue, revidirte Ausgabe. 8°. *Berlin*, 1831. L.

Asiatic cholera.
[BOSTON Med. & Surg. Jour., 1849, XXXIX, pp. 369–377.]

Asiatic (The) cholera, and its treatment.
[MED. Times, 1848, XVII, pp. 6–7, etc.; XVIII, pp. 181, 193, etc.; 1849, XIX, pp. 280, 643.]

Bekanntmachung [extr.]: Wenn gleich der mildere Character, den die Cholera bei ihrem Vorschreiten im nördlichen Deutschland gezeigt hat, . . . so hält es der Magistrat dennoch für seine Pflicht, die Bewohner hiesiger Residenz von denjenigen Maassregeln hiermit in Kenntniss zu setzen, [etc.] [Hannover 13. Oct. 1831.] fol. [*n. p., n. d.*] L.

Belehrung über die asiatische Cholera für Nichtärzte. Auf allerhöchsten Befehl in dem Königreiche Sachsen bekannt gemacht. 8°. *Dresden*, 1831. L.

Belehrung über die gegen die ansteckende oder asiatische Cholera anzuwendenden Schutzmaasregeln und ersten Hülfsleistungen. 8°. [*n. p., n. d.*] L.

Belehrung über die orientalische Cholera, für Nichtärzte amtlich bekannt gemacht. 8°. *München*, 1831. L.

Belehrung über die orientalische Cholera, für Wundärzte und nicht approbirte Kandidaten der Medizin, [etc.] 8°. *Köln*, 1831.

Bemerkungen über die Furcht vor der herrschenden Brechruhr, zugleich enthaltend eine wissenschaftlich begründete Vorstellung an die oberpolizeilichen und Gesundheitsbehörden zur Beruhigung des Publikums. 8°. *Leipzig*, 1831. L.

Beobachtungen über die epidemische Brechruhr und ihre Heilart. [Aus den vorgelegten Berichten der Wiener Aerzte zusammengestellt.]
[MED.-CHIRURG. Zeitg., Salzburg, 1832, I, pp. 241–256, etc.; *also*, reprint in 8°, Marburg, 1832.]

Bericht der epidemiologischen Section der Berliner medicinischen Gesellschaft über die Cholera-Frage.
[BERLIN. klin. Wochenschr., 1867, IV, p. 296.]

Bidrag til Kundskab om den epidemiske Cholera, dens Behandling og Forebygelsesmidler.
[BIBL. for Laeger, 1831, XV, pp. 209–276.]

Bijzondere Ziens wijze over de aziatische Cholera. Wat is hare Oorzak? Hoe werkt zij? 8°. *Leyden*, 1853.

Breve instruzione per la cognizione e cura del cholera-morbus, secondo le più recenti esperienze, scritta ad insinuazione della commissione speciale per la cholera residente in Berlino; traduzione dal Tedesco sulla seconda ed., con note del G. Pozzi. 8°. [1831.]

Cholera.

[BLUFF'S Leistung. d. Med., Berlin, 1833, I, pp. 161–220; 1834, II, pp. 217–248.]

Cholera.

[GAZ. med. it. prov. Venete, 1872, XV, pp. 331–336, 339–345, 355–359, 363–367, 374–376.]

Cholera. [Editorial.]

[NEW ORLEANS Med. & Surg. Jour., 1866–67, XIX, pp. 544–558.]

Choléra (Du) dit sporadique coïncidant avec l'influence cholérique actuelle et de son traitement.

[BULL. gén. de thérap., méd. et chirurg., Paris, 1849, XXXVII, pp. 337–342.]

Choléra (Le) et son traitement [signé : F. B.] 8°. *Paris*, 1865.

Choléra (Du). [Extrait du "Vigilant", du lundi, 2 avril 1832.] 8°. *Versailles* [1832].

Cholera (Die), ihre Präservativmittel, ihre Symptome und ihre Heilung. Nach praktischer Erfahrung zur Belehrung und Beruhigung niedergeschrieben von einem polnischen Arzte, und in's Deutsche übertragen von A. L. Nebst einem Anhang von Cholera-Anekdoten. 8°. *Ulm*, 1837.

Choléra (Le), les médecins, la médecine, ou examen raisonné de quelques erreurs populaires et hygiéniques; suivi de nouvelles propositions physiologiques, pour expliquer l'action des médicaments. 8°. *Paris*, 1832.

Choléra (Du). Moyens d'en reconnaître les premiers symptômes et d'en arrêter la maladie au début par une société de docteurs en médecine. 8°. *Paris*, 1865. L.

Choléra (Du). Notes écrites en 1845 par quelqu'un qui se fit infirmier des cholériques. 8°. *Toulouse* [1854].

Cholera-Angelegenheit.

[RHEIN. Monatssch. f. prakt. Aerzte, Köln, 1849, III, pp. 547–568; 1850, IV, pp. 44–61.]

Cholera-Arzt (Der), oder Abwehrung und erste Behandlung der Cholera, in so weit sie dem Nichtarzte überlassen werden kann. 12°. *Hamburg* [*n. d.*] L.

Cholera-Büchlein (Das) [zusammengestellt aus öffentlichen Blättern], worin die Erklärung des Wortes Cholera, die Kennzeichen dieser Krankheit, ihre Entstehung und Ausbreitung, und die gegen diese Krankheit empfohlenen bewährtesten Schutz- und Heilmittel enthalten. 16°. *Karlsruhe*, 1831.

Cholera fantasies.

[WEST. Jour. of Med. & Phys. Sci., Cinc. 0 [illegible] IX, pp. 13–24.]

Cholera-Maatregeln, voorgesteld door Griesinger, v. Pettenkofer en Wunderlich, vertaaldt door Gori. 8°. [illegible] 1866.

Choléra-morbus (Le) chez les enfans et son traitement.

[GAZ. des hôp., 1832, VI, pp. 91–92.]

Choléra-morbus (Du) et de son traitement. 8°. *Bourges*, 1832.

Choléra-morbus. Instruction à la portée de tout le monde. fol. *Lyon* [n. d.]

Cholera-morbus; its causes, prevention and cure. 8°. *Glasgow*, 1831.

Choléra-morbus (Le). Moyens à employer pour guérir de cette maladie, augmentés de l'histoire de ce fléau et de quelques réflexions sur la salubrité de la ville de Nantes. Par un médecin de cette ville. 8°. *Nantes*, 1832.

Cholera-Morbus (Die), oder die asiatische Brechruhr. Von einem praktischen Arzte. 8°. *Stuttgart*, 1831.

Cholera-Morbus (Die) oder asiatische Brechruhr. Eine für Jedermann fassliche Zusammenstellung des Wissenswürdigsten aus den vorzüglichsten, bisher über diese Krankheit erschienenen Schriften. 8°. *Tübingen*, 1831. L.

Choléra-morbus (Du), ou de l'asthénie des organes gastriques, par Alex. B. . . . *Rouen*, 1832.

Choléra (Du), ou plutôt principes généraux, théoriques et pratiques sur toutes les maladies en général et sur le choléra en particulier [signé D. . . . D. M. . . . *Toulouse* [1832].

Cholera, the precursor of great sanitary improvements.

[MED. Times, 1849, XIX, p. 274.]

Choleratic beguiratzeco harta bat diren moyenac. Cholera datenen eguiteco behar diren lehen bicico laguntzac. 4° *Bayonne* [1855].

Cholériques (Les) guéris et comment ont été guéris. 32°. *Paris*, 1849.

Conseils aux hospitaliers, aux veilleurs charitables et à toutes les personnes

Conseils, *etc.*—continued.
leur charité appelleront auprès des malades atteints par le choléra [1832]. 8°. *Lyon* [*n. d.*]

Considérations sur le choléra-morbus. 8°. *Marseille* [*n. d.*]

Considérations pratiques sur le choléra-morbus, et sur les moyens de s'en préserver.
[JOUR. de méd. et de chirurg. prat., Paris, 1837, VIII, pp. 433-437.]

Consolations cholériques, lettre touchant quelques considérations statistiques et morales au sujet du choléra. 8°. *Turin* [*n. d.*]

Copie de l'instruction sur la manière de se préserver et de se guérir du choléra, rédigée par MM. Bechut père, Bonfils père. 12°. *Vic*, 1832.

Correspondance et communications relatives au choléra.
[L'ABEILLE méd., 1865, XXII, pp. 305-308.]

Debate in the Harveian Medical Society of London on cholera, etc. 1866.

Détails curieux de la découverte importante d'une recette, pour se préserver et se guérir de la peur. Aventure arrivée à une dame de distinction qui croyait avoir le choléra. Manière dont elle fut guérir de la peur. 8°. *Paris* [1832].

Détails historiques sur le choléra-morbus, suivis de la manière aisée de le reconnaître et des moyens faciles à toutes les classes de s'en préserver. 8°. *Paris* [1832].

Deutsche (Die) Cholera-Commission.
[BERLIN klin. Wochenschr., 1873, X, pp. 382, 392, 623.]

Dialogue entre le curé de Lapège et son premier margouillis, ou instruction pour les soins à donner aux personnes attaquées de la maladie épidémique. 8°. *Foix* [1855].

[Discussion on cholera.]
[BULL. de l'Acad. roy. de méd. de Belg., 1848-49, VIII, pp. 386-422, et seq.; IX, pp. 99-124, et seq.—BULL. Soc. de méd. de Gand., 1849, XVI, pp 106-137, et seq.—(SOC. de méd. de Paris,) JOUR. de méd. prat., Paris, 1831, V, pp. 285-293; VI, pp. 5-6.—BULL. de l'Acad. de méd., Paris, 1874, XXXVIII, pp. 632-638; 1875, IV, 2e s., pp. 530-535.—GIORN. d. R. Accad. di med. di Torino, 1867, III, 3a s., pp. 256-265, 267-272.—BULL. N. Y. Acad. of Med., 1866, III, pp. 1-52.—(ST. LOUIS Med. Soc. Repts.,) ST. LOUIS Med. & Surg. Jour., 1859, XVII, pp. 216-221; 1866, III, n. s., pp. 249-262; 1873, X, n. s., pp. 396-401.—GAZ. med. d'orient, 1866-67, X, pp. 13-16, et seq.—WIEN. med. Presse, 1867, VIII, pp. 945-948.]

Diverses (Des) théories qui ont été proposées sur le choléra-morbus épidémique,

Diverses, *etc.*—continued.
et des méthodes curatives qui en découlent.
[ANN. de la méd. phys., Paris, 1832, XXI, pp. 461-552.]

Documenti (I) ed atti intorno alla peste orientale prodotti al congresso scientifico di Milano nel Settembre 1844, passati in rivista dalla commissione a ciò instituita, notificati al pubblico ed illustrati da un membro della medesima. 4°. *Milano*, 1845.

Einige Bemerkungen über die Cholera.
[MITTHEIL. d. bad. ärztl. Vereins, Karlsruhe, 1849, III, pp. 109-114, et seq.; 1854, VIII, pp. 143-144, et seq.; 1855, IX, pp. 143-144, et seq.; 1866, XX, pp. 128, 135-136, et seq.; 1867, XXI, pp. 146-147, et seq.]

Einige Worte über die asiatische Cholera. 4°. *Clausthal*, 1831. L.

Einige Worte über die Cholera-Morbus, nebst kurzer Hindeutung, was man bei ihrer allöopathischen Behandlung sowohl zu thun, als wie man sich bei Anwenden der homöopathischen Heilart zu verhalten habe, etc. 8°. *Oschatz*, 1831.

Einige Worte zur Beruhigung und Belehrung an meine Mitbürger, und besonders die Landbewohner, bei Herannäherung der gefürchteten Cholera. Hannover. Magazin, 1831, No. 82. 4°. [*n. p.*, *n. d.*] L.

Einige zeitgemässe Erinnerungen, die Cholera betreffend. Als Nachtrag über die Ausbildung, etc., derselben in den klin. Ann., 1831, H. III.
[HEIDLB. klin. Ann., 1831, VII, pp. 546-553.]

Ensaio á cerca de que ha de mais essencial sobre a cholera-morbus epidemica, redigi do pela commissão medica da Academia real das sciencias de Lisboa. 4°. *Lisboa*, 1833.

Entdeckung und Beleuchtung des bisher unbekannt gebliebenen Wesens und eigentlichen Sitzes der Cholera morbus, nebst der Darstellung der Behandlungsart und der Schutzmittel gegen dieselbe für Gesunde. Für Jedermann faslich dargestellt von einem erfahrnen, praktischen Arzt nach den sehr ausführlichen und bestimmten Aussagen einer besonders hellsehenden Somnambüle [Schlafwachenden]. 8°. *Hamburg* [*n. d.*] L.

Epidemic cholera.
[HORTON'S Dis. of Trop. Clin., London, 1874, pp. 290-385.]

Epidemic cholera: its mission and mystery, haunts and havocs, pathology and

Epidemic, *etc.*—continued.
treatment. With remarks on the question of contagion, the influence of fear, and hurried and delayed interments. By a former surgeon in the service of the East India Company. 12°. *New York*, 1866. L.

Epitome of the symptoms and treatment of cholera.
[LONDON Med. Gaz., 1831, VIII, pp. 404–410.]

Essai d'études sur la véritable manière d'envisager le développement du choléra pour 1850 et années suivantes. 8°. *Beauvais*, 1849.

Études sur la choladrée lymphatique ou choléra indien, et sur la fièvre jaune. Moyens préservatifs. 8°. *Paris*, 1835. L.

Examen de la doctrine physiologique appliquée à l'étude et au traitement du choléra-morbus. Suivie de l'histoire de la maladie de M. Casimir Périer par les rédacteurs principaux de la Gaz. méd. de Paris. 8°. *Paris* [1832]. L.

Facts relating to cholera.
[LONDON Med. Gaz., 1831, VIII, pp. 246–248.]

Five minutes' common sense about the Asiatic cholera, or short and plain rules for the prevention, management and treatment of the early symptoms of that disease, etc. By a fellow Roy. Coll. Surg. Eng. 5th ed. 12°. *London*, 1848.
[1st ed., 1831.]

Gedachten over de Theorie der Cholera. 8°. *Utrecht*, 1831. L.

Gemeinnützige Parallel- und Differenz-Tabellen, oder Gegeneinanderhaltung anderer Krankheitsformen mit der Cholera morbus, um durch deren tabellarisch dargestellten Unterschied die Erkenntniss derselben zu erleichtern, ihrer Verwechslung und den daraus entstehenden Missgriffen vorzubeugen; etc. 8°. *Wien*, 1832.

General-Bericht des Cholera-Ausschusses an den E. kleinen Rath. 8°. *Basel*, 1856. L.

Handbill (A) relating to cholera. [*London*, 1831.] L.

Heilung (Die) und Prophylaxis der asiatischen Cholera. Als Abschrift eines von J. E. Veith zu Wien auf Verlangen der königlich-bayerischen Regierung entworfenen Aufsatzes, vom Verfasser selbst beglaubigt und übersendet an C. v. Bönninghausen. 12°. *Hamm*, 1832.

Histoire détaillée du choléra-morbus [illegible] origine et extrait de l'acte officiel indiquant d'après les plus habiles médecins le moyen de s'en préserver. [illegible] *Paris* [1832].

Indole (Dell') astenica del cholera [illegible] introdotto si ultimamente in Europa. Riflessioni mediche del dott. H. G. [illegible] *Firenze* [*n. d.*]

Influenza and cholera.
[LANCET, 1836–37, II, p. 115.]

Instructio nou var un evess a ou gér[illegible] da guemer en amzer ar c'holera. [illegible] *Montroulez* [*n. d.*]

Instruction populaire relative au choléra morbus, en partie tirée de celle publiée en 1832 par la commission centrale établie à Paris, par L. C. H. P. 18°. *Besançon* 1854.

Instruction populaire sur le choléra sur les premiers soins à donner aux personnes qui en sont atteintes. 8°. [illegible] [1854].

Instruction populaire sur le choléra-morbus, et rapport fait à l'intendance sanitaire du Bas-Rhin par son comité médical et publié par cette intendance. [Signé : Lobstein, rapporteur.] *Strasbourg* [1832].

Instruction populaire sur les premiers signes du choléra et sur les soins à donner aux personnes qui en sont atteintes. [Extrait des rapports publiés par l'Académie royale de médecine.] 8°. *Paris* 1832. L.

Instruction pour les corps de troupe, les hôpitaux militaires, en prévision d'une épidémie du choléra . . . . [illegible] suivie de l'instruction relative à l'épidémie régnante. 8°. *Metz*, 1849.

Instruction relative au choléra-morbus de l'Inde, adressée par le conseil de santé aux habitants de la ville et du canton de Genève. 8°. *Lons-le-Saulnier* [1832].

Instruction sur le choléra-morbus contenant les moyens de s'en préserver, d'en guérir et d'empêcher sa propagation; publiée par les DDrs. E. Horn et G. Wagner. Traduite, etc., M. L. P. 8°. *Paris*, 1831.

Instruction sur le choléra-morbus, [illegible] près les principes et la méthode de Dupail, par J. C. 8°. *Paris* [1849].

Instruction sur le choléra, publiée par l'Académie des sciences. [illegible] [*n. d.*]

Instruction sur le choléra, rédigée par le conseil de salubrité du Bas-Rhin [1854]. 8°. *Strasbourg* [*n. d.*]

Instruction sur les symptômes, la marche et le traitement du choléra-morbus, suivie d'une observation de cette maladie récueillie par MM. Ansel, Courot, etc. 8°. *Auxerre*, 1832.

Instruction über das bei der Annäherung der Cholera in den k. preussischen Staaten zu beobachtende Verfahren. fol. *Berlin*, 1831. L.

Instructions de l'intendance sanitaire du département de la Moselle, à MM. les maires, aux habitants des villes, à ceux des campagnes, etc. 8°. *Metz*, 1831.

Instructions relatives au choléra-morbus, travail confié par la commission composée de MM. Parisot, Esquirol et Marc. 8°. *Paris*, 1832.

[Also, many other editions.]

Instructions simples et abrégées relatives au temps du choléra. 12°. *Poligny* [*n. d.*]

Korte Beschouwing der Oorzaken en het Wezen der Cholera asiatica; benevens eene eenvoudige Behandelingswijze dier Ziekte, zijnde een Mittreksel uit twee hoogd. Verhandelingen, door F. Jencken, etc. 8°. *Zierikz*, 1833.

Kunst (Die) Cholera-Krankheiten zu pflegen. 8°. *München*, 1832.

Kurze Anweisung zur Erkenntniss und Heilung der asiatischen Cholera. Nebst zwei kleinen, diese Krankheit betreffenden Aufsätzen. 8°. *Hannover*, 1831. L.

—— The same. [2te Ausgabe.] 8°. *Berlin*, 1831. L.

Kurze Anweisung zur Heilung der unter dem Namen Cholera-Morbus bekannten Krankheit, verfasst von dem Medicinalrathe in St. Petersburg, den 24. August 1823.

[HUFELAND'S Jour. d. prakt. Heilk., 1824, LIX, pp. 94-103.]

Laws (The) of cholera. 16°. *London*, 1866. C. L.

Letter to Dr. Barry, member of the central board of health in London, &c., &c., on the character and treatment of cholera. 8°. *London*, 1831. L.

Letters on cholera.

[Med. Times, 1849, XX, pp. 244-246, et seq.; 1850, XXI, p. 11.]

Letters on the cholera-morbus. By a professional man of thirty years' experience in various parts of the world. 8°. [*Dublin*,] 1831.

Lettre à un médecin de province sur le choléra-morbus.

[JOUR. de méd. prat., Paris, 1831, V, pp. 395-436; 1831, VI, pp. 119-139, etc.]

Lettre sur le choléra-morbus [16 octobre 1831]. Extr. du "Cri du peuple". 8°. [*Lyon*, 1831.]

Lettre sur l'origine et le traitement du choléra-morbus, par M. R. G. 8°. *Paris* [*n. d.*]

Maladies régnantes, choléra-morbus.

[JOUR. de méd. et de chirurg. prat., Paris, 1851, XXV, 2e s., pp. 241-243.]

Manuel complet préservatif et curatif du choléra-morbus, rédigé par plusieurs médecins.

Manuel des gens du monde au lit des cholériques. [Extr. de Broussais, Sophianopoulo, . . .] Par P. D. M. 8°. *Vitry-le-François*, 1832.

Medicinische Böcke von Aerzten, welche sich für infallible Herren über Leben und Tod halten, in der Cholera geschossen. 4°. *Bocksdorf und Schussbach* [*n. d.*] L.

Memorie sul choléra-morbus. Appendice al Bullettino delle scienze mediche, pubblicato per cura della Società med.-chirurg. di Bologna. [Fasc. 2.] 8°. *Bologna*, 1836. L.

Mittheilungen aus einer am Johannistage 1832 in der Loge zu den drei Degen zu Halle gehaltenen Rede. Zum Besten der durch die Cholera Verwaisten in Druck gegeben. 8°. *Halle*, 1832. L.

Mot (Un) sur le choléra-morbus, suivi d'une instruction pratique sur les moyens de le prévenir, de s'en préserver, de le combattre. 8°. *Epinal* [1854].

Mot (Un) sur le choléra; traitement rationnel de cette maladie; moyens simples de s'en préserver, par M. G. de C., qui a observé cette épidémie aux Indes, à Paris et à Londres. 8°. *Toulouse* [*n.d.*]

Nachricht über die Cholera, bekannt gemacht von dem Collegium Medicum des Königreichs Polen. Aus dem Polnischen übersetzt von F. D. 2te Aufl. 8°. *Danzig*, 1831.

Necessity of fixing upon some standard in cholera.

[LONDON Med. Gaz., 1832, X, pp. 612-613.]

Noermere Underretning om Cholera morbus m. v. tilligemed Beviis for at Kjobenhavn noeppe vil have dens komme at befrygte. 8°. *Kjobenhavn*, 1831.

Nota ed avertenze pratiche del consiglio superiore di sanità del regno d'Italia sul colera e pratiche per l'espenzo dei luoghi e degli oggetti che hanno servito ai colerosi. 8°. *Perugia*, 1873.

Notice sur la manière la plus certaine de se préserver du choléra et de le traiter, par un médecin de Tifflis. 8°. *Belleville* [1848].

Notice sur le choléra. 8°. *Paris*, 1832.

——— The same. 4°. [1866.]

Notice sur le choléra-morbus, sur son mode de propagation, ses causes, . . . et sur l'emploi des chlorures désinfectants. 15 avril 1832. 8°. *Paris*, 1832.

Notizie sul cholera-morbus, lette nella conversazione della Soc. del Gambinetto di Minerva in Trieste, etc. 4°. *Trieste* [1830].

Notizie sul cholera-morbus, ossia collezione delle principali memorie scritte intorno a questa malattia, riportate nei varj giornali scientifici inglesi, francesi, tedeschi ed italiani, dalla sua prima comparsa in Europa fino al presente, e ridotta ad intelligenza commune da V. Michelotti. *Livorno*, 1831.

Official paper on cholera. 12°. *Philadelphia* [?] 1832. L.

[*From* LONDON Med. Gaz.]

Official reports and analysis of publications on cholera. 8°. *Edinburgh, February*, 1832.

[EDINB. Med. & Surg. Jour.; suppl.]

On cholera [review].

[BRIT. & For. Med.-Chirurg. Rev., 1849, III, pp. 1–30; 1869, XLIII, pp. 405–425.]

On cholera: its nature and treatment: being the debate in the Harveian Medical Society of London. 8°. *London*, 1866. L.

Opinion du Dr. Menville sur les travaux et les transformations de . . . . . Paris . . . par rapport à l'hygiène publique et aux conditions de salubrité que Paris peut opposer avec succès à l'influence des épidémies, à l'invasion, à l'intensité du choléra et à la gravité de ses symptômes, suivie de considérations sur cette maladie et les moyens hygiéniques et thérapeutiques les mieux appropriés

Opinion, *etc.*—continued.

pour la combattre et la prévenir [etc.] 8°. *Paris* [*n. d.*]

Opinion of the consulting physicians · cholera, 1866. Boston city doc. 55. · [*n. p., n. d.*]

Origin (The), history, cause, prevent · and cure of cholera, with an account its progress and ravages through the world, and the latest and most successful treatment, endorsed and appr · by the medical faculty. By a New Y · physician. 4°. *New York* [*n. d.*] ·

Origine du choléra, ses causes, sa marc · et les moyens simples et peu dispendieux de le combattre et de s'en préserver. Le tout suivi d'une prière à · Roch, afin d'être préservé des maladies contagieuses et en particulier du choléra. 16°. *Bordeaux* [1850].

Osservazioni sul cholera morbus epi · mico, e suo metodo di cura; compo · dietro i rapporti dei medici di Vienna serventidi seguito ai rapporti dei med · Lombardi già inseriti negli Annali u · di med. [Omodei], fasc. di Nov. e · 1831, e Genn. 1832. 8°. [*n. p., n. d.*]

Papers relative to the disease called c · lera spasmodica. Published by author of H. M.'s privy council. 8°. *Lon* 1832.

Pathology and treatment of cholera.

[LANCET, 1865, II, pp. 544–546.]

Plus de choléra! Instruction, trait · et remède contre cette maladie. · *Marseille*, 1866.

Popular writers on cholera.

[LONDON Med. Gaz., 1831, VIII, pp. 736–7 ·

Praktische Beiträge zur Kenntniss · Behandlung der Cholera, gesam · und herausgegeben vom K. Rhein · Coll., Nr. I. und II. *Coblenz*, 1831.

Projet d'instruction sur le choléra · *Paris* [*n. d.*] ·

Publikum (Das) und die Aerzte wäh · der Cholera.

[WIEN. med. Wochenschr., 1854, IV, pp. 4 ·

Quelques faits nouveaux de choléra.

[GAZ. des hôp., 1847, pp. 553–556.]

Quelques mots sur le choléra.

[REVUE méd., 1865, II, pp. 385–397.]

Rapport et instructions pratiques s · choléra-morbus, rédigés et publ · près la demande du gouvernement · l'Académie royale de médecine.

[GAZ. des hôp., 1832, VI, pp. 145–150.

Rapport, *etc.*—continued.

—— The same. 8°. *Paris*, 1832. L.

Rapport sur le choléra-morbus, lu à l'Acad. roy. de méd. . . . les 26 et 30 juillet 1831. Signé Keraudren, Marc, Chomel, Desgenettes, Dupuytren, Louis, Emery, Boisseau, Desportes, Pelletier, Itard, Double. 8°. *Paris*, 1831. L.

Rapporto sul cholera, letto nell'adunanza della Soc. med.-fis. Fiorentina dalla commissione dei medici Landi, Gonelli e Lemmi. *Firenze*, 1854.

Rational view of the spasmodic cholera; by a physician. 12°. *Boston*, 1832.

Recherches sur les causes, la nature et le traitement du choléra asiatique. 1e partie. 8°. *Paris*, 1835. L.

Reclamation of Dr. Murray [on cholera].

[Brit. & For. Med.-Chirurg. Rev., 1871, xlvii, pp. 223-226.]

Recueil des faits les plus nouveaux et les plus intéressants sur le choléra-morbus de l'Asie. Publié par une société de savants étrangers et nationaux, sous la direction du docteur Justus Radius. Traduit de l'allemand par M. F. S. Ratier. 8°. [*n. p., n. d.*] L.

Réflexions de M. Dumanian à l'occasion d'un écrit sur le choléra, fait par un jeune docteur, client peut-être, et à coup sûr sans clients. 8°. *Toulouse*, 1835.

Réflexions sur le choléra-morbus, communiquées à l'Académie de médecine.

[Gaz. des hôp., 1831, v, pp. 219-220.]

Remarks on Dr. Abercrombie's suggestions on the characters and treatment of the malignant cholera. By a young physician. 8°. *Edinburgh*, 1832.

Réponse de l'abbé —— à M. Nicolas Pantaloup, auteur des commandements du choléra. 16°. *Marseille*, 1866.

Report of the College of Physicians of Philadelphia, to the board of health, on epidemic cholera. 8°. *Philadelphia*, 1832. L.

Report of the Royal Academy of Medicine to the minister of the interior, upon the cholera-morbus. Published by order of the French government. Translated from the French by J. W. Sterling. 12°. *New York*, 1832. L.

Report on spasmodic cholera, prepared by a committee under the direction of the counsellors of the Massachusetts Medical Society. 8°. *Boston*, 1832. L.

Report upon cholera. Royal Academy of Medicine of France. Translated by J. W. Sterling. 12°. *New York*, 1832. C. L.

Report (A) upon sundry documents relating to Asiatic cholera, transmitted by the governor of Rhode Island to the board of health of the city of Providence. 4°. *Providence*, 1865. L.

Reports on epidemic cholera.

[Brit. & For. Med.-Chirurg. Rev., 1855, xvi, pp. 137-144.]

Résumé des recherches et conseils du Dr. Récamier sur le choléra, pouvant servir de guide aux familles. 8°. *Beaune* [1854].

Sammlung der wichtigsten Abhandlungen über die jetzt herrschende Cholera-Seuche. Aus dem Englischen übersetzt von F. F. Reuss. 2 Th. in 1. 8°. *Stuttgart und Tübingen*, 1831. L.

CONTENTS.

1. Th. Nachrichten über die Cholera-Seuche, wie sie in Hindostan und in der indischen Halbinsel in den Jahren 1817, 1818 und 1819 geherrscht hat. Gesammelt und auf Verordnung der Regierung herausgegeben von der Medicinalbehörde in Bombay.
2. Th. Bericht über die Cholera-Seuche, welche das Gebiet der Präsidentschaft von Bengalen in den Jahren 1817, 1818 und 1819 heimgesucht hat. Auf Befehl der Regierung unter der Aufsicht der Medicinalbehörde aufgesetzt von Jacob Jameson.

Short (A) treatise on the cholera morbus; or Indian spasmodic cholera. *Cork*, 1832.

Sitzungs-Protokolle des Münchener aerztlichen Vereines während der Cholera-Epidemie 1873.

[Aerztl. Intell.-Bl., 1873, xx, pp. 596-597, 612-613, 657-659, 687-688, 717-719.]

Stimme aus Danzig über die Cholera. Zur Beruhigung aller, die sie fürchten. 8°. *Danzig*, 1831.

Stimme aus Hamburg zur Beruhigung.—Die Cholera morbus auf Isle de France, etc. 8°. *Leipzig*, 1831.

Sul cholera morbus. Nozione storiche e terapeutiche ed istruzioni sanitarie. *Parma*, 1831.

Sur la diarrhée et le choléra. [Discussion.]

[Bull. de l'Acad. imp. de méd., Paris, 1868, xxxiii, pp. 709-713, 724-744.]

Sur le choléra. [Discussion.]

[Bull. de l'Acad. nat. de méd., 1848-49, xiv, pp. 610-624, et. seq.]

Sur le choléra-morbus, opinion d'un médecin à ses confrères. 8°. *Lyon*, 1835.

Symptoms of the approach of Asiatic cholera.

[Med. Times, 1848, xviii, pp. 202, 227.]

Traité très-succinct sur le choléra-morbus. 8°. *Strasbourg*, 1831.

Ueber die Ausbildung, Fortpflanzung, Vorbeugungs- und Heilmittel der Cholera. [HEIDELBERG. klin. Annal., 1831, VII, pp. 329–360.]

Ueber die Natur der Cholera und ihre Heilung. Für Männer von Fach und als ein Rathgeber für das Haus. Von S. P. 8°. *Posen*, 1853. L.

Unterscheidungs-Merkmale der einheimischen Brechruhr von der asiatischen Cholera. Mitgetheilt von der kön. ärztlichen Prüfungsbehörde. 4°. *Hannover*, 1831. L.

Verdeeling der Stad Utrecht in Districten. Aanwyzing van Geneeskunstoefenaren in de onderscheidene Wyken en Instructien vor dezelven als anderzins in Zake der Cholera. 8°. *Utrecht*, 1832. L.

Verhüllte (Der) Bote, ein Gedicht. Zum Besten der durch die Cholera verwaiseten. 1831. 12°. [*Magdeburg.*]

Wesen und rationelle Therapie der Cholera, geschöpft aus Beobachtungen des Ausbruches zu Erding. F.G.K. *Wien*, 1854.

Wissenschaftliche Plenarversammlung des Doctoren-Kollegiums der medicinischen Facultät. Diskussion über Cholera. [WIEN. med. Presse, 1866, VII, pp. 879–880, 920, 943–944, 965–967, 988–989.]

Zur Beruhigung für Jedermann bei Annäherung der Cholera. Schreiben eines Familienvaters in St. Petersburg an seinen Freund in Deutschland. *Hamburg*, 1831.

III.—CAUSES AND PREVENTION.

A.—CAUSES, THEORIES OF CAUSATION, AND CONTAGION.

INCLUDING CHOLERA IN ANIMALS.

Adams (A. L.) Notes on certain meteorological phenomena in connection with cholera and other diseases. [MED. Times & Gaz., 1867, I, pp. 276, 305–306.]

Adamson (J.) Cause and cure of Asiatic cholera. 8°. *London*, 1851.

Agar de Bus (d'). Théorie des causes physiques qui produisent le choléra-morbus asiatique, et déterminent sa marche constante des frontières sud-est de l'Hindostan et de la Chine vers le pôle nord-ouest de l'Europe, présentée à l'Académie des sciences. 8°. *Issoudun*, 1849. L.

——— Institut de France. À MM. les membres de l'Académie des sciences. "Demande d'une enquête en orient, ayant pour objet de découvrir s'il y aurait en effet une coïncidence entre les éruptions volcaniques des mers de l'Inde, de la Chine, du Japon, et de l'Océanie, et l'apparition du choléra asiatique dans les divers états de l'Europe." 4°. *Issoudun*, 1849–50.

——— Théorie des causes physiques qui produisent le choléra-morbus en Asie et en Amérique. Nouvelle éd. 4°. *Châteauroux*, 1852. L.

——— Concours au prix Bréant, . . . Découverte des causes du choléra. 4°. *Issoudun* [1855].

Ailhaud de Brisis (A.-L.-H.) Étiologie du choléra-morbus épidémique, etc. 4°. *Paris*, 1840.

Alexandre. Lettre sur plusieurs cas de transmission du choléra. [GAZ. méd. de Paris, 1849, IV, 3e s., p. 2[illegible]

Alison (W. P.) On the communication of cholera by dejections. [EDINB. Med. Jour., 1865, II, pp. 481–482.]

Allsop (J.) Mode in which cholera is propagated. [LONDON Med. Gaz., 1832, IX, pp. 644–678.]

Alston (W.) Cholera: does it originate de novo? A sketch of prevalent opinions on the subject, with a remarkable case. [N. Y. Med. Jour., 1875, XXI, pp. 129–[illegible]

Ancelon. Note sur les conditions lesquelles se développe la contagion du choléra-morbus. [COMPT. rend. d. séanc. de l'Acad. d. sc., 1854, XXXIX, pp. 1086–1087; ann. sc. nat. et de méd., 1854, I, p. 1096.]

Andräas. Entstehung der Cholera aus Malaria. [ARZTL. Intell.-Bl., 1873, XX, pp. 3[illegible]

Archauer (A.) Zur Aetiologie der Cholera. 8°. *Erlangen*, 1856.

Arnoldi (F. A.) Wie kann eine Krankheit sich blos contagiös verbreiten, ohne dass am Krankenbette Ansteckung [illegible]

rnoldi (F. A.)—continued.
weisen ist? In Beziehung auf Cholera und gelbes Fieber erfahrungsgemäss beantwortet. 8°. *Köln*, 1836.

rnott (N.) Memorandum on Asiatic cholera and other epidemics as influenced by atmospheric impurity.
[APPENDIX to Rept. of the Com. for Scien. Inq. in Relation to the Cholera Epid. of 1854, Lond., 1855, pp. 168–175.]

tkinson (J. C.) Electrical phenomena in cholera.
[LONDON Med. Gaz., 1848, XLII, pp. 813–814.]

—— On the connection of meteorological phenomena with cholera, influenza, and other epidemic diseases.
[LANCET, 1850, I, p. 240.]

—— Meteorology and cholera.
[LANCET, 1853, I, n. s., pp. 322–323.]

udhoui (V.) Les causes occasionnelles du choléra indien.
[GAZ. hebdom. méd., 1873, X, 2e s., pp. 665–668.]

udouard. Les relations commerciales maritimes servent-elles à propager le choléra?
[REVUE méd., 1832, II, pp. 211–215.]

—— Sur la contagion du choléra.
[BULL. de l'Acad. nat. de méd., 1848–49, XIV, pp. 1113–1114.]

ugust (E. F.) Luftfeuchtigkeit und Cholera, ein meteorologischer Beitrag zur allgemeinen Charakteristik der Krankheit. 4°. *Berlin*, 1831. L.
[2d ed. in 1832.]

yenfeld (A.) De la cholérophobie.
[L'UNION méd., 1849, III, pp. 550–551, 553–554, 558.]

yres (P. B.) On the fungoid and animalecular theories of epidemic diseases.
[MED. Times, 1850, XXI, pp. 293–294.]

—— On the communicability of cholera.
[LANCET, 1858, II, n. s., pp. 574–575, 602–603.]

abbington (J. H.) Is the cholera contagious?
[LONDON Med. Gaz., 1849, XLIV, pp. 685–686.]

adham (D.) Cholera,—is it contagious?
[LONDON Med. Gaz., 1832, IX, pp. 298–299.]

aginski (A.) Berichtigung "zur Aetiologie der Cholera von Guttmann".
[BERL. klin. Wochenschr., 1867, IV, p. 481.]

allot (A. M.) Het Drinkwater in eenige onzer Steden uit een hygienisch Oogpunt beschouwed, vooral in Betrekking tot Cholera. 8°. [*n. p., n. d.*] L.

—— On impure water as a cause of the excessive mortality from cholera in Holland during the five epidemic visitations since 1832.
[MED. Times & Gazette, 1869, I, pp. 459–463.]

Baltz. Ueber die Nicht-Existenz eines Cholera-Contagiums.
[ALLG. med. Central-Zeitung, 1850, XIX, pp. 585–587, 593–596.]

Baly (W.) Report on the cause and mode of diffusion of epidemic cholera, in reports Royal College of Physicians. 8°. *London*, 1854. L.

Barbieri (F.) Su la trasmissibilità del coléra asiatico.
[GAZ. med. it. Lomb., 1856, I, 4a s., pp. 191–195.]

Barker (T. H.) On malaria and miasmata, and their influence in the production of typhus and typhoid fevers, cholera, [etc.]
[LANCET, 1863, I, pp. 607–608.]

Barry (D.) Propagation of cholera.
[LONDON Med. Gaz., 1832, X, p. 30.]

Bartoletti. Rapport à la conférence sanitaire internationale sur la marche et le mode de propagation du choléra en 1865.
[GAZ. méd. d'orient, 1866–67, X, pp. 149–160, 164–172.]

Bayard (A.) Sur la contagion du choléra.
[GAZ. des hôp., 1854, p. 343.]

Beaman (G.) The salt monopoly in India the alleged cause of cholera.
[LANCET, 1855, I, n. s., p. 417.]

Beaumont (*Le baron* de). Mémoire sur la formation et la contagion apparente des atmosphères cholériques, présenté à l'Académie des sciences. 8°. *Paris*, 1833. L.

Bedingfield (C.) "Asiatic cholera" in Hertz.—Its non-contagion.
[LANCET, 1840–41, I, pp. 87–88.]

Beesel. Ueber die Erscheinungen in der Natur beim Beginn der Cholera und über ihren möglichen Zusammenhang mit dieser Krankheit.
[MED. Zeitg., 1849, pp. 166–167, 177–178, 184.]

Beherens. Etiologia del colera epidemico.
[GACETA med., Lima, 1866, II, pp. 83–84.]

Bell (T. S.) Remarks on the cause of cholera.
[TRANSYLV. Jour. of Med., 1833, VI, pp. 475–489.]

Berti (A.) Delle pressioni barometriche in rapporto con le epidemie coleriche.
[GAZ. med. it. Lomb., 1857, II, 4a s., pp. 429–432, 437–442.]

Berti e Namias. Sulla contagiosità del cholera. *Venezia*, 1866.

Bertini (P.) Il cholera è, o no, contagioso? 8°. *Lucca*, 1854.

Bertulus (E.) Quelques mots sur la brochure de M. le Dr. Tholozan, intitulée:

Bertulus (E.)—continued.

"L'origine nouvelle du choléra asiatique".

[MARSEILLE méd., 1873, X, pp. 271–282.]

Bidder (F. H.) Erfahrungen über die Verbreitungsweise der Cholera.

[MAG. f. d. gesammt. Heilk., 1832, XXXVI, pp. 139–197; *also*, reprint in 8°, Berlin, 1832.]

Bidie (G.) The etiology of cholera, gleaned from the pages of its history, with practical remarks.

[MADRAS Quar. Jour. of Med. Sci., 1860, I, pp. 25–37.]

Bidlot (F.) Sur un mode particulier de contagion du choléra. Réponse à la note de M. le Dr. Romiée: "Sur les cimetières".

[ANN. Soc. méd.-chirurg. de Liége, 1874, XIII, pp. 221–248.]

Bidwell (E. C.) On the contagiousness of cholera.

[OHIO Med. & Surg. Jour., 1849–50, II, pp. 19–23.]

Biermer (A.) Ueber die Ursachen der Volkskrankheiten, insbesondere der Cholera. Ein populärer Vortrag gehalten in der ersten Versammlung der Gesellschaft für öffentliche Gesundheits-Pflege zu Zürich am 4. Nov. 1867. 8°. *Zürich*, 1867. L.

Bigelow (J.) Whether cholera is contagious.

[BOSTON Med. & Surg. Jour., 1866, LXXIV, pp. 89–92; *also*, *in* BUFFALO Med. & Surg. Jour., 1866, V, pp. 319–323.]

Billerey (F.) La contagion du choléra-morbus de l'Inde dénoncée et démontrée par les faits et le raisonnement, ou opinion d'un médecin de province sur la nature de cette maladie [etc., avec postscriptum]. 8°. *Grenoble*, 1832. L.

Billiard. Cause secondaire du choléra-morbus.

[COMPT. rend. d. séanc. de l'Acad. d. sci., Paris, 1854, XXXIX, p. 1087.]

Bini (F.) Se il cholera sia o no contagioso. Discorso.

[GAZ. med. it. Tosc., 1854, IV, 2a s., pp. 373–376, 381–385.]

——— Sull'etiologia del contagio del cholera. Discorso inaug. l'apertura delle scuole d'insegnamento nell'arcispedale di S. M. Nuova. *Firenze*, 1854.

Bird (H.) An antidote to the pernicious doctrines of non-contagion, with a review of a pamphlet lately published entitled "An essay upon the origin, symptoms, and treatment of cholera morbus, and other epidemic disorders, &c." 8°. *Chelmsford*, 1831. L.

Blumenthal (H.) Ueber die Ve[r]tungsart der Cholera.

[ST. PETERSB. Med. Zeitsch., 1865, II, pp. [illegible]; *also*, reprint in 4°, St. Petersburg. [illegible]

Blundell (E. S.) Production of c[holera] by rice amongst Belgian troops.

[LANCET, 1834, I, pp. 181–182.]

Böttcher (C.) Blicke in die Natur über die Bildung der Kohle aus der Kohlensäure, . . . über das Leben der [illegible] und Schlüsse die Cholera betreffend. *Altenburg*, 1839.

Boisseuil (E. A.) De la contagion d[u] léra. 8°. *Bordeaux*, 1856.

Bonnafont. Sur la contagion du c[holera]

[BULL. de l'Acad. nat. de méd., 1[illegible] 1110–1113.]

Bonnet (A.) Du mode de propaga[tion] choléra-morbus et des moyens pre[ventifs] qu'il réclame. 8°. *Bordeaux*, 1[illegible]

——— Du mode de propagation du c[holera]-morbus.

[L'UNION méd., 1856, X, pp. 183–184, 1[illegible]

——— De la contagion en général, [et] ticulier du mode de propaga[tion] cholera-morbus et de sa propl[hylaxie]. roy. 8°. *Paris*, 1866.

Bossu (A.) La contagion du ch[olera]

[L'ABEILLE méd., 1865, XXII, pp. 377–[illegible]

——— Le choléra est-il ou ne[n] gieux?

[L'ABEILLE méd., 1866, XXIII, pp. [illegible]

Boubée. Troisième note sur [les] tions géologiques du choléra.

[COMPT. rend. d. séanc. de l'Acad. [des] Paris, 1854, XXXIX, pp. 794–795.]

Bouchardat. Sur l'étiologie du c[holera]

[BULL. de l'Acad. de méd., Paris, 1[illegible] pp. 195–200.]

Boudin. Considérations sur [les] de propagation du choléra.

[GAZ. méd. de Paris, 1849, IV, pp. 53[illegible]

Boulay (F.-J.) *Des modes de pro[pa]tion du choléra. 4°. *Paris*, 1[illegible]

Bourdon (J.) Preuves de la con[ta]gion du choléra. Lues à l'Acad[émie] sciences, seance du 2 avril 1[illegible] [*Paris*, 1849.]

Boureau (F.) Choléra. Mode [de] gation et moyens préserva[tifs]. *Paris*, 1868.

Bowron (J. S.) Observations [on] original causes of malignant [fe]. *New York*, 1835.

Branson (F.) New hypothesis [to] for the presence of fungoid [gr]cholera.

[PROV. Med. & Surg. Jour., 1[illegible] pp. [illegible]

Brassington (G.) The contagiousness of cholera.
[DUBLIN Med. Press & Circ., 1866, II, pp. 421–422.]

Brault (L.) Observations de choléra-morbus contagieux.
[JOURN. univ. et hebd. de méd. et de chir., 1832, VIII, pp. 386–392.]

——— Remarkable cases indicative of the transmission of malignant cholera by human intercourse.
[LANCET, 1832-33, I, pp. 71–72.]

Breggen (F. van der). Bouwstoffen voor het Contagieuse der asiatische Cholera uit verschillende Schrijvers bijeenverzameld. Mit einen Brief aan Dr. C. G. Ontijd. 8°. *Amsterdam*, 1832. L.

Brierre de Boismont. De la contagion dans le choléra.
[L'UNION méd., 1849, III, p. 202.]

Brocard (J. L.) Choléra-morbus. Découverte du poison cholérique et préservatif. 16°. *Paris* [1865].

Brochard. Sur la contagion du choléra.
[L'UNION méd., 1850, IV, pp. 5–6, 9–10.]

——— Du mode de propagation du choléra et de la nature contagieuse de cette maladie. Relation médicale de l'épidémie de choléra qui a régné pendant l'année 1849 à Nogent-le-Rotrou (Eure-et-Loir). 8°. *Paris*, 1851. L.

Bron (F.) Note sur une cause probable de propagation du choléra.
[GAZ. méd. de Lyon, 1865, XVII, pp. 438–439.]

Bruck (C.) Le choléra ou la peste noire, son origine et ses conditions de développement. 8°. *Paris*, 1867. L.
[*Rapport en* BULL. de l'Acad. roy. de méd. de Belgique, 1868, II, pp. 421–441.]

Brunetti. Sugli agenti choleriferi. Lettera. 8°. *Milano*, 1872. L.

Bryne (B. M.) An essay to prove the contagious character of malignant cholera.
[MED. Mag., Boston, 1834, II, pp. 393–395.]

Bryson. On the infectious origin and propagation of cholera.
[MED. Times, 1851, II, n. s., pp. 506–510, 648–651, 666–671.]

Buchanan (G.) On Prof. von Pettenkofer's theory of the propagation of cholera and enteric fever.
[MED. Times & Gaz., 1870, I, pp. 283–285.]

Bucquoy (J.) Note sur deux nouveaux exemples d'importation et de transmission du choléra par des nourices.
[BULL. et mém. Soc. méd. des hôp. de Paris, 1866, II, pp. 240–242; 1867, III, pp. 256–258.]

Budd (W.) Malignant cholera: its mode of propagation, and its prevention. 8°. *London*, 1849. L.

Budd (W.)—continued.

——— Cholera: its cause and prevention.
[ASSOCN. Med. Jour., 1853, I, pp. 207–208, 231.]

——— Mode of propagation of cholera.
[LANCET, 1856, I, n. s., p. 379.]

——— Memoranda on Asiatic cholera, its mode of spreading and its prevention. 3d ed. Reprinted from the "Report of the special commission appointed to enquire into the cholera epidemic of 1861 in Northern India." 8°. *Bristol*, 1866.

Buek (H. W.) Die bisherige Verbreitung der jetzt besonders in Russland herrschenden Cholera; etc. 8°. *Hamburg*, 1831.

——— Die Verbreitungsweise der epidemischen Cholera, mit besonderer Beziehung auf den Streit über die Contagiosität derselben, historisch und critisch bearbeitet. 8°. *Halle*, 1832. L.

Buel (W. P.) Is Asiatic cholera contagious or communicable from person to person?
[N. Y. Jour. of Med., 1850, V, n. s., pp. 12–22.]

Bufalini (M.) 1., Esame degli esperimenti addotti in prova dello svilupparsi la coléra per contagio. 2., Alterazioni del sangue nei colerosi, e deduzioni dalle medesime ricavate. 3., etc.
[GAZ. med. Ital. Tosc., Firenze, 1855, I, 3a s., pp. 165–166, 173–174, 185–188, 193–199.]

Bulmer (T. S.) Cosmical view of chemistry, and its relations to cholera and other diseases. 8°. *Montreal*, 1866. L.

Burggraeve. Parasitisme du choléra.
[RÉPERT. de méd. dosimétr., 1872-73, I, pp. 543–545.]

Burq (V.) Choléra. De l'immunité acquise par les ouvriers en cuivre par rapport au choléra, enquêtes faites à ce sujet en France et en Italie. Préservation et traitement par les armatures et les sels de cuivre. Observations et expériences depuis 1849. 8°. *Paris*, 1867.

Byrne (B. M.) An essay to prove the contagious character of malignant cholera; with brief instructions for its prevention and cure. 2d ed., with additional notes by the author. 8°. *Philadelphia*, 1855. L.

Caffe (P.) Choléra, sa contagion. Rapport fait à la Soc. méd. d'émulation de Paris . . . 12°. *Paris*, 1853.

Calvy. Quelques considérations sur la contagion du choléra épidémique.
[L'UNION méd., 1866, XXXI, 2e s., pp. 145–152, 180–188.]

Cambrelin, *père*. Du choléra asiatique: est-il contagieux ?

[BULL. de l'Acad. roy. de méd. de Belg., 1867, I, pp. 456–510.]

——— Extrait de deux lettres, sur la contagiosité du choléra, adressées à M. le Dr. Lequime.

[BULL. de l'Acad. roy. de méd. de Belg., 1874, VIII, 3e s., pp. 967–972.]

Cameron (C.) New theory of the influence of variety in diet, tending to elucidate the nature and treatment of cholera, &c. 8°. *London*, 1832.

Campbell (J.) The contagiousness of cholera.

[MED. Circular, 1854, IV, p. 386.]

Candelon. Note sur la contagion du choléra.

[L'UNION méd., 1855, IX, pp. 13–14.]

Canstatt (C.) Darstellung und kritische Beleuchtung des Wesens der ostindischen Brechruhr (Cholera). 8°. *Regensburg*, 1831.

Cardinal (J. B.) * Essai sur la contagion dans le choléra-morbus épidémique. 4°. *Paris*, 1840. L.

Carpenter (A.) The causation of cholera.

[LANCET, 1871, II, pp. 771–773.]

Casotti (G.) Brevi cenni sulla contagiosità del colera. 8°. *Reggio nell'Emilia*, 1873.

[*Estratto dall* ITALIA centrale.]

Castle (A. C.) The Asiatic cholera traceable to certain electric influences.

[BOSTON Med. & Surg. Jour., 1849, XXXIX, pp. 351–357, 1 pl.]

——— Non-contagiousness versus "contagiousness of Asiatic cholera."

[BOSTON Med. & Surg. Jour., 1849, XXXIX, pp. 516–522.]

Cazalas. Examen pratique de la question relative à la contagion ou à la non-contagion du choléra.

[BULL. de l'Acad. Imp. de méd., 1865–66, XXXI, pp. 487–489; *also, in* GAZ. hebd. de med., 1866, III, 2e s., pp. 228–232.]

Chabasse. Quelques considérations sur l'étiologie et sur le traitement du choléra asiatique.

[L'UNION méd., 1863, XIX, 2e s., pp. 281–285.]

Chambay. De la contagion du choléra.

[L'UNION méd., 1849, III, pp. 221–222.]

Chapman (J.) Cholera poisons.

[MED. Times & Gaz., 1872, I, pp. 355–356.]

Charlton (E.) Illustrations of the propagation of Asiatic cholera by human intercourse.

[MED. Times & Gaz., 1854, VIII, pp. 374–375, 7 430.]

Charrier. Contagion du choléra.

[BULL. de l'Acad. nat. de méd., 1849–[illegible] pp. 649–650.]

Chauffard. Étude sur les diarrhées saisonnières et le choléra sporadique, et sur leurs prétendus rapports avec les épidémies cholériques vraies.

[REVUE de thérap. méd.-chirurg., Paris, [illegible] pp. 452–457.]

Chereau (A.) Des causes tangibles du choléra.

[L'UNION méd., 1865, XXVIII, 2e s., pp. [illegible]

Chervin (N.) Lettre à M. le président du conseil, ministre secrétaire-d'état au département de l'intérieur, touchant les expériences qu'il est urgent de faire pour s'assurer si le choléra-morbus est contagieux. 8°. *Paris*, 1831.

——— À propos de la contagion ou de la non-contagion du choléra-morbus.

[GAZ. des hôp., Paris, 1831, V, pp. 111–112.]

——— Du choléra-morbus; sa contagion ou non-contagion.

[GAZ. des hôp., Paris, 1832, VI, pp. 193–194, 203–204.]

——— Lettres à M. le ministre du commerce, et des travaux publics, sur la nécessité de former une commission spéciale pour recueillir les faits qui peuvent faire connaître le mode de propagation du choléra-morbus en France. [illegible] 1832.

Chorin (J.) Wie kann dem Umsichgreifen der Cholera Einhalt geschehen? *Prag*, 1855.

Clanny (W. R.) On the epidemic and endemic nature of the cholera.

[MED. Times, 1849, XX, p. 463.]

Clark (A.) Causes and nature of cholera.

[BUFFALO Med. & Surg. Jour., 1865–66, V, pp. 351.]

Clark (H. G.) The contagiousness of cholera.

[BOSTON Med. & Surg. Jour., 1857–58, III, 513–517; *also, in* PUBL. Mass. Med. Soc., II, pp. 245–250.]

Clarus (J. C. A.) Ansichten eines Vereins praktischer Aerzte in Leipzig über die Verbreitung der asiatischen Cholera auf doppeltem Wege. Mit einer diätetischen Haustafel für die Choleraszeit. [illegible] *sig*, 1831.

Clayton (W. B.) On the contagiousness of cholera.

[DUBLIN Med. Press, 1849, XXII, pp. 121–[illegible]

Clemens (T.) Reflexionen über Cholera-Aetiologie.

[DEUTSCHE Klinik, 1873, XXV, pp. 413–[illegible] XXVI, pp. 29–30, 157–158, 294, 326–327.]

Cogswell (C.) On the propagation of cholera by contagion.
[London Med. Gaz., 1849, xliv, pp. 752-755.]

Cohen (A.) Cholera en Drinkwater.
[Nederl. Tijdschr. v. Geneesk., 1867, i, pp. 312-313.]

Cohen (L. A.) Het Verband tusschen de Gesteldheid van den Bodem en het Heerschen van Cholera.
[Nederl. Tijdschr. v. Geneesk., 1862, vi, pp. 67-70.]

Cohn. Mikroskopische Untersuchungen des Trinkwassers während der Cholera-epidemie dieses Sommers.
[Wien. med. Presse, 1866, vii, pp. 1063-1064.]

Colin (L.) Le choléra; ses foyers; influence de l'air et de l'eau sur sa propagation.
[L'Union méd., 1873, xvi, 3e s., pp. 473-480.]

Colombe (L.) Du choléra-morbus, de son mode d'invasion, des preuves de sa non-contagion, de ses causes. 8°. *Paris*, 1832.

Copland. Age a predisposing cause of Asiatic cholera.
[Dublin Med. Press, 1846, xvi, p. 173.]

Cornish (W. R.) Observations on the level of sub-soil water in selected stations in reference to cholera prevalence.
[Rept. Sanitary Commissioner for Madras, 1871, app. ii, pp. xiv-xvi, 5 charts.]

Cowdell (C.) A disquisition on pestilential cholera: being an attempt to explain its phenomena, nature, cause, prevention, and treatment, by reference to an extrinsic fungous origin. 8°. *London*, 1848. L.

Cowdell (C.) [*and others*]. The cholera and Dr. Brittan's views.
[Med. Times, 1849, xx, pp. 272, 285-286, 290.]

Cozzi (A.) Osservazioni di fisica medica sul coléra morbo.
[Gaz. med. Ital. Tosc., Firenze, 1855, i, 3a s., pp. 369-372, 389-394, 397-402, 428-430.]

Crocq. De la contagion du choléra.
[Bull. de l'Acad. roy. de méd. de Belgique, 1866, ix, pp. 900-924.]

—— Cholera contagion.
[Lancet, 1871, ii, p. 612.]

Crudeli (C. T.) Stato attuale delle nostre cognizioni sulla propagazione del cholera asiatico e sui mezzi più acconci a limitarla od impedirla.
[L'Imparziale. Firenze, 1868, viii, pp. 233-240, 270-274, 299-310.]

Cunningham (D.) Untersuchungen über Pettenkofer's Theorie auf Madras angewendet.
[Ztschr. f. Biologie, München, 1872, viii, pp. 267-293.]

Cunningham (D. D.) *and* **Lewis** (T.) Scientific investigation into the causes of cholera. [Plates.]
[Lancet, 1869, i, pp. 3-4, 38-41, 76-78.]

Cunningham (J. M.) On the propagation of cholera in India.
[Brit. Med. Journal, 1874, i, pp. 137-138.]

Cuvry (de). Die äusseren oder epidemischen Ursachen der Cholera.
[Med. Zeitung, 1848, p. 194.]

Daffner (F.) Ueber die Ursachen der Cholera. 8°. *München*, 1868. L.

Damon (H. F.) A communication from the city physician on Asiatic cholera. Is it a contagious disease? 1866. 8°. *Boston*, 1866. L.

Danet (G. A.) * De l'alimentation insuffisante, comme cause prédisposante au choléra. 4°. *Paris*, 1857. L.

Davey (J. G.) Cholera perhaps ascribable to disease of the solar plexus.
[Lancet, 1842-43, i, pp. 121-123.]

Decaisne (E.) La théorie tellurique de la dissémination du choléra et son application aux villes de Lyon, Versailles et Paris en particulier. [Extrait d'un mémoire.]
[L'Union Med., 1874, xxviii, pp. 929-930.]

Deloche (D.) Étude sur le choléra. Théorie sur la manière dont le fléau distribue ses coups dans les localités qu'il ravage. Application de cette théorie à la mortalité cholérique due aux quatre épidémies que la ville de Nimes a subies. 8°. *Paris*, 1867. L.

Demonchaux (J.-L.-C.-E.) * Réflexions sur les causes occasionnelles et le mode de transmission du choléra-morbus épidémique, déduites de faits recueillis à Saint-Quentin et aux environs. 4°. *Paris*, 1833. L.

Derblich. Die Frage über die Verbreitungsweise der Cholera.
[Allg. militärärztl. Zeitg., Bige. zu "Wien. med. Presse", 1866, vii, pp. 373-374.]

De Renzy (A. C. C.) The water theory of cholera, and the Indian sanitary commission.
[Med. Times & Gaz., 1871, i, pp. 411-412.]

Descourtilz. Probabilités sur la cause du choléra.
[Gaz. des hôp., 1832, vi, pp. 291-292.]

Desmartis (T., *fils*). Causes et préservatifs du choléra et des maladies contagieuses. 8°. *Paris* [*n. d.*] C.

Desportes (E.) Exposition succincte de faits divers et d'idées critiques concernant la propagation du choléra de l'Inde. 8°. *Paris*, 1851. L.

Despres (A.) De la non-contagion du choléra. [Résumé of Stanski's work.]
[Gaz. des hôp., 1866, pp. 365–366, 381–382.]

Dickson (S.) Revelations on cholera; or its causes and cure. 12°. *London*, 1848. L.

——— The same. 8°. *New York*, 1849. L.

Dickson (S. H.) On the communicability of cholera.
[Amer. Jour. of the Med. Sci., 1833, xiii, pp. 359–366.]

Dinger. Zur Aetiologie der Cholera.
[Archiv der Heilk., 1867, pp. 94–95.]

Documents on the hypothesis which ascribes cholera to the presence of fungi.
[Edinb. Med. & Surg. Jour., 1850, lxxiii, pp. 81–118.]

Dörne (F.) Louis Stromeyer zu Danzig in Ostpreussen. Ein Beitrag zur Geschichte der Cholera-Contagionisten. 8°. *Altenburg*, 1832.

Donovan (D.) Contagiousness of cholera.
[Dublin Med. Press, 1849, xxii, pp. 406–408.]

Doorjak (C.) Mémoire sur le développement, les causes et le traitement du choléra. 8°. *St. Pétersbourg*, 1848. L.

Douglas (J. C.) An examination of some of the principal points in cholera hypotheses.
[Madras Quar. Jour. of Med. Sci., 1867, ii, pp. 76–102.]

Downing (T.) The proximate cause and treatment of epidemic cholera.
[Med. Times, 1849, xx, pp. 425–426.]

——— On the proximate cause of epidemic cholera.
[Med. Times, 1849 xx, p. 464.]

Drasche. Die Cholera und der Krieg.
[Wien. med. Wochenschr., 1866, pp. 651–655.]

Dubarry (L.) * De la contagion du choléra, et de son traitement. 4°. *Paris*, 1851. L.

Duboir (H.) Recherches sur l'origine et la nature du choléra d'Asie et traitement de cette maladie. 8°. *Soissons*, 1832. L.

Duckes. Zur differentiellen Diagnostik und zur Theorie der contagiösen Natur der Cholera.
[Zeitschr. f. Natur- u. Heilk. in Ungarn, 1857, viii, pp. 97–101.]

Duvernoy (G.) Einige Bemerkungen, die Contagiosität der asiatischen Cholera betreffend.
[Med. Correspbl. des württemberg. aerztl. Vereins, 1837, vii, pp. 417–423, 425–430.]

Ebsworth (A.) The communication of cholera poison from man to man.
[Med. Times, 1849, xx, pp. 380, 464.]

Ehrenberg (C. G.) Ein Wort zur Zeit über Erfahrungen über die Pest im Orient und über verständige Vorkehrungen zur Pest-Ansteckung zur Nutzanwendung bei der Cholera. 8°. *Berlin, Posen, Bromberg*, 1831. L.

Eichhorn (G.) Das Wesen der Cholera.
[Zeitschr. f. d. gesammt. Med., 1865, iii, pp. 289–293.]

Eissen (E.) Lettre sur la contagion du choléra.
[Gaz. méd. de Paris, 1866. xxi, pp. 193–195.]

——— La doctrine réaliste et la doctrine fantaisiste du choléra indien.
[Gaz. méd. de Strasbourg, 1867, xvii, pp. 249–256, 270–271; *also*, reprint in 8°, Strasbourg, 1868.]

Eitner. Ist die Cholera ansteckend?
[Med. Zeitg., 1852, pp. 199–200.]

Erichsen (J.) Bemerkungen über Ausbreitungsart und den bisherigen Gang der Cholera zur Zeit ihrer ersten Pandemien.
[St. Petersb. med. Zeitschr., 1866, i, pp. 335; *also*, reprint in 4°.]

Espagne (A.) Immunité cholérique observée en 1849 et 1854 dans les salles des maladies vénériennes et cutanées des hôpitaux de Montpellier.
[Gaz. hebd. de méd. et de chirurg., 1866, pp. 584–585.]

——— De la transmissibilité du choléra.
[Gaz. hebd. de méd. et de chirurg., 1866, pp. 276–280.]

Evans (J.) Observations upon the nature of Asiatic cholera, and its communicable nature.
[North-Western Med. & Surg. Jour., vi, pp. 245–285.]

——— The same. 8°. *Chicago*, 1867.

Evans (M. A.) Facts bearing on the American etiology of cholera.
[Lancet, 1854, i, pp. 624–625.]

Falger (F.) Der Ansteckungs-Process. Cholera-Pilz mittelst der Luft künstlich gestellt durch Ueberleitung von Pilzsporen auf Gährungsstoffe etc. *Munster*, 1867.

Faraday (M.) The state of the Thames, the public health and the cholera.
[Lancet, 1855, ii, n. s., p. 41.]

Fauconnet. Du choléra asiatique, sa conséquence d'un élément morbide de nature organisée. Concours pour Bréant. 8°. *Paris*, 1866.

Fauvel (A.) Rapport à la conférence sanitaire internationale sur les questions du programme relatives à l'origine, à l'endémicité, à la transmissibilité et à la propagation du choléra.

[Gaz. méd. d'orient, 1866–67, x, pp. 85–94, 100–110, 118–127, 131–140; *also*, reprint in 8°, Constantinople, 1866.]

—— Ueber Ursprung und Verbreitungsart der Cholera. Commissionsbericht der internationalen Sanitäts-Conferenz. Autorisirte deutsche Ausgabe. 8°. *München*, 1867. L.

Fennings (A.) The volcanic cause of epidemic cholera. 1855.

Ferrand. Sur la transmissibilité du choléra.

[L'Union méd., 1868, xxxii, 2e s., pp. 253–255.]

Ferrari (M.) Due parole intorno l'articolo contagion del colera-morbus, publicato dal dott. Valleix, nella Guide de médecin praticien, ed. del 1850, t. II, p. 692.

[Gaz. med. it. Lomb., Milano, 1854, v, 3a s., pp 395–396.]

—— Su le condizione locali favorevoli allo sviluppo del colera morbus del dott. Sella.

[Gaz. med. it. Lomb., Milano, 1854, v, 3a s, pp. 413–414.]

Fesq (A.) *Essai sur la non-contagion du choléra-morbus. 4°. *Paris*, 1835. L.

Figuier (L.) De l'ozone à propos du choléra.

[Gaz. hebd. de méd. et de chirurg., 1853–54, I, pp. 902–905; 1855, II, pp. 156–157.]

Fischer (A. F.) Es wird Tag!—Deutschland darf die herrschende Brechruhr (Cholera) nicht als Pest und Contagion betrachten. 8°. *Gotha*, 1832.

Flemming (*jun.*) Cholera und Ozon.

[Allg. med. Central-Zeitung, 1855, xxiv, pp. 785–791.]

Fleury (C.-A.) *I. Étiologie du choléra-morbus épidémique. [etc.] 4°. *Paris*, 1840. L.

Förster (R.) Die Verbreitung der Cholera durch die Brunnen. 8°. *Breslau*, 1873. L.

—— Das Wasser als Träger des Cholera-gifts.

[Allg. Ztschft. f. Epidemiol., Erlangen, 1874, I, pp. 81–93.]

Foissac. Considérations sur l'origine, les causes et le mode de propagation du choléra.

[L'Union méd., 1865, xxviii, 2e s., pp. 97–100, 163–168, 193–197.]

Forster (T.) On the atmospherical and terrestrial commotions which have accompanied the cholera morbus of the present period.

[Lancet, 1831–32, I, pp. 113–114.]

Fortina (F.) *Sur la nature probable du choléra-morbus asiatique et sur son mode de transmission. 4°. *Paris*, 1858. L.

Fourcault. Causes générales du choléra asiatique. Première application de la géologie à la médecine.

[L'Union méd., 1848, II, pp. 475–476.]

—— Conditions géologiques et hydrographiques qui favorisent le développement et la marche du choléra asiatique.

[Gaz. méd. de Paris, 1849, IV, pp. 7–10, 157–161.]

French (J. G.) On contagion, in reference to typhus fever and Asiatic cholera.

[London Med. Gaz., 1848, xlii, pp. 675–677.]

Friedberg (H.) Zur Verbreitung der Cholera.

[Allg. Ztschft. f. Epidemiol., Erlangen, 1874, I, pp. 94–97.]

Friedmann. Neuere Erfahrungen und Ansichten über Temperatur der Luft, Jahreszeit und Luftverunreinigung als disponirende Momente zur asiatischen Cholera.

[Deutsche Klinik, 1867, xix, pp. 337, 345, 367.]

Frizon (A. B.) Coup-d'œil sur les diverses opinions émises concernant les causes productrices du choléra-morbus épidémique. 8°. *Marseille*, 1836.

Fuller (H. W.) On certain points relating to cholera.

[Lancet, 1867, I, pp. 37–39.]

Funcke (F.) *Choleram Asiaticam non esse contagiosam paucis ostenditur. Praemittuntur quaedam e contagiorum doctrina. 16°. *Berolini*, 1831. L.

Furnell (M. C.) The etiology of cholera.

[Madras Quar. Jour. of Med. Sct., 1867, II, pp. 103–104.]

Gairdner (W. T.) The fungous theory of cholera.

[Med. Times, 1849, xx, p. 344.]

Galli (A.) La non contagione del colera-morbus combattuta. *Novara* 1855.

Garin (J.) Sur la prétendue contagion du choléra de Craponne.

[Gaz. méd. de Lyon, 1854, VI, pp. 309–311.]

Gendron (A.) Lettre sur quelques cas de transmission du choléra-morbus. (3 cases.)

[Gaz. méd. de Paris, 1832, III, pp. 484–485.]

Géorgiade (A.) Mémoire sur la contagion des maladies exotiques, telles que la peste orientale, le choléra-morbus, la

Géorgiade (A.)—continued.
fièvre jaune, etc., où il est démontré que les miasmes de ces maladies ne peuvent jamais infecter l'air atmosphérique, ni se propager par lui, et qu'ils se communiquent seulement par le contact immédiat. 8°. *Paris*, 1832. L.

Gérard (A.) Théorie de l'antagonisme et de la pondération appliquée au choléra asiatique, aux fièvres et autres dérangements de la circulation. 8°. *Verdun*, 1856.

Giordano (S.) What causes cholera?
[Med. & Surg. Reptr., 1872, xxvii, p. 18.]

Giromini (F.) Se il cholera morbus è epidemico o contagioso, e della causa che impedisce a molti medici di accogliere la verità in proposito.
[Gaz. med. it. Lomb., 1850, iii, 2a s., pp. 43-44, 49-54.]

Gleich. Aufklärung über das Wesen der Cholera.
[Putzar's Jour. f. naturgem. Gesundh.-Pflege, 1855, iii, pp. 321-324.]

Goblin. De la non-contagion du choléra-morbus, suivie du charlatanisme dévoilé. 18°. *Paris*, 1832.

Goudas (A. N.) Sur la contagion du choléra et sur l'efficacité des mesures quarantenaires contre sa propagation.
[Gaz. méd. de Paris, 1850, v, p. 612.]

Gibson (W. A.) Reasons why cholera should be regarded as a contagious disease.
[St. Louis Med. Reptr., 1866-67, i, pp. 437-441.]

Graslin (L. F.) Dissertation critique sur les seules causes possibles tant du choléra-morbus que de toutes les maladies contagieuses, et sur la nature des seuls remèdes qui puissent les combattre avec succès. 4°. *Paris*, 1832.

Graves (R. J.) Letter on the contagiousness of cholera.
[Dublin Quar. Jour. of Med. Sci., 1848, vi, pp. 475-476; 1849, vii, pp. 1-39.]

——— Observations on cholera, and especially on its mode of propagation.
[Dublin Quar. Jour. of Med. Sci., 1850, x, pp. 257-286.]

Greenhow (E.) Contagiousness of cholera.
[London Med. Gaz., 1832, ix, pp. 471-472.]

——— Alleged exemption of Jews from cholera.
[Lancet, 1855, i, n. s., p. 50.]

Gregory (G.) Cholera an imported disease.
[London Med. Gaz., 1833, xi, p. 479.]

Grieve (J.) Contagiousness of cholera. Dumfries.
[Month. Jour. of Med. Sci., Edinburgh, 3d s., pp. 193-194.]

Grove (J.) The vitality of the cholera fungi demonstrated.
[Lancet, 1849, ii, n. s., pp. 427-429, 457-458.]

Guérard *et* **Delasiauve.** Communication sur le choléra.
[Bull. et mém. Soc. méd. des hôp. de Paris, iii, pp. 207-208.]

Guibout (E.) Du mode de transmission du choléra.
[L'Union méd., 1854, viii, p. 429.]

Guttmann (P.) Beobachtungen zur Aetiologie der Cholera und Infectionsversuche bei Thieren.
[Berlin. klin. Wochenschr., 1867, iv, pp. 77-84.]

——— Erwiederung auf die "Berichtigungen" des Dr. Baginski.
[Berlin. klin. Wochenschr., 1867, iv, p. 4[illegible].]

Hahnemann (C. F. S.) Aufruf an sterbende Menschenfreunde über die Ansteckungsart der asiatischen Cholera. 8°. *Leipzig*, 1831.

Hall. Non-contagiousness of the cholera.
[Nashv. Jour. Med. & Surg., 1858, xv, pp. [illegible].]

Hallier (E.) Das Cholera-Contagium. Botanische Untersuchungen. Aerzten und Naturforschern mitgetheilt. *Leipzig*, 1867.

——— Die Cholera-Untersuchungen der Engländer in Ostindien.
[Zeitschr. f. Parasitenk., Jena, 1868, i, pp. 219.]

Halmagrand. Le choléra est-il contagieux? 8°. *Paris*, 1866.

Hamilton (F. H.) Vegetable matter as one of the exciting causes of Asiatic cholera; being a report on the immediate exciting cause of the Asiatic cholera which appeared in Buffalo, N. Y. Also the report of a committee appointed to investigate the relation of epidemics of the soil to the causation of the cholera. 8°. *Buffalo*, 1852.

Hammer. Is cholera a contagious disease?
[St. Louis Med. & Surg. Jour., 1851, ii, p. 312.]

Hardie (G. K.) Cholera. Illustrating the doctrine of contagion in cholera, drawn from the epidemics of 1854-56, at Mauritius.
[Dublin Quar. Jour. of Med. Sci., 1857, i, pp. 233-249.]

Hartshorne (H.) On animal decomposition as the chief promotive cause of cholera. 8°. *Philadelphia*, 1855. L.

Harty (W.) On the contagion of cholera.
[Dublin Jour. of Med. Sci., 1833, II, pp. 74–86.]

Harwood (T.) Contagiousness of cholera.
[London Med. & Surg. Jour., 1833, II, pp. 363–364.]

Haskins (E. B.) Some remarks on the febrile stage of epidemic cholera; with the suggestion of a new theory of the propagation and spread of cholera.
[West. Jour. of Med. & Surg., 1849, III, 3d s., pp. 379–387.]

Hasper (M.) Bemerkungen über die verschiedenen Ursachen, welche in heissen Ländern Krankheiten des Magens und Darmkanals erzeugen, und insbesondere über den Einfluss einer kalten und feuchten Luft auf Erzeugung von Diarrhöen, Ruhren und Cholera.
[Jour. d. prakt. Heilk., 1830, LXXI, pp. 23–52.]

Haughton (S.) A scientific inquiry into some of the causes alleged to produce Asiatic cholera.
[Med. Times & Gaz., 1867, I, pp. 84–85, 164, 247–248, 1 pl., 329–330, 439–441, 1 map, 490–491, 713–714, 1 pl.]

Haycraft. On the cerealean origin of cholera.
[London Med. Gaz., 1832, IX, pp. 255–260.]

Hayes (G. F.) Cholera, and the good and healthy condition of the teeth.
[Med. Circular, 1854, V, p. 249.]

Haslewood *and* **Mordey.** On the contagion of cholera.
[London Med. Gaz., 1832, X, pp. 31–32.]

Hearne (E.) Influence of water on cholera.
[Dublin Med. Press & Circ., 1867, IV, pp. 372.]

Hefft. Die Cholera ist nicht contagiös
[Deutsche Klinik, 1850, II, pp. 459–462.]

Herbst (E. F. G.) Untersuchung über die Verbreitungsart der asiatischen Cholera. 8°. *Göttingen*, 1832. L.

Hermann. Opinions on certain points connected with cholera.
[London Med. & Surg. Jour., 1833, II, p. 559.]

Hingeston (J. A.) Atmospheric changes relating to the prevalence of cholera.
[Assn. Med. Jour., 1854, pp. 353, 596, 720, 1016–1075.]

—— Atmospheric phenomena in relation to the prevalence of Asiatic cholera.
In his "Topics of the Day," 8°, Lond., 1863, pp. 1–77.]

Hinterholzer (J. N.) Cholera und Wärme, eine pathogenetische Studie.
[Allg. Wien. med. Zeitg., 1866, XI, pp. 342–343, 353–354, 359–360.]

Hirsch. Ueber die specifische Ursache der Cholera und ihre erfolgreiche Behandlung mit Schwefelammonium. Den Regierungen und Aerzten empfohlen. 8°. *Mainz*, 1866. L.

Hirsch (G.) Ueber die Contagiosität der Cholera. Bemerkungen zu dem Sendschreiben des Dr. Rust an A. v. Humboldt. 8°. *Königsberg*, 1832. L.

Hoffmann (H.) Miasma und Contagium der Cholera orientalis.
[Med. Conversbl., 1831, pp. 297–300, 337–338.]

Holmes (H.) Cholera; its electrical origin, electro-galvanic phenomena, and treatment by isolation and oxygen gas. 8°. *London*, 1848.

Hood (S.) Reasons why the medical staff in India did not consider spasmodic cholera contagious.
[London Med. & Surg. Jour., 1832, I, pp. 224–228.]

Horn (F. X. H.) Nachweis der Ursachen und des Wesens der Cholera sowie des positiv-elektrischen Erdstromes, vulkanischen Ursprungs, des Hauptfactors der Cholera. 8°. *München*, 1873. L.

—— Nachweis der Ursachen und des Wesens der Cholera. Die Erde ein schwingender Magnet. Abnahme des Erdmagnetismus, zweiter Hauptfactor der Cholera. 2te Lief. 8°. *München*, 1874. L.

—— Die Cholera ist eine Blausäure-Vergiftung. Ozon und Jodosmon, Miasma. 3te Lief. 8°. *München*, 1874. L.

Hort (W. P.) Remarks on cholera. Its contagion, its animalcular origin, its mode of propagation, &c., &c.
[N. O. Med. & Surg. Jour., 1849–50, VI, pp. 289–306.]

Horton (R.) On smoking tobacco, as inducing or preventing cholera.
[Lancet, 1848, II, p. 462.]

Howe (A. H.) Reflections on cholera. 8°. *London*, 1866.

Huette. Du développement et de la propagation du choléra.
[Archiv. gén. de méd., 1855, II, pp. 571–583.]

Hufeland (C. W.) Bestätigung der Eigenschaft des Barbenroggen, Cholera zu erregen.
[Jour. der pract. Heilk., 1824, LVIII, pp. 114–115.]

Hufeland (C. W.)—continued.

——— Die epidemische, endemische, und progressive Luftansteckung. Ein Beitrag zur Aufklärung der Cholera orientalis.

[JOUR. der prakt. Heilk., 1830, LXXI, pp. 107–112.]

——— Fortgesetzte Bemerkungen über die Verbreitung und Fortpflanzungsart der orientalischen Cholera. Vermuthungen über die Zukunft.

[JOUR. der prakt. Heilk., 1831, LXXIII, pp. 113–129.]

——— Ueber den Unterschied von epidemischer Constitution, Epidemie, und Contagion, und die Verschiedenheit mittelbarer und unmittelbarer, lebender und todter Contagiosität, mit Rücksicht auf die orientalische Cholera.

[JOUR. der prakt. Heilk., 1831, LXXII, pp. 91–106.]

——— Ueber die Contagiosität der Cholera.

[MED.-CHIR. Zeitung, 1831, IV, pp. 189–191.]

——— Worüber streitet man? Was heisst Ansteckung? Was heisst Contagionist und Nichtcontagionist bei der Cholera?

[JOUR. der prakt. Heilk., 1832, LXXIV, pp. 109–116.]

Hunter (R. H. A.) The contagion of cholera.

[LONDON Med. Gaz., 1846, XXXVIII, pp. 595–596.]

Husemann (G.) Die Contagiosität der Cholera nachgewiesen aus mannichfachen nach den mitgetheilten Beobachtungen der Aerzte von Unterfranken und Aschaffenburg, sowie aus eigner Anschauung geschöpften Thatsachen—nebst Angabe zu empfehlender Sanitätsmaassregeln. 8°. *Erlangen*, 1855. L.

Ilisch (F.) Untersuchungen über die Entstehung und Verbreitung des Cholera-Contagium und über die Wirksamkeit verschiedener Desinfections-Mittel.

[ST. PETERSB. med. Zeitschr., 1866, XI, pp. 129–204.]

——— The same. 8°. *St. Petersburg*, 1866. L.

——— Untersuchungen über Entstehung und Verbreitung des Cholera-Contagium.

[AERZTLICHES Intelligenz-Blatt, 1867, XIV, pp. 195–201, 217–221, 230–236.]

[Immink (W. J.)] Ontstaan, Verbreiding en statistieke Verhouding van den aziatischen Braakloop binnen Alkmaar in 1849. 8°. *Alkmaar*, 1850.

James (J. H.) Some remarks on the

James (J. H.)—continued.

nature and probable causes of the propagation of cholera maligna.

[LONDON Med. Gazette, 1848, XLII, pp. 29–31.]

Jeffray (T. R. W.) On the non-contagiousness of cholera asiatica.

[WESTERN Lancet, 1856, XVII, pp. 39–45, 337–343.]

Jodin. De la génération des foyers cholériques.

[REVUE méd., 1851, II, pp. 513–530.]

Johnson (F. H.) Causes which influence the arrest or spread of cholera.

[BRITISH Med. Jour., 1858, p. 55.]

——— On the localised causes of cholera.

[TRANS. Epidemiol. Soc., 1858 (appended to Pub. Health, 1858, IV), pp. 53–64.]

Johnson (J.) Propagation of the cholera.

[LANCET, 1831–32, II, pp. 209–210.]

Jolly. Si le choléra est contagieux.

[BULL. de l'Acad. nat. de méd., 1848–49, XIV, 823–833.]

——— Un mot de réponse à la lettre de M. Brochard, en attendant le rapport de l'Académie de médecine, sur la question de contagion du choléra. 8°. *Paris* [1850].

——— Mémoire sur la propriété épidémique du choléra, lu à l'Académie royale de médecine, . . . 1853. 8°. *Paris* 1853.

——— De la propriété épidémique du choléra.

[L'UNION méd., 1853, VII, pp. 521–522, 553–554, 565–567.]

Joyaux (A.) De la contagion du choléra. 4°. *Paris*, 1866. L.

Kaczorowski. Cholera, suo modo di diffusione e contagio, mezzi per prevenirla e cura. Traduzione italiana di F. Steverenzo.

[GAZ. med. it. prov. Venete., 1873, XVI, 295–296.]

Kalisch (M.) Zur Lösung der Ansteckungs- und Heilbarkeitsfrage der Cholera. 8°. *Berlin*, 1831. L.

Kandler (J.) Ueber die Contagion der orientalischen Cholera.

[OESTERR. med. Wochenschr., Wien, 1849, 1505–1512.]

King (H. W.) Is Asiatic cholera contagious?

[BOSTON Med. & Surg. Jour., 1866, LXXV, 249–252.]

Klose. Immunität der Brauer vor Cholera. (?)

[MED. Zeitung, 1833, p. 90.]

Knox (R.) The cholera fly.

[LANCET, 1853, I, n. s., pp. 479–480.]

Coeppe (J. M.) De cholerae epidemicae propagationis natura ac ratione. 12°. *Halis*, 1856. L.

Crecke (F. W. C.) Iets over Grondbeschuldigen in en om Utrecht.

[Verken. tot Verbet. ter Volksgezondh., Utrecht, 1869, IV, pp. 49-56.]

Küchenmeister (F.) Handbuch der Lehre von der Verbreitung der Cholera. *Erlangen*, 1872.

—— Offene Briefe über Cholera, als Erläuterung und Nachtrag zu meinem "Handbuch der Lehre von der Verbreitung der Cholera".

[Allg. Wien. med. Zeitg., 1873, XVIII, pp. 35-37, 50-52, 69-71, 85-86, 102-103, 118, 137-138, 153-156, 172-(0), 188-189, 254-255, 270-271, 289-290, 306-308, 345-347, 417-418, 427-428, 435-436, 447-448, 454-455.]

Labat (L.) De la non-contagion du choléra-morbus asiatique ou réponse critique à l'ouvrage de M. le docteur Valle. 8°. L.

[From Ann. de la méd. physiol.]

Lannelongue (F.) * Essai sur l'étiologie et le mode de propagation du choléra asiatique envisagés dans leurs rapports avec la prophylaxie. 4°. *Montpellier*, 1867. C.

Latour (A.) Opinions sur la non-contagion du choléra.

[L'Union méd., 1866, XXXI, 2e s., pp. 241-247, 283-284.]

Latour-Marliac. Observations sur les phénomènes extraordinaires produits par les insectes, leur influence sur les plantes, les animaux et l'homme. Suivies de son opinion sur les causes qui produisent le choléra, contre lequel il propose un préservatif. [1837.]

Laugaudin. De la contagion du choléra. *Nice*, 1865.

Lawson. Observations on the influence of pandemic waves in the production of cholera.

[Stat., San., and Med. Repts. Army Med. Dept. Gr. Br., 1866, pp. 383-425.]

Lea (J.) Cholera, with reference to the geological theory: a proximate cause—a law by which it is governed. 8°. *Cincinnati*, 1850. L.

—— Cholera—the geological theory.

[Western Lancet, 1851, XII, pp. 89-97, 217-221.]

—— The same. 8°. *Cincinnati*, 1851. L.

Lebon (R.) De la non-contagion du choléra.

[L'Union méd., Paris, 1854, VIII, p. 475.]

Lecadre. Lettre à M. le docteur Cazalas, concernant la contagion du choléra.

[L'Union méd., 1866, XXXII, 2e s., pp. 183-187.]

Lecocq. Note sur la contagion du choléra.

[Arch. méd. belges, 1866, IV, 2e s., pp. 65-71.]

Lecocq (J.) Note sur la propagation du choléra.

[Arch. méd. belges, 1873, IV, 3e s., pp. 294-305.]

Ledeganck (K.) Le champignon du choléra asiatique. Étude médico-botanique, à propos d'l'ouvrage: Das Cholera-Contagium, botanische Untersuchungen, Aerzten und Naturforschern mitgetheilt von Dr. Ernst Hallier.

[Jour. de méd., de chir. et de pharm., Bruxelles, 1872, LIV, pp. 313-319.]

Ledeschault (P.) Recherches sur la nature et la cause du choléra-morbus. 8°. *Paris*, 1832. L.

Lee (C. A.) Contagiousness of cholera.

[Boston Med. & Surg. Jour., 1866, LXXIV, pp. 139-141.]

—— Is cholera contagious?

[Med. & Surg. Reporter, 1866, XIV, pp. 204-206.]

Lefebvre (E.) Faits relatifs à la non-contagion du choléra.

[L'Union méd., 1850, IV, pp. 61-62.]

Legros (F.) Sur le choléra et le coït comme cause de cette maladie.

[Gaz. des hôp., 1832, VI, p. 335.]

Leisinger (J.) Die Cholera, ihr Ursprung, Wesen, Verlauf, etc. 8°. 1849.

Leithead (T.) The communicability of cholera poison from man to man.

[Med. Times, 1849, XX, p. 496.]

Le Maout (C.) Expériences chimico-microscopiques sur le miasme du choléra, constatant l'existence dans l'air d'un nombre infini de globules appartenant au règne animal et tirant leur origine du sang . . . . 8°. *Paris*, 1833.

Lerche (W.) Ist die in St. Petersburg herrschende Cholerakrankheit contagiöser Natur? Mit einer Nachschrift von Hufeland über die Contagiosität der Cholera.

[Jour. d. prak. Heilk., 1831, LXXIII, pp. 127-133.]

Lersch. Die Cholera-Körperchen oder Cholera-Fungen.

[Rheinische Monatschr. f. prakt. Aerzte, 1850, IV, pp. 172-174.]

Letheby. Propagation of cholera.

[Dublin Med. Press & Circ., 1868, V, pp. 55-57.]

Lewis (T. R.) Concerning the theory of the fungoid origin of cholera and the microscopic objects found in choleraic evacuations.
[SIXTH Ann. Rept. Sanitary Comr. with the Govt. of India, 1869, app. A, pp. 126–164, 21 pl.]

——— Remarks regarding the soil, &c., of certain places in relation to Pettenkofer's theory of the connection of cholera with the variation in the level of the subsoil water.
[IBID., pp. 165–178, 6 pl.]

——— The fungoid theory of cholera.
[MED. & Surg. Reporter, 1871, XXIV, pp. 515–516.]

Lichtenstädt. Aetiologie der asiatischen Cholera. (Bruchstück.)
[LITTER. Ann. der gesammt. Heilk., 1831, XXI, pp. 219–225.]

Liebig. Etiology of cholera.
[MED. Times & Gaz., 1854, IX, n. s., p. 515.]

Lochner. Ueber das Auftreten der Cholera im allgemeinen Krankenhause in Nürnberg.
[AERZTL. Intell.-Bl., 1854, I, pp. 353–356, 378–382, 444–448, 449–455.]

Loret. Extrait de deux observations de cholóra-morbus tendant à prouver la non-contagion de cette maladie.
[JOUR. sect. de méd. Soc. acad. dépt. Loire-Inf., 1836, XII, pp. 188–192.]

Louvrier (P.-J.-F.) * Dissertation sur les causes du cholóra-morbus. 4°. *Paris*, 1833. L.

Lussinpiccolo (N. di). Intorno ogli studi sul cholera asiatico del dottor G. A. Goracuchi di Trieste.
[GIORN. venet. d. sc. med., 1851, III, pp. 592–599, 744–765.]

Lustig. Ist die Cholera ansteckend?
[MED. Zeitung, 1856, p. 94.]

Lutostański (B.) Jad cholery i odtruwanie przenośnikoń tegoż jadu. Sprawozdanie z najnowszych poszukiwań.
[PRZEGLAD Lekarski, Krakow, 1867, VI, pp. 369, 393, 401, 410; 1868, VII, pp. 1, 9, 17, 125, 141, 149, 163, 170, 179, 185, 193, 203, 209, 219, 231, 239, 247, 255.]

McElvoy (W. S.) Cholera spreading by contagion.
[LONDON Med. Gaz., 1833, XI, p. 255.]

McGowan (A. T.) Malaria, the common cause of cholera, intermittent fever and its allies. *London* [1867 ?].

Maclean (W.) Proclamation of the central board of health that epidemic cholera is not contagious!!!
[LONDON Med. & Surg. Jour., 1833, II, pp. 632–633.]

Macloughlin (D.) Result of an [illegible] whether cholera can be conveyed [illegible] human intercourse from an infected [illegible] healthy locality; or, from an infected [illegible] a healthy person: that is, Is cholera a contagious disease? 8°. *London*, 1[illegible]

Macmichael (W.) Is the cholera [illegible] modica of India a contagious disease? The question considered in a letter addressed to the president of the board of health. 8°. *London*, 1831.

Macneven (W. H.) Remarks on the mode by which cholera is propagated, being an attempt to reconcile the conflicting opinions of medical writers in relation to its contagious or non-contagious character.
[N. Y. Jour. of Med., 1849, II, n. s., pp. [illegible]

Macpherson (J.) Conditions under which cholera appears in its home.
[MED. Times & Gaz., 1866, I, pp. 5–7, 6[illegible]

——— Die atmosphaerischen Niederschläge und die Cholera in Indien.
[AERZTL. Intell.-Bl., 1867, XIV, pp. 127–[illegible]

Mainwaring (E. V.) Asiatic cholera, atmospheric phenomena in Dec. [illegible] cholera; its non-contagious character; theory of its production and propagation, etc.
[LANCET, 1848, I, pp. 337–338.]

Manicus (C.) Bidrag til Kundskab om Cholera.
[BIBL. for Laeger, Copenhagen, 1831, V[illegible] 377.]

——— Om Contagiernes Natur og Forplantelse.
[BIBL. for Laeger, Copenhagen, 1831, II[illegible]

Mansill (R.) Cholera and planetary epidemics. Cholera waves or periodical rise and fall of the scourge. Epidemics and other pestilences, [etc.] *Island*, 1874.

Maréchal (J.-B.) * Considérations sur l'étiologie et le traitement du cholera-morbus. 4°. *Paris*, 1855.

Marsden (W.) On the contagion of cholera.
[BRIT. Amer. Jour. of Med. & Phys. Sc., pp. 197–198.]

Martin (R.) Intemperance and cholera.
[BRIT. Med. Jour., 1871, II, pp. 198–199.]

Martineng. De la non-contagion du choléra, de ses causes, et de son traitement.
[L'UNION méd., 1854, VIII, pp. 356–357, 384–385, 399–400.]

Maurin (S.-E.) Analyse et synthèse de l'epidémicité cholérique. Question sociale: origine, développement, propagation des épidémies de choléra. 8°. *Marseille*, 1866. L.

Mayer (M.) Ist die Cholera epidemisch oder contagiös? Ist die Quarantäne ein hinlänglicher Schutz? Zwei Fragen vom Standpunkte der Erfahrung aus beantwortet. 8°. *Berlin*, 1831.

Meray (R. F.) Recherches géologiques et philosophiques sur le refroidissement animal improprement appelé choléra-morbus; sa cause essentielle. 8°. *Paris*, 1833.

Merryweather (G.) Proof of the communicability of Asiatic cholera.
[London Med. Gaz., 1842, xlii, p. 812.]

Meunier (A.-F.) * De la contagion et de l'infection, spécialement étudiées dans le choléra. 4°. *Paris*, 1855. L.

Meyer (J.) Impfversuche mit dem Blute und den Ausleerungen Cholerakranker.
[Virchow's Archiv, 1851, iv, pp. 29–54.]

Meyer (J. N., *Edlem von*). Einige neue Beobachtungen über das Wesen der Cholera morbus aus der Erfahrung geschöpft, in besonderer Beziehung auf die Haare als Leiter des Contagiums. 8°. *Wien*, 1831. L.

Mile. Ansichten über die Verbreitung der Cholera. Aus dem Polnischen übersetzt von Dr. Leo.
[Journ. der prakt. Heilk., 1831, lxxiii, pp. 3–26; 1832, lxxiv, pp. 85–127.]

Milhau (J.-P.) * Du mode de propagation du choléra épidémique. 4°. *Paris*, 1853. L.

Mille (H.) Observations sur la cause du choléra dit asiatique.
[Gaz. méd. de Paris, 1835, iii, p. 588.]

Mitchell (J. T.) Supposed discovery of Professor Delpech of an affection of the semilunar ganglia in the malignant cholera, shown to be erroneous.
[Lancet, 1832, i, pp. 884–885.]

Mitchell (T. K.) The theory of the fungous origin and propagation of cholera.
[London Med. Gaz., 1849, xliv, pp. 602–603.]

Moffat (T.) Cholera and ozone.
[Lancet, 1865, ii, p. 303.]

Moir (D. M.) Proofs of the contagious nature of malignant cholera. 8°. *Edinburgh*, 1832.

Mojon (B.) Conjectures sur la nature du miasme producteur du choléra asiatique. Traduit de l'italien par J. de Fontenelle. 8°. *Paris*, 1833. L.

Montegnie *et* **Decondé.** Notes sur la contagion du choléra épidémique. Rapport de M. Lombard.
[Bull. de l'Acad. roy. de méd. de Belg., 1849–50, ix, pp. 610–616.]

Montgomery (H. B.) On the origin and propagation of cholera in India by means of religious festivals and pilgrimages.
[Med. Times & Gaz., i, 1866, pp. 100–105.]

Monti (P.) Unica e vera genesi del colera-morbus. *Cremona*, 1866.

Moore. Apparent causes of fever and cholera. *London*, 1866.

Moreau. Note sur la contagion du choléra épidémique. Rapport de M. Fallot.
[Bull. de l'Acad. roy. de méd. de Belg., 1849–50, ix, pp. 616–620.]

——— Lettre sur la contagion du choléra.
[Gaz. méd. de Paris, 1850, v, p. 760.]

Moss (W.) Cholera, its cause and prevention.
[Lancet, 1853, i, n. s., p. 377.]

Moyle (J.) The communicability of cholera poison from man to man.
[Med. Times, 1849, xx, p. 427.]

Mudge (J. W.) The cause of cholera.
[Med. Times & Gaz., 1867, i, pp. 534–535.]

Mühlig. Rapport sur la question de la transmissibilité du choléra.
[Gaz. méd. d'orient, 1867–68, xi, pp. 103–107, 115–119.]

Mugna (J. B.) Sul contagio del cholera indiano.
[Giorn. venet. d. sci. med., 1850, i, pp. 443–448.]

Mulder (G. J.) Besmettelijkheid der Cholera.
[Nederland. Lancet, 1848–49, 2e s., iv, pp. 278–294.]

——— Ansteckung der Cholera. (Aus dem Holländischen.)
[Archiv f. physiol. Heilk., 1849, pp. 489–499.]

Murray (J.) Deductions from experiments on the nature of cholera and other epidemics.
[Lancet, 1848, ii, pp. 444–448, 499–501.]

——— Electricity as a cause of cholera or other epidemics, and the relation of galvanism to the action of remedies. 12°. *Dublin*, 1849.

——— On the channels through which cholera is communicable.
[British Med. Jour., 1873, ii, pp. 216, 220.]

Mussey (R. D.) Animalcula in the atmosphere of cholera patients.
[Western Lancet, 1849, x, pp. 293–296.]

——— The same. 8°. 1849. L.

Nanninga (H. D.) *Over den Invloed van de Lucht-Electriciteit op het heerschend Ziekte-Karakter, vooral met Betrekking tot de Cholera. 8°. *Groningen*, 1859. L.

Nardo (D.) Quali sieno i fatti principali che condurrebbero a supporre essere una mucedinea venefica la causa efficiente del cholera. *Venezia*, 1865.

Neale (A.) Researches to establish the Linnæan doctrine of animate contagions; origin, etc., of spasmodic cholera, etc. 8°. *London*, 1831.

Neale (R.) The cause of cholera.
[Med. Times & Gaz., 1866, II, p. 5.]

Netter (A.) Sur la contagion du choléra.
[Gaz. hebd. de méd. et de chirurg., Paris, 1866, 2e s., III, p. 298.]

Nichols (J.) The water theory of cholera.
[Lancet, 1868, II, p. 400.]

Nissen (W.) Ueber die Ursachen der Cholera, nebst Vorschlägen zur Bekämpfung derselben. Eine Abhandlung. 8°. *Altona*, 1831. L.

Noble (D.) On the question of contagion in cholera.
[London Med. Gaz., 1849, XLIII, pp. 141–149.]

Nolte (E.) Die grossen und merkwürdigen kosmisch-tellurischen Erscheinungen im Luftkreise unserer Erde in Folge zwanzigjähriger Beobachtungen auch in Beziehung zu der im Laufe der neuern Zeit herrschenden orientalischen Cholera dargestellt. . . . 8°. *Hannover*, 1831.

Oesterlen (F.) Choleragift und Pettenkofer, als Beitrag zum heutigen Stand der Cholerafrage. 8°. *Tübingen*, 1868. L.

——— Gegen die Spezifität und Kontagiosität der Cholera.
[Wien. med. Presse, 1873, XIV, pp. 73–77, 97–100, 117–120, 170–172, 194–195, 316–318, 373–375, 512–515.]

Ohlsen (G.) Le precipitazioni atmosferiche ed il cholera nelle Indie. Studio critico fatto ..... sulle ricerche del dott. John Macpherson, secondo le vedute del prof. Dr. Pettenkofer.
[Gaz. med. it. Lomb., 1869, XXIX, pp. 377–381, 388–390.]

Orton. Report on cholera and the water supply.
[Dublin Med. Press & Circ., 1868, V, pp. 268–269.]

Orton (R.) On contagion [of cholera].
London Med. Gaz., 1832, X, pp. 222–226.]

Owen (W. T.) The cause of cholera.
[Med. & Surg. Reptr., 1867, XVII, pp. 45–51.]

Pacini (F.) Sulla causa specifica del colera asiatico, il suo processo patologico e la indicazione curativa che ne resulta. 8°. *Firenze*, 1865.

——— The same. Traduit de l'italien par M. le docteur E. Janssens.
[Jour. de méd., etc., Bruxelles, 1865, XLI, 417–432, 513–533.]

Packman (W.) Is cholera contagious or non-contagious?
[Med. Times, 1846, XV, p. 49.]

Paganuzzi (A. B.) L'ozono durante l'ultima invasione cholerica nell'anno 1867. 8°. *Firenze*, 1867. S. C.

Paone (P.) Sulla teorica miasmatica del cholera.
[Sperimentale (Lo), Firenze, 1866, XVII, pp. 280–281.]

Pariset. Lettre sur l'opinion contagioniste en Italie.
[Gaz. des hôp., Paris, 1832, VI, pp. 375–376.]

Parkes (E. A.) An inquiry into the bearing of the earliest cases of cholera, which occurred in London during the present epidemic, on the strict theory of contagion.
[Brit. & For. Med.-Chir. Rev., 1849, IV, pp. 275–276.]

——— The contagion of cholera.
[Med. Times & Gaz., 1853, VI, pp. 197–198.]

Parkin (J.) The remote cause of epidemic diseases; or, the influence of volcanic action in the production of general pestilences. 8°. *London*, 1853. L.

Pascal. Considérations pratiques sur la propagation du choléra-morbus. *Bayonne*, 1855.

Peiffer (G.) *De cholerae morbi contagio. 8°. *Berolini* [1831]. L.

Pellarin (A.) L'origine des épidémies de choléra.
[Gaz. hebd. de méd. et de chirurg., Paris, 1871, 2e s., VIII, pp. 533–534.]

——— De l'importation et de la contagion du choléra.
[L'Union méd., 1873, XVI, 3e s., pp. 536–539.]

Pellarin (C.) De l'infection et de la contagion, à propos du choléra.
[Revue méd., 1851, II, pp. 321–333, et seq.]

——— Sur la contagion du choléra.
[L'Union méd., 1866, XXXI, 2e s., pp. 600–601.]

——— Le choléra comment il se propage et comment l'éviter. Solution trouvée et publiée en 1849. 8°. *Paris*, 1873. L.

Pellarin (C.)—continued.

——— A propos du choléra.—L'importation et ses conséquences au point de vue de la pathologie et de la thérapeutique du choléra épidémique.

Gaz. heb. méd. et chir., 1873, x, 2e s., pp. 604–605.]

Peters (J. C.) Notes on the origin, nature, prevention, and treatment of Asiatic cholera. 2d ed. 12°. *New York*, 1867. L.

——— Notes on cholera.

[Nashville Jour. of Med. & Surg., 1874, xxxv, pp. 206–214.]

——— The origin and spread of Asiatic or Bengal cholera.

Amer. Public Health Assn. Reports & Papers, N. Y., 1875, I, pp. 336–342, 1 map.]

Pettenkofer (M. v.) Recherches et considérations sur le mode de propagation du choléra, etc. *Munich*, 1855.

——— Untersuchungen und Beobachtungen über die Verbreitungsart der Cholera, nebst Betrachtungen über Massregeln, derselben Einhalt zu thun. 8°. *München*, 1855. L.

——— Zur Frage über die Verbreitungsart der Cholera. Entgegnungen und Erläuterungen zu seiner Schrift "Ueber die Verbreitungsart der Cholera". 8°. *München*, 1855. L.

——— De l'étiologie du choléra.

Gaz. hebd. de méd. et de chirurg., Paris, 1856, III, pp. 213–225.]

——— Fünf Fragen aus der Aetiologie der Cholera.

[Pappenheim's Monatsschr., 1859, I, pp. 1–36, 73–84.]

——— The same. 8°. *Berlin* [*n. d.*] L.

——— Die Cholera und di Bodenbeschaffenheit in der k. k. österreichischen Provinz Krain.

[Aerztl. Intell.-Bl., 1861, VIII, pp. 89, 103, 113.]

——— Ueber die Verbreitungsart der Cholera.

[Ztschr. f. Biologie, München, 1865, I, pp. 322–374.]

——— Regen-Menge und Cholera in Indien und der gegenwärtige Standpunkt der Frage der Cholera-Verbreitung.

[Aerztl. Intell.-Bl., 1867, XIV, pp. 155–161.]

——— Boden und Grundwasser in ihren Beziehungen zu Cholera und Typhus. [Erwiederung auf Rudolf Virchow's hygienische Studie: "Canalisation oder Abfuhr?"]

[Ztschr. f. Biologie, München, 1869, V, pp. 171–310.]

Pettenkofer (M. v.)—continued.

——— Causes of cholera.

[Med. Press & Circ., 1869, VII, p. 405.]

——— Observations on Dr. Buchanan's lecture on Professor Pettenkofer's theory of the propagation of cholera and enteric fever.

[Med. Times & Gaz., 1870, I, pp. 629–632, 661–663, 687–689.]

——— Verbreitungsart der Cholera in Indien.

[Aerztl. Intell.-Bl., 1871, XVIII, p. 614.]

——— Ozon und Cholera.

[Berl. klin. Wochenschr., 1873, X, p. 397.]

Pfeiffer (L.) Untersuchungen über den Einfluss der Bodenwärme auf die Verbreitung und den Verlauf der Cholera.

[Ztschr. f. Biologie, München, 1871, VII, pp. 263–305, 1 pl.]

Phillips (H. H.) The influence of impure water in the diffusion of cholera.

[British Med. Jour., 1873, II, pp. 220–222.]

Picard (J. P.) L'étiologie et le mode de propagation du choléra.

[Gaz. hebd. de méd. et de chirurg., Paris, 1855, II, pp. 697–700.]

Pirondi (P.) Considerazioni sulla contagiosità del cholera morbus asiatico, precedute da una critica analisi delle due memorie del signor Bo: "Le quarantene e il cholera-morbus." 8°. *Marsiglia*, 1856.

——— Sullo spiritoso libello intitolato Riflessioni del medico collegiato Giovanni Demarchi considerazioni sulla contagiosità del cholera-morbus asiatico. 8°. *Torino*, 1857. L.

Ploss (H.) Ueber die Ursachen der epidemischen Verbreitung der Cholera. Nach Beobachtungen, angestellt in der Umgegend von Leipzig im Jahre 1866. (Sep.-Abd aus der Zeitschr. für Med., Chir. und Geburtsh., 1868, Bd. vii, Heft 8.) 8°. *Leipzig*, 1868. L.

[*Bound with* Ploss (H.), Vorläufige Mittheilungen über die Cholera-Epidemie, 1866.]

Polak (I. E.) Ueber die Cholera-Conferenzen von Constantinopel und Tiflis. Die Pilgerfahrten der Orientalen mit Beziehung auf Verbreitung von Cholera. Massnahme gegen dieselbe.

[Oesterr. Zeitschr. f. prakt. Heilk., Wien, 1872, XVIII, pp. 785–788, 800–803, 816–820.]

Porter (J. B.) On the contagion of cholera.

[St. Louis Med. & Surg. Jour., 1850, VIII, pp. 223–226; *also, in* N. Y. Jour. of Med., 1850, IV, pp. 351–355.]

Potts (W. S., *practical phrenologist*). No humbug: but to put down humbug. The cholera or pestilence, in Asia, a Chinese humbug. The cause discovered and written out in a plain way. 8°. *Eaton, O.*, 1855. L.

Poyser (T.) Contagiousness of cholera: Professor Owen and the sanitary commission.
[PROV. Med. & Surg. Jour., 1848, p. 699.]

Poznanski. Zur Aetiologie der Cholera.
[ALLG. med. Central-Zeitg., 1857, XXVI, pp. 729–730.]

Prangé (L.) Des causes générales du choléra.
[GAZ. des hôp., 1850, pp. 221–222.]

Preu (K.) Was haben wir von der Cholera morbus zu fürchten? Ein Versuch die aufgeschreckten Völker zu beruhigen. 12°. *Nürnberg*, 1831. L.

Quade (J.) *Aetiologie der Cholera asiatica mit besonderer Berücksichtigung der praktischen Verwerthung. sm. 8°. *Berlin* [1872]. L.

Radlkofer (L.) Auszug aus den Untersuchungen von Dr. Douglas Cunningham in Ostindien über die Verbreitungsart der Cholera.
[ZEITSCHR. f. Biologie, München, 1872, VIII, pp. 250–266.]

Raimbert (L. A.) De la dyspepsie accescente, considérée comme cause prédisposante des affections cholériques. 8°. [*Paris*, 1851.]

Rambaud. Du mode de propagation du choléra et de la nature contagieuse de cette maladie.
[GAZ. méd. de Lyon, 1854, VI, pp. 192–195; *also*, in ANN. de la Soc. de méd. de Lyon, 1854, II, pp. 315–327.]

Rea (R. L.) Contagion of cholera.
[CHICAGO Med. Jour., 1867, XXIV, pp. 355–359.]

Read (W.) The communicability of cholera.
[MED. & Surg. Reporter, 1866, XIV, pp. 355–356.]

——— A communication from the city physician on Asiatic cholera. Is it a contagious disease? 1866, Boston, city document No. 21. 8°. *Boston*, 1866. L.

Reeves (W.) On the magnetic theory of cholera and the potato blight.
[LANCET, 1849, I, n. s., pp. 532–533.]

Reid (W.) A letter to Lord Morpeth and the members of the board of health, on the question:—Is cholera contagious or not? 8°. *London* [1848]. L.

Reid (W.)—continued.

——— The propagation of cholera by contagion.
[LONDON Med. Gaz., 1849, XLIV, pp. 17[illegible].

Reider. Über die Verbreitung der asiatischen Cholera.
[ZEITSCHR. d. k. k. Ges. der Ärzte zu Wien, [illegible] pp. 189–204.]

Reigert (J. F.) A treatise on the cause of cholera. An interesting discovery. 8°. *Lancaster City, Pa.*, 1855. L.

Renzy (A. C. C. de). Cholera and the water theory.
[LANCET, 1871, II, p. 449.]

——— Water theory of cholera.
[BRITISH Med. Jour., 1871, II, pp. 626–627.]

Revillout (V.) De la contagion ou : contagion du choléra.
[GAZ. des hôp., 1866, pp. 401–403.]

Rézard de Wouves. Du choléra. Preuves de sa non-contagion. Nature, causes et symptômes. Signe certain pour le diagnostic. Son traitement. Les quarantaines. 8°. *Paris*, 1866.

Rhades (F. G. F.) Beitrag zur Beantwortung der Frage: ob die Cholera ansteckend sei? 8°. *Stettin*, 1832.

Richardson (B. W.) On the theory of mode of propagation of cholera.
[TRANS. Epid. Soc. Lond., 1866, II, pp. 424–[illegible].

Rieux (L.) Du choléra au point de vue de la contagion.
[GAZ. méd. de Lyon, 1867, XIX, pp. 289–290, 307, 315–319, 327–329.]

Ritchie (H.) An inquiry into Professor Frick's theory of cholera, in connexion with ozone.
[NORTH-WESTERN Med. & Surg. Jour., [illegible] pp. 220–226.]

Ritter (B.) Ueber das Wesen der asiatischen Cholera, nach eigenen Beobachtungen.
[MED. Correspbl. des württemberg. ärztl. [illegible] 1838, VIII, pp. 41–44.]

Rives (E.) Etiology of cholera.
[CINC. Jour. of Med., 1866, I, pp. 468–469.]

Robertson (F.) An essay on the contagiousness of cholera asiatica.
[TRANSYL. Jour. of Med., 1836, IX, pp. [illegible].

Robertson (J. J.) On Dr. Snow's theory of cholera.
[MED. Circular, 1855, VI, p. 20.]

Roche (L. C.) Réponse à M. Jolly's contagion of cholera.] [1855].

oger (H.) Observations de contagion du choléra; et discussion. (2 cases.)
[Bull. et mém. Soc. méd. des hôp. de Paris, 1867, III, pp. 196–205.]

—— Le choléra indien devient-il stérile en Europe, et de grandes épidémies ne peuvent-elles pas débuter sur notre continent?
[Bull. de l'Acad. de méd., Paris, 1875, IV, 2e s., pp. 463–472; discussion, pp. 472–477.]

ohnstock (R.) *An et quibus argumentis contagium cholerae asiaticae evinci possit? 8°. *Vratislaviae*, 1833. L.

olleston (G.) The propagation of cholera.
[Lancet, 1871, II, p. 339.]

usseau. Sur la contagiosité du choléra-morbus.
[Gaz. méd. de Strasbourg, 1849, IX, pp. 337–342.]

—— Sur la contagion du choléra.
[L'Union méd., 1849, III, pp. 437–438.]

—— De la contagion du choléra-morbus de l'Inde. 8°. [*Épernay, n. d.*] L.

—— Lettres sur la contagion du choléra-morbus indien. *Épernay*, 1866.

chs (J. J.) Ueber die schwankende Aetiologie der Cholera.
[Berliner med. Central-Zeitung, 1832, I, pp. 53–55, 65–68.]

lmon (J.) Evidences of the propagation of malignant cholera by contagion.
[Lancet, 1832–33, I, pp. 182–183.]

ader (F.) Untersuchungen über die Cholera in ihren Beziehungen zu Boden und Grundwasser, zu socialen und Bevölkerungs-Verhältnissen, sowie zu den Aufgaben der öffentlichen Gesundheitspflege. 4°. *Köln*, 1872. L.

derson (B.) Report on the experimental proofs of the communicability of cholera.
[Rep. Priv. Counc., 1866 (appendix), pp. 434–458.]

som (A. E.) The nature of the cholera-poison. L.
[Dublin Med. Press & Circ., 1867, IV, pp. 415–418.]

(J. J.) Besmettelijkheid der Cholera.
[Nederl. Courant, Tiel, 1848, No. 52; 1849, No. 35.]

se (A.) Over den Aard der Cholera-ziektestof.
[Nederl. Tijdschr. v. Geneesk., 1866, I, pp. 401–411.]

oyen. De la météorologie dans ses rapports avec le choléra et l'épidémie de certains végétaux. *Chambéry*, 1856.

haeffer. Die Contagiosität der asiatischen Cholera.
[Zeitung, 1849, pp. 159–161.]

Schleis v. Loewenfeld. Über die Entstehung von Epidemien, mit besonderer Rücksicht auf Cholera und Typhus. 8°. *München*, 1869.

Schlothauer (K. O.) *Aetiologie der miasmatisch-contagiösen Krankheiten, mit besonderer Beziehung zur Aetiologie der Cholera. 8°. *Salzungen*, 1868. L.

Schmädig. Mittheilungen über die Verbreitungsweise der Cholera.
[Russ's Mag. f. d. gesammt. Heilk., 1833, XL, pp. 163–189.]

Schmid (G.) Das Choleragift, eine Cyanverbindung: bald Blausäure, meist Cyanammonium. Mit Bezugnahme auf Desinfection und Therapie. 8°. *Leipzig*, 1868. L.

—— Das Choleragift eine Cyanverbindung.
[Allg. Wien. med. Zeitg., 1871, XVI, pp. 232–233, 255–256.]

Schmoele (W.) An essay on the cause, diffusion, localization, prevention and cure of the Asiatic cholera and other epidemics. 8°. *Philadelphia*, 1866. L.

Schouten (H. J.) Pathologisch en physisch Betoog, dat de aziatische Brakloop, zoodanig als dezelve in Europa en ook hier te Lande is waargenomen, eene besmettelijke of contagieuse Ziekte is. 8°. *Amsterdam*, 1833. L.

Schreiber (K.) Ueber die Beziehungen der Cholera zu den allgemeinen Naturkräften, insbesondere zur Electricität.
[Deutsche Klinik, 1862, XIV, pp. 352–354, 364–366, 370–372.]

Schröder. Dynamische Abweichungen in der Atmosphäre, als krankmachendes Princip lebender Organismen, durch organisch-physikalische Untersuchungen in Bezug auf die Aetiologie der Cholera. 8°. *Rostock*, 1833.

Schultz (A.) Ueber den Ozongehalt der Luft zu Berlin im November 1853 und während der Cholera-Epidemie daselbst in demselben Jahre.
[Med. Zeitg., 1854, pp. 39–40.]

Schurtz (H.) Beiträge zur Kenntniss der pflanzlichen Parasiten der Cholera, der Vaccine, des Scharlach und der Intermittens. (Mit einer Tafel.)
[Arch. d. Heilk., Leipzig, 1868, pp. 64–70.]

Schwarzmann (C.) *Ueber die Entstehung und Ausbreitung der Cholera. 8°. *München*, 1855. L.

Scobey (W. H.) Is cholera contagious?
[Western Lancet, 1856, xvii, pp. 205–208.]

Scoutetten. Sur l'ozone atmosphérique à propos du choléra.
[Gaz. des hôp., 1865, pp. 510–511.]

Searle (C.) On the poisonous influence of malaria, and the diseases it gives rise to, cholera and fever.
[Lancet, 1842–43, ii, pp. 229–234.]

Sebregondi. Versuch, die Ursachen und das Wesen der asiatischen Cholera darzustellen.
[Heidelberg. klin. Ann., 1834, x, pp. 206–237.]

Seidlitz. Ueber die Nichtcontagiosität der Cholera.
[St. Petersb. med. Zeitschr., 1866, x, pp. 52–57, 104–110, 178–179, 363–368.]

Sellier. Électricité résineuse considérée comme cause possible du choléra-morbus.
[Gaz. des hôp., 1832, vi, p. 127.]

Seux (V.) Encore quelques mots de la contagion du choléra épidémique. *Marseille*, 1867.

Shapter (T.) *and* **Clapp** (W.) Fungoid theory of cholera. Notes of some observations on the evacuations and ingesta of cholera patients.
[London Med. Gaz., 1849, xliv, pp. 961–962.]

Sharkey (E.) A letter on the question of the contagious nature of Asiatic cholera, addressed to the editors of the Dublin Journal of Medical Science.
[Dublin Jour. of Med. Sci., 1839, xvi, pp. 13–20.]

Shrimpton (C.) Le choléra est-il, oui ou non, une maladie contagieuse?
[Gaz. méd. de Paris, 1866, xxi, pp. 150–152.]

Siemerling (F.) Entschleierung der Cholera, nebst dem sprechendsten Beweise ihrer Nicht-Contagiosität, und Angabe der Heilmittel, so wie des einzig und allein auf Vernunft basirten Vorbeugungsverfahrens gegen das Einathmen der Malaria animata, (belebten Sumpfluft.) Auf den Altar der Menschheit niedergelegt. 8°. *Hamburg*, 1831. L.

Simpson. Contagion in cholera.
[Monthly Jour. of Med. Sci., Edinburgh, 1848–49, ix, p. 546.]

Simpson (J. Y.) On the evidence of the occasional contagious propagation of malignant cholera, which is derived from cases of its direct importation into new localities by infected individuals.
[Edinb. Med. & Surg. Jour., 1832, xlix, pp. 355–408.]

Smee (A.) On the production of cholera by insufficient drainage.
[Lancet, 1849, ii, n. s., pp. 232–233.]

Snow (E. M.) Is Asiatic cholera contagious?
[Med. & Surg. Reporter, 1866, xiv, pp. 356–357.]

Snow (J.) On the mode of communication of cholera. 8°. *London*, 1849. L.

——— The same. 2d ed. 8°. *London*, 1855. L.

——— The same. [In German.] 8°. *Quedlinburg*, 1856. L.

——— [Mode of propagation of cholera.]
[Med. Times, 1851, iii, n. s., pp. 559–562, 611–612.]

——— Communication of cholera by Thames water.
[Med. Times & Gaz., 1854, ix, n. s., pp. 267–268, 365–366.]

——— Further remarks on the mode of communication of cholera; including some comments on the recent reports on cholera by the general board of health.
[Med. Times & Gaz., London, 1855, xi, n. s., pp. 31–35, 84–88.]

——— Cholera and the water supply in the south districts of London, in 1854.
[Jour. of Pub. Health, 1856, ii, pp. 239–257.]

——— The mode of propagation of cholera.
[Lancet, 1856, i, n. s., p. 184.]

——— Cholera, and the water supply in the south districts of London.
[Assocn. Med. Jour., 1857, ii, pp. 864–865.]

Spinzig. The apparent nature and cause producing an epidemic of cholera.
[St. Louis Med. & Surg. Jour., 1867, iv, pp. 37–41.]

Spitta (H.) De contagio praesertim cholerae orientalis. 4°. *Rostochii* [1832]. L.

Spooner (E. O.) The contagion of Asiatic cholera.
[Prov. Med. Jour., 1849, pp. 34–37, 62–65, 91–[illegible].]

——— The contagion of Asiatic cholera deduced from its recent progress, its early history, and its pathological correlations. 12°. *London*, 1849. L.

Stanski (G. P.) Le choléra est-il contagieux? 8°. *Paris*, 1866.

——— Examen critique des diverses opinions sur la contagion du choléra. 8°. *Paris*, 1866. L.

——— La contagion du choléra devant les corps savants. 8°. *Paris*, 1874. L.

Starr (D. L.) Remarks on the non-contagion of spasmodic or algide cholera.
[West. Lancet, 1849, ix, pp. 146–156.]

ırr (D. L.)—continued.

— Reasons for concluding that an excess of carbonic acid is the atmospheric ause of cholera.

N. Y. Jour. of Med., 1851, VI, pp. 203–215.]

ırling (J. W.) On the communicability f the cholera asphyxia.

N. Y. Jour. of Med., 1852, VIII, n. s., pp. 343–348.]

ıvens (A. H.) On the communicability f Asiatic cholera.

TRANS. N. Y. Med. Soc., 1850, pp. 32–39.]

ıkvis (B. J.) Infections-Versuche mit holera-Excrementen bei Thieren. Vorufige Mittheilung.

ZENTRALBL. f. d. med. Wissensch., Berlin, 1866, pp. 853–854.]

ısch (A. W. v.) Die Frage über Conagiosität oder Nicht-Contagiosität der siatischen Cholera, wissenschaftlich örtert. 8°. *Berlin*, 1831. L.

ambio (G.) Su l'ozono atmosferico urante l'ultima epidemia colerosa in ilano.

AZ. med. it. Lomb., Milano, 1856, I, 4a s., pp. 217–221, 225–228, 1 tav.]

— The same. 8°. *Milano*, 1856. L.

eicher (P. E.) Die Entlarvung der ientalischen Cholera. Eine auf Theoe und Erfahrung gegründete Systemak. 8°. *Magdeburg*, 1832.

ey. Théorie nouvelle sur la cause du oléra. Traitement simple et efficace. REVUE de thérap., Paris, 1854, II, pp. 122–123.]

ijorensis. Cholera non-contagiosa. OSTON Med. & Surg. Jour., 1833, II, p. 437.]

ain. Sur l'étiologie du choléra. ABEILLE méd., 1854, XI, pp. 268–269.]

r. Versuch einer Aetiologie der Chora, nebst Ideen über einige verwandte gegenstände.

YR. Ann. d. gesammt. Heilk., 1832, XXIII, pp. 113–146.]

riano (G.) Essai d'une théorie sur la ture de l'agent dont l'influence produit choléra-morbus épidémique. 8°. *Pa*, 1–48. L.

erge (A.) Note pour servir à l'histre de la marche et du mode de propation du choléra.

AZ. des hôp., 1854, pp. 555–556.]

ozan (J. D.) Origine nouvelle du olera asiatique, ou début et développent en Europe d'une grande épidémie olérique. 8°. *Paris*, 1870. L.

— Durée du choléra asiatique en Eue et en Amérique, ou persistance des

Tholozan (J. D.)—continued.

causes productrices des épidémies cholériques hors de l'Inde. 8°. *Paris*, 1872. L.

——— Nouvelles preuves de l'origine européenne du choléra.

[GAZ. hebd. méd. et chirurg., Paris, 1873, X, 2e s., pp. 459–461; *also*, reprint in 8°, Paris, 1873.]

——— Origine nouvelle du choléra asiatique. (Rapport par Seux père.)

[MARSEILLE méd., 1873, X, pp. 65–84.]

Thomas (L.) Die Verbreitungsweise der Cholera.

[ARCHIV d. Heilk., 1867, pp. 199–213.]

Thomas (W. J.) Progress in cholera. (Alteration of polarity of light the proximate cause of epidemic cholera.)

[MED. Times, 1850, I, n. s., pp. 155–156.]

——— On the constitution of choleraic light, and the transits of the epizonic power.

[LANCET, 1854, II, p. 190.]

Thomson (R. D.) Chemical researches on the nature and cause of cholera.

[MED.-CHIRURG. Trans., London, 1850, XXXIII, pp. 67–98; *also*, in LONDON Jour. Med., 1850, II, pp. 294–296.]

——— On the chemical conditions of cholera atmospheres.

[LANCET, 1856, I, n. s., pp. 63–64.]

Thur. Die Cholera ist ein Menschenwerk. Ein Lehrsatz der Thatsachen, für Arzte und Laien. 8°. *Schivelbein*, 1858. L.

——— Zur Aetiologie der Seuchen. I. Cholera.

[ALLG. med. Central-Zeitg., 1858, XXVII, p. 409.]

Tiersot. Le choléra n'est pas contagieux.

[GAZ. méd. de Lyon, 1866, XVIII, pp. 423–425, 442–445.]

Tognola (A.) Genesi, natura e modo di propagazione del colera asiatico. 4°. *Pavia*, 1868. S. C.

Trautmann. Die Zersetzungsgase als Ursache zur Weiterverbreitung der Cholera und Verhütung derselben durch zweckmässige Desinfection, mit besonderer Berücksichtigung des Süvern'schen Desinfections-Verfahrens. 8°. *Halle*, 1869. L.

Tucker (J. H.) To what agent or agents are the Jews indebted for their reported exemption from cholera?

[LANCET, 1854, II, n. s., p. 532.]

——— Alleged exemption of the Jews from cholera.

[LANCET, 1855, I, n. s., p. 110.]

Turnbull (W.) Examples of cholera spreading by contagion.
[LONDON Med. Gaz., 1832, IX, pp. 823-824.]

Tweedie (A.) Contagious nature of cholera in London.
[LONDON Med. Gaz., 1832, X, pp. 110-114.]

Tytler (R.) Remarks upon morbus oryzeus, or diseases occasioned by the employment of noxious rice as food. 2 parts. 8°. *Calcutta*, 1820.

——— Facts establishing the deleterious properties of rice, used as an article of food. 8°. *London*, 1833.

——— Reappearance of malignant cholera.
[LANCET, 1833-34, II, pp. 633-636.]

——— Production of cholera by rice.
[LANCET, 1834, II, pp. 895-896.]

——— Cholera from eating rice.
[LONDON Med. & Surg. Jour., 1835, VI, pp. 217-218.]

Ullmann (F.) Beitrag zu den oro- und hydrographischen Verhältnissen der Cholera.
[ZEITSCHR. f. Natur- u. Heilk. in Ungarn, 1856, VII, pp. 386-387.]

Vandenbroeck. Le choléra est-il contagieux?
[ARCH. belges de méd. mil., 1850, VI, pp. 266-273.]

Vannaire (A.-V.) * D'une des causes du choléra. 4°. *Paris*, 1859. L.

Velpeau. Remarques sur la manière dont s'est propagé le choléra.
[GAZ. méd. de Paris, 1832, III, pp. 863-864.]

Ventura (L.) Riflessioni critiche su la volnta contagione del cholera asiatico. 8°. *Napoli*, 1837.

Vergé (F.) De l'électricité comme cause de choléra. De l'hydrothérapie comme moyen de guérison. 4°. *Foix*, 1858.

Vésignié (J. B.) Documents sur le choléra asiatique considéré comme maladie contagieuse. *Abbeville*, 1847.

Vest (L., *Edler* v.) Ist die asiatische Cholera ansteckend?
[MED.-CHIR. Zeitg., 1831, IV, pp. 257-272, 273-280.]

——— Il cholera asiatico è egli contagioso? [*Milan*, 1835.]

Vialle. Réfutation de quelques-unes des assertions alléguées, en faveur de la contagion du choléra.
[ANN. de la méd. phys., 1834, XXV, pp. 852-859.]

——— Réponse à M. L. Labat, sur la contagion et la nature du choléra-morbus épidémique. 8°. 1834. L.

Vialle—continued.

——— Sur la contagion et la nature du choléra-morbus épidémique.
[ANN. de la méd. phys., 1834, XXV, pp. 84-92.]

Vogt (F. A.) Cholera und Grundwasser.
[AERZTL. Intell.-Bl., 1869, XVI, pp. 15-61.]

Walker (W.) Report on the cholera influence in the atmosphere of the [illegible] western provinces, between the 7th and 15th June, 1864.
[SELECTIONS from the records of the north western provinces, India, [illegible] part XLII, pp. 14-15.]

Wallace (J.) Cholera, its cause [illegible]. 8°. *Belfast*, 1866.

Walsh (P. D.) Contagiousness of cholera.
[BOSTON Med. & Surg. Jour., 1849, [illegible] 432-433.]

Walton (H. B.) Cholera in Nottingham in relation to limestone.
[WEST. Jour. Med. & Surg., 1849, [illegible] 271-272.]

Ward (F. H.) Cholera mist.
[MED. Times & Gaz., 1866, II, p. [illegible]]

Ward (T. O.) Inquiry into the [illegible] of cholera.
[PROV. Med. Jour., 1843, pp. 694-697]

Waterman (S.) On the influence of deficient supply of chloride of sodium upon the rise and progress of cholera.
[N. Y. Med. Record, 1872, VI, p. 5[illegible]]

Watson. The cholera of India: its diffusion by contagion.
[LONDON Med. Gaz., 1848, XLI, pp. 45-[illegible]]

Weber (H.) On Prof. Pettenkofer's theory of the mode of propagation of cholera.
[TRANS. Epid. Soc., Lond., 1853, II, pp. 4[illegible]]

Weber (H.) * Ueber den ätiologischen Zusammenhang zwischen Cholera und Boden. sm. 8°. *Berlin* [1867]

Wieger. La mucédinée du choléra.
[GAZ. hebd. de med. et de chir., 1866, 65-67, 97-100.]

Wilkins (R.) Thoughts on the nature of cholera.
[MADRAS Quar. Jour. Med. Sci., [illegible] 337.]

Wille (V.) Ueber den Einfluss des Bodens auf die Verbreitung der Cholera.
[AERZTL. Intell.-Bl., 1873, XXII, p. 112, 117-122, 128-131, 136-143.]

Willemin (A.) Considérations sur la marche de propagation du choléra. 8°. 1866.

'illiams (B. B.) A treatise upon the electrical philosophy and cure of cholera. 12°. *Richmond*, 1849. L.

'illiams (N.) The remote and immediate causes of cholera.
[Boston Med. & Surg. Jour., 1849, XL, pp. 396–398.]

illiamson (M. S.) Strange coincidence n connexion with cholera. [Case from handling articles infected the year before.]
[Med. Times & Gaz., 1854, IX, n. s., pp. 401–402.]

ilson (E.) Contagiousness of cholera.
[Lancet, 1853, II, p. 422.]

ittelshöfer (L.) Ist die Cholera ansteckend oder nicht? Sanitäts-polizeiliche Bemerkungen, mit Rücksicht auf in diesbezügliches französisches Votum.
[Wien. med. Wochenschr., 1866, pp. 1257–1260, 1273–1276, 1305–1308.]

orms (J.) De l'invasion du choléra et de son mode de propagation.
[Gaz. hebd. de méd. et de chirurg., Paris, 1865, 2e s., II, pp. 679–682, 709–716.]

— De la propagation du choléra et des moyens de la restreindre. 8°. *Paris*, 1865. L.

—De Wijze van Verspreiding der Cholera en de Middelen om die te stuiten. Naar het Fransch door P. J. Van Eldik Thieme. 8°. *Amsterdam*, 1866. L.

— Choléra. Contagion et non-contagion. (Rapport lu à la Société de médecine de Paris dans les séances des 1er et 15 février 1867.)
[Gaz. des hôp., 1867, pp. 269–283.]

ight (T. G.) Cause of cholera.
[Lancet, 1833, II, p. 112.]

ıgl. Blattern und Cholera, verbreiten sich selbe ganz gleichartig durch Contagien?
[Aerztl. Intell.-Bl., 1875, XXII, pp. 51–53.]

ıdyck. Sur la propagation du choléra.
[Bull. de l'Acad. nat. de méd., 1848–49, XIV, pp. 1061–1069.]

suchtung (Freimüthige), des Benehmens der Berliner verordneten Contagionisten in Bezug auf die Cholera, &c. 8°. *Altenburg*, 1832.

mettelijkheid der Cholera.
[Nederland. Lancet, 1849–50, 2e s., V, pp. 100–107, 253–264, 265–272.]

ses of cholera.
[Med. Times, 1850, I, n. s., p. 154.]

ses of the epidemic cholera.
[Jour. of Health, 1832, III, pp. 27–30.]

Cholera (Die), als Folge eines tellurischen, mineralischen Giftes.
[Berlin. med. Central-Zeitung, 1839, I, pp. 235–236.]

Cholera and air currents.
[Lancet, 1868, II, p. 550.]

Cholera and impure water.
[Med. Times & Gaz., 1854, IX, n. s., pp. 420–421.]

Cholera and the London water supply.
[Med. Circular, 1853, III, p. 426; *also*, in Med. Times & Gaz., 1853, VII, n. s., pp. 558–559.]

Cholera (The) and the market gardens.
[London Med. & Surg. Jour., 1833, II, pp. 59–60.]

Cholera and water.
[Med. Press & Circ., 1868, VI, pp. 188–189.]

Cholera atmosphere.
[Med. Times & Gaz., 1863, II, pp. 498–499.]

Cholera (The.) Contagion and quarantine.
[Boston Med. & Surg. Jour., 1866, LXX, pp. 382–386.]

Cholera contagious.
[London Med. & Surg. Jour., 1832, I, pp. 371–372.]

Cholera en Vergiftiging.
[Nederl. Tijdschr. v. Geneesk., 1857, I, pp. 340–342.]

Cholera from rice.
[Dublin Med. Press & Circ., 1867, IV, p. 233.]

Cholera (De) geene besmettelijke Ziekte. Een bemoedigend Volkswoord. 8°. *Nijm*, 1832.

Cholera (Die) nicht ansteckend. Für Aerzte, so wie zur Beherzigung und Beruhigung für alle die, welche derselben mit Furcht und Zagen entgegensehen, etc. 8°. *Posen*, 1831.

Cholera.—Question de la contagion.—Influence de la température sur la marche de l'épidémie.
[Gaz. méd. de Paris, 1849, IV, pp. 729–730.]

Cholera versus filth.
[Boston Med. & Surg. Jour., 1867, LXXVI, pp. 438–441.]

Choleraic poison. [Letter to the editor of the Times,] dated September 5, 1866. [Ext.] L.

Choléra-morbus (Le) de Madrid: ses médecins non-contagionists.
[Gaz. des hôp., 1834, VIII, pp. 437–473.]

Communicability (The) of cholera.
[Lancet, 1867, II, pp. 488, 530–531.]

Contagion (De la) du choléra.
[Gaz. des hôp., 1849, pp. 267–268, 481–482; *also*, in Bull. gén. de thérap., méd. et chir., 1849, XXXVII, pp. 12–18.]

Contagion of cholera.
[London Med. & Surg. Jour., 1833, II, pp. 183–184.—Lancet, 1841, I, pp. 227–228.—Dublin Med. Press & Circ., 1866, I, p. 467.]

Contagion (The) of cholera vindicated.
[LONDON Med. & Surg. Jour., 1833, II, pp. 168–171.]

Contagion (De la) ou non-contagion du choléra.
[GAZ. des hôp., 1866, pp. 449–450, 461–462.]

Contagiousness of cholera.
[BOSTON Med. & Surg. Jour., 1831, V, pp. 405–412 *also, in* MED. Press & Circ., London, 1874, XVII, n. s., pp. 383–384.]

Contribution à l'histoire de la transmission du choléra.
[L'UNION méd., 1865, XXVIII, 2e s., pp. 509–510.]

Coup-d'œil rétrospectif sur le choléra de 1832 et 1849, au point de vue du mode de propagation de cette épidémie.
[REVUE méd., 1866, I, pp. 28–38.]

Cryptogamic theory of cholera.
[LONDON Jour. of Med., 1849, I, pp. 1048–1059, 2 pl.]

Curious case of malignant cholera—strong proof of contagion.
[LANCET, 1833, I, pp. 601–603.]

Diffusion of cholera by articles of clothing—disinfection of clothing by heated currents of air.
[LONDON Med. Gaz., 1849, XLIII, pp. 199–202.]

Discussion on the propagation of cholera by water.
[BRITISH Med. Jour., 1867, I, pp. 701–702.]

È égli il colera d'oggi giorno veramente contagioso? Riposta a questo quesito data dal dottor Luigi Emiliani. 8°. *Bologna*, 1836.

Effect of inhaling the atmosphere emanating from the person of a cholera patient.
[BOSTON Med. & Surg. Jour., 1833, VII, pp. 81–83.]

Enquiry (An) into the remote cause of cholera. 8°. *London*, 1832. L.

Etiological anomalies in cholera.
[MED. Times & Gaz., 1854, IX, n. s., p. 167.]

Fallacies about cholera.
[DUBLIN Med. Press, 1865, XII, pp. 165–168.]

Foranstaltninger i Anledning af Cholera.
[NORSK Mag. for Laegevid., Christiania, 1848, II, pp. 125–128, 487, 707; 1849, III, pp. 149, 344, 418, 558, 652; 1850, IV, pp. 195, 335, 582, 660, 736, 798; 1851, V, pp. 61, 178, 297, 423; 1853, VII, pp. 188, 573, 661, 868; 1854, VIII, pp. 69, 135, 200, 270, 349, 609.]

Fungoid (The) theory of cholera.
[BRITISH Med. Jour., 1870, II, pp. 535–536.]

How is the cholera propagated? The question considered, and some facts stated. [By an American physician.] 8°. 1831. L.

Immunité (De l') acquise par les ouvriers en cuivre par rapport au choléra.
[GAZ. des hôp., 1866, pp. 173–174, 229–230, 265–266.]

Immunity of Jews from cholera.
[MED. Times & Gaz., 1853, VII, n. s., p. 356.]

Impure water and cholera.
[MED. Gaz., 1869, III, p. 22.]

Impure water and cholera—prevention of the disease.
[WILSON'S Herald of Health, 1873, I, pp. 38–47.]

Infectious (The) nature of [pestilential] cholera.
[LONDON Med. Gaz., 1846, XXXVIII, pp. 517–522.]

Influence de la peur dans l'épidémie de choléra-morbus de Paris.
[GAZ. méd. de Paris, 1832, III, pp. 727–732.]

Influence (The) of elevation of site in cholera.
[MED. Circular, 1854, V, pp. 275–276.]

Inquiry (An) into the remote cause of cholera. 8°. *Edinburgh*, 1832.

Insectes cholérifères.
[GAZ. med. de Paris, 1836, IV, p. 756.]

Interesting details, shewing that malignant cholera does not spread from the persons of the sick.
[LONDON Med. & Surg. Jour., 1833, II, pp. 249–250.]

Intorno alla natura del miasma colerico asiatico congetture di B. M. trasmesse alla Società med. chir. di Berlina. 8°. *Lucca*, 1832.

Invloed (De) van het Drinkwater op de Verspreiding der Cholera.
[NEDERL. Tijdschr. v. Geneesk., 1867, II, pp. 372–376.]

Is cholera in this country contagious?
[LONDON Med. Gaz., 1832, X, pp. 165–171.]

Können Epidemien allein durch die Luft verbreitet werden? Anfrage und Aufruf an die Aerzte, etc., zur Beruhigung des Publikums, veranlasst durch die wiederausgebrochene Cholera-Morbus. 12°. *Danzig*, 1831.

Letters on the cholera morbus, containing ample evidence that this disease, under whatever name known, cannot be transmitted from the persons of those labouring under it to other individuals by contact through the medium of inanimate substances, or through the medium of the atmosphere; and that all restrictions, by cordons and quarantine regulations, are as far as regards this disease, not merely useless, but highly injurious to the community. By a professional man of thirty years' experience, in various parts of the world. 8°. *London*, 1831. L.

[o]de in which cholera is propagated.
[London Med. Gaz., 1832, IX, pp. 185-196, 234-238.]

[o]de of propagation of cholera.
[London Med. Gaz., 1849, XLIV, pp. 197-199.]

ew contagious disease identical with cholera.
[London Med. & Surg. Jour., 1833, II, p. 631.]

ew hygrometric theory of cholera.
[Lancet, 1859, I, n. s., p. 299.]

on-contagion (De la) du choléra.
[Gaz. des hôp., 1866, pp. 377-378.]

on-contagiousness of cholera.
[London Med. & Surg. Jour., 1832, I, p. 358.]

ouvelle (D'une) théorie étiologique et prophylactique du choléra.
[Gaz. des hôp., 1855, p. 5.]

a the causes and diffusion of Cholera.
[Brit. & For. Med.-Chir. Rev., 1848, II, pp. 62-107.]

a the causes and propagation of Asiatic cholera. (Review.)
[Brit. & For. Med. Rev., 1847, XXIII, pp. 313-345.]

a the causes of cholera.
[Doctor, 1833, I, p. 11.]

a the contagiousness of Asiatic cholera.
[Boston Med. & Surg. Jour., 1849, XXXIX, pp. 429-440.]

a the editorial remarks on the fungoid theory of cholera.
[Prov. Med. & Surg. Jour., 1849, p. 697.]

a the effect of fear in predisposing to cholera.
[Doctor, 1833, I, p. 34.]

a the fungoid theory of cholera.
[Prov. Med. & Surg. Jour., 1848, pp. 685-686.]

a the local causes of cholera.
[Brit. & For. Med.-Chir. Rev., 1857, XIX, pp. 61-85.]

a the magnetic theory of cholera.
[Lancet, 1848, I, p. 68.]

a the propagation of cholera by water as a medium, with special reference to the outbreak at Theydon Bois (Essex), 1865.
[Med. Times & Gaz., 1867, I, pp. 510-511.]

a the proximate cause of cholera.
[London Med. Gaz., 1832, IX, pp. 529-532.]

a the proximate cause of epidemic cholera.
[Med. Times, 1849, XX, p. 464.]

nuleurs lettres sur la question de la contagion du choléra.
[Gaz. méd. de Paris, 1849, IV, 3e s., pp. 405-407.]

ostscript to Dr. Graves's paper on the diffusion of cholera.
[Dublin Quar. Jour. of Med. Sci., 1849, VII, pp. 242-248; 1851, XI, pp. 214-216.]

Production (The) of Asiatic cholera ascribed to the use of diseased rice as food.
[Lancet, 1834, I, pp. 67-72.]

Proofs of the contagion of cholera.
[London Med. Gaz., 1848, XLIII, pp. 740-741, 1 table.]

Proofs that the cholera is not contagious.
[London Med. & Surg. Jour., 1833, II, pp. 146-151.]

Propagation of cholera.
[London Med. Gaz., 1832, IX, pp. 527-528: *also in* Lancet, 1832, I, p. 417; II, pp. 217-219.]

Proximate cause of cholera.
[London Med. Gaz., 1831, VIII, pp. 466-467.]

Query—do cholera vegetables produce cholera?
[London Med. Gaz., 1833, XI, pp. 261-264.]

Remarks on the mode of propagation of cholera.
[London Med. Gaz., 1848, XLI, pp. 13-16.]

Sulla causa specifica del colera asiatico, il suo processo patologico e l'indicazione che ne resulta. *Firenze*, 1865.

Sur la transmissibilité du choléra.
[Gaz. des hôp., 1865, p. 585.]

Sur l'influence des conditions géologiques sur le développement du choléra.
[Gaz. hebd. de méd. et de chirurg., Paris, 1853-54, I, p. 1136.]

Sur l'influence des eaux potables sur le développement du choléra.
[Gaz. hebd. de méd. et de chirurg., Paris, 1853-54, I, pp. 843, 1020.]

Théories (Des) sur le choléra et de l'influence qu'elles ont exercée sur la thérapeutique de cette maladie. Le choléra est-il une gastro-entérite?
[Bull. gén. de thérap., méd. et chir., 1872, II, pp. 276-279.]

Transmission (De la) du choléra.
[Bull. gén. de thérap., méd. et chir., 1866, LXXI, pp. 321-324.]

Ueber die Ursachen der Cholera, nebst Vorschläge zur Bekämpfung derselben. *Altona*, 1831.

Untersuchungsplan zur Erforschung der Ursachen der Cholera und deren Verhütung. Denkschrift, verfasst im Auftrage des Reichskanzler-Amts von der Cholera-Kommission für das deutsche Reich.
[Med. Corrsbl. d. württemb. ärztl. Vereins, Stuttgart, 1873, XLIII, pp. 249, 257, 265.]

——— The same. 8°. *Berlin*, 1873. L.

Ursprung und Verbreitungsart der Cholera; Commissionsbericht der interna-

Ursprung, *etc.*—continued.

tionalen Sanitätsconferenz. 8°. *München*, 1867.

Vatbaarheid voor Cholera.

[NEDERLAND. Lancet, 1849–50, 2e s., v, pp. 60–62.]

Water supply of London and Cholera.

[MED. Times & Gaz., 1854, IX, n. s., pp. 427–429.]

Zur Aetiologie der Cholera.

[ALLG. med. Central-Zeitg., 1865, XXXIV, pp. 757–759, 769–772, 785–789.]

Zur Aetiologie der Cholera. Aus der Cholera-Conferenz zu Weimar am 28. und 29. April 1867.

[ARZT. Intell.-Bl., 1867, XIV, pp. 425–430.]

CHOLERA IN ANIMALS.

Bartholow. Observations, pathological and experimental, upon cholera.

[CINC. Lancet & Observ., 1866, IX, pp. 652–664.]

Bochdalek. Cholera bei Thieren.

[VIERTELJAHRSCHR. f. d. prakt. Heilk., Prag, 1850, I, part 2, Erg.-Blätt., pp. 7–8.]

Botkin. Versuche über die Infection von Thieren durch die Ausleerungen Cholerakranker, mit besonderer Beziehung zur Lehre über die Wirkung von Fäulnissproducten.

[BERL. klin. Wochenschr., 1872, IX, p. 393.]

Caffe (P.) Du choléra-morbus observé chez les lapins. Spécialités anatomico-physiologiques.

[GAZ. des hôp., Paris, 1832, VI, pp. 312–316, 339–340.]

Charcellay. Choléra-morbus transmis de l'homme à la poule par des matières cholériques mêlées aux aliments.

[GAZ. hebd. de méd. et de chirurg., Paris, 1856, III, pp. 240–241.]

Churchill (F.) Observations on epizootic cholera.

[DUBLIN Jour. of Med. Sci., 1832, II, pp. 27–29.]

Colvan (J.) Epizootic disease in a pig, similar to that prevailing among swine during the last two years, and somewhat analogous to malignant cholera, apparently induced by contagion from infected clothes.

[LANCET, 1834, II, pp. 192–193.]

Dechambre (A.) Expériences sur la transmission du choléra aux animaux.

[GAZ. hebd. de méd. et de chirurg., Paris, 1853–54, I, pp. 939–940; 1855, II, pp. 397–398.]

Eletti (G.) Intorno all'inoculazione del coléra morbo asiatico sopra li animali domestici.

[GAZ. med. It. Lomb., Milano, 1855, VI, 3a s., pp. 150–151.]

Ferguson (P.) On a remarkable instance of cholera in the horse.

[LANCET, 1849, I, n. s., p. 267.]

Guttmann (P.) *und* **Baginsky** (A.) Zur Cholera. Einige Versuche an Thieren. Vorläufige Mittheilung.

[CENTRALBL. für die med. Wissensch., 1866, pp 689–692.]

Levestamm (A.) Die Cholera orientalis als enzootischer Vergiftungs-Prozess dargestellt. 8°. *Kiel*, 1831.

Liégey. Le choléra du cheval.

[L'UNION méd., 1849, III, p. 509.]

——— Le choléra dans la race ovine et l'influence cholérique chez l'homme dans une même localité.

[JOUR. de méd., chir. et pharm., Bruxelles, 1854, XIX, pp. 245–247.]

Lindsay (W. L.) On the communicability of cholera to the lower animals.

[EDINB. Med. & Surg. Jour., 1854, pp. 275–300, 630–648.]

——— The same. 8°. *Edinburgh*, 1854. C.

——— On the influence of cholera on lower animals.

[EDINB. Med. Jour., 1857, III, pp. 33–45.]

——— On choleraization.

[LANCET, 1866, II, pp. 600–601.]

Montani. Sintomi di cholera che si svilupparono nei gatti.

[GIORN. p. serv. al progr. d. patolog., Venezia, 1836, V, pp. 413–414.]

Namias (G.) Esperienze sugli animali col sangue dei cholerosi.

[OMODEI, Ann. un. di med., 1836, LXXIX, pp. 162–168.]

Novati (G.) Sperienze sugli animali vivi con materie tratte dai cholerosi.

[GIORN. p. serv. al progr. d. patolog., Venezia, 1836, V, pp. 373–407; 1837, VI, pp. 207–238.]

Ranke (H.) Cholera-Infections-Versuche an weissen Mäusen.

[ARZTL. Intell.-Blatt, 1874, XXI, pp. 131–135.]

Semmola (G.) Degli sperimenti fatti col sangue de colerosi in taluni animali.

[OMODEI, Ann. un. de med., 1838, LXXXIV, pp. 150–172.]

Snellen (H.) *and* **Miller** (H. G.) Can cholera be communicated to animals?

[DUBLIN Med. Press & Circ., 1867, IV, pp. 323–325.]

Thiersch (C.) Infections-Versuche an Thieren mit dem Inhalte des Cholera-darmes. 8°. *München*, 1855–56. L.

——— Meine Cholera-Infectionsversuche vom Jahre 1854 und die des Herrn Dr. B. J. Stockvis vom Jahre 1866.

[ZUR Abwehr u. Berichtigung Ztschr. f. Biol., 1867, III, pp. 137–140.]

Wolffhügel (G.) Zur experimentellen Bearbeitung der Cholerainfectionsfrage.
[Archiv f. exper. Path. u. Pharmak., 1873, I, pp. 414–419.]

Bemerkungen der medicinischen Facultät in Wien über den, während der Cholera-Epidemie beobachteten Einfluss der epidemischen Constitution auf Thiere.
[Med. Jahrb. des kaiserl. königl. oesterreich. Staates, 1834, VI, n. F., pp. 544–547.]

Choléra (Le) des chevaux. [From the "Lucknow Times".]
[Tribune (La) méd., Paris, 1874, VII, p. 202.]

Cholera in domesticated animals.
[Lancet, 1833, II, pp. 138–142.]

Choléra-morbus (Le) chez les animaux.
[Gaz. des hôp., 1832, VI, p. 82.]

Cholera simulated in sheep.
[Med. Times & Gaz., 1853, VII, n. s., p. 568.]

Communicability (The) of cholera to animals.
[Brit. & For. Med.-Chir. Rev., 1853, XI, pp. 390–409.]

Épidémie (D'une) cholériforme chez les gallinacés.
[Gaz. des hôp., 1836, X, p. 588.]

Human (The) blight and cattle blight, or an explanation of the cholera and cattle plague. 8°. *London*, 1866.

Tast de Cholera ook de Dieren aan?
[Genees. Courant, Tiel, 1849, No. 33.]

B.—HYGIENE AND METHODS OF PREVENTION.

Adam (D. L.) Moyens préservatifs du choléra. Préparation désinfectante anticholérique. 8°. *Alger*, 1867.

Addison (W.) An investigation of the effects of terrestrial radiation, with reference to malaria in general, indicating precautionary measures against cholera in particular.
[London Med. Gaz., 1832, IX, pp. 752–756.]

Agar de Bus (d').] Préservatif du choléra épidémique. (1855.) 4°. *Issoudun* [*n. d.*]

Agostini (C.) Risposte della deputazione sanitaria comunale di Forlì alla circolare di quella delegazione. [Sul colera.]
[Gaz. med. it. Tosc., Firenze, 1856, II, 3a s., pp. 152–157.]

Aiton (W.) Dissertations on malaria, contagion, and cholera; explaining the principles which regulate endemic, epidemic, and contagious diseases, with a view to their prevention: intended as a guide to magistrates, clergymen, and heads of families. 8°. *London*, 1832. L.

Albu (J.) Der Schutz gegen die Cholera. 12°. *Berlin*, 1866. L.

Aliés (B.) Possibilité d'amoindrir considérablement les ravages du choléra, rectification de quelques préjugés populaires relativement à cette maladie. 2e éd. 8°. *Luxeuil*, 1853. L.
[1st ed., 8°, Besançon, 1850.]

Allison (E. D.) Letters on the early interment of persons who die of cholera. 8°. *Edinburgh*, 1832.

Ambach (E. v.) Die Choleraepidemie oder: Einzig wahres Schutzmittel gegen Furcht und Angst vor dieser Seuche. 8°. *Wien*, 1854. L.

Andreucci (O.) Manuale populare di precetti igienici e sanitarii per il cholera-morbus. 8°. *Firenze*, 1855.

Antonini (G.-B.) Sull'opuscolo del prof. Angelo Bo, intitolato: "Le quarantene ed il cholera-morbus". 8°. *Genova*, 1855.

Armieux. Prophylaxie du choléra—aux des actes du comité médical des Bouches-du-Rhône.
[Rev. méd., Toulouse, 1867, I, pp. 106–111.]

Arnim (v.) Wie hat man sich bei der jetzt (1837) hier herrschenden Cholera-Epidemie zu verhalten. 8°. *Berlin*, 1837.

Aschenbrenner (G.) Ueber die asiatische Cholera und deren Verhütung. 8°. *Regensburg*, 1831.

Auerbach (H. M.) Aufklärungen und Verhaltungsregeln zur Abwehr der Cholera. 8°. *Berlin*, 1854. L.

Axmann (C.) Zur Cholera-Frage. Mahnung an alle Diejenigen, welchen die öffentliche Gesundheitspflege am Herzen liegt. 8°. *Erfurt*, 1867.

Babington (B. G.) The admission of cholera patients into hospital.
[Med. Circular, 1853, III, pp. 248–249; *also*, in Lancet, 1853, II, p. 305.]

Balestreri (F. M.) I preservativi del cholera. *Genova*, 1865.

Ballot (A. M.) Het Drinkwater in eenige onzer Steden uit een hygienisch Oog-

Ballot (A. M.)—continued.
punt beschouwd, vooral in Betrekking tot Cholera.
[NEDRL. Tijdschr. v. Geneesk., 1868, II, pp. 175–248, 1 pl.]

——— Remarks on the influence of a pure supply of water.
[MED. Times & Gaz., 1872, II, pp. 349–351.]

Bang (O.) Om de for Kjöbenhavn passende Foranstaltningen under en Cholera-Epidemi.
[UGESKR. for Laeger, Copenhagen, 1853, XIX, pp. 129–144.]

Barrie (C.) Wodurch kann die Weiterverbreitung der Cholera in Deutschland verhindert und der Stoff zu dieser Krankheit in der Wurzel vernichtet werden? 8°. *Leipzig*, 1831.

Barthélemy (C.) Das Schutz- und Heilmittel der Cholera sowie der Pocken oder Blattern auch dienlich bei anderen, sowohl schleunigen als andauernden Krankheiten oder Leiden. 8°. *Elberfeld*, 1851. L.

Barzellotti (G.) Due lettere importanti, l'una d'illustre dama Toscana sul timore del cholera-morbus al . . . . . ; l'altra responsiva del medesimo professore Rinfrancando La Dama dal concepito timore. 8°. *Pisa*, 1855. L.

Barzilai (C.) Il cholera; manuale ad uso di ogni classi di persone. 16°. *Venezia*, 1855.

Beaman (G.) On the prevention of cholera amongst our troops and seamen in the east.
[LANCET, 1855, I, n. s., pp. 430–431.]

Bédor (H.) Sur l'appréhension du choléra-morbus, les moyens proposés pour s'en préserver, ceux qui conviendraient surtout à Troyes, si cette ville s'en voyait menacée. 8°. *Troyes*, 1831.

Bell (G. H.) Letter to Sir Henry Halford on the tendency of the proposed regulations for cholera. With observations as to the nature of the disease, and the course to be followed immediately on its appearance in a family. 8°. *Edinburgh*, 1831. L.

Bellanger. Du choléra, et des moyens de prévenir son développement.
[L'ABEILLE méd., 1853, X, pp. 321–323.]

Berruti (S.) Relazione sulle memorie del prof. A. Bo intitolate "Le quarantene e il cholera-morbus," letta alla R. accademia med. chir. di Torino. 8°. *Torino*, 1855.

Berruti (S.)—continued.
tene e il cholera-morbus," letta alla R. accademia med. chir. di Torino. 8°. *Torino*, 1855.

Berti (A.) Il cholera e i ministri francesi.
[GAZ. med. ital. prov. Venete, 1865, VIII, pp. 357–362, 373–375.]

Bestel (C.) * Considérations sur les épidémies en général, et particulièrement sur celles du choléra, au point de vue des moyens prophylactiques. 4°. *Paris*, 1858. L.

Beullac (J. F.) Nouvelle instruction sur les diverses précautions à prendre pour se préserver de la maladie régnante du choléra-morbus. (1835.) 8°. *Marseille* [*n. d.*]

Beynat (G. M.) Nouveau moyen de se préserver du choléra-morbus, mémoire présenté à la Société médicale de Montpellier.
[GAZ. méd. de Paris, 1832, III, p. 636.]

——— The same. . . . spécialement appliqué a la salubrité des habitations. 8°. *Paris*, 1832.

Bidlot (F.) A propos du choléra: Conseil d'hygiène publique sur le cimetière de Robermont.
[ANN. Soc. méd.-chirurg. de Liége, 1874, XIII, 33–43.]

Bird (S. D.) On the nature and treatment of epidemic cholera, and the influence of quarantine and hygienic precautions in arresting its progress. 8°. *Bournemouth*, 1866.

Bischoff (I. R.) Brevi cenni sul cholera e mezzi preservativi del cholera. 12°. [1831.]

Blache. Instruction populaire sur les moyens de prévenir le choléra et de combattre les premiers symptômes. 8°. *Cherbourg*, 1849.

Black (A.) Et par Ord om de Foranstaltninger der Maatte kunne traeffes i Landdistrikterne under Faren for en Cholera-Epidemie.
[UGESKR. for Laeger, 1851, XIV, pp. 177–[illegible]

Blacklock (A.) Do smallpox and cowpox afford any protection from the cholera? *London* [1867?].

Blanc (H.) Choléra et chloralum: prophylactif et antidote. 8°. *Paris* [1]

——— Cholera; how to avoid and treat it. 12°. *London*, 1873.

Blanc (H.)—continued.

—— Les moyens de se préserver du choléra.

[Compte rendu, Ass. franc. pour l'avancement des sc. (2e sess., Lyon), Paris, 1874, pp. 20–39.]

Blane (G.) Warning and admonition to the British public on the introduction (now well ascertained) of the cholera of India. 8°. *London*, 1831. L.

—— Warning to the British public against the alarming approach of the Indian cholera. 8°. *London*, 1831. L.

Blétry. Instruction abrégée sur les moyens préservatifs contre le choléra. 4°. *Belfort* [1832].

Bo (A.) Le quarantene ed il cholera-morbus. (2 parties en 1 vol.) 8°. *Genova* [n. d.]

—— Rapporto sulle quarantene e sul modo di riformarle.

[Omodei, Ann. un. di med., 1849, cxxxi, pp. 161–179.]

—— Basi generali di un progetto di congresso quarantenario di delegati di tutte le potenze marittime che hanno porti nel Mediterraneo.

[Omodei, Ann. un. di med., 1851, cxxxvii, pp. 397–403.]

—— Sull'ordinamento sanitario stabilito in Francia con decreto 24 Dicembre 1840.

[Omodei, Ann. un. di med., 1851, cxxxvii, pp. 398–403.]

Boddy (W. B.) Diet and cholera; showing the vital importance of wholesome diet, and that its impurities and deficiencies are chief cause of cholera. 8°. *London*, 1848.

Boisseau (F. G.) Traité du choléra-morbus, considéré sous le rapport médical et administratif, ou recherches sur les symptômes, la nature et le traitement de cette maladie, et sur les moyens de l'éviter. Suivi des instructions concernant la police sanitaire. 8°. *Paris*, 1832. L.

Bonnafont (J. P.) Discours sur les moyens à opposer à l'invasion du choléra asiatique. 8°. *Paris* [1853].

—— Moyen prophylactique, le seul efficace à opposer aux invasions ultérieures du choléra . . . . . 8°. *Paris*, 1865.

—— Le choléra et le congrès sanitaire diplomatique international. 8°. *Paris*, 1866. L.

—— Prophylaxie du choléra.

[L'Union méd., 1873, xvi, 3e s., pp. 489–495.]

Bories (A.) Note sur l'emploi de l'iode comme moyen disinfectant et préservatif du choléra.

[L'Union med., 1854, viii, pp. 421–422.]

Borsarelli. Risultato di alcuni sperimenti comparativi delle varie sostanze proposte per la disinfezione delle materie emesse dai colerosi.

[Giorn. d. R. accad. di med. di Torino, 1865, liv, pp. 295–297.]

—— Del valore di alcuni nuovi mezzi disinfettanti in riguardo al cholera.

[Giorn. d. R. accad. di med. di Torino, 1865, liv, pp. 233–238.]

Boureau (F.) Choléra. Mode de propagation et moyens préservatifs. 8°. *Paris*, 1868. L.

Bourgeois-Pin (J. M.) Traité du choléra et des moyens préservatifs de cette épidémie; suivi du petit traité de la maladie des pommes de terre et de la vigne. 32°. 1854.

Bourgogne (*père*). Considérations générales appliquées à l'hygiène publique et privée pendant le cours d'une épidémie de choléra asiatique. [3e mémoire.]

[Jour. de méd., chir. et pharm., Bruxelles, 1856, xxiii, pp. 206–224, 309–330.]

—— Réponse au rapport de M. le Dr. Dehous sur un mémoire adressé à la Société d'agriculture, sciences et arts de Valenciennes, intitulé: "Considérations générales appliques à l'hygiène publique et privée pendant le cours d'une épidémie de choléra indien." 8°. *Valenciennes*, 1857.

Boutraye (de la). Circulaire adressée par le consul de France à Dantzick à Mess. les membres de l'intendance sanitaire à Nantes.

[Jour. sect. de méd. Soc. acad. dept. Loire-Inf., 1832, viii, pp. 27–55.]

Bouyer. Communications sur le choléra. De quelques moyens prophylactiques contre le choléra.

[L'Union méd., 1865, xxviii, 2e s., pp. 88–89.]

Brambilla (A.) Sulla necessità di attivare pronte ed energiche misure nei primi casi di cholera.

[Gaz. med. it. Lomb., 1849, ii, 2a s., pp. 352–353.]

Brand (E.) Verhaltungsmassregeln während der Anwesenheit der Cholera-Epidemie und Anweisung, wie im Nothfalle sich selber zu helfen. 2te Aufl. 8°. *Stettin*, 1866.

Briand. Instructien raisonnée sur les moyens de se préserver du choléra-morbus. 2e éd. 8°. *Rennes*, 1832.
[1e éd. same year.]

Broca (P.) Des mesures préventives contre le choléra.
[Gaz. hebd. de méd. et de chirurg, 1853–54, I, pp. 53–57.]

Bronson (H.) Observations on the chlorides and chlorine as disinfecting agents and as preventives of cholera. 8°. *Boston*, 1832. L.
[*Also reprinted in* Boston Med. & Surg. Jour., 1833, VII, pp. 85–94.]

Brookes (J.) Thoughts on the best means of lessening the destructive progress of the cholera. 8°. *London*, 1831.

Broquin (L. P.) Mémoire sur une méthode prophylactique du choléra-morbus asiatique. 8°. *Nîmes*, 1832.

Brown (F. C.) On the prophylactic properties of salt as preventive of cholera.
[Madras Quar. Jour. of Med. Sci., 1863, VII, pp. 439–451.]

Bubola (G.) La rivaccinazione si potrebbe cimentare quale mezzo preservativo nel caso di una epidemia colerica? [Con appendice.]
[Gaz. med. Ital. prov. Venete, 1858, I, pp. 249–250, 307.]

——— La rivaccinazione profilattica del cholera.
[Gaz. med. Ital. prov. Venete, 1867, X, p. 343.]

——— Dell'innesto vaccinico come profilattico del cholera.
Gaz. med. Ital. prov. Veneta, 1868, XI, pp. 81–82.]

Bucquoy (J.) De l'opportunité de l'isolement des cholériques dans les hôpitaux, prouvée par les documents administratifs.
[Gaz. hebd. de méd. et de chirurg., Paris, 1865, 2e s., II, pp. 652–654; *also*, reprint in 8°, Paris, 1865.]

——— Opportunité de l'isolement des cholériques dans les hôpitaux, prouvée par les documents administratifs.
[Bull. et mém. Soc. méd des hôp. de Paris, 1866, II, pp. 185–195; discussion, ibid., pp. 183–185, 216–220.]

Bücheler (J.) Verhaltungsregeln vor und während der asiatischen Cholera, für Jeden, insbesondere für den Landmann. 8°. *Düsseldorf*, 1832. L.

[Buet.] Aux habitants des quartiers du Temple et du Mont-de-Piété. Soins à prendre pour se préserver du choléra-morbus. 8°. [*Paris, n. d.*]

Bufalini. Sui mezzi più acconci ad impedire la diffusione dei morbi epidemic. Lette all'Accademia de'Georgofili n l'adunanza dell'11 Marzo 1855.

Burghardt. Das Rohitscherwasser in Cholerazeit.
[Allg. Wien. med. Zeitg., 1866, XI, pp. 321–32

Caballos (D. J.) Consejos hygienico-preservativos del colera-morbo, discurso sobre su contagio. 8°. *Cadiz*, 1855. L.

Caldwell. Directions for the prevention or mitigation of cholera. With a review of Cooke, Hodge, and Reese on cholera &c. 8°. *Lexington, Ky.*, 1832.

Camps (W.) Epidemic cholera and epidemic diarrhœa: can these diseases be prevented? *London*, 1866.

Cantani (A.) Istruzioni populari concernenti il cholera asiatico. 8°. *Napoli*

Carraro (G.) Sulla rivaccinazione come preservativo dal cholera asiatico.
[Gaz. med. Ital. prov. Venete, 1867, X pp. 315–316.]

Castelnau (H. de). Doit-on instituer, en temps de choléra, des visites préventives à domicile?
[Monit. des hôp., Paris, 1854, II, pp. 41–42

Castéra. Observations hygiéniques sur les moyens d'éteindre le choléra en France.
[Gaz. méd. de Paris, 1832, III, pp. 369–373.

Chadwick (E.) The precautions to be taken against cholera. fol. [*East Sheen, n. d.*] L.

——— Precautions against cholera. Second paper. (Principles of central action.) fol. [*East Sheen, Mortlake, Surrey*, 1871.] L.

——— *and* **Smith** (T. S.) The cholera. Directions and regulations of the general board of health.
[Med. Times & Gaz., 1853, VII, n. s., pp. 53

Challice (J.) Should the cholera come, what ought to be done? 8°. *London* 1848.

Champoricin. Kurze Belehrung über Verhütung der asiatischen Cholera, die erste Hülfsleistung bei den davon Befallenen. Nach den neuesten und geprüftesten Erfahrungen bearbeitet, auf höchste Veranlassung von der fürstl. Sanitätsbehörde zu Schleiz bekannt gemacht und herausgegeben. 8°. *Schleiz* 1831. L.

Champouillon. Prophylaxie du choléra.
[Gaz. des hôp., 1854, p. 49.]

——— Des agents physiques et chimiques réputés destructeurs du principe cholérique.
[Gaz. des hôp., 1865, pp. 558–559.]

Charruau. Académie des arts et métiers, [etc.] de Paris: Conseils relatifs à l'épidémie de choléra, (1853.) 8°. [*Paris, n. d.*]

Chevillion (O.) Instruction populaire contre le choléra-morbus. 12°. *Paris*, 1849.

[Chevreuse (A.)] Moyens préservatifs du choléra. 8°. *Charmes* [1854].

——— Choléra, moyens de le prévenir. 8°. *Charmes* [1854].

Chiari (P.) Riflessioni sul cholera morbus del 1835 applicabili a quello del 1854.
[Gaz. med. ital. Tosc., Firenze, 1854, IV, 2a s., pp. 349–351, 356–359.]

Cioccari (C.) Tra le minacce del colera, quattro parole a tempo. 8°. *Napoli*, 1873.

Clemens (T.) Die Chlorkupferlampe als bestes und einfachstes Desinfectionsmittel der Luft während der Cholera-epidemien.
[Deutsche Klinik, 1865, XVII, pp. 418–419.]

——— Der Chlorkupferspiritus und sein Gebrauch als Schutzmittel bei Cholera-epidemien.
[Deutsche Klinik, 1866, XVIII, pp. 115–118, 261–262.]

Clubbe (W. H.) Floating hospitals for cholera patients.
[Lancet, 1872, II, p. 468.]

Cohen (A.) Maatregelen tegen het Ontsnappen der stinkende Gassen uit de Openingen in de Riolen.
[Nederl. Tijdschr. v. Geneesk., 1867, I, pp. 1–4.]

Cohnstein (W.) Trost- und Beruhigungsgründe für die durch das Herannahen der Cholera aufgeschreckten Gemüther, nebst Angabe aller gegen diese Krankheit bisher empfohlenen Schutzmittel. 8°. *Glogau*, 1831.

Colin (L.) La conférence sanitaire internationale de Vienne et le choléra.
[Gaz. hebd. de méd. et de chir., 1874, XXI, pp. 473–476.]

Collier (G. F.) The code of safety; or, causes, effects, and aids, preventive and curative, as well of other epidemics, as also of Asiatic cholera. 8°. *London*, 1849. L.

Colucci (G.) Provvedimenti igienici contro il cholera: prefettura di Genova, divisione III, sezione II, protocollo n. 2223, spedizione 297.
[Nuova (La) Liguria med., 1874, XIX, pp. 119–122; *also, in* Salute (La), Genova, 1874, IX, pp. 160–162.]

Consonne (F.) Sull'opportunità di alcune misure profilatiche contro il cholera.
[Gaz. med. it. Lomb., Milano, 1868, I, 6a s., pp. 207–208.]

Corrado (T. C.) Stato attuale delle nostre cognizioni sulla propagazione del cholera asiatico e sui mezzi più acconci a limitarla od impedirla. 16°. *Palermo*, 1867. S. C.

Coulogne. Traitement préservatif du choléra. 8°. *Roubaix* [1866].

Cowper (W.) Precautionary advice to local boards of health with reference to epidemic cholera.
[Lancet, 1857, II, n. s., pp. 374–375.]

——— Prophylaktische Rathschläge der obersten Gesundheits-Behörde Englands an die einzelnen Local-Gesundheits-Behörden, betreffend die epidemische Cholera.
[Aerztl. Intell.-Bl., 1857, IV, p. 573.]

Cunningham (J. S. A.) Cholera hospitals.
[Dublin Med. Press & Circ., 1866, II, pp. 22–23.]

Curie (E.) De l'emploi thérapeutique des champignons vénéneux contre le choléra, la maladie de Bright et les fièvres intermittentes. 8°. *Paris* [1867].

Curtin (R. G.) Sulphuric acid as a prophylactic in cholera.
[Phila. Med. Times, 1873, III, pp. 649–651.]

Danziger. Ueber den destructiven Einfluss des Chlors auf das contagiöse Princip. (Cholera.)
[Med. Zeitg., 1851, p. 20.]

Darbel (G. E. M.) Des préservatifs contre le choléra-morbus. 8°. *Paris*, 1831.

Davis (N. S.) The cholera, and the influences which favor or retard its spread or diffusion.
[North-West. Med. & Surg. Jour., 1849–50, VI, pp. 482–497.]

Dechambre (A.) Des mesures hygiéniques projetées à l'occasion du choléra.
[Gaz. hebd. de méd. et de chirurg., 1853–54, I, pp. 13–15.]

Delarue (F.) De la peur et de la folie des gouvernements de l'Europe au sujet du choléra, et de la seule manière d'en préserver les peuples. 8°. *Paris*, 1831.

Delpech. Prophylaxie du choléra-morbus épidémique.
[Ann. d'hyg. pub. et de méd. lég., 1874, XLI, 2e s., pp. 5–24.]

Del Valle (A. G.) Cólera. Avisos para precaverse ó salvarse de él, y conveniencia de que se divulguen los consejos de la higiene, hasta formar costumbres. (Anales de la academia, sesion del 25 de Setiembre 1870.) 8°. [*n. d.*] L.

Dély. De la nature des maladies contagieuses, extinction de la variole et du choléra. 8°. *Tarbes*, 1874.

Derby (G.) The prospect of cholera.
[Boston Med. & Surg. Jour., 1873, LXXXVIII, p. 661.]

Desmartis (T.) Causes et préservatifs du choléra et des maladies contagieuses. 8°. *Paris* [1865].

De Vita (A.) A proposito del cholera. Precetti igienici e profilattici.—Presidii curativi.—Provvidenze dei comuni. *Catanzaro*, 1867.

Diday (P.) Réunion d'une conférence internationale pour neutraliser le développement du choléra épidémique.
[Gaz. méd. de Lyon, 1865, XVII, pp. 469–472.]

Dillon (E. C.) Spasmodic cholera, its prevention and cure. 8°. *London*, 1833.

Dornblüth (F.) Ursachen und Verbreitungsweise der Cholera und Schutzmaassregeln gegen dieselbe. 12°. *Rostock*, 1960. L.

Doucet (F.) Tratado del chólera-morbus de la India, parte primera, ó sea ensayo sobre la higiene publica y privada. 4°. *Vera-Cruz*, 1832.

Drouyn de Lhuys. Circular proposing a cholera-conference.
[Med. Circular, 1865, XXVII, pp. 312–313.]

Dufay (P.) Avis au peuple sur le choléra-morbus. 8°. *Paris*, 1833.

Dujac (X.) Instruction sanitaire contre les ravages du choléra asiatique, et sur l'utilité des chlorures désinfectants pour en arrêter et prévenir l'extension. 8°. *Toulouse*, 1832.

Dukerley (E.-I.) Notice sur les mesures de préservation prises à Batna (Algérie) pendant le choléra de 1867, et sur leurs résultats. 8°. *Paris*, 1868. L.

Du Laurens (H.) Avis salutaires contre le choléra indien, extraits des meilleurs auteurs. 12°. *Avignon* [1835].

Duncan (W. H.) Preparations for cholera.
[Journ. of Pub. Health, 1866. I, pp. 383–384.]

Durande. Quelques idées sur la maladite choléra, notamment sur les moyens de prévenir ses effets et de diminuer son intensité. 8°. *Dijon*, 1832.

Duvernoy. Medicinal- und Sanitäts-Verordnungen, die Cholera betreffend.
[Vereinte deutsche Zeitschr. f. d. Staatsarznei, 1849, VI, 2. F., pp. 129–192.]

Eckart (A.) Die beim k. bayerischen Militär gegen die Cholera ergriffenen Schutz- und Hilfsmassregeln.
[Allgem. Intell.-Bl., 1854, I, pp. 429–462.]

Egeling (W.) Raadgevingen ten Voorbehoeding tegen de Cholera. 8°. *Haarlem*, 1832.

Eisenstein. Lebens- und Vorbeugungsmassregeln bei der Epidemie der nervösen Cholera. 8°. *Wien*, 1848. L.

Énault (P. A.) Choléra-morbus, conseils hygiéniques à suivre pour s'en préserver. 8°. *Paris*, 1831.

Engelsted. Almindelig Hospitals Lazareafdeling under Cholera-Epidemien.
[Bibl. for Laeger, Copenhagen, 1853, III. pp. 377–404.]

Escallier. Instruction relative au choléra. 8°. *Paris* [1853].

Espagne (A.) Le choléra et les quarantaines en 1865.
[Gaz. hebd. de méd. et de chirurg., Paris, 1865, 2 s., II, pp. 593–595, 609–611, 629–631, 657–661, 689–692; *also*, reprint in 8°, Paris, 1865.]

[Espanet (E. A.)] Lettre sur prophylaxie du choléra (1854). 8°. *Montélimart*. *d.*]

Euphemison. On the exterminative annihilation of the Asiatic cholera.
[London Med. & Surg. Jour., 1832, II, pp. 397–399.]

Fabretti (G.) Della trasmissione del cholera asiatico e dei relativi mezzi di preservazione.
[Gaz. med. it. prov. Veneta, 1866, IX, pp. 341–343.]

Falger (F.) Die sichere Verhütung der Cholera-Ansteckung. 3te Aufl. *Münster*, 1867.

Fasoli (G. B.) e Guarri (L.) Il cholera i disinfettanti: Nuovi studi sperimentali eseguiti nel R. laboratorio di chimica farmaceutica in S. M. nuova di Firenze.
[Sperimentale (Lo), Firenze, 1867, XX, pp. 81–88; *also*, reprint in 8°, Firenze, 1867.]

Fauvel (A.) Rapport sur les mesures à prendre en orient pour prévenir de la

auvel (A.)—continued.
velles invasions du choléra en Europe. *Constantinople*, 1866.

——— Rapport à la conférence sanitaire internationale sur les mesures à prendre en orient pour prévenir de nouvelles invasions du choléra en Europe.
[Gaz. méd. d'orient, 1866-67, x, pp. 179-187; 1867-68, xi, pp. 4-12, 19-29, 38-43.]

——— Le choléra, étiologie et prophylaxie. Origine, endémicité, transmissibilité, propagation, mesures d'hygiène, mesures de quarantaine et mesures spéciales à prendre en orient pour prévenir de nouvelles invasions du choléra en Europe. Exposé des travaux de la conférence sanitaire internationale de Constantinople. Avec une carte coloriée indiquant la marche du choléra en 1865. 8°. *Paris*, 1868. L.

——— Etiologie et prophylaxie du choléra.
[Annales d'hyg. pub., 1868, xxx, 2e s., pp. 1-16.]

——— Compte rendu sommaire des travaux de la conférence internationale réunie à Vienne [juillet 1874].
[Bull. de l'Acad. de méd., Paris, 1874, iii, 2e s., pp. 914-929, 934-949.]

Favrot. Des meilleurs moyens pour se préserver du choléra. 18°. *Paris*, 1848.

[Fechner (G. T.)] (**Mises**, *pseudonym.*) Schutzmittel für die Cholera, nebst einem Anhange, enthaltend die vornehmsten Meinungen der Aerzte über den Sitz und das Wesen oder die nächste Ursache, die Contagiosität oder Nichtcontagiosität dieser Krankheit. 8°. *Leipzig*, 1832. L.

Fergus (A.) Preventibility of cholera, with remarks on Dr. Johnson's theory of the disease.
[Glasgow Med. Jour., 1866, i, n. s., pp. 193-203; *also*, reprint in 8°, Glasgow, 1866.]

Ferrario (G.) Istruzione storica al popolo per difendersi dal pestilenziale cholera morbus asiatico. 16°. *Milano*, 1865. s. c.

Ferrini (G.) Le quarantene ed il contagio colerico, o sia osservazioni critiche al prof. Bo.
[Gaz. med. it. Lomb., Milano, 1855, vi, 3a s., pp. 77-82.]

Ferro (G.) Sulla profilassi del cholera epidemico.
[L'Imparziale, Firenze, 1868, viii, pp. 497-502, 557-563.]

Fick. Cholera-Prophylaxis.
[Wien. med. Wochenschr., 1872, xxii, pp. 1161-1162.]

Fife (G.) On the speedy interment of persons dying from cholera.
[Prov. Med. & Surg. Jour., 1848, p. 532.]

Filhos. Traitement prophylactique du choléra.
[Gaz. des hôp., 1849, p. 178.—L'Union méd., 1853, vii, pp. 593-595; *also*, reprint in 8°, Paris, 1853.]

Focke (W. O.) Die Cholera und die Desinfectionsmittel.
[Deutsche Klinik, 1871, xxiii, pp. 329-330.]

Foissac. Remarques sur la prophylaxie et le traitement des prodromes du choléra.
[L'Union méd., 1865, xxviii, 2e s., pp. 65-70.]

Forster (T.) Essay on the origin, symptoms, and treatment of cholera morbus, and of other epidemic disorders, with a view to the improvement of sanitary regulations. 8°. *London*, 1831. L.

Fossion. La pathogénie et la prophylaxie du choléra.
[Bull. de l'Acad. roy. de méd. de Belgique, 1871, v, pp. 864-897.]

Fox (J. M.) Advice to sanitary authorities and to individuals on the threatened approach of Asiatic cholera. 12°. *Cockermouth and London* [1872].

Fox (T.) Cholera prospects: compiled from personal observation in the east for the information and guidance of individuals and governments. 8°. *London*, 1865. L.

Fox (W. J.) Moral cautions on the anticipated approach of the cholera. A sermon delivered Nov. 6, 1831. 8°. *London*, 1831. L.

Franchard. Voilà le choléra! Qu'en ferons-nous? 8°. *Paris*, 1865.

Frank (X.) Alle vorzüglich öffentlich gepriesenen Mittel gegen die Cholera, gesammelt und herausgegeben zum Gebrauch für Jedermann. 8°. *Leipzig*, 1831.

Fremaux. Du moyen naturel de mettre fin, pour l'avenir, aux retours périodiques d'une triste et redoutable calamité . . . . basé sur ce qui s'est passé à cet égard depuis 1831. 8°. *Saint-Cloud*, 1867.

French (J. G.) Free sulphurous acid as a prophylactic against cholera.
[Indian Med. Gaz., 1875, x, p. 110.]

Friedmann. Untersuchungen und Beobachtungen über die Verbreitungsart der Cholera, nebst Betrachtungen über

Friedmann—continued.
Maassregeln, derselben Einhalt zu thun, von M. Pettenkofer.
[*Reviewed by* DEUTSCHE Klinik, 1855, VII, pp. 460–463, 470–473.]

Friedmann (8.) Diätetik zur Vorbauung gegen die asiatische Cholera. 8°. *München*, 1865. L.

Fromont. Rapport sur l'état sanitaire des troupes campées pendant la période de manœuvres de 1866, précédé d'un exposé des mesures prises pour prévenir l'invasion et la propagation du choléra.
[ARCHIV. méd. belg., 1867, v, 2es., pp. 538, 113, 173.]

Fröriep (L. F. v.) Amtliche Äusserungen über die im Grossherzogthum Sachsen-Weimar-Eisenach gegen die Cholera gerichteten medicinal-polizeilichen Maassregeln. 4°. *Weimar*, 1832. L.

Fürst. Cholera und Rinderpest vor den Schranken der Humanität.
[AERZTL. Intell.-Bl., 1867, XIV, p. 438.]

Fuller. On certain points in connexion with cholera.
[MED. Times & Gaz., 1866, II, p. 571.]

Fuster. Des phénomènes précurseurs du choléra-morbus et de leur traitement.
[BULL. gén. de thérap., méd. et chir., 1832, II, pp. 255–261.]

Gaillard (R.) Hygiène des lycées, colléges et des institutions de jeunes gens. Extrait relatif aux précautions à prendre en temps d'épidémie cholérique. 8°. *Paris*, 1865.

Galligo (I.) Il cholera, il governo ed i medici.
[L'IMPARZIALE, Firenze, 1865, V, pp. 481–485.]

[Gary (C.)] Mémoire sur le salpêtre et sur une préparation contre le choléra-morbus . . . . à MM. les membres de l'Institut. (1855.) 4°. *Paris* [*n. d.*]

Gensoul. Moyens à employer pour arrêter la propagation du choléra. 8°. [*Paris*, 1854.]

Gessler. Erlass des Ministeriums des Innern an die Oberämter und Oberamts-Physikate, betreffend die Cholera. Und: Instruction zur Ergänzung der Verfügung des k. Ministeriums des Innern vom 3. September 1849, betreffend die Cholera.
[MED. Corresphl. des württemberg. aerztl. Vereins, 1868, XXXVIII, pp. 200–202.]

Giacich. Der jüngste internationale medizinische Kongress und die Vorkehrungen gegen die Cholera.
[WIEN. med. Wochenschr., 1873, XXIII, pp. 947–951.]

Gianelli (G. L.) La questione delle quarantene nel cholera presso la conferenza sanitaria internazionale di Costantinopoli.
[GAZ. med. ital. prov. Venete, 1866, XI, pp. 381–383, 389–395.]

——— Sul programma proposto alla . . . della commissione sanitaria a Costantinopoli. Note. *Firenze*, 1866.

Gibbons (H.) Hygiene of cholera.
[PACIFIC Med. & Surg. Jour., 1865–67, pp. 239–250, 297–310; 1866–67, II, pp. 9–12, . . .

Giordano (M.) Cura fermenticida . . . servativa del colera asiatico. 4°. *Bologna*, 1865.

Giotti (D.) Sul cholera, paroli . . . cipj.
[GAZ. med. ital. Tosc., Firenze, 1855, I, . . . 65–70.]

Girard de Caudemberg. Choléra. Moyen d'en arrêter la propagation, et de préserver les cités et les individus, sans apporter aucune entrave aux relations internationales. 8°. *Paris*, 1865.

Giraud (A.) Précis histotique; prévention et guérison du choléra par tout le monde, . . . suivi du traitement et de la guérison de la fièvre jaune et autres maladies. 4e éd. 8°. *Paris*, 1865.

Giraud (J. L.) Choléra-morbus. Instruction populaire sur les principaux moyens à employer pour se garantir du choléra-morbus (1837). 8°. *Marseille* [*n. d.*]

Girault. Choléra. Conseils et moyens préservatifs . . . . . 1866. 8°. [*n. d.*]

Glatter. Ueber die Wahrscheinlichkeit . . . gefahr der Cholera in Wien im Jahre 1871.
[WIEN. med. Presse, 1871, XII, pp. 891–893, 912–914, 941–942.]

Glatter (E.) Die Massnahmen gegen die Cholera.
[WIEN. med. Presse, 1865, VI, pp. 953–954.]

Godfrey (R. T.) Cholera: a few practical remarks on its prevention.
[CANADA Med. Jour., 1866, II, pp. 342–347.]

Godlewski (A.-P.-L.) *Étude sur le choléra: quelques considérations sur sa transmissibilité et sa prophylaxie. 8°. *Paris*, 1869.

Góes Sequeira (J. de). Algumas considerações e conselhos preventivos contra a cholera morbus epidemica. *Bahia*, 1866.

Góes Sequeira (J. de)—continued.

—— Influencia nociva das dejecções cholericas: meios que convem empregar para neutralisar, ou evitar os seus effeitos.

[Gaz. med. da Bahia, 1866, I, pp. 64–67.]

Göttsche (A. O.) Würdigung der Schrift: Zur Kenntniss und Verhütung der Cholera von Dr. Boeneck.—Ein Wort in Betreff der Cholera. 8°. *Itzehoe*, 1831.

Goodeve (E.) On the international sanitary conference and the preservation of Europe from cholera.

[Lancet, 1866, II, pp. 659–663.]

Goring (C. R.) Cholera or no cholera. Tricks of some governments.

[Lancet, 1832, I, pp. 377–378.]

Gorlier (J.) La constitution médicale actuelle indique-t-elle l'imminence d'une épidémie de choléra?

[L'Union méd., 1865, XXVII, 2e s., pp. 497–501.]

Gossement. Sur un signe précurseur du choléra et sur un mode de traitement prophylactique [ipécacuanha] de cette maladie.

[Journ. des connaiss., Paris, 1848, XV, pp. 21–23.]

Gouraud (H.)] Instruction sur le traitement préventif du choléra. 16°. *Verdun* [1854].

[Numerous other editions.]

—— Traitement préservatif du choléra. 8°. *Besançon* [1854].

Gräfe (E. A.) Cholera-Diät-Zettel. 8°. [*Berlin*, 1837.]

Grainger (R. D.) A lecture on the sanitary question, especially as it is connected with epidemic cholera.

[Med. Times, 1849, XIX, pp. 229–230.]

Granara (R.) Esposizione testuale italiana dei processi verbali della conferenza sanitaria internazionale di Parigi in quella parte che comprendono la importante discussione sul cholera-morbus, con note e commenti.

[Comodi Ann. un. di med., 1852, CXLI, pp. 5–32; CXLII, pp. 25–78.]

Grand-Boulogne (A. de). Instruction populaire sur les symptômes précurseurs du choléra, moyens faciles de les reconnaître et de les arrêter. 16°. *Paris*, 1865.

—— Des symptômes précurseurs du choléra, moyen certain de les reconnaître et de les arrêter. (1865.) 8°. *Metz.*

Grandessi-Silvestri (O.) Nuovi casi di vaccinazione e rivaccinazione che preservò dal cholera-asiatico.

[Gaz. med. ital. prov. Venete, 1867, X, pp. 279–280, 315–316, 372–374.]

—— Riflessioni sulla efficacia della vaccinazione e rivaccinazione come mezzo preservativo dal cholera.

[Gaz. med. ital. prov. Venete, 1868, XI, pp. 153–154.]

Grauvogl (von). Zum Schutze gegen die Cholera. 2te Aufl. 8°. *Ansbach*, 1854. L.

Greenhow (T. M.) Hints on the probable approach of cholera. 8°. *Newcastle*, 1848.

—— Cholera from the east. 8°. *Newcastle*, 1852.

Griesinger (W.), **Pettenkofer** (M.), *und* **Wunderlich** (C. A.) Cholera-Regulativ. [Für die Sanitätsbehörden, die Aerzte und das Publikum.]

[Zeitschr. f. Biologie, München, 1866, II, pp. 434–458; *also*, reprint in 8°, München, 1866.]

Gueneau de Mussy *et* **Martin-Solon.** Instruction populaire sur les précautions à prendre contre le choléra, sur les premiers signes de la maladie, et les premiers soins à donner aux personnes qui en sont atteintes.

[Journ. des connaiss., Paris, 1849, XVI, pp. 174–176.]

Guerin (J.) Moyens de prévenir le développement épidémique du choléra.

[Gaz. méd. de Paris, 1853, VIII, 3e s., pp. 661–662.]

Guilbert (A.-M.-D.) Moyens préservatifs contre le choléra-morbus, suivis d'une méthode simple pour soigner le cholérique en attendant le médecin, précédés d'une définition de cette maladie, éclairée par les observations météorologiques faites à Paris, en 1832 et confirmée par celles de 1849. 8°. *Paris*, 1849. L.

—— The same. 2e éd. 8°. *Paris*, 1854. L.

Guilbert (J. N., de S. D.) Moyens à opposer au choléra pestilentiel; fautes qu'on doit éviter. 8°. *Paris*, 1832. L.

Guldberg (H.) Betnaerkninger og Forslag angaaende Ordningen af den offentlige Sundhedspleie i det söndre sjaellandske Landphysicat under en udbrydende Cholera-Epidemi.

[Ugeskr. for Laeger, Copenhagen, 1853, XIX pp. 123–128, 183–191.]

Guyon. Sur l'opinion que les vapeurs sulfureuses pourraient neutraliser les causes du choléra.
[Gaz. méd. de Paris, 1866, XXI, pp. 169–170.—Gaz. des hôp., 1866, p. 108.]

Guyton-Morveau. Metodo per purgare le arie infette e per preservarsi da tutte le malattie contagiose; ed estratto di notizie relative al metodo stesso di Cadet de Veaux, con esperienze del sig. Paroletti . . . usato a Napoli nel 1816, tratto dall'opera di F. Romani. 2a ed. 8°. [1831.]

Hahnemann (S.) Zekerste Geneeswijze en Uitroeijing der asiatische Cholera. 8°. *Amsterdam*, 1831.

Halford (H.) Extracts from the public notification respecting the cholera morbus, issued by the privy council at the instance of the board of health.
[Lancet, 1831–32, I, pp. 158–160.]

Hall (J. C.) A letter to the chairman of the board of guardians of the Sheffield union, on the prevention of cholera. 8°. *London*, 1853. L.

Hamon. Traitement abortif des affections cholériques.
[Revue de thérap., Paris, 1855, III, p. 625.]

Handy (W. R.) Diet in cholera.
[Med. Exam., Phila., 1849, V, n. s., pp. 585–591.]

Hanmann (K.) Kurze Diätetik während der Cholera-Epidemie zu Rostock. Für seine Mitbürger herausgegeben. 8°. *Rostock*, 1832.

Harless (C. F.) Die indische Cholera, nach allen ihren Beziehungen, geschichtlich, pathologisch-diagnostisch, therapeutisch und als Gegenstand der Staats- und Sanitäts-Polizei dargestellt. 2 v. 8°. *Braunschweig*, 1831. L.

——— Bemerkungen über die Nothwendigkeit der Fortdauer gewisser sanitätspolizeilicher Massregeln gegen die Cholera, aus dem Gesichtspunkt ihrer bedingten Ansteckungsfähigkeit.
[Heidelberg. klin. Ann., 1832, VIII, pp. 152–164.]

Harris (E.) Report by the council of hygiene and public health, of the Citizens' Association of New York City, upon epidemic cholera and preventive measures. 8°. *New York*, 1865. L.

——— Report on sanitary police measures applied to the prevention and control of epidemic cholera.
[Bull. N. Y. Acad. of Med., 1866, III, pp. 101–122.]

Harris (E.)—continued.

——— Cholera prevention: examples a practice: and a note on the pres[illegible] pects of the epidemic. 8°. *New* [illegible] 1867.

——— Epidemic cholera: its cause[illegible] the means for its prevention.
[Trans. Am. Med. Assoc., 1867, XVIII, pp. [illegible] 437.]

——— Practical conclusions con[illegible] cholera. — Evidence respecting [illegible] and preventive measures.
[Amer. Public Health Assn. Reports & Pa[illegible] N. Y., 1875, I, pp. 343–358.]

Hartshorne (H.) Cholera and quarantine.
[Med. & Surg. Reporter, 1866, XIV, [illegible]

Hassall (R.) Cholera: its nature, treatment, and the preventive measures communities and individuals should adopt. 8°. *London*, 1854.

Heidenreich (F. W.) Anweisung zum richtigen Gebrauche der Präservativ gegen die Cholera. Unter Beistimmung sämmtlicher Ansbacher Aerzte herausgegeben. 16°. *Ansbach*, 1831.

——— Vorkehr und Verfahren gegen die Cholera. Nach eigenen Beobachtungen in München und Augsburg. [illegible] *bach*, 1854.

Heidler (C. J.) Die Schutzmittel gegen die Cholera mit Rücksicht auf einsächliches Luftinfusorium und [illegible] nicht-contagiöse Natur. [illegible] 1854.

Heim. Entschiedener Nutzen einer beharrlich angewendeter Schutzmassregeln vor der asiatischen Cholera dem oesterreichischen vierten Jäger taillon zu Kuttenberg in Böhmen Jahr 1831–1832.
[Schweiz. Zeitsch. f. Kat.- u. Heil-Kunde, 1837, II, pp. 99–99.]

Helm (T.) Zur Wasserfrage. [illegible] Brief an . . . . Edward Smith regard to disinfection in cholera.
[Wien. med. Wochenschr., 1866, pp. [illegible]

Helsby (T. H.) Cholera.
[Popular Jour. of Phys. & Ment. Hyg pp. 86–89.]

Hempel (F.) Kurzer Bericht über öffentlichen und privaten Schutz-Massregeln, welche in den Jahren 1[illegible] der Türkei und in Russland gegen steckung durch die orientalische [illegible] unzweifelhaftem Erfolge an[illegible]

Hempel (F.)—continued.
worden sind, in Rücksicht auf die Hemmung der Cholera zum Besten der Hospitäler zu Danzig erstattet. 8°. *Berlin*, 1831. L.

Herëau (J.) Communication faite à la commission sanitaire départementale de l'Yonne, etc. 8°. *Auxerre*, 1832.

Hoffmann (C., *jr.*) Erfahrungen über die Anwendung des dreifachen Chlorkohlenstoffes bei der epidemischen Cholera. 8°. *Frankfurt a. O. und Berlin*, 1849. L.

Hoffmann (S. E.) Entwurf zur Einrichtung eines Cholera-Hospitals. Mit einer genauen Angabe eines, für die Behandlungsart der Cholera-Kranken in Vorschlag gebrachten, bequemen Krankenlagers. 8°. *Berlin*, 1831. L.

Holst (D.) Actstykker angaaende Cholera.
[Norsk Mag. f. Laegevid., Christiania, 1848, II, pp. 175–180, 247–249.]

Honé. Préservation du choléra vulgarisée. Livres de préservation contre le choléra, renseignements pour s'en garantir. 18°. *Paris*, 1874.

Horn (E.) *und* **Wagner** (W.) Wie hat man sich vor der Cholera zu schützen und was hat man bei ihrem Eintritt zu ihrer Heilung und zur Verhütung der weiteren Verbreitung zu thun? 8°. *Berlin*, 1831. L.

Hornemann (E.) Om Foranstaltninger mod Cholera, naermest med Hensyn til Kjöbenhavn.
[Hygiea. for Laeger, Copenhagen, 1865, XLIII, pp. 441–454.]

Hufeland (C. W.) Verbreitungsgeschichte der Cholera. (Abgedruckt aus der allgemeinen Zeitung.)
[Journ. der prakt. Heilk., 1830, LXXI, pp. 113–116.]

—— Einige Worte zur Beherzigung über Sperren und Contumazen bei der Cholera.
[Journ. der prakt. Heilk., 1831, LXXIII, pp. 123–126.]

Hunt (W.) A letter, &c., on the best means of preventing the extension of cholera morbus. 12°. *London*, 1832.

Ianor (S. v.) Sopra certe misure adottate per impedire la diffusione del cholera.
[L'Imparziale, Firenze, 1866, VIII, pp. 6–10.]

Izard (A.)] Choléra, prophylaxie, symptômes. Traitement mis à la portée de tout le monde. 12°. *Paris*, 1865.

Jähnichen. Ueber die Sicherung gegen die Cholera, eine dem temporären Medicinalrathe zu Moskau vorgelegte Abhandlung. (Aus dem Französischen übersetzt.)
[Litt. Ann. d. ges. Heilk., Berlin, 1831, XX, pp. 79–95.]

Jakubowits (F.) Vorschlag zu einem Präservativ gegen die Cholera.
[Wien. med. Presse, 1866, VII, pp. 962–963.]

Jörg (J. C. G.) Diätetisch-medicinischer Rath für Nichtärzte, die ostindische Cholera betreffend. 8°. *Leipzig*, 1831. L.

Jolly (P.) Quelques remarques pratiques sur la prophylaxie et le traitement du choléra. Mémoire lu à l'Académie impériale de médecine, dans les séances des 28 mars et 6 avril 1854. 8°. *Paris*, 1854. L.

Jousset. [Sur la propagation du choléra et les mesures à prendre contre ce terrible fléau.]
[Bull. gén. de thér., med. et chir., 1866, LXXI, pp. 176–180.]

Jousset de Bellesme. Hygiène des épidémies: courtes instructions pratiques pour se préserver sûrement des maladies contagieuses, choléra—fièvre typhoïde—croup et angine couenneuse—variole—rougeole—scarlatine. 12°. *Paris*, 1873. L.

Jumné. Le choléra et les bains de mer. 8°. *Gand*, 1849.

Kidd (C.) Cholera and the board of health.
[Med. Circ., 1852, I. pp. 414–415.]

King (B.) Aloes as a prophylactic against cholera.
[Med. Times & Gaz., 1866, II, pp. 209–210.]

Kraus. Fürsorge zur Abwehr der Cholera.
[Allg. Wien. med. Zeitg., 1866, XI, p. 297.]

—— Unser Optimismus in der Cholera.
[Allg. Wien. med. Zeitg., 1866, XI, pp. 280–281.]

Kreus. Guter ärztlicher Rath für Hausväter in den Rhein-, Main- und Neckar-Gegenden, zur möglichst sichern Abwendung und Heilung der vielleicht bald uns heimsuchenden asiatischen Brechruhr oder Cholera. 12°. *Hanau*, 1831.

Küchenmeister (F.) Handbuch der Lehre von der Verbreitung der Cholera und von den Schutzmaassregeln gegen sie. Nach einem neuen Desinfectionsplane bearbeitet. 8°. *Erlangen*, 1872. L.

Küchenmeister (F.)—continued.

——— Ueber Desinfection bei Cholera.

[Wien. med. Presse, 1872, xiii, pp. 1033–1036, 1049–1052.]

Lair (S.) Notice sur un moyen de se préserver du choléra-morbus. 8°. *Paris*, 1831.

Laming (R.) Musk as an antidote for malignant cholera.

[Lancet, 1832–33, i, pp. 74–75.]

Lankester (E.) Cholera: what is it? and how to prevent it. 12°. *London*, 1866. L.

Lannelongue (F.) * Sur l'étiologie et le mode de propagation du choléra asiatique envisagés dans leurs rapports avec la prophylaxie. 4°. *Montpellier*, 1867. L.

Laycock (T.) Lecture on the prevention of Asiatic cholera.

[London Med. Gaz., 1848, xlii, pp. 695–700.]

Lebreux (E.) Choléra-morbus. Principes généraux d'hygiène, adressés plus particulièrement aux ouvriers des mines de Vicoigne, dans la prévision de la réapparition du choléra, etc. 12°. *Valenciennes*, 1849.

Le Brun Du Mesuil (C. F.) Choléra-morbus asiatique, moyen de s'en préserver et d'en prévenir les suites. 8°. *Paris*, 1832.

Lefebvre. Rapport sur la prophylaxie du choléra. Discussion.

[Bull. Ac. roy. de méd. Belgique, 1873, vii, 3e s., pp. 514, 634, 645, 697.]

——— Communication sur les travaux de la conférence sanitaire internationale de Vienne, qui a eu lieu en 1874.

[Bull. de l'Acad. roy. de méd. de Belg., Bruxelles, 1875, ix, 3e s., pp. 43–77.]

Leroy (C.) Instruction relative au choléra-morbus et à l'emploi des moyens désinfectants. 8°. *Grenoble*, 1832.

Le Viseur (C. J.) Rath gegen die Cholera. 8°. *Posen*, 1866.

Levrat (C. M. F., *aîné*). Instruction familière sur les précautions sanitaires à prendre dans chaque maison ou établissement pour se préserver du choléra-morbus. 8°. *Lyon*, 1832.

Levrat (E.) Du choléra, son début; de quelques précautions à prendre . . . . 8°. *Paris*, 1853.

Levy (A.) Die Cholera, ihre Verbreitung und der wirksamste Schutz gegen dieselbe. 8°. *Trier*, 1866.

Leymerie (J.) Choléra. Protestation contre la loi sanitaire intervenue, suivie d'une analyse . . . . . de tout ce qui a été publié en Russie, etc., sur ce fléau, sur le seul moyen avéré de s'en garantir. 18°. *Paris*, 1831.

Lichtenstadt (J. R.) Rathschläge an das Publikum zur Verhütung und Heilung der herrschenden asiatischen Cholera. 8°. *Berlin*, 1831. L.

Lichtenstein (E.) Neuer Vorschlag zur localen Prophylaxis bei drohender Cholera-epidemie.

[Deutsche Klinik, 1867, xix. p. 69.]

Lobethal. Über die bewährtesten Mittel zur Verhütung der Cholera. 8°. *Leipzig*, 1866.

Logan (R. F.) How to prevent cholera. 8°. *Shelbyville*, 1873.

Lucas. Du charbon de terre considéré comme préservatif du choléra-morbus. 8°. *Orléans*, 1833.

——— Réponse au rapport fait au nom de la Société de médecine d'Orléans sur un mémoire intitulé: "Du charbon de terre considéré comme préservatif du choléra-morbus", ou moyens de se préserver de cette maladie. 8°. *Orléans*, 1833.

Lucas (J. G.) Worin besteht die Kunst sich vor der Ansteckung der tödtlichen Cholera zu sichern? 8°. *Halle*, 1832.

Lucianni. Intorno all'accordo dei medici coi parrochi pei provvedimenti sanitari nelle malattie popolari; lettera al . . . P. Vieusseux. *Firenze*, 1854.

Macbeth (J.) A few practical remarks and reminiscences, bearing on Asiatic cholera, and the best prophylactics as well as antagonistic means to resist the poison, when it has invaded the system.

[Madras Quar. Jour. of Med. Sci., 1861, iv, 305–320.]

McClellan (E.) Cholera hygiene.

[Amer. Practitioner, 1874, ix, pp. 65–86.]

——— The same. 8°. *Louisville* [1874].

McCormac (H.) Asiatic cholera and its prevention.

[Amer. Med. Gaz. & Jour. of Health, 1849, pp. 4–5.]

——— On the prophylaxis of Asiatic cholera by means of dilute sulphuric acid.

[Dublin Med. Press & Circ., 1866, ii, p. 4.]

——— Prophylaxis of Asiatic cholera.

[Med. Press & Circ., 1869, p. 393; *also*, in British Med. Jour., 1873, ii, p. 222.]

McCraith (J.) Cholera quarantine.

[Med. Times & Gaz., 1866, i, pp. 480–481.]

Magaluso (A.) Riflessioni critiche su due memorie intitolate: Istruzioni popolari sul colera, del Dr. La Loggia. Metodo di frenare ed estinguere il colera, del Prof. Castellana. 8°. *Palermo*, 1856. S. C.

Manassei (C.) Ciò che si può fare contro il cholera per il dott. Max v. Pettenkofer. Traduzione dall'originale tedesco con nôte ed applicazione de'principj stabiliti in quel dotto consesso alla città di Roma.

[ARCH. di med., chirurg., ed ig., Roma, 1874, XI, pp. 232–235, 297–307, 366–374; XII, pp. 23–33, 101–106, 158–163.]

Mantell (G.) Short and plain rules for the prevention and cure of the cholera morbus; intended for the unprofessional reader. 8°. *London*, 1831. L.

Marc. Instruction populaire sur les principaux moyens à employer pour se garantir du choléra-morbus. 8°. *Paris*, 1831. L.

Marcus (M.) Giebt es Schutzmittel gegen die Cholera und welche? Eine vom Verein badischer Aerzte zur Förderung der Staatsarzneikunde für das Jahr 1854 gestellte Preisfrage. 8°. *Erlangen*, 1856. L.

Marie (J. P. F.) * Quelques propositions de médecine et en particulier sur l'hygiène prophylactique du choléra épidémique. 4°. *Paris*, 1832. L.

Marsden (W.) Plan of quarantine for cholera.

[CANADA Med. Jour., 1866, II, pp. 337–343, 1 pl.]

——— Plan of a hospital and cleansing establishment for the treatment of cholera and guarding against its introduction at ports and places of entrance.

[AMER. Public Health Assn. Reports & Papers, N. Y., 1875, I, pp. 184–187, 1 pl.]

Martin (A. de). Die Mittel, die Luft bei epidemischen miasmatischen Krankheiten insbesondere der Cholera in ganzen Städten und bewohnten Räumen zu verbessern. 8°. *München*, 1854. L.

——— Rimedio per prevenire il cholera. 8°. *Napoli*, 1854. L.

Mason (A.) The cholera. Brief hints for the prevention of cholera, with a plain account of its symptoms, the proper preventive measures,—and the management of its early stages. 8°. *Lowell*, 1849. L.

——— The same. 14th ed. 8°. *Boston*, 1866. L.

Massart. Note relative à une remède prophylactique du choléra. Rapport de M. Lequime.

[BULL. de l'Acad. roy. de méd. de Belg., 1849–50, IX, pp. 342–351.]

Maurin (S. E.) Prophylaxie du choléra. 16°. *Marseille*, 1865.

[2e éd., 8°, same year.]

Mayer (M.) Ueber die Anwendung des Feuers gegen die Cholera.

[MED. Conversationsblatt, 1832, pp. 387–390.]

Mayor (M.) Guide contre le choléra. 8°. *Lausanne*, 1831.

[Mazielle.] Moyens à la portée de tout le monde pour se préserver du choléra ou pour le combattre avec succès. 8°. *Paris* [1849].

M[eiern] (C. v.) Entdeckung des Geheimnisses die Cholera-Krankheit im Keime zu ersticken, etc. 8°. *München*, 1831. L.

Meijer (B. J.) Behoed- en Geneesmiddelen tegen de Cholera morbus, de Kinkhoest en Kankerklieren. 8°. *Rotterdam*, 1831.

Mendonca (J. J. de). Medidas e providentias em soccorro da população da mesma provincia affectada do cholera morbus desde 1862 até 1863. 4°.

Merlot. Moyens prophylactiques contre la diarrhée prémonitoire (choléra).

[BULL. de l'Acad. de méd., 1873, II, p. 1090.]

Merryweather (G.) On preventive measures in cholera.

[LONDON Med. Gaz., 1849, XLIV, pp. 732–733.]

Messerschmidt (H.) Beweisführung, dasz die Häusersperre als Abwehrungsmittel gegen die Verbreitung der asiatischen Cholera nicht allein nicht nützt, sondern vielmehr schädlich und darum zu unterlassen ist, bei Gelegenheit des Zusammentritts der hiesigen Gesundheits-Comité abgefaszt. 8°. *Naumburg*, 1831. L.

Meyer (M. A.) Diätetische Verhaltungsregeln und erste Hülfe bei der asiatischen Cholera. 8°. *Hannover*, 1848. L.

Meyhoffer. Le choléra, son mode de propagation et les moyens de s'en préserver. 8°. *Nice*, 1865.

Meynne. [Hôp. mil. de Bruges.] Conférence du mois du septembre 1871. Précautions à prendre au début d'une épidémie de choléra.

[ARCH. méd. belges, Bruxelles, 1871, XIV, pp. 385–388.]

Millet (A.) Moyens préservatifs du choléra. 8°. *Tours* [1865].

Mises. *See* **Fechner** (G. T.)

Morache (G.) À propos du choléra et de sa prophylaxie.

[Gaz. hebd. med. et chir., 1873, x, 2e s., pp. 681-684.]

Morehead (C.) Notes on the prevention and treatment of cholera.

[Lancet, 1866, i, pp. 61–62, 383; remarks on, by E. A. Parkes, ibid., p. 160.]

Mosler (F.) Vorsichts-Massregeln wider die Cholera. 16°. *Greifswalde*, 1866.

Mühlig. Rapport sur la désinfection appliquée au choléra.

[Gaz. méd. d'orient, 1867–68, xi, pp. 56–62, 77–80.]

Mühry (G. F.) Rathschläge und Vorsichtsregeln, seinen Mitbürgern gegen die bevorstehende Cholera zur Beachtung empfohlen. 12°. *Hannover*, 1831. L.

Mulder (J. S.) *Eenige belangrijke Uitkomsten van de laatste Jaren ter Beantwoording van de Vraag, in hoe ver de aziatische Cholera voor eene besmettelijke Ziekte moet worden gehouden. 8°. *Groningen*, 1860. L.

Navarini (A.) L'innesto del vaccino non preserva dal cholera.

[Gaz. med. ital. prov. Venete, 1868, xi, pp. 121–122.]

——— Sulla rivaccinazione e sul cholera indiano.

[Gaz. med. ital. prov. Venete, 1868, xi, pp. 65–68.]

Neuber (A. W.) Zur Abwendung der morgenländischen Brechruhr, Cholera morbus orientalis. Erster Auszug aus einer grösseren Arbeit über die genannte Krankheit. *Apenrade*, 1831.

Neumann (A. C.) Ein Specificum gegen die asiatische Cholera.

[Allg. med. Central-Zeitung, 1848, xvii, pp. 569–571.]

Newell (T.) Prevention of the malignant cholera at Cheltenham.

[Lancet, 1832–33, i, pp. 210–211.]

——— Value of preventive measures,—Cheltenham exempt from cholera.

[London Med. Gaz., 1833, xi, pp. 182–183.]

[Noirot (L.)] Précautions hygiéniques contre le cholera. 8°. *Besançon* [1854].

——— Sur l'emploi des fumigations chlorées en vue de désinfecter l'air et de diminuer les ravages du choléra.

[Bull. et mém. Soc. méd. des hôp. de Paris, 1866, ii, pp. 200–204; *also, in* Revue méd., 1865, ii, pp. 598–605.]

Nonat (A.) Note sur l'hygiène des [illegible]taux, et spécialement sur un proc[illegible] désinfection économique et d'une [illegible]cation facile.

[Gaz. hebd. de méd. et de chirurg., Paris [illegible] pp. 66–67.]

Nourse (W. E. C.) The cholera—pr[illegible]tionary measures.

[Lancet, 1853, ii, p. 423.]

Oertil. L'eau fraîche spécifique infa[illegible] contre le choléra. 8°. *Paris*, 1831.

Ollenroth. Leiddraad ter Erke[illegible] Voorkoming en Genezing der aziatis[illegible] Cholera, voor hen die of in het G[illegible]met of niet spoedig eenen Genees[illegible] kunnen bekomen. Uit het Hoogd[illegible] P. Mazirel. 8°. *Amsterdam*, 1832.

Orsi (G.) Necessità di uniformi pr[illegible] denze igienico-sanitarie contro il [illegible] lera. *Ancona*, 1871.

Oser. Die Quarantaine-Frage mit [illegible] zieller Beziehung auf Cholera.

[Wien. med. Presse, 1873, xiv, pp. 701–7[illegible]

Otto (H.) Zur Prophylaxis der Ch[illegible]

[Virchow's Archiv, 1866, xxxvii, pp. 412–41[illegible]

Oxenden (A.) The cholera. How s[illegible] I best meet it? 12°. *London*, 184[illegible]

Ozanam. Conseils sur les moyens de [illegible] garantir du cholera, et sur les preu[illegible] soins à donner à ceux qui en sont at[illegible] qués. 8°. *Lyon* [1832].

Parkin (J.) Cholera and its treatme[illegible] Suggestions on the prevention of [illegible] demic cholera, with notes on the inf[illegible] ence of locality in the production [illegible] that disease in India, and elsewhe[illegible] and on the immunity attaching to th[illegible] vicinities of mineral springs and oth[illegible] places where large quantities of ca[illegible] bonic acid gas are evolved.

[Lancet, 1848, ii, pp. 289–290.]

——— The antidotal treatment of [illegible] epidemic cholera: with directions, ge[illegible] eral and individual, for the preventi[illegible] of the disease. 3d ed. 8°. *Lond[illegible]* 1866. L.

Pascal (H.) Du guaco et de ses pr[illegible] priétés hygiéniques et médicales [illegible] moyens . . . . pour se préserver du c[illegible] léra et le combattre efficacement. [illegible] *Paris*, 1866.

Pasqua. Choléra et quarantaine.

[Gaz. hebd. de méd. et de chir., 1870, 2e s., [illegible] p. 192.]

tzelt (J. E.) Ueber die zu ergreifenden sanitäts-polizeilichen Massregeln beim Ausbruche von Choleraepidemien unter der Arbeiterbevölkerung grossartiger Bauunternehmungen. [Aus dem Schlussberichte über die Choleraepidemie am Semmering im Jahre 1850.]

OESTERR. Zeitschr. f. pract. Heilk., Wien, 1855, I, pp. 284–286, 291–293, 309–301, 313–309.]

aulizky (F. C.) Anleitung zur Verhütung und Heilung der asiatischen Cholera. 8°. [*n. p.*,] 1832.

aulus. Rath, wie man sich zur Vermeidung der Cholera morbus zu verhalten habe. 8°. *Stuttgart*, 1831. L.

—— Schutzmittel gegen Cholera und alle aus naturwidriger Nahrungsart entspringenden Uebel; zugleich zeitgemässe Beantwortung der Frage: wie verhalten sich die ärztlichen Methoden zur nackten Wahrheit. 12°. *Schaffhausen*, 1855. L.

avesi (A.) Il cholera ed i disinfettanti.

OMODEI, Ann. un. di med., 1866, CIIC, pp. 387–412.]

ayne (A. J.-M. D.) Quarantine and cholera. Pamphlet. (Report from "Calcutta Review", 1869.)

ellarin (C.) De la prophylaxie du choléra.

Jour. de connaiss., 1850, XVIII, pp. 66–68.]

—— Épidémiologie cholérique, tribut à l'étude des moyens de préservation.

GAZ. des hôp., 1873, p. 939.]

ellarzi (G.) Se i chinacei si devono avere siccome preservativi del cholera, e che sia ormai a pensare di una tale proposta.

OMODEI, Ann. un. di med., 1838, LXXXVIII, pp. 339–410.]

ennès (J. A.) Emploi du sel de Pennès contre le choléra. 8°. *Paris* [1865].

ettenkofer (M. v.) Gevoelen over Desinfectie als Maatregel tegen de Verspreiding der Cholera. Uit het Hoogduitsch door R. J. Opwyrda. 8°. *Vlaardingen*, 1866. L.

—— Ueber das Moment der örtlichen und zeitlichen Disposition für Cholera und über den Verlauf der Epidemie in mehreren Städten an der nördlichen Abdachung des Thüringer Waldes im Jahre 1866.

ÄRZTL. Intell.-Bl., 1867, XIV, pp. 121–126.]

—— Il cholera sulle navi e lo scopo delle quarantene. Traduzione . . . . del dott. G. Ohlsen. *Palermo*, 1872.

Pettenkofer (M. v.)—continued.

—— Was man gegen die Cholera thun kann. Ansprache an das Publikum. Im Auftrage der Gesundheitsrather der königl. Haupt- und Residenzstadt München. 8°. *München*, 1873. L.

—— Cholera: how to prevent and resist it. From the German. Translated (with introduction and appendix on the international cholera-conference of Vienna) by Thomas Whiteside Hime. Revised by Dr. von Pettenkofer. 8°. *London*, 1875. L.

—— Künftige Prophylaxis gegen Cholera nach den Vorschlägen in dem amtlichen Berichte des königl. bayr. Bezirks- und Stadtgerichtsarztes Dr. Frank. 8°. *München*, 1875. L.

—— What we can do against cholera. Practical instructions concerning what to do to prevent an epidemic as well as how to guard against it during its prevalence.

[AMER. Public Health Assn. Reports & Papers, N. Y., 1875, I, pp. 317–335.]

Pezzoni (A.) L'inefficacité des quarantaines contre le cholera-morbus asiatique. Est-il un fait tellement démontré qu'on puisse l'admettre sans réplique? 8°. *Paris*, 1854.

—— Igiene o quarantene contro il coléra?

[GAZ. med. it. Lomb., Milano, 1856, I, 4a s., pp. 183–186.]

Pfeufer (K.) Conseils pour se préserver du choléra. Traduit de l'allemand par le Dr. F. J. Herrgott. 8°. *Belfort*, 1848. [2e éd. 8°, 1854.]

—— Zum Schutze wider die Cholera. 8°. *Heidelberg*, 1849. L.

—— The same. 3te Aufl. 8°. *Heidelberg*, 1854. L.

—— Wenken omtrent de te volgen Levenswijze en de Middelen ter Verhoeding der Cholera . . . . voor onzen Landaard bewerkt, ... door A. M. Ballot. 3e Druk. 8°. *Rotterdam*, 1853.

—— Avvertimento per preservarsi dal cholera. Tradotto dal dottor Erhardt in Roma. 8°. *Firenze*, 1854. L.

Pietra-Santa (P. de). Des visites médicales préventives contre le choléra morbus du general board of health et du registrar general.

[REVUE méd., 1853, II, pp. 449–456.]

Pietra-Santa (P. de)—continued.

——— Sur l'efficacité des mesures préventives et prophylactiques pour prévenir la manifestation des périodes successives du choléra, en l'attaquant dans ses prodromes.

[COMPT. rend. d. séanc. d. l'Acad. d. scienc., 1854, XXXIX, pp. 847–848.]

——— Publications. . . . 2e lettre à M. le Dr. A. Latour . . . . sur l'efficacité des soins préventifs et hygiéniques et sur l'utilité de la prophylaxie du choléra. (1854.) 8°. *Paris* [*n. d.*]

Pirondi (S.) *et* **Fabre** (A.) Étude sommaire sur l'importation du choléra et les moyens de la prévenir. 8°. *Paris*, 1865. L.

Plagge. Welche Maassregeln sind militairischer Seits zur Verhütung der Verbreitung der asiatischen Cholera zu ergreifen?

[MED. Zeitg. Russlands, 1857, pp. 260–262; *also, in* AERZTL. Intell.-Bl., 1857, IV, 669; 1857, V, pp. 636–638.]

Podrecca (G. L.) Avvertimenti per preservarsi dal colera. 8°. *Padova*, 1865. L.

Poggioli (P.) Préservatifs et remèdes du choléra à la portée de tout le monde. 8°. *Paris*, 1866.

Pointe (J. P.) Conseils pour les temps de choléra. 8°. *Lyon*, 1854.

Power (A.) Sanitary rhymes. . . . personal precautions against cholera, etc. 8°. *London*, 1871. L.

Preu (K.) Was haben wir von der Cholera zu fürchten? Ein Versuch die aufgeschreckten Völker zu beruhigen. 8°. *Nürnberg*, 1831.

Proust (A.) Essai sur l'hygiène internationale: ses applications contre la peste, la fièvre jaune et le choléra asiatique. (Avec une carte indiquante la marche des épidémies de choléra, par les routes de terre et la voie maritime.) 8°. *Paris*, 1873. L.

——— La conférence sanitaire internationale de Vienne.

[ANNAL. d'hyg. pub., etc., Paris, 1875, XLIII, 2e s., pp. 241–261.]

Pujade. Épidémies. Choléra. Atmosphères sulfureuses, naturelles et artificielles.

[JOUR. de méd. et de chir. prat., 1858, XXIX, 2e s., pp. 410–413.]

Py. Lettre sur les moyens de se préserver du choléra.

[BULL. Acad. de méd., 1837–38, II, p. 81.]

Pym (W.) Malignant cholera. [illegible] regulations issued by the [illegible] board of health, in August, 1832.

[LANCET, 1831–32, II, pp. 652–655.]

Raikem. Rapport sur les mesures prophylactiques contre le choléra-[illegible]. [Discussion.]

[BULL. de l'Acad. roy. de méd. de Belg[illegible] 48, VII, pp. 335–376, 458–507.]

Ramorino (E.) Riflessioni sul [illegible] de A. Bo, le quarantene ed il [illegible] 8°. *Genova*, 1854.

Reid (W.) Plan for the extinction [illegible] cholera.

[LONDON Med. Gaz., 1849, XLIV, pp. 63[illegible]]

Reiner (F. X.) Die epidemische [illegible] ruhr; ihre Verhütung im Nothfalle [illegible] ohne Arzt. 12°. *Nürnberg*, 1[illegible]

[Rémond (B.)] Préservatifs du [illegible] 18°. *Marseille*, 1865.

Révélaky. Mesures sanitaires contre le choléra.

[GAZ. hebd. de méd. et de chirurg., [illegible] pp. 749–751.]

Richardson. On the prevention of cholera.

[MED. Circular, 1865, XXVII, p. 423.]

Richmond (R. B.) "Prevention better than cure." Practical remarks on the prevention of cholera, and remedies for other troublesome states of the bowels. 8°. *London*, 1849.

Righini (G.) Manuale anticholerico. *Torino*, 1866.

Rios. Informe de la comision [illegible] para lo relativo al cólera epidemico.

[GAC. med., Lima, 1867, II, pp. 124–[illegible]]

Ritson (T.T.) Cholera—preventive properties of carbonic acid gas and carbonic [illegible]

[LANCET, 1848, II, p. 335.]

Ritter (A. F.) Sichere Mittel sich vor Cholera zu schützen. Nebst einer [illegible] trüglichen Heilmethode derselben, [illegible] den während der Epidemie in Ber[illegible] gemachten Erfahrungen. 12°. Berlin, 1848.

Robert (L. J. M.) Guide sanitaire des gouvernemens européens, ou nouvelles recherches sur la fièvre jaune et le choléra-morbus, etc. 8°. *Paris*, 1[illegible]

Rochard. De l'hygiène dans ses rapports avec le développement et la propagation du choléra.

[L'UNION méd., 1854, VIII, pp. [illegible] reprint in 8°. Paris, 1854.]

Rochard—continued.

——— Quelques considérations sur la prophylaxie du choléra.

[L'Union méd., 1854, VIII, pp. 418–419.]

Röder (A.) Bewährte Schutzmittel gegen die asiatische Cholera. 12°. *Basel*, 1854. L.

Rodolfi (R.) Profilassi possibile del coléra asiatico.

[Gaz. med. it. Lomb., Milano, 1855, VI, 3a s, pp. 96–97.]

Rollet (F.) Du choléra-morbus et des moyens de s'en préserver, ouvrage spécialement destiné aux gens de monde et contenant tout ce qu'il est essentiel de connaître pour se soustraire à cette maladie. 8°. *Paris*, 1831.

[2d ed. same year.]

Romiée (H.) Note sur les cimetières. Réponse au travail de M. le Dr. Bidlot: "À propos du choléra."

[Ann. Soc. méd.-chirurg. de Liége, 1874, XIII, pp. 153–179.]

Rosao. Profilaxis del colera.

[Gac. med., Lima, 1867, II, pp. 285–288, XII, pp. 74–75.]

Rose (H.) Precautions against cholera.

[Madras Quar. Jour. of Med. Sci., 1862, V, pp. 230–232.]

Roth. Instruction sanitaire contre le choléra-morbus. 8°. *Paris*, 1832.

Roth (J. J.) Ueber die Schütz-Kraft des Kupferbleches bein Herannahen der Cholera. 12°. *München*, 1831.

Russo (S.) Le quarantene e l'apertura dell'istmo di Suez. *Genova*, 1869.

Sacchi (G. A.) Norma teorico-practica per prevenire, curare e disinfettare il cholero asiatico. 8°. *Torino*, 1872.

Sachs (A.) Betrachtung über die unter dem 31. Jan. 1832 erlassene Instruction durch welche das in Betreff der asiatischen Cholera im Preussischen Staate zu beobachtende Verfahren festgesetzt wird. Für Aerzte und Verwaltungsbeamte. 4°. *Berlin*, 1832.

Sachs (J. J.) Allgemeine Lehren von den epidemischen und ansteckenden Krankheiten, insbesondere die Cholera und den zu ihrer Hemmung oder Minderung geeigneten Massregeln. 8°. *Berlin*, 1831.

St. Genis (M. de). Choléra-morbus. Contagion pestilentielle. Préservatifs. 8°. *Lyon*, 1831.

Salisbury (S. S.) The prevention of epidemic cholera.

[Chicago Med. Jour., 1865, XXII, pp. 490–492.]

Sander (G. C. H.) Beiträge zur Polecoprophylaxis gegen die gangetische Pest, gewöhnlich Cholera genannt. 8°. *Braunschweig*, 1831–32.

Sanders (J.) A letter on the extermination of cholera. 8°. *Edinburgh*, 1832.

Sansom (A. E.) The arrest and prevention of cholera; being a guide to the antiseptic treatment, with new observations on causation. 12°. *London*, 1866. L.

Sanson, *jeune.* Rapport sur les moyens qui ont réussi d'arrêter les progrès du choléra dans la caserne de la rue du Columbier [caserne des sapeurs-pompiers].

[Gaz. des hôp., 1832, VI, p. 129.]

Saucerotte (C.) Instruction sur les moyens propres à se préserver du choléra-morbus. 8°. *Paris*, 1831.

Saunders (W. S.) Report to the board of guardians of the city of London union, and to the special committee appointed under the direction of the privy council, on the causes and prevention of cholera. 8°. *London*, 1866. L.

Schäfer (H.) Bemerkungen über die Cholera, nebst einem Praeservativ-Mittel gegen dieselbe. 8°. *Hamburg* [1831]. L.

Schäffer. Die Sanitäts-Polizei in Bezug auf die Cholera.

[Med. Zeitung, 1852, pp. 169–171.]

Schelzel (H. O.) Die Prophylaxis der Cholera bei Armeen im Felde. 8°. *Leipzig* [1870]. L.

Schlayer. Verfügung des Ministeriums des Innern, betreffend die öffentliche Fürsorge gegen die asiatische Brechruhr.

[Med. Corspdzbl. d. württ. aerztl. Vereins, Stuttgart, 1836, VI, pp. 367–372.]

Schlegel. Anleitung zur sanitäts-polizeilichen Behandlung der asiatischen Cholera.

[Med. Zeitung, 1851, pp. 5–6.]

——— Die Schutzmaassregeln gegen die asiatische Cholera.

[Med. Zeitung, 1851, pp. 1–2.]

——— Beiträge zur Erforschung des Werthes der Schutzmaassregeln gegen die Verbreitung der asiatischen Cholera.

[Med. Zeitung, 1852, pp. 219–221.]

——— Anleitung zur sanitätspolizeilichen Behandlung der asiatischen Cholera nach Maassgabe der im Regierungs-

Schlegel—continued.
Bezirk Liegnitz in dem Zeitraume von 1831 bis einschl. 1852 gemachten Erfahrungen nebst einigen Vorbemerkungen.
[MED. Zeitung, 1853, pp. 181–183, 185–186.]

Schneemann (M. W.) Welches ist die beste Diätetik zur Vermeidung der asiatischen Cholera? 8°. *Ulm*, 1837.

Schnitzler (J.) Der heutige Stand der Cholera-Therapie. Nach Drasche, Griesinger, Niemeyer, Oppolzer, Skoda u. A.
[WIEN. med. Presse, 1866, VII, pp. 787–791, 803–805, 827–830.]

Schultz (A.) Sanitätspolizeiliche Maassregeln bei der Cholera-Epidemica.
[MED. Zeitung, 1852, pp. 187–188.]

Schumacher (W.) Verständlichste und bewährteste Belehrungen über die mit Gefahr bedrohende pestartige Krankheit Cholera-Morbus. Mit einem Rezepte versehen, welches das sicherste Schutzmittel wider die Cholera lehrt, und alle hierüber schon erschienenen und vielleicht noch erscheinenden Büchlein übertrifft und überflüssig macht. Nach den Hauptresultaten ärztlichen in Indien, Persien, Russland und Polen gemachten Erfahrungen, sorgfältig zusammengestellt. 4te Aufl. 8°. *Graudenz*, 1831.

[**Schwickardi** (A.)] Mémoire adressé aux souverains, villes et peuples qui voudront se préserver du choléra et des incendies, ainsi que le prouvent les nouveaux faits cités dans ce mémoire. 8°. *Paris* [1855].

Seaton (E. C.) A plan for the registration of cholera cases.
[LANCET, 1848, II, p. 535.]

Sertürner (F.) Weitere Entwickelung der neuen zuversichtlichen Schutzmethode gegen die Cholera, und der Ansicht über ihren höchstwahrscheinlichen Ursprung. 8°. *Göttingen*, 1831.

Shapter (T.) Sanitary measures and their results. 3d ed. *Exeter*, 1866.

Shinkwin (T. C.) On the admission of cholera patients into public hospitals.
[MED. Times & Gaz., 1853, VII, n. s., p. 380.]

Sievierna Potch-ta. O komitetie vyso tchay she utvier j dennom . . . ola pry niatúr mier na slutchay poiavlenia cholery.
[MEDYTZYNSKIY Viestnik, St. Petersburg, 1866, 6th year, No. 3, pp. 31–32.]

Sim (T.) No. 2. "Health tracts for the people." Cholera, how to avoid it, and how to treat it in the absence of a competent physician. 8°. *Charleston* 1866.

Simon (F. A.) Oeffentliche und persönliche Vorsichtsmaassregeln gegen die ostindische Brechruhr oder Cholera morbus, ihre unwidersprechliche nur alleinige Verbreitung durch Menschenverkehr sowol in Asien als in Europa und die dringende Nothwendigkeit der strengsten Quarantaine gegen die, aus damit angesteckten oder kürzlich angesteckt gewesenen Städten und Gegenden kommenden Personen, gegründet auf endliche, naturgemässe Schlichtung des Streites über Kontagium und Nichtkontagiosität derselben. 12°. *Hamburg*, 1831.

——— Persönliche Vorsichtsmaassregeln gegen die Cholera morbus, nebst Angabe der nothwendigen, im Hause vorhaltenden Hülfsmittel und Medicamente, und Anwendung derselben bis Ankunft des hinzugerufenen Arztes. Trost und Rath für Jedermann. 8°. *Hamburg*, 1831.

——— Weg mit den Kordons! qui même . . . der epidemisch-miasmatische Charakter der indischen Brechruhr, ein grober Verstoss gegen Geschichte ihres Zuges von Dschessore in Mittelindien nach dem tiefen Kessel in Hamburg und der gröbste gegen den gesunden Menschenverstand mit Beziehung auf die von Burdach, Lorinser und C. W. Hufeland in No. 265, 275, 276, 277 und 307 der preussischen Staatszeitung von 1831 enthaltenen Artikel. 12°. *Hamburg*, 1832.

Simon (J.) Precautions issued by the medical department of the privy council against the infection of cholera.
[MED. Times & Gaz., 1871, II, pp. 233–235.]

Simon (M.) De la préservation du choléra épidémique, et d'une hygiène spéciale applicable au traitement de la maladie réalisée. 12°. *Paris*, 1865.

Sirus-Perondi *et* **Fabre** (A.) Étude sommaire sur l'importation du choléra et des moyens de le prévenir. *Marseille* 1865.

Siviale (V.) Considérations générales sur l'hygiène publique et privée, et

Viviale (V.)—continued.
sagées sous le rapport prophylactique ou préservatif du choléra. 8°. *Perpignan*, 1835.

Smith (F.) Cholera. On the duty of presenting petitions to the privy council and parliament.
[Homœopathic Review, 1865, IX, pp. 649–657.]

Smith (S.) The common nature of epidemics, and their relation to climate and civilization, also remarks on contagion and quarantine. Edited by T. Baker. 8°. *Philadelphia*, 1866. L.

Smith (Stephen). Local measures of prevention and relief to be adopted during the prevalence of epidemic cholera.
[Amer. Public Health Assn. Reports & Papers, N. Y., 1875, I, pp. 306–316.]

—— Report on the measures of prevention and relief to be adopted during the prevalence of epidemic cholera.
[Bull. N. Y. Acad. of Med., 1866, III, pp. 59–72.]

Snow (E. M.) Asiatic cholera,—contagion and quarantine.
[Med. & Surg. Reporter, 1866, XIV, pp. 176–177, 257–258, 493–494.]

Snow (J.) On the prevention of cholera.
[Med. Times & Gaz., 1853, VII, n. s., pp. 367–369.]

[Solari (L. J. M.)] Destruction des agents propagateurs du choléra. 8°. *Marseille*, 1866.

Sonsino (P.) I progressi del cholera e la sua profilassi.
[L'Imparziale, Firenze, 1868, VIII, pp. 641–643; 1869, IX, p. 513.]

Sousa Martins (J. T. de). Relatorio dos trabalhos da conferencia sanitaria internacional reunida em Vienna em 1874.
[Correio med. de Lisboa, 1875, IV, pp. 73–76, 102–105, 114–116, 122–124, 135–136, 147–149, 169–171, 186–188.]

Speyer (C. F.) Unterweisung für die Cholera-Krankenwärter des platten Landes. 8°. *Bamberg*, 1837.

Squibb (E. R.) Report on disinfectants. With special reference to the prevention of epidemic cholera.
[Bull. N. Y. Acad. of Med., 1866, III, pp. 73–90.]

Staebe (C. L.) Boden-Ventilation als Schutzmassregel wider Cholera und Typhus vorgeschlagen. Mit Betrachtungen über die Magdeburger Epidemie als Einleitung sowie einigen Zusätzen herausgegeben von Dr. Paul Niemeyer. 8°. *Magdeburg*, 1873. L.

Stamm (A. T.) Die Verhinderungsmög. lichkeit der Choleraverbreitung.
[Allg. Med. Central-Zeitung, 1866, XXXV, pp. 29–33.]

—— Die Entstehung, die Verbreitungsursachen und die Vernichtungsmöglichkeit der Cholera.
[Wien. med. Presse, 1869, X, pp. 105–108, 147–150, 196–198, 221–223.]

Stanski (G. P.) Les conclusions du congrès sanitaire international de Vienne et les commentaires de M. Fauvel, devant la logique. 8°. *Paris*, 1875. L.

Stewart (E.) Sanitary hints respecting cholera.
[London Med. Gaz., 1832, IX, pp. 246–247.]

Strambio (G.) Riforma delle leggi sanitarie contro l'importazione della peste. 8°. *Milano*, 1845.

Stricker (W.) Lebensregeln zum Schutze gegen asiatische Cholera. 8°. *Frankfurt a. M.*, 1854.

Tardieu (A.) Comité consultatif d'hygiène publique. Rapport sur un projet de modification du régime sanitaire concernant le choléra.
[Gaz. des hôp., 1866, pp. 317–318.]

Taylor (T.) Interment of the bodies of cholera patients.
[Lancet, 1854, II, n. s., p. 461.]

Tedesco (A. de). La cremazione dei cadaveri. Del colera-morbus nei suoi rapporti colla cremazione ed i sotterramenti dei morti alle Indie, in Egitto ed in Europa. Utili norme di salubrità pubblica. 8°. *Trieste*, 1874. L.

Teljer (G. J.) De cholera.
[Genees. Courant, Tiel, 1867, No. 40.]

Theis. Rapport du conseil supérieur d'hygiène publique sur les instructions concernant le choléra.
[Archiv. méd. belges, 1866, IV, 2e s., pp. 129–130.]

Tholozan. Les théories du cholera.—L'influence des causes d'insalubrité sur son développement. — L'agglomération des cholériques dans les hôpitaux.
[Gaz. méd. de Paris, 1853, VIII, 3e s., pp. 673–677.]

Thomas. Verhandlungen der Cholera-Conferenz in Weimar am 28. und 29. April 1867. Mit einem Vorworte von Dr. Max von Pettenkofer. 8°. *München*, 1867. L.

Thomas (W. J.) The sanitary conditions of light and epidemic cholera.
[Lancet, 1854, I, n. s., pp. 490–491.]

Thomson (A.) The only precautions feasible against the cholera.
[LONDON Med. & Surg. Jour., 1832, pp. 448–449.]

Tijken (P. C.) Nog Iets over Teerverdamping bij Cholera.
[GENEESK. Courant, Tiel, 1867, No. 37.]

Tourrette. Du traitement curatif du choléra-morbus épidémique, et de sa prophylaxie, suivi de quelques réflexions sur son mode de transmission. 8°. *Paris*, 1853. L.

——— De la saignée préalable comme moyen préventif du choléra-morbus.
[REVUE méd., 1863, I, pp. 321–330.]

Tourrette (L.) Prophylaxie du choléra.
[GAZ. des hôp., 1849, p. 364.]

Troy (D.) Précis historique sur le choléra-morbus, ou précautions à prendre contre ce . . . fléau. 8°. *Paris*, 1831.

Tucker (J. H.) On the prophylaxis of cholera by some of the vegetable and mineral acids.
[TRANS. Epidem. Soc., 1856, *with* JOUR. of Pub. Health, 1856, II, pp. 10–23; *also, in* MED. Times & Gaz., 1856, XII, n. s., pp. 100–101.]

Turchetti (O.) Delle leggi con le quali si governa il cholera morbus, e del modo di prevenirlo nei popoli e negli individui. 8°. *Firenze*, 1855.

Turck (L.) Du choléra et des moyens de le prévenir.
[REVUE de thérap., 1855, III, pp. 202–207.]

——— The same. 8°. *Paris* [1855]. L.

Tutschek (L.) Guter Rath für Jeden, Hoch und Nieder, der sich von dem Anfalle der Cholera behüten will. 8°. *München*, 1874. L.

Uffreduoci (A.) Appendice al sistema di preservazione dal cholera, da servire di base ad una convenzione internazionale sanitaria.
[GAZ. med. it. Lomb., Milano, 1867, VI, 5a s., pp. 253–255.]

Vahu. Prophylaxie du choléra. Maximes d'hygiéne populaire. 12°. *Paris* [1848].

Vaïsse. Circulaire du préfet du Rhône relative au choléra.
[GAZ. méd de Lyon, 1854, VI, pp. 271–272.]

Valtier (A.) Du choléra, moyens prophylactiques et dans le cas où ces moyens n'auraient par été employés, traitement et prompte guérison. 8°. *Lille*, 1865.

Vergne (J. D.) Quelques conseils pour se préserver du choléra. 8°. *Paris*, [illegible].

Vezin (H.) Vorschriften wie man . . . beim Herannahen und während des Herrschens der Cholera zu verfahren und wie man die von derselben befallenen Kranken in dem ersten Zeitraume der Krankheit zu behandeln hat. 8°. *Osnabrück*, 1831.

Vidal (E.) Communications sur le choléra.
[L'UNION méd., 1865, XXVIII, 2e s., pp. [illegible].]

Vleminckx. Sur l'hygiène publique à propos du choléra.
[BULL. de l'Acad. roy. de méd. de Belgique, IX, pp. 951–958.]

——— Rapport concernant les inhumations des cadavres mort du choléra.
[BULL. de l'Acad. roy. de méd. de Belgique, I, pp. 811–825.]

Vogt (F. A.) Ueber Desinfections-M[illegible] bei der Cholera.
[ARZTZL. Intell.-Bl., 1865, XII, pp. 723–726.]

——— Cholera und Rinderpest vor den Schranken der Humanität.
[ARZTZL. Intell.-Bl., 1867, XIV, p. 361.]

Wasserfuhr (A. F.) Waarnemingen . . . Aanmerkingen betrekkelijk de Besmettelijkheid der Cholera. . . . . Uit het Hoogduitsch. 8°. *Amsterdam*, 1832.

Wayte (J.) Prevention of cholera.
[LANCET, 1831–32, II, pp. 731–732.]

——— Prophylaxis of cholera.
[LONDON Med. Gaz., 1833, XI, pp. 42–44.]

Wedekind (*Freiherr* v.) Ueber die Maßregeln zur Verhütung des Fortschreitens der ansteckenden weissen Cholera.
[MED. Conversbl., 1831, pp. 329–334.]

Weisenberg (A.) Ansicht über die Abwehr und Heilung der asiatischen Cholera. 8°. *Ansbach*, 1831.

Weissbrod (J. B. von). Denkschrift über die asiatische Cholera in sanitätspolizeilicher Beziehung, nebst einem Anhange aphoristischer Bemerkungen über die Epidemie vom Jahre 1836 in München. 4°. *München*, 1852. L.

Wenzl. Sanitäts-Massregeln gegen die asiatische Brechruhr. 8°. *München*, 1831.

Wernert (P. J.) Schutz gegen die asiatische Cholera. 8°. *Rastatt*, 1831.

White (W.) Means of prevention . . . method of cure of the cholera-morbus and the atrocities of the cholera pa[illegible]. 8°. *London*, 1837. C. L.

Wibmer (K.) Schutz gegen die asiatische Cholera. 8°. *München*, 1831.

Wilbrand (J.) Hildesheim's Cholera- und Typhusverhältnisse und die Desinfection der Stadt während der Cholera-Epidemie von 1867. 8°. *Hildesheim*, 1868.

——— Die Desinfection im Grossen bei Cholera-Epidemien. Nach wissenschaftlichen Principien practisch durchgeführt im Jahre 1867 zu Hildesheim. Officieller Bericht über die Entwickelungsgeschichte der Krankheit, die Massregeln der Behörden und die Grundsätze und Erfahrungen der Desinfections-Commission. Im Auftrage der königlichen Landdrostei zu Hildesheim. 2te Ausgabe. 8°. *Hildesheim*, 1873. L.

Worms (J.) De la progagation du choléra et des moyens de la restreindre. 8°. *Paris*, 1865. L.

——— Le choléra et les quarantaines.

[GAZ. hebd. de méd. et de chirurg., 1866, 2e s., III, pp. 399–400.]

——— Traitement du choléra à la période prodromique. Note .... suivie d'une exposition succincte des moyens les plus propres à preserver en temps d'épidémie les localités et les individus. 8°. *Avignon*, 1866.

Wunderlich (C. A.) Istruzione sul modo come ciascuno deve comportarsi durante un'epidemia di colera. Traduzione del E. G. Ohlsen. *Napoli*, 1866.

Zachariae. Hvorledes er Kjöbenhavn forberedt paa at Modtage en Cholera-epidemi, og hvilke Foranstaltninger ere efterhaanden foretagne istedenfor den ophævede Karantaenelov til at forebygge dens Indgang?

[UGESKR. for Laeger, Copenhagen, 1866, III, pp. 372–376.]

Zambianchi (A.) Sul cholera e sulle memorie del dott. A. Bo intitolate "Le quarantene ed il cholera morbus". 8°. *Torino*, 1854.

Zerby (J., *fils*). Traité sur le choléra-morbus. 1° Soins à exécuter pour arrêter les progrès meurtriers du choléra; 2° Moyens de s'en préserver. 8°. *Paris*, 1849.

Zimmermann (H. H. F.) Vorsichts-Massregeln gegen die Cholera. 2te Aufl. 8°. *Mühlhausen*, 1867.

Aanschrijvingen betrekkelijk de Cholera.

[NEDERL. Tijdschr. v. Geneesk., 1866, I, pp. 262–270.]

Aanwijzing ter Bewaring van de Gezondheid, en ter Voorbehoeding van de Aansteking van den aziatischen Braakloop of Cholera. 8°. *Gravenhage*, 1831. L.

Abgefordertes Gutachten [ueber die Maassregeln zur Verhinderung der Weiterverbreitung der Cholera im Innern des Landes].

[VERHANDL. d. phys.-med. Gesell. zu Königsberg über die Cholera, 1832, pp. 10–35.]

Amtliche Verfügungen, betreffend den Transport von Cholera-Leichen.

[VIERTELJAHRSSCHR. f. gerichtl. u. öffentl. Med., Berlin, 1866, IV, p. 355.]

Amtlicher Bericht über die Wirkung der Sperr-Maassregeln gegen die Cholera.

[VERHANDL. d. phys.-med. Gesell. zu Königsberg über die Cholera, Beilage, 1832, pp. 424–452.]

Anordnungen, die im Betreff der herannahenden Cholera morbus zu befolgen sind. fol. [*n. p., n. d.*] L.

Ansprache ans Publicum, zunächst der Herzogthümer Schleswig und Holstein über die epidemische Cholera vom königlich schleswig-holsteinischen Sanitätscollegium zu Kiel. 8°. *Kiel*, 1831. L.

Anweisung über die Bereitung und Anwendung des Chlors als Schutzmittels gegen Ansteckung durch Choleragift. 8°. *Berlin*, 1831. L.

Anweisung zu dem die Zerstörung des Ansteckungstoffes der Cholera bezweckenden Reinigungsverfahren (Desinfectionsverfahren). 8°. [*n. p., n. d.*] L.

Anweisung zur Erhaltung der Gesundheit und Verhütung der Ansteckung bei etwa eintretender Cholera-Epidemie. Neue, revidirte Ausgabe. 8°. *Berlin*, 1831. L.

Anweisung zur Erhaltung der Gesundheit und Verhütung der Ansteckung beim etwaigen Ausbruche der asiatischen Cholera. Hannover, den 18ten Junius 1831. 4°. [*n. p., n. d.*] L.

Apothekernes Forsyning i Anledning af Cholera.

[NORSK Mag. for Laegevid., Christiania, 1848, II, pp. 566–574.]

Are cholera hospitals beneficial or injurious?

[LONDON Med. Gaz., 1848, VII, n. s., pp. 419–421.]

Asiatic cholera,—precautionary measures in Buffalo.

[BUFFALO Med. & Surg. Jour., 1865–66, V, pp. 160–170.]

Asiatic cholera.

[DUBLIN Med. Press, 1848, XX, p. 63.]

Avis au peuple sur les moyens de se préserver du choléra-morbus. 16°. *Lyon*, 1831.

Avis sur les moyens à employer pour se préserver du choléra-morbus, publié par l'intendance sanitaire . . . . du Rhône. (1832.) 8°. *Lyon* [*n. d.*]

Behoedmiddelen ter Voorkoming van de Cholera (een Uittreksel uit het Rapport der Geneeskundigen, welke aangaande deze Ziekte van Gouvernementswege belast zijn geweest met het Onderzoek in loco te Hamburg en in Berlijn). 8°. *'s Hage*, 1832.

Beiträge zur Geschichte des Sanitäts-Wesens im königlich-preussischen Staate. Maassregeln gegen die Verbreitung der Cholera.

[MAG. f. d. gesammt. Heilk., 1831, XXXIV, pp. 570–637.]

Beiträge zur Geschichte des Sanitäts-Wesens im Preussischen Staate. Regulativ, die sanitäts-polizeilichen Vorschriften bei den am häufigsten vorkommenden ansteckenden Krankheiten enthaltend. II. Specielle sanitäts-polizeiliche Vorschriften für die einzelnen ansteckenden Krankheiten. 1. Cholera. 2. Typhus. 3. Ruhr.

[MAG. f. d. gesammt. Heilk., 1836, XLVI, pp. 328–337, 528–530; 1836, XLVII, pp. 360–380.]

Beiträge zur Poleoprophylaxis gegen die gangetische Pest, gewöhnlich Cholera genannt. 8°. *Braunschweig*, 1831. L.

Bekanntmachung: den Verkehr mit den von der Cholera inficirten Gegenden des In- und Auslandes betreffend. Gesetz-Sammlung. I. Abtheilung. No. 39. Hannover, den 12ten Oct. 1831. 4°. [*n. p.*, *n. d.*] L.

Bekanntmachung der königlichen Landdrostei zu Stade, die Zurückweisung aller von Stettin oder aus einem zwischen Stettin und Danzig gelegenen Ostseehafen kommenden Schiffe von der Elbe und Weser betreffend. Beilage zu No. 74. der Hannover'schen Anzeigen, den 14. September 1831. 4°. [*n. p.*, *n. d.*] L.

Bekjendtgjörelse i Anledning af den epidemiske Cholera.

[UGESKR. for Laeger, Copenhagen, 1849, X, pp. 203–204.]

Belehrung (Ganz einfache) über die Cholera oder Brechruhr für das Landvolk. 8°. *Nürnberg*, 1831.

Belehrung über die orientalische Cho[le]ra für Nichtärzte, amtlich bekannt gemacht. 12°. *München*, 1831. L.

Bericht eines Spezial-Comite der Sanitäts-Commission der Stadt Detroit, enthaltend Vorschläge zu Maszregeln für die Abwendung der asiatischen Cholera und für die Beförderung des allgemeinen Gesundheitszustandes, sowie auch einen Plan für ein städtisches Dispensary und dessen Wirkungen. [Im Auftrag des Stadtraths, den 12. Dezember 1865.] 8°. *Detroit*, 1865. L.

Bericht über die Cholera-Conferenz in Weimar, erstattet von Dr. Lent. 8°. *Köln*, 1867. L.

Berliner medizinische Gesellschaft: Bericht der epidemiologischen Sektion über die Cholerafrage.

[WIEN. med. Presse, 1867, VIII, pp. 842–845.]

Bestimmungen (Vorläufige) für den Fall des Ausbruchs der Cholera in den Städten, Flecken und grösseren Ortschaften des Königreichs Hannover, etc. 4°. *Hannover*, 1832.

Can cholera be excluded or confined?

[LONDON Med. Gaz., 1832, IX, pp. 126–129.]

Central board of health—*instructions* to the public respecting the treatment of cholera.

[LONDON Med. Gaz., 1848, VII, n. s., pp. 595–597.]

Cholera.

[SCHAT d. Gezondh., Haarlem, 1859, II, pp. 337–358.]

Cholera (The)—abolition of intramural interments.

[LONDON Med. Gaz., 1849, XLIV, pp. 458–462.]

Cholera (The) and quarantine.

[CANADA Med. & Surg. Jour., 1873, I, pp. 425–436.]

Cholera and sanitary reform.

[BRIT. & For. Med.-Chir. Rev., 1850, V, pp. 215–226.]

Cholera (The) and the board of health.

[MED. Times & Gaz., 1853, VII, n. s., pp. 271–272.]

Cholera asiatica. Königlich baierische Verordnung die prophylactischen Maasregeln gegen die morgenländische Brechruhr betreffend.

[ANNAL. d. Staatsarzneik., Tübingen, 1838, III, pp. 234–249.]

Cholera, Bekjendtgjörelser om dens Gang i Rigets Naerhed, paa Bandholm, om Qvarantaenen og offentliche Foranstaltninger i Anledning af samme, fra Finansministeriet, Sundhedscollegiet, m. m.

[UGESKR. for Laeger, Copenhagen, 1850, XII, pp. 112, 136, 152, 173, 208, 224, 248, 278, 295, 312.]

Cholera! Caution to the public. [By the commissioners of health of the city of New York, by request, Nov. 1865.] 8°. [*n. p., n. d.*] L.

Cholera (The) conference at Weimar.
[BRIT. Med. Jour., 1867, I, pp. 625–626.]

Cholera. Copy letter [of W. S. Walker] secretary to the board of supervision for the relief of the poor, to Dr. J. Smith, president Royal College of Physicians, Edinburgh, requesting suggestions for the guidance of visitors engaged in house-to-house visitation. [With suggestions made for preparation for the advent of Asiatic cholera by the committee.] 1866. 8°. [*Edinburgh, n. d.*] L.

Choléra (Du) et des moyens d'empêcher son développement.
[L'ABEILLE méd., 1853, X, pp. 291–292.]

Choléra (Du) et des quarantaines.
[JOUR. de méd. et de chir. prat., 1866, XXXVII, 2e s., pp. 193–194.]

Choléra (Le). Étiologie et prophylaxie. Exposé des travaux de la conférence sanitaire internationale de Constantinople. 8°. *Paris*, 1866. L.

Cholera hospitals.
[LANCET, 1866, II, p. 105.]

Cholera in its relations to sanitary measures.
[BRIT. & For. Med.-Chir. Rev., 1851, VII, pp. 2–40.]

Cholera instructions. (India.)
[STATIST., Sanit., & Med. Repts. Army Med. Dept. Gr. Br., 1866, pp. 638–643.]

Cholera. (Instrux angaaende de almindelige Forholdsregler, der Blive at lagttage ved en Cholera-Epidemis optraeden.)
[UGESKR., Copenhagen, 1849, X, pp. 209–219.]

Cholera—its prophylaxis.
[ST. LOUIS Med. & Surg. Jour., 1853, XI, pp. 138–144.]

Cholera; Kvarantaenebestemmelser, Discussioner om i det medicinske Selskab i Christiania.
[NORSK Mag. for Laegevid., Christiania, 1866, XX, pp. 557, 563, 698, 1088.]

Cholera (The), necessity of sanitary reform to meet it.
[JOUR. of Pub. Health, 1849, II, pp. 15–16.]

Cholera preventive.
[ST. LOUIS Med. & Surg. Jour., 1866, III, pp. 489–492.]

Cholera preventive service.
[MED. Times & Gaz., 1866, II, pp. 447–448.]

Choléra (Le), prophylaxie ou moyens de s'en préserver. Premiers soins à donner aux cholériques en attendant l'arrivée du médecin . . . . . Par M. D. 16°. *Douai*, 1866.

Cholera, *etc.*—continued.

Cholera—quarantine.
[MED. Times, 1850, I, p. 152.]

Cholera refuges.
[MED. Times & Gaz., 1865, II, pp. 630–631.]

Cholera-Conferenz (Die) in Weimar am 28. und 29. April 1867.
[WIENER med. Wochenschr., 1867, XVII, pp. 683–687.]

Cholerakarantäner.
[FORHANDL. vid Svenska Läk.-Selsk., Stockholm 1866, pp. 166–172.]

Choléra-morbus. Conseils aux citoyens. 4°. [*Paris*, 1831.]

Choléra-prophylaxie (Le); par le Dr. Ch. Pellarin . . . . Des symptômes précurseurs du choléra; par le Dr. A. de Grand-Boulogne . . . . Publié par Dollfus-Ausset. 8°. *Strasbourg*, 1865.

Cholera-Regulativ: den Sanitätsbehörden, den Aertzen und dem Publikum vorgelegt von W. Griesinger, Max von Pettenkofer und C. A. Wunderlich. 8°. *München*, 1866. L.

—— The same. 2te Aufl. 8°. *München*, 1867. L.
[*See, also*, REGOLAMENTO sul cholera, *infra*.]

Cholera-Schutz und Cholera-Behandlung. Von einem Fachmanne. 8°. *Wien*, 1873. L.

Cholernye priniuty.
[MEDYTSYNSKIY Viestnik, St. Petersburg, 1866, 6th year, No. 30, pp. 355–356.]

Circulaire aux recteurs concernant les précautions hygiéniques à prendre dans les établissements scolaires.
[GAZ. méd. de Paris, 1866, XXI, pp. 635–636.]

Circulaires ministérielles relatives aux mesures sanitaires contre le choléra-morbus.
[GAZ. méd. de Paris, 1831, II, pp. 333–334.]

City of Boston. 1832. [Ordered, that a board of commissioners of health be appointed, ... for the purpose of preventing the introduction and limiting the ravages of cholera.] 8°. [*n. p., n. d.*] L.

[**Committee** (The) appointed to consider what measures this board [health commissioners of the city of Boston] ought to take for the care and treatment of the sick, in case the cholera should actually appear in the city.] 8°. *Boston*, 1832. L.

ıustafel, *etc.*—continued.

Schutzmittel gegen diese und alles dessen, was bei einem Ausbruch derselben bis zur Ankunft des Arztes zu thun ist. fol. *Glogau*, 1831.

ilfsbüchlein in Choleragefahr. 3te Aufl. 8°. *Leipzig*, 1866.

strucciones para evitar y combatir el cólera morbus.

[Revista med.-quirúrg., Buenos Aires, 1874, x, pp. 330–335, 342–345.]

ıstruction für die Aerzte der Herzogthümer Schleswig und Holstein über das Verfahren bei einem Ausbruche der epidemischen Cholera in den Herzogthümern vom königlich schleswig-holsteinischen Sanitätscollegium zu Kiel. 8°. *Kiel*, 1831. L.

ıstruction für die Sanitäts-Behörden, und für das bei den Contumaz-Anstalten verwendete Personale, zum Behufe die Gränzen der k. k. österreichischen Staaten vor dem Einbruche der im kaiserlich-russischen Reiche herrschenden epidemischen Brechruhr (Cholera morbus) zu sichern, und im möglichen Falle des Eindringens, ihre Verbreitung zu hemmen. 8°. *Hannover*, 1831. L.

nstruction, hygiène, régime préservatif. fol. *Paris* [1853].

nstruction populaire contre le choléra. 4°. *Nancy* [1854].

——The same. 12°. *Bar-le-Duc* [1854].

nstruction populaire sur les principaux moyens à employer pour se garantir du choléra-morbus, et sur le conduite à tenir lorsque cette maladie se déclare. 8°. [*Paris*, 1832.] L.

nstruction raisonnée sur les moyens de se préserver du choléra-morbus. 8°. *Rennes* [1832].

nstructions concernant les mesures générales à prendre à l'occasion de l'épidémie de choléra, envoyées aux préfets par le ministre de l'agriculture et du commerce.

[Gaz. méd. de Paris, 1849, IV, 3e s., pp. 57–59.]

nstructions to army medical officers, for their guidance on the appearance of spasmodic cholera in this country. (War office, 1848.) 8°. *London*, 1849. L.

[*Also, in* Med. Times & Gaz., 1853, VII, n. s., pp. 595–596.]

Instructions to local authorities on preventive measures in relation to epidemic cholera, under the nuisances removal acts. 8°. *London*, 1854. L.

Instructions sanitaires sur les moyens préservatives du choléra-morbus. Précédées d'une notice sur l'assainissement de Paris. 8°. *Paris*, 1849. L.

Instruzione per mantenere la salute e per preservarci dal contagio della cholera; traduzione dal tedesco sulla nuova edizione emendata, pubblicatasi in Berlino nel 1831, con note del G. Pozzi. (1831.)

Instruzione popolari di preservazione dal cholera discusse ed approvate dal comitato medico napolitano. *Napoli*, 1865.

Intendance (De l') sanitaire de Marseille, et des quarantaines contre le choléra-morbus.

[Revue méd. chir. de Paris, 1850, VIII, pp. 127–128.]

International (The) cholera commission.—Who are the culprits, the Turks or the English?

[Med. Times & Gaz., 1865, II, pp. 469–470.]

International hygiene: the diffusion of cholera in Europe.

[Practitioner, 1874, XIII, pp. 456–460.]

International (The) sanitary conference.

[Practitioner, 1874, XIII, pp. 220–228.]

Internationale (Die) Konferenz zur Erzielung gleichmässiger Quarantänemassregeln gegen die Cholera.

[Wien. med. Wochenschr., 1874, XXIV, pp. 527–529, 667–670, 687–690.]

Invloed (De) van Woning, Stand en algemeene Maatregelen.

[Nederl., Tijdschr. v. Geneesk., 1867, II, pp. 110–116.]

Isolement (De l') des cholériques.

[Lyon médical, 1873, XIV, pp. 201–203.]

Istruzione popolare intorno al cholera morbus, emanata in Pavia da una commissione sanitaria sotto gli auspicj di quel municipio.

[Gaz. med. it. Lomb., Milano, 1849, II, 2a s., pp. 325–326.]

Istruzione popolare sul colera-morbus, adottato dal consiglio provinciale sanitario di Parma. *Parma*, 1873.

Karantaene-Foranstaltninger og Bestemmelser angaaende Cholera.

[Bibl. for Laeger, Copenhagen, 1848, IV, pp. 231, 474–478.]

Können Epidemien allein durch die Luft verbreitet werden? Anfrage und Aufruf an die Aerzte, Physiker und Medizinalbehörden, zur Beruhigung des Publikums,

Können, *etc.*—continued.
veranlaszt durch die wieder ausgebrochene Cholera morbus Dec. 1830. 8°. *Danzig*, 1831. L.

Kongelige Resolution om Cholerasmittede steder.
[NORSK Mag. for Laegevid., Christiania, 1840, I, pp. 80, 197.]

Kongelige (Der) Sundheds-Collegium i Kjøbenhavn; Anviisning til Forebyggelse af Smitte ved indtraffende Cholera-Epidemie. fol. *Kjøbenhavn*, 1831.

Kongelige (Der) Sundheds-Collegium i Kjøbenhavn; kort Anviisning til at Kjende den epidemiske Cholera, samt Underretning om de hidtil anvendte Logemidler imod Sygdommen. fol. *Kjøbenhavn*, 1831.

Kongelige (Der) Sundheds-Collegium i Kjøbenhavn; Veiledning til at anvende passende Midler imod den farlige Cholera-Syge indtil Lægehjelp kan faaes. 8°. *Kjøbenhavn*, 1831.

Korte Aanwijzingen voor de Geneeskundigen in Vriesland, hoedang te handelen bij het onverhoopt Ontstaan der oostindische Cholera hier te Lande, door de prov. Commissie van geneeskundig Onderzoek en Toevoorzigt. 8°. [*Leeuwarden*, 1831.]

Liabilities to an attack of cholera.
[JOUR. of Health, 1832, III, pp. 155–159.]

Lovgivning og offentliche Foranstalninger med Hensyn til Cholera.
[UGESKR. for Laeger, Copenhagen, 1848, IX, pp. 95–96.]

Maatregelen bij het Dreigen der Cholera asiatica in 1870 en 1871.
[VEREIN. tot Verbet. der Volksgezondh., Utrecht, 1872, VI, p. 62.]

Maatregelen wegens de Cholera in 1867 in Nederland.
[NEDERL. Tijdschr. v. Geneesk., 1867, I, pp. 527, 557–559, 573.]

Malignant (The) cholera. Abstract of documents communicated by the central board of health.
[LANCET, 1832–33, I, pp. 48–50.]

Massregeln zur Verhütung und Beschränkung der Cholera.
[ALLG. Wien. med. Zeitg., 1866, XI, pp. 295–296, 303–305, 311–312.]

Measures proposed for the prevention of Asiatic cholera in Providence. A report to the board of health. 8°. *Providence*, 1865. L.

Memorandum of a plan of united action in the case of an epidemic of cholera to be communicated to vestries and district boards, by the metropolitan medical officers of health. 8°. *London* [n. d.]

Memorandum on cholera, adopted at a medical conference held in the board of agriculture, in March, 1866. 12°. 1866.

Memorandum on precautions to be taken against infection of cholera.
[REPORT of Medical Officer of Privy Council, London, 1874, I, n. s., pp. 28–31.]

Memorandum relative to cholera issued by the board of health. College of Physicians, London. 8°. (Circ., 1831.)
[*Bound with* CHOLERA Gazette.]

Mesures de salubrité concernant les injections des cholériques. Documents relatifs au choléra de 1865 et de 1866.
[JOUR. de méd. et de chir. prat., 1866, XLIII, 385–389.]

Mesures (Des) sanitaires contre le choléra morbus.
[GAZ. des hôp., Paris, 1831, V, pp. 229–232.]

Méthode Broussais. .... Moyens à employer pour se préserver d'une maladie certaine du choléra-morbus. Suivie de moyens curatifs. 8°. *Lyon* [n. d.]

Miery k unitchtojeniu zlovopia cholery.
[MEDYTZYNSKIY Viestnik, St. Petersburg, 6th year, No. 30, pp. 355–356.]

Miery protiv cholery.
[MEDYTZYNSKIY Viestnik, St. Petersburg, 6th year, No. 4, p. 104.]

Militär-aerztliche Verwahrungsmassregeln gegen die Cholera.
[WIENER med. Wochenschrift, 1865, XV, pp. 1702, 1718–1719.]

Mittheilungen über öffentliche Aufgaben und Interesse der öffentlichen Gesundheitspflege, mit Rücksicht auf Epidemien.
[ALLG. Zeitschr. für Epidemiol., Erlangen, pp. 236–240, 309–318.]

Moet men de Cholera asiatica houden als eene besmetteligke Ziekte?
[GENEESK. Courant, 1855, No. 35.]

Moet men het eerste Uitbreken der Cholera verzwijgen?
[GENEESK. Courant, Tiel, 1855, No. 32.]

Moet men het Weder-Uitbreken der Cholera geheim houden.
[GENEESK. Courant, Tiel, 1867, No. 3.]

Monsieur choléra et madame Santé. (Signé: Madame Santé. Pour copie conforme: J.-M. Dejey.) 16°. [1867].

Faõ deveremos receiar a importação da cholera-morbus ?
[Gaz. med. da Bahia, 1866, I, pp. 37-39.]

Few (The) Indian barracks and cholera.
[Med. Times & Gaz., 1870, I, p. 184.]

Fota ed avvertenze pratiche del consiglio superiore di sanità del regno d'Italia sulla colera.
[Sperimentale (Lo), Firenze, 1865, XVI, pp. 150-162.]

Offentlige Foranstaltninger med Hensyn til den epidemiske Cholera.
[Ugeskr. for Laeger, Copenhagen, 1849, pp. XI, 15, 30.]

Om Forandring i de bestaaende Kvarantaenebestemmelser mod Cholera.
[Norsk Mag. for Laegevid., Christiania, 1866, XX, pp. 872-888; 1867, XXI, pp. 846-856.]

Om Indförelse af en modificeret Soqvarantaene mod Cholera.
[Supplement. til Bibl. for Laeger, Copenhagen, 1-55, pp. 260-274.]

On the admission of cholera patients into public hospitals.
[Med. Times & Gaz., 1853, VII, n. s., pp. 351-352.]

On the duties of the public during the prevalence of the cholera.
[Lancet, 1848, II, p. 515.]

On the means of prevention of cholera.
[N. Y. Med. Gaz. & Jour. of Health, 1854, V, pp. 433-445.]

Opinions of eminent medical men, with regard to vegetable diet, in reference to cholera. 8°. *London* [*n. d.*] L.

Order as to detention and examination of ships suspected of cholera.
[Report of Medical Officer of Privy Council, London, 1874, I, n. s., No. 1, pp. 25-27.]

Ordonnance poético-médicale contre le choléra-morbus . . . Par un antipolypharmaque (signé F. R., 1832).

Overzigt van de voornaamste Maatregelen tegen de aziatische Cholera of Braakloop, en de beste Middelen daartegen te bezigen van het gegin der Besmetting af tot aan de komst van een Geneesheer. Uit het Hoogduitsch, etc. 8°. *Groningen*, 1831.

Papers relating to the conclusions arrived at by the cholera conference at Constantinople. *London*, 1868.

Par (Et) Ord om vor Karantaenelovgivning.
[Ugeskr. for Laeger, Copenhagen, 1865, XLIII, pp. 401-412.]

Plain advice to all during the visitation of the cholera.
[Med. Times & Gaz., 1853, VII, n. s., pp. 355-356.]

Plain and simple rules for the prevention and cure of cholera. 8°. *Philadelphia*, 1832.

Plus de choléra ! Préservatif contre toute épidémie et toute contagion. 12°. *Digne*, 1835.

Ports of Tyne floating cholera hospital. (Plate.)
[Lancet, 1872, I, pp. 15-16.]

Praeventive Forholdsregler imod, om Cholera.
[Norsk Mag. for Laegevid., Christiania, 1866, XX, pp. 860, 865, 942, 962, 987, 1005.]

Precauciones contra el cólera morbo.
[Gac. med., Lima, 1866, II, pp. 69-70.]

Precautionary advice to local boards of health with reference to epidemic cholera.
[Med. Circular, 1857, XI, pp. 201-202.]

Precautionary measures against the contagion of cholera.
[London Med. & Surg. Jour., 1833, II, pp. 184-185.]

Precautions against cholera.
[London Med. Gaz., 1832, IX, pp. 158-161.—Lancet, 1872, II, p. 123.—London Med. Record, 1873, I, p. 513.]

Précautions à prendre contre le choléra. 18°. *Sisteron*, 1854.

——— The same. [Extrait de l'instruction adoptée par l'Académie nationale de médecine, 1849.] 8°. [*Paris, n. d.*]

Précautions (Des) à prendre contre le choléra.
[Gaz. hebd. de méd. et de chirurg., 1866, 2e s., III, pp. 495-496.]

Precautions in the north against cholera.
[Lancet, 1871, II, p. 226.]

Précautions hygiéniques à prendre dans les hôpitaux et les hospices pendant les épidémies, et en particulier pendant les épidémies cholériques.
[Gaz. méd. de Paris, 1866, XXI, pp. 636-638.]

Premiers soins contre le choléra. 8°. *Bordeaux* [1854].

Preparations for the cholera.
[Dublin Med. Press, 1848, XX, pp. 125-126.]

Preparations made against epidemic cholera, in Glasgow.
[Glasgow Med. Jour., 1866, I, n. s., pp. 229-235.]

Préservatif contre le choléra-morbus. 8°. [*Paris*, 1831.]

Préservatifs et remèdes contre le choléra . . . . précédés de l'historique du fléau, et de documents nouveaux et intéressants. 12°. *Paris*, 1847.

Preservation (The) of Europe from cholera.
[Lancet, 1868, I, p. 62.]

Prevention of cholera.
[LANCET, 1848, I, pp. 67–68.—MED. Times, 1851, II, n. s., pp. 40–41.—MED. Times & Gaz., 1853, VI, p. 279.]

Prevention of cholera. 12°. *Boston*, 1849.

Prevention (The) of cholera a governmental duty.
[MED. Times, 1851, III, n. s., pp. 100–101.]

Prevention of cholera. Appeal to the rich on behalf of the poor.
[LANCET, 1832, I, pp. 518–519.]

Proclamation against the cholera.
[DUBLIN Med. Press, 1848, XX, pp. 218–219.]

Propagation of cholera by emigration.
[MED. Chronicle, 1855, II, pp. 409–412.]

Prophylactic treatment during the prevalence of cholera.
[LONDON Med. Gaz., 1849, XLIV, p. 435

Provedimenti sanitari della città di Trieste, nell'anno 1865. *Trieste*, 1866.

Provisorisk Anordning. . . . . [Ordonnance provisoire au sujet des précautions contre le choléra. Christiania, 25 septembre 1831.] 4°. *Christiania* [*n. d.*]

Publicandum, enthaltend die abändernden und erweiternden Bestimmungen zur Ausführung der Ministerial-Instruction vom 13. Junius 1831, über das bei der Annäherung der asiatischen Cholera, so wie über das bei dem Ausbruche derselben im Königreiche zu beobachtende Verfahren. Hannover, den 10. October 1831. 4°. [*n. p.*, *n. d.*] L.

Quarantaine — Voorzorgsmaatregelen — Cholera.
[NEDERL. Tijdschr. v. Geneesk., 1867, I, pp. 431, 637.]

Quarantine and epidemic cholera [review].
[BRIT. & For. Med.-Chirurg. Rev., 1874, II, pp. 30–49.]

Quelques déductions d'une statistique du choléra dans l'asile d'Auxerre, relativement à l'influence préventive de l'aération et des conditions hygiéniques générales.—Constance des prodromes.
[GAZ. des hôp., 1855, p. 67.]

Raadgevingen aan den Burger- en Boerenstand, hoedanig zich te gedragen ter krachtdadige Afwering der Cholera, benevens Aanwijzing van de Middelen. 8°. *Breda*, 1832.

Rapport aan den Minister van binnenlandsche Zaken over Desinfectie met Betrekking tot de Cholera, uitgebragt door de algemeene Cholera-Commissie.
[GENEESK. Courant, Tiel, 1866, Nos. 29–30.]

Rapport, *etc.*—continued.
——— The same. 8°. *Groningen*, [1866].

Rapport de la commission du choléra et le mémoire de M. Gilleau et la lettre relative à l'hygiène publique: critique de celle-ci.
[BULL. de l'Acad. roy. de méd. de Belg., 2e s., 1867, I, 3e s., pp. 694–704.]

Rasporajenia po slutchaiu cholery.
[MEDITZINSKIY Viestnik. St. Petersb., 6th year, No. 28, pp. 231–232.]

Rathgeber für alle, welche sich gegen Cholera morbus schützen wollen. Nebst Angaben, wie man beim Ausbruche dieser Krankheit sich selbst augenblickliche zweckmässige Hülfe leisten kann. Nach den neuesten Erfahrungen der russischen Aerzte bearbeitet von einem praktischen Arzte. 4te Auflage. *Breslau*, 1831.

Recommendations of the College of Physicians of Ireland relative to the prevention of an outbreak of cholera and the treatment of its earlier stage.
[DUBLIN Quar. Jour. Med. Sci., 1853, XV, 485.]

Régime à suivre dans la dysenterie cholérique qui règne dans ce moment. *Nantes* [1834].

Regolamento per guarentire le provincie del regno dalla diffusione del cholera asiatico, qualora vi penetrasse. *Napoli*, 1849.

Regolamento sul colera proposto dal collegi di sanità, ai medici ed alla gente co dai prof. W. Griesinger, M. Pettenkofer, C. A. Wunderlich. Tradotto dal tedesco in italiano dal dott. E. G. *Napoli*, 1866.

Regulations for England and Wales against importation of cholera.
[LANCET, 1873, II, p. 121.]

Relief association. [Report of committee on organizing a relief association in Boston in view of approaching cholera. Signed Charles G. Loring, chairman.] 4°. *Boston* [183-].

Remède contre le choléra. [1854].

Report of a special committee of the board of health of the city of Detroit, suggesting measures for the prevention of Asiatic cholera and the protection of the public health, also, containing plan and operations of a city dispensary. By order of the common council, 12, 1865. 8°. *Detroit*, 1865.

Report of the committee on cholera, Royal College of Physicians of London. Containing instructions for captains of merchant vessels. *London*, 1866.

Report of the council of hygiene and public health, etc. *See* **Harris** (E.)

Report of the Edinburgh board of health. [On the steps taken for checking the epidemic cholera if it should appear in the city. With directions for the guidance of the inhabitants. Also, a second report on the importance of cleanliness among the working classes, and fixing stations for the reception of patients.] 8°. [*n. p., n. d.*] L.

Report of the medical officer of health. Proposed action in the event of an outbreak of cholera occurring in this district, Hackney, London, July 18, 1872. 8°. [*n. p., n. d.*] L.

Report of the sanitary committee of the board of health of Philadelphia on the subject of the Asiatic cholera. 8°. *Philadelphia*, 1848. L.

Report on the common and model lodging houses of the metropolis, (with reference to epidemic cholera in 1854.) To the general board of health, Jan. 20, 1855. 8°. *London*, 1855. L.

Report to the international sanitary conference, of a commission from that body, to which were referred the questions relative to the origin, endemicity, transmissibility and propagation of Asiatic cholera. Translated by S. L. Abbot. 8°. *Boston*, 1867. L.

Report to the Rochdale board of guardians on disinfectants, &c., in connection with cholera. By Daniel Stone. 8°. *Manchester*, 1866. L.

Reports on the existing conditions of town and country, and their state of preparation against the invasion of cholera.
[Med. Times & Gaz., 1865, II, pp. 479-481, 503-504, 559-560; 1866, I, pp. 128-129.]

Return to an address of the House of Lords, dated March 9th, 1854, for copy of a memorandum addressed to Viscount Palmerston, secretary of state for the home department, on behalf of a deputation which waited on him on the 27th February 1854, for the purpose of urging the necessity of preparations against the apprehended return of cholera. (1854.) fol. [*n. p., n. d.*] L.

Rules and regulations proposed by the board of health for the purpose of preventing the introduction and spreading of the disease called cholera morbus, with the most approved treatment. To which are added a warning to the British public against the alarming approach of the Indian cholera, by Sir Gilbert Blane, and the history of the epidemic cholera of India, from its first appearance in the year 1817, to 1831, and the dreadful ravages it has committed, with the dates of its first appearance in the different provinces. 8°. *London*, 1831. L.

Rules regarding the measures to be adopted on the outbreak of cholera or appearance of small-pox.
[Sixth Ann. Rept. San. Commr. with the Govt. of India, 1869, app. C, pp. 243-263; *also, in* Rept. on Measures adopted for the San. Impt. in India from June, 1870, to June, 1871, London, 1871, pp. 203-216.]

Sammlung badischer Verordnungen über die Cholera. *See* **Cholera-Büchlein.**

Sammlung der Sanitäts-Verordnungen. Als Fortsetzung der von Ferro'schen, v. Guldner'schen, und Böhm'schen Sammlung (die Verordnungen von den Jahren 1830-1832, nebst einer Darstellung der Brechdurchfalls-Epidemie) herausgegeben. 8°. *Wien*, 1832.

Sammlung der von den Regierungen der deutschen Bundesstaaten ergangenen Verordnungen und Instructionen wegen Verhütung und Behandlung der asiatischen Brechruhr (Cholera-Morbus). 4°. *Frankfurt a. M.*, 1831.

Sammlung kaiserlich russischer Verordnungen zur Verhütung und Unterdrückung der Cholera. Aus dem Russischen übersetzt von J. A. E. Schmidt. Nebst einer Vorrede von Joh. Christ. Aug. Clarus. 8°. *Leipzig*, 1831. L.

Sanitary and preventive measures, or what may be done by the public in anticipation of the cholera. By the sanitary committee of the board of health of Philadelphia. 12°. *Philadelphia*, 1866. L.

——— The same. 8°. *Philadelphia*, 1866. L.

Sanitary regulations and the cholera.
[Lancet, 1832, II, a. s., p. 316.]

Sanitary suggestions of the advisory committee of physicians to the board of health of the city of Albany, in regard

Sanitary, *etc.*—continued.

to measures for preventing the spread of Asiatic cholera. Transmitted to the board, April 18th 1866. 8°. *Albany*, 1866. L.

Schlusssätze des aerztlichen Vereines zu München, Cholera-Prophylaxis betreffend.

[AERZTL. Intell.-Bl., 1875, XXII, pp. 221-222.]

Schutz- und Rettungs-Schild, oder die hauptsächlichen Vorsichtsmassregeln gegen die Cholera, und die wirksamste Heilungsart nach geschehener Ansteckung bis zur Ankunft ärztlicher Hülfe. fol. [*Stuttgart*, 1831.]

Schutzwehr, auf Erfahrung gegründet, gegen die Cholera. Mittheilungen über deren Kennzeichen, Verhütung und Heilung, aus den neuesten Berichten der Aerzte Ewertz, Krajewski, Sinogowitz u. m. A. Als Anhang: Beschreibung und Abbildung eines einfachen Dampfbades und eines transportabeln russischen Dampfbades, als Schutzmittel gegen die Cholera. 8°. *Landberg*, 1831.

Second report on the prevention and treatment of spasmodic cholera, most respectfully submitted to his excellency the lord lieutenant of Ireland, by the general board of health, in Dublin. 8°. *Dublin*, 1831. L.

Secretaria de estado en el despacho de beneficencia: [Opinion de la comision nombrada por el señor decano de la facultad de medicina para informar á cerca de las medidas que deben adoptarsi con el fin de impedir la invasion del cólera asiático en nuestra territorio (Peru).]

[GAC. med. de Lima, 1866, XI, pp. 66-68.]

Skrivelser angaaende Cholera-Foranstaltninger.

[SUPPLEMENT. til Bibl. for Laeger, Kjöbenhavn, 1865, pp. 338-354.]

Special hospitals for cholera.

[PROV. Med. & Surg. Jour., 1848, pp. 518-519.]

Suggestions in connection with the threatened approach of cholera, reprinted from the report of the working committee of the Dublin Sanitary Association. 12°. *Dublin*, 1873. L.

Sundhedscollegiets Rundskrivelse til Physici angaaende Cholera.

[UGESKR. for Laeger, Copenhagen, 1851, XIV, pp. 222-224.]

Sundhedskollegiet og Cholera.

[BIBL. for Laeger, Copenhagen, 1866, VI, pp. 230-231.]

Traité sur le choléra-morbus et les moyens de s'en préserver, publié par le [illegible]. 8°. *Paris*, 1831.

Ueber das ärztliche Verfahren gegen die orientalische Cholera. Amtlich mitgetheilt. 8°. *München*, 1831.

Ueber den Werth von Massregeln gegen Epidemien.

[WIEN. med. Wochenschr., 1874, XXIV, pp. 736-737.]

Ueber Desinfection, als Massregel gegen die Verbreitung der Cholera.

[WIEN. med. Wochenschr., 1866, p. 1171.]

Ueber Ursprung und Verbreitungsart der Cholera. Commissionsbericht der internationalen Sanitäts-Conferenz. *München*, 1867.

Uebersicht der hauptsächlichsten Vorsichtsmassregeln gegen die asiatische Cholera und die wirksamste Heilmethode nach erfolgter Ansteckung bis zur Ankunft eines Arztes. (Publicirt mit der Approbation der königlich-preussischen Prüfungs-Behörde.) 4. *Hannover*, 1831.

Uebersichts-Tabelle der hauptsächlichsten Vorsichtsmassregeln gegen die Cholera, etc. fol. *Stuttgart*, 1831.

Unentbehrlicher Rathgeber für Alle, welche sich durch zweckmässige Diät in Bezug auf Speisen und Getränke vor der asiatischen Cholera schützen wollen. Von einem praktischen Arzte. 8°. *Berlin, Stettin und Elbing*, 1831.

Untersuchungsplan zur Erforschung der Ursachen der Cholera und deren Verhütung. Denkschrift, verfasst im Auftrage des Reichskanzleramtes von der Choleracommission für das deutsche Reich.

[OESTERR. *Zeitschr. f. prakt. Heilk.* Wien, XIX, pp. 597-601, 617-619, 633-638, 649-654, 668, 681-682, 690-692, 704-705, 727-730.]

——— The same. 8°. *Berlin*, 1873.

Verhaltungs-Massregeln für Armee im Felde zur Zeit der Cholera.

[ALLG. militärärztl. Zeitg., Beilage zur "med. Presse", 1866, VII, pp. 310-312.]

Verhaltungsregeln für das Publikum in Beziehung auf die asiatische Brechruhr.

[MED. Correspondbl. des württemberg. ärztl. Vereins, 1836, VI, pp. 377-380, 385-387.]

Verhaltungsregeln für das Publikum in Bezug auf die asiatische Cholera. Königliches Medicinal-Collegium, Stuttgart.

[MED. Correspondbl. des württemberg. aerztl. Vereins, 1849, XIX, pp. 170–172.]

Verhaltungsregeln zur Verhütung des Ausbrechens der Cholera und während einer Cholera-Epidemie. 8°. *Leipzig*, 1867.

Verordening (De) der Gemeente Maastricht, van 4. Sept. 1866, op het Ontsmetten en Reinigen van Woningen bij het Ontstaan van epidemische Ziekten aldaar.

[NEDERL. Tijdschr. v. Geneesk., 1867, I, pp. 241–242.]

Verordnung des k. k. Statthalters in Niederösterreich, betreffend jene Massregeln, welche aus Anlass der Cholera-gefahr, beziehungsweise während des epidemischen Herrschens der Cholera durchzuführen sind.

[OESTERR. Zeitschr. f. prakt. Heilk., Wien, 1872, XVIII, pp. 742–744, 761–762, 781–785.]

Verordnung: die Bestrafung der Vergehungen gegen die zur Abwendung der Cholera erlassenen Vorschriften betreffend. Gesetz-Sammlung. I. Abtheilung. No. 33. Hannover, den 14ten Sept. 1831. 4°. [*n. p., n. d.*] L.

Verordnung die Cholera betreffend.

[ERSTER Jahresbericht des Landes-Med.-Colleg., über das Med.-Wesen im Königr. Sachsen, 1867, Dresden, 1869, pp. 123–128.]

Verslag der amsterdamsche Cholera-Commissie. 8°. *Amsterdam*, 1867.

Verslag van de Cholera-Behandeling in de Fabriek der Heeren Previnaire en Co. te Haarlem.

[NEDERL. Tijdschr. v. Geneesk., 1867, II, pp. 366–373.]

Verslagen van de Vereeniging tot Verbetering der Volksgezondheid, opgericht te Utrecht gedurende de Cholera-Epidemie in 1866. 2 v. 8°. *Utrecht*, 1867–74. L.

Verwahrungsmittel vor, und Verwahrungsweise bey dem Befallen der Cholera morbus. 8°. *Wien*, 1831.

Voorbehoedende Maatregelen tegen de Cholera.

[GENEESK. Courant, Tiel, 1853, No. 38.]

Voorbehoeding tegen te Cholera.

[GENEESK. Courant, Tiel, 1854, No. 46.]

Vorbauungsmittel (Die sichersten) gegen die Brech-Ruhr (Cholera), etc. 8°. *Elberfeld*, 1831.

Vorschriften zur Verhütung der asiatischen Cholera. 4°. *Hannover*, 1831. L.

Vorsichts- und Verhaltungsregeln in Beziehung auf die ansteckende asiatische Cholera. Mitgetheilt von der königlich-ärztlichen Prüfungsbehörde. Hannover, den 31. Juli 1831. 4°. [*n. p., n. d.*] L.

Vorsichtsmassregeln (Schützende) und Heilart der Cholera-Morbus. [etc.] 8°. *Nordhausen*, 1831.

Vraag (Over de) wat moet men bij het Naderen der Cholera in het Werk stellen, om zich tegen die Ziekte te waarborgen; en welke Middelen moet men te baat nemen, bijaldien dezelve ons onverwacht mogt overvallen. 8°. *Weesp*, 1832.

Vremiennyia bolnitzy dla cholernych &c.

[MEDYTZYNSKIY Viestnik, St. Petersburg, 1866, 6th year, No. 30, p. 355.]

Vysochayshcie povielenie o hlavnych osnovaniach dieiatelnosti St. Peterburgskaho gorodskaho obschestva po pryniatiu miery k preduprejdeniu cholery.

[MOSKOVSKAIA medytzynskaia gazeta, Moscow, 1866, No. 17, p. 149.]

What we did to stop the cholera.

[MED. Times & Gaz., 1853, VI, pp. 197–198.]

Why not stamp out the cholera?

[MED. Times & Gaz., 1866, II, pp. 146–147.]

Wichtige Nachricht, von zuverlässigen Schutzmitteln gegen die Cholera, etc. 8°. *Leipzig*, 1831.

Wie schützt man sich gegen die Cholera und was hat man am Bette eines Cholerakranken zu beobachten? 12°. *München*, 1866.

Zehn (Die) Vorsichtsmassregeln zur Abwendung der Cholera-Morbus. fol. *Straubing*, 1831.

Zum III. internationalen medizinischen Congress: die Quarantaine-Frage mit specieller Beziehung auf Cholera.

[ALLG. Wien. med. Zeitg., 1873, XVIII, pp. 463, 517–518, 530.]

Zur Desinfektionsfrage. [With regard to cholera.]

[WIEN. med. Wochenschr., 1867, pp. 1211–1212.]

Zur Prophylaxis der Cholera.

[ALLG. med. Central-Zeitung, 1865, XXXIV, pp. 821–822.]

IV.—PATHOLOGY AND PATHOLOGICAL ANATOMY.

Abeille. Quelques considérations sur un point de physiologie pathologique dans le choléra.
[Gaz. des hôp., 1849, pp. 495–496.]

Accordi (G.) Su quanto risposero i fratelli G. e G. Rensi, medici in Villafranca alle obiezioni mosse alla loro opinione sulla condizione patologica del colera-morbus.
[Gaz. med. ital. prov. Venete, 1866, IX, pp. 64–66.]

Ahronheim (A.) Das Choleratyphoid im Jahre 1866.
[Deutsche Klin., Berlin, 1867, XIX, pp. 317–321.]

Ainsworth (W.) Cholera not an epidemic.
[London Med. Gaz., 1832, IX, pp. 671–673.]

Alderson (J.) Pathology of cholera.
[Lancet, 1867, I, pp. 35–36.]

Allen (J. A.) Post mortem examination of a case of supposed spasmodic cholera, with remarks.
[Boston Med. & Surg. Jour., 1832, VI, pp. 367–369.]

Andral (M.) On the nature of the liquid secreted by the mucous membrane of the intestine in cholera.
[Lancet, 1848, II, p. 479.]

Andrew. Case of cholera—death—autopsy.
[Med. Times & Gaz., 1866, II, pp. 60–61.]

Anger (T.) Observation sur certains accidents convulsifs du choléra.
[Recueil des trav. Soc. méd. d'observ. de Paris, 1865–66, 2e s., I, pp. 245–250.]

Annesbury (W. B.) The pathology of cholera; its causes, symptoms, and treatment, &c.

Arrowsmith (R.) Digest of cholera reports proposed.
[London Med. Gaz., 1833, XI, pp. 44–46.]

Asbury (J. V.) A treatise on epidemic cholera; illustrating a new theory of the disease, on which the principles of a systematic mode of treatment are established. 8°. *London*, 1833. L.

Atkinson (J. C.) On an electrical phenomenon observed in cholera.
[Lancet, 1848, II, p. 504.]

——— Practical observations on epidemic cholera, and its identity with epidemic influenza. 32°. *London*, 1848.

——— The human mind under the influence of choleraic poison.
[Lancet, 1854, II, n. s., pp. 352–353.]

Auriac. Observations sur la mort des cholériques et les phénomènes vitaux observés sur le cadavre des cholériques.
[Gaz. méd. de Paris, 1836, IV, pp. 641–643.]

Auvert (A.) Læsiones intestinorum choleræ propriæ.
[Selecta praxis med.-chir., 2d ed., 1856, II, pp. 113–119, pl. 105–108.]

Ayre (J.) On the pathology of cholera.
[Lancet, 1848, II, pp. 527–529, 552–553, 583–585, 631–633.]

Ayres. Some points in the pathology of epidemic cholera.
[Med. Times & Gaz., 1856, XII, n. s., pp. 295–296.]

Bain (A.) Inquests in cases of death caused by cholera.
[Lancet, 1849, I, pp. 703–704.]

Bally (V.) Anatomie de la choladrée lymphatique ou hydrocholadrée.
[Mem. Acad. roy. de méd., 1846, XII, pp. 152–240.]

——— Études anatomiques sur l'hydrhémo choladrée, écoulement de l'eau du sang par le tube digestif. 8°. *Paris*, 1856.

Barbier (J. B. G.) Quelques considérations sur le choléra-morbus épidémique.
[Gaz. méd. de Paris, 1854, IX, 3e s, pp. 789–796.]

Barclay (A. W.) Altered condition of the blood not essential in cholera.
[Med. Times & Gaz., 1853, VII, n. s., p. 486.]

Barlow (F.) Note on Dr. Davy's observations on the amount of carbonic acid expired in cholera, and on animal putrefaction.
[London Med. Gaz., 1850, XLVI, pp. 289–290.]

Barlow (G. H.) Remarks on the pathology of cholera.
[Med. Times & Gaz., 1866, II, pp. 83–85, 113–115, 137–139.]

Barlow (W. F.) On the muscular contractions which are occasionally to be observed after death from cholera.
[London Med. Gaz., 1849, XLIV, pp. 798–803; 1850, XLV, pp. 184–192; *also*, A supplement to . . . . 1850, XLVI, pp. 654–660, 739–749; *also*, in Dublin Med. Press, 1849, XXII, p. 294.]

——— The same. 8°. 1849. L.

——— The same. 8°. 1850. L.

——— Observation of the condition of the body after death from cholera.
[London Med. Gaz., 1850, XLVI, pp. 10–21, 53–61, 144–145.]

——— The same. 8°. *London*, 1850. L.

Barnard (G.) Cholera maligna is a specific acute inflammation of the mucous tissue of the small intestines. 8°. *Calcutta*, 1869.

Barrie (C.) Relation über die Natur der asiatischen Cholera, nach amtlichen Bestätigungen, praktischen Wahrnehmungen und zuverläseigen Erfahrungen, wie diese Krankheit abzuwehren, unschädlich zu machen und der Stoff derselben zu vernichten sei (französisch und deutsch). 4°. *Hamburg*, 1832.

Barthez. Ueber die Cholera bei den Kindern, gestützt auf Beobachtungen in der klinischen Abtheilung des . . . im St. Eugenien-Hospitale zu Paris, von Dr. Fernet.

[Journ. f. Kinderkrkhtn., Erlangen, 1866, xlvii, pp. 208–226.]

Bartholow. Observations, pathological and experimental, upon cholera.

[Cinc. Lancet & Observ., 1866, ix, pp. 652–664.]

Bascome (E.) On Dr. Copland's views on cholera.

[Med. Times, 1849, xx, p. 345.]

Basham. Case of cholera—death—autopsy.

[Med. Times & Gaz., 1866, ii, p. 118.]

Baxire (V.) Is dysentery antagonistic to cholera?

[Lancet, 1862, ii, n. s., p. 352.]

Beale (L. S.) Desquamation of epithelium in cholera.

[Med. Times & Gaz., 1866, ii, p. 378.]

—— Microscopical researches on the cholera.

[Med. Times & Gaz., 1866, ii, pp. 109–110, 166–167, 310–311, 336–337, 366–367, 389–391; 1867, i, pp. 1–2, 1 pl.]

Beaunez (L. de). Réflexions sur la nature du choléra-morbus, ainsi que sur sa propagation.

[Rec. de mém. de méd., chir. et pharm. mil., 1831, xxxi, pp. 44–65.]

Beauregard. Nouvelles recherches sur la nature et le traitement du choléra épidémique.

[Comptes rend. hebd. d. séances de l'Acad. d. sci., Paris, 1854, xxxvii, pp. 862–863.]

Becquerel (A.) Note relative à quelques analyses du sang, des vomissements, des évacuations alvines et des urines des cholériques.

[Arch. gén. de méd., Paris, 1849, iii, pp. 192–206.]

Begbie (J. W.) Observations on the urine in cholera.

[Month. Jour. of Med. Sci., 1849, iii, n. s., pp. 1207–1213.]

Begbie (J. W.)—continued.

—— The same. 8°. *Edinburgh*, 1849. L.

Bell (C. W.) Lecture on the nature and treatment of cholera, considered with reference to its analogy with congestive agues of quotidian type.

[Prov. Med. & Surg. Jour., 1848, pp. 645–654, 673–681, 701–707.]

—— On the relation of cholera to malarial fever.

[Month. Retrospect of the Med. Sci., 1849, pp. 25–27.]

Belon. Note sur le choléra-morbus; considérations physiologiques et pathologiques; moyens préservatifs.

[Comptes rend. hebd. d. séances d. l'Acad. d. sci., Paris, 1854, xxxvii, pp. 903–904.]

Benvenisti. Sulle leggi che governano la produzione delle cellule proteiche intra ed extra-vascolari, dei miasmi e dei contagi. *Padova*, 1865.

Besnier (J.) Du mode et du rôle de l'asphyxie chez les cholériques.

[Archiv. gén. de méd., Paris, 1866, ii, pp. 257–273, 454–470.]

Biaggi (L.) Risultamenti necroscopici osservati nei cholerosi di Padova.

[Omodei, Ann. un. di med., 1849, cxxxi, pp. 105–135.]

Biermann. Wie unterscheidet sich die gewöhnliche Herbstbrechruhr (europäische Cholera) von der indischen Cholera morbus? 8°. *Braunschweig*, 1831. L.

Bird (J.) Contributions to the pathology and treatment of cholera.

[London Jour. of Med., 1849, i, pp. 313–321, 715–724, 829–844.]

Bischoff (E.) Ueber die Ausscheidung der Phosphorsäure durch den Thierkörper.

[Ztschr. f. Biologie, München, 1867, iii, pp. 309–323.]

Blandet. Les entérozoaires du choléra.

[Courr. (Le) méd., Paris, 1874, xxiv, pp. 12–13.]

Bodington (G.) On the theory of cholera, and the treatment.

[Brit. Med. Jour., 1866, ii, pp. 368–369.]

Boehm (L.) Die kranke Darmschleimhaut in der asiatischen Cholera mikroskopisch untersucht. 8°. *Berlin*, 1838. L.

Boera. De los envenenamientos en general y del cólera en particular.

[Tribuna méd., Paris, 1873, i, pp. 25–26.]

Bonnet. De la nature et du siége du choléra-morbus.

[L'Union méd., 1849, iii, pp. 233–235.]

Boret (J. de). * Le choléra-morbus n'est pas une gastro-entérite. 4°. *Paris*, 1832. L.

Borsatti (J.) Dell'ultimo stadio del cholera asiatico, o stadio di morte apparente e sulle misure da adottarsi per i cadaveri dei cholerosi.

[Gaz. med. ital. prov. Venete, 1873, XVI, pp. 272–273.]

Botkin. Zur pathologischen Histologie der Leber bei Cholera und zur Lehre von der Lebercirrhose.

[Berl. klin. Wochenschr., 1872, IX, p. 261.]

Bouchut. Note sur les bruits du cœur dans le choléra.

[Gaz. méd. de Paris, 1849, IV, 3e s., p. 437; *also, in* Mem. Soc. de biol., 1849, I, pp. 8–11.]

——— Sur les embolies capillaires et les infarctus hémorrhagiques du cholera.

[Gaz. des hôp., 1873, p. 1035.]

Bourgogne. De l'identité du choléra asiatique et des fièvres paludéennes pernicieuses, ou réponse aux objections qui tendent à nier cette identité, suivies de quelques observations à l'appui du traitement abortif du choléra, selon la méthode décrite par l'auteur dans sa lettre à M. Bouillaud.

[Jour. de méd., de chir. et pharmacol., Bruxelles, 1855, XXI, pp. 409–421.]

Bourgogne, *fils.* Examen critique du rapport de M. le docteur Hérard et des discussions soulevées à l'Académie de Paris, à propos de l'identité du choléra asiatique avec certaines fièvres paludéennes pernicieuses et de l'action thérapeutique du tannate de quinine. Concours du prix Barbier en 1871.

[Jour. de méd., de chir. et pharmacol., 1872, LV, pp. 10–20, 107–114, 205–213, 285–292, 380–392, 474–486; 1873, LVI, pp. 42–47, 130–135, 228–235, 418–425; LVII, pp. 125–133, 309–315, 390, 515–525; 1874, LVIII, pp. 224–236, 433–439; LIX, pp. 116–127, 220–232, 317–325.]

Bourgogne, *père.* Examen critique du mémoire de M. Libermann, touchant la non-identité du choléra asiatique avec les fièvres cholériformes qui règnent dans cette contrée de l'Inde.

[Jour. de méd., de chir. et pharmacol., Bruxelles, 1864, XXXVIII, pp. 351–360, 549–558; 1864, XXXIX, pp. 3–22, 115–123, 205–215, 320–337, 428–441, 500–528; 1865, XL, pp. 135–145.]

Boursier. Quelques mots sur la coïncidence de la suette et du choléra en 1849.

[L'Union méd., 1849, III, pp. 353–354, 358–359.]

Boussiron (B.) * III. Quels sont les caractères du sang dans le cholera asiatique? IV. . . . [etc.] 4°. *Paris,* 1844. L.

Boutieller. [Lesions of intestine after death from cholera.]

[Bull. Soc. anat., Paris 1849, XXIV, pp. 98–99.]

Bouvier. Choléra; gangrène du gros intestine; ulcérations succédantes à la chute des escarres.

[Bull. de l'Acad. nat. de méd., 1848–49, XIV, pp. 751–753.]

Bowen (W. S.) On the general and previous post-mortem appearances of the cholera.

[N. Y. Jour. of Med., 1850, IV, pp. 193–196.]

Braun. Ueber die Erscheinungen bei den Leichen der an Cholera Verstorbenen.

[Vereinte deutsche Zeitschr. f. d. Staats-Arzneikunde, 1850, VII, n. F., pp. 374–375.]

Brechemier (F.-E.-N.) * Des [illegible] anatomiques du choléra. 4°. *Paris,* 1852. L.

Brittan (F.) Report of a series of microscopical investigations on the pathology of cholera.

[London Med. Gaz., 1849, XLIV, pp. 530–542; 2 tables; *also,* reprint in 8°. London, 1849.]

Brocard (J. L.) Nouvelle théorie sur le choléra-morbus. Moyens préservatifs. 8°. *Paris,* 1855.

Brochin. De la période prodromique du choléra.

[Gaz. des hôp., 1854, p. 445.]

——— De l'absorption dans la période algide du choléra.

[Gaz. des hôp., 1855, pp. 413–414.]

Broussais. Leçons sur le choléra.

[Gaz. des hôp., 1832, VI, pp. 93–97, 105–107, 111; *see, also, under* General Treatises, 1832.]

Brown-Séquard. Tremblement des [illegible] cholériques après la mort.

[Mém. Soc. de biologie, 1849, I, p. 81.]

Bruberger (M.) Chemish-mikroskopische Beobachtungen aus dem städtischen Cholera-Lazareth Nro. III in Berlin. Erbrochenes und Dejectionen.

[Virchow's Archiv, 1867, XXXVIII, pp. 294–303, 4 tables.]

Bruberger (M. E. R.) * Studien über Cholera-Ausscheidungen. 8°. *Berlin,* 1867. C.

Buhl (L.) Ueber das Vorkommen von Cylinderepithel in den Cholera-Stühlen.

[Zeitschr. f. Biolog., München, 1867, III, pp. 256–257.]

Bullar (J.) On epithelial cells occurring in cholera.

[Brit. Med. Jour., 1866, II, p. 301.]

Bullen (D. B.) Recent variations in the type of cholera.

[London Med. Gaz., 1833, XI, pp. 84–85.]

Burdach (E.) Pathologisch-anatomische Bemerkungen in Betreff der Cholera.

[Verhand. d. physik.-med. Gesell. zu Würzburg über die Cholera, 1832, pp. 294–314.]

Burtz. Witterungs- und Krankheits-Constitution in Berlin während des Monats August 1853. Cholera (in ihrer eigenthümlichen schweren Form).
[MED. Zeitg., 1853, p. 168.]

Busk (G.) The uredo and the microscopical appearances in choleraic discharges.
[LONDON Med. Gaz., 1849, XLIV, pp. 733–734.]

Caldwell (J. J.) Comparative pathology of cholera, yellow fever, and malignant fever, or pernicious malarial fever.
[MED. & Surg. Reporter, 1873, XXIX, pp. 163–165.]

Carville (C.-P.) * Des lésions cadavériques du choléra. 4°. *Paris*, 1849. L.

Charcot. Sur la température du rectum dans le choléra asiatique.
[GAZ. méd. de Paris, 1866, XXI, pp. 185–188.]

Chauffard. Note sur quelques états morbides spéciaux observés durant le règne des épidémies de choléra, et en particulier sur la diarrhée dite prémonitoire.
[REVUE de thérap. méd.-chir., Paris, 1866, XIV, pp. 5–8, 31–34; *also, in* BULL. et mém. Soc. méd. des hôp. de Paris, 1866, II, pp. 204–215.]

Chevers *and* **Banerjee** (R. M.) Report of an enquiry into the conditions, during life, of the liver and kidneys in Asiatic cholera, with especial reference to the management of the stage of collapse and to the prevention and treatment of the cholo-uræmic complication of the reaction stage of cholera.
[INDIAN Med. Gaz., 1875, X, pp. 90–94.]

Christie (A. T.) On the autopsy of epidemic cholera.
[JAMAICA Phys. Jour., 1834, I, pp. 10–17.]

Ciaccari (C.) Sulla patogenesi del cholera-morbus asiatico. 8°. *Palermo*, 1865. S. C.

Clanny (W. R.) Case of cholera at Sunderland, with an analysis of the blood taken from the patient.
[LANCET, 1831–32, I, pp. 505–508.]

——— Composition of healthy and of cholera blood.
[LANCET, 1831–32, II, pp. 232–234.]

——— Gases in the fluids ejected in a case of malignant cholera.
[LANCET, 1835, I, pp. 313–314.]

Clark (B.) On the analogy between the gripes in horses and the epidemic cholera.
[LONDON Med. Gaz., 1833, XI, pp. 111–115, 513–515.]

Clegg (W.) Premonitory diarrhœa in cholera.
[LANCET, 1858, I, n. s., pp. 21–22.]

Cockle (J.) Thoughts on the present theories of the algide stage of cholera. *London*, 1866.

——— The influence of the discharges and nervous shock on the collapse of cholera.
[DUBLIN Med. Press & Circ., 1867, III, pp. 181–183, 208–210.]

Cohen (L. A.) Studiën over de Cholera asiatica. De Cholera is eene miasmatisch-contagieuse Ziekte; de Gevolgen van die Daadzaak, en het Belang er van voor den Staat en zijne Bevolking.
[PRACT. Tijdschr. voor de Geneesk., Gorinchem, 1850, XXIX, pp. 7–19, 65–80.]

Contini (A.) Sommi corollarii relativi al cholera morbus asiatico.
[GAZ. med. it. Lomb., 1849, II, 2a s., pp. 398–399.]

Cooper (H.) The relation between cholera and the diarrhœa which accompanies it, and on the treatment of the latter disease.
[BRIT. Med. Jour., 1866, I, pp. 631–632.]

Corbin. Sur l'existence d'une pseudo-membrane blanche dans l'œsophage des cholériques.
[GAZ. méd. de Paris, 1849, IV, 3e s., p. 526.]

Cormack (J. R.) Notes on the pathology and treatment of cholera. 8°. *London*, 1854. L.

Cornevin (A. M. C. I.) * De la nature du choléra et des grandes épidémies. 4°. *Paris*, 1867. L.

Coster (J.) Du choléra asiatique, de son analogie avec les fièvres pernicieuses, et de la possibilité d'en prévenir l'accès. 3e éd. 8°. *Paris*, 1831–32, 1849.
[4e éd., 1865.]

Cowan (J. M.) Case of cholera, in which the blood was remarkably altered.
[MONTH. Jour. of Med. Sci., 1854, IX, 3e s., pp. 248–252, 1 plate.]

Cowdell (C.) Discovery of peculiar bodies in the perspiration of cholera.
[LONDON Med. Gaz., 1849, XLIV, p. 555.]

——— Miscroscopic bodies in cholera.
[LANCET, 1849, II, p. 360.]

——— Microscopical discoveries in cholera.
[PROV. Med. & Surg. Jour., 1848, pp. 586–587; 1849, pp. 559–560.]

Cox (W. J.) Premonitory diarrhœa in cholera.
[MED. Circular, 1857, XI, pp. 293–294.]

Coze. Sur la construction des conduits biliaires et lymphatiques chez les cholériques.
[COMPTES-RENDUS hebd. des séances de l'Acad. des sci., Paris, 1849, XXIX, pp. 457–458.]

——— Sur une lésion anatomo-pathologique observée dans les cadavres des cho-

Coze—continued.
lériques. (Extrait d'une lettre de M. Coze à M. Flourens.)
[COMPTES-RENDUS hebd. des séances de l'Acad. des sci., Paris, 1849, XXIX, pp. 388–390.]

Cruveilhier (J. P.) Anatomie pathologique du corps humain.
[14e livraison, pl. 1–5; 20e livraison, pl. 5–6; 38e livraison, pl. 4.]

Cunningham (D. D.) Microscopic examinations of air [of Northern India].
[NINTH Ann. Rept. San. Commissioner with the Govt. of India, 1872, app. A, pp. i–liv, xvi pl.]

Currie (J. S.) On the pathology of the congestion in malignant cholera, and the treatment of that disease.
[LANCET, 1849, I, n. s., pp. 583–584.]

Damaschino. De la diarrhée dite prémonitoire du choléra.
[BULL. et mém. de la Soc. méd. des hôp. de Paris, 1873, II, 2e s., p. 317.]

Danforth (J. N.) Note upon the results of microscopic examination of the choleraic discharges.
[AMER. Publ. Health Assn. Reports & Papers, N. Y., 1875, I, pp. 264–266.]

Davaine. Sur des animalcules infusoires trouvés dans les selles des malades atteints du choléra et d'autres affections.
[MÉM. de la Soc. de biol., 1849, I, pp. 129–130.]

Davey (J. G.) Pathology of fever and malignant cholera.
[LANCET, 1835–36, II, pp. 865–867.]

Dawson (J.) Extract from a dissertation on the theory of cholera asiatica epidemica.
[BOSTON Med. & Surg. Jour., 1849, XL, pp. 229–232.]

Debey. Die microscopischen Organismen in den Cholera-Dejectionen.
[DEUTSCHE Klinik, 1867, XIX, pp. 2, 13, 47.]

Debreyne. Théorie nouvelle du choléra épidémique, ou typhus d'Asie, avec un traitement curatif et prophylactique également nouveau.
[REVUE de thérap., Paris, 1854, II, pp. 253–260.]

Dechambre (A.) Non-absorption des médicaments dans le choléra.
[GAZ. hebd. de méd. et de chirurg., 1853–54, I, pp. 977–978.]

Decroix. Analogies entre le choléra et la peste bovine. (Ext. du Bulletin de la Soc. cent. de méd. vet.) 8°. *Paris*, 1872. L.

Delpech. Choléra-morbus d'Écosse. (Lettre adr. à M. le prof. Lizars.)
[GAZ. méd. de Paris, 1832, III, pp. 116–118.]

Dendy (W.) Pathology of cholera.
[LANCET, 1832–33, II, p. 626.]

Depasse (A.-M.) *Dissertation sur la nature du choléra-morbus épidémique. 4°. *Paris*, 1832. L.

Desiderio (A.) La colèra richiamata a principio dinamico.
[GIORN. venet. d. sc. med., 1852, V, pp. 161–175, 391–425, 763–804; 1853, I, 2a s., pp. 365–414, 762; II, pp. 703–728; 1854, III, pp. 421–457, 702.]

Desmarres d'Évereux (L. A.) *L'Identité de nature du choléra-morbus épidémique. II. . . . [etc.] 4°. *Paris*, 1839. L.

Dick (R.) A few observations on cholera.
[LANCET, 1849, I, n. s., pp. 665–666.]

——— Some observations on the nature of cholera.
[LONDON Med. Gaz., 1849, XLIV, p. 312.]

Dieffenbach (J. F.) Physiologisch-chirurgische Beobachtungen bei Cholera-Kranken. 2. Aufl. 8°. *Güstrow*, 1834. L.
[1st ed., Berlin, 1832.]

Dowler (B.) Contributions to the pathological anatomy and natural history of cholera.
[NEW ORLEANS Med. & Surg. Jour., 1850, VII, pp. 194–200.]

Doyère (L.) Observations sur la respiration et la température des cholériques.
[COMPTES-RENDUS hebd. des séances de l'Acad. des sci., Paris, 1849, XXIX, pp. 454–456.]

——— Sur la sueur visqueuse des cholériques.
[COMPTES-RENDUS hebd. des séances de l'Acad. des sci., Paris, 1849, XXIX, pp. 221–222.]

——— Mémoire sur la respiration et la chaleur humaines dans le choléra.
[MONIT. des hôp., 1854, II, pp. 97.]

——— The same. [Travail auquel l'Acad. des sci. a décerné un prix de 5000 francs.] 8°. *Paris*, 1863. L.

Drasche (A.) Über den Harnstoff-Beschlag der Haut und Schleimhäute bei Cholera-Typhoide.
[ZEITSCHRIFT d. k. k. Ges. der Aerzte zu Wien, 1856, pp. 161–180.]

——— Ueber die Muskel-Contractionen an Choleraleichen.
[ALLG. Wien. med. Zeitg., 1868, XII, pp. 349–351, 357–358, 365–366.]

——— Untersuchungen über das Verhalten des Körpergewichtes bei der Cholera.
[ALLG. Wien. med. Zeitg., 1867, XII, pp. 367–368, 379–380, 387–388.]

Dubini (A.) Rendiconto dell'andamento della Casa di Soccorso detta della carità cristiana di S. Nazzaro in Milano, ed osserva-

Dubini (A.)—continued.
zione intorno alla condizione dei colerosi ivi accolti, alla cura in essi praticata, alla specialità dei sintomi osservati ed ai risultamenti necroscopici notati nei decessi per colera in diversi stadii della malattia.
[Gaz. med. it. Lomb., Milano, 1850, I, 3a s., pp. 169–175, 181–185, 189–191.]

Dubourg. Doctrine de M. Broussais sur le choléra-morbus.
[Jour. univ. et hebd. de méd. et de chir. prat., 1832, VII, pp. 67–77.]

Dubun-Peyre-Longue. Sur la coïncidence et les analogies de la suette épidémique et du choléra.
[Trans. méd., Jour. de méd. prat., Paris, 1832, IX, pp. 197–210.]

Dunaer (V. E.) Temperature in cholera patients, its significance for prognosis and treatment. Communicated to the Medical Society of Kasan, 1871. 8°. [Extract.] L.
[Russian text.]

Elsässer. Beobachtung eines Brechdurchfalls mit gallertartiger Magen- und Darmerweichung.
[Med. Correspbl. d. württ. aerztl. Ver., Stuttgart, 1832, pp. 160–161.]

——— Sections-Befund an Cholera-Leichen aus dem Hauptbericht des .... über "die epidemische Cholera nach eigenen, aus Auftrag der königlich württembergischen Regierung angestellten Beobachtungen in Wien und Mähren, besonders in Brünn."
[Med. Correspbl. d. württ. aerztl. Ver., Stuttgart, 1832, pp. 23–24, 29–32.]

Endres (C.) Aphoristische Bemerkungen zur Pathologie der asiatischen Brechruhr. 8°. *Ulm*, 1837.

England (W.) On the coldness of the tongue in malignant cholera.
[London Med. Gaz., 1832, X, pp. 81–82.]

Erman (F.) Beobachtungen über Temperaturverhältnisse in der Cholera. (8 cases.)
[Berl. klin. Wochenschr., 1873, X, pp. 397, 412.]

——— Thermometric observations in cholera.
[Richmond & Louisville Med. Jour., 1873, XVI, pp. 599–606.]

Eulenburg (A.) Ueber die Circulationsstörungen im asphyctischen Stadium der Cholera.
[Wien. med. Wochenschr., 1866, pp. 1433–1436, 1449–1451.]

Eve (E. A.) An essay in answer to the question "What is the pathology and treatment of cholera asphyxia?" Read before the Medical Society of Augusta.
[Southern Med. & Surg. Jour., 1839, III, pp. 393–400.]

Falkenthal (C. H. F.) *Nonnulla ad choleræ morbi pathologiam et therapiam. 4°. *Berolini* [1832]. L.

Fallot (L.) Coup-d'œil sur le cholera, où on traite la question le choléra est-il une gastro-entérite? 8°. *Paris*, 1832. L.

Farquhar (T.) What is cholera collapse?
[Med. Times & Gaz., 1870, II, pp. 117–118.]

Filhos. Choléra avec plaques gangreneuses dans les intestins.
[Gaz. des hôp., Paris, 1832, VI, pp. 517–518.]

Férrès (A.) Du choléra, d'après la doctrine de Broussais. 12°. *Lyon*, 1856.

Fickel (C. W.) Versuch einer auf physiologischen Untersuchungen gestützten Darstellung des Wesens der Cholera, etc. Für Aerzte und Nichtärzte. 8°. *Zwickau*, 1831.

Fickel (W.) Die epidemische Cholera, oder Eklyse des Nervus vagus, ihrer Natur nach dargestellt. 8°. *Dresden*, 1861. L.

Fischer (O.) Die Choleroiden und ihr Verhältniss zur Cholera asiatica.
[Deutsche Klinik, 1851, III, pp. 193–196, 201–204.]

Flamm (J. K.) Cholera und Vergiftung.
[Aerztl. Intell.-Bl., 1857, IV, p. 73.]

Flora (D. W.) Remarks on Dr. Wright's theory of cholera.
[Chicago Med. Examiner, 1866, VII, pp. 470–475.]

Ford (W. H.) The pathology of passive congestion, and its relation to Asiatic cholera; an inductive research, read by special appointment before the Medical Society of South Carolina, May, 1866.
[New Orleans Jour. of Med., 1868, XXI, pp. 1–29, 223–252.]

Fox (W.) Report on the pathological appearances observed in the stomach and intestines of patients dying of cholera at the University College hospital during the autumn of 1866.
[Trans. Pathol. Soc., London, 1867, XVIII, pp. 88–90, 1 pl.

Franceschi (G.) Teoria induttiva del periodo algido colerico. 8°. *Macerata*, 1836.

Freke (H.) The pathology of cholera.
[London Med. Gaz., 1848, XLIII, p. 1051; *also*, in Med. Times, 1849, XIX, p. 648.]

French (J. G.) On vomiting, as antagonistic to syncope, with remarks on cholera.
[LONDON Med. Gaz., 1849, XLIX, pp. 278-280.]

——— On the physiological conditions which avert a fatal result in cholera.
[MED. Times & Gaz., 1866, II, p. 56.]

——— On the probable cause of the post-mortem muscular contractions in cholera; and on the philosophical treatment of that disease.
[MED. Times & Gaz., 1871, I, pp. 668-669.]

Friedländer (M.) Ueber den Zutritt der Cholera zu fieberhaften Krankheiten. Nebst einer Curventabelle.
[ARCHIV der Heilkunde, Leipzig, 1867, pp. 439-448.]

Furlonge (J.) What is cholera?
[LANCET, 1854, II, p. e., p. 148.]

Gairdner (W. T.) On the pathological anotomy of cholera.
[MONTH. Jour. of Med. Sci., 1848-49, IX, pp. 901-908.]

——— Reply to Dr. Beale, desquamation of epithelium in cholera.
[MED. Times & Gaz., 1866, II, p. 392.]

Galter (H.) Peyer's glands enlarged in cholera.
[LONDON Med. Gaz., 1832, X, pp. 53-54.]

Garrod (A. B.) On the pathological condition of the blood in cholera.
[LONDON Jour. of Med., 1849, I, pp. 409-437.]

Gaskell (S.) Notes on the mode in which death takes place in cholera.
[EDINB. Med. & Surg. Jour., 1833, XL, p. 94.]

Gfrörer. Krankheitsgeschichte und Sektionsbericht über einen unter den Erscheinungen der Cholera aufgetretenen und schnell tödtlichen Krankheitsfall.
[MED. Correspbl. des württemberg. aerztl. Vereins, 1854, XXIV, pp. 292-295.]

Gibon (J. L. C.) *I. Des caractères anatomiques du choléra-morbus épidémique. II. . . . [etc.] 4°. *Paris*, 1839. L.

Goldbaum (M.) Der Transsudationsprocess in der Cholera.
[BERL. klin. Wochenschr., 1873, X, p. 548.]

Gottheil (S.) *De emetodiarrhoea epidemica anni MDCCCXXXVII nonnulla. 8°. *Berolini* [1838]. L.

Gouraud (H.) Réflexions sur la nature . . . . du choléra-morbus. 8°. *Paris*, 1831.

Gower. Cases simulating malignant cholera.
[LANCET, 1833, II, p. 721.]

Grandesso-Silvestri (O.) Annotazioni sull'esame critico fatto dal dott. G. A. Cordi all'opinione del Biaggi sul morbo cholera.
[GAZ. med. ital. prov. Venete, 1866, XI, pp. 175-177.]

Graux. Communication sur le choléra épidémique; résumé analytique. [Discussion.] Rapport de M. Raikem.
[BULL. de l'Acad. roy. de méd. de Belgique, 1853-54, XIII, pp. 237-289, 475-476.]

Green. [Letter on the pathology of cholera.]
[ST. LOUIS Med. & Surg. Jour., 1857, IV, pp. 272-274.]

Green (P. H.) Observations on some points connected with the anatomical pathology of the malignant cholera.
[LANCET, 1831-32, II, pp. 83-84.]

Greenhow. Case of cholera—death—autopsy.
[MED. Times & Gaz., 1866, II, pp. 223-224.]

Greser (J. F.) Hypothese von der Natur der Cholera morbus. 8°. Nürnberg, 1831.

Gressin (P. A.) Étude sur le choléra particulièrement au point de vue de l'épidémie de 1873. 4°. *Paris*, 1874.

Griffith (J. W.) Remarks on the so-called cholera bodies.
[LONDON Med. Gaz., 1849, XLIV, pp. 1094-1095.]

Grünberg (L.) Theorie der orientalischen Cholera oder versuchte Beantwortung der von der russischen Regierung aufgegebenen Frage über diese Krankheit. 8°. *Berlin*, 1836. L.

Gubler. Coloration bleue des urines cholériques.
[MÉM. Soc. de biol., 1849, I, p. 103;

——— Glycosurie dans le choléra.
[L'ABEILLE méd., 1867, XXIV, pp. 17-19;

——— Glycosurie transitoire pendant la période de réaction du choléra.
[BULL. et mém. Soc. méd. des hôp. de Paris, 1867, IV, pp. 267-268.]

Günsburg (F.) Vergleichende Uebersicht des Leichenbefunds an den während der beiden Hauptabschnitte der Cholera-Epidemie zu Breslau 1848-1849 Verstorbenen. Amtlicher Bericht.
[ZEITSCHR. f. klin. Med., 1850, I, pp. 433-467.]

Guerin (J.) Mémoire sur la choléra considérée comme période d'incubation du choléra-morbus.
[GAZ. méd. de Paris, 1837, V, pp. 449-454.]

——— The same. 8°. *Paris*, 1837. L.

Guerin (J.)—continued.

——— Nouvelles observations sur la période prodromique ou prémonitoire du choléra-morbus.
[GAZ. des hôp., 1865, p. 478.]

Güterbock (L.) Die Temperaturverhältnisse in der Cholera.
[VIRCHOW's Archiv, 1867, XXXVIII, pp. 30–64.]

Gull (W. W.) Report on the morbid anatomy, pathology, and treatment of epidemic cholera. In reports of Royal College of Physicians. 8°. *London*, 1854. L.

Guttmann (P.) Zur Pathologie der Cholera.
[ALLG. Wien. med. Zeitg., 1866, XI, pp. 310–311, 318–319; *also, in* BERL. klin. Wochenschr., 1866, III, pp. 369–372.]

Guttstadt (A.) * De signis anatomicis in epidemia cholerae asiaticae Berolini anno [1866] orta observatis. 8°. *Berolini*, 1866. L.

——— Ueber den anatomischen Character der Cholera-Epidemie zu Berlin im Jahre 1866. (5 cases.)
[DEUTSCHE Klin., 1867, XIX, pp. 243, 255, 267, 275.]

Guyon (M.) Quelques expériences négatives au point de vue de la transmission du choléra de l'homme aux animaux, faites à l'hôpital des cholériques de Varsovie en 1831.
[GAZ. méd. de Paris, 1866, XXI, pp. 13–15.]

——— Quelques observations tendant à établir l'identité du choléra avec des épizooties concomitantes.
[GAZ. méd. de Paris, 1866, XXI, pp. 31–35.]

Habershon. Great enlargement of the aggregate and solitary glands of the intestine, in a case of Asiatic cholera.
[TRANS. Path. Soc. of London, 1853–54, V, pp. 169–170.]

Hallier (E.) Kultur eines Pilzes aus den Cholera-Dejectionen. Vorläufige Mittheilung.
[CENTRALBL. f. die med. Wissensch., 1867, pp. 465–467.]

——— Ueber einen in den Cholera-Dejektionen aufgefundenen Pilz.
[WIEN. med. Presse, 1867, VIII, pp. 657–659.]

Hanlo (J.) Over de Nosologie der Cholera.
[NEDERL. Tijdschr. v. Geneesk., 1867, I, pp. 226–229.]

Hawkins. Identity of the Russian and the Indian cholera. Distinction between the common bilious cholera and the spasmodic cholera.
[BOSTON Med. & Surg. Jour., 1831, V, pp. 220–222.]

Hayden. Morbid specimens taken from patients who had died of cholera.
[DUBLIN Quar. Jour. of Med. Sci., 1867, XLIII, pp. 190–193.]

Hekmeijer (F. C.) De Rinderpest met de Cholera vergeleken.
[GENEESK. Courant, Tiel, 1867, No. 3.]

Herapath (T. J.) An account of certain chemical and microscopical researches on blood, excretions, and breath in cholera.
[LONDON Med. Gaz., 1849, XLIV, pp. 838–846.]

——— Detection of carbonate of ammonia in the evacuations of cholera.
[LONDON Med. Gaz., 1849, XLIV, pp. 638–639.]

Hermann. Examen des expériences de M. . . . , sur le sang cholérique et non cholérique.
[GAZ. méd. de Paris, 1832, III, pp. 346–347.]

——— Sur les altérations du sang dans le choléra.
[GAZ. méd. de Paris, 1832, III, pp. 810–811.]

Hermann (A.) Ein sicheres Zeichen, die Cholera zu erkennen [die Diagnose der Cholera].
[ALLG. Wien. med. Zeitg., 1873, XVIII, pp. 52–53, 71–72, 87–89, 118–119, 138–139, 189–190, 207–208, 223–225, 239, 256, 272; *also, in* WIENER med. Presse, 1873, XIV, pp. 1024–1025.]

Hermann (M. R.) Analyses chimiques. Contenant l'exposé des altérations que subissent le sang et les sécrétions du corps humain pendant le choléra. 4°. [*n. p., n. d.*] L.

Herrmann. Beobachtungen über Cholerafälle.
[ST. PETERSB. med. Zeitschr., 1866, X, pp. 101–102.]

Hilf (J.) Die Cholera und das Wechselfieber.
[WIEN. med. Presse, 1873, XIV, pp. 755–756.]

Hinterberger (J.) Beschreibung der Section einer Choleraleiche, wobey vorzüglich Entzündung der weichen Rückenmarkshaut gefunden wurde, und wodurch vielleicht einer der wichtigsten Aufschlüsse über den Sitz der Cholera erlangt werden könnte.
[MED.-CHIR. Zeitung, 1832, II, pp. 89–96, 105–112, 121–128, 136–144, 154–160.]

Hirsch. Ueber die verschiedenen Formen der Cholera.
[VERHAND. d. physik. med. Gesell. zu Königsberg über die Cholera, 1832, pp. 188–205.]

Hoefle (M. A.) Darminhalt eines Cholerakranken.
[JENA. Ann. f. Physiol. u. Med., 1851, II, pp. 269–272.]

Hogyes (A.) Experimentelle Fragmente über die Wirkung der Cholerae-Excretionen auf Thiere.
[Allg. Zeitsch. f. Epidemiol. Erlangen, 1874, I. pp. 46–52. 1 pl.]

Hohl (A. F.) Analogien der asiatischen Cholera mit der blauen Krankheit und daraus entnommene Resultate. 8°. *Halle*, 1831. L.

Hood (S.) Pathology of spasmodic cholera.
[Lond. Med. & Surg. Journ., 1832, I. pp. 306–311.]

Hope (J.) On the pathology of cholera.
[Lond. Med. Gaz., 1832, IX. pp. 905–908.]

——— State of the intestines in cholera.
[Lond. Med. Gaz., 1832, IX. pp. 926–927.]

Horner (E. W.) Pathological conditions of the intestinal canal in Asiatic cholera.
[Lancet, 1848, II, p. 479.]

Horner (W. E.) Note on the anatomical characters of cholera.
[Amer. Journ. of Med. Sci., 1834, XV. p. 545.]

——— On the anatomical characters of Asiatic cholera, with remarks on the structure of the mucous coat of the alimentary canal.
[Amer. Journ. Med. Sci., 1835, XVI. pp. 56–81, 277–295, 2 plates.]

Houette (F.) Albuminurie guérie, en moins momentanément, par une attaque de choléra.
[Gaz. des hôp., 1849, pp. 244–245.]

Houlès (B.) Réflexion pratique sur les rapports intimes du choléra et de la suette.
[Revue méd., 1855, I, pp. 23–25.]

Hounslow. A theory of the pathology of cholera.
[Lancet, 1848, II, p. 515.]

Hufeland (C. W.) Verwandtschaft der Cholera mit dem Wechselfieber.
[Journ. der pract. Heilk., 1831, LXXIII, pp. 126–127.]

Huppert (H.) Ueber die Glykosurie bei Cholera, mit Bemerkungen über die Zuckerharnruhr.
[Archiv der Heilkunde, 1867, pp. 331–345.]

Jackson (H.) Case of cholera—death—autopsy.
[Med. Times & Gaz., 1866, II, pp. 58–59.]

——— A fatal case of cholera; autopsy.
[Lancet, 1866, II, pp. 66–67.]

Jacquot (L.-A.) * I. Des caractères anatomiques du choléra-morbus épidémique. II. . . . [etc.] 4°. *Paris*, 1840. L.

Jaenichen et **Marcus** (F. C. H.) Animadversiones anatomico-pathologicæ de cholera morbo. Mosq. gramm. 4°. *Lipsiæ*, 1830.
[Also in Mag. der ausländ. Lit. der ges. Heilk., 1831, XXV. pp. 3–63, 1832, XXVI. pp. 296–321.]

Jahn (F.) Die Aehnlichkeit der Cholera mit der Wintererstarrung der Thiere.
[Wochenschr. für die gesammt. Heilk. herausg. von Casper, 1834, III. pp. 185–188.]

Jeaffreson (H.) On the pathology of cholera collapse.
[Edinb. Med. Journ., 1866, XII. pp. 32–37.]

Johnson (G.) The collapse of cholera compared and contrasted with other forms of collapse.
[Med. Times & Gaz., 1866, I. pp. 465–467.]

——— Anatomical condition of the blood and heart in the collapse stage of cholera.
[Med. Times & Gaz., 1867, I, p. 362.]

——— The pathology of cholera.
[Lancet, 1866, I. pp. 730, 831–832, and Edinburgh Med. Journ., 1866, I. pp. 70–71.]

——— Action of the cholera-poison.
[British Med. Journ., 1870, II. pp. 138–140.]

——— On some points in the pathology of cholera and apnœa.
[Brit. & For. Med.-Chir. Rev., 1870, XLV. pp. 495–496.]

——— On some physiological errors connected with cholera.
[Lancet, 1871, II, p. 547.]

——— The theory and treatment of cholera.
[Lancet, 1871, II, pp. 806–808.]

Johnson (H.) Urea detected in the rice-water evacuations of cholera.
[Prov. Med. & Surg. Journ., 1848, pp. 57–58.]

Jones (C. H.) Considerations respecting choleraic collapse.
[Brit. Med. Journ., 1866, II, p. 251.]

Joslin (B. F.) The physiology of respiration and chemistry of the blood, applied to epidemic cholera.
[Trans. N. Y. Med. Soc., 1834-35, pp. 77–96; also, reprint in 8°, New York, 1835.]

Kelsch (A.) Pathologie et histologie du rein chez les cholériques.
[Progrès (Le) méd., Paris, 1874, II. pp. 497–498, 499–500.]

Kikyn (A.), **Kudriaweff** (T.), et **Bogdanow** (A.) Disquisitio anatomico-pathologica in hominibus cholera-morbo tinctis. 8°. *Moscuæ*, 1831.
[Also, in Mag. der ausländ. Lit. der ges. Heilk., 1832, XXIII, pp. 51–64.]

Kingsford (C. D.) Cholera: a new theory. 8°. *London*, 1866. L.

Kleeberg (W.) Pathologisch-anatomische Untersuchungen an Cholera-Leichen.
[VERHAND. d. physik.-med. Gesell. zu Königsberg über die Cholera, 1832, pp 206–238.]

Kletzinsky (V.) Chemische Miszellaneen über Cholera.
[WIEN. med. Wochenschr., 1854, pp. 773, 785.]

Klob. Pathologisch-anatomische Beobachtungen über Cholera.
[WIEN. med. Wochenschr., 1867, pp. 183–184.]

——— Ueber die Ergebnisse seiner pathologisch-anatomischen Untersuchungen der Cholera-Dejectionen und des Inhaltes von Choleraleichen.
[OESTERR. Zeitschr. f. prakt. Heilk., Wien, 1867, XIII. pp. 125–126.]

Klob (J. M.) Pathologisch-anatomische Studien über das Wesen des Cholera-Processes. 8°. *Leipzig*, 1867. L.

Koch (A. B.) * De tunicis mucosis tractatus adjecta de cholera asiatica observatione. 8°. *Gryphiae* [1838]. L.

Kooyker (H. A.) Waarnemingen betreffende de Temperatuur bij cholera asiatica.
[NEDERL. Tijdschr. v. Geneesk., 1867, II, pp. 345–366, 3 tables.]

Kueckelhan (A.) Theory and pathology of cholera.
[ST. LOUIS Med. Reporter, 1866–67, I, pp. 385–392.]

Künckel (P.-N.) * Des diverses opinions émises jusqu'à ce jour sur la nature du choléra-morbus asiatique. 4°. *Paris* 1832. L.

Kyber (E.) Mikroskopische und kritische Studien über die niederen pflanzlichen Organismen aus dem Choleradarme, nebst einzelnen Experimenten und Bemerkungen in Bezug auf die diesen Organismen überhaupt zugeschriebenen Veränderungen.
[DORPAT. med. Zeitschr., 1872, III, pp. 44–95.]

Lassaigne. Examen chimique du sang des cholériques.
[GAZ. des hôp., 1832, VI, pp. 159–160.]

Latour (A.) De l'absorption des médicamens dans le choléra.
[L'UNION méd., 1854, VIII, pp. 433–434.]

Lawson (R.) On the influence of epidemics of fever in checking the advance of those of cholera.
[MED. Times & Gaz., 1872, II, pp. 4–6.]

Leadbrook (L.) *and* **Allsop** (J.) State of the mucous membrane in cholera.
[LONDON Med. Gaz., 1832, X, pp. 597–602.]

Leared (A.) Some new views respecting Asiatic cholera. 8°. *London*, 1848.

Lebert. Compte rendu des recherches anatomo-pathologiques du docteur Virchow, pendant la dernière épidémie de choléra à Berlin.
[GAZ. méd. de Paris, 1849, IV, 3e s., pp. 42–43.]

Lebert (H.) Traité d'anatomie pathologique, t. 2, 1851, pl. 107, 115, 116, 117, 139.

Le Canu. Lettre sur l'état du sang dans le choléra-morbus.
[TRANS. méd., Jour. de méd. prat., Paris, 1832, IX, pp. 293–296.]

——— New analysis of the blood in cholera.
[LONDON Med. Gaz., 1833, XI, pp. 61–62.]

Lee (C.) Further remarks on uræmia in cholera, with a case illustrating the benefit of local depletion.
[MADRAS Quar. Jour. of Med. Sci., 1862, IV, pp. 193–197.]

Legros (C.) *et* **Goujon** (E.) Recherches expérimentales sur le choléra faites au laboratoire de la faculté de médecine de Paris.
[JOUR. de l'anat. et de la phys., 1866, III, pp. 584–593.]

Lehmann (F.) Physikalische und chemische Studien ueber die Cholera. 8°. *Zürich*, 1857. L.

Lemmi. La valeur pathologique de la diarrhée dite prémonitoire.
[GAZ. hebd. de méd. et de chirurg., 1853–54, I, pp. 940–943.]

Lespiau. Interprétations physiologiques des symptômes et des lésions anatomiques du choléra.
[L'ABEILLE méd., 1866, XXIII, pp. 334–335, 337–339, 346–350, 354–358; *also*, reprinted in 8°.]

Lévy (M.) Note sur la sueur et sur l'urine des cholériques.
[GAZ. méd. de Paris, 1849, IV, 3e s., pp. 277–278.]

Lewis (T. R.) *and* **Cunningham** (D. D.) Microscopical and physiological researches into the nature of the agent or agents producing cholera.
[EIGHTH Ann. Rep. Sanitary Commissioner with the Govt. of India, 1871, app. C, pp. 141–203, 1 pl.]

——— The same. 8°. *Calcutta*, 1872. L.

——— The same. (2d series.)
[TENTH Ann. Rep. of the San. Com. with the Govt of India, Calcutta, 1874, pp. 73–110.]

Lélégey. Le choléra actuel et la méningite encéphalo-rachidienne épidémique.
[L'UNION méd., 1849, III, p. 178.]

Hogyes (A.) Experimentelle Fragmente über die Wirkung der Choleraentleerungen auf Thiere.
[ALLG. Ztschft. f. Epidemiol., Erlangen, 1874, I. pp. 98–129, 1 pl.]

Hohl (A. F.) Analogien der asiatischen Cholera mit der blauen Krankheit und daraus entnommene Resultate. 8°. *Halle*, 1831. L.

Hood (S.) Pathology of spasmodic cholera.
[LONDON Med. & Surg. Jour., 1832, I, pp. 306–310.]

Hope (J.) On the pathology of cholera.
[LONDON Med. Gaz., 1832, IX. pp. 905–908.]

——— State of the intestines in cholera.
[LONDON Med. Gaz., 1832, IX, pp. 926–927.]

Horner (E. W.) Pathological conditions of the intestinal canal in Asiatic cholera.
[LANCET, 1848, II, p. 479.]

Horner (W. E.) Note on the anatomical characters of cholera.
[AMER. Jour. of Med. Sci., 1834, XV. p. 545.]

——— On the anatomical characters of Asiatic cholera, with remarks on the structure of the mucous coat of the alimentary canal.
[AMER. Jour. Med. Sci., 1835, XVI. pp. 58–81, 277–295, 2 plates.]

Houette (F.) Albuminurie guérie, au moins momentanément, par une attaque de choléra.
[GAZ. des hôp., 1849, pp. 944–945.]

Houlès (B.) Réflexion pratique sur les rapports intimes du choléra et de la suette.
[REVUE méd., 1833, I, pp. 23–25.]

Hounslow. A theory of the pathology of cholera.
[LANCET, 1848, II. p. 515.]

Hufeland (C. W.) Verwandtschaft der Cholera mit dem Wechselfieber.
[JOUR. der pract. Heilk., 1831, LXXIII, pp. 126–127.]

Huppert (H.) Ueber die Glykosurie bei Cholera, mit Bemerkungen über die Zuckerharnruhr.
[ARCHIV der Heilkunde, 1867, pp. 331–345.]

Jackson (H.) Case of cholera—death—autopsy.
[MED. Times & Gaz., 1866, II, pp. 58–59.]

——— A fatal case of cholera; autopsy.
[LANCET, 1866, II, pp. 66–67.]

Jacquot (L.-A.) *I. Des caractères anatomiques du choléra-morbus épidémique. II. . . . [etc.] 4°. *Paris*, 1840. L.

Jaenichen *et* **Marcus** (F. C. M.) Animadversiones anatomico-pathologicæ de cholera morbo, Mosq. grassante. 8°. *Moscuæ*, 1830.
[*Also*, in MAG. der ausländ. Lit. der ges. Heilk., 1831, XXII, pp. 2–69; 1832, XXV. 295–323.]

Jahn (F.) Die Aehnlichkeit der Cholera mit der Wintererstarrung der Organismen.
[WOCHENSCHR. für die gesammte Heilk. &c., 1834, III, pp. 329–335.]

Jeaffreson (H.) On the pathology of cholera collapse.
[EDINB. Med. Jour., 1866, XII, pp. 397–[illegible]

Johnson (G.) The collapse of cholera compared and contrasted with other forms of collapse.
[MED. Times & Gaz., 1866, I, pp. 465–467.]

——— Anatomical condition of the liver and heart in the collapse stage of cholera.
[MED. Times & Gaz., 1867, I, p. 363.]

——— The pathology of cholera.
[LANCET, 1868, I, pp. 726, 831–832; also in BRITISH Med. Jour., 1868, I, pp. 70–71.]

——— Action of the cholera-poison.
[BRITISH Med. Jour., 1870, II. pp. 185–186.]

——— On some points in the pathology of cholera and apnœa.
[BRIT. & For. Med.-Chir. Rev., 1870, XLV. pp. 485–496.]

——— On some physiological errors connected with cholera.
[LANCET, 1871, II, p. 547.]

——— The theory and treatment of cholera.
[LANCET, 1871, II, pp. 806–808.]

Johnson (H.) Urea detected in the rice-water evacuations of cholera.
[PROV. Med. & Surg. Jour., 1848, pp. 337–338.]

Jones (C. H.) Considerations respecting choleraic collapse.
[BRIT. Med. Jour., 1866, II, p. 251.]

Joslin (B. F.) The physiology of respiration and chemistry of the blood, applied to epidemic cholera.
[TRANS. N. Y. Med. Soc., 1834–35, pp. [illegible]; also, reprint in 8°, New York, 1835.]

Kelsch (A.) Pathologie et histologie du rein chez les cholériques.
[PROGRÈS (Le) méd., Paris, 1874, II, pp. 485–488, 498–500.]

Kikyn (A.), **Kudriawseff** (T.), *et* **Bogarbow** (A.) Disquisitio anatomico-pathologica in hominibus cholera-morbo extinctis. 8°. *Moscuæ*, 1831.
[*Also* in MAG. der ausländ. Lit. der ges. Heilk., 1832, XXIII, pp. 5–64.]

Kingsford (C. D.) Cholera: a new theory. 8°. *London*, 1866. L.

Kleeberg (W.) Pathologisch-anatomische Untersuchungen an Cholera-Leichen.

[VERHAND. d. physik.-med. Gesell. zu Königsberg über die Cholera, 1832, pp 206–238.]

Kletzinsky (V.) Chemische Miszellaneen über Cholera.

[WIEN. med. Wochenschr., 1854, pp. 773, 785.]

Klob. Pathologisch-anatomische Beobachtungen über Cholera.

[WIEN. med. Wochenschr., 1867, pp. 183–184.]

——— Ueber die Ergebnisse seiner pathologisch-anatomischen Untersuchungen der Cholera-Dejectionen und des Inhaltes von Choleraleichen.

[OESTERR. Zeitschr. f. prakt. Heilk., Wien, 1867, XIII, pp. 125–126.]

Klob (J. M.) Pathologisch-anatomische Studien über das Wesen des Cholera-Processes. 8°. *Leipzig*, 1967. L.

Koch (A. B.) * De tunicis mucosis tractatus adjecta de cholera asiatica observatione. 8°. *Gryphiae* [1838]. L.

Kooyker (H. A.) Waarnemingen betreffende de Temperatuur bij cholera asiatica.

[NEDERL. Tijdschr. v. Geneesk., 1867, II, pp. 345–366, 3 tables.]

Kueckelhan (A.) Theory and pathology of cholera.

[ST. LOUIS Med. Reporter, 1866–67, I, pp. 385–392.]

Künckel (P.-N.) * Des diverses opinions émises jusqu'à ce jour sur la nature du choléra-morbus asiatique. 4°. *Paris* 1832. L.

Kyber (E.) Mikroskopische und kritische Studien über die niederen pflanzlichen Organismen aus dem Choleradarme, nebst einzelnen Experimenten und Bemerkungen in Bezug auf die diesen Organismen überhaupt zugeschriebenen Veränderungen.

[DORPAT. med. Zeitschr., 1872, III, pp. 44–95.]

Lassaigne. Examen chimique du sang des cholériques.

[GAZ. des hôp., 1832, VI, pp. 159–160.]

Latour (A.) De l'absorption des médicamens dans le choléra.

[L'UNION méd., 1854, VIII, pp. 433–434.]

Lawson (R.) On the influence of epidemics of fever in checking the advance of those of cholera.

[MED. Times & Gaz., 1872, II, pp. 4–6.]

Leadbrook (L.) *and* **Allsop** (J.) State of the mucous membrane in cholera.

[LONDON Med. Gaz., 1832, X, pp. 597–602.]

Leared (A.) Some new views respecting Asiatic cholera. 8°. *London*, 1848.

Lebert. Compte rendu des recherches anatomo-pathologiques du docteur Virchow, pendant la dernière épidémie de choléra à Berlin.

[GAZ. méd. de Paris, 184[illegible], IV, 3e s., pp. 42–43.]

Lebert (H.) Traité d'anatomie pathologique, t. 2, 1861, pl. 107, 115, 116, 117, 139.

Le Canu. Lettre sur l'état du sang dans le choléra-morbus.

[TRANS. méd., Jour. de méd. prat., Paris, 1832, IX, pp. 293–296.]

——— New analysis of the blood in cholera.

[LONDON Med. Gaz., 1833, XI, pp. 61–62.]

Lee (C.) Further remarks on uræmia in cholera, with a case illustrating the benefit of local depletion.

[MADRAS Quar. Jour. of Med. Sci., 1862, IV, pp. 193–197.]

Legros (C.) *et* **Goujon** (E.) Recherches expérimentales sur le choléra faites au laboratoire de la faculté de médecine de Paris.

[JOUR. de l'anat. et de la phys., 1866, III, pp. 524–593.]

Lehmann (F.) Physikalische und chemische Studien ueber die Cholera. 8°. *Zürich*, 1857. L.

Lemmi. La valeur pathologique de la diarrhée dite prémonitoire.

[GAZ. hebd. de méd. et de chirurg., 1853–54, I, pp. 940–943.]

Lespiau. Interprétations physiologiques des symptômes et des lésions anatomiques du choléra.

[L'ABEILLE méd., 1866, XXIII, pp. 334–335, 337–339, 346–350, 354–358; *also*, reprinted in 8°.]

Lévy (M.) Note sur la sueur et sur l'urine des cholériques.

[GAZ. méd. de Paris, 1849, IV, 3e s., pp. 277–278.]

Lewis (T. R.) *and* **Cunningham** (D. D.) Microscopical and physiological researches into the nature of the agent or agents producing cholera.

[EIGHTH Ann. Rep. Sanitary Commissioner with the Govt. of India, 1871, app. C, pp. 141–203, 1 pl.]

——— The same. 8°. *Calcutta*, 1872. L.

——— The same. (2d series.)

[TENTH Ann. Rep. of the San. Com. with the Govt of India, Calcutta, 1874, pp. 73–110.]

Légey. Le choléra actuel et la méningite encéphalo-rachidienne épidémique.

[L'UNION méd., 1849, III, p. 178.]

Liégey—continued.

——— Nouvelles réflexions sur l'identité de la fièvre cholérique et le choléra; nécessité de l'emploi du sulfate de quinine.

[L'UNION méd., 1849, III, pp. 295–296.]

Lindgren. Versuch einer Nosologie der Cholera oriental. *Kasan*, 1848.

Lindsay (W. L.) Cases of cholera; illustrative of the presence of fat in the fæces, and of certain alterations of the blood.

[MONTH. Jour. of Med. Sci., 1854, XIX, pp. 125–133.]

——— On the presence of certain crystalline fatty bodies in the vomit of cholera.

[MED. Times & Gaz., 1854, IX, n. s., pp. 10–11, 134–135.]

———The development of a blue colouring matter in the urine of cholera.

[MED. Times & Gaz., 1855, X, n. s., pp. 460–461.]

——— Histology of mucoid evacuations in . . . cholera.

[ASSOC. Med. Jour., 1855, p. 251.]

——— Histology of the cholera evacuations.

[EDINB. Med. Jour., 1856, II, pp. 728–743, 1 plate, pp. 810–819.]

Liouville. [Remarks on cholera-psorenteria.]

[BULL. Soc. anat., Paris, 1865, XL, pp. 676–677.]

Lizars (J.) Substance of the investigations regarding cholera asphyxia in 1832, with cases and dissections communicated by Prof. Delpech, and Dr. Coste of Montpelier, and Dr. Lowenhayn of Moscow, during their residence in this country. To which are added observations on the disease in Edinburgh and the neighboring districts. 2d ed. 8°. *Edinburgh* [1848]. L.

Lookstädt (G. A.) Thermometer-Beobachtungen an Cholera-Kranken.

[RUST's Mag. für die gesammt. Heilk., 1832, XXXVI, pp. 356–396.]

Logan (T. G.) The scientific investigation of cholera.

[LANCET, 1868, II, p. 827.]

Lolli. Sul cholera. Tentativo di spiegazioni di alcuni fenomeni più gravi. 4°. *Trieste*, 1866. S. C.

Lowther (G.) The intestinal discharges in malignant cholera.

[LANCET, 1850, II, p. 357.]

Lutz (*Dr.*) Zur Cholera-Frage.

[AERZTL. Intell.-Bl., 1866, XIII, p. 303.]

Mader. Beobachtungen auf der Cholera-Abtheilung des Krankenhauses "Rudolf-Stiftung".

[OESTERR. Zeitschr. f. prakt. Heilk., Wien, 1867, XIII, pp. 108–111, 124–125.]

Mæ. Pathology of cholera.

[MADRAS Quar. Med. Jour., 1839, I, pp. 96–[illegible] 349.]

McCormac (H.) Animal temperature after death from cholera.

[MED. Times & Gaz., 1866, II, p. 636.]

Macloughlin (D.) [Premonitory diarrhœa of cholera.]

[MED. Times & Gaz., 1853, VII, n. s., p. 56.]

——— Cholera and premonitory diarrhœa.

[MED. Times & Gaz., 1854, VIII, p. 386.]

——— Premonitory symptoms in cholera.

[LANCET, 1854, II, n. s., pp. 283–284.]

——— Result of an inquiry into the invariable existence of a premonitory diarrhœa in cholera. 2d ed. 8°. *London*, 1854. L.

——— On the premonitory symptoms of cholera. In a letter to Dr. McCormac editor of the "Association Medical Journal." 8°. *London*, 1855.

——— Additional observations on the invariable existence of a premonitory diarrhœa in cholera; being a reply to Dr. Hutchison's article of Sept. 1855.

[N. Y. Jour. of Med., 1856, XVI, n. s., pp. 63–67.]

——— Remarks on the invariable existence of a premonitory diarrhœa in cholera.

[MO. Stethoscope & Med. Rep., 1856, I, pp. 517–520.]

Man (J. W. E. de). Lijkopeningen gedurende de epidemische Cholera-Mortaliteit op Java, in 1821.

[GENEESK. Courant, Tiel, 1851, No. 32.]

Mandt (M.) Rückenmark und Darmschleimhaut und ihr Verhältniss zur Cholera. 8°. *St. Petersburg*, 1849. L.

Marey. Essai de théorie physiologique du choléra.

[GAZ. hebd. de méd. et de chirurg., 1865, II, pp. 743–746, 762–766.]

Marrotte. Communications sur le choléra. Un mot sur les prodromes du choléra.

[L'UNION méd., 1865, XXVIII, 2e s., pp. 132–134]

Masselot. Recherches anatomo-pathologiques sur le choléra-morbus.

[GAZ. des hôp., 1849, pp. 223–224, 227–229, 233.]

——— Sur les selles des cholériques traités dans le service de M. Michel Lévy.

[GAZ. med. de Paris, 1849, IV, 3e s., pp. 307–[illegible]

Masselot (A.-F.) * Recherches anatomo-pathologiques sur le choléra-morbus dans sa période algide, observé dans le service clinique du Val-de-Grâce. 4°. *Paris*, 1849. L.

Maxwell (W. G.) The blood in cholera.
[India Jour. of Med. & Phys. Sci., 1839, IV, pp. 258–261.]

Meyer (J.) Impfversuche mit dem Blute und den Ausleerungen Cholerakranker. 8°. [*n. p., n. d.*] L.

Meyer (L.) Beitrag zur Pathologie des Choleratyphoids.
[Virchow's Archiv, 1853, VI, pp. 471–510, taf. 6.]

Meyerhoff (J.) Zur Physiologie der Cholera.
[Med. Zeitung Russlands, 1857, pp. 289–293.]

Miahle. Considérations sur la nature du liquide sécrété par la membrane muqueuse des intestins dans le choléra.
[Bull. de l'Acad. nat. de méd., 1848–49, XIV, pp. 669–670, 674–677.]

Michaal. Grundriss der Cholera-Krankheit.
[Zeitschr. d. deutsch. Chirurg.-Vereins f. Med., Chirurg. u. Geburtsh., 1849, III, pp. 212–215.]

Middeldorpf (A.) Chemische Untersuchungen in der Cholera.
[Zeitschr. für klin. Med., 1852, III, pp. 63–68.]

Mignot. La température du corps dans le choléra.
[Gaz. hebd. de méd. et de chirurg., 1870, VII, 2e s., pp. 8–9.]

Miner (T.) The spotted fever and the cholera.
[Boston Med. & Surg. Jour., 1832, VI, pp. 395–397.]

——— Sinking typhus compared with malignant cholera.
[Boston Med. & Surg. Jour., 1833, VII, pp. 21–26, 44–45.]

Möller. Zur Pathologie der Cholera. (Vergrösserung und Schmerzhaftigkeit der Leber—Erbrechen reinen Blutes—Frühes Auftreten von Dysenterie.) (4 cases.)
[Deutsche Klinik, 1858, X, pp. 378–379.]

Molloy (R.) Observations on cholera.
[Lancet, 1854, II, p. 456.]

Monti (A.) Die epidemische Cholera im Kindesalter. Eine monographische Skizze.
[Jahrb. der Kinderheilk., Leipzig, 1869, n. F., II, pp. 401–422; 1871, n. F., IV, pp. 11–33.]

Morgon. Spotted fever and malignant cholera.
[Boston Med. & Surg. Jour., 1833, VII, pp. 14–16.]

Moxon (W.) Case of cholera—death—autopsy.
[Med. Times & Gaz., 1866, II, p. 98.]

——— On Dr. Johnson's theory of cholera.
[Med. Times & Gaz., 1866, II, pp. 415–416, 578–581; 1867, I, pp. 56–58, 82–84.]

Mühlhäuser (F. A.) Ueber Diarrhöen während der Choleraepidemie.
[Berl. klin. Wochenschr., 1873, X, p. 595.]

Munroe (W. F.) Pathological anatomy of cholera.
[Boston Med. & Surg. Jour., 1866, LXXIV, pp. 309–311.]

Murray (J.) Action of the cholera poison.
[British Med. Jour., 1870, II, pp. 106–107.]

——— Observations on the pathology and treatment of cholera, the result of forty years' experience. 12°. *London*, 1874. L.

Namias (G.) Intorno all'idea del Prof. Giacomini di Padova sulla condizione essenziale del colera. 8°. *Venezia*, 1836.

Nedswetzky (E.) Zur Mikrographie der Cholera. 8°. *Dorpat*, 1874. L.

Newman (J. M.) Congestion of the brain in cholera.
[Iowa Med. Jour., 1855, II, pp. 157–158.]

Nonat. Observation de choléra-morbus terminé par la mort. Autopsie. Psorentérie.
[Gaz. des hôp., 1853, pp. 579–580.]

Obre. Case of cholera in which crystals formed on the surface of the body previous to death.
[Med. Times, 1851, III, n. s., pp. 473–474; *also, in* Trans. Path. Soc. of London, 1851–52, III, pp. 441–443.]

Oettingen (O. v.) Sectionsbefund und Untersuchung des Bluts und des Harns in der Cholera nach den in der Cholera-epidemie zu Warschau (vom August bis November [incl.] 1848) gemachten Beobachtungen.
[Jenaische Ann. für Phys. u. Med., 1850, I, pp. 47–67.]

——— Rechtfertigung des Aderlasses in der Cholera.
[Beiträge zur Heilk., Riga, 1853, II, pp. 437–444.]

Oliver (W. S.) What is cholera?
[Med. & Surg. Reptr., 1873, XXIX, p. 274.]

Osborn (H.) Detection of blue matter in the urine of a cholera patient.—With remarks on the action of acids on the same.
[Med. Times & Gaz., 1855, X, n. s., pp. 307–309, 337–338.]

Osborn (H.)—continued.

——— A few additional observations on the existence of blue matter in cholera urine.

[MED. Times & Gazette, 1855, XI, n. s., p. 131.]

O'Shaughnessy (W. B.) Analysis of the blood in cholera.

[LONDON Med. Gaz., 1832, IX, pp. 486–487.]

——— Experiments on the blood in cholera.

[LANCET, 1832, I, p. 490.]

——— Report on the chemical pathology of the malignant cholera: containing analyses of the blood, dejections, &c., of patients labouring under that disease in Newcastle and London. 8°. *London*, 1832. L.

Otto (A. W.) Einige Bemerkungen über die Cholera im lebenden und todten Körper.

[RUST's Mag. f. d. gesammt. Heilk., 1832, XXXVI, pp. 249–299.]

Pacini (F.) Osservazioni microscopiche e deduzioni patologiche sul cholera asiatico.

[GAZ. med. it. Tosc., Firenze, 1854, IV, 2a s., pp. 397–401, 405–412; *also, in* GIORN. venet. d. Sci. med., 1854, IV, 2a s., pp. 204, 385–396; 1855, V, pp. 146–162.]

——— The same. 8°. *Firenze*, 1854. L.

[*Also, in* (French) ARCH. belg. de méd. mil., 1855, XVI, pp. 241–283.]

——— Du choléra asiatique au point de vue de sa cause spécifique, de ses conditions pathologiques et de ses indications thérapeutiques. Traduit de l'italien par E. Janssens. 8°. *Bruxelles*, 1865. L.

——— Sull'ultimo stadio del colera asiatico, o stadio di morte apparente dei colerosi, e sul modo di farli risorgere.

[L'IMPARZIALE, Firenze, 1871, XI, pp. 481–494.]

Paine (M.) The pathologiac varieties of cholera.

[BOSTON Med. & Surg. Jour., 1833, VII, pp. 95–96.]

——— Post-mortem appearances of a cholera subject.

[BOSTON Med. & Surg. Jour., 1833, VII, pp. 34–35.]

Papillon (F.) Expériences et remarques sur les effets physiologiques de la diastase rapprochés des symptômes du choléra.

[GAZ. méd. de Paris, 1867, XXII, 3e s., pp. 706–707.]

Papin-Ruillier-Beaufond (A.) *Doctrine stæchiologique du choléra d'après les travaux récents. 4°. *Paris*, 1866. L.

Pari (A. G.) Condizione patologica del colera dominante, chiarita dalle [illegible] della innervazione e analiticamente dotta.

[GIORN. p. serv. al progr. di patolog. [illegible] 1836, V, pp. 185–264.]

Parker (N.) On the microscopical [illegible] thology of cholera.

[LONDON Med. Gaz., 1849, XLIV, pp. 66–[illegible]

Parkes (E. A.) Note on the existence of bile in the stools of cholera, and [illegible] first urine secreted after the algide stage.

[MONTH. Jour. of Med. Sci., 1849, [illegible] 1127–1130.]

——— On the intestinal discharges in cholera.

[LONDON Jour. of Med., 1849, I, pp. 12[illegible]

——— The detachment of the [illegible] epithelium in cholera.

[MED. Times & Gaz., 1866, II, pp. 2[illegible]

——— On the morbid anatomy of [illegible]

[MED. Times, 1848, XVII, p. 372.]

Paterson (G. K. H.) Inquiry [illegible] morbidly affected state of the [illegible] vessels in cholera.

[MED. Circular, 1854, IV, pp. 247–248

Patterson (J.) Experiments in [illegible]

[MED. Times & Gaz., 1872, I, pp. 473–47[illegible]

Peltier (H.) Remarks on vomiting [illegible] sign of cholera.

[MED. Chron., Montreal, 1854–55, II, pp. [illegible]

Périer. Note sur la présence d'un [illegible] aériforme découvert dans le [illegible] vasculaire des cholériques.

[JOUR. hebd. des prog. des sci., 1853, IV, p[illegible]

Perini (G.) Annotazioni patologi[illegible] colèra asiatico.

[OMODEI, Ann. un. di med., 1836, LXX[illegible] 105.]

Phoebus (P.) Ueber den Leichen[illegible] bei der orientalischen Cholera. [illegible] lin, 1833.

Pidduck (I.) Post-mortem appe[illegible] in cholera.

[LANCET, 1854, II, n. s., p. 157.]

Pirogoff (N.) Anatomie pathologi[illegible] choléra-morbus. (Épidémie de [illegible] Atlas. fol. *St. Pétersbourg*, 1[illegible]

Pistelli (E. M.) Ricerche sulla [illegible] del cholera-morbo.

[OMODEI, Ann. un. di med., 1831, LX Pi[illegible]

Plagge (T.) Welche wesentliche Unterschiede bestehen zwischen gewöhnlicher und epidemischer Cholera?

[AERZTL. Intell.-Bl., 1857, IV, p. 47[illegible]

Fleischl (T.) Ueber das Vorkommen von Perikardialreibungsgeräusch bei Cholerakranken im Stadio algido.
[Vierteljahrschr. f. d. prakt. Heilk., 1851, I, pp. 105–109.]

Plummer (J. T.) Animalcula discovered in the dejections in cholera patients.
[Western Lancet, 1849, X, pp. 290–293.]

Poirson. Constatation du fait annoncé par M. Doyère, relativement à l'existence du sucre dans la sueur des cholériques. (Lettre de M. Poirson à M. Dumas.)
[Comptes-rendus hebd. des séances de l'Acad. des sci., Paris, 1849, XXIX, pp. 422–423.]

Potain. Présentation du cerveau d'une femme, morte à la suite du choléra avec des contractures intermittentes des extrémités et dont le bulbe rachidien offre un ramollissement très-prononcé des pyramides antérieures.
[Bull. et mém. Soc. méd. des hôp. de Paris, 1867, III, pp. 205–206.]

Quissac (J.) Choléra asiatique, sa nature et son traitement.
[Montpellier méd., 1875, XXXIV, pp. 93–108.]

Raikem. Recherches anatomo-pathologiques sur le choléra.
[Gaz. méd. de Paris, 1849, IV, 3e s., pp. 519–522.]

Rainy (H.) Urea in the blood in cholera.
[London Med. Gaz., 1838–39, XXIII, n. s., pp. 518–519.]

Ramskill. Cholera—death in commencing reaction—autopsy.
[Med. Times & Gaz., 1867, II, p. 348.]

Rayer (P.) De l'altération du sang dans le choléra, et de ses principaux effets; expériences comparatives sur des animaux, avec le sang cholérique et non cholérique.
[Gaz. méd. de Paris, 1832, III, pp. 427–430.]

——— The same. 8°. [*n. d.*] L.

——— Étude du sang, sous le rapport de son aptitude à se combiner avec l'oxygène de l'air.
[Gaz. méd. de Paris, 1832, III, pp. 329–333.]

——— The same. 8°. [*n. d.*] L.

——— Examen comparatif de l'air expiré par des hommes sains et des cholériques, sous le rapport de l'oxygène absorbé.
[Gaz. méd. de Paris, 1832, III, pp. 277–278.]

——— Recherches anatomiques sur le choléra. (Avec observations de choléra terminés par guérison, recueillies dans le service de M. Rayer (hôpital de la Charité) par M. Duplay.)
[Arch. gén. de méd., Paris, 1832, XXVIII, pp. 522–544, 579–599; XXIX, pp. 57–98.]

——— The same. 8°. *Paris*, 1832. L.

Rees (G. O.) Clinical remarks on cholera.
[Lancet, 1866, II, pp. 720–721.]

——— The pathology of cholera.
[Lancet, 1868, I, p. 801.]

Reeves (W.) Cholera the result of inflammation of the spinal cord.
[Lancet, 1845, I, pp. 320–321.]

Reid (R.) The pathology and treatment of cholera asphyxia. 8°. *Dublin*, 1832. L.

Reijnhout (M. J.) Waarneming van het, te Amsterdam gedurende de heete Zomermaanden van 1824, geheerscht hebbende Bord (Cholera), en Vergelijking van deze Ziekte met de Cholera morbus orientalis.
[Hippocr. Mag., Rotterdam, 1827, VII, pp. 144–164.]

Rensi (G. e G.) Sulla condizione patologica del cholera-morbus. *Verona*, 1856.

——— In risposta ad alcune obiezioni mosse dal dott. Accordi Giuseppe di Bovolone alla nostra opinione sulla condizione patologica del cholera-morbus.
[Gaz. med. Ital. prov. Venete, 1866, IX, pp. 25–28.]

Renzi (S. de). Découverte d'un entozoaire dans les intestins des cholériques de Naples.
[Gaz. méd. de Paris, 1836, IV, pp. 801–802.]

Riddell (J. L.) Animalcules in cholera dejections.
[New Orleans Med. & Surg. Jour., 1849–50, VI p. 793.]

Ritter (B.) Zur Physiologie und Pathologie des Blutes. Von den Veränderungen des Blutes im krankhaften Zustande. ... Typhöse Fieber. ... Das Blut bei der Cholera. ...
[Rust's Mag. für die gesammt. Heilk., 1843, LXII, pp. 219–224, 239–241.]

Robert (L. J. M.) Lettre à M. De Tourguenef, sur le choléra-morbus de l'Inde importé à Moscou, et sur son analogie avec l'horrible contagion, connue sous le nom de peste noire, qui partie de la Chine, au milieu du 14me siècle, vint ravager l'Europe pendant 17 ans. 8°. *Marseille*, 1831. L.

Robertson (J. J.) Some remarks on the identity of sporadic and epidemic cholera. 8°. *St. Helier's*, 1838. L.
[*Also, in* Med. Circular, 1854, V, pp. 97–98, 108–109.]

Robertson (W.) Observations on the blood of cholera patients.
[Month. Jour. of Med. Sci., 1853, VIII, 3d s., pp. 243–252.]

Robinson (G.) Post-mortem appearances in cholera.
[LANCET, 1854, II, n. s., pp. 121–122; *also, in* MED. Times & Gaz., 1854, IX, n. s., pp. 121–122.]

Rochoux (J. A.) Le choléra-morbus; anatomie pathologique.
[GAZ. des hôp., 1832, VI, pp. 113–114.]

Rœren (H.) Collecta et cogitata quædam ad choleræ epidemicæ pathologiam spectantia. 8°. *Bonnæ*, 1849. L.

Roger (H.) Recherches expérimentales sur l'abaissement de la température du corps dans le choléra.
[ACTES de la Soc. méd. des hôp. de Paris, 1850, pp. 19–37.]

Rogier (A.-E.) * Essai sur la nature du choléra-morbus épidémique. 4°. *Paris*, 1834. L.

Romanowski. Notes sur le choléra asiatique. Rapport de M. Craninx.
[BULL. de l'Acad. roy. de méd. de Belgique, 1848–49, VIII, pp. 77–80.]

Rose (B. F.) Extract from an inaugural thesis, upon the changes of the blood in cholera, submitted to the professors of the medical department of the Columbia College, District of Columbia, Febry. 1833.
[BOSTON Med. & Surg. Jour., 1833, VIII, pp. 119–123.]

Roucher. Note sur la présence de l'urocyanine dans lés urines des cholériques.
[REC. de mém. de méd. de chir. et de phar. mil., 1866, XVII, 3e s., pp. 60–62.]

Roux (J.) Du choléra cutané ou sudoral.
[L'UNION méd., 1855, IX, pp. 111, 113–114, 119, 126–127, 130–131; 1857, XI, pp. 533–534, 565–566, 577, 581–582.]

——— The same. 8°. *Paris*, 1857. L.

Rumsey (N.) Motion of the limbs, and increase of temperature, after death from cholera.
[LONDON Med. Gaz., 1833, XII, pp. 836–837.]

Russell (G. H.) On the operation of physical agencies in the functions of organized bodies, with suggestions as to the nature of cholera.
[[BRIT. AMER. Jour. of Med. & Phys. Sci., 1848, IV, pp. 322–325; 1849, V, pp. 6–9, 41–45; *also*, reprint in 12°, Montreal, 1849.]

Sabatier. Observation d'une maladie offrant plusieurs symptômes analogues à ceux du choléra spasmodique, terminée, en quelques heures, par la mort, et n'offrant à l'ouverture du cadavre qu'un petit nombre de lésions appréciables, etc.
[GAZ. des hôp., 1832, VI, pp. 225–226.]

Sadun (B.) Intorno agli studi da fare sulle cagioni del cholera.
[GAZ. med. it. Tosc., Firenze, 1854, IV, 2a s., pp. 333–336.]

Saint-Vel (O.) De quelques analogies entre le choléra et la fièvre jaune.
[GAZ. hebd. méd. et chir., 1873, X, 2e s., pp. 653–655.]

Salter. Fatal case of cholera.
[Med. Times & Gaz., 1866, II, p. 89.]

Salvatore de Renzi. Lettre sur la cholérine considérée comme période d'incubation du choléra-morbus.
[GAZ. méd. de Paris, 1837, V, pp. 824–825.]

Samoje (F.) * De systematis nervosi in cholera asiatica statu. 8°. *Lipsiæ*, 1850. L.

Sanderson *and* **Hulke.** Report on Dr. Thomé's preparations of cylindrotænium choleræ asiaticæ.
[TRANS. Pathol. Soc., London, 1868, XIX, pp. 453–454.]

Sandras. Lettre sur le choléra-morbus adressée à M. Bally.
[GAZ. méd. de Paris, 1831, II, pp. 367–371.]

Sandras (S.) Des indications thérapeutiques dans le choléra.
[BULL. gén. de thérap. méd. et chir., 1850, II, pp. 410–420.]

Sansom (A. E.) On the mode of action on the cholera poison.
[MED. Press & Circ., 1869, VII, pp. 155–157, 201, 264–265, 307–309.]

Sasse (A.) Cholera: dierlijke Stoffen. Staat van Ontbinding; Koper.
[NEDERL. Tijdschr. v. Geneesk., 1870, I, pp. 217–222.]

Schalle (E.) Schilderung der verschiedenen Natursphären, in welchen die Cholera sich bewegte, und Angabe ihres Verhaltens in ihnen.
[RUST's Mag. f. d. gesammt. Heilk., 1833 XL, 72–118.]

Schartler (F. C.) Neueste Diagnose und Therapie der Cholera morbus. 8°. *Brünn*, 1838. L.

Schleiss von L[öwenfeld]. Hernia incarcerata mit Symptomen jenen der Cholera algida ähnlichen.
[MED. Correspbl. bayer. Aerzte, Erlangen, 1857, pp. 46–48.]

Schmid (G.) Das Choleragift eine Cyanverbindung: bald Blausäure, meist Cyanammonium. Mit Bezugnahme auf Desinfection und Therapie. 8°. *Leipzig*, 1868.

——— The same. 2 Theile. 1870.

Schmidt (J. H.) Physiologie der Cholera. 8°. *Berlin*, 1832. L.

chuld (J. F.) Cholera.
[Geneesk. Courant, Tiel, 1865, No. 36.]

chultz-Schultzenstein. Untersuchung des Cholerabluts.
[Allg. med. Centr.-Zeitg., 1848, xvii, pp. 776–778, 783–786, 791–793.]

churtz (H.) Beiträge zur Kenntniss der pflanzlichen Parasiten der Cholera, der Vaccine, des Scharlach und der Intermittens. 1. Cholera.
[Archiv d. Heilk., 1868, pp. 65–67.]

chweikert (J.) Die Cholera, eine epidemische Lähmung der Capillaren der Darmschleimhaut und ihrer Nerven, zugleich Widerlegung der Professor Haller'schen und Dr. Georg Schmied'schen Hypothesen. 8°. *Breslau*, 1868. L.

coutetten (H.) Ueber den Leichenbefund nach der Cholera.
[Litt. Ann. d. gesammt. Heilk., 1832, xxiii, pp. 165–170.]

—— La température du corps dans le choléra.
[Gaz. hebd. de. méd. et de chirurg., 1870, 2e s., vii, pp. 35–36.]

Searle (C.) On the connection between cholera and fever.
[London Med. Gaz., 1832, ix, pp. 505–507.]

—— Cholera, dysentery, and fever pathologically and practically considered; or, the nature, causes, connexion, and treatment of these diseases in all their forms. 12°. *London*, 1847. L.
[2d ed. was 1830?]

Sedgwick (W.) On the nature of cholera as a guide to treatment. 8°. *London*, 1856.

—— The same. [2d issue.] With a new section on treatment. 12°. 1866. L.

—— Die Natur der Cholera.
[Aerztl. Intell.-Bl., 1857, iv, p. 46.]

—— On the analogies of cholera.
[Med. Times & Gaz., 1867, ii, p. 633.]

—— On some anologies of cholera in which suppression of urine is not accompanied by symptoms of uræmic poisoning.
Lancet, 1867, ii, pp. 611–612.—Med.-Chir. Proc., 1867–71, pp. 2–7.—Med.-Chir. Trans., London, 1868, li, pp. 1–43.—Med. Times & Gaz., 1867, ii, pp. 609–610.]

—— On the continuance of the mammary secretion when the urine is suppressed in choleraic collapse.
[British Med. Jour., 1868, ii, pp. 307–309.]

—— On some physiological errors connected with cholera.
[Lancet, 1871, ii, pp. 597–599, 670–672.]

Sedgwick (W.)—continued.

—— On the initial pathology of cholera with reference to treatment.
[Lancet, 1871, ii, pp. 393–394.]

Seidler (F.) Gründe für die Wahrscheinlichkeit, dass die orientalische Cholera ein Wechselfieber sey und als solches geheilt werden müsse. 8°. *Leipzig*, 1831. L.

Semmola (G.) Sperimenti col sangue degli infermi di colera. Memoria letta all'Accad. reale delle scienza 1837. 4°. *Napoli*, 1845. L.

Senelle. Observation d'un choléra artificiel.
[Jour. univ. et hebd. de méd. et de chir. prat., 1832, ix, pp. 422–424.]

Serres. Observations sur le choléra-morbus de Paris; psorentérie.
[Gaz. méd. de Paris, 1832, iii, pp. 206–208.]

Sherrill (H.) On the pathology of epidemic cholera, with some preliminary observations on the history of the disease, and the general cause and nature of epidemics: containing an improved plan of treatment, the means of prevention and rules for corporations and individuals to pursue. 8°. *New York*, 1835. L.

Siegert (E. M.) Pathologia et therapia cholerae asiaticae summatim exposita. 8°. *Lipsiae* [1850]. L.

Silvestri (C.) Sul cholera, osservazioni di medicina pratica e studii di anatomia patologica, fatti nell'ospedale di Parma l'anno 1849. 8°. *Parma*, 1850.

Simms (F.) The pathology of cholera.
[Lancet, 1868, ii, p. 162.]

Simpson (W.) Attempt to show that the malignant cholera, and the "congestive fever" of Armstrong are the same disease.
[Lancet, 1831–32, ii, pp. 19–20.]

Sing (G.) Hindu view of cholera. 8°. *London*, 1871.

Smith (A.) Fever and cholera from a new point of view. 12°. *Calcutta*, 1873. L.
[*Also*, in 8°, London, n. d.]

Smith *and* **Beale.** Cases of cholera, with examination of the urine.
[Med. Times, 1851, ii, n. s., pp. 372–374.]

Snow (J.) On the pathology and mode of communication of cholera.
[London Med. Gaz., 1849, xliv, pp. 745–752, 923–929.]

Snow (J.)—continued.

——— The same. 8°. [*n. d.*] L.

Solari (E.) Cenni pathologici sopra il cholera-morbus dominante in varie parti d'Europa. 8°. *Genova* [1831]. L.

Souville (G. F.) II. Quels sont les caractères du sang dans le choléra asiatique. 4°. *Paris*, 1838. L.

Späth. Erwiederung auf Herrn Dr. Bernhard Ritter's Aufsatz über das Wesen der epidemischen Cholera in No. 6 des 8. Bandes unseres Correspondenz-Blattes.

[MED. Correspbl. d. württ. aerztl. Ver., 1838, VIII, pp. 204–205.]

Staeger (J. L.) Die Cholera als Krankheit der Haut. 8°. *Mitau und Leipzig*, 1850. L.

Steifensand (C. A.) Die asiatische Cholera auf der Grundlage des Malaria-Siechthums. 8°. *Crefeld*, 1848. L.

Stephens (H. O.) Microscopical investigations in cholera.

[LANCET, 1849, II, n. s., p. 689.]

Stitelet (C.) "De quelques états organopathiques dépendant de l'indoloiosie (choléra). 4°. *Paris*, 1855. L.

Stokvis (B. J.) Infecte-Proeven bij Dieren met Cholera-Excrementen.

[NEDERL. Tijdschr. v. Geneesk., 1866, II, pp. 284–304.]

——— Bijdragen tot de Kennis der eerste na den Cholera-Aanval geloosde Urine.

[NEDERL. Tijdschr. v. Geneesk., 1867, II, pp. 330–344.]

Storr (T. H.) Animalcular character of the organic bodies discovered in cholera patients. Modes of action of calomel and salt in cholera.

[LANCET, 1849, II, pp. 490–491.]

Strambio (G.) Di un nuovo e sicuro sintomo diagnostico che suol precedere lo stadio d'invasione del cholera.

[GAZ. med. it. Lomb., 1849, II, 2a s., p. 408.]

Strohl (E.) Lettre sur la formation de l'emphysème pulmonaire dans le choléra.

[GAZ. méd. de Paris, 1849, IV, 3a s., pp. 599–600.]

Stunde (L.) Besprechung einer höchst ungewöhnlichen Erscheinungsweise der Cholera.

[ST. PETERSB. Med. Zeitschr., 1864, VI, pp. 159–162.]

Sutro *and* **Weber** (H.) Cases of cholera—internal temperature—condition of urine.

[Med. Times & Gaz., 1866, II, p. 234.]

Sutton (G.) Report on cholera.

[TRANS. Ind. State Med. Soc., 1852, pp. 5–<illegible>

——— The same. 8°. [n. p.,] 1850. L.

Sutton (H. G.) A report on the <illegible> anatomy of cholera, as observed in the London hospital during the epidemic of 1866.

[CLIN. Lec. & Rep. of London Hospital [illegible] IV, pp. 443–505.]

Swayne (J. G.) An account of certain organic cells peculiar to the evacuations of cholera.

[LANCET, 1849, II, n. s., pp. 368–371, [illegible]

——— The cholera fungi and uredo.

[LONDON Med. Gaz., 1849, XLIV, pp. 69–[illegible]

——— Discovery of cells in cholera evacuations.

[LANCET, 1849, II, pp. 410.]

——— Microscopical researches on cholera.

[LONDON Med. Gaz., 1849, XLIV, p. 555.]

——— Observations on the report of the College of Physicians relative to the organic bodies discovered in the evacuations of cholera patients.

[LANCET, 1849, II, pp. 530–532.]

Tatham (E.) On the duration of cholera.

[EDINB. Med. & Surg. Jour., 1838, XLIX, [illegible]

Taylor (A. S.) Examination of the liquid vomited during an attack of cholera.

[LONDON Med. Gaz., 1849, XLIII, pp. 136–[illegible]

Taylor (J.) Is dysentery antagonistic to cholera?

[LANCET, 1863, I, p. 198.]

Terrillon. Note sur l'algidité et les symptômes cholériformes accompagnant les étranglements intestinaux.

[GAZ. méd. de Paris, 1875, 4e s., pp. 29–3[illegible]

Thiersch (C.) Meine Cholera-Infectionsversuche vom Jahre 1854 und die Herrn Dr. B. J. Stockvis vom Jahre 1866. Zur Abwehr und Berichtigung.

[ZTSCHR. f. Biologie, 1867, III, pp. 137–[illegible]

Tholozan. Recherches sur quelques points d'anatomie et de physiologie pathologiques du choléra. extraites des conférences cliniques de M. le professeur Michel Lévy.

[GAZ. méd. de Paris, 1849, IV, 3a s., pp. 576–578, 593–596, 630–633, 654–657, [illegible]

——— The same. 8°. *Paris* [n. d.]

Thomas (L.) Zur Lehre von der Cholera, nach den neuern Untersuchungen zusammengestellt.

[SCHMIDT's Jahrbücher, 1866, CXXXII, [illegible] 123.]

Thomas (W. J.) Facts and observations relative to the symptomatic modifications and communicability of the fever of the pestilence commonly called the cholera morbus.'
[LONDON Med. Gaz., 1832, X, pp. 641–646, 823–828.]

——— Treatment of cholera on algebraic principles.
[LANCET, 1849, I, n. s., pp. 149–150.]

Thomé (O. W.) Cylindrotænium choleræ asiaticæ, ein neuer, in den Cholera-Ausleerungen gefundener Pilz.
[VIRCHOW's Archiv, 1867, XXXVIII, pp. 221–244, 2 pl.]

Thomson (A.) State of the body of those destroyed by cholera.
[LONDON Med. & Surg. Jour., 1832, I, pp. 508–510.]

Thudichum (J. L. W.) Report on cholera chemically investigated.
[REP. Priv. Counc., 1866 (appendix), pp. 458–512.]

Tonoli (L.) Succinto paralello fra il cholera e l'avvelenamento del nitro.
[GAZ. med. it. Lomb., Milano, 1849, II, 2a s., pp. 374–375.]

——— Parola relativamente di Baineri.
[GAZ. med. it. Lomb., Milano, 1849, II, 2a s., p. 432.]

Toulmin. On the pathology of cholera, with an exposition of the causes that necessarily render all medicine inoperative in that disease.
[LANCET, 1861, II, n. s., p. 162.]

Tuwar (W. A.) Das Wesen der asiatischen Brechruhr. 8°. *Prag*, 1832.

Tweedie (A.) Liability to cholera lessened by having had the disease.
[LONDON Med. Gaz., 1832, IX, p. 601.]

Verouden. Cholera asiatica.
[GENEESK. Courant, Tiel, 1848, No. 43.]

Vogl (A.) Erfahrungen über Cholera mit besonderer Würdigung und Darlegung der Temperatur-Verhältnisse des menschlichen Körpers in den verschiedenen Stadien dieser Krankheit. 8°. *München*, 1874. L.

Vogt (E.) *Cholerae asiaticae anatomia pathologica. 8°. *Berolini* [1837]. L.

Waardenburg. Aan de Redactie van de Geneeskundige Courant. (Cholera asiatica.)
[GENEESK. Cour., Tiel, 1848, No. 47.]

Waddington (J.) Are there premonitory symptoms in cases of Asiatic cholera?
[LANCET, 1849, II, p. 624.]

Wadham. Case of cholera—death—autopsy.'
[M. D. Times & Gaz., 1856, II, p. 171.]

Wageninge (P. J. van). Cholera.—Neuronismus.
[GENEESK. Cour., Tiel, 1848, Nos. 39–43, 48; *see* Fokker (A. A.), No. 45.]

Wagner (J.) Einige Bemerkungen über die Cholera-Epidemie in Wien, aus dem pathologisch-anatomischen Gesichtspunte.
[MED. Jahr. d. k. k. oesterr. Staates, 1832, II, n. F., pp. 591–610.]

Walther (A.) Études anatomo-pathologiques sur le choléra, et en particulier sur les altérations cholériques des poumons.
[ARCHIV. gén. de méd., 1850, III, pp. 162–172.]

Warren (J. C.) Free oil existing in the blood of cholera patients.
[BOSTON Med. & Surg. Jour., 1833, VII, pp. 74–76.]

Washington (B. H.) Cholera.
[NASHVILLE Jour. Med. & Surg., 1852, III, pp. 84–88.]

Waters (J.) Remarks on the investigations and alleged discoveries of Professor Delpech in the pathological anatomy of the maliguant cholera.
[LANCET, 1831–32, II, pp. 266–268.]

Watson. Mode of attack of cholera.
[LONDON Med. Gaz., 1848, XLI, p. 569.]

Wawruch (A.) Versuch, die Natur der ostindischen Cholera pathologisch zu enträthseln.
[MED. Jahr. d. k. k. oester. Staates, 1832, II. n. F., pp. 530–554; 1832, III, n. F., pp. 260–275, 400–425; 1833, IV, n. F., pp. 337–360, 498–527.]

Weber *and* **Ranke.** Asiatic cholera. Partial recovery. Cerebral congestion. Death. Autopsy.
[LANCET, 1833, I, pp. 344–347; *also, in* MED. Circular, 1853, III, pp. 287–289.]

——— ——— Two cases of cholera; death; autopsy.
[LANCET, 1853, II, p. 520.]

Weiss (R.) Ein Beitrag zur nähern Begründung der Natur der Cholera. 2te Aufl. 8°. *München*, 1831.

Wentzke (T.) *Cholera asiatica cum febre intermittente perniciosa comparata. 8°. *Vratislaviae*, 1833. L.

Wiener (J.) Febris intermittens und Cholera. Eine Parallele.
[WIEN. med. Wochenschr., 1866, pp. 1421–1423, 1436–1438, 1451–1453, 1468–1469.]

Wienkowski. Ueber das Verhalten der in den Darmentleerungen der Cholerakranken enthaltenen Pilze gegen Kali hypermanganicum und Chinin.
[WIEN. med. Wochenschr., 1873, XXIII, pp. 1017–1023.]

Williams (T.) Microscopic examination of the discharges in cholera.
[LONDON Med. Gaz., 1849, XLIV, pp. 579–580, 2 pl., 2 pl., 622–623, 1 pl.]

Wittstock (C.) Chemical researches into the nature of cholera.
[LANCET, 1833–34, I, pp. 169–171.]

Woakes (E.) The theory of cholera collapse.
[BRIT. Med. Jour., II, 1866, p. 403; reply to, by G. Johnson, *ibid.*, p. 436.]

Wright (C. W.) On the difficulty of breathing during the prevalence of the Asiatic cholera.
[WESTERN Lancet, 1850, XI, pp. 17–19.]

Wyss (O.) Ueber die Beschaffenheit des Harns im Reactionsstadium der Cholera asiatica.
[ARCHIV der Heilk., 1868, pp. 232–274.]

Zdekauer. Ueber die Prodromalsymptome der Cholera.
[ST. PETERSB. med. Zeitschr., 1871, II, n. s., pp. 555–557.]

Zimmermann (G.) Ueber des Blut der Cholera-Kranken.
[MED. Zeitung, 1853, pp. 221–224, 225–227, 231–233, 235–237.]

——— Ueber die Temperatur-Verhältnisse der Cholera-Kranken.
[MED. Zeitung, 1853, pp. 113–115, 117–119.]

——— Ueber einen sehr eigenthümlichen Farbstoff im Blute der Cholerakranken.
[DEUTSCHE Klinik, 1855, VII, pp. 51–54.]

——— Zur pathologischen Physiologie der epidemischen Cholera. (3 cases.)
[DEUTSCHE Klinik, 1856, VIII, pp. 73–77, 92–95, 102–104.]

——— Zur pathologischen Physiologie der epidemischen Cholera. Analytischer Theil.
[DEUTSCHE Klinik, 1858, X, pp. 289–291, 300–302, 309–311, 326–328, 338–340, 345–348.]

——— Zur pathologischen Physiologie der epidemischen Cholera. II. Das Blut.
[DEUTSCHE Klinik, 1859, XI, pp. 41–45, 55–57, 93–95, 125–127, 150–151, 179–180, 219–221.]

Zorn (H.) Beiträge zu den Temperaturverhältnissen in der Cholera.
[ST. PETERSBURG. med. Zeitschr., 1872, n. F., III, pp. 27–58.]

Zuelzer (W.) Ueber eine eigenthümliche Einwirkung des Choleragiftes auf die Körpertemperatur.
[BERLIN. klin. Wochenschr., 1874, XI, p. 165.]

Zyngorn (I.) O cholerytchny'ch sudorohach.
[MEDYTZYNSKIY Viestnik, St. Petersburg, 1867, VII, pp. 27–28, 40–42, 48–50, 59–62, 75–76, 83–86.]

Analyse chimique des liquides e[illegible] jections dans le choléra.
[L'UNION méd. 1849, III, p. 186.]

Anatomy of malignant cholera.
[LANCET, 1833, I, pp. 269–273.]

Animadversiones anatomico-pathologicæ de cholera-morbo Mosquæ grassante. 4°. [*n. p., n. d.*]

Bidrag til Kundskab om den epidemiske Cholera.
[BIBL. for Laeger, Copenhagen, 1[illegible] 496–617.]

Bijdrage tot de meer algemeene en naauwkeurige zakelijke Kennis der Cholera, derzelver Voorbehoeding en Geneeswijze. [illegible] *terdam*, 1831.

Cases of cholera in Boston, with [illegible] ances on dissection.
[BOSTON Med. & Surg. Jour., 1833, [illegible] 67–68.]

Cases of cholera, with the appear[illegible] on dissection. Being an extract from medical report of the diseases [illegible] occurred in the 16th Lancers, from [illegible] to September, 1823.
[LONDON Med. & Phys. Jour., 1824, [illegible] 387.]

Chemical pathology of the [illegible] cholera.
[MED. Mag., 1833, I, pp. 102–108.]

Cholera, a disease of debility.
[MED. Circular, 1854, V, p. 176.]

Choléra, épidémie regnante, [illegible] tion pendant la période algide.
[JOUR. de méd. et de chir. prat., 1854, pp. 337–340, 433–438, 481–486.]

Cholera: its pathological anat[illegible] pathology.
[DUBLIN Med. Press & Circ., 1866, [illegible] 272–273.]

Choléra - morbus. — Mort. — [illegible] prodromes et de lésions anato[illegible]
[GAZ. des hôp., 1853, p. 593.]

Corpuscules (Les) du choléra.
[L'UNION méd., 1849, III, pp. 490–491]

Essai de théorie physiologique d[illegible]
[GAZ. des hôp., 1865, p. 605.]

Excretion of serum in cholera.
[LANCET, 1842–43, I, pp. 94–95.]

Expériences chimico-microscopiques [illegible] le miasme du choléra. [illegible] 1833].

Lésions cadavériques constatées [illegible] sujets morts de choléra.
[L'ABEILLE méd., 1853, X, p. 339.]

Microscopical discoveries in [illegible]
[PROV. Med. & Surg. Jour., 1849, [illegible]

Nécropsie des deux cholériques morts le 2 avril à l'hôpital Cochin.
[Gaz. des hôp., 1832, VI, pp. 57–58.]

Note (A) on the pathology of cholera.
[Lancet, 1849, II, p. 219.]

Djurlênie orhanov pry cholerie.
[Medytzynskiy Viestnik, St. Petersburg, 1866, VI, p. 432.]

Om de alvorlige Former af Cholerine.
[Ugesk. for Laeger, Copenhagen, 1867, IV, pp. 272–274.]

Om Pathologien af den ostindiske Cholera.
[Bibl. for Laeger, Copenhagen, 1827, pp. 12–21.]

On the morbid condition of the blood in cholera.
[London Med. & Surg. Jour., 1833, II, p. 570.]

Opinions of the consulting physicians on cholera. Boston, city doc. No. 55, May 7, 1866. 8°. [*n. p., n. d.*] L.

Over de Belemmeringen in den Bloedsomloop gedurende het asphyctische Tijdperk der Cholera.
[Geneesk. Courant, Tiel, 1867, No. 4.]

Pathological condition of the blood in cholera.
[Lancet, 1849, I, n. s., pp. 511–512.]

Preliminary (The) diarrhœa and consecutive fever of the malignant cholera; features alike, of that disease, in India and England.
[Lancet, 1831–32, II, pp. 14–17.]

Rapporto letto nell'adunanza della Società medico-fisica fiorentina del dì 3 Settembre 1854 sull'incarico: "D'istituire gli studj opportuni sul valor patologico della, così detta, diarrea prodromica del cholera; di osservare i resultati di cura, che si sono avuti nei paesi, ove essa ha dominato; e di riferire sull'indole delle affezioni gastro-enteriche, che dominan ora nel nostro paese".
[Gaz. med. Ital. Tosc., Firenze, 1854, IV, 2a s., pp. 293–297.]

Recherches d'anatomie pathologique et opinion de M. le professeur Delpech sur la nature du choléra-morbus.
[Jour. de méd. et de chir. prat., 1832, III, pp. 120–121.]

Réflexions sur le siége du choléra.
[Bull. gén. de thérap. méd. et chir., 1832, III, pp. 153–155.]

Report on the bodies, exhibited to the Physiological Society of Edinburgh, in the blood and some of the organs of a patient dying of cholera.
[Month. Jour. Med. Sci., 1854, XIX, pp. 178–179.]

Report on the nature and import of certain microscopic bodies found in the intestinal discharges of cholera. Presented to the cholera committee of the Royal College of Physicians of London, by their sub-committee, on October 17, 1849.
[Med. Times, 1849, XX, pp. 351–353.]

——— The same. 8°. *London*, 1849. L.

Scientifische (Die) Seite der asiatischen Cholera. Ein Versuch von einem praktischen Arzte aus den Rheingegenden.
[Med. Annalen, 1832, IV, pp. 560–582.]

Secretions in malignant cholera. Evidence of contagion.
[Lancet, 1832–33, I, p. 147.]

Temperature (The) and the breath in cholera.
[Lancet, 1859, I, n. s., p. 326.]

Three queries respecting cholera: 1. Have the limbs of persons dead of cholera been observed to move? 2. Have oily dejections been noticed in cases of cholera? 3. What are the powers of mercury in the complaint? How are they displayed, and in how short a time after its employment?
[Lancet, 1833, XII, p. 512; Reply to the three queries by T. R. Jameson and S. M'Coy, pp. 614, 639–640.]

What is cholera?
[Hall's Jour. Health, N.Y., 1866, XIII, pp. 1–20.]

V.—COMPLICATIONS, SEQUELÆ, AND CASES.

A.—COMPLICATIONS.

Fouache (P. P.) *I. Des complications du choléra-morbus épidémique. 4°. *Paris*, 1841. L.

Girouard (P. F.) *I. Des complications du choléra-morbus épidémique. 4°. *Paris*, 1838. L.

Limousin (A.) Influence du choléra sur les maladies dans le cours desquelles il survient. 8°. *Paris*, 1859. L.

Rochoux. Influence du choléra sur les maladies.
[Bull. de l'Acad. nat. de méd., Paris, 1849–50, XV, pp. 860–864.]

Complications du choléra.
[L'Union méd., 1849, III, p. 177.]

Cerebral.

Piorry. Hémiplégie du côté gauche; apparition de symptômes cholériques à

Piorry—continued.
la suite de l'administration de deux lavemens purgatifs; mort. Cerveau ne présentant aucune altération capable de rendre compte de l'hémiplégie.
[Gaz. des hôp., Paris, 1832, VI, p. 228.]

Complications (Des) cérébrales ou états méningitiques dans le choléra.
[Gaz. des hôp., 1866, p. 149.]

In children.

Barthez. Du choléra chez les enfants. Note sur les cas observés dans le service de M. . . . , à l'hôpital Ste.-Eugénie.
[Bull. et mém. Soc. méd. des hôp. de Paris, 1866, II, pp. 227–240.]

With fever.

Elliotson (J.) Clinical lecture on malignant cholera, following continued fever.
[Lancet, 1832–33, I, pp. 224–229.]

Finley (J. C.) A case of cholera, combined with symptoms of remittent fever.
[Western Jour. of the Med. & Phys. Sci., 1833, VI, pp. 367–370.]

Gruber (J.) Cholera epidemica cum quartana complicata.
[Oesterr. med. Wochenschr., Wien, 1845, p. 925.]

Montanier. Observations de fièvre typhoïde compliquée de choléra asiatique, de scorbut et de contracture musculaire douloureuse. Guérison.
[Gaz. des hôp., 1855, pp. 358–359.]

With gout.

Descourtilz. Observation d'un accès de goutte compliquée de choléra.
[Gaz. des hôp., 1832, VI, p. 252.]

Heart.

French (J. G.) Affection of the heart in cholera.
[Lancet, 1841–42, II, pp. 890–891.]

In the insane.

Lélut (F.) Sur le choléra-morbus de Bicêtre, et en particulier sur celui des aliénés.
[Gaz. méd. de Paris, 1832, III, pp. 372–374.]

Cholera among the lunatics of Haslar hospital.
[London Med. & Surg. Jour., 1833, II, p. 251.]

After labor.

Church (H. E.) Case of malignant cholera three days after parturition.
[Lancet, 1831–32, II, p. 752.]

Eastlake (H. E.) On a case of cholera occurring during labor. Death immediately after delivery.
[Lancet, 1865, II, pp. 672–673.]

With pneumonia.

Wasseige. Cas de choléra se substituant à une pneumonie. Rapport de M. Gra[illegible].
[Bull. de l'Acad. roy. de méd. de Belgique, [illegible] 50, IX, pp. 24–30.]

With pregnancy.

Alleyne (J. S. B.) On the frequency of abortion in the cholera epidemic of 1[illegible] in St. Louis.
[St. Louis Med. Reporter, 1866–67, I, pp. 392–[illegible]

Basedow (v.) Rettung einer Cholerakranken durch künstliche Frühgeburt.
[Med. Zeitung, 1833, pp. 142–143.]

Bouchut (E.) De l'influence du choléra sur la grossesse.
[Mém. Soc. de biol., 1849, I, pp. 33–42; also Gaz. Med. de Paris, 1849, IV, 3e s., pp. 794–[illegible]

Chailly (H.) Transmission présumée de la cholérine de la mère à l'enfant; emploi du chloroforme pour faire cesser les vomissemens pendant la grossesse chez une femme affectée de cholérine.
[L'Union méd., 1849, III, p. 283.]

Colombe (L.) Du choléra-morbus pendant la gestation.
[Gaz. des hôp., 1832, VI, pp. 111–112.]

Güterbock. Ueber den Einfluss der Cholera auf die Schwangerschaft und die Geburt.
[Deutsche Klinik, 1866, XVIII, pp. 345–347, 359.]

Helm (T.) Über Modification der epidemischen Brechruhr in ihrer Form bei Schwangeren, Gebärenden, Wöchnerinnen und Neugebornen.
[Med. Jahrb. d. k. k. oesterr. Staates, Wien, [illegible] XV, n. F., pp. 223–232.]

Picard (J.) Quelques observations de choléra chez des femmes enceintes recueillies pendant l'épidémie de Soultzmatt, août et septembre 1855.
[Gaz. méd. de Strasbourg, 1855, pp. 399–[illegible]

——— The same. 8°. *Strasbourg*, 1855.

Proegler (C.) Cholera, and its relation to pregnancy and child-birth.
[Chigago Med. Jour., 1871, XXVIII, pp. 536–[illegible]

Tallon (J. L. A. É.) *De l'influence du choléra sur l'état puerpéral. 4°. *Paris*, 1850. I.

Thümmel. Geburtsact in asphyktischer Cholera.
[Med. Zeitung, 1832, p. 44.]

Weber (F.) Ueber den Verlauf der Cholera bei den Schwangern und den Einfluss derselben auf die Schwangerschaft.
[ALLG. med. Cen.-Zeitg., 1871, XL, pp. 25–28, 36–39.]

West (F.) Case of malignant cholera, in which delivery at term took place, during its advanced or collapsed stage, and the patient recovered.
[AM. Jour. of Med. Sci., 1834, XV, pp. 548–549; *also, in* LOND. Med. & Surg. Jour., 1835, VII, pp. 572–573.]

Whitmore (H.) Cholera with abortion.
[LONDON Med. Gaz., 1832, X, pp. 258–260.]

Deux exemples de choléra survenu pendant la grossesse double dans un cas.—

Deux *etc.*—continued.
Mort.—Avortement dans le premier; continuation de la gestation dans l'autre.
[GAZ. des hôp., 1853, pp. 611–612.]

Influence de la grossesse et de l'accouchement sur la marche du choléra.
[BULL. gén. de thérap. méd. et chir., 1849, XXXVII, pp. 323–325.]

With small-pox.

Choléra et variole sévissant simultanément sur le même individu. Influence qu'exercent ces deux maladies l'une sur l'autre.
[GAZ. des hôp., 1854, p. 297.]

B.—SEQUELÆ.

Andrews. Case of roseola cholerica.
[MED. Times & Gaz., 1866, II, p. 143.]

Anger (T.) Observation sur certains accidents convulsifs du choléra.
[GAZ. des hôp., 1866, p. 117–118.]

Babington (B. G.) Cutaneous eruption in cholera.
[LONDON Med. Gaz., 1832, X, pp. 578–579.]

Ballard (E.) A case of cholera terminating with pericarditis.
[LONDON Jour. of Med., 1851, III, pp. 1062–1069.]

Barthélemy. Observation d'un cas de gangrène causé par le choléra.
[GAZ. méd. de Paris, 1838, VI, pp. 574–575.]

Bassereau (A.-H.) Note sur les fièvres qui ont succédé à l'épidémie de choléra de 1848, à Jassy (Moldavie).
[GAZ. méd. de Paris, 1849, IV, 3e s., pp. 918–921.]

Becker (L.) *De morbo typhoide cholerain asiaticam sequente. 8°. *Berolini*, 1867. C.

Bourgogne, *père.* Quelques mots à propos des paralysies qui peuvent se montrer pendant le cours du choléra, ou consécutivement à cette maladie. Nouvelle constatation de la forme soporeuse du choléra asiatique.
[JOUR. de méd. de chir. et de pharm., Bruxelles, 1860, XXXI, pp. 437–444.]

Bourjot-St.-Hilaire. Note sur quelques affections des yeux dans le choléra.
[GAZ. méd. de Paris, 1832, III, pp. 311–312.]

Briquet. Affections cholériques. Choléra algide survenant dans le cours d'une fièvre typhoïde.
[JOUR. des connais., 1846, XIV, pp. 177–180.]

Burggraeve. Diarrhée cholériforme. Accidents typhoïdes. Emploi dosimétrique de l'aconitine, de la digitaline, de l'hydroferro-cyanate de quinine.
[REPERT. de méd. dosimétr., 1872–73, I, pp. 183–185.]

Christiani (A.) Note sur un phénomène consécutif au choléra-morbus parvenu à la période algide, terminé par la guérison.
[REC. de mém. de méd. et de pharm. mil., 1838, XLIV, pp. 334–337.]

Cormack (J. R.) Paralysis during and after cholera.
[BRIT. Med. Jour., 1873, I, pp. 571–572.]

Duplay. Mémoire sur la roséole consécutive au choléra. (7 cases.)
[GAZ. méd. de Paris, 1832, III, pp. 583–587.]

Engelskjon. Et Tilfaelde af Hjernecongestion efter Cholerine. (Case.)
[NORSK Mag. for Laegevid., Christiania, 1864, XVIII, pp. 855–859.]

Facen (J.) Delle affezioni succedanee ed affini al morbo cholera.
[GIORN. veneto. d. sc. med., 1856, VII, 2a s., pp. 557–580; VIII, pp. 182–184.]

Fritsch. Das Cholera-Exanthem.
[MED. Zeitung, 1848, p. 204.]

Graf. Merkwürdige Ausscheidung eines necrotisch gewordenen Oberkiefers und Jochbeines der linken Gesichtshälfte, nach der Cholera entstanden.
[MED. Jahrb. d. k. k. oesterr. Staates, 1838, XV, n. F., pp. 215–223, 1 pl.]

Gubian (C. J. L.) *Sur un typhus pneumonique succédant au choléra (épidémie de Serves). 4°. *Paris*, 1855. L.

Gubler (A.) Sur la glycosurie symptomatique dans la période réactionelle du choléra.
[GAZ. des hôp., 1866, p. 410.]

Güterbock (L.) Ueber einige Cholera-Nachkrankheiten.
[BERL. klin. Wochenschr., 1868, V, p. 177.]

Henry. Choléra épidémique.—Gangrène des extrémités inférieures. Mort.
[GAZ. des hôp., 1854, pp. 41–42.]

Heubner (O.) Ueber die unvollständige Reaktion nach dem Choleraanfalle.
[ARCHIV der Heilkunde, 1867, pp. 214–245.]

Jaubert (H.) *De la convalescence du choléra. 4°. *Paris*, 1866. L.

Joseph (G.) Bemerkungen über krankhafte Vorgänge an den Augen von Cholerakranken, ein Beitrag zur Pathologie des menschlichen Auges.
[ZEITSCHR. für klin. Med., 1856, VII, pp. 370–377.]

——— Ueber das Choleraexanthem.
[ZEITSCHR. für klin. Med., 1856, VII, pp. 30–38.]

Kerschensteiner (J.) Das Cholera-typhoid der Kinder.
[AERZTL. Intell.-Bl., 1856, III, p. 313.]

Kräuter (J.) Ueber einige Nachkrankheiten der Ruhr. Ein Beitrag zur Aetiologie der acuten und chronischen Gelenkentzündungen und der Blennorrhöen der Conjunctiva. 8°. *Cassel*, 1871. L.

Lawrie (J. A.) On the reaction, or secondary fever of cholera.
[LONDON Med. Gaz., 1832, X, pp. 666–670.]

Le Goupils. De l'érythème cholérique [roséole cholérique de M. Rayer], et particullèrement de son importance pour le pronostic du choléra.
[REVUE méd.-chirurg. de Paris, 1849, VI, pp. 193–201.]

Leudet. Choléra. Abcès multiples du rein droit. Éruption érythémato-papuleuse. Destruction du cartilage thyroïde. Mort. Autopsie.
[BULL. Soc. anat. de Paris, 1849, XXIV, pp. 243–245.]

Louis. Parotides et éruptions cutanées dans le choléra. Quelques mots sur le traitement de cette maladie.
[GAZ. des hôp., 1849, pp. 274–275.]

Macpherson (J.) Notes on cholera, along with some cases of the disease terminating in an unusual manner.
[INDIAN Ann. of Med. Sci., 1853, I, pp. 110–129.]

Middlemore (R.) On certain forms of diseases of the eye, observed in individuals who were suffering from, or had recently been attacked by cholera.
[LONDON Med. Gaz., 1833, XII, pp. 492–494.]

Moering (F. G.) *Diss. inaug. sistens historiam cholerae, cum subsequente pleuroperipneumonia. 4°. *Lipsiae* [1830]. L.

Morehead. [Case of cholera. Recovery from stage of collapse. Coma. Death. Thickening of arachnoid.]
[TRANS. Med. & Phys. Soc., Bombay, 1843, VI, pp. 67–68.]

Mouchet (A.) *Des affections secondaires du choléra, observées dans l'épidémie de 1866. 4°. *Paris*, 1867. L.

——— Observations d'accidents gangreneux chez des cholériques.
[ARCHIV. gén. de méd., 1867, I, pp. 425–441.]

Newman (J. M.) Congestion of the liver in cholera. Its etiology, diagnosis, and treatment. A paper read before the Buffalo Medical Association, October 1854. 8°. *Buffalo*, 1854. L.

Nonat. Choléra suivi d'une gastro-entérite aiguë [fièvre typhoïde]; traitement antiphlogistique; vésicatoires; alimentation; guérison.
[GAZ. des hôp., 1832, VI, p. 393.]

Parkes (E. A.) Repeated attacks of diarrhœa—: during a diarrhœal attack choleroid seizure: nine days afterwards a cutaneous eruption identical with the cholera-exanthem.
[MED. Times & Gaz., 1852, IV, a. a. pp. [illegible]]

Paulicki. Zahlreiche Haut-Abscesse in der Rekonvalescenz von Cholera asiat.
[MEMORAB., Heilbronn, 1869, p. 117.]

Polak (J. E.) Simultane Krankheits-Ausgänge und Metastasen der Cholera.
[ZEITSCH. d. k. k. Ges. d. Aerzte., Wien, 1[illegible] 84–87.];

Samoje (F.) Die Nervenerscheinungen und ihre Entwickelung in der asiat. Cholera.
[DEUTSCHE Klinik, 1850, II, pp. 53–56.]

Sedgwick (W.) On temporary glycosuria as a sequel of cholera.
[MED.-CHIR. Proceedings, 1867–71, VI, [illegible] 319; *also*, in MED.-CHIRURG. Trans., [illegible] pp. 63–93.]

Simon (G.) Das Cholera-Exanthem.
[MED. Zeitg., 1848, pp. 190–191.]

Slavjansky (K.) Endometritis decidualis haemorrhagica bei Cholera-Kranken.
[ARCH. f. Gynaekol., Berlin, 1872, IV, pp. [illegible]]

Smith (G. S.) Case of tetanus following an attack of cholera.
[DUBLIN Med. Press & Circ., 1852, V, p. [illegible]]

Smith (W. G.) Case of general paralysis subsequent to cholera.
[DUBLIN Med. Press & Circ., 1852, V, pp. [illegible]]

Smoler. Geistesstörung nach Cholera.
[MEMORAB., Heilbronn, 1866, pp. 220–222.]

Thore. Sur les exanthèmes cholériques.
[GAZ. méd. de Paris, 1850, V, 3e s., pp. [illegible]]

——— Observations de roséole cholérique suivie de réflexions sur les exanthèmes consécutifs au choléra.
[GAZ. des hôp., 1835, pp. 10–11.]

Van Holsbeek (H.) De l'influence du choléra sur la production de la folie.
[BULL. de l'Acad. roy. de méd. de Belg., Bruxelles, 1867, I, 3e s., pp. 991–996; *also*, in RAPPORT de M. Marinus, pp. 930–932.]

Volpelière (C.) *et* **Serre** (A. H.) Des rapports sympathiques de l'œil avec l'appareil gastro-intestinal dans l'étude du choléra.
[GAZ. des hôp., 1835, IX, p. 373.]

Wells (T. S.) Uterine epistaxis in cholera, fever, and inflammation.
[MED. Times & Gaz., 1866, II, p. 237.]

Wolff. Trismus und Tetanus rheumaticus und Cholera epidemica.
[MED. Zeitg., 1854, pp. 95–96.]

Worms (J.) Note sur la période de réaction consécutive à l'accès du choléra épidémique. 8°. *Paris*, 1866. L.

Zenker (F. A.) * De genetico affectionis renum in cholera connexu cum ceteris hujus morbi partibus. 8. *Dresdæ* [1851]. L.

Zimmermann (K. G.) Uebergangsformen und Complicationen der Cholera mit Scharlach und Wechselfieber.
[LITTER. Ann. d. ges. Heilk., 1832, XXIV, pp. 415–466.]

Cholera—consecutive fever—venesection mal-apropos—delirium tremens—death.
[LONDON Med. & Surg. Jour., 1833, II, pp. 440–443.]

Choléra.—Gangrène consécutive.
[GAZ. des hôp., 1866, pp. 577–578.]

Quelques (De) accidens qui surviennent pendant la convalescence du choléra-morbus.
[GAZ. des hôp., 1832, VI, pp. 221–222.]

C.—CASES.

[N. B.—The titles of journal-articles are omitted in most cases, as they are nearly alike; being "Cases of cholera", "A case of malignant cholera", etc.]

Andral.
[GAZ. des hôp., 1831, V, p. 26.]

Baines (J. K.)
[LANCET, 1849, I, p. 94.]

Barnett (W. D.)
WEST. Jour. of Med. & Surg., 1849, I, pp. 387–389.

Barron (G. B.)
[MED. Times, 1850, XXI, pp. 88–89.]

Bartlett (J.) Cholera in Marylebone.
[LONDON Med. Gaz., 1832, IX, pp. 827–828.]

Basham (W. R.)
[LANCET, 1846, II, p. 6.]

Behrend (H.)
[LANCET, 1853, I, n. s., pp. 245–246.]

Bertrand (P.)
[PRECIS des trav. de la Soc. méd. de Boulogne-sur-Mer, 1839, pp. 311–312.]

Bird (H.)
[LANCET, 1832–33, II, pp. 753–755.]

Birtwhistle (J.)
[LANCET, 1831–32, I, pp. 917–918.]

Birtwhistle (W.)
[LANCET, 1831–32, I, pp. 160–161.]

Black (P.) Case of cholera without premonitory diarrhœa.
[MED. Times & Gaz., 1853, VII, n. s., pp. 562–563.]

Blair (C. E.)
[LANCET, 1832, I, pp. 825–826.]

Bosc.
[GAZ. des hôp., 1832, VI, pp. 61–62.]

Bouillaud.
[BULL. de l'Acad. de méd., Paris, 1872, I, pp. 159–164.]

Bricheteau.
[GAZ. des hôp., 1832, VI, pp. 157–158, 191–192.]

Broussais (C.)
[ANN. de la méd. phys., 1834, XXV, pp. 400–402.]

Brunjes (M.)
[MED. Times & Gaz., 1866, II, p. 337.]

Budd (G.) *and* **Busk** (G.) Report of 20 cases of malignant cholera that occurred in the seamen's hospital-ship "Dreadnought", between the 8. and 28. October, 1837.
[MED.-CHIRURG. Trans., London, 1838, XXI, pp. 152–186.]

Bulley (F. A.)
[MED. Times & Gaz., 1851, IX, n. s., pp. 339–341.]

Burgess (J.)
[LANCET, 1831, II, pp. 813–814.]

Burrows.
[MED. Circular, 1853, III, pp. 289, 361–362.]

Burt (J. W.)
[INDIA Jour. of Med. Sci., 1834, I, pp. 294–296.]

Carlier.
[BULL. de l'Acad. roy. de méd. de Belgique, 1842–43, VIII, pp. 263–277.]

Carr (A.)
[LANCET, 1848, II, p. 444.]

Casey (E.)
[MED. Times & Gaz., 1866, II, pp. 303–304.]

Chaumonot.
[GAZ. des hôp., 1832, VI, p. 368.]

Chomel.
[GAZ. des hôp., 1833, VII, p. 485.]

Chrestien (A. T.)
[OBSERV. de clin. méd. par A. T. Chr., Montpellier, 1852, pp. 286–294.]

Clark (A.)
[MED. Times & Gaz., 1866, II, p. 59.]

Clemens (A.)
[MED. Conversbl., 1832, pp. 198–200.]

Cliet.
[GAZ. med. de Paris, 1849, IV, 3e s., pp. 321–325.]

Coley.
[N. Y. Med.-Chir. Bull., 1831, II, pp. 6–8.]

Collier (J.)
[LONDON Med. Gaz., 1842–43, I, n. s., pp. 369–370.]

Colombat.
[GAZ. des hôp., 1830, IV, pp. 128–129.]

Cooke.
[MED. Times & Gaz., 1861, II, p. 322.]

Corsin.
[GAZ. des hôp., 1831, IV, p. 265.]

Cotting.
[*From* RECORDS of Bost. Soc. for Med. Improv., 1856, II, pp. 281–282.]

Coxe (E. J.)
[BOSTON Med. & Surg. Jour., 1855, LI, pp. 369–373.]

Crawford (J.)
[LANCET, 1849, I, n. s., p. 97.]

Da-Camino (F. S.)
[GIORN. venet. d. sc. med., 1855, VI, 2a s., pp. 197–212, 517–536.]

Davis (E. G.)
[BOSTON Med. & Surg. Jour., 1833, VII, pp. 111–112.]

Dayman (H.)
[BRIT. Med. Jour., 1865, II, pp. 549–550.]

De la Rue.
[GAZ. des hôp., 1833, VII, p. 211.]

Delorme (E.)
[JOUR. univ. et hebd. de méd. et de chir. prat., 1832, IX, pp. 77–81.]

Dobson (W.)
[LANCET, 1831–32, II, p. 651; *also, in* LOND. Med. & Surg. Jour., 1833, II, p. 156.]

Dowler (B.)
[N. O. Jour. Med. & Surg., 1856, XIII, pp. 620–640; 1857, XIV, pp. 37–44.]

Dumontpallier.
[BULL. et mém. de la Soc. méd. des hôp. de Paris, 1872, VIII, pp. 57–59.]

Ellis (W. H.)
[MED. Times & Gaz., 1866, II, pp. 142–143.]

Ensor (S. R.)
[LANCET, 1831–32, I, p. 620.]

Fabas. Souvenirs de 1832. Trois cas de choléra asiatique guérir par l'emploi combiné et simultané des antispasmodiques, des alcalins, des sédatifs et des révulsifs. 8°. *Tarbes* [1854].

Fabré-Palaprat.
[GAZ. des hôp., 1835, IX, p. 228.]

Fairbrother (W. M.)
[LANCET, 1848, II, p. 125.]

Fenner (E. D.)
[N. O. Med. & Surg. Jour., 1848-49. V [illegible] 810.]

Fokker (A. A.)
[GENEESK. Courant, Tiel, 1848, No. 43.]

Foote (G.)
[BRITISH Med. Jour., 1871, II, p. 352.]

Forrest (J.)
[LONDON Med. Gaz., 1831, VIII, pp. 657–[illegible]

Fox (W.) *and* **Ringer** (S.)
[MED. Times & Gaz., 1866, II, pp. 39[illegible]

François (V.)
[GAZ. méd. de Paris, 1832, III, p. 784.]

Fraser.
[MED. Times & Gaz., 1866, II, pp. 59–6[illegible]

Friedländer.
[BERL. klin. Wochenschr., 1873, X. p. 4[illegible]

Fritz.
[MED. Correspbl. d. württ. aerztl. Verei[illegible] pp. 119–120.]

Gardner (H.)
[LANCET, 1849, I, n. s., p. 12; *also, in* MED. [illegible] 1851, III, n. s., p. 77.]

George (H.)
[LONDON Med. Gaz., 1832, X. pp. 413–4[illegible]

Goodfellow.
[LANCET, 1833, II, p. 311.]

Goyard.
[BURGGRAEVE, Répert. de méd. domest[illegible] pp. 263–265.]

Graham (C. W.)
[EDINB. Med. & Surg. Jour., 1832, XL[illegible] 6–10.]

Grant (N.)
[LOND. Med. & Phys. Jour., 1831, XI, n. s[illegible] 290.]

Greenhow.
[MED. Times & Gaz., 1866, II, pp. 5[illegible] 393.]

Grove (J.)
[LANCET, 1849, II, p. 425.]

Guckelberger *und* **Elben.**
[MED. Correspbl. d. württemb. aerztl. V[illegible] 1854, XXIV, pp. 251–254.]

Gübner (I.)
[MEDYTZYNSKIY Viestnik, St. Peters[illegible] VI, pp. 547–548.]

Guersent *et* **Baudelocque.**
[GAZ. des hôp., 1833, VII, pp. 379–381.]

Haden (F. S.)
[LONDON Med. Gaz., 1848, XLII, pp. 637–[illegible] 675.]

——— Case-taking in cholera cases.
[LANCET, 1865, II, p. 469.]

Handvogel.
[GAZ. des hôp., 1849, p. 552.]

Hart (W. B.)
[LANCET, 1848, II, p. 419.]

Hayward (G.)
[MED. Mag., 1834, III, pp. 251–256.]

Hencke (C.)
[AMER. Homeop. Obs., 1871, VIII, p. 553.]

Hodgson (J.)
[LONDON Med. Gaz., 1849, XLIII, p. 478.]

Hollifield (H. N.)
[ATLANTA Med. & Surg. Jour., 1856, I, p. 269.]

Hooker (C.)
[BOSTON Med. & Surg. Jour., 1833, VIII, pp. 378–381.]

Howard (J. C.)
[BOSTON Med. & Surg. Jour., 1833, VII, pp. 282–285, 351–352.]

Hufeland (F.) Entscheidung der orientalischen Cholera durch eine heilsame Metastase, deren Unterdrückung tödtliche Folgen hatte.
[JOUR. d. prakt. Heilk., 1832, LXXIV, pp. 131–133.]

Jackson (J., *jr.*)
[MED. Mag., 1833, VI, pp. 174–177.]

Johnson.
[LANCET, 1866, II, p. 547.]

Kirby (J.)
[DUBLIN Jour. of Med. Sci., 1839, XVI, pp. 283–284.]

Lane (J. W.)
[MED. Circular, 1865, XXVII, pp. 131–132, 191.]

Langley (J.)
[LONDON Med. & Surg. Jour., 1835, VI, pp. 54–55.]

Lawson (W.)
[LANCET, 1854, II, n. s., p. 145.]

Lelut (F.)
[JOUR. univ. et hebd. de med. et de chir. prat., 1832, VIII, pp. 73–80.]

Little.
[LONDON Med. Gaz., 1848, XLII, pp. 1008–1015.]

Little (P. C.)
[DUBLIN Med. Press & Circ., 1866, II, pp. 119–121.]

Lloyd (W.)
[EDINB. Med. & Surg. Jour., 1821, XVII, pp. 527–529.]

Lombard.
[L'UNION méd., 1849, III, p. 238.]

Lorain (P.)
[GAZ. méd. de Paris, 1866, XXI, pp. 765–767.]

Lumina (P.)
[GAZ. med. it. Lomb., 1849, II, 2a s., pp. 185–187.]

Mabit.
[JOUR. sect. de méd. Soc. acad dépt. Loire-Inf., 1836, XII, pp. 48–50.]

M'Cormack (M. J.)
[LANCET, 1846, II, pp. 145–146.]

Machelard.
[GAZ. des hôp., 1853, pp. 39–40.]

M'William (J. O.)
[LONDON Med. Gaz., 1848, XLII, pp. 1031–1035.]

Madge (H.)
[LANCET, 1857, II, n. s., p. 190.]

Mann (J.)
[LANCET, 1836–37, II, pp. 815–816.]

Mareschal.
[JOUR. sect. de méd. Soc. acad. dept. Loire-Inf., 1834, X, pp. 144–150.]

Marsden (W.)
[LONDON Med. & Surg. Jour., 1833, III, pp. 763–764.]

Martin (P. W.)
[BOSTON Med. & Surg. Jour., 1850, XLI, pp. 97–101.]

Mascherpa (G.)
[GAZ. med. it. Lomb., Milano, 1857, II, 4a s., pp. 17–20, 45.]

Masfen (G. B.)
[LANCET, 1849, II, n. s., pp. 505–506.]

Masse *et* **Roussel.**
[REVUE d. thérap. méd.-chirurg., 1875, pp. 18–20.]

Meigs (J. F.)
[MED. Examiner, 1855, VII, n. s., pp. 402–404.]

Meldon (A. S.) The cholera in Paris. Cases noted in the Hôtel-Dieu.
[DUBLIN med. Press, 1865, XVI, n. s., p. 413.]

Menard (J. F.)
[GAZ. des hôp., 1853, p. 80.]

Meza.
[REVISTA med.-quirûrg., Buenos Aires, 1874, X, pp. 303–304, 319–320, 377–378.]

Mitchell (J. T.)
[LANCET, 1831–32, I, pp. 885–886.]

Morehead.
[TRANS. Med. & Phys. Soc., Bombay, 1844, VII, pp. 80–94.]

Mosse.
[DUBLIN Med. Press, 1849, XXI, p. 150.]

Moure.
[JOUR. univ. et hebd. de méd. et de chir. prat., 1832, VII, pp. 77–79.]

Münzenthaler.
[JOUR. der pract. Heilk., 1830, LXXI, pp. 107–111.]

Mullally (B.)
[DUBLIN Med. Press, 1846, XV, p. 264.]

Myers (R. P.)
[NORTH WESTERN Med. & Surg. Jour., 1872–73, III, pp. 380–383.]

Namias (G.) Cenni intorno a 177 colerosi curati nell'anno 1836.
[GIORN. p. serv. ai progr. di patolog., Venezia, 1837, VII, pp. 298–329.]

Oliver (J. R?)
[LANCET, 1854, II, n. s., p. 301.]

Orfila *et* **Barruel.**
[ANN. d'hygiène pub., Paris, 1833, IX, 1e s., pp. 405, 410.]

Patrix.
[GAZ. des hôp., 1833, VII, pp. 127–128.]

Pavy (F. W.)
[LANCET, 1865, II, pp. 144–145.]

Peck (G. M.)
[N. O. Med. & Surg. Jour., 1848–49, V, pp. 810–811.]

Péger.
[GAZ. des hôp., 1833, VII, pp. 315–316.]

Perdrix.
[GAZ. des hôp., 1832, VI, pp. 70, 520.]

Pike (T.)
[LANCET, 1867, II, p. 53.]

Pinckard (R.) Reports and statistical tables of the cases at the cholera hospital of St. Giles's, in the Fields, in 1832.
[LANCET, 1849, I, n. s., pp. 290–293.]

Plimmer (G.)
[MED. Times, 1848, XVIII, p. 321.]

Popham (W. H.)
[MED. Times, 1849, XIX, pp. 673–674; *also, in* LANCET, 1849, II, p. 14.]

Prausnitz (M. S.) * Cholera indica affectorum historiae quinque notatu dignae. 12°. *Berolini* [1832]. L.

Puccianti (G.) Intorno ai casi di cholera curati nello spedale provvisorio di Pisa dall'Agosto al Novembre del 1854. 8°. *Firenze*, 1855.

Purcell (F. A.) Cholera. A report of thirty-eight cases of cholera occurring consecutively in the city of Cork during the outbreak of this year (1866); recording the first cases and introduction of the epidemic.
[DUBLIN Quar. Jour. of Med. Sci., 1867, XLIV, pp. 253–259.]

Ramière. Choléra avec récidive.—Emploi successif de la méthode des émissions sanguines locales et de l'ipécacuanha.—Guérison.
[JOUR. univ. et hebd. de méd. et de chir. prat., 1832, VIII, pp. 382–385.]

Reid (J. S.)
[DUBLIN Med. Press & Circ., 1866, II, pp. 432–435.]

Ricobelli (P.) Storie di alcuni casi di cholera morbus con alcune annotazioni relative alla stessa malattia.
[GIORN. p. serv. ai progr. di patolog., Venezia, 1837, VII, pp. 470–529.]

Robards (Z. T.)
[TRANSYLVANIA Jour. of Med., 1834, VII, pp. 334–336.]

Robertson (R.)
[LANCET, 1866, I, p. 575.]

Robinson (C. H.)
[LANCET, 1872, II, p. 473.]

Rodet (A.)
[GAZ. méd. de Paris, 1848, III, 3e s., pp. 708–712.]

Röbbelen (A. H.)
[DEUTSCHE Klinik, 1858, X, p. 372.]

Rösch.
[MED. Corresp. des württemberg. ärztl. V. 1832, I, pp. 38–40.]

Russell.
[MED. Times & Gaz., 1865, I, pp. 87–89.]

Scruggs (R. L.)
[WEST. Jour. of Med. & Surg., 1848 [illegible] 128.]

Seidler.
[MAG. f. d. gesammt. Heilk., 1833, XLIII, 536–543.]

Sestié.
[GAZ. méd. de Paris, 1833, I, pp. 453–454.]

Shaw.
[MED. Times & Gaz., 1866, II, p. 89.]

Sherman (L. W.)
[BOSTON Med. & Surg. Jour., 1833, VII, 332.]

Shorter (H. G.)
[MED. Times & Gaz., 1866, II, p. 60.]

Sibson.
[LANCET, 1853, II, pp. 310–311.]

Simpson (W.)
[PROVINCIAL Med. Jour., 1843, V, p. 2[illegible]

Slane (J.)
[INDIAN Med. Gaz., 1875, X, pp. 40–41.]

Smith (P.)
[LANCET, 1831–32, II, pp. 171–172; 1866 I

Speyer (A. F.)
[DEUTSCHE Klinik, 1853, V, pp. 231–237, 254–256, 266–267.]

Stephens.
[LONDON Med. Gaz., 1832, IX, pp. 734–[illegible]

Stürmer.
[JOUR. der prakt. Heilk., 1832, LXXV, p. [illegible]

Sutro.
[LANCET, 1853, II, p. 346.]

Sutro *and* **Weber** (H.)
[MED. Times & Gaz., 1866, II, pp. [illegible]

Sutton.
[MED. Times & Gaz., 1866, II, pp. [illegible] II, p. 348.]

Téallier.
[GAZ. des hôp., 1832, VI, pp. 54–55.]

Ussher (H.)
[MED. Times & Gaz., 1865, II, p. 454.]

Valentine (W.)
[AUSTRAL. Med. Jour., 1873, XVIII, [illegible]

Vliet (J. van der).
[NEDERL. Tijdschr. v. Geneesk., [illegible] 367.]

Walker (J. H.)
[EDINB. Med. & Surg. Jour., [illegible] 427.]

Ward (S.)
[LANCET, 1868, II, p. 77.]

Ware (J.)
[BOSTON Med. & Surg. Jour., 1833, VII, pp. 299–301.]

Weiser (M. E.)
[ALLG. militärärztl. Zeitg., Beilage zur "WIEN. med. Presse", 1866, VII, pp. 364–366, 381–383, 388–390, 396–398.]

West (J. W.)
[PROV. Med. & Surg. Jour., 1842, I, pp. 437–438.]

Whiting (J.)
[EDINB. Med. & Surg. Jour., 1820, XVI, pp. 312–313.]

Wilczkowski.
[DEUTSCHE Klinik, 1858, X, pp. 100–101.]

Wilde (W. R.)
[LONDON Med. Gaz., 1847, XL, pp. 883–889.]

Wilks.
[MED. Times & Gaz., 1865, I, p. 573; *also, in* LANCET, 1866, I, p. 709.]

Wilson (J.)
[LONDON Med. Gaz., 1832, X, pp. 603–604.]

Woodman.
[MED. Times & Gaz., 1866, II, p. 224.]

Woodworth (J. H.)
[PENINS. Jour. of Med., 1854–55, II, pp. 206–208.]

Wyatt.
[LANCET, 1867, I, pp. 267–268.]

Wylde (R. T.)
[LONDON Med. Gaz., 1848, XLII, pp. 1105.]

Yvoix (J. A.) **Rapport historique sur un cas de typhus cholérique développé dans la famille de Jean Martin . . . . accompagné de la nécropsi d'un des individus . . . . . suivi d'observations d'hygiène publique.** 4°. *Angoulême,* 1835.

Zaggl.
[AERZTL. Intell.-Bl., 1875, XXII, pp. 211–213.]

Zeller (M.)
[MED. Correspbl. d. württemb. aerztl. Vereins, Stuttgart, 1865, XXXV, p. 175.]

Zuffi (L.)
[GAZ. med. it. Lomb., 1849, II, 2a s., pp. 348–349.]

Case (A) **of cholera; with observations.**
[DUBLIN Med. Press, 1856, XXXV, pp. 225–229.]

Cases of cholera.
[MED. Times & Gaz., 1853, VII, n. s., p. 396; 1854, IX, n. s., p. 136; 1866, II, pp. 86–88, 117–118, 223; 1867, II, pp. 255–256.—BRIT. Med. Jour., 1867, II, p. 447.—LANCET, 1873, II, pp. 452–453.—MED. Press & Circ., 1873, XIII, pp. 240–241.—FORHANDL. vid Svenska Läk.-Selsk., Stockholm, 1866, pp. 187–209, 229–233, 243–244, 246.]

Cure for cholera.
[INDIA Jour. of Med. & Phys. Sci., 1838, III, n. s., pp. 276–277.]

Epidemic or Asiatic cholera. Rice-water diarrhœa.
[GALVESTON Med. Jour., 1866, I, pp. 33–39.]

Ob isliedovaniach po povodu cholery.
[MEDYTZYNSKIY Vlestnik, St. Petersburg, 1868, VIII, pp. 131–134, 183–186, 191–194, 199–203, 207–210.]

Prophylaxen ved Cholera, om Discussioner i det medicinske Selskab i Christiania.
[NORSK Mag. for Laegevid., 1865, XIX, pp. 1107–1129.]

Quadro statistico de 227 militari indocolerici curati in Roma l'anno 1867. De quali innanzi l'apertura del lazzaretto (cise a tutto il 18 Luglio) 59, el 68 nell'apposito lazzaretto aperto dal 19 Luglio al 4 Novembre dello stesso anno. 4°. [*n. d.*] C.

Table of cholera cases.
[LANCET, 1854, II, n. s., pp. 372–373.]

VI.—TREATMENT.

A.—GENERAL.

Abeille. Note sur la non-absorption des médicaments dans la période algide du choléra.
[GAZ. des hôp., 1855, pp. 339–340.]

Aguiar (A. A. de). Breve noticia sobre os granulos chinezes anti-colericos.
[JORN. d. sc. mathem., phys. e natur., 1872, IV, pp. 57–61.]

Alderson (J.) Treatment of cholera.
[LANCET, 1867, I, pp. 73–74.]

Allen (C. A.) Practical observations on the treatment of the malignat cholera.
[DUBLIN Med. Press, 1849, XXII, pp. 194–196.]

Allen (G.) Observations on the treatment of cholera.
[LANCET, 1854, II, p. 371.]

Allen (T.) Plain directions for the prevention and treatment of cholera. 8°. *Oxford,* 1848. L.
[3d ed. same year.]

Ammon (F. A.) Pharmacopoea anticholerica extemporanea. Exhibens compositiones medicamentorum a medicis experientissimis ad curam cholerae asiaticae tam internam quam externam accommodatorum. 16°. *Lipsiae,* 1832. L.

[André, *fils.***]** Premiers secours à donner aux personnes atteintes du choléra, (1854.) 8°. *Metz* [*n. d.*]

Andrews (C. A.) Report upon the treatment of cholera.
[MADRAS Quar. Jour. of Med. Sci., 1869, I, 2d s., pp. 88–99.]

Anthoine. Médecine symptomatique dans le choléra.
[REVUE méd., 1865, II, pp. 520–535, 585–598, 729–737.]

Armstrong (G. C.) Remarks on the treatment of Asiatic cholera.
[LANCET, 1848, II, pp. 236–237.]

Arnold (T. J.) Einziges Heilmittel der Cholera. Durch Gott, Kunst und Natur entstand das Balsammonika zum Wohl der ganzen Menschheit. 8°. *Heilbronn am Neckar*, 1836. L.

Auerbach (H.) Bekanntmachung an meine lieben Landsleute, wie die jetzt herrschende Krankheit, genannt Cholera morbus, vom ersten Entstehen bis zu ihrem Vergehen zu behandeln ist. 8°. *Göttingen*, 1831. L.

Autenrieth (H.) Vorschläge zur Behandlung der ostindischen Cholera.
[MED. Convers.-Bl., 1831, pp. 249–256, 257–258.]

Ayre. Lettre sur le traitement du choléra. *Paris*, 1857.

Ayre (J.) Treatment for the malignant cholera. 8°. *London*, 1833. C. L.

——— Treatment of cholera.
[LANCET, 1849, II, p. 217; 1853, I, pp. 321–322.]

——— Letter on the treatment of epidemic cholera. 8°. *London*, 1854.

——— A memoir on the treatment of the epidemic cholera, read before the members of the French Academy of Sciences; with their report thereon. 8°. *London*, 1859. L.

Bähr (E.) Anweisung zur Heilung der Cholera und Sommer-Durchfälle [Cholerine]. 8°. *New York*, 1866.

Balkers (J.) Behandlung der Cholera asiatica.
[MED. Correspbl. bayer. Aerzte, Erlangen, 1849, pp. 270–272.]

Bally. The treatment of Asiatic cholera.
[MED. Times, 1848, XVII, p. 458.]

Baly (W.) *and* **Gull** (W. W.) The various modes of treating cholera.
[LONDON Med. Gaz., 1849, XLIV, pp. 495–499.]

Bangssel (E.) Der Schumacher Haamann in Heubude und seine Wundertropfen wider die Cholera. Zweiter Bogen. Nachrichten für Jedermann. Ein Anerbieten. Ein Gesuch an alle Aerzte in Preuszen. Chemische Zergliederung der

Bangssel (E.)—continued. Haamann'schen Tropfen. Die bei Wohnung vorgefundenen Zuthaten eigene Erklärung. Zweite unveränderte Auflage. 12°. *Danzig*, 1831.

Barchewitz (E.) Die Behandlung Cholera in ihren verschiedenen Per und Graden. 8°. *Danzig*, 1831.

Barclay (A. W.) The treatment of ch
[BRITISH Med. Jour., 1866, I, pp. 561–563.]

Bardsley (J. L.) Hospital facts observations, . . . , with a compar view of the treatment of cholera 8°. *London*, 1830.

Barlow, Rees, *and* **Moxon.** Note the treatment of cases of cholera.
[MED. Times & Gaz., 1866, II, pp. 170–17

Baudrimont (E.) Observations s nature du choléra épidémique et les principaux traitements emp pour combattre cette maladie. (Ext
[COMPT. rend. d. séanc. de l'Acad. d. s. 1854, XXXIX, pp. 739–740.]

——— Note sur un mode de traitem choléra. 8°. *Paris* [1854].

Baumgärtner (K. H.) Behandlung Cholera. 8°. *Freib.*, 1832.

Beamish (W.) On the treatment cholera.
[DUBLIN Med. Press, 1849, XXII, p. 178.]

Bell (C. W.) On the treatment of ch
[PROV. Med. & Surg. Jour., 1848, pp. 706–7

Bena. Beitrag zur Behandlung der lera.
[ALLG. militärärztl. Zeitg., Beilage zur "med. Presse", 1866, VII, pp. 339–340.]

Benech (L. V. Du choléra-morbus de son traitement naturel compar traitement empirique suivi par le m chal Bugeaud. 8°. *Paris* [1849].

Bennett (J. R.) On the treatment Asiatic cholera in the stage of collap
[BRIT. Med. Jour., 1865, II, p. 444.]

Béraud (C. V.) Du traitement du léra épidémique. 4°. *Paris*, 1832.

Bergel (J.) Zur Cholera-therapie.
[ZEITSCHR. f. Natur- u. Heilk. in Ungarn, VII, pp. 49–53.]

Berton. Notes sur le choléra et son ment.
[GAZ. des hôp., 1832, VI, pp. 107–109.]

Betz (F.) Maximen zur Cholera-Beh lung.
[MEMORABILIEN, Heilbronn, 1866, pp. 1

Bianchi (G.) Sopra la cura del colera
[GIORN. venet. d. sc. med., 1855, V, pp. 561–567.]

Biernacki (C.) *et* **Czernicki** (J.) Traitement spécifique du choléra asiatique de 1865. 8°. *Marseille*, 1866.

—— Traitement du choléra.
[L'Abeille méd., 1866, xxiii, p. 230.]

Billing (A.) On the treatment of cholera.
[Lancet, 1831-32, i, pp. 652-653.]

—— On the treatment of Asiatic cholera. 2d ed. 8°. *London*, 1848. L.

—— The same. New ed. 8°. *London*, 1866. L.

—— On the nature and treatment of Asiatic cholera. 5th ed. 8°. *London*, 1875. L.

Blanc (H.) Notes pratiques sur les symptômes et le traitement du choléra.
[Comte rendu. Assn. franç. pour l'avancement des sc., 1874, pp. 802-810.]

Blaustein (A.) Mein Heilverfahren gegen die Cholera.
[Wien. med. Presse, 1866, vii, p. 798.]

Bloch (S.) Zur Choleratherapie.
[Allg. Wien. med. Zeitg., 1856, i, pp. 7, 10-11.]

Blume (C. L.) Vruchten mijner Ondervinding in het Afweren en Genezen der Cholera. 8°. *Amsterdam*, 1832.

Boardman (C. H.) The treatment of cholera.
[Northwestern Med. & Surg. Jour., 1874, iv, pp. 431-436.]

Boele (A.) [Over de Behandeling der Cholera.]
[Pract. Tijdschr. voor de Geneesk., Gorinchem, 1855, i, n. s., pp. 663-667.]

Boenninghausen (C. M. F. v.) Die Heilung der asiatischen Cholera und das sicherste Schutzmittel gegen Dieselbe, nach des Hofr. Dr. S. Hahnemann neuestem Schreiben an den Verfasser. 8°. *Münster*, 1831.

Bolle. Anleitung zur sichern und schnellen Heilung der Cholera. 8°. *Aachen.*

Borgien (H.) *Ueber die symptomatische Behandlung der Cholera. 8°. *Greifswald*, 1869. C.

Borlée (J.) Traitement rationnel du choléra épidémique.
[Bull. de l'Acad. roy. de méd. de Belgique, 1866, ix, pp. 847-883.]

—— The same. 8°. *Bruxelles*, 1866. L.

Bosch (H. van den). Eenige weinige Wenken omtrent de Behandeling der Cholera. 8°. *Rotterdam*, 1832. L.

Bossey (P.) Comparison of various modes of treatment of cholera—efficacy of sa[l]ines.
[London Med. Gaz., 1832, x, pp. 729-731.]

Bossu (A.) Traitement du choléra.
[L'Abeille méd., 1854, xi, pp. 271-273.]

Boudard (A.) Traitement curatif du choléra. 8°. *Clamecy*, 1854.

Bourgeois (X.) Du traitement préservatif et curatif du choléra. 8°. *Roubaix*, 1866.

Bourgogne. Étude sur la cachexie cholérique primitive. Traitement.
[L'Abeille méd., 1865, xxii, pp. 402-404; xxiii, pp. 3-4.]

[**Bourgogne**, *père.*] Notice à consulter par les personnes qui se trouveraient appelées à donner des soins aux malades atteints du choléra, en l'absence d'un médecin. 12°. *Valenciennes*, 1848.

—— Lettre à M. Bouillaud, sur le traitement abortif du choléra asiatique. 8°. *Valenciennes*, 1854.

Bourgogne, *fils.* Le choléra asiatique et son traitement.
[Jour. de méd., de chirurg. et de pharm., 1874, lix, pp. 519-529.]

Bourgogne (L. F.) De l'insuffisance des moyens employés jusqu'aujourd'hui contre le choléra asiatique, avec l'exposition d'une méthode nouvelle pour traiter cette maladie. 12°. *Anzin*, 1854.

Bourne (G. M.) Cholera conquered. Guide to the prevention and cure of epidemic cholera, diarrhœa, dysentery, etc. Based upon natural and simple laws. With a note to travellers and mothers. 8°. *New York*, 1849. L.

Boutigny (C. C.) Du choléra et de son traitement. 4°. *Paris*, 1872. L.

[**Brasme de Ryckère.**] Recette contre le choléra. 8°. *Valenciennes* [1854].

Brae (C. R.) On the treatment of cholera.
[Lancet, 1861, i, n. s., p. 213.]

Breuning (G. v.) Zur Heilart der Brechruhr.
[Deutsche Klinik, 1853, v, pp. 361-364.]

—— Zur Regelung der Choleratherapie.
[Zeitschr. f. Natur- u. Heilk. in Ungarn, 1853, vi, pp. 89-91, 97-100.]

—— Heilverfahren gegen die asiatische Brechruhr. Erprobt in mehrfachen Cholera-Epidemieen. 3. Aufl. 8°. *Wien*, 1865. L.

Brierre de Boismont (A.) Des premiers secours à donner aux personnes atteintes du choléra-morbus, et des moyens préservatifs. 8°. *Paris*, 1832. L.

Briquet (P.) *et* **Goupil** (E.) Coup-d'œil sur l'épidémie cholérique, au point de vue de la thérapeutique.
[Bull. gén. de thérap. méd. et chir., 1854, xlvi, pp. 26–32, 49–60.]

Brochin. Choléra.—Sa prophylaxie et son traitement.
[Gaz. des hôp., 1865, pp. 497, 509, 517.]

Broussais. Le choléra vaincu . . . . . nouveau traitement enseigne. 8°. [*Paris, n. d.*]

Brown. Heilart der choléra morbus. 8°. *Nordhausen*, 1831.

Bruck (M.) Rationelle Behandlung der Cholera und Widerlegung der herrschend gewordenen falschen Ansichten über die Natur und Heilung derselben, nebst einem Anhange über den Character, mit welchem sie in Berlin auftritt. 8°. *Berlin*, 1831. L.

Brückner (C.) Behandlungsweise der Cholera asiatica.
[Deutsche Klinik, 1873, xxv, pp. 326–327; 1674, xxvi, pp. 85–86, 326–327.]

Brünninghausen (H. J.) Von der Heilung der asiatishen Cholera durch ein bekanntes, einfaches, naturgemässes Mittel. 8°. *Würzburg*, 1832.

[Buchanan (T.)] Treatment of cholera.
[London Med. Gaz., 1839, x, pp. 441–443.]

Burdach (E.) Belehrung für Nichtärzte über die Verhütung der Cholera. Im Auftrage der Sanitäts-Kommission zu Königsberg verfasst. 8°. *Königsberg*, 1831. L.

Byrd (H. L.) Suggestions for the treatment of the algid stage of cholera.
[Phila. Med. Times, 1873, iii, p. 302.]

Carr (A.) Remarks upon the theory and treatment of Asiatic cholera.
[Lancet, 1849, i, n. s., p. 67.]

Canstatt (C.) Darstellung und kritische Beleuchtung des Wesens und der bis jetzt aufgefundenen Behandlungsweisen der ostindischen Brechruhr, (Cholera). 8°. *Regensburg*, 1831. L.

Casan (D. J.) Consejos populares sobre la curacion y prevencion del cólera-morbo asiatico. 2a ed. 8°. [*n. p.,*] 1854. L.

Cayol (J. B.) Instruction pratique sur le régime et le traitement du choléra-morbus épidémique au printemps de 1832.
[Revue méd. franç. et étrang., 1832, ii, pp. 178–185.]

——— The same. 1e et 3e éd. 8°. *Paris*, 1832. L.

Caseneuve (J. B.) La planche de salut. Méthode contre le choléra-morbus et révélations sur les preuves de guérison de peste, de fièvre jaune et de choléra-morbus [etc.] 8°. *Marseille*, 1837.

Chabot (E.) On the treatment of cholera.
[Lancet, 1859, ii, n. s., pp. 209–211.]

Chavasse (C. A.) Treatment of cholera.
[Lancet, 1853, ii, pp. 354–355.]

Chitty (A. J. J.) Observations on the treatment of cholera.
[Lancet, 1853, i, n. s., pp. 282–283.]

Clanny (W. R.) Mode of treating the four stages of cholera.
[Lancet, 1831–32, i, pp. 653–654.]

Clay (D. M.) Cholera—pathology and treatment.
[Southern Jour. of Med. Sci., 1866, i, pp. 625–632.]

Coillot (N.) Observations médicales d'un officier de santé. Simple note sur un nouveau traitement du choléra. 8°. *Besançon*, 1866.

Coldstream (J.) Note on the treatment of cholera by the Chinese.
[Month. Jour. of Med. Sci., 1848, viii, pp. 62–64.]

Colin (C.) Instruction sur le choléra-morbus, crainte exagérée qu'inspire cette maladie, préservatif et traitement qu'elle exige. 8°. *Paris*, 1831.

Comarmond. Administration du département de Lyon. Instruction ou manuel à l'usage des gens du monde, pour reconnaître, prévenir et traiter le choléra-morbus en attendant l'arrivée du médecin. 8°. *Lyon*, 1832.

Cooke (T.) Treatment of cholera.
[Med. Times, 1850, i, n. s., pp. 286–287.]

Copes (J. S.) Epidemic cholera in 1854. The late Professor Geo. McClellan. His letter on the nature and treatment of that epidemic.
[N. O. Med. & Surg. Jour., 1853–54, vi, pp. 241–242.]

Cotter (G. S.) Treatment of cholera.
[Dublin Med. Press, 1849, xxii, pp. 49–50.]

Cotting (B. E.) Cholera—its management and medical treatment.
[Boston Med. & Surg. Jour., 1866, lxxv, 489–493.]

Coulon (J. V.) Brief over de Cholera hetgeen men in de eerste Plaats te doen, wanneer men, door dezelve bevallen, niet dadelijk geneeskundige Hulp in Staat is te bekomen, en de Voorbehoedmiddelen tegen deze. 8°. *Leeuwarden*, 1832.

Courties. Guérison du choléra-morbus. 8°. *Paris*, 1832.

Cox (A. L.) The pathology and treatment of Asiatic cholera. 2d ed. 8°. *New York*, 1849. L.

Cox (W. J.) Treatment of epidemic cholera.
[MED. Circular, 1853, III, pp. 149–150, 402, 436.]

Coxe (E. J.) Remarks upon epidemic cholera, more especially in reference to the treatment proper for its different stages.
[N. O. Med. & Surg. Jour., 1849–50, VI, pp. 476–492.]

Creighton (R. O'N.) Suggestions respecting the treatment of cholera.
[DUBLIN Med. Press, 1849, XXII, p. 194.]

Cribier (A. F.) * Du traitement du choléra. 4°. *Paris*, 1851. L.

Crichton (W.) Account of the various modes of treatment adopted in cholera by the German physicians in St. Petersburgh.
[LONDON Med. Gaz., 1832, IX, pp. 491–494.]

Crimotel. Instructions sur le traitement préventif et curatif du choléra, mises à la portée de tout le monde. 8°. *Paris* [1854].

——— Traitement du choléra et moyens de s'en préserver. 12°. *Paris* [1865].

Cullerier. Le traitement du choléra-morbus à l'hôpital des vénériens.
[GAZ. des hôp., 1832, VI, pp. 118–119, etc.]

Czernicki (J.) Traitement du choléra.
[L'ABEILLE méd., 1866, XXIII, p. 252.]

Davasse (J.) De la méthode empirique et de la méthode des indications dans le traitement du choléra. Des effets de la strychnine, et de la noix vomique dans cette maladie.
[MONIT. des hôp., 1854, II, pp. 873–878, 881–884, 889–894.]

Davey (G.) The pathology and treatment of cholera.
[LANCET, 1854, I, n. s., pp. 512–513.]

Davies (D.) Practical notes on the treatment of cholera.
[LANCET, 1849, II, p. 533.]

Davis (J.) On the treatment of cholera.
[TRANS. Ohio State Med. Soc., 1867, pp. 57–69.]

Davis (N. S.) Report on the pathology and treatment of epidemic cholera.
[TRANS. Ill. State Med. Soc., 1866, pp. 64–71.]

Davis (R.) On the treatment of cholera.
[LANCET, 1855, II, n. s., p. 133.]

Debeney. Prophylaxie et traitement abortif de la fièvre typhoïde et du choléra-morbus.
[L'UNION méd., 1854, VIII, p. 504.]

Debreyne. Traitement du choléra asiatique.
[JOUR. des connaiss., 1849, XVI, p. 100.]

Dechaineux (F.) Quelques mots sur la thérapeutique du choléra.
[ARCH. belg. de méd. mil., 1851, VII, pp. 483–507.]

Déclat. Du choléra. Nouvelle méthode et deux nouveaux moyens de traiter la cholérine et le choléra. 12°. *Paris*, 1873. L.

Delahaye. Note sur le traitement du choléra épidémique.
[BULL. de l'Acad. roy. de méd. de Belg., 1848–49, VIII, pp. 1125–1131.]

Deleau, *jeune.* Du danger des opinions exclusives dans le traitement du choléra-morbus, pour servir de guide pratique aux médecins qui ont peu observé cette maladie. 8°. *Paris*, 1832. L.

Deleau (J. E., *fils.*) Documens sur le traitement du choléra.
[L'UNION méd., 1854, VIII, pp. 446–447.]

[Defontaine.] Manière d'employer le remède anticholérique du Nord. 8°. *Metz* [*n. d.*]

[Defontaine.] Recette contre le choléra (1848). 8°. *Cambrai* [*n. d.*]

——— The same. 4°. *Paris* [*n. d.*]

[Defontaine.] Remède contre le choléra de M. Def.... 18°. *Verdun*, 1854.

Delfraysse (H.) Prophylaxie et thérapeutique du choléra.
[REVUE de thérap. méd.-chirurg., 1856, IV, pp. 514–515.]

Delstanche. Du traitement du choléra d'après les indications instinctives.
[ARCH. méd. mil., 1849, III, pp. 296–304; IV, pp. 104–118.]

Demeure. Traitement préservatif et curatif du choléra-morbus. 18°. *Albi*, 1854.

Denonvilliers. Note sur le traitement du choléra-morbus pendant l'épidémie de 1832.
[BULL. gén. de thérap. méd. et chir., 1849, XXXVI, pp. 337–345.]

Dermott (G. D.) Views on the pathology and treatment of cholera.
[LONDON Med. & Surg. Jour., 1832, I, pp. 274–276.]

De Rogatis (A.) Osservazioni ed esperienze sulla cura profilattica e curativa del rame e suoi preparati nel cholera asiatico. *Napoli*, 1865.

Deschamps (F.) Notice sur le choléra et son traitement. 8°. *Caen*, 1849.

Descourtilz. Traitement du choléra-morbus aux Antilles, employé avec succès dans le choléra de Paris.
[BULL. gen. de thér. méd. et chir., 1832, II, pp. 269–273.]

Després (A.) De l'isolement des cholériques dans ses salles spéciales.
[GAZ. des hôp., 1866, p. 373.]

Desruez (R.) Traitement contre le choléra-morbus. 4°. [*Paris, n. d.*]

Des Guidi (S.) Traitement mutuel du choléra asiatique. 8°. *Lyon*, 1835.

Devergie (A.) Nouvel agent thérapeutique employé pour combattre certains symptômes graves du choléra-morbus.
[L'UNION méd., 1849, III, pp. 174–175.]

Devonald (E. L.) Observations on the pathology and treatment of cholera.
[LONDON Med. & Surg. Jour., 1833, II, pp. 209–210.]

Dexter (R.) Epidemic cholera: its pathology and treatment.
[CHICAGO Med. Jour., 1866, XXIII, pp. 351–354.]

Dickson (S.) On the treatment of cholera.
[MED. Times, 1849, XIX, pp. 279–280.]

Dingham (J.) On cholera and its treatment.
[MED. Times, 1849, XX, p. 345.]

Dissel (J. A. van). Eenige Opmerkingen omtrent de Behandeling der Cholera.
[NEDERL. Tijdschr. v. Geneesk., 1866, I, pp. 65–66.]

Djörup (F.) [Bemaerkninger om Choleraens Behandling.]
[UGESKR. for Laeger, 1853, XIX, pp. 145–155.]

Dubini (A.) Alla I. R. delegazione di Milano (ufficio sanitario) communicazione relativa alla cura dei choleroci nello stato algidocianotico.
[GAZ. med. it. Lomb., 1849, II, 2a s., pp. 369–371.]

Duchaussoy (A. P.) * Essai pratique sur l'absorption des médicaments dans le choléra. 4°. *Paris*, 1854. L.

Duchesne-Duparc. De l'efficacité du traitement anticholérique d'Alibert, à l'hôpital St.-Louis, pendant l'épidémie de 1832. Suivi de considérations pratiques sur les soins particuliers qu'exige la convalescence des cholériques. . . . . 8°. *Paris*, 1849.

Duclos (P.) Communications sur le choléra. Notes pour servir au traitement du choléra.
[L'UNION méd., 1865, XXVIII, 2e s., pp. 180–183.]

Dugas (T.) Études sur le traitement du choléra-morbus épidémique. 8°. *Marseille*, 1849.

Dupuy. Traitement du choléra. *Paris*, 1865.

Durant. Mémoire sur le traitement du choléra épidémique. Rapport de M. Lequime.
[BULL. de l'Acad. roy. de méd. de Belgique, 51, X, pp. 372–374.]

Dyes (A.) Die rationelle Heilung der Cholera.
[DEUTSCHE Klinik, 1867, XIX, pp. 445, 462, 47

——— The same. 8°. *Hildesheim*, 186

Dyke (T. J.) Treatment of cholera
[MED. Times & Gaz., 1866, II, p. 128.]

Earle (J. W.) Account of the method of treatment adopted in cholera, at Hollowell and Earsdon, and which proved eminently successful.
[LONDON Med. Gaz., 1832, X, pp. 46–51.]

——— Treatment of cholera.
[LONDON Med. Gaz., 1832, X, pp. 739–75

Eckart. Zur Behandlung der Cholera.
[AERZTL. Intell.-Bl., 1865, XII, pp. 713–714.]

Eichmann. Mittheilungen aus der Praxis Cholera.
[ALLG. med. Central-Zeitung, 1854, LXII, pp. 777–780.]

Emmett. Treatment, and theories Asiatic cholera.
[LANCET, 1849, I, pp. 66–67.]

Erb (J.) Der Selbstarzt in der Cholera oder keinerlei Furcht vor der Brechruhr. Deutliche Beschreibung eines sicheren untrüglichen Heilverfahrens, bei dessen Anwendung gegen die Cholera noch kein Todesfall vorgekommen ist, und auch keiner vorkommen kann. 2. Aufl. 8°. *Wien* [n. d.]

Escallier. Convient-il d'interdire l'emploi des vomitifs et des purgatifs en temps de choléra ? 8°. *Paris*, 1849.

Evans (W. P.) Cholera [and its treatment].
[MED. Circular, 1853, III, pp. 423–424.]

Ewertz (J. U.) Ueber eine, bei glückliche, zu Dünaburg befolgte Behandlung der asiatischen Cholera. An einem Sendschreiben des Dr. Ewertz an den Dr. von Gräfe. 8°. *Pyrmont*, 18

——— The same. [In English.] 8° *don*, 1831.

Fairbrother (W. M.) On the treatment of malignant cholera.
[LANCET, 1849, II, n. s., pp. 329–330

Falc (N.) *Essai sur le traitement du choléra. 4°. *Montpellier*, 1866. L. C.

Fallani (L.) Cenni sulla cura della coléra.
[Gaz. med. ital. Tosc., Firenze, 1855, I, 3a s., pp. 245-248, 253-255, 261-264, 269-271, 277-281.]

Faust (B. C.) Faust's guide to health, with remarks on the cholera. 8°. *London* [*n. d.*] L.

[Felix.] Choléra-morbus. Conseils aux familles. Premiers soins à administrer au début de la maladie. 8°. *Paris* [1849].

Fenger (E.) Jagttagelser om Behandlingen af den asiatiske Cholera.
[Ugeskr. for Laeger, 1853, XIX, pp. 97-111.]

Ferrand (A.) Indications thérapeutiques du choléra.
[L'Union méd., 1875, XVI, 3e s., pp. 462-465.]

Ferrario (G.) Istruzione al popolo per curarsi dal cholera asiatico. 2a ed. 8°. *Milano*, 1854. L.

Fiévée de Jeumont (F.) Nouvelle étude pratique sur le traitement du choléra sous toutes ses formes, utile aux familles et nécessaire aux médecins qui n'ont pas été témoins plusieurs fois de cette fatale épidémie. 8°. *Paris*, 1854. L.

Fiévet. Traitement du choléra.
[Revue de thérap., 1855, III, pp. 625-626.]

Fife (G.) On the treatment of spasmodic cholera.
[Prov. Med. & Surg. Jour., 1843, VI, pp. 128-130.]

Finley (C. A.) Treatment of cholera.
[Med. Exam., Phila., 1849, V, n. s., p. 524.]

Fischer (G. A.) *De choleræ asiaticæ therapia nonnulla. 16°. *Berolini* [1833.] L.

Flies (E. L.) Kurzgefasste Mittheilung einer sichern Behandlungsart der Cholera, nach vielfältig darüber gemachten Erfahrungen. 8°. *Berlin*, 1831.

Foissac. Note sur le traitement du choléra.
[L'Union méd., 1865, XXVIII, 2e s., pp. 49-55.]

Forsayeth (R. M.) Treatment of Asiatic cholera.
[Canada Med. Jour., 1866, II, pp. 565-568.]

Fränkel (A.) Zur Behandlung der Cholera.
[Wien. med. Presse, 1866, VII, p. 895.]

Franceschi. Note sur le traitement du choléra épidémique.
[Bull. de l'Acad. roy. de méd. de Belgique, 1848-49, VIII, pp. 454-456, 1059-1060.]

Francis (C. B.) The treatment of cholera.
[Indian Med. Gaz., 1868, III, pp. 99-101.]

Francis (C. R.) On the treatment of cholera.
[Lancet, 1855, I, n. s., pp. 248-249.]

Franck (C.) Choléra; prophylaxie; traitement.
[France (La) méd. et pharm., 1854, I, pp. 131-135.]

Fraser (P.) Practical remarks on the treatment of Asiatic cholera.
[London Med. Gaz., 1848, XLI, pp. 363-366, 494-496.]

[Frémanger.] Notice sur la marche à suivre dans le traitement du choléra. 8°. *Metz* [1849].

Fremy. Note sur le traitement du choléra-morbus.
[Monit. des hôp., 1854, II, pp. 785-787.]

Fuentes (M. M. de) Méthode brève et simple pour guérir ou prévenir l'épidémie régnante connue sous le nom de choléra-morbus. 8°. *Paris*, 1865.

Fuller (H. W.) On the treatment of cholera and choleraic diarrhœa.
[Med. Times & Gaz., 1854, IX, n. s., pp. 169-170.]

G[alau] de C[uendias]. Un mot sur le choléra, traitement rationnel de cette maladie, moyens simples de s'en préserver. 8°. *Toulouse*, 1835.

Gardes (J. J.) Remède qui guérit l'épidémie régnante; par M. Morvay . . . . et employé avec le plus heureux succès par M. Fraissinet. 1. Lettres de MM. Morvay et Fraissinet, ... 2. Lettre du Dr. Lévicaire . . . 8°. *Nîmes*, 1854.

Gardner (J.) Treatment of cholera.
[Brit. Med. Jour., 1865, II, pp. 468-469.]

Gaskell (S.) An attempt to account for the various methods adopted in the treatment of malignant cholera.
[Edins. Med. & Surg. Jour., 1834, XLII, pp. 75-81.]

Gaskoni (J. S.) Non-medical treatment of cholera.
[London Med. Gaz., 1832, IX, pp. 176-177.]

Gason (J.) On the treatment of cholera.
[Lancet, 1866, II, p. 96.]

Gasse (A.) De Cholera. Opmerkingen naar Aanleiding van G.J.Mulder's Werk: De natuurkundige Methode en de Cholera. 8°. *Amsterdam*, 1867. L.

Gaudin de la Coffinière. Note sur le traitement du choléra.
[Bull. gén. de thérap. med. et chir., 1854, XLVII, pp. 88-90.]

Geary (J. F.) Epidemic cholera: its modes of treatment; their respective

Geary (J. F.)—continued.
results; with directions for prevention; and what to do in cases of sudden emergency. 8°. *San Francisco*, 1866. L.

Gelpke (J. H. F.) Mijn Plan ter Behandeling van de epidemische Cholera, wanner dezelve in onze Gewesten, op het platte Land, verschijnen mogt.
[PRACT. Tijdschr. v. d. Geneesk., Gorinchem, 1832, pp. 374–376.]

Gendrin (A. N.) Die Cholera und ihre rationelle Behandlung. Uebersetzung aus Gendrin's "Monographie du choléra-morbus épidémique de Paris". 2te Aufl. 8°. *Köln*, 1849. L.

George (J.) Observations on the treatment of cholera, with cases.
[LONDON Med. Gaz., 1849, XLIV, pp. 1094–1098.]

Gerhard. Zur Therapie der Cholera.
[ZEITSCHRIFT für Erfahrungsheilkunst, Berlin, 1848, II, pp. 215–218.]

Gibb (G. D.) On the successful treatment of cholera in Canada.
[LANCET, 1854, I, n. s., pp. 5–6.]

Gillkrest (J.) Cholera gleanings, a family hand book. 8°. *Gibraltar*, 1848.

Giraud (R.) On the treatment of cholera.
[PROV. Med. & Surg. Jour., 1849, pp. 37–38.]

Gordon (T. W.) Treatment of cholera.
[OHIO Med. & Surg. Jour., 1852–53, V, pp. 371–379.]

Goupil. Traitement du cholera.
[REVUE de thérap. méd.-chirurg., 1854, II, pp. 94–95.]

Gower (S.) On the treatment of cholera.
[LANCET, 1848, II, pp. 155–156.]

Gmelin (F. G.) Die Behandlung der ostindischen Cholera nach ihren verschiedenen Graden, Formen und Stadien. Mit Zusätzen von Ober-Medicinal-Rath Dr. Köstlin in Stuttgart. 8°. *Tübingen*, 1832. L.

Gorlier (J.) Du choléra morbus épidémique. Traitement véritablement préventif. I^re^ parte. Nature, cause, traitement. II^e^ parte. Correspondance avec la presse médicale. 8°. *Paris*, 1856. L.
[2d ed., 1866, L.]

Goudas (A. N.) Seconde mémoire sur les succès du traitement contre le choléra-morbus. (Modern Greek and French text.) 8°. *Athènes*, 1865. L.

Gouzée. Traitement du choléra.
[ARCH. belg. de med. mil., Bruxelles, 1855, XV, pp. 69–72.]

Graf (v.) Die Behandlung der Diarrhöen während der Cholera-Epidemie.
[AERZTL. Intell.-Bl., München, 1873, XX, pp. 525–527.]

[Grand-Boulogne (A. de).] Médication et renseignements utiles à l'époque de le choléra episte. (1865.) 8°. *Paris* [n.d.]

Grangé. Ueber Behandlung der Cholera.
[DEUTSCHE Klinik, 1857, IX, pp. 308–309.]

Greenhow (E.) Treatment of cholera: with cases.
[LONDON Med. Gaz., 1832, IX, p. 581.]

——— Observations on the nature and treatment of cholera.
[EDINB. Med. & Surg. Jour., 1835, XLIII, pp. 336–359.]

Greenhow (E. H.) On the treatment of cholera.
[MED. Times & Gaz., 1854, IX, n. s., pp. 234–23?]

Grigg (T.) Results of the treatment of cholera.
[LANCET, 1839–33, II, pp. 111–112.]

Grimaud de Caux (G.) Du choléra: le moyen de s'en préserver et de son traitement specifique. 4°. *Paris*, 1866. L.

Grünberg (L.) Ueber die Heilung der jetzt epidemisch Cholera. 8°. *Warschau*, 1848.

Gubler (A.) Traitement du choléra.
[BULL. gén. de thérap. méd. et chir., 1853, LIX, pp. 97–112, 145–157; *also*, reprint in 8°, Paris.]

Guerin (J.) Prophylaxie et traitement du choléra.
[GAZ. méd. de Paris, 1853, VIII, 3e s., pp. 815–839–831; 1854, IX, pp. 1–9.]

Guibert (H.) Le choléra guéri par une opération indienne praticable par tout le monde. 8°. *Paris*, 1855.

——— The same. Traduzione dal francese di P. A. de Fabianis. [1855.]

Guisan *et* **Perret.** Instruction populaire sur le choléra asiatique. 8°. *Lausanne* 1831.

Gunning (W. M.) Eene Opmerking betreffende de Behandeling van de Cholera asiatica.
[NEDERL. Tijdschr. v. Geneesk., 1866, I, pp. 325–334.]

Guttait (H. L. von). Bijdrage tot de juiste Kennis, Voorbehoeding en Behandeling der Cholera in 1847–48. Naar het Hoogduitsch. 8°. *Amsterdam*, 1848.

Guttmann. Zur Therapie der Cholera.
[ALLG. Wien. med. Zeitg., 1866, VI, p. 280.]

Guttmann (P.) Zur Therapie der Cholera.
[BERL. klin. Wochenschr., 1866, III, pp. 333–33?]

Guyon. Sur la nature et le traitement du cholera. 4°. [*Paris.*]

Hahnemann (C. F. S.) Heilung der asiatischen Cholera und Schutzmittel gegen. 8°. *Cöthen*, 1831.

Hahnemann (C. F. S.)—continued.

——— Guérison du choléra asiatique, et préservatifs contre ce fléau. 2e article. 8°. *Lyon*, 1831.

Haines (C. Y.) Practical remarks on the treatment of malignant cholera. 8°. *Cork*, 1838.

Hall (A. R.) The pathology and treatment of cholera.

[Brit. Med. Jour., 1875, I. p. 174.]

Hameau. Lettre sur le traitement spécifique du choléra, considéré comme maladie virulente.

[Revue méd., 1831, I, pp. 212-219.]

Hamlin (C.) Dr. Hamlin's essay on the cholera: preparation for its prevention and cure by eminent men who treated the cholera with unparalleled success in Europe and America in 1848, 1855, and 1865. 12°. *New York*, 1866. L.

——— Treatment and cure of cholera. 32°. *Washington*, 1866. L.

Hammer. Vorschlag eines spezifischen und rationellen Verfahrens zur sichern und schnellen Heilung der asiatischen Cholera, begründet durch Untersuchungen über das Spezifische in den Krankheiten, in den Heilmethoden und Heilmitteln. 8°. *Hanau*, 1831.

Hancorn (J. R.) On the treatment of Asiatic cholera.

[London Med. Gaz., 1848, VII, n. s., pp. 452-453.]

Harrison (J.) Treatment of the malignant cholera amongst the soldiers of the 2d battalion grenadier guards.

[Lancet, 1831-32, II, p. 597.]

——— Treatment of cholera.

[Med. Circular, 1853, III, p. 325.]

Harst. Erprobte Behandlung der Cholera. 8°. *Heilbronn*, 1831.

Hartmann (B.) Die Behandlung der Cholera.

[Aerztl. Literaturbl., Beilage zur "Allg. Wien. med. Zeitg.", 1866, XI, pp. 90-91.]

——— Ueber die Behandlung der Cholera.

[St. Petersb. med. Zeitschr., 1866, X, pp. 86-92.]

Harvey (G.) The queries of the College of Physicians.—The treatment of choleraic diarrhœa.

[London Med. Gaz., 1849, XLIV, pp. 596-597.]

Hasper (M.) Die Behandlung der epidemischen Cholera auf Theorie und Erfahrung gestützt.

[Jour. der prakt. Heilk., 1831, LXXIII, 3. St., pp. 33-81; 4. St., pp. 16-55.]

Hatin (F.) Traitement du choléra-morbus asiatique.

[Gaz. méd. de Paris, 1849, IV, 3e s., pp. 196-202, 216-221, 236-239.]

——— The same. 8°. *Paris* [1849]. L.

Hegar (J. A.) Vademecum für die Behandlung der morgenländischen Cholera, oder Materia Medica, und Handbuch, welches nach den ältern, neuern und neuesten Erfahrungen in Russland, Pohlen, Preussen, Gallicien und Ungarn, für praktische Aerzte bearbeitet worden ist. am. 4°. *Darmstadt*, 1831. L.

Helin (M.) Traitement abortif du choléra.

[Jour. de méd., de chir. et de phar., 1849, VIII, pp. 143-145.]

Henderson. Treatment of cholera.

[Edinb. Med. & Surg. Jour., 1826, XXVI, pp. 41-46.]

Hennemann (W.) Wand-Tafel zur leichten Uebersicht der gegen die Cholera bewährten Vorsichtsmaassregeln und Hülfsmittel. (2te Aufl.) *Rostock* [1831].

Henschel (A. W.) Gelegentliche Erwähnung einiger indischen Volksarzneimittel gegen die Cholera.

[Rust's Mag. f. d. gesammt. Heilk., 1831, XXXIII, pp. 464-490; 1832, XXXVI, pp. 448-507.]

Herberger (C.) Des moyens à employer avant, pendant et après l'invasion du choléra-morbus.

[Gaz. des hôp., 1831, V, pp. 223-224.]

Hermann (A.) Beiträge zur Behandlung der Cholera.

[Wien. med. Wochenschr., 1867, pp. 1219-1222, 1236-1238, 1252-1254.]

Hertz (M.) Vorschlag zu einer Heilmethode der Cholera. 8°. *Königsberg*, 1831.

Hervieux. Du choléra chez les enfans et de son traitement.

[L'Union méd., 1854, VIII, pp. 38-39, 59, 74-75, 87-88, 117-118, 132-133.]

Herzog (C. H. E.) De remediorum nonnullorum in curanda cholera epidemica abusu. 4°. *Lipsiæ*, 1831. L.

Hickman (E.) Treatment of malignant cholera.

[Lancet, 1833, I, pp. 20-21.]

Hoddick. Ueber Cholerabehandlung; insbesondere Verhütung des Choleratyphoids betreffend.

[Berlin. klin. Wochenschr., 1873, X, p. 435.]

Hönigberger (J. M.) Le choléra, traitement et guérison. 8°. *Paris*, 1859. L.

Hofer. Zur Behandlung der Cholera orientalis.

[Med. Correspbl. d. württemb. aerztl. Vereins, 1832, I, pp. 215-216.]

Hoffmann. Remède et traitement contre le choléra. (1854.) 8°. *Narbonne* [*n. d.*]

Hoffmann (A.) Le choléra. Traitement préservatif et curatif. 8°. *Paris* [1848].

——— Traitement complet du choléra, mis à la portée de tout le monde. (1849.) 8°. *Paris* [*n. d.*]

——— Guérison certaine des premiers symptômes du choléra, quels qu'ils soient. 8°. [*Paris*, 1854.]

——— Traitement anticholérique. 8°. *Bordeaux* [1854].

Hoffmann (H.) Rationelle Heilmethode der Cholera orientalis.
[MED. Conversbl., 1832, pp. 121–125.]

Hohnbaum (C.) Hausmittel zur Verhütung und Behandlung der Cholera. 8°. *Hildburghausen*, 1831.

Holroyd (A. T.) Treatment of cholera.
[LONDON Med. Gaz., 1833, XI, pp. 17–18.]

Hubbard (S. P.) Treatment of cholera.
[BOSTON Med. & Surg. Jour., 1866, LXXIV, pp. 16–17.]

Huber (C. U. J.) Over de Besmettelijkheid en de Behandeling der Cholera asiatica. 8°. *Groningen*, 1850. L.

Hübenthal (C. P. W. van). Schets en Behandeling van den oosterschen Braakloop (Cholera orientalis), van de perzische Grenzen medegedeeld. Met eene Afb. Uit het Hoogduitsch door P. J. van Wageninge. 8°. *Rotterdam*, 1831.

Hureaux. Choléra, son traitement préservatif et curatif par la médecine naturelle ; suivie de l'exposition des traitements de la médecine officielle, et de remarques critiques. 18°. *Paris* [1865].

Hussey (Z.) A comprehensive and practical treatise on the prevention and cure of epidemic cholera. 8°. *Cincinnati*, 1849. L.

Hymans (H. S.) Opmerkingen ter Geruststelling de Vrees voor den thans heerschenden Braakloop. 8°. *Rotterdam*, 1832.

Isnard (C.) Note sur le traitement du choléra.
[L'UNION méd., 1865, XXVIII, 2e s., pp. 267–269.]

Jacobovics (M.) Zur Cholera-Behandlung.
[WIEN. med. Wochenschr., 1854, IV, pp. 708–710.]

Jacques (L. H. J.) *Du traitement du cholera épidémique. 4°. *Paris*, 1859. L.

Jahn (F.) Darstellung der Erscheinungen und der Behandlung der asiatischen Cholera. 8°. *Hildburghausen*, 1831.

Jamison (D.) On the treatment of cholera.
[DUBLIN Hosp. Gaz., 1855, II, pp. 293–295.]

Jan (J.) Des premiers soins à donner aux personnes atteintes du choléra asiatique. Précédés des précautions hygiéniques qu'on doit prendre pour s'en préserver. 8°. *Le Havre* [1849].

Janssen (J. H.) Korte Verslag eener eigene Ondervinding berustende behandeling der Cholera. 8°. [1832.

Jeanneret (H.) Epidemic cholera, diarrhœa, and dysentery. Pointing out an effectual and expeditious method of cure. With cases submitted to the medical council of the board of health, during the epidemic of 1854. 8°. *Leeds* 1857. L.

Joanne. Chimiothérapie. Précis de cholléraologie, ou le choléra dévoilé, prévenir et guérir par la cholérisation physozonogénique. 8°. *Paris*, 1855.

Johnson (G.) The treatment of cholera.
[MED. Times & Gaz., 1854, IX, n. s., pp. 399–400–401.]

——— The treatment of cholera.
[MED. Times & Gaz., 1866, I, pp. 632–633.]

——— Rules for the treatment of epidemic diarrhœa and cholera.
[BRIT. Med. Jour., 1866, II, pp. 63–65.]

Johnson (R. H.) Pathology and treatment of cholera.
[OHIO Med. & Surg. Jour., 1849–50, II, pp. 506–5[illegible]

Jones (de). Treatment of cholera.
[LONDON Med. Gaz., 1832, IX, pp. 468–470.]

Jones (C. H.) How shall we treat incipient cholera ?
[BRITISH Med. Jour., 1866, I, pp. 633, 659, 6[illegible]

Jones (T.) Treatment of cholera.
[MED. Times & Gaz., 1866, II, p. 209.]

Kaliçki (St. de). Le choléra, son traitement facile et infaillible mis à la portée de tout le monde. Moyens de s'en préserver et de s'en guérir. 8°. *Paris* 1853. L.

Kildjuschewsky (P. v.) Ueber die Cholera, mit besonderer Rücksicht auf deren Heilung durch einfache Hausmittel. Nach einigen schriftlichen Aufsätzen des Verfassers. 3ter Abdr. 8°. *Berlin*, [illegible]

King (J.) On the treatment of cholera.
[MED. Times, 1846, XIV, pp. 411–412.]

Koch (K. W.) Die Kur der Cholera nach antipathischem Prinzipe. 8°. *Breslau* 1854. L.

Kolinsky. Zur Cholera-therapie.
[WIEN. med. Presse, 1866, VII, pp. 1010-1011.]

Kool (J. A.) Verwarmings-Krib, tot het Aanbrengen van drooge uitwendige Warmte. 8°. *Amsterdam*, 1832. L.

Kostial. Ueber Behandlung der Muskelkrämpfe bei Cholera.
[ALLG. Wien. med. Zeitg., 1866, XI, p. 335.]

Kreysig (F. L.) Versuch einer leichtfasslichen und ausführlichen Belehrung über die rechten Mittel, durch welche ein Jeder die Cholera von sich meistens abwenden, oder auch grösstentheils selbst heilen könne, etc. 8°. *Dresden*, 1831.

Kronser (V. N.) Studien über die Cholera und die interessantesten Daten der vorzüglichsten und zweckmässigsten Behandlungsmethoden nach dem neuesten Standpunkte der medicinischen Wissenschaft. 8°. *Wien*, 1848. L.

Krzis. Zur Cholera-therapie.
[WIEN. med. Presse, 1866, VII, pp. 1060-1061.]

Kuborn (H.) Quelques observations sur le choléra au point de vue de son traitement comme tel et dans la période dite typhoïde.
[BULL. de l'Acad. roy. de méd. de Belgique, 1866, IX, pp. 928-951.]

Kyle (J. G.) Treatment of cholera.
[MED. Counselor, 1855, I, pp. 629-631.]

Lachaume (J. B.) Le choléra vaincu, ou traitement infaillible de cette maladie. 8°. *Lyon*, 1866.

Lachmann (W.) Die Behandlung der von der Cholera Befallenen in Ermangelung schleuniger ärztlichen Hülfe. 8°. *Braunschweig*, 1831.

Lafargue (R.) On the cholera and its treatment.
[MED. Times, 1849, XX, p. 368.]

La Fontaine (A.) Conseils aux habitants des campagnes . . . . pour se préserver et se guérir du choléra épidémique. 8°. *Foix*, 1854.

Landman (N. J. B.) Cholerologische Mededeelingen.
[PRACT. Tijdschr. voor de Geneesk., 1849, XXVIII, pp. 623-640.]

Lando. Du choléra-morbus et de sa méthode curative. 8°. [*Paris*, 1832.]

Latour (A.) Communications relatives au traitement du choléra.
[L'UNION méd., 1854, VIII, p. 413.]

Leaman (E.) Cholera asiatica.
[CLINIC, 1874, VII, pp. 205-207, 218-219.]

Lebled. Traitement du choléra, période algide.
[GAZ. des hôp., 1865, p. 514.]

Lèbre (X.) Le choléra attaqué, raisonné et vaincu par un moyen très-simple. 18°. *Aix*, 1866.

Lecointe. Du traitement de la cholérine.
[BULL. gén. de thérap. méd. et chir., 1853, XLV, pp. 313-315, 481-484.]

——— Traitement du choléra.
[BULL. gén. de thérap. méd. et chir., 1865, LXIX, pp. 366-373; *also*, reprint in 8°, Paris, n. d.]

Legroux. Coup d'œil sur les indications curatives du choléra asiatique; effets de la saignée au début de la maladie.
[BULL. gén. de thérap. méd. et chir., 1848, XXXV, pp. 440-448, 481-487; *also*, reprint in 8°, Baligneolles, 1848.]

——— Quelques considérations sur le traitement du choléra, et spécialement sur l'emploi de la chaleur et du froid.
[GAZ. hebd. de méd. et de chirurg., 1853-54, I, pp. 775-778.]

Leguyer (J.) Sur l'eau anticholérique ou de la roquette. 8°. *Paris*, 1832.

Leigh. Treatment of cholera.
[MED. Times, 1849, XX, p. 246.]

Leonard (J.) Treatment of cholera.
[LANCET, 1866, II, p. 397.]

Lepetit (É.) Traitement préservatif et curatif du choléra asiatique. 8°. *Paris*, 1855. L.

Lespiau. Des prétendus spécifiques du choléra.
[L'ABEILLE méd., 1866, XXIII, pp. 233-234.]

Le Thière. Instruction sur le traitement du choléra. 1 sheet. fol. [*Paris*, n. d.] L.

Levicaire. Une indication physiologique et clinique pour le traitement de la forme lymphorrhagique du choléra épidémique indien. 8°. *Toulon*, 1865.

Le Viseur. Amtlich constatirte Thatsachen aus dem Garnison-Lazareth in Posen, die Cholera-Therapie betreffend.
[DEUTSCHE Klinik, 1866, XVIII, pp. 355-356.]

——— Choléra. Méthode curative employée à Posen.
[JOUR. de méd. et de chir. prat., 1866, XXXVII, pp. 542-544.]

Lewis (D.) On the treatment of cholera on specific principles.
[LANCET, 1849, II, n. s., pp. 426-427.]

Lewy (E.) Beiträge zur Cholera-therapie.
[WIEN. med. Presse, 1866, VII, pp. 934-936.]

Ley (J.) Traitement du choléra mis à la portée de tout le monde. 8°. *Paris*, 1865.

Lichtenstadt (J. R.) Ueber die Verhütung und Heilung der herrschenden asiatischen Cholera. Für Nichtärzte. 8°. *St. Petersburg*, 1831. L.

[*Also*, Berlin, same year.]

——— The same. [In English.] 8°. *London*, 1831. L.

Lindsey (O.) Cholera—practical remarks on various remedies.
[LONDON Med. Gaz., 1832, IX, pp. 602-603.]

——— Further remarks on the treatment of cholera.
[LONDON Med. Gaz., 1832, XI, pp. 590-591.]

Lisio (F. de'). Sul trattamento dei militari colerosi della soccorsale dell pegno. 8°. *Palermo*, 1837.

Loewenglück (J.) Einige Bemerkungen über die Prophylaxis gegen die orientalische Cholera und über die Behandlung dieser Krankheit, nach den in der soeben erloschenen Epidemie in Warschau gewonnenen Erfahrungen.
[ALLG. med. Central-Zeitung, 1832, XXII, pp. 781-783, 789-792.]

[Loget.] L'Anticholérique, ou Le médecin malgré lui et malgré la Faculté de médecine. 8°. *Paris*, 1833.
[2e éd., 1832.]

[Loget.] Prompt moyen de se guérir gratuitement du choléra. 8°. *Belleville* [1849].

Lotte. Nouveau traitement du choléra. (1854.) 8°. *Paris* [n. d.]

Lownds (T. M.) Notes on the treatment of cholera.
[BRITISH Med. Jour., 1862, II, pp. 215-216.]

——— On the treatment of cholera.
[LANCET, 1871, II, pp. 319-320.]

Lutze (A.) Anweisung zur schnellen Selbsthülfe bei der Cholera. 12°. *Cöthen*, 1851. L.

——— The same. 6. Aufl. 8°. *Cöthen*, 1866.

Lyman (H. M.) The pathology and treatment of cholera.
[CHICAGO Med. Jour., 1866, XXIII, pp. 907-922.]

McBride (A.) Treatment of cholera.
[CINC. Lancet & Observer, 1866, IX, pp. 273-286.]

McCabe (J.) Treatment of cholera.
[LONDON Med. Gaz., 1832, X, pp. 543-545.]

M'Cloy (J. W.) *and* **Robertson** (R.) On the treatment of cholera and epidemic diarrhœa; with a record of cases.
[MED.-CHIRURG. Trans., London, 1867, L, pp. 127-132; *also*, in LANCET, 1867, I, pp. 53-54.]

M'Greevy (N.) The treatment of cholera.
[MED. Circular, 1861, XIX, p. 139, 1863, XIX, pp. 151, 272.]

Mackay (G.) Remarks on the treatment of cholera in India; its pathology, the advantages of remedies which may be administered by inhalation.
[LANCET, 1849, II, n. s., pp. 602-603.]

Mackiewicz (J.) Mémoire sur le choléra épidémique et sur le traitement des prédispositions à cette maladie. *Paris*, 1857.

Maclean (W. C.) The treatment of cholera.
[LANCET, 1866, I, pp. 113-114; 1866, II, pp. 165.]

Macleod (A. C.) On the pathology and treatment of Asiatic cholera.
[LANCET, 1865, II, pp. 409-412.]

Macloghlin (E. P.) On the treatment of cholera.
[DUBLIN Med. Press, 1849, VI, pp. 252-254.]

Macloughlin (D.) On the early treatment of cholera.
[LANCET, 1861, II, p. 579.]

McSherry (R.) Remarks on the treatment of cholera.
[AMER. Jour. of Med. Sci., 1851, XII, n. s., p. 79.]

Maison. Traitement du choléra-morbus de Vienne.
[GAZ. méd. de Paris, 1832, III, p. 16.]

Malgaigne. Note comparative sur le traitement du choléra-morbus de Bologne et de Paris.
[GAZ. méd. de Paris, 1832, III, pp. 164, 165.]

Mammi (B.) Sul cholera e sulle sue indicazioni terapeutiche in genere.
[GAZ. med. it. Lomb., 1853, IV, 3e s., 3.]

Mann. On treatment of cholera.
[MED. Times, 1849, XX, p. 246.]

[Marchand (A.)] Liberté, égalité, fraternité. Avis. Le maire de la ville à l'Aigle à ses concitoyens. 1849. *L'Aigle* [n. d.]

Marlot. Avis au peuple relativement à l'épidémie actuelle de choléra. *Dijon*, 1854.

Martin-Lauzer. Traitement du choléra-morbus.
[REVUE de thérap., 1854, II, pp. 421-422.]

Martin-Lauzer—continued.

——— *et* **Cotin** (H.) Instruction pratique sur le traitement du choléra-morbus.
[Jour. des connaiss., 1849, xvii, pp. 3-23.]

Maunsell (S. E.) Treatment of cholera.
[Dublin Med. Press, 1861, iv, n. s., pp. 424-425.]

Maxwell (W.) Treatment of cholera in India.
[Lancet, 1849, ii, p. 438.]

Maxier (P. A. F.) Premiers soins à donner à un cholérique. 8°. *L'Aigle*, 1832.

Meiern (C.) Entdeckung des Geheimnisses die Cholera-Krankheit im Keime zu ersticken. 8°. *München*, 1831.

Mendini (L.) Sperimenti di confronto sulla cura del cholera indiano.
[Gaz. med. ital. prov. Veneto, 1866, ix, pp. 198-200.]

Messerschmidt (H. G.) Ueber den zweckmässigen Gebrauch der Präservative gegen die asiatische Cholera, und über die, für die erste Anwendung beim Ausbruche derselben im Hause vorräthig zu haltenden, Hülfsmittel; dem grossen Publiko gewidmet. 8°. *Naumburg*, 1831.

Mettauer (J. B.) Treatment of Asiatic cholera.
[Nashville Med. Jour., 1871, vii, pp. 241-252.]

Metz (C. A.) Haustafel der Kennzeichen und nothwendigen Vorsichts-Maassregeln gegen die Cholera, und die wirksamsten Mittel nach ausgebrochener Krankheit bis zur Ankunft der ärztlichen Hülfe. fol. *Frankfurt a. M.*, 1831.

——— Das sicherste Mittel zur Ausrottung der sogenannten Cholera asiatica, richtiger Arsenikalkrankheit (morbus arsenicalis). Ein Sendschreiben an sämmtliche Aerzte und denkende Köpfe Deutschlands über ein rationelles Prophylacticum gegen besagte Krankheitsform. 12°. *Darmstadt*, 1837.

Meunier. Sur le traitement du choléra-morbus asiatique. Rapport de M. Raikem.
[Bull. de l'Acad. roy. de méd. de Belgique, 1847-48, viii, pp. 507-513.]

Middendorp (H. W.) De Aanwending der Geneesmiddelen door de Huid bij Cholera. 8°. *Groningen*, 1866. L.

Miramonde. Thérapeutique du choléra.
[Gaz. des hôp., 1849, p. 170.]

Moon (H.) Cholera and its treatment.
[Lancet, 1848, ii, pp. 419-420.]

Moore (W. H.) On the treatment of cholera.
[Lancet, 1853, ii, p. 436.]

Moguette (J. B., *jr.*) Vrijmoedige Gedachten over het middel tegen Buikpijnen door J. van Wijk afgegeven, doch door de Prov. Comm. van Geneeskundige toevoorzigt verboden. 8°. *Rotterdam*, 1833.

Morehead (C.) Notes on the prevention and treatment of cholera.
[Lancet, 1866, i, pp. 61-63.]

[**Morvay** (J).] Copie d'une lettre du curé de Fisza-Babolna, comitat de Bersoeder (Hongrie), sur le traitement du choléra, qu'il a employé avec les plus heureux résultats. 8°. *Le Mans* [*n. d.*]

Mouton (M.) Nouvelle brochure. Plus rien à craindre du choléra ni du typhus, par une médication des plus simples et des plus naturelles, ainsi que de la médication de toutes les maladies en général. 8°. *Paris*, 1866.

Müller (F. C. J.) Rationelle Methode, die Cholera durch Mittel zu heilen, welche den jedesmaligen Symptomen entsprechen. Eine Verbindung des homöopathischen mit dem allopathischen Verfahren. Für Aerzte und Nichtärzte. 8°. *Leipzig*, 1831.

Mulder (J. S.) Eenige belangrijke Uitkomsten van de laatste Jaren ter Beantwoording van de Vraag, in hoe ver de aziatische Cholera voor eene besmettelijke Ziekte moet worden gehouden? 8°. *Groningen*, 1860. L.

Mullen (B. F.) Treatment of cholera.
[North-Western Med. & Surg. Jour., 1850-51, pp. 306-307.]

Munday (W.) On cholera treatment.
[Med. Circular, 1854, v, pp. 220, 282.]

Murray (J.) Practical deductions from experiments on the nature of epidemics; with suggestions of remedial means for treating cholera.
[Lancet, 1848, ii, pp. 477, 478.]

——— Bericht über die Behandlung der epidemischen Cholera. [Uebersetzt.]
[Oesterr. Zeitschr. f. prakt. Heilk., 1869, xv, pp. 715-718, 735-738, 754-758, 775-780.]

——— Bericht über die Behandlung der epidemischen Cholera in Ostindien. Mitgetheilt von Dr. Prieger.
[Berlin klin. Wochenschr., 1870, vii, pp. 26-27.]

Reid (D. A.) The treatment of cholera. [LANCET, 1866, II, p. 442.]

Rein (v.) Zur Therapie der Cholera. Nach den Erfahrungen des . . . . mitgetheilt von Otto.
[MEMORABILIEN, Heilbronn, 1867, pp. 132–137.]

Reiner (F. X.) Die epidemische Brechruhr; ihre Verhütung und Heilung im Nothfalle auch ohne Arzt. 8°. *Nürnberg*, 1837. L.

Remer (K. J. W. P.) *und* **Neugebauer** (L. A.) Die asiatische Cholera, ihre Behandlung und die Mittel sich gegen sie zu verwahren, nach früheren Erfahrungen und den neuesten Beobachtungen für Ärzte und Nichtärzte. 8°. *Görlitz*, 1848. L.

Rendle (J. D.) On the importance of rest in bed, as a part of the treatment of the premonitory diarrhœa of cholera.
[BRIT. Med. Jour., 1866, II, pp. 267–268.]

Renoul (F.) Le choléra-morbus combattu, médicaments propres à chaque tempérament. 8°. *Le Mans*, 1832.

Reuse (L. P.) Een Woord over de Behandeling der Cholera, aan mijne Mede-Inwoners der Gemeente Koudekerke, die bij het Ontstaan derzelve mijne Hulp moesten verlangen. 8°. *Moens*, 1833.

Reuss (F. F.) Du choléra contagieux, des moyens sûrs de guérir de cette maladie. 8°. *Paris*, 1833.

Ribaudo (A.) Metodo di cura pel cholera morbus. 8°. *Palermo*, 1837.

Richard (B.) Un mot sur le choléra actuel et son traitement. (1854.) 8°. *Nantes* [*n. d.*]

Richardson (L.) On treatment of cholera.
[MED. Times, 1849, XX, p. 246.]

Richmond (B. B.) On cholera and its treatment.
[MED. Times, 1849, XX, pp. 179–180.]

Richmond (R. K.) On the treatment of cholera.
[MED. Times, 1849, XX, pp. 225–226.]

Righini (G.) Manuale anticolerico. *Torino*, 1866.

Robert (L. J. M.) Appel aux amis de l'humanité, sur l'emploi d'un remède qui peut être, considéré comme l'antidote et le contre-poison du choléra. 16°. *Digne*, 1849.

Robertson (J. J.) Treatment of cholera.
[MED. Circular, 1854, V, p. 248; 1855, VII, p. 175.]

Robertson (W.) Some account of practice in the cholera hospital [illegible] geon Square.
[MONTH. Jour. of Med. Sci., 1849, III, pp. 394–399.]

Rochard (F.) Des avantages de la [illegible] au début de la période asphyxique algide du choléra.
[L'UNION méd., 1865, XXVIII, 2e a., pp. [illegible]

[Rondard.] Seul remède universel et sans danger contre le choléra. *Lyon* [1849].

Rooke (T. M.), **Fletcher, Heygate Thorburn,** *and* **Drysdale.** The treatment of cholera, &c.
[BRIT. Med. Jour., 1866, I, pp. 678, 681.]

Rota (A.) Sulla cura del cholera.
[GAZ. med. it. Lomb., 1867, VI, 5a s., pp. 397–402.]

——— The same. 8°. *Milano*, 1867.

Roupell (G. L.) Treatment of cholera.
[LONDON Med. Gaz., 1833, XI, p. 18.]

Rucco (J.) Mémoire sur le traitement vrai choléra-morbus . . . . précédé l'exposition des préservatifs contre maladie. 8°. *Paris*, 1849.

Ruspini (G.) Alcune note sul [illegible] 8°. *Milano*, 1867.

Russell (V. W.) On the treatment cholera.
[DUBLIN Med. Press, 1849, XXI, pp. 33[illegible]

Rust (J. N.) Brief over den [illegible] ken Aard der aziatische Cholera Alex. von Humboldt. Uit het duitsch vertaald door G. Vro[illegible] *Amsterdam*, 1832.

Sabbatini (L.) Sulla cura specifica cholera asiatico. 8°. *Roma*, 1[illegible]
[*Also, in* GIORN. veneto d. sc. med., 1[illegible] pp. 182–216.]

Saintin (A.) Traitement pour [illegible] ra. 12°. *Paris* [1849].

[Saint-Vincent (T.)] Résumé [illegible] ens qui . . . doivent . . . être [illegible] plus grande majorité des cas [illegible] usage lors de la manifestation du morbus. (1832.) 8°. *Brux*[illegible]

Sansom (A. E.) Suggestions treatment of cholera.
[MED. Times & Gaz., 1868, II, pp. 53[illegible]

Schacken. Traitement du choléra [illegible] bus. 2e éd. 8°. *Nancy* [1[illegible]
[1st edition appeared under the title sur l'épidemie de Velaine en Hay[illegible]

Schäfer. Schutz- und Heilm[illegible] die Cholera. [illegible]. [*Leipzig*[illegible]

Schäfer (H.) Bijdrage ter Behandeling der Cholera. Benevens een Woord aan mijne lieve Medeburgers, over de Besmettelijkheid der Cholera en de beste Wijze om dezelve te verhoeden; van C. W. Hufeland. (Uit de Algemeene Pruissische Staats-Couranten van den 9 en 11. Sept. 1831 vertaald.) 8°. *Nymegen*, 1831. L.

Schelt. Das von dem hollaendischen Apotheker Schelt erfundene Heilmittel gegen die Cholera. (Von dem Medicinal-Departement des Ministerium des Innern zur Veröffentlichung in der Med. Zeitung Russlands offiziell mitgetheilt.)
[Med. Zeitung, Russlands, 1835, p. 363.]

Schlesinger. Méthode curative du choléra et de la suette. 8°. *Bayonne* [1835].

—— Quelques remarques sur le traitement du choléra.
[Revue méd., 1865, II, pp. 458–460.]

—— De la valeur du stade de la réaction algide dans le choléra et de son traitement.
[Revue méd., 1865, II, pp. 670–673.]

Schlesinger (M.) Über die specifische Behandlung der Cholera. 8°. [*Berlin*,] 1831.

Schmit (A.) Heilung der asiatischen Cholera und Schützung vor derselben. 8°. *Leipzig*, 1831.

Schöckel. Zur Therapie der Cholera.
[Med. Zeitung, 1854, p. 12.]

Schouten (H. J.) Beknopte doch volledige Handleiding tot de ware Kennis en zekerste Geneeswijze van den aziatischen Braakloop. 8°. *Amsterdam*, 1834.

Schreiber (K.) Gedanken über die Cholera morbus und die Mittel sie zu bekämpfen. 8°. *Eschwege*, 1831.

Scoutetten (H.) Des moyens préservatifs et curatifs du choléra épidémique. 8°. *Metz*, 1849.

Searle (C.) On the treatment of cholera and the severe forms of fever.
[Lancet, 1842–43, II, pp. 506–508.]

Sedgwick (W.) On the nature of cholera, as a guide to treatment. 8°. *London*, 1856.

—— The same. 2nd issue. With a new section on treatment. 12°. *London*, 1866. L.

—— On the treatment of cholera.
[Lancet, 1871, II, p. 290.]

Sedgwick (W.)—continued.

—— The theory and treatment of cholera.
[Lancet, 1871, II, p. 902.]

Seitz. Ueber die Behandlung der Cholera.
[Aerztl. Intell.-Bl., 1858, V, p. 54.]

Sémanas. Note sur le traitement de la cholérine chez les enfants en particulier.
[Gaz. méd. de Lyon, 1854, VI, pp. 242–244.]

Senior. Allein sichere . . . Behandlung der epidemischen Cholera für Nichtärzte. 16°. *Graz*, 1856. L.

Sentimer (F.) Etliche Worte für Aerzte und Nichtärzte als Vorbereitung zu meiner Heilmethode cholerischer Kranken. 8°. *Berlin*, 1833.

Servière (E. G. de). Remèdes contre le choléra.
[Gaz. hebd. de méd. et de chir., 1865, II, 2e s., pp. 657–660.]

Shasted (T. W.) Treatment of cholera.
[Boston Med. & Surg. Jour., 1867, LXXV, pp. 496–498.]

Shearman (E. J.) On the rational treatment of algide cholera.
[London Med. Gaz., 1848, XLII, pp. 630–631.]

Siebenhaar (F. J.) Die ostindische Cholera, ihre Verhütung und erste Behandlung. 8°. *Leipzig*.

Siwillow (W.) Behandlung der epidemischen Cholera.
[Med. Zeitschr. Russlands, 1857, pp. 411–412.]

Skiers (E.) A sketch of a popular and novel treatment for diarrhœa, dysentery and English and Asiatic cholera; with illustrative cases of the diseases. 8°. *London*, 1849.

Skinner (T.) How shall we treat cholera?
[Brit. Med. Jour., 1866, I, pp. 587–588; II, pp. 52–55; 1868, III, pp. 234–235.]

Smith (A.) On the treatment of cholera.
[Brit. Med. Jour., 1869, I, pp. 71–72.]

Smith (J. A.) On the rational treatment of cholera asphyxia.
[Amer. Med. Gaz. & Jour. of Health, 1855, VI, pp. 200–203.]

Snow (J.) The principles on which the treatment of cholera should be based.
[Med. Times & Gaz., 1854, VIII, pp. 180–182.]

Spiess (J. S.) Schutz- und Trutzmittel gegen die asiatische Cholera: oder Anweisung, wie man alle Furcht vor dieser Seuche verscheuchen, und sich vor der letztern verwahren und sich sicher und schnell heilen kann. 8°. *Leipzig*, 1831.

Spring (A.) Note sur le traitement du choléra asiatique.
[BULL. de l'Acad. roy. de méd. de Belg., 1848-49, VIII, pp. 300-307.]

Squibb (E. R.) Advice upon epidemic cholera. 8°. *New York*, 1866. L.

Squires (W. W.), **Lane** (J. H.), **Beran** (J.), *and* **Turner** (W.) Treatment of malignant cholera at Liverpool, at the cholera hospital.
[LANCET, 1832-33, I, pp. 75-76.]

Staines (J. F.) Treatment of cholera.
[LANCET, 1872, II, p. 360.]

Stanley (E.) On the treatment of cholera.
[LONDON Med. Gaz., 1832, IX, pp. 175-176.]

Stark (J.) Treatment of cholera.
[LANCET, 1854, II, n. s., pp. 219-220.]

Stevens (W.) Observations sur le traitement du choléra. Traduit de l'anglais par Frank Nicholls. 12°. *Toulouse*, 1835.

Stewart (E.) Treatment of cholera.
[LONDON Med. Gaz., 1832, IX, pp. 406-408.]

Stoettner (M. A.) Vorschlag zur Heilung der Cholera oder Brechruhr nach physischen Prinzipien. 12°. *Nürnberg*, 1831. L.

Stokes (G.) On the treatment of cholera.
[DUBLIN Med. Press, 1849, XXI, pp. 359-360.]

Stone (W.) Cholera and its treatment.
[N. O. Med. & Surg. Jour., 1866-67, XIX, pp. 17-28.]

Strumpf. Zur Behandlung der Cholera.
[MED. Zeitg., 1854 pp. 111-112.]

Sullivan (E. W.) Treatment of cholera.
[MED. Times & Gaz., 1854, IX, n. s., p. 451.]

Tallois. Rapport sur les mémoires envoyés au concours de 1858-1860, sur la question : Discuter la valeur des diverses méthodes thérapeutiques relatives au choléra asiatique.
[BULL. de l'Acad. roy. de méd. de Belgique, 1861, IV, pp. 245-327.]

Tardieu (A.) Traitement du choléra-morbus asiatique.
[JOUR. des connaiss., 1849, XVI. pp. 45-53; *also, in* L'UNION méd., 1849, III, pp. 14-15, 18-19, 22-23.]

Taron (B.) Du choléra, moyens de le prévenir et de le combattre. 8°. *Paris*, 1849.

Taylor (G.) Treatment of blue cholera in India.
[LANCET, 1831-32, I, p. 365.]

Taylor (J. H.) Treatment of cholera.
[LONDON Med. Gaz., 1833, XI, p. 19.]

Thayer (W. H.) "Treatment of cholera."
[N. Y. Med Record, 1873, VIII, p. 326.]

Thomas (J.) Synopsis of the treatment of the malignant cholera.
[LANCET, 1831-32, I, pp. 799-800.]

Thompson (A.) Note on the treatment of blue cholera.
[LONDON Med. & Surg. Jour., 1834, IV, p. 1.]

Thouvenin. Conseils aux gens de la campagne pour se garantir du choléra, et instructions du meilleur mode de traitement à opposer à cette maladie. 12°. [1859].

Tilesius (W. G.) Jets over de Cholera en eenige Artsenijen, die eene heilzame Werking tegen dezelve oefenen. Uit het Hoogduitsch door B. Meijer. *Deventer*, 1831.

Tinn (G.) Treatment of cholera.
[MED. Times & Gaz., 1854, IX, n. s., p. 1.]

[Tissier.] Traitement préservatif du choléra-morbus par la liqueur japonaise anticholérique. 8°. *Paris*, 1849.

Tissot. Conseils au peuple sur le traitement du choléra-morbus. 8°. 1832.

Todd (S. S.) Experience in the treatment of cholera.
[CINC. Lancet & Obs., 1867, X, pp. 385-39[illegible].]

Toffoletto (G.) Saggio di terapeutica sul cholera morbus, fondata sulla dottrine delle di lui forme fondamentali. *Vicenza*, 1868.

Tourrette. Traitement du choléra.
[L'ABEILLE méd., 1861, XXI, p. 215.]

Trimble (D. B.) On the treatment of cholera.
[CHICAGO Med. Jour., 1866, XXIII. pp. [illegible].]

Tucker (J. H.) On the treatment of rhœa and cholera.
[LANCET, 1853, I, n. s., pp. 390-391.]

Tuppert (F.) Zur Cholera-Frage.
[AERZTL. Intell.-Bl., 1866, XIII, p. 307.]

Turchetti (O.) Sopra alcuni rimedi e provvedimenti proposti e da proporsi per la cura del cholera morbus.
[GAZ. med. it. Tosc., 1854, IV, 2a s. pp. 276-279.]

Turck (S. A.) La médecine du choléra. 12°. *Nancy*, 1854.

Tuson (E. W.) On the pathology and treatment of cholera.
[LANCET, 1848, II, pp. 488-489.]

Vacca. Observation sur le choléra-morbus et sur diverses maladies de l'enfance; leurs causes, symptômes et traitement à l'aide du sucre saponé. 8°. *Paris*, 1837.

:he. On the treatment of cholera.
[ST. LOUIS Med. & Surg. Jour., 1850, VIII, pp. 239, 240.]

entin. Moyen d'obtenir une réaction anche et naturelle dans le choléra.
[L'UNION méd., 1854, VIII, pp. 434–435.]

erius (A.) Exposé des méthodes de traitement du choléra asiatique, suivies pour cette épidémie, en 1854, à Arlon, à ischen et à Waltzing, et au mois d'avril 856, à Diekirch.
[JOUR. de méd., de chir. et de pharmacol., 1856, XLII, pp. 395–404.]

aseur (L.-H.) *I. Du traitement du choléra-morbus épidémique. 4°. *Paris*, 44. L.

rgé (F.) Traitement nouveau et rationnel sur l'épidémie qui règne. 8°. *Foix* [1855].

—— De l'électricité comme cause de choléra. De l'hydrothérapie comme moyen de guérison. 4°. *Foix*, 1858.

ogel. Cholera.
[MED. Correspbl. des württ. aerztl. Vereins, 1854, XXIV, pp. 342–344.]

ies (J. H.) Petit aperçu thérapeutique contre le choléra. 8°. *Paris*, 1865.

addington (J.) Remarks on the state of pathological science, illustrated by an enumeration of cholera specifics.
[LANCET, 1848, II, p. 703.]

ard (O.) The treatment of Asiatic cholera in the stage of collapse.
[MED. Times, 1848, XVII, pp. 196–197; *also, in* LANCET, 1847, II, pp. 655–657.]

are (J.) On the symptoms of cholera in New York; with some remarks on the management of the disease.
[BOSTON Med. & Surg. Jour., 1832, VI, pp. 411–419.]

aring (E.) Remarks on the treatment of cholera, with illustrative cases.
[LANCET, 1830–31, II, pp. 809–811.]

aterton (G. E.) Cholera and the public health. Remarks on the pestilence, and its progress in Europe, with important evidence in favor of a specific cure for the disease. 8°. *London*, 1852. L.

Watson. Treatment of cholera.
[MED. Times, 1842, VI, p. 62.]

—— Failure of treatment of the cholera of 1831–32.
[LONDON Med. Gaz., 1848, XLI, p. 641.]

—— Treatment of Asiatic cholera.
[LONDON Med. Gaz., 1848, XLI, pp. 701–702.]

Watson (J.) Practische Winke über die Behandlung der Cholera.
[OESTERR. med. Wochenschr., 1848, pp. 1441–1444.]

Weber (H.) Remarks on the treatment of cholera.
[MED. Times & Gaz., 1866, II, p. 141.]

Wedekind (F.) Ueber Heilung der Cholera morbus.
[MED. Conversationsblatt, 1831, pp. 118–120.]

Weinberger (R.) Pharmaco-dynamische Notizen über mehrere, während der diessjährigen Cholera-Epidemie sowohl im k. k. allgemeinen Krankenhause, als in der Privatpraxis angewendete Arzneikörper.
[OESTERR. Zeitschr. f. pract. Heilk., 1855, I, pp. 39–42.]

White (D. B.) Hints on the practicability of contracting the extension, and greatly diminishing the fatality of the malignant cholera. With practical remarks upon the most successful plans of treatment hitherto adopted in this country. In a letter addressed to the Rev. J. Collinson. Illustrative cases are appended. 8°. *Newcastle upon Tyne*, 1832. L.

Whitehead (J.) Treatment of cholera.
[MED. Times & Gaz., 1866, II, p. 189.]

Whitely (G. F.) Is the treatment of cholera empirical?
[LANCET, 1841–42, II, p. 854.]

Whittle (E.) The symptomatic treatment of Asiatic cholera. 12°. *London*, 1850. L.

Wifs (E.) Beiträge zur Behandlung der Cholera.
[VIRCHOW's Archiv, 1853, VI, pp. 60–88.]

Wilhelm. Neu entdeckte sicherste und erprobte Schutzmittel gegen die Cholera morbus, oder praktische Bemerkungen über diese Krankheit, das schützende Verfahren vor und bei derselben, so wie ihre Behandlung. Ein nöthiges Handbüchlein für Alle. 8°. *Darmstadt*, 1836.

Wilhelmi (A. P.) Die bewährtesten und auf Autoritäten gegründeten Heilmethoden und Arznei-Vorschriften über die bis jetzt bekannt gewordenen verschiedenen Hauptformen der Cholera, oder das Wissenswürdigste über die sogenannte epidemische asiatische Brechruhr, nebst einer vollständigen Pharmacopoea anticholerica. . . . . Nebst einem Anhange über die Anwendung des Chlors, der Räucherungen und die Bereitung sowohl dieser als andrer Luftreinigungsmittel. Mit einem Vorwort von L. Cernutti. 8°. *Leipzig*, 1831. L.

[redacted]

Arnaiviss [redacted] treatment of cholera.

Anweisung der Unerfahrenen, wie er behandle den entartet[en] [redacted] Leyden, wie kan erholden.

[NORSK Mag. for Lægevid., 1849.]

Aphorismen über die Behandlung der Cholera in Wien.

[MED. Conversationsblatt, 1831, p. [redacted]

Arzneiverordnung gegen die asiatische Cholera, angegeben [redacted] Sonnambüle in magnetischem [redacted]. *Würzburg*, 1831.

Asiatic cholera: deaths from [redacted] newspaper nostrums.

[LANCET, 1849, II, p. 490.]

Auszug eines dem königlich [redacted] zischen Ministerio der geistlichen [redacted] richts- und Medicinal-Angelegenheiten eingesandten, die Behandlung der Cholera betreffenden Aufsatzes [redacted] in dieser Krankheit erfahren [redacted] Beilage zu No. 74 der Hamburger Anzeigen, den 14. September [redacted]

[n. p., n. d.]

Behandlung der Cholera in [redacted] Hospitälern.

[WIEN. med. Presse, 1866, VII, [redacted]

Behandlung (Die) der Cholera [redacted] Spitälern zu Paris, während [redacted] mie im Jahre 1865.

[WIEN. med. Presse, 1867, [redacted]

[redacted]

[redacted]

[

dlung der Cholera in den verschie- i Spitälern von Paris bei der eben chenden Epidemie.
ER med. Wochenschrift, 1865, XV, pp. 1718-]

dlung (Die) der Cholera in der italklinik der Universität in Mos-

Zeitung Russlands, 1856, p. 365.]

dlung (Die) der Cholera. Von ei- Pariser Arzte.
g. med. Central-Zeitung, 1848, XVII, pp. 617-626-632.]

at über die Behandlung der Cholera ous in Berlin; erstattet von den . Heindl und Alois Martin an das glich bayerische Ministerium des rn. [Extract by Dr. Besnard.]
Z. med.-chir. Zeitung, 1848, IV, pp. 257-259, 289-290; 1849, I, pp. 1-2.]

e istruzione popolare pel caso che si uppi il cholera, publicata per cura a commissione straordinaria di sanità Milano.
Z. med. ital. prov. Veneta, 1866, IX, pp. 301-3.]

s of cholera—notes on treatment.
ED. Times & Gaz., 1866, II, pp. 140, 169-170.]

era and diarrhœa—nature and art in treatment of poisoning.
ED. Times & Gaz., 1866, I, pp. 636-637.]

lera and its treatment.
ANCET, 1848, II, p. 194.]

lera,—its treatment.
N. Y. Med. Gaz. & Jour. of Health, 1854, V, pp. 369-370.]

olera (Die) oder ostindische Brechruhr. ine für Jedermann fassliche Zusam- enstellung der wichtigsten, aus den orzüglichsten bisher über diese Krank- eit erschienenen Schriften. 8°. *Tübingen*, 1831.

oléra—son traitement.
BULL. de l'Acad. de méd., Paris, 1872, I, pp. 868, 934, 938.]

oléra, stimulant extérieur.
JOUR. de méd. et de chir. prat., 1853, XXIV, 2e s., pp. 513-514.]

holera; Studier om dens Natur og Behandling.]
[NORSK Mag. for Laegevid., 1851, V, pp. 402-417.]

holéra. Traitement.
[GAZ. des hôp., 1853, p. 579.]

holera (Die) und Herrn Jäger's Mittel.
[WIEN. med. Wochenschr., 1874, XXIV, pp. 21-22.]

holerabehandling.
[FÖRHANDL. vid Svenska Läk.-Sälsk., 1866, p. 212.]

Choléra-morbus (Le), moyens de s'en préserver, traitement pour s'en guérir. fol. *Paris* [1848].

Choléra-morbus. Moyens simples, faciles et certains de s'en préserver et de s'en guérir. 32°. *Paris* [1849].

Choléra-morbus, ou recueil des remèdes au moyen desquels on a sauvé . . . . l'empereur de Russie. 8°. *Paris*, 1832.

Choléra-morbus. Traitement. . . . . Publié par le conseil de santé de Hambourg, en août 1831. 8°. *Paris* [*n. d.*]

Choléra-morbus. Traitement de M. Rayer. 4°. *Paris* [*n. d.*]

Choleraschutz und Cholerabehandlung. Von einem Fachmanne.
[ALLG. Wien. med. Zeitg., 1871, XVI, pp. 653-654, 671-672; 1873, XVIII, pp. 5-6.]

Cholérine (De la) et de son traitement.
[GAZ. méd. de Paris, 1832, III, pp. 165-166.]

Cholérine. Méthode évacuante. Élixir amer de M. Moissenet.
[JOUR. de méd. et de chir. prat., 1865, XXXVI, pp. 552-553.]

Common (The) sense of cholera. By a practical practitioner. 12°. *London*, 1854.

Coup d'œil sur la thérapeutique du choléra.
[L'UNION méd., 1849, III, pp. 146-147.]

Diverses (Des) médications employées dans les hôpitaux, et des rapports numériques des guérisons et de la mortalité avec ces médications.
[GAZ. méd. de Paris, 1849, IV, 3e s., pp. 362-368, 381-386, 401-405.]

Eenige Opmerkingen omtrent de Behandeling der Cholera. 8°. [*Amsterdam*,] 1866. L.

Einige Worte über die Behandlung der Cholera-Morbus. Eingesandt aus Moskwa von Dr. . . . . nn.
[LITTER. Ann. der gesammt. Heilk., 1832, XXII, pp. 225-232.]

État (De l') réel de la science touchant le traitement du choléra.
[REVUE méd. chir. de Paris, 1849, V, pp. 321-323.]

Formules contre le choléra.
[BULL. gén. de thér. méd. et chir., 1865 LXIX, pp. 365-366, 411-412.]

Grain (Le) de bon sens, ou un mot à l'occasion du choléra ou de toute autre épidémie. .... Par le premier médecin de lui-même. 8°. *Paris*, 1832.

Guérison du choléra-morbus sans médecin. 12°. *Paris*, 1832.

Wilhelmi (A. P.)—continued.

——— Pharmacopoea anticholerica, oder vollständiger Apparatus Medicamentorum gegen die verschiedenen Hauptformen der Cholera. Ein Handbuch für praktische Aerzte und Chirurgen, enthaltend 283 der bewährtesten, auf Autoritäten und rationelle Heilmethoden gegründeten Arzneivorschriften. 16°. *Leipzig*, 1831. L.

Wilkinson (J.) Outlines for a proper theory and cure of cholera. 8°. *Edinburgh*, 1832.

Wilkinson (W.) On the treatment of cholera.
[LANCET, 1854, II, n. s., p. 100.]

Williams (N.) Treatment of cholera morbus.
[BOSTON Med. & Surg. Jour., 1855, LI, pp. 74–75.]

Williams (W. H.) A plain brief sketch of cholera, with a simple and economical mode for its treatment, submitted with confidence from repeated success in its application. 2d ed. 8°. *Ipswich*, 1832. L.

Wilson (H. H.) On the native practice in cholera, with remarks.
[TRANS. of the Med. & Phys. Soc. of Calcutta, 1826, II, pp. 282–292.]

Wilson (J.) Treatment of cholera in the royal hospital Haslar. 8°. *London*, 1849.

Wise (T.) Treatment of cholera.
[MED. Circular, 1854, V, p. 153.]

Woodman (W.) Treatment of the malignant cholera at St. Thomas's, Exeter.
[LANCET, 1832–33, I, pp. 81–82.]

——— Treatment of cholera.
[MED. Times & Gaz., 1853, VII, n. s., pp. 433–434.]

Worms (J.) Note sur le traitement de la période comateuse du choléra.
[GAZ. méd. de Paris, 1849, IV, pp. 256–258, 280–282.]

——— Traitement du choléra à la période prodromique.
[GAZ. hebd. de méd. et de chirurg., 1865, II, 2e s., pp. 634–635.]

Wright (J.) Treatment of the malignant cholera at the cholera hospital Westminster.
[LANCET, 1832, II, pp. 559–561.]

Wright (S.) Lecture on the treatment of the cholera of 1846.
[MED. Times, 1847, XVI, pp. 1–2.]

Wyer (G. G.) On cholera and its treatment.
[LANCET, 1849, II, p. 603.]

Zendrini. Intorno al trattamento cholera-morbus.
[GAZ. med. it. Lomb., 1849, II, 2a s., pp. [illegible]

Ziegler (J.) Die Cholera nach einfachen Methode zu überwinden. *Anklam*, 1869.

Allgemeine fassliche **Anweisung** zur kennung, Verhütung und Heilung asiatischen Cholera, nebst Anleitung über die Gefahr derselben im Allgemeinen, zur Belehrung und Beruhigung der Nichtärzte herausgegeben von praktischen Arzte. . . . Auswahl besten Mittel und Recepte gegen Cholera morbus, gesammelt aus Schriften der berühmtesten Aerzte. 12°. *Leipzig*, 1831.

Algemeen Rapport der Commissie het Onderzoeken van den Aard en meest geschikte Wijze van Behandeling van den aziatischen Braakloop. *Gravenhage*, 1832.

Analyses of communications on treatment of cholera.
[LANCET, 1849, II, pp. 315–317, 533–535.]

Anviisning for Ulægkyndige til at og behandle den ondartede Cholera til Lægehjælp kan erholdes.
[NORSK Mag. for Laegevid., 1849, III, pp. [illegible]

Aphorismen über die Behandlung Cholera in Wien.
[MED. Conversationsblatt, 1831, pp. 413–41[illegible]

Arzneiverordnung gegen die orientalische Cholera, angegeben von Somnambüle in magnetischem S[illegible] 8°. *Würzburg*, 1831.

Asiatic cholera: deaths from reliable newspaper nostrums.
[LANCET, 1849, II, p. 490.]

Auszug eines dem königlich [illegible] zischen Ministerio der geistlichen, Unterrichts- und Medicinal-Angelegenheiten eingesandten, die Behandlung der Cholera betreffenden Aufsatzes, von [illegible] in dieser Krankheit erfahrenen Ärzte. Beilage zu No. 74 der Hannoverschen Anzeigen, den 14. September 1[illegible] [n. p., n. d.]

Behandlung der Cholera in den englischen Hospitälern.
[WIEN. med. Presse, 1866, VII, pp. 910–[illegible]

Behandlung (Die) der Cholera in Spitälern zu Paris, während der Epidemie im Jahre 1865.
[WIEN. med. Presse, 1866, VII, pp. 776–[illegible]

handlung der Cholera in den verschiedenen Spitälern von Paris bei der eben herrschenden Epidemie.

[WIENER med. Wochenschrift, 1865, XV, pp. 1748–1750.]

handlung (Die) der Cholera in der Hospitalklinik der Universität in Moskau.

[MED. Zeitung Russlands, 1856, p. 365.]

ehandlung (Die) der Cholera. Von einem Pariser Arzte.

[ALLG. med. Central-Zeitung, 1848, XVII, pp. 617–622, 626–632.]

ericht über die Behandlung der Cholera morbus in Berlin; erstattet von den DDr. Heindl und Alois Martin an das königlich bayerische Ministerium des Innern. [Extract by Dr. Besnard.]

[NEUE med.-chir. Zeitung, 1848, IV, pp. 257–259, 289–290; 1849, I, pp. 1–2.]

reve istruzione popolare pel caso che si sviluppi il cholera, publicata per cura della commissione straordinaria di sanità di Milano.

[GAZ. med. Ital. prov. Venete, 1856, IX, pp. 301–305.]

Cases of cholera—notes on treatment.

[MED. Times & Gaz., 1866, II, pp. 140, 169–170.]

Cholera and diarrhœa—nature and art in the treatment of poisoning.

[MED. Times & Gaz., 1866, I, pp. 636–637.]

Cholera and its treatment.

[LANCET, 1848, II, p. 194.]

Cholera,—its treatment.

[N. Y. Med. Gaz. & Jour. of Health, 1854, V, pp. 369–370.]

Cholera (Die) oder ostindische Brechruhr. Eine für Jedermann faessliche Zusammenstellung der wichtigsten, aus den vorzüglichsten bisher über diese Krankheit erschienenen Schriften. 8°. *Tübingen*, 1831.

Choléra—son traitement.

[BULL. de l'Acad. de méd., Paris, 1872, I, pp. 808, 934, 938.]

Choléra, stimulant extérieur.

[JOUR. de méd. et de chir. prat., 1853, XXIV, 2e s., pp. 513–514.]

Cholera; Studier om dens Natur og Behandling.]

[NORSK Mag. for Laegevid., 1851, V, pp. 402–417.]

Choléra. Traitement.

[GAZ. des hôp., 1853, p. 579.]

Cholera (Die) und Herrn Jäger's Mittel.

[WIEN. med. Wochenschr., 1874, XXIV, pp. 21–22.]

Cholerabehandling.

[FÖRHANDL. vid Svenska Läk.-Sälsk., 1866, p. 212.]

Choléra-morbus (Le), moyens de s'en préserver, traitement pour s'en guérir. fol. *Paris* [1848].

Choléra-morbus. Moyens simples, faciles et certains de s'en préserver et de s'en guérir. 32°. *Paris* [1849].

Choléra-morbus, ou recueil des remèdes au moyen desquels on a sauvé . . . . l'empereur de Russie. 8°. *Paris*, 1832.

Choléra-morbus. Traitement. . . . . Publié par le conseil de santé de Hambourg, en août 1831. 8. *Paris* [*n. d.*]

Choléra-morbus. Traitement de M. Rayer. 4°. *Paris* [*n. d.*]

Choleraschutz und Cholerabehandlung. Von einem Fachmanne.

[ALLG. Wien. med. Zeitg., 1871, XVI, pp. 653–654, 671–672; 1873, XVIII, pp. 5–6.]

Cholérine (De la) et de son traitement.

[GAZ. méd. de Paris, 1832, III, pp. 165–166.]

Cholérine. Méthode évacuante. Élixir amer de M. Moissenet.

[JOUR. de méd. et de chir. prat., 1865, XXXVI, pp. 552–553.]

Common (The) sense of cholera. By a practical practitioner. 12°. *London*, 1854.

Coup d'œil sur la thérapeutique du choléra.

[L'UNION méd., 1849, III, pp. 146–147.]

Diverses (Des) médications employées dans les hôpitaux, et des rapports numériques des guérisons et de la mortalité avec ces médications.

[GAZ. méd. de Paris, 1849, IV, 3e s., pp. 362–368, 381–386, 401–405.]

Eenige Opmerkingen omtrent de Behandeling der Cholera. 8. [*Amsterdam*,] 1866. L.

Einige Worte über die Behandlung der Cholera-Morbus. Eingesandt aus Moskwa von Dr. . . . . nn.

[LITTER. Ann. der gesammt. Heilk., 1832, XXII, pp. 225–232.]

État (De l') réel de la science touchant le traitement du choléra.

[REVUE méd. chir. de Paris, 1849, V, pp. 321–323.]

Formules contre le choléra.

[BULL. gén. de thér. méd. et chir., 1865, LXIX, pp. 365–366, 411–412.]

Grain (Le) de bon sens, ou un mot à l'occasion du choléra ou de toute autre épidémie. .... Par le premier médecin de lui-même. 8. *Paris*, 1832.

Guérison du choléra-morbus sans médecin. 12°. *Paris*, 1832.

Heilung und Ausrottung [Sicherste] der asiatischen Cholera. 12°. *Leipzig*, 1831.

How shall we treat cholera?
[BRITISH Med. Jour., 1866, I, pp. 556–559.]

Hülf-Büchlein gegen die Cholera-Morbus. .... (Extr. de la Gaz. off. de Hanovre.) 8°. *Strasbourg*, 1831.

Indications (Des) rationelles dans le traitement du choléra-morbus.
[BULL. gén. de thérap. méd. et chir., 1853, XLV, pp. 555–556.]

Infallible remedies and specifics for Asiatic cholera.
[LONDON Med. Gaz., 1848, VII, n. s., pp. 510–511.]

Instructions for the treatment of epidemic cholera.
[LONDON Med. Gaz., 1848, XLI, pp. 717–720.]

Instructions of the College of Physicians for the treatment of cholera.
[LANCET, 1866, II, p. 135.]

Latest (The) treatment of cholera.
[MED. & Surg. Reporter, 1871, XXV, pp. 259–261.]

Malignant cholera,—stimulants, calomel and cold water. Contagion.
[LANCET, 1832–33, II, pp. 719–721.]

Malignant or Asiatic cholera. Deaths from reliance on useless and hurtful nostrums.
[LANCET, 1853, II, p. 304.]

Médecine populaire du choléra-morbus. .... Par un médecin allemand. 12°. *Lyon*, 1831.

Médications diverses applicables au choléra.
[JOUR. de med. et de chir. prat., 1865, XXXVI, pp. 508–514.]

Meilleur (Le) traitement du choléra, (Par l'abbé L....) 8°. *Nancy* [1849].

Mémoire sur le traitement du choléra-morbus, par M. Abeille. (Rapport de M. Gérardin.)
[BULL. de l'Acad. nat. de méd., 1852–53, XVIII, pp. 1057–1067.]

Méthode ou moyen naturel, simple, facile, ... pour détruire immédiatement le choléra. (Signé: F. D.) 8°. *Marseille*, 1865.

Militär-Cholera-Spital zu Tyrnau.
[ALLG. militärärztl. Zeitg., Beilage zur "WIEN. med. Presse", 1866, VII, pp. 355–357.]

Mittel und Methoden gegen die Cholera. Von einem Praktiker.
[WIEN. med. Presse, 1865, VI, pp. 906–907, 930–932, 977–978, 1025–1027, 1099–1101, 1219–1221.]

Mittel und Methoden bei der Behandlung der Cholera, in der Epidemie vom Jahre 1866.
[WIEN. med. Presse, 1866, VII, pp. 854–855, 878–881, 893–894, 907–910, 931–934, 960, 983–984, 1027–1030.]

Moyen de guérir du **choléra** morbus s'en préserver. 8°. *Paris* [n. d.]

Moyens (Des) préservatifs et curatifs du choléra-morbus. (Signé: B. F^re.) *Pont-à-Mousson* [1854].

Moyens simples et sûrs pour [illegible] choléra, à défaut de médecins. [illegible] *ville* [1849].

Nosology (The) and treatment of rhœa, cholerine, and Asiatic cholera.
[BRIT. Med. Jour., 1871, II, pp. 334–336.]

Note on the pathology and treatment of cholera.
[LONDON Med. & Surg. Jour., 1834, [illegible] 536.]

Note sur le choléra; teucrium [illegible] médication saline; sous-nitrate de bismuth; haschich; chloroforme.
[JOUR. de méd. et de chir. prat., 1849, XX [illegible] 197.]

Notice sur le sirop du choléra. [illegible] [1854].

Notizen zur Cholera-Therapie.
[ALLG. med. Central-Zeitung, 1866, XXXV, [illegible] 663, 669–673.]

Nouveau traitement pour le choléra [illegible] trait de "L'Émancipateur.") [illegible] *brai* [1849].

Nuovo rimedio contro il cholera.
[GAZ. med. it. Lomb., 1872, XXXII, p. [illegible]

Observations on some of the remedies proposed in cholera. Efficacy of [illegible] of lead.
[LONDON Med. Gaz., 1833, XI, pp. 251–[illegible]

Observations on the treatment of cholera.
[LONDON Med. & Surg. Jour., 1833, II, [illegible] 530.]

On the treatment of malignant cholera.
[LANCET, 1853, I, n. s., pp. 226–227.]

Overzigt van de voornaamste Maatregelen tegen de asiatische Cholera. Braakloop, en de beste Middelen om tegen te bezigen, van het Begin der Besmetting of tot aan de komst van een Geneesheer. 8°. *Groningen*, 1831.

Praktische Mittheilungen aus den [illegible] Hospitälern. [Extract from a report to the department of the interior.] Behandlung der Cholera.
[MED. Zeitung Russlands, 1858, XV, pp. 1[illegible]

Present state of knowledge on the treatment of cholera.
[LONDON Med. Gaz., 1847, XL, pp. 677–68[illegible]

Prophylaxie et traitement du choléra.
[JOUR. de méd. et de chir. prat., 1865, XXX 411–415.]

Recette infaillible contre le choléra. 12°. *Senlis*, 1865.

Remarks on the pathology and treatment of cholera.
[LANCET, 1848, II, pp. 476–477.]

Remède contre le choléra, la diarrhée et les coliques. Importation des missionnaires de l'Inde. 4°. *Toulon* [1854].

Remède efficace contre le choléra. 8°. *Versailles* [1849].

Remède pour le choléra. fol. *Saint-Cloud* [*n. d.*]

Remède très-certain du choléra-morbus. (1831.)

Remedies tried at Sunderland, in cholera—others suggested.
[LONDON Med. Gaz., 1832, IX, pp. 317–318.]

Report of the committee of the Kappa Lambda Society (New York) appointed for the purpose of preparing an account of the mode of treatment of epidemic cholera. June. Together with an additional report presented August 15, 1832. 8°. *New York*, 1832. L.

Report on the results of the different methods of treatment pursued in epidemic cholera. 8°. *London*, 1855.
[*Also, in* ASSOCN. Med. Jour., 1855, I, pp. 345–348.—BRIT. & For. Med.-Chir. Rev., 1855, XVI, pp. 137–144.]

Schützende Vorsichtsmassregeln und Heilart der Cholera morbus. Aus dem Englischen des Arztes Brown, welcher selbst die Cholera zweimal gehabt hat und sich gegenwärtig in London befindet. Eine nützliche Schrift für Jedermann. 12°. *Nordhausen*, 1831. L.

Simple (A) explanation of cholera and a rational mode of treating it. By Yod, M. D. 8°. *London*, 1866. L.

Sundheds-Collegiets Anviisning til Behandling af den indiske Cholera, dat. 19. Juli 1848.
[ARCHIV for Pharm. og techn. Chemie, 1848, V, pp. 449–450.]

Symptoms and treatment of the malignant cholera. [Report of the medical board of health of the parish of Saint Mary, Whitechapel.]
[LANCET, 1832, I, pp. 713–714.]

Thérapeutique du choléra.
[GAZ. des hôp., 1853, p. 563.—L'ABEILLE méd., Paris, 1849, VI, pp. 133–136.—L'UNION méd., 1849, III, pp. 165–166, 230, 237–238.]

Traitement curatif du choléra. 4°. [*Paris, n. d.*]

Traitement de l'épidémie cholérique. Département de l'Ariége. Arondissement de Saint-Girons. 8°. *Foix* [*n. d.*]

Traitement (Le) domestique et les préservatifs du choléra oriental. 8°. *Paris*, 1831.

Traitement du choléra dans les hôpitaux de Paris.
[BULL. gén. de thér. méd. et chir., 1865, LXIX, pp. 467–474; *also*, GAZ. des hôp., 1865, pp. 573–574.]

[**Traitement** du choléra, d'après F. V. Raspail, commençant par ces mots:] La médecine actuelle est impuissante à combattre le choléra. 4°. *St. Amand* [*n. d.*]

Traitement du choléra. Lettre du Dr. Duvard au rédacteur en chef de la "Gazette des hôpitaux," insérée dans le n° 148 (20 décembre 1849). 12°. *Caen* [*n. d.*]

Traitement du choléra-morbus. Réflexions sur les effets des traitemens employés à l'Hôtel-Dieu.
[BULL. gén. de thér. méd. et chir., 1832, II, pp. 214–223, 232–237.]

Traitement employé avec succès par une ancienne sœur de charité contre le mal épidémique appelé choléra-morbus. 8°. *Paris* [*n. d.*]

Traitement (Du) et de la prophylaxie du choléra.
[GAZ. des hôp., 1854, p. 381.]

Traitement (Du) suivi, à l'hôpital Lariboisière, pendant le cours de la dernière épidémie cholérique 1865–1866.
[GAZ. des hôp., 1866, p. 369.]

Traitements du choléra mis à la portée de tout le monde. 8°. *Paris*, 1865.

Traitements (Des) du choléra-morbus.
[GAZ. des hôp., 1832, VI, pp. 51, 53–54, 57, etc.]

Treatment of cholera and diarrhœa in the various hospitals, infirmaries, and dispensaries in the metropolis.
[LANCET, 1854, II, p. 145.]

Treatment of cholera.
[LANCET, 1830–31, p. 442; 1849, II, p. 219; 1854, II, pp. 163, 191, 268; *also, in* MED. Times & Gaz., 1853, VII, p. 375.]

Treatment of cholera at all the metropolitan hospitals.
[LANCET, 1849, II, pp. 154–159.]

Treatment of cholera on board of the "Belleisle."
[MED. Times & Gaz., 1866, II, p. 590.]

Treatment (The) of epidemic cholera
[MED. Circular, 1853, VII, pp. 131–132.]

Treatment of the premonitory diarrhœa.
[LANCET, 1849, I, n. s., p. 68.]

Ueber die Behandlung der Cholera. [Ausz. aus d. Protokoll d. deutsch. ärztl. Vereins zu St. Petersburg, Saison 1870–1871.]
[ST. PETERSB. med. Zeitschr., 1871, II, n. s., pp. 558–559.]

Ueber Heilung der Cholera. 4°. *Bückeburg*, 1831. L.

Unfehlbares Mittel gegen die Cholera. 8°. *Leipzig*, 1831.

Vorläufige Nachricht von des Hrn. [illegible] Leviseur glücklicher Methode gegen die Cholera. 8°. *Kiel*, 1831.

Vorschläge zur Heilung der orientalischen Cholera.
[JOUR. der prakt. Heilk., 1831, LXXIII, pp. 103–131, 103–125, 122–124.]

What are the remedies for cholera?
[LANCET, 1848, II, p. 49.]

Zur Therapie der Cholera.
[ALLG. med. Central-Zeitung, 1835, XXXIV, pp. 529–530, 1865, XXXIV, pp. 697–699.]

B.—SPECIAL.

Acids.

Bodington (G.) The acid treatment of cholera.
[LANCET, 1854, II, n. s., p. 390.]

Boys (S.) A remedy and prevention for the cholera morbus; pointing out the properties of oils and acids, and their good effects in this disease. Illustrated by the remarks of a physician; and also some well-authenticated cures, medical correspondence, &c., &c. 8°. *London*, 1832. L.

Reeves (W.) The treatment of cholera by acids.
[LANCET, 1853, II, n. s., p. 354.]

Tucker (J. H.) On the use of vegetable and mineral acids, in the treatment preventive, and remedial, of cholera, and other epidemic disorders of the bowels. 8°. *London*, 1854. L.

Worms. Note sur le traitement de la première période du choléra confirmé par les acides; suivie de propositions relatives à la cause et à la nature de cette affection.
[GAZ. méd. de Paris, 1849, IV, 3e s., pp. 525–526.]

Worms. De l'emploi des acides concentrés dans le choléra.
[REVUE de thérap., 1854, II, pp. 34–36.]

Traitement (Du) de la diarrhée prodromique du choléra par l'emploi des acides.
[BULL. gén. de thérap. méd. et chir., 1853, XLV, pp. 556–559.]

Acid (*Acetic*).

Lebatard. Note sur l'emploi du sirop acétique et de l'acide acétique, comme moyen de déterminer la réaction au début du choléra.
[GAZ. méd. de Paris, 1849, IV, 3e s., pp. 323–324, 441–443.]

Acid (*Carbolic*).

Bogdán (M.) Anwendung der Karbolsäure bei der Cholera.
[WIEN. med. Presse, 1874, XV, pp. 175–[illegible]]

Hasper. Schon wieder ein neues Mittel gegen die Cholera.
[WIEN. med. Presse, 1873, XIV, pp. 1303–1304]

Rothe. (C. G.) Carbolsäure innerlich gegen Diarrhöen und Cholera.
[BERLIN. klin. Wochenschr., 1871, VIII, pp. 525–526.]

Karbolzuurwater bij Cholera als preventief Middel.
[NEDERL. Tijdschr. v. Geneesk., 1867, I, p. [illegible]]

Acid (*Carbonic*).

Heidler (C. J.) Ueber die Schutzmittel gegen die Cholera, und darunter besondere über das kohlensaure Gas zum äusserlichen und innerlichen Gebrauche. 8°. *Prag*, 1832.

Acid (*Hydrochloric*).

King (A.) On the use of hydrochloric acid in cholera.
[MED. Times, 1849, XX, pp. 515–516.]

Stefano (O. de). Speciale trattamento del cholera-morbus [limonea cum idrica].
[CAMPANIA (La) med. Caserta, 1874, III, pp. 4–[illegible]]

Wiederhold. Die Zerstörung der Entleerungen Cholera-Kranker mittelst Salzsäure und chlorsaurem Kali.
[VIRCHOW's Archiv, 1866, XXXVII, p. 4[illegible]]

Acid (*Hydrocyanic*).

Curtis (J.) On the utility of hydrocyanic acid in English cholera.
[LANCET, 1831, II, pp. 696–699.]

Erichsen (J.) Ueber "Diagnose und traitement du choléra, par le docteur F. X. Posnansky".
[ST. PETERSB. med. Zeitschr., 1862, VII, pp. [illegible]–226.]

Garner (R.) On the administration of prussic acid in cholera.
[LANCET, 1831, II, p. 650.]

Jones (J.) Efficacy of hydrocyanic acid in cholera.
[LONDON Med. & Surg. Jour., 1833, II, pp. 221, 222.]

Acid (*Nitric*). (See, also, *Bath*, *Nitric-acid.*)

Bowes (C.) Cases of cholera morbus successfully treated with dilute nitric acid.
LONDON Med. Repository, 1816, V, n. s., pp. 68–70.]

Warwick (R. A.) Dilute nitric acid in cholera.
[MED. Times & Gaz., 1866, II, p. 102.]

Acid (*Nitrous*).

Nicholas (G. E.) Case of Asiatic cholera successfully treated by nitrous acid; with remarks.
[MED. Times & Gaz., 1866, II, pp. 193–194.]

Acid (*Nitro-muriatic*).

Drei unfehlbare Mittel gegen die Cholera. Nebst einer Abhandlung über das salpetersaure Chlor, Räucherungen und Waschungen mit Wasser. 8°. *Stettin*, 1831.

Acid (*Sulphuric*).

Bellencontre. Choléra grave traité par l'acide sulfurique dilué et l'essence de térébenthine en frictions sur le rachis. Guérison.
[GAZ. des hôp., 1854, p. 31.]

Bodington (G.) Treatment of cholera by sulphuric acid.
[LANCET, 1853, I, n. s., pp. 322, 400.]

Buxton (T.) Treatment of diarrhœa and cholera by sulphuric acid.
[LANCET, 1851, II, p. 215.]

Cox (W. J.) The Austrian remedy [sulphuric and nitric acids] for cholera.
[LANCET, 1851, II, pp. 142–143.]

Giacich. Dichiarazione circa il liquore anticolerico del sig. Fatour.
[GIORN. venet. d. sc. med., 1855, V, 2a s., pp. 559–560.]

Greenhow (E.) Cholera—treatment by sulphuric acid.
[LONDON Med. Gaz., 1834, XIV, pp. 850–851.]

Guilhaud (A., *fils*). De l'emploi de l'acide sulfurique dans le traitement du choléra épidémique.
[JOUR. de méd., de chir. et de pharmacol., 1854, XIX, pp. 516–519.]

King (G.) Sulphuric acid in cholera.
[MED. Circular, 1854, V, pp. 162, 198.]

Lepetit (E.) Traitement préservatif et curatif de la diarrhée, de la cholérine et du choléra sporadique par l'acide sulfurique dilué et les bains salés. Application de ce traitement au choléra épidémique.
[GAZ. des hôp., 1853, pp. 612–614, 615.]

——— Traitement du choléra par l'acide sulfurique.
[GAZ. des hôp., 1854, p. 76.]

——— Traitement préservatif et curatif de la diarrhée, de la cholérine et du choléra sporadique par l'acide sulfurique dilué et les bains salés. Application de ce traitement au choléra épidémique. 8°. *Paris*, 1854.

MacCormac (H.) On the treatment, but especially the prophylactic arrest of Asiatic cholera by dilute sulphuric acid.
[MED. Times & Gaz., 1866, II, p. 57.]

——— Choléra et diarrhée; et l'emploi de l'acide sulfurique.
[GAZ. hebd. de méd. et de chirurg., 1866, 2e s., III, p. 544.]

Piorry. Sur l'emploi de l'acide sulfurique dans le cholera, et sur un moyen rationnel de remédier à la diarrhée cholérique et à la perte de la sérosité du sang qui en est la consequence;—compression de l'aorte et de l'abdomen.
[MONIT. des hôp., 1855, III, pp. 893–894.]

Smith (J. A.) Treatment of diarrhœa and cholera by sulphuric acid.
[LANCET, 1851, II, n. s., pp. 359–360.]

Willing (G. F. B.) On the treatment of cholera and choleraic diarrhœa with sulphuric acid, with cases.
[MED. Times & Gaz., 1853, VII, n. s., pp. 460–462.]

Worms. De l'emploi de l'acide sulfurique dans le choléra.
[GAZ. des hôp., 1853, pp. 615–616.]

Austrian specific for cholera.
[MED. Times & Gaz., 1853, VII, n. s., p. 513.]

Sulphuric acid in cholera.
[LANCET, 1852, II, n. s., p. 523.]

Acid (*Sulphurous*).

Parker (C. R. G.) On sulphurous acid as a remedy for cholera.
[LANCET, 1873, II, pp. 839–840.]

Aconite.

Cramoisy (E. P.) L'alcoolature d'aconit napel dans le traitément du choléra-morbus épidémique. 8°. *Paris*, 1856.

Agrimony.

Bard (R.) Cure [Agrimonia Eupatoria root] for Asiatic cholera.
[ELECTIC Med. Jour., 1873, XXXIII, p. 506.]

Air (Insufflation of).

Bruno (G.) La insufflazione di forte corrente atmosferica come rimedio dei colerosi.
[SPERIMENTALE (Lo), 1865, XVI, pp. 405-411.]

Albumen.

Levacher. Emploi de l'albumine du blanc d'œuf contre le choléra et la cholérine.
[JOUR. hebd. des prog. des sci., 1834, III, pp. 403-404.]

Alcohol.

Barthez. Du traitement du choléra chez les enfants, et notamment de la période algide par les alcooliques.
[REVUE de thérap. méd.-chir., 1854, II, pp. 568-572.]

Gaillard. Deux cas de choléra guéris par les boissons alcooliques à haute dose.
[BULL. de la Soc. de méd. de Poitiers, 1864, pp. 1-8.]

Guyot (J.) Du traitement du choléra par les alcooliques et le sulfate de soude.
[L'UNION méd., 1854, VIII, p. 459.]

Menville. Choléra, traitement préventif et curatif par le punch fortifiant et réparateur et par le liniment confortatif et stimulant formulés. 8°. *Paris*, 1866.

Rouhier. Sur la période prodromique du choléra et sur son traitement par les alcooliques et le sulphate de soude.
[REVUE méd. chir. de Paris, 1854, XVI, pp. 180-181.]

Suley. Théorie nouvelle sur la cause du choléra. Traitement simple et efficace [agents alcooliques joints aux eaux gazeuses].
[REVUE de thérap. méd.-chir., 1854, II, pp. 122-123.]

Alkalies. (See, also, *Ammonia, Lime, Potassa, Soda.*)

B[aud] (C.) De l'emploi des alcalis et du café de santé dans le traitement du choléra-morbus. 8°. *Paris*, 1832.

Baudrimont (E.) Instructions pratiques sur le traitement du choléra par la médication alcaline. 8°. *Paris*, 1865.

Dodd (H. W.) Cholera, or orotra; an essay on the use of liquor potassæ and liquor alkalinus in the treatment of malignant cholera, with numerous cases. 3d ed. *London*, 18—.

Dodd (H. W.)—continued.

Hamburger (E.) Die Cholera und ihre Heilung durch kohlensaure Alkalien. 8°. *Breslau*, 1850.

Heard (T. J.) Alkaline treatment of epidemic cholera.
[GALVESTON & Texas Med. Jour., 1868, III, pp. 110-115, 129-133.]

Knight (P. S.) On the use of alkaline salts.
[LONDON Med. Gaz., 1832, IX, pp. 889-905.]

Lewis (D.) On the treatment of cholera on specific principles.
[LANCET, London, 1849, II, pp. 426-427.]

——— Alkaline remedies in malignant cholera.
[LANCET, 1832-33, I, pp. 22-23.]

Aloes.

Guillemin. Note sur l'emploi de l'aloès dans le traitement du choléra-morbus.
[GAZ. méd. de Paris, 1832, III, pp. 572-573.]

Alum.

Strempel. Bemerkungen über den Alaun und das Carlisle'sche Instrument in Bezug auf ihre Anwendbarkeit in der Cholera.
[RUST's Mag. f. d. ges. Heilk., 1831, XXXIV, pp. 637-642.]

Ammonia.

Audouard. Observation sur l'emploi de l'ammoniaque contre le choléra-morbus.
[TRANS. méd., Jour. de méd. prat., 1832, X, pp. 237-242.]

Carrière (E.) De l'ammoniaque dans le choléra.
[L'UNION med., 1865, XXVIII, 2e s., pp. 134-136.]

Chawner (D.) On the employment of embrocations and injections of strong liquid ammonia in the collapse stage of cholera.
[LANCET, 1849, II, p. 236.]

Clutterbuck (J. B.) Injection of ammonia in the collapse of cholera.
[AUSTRAL. Med. Jour., 1874, XIX, pp. 306-314.]

Pinot. De l'ammoniaque pour amener la réaction dans le choléra.
[REVUE de thérap., 1854, II, p. 626.]

Levicaire. Un mot sur le choléra et sur l'emploi de l'alcali volatil pour le combattre. 8°. *Toulon*, 1837.

Steart (A.) On the use of liquor ammoniae purae in cholera.
[Trans. Med. & Phys. Soc. of Calcutta, 1833, vi, pp. 375–386.]

Ammonia (Carbonate of).

Courtois (De.) Cholera. Bons effets du carbonate d'ammoniaque.
[Jour. de méd. et de chir. prat., 1865, xxxvi, pp 450–451.]

Eisenmann. Sendschreiben des Dr. Eisenmann in Würzburg an alle denkenden Aerzte. Mitgetheilt von Professor Dr. Jüger zu Stuttgart. (Ammonium carbonicum als souveraines Mittel gegen Cholera asiatica.)
[Med. Correspbl. des württemb. aerztl. Vereins, 1832, i, pp. 13–15.]

Radcliffe (H. J.) Malignant cholera treated with carbonate of ammonia, saline draughts, and calomel.
[Lancet, 1832–33, i, pp. 21–22.]

Ammonia (Urate of).

Baur (H.) De l'urate d'ammoniaque dans les affections intermittentes et dans le choléra.
[Monit. des hôp., 1853, i, p. 1216.]

Ammonia (Valerianate of).

Oettinger. Ammonium valerianicum gegen Cholera.
[Aerztl. Intell.-Bl., 1854, i, pp. 278–279.]

Smith. De quelques moyens nouveaux employés contre le choléra dans les pays étrangers pendant l'année 1854 [Valérianate d'ammoniaque, seigle ergoté, hydrocyanate de zinc, acétate de zinc, huile de cannelle.]
[Revue de thérap. méd.-chir., 1856, iv, pp. 64–65.]

Amyl (Nitrite of).

Brunton (T. L.) On the employment of nitrite of amyl in the collapse of cholera.
[British Med. Jour., 1872, i, pp. 42–45.]

Jones (T.) Nitrite of amyl; its physiological action and medicinal uses; with suggestions for its employment in cholera.
[Practitioner, 1871, vii, pp. 213–224.]

——— Suggestions for the employment of nitrite of amyl in the collapse and cramps of cholera.
[British Med. Jour., 1871, ii, pp. 378–379.]

Anæsthetics.

Suggestions for the treatment of cholera by anæsthetic agents.
[Lancet, 1848, ii, pp. 82–83.]

Anthelmintics.

Valle (F.) Sul trattamento antelmintico nel cholera-morbus. 8°. *Mortara*, 1874.

Antimony.

Charpentier de Joigny. Choléra-morbus grave traité et guéri par le tartre stibié.
[Gaz. des hôp., 1832, vi, pp. 97–98.]

Fearnley (G.) Tartar-emetic in spasmodic cholera.
[Lancet, 1838–39, i, pp. 200–201.]

Hall (C. R.) On the employment of tartar-emetic in cholera.
[Lancet, 1848, ii, pp. 311–312.]

Langford (J.) Treatment of malignant cholera with tartar emetic, at Manchester.
[Lancet, 1831–32, ii, p. 781.]

——— The treatment of Asiatic cholera and choleric diarrhœa, with tartarized antimony. 8°. *London*, 1833.

Littleton (N.) Treatment of the malignant cholera with tartarised antimony.
[Lancet, 1832–33, i, pp. 105–107.]

Pinel. Choléra très-intense. Emploi du tartre stibié; amélioration momentanée; mort en 24 heures.
[Gaz. des hôp., 1833, vii, p. 52.]

Tweedie (A.) Treatment of malignant cholera at the Abchurch-Lane hospital.
[Lancet, 1831–32, ii, p. 782.]

Tartar emetic in cholera.
[London Med. & Surg. Jour., 1835, vi, p. 87.]

Arsenic.

Atkins. Case of Asiatic cholera successfully treated with arsenic.
[Med. Times, 1848, xviii, p. 253.]

Black (C.) Arsenic a remedy for cholera.
[Assn. Med. Jour., 1854, pp. 971, 1039.]

——— On the value of arsenic in cholera.
[Lancet, 1857, ii, n. s., pp. 338, 401–402, 541–542, 573–575, 636.]

Cahen. Du traitement du choléra par l'acide arsénieux. (1866.) 8°. *Paris* [n. d.]

Hitchman (W.) Arsenic in cholera.
[Lancet, 1857, ii, p. 534.]

Hitchman (W.)—continued.

——— The treatment of cholera by arsenic.

[LANCET, 1857, II, n. s., pp. 611–613.]

Sargent (A.) The treatment of cholera by arsenic.

[LANCET, 1857, II, n. s., p. 562.]

Arnica.

Bekanntmachung einer besondern Methode zur Erhöhung der Heilkräfte der Wolverlei-Blume, Fl. Arnica, gelegentlich als rational vorzügliches Schutz- und Heilmittel in der Cholera. 8°. *Frankfurt a. M.*, 1831.

Wolverlei-Blume. Die Schutz- und Heilmittel bei der Cholera. 8°. 1832.

Astringents.

Eastman (D.) Successful use of astringents in the treatment of malignant cholera.

[BOSTON Med. & Surg. Jour., 1833, VII, pp. 203–208.]

——— Astringents in the treatment of cholera.

[BOSTON Med. & Surg. Jour., 1849, XL, pp. 49–55.]

Hardy (H. N.) Case of malignant cholera treated with astringents and hypodermic injections of morphia; recovery.

[LANCET, 1872, II, p. 294.]

Liégard. Choléra-morbus guéri par une médication astringente et tonique.

[REVUE méd. franç. et étrang., 1831, III, pp. 369–372.]

——— Treatment of cholera by preventing the discharge of the serum of the blood, or supplying it artificially.

[LONDON Med. Gaz., 1849, XLIV, pp. 755–757, 1054–1057; *also, in* LANCET, 1849, II, p. 532.]

Astringents in the treatment of cholera.

[BOSTON Med. & Surg. Jour., 1849, XL, pp. 49–55.]

Atropia. (See *Belladonna.*)

Bandaging.

Bowden (E.) Tight bandaging in cholera.

[LONDON Med. Gaz., 1832, X, p. 454.]

Drouet (A.) Emploi du badigeonnage au collodion ricin6 comme moyen abortif de la cholérine et comme moyen de calorification dans le choléra confirmé.

[L'UNION méd., 1866, XXXI, 2e s., pp. 171–172.]

Kennedy (E.) On the use of bandaging in relieving the cramps in cholera.

[DUBLIN Quar. Jour. of Med. Sci., 1849, VIII, 451–452.]

Bath (Chloride of calcium).

Sabbatini (L.) Sulla sorprendente efficacia de' bagni generali caldi di cloruro di calce contro il colera asiatico o[illegible] mata da ulteriori sperimenti, con [illegible] statistica de' risultati ottenuti dal [illegible] verso trattamento de' colerosi ne[illegible] ospedale di S. Spirito in Sassia. [illegible] Corrispondenza scientifica in Roma [illegible] tobre 5, 1855.) 4°. [illegible]

——— The same. [Reprint.] [illegible]. [n. d.]

Bath (Hot).

Girault (E.) Les moyens employés p[illegible] communiquer la chaleur aux c[illegible] riques.

[GAZ. des hôp., 1832, VI, p. 236.]

Bath (Hot-air).

Carey (E.) On the use of hot-air [illegible] in cholera.

[LANCET, 1849, II, pp. 163–164.]

Green (J.) On the use of dry-heat [illegible] in cholera.

[LONDON Med. Gaz., 1832, IX, p. 429.]

Hallett (J. J.) On the efficacy of the [illegible] air bath in cholera.

[LONDON Med. & Surg. Jour., 1833, II, pp. 22[illegible]

La Beaume (M.) On the portable [illegible] tory, or hot-air-bath; with cases [illegible] trative of its medical powers in var[illegible] disorders, and its great utility in c[illegible] era morbus, with directions for its [illegible] ministration; together with remark[illegible] the applicability of galvanism in [illegible] first stage of that disease. 2d ed. [illegible] *London*, 1832.

Russell (J.) Hot-air-bath in cholera.

[LONDON Med. Gaz., 1832, IX, pp. 470–47[illegible]

Air-baths for the treatment of cholera.

[LANCET, 1848, II, pp. 402–403.]

Bath (Mustard). (See *Counter-irritation.*)

Bath (Nitric-acid).

Dufton (W.) Treatment of ma[illegible] cholera (when collapse has taken pl[illegible] with the nitric acid bath, etc.

[LANCET, 1831–32, II, p. 753.]

Bath (Salt-water).

Starr (T. H.) On the use of sa[illegible] baths in cholera.

[LANCET, 1855, II, n. s., pp. 42–43.]

Bath (Sand).

Fronmüller (G. C. C.) Das künst[illegible] Sandbad, besonders in Bezug auf Behandlung der Cholera. [illegible] *berg*, 1832.

Bath (Stimulating).

Pennès (J. A.) Des bains stimulants dans le traitement du choléra.
[Gaz. des hôp., 1866, p. 412.]

Bath (Vapor).

Ascherson (F. M.) Beschreibung tragbarer Dampfbad-Apparate, zur Abwehrung der Cholera. 8°. *Berlin*, 1831. L.

Bulley (F. A.) An account of a case of spasmodic cholera successfully treated by the use of the spirit-vapour-bath, and stimulating cataplasms to the spine, with remarks.
[Med. Times, 1848, xviii, pp. 286-287.]

Cazalas. Note sur l'emploi du bain de vapeur dans le traitement du choléra algide.
[Rec. de mém. de méd. mil., 1856, xviii, 2e s., pp. 207-212.]

Gebhard (C. J.) Abbildung und Beschreibung eines einfachen Apparates zur schnellen und sicheren Anwendung von Dampfbädern aus Weingeist oder Essig, so wie auch dessen gleichzeitiger Benutzung zu . . . . der dringendsten Zufälle der Cholera, etc. 8°. *Hannover*, 1831.

Hawkins (J. A.) Das amerikanische arzneihaltige Dampfbad als Schutzmittel gegen Ansteckung und als das schnellste, kräftigste und sicherste Heilmittel der Cholera, etc. 8°. *Berlin*, 1831. L.

Hempel (F.) Das weingeistige Dampf-Bad, ganz besonders in Beziehung auf die Cholera, etc. (4. Aufl.) 8°. *Berlin*, 1831.

Koch (C. F.) Beschreibung eines einfachen und wohlfeilen Zeltes und Bettes für Dampfbäder in beliebigen Wärmegraden, als das zur Zeit bewährteste Vorbauungs- und Heilmittel gegen die orientalische Cholera, nebst einer kurzen Gebrauchsanweisung. 8°. *Magdeburg*, 1831. L.

Koppenstätter (J.) Nützliche Erfindung eines Dampf- und Wasser-Heitz-Apparats, nebst Abbildung und einer kurzen Gebrauchsanweisung. Ein zuverlässiges Heilmittel gegen die orientalische Cholera, etc. 12°. *München*, 1831.

Mangold (L. G.) Der Dampfbad-Kasten, ein neuer einfacher Apparat zur zweckmässigen Behandlung verschiedener krankhafter Affectionen des Rückgrathes und Rückenmarks, so wie anderer Körpertheile, mit Kräuter-Dämpfen . . . . . die von der Cholera befallen zu sein glauben, etc. 8°. *Berlin*, 1831.

Mangold (L. G.)—continued.

[**Phöbus** (P.)] Abbildung und Beschreibung der in der Berliner Cholera-Heilanstalt Nr. 11. eingeführten Erweiterung und Verbesserung des Schneiderschen Dampf-Apparates. 8°. *Berlin*, 1831.

Schmitz (F. J.) Beschreibung eines zum Gebrauche für Kranke, besonders aber für an der epidemischen Cholera Leidende, auch zur Bereitung eines Dampfbades eingerichteten zweckmässigen Bettes. 8°. *Barmen*, 1831.

Abbildung und Beschreibung der in der Berliner Cholera-Heilanstalt No. II. eingeführten Erweiterung und Verbesserung des Schneiderschen Dampfbad-Apparates. 8°. *Berlin*, 1831. L.

Gebrauchs-Anweisung zu dem von den Gebr. Aston in Magdeburg erfundenen Cholera-Schwitzbad. 8°. *Magdeburg*, 1831.

Influence of the Russian vapour-baths on cholera.
[Med. Times, 1848, xviii, p. 297.]

Belladonna.

Chalvet (J.) Emploi de la belladone à dose toxique dans certaines formes du choléra.
[Gaz. des hôp., 1859, p. 473.]

Hodgen (J. T.) Treatment of cholera by atropine and saline solutions.
[St. Louis Med. & Surg. Jour., 1866, iii, pp. 497-502.]

——— The same. 8°. [*n. p., n. d.*] L.

Leclerc (F.) De la médication curative du choléra (traitement par la belladone). 8°. *Tours* [1855 *or* 1865].

——— The same. 2e éd. . . . . recherches expérimentales sur le sang veineux. 8°. *Tours*, 1856.

Truesdale (C.) Hypodermic use of belladonna and atropia in cholera.
[Med. Exam., 1873, xiv, pp. 213-214.]

Viardin. Observations sur l'emploi de la belladone dans le traitement du choléra-morbus. (10 cases.)
[Gaz. méd. de Paris, 1832, iii, pp. 310-311.]

Benzoin.

Blin. Antidote contre le choléra-morbus. Liqueur de benzoin composée. 8°. *Caen*, 1851.

Bile.

Hood (P.) Ingestion of bile in cholera.
[LONDON Med. & Surg. Jour., 1834, IV, p. 61.]

Bismuth.

Ceresa (C. de). Bemerkungen über die epidemische Brechruhr. (Cholera-Morbus.) Nebst einem Nachtrag: Ueber das Magisterium Bismuthi. 8°. *Vienne* 1831.

Leo. Del curare il cholera-morbus col magistero di bismuto.
[OMODEI, Ann. un. di med., 1831, LIX, pp. 216–219.]

Leo (L.) Ideen und Erfahrungen über die Natur und Behandlung der asiatischen Brechruhr, mit besonderer Beziehung auf die Anwendung des Wismuths gegen dieselbe. 8°. *Warschau*, 1832.

——— Le traitement du choléra-morbus [par le magistère de bismuth].
[GAZ. des hôp., 1831, V, pp. 110–111.]

Mayer. Ueber das Wismuth in seiner Wirkung auf die thierische Organisation, mit besonderer Rücksicht auf seine Heilkraft in der Cholera morbus.
[JOUR. der prakt. Heilk., 1831, LXXIII, pp. 65–79.]

Schmidt (F. J. J.) De Onschadelijkheid van Magisterium Bismuthi in Cholera asiatica. [From Ned. Lancet, 1850.] 12°. L.

Siebenhaar (F. J.) Ueber die rationelle Behandlung der asiatischen Cholera, mit besonderer Berücksichtigung des Gebrauchs des Wismuths und des frischen Wassers in derselben.
[JOUR. der prakt. Heilk., 1831, LXXII, pp. 114–123.]

——— Wunderbare Einführung des Magisterium Bismuti in die Praxis der Cholera contagiosa.
[JOUR. der prakt. Heilk., 1831, LXXII, pp. 107–112.]

Lettre sur l'emploi du sous-nitrate de bismuth dans le traitement du choléra.
[GAZ. méd. de Paris, 1849, IV, 3e s., pp. 526–527.]

Bladder (Injection of).

Postelberg (A.) Injectionen in die Blase bei Cholera.
[ALLG. Wien. med. Zeitg., 1867, XII, p. 311.]

Proposal to inject the bladder in dropsy and cholera.
[LONDON Med. & Surg. Jour., 1833, II, p. 477.]

Blisters. (See *Counter-irritation.*)

Blood-letting.

Bell (G. H.) Tables illustrating the effects of the employment of **blood** letting in the treatment of cholera, in the Cholera Hospital in 1832.
[EDINB. Med. & Surg. Jour., 1849, LXXI, pp. 147–148.]

Colclough (A. C.) **Cholera**—effects of blood-letting.
[LONDON Med. Gaz., 1832, X, pp. 638–641.]

Collyns (W.) **Malignant cholera.** Bleeding. Cold salt and **water** in great quantity. Mercurial frictions.
[LANCET, 1832–33, I, p. 113.]

Fallot. Deux observations de choléra-morbus asiatique, traité avec le plus grand succès par la **saignée** veineuse pendant la période algide.
[GAZ. méd. de Paris, 1832, III, pp. 714–717.]

Gale (W.) Case of **malignant** cholera successfully treated.
[LONDON Med. Gaz., 1836, XVIII, pp. 870–871.]

Marsden (W.) On blood-letting in cholera.
[BRIT. AMER. Jour of Med. & Phys. Sci., pp. 141–145.]

May (B. H.) Treatment **of** cholera. blood-letting, and emetics *of* salt and water.
[N. O. Med. & Surg. Jour., 1848–49, pp. 532–544.]

Middrie (P.) Danger **of large** bleeding in cholera.
[LANCET, 1834–35, II, pp. 13–14.]

Oliver (G.) Treatment of cholera by abstraction of blood.
[LANCET, 1849, II, pp. 270–271.]

Roberts (R. W.) Mr. Corbyn's treatment of cholera.
[LANCET, 1834, II, pp. 542–543.]

Tanchou. Trois observations de choléra algide traité par la saignée, et les boissons chaudes laudanisées à très petites doses.
[GAZ. des hôp., 1833, VII, pp. 365–366.]

Whittle (E.) Bleeding in cholera.
[MED. Times & Gaz., 1853, VII, n. s., p. 431—CANADA Med. Jour., 1866, II, pp. 568–570—Med. Times & Gaz., 1866, I, p. 518.]

On phlebotomy in cholera.
[BOSTON Med. & Surg. Jour., 1834, IX, pp. 309–310.]

Quelques considérations sur les avantages et les inconvéniens des évacuations sanguines dans le traitement du choléra.
[BULL. gén. de thér. méd. et chir., 1832, II, pp. 308–309.]

Temperance (A) method of treating epidemic cholera, by a physician. (Written by request.) 8°. *New York*, 1849. L.

Blood (Transfusion of).

Byrd (H. L.) Suggestions for the treatment of the algid stage of cholera.
[Med. Times, Phila., 1872-73, III, pp. 802-803.]

Dieffenbach (J. F.) Versuche über die Transfusion des Blutes in der Cholera.
[Litter. Ann. der gesammt. Heilk., 1832, XXII pp. 129-141.]

Edwards (C.) On the pathology of the collapse in cholera, and the treatment of that stage by transfusion.
[Lancet, 1848, II, pp. 478-479.]

Routh (C. H. F.) Report of a case of cholera treated by transfusion.
[Lancet, 1849, II, n. s., pp. 71-73.]

Schilts. Transfusion bei Cholera. (Case.)
[Deutsche Klinik, 1867, XIX, p. 357.]

Smart (T. W. W.) Transfusion of blood in cholera, &c.
[London Med. Gaz., 1832, IX, pp. 260-262.]

Stadthagen. Transfusion bei Cholera.
[Berl. klin. Wochenschr., 1873, X, p. 453.]

Thomas (W. J.) Proposal to transfuse blood after saline injections in cholera.
[Lancet, 1832, II, p. 455.]

Choléra-morbus; son traitement par la transfusion.
[Jour. de méd. et de chir. prat., 1832, III, pp. 12-15.]

Transfusion in cholera.
[Boston Med. & Surg. Jour., 1832, VI, pp. 32-34.]

Botanic and eclectic.

Forward (S.) The cholera—how to cure it.
[Ecl. Med. Jour., 1849, I, n. s., pp. 112-115.]

Jones (L. E.) Cholera.
[Ecl. Med. Jour., 1866, XXVI, pp. 65-73.]

Morrow (T. V.) Lecture on the practical management of spasmodic cholera.
[Ecl. Med. Jour., 1849, I, n. s., pp. 277-282.]

Statistics of cholera practice.
[Ecl. Med. Jour., 1849, I, n. s., pp. 314-316.]

Treatment of cholera.
[Ecl. Med. Jour., 1849, I, n. s., pp. 433-442.]

Buchu.

Hoffmann. Erläuterung über die Bucco-Blätter.
[Rust's Mag. f. d. gesammt. Heilk., 1832, XXXVI, pp. 198-202.]

Magnus (v.) Wirkung der Bucco-Blätter gegen Cholera.
[Rust's Mag. f. d. gesammt. Heilk., 1831, XXXV, pp. 145-149.]

Calabar bean.

Mapother (E. D.) Reasons for suggesting Calabar bean in the treatment of cholera.
[Dublin Med. Press & Circ., 1868, II, pp. 267-268.]

Munro (W.) Suggestions as to the use of Calabar bean, in cholera asiatica.
[Edinb. Med. Jour., 1871, XVII, pp. 327-329.]

Calcium (Chloride of). (See, also, *Chalk.*)

Hempel (F.) Ueber Chlor und Chlorkalk, deren Nutzen, Bereitung und Anwendung in Beziehung auf die Cholera. 8°. *Berlin*, 1831.

Mackay. Disinfecting treatment of cholera.
[Madras Quar. Jour. of Med. Sci., 1863, VI, pp. 451-454.]

Priest (A.) Chloride of calcium in cholera.
[Med. Circular, 1864, V, p. 153.]

Ausführliche Anweisung für Bürger und Landleute über den Gebrauch des Chlorkalks als Reinigungs- und Schutzmittel gegen die Cholera und andere Krankheiten. 12°. *Aschersleben* [*n. d.*] L.

Calomel.

Adkins (I. L.) Cholera—the sedative plan of treatment. (Calomel, acetate of lead, opium.)
[Med. Examiner, 1849, V, n. s., pp. 525-538.]

Askwith (J. H.) A specific for the cramp or spasms in epidemic cholera.
[Med. Circular, 1853, III, pp. 110-111.]

Ayre (J.) Efficiency of calomel in the treatment of malignant cholera.
[Lancet, 1831-32, II, pp. 271-274.]

——— On the treatment of the malignant cholera, by small and frequent doses of calomel.
[Lancet, 1831-32, II, pp. 458-461; 1832, II, pp. 615-617; 1832-33, I, p. 18; 1833-34, II, p. 689; 1835, I, p. 64; 1848, II, p. 473; 1849, II, pp. 145, 327, 378.]

——— A report of the method and results of the treatment for the malignant cholera by small and frequently repeated doses of calomel; with an enquiry into the nature and origin of the complaint, with a view to a more just appreciation of the means for its prevention and cure; with illustrative cases. 8°. *London*, 1833. L.

——— On the error of certain published opinions concerning the nature of the malignant cholera, and on the treatment of that complaint in its collapsed stage by single doses of calomel.
[Lancet, 1849, I, pp. 260-263, 1 table.]

——— The treatment of cholera in Hull.
[Lancet, 1849, II, pp. 408-409, 491-492.]

Ayre (J.)—continued.

——— On the treatment of cholera by calomel.
[LANCET, 1854, II, n. s., pp. 311–312.]

Bargellini (D.) Intorno all'uso del calomelano nel coléra.
[GAZ. med. ital. Tosc., Firenze, 1855, I, 3a s., pp. 329–332.]

Beckett (C.) On the cholera at Hull.
[LANCET, 1849, II, n. s., pp. 312–313.]

Bloxam (W.) Case of malignant cholera treated with calomel; recovery.
[LANCET, 1872, II, pp. 256–257.]

Bordes. Traitement du choléra-morbus par le calomel et l'opium à doses réfractées.
[REVUE de thérap., 1854, II, pp. 600–601.]

Brickell (D. W.) Calomel in cholera.
[N. O. Med. & Surg. Jour., 1849–50, VI, pp. 189–193.]

Bullar (J.) On Dr. Ayre's treatment of malignant cholera.
[LANCET, 1849, II, pp. 425–426; *also, in* LOND. Med. Gaz., 1849, XLIV, p. 621.]

Contini (G.) Notizie e memorie sulla cholera orientale, e sull'uso del calomelano nella cura di essa. *Napoli*, 1866.

Cortis (T. T.) Rewards to the cholera doctors at Hull.
[LANCET, 1849, II, pp. 590–591.]

Cory (E. A.) Malignant cholera—large doses of mercury—death.
[LONDON Med. & Surg. Jour., 1834, IV, pp. 59–60.]

Cox (W. I.) On the value of Dr. Ayre's treatment of malignant cholera.
[LANCET, 1849, II, n. s., p. 151.]

——— Treatment of cholera by small and repeated doses of calomel.
[LANCET, 1849, II, n. s., pp. 219–220, 409.]

Craigie (W.) Dr. Ayre's treatment of cholera by calomel.
[LANCET, 1854, II, pp. 427–428.]

Dermott (H.) Ptyalism and cure of cholera under large doses of calomel.
[LANCET, 1849, II, p. 236.]

Dowler. Calomel in cholera.
[MED. Mag., 1834, II, pp. 595–598.]

Foote (J.) Registration of cholera cases, and treatment of cholera by small doses of calomel.
[LANCET, 1849, II, pp. 437–438.]

Foster (W. P.) Treatment of malignant cholera by calomel, opium, brandy, and hydrocyanic acid.
[LANCET, 1831–32, II, p. 720.]

Gibson (J. H.) The cholera at Hull,—remarks on the treatment by Dr. Ayre, &c.
[LANCET, 1849, II, pp. 163–163.]

Gibson (J. H.)—continued.

——— **Sleight** (R. P.), *and* **Horner** (F. Treatment of cholera at Hull.
[LANCET, 1849, II, pp. 376–378.]

Greenhow (T. M.) Calomel, ginger, opium, followed by a purgative—c[illegible] enemata—fresh air, &c.
[LONDON Med. Gaz., 1832, X, pp. 833–835.]

Hall (A.) On the calomel treatment algide or Asiatic cholera.
[BRIT. AMER. Jour. of Med. & Phys. Sci. V, pp. 85–89.]

Hardinge. A case of cholera treated calomel; recovery.
[LANCET, 1872, II, p. 449.]

Hughes (H. M.) The inefficiency of calomel treatment in cholera.
[LONDON Med. Gaz., 1849, XLIV, pp. 425–427.]

——— On the treatment of cholera by omel, etc.
[LANCET, 1849, II, n. s., pp. 328–329.]

Jones (J.) On the treatment of cho[illegible] by calomel and colocynth.
[PROV. Med. Jour., 1852, pp. 579–582.]

Livingstone (A. C.) On the treatment cholera at Leith.
[LANCET, 1849, I, n. s., pp. 123–124.]

Mackinlay (J.) On the treatment cholera with calomel. With a report a case interrupted by delivery.
[LANCET, 1854, II, n. s., p. 352.]

Marshall (F. W.) A report of two cases of cholera successfully treated by omel.
[LANCET, 1849, II, p. 149.]

May (G. P.) On the treatment of malignant cholera by calomel. [2 cases.]
[LANCET, 1874, I, p. 185.]

Melo (G. B.) Del calomelano nella cura del cholera.
[GAZ. med. ital. prov. Veneto, 1867, X, pp. 29–3[illegible]

Morley (J.) Dr. Ayre's treatment of cholera.
[LANCET, 1848, II, pp. 566–567.]

——— The cholera in Hull.
[LANCET, 1849, II, n. s., p. 437.]

Nankivell (J. H.) On the treatment of cholera by repeated doses of calomel.
[LANCET, 1849, II, pp. 268–269.]

Niddrie (P.) Medicines at long intervals in cholera,—value of calomel and carbonic acid gas at short intervals.
[LANCET, 1849, II, pp. 235–236.]

——— On the treatment of cholera. Calomel and carbonic acid gas curative when perseveringly and watchfully exhibited.
[LANCET, 1849, II, n. s., pp. 152–153.]

wen (A. P.) Malignant cholera treated with calomel.
[LANCET, 1872, II, p. 322.]

ainter (R. B.) Report of a recent case of cholera successfully treated by frequent doses of calomel, effervescent draughts and brandy.
[LANCET, 1850, II, n. s., p. 205.]

Patterson (C.) Practical observations on a successful method [calomel and the compound sulphate injection] of treating cholera.
[DUBLIN Med. Press, 1848, XX, pp. 178–179.]

Payne (G. B.) Treatment of cholera on the plan of Dr. Ayre.
[LANCET, 1849, II, p. 270.]

Peacock (J.) Malignant cholera. Small and frequent doses of calomel.
[LANCET, 1834, II, pp. 930–932.]

Pickop (J.) Successful treatment of cholera by small and repeated doses of calomel.
[LANCET, 1849, II, p. 289.]

Popham (W. H.) Calomel in cholera.
[LANCET, 1849, I, p. 214.]

Pritchett (G. M.) Successful treatment of malignant cholera on the plan of Dr. Ayre.
[LANCET, 1849, II, n. s., p. 147.]

Rance (T. F.) Treatment of malignant cholera in the parish of St. Luke, Middlesex. Calomel and opium—salines—venous injection.
[LANCET, 1832–33, I, pp. 110–112.]

Robinson (C. H.) Case of Asiatic cholera treated by large doses of calomel.
[DUBLIN Med. Press & Circ., 1866, II, p. 606.]

Sandwith (H.) Treatment of cholera in Hull.
[LANCET, 1849, II, p. 545.]

—— The cholera at Hull.
[LANCET, 1849, II, n. s., pp. 463–466.]

Shearman (E. J.) On Dr. Ayre's treatment of cholera.
[LANCET, 1854, I, n. s., pp. 651–652.]

Spong (W. N.) A case illustrating the efficacy of Dr. Ayre's treatment of cholera.
[LANCET, 1849, II, n. s., p. 124.]

Stanly (J.) Treatment of malignant cholera by calomel.
[LANCET, 1831–32, II, pp. 721–722.]

Stedman (W.) Cholera treated with calomel and brandy.
[MED. Times, 1849, XIX, p. 674.]

Stephens (H.) Malignant cholera. Treatment with mercury—venous injection as an accessory.
[LANCET, 1832–33, II, pp. 657–658.]

Sutton (W. L.) On large doses of calomel in cholera.
[BOSTON Med. & Surg. Jour., 1850, XLI, pp. 15–18, 269–277.]

Taylor (J.) On the modus operandi of mercury in the cure of Asiatic cholera.
[LANCET, 1854, II, pp. 166–168.]

Taylor (J. H.) Treatment of malignant cholera with large doses of calomel.
[LANCET, 1832–33, I, pp. 53–54.]

Tod (D.) Cases of malignant cholera treated with large doses of calomel.
[LANCET, 1831–32, II, pp. 585–587.]

Tripe (J. W.) Cases of cholera treated by calomel and ipecacuanha.
[MED. Times, 1849, XX, pp. 449–450.]

Waddington (J.) On the Asiatic cholera and the board of health,—treatment by calomel.
[LANCET, 1848, II, p. 490.]

—— Malignant cholera, Dr. Ayre's plan of treatment.
[LANCET, 1850, I, p. 33.]

Wearne (J.) Calomel and bichloride of mercury in cholera.
[LANCET, 1854, II, n. s., pp. 190–191.]

Weber (H.) Two cases of cholera—calomel treatment—favorable progress.
[MED. Times & Gaz., 1866, II, pp. 88–89.]

Wilson (W. M.) Objections to the mercurial treatment of malignant cholera.
[LANCET, 1833–34, I, pp. 744–745.]

Woodman (W.) On the successful treatment of a case of cholera by repeated doses of calomel.
[LANCET, 1849, II, pp. 503.]

Ayre's (Dr.) treatment of cholera.
[PROV. Med. & Surg. Jour., 1848, p. 630.]

Cura del cholera col calomelano. Metodo di Ayre.
[GAZ. med. ital. prov. Veneto, 1873, XVI, pp. 213–218.]

On the use of repeated doses of calomel in cholera.
[LANCET, 1849, II, pp. 236–237.]

Traitement par le calomel à doses fractionnées.
[L'UNION méd., 1849, III, pp. 189–190.]

Treatment of malignant cholera. Stimulants injurious,—efficacy of calomel and counter irritants,—danger of bleeding, etc.
[LANCET, 1832, II, pp. 587–588.]

Camphor.

Bagot (C. E.) Solution of camphor in chloroform in cholera.
[DUBLIN Med. Press, 1849, XXII, p. 150.]

Bayes. The cholera, and its treatment, by camphor alone, according to the method of Dr. Rubini.
[HOMŒOPATHIC Rev., 1866, X, pp. 333–342.]

Hall (J.) Treatment of Asiatic cholera; with tincture of rye and strong spirits of camphor.
[MED. Times, 1849, XIX, pp. 165–166.]

Leviseur. Die Cholera und der methodische Gebrauch des Camphers. *Berlin und Posen*, 1848.

Murray (J.) Alleged utility of camphor in the treatment of cholera.
[LONDON Med. Gaz., 1848, XLII, p. 819.]

Pope (A. C.) Camphor in its relation to cholera.
[HOMŒOPATHIC Rev., 1867, XI, pp. 159–167.]

Result of the treatment of nineteen cases of cholera by camphor.
[MED. Times & Gaz., 1866, II, pp. 118–119.]

Capsicum.

Plant (G.) Treatment of spasmodic cholera by cayenne pepper and brandy.
[LANCET, 1848, II, p. 178.]

Carbon.

Evans (W. P.) On the treatment of cholera by carbon and carbonic acid.
[LANCET, 1848, II, p. 290.]

——— Treatment of cholera by carbon.
[LANCET, 1848, II, p. 247.]

Parkin (J.) Treatment of cholera by carbon and carbonic acid.
[LANCET, 1848, II, pp. 220–221.]

On the alleged good effects of powdered charcoal and carbonic acid in the treatment of cholera.
[LONDON Med. Gaz., 1848, XLII, pp. 1081–1083.]

Carbon (Bisulphuret of).

Hastings (J.) On the use of the bisulphuret of carbon in cholera. [Cases.]
[MED. Times, 1849, XX, pp. 320–322.]

Carbon (Chloride of).

Boyton (J. E.) Terchloride of carbon in cholera.
[MED. Times, 1849, XIX pp. 62–63.]

Koreff. Note sur le sesquichlorure de carbone, et sur son emploi contre le choléra.
[REVUE méd.-chirurg. de Paris, 1849, V, pp. 86–87.]

Hoffmann (K., *d. J.*) **Der** [illegible] Chlorkohlenstoff in **der Cholera** [illegible] wendet.
[MED. Zeitung, 1848, pp. 187–188, 196–19[illegible].

Lamprey (J.) **Terchloride of car**[illegible] a remedy for cholera.
[MED. Times, 1849, XIX, p. 213.]

Cataplasms.

Ranque (H. F.) **Mémoire sur un** [illegible] traitement du **choléra-morbus** et affections typhoïdes, **lu le 4 mars** [illegible] la Société royale des **sciences**, [illegible] lettres et arts d'Orléans; **envoyé** [illegible] mai 1831 à l'Académie **royale de** [illegible] cine. 8°. *Paris et London*, **1831.** [illegible]

Cauterization.

Mayor. Sur la **cautérisation avec** [illegible] bouillante contre le **choléra-morbus**.
[GAZ. des hôp., 1831, V, p. 164.]

——— Ueber die **Cauterisation** mit [illegible] chendem Wasser gegen **die Cholera**.
[NOTIZEN aus dem Gebiete der Natur- und [illegible] 1831, XXXI, pp. 285–287.]

Chalk.

Pasquali (A.) **Der Kalk als directes** [illegible] mittel gegen die asiatische **Cholera**. [illegible] *Wien*, 1855.

Charcoal. (See *Carbon.*)

Chloral.

Blumenthal. Behandlung der **Cho**[illegible] kranken mit Chloralhydrat im [illegible] schen Kriegshospital.—**Neun Cho**[illegible] fälle behandelt mit Chloralhydrat.
[ALLG. med. Central-Zeitung, 1871, XL, pp. [illegible] 1084, 1094–1096.]

Hall (A. R.) On the pathology and [illegible] ment of cholera.
[PRACTITIONER, 1875, XV, pp. 1–13.]

Liebreich (O.) **und Reichard** (W. [illegible] Ueber den therapeutischen **Werth** [illegible] Chloralhydrat bei der **Cholera**.
[BERLIN. klin. Wochenschr., 1871, VIII, pp. [illegible] 409.]

Nepveu. Du chloral dans la **cholera** et le choléra.
[GAZ. méd., 1873, XXVIII, pp. 494–495.]

Reichard (v.) Chloral in **cholera**.
[MED. & Surg. Reporter, 1871, XXV, p. 573.]

Chloralum.

Blanc (H.) Choléra et **chloralum**.
[L'UNION méd., 1873, XVI, 3e s., pp. 533–534, 569–573, 653–656, 685–689.]

anc (H.)—continued.

—— On the internal use of chloralum in cholera.
[LANCET, 1873, II, pp. 226-227.]

aulier. Choléra et chloralum.
[GAZ. hebd. méd. et chir., 1873, X, 2e s., pp. 717, 718, 751, 752.]

Chlorine.

Bull (E.) On cholera; and its treatment by chlorine.
[MED. Circular, 1854, V, pp. 140, 187.]

Dobie (W. M.) On the use of chlorine in the treatment of Asiatic cholera.
[EDINB. Med. Jour., 1867, XII, pp. 829-835.]

Dugès (A.) Lettre sur l'emploi du chlore dans le choléra.
[GAZ. méd. de Paris, 1835, III, pp. 637-638.]

Heindl (A.) Chlor gegen Cholera als therapeutischer Beitrag. 8°. *Augsburg*, 1849.

Le Carpentier (J.) Nature and treatment of epidemic cholera, according to the method of Dr. Delfeau.
[ST. LOUIS Med. Reporter, 1867-68, II, pp. 740-742.]

Namias (G.) Sui buoni effetti del cloro usato internamente nella cura dei colerosi.
[GIORN. p. serv. al progr. d. patolog., Venezia, 1835, III, pp. 75-87.]

Schlegel. Die asiatische Cholera und das Chlor.
[MED. Zeitung, 1849, pp. 135-137.]

Toulmouche (A.) De l'emploi du chlore dans le traitement du choléra épidémique.
[ARCH. gén. de méd., 1835, VIII, 2e s., pp. 365-368.]

Anweisung über die Bereitung und Anwendung des Chlors als Schutzmittel gegen Ansteckung durch Choleragift. 8°. *Berlin*, 1831. L.

Chlorodyne.

Stree Ramooloo Naidoo (P.) Chlorodyne a remedy for cholera.
[MADRAS Quar. Jour. of Med. Scl., 1866, IX, pp. 353-356.]

Chloroform.

Boate (A. C.) New treatment of cholera: its origin and cure.
[LANCET, 1857, II, n. s., pp. 135-137.]

Bournonville (A.) Report of several cases of Asiatic cholera successfully treated by chloroform.
[MED. Exam., 1849, V, pp. 459-468.]

Brady (P.) Asiatic cholera successfully treated by chloroform, given internally; with remarks.
[MED. Times, 1848, XVIII, pp. 237-238, 320-321.]

Brady (P.) *and* Davies (J.) Chloroform in cholera.
[MED. Times, 1849, XX, pp. 18, 227.]

Davies (T.) Treatment of cholera by chloroform.
[LANCET, 1849, II, p. 327.]

Fairbrother (W. M.) A case of Asiatic cholera successfully treated by the inhalation of chloroform.
[LANCET, 1849, II, n. s., pp. 129.]

Fleischmann. Zur Chloroform-Therapie, zumal in der Cholera.
[AERZTL. Intell.-Bl., 1866, XIII, pp. 150-152.]

Griffith (G. de G.) Treatment of cholera by chloroform inhalation.
[DUBLIN Med. Press & Circ., 1866, II, pp. 228-229.]

Guidraud. Chloroforme à haute dose dans le choléra.
[GAZ. des hôp., 1867, p. 55.]

Heath (G. Y.) Chloroform in cholera; vomiting.
[LANCET, 1853, I, n. s., pp. 377-378.]

Hewlett (T.) Chloroform in cholera.
[PROVINCIAL Med. & Surg. Jour., 1847-48, pp. 585-587.]

Hill (J.) Treatment of the cholera by chloroform, etc., in Peckham House (poor) asylum.
[LANCET, 1848, II, pp. 514, 566.]

Lamprey (J.) Chloroform as a remedy for cholera.
[MED. Times, 1849, XIX, pp. 286-287.]

McClellan (E.) Chloroform in sporadic cholera.
[MED. & Surg. Reporter, 1867, XV, pp. 158-160.]

Merrill (A. P.) Suggestions regarding cholera.
[N. Y. Med. Jour., 1866, II, pp. 126-128.]

Mighels (J. W.) On the use of chloroform in the treatment of cholera.
[WESTERN Lancet, 1849, IX, pp. 211-217.]

Moffat (J.) On chloroform in cholera.
[LANCET, 1848, II, pp. 551-552; *also, in* MED. Times, 1849, XIX, pp. 242, 307.]

Stedman (J. B.) Chloroform in cholera.
[MED. Times, 1848, XVIII, p. 271.]

Strother (R. S.) Case of cholera in which chloroform was successfully given internally.
[WEST. Jour. of Med. & Surg., 1849, I, pp. 119-120.]

Van Wyck (P. C.) On the use of chloroform in the collapse of cholera.
[N. Y. Jour. of Med., 1850, IV, pp. 207-210.]

Vincent (H.) Mémoire à l'Academie de médecine sur le traitement du choléra asiatique par le chloroforme, précédé de quelques considérations générales sur l'épidémie de suette et de choléra qui a régné en 1854 dans le canton d'Ay. 8°. *Épernay*, 1856.

Wolseley (W. A.) On the use of chloroform in spasmodic diarrhœa.
[EDINB. Med. Jour., 1858, IV, pp. 117–118.]

——— Chloroform in cholera.
[LANCET, 1853, II, n. s., p. 354.]

Emploi du chloroforme dans le choléra au début.
[L'UNION méd., 1849, III, p. 162.]

Cider.

Mitchell (W.) Rough cider in cholera.
[LANCET, 1853, II, pp. 354.]

Tucker (J. H.) Cider as a remedy for cholera.
[LANCET, 1856, II, n. s., p. 237.]

Cinchona. (See, also, *Quinine.*)

Ensor (S. R.) Bark in cholera. Appearance in Mr. Ensor's case.
[LANCET, 1831–32, I, pp. 800–801.]

Negri (C.) Observations on Mr. Ensor's supposed case of cholera; and the treatment of that disease with bark.
[LANCET, 1831–32, I, pp. 696–697.]

——— Character and treatment of cholera.
[LONDON Med. Gaz., 1832, IX, pp. 349–351.]

Neue specifische Heilmethode der epidemischen Cholera oder (richtiger) des Cholera-Fiebers, mittelst des fiebervertreibenden Princips der Chinarinde. 8°. *Hannover*, 1831. L.

Cinnamon (*Oil of*).

Scheider. Versuche mit dem Oleum Cinnamomi acuti in der Cholera.
[ALLG. med. Cent.-Zeit., 1854, XXXIII, pp. 201–203.]

Coca.

Reis. Note sur l'emploi du coca en thérapeutique, et notamment dans le traitement du choléra.
[BULL. gén. de thérap. méd. et chir., 1866, LXX, pp. 175–177.]

Coffee.

[B[aud] (C.)] De la préservation du choléra et de l'emploi du café de santé dans le traitement de cette maladie. 8°. *Paris* [1832].

Cold. (See *Temperature.*)

Columbo.

Caron. De l'emploi du vin de ... composé dans le traitement du ...
[GAZ. des hôp., 1854, p. 256.]

Hoppé (G.) Notice sur l'emploi ... trait aqueux de la racine de ... dans le choléra. .... 8°. *Par...*

Observations lues à la Société ... cine pratique, sur le traitement ... léra par l'emploi du vin de ... composé, du Dr. C. A. **Caron**. ... Letellier. ... 8°. *Paris*, 1854.

Copper (*Salts of*).

Burq. L'emploi du cuivre et de ... l'intérieur et à l'extérieur dans le ... ment du choléra.
[FRANCE (La) méd. et pharm., Paris, ... 184.]

Burq (V.) Emploi du sulfate de ... dans le traitement du choléra.
[L'UNION méd., 1865, XXVIII, 2e s., pp. 57...

——— Mémoire sur l'action préser... et curative du cuivre dans le ch... ... Précédé d'une lettre à M. le M... 8°. *Paris*, 1865.

Escallier. De l'emploi du cuivre ... moyen préservatif et curatif dans le ... léra asiatique, à propos du mémoire ... Dr. Burq. 8°. *Paris*, 1853.

——— Préservation du choléra asi... De la vertu préservatrice du cui... propos du mémoire du Dr. Burq. ... 8°. *Paris*, 1854.

Groussin. Choléra. Traitement par ... sulfate de cuivre.
[GAZ. des hôp., 1866, p. 394.]

Guttmann (P.) Ueber die Anwend... der Kupferpräparate in der Cholera ... cases.)
[BERL. klin. Wochenschr., 1866, III, pp. 4...

Lisle (E.) Note sur le traitement du ... léra par le sulfate de cuivre.
[GAZ. des hôp., 1865, pp. 506–507.—L'U... 1865, XXVIII, 2e s., pp. 145–149.—Wie... Wochenschr., 1866, pp. 1132–1134, 1...

Morrah (J.) Sulphate of copper in ... era.
[LONDON Med. Gaz., 1832, X, pp. 601–602.]

——— Sulphate of copper in mal... cholera.
[LANCET, 1832–33, I, p. 54.]

Pellarin (C.) Traitement du choléra ... le sulfate de cuivre.
[L'UNION méd., 1865, XXVIII, 2e s., pp. 93–96

Bur les expériences faites à l'hôpital Lariboisière avec les sels de cuivre dans le traitement du choléra.
[Gaz. des hôp., 1866, pp. 425–426.]

Traitement du choléra par le sulfate du cuivre.
[Gaz. des hôp., 1867, pp. 89–90.]

Counter-irritation. (See, also, *Cupping.*)

Alberti (P.) Preparazione di una sostanza ammoniacale da impiegarsi esternamente nella cura del cholera-morbus.
[Gaz. med. it. Lomb., 1849, II, 2a s., pp. 351–352.]

Barclay (J.) Hot mustard baths in the collapse stage of British cholera.
[Brit. Med. Jour., 1865, II, pp. 494–495.]

Baudon (A., *fils*). Bons effets des grands bains sinapisés au début du choléra.
[Bull. gén. de thérap. méd. et chir., 1855, XLIX, pp. 317–321.]

Bullar (J.) The hot mustard hip-bath in diarrhœa and choleraic diarrhœa.
[Brit. Med. Jour., 1865, II, pp. 524–525.]

——— On mustard hot baths in the collapse of Asiatic cholera.
[Brit. Med. Jour., 1865, II, p. 416.]

——— On the hot water and mustard hip-bath in cholera.
[Brit. Med. Jour., 1865, II, pp. 469–470.]

Charmasson (A.) Note sur une méthode de traitement du choléra qui a donné les résultats le plus constamment heureux [d'essence de mente et de sinapismes aux extrémités].
[Jour. des connaiss., 1848, XVI, pp. 8–10.]

Crawcour (J. L.) Treatment of cholera by spirituous affusion and friction.
[Lancet, 1854, II, n. s., p. 216.]

Dangel. De l'urtication pour amener la réaction dans le choléra.
[Revue de thérap., 1854, II, pp. 425–426.]

Frary (F. B.) * De la méthode révulsive cutanée dans le traitement du choléra-morbus épidémique. 4°. *Paris*, 1834. L.

Greenhow (T. M.) External stimulus in cholera.
[Lancet, 1853, II, n. s., p. 323.]

Humpel (J. G.) De abdomine cantharidibus exulcerando, in cholerae morbi curatione remedio. 8°. *Vindobonae*, 1830. L.

Joseph (E.) Malignant cholera, treated with turpentine frictions and enemas, and bleeding.
[Lancet, 1835–36, II, pp. 824–825.]

Kelly. Nitrous acid blister in cholera.
[Med. Times, 1849, XIX, pp. 531–532.]

Landerer. Ueber eine den Juden in Smyrna eigenthümliche glückliche Methode die Cholerakranken zu kuriren. (With "Anmerkung von Dr. A. Buchner sen.") [Counter-irritation.]
[Neue med.-chir. Zeitung, 1848, IV, pp. 161–165.]

Lee (C. A.) Cholera ointment.
[Boston Med. & Surg. Jour., 1833, VII, pp. 17–18.]

Lefebure. Réaction locale tardive, mais très énergique, développée à la suite de l'application dès sinapismes ou des vésicatoires.
[Gaz. des hôp., 1832, VI, pp. 170–171.]

Lindsey. On the treatment of cholera, particularly with reference to the use of mustard poultices.
[London Med. Gaz., 1832, IX, pp. 519–523.]

Ranque. Nouveau traitement du choléra-morbus.
[Bull. gén. de thérap. méd. et chir., 1832, I, pp. 10–14.]

Reeves (W.) On the pathology and treatment of cholera. Disturbance of the spinal centre remedied by counter-irritation over the spine.
[Lancet, 1849, II, pp. 269–270.]

Rodet. Choléra; révulsion par la moutarde.
[Jour. de méd. et de chir. prat., 1848, XIX, pp. 609–610.]

Schrattenholz (W.) "Choleracontra", ein neuentdecktes, einfaches Hausmittel zur radicalen und sichern Heilung der Cholera-Morbus und vieler andern, bisher für unheilbar gehaltenen Krankheiten und Gebrechen auf mechanischem Wege; zugleich das sicherste Schutzmittel gegen Ansteckung. 12°. *Bonn*, 1855. L.

Sheldrake (T.) Treatment of cholera on a new principle.
[Lancet, 1832, I, pp. 491–492.]

Sylva. Révulsifs puissants contre la période algide du choléra.
[Jour. des connais., 1849, XVI, p. 101.]

Turnbull (A.) On the treatment of malignant cholera with capsicum embrocations.
[Lancet, 1848, I, pp. 119–120.]

Wernicki. De la médication stimulante dirigée principalement sur la peau dans le choléra.
[Jour. des connais., 1849, XVII, pp. 197–198.]

Blisters in cholera; their mode of action.
[Western Jour. of Med., 1867, II, pp. 42–44.]

Boule (La) du choléra, ou traitement du choléra par l'opération indienne.
[Gaz. hebd. de méd. et de chirurg., 1853-54, I, p. 844; 1855, II, pp. 467-468.]

Counter-irritation in cholera.
[London Med. Gaz., 1832, IX, p. 540.]

Creosote.

Cain (D. J.) The use of creosote in cholera morbus, cholera infantum, and other morbid states of the system—its mode of action.
[Charleston Med. Jour. & Rev., 1852, VII, pp. 145-154.]

Dartigue (G. B.) Creosote in cholera.
[Phila. Med. Times, 1871, II, p. 8.]

Healey (E. A.) Creosote in cholera.
[Lancet, 1837-38, I, p. 214.]

Holderness (E.) Creosote injections in cholera.
[Med. Counselor, 1855, I, pp. 551-552.]

Mackenzie (J.) The cholera at Archangel—failure of kreosote as a remedy.
[London Med. Gaz., 1848, VII, n. s., pp. 811-812.]

Cupping.

Hoggan (W. J.) Cupping, a remedy for cholera.
[Med. Circular, 1854, V, p. 140.]

Hufeland (C. W.) Trockne Schröpfköpfe (Ventosen) gegen die Cholera.
[Jour. d. prakt. Heilk., 1831, LXXI, pp. 128-129.]

Cupping in asphyxia and cholera.
[Lancet, 1831-32, I, pp. 167-168.]

Diuretics.

Barracano (G.) Le choléra-morbus, traité par une nouvelle méthode qui a produit les plus heureux résultats dans les années 1836 et 1837, pendant que ce terrible fléau exerçait ses ravages sur la ville de Naples. 8°. *Naples*, 1852. L.

——— The same. [In English.] 8°. *Naples*, 1853. L.

Meldon (A.) Contributions to the pathology and treatment of cholera: some cases successfully treated on the diuretic plan.
[Dublin Med. Press & Circ., 1866, II, pp. 538-539, 577-578.]

Dosimetric.

Burggraeve. Instructions pour le choléra [traitement dosimétrique].
[Répert. de méd. dosimétr., 1872-73, I, pp. 515-516, 530.]

Traitement dosimétrique de la diarrhée prémonitoire [diarrhée cholérique].
[Répert. de med. dosimétr., 1872-73, I, pp. 73-77.]

Dry-packing.

Dry packing in cholera.
[Med. Times & Gaz., 1866, II, p. 65.]

Electricity. (See, also, *Galvanism.*

Atkinson (J. C.) Electricity in ch-ra
[Lancet, 1849, II, p. 50.]

Beroaldi (P.) Sugli esperimenti co... corrente elettro-magnetica nella cura d... choléra, eseguite nell'ospedale civile pr... vinciale di Venezia.
[Giorn. venet. d. sc. med., 1855, V, 3a s., pp. ...-298.]

Byrd (H. L.) The therapeutical application of electro-magnetism in cholera.
[Charleston Med. Jour. & Rev., 1853, VIII, pp. 628-630.]

Culis *et* **Courtray** (de). Essais faits à l'hôpital de Mons pour le traitement du choléra asiatique à l'aide de l'électro-magnétisme.
[Bull. de l'Acad. roy. de méd. de Belgique, 1858-59, II, suppl., p. 179.]

Dupeyron. Le cholera traité par l'électricité. 8°. *Nîmes*, 1866.

Morrill (*Mrs.* S. E.) Electricity the remedy of cholera.
[Eclectic Med. Jour., 1873, XXXIII, pp. 230-23...]

Poggioli (M. P.) Nouvelle application de l'électricité par frottement sans commotion sur l'homme sain et sur l'homme malade. (Cause et traitement rationnel du choléra.) 8°. *Paris*, 1854.

Pravaz. Sur un nouveau mode d'emploi de l'électricité dans le traitement du choléra-morbus.
[Gaz. méd. de Paris, 1832, III, pp. 163-164.]

Rebold (E.) Moyens simples et faciles de combattre le choléra asiatique, la peste et la fièvre jaune, avec indication des causes de ces maladies, des lieux de leur naissance et des moyens d'en préserver à jamais les populations. 8°. *Paris*, 1865. L.

Schulz (B.) Das Resultat einiger Versuche über die elektrische Sensibilität und elektro-muskulöse Kontraktilität bei Cholera-Kranken, ferner über das Verhalten der Elektricität gegen einige charakteristische Cholera-Symptome.
[Wien. med. Wochenschr., 1855, pp. 37-52.]

Zantedeschi (F.) Studj di elettro-fisiologia considerato ne' suoi rapporti con la terapia del coléra-morbus principalmente.
[Gaz. med. it. Lomb., 1855, VI, 3a s., pp. 29...-30...]

Eliminative.

Bourne (E.) Anti-stimulant and anti-narcotic treatment of the malignant cholera.
[LANCET, 1832-33, I, pp. 306-311.]

Flint (A.) Remarks on the theory of elimination as applied to epidemic cholera.
[MED. Record, 1866-67, I, pp. 97-98.]

Kinglake (H.) On the evacuant and astringent plans of treating cholera.
[BRIT. Med. Jour., 1866, II, p. 281.]

Laloy. Traitement du choléra par la méthode évacuante.
[ARCH. gén. de méd., 1849, III, pp. 129-153.]

Larroque (B. de). De la méthode évacuante dans le traitement du choléra.
[L'UNION méd., 1849, III, pp. 201-202, 213-214.]

Phelan (D.) The eliminative treatment of cholera.
[DUBLIN Med. Press & Circ., 1866, II, pp. 255-256.]

Tebay (T. G.) Remarks on cholera treatment and the eliminative theory.
[LANCET, 1866, II, pp. 203-204.]

Traitement du choléra par la méthode évacuante.
[L'UNION méd., 1849, III, pp. 161-162, 173-174.]

Emetics.

Beaman (G.) On the treatment of malignant cholera, chiefly with emetics of common salt.
[LANCET, 1833-34, II, pp. 754-755; *also, in* LONDON Med. Gaz., 1834, XIV, pp. 781-782.]

Behrend (F. J.) Ueber die Anwendung des Brechmittels gegen die Cholera. *Schönberg*, 1831.

Burrows (I.) Cases of malignant cholera successfully treated with emetics of common salt.
[LANCET, 1833-34, II, pp. 892-894.]

Evans (G.) Treatment of cholera by emetics.
[INDIA Jour. of Med. Sci., 1835, I, pp. 212-213.]

Furlong (J. S.) A note on mustard emetics in cholera.
[ARMY Stat., San., & Med. Repts., London, 1865, VII, pp. 577-578.]

Furnivall (J. J.) Administration of emetics of common salt in cholera.
[LANCET, 1833-34, II, p. 836.]

Godrich (F.) Objections to reliance on salt emetics in all stages of malignant cholera.
[LANCET, 1834, II, p. 895.]

Haslewood (W.) Mustard emetics in cholera.
[LONDON Med. Gaz., 1832, IX, p. 592.]

Jones (R.) Treatment of cholera by emetics, warm water, and acids.
[MED. Times & Gaz., 1858, XVI, p. 230.]

Leighton (J.) On the treatment of cholera and dysentery, with emetics.
[LANCET, 1833-34, II, pp. 834-835.]

Lesage. Observation sur un choléra-morbus guéri par l'émétique [tartre stibié].
[GAZ. des hôp., 1832, VI, p. 218.]

Milroy (G.) On the use of emetics in cholera.
[LONDON Med. Gaz., 1848, XLII, pp. 714-717, 879-883, 961-966; 1849, XLIII, pp. 54-58.]

Mordy (W.) General results of emetics in cholera.
[LONDON Med. Gaz., 1832, IX, pp. 795-796.]

Musgrave (H. B.) Observations on the use of emetics in cholera.
[WESTERN Lancet, 1849, X, pp. 284-290.]

Pollock (T.) Cure of cholera with salt emetics.
[LANCET, 1834, II, p. 837.]

Reed (S.) Observations on the utility of emetics in cholera.
[WESTERN Med. Gaz., 1835, II, pp. 49-58.]

Robertson (A.) Treatment of malignant cholera on board the Cumberland, convict hulk. Efficacy of mustard emetics—failure of the saline treatment and venous injections—evidences of contagion.
[LANCET, 1831-32, II, pp. 557-559.]

Téallier. De l'emploi des émétiques dans le traitement du choléra-morbus.
[TRANS. méd., Jour. de méd. prat., 1832, IX, pp. 172-197.]

Todd (R. B.) Emetics of common salt in malignant cholera.
[LANCET, 1834, II, p. 806.]

Venables (R.) Administration of emetics in malignant cholera.
[LANCET, 1833-34, II, pp. 807-808.]

Enemata (Cold-water).

Ueber die ausserordentlich vortheilhafte Wirkung der kalten Wasserklystiere in der Brechruhr oder Cholera.
[JOUR. der prakt. Heilk., 1831, LXXII, pp. 69-86.]

Enemata (Narcotic.)

Hallett (W.) Narcotic clysters in cholera.
[LONDON Med. Gaz., 1832, X, p. 513.]

Enemata (Saline).

Morgan (A. B.) On hot saline enemata in cholera.
[LONDON Med. Gaz., 1838-39, XXIII, pp. 478-480.]

Murray (J.) Saline enemata in cholera.
[LONDON Med. Gaz., 1838-39, XXIII, pp. 892-894.]

On the use of saline enemata in cholera, being extracts from a correspondence in the conservative newspaper. *Madras*, 1838.
[MADRAS Quar. Med. Jour., 1839, I, pp. 216-228.]

Enemata (Tobacco).

Casanova. Account of several cases of cholera, treated by tobacco enema.
[TRANS. Med. & Phys. Soc., Calcutta, 1835, VII, pp. 485, 486.]

Ergot.

Hamburger (W.) Ueber das Wesen der asiatischen Brechruhr und die Behandlung Derselben mit Secale cornutum. 8°. *Dresden und Leipzig*, 1849. L.

Preston (W. B.) The ergot of rye in cholera.
[LANCET, 1842-43, II, pp. 655-656.]

Sussdorff (G. E.) Ergot as a remedial agent in epidemic cholera.
[ATLANTA Med. & Surg. Jour., 1873, XI, p. 183.]

Ether.

Beauregard. Le choléra-morbus traité par l'éther et l'opium à haute dose.
[REVUE de thér., 1854, II, pp. 423-424.]

Bernard. Avis au peuple sur le choléra-morbus asiatique, traité au moyen de l'éther sulfurique opiacé à haute dose. 8°. *Paris*, 1849,

Lemberger (J.) Vorschlag, Einathmungen von Aethyloxyd- [Schwefeläther-], insbesondere von Aethylchlorür- [Salzäther-] Dämpfen im ersten Stadio der asiatischen Cholera anzuwenden.
[OESTERR. med. Wochenschr., 1847, pp. 1483-1494.]

Mead (G. B.) Chloric ether: its properties and uses, especially in choleraic and other forms of diarrhœa and in cholera.
[ASSOC. Med. Jour., 1854, II, pp. 819-820, 905-908.]

Pitt (W.) Inhalation of æther in Asiatic cholera.
[SAN FRANCISCO Med. Press, 1860, I, p. 11.]

Roux (A. L.) Recherches sur la dilution du sang par l'éther sulfurique soufré, comme moyen préventif et curatif du choléra.
[MONIT. des hôp., 1856, IV, pp. 740-744.]

Roux (A. L.)—continued.

——— Mémoire sur la dilution du sang par l'éther sulfurique soufré, comme moyen préventif et curatif du choléra. 4°. *Paris*, 1856.

Choléra guéri par les inhalations de l'éther sulfurique.
[GAZ. des hôp., 1847, pp. 513-514.]

Eupatorium.

Hill (R.) On the use of eupatorium cannabinum in the treatment of cholera.
[NEW YORK Med. Times, 1855, IV, pp. 48-51.]

Stulo (W. E.) On the use of eupatorium villosum and nervosum in the treatment of cholera.
[LANCET, 1854, II, p. 113.]

Van Dromme. Sur l'emploi de l'eupatorium cannabinum contre le choléra asiatique. [Extrait.]
[BULL. de l'Acad. roy. de méd. de Belgique, 1861, IV, pp. 359-368.]

Galvanism. (See, also, *Electricity.*)

Bowie (R.) Treatment of cholera by galvanism.
[LONDON Med. & Surg. Jour., 1832, I, pp. 259-261.]

Burq (M. V.) Mémoire sur quelques accidents nerveux consécutifs au choléra et sur leur traitement par les armatures métalliques.
[GAZ. méd. de Paris, 1850, V, pp. 82-87.]

Favel (C. F.) On the employment of galvanism in cases of malignant cholera.
[LANCET, 1832-33, I, pp. 710-713.]

Ingle (T.) Application of galvanism in cholera.
[LONDON med. Gaz., 1832, IX, p. 264.]

Knapp (J.) Case of cholera treated by means of galvanism.
[LONDON Med. Gaz., 1832, IX, p. 896.]

Knight (P. S.) Galvanism and soda in cholera.
[LONDON Med. Gaz., 1832, IX, pp. 593-594.]

Kowalewsky (O.) Locale Faradisation bei der Cholera.
[MED. Zeitung Russlands, 1857, p. 237.]

Meinig (C.) Use of a galvanic current in cholera.
[MED. Times & Gaz., 1854, IX, n. s., p. 334.]

Munsell (L.) On the use of galvanism in cholera.
[AMER. Jour. of Med. Sci., 1832, XI, pp. 250-251.]

Poelman. Rapport sur le traitement du choléra par l'électro-galvanisme.
[BULL. de l'Acad. roy. de méd. de Belgique, 1860, III, pp. 165-168.]

Tweedale (J.) Galvanism in cholera, &c.
[London Med. Gaz., 1832, IX, pp. 262-264.]

——— Galvanism, without shock, in cholera—fever in general.
[London Med. Gaz., 1832, IX, pp. 502-510.]

Maladies régnantes.—Choléra endémique. —Crampes des cholériques. Traitement par les armatures métalliques.
[Gaz. des hôp., 1861, p. 393.]

On the use of galvanism in the treatment of cholera.
[London Med. Gaz., 1849, XLIV, pp. 435-436.]

Proper mode of employing galvanism in cholera.
[London Med. Gaz., 1832, IX, pp. 860-861.]

Thérapeutique du choléra.—Emploi du galvanisme, du haschich et du stachys anatolica.
[Gaz. des hôp., 1849, pp. 151-152.]

Garlic.

Granich (G. F.) Sur l'emploi de l'ail et de ses préparations contre le choléra.
[Revue méd.-chir. de Paris, 1853, XIV, pp. 321-325.]

Lange. De la propriété fébrigène de l'ail et de son emploi dans le choléra.
[Revue méd.-chir. de Paris, 1853, XIII, pp. 65-72.]

Gold (Chloride of).

Biermann. Idee zur Anwendung des salzsauren Goldes (Aurum muriaticum) in der Cholerakrankheit.
[Med. Conversationsblatt, 1831, pp. 302-304.]

Guaco.

Bally. Nouveaux cas de choléra ; emploi du guaco.
[Gaz. des hôp., 1832, VI, pp. 400, 413-414.]

Chabert (J. L.) Du huaco et de ces vertus médicinales. Réflexions médicales sur le choléra-morbus et son traitement avec la mikania huaco. 8°. *Paris*, 1853.

Pereyra (E.) Essais de la plante huaco dans le traitement du choléra. 8°. *Paris et Bordeaux*, 1832.

——— Ensayos hechos en Burdeos de la planta huaco, para la curacion del cólera-morbo. Puesto en español por J. R. Pacheco. 8°. *Paris*, 1833.

Valentin (W.) Die Mikania Guaco, ein Mittel gegen die Cholera.
[Wien. med. Wochenschrift, 1853, III, pp. 689-693.]

"**Tincture** of guaco" in the treatment of cholera asiatica.
[Med. Circular, 1853, III, p. 325.]

Treatment of the cholera of Mexico with the guaco.
[Lancet, 1834-35, II, p. 596.]

Gunpowder.

Roux (A. L.) Note sur l'emploi de la poudre à canon dans le traitement du choléra.
[Gaz. méd. de Paris, 1853, VIII, 3e s., pp. 822-823.]

Hæmospasia.

Junod (T.) De l'emploi de la méthode hémospasique dans le traitement du choléra épidémique.
[Revue méd., 1849, II, pp. 393-414; 1855, I, pp. 272-280.]

——— The same. 8°. *Paris*, 1849. L.

McKenna (J. W.) Efficacy of Dr. Murray's exhausted air-bath in cholera.
[London Med. & Surg. Jour., 1833, II, p. 186.]

Murray (J.) Success of Dr. Murray's exhausted air bath in cholera.
[London Med. & Surg. Jour., 1832, I, p. 806.]

——— Removal of atmospheric pressure from the bodies of cholera patients.
[London Med. & Surg. Jour., 1833, II, p. 186.]

Cholera in Dublin. Dr. Murray's plan of treatment. [Removing the pressure of the atmosphere from the body.]
[London Med. & Surg. Jour., 1832, I, p. 765.]

Heat. (See *Temperature.*)

Homœopathy.

Andrien (A. F.) Instruction pour le traitement homœopathique préservatif et curatif du choléra. 8°. *Agen*, 1854.

[**Béchet.**] Appréciation de l'expérimentation clinique du traitement homœopathique contre le choléra, faite à l'Hôtel-Dieu de Marseille . . . . 8°. *Avignon*, 1855.

Bigel (J.) Ausführliche Vorlegung der von dem berühmten Dr. Hahnemann vorgetragenen Heilungsart der asiatischen Cholera, mit der Anweisung des Mittels, sich vor dieser Krankheit zu schützen. 8°. *Breslau*, 1831.

Bolle. Anleitung zur sicheren und schnellen Heilung der Cholera—für verständige Laien und angehende homöopathische Aerzte. 8°. *Aachen*, 1866. L.

Campani (M.) Il cholera e l'omiopatia.
[Gaz. med. Ital. Tosc., 1854, IV, pp. 301-305.]

Chargé. Traitement homœopathique préservatif et curatif du choléra épidémique. Précédé de quelques aphorismes par le Dr. Turrel. 16°. *Toulon*, 1849.

Chargé—continued.

——— The same. . . . Instruction populaire pouvant servir de guide en l'absence du médecin. Notes relatives à la dernière épidémie. 8e éd. 8°. *Marseille*, 1854. L.

[4th to 7th ed., same place and year; 10th and 11th ed., Paris, 1865–66.]

——— L'homœopathie et ses détracteurs, à l'occasion de l'épidémie de choléra qui a régné à Marseille en 1854. 8°. *Paris*, 1855.

——— Congrès homœopathique de Bruxelles. Trois jours d'homœopathie à l'Hôtel-Dieu de Marseille, pendant le choléra de 1855. 8°. *Paris*, 1857.

Cricca (A.) À propos du choléra. 2e éd. Après le choléra. 8°. *Smyrne*, 1865. L.

——— L'homœopathie en présence du choléra à Smyrne en 1865. Nouvelle éd. 8°. *Paris*, 1866. L.

Cruchet (F.) L'homœopathie et le choléra de 1854, à Marseille. Réponse aux homœopathes en général et à M. Chargé en particulier. 8°. *Marseille*, 1854.

Curie (P. F.) A treatise on cholera, English and Asiatic, with directions for the homœopathic treatment. 8°. *London*, 1849. L.

Dechenaux. Choléra. Instruction populaire sur les moyens préservatifs de cette maladie, selon la méthode homœopathique. 12°. *Paris* [1854].

[2d ed., same year.]

Duplat. Traitement homœopathique . . . du choléra épidémique. 8°. *Lyon*, 1849.

[Feuillet.] Préservatifs homœopathiques du choléra. (1854.) 8°. *Lons-le-Saunier* [*n. d.*]

Gerstel (A.) Mittheilungen über die homöopathische Therapie der Cholera.

[Homöopathische Vierteljahrschr., 1855, VI, pp. 91–108.]

Guillon, *dit* Le Thière. Instruction sur le traitement homœopathique de la cholérine et du choléra. 8°. *Paris* [1856].

Häusaler (F.) Dr. Samuel Hahnemann und die asiatische Cholera.

[Med. Conversbl., 1831, pp. 305–312, 313–315.]

Hamilton (E.) A short history of the cholera; with a few hints as to its prevention by homœopathic treatment. 2d ed. 8°. *London*, 1848. L.

Hempel. Homœopathic treatment of cholera.

[Ecl. Med. Jour., 1849, I, n. s., pp. 449–451.]

Henoke. Zur homöopathischen Therapie der Cholera.

[Beiträge zur Heilk., Riga, 1851, I, pp. 129–134.]

Hoffendahl (C. F.) On the homœopathic treatment of cholera. 8°. *Boston*, 1849. L.

Hufeland (C. W.) Arsenik das homöopathische Mittel gegen die Cholera.

[Jour. der pract. Heilk., 1830, LXXI, p. 112.]

——— Homöopathie. Die Homöopathie gegen die orientalische Cholera angewendet.

[Jour. der pract. Heilk., 1832, LXXIV, pp. 4–17.]

Humphreys (F.) The cholera and its homœopathic treatment. 8°. *New York*, 1849. L.

Jahr (G. H. G.) Du traitement homœopathique du choléra, avec l'indication des moyens de s'en préserver. 18°. *Paris*, 1848.

Jal. Le choléra-morbus, traité en Russie par l'homœopathie. 8°. *Paris*, 1848.

Joslin (B. F.) The varieties, different stages and symptoms of cholera, and the homœopathic treatment.

[Ecl. Med. Jour., 1849, I, n. s., pp. 363–374.]

——— Homœopathic treatment of epidemic cholera. 3d ed. 8°. *New York*, 1854. L.

Kallenbach. Alweêr een Cholera-Middel!

[Schat d. Gezondh., Haarlem, 1866, IX, pp. 316–317.]

Kammerer (K.) Homöopathische Behandlung der asiatischen Cholera nach Herrn Dr. Samuel Hahnemann, als die sicherste unter den bisher bekannten Behandlungsarten, seinen Landsleuten empfohlen. 12°. *Stuttgart*, 1832. L.

Kurtz (P. T. E.) Kurze Anweisungen über die homöopathische Behandlung der asiatischen Cholera. Für Aerzte und Nichtärzte. 8°. *Breslau*, 1836.

Lade (G.) Case of cholera treated with irisin.

[Homœopathic Rev., 1866, X, pp. 503–505.]

Latière. De l'homœopathie et du choléra. Le choléra à la Seyne en septembre 1865. 8°. *Toulon*, 1865.

Lee (J. G.) De aziatische Cholera. Hare Kenteekenen, homœopathische Genezing. Eerste Gedeelte, voor Geneeskundigen en Niet Geneeskundigen. 8°. *Gravenhage*, 1848. L.

Lecoupeur (V. E.) Du cholera épidémique, de sa préservation et de son traitement homœopathique. 8°. *Paris*, 1854. L.

Libaudière (A.) Traitement préservatif et curatif du choléra-morbus asiatique .... d'après les procédés de l'homœopathie. 8°. *Nantes*, 1848.

Lippe (A.) Cholera. [Lecture delivered at the Homœopathic Med. Coll. of Penna., Dec. 8, 1865.] 8°. *Philadelphia*, 1866. L.

Lobethal. Ueber die glückliche Behandlung der asiatischen Cholera durch die homöopathische Heilmethode. 8°. *Breslau*, 1848. L.

Mabit (J.) Lettre au conseiller Sam. Hahnemann, sur le traitement homœopathique du choléra-morbus asiatique. 8°. *Bordeaux*, 1833.

Malapert Du Peux (J. U.) Traitement homœopathique, préservatif et curatif du choléra-morbus. 18°. *Lille*, 1865.

Martin de Roguebrune. Choléra. Homœopathie. Quelques mots à M. le Dr. Chargé. 8°. *Marseille*, 1854.

Merrill (A. P.) Homœopathy and cholera.

[Med. Record, 1866–67, I, pp. 273–275.]

Mordwinoff (N. L. v.) Ein Wort über Homöopathie. Nebst einem Briefe und Verzeichniss über die im Gouvernement Saratoff in Russland bei Cholerakranken mit dem glücklichsten Erfolge angewandten homöopathischen Heilmittel. Ins Deutsche übersetzt von J. Ekkenstein. 8°. *Dresden*, 1832.

Moreau. Remèdes homœopathiques préservatifs et curatifs du choléra. 12° *Bordeaux* [1855].

Perrussel (F.) La suette et le choléra épidémiques traités par l'homœopathie. Rapport à S. E. le ministrie de l'agriculture, du commerce et des travaux publics. 8°. *Paris*, 1856. L.

Pitet. Official report on the treatment of cholera, cholerine, and the sweating sickness in the department of L'Aube in France.

[Monthly Homœop. Rev., 1857, I, pp. 213–223.]

Quin (F. F.) Du traitement homœopathique du choléra, avec notes et appendice. 8°. *Paris*, 1832. L.

—— The same. [In German.] 8°. *Dresden und Leipzig*, 1832. L.

[Rapou (A.)] À M. le Dr. Villeneuve, président de la commission chargée du rapport sur la brochure intitulée: "L'homœopathie et ses détracteurs." 1855. 4°. *Lyon* [*n. d.*]

Rapou (T.) Seul traitement préservatif et curatif du choléra asiatique .... d'après les procédés homœopathiques. 8°. *Paris*, 1835.

Richard (B.) L'homœopathie en présence du choléra de 1865, ou correspondance d'un médecin de province avec les ministres de S. M. l'empereur Napoléon III. 8°. *Nantes*, 1866.

Röhl. Bestätigte Heilung der Cholera durch homöopathische Arzneien. Ein Wort des Trostes an die Bewohner des seiner Obhut anvertrauten Bezirks. 8°. *Eisleben*, 1831.

Romani (F.) Su i preservativi omiopatici del colera indiano, e su la disinfettazione degli edifizi e de' mobili contagiati. 8°. *Napoli*, 1836.

Roth (J. J.) Die homöopathische Heilkunst in ihrer Anwendung gegen die asiatische Brechruhr dargestellt. 8°. *Leipzig*, 1833. L.

—— Neueste Erfahrungen auf dem Felde der homöopathischen Heilkunde, zur freundlichen Mittheilung für homöopathische Aerzte. 1. Heft. Cholera morbus. 8°. *München*, 1837.

Roux. Préservatifs homœopathiques à mettre en usage contre le choléra-morbus épidémique, et résultats obtenus par l'homœopathie dans le traitement curatif de cette affection. 8°. *Montpellier* [1854].

—— L'homœopathie appliquée au traitement du choléra-morbus épidémique. Observations recueillies en 1854 et en 1855, avec un appendice sur la question des doses infinitésimales. 8°. *Paris*, 1857.

Rubini (R.) Statistica dei colerici curati omiopaticamente in Napoli nel real albergo dei poveri nel 1854, e di quei in altri tempi omiopaticamente ed allopaticamente curati qui ed altrove. 8°. *Napoli*, 1855. L.

Russell (J. R.) A treatise on epidemic cholera, with an appendix of cases treated in the Edinburgh homœopathic dispensary, 1848–49, and a map showing

Russell (J. R.)—continued.
the course of the cholera from India to Britain. 8°. *London*, 1849. L.

Salevert de Fayolle. Résumé du traitement homœopathique, préservatif et curatif du choléra épidémique. 12°. *Lyon*, 1849.

Sèbe. Traitement homœopathique du choléra, avec la manière de s'en préserver. 8°. *Toulouse*, 1865.

Schmit (A.) Anhang zu Sam. Hahnemann's Aufruf an denkende Menschenfreunde über die Ansteckungsart der asiatischen Cholera. 8°. *Leipzig*, 1831.

Schröter *in Lemberg.* Glückliche Heilung der Cholera asiatica, auf homöopathischem Wege. Nach einem Schreiben an die Versammlung homöopathischer Aerzte in Naumburg. 8°. *Leipzig*, 1831.

Schubert (J. A.) Die asiatische Cholera und ihre durch die Erfahrung bestätigte homöopathische Heilung und Verhütung. 8°. *Leipzig*, 1848. L.

Schwabe (W.) Die Cholera, ihre schnelle und sichere Heilung durch die Homœopathie. Nach den neuesten und besten Erfahrungen zusammengestellt. 12°. *Berlin* [1866]. L.

—— The same. 6. Aufl. 12°. *Leipzig.* L.

Schweikert (J.) Homöopathischer Rathgeber bei Cholera-Erkrankungen, enthaltend eine kurze Darstellung cholera-artiger Erkrankungen und der asiatischen Cholera, nebst Angabe der für den ersten Augenblick anzuwendenden nöthigsten homöopathischen Arzeneimittel. 8°. *Breslau*, 1853. L.

Sollier, Rampal, *et* **Gillet.** Lettre à M. le président de la Société impériale de médecine de Marseille, en réponse au rapport sur la brochure du Dr. Chargé, intitulée: "L'homœopathie et ses détracteurs." 8°. *Marseille*, 1855.

Sollier (*père*), **Rampal, Gillet** *et* **Sollier** (*fils*). Traitement homœopathique . . . du choléra épidémique. 8°. *Marseille*, 1854.

Tessier (J. P.) Recherches cliniques sur le traitement de la pneumonie et du choléra suivant la méthode de Hahnemann, précédées d'une introduction sur [illegible] de la statistique en médecine

Tessier (J. P.)—continued.
—— **Clinical researches** concerning the homœopathic **treatment** of Asiatic cholera. Preceded by a review on the use of the numerical method in medicine. Translated by Ch. J. Hempel. 8°. *New York*, 1855. L.

Vernois (M.) Sur le traitement du choléra par l'homœopathie.
[L'UNION méd., 1849, III. pp. 173-176.

Auszüge brieflicher Mittheilungen aus Wien, die asiatische Cholera, deren Eigenthümlichkeiten und ihre homöopathische Behandlung betreffend. 8°. *Leipzig*, 1832.

Authentischer Bericht über die glücklichen Erfolge der homöopathischen Heilmethode in der asiatischen Cholera. 8°. [*n. p.*,] 1831. L.

Cholera.
[HOMŒOPATHIC Rev., 1865, IX. pp. 577-[illegible]

Choléra, homœopathie, compression de l'abdomen.
[JOUR. de méd. et de chir. prat., 1855, XXVI. pp. 433-435.]

Cholera, Homöopathik und Medicinalbehörde in Berührung. Thatsachen zum Besten des homöopathischen Noththeilungsfonds herausgegeben vom Leipziger Localverein homöopathischer Aerzte. 8°. *Leipzig*, 1831. L.

Cholera (Die) mit dem besten Erfolge bekämpft durch die homöopathische Curart. Nach Auszügen aus den Schriften von Hahnemann, A. Schmidt, Bute, F. Quin, J. A. Schubert, J. J. Roth. 8°. *Bremen*, 1835. L.

Cholera. Return to an address of the house of commons, dated 17 May 1855, for, "copies of any letters which have been addressed to the general board of health, complaining of the omission of any notice of certain returns in relation to the treatment of cholera, which returns were sent to the general board of health in pursuance of a circular dated September last, and issued by the board; and of any correspondence which has passed between the president of the board and the medical council: together with copies of the returns which have been rejected by the medical council." (Ordered, by the house of commons, to be printed, 21 May 1855.) 8°. [*n. p., n. d.*] L.

Choléra-morbus épidémique: de son traitement préventif et curatif selon la méthode homœopathique. 8°. *Paris*, 1848. L.

Einfache Schutz- und Heilmittel wider die Cholera, nach homöopathischen Grundsätzen. Nebst einem Verzeichniss der erlaubten und unerlaubten Speisen und Getränke vor und während dem Daseyn dieser Krankheit. 8°. *Dresden*, 1831?

Homœopathie (L') et le choléra.
[L'UNION méd., 1849, III, p. 170.]

Homöopathische Heilung der Cholera. Mittheilungen eines praktischen Arztes in Italien. 8°. *Leipzig*, 1837.

Homœopathy and cholera.
[PROV. Med. & Surg. Jour., 1848, pp. 587-588.]

Returns from homœopathic hospitals as to their treatment of cholera. 1855.

Sicherste Heilung und Ausrottung der asiatischen Cholera. (Von Sam. Hahnemann.) 4. mit den Regeln der homöopathischen Diät stark vermehrte und verbesserte Anfl. 12°. *Leipzig*, 1831.

Traitement homéopathique du choléra-morbus, d'après plusieurs médecins du nord. 8°. *London*, 1832. L.
[Ms. note "par Gueyrard."]

Traitement homœopathique, préservatif et curatif du choléra épidémique. Résumé succinct des meilleurs ouvrages homœopathiques, par J. A. . . . . 16°. *Marseille* [1854].

Horseradish.

Le Neve (G. F.) Malignant cholera. Treated with compound infusion of horseradish.
[LANCET, 1831-32, II, p. 747.]

Stevens (R.) Infusion of horse radish, calomel, opium, etc., in the malignant cholera.
[LANCET, 1832-33, I, p. 178.]

Huaco. (See *Guaco.*)

Hydrotherapia. (See, also, *Water.*)

Bloch (A.) Choléra traité pendant la période algide par l'enveloppement dans un drap mouillé et dans une couverture de laine. (Case.)
[GAZ. des hôp., 1873, p. 931.]

Costa Saya (A.) L'idroterapia, il colera e l'igiene pubblica. Lettera al Dr. Francesco Genovesi. 12°. *Messina*, 1873. L.

Czerwinski (J.) Hydrotherapie der Cholera, sammt Darlegung physiologischer Principien, auf denen jene im Allgemeinen beruht. 8°. [*n. p.*,] 1867. L.

Griffith (R.) Cholera from a hydropathic standpoint.
[MED. Mirror, 1868, V, pp. 135-141.]

Guettet. De l'hydrothérapie appliquée au traitement du choléra [méthode de Priessnitz tui-même].
[REVUE méd., 1853, I, pp. 331-343.]

Honsebruck (Van). Note sur l'usage des bains froids administrés suivant la méthode hydropathique, comme moyen préservatif du choléra épidémique. Rapport de M. Craninx.
[BULL. de l'Acad. roy. de méd. de Belgique, 1848-49, VIII, pp. 3-10.]

Monchet. De l'hydrothérapie contre le choléra.
[REVUE méd., 1852, II, pp. 599-602.]

Ray (G.) *and* **Farmer** (J.) Treatment of cholera by external cold and moisture.
[LANCET, 1849, II, p. 104.]

Richter (C. A. W.) Die Wasserkur verhütet und beseitigt die Cholera.
[PUTZAR'S Jour. f. naturgem. Gesundh.-Pflege 1855, III, pp. 257-267.]

Shew (J.) The cholera, its causes, prevention, and cure: showing the inefficacy of drug-treatment, and the superiority of the water-cure, in this disease. 8°. *New York*, 1849. L.

——— The same. 1855. L.

Steadman. Asiatic cholera. Hydropathic treatment.
[AMER. Jour. of Med. Sci., 1850, XIX, pp. 76-78; *also, extr. from* REC. of Bost. Soc. for Med. Imp., Boston, 1853, I, pp. 51-54.]

Wertheim. Traitement du choléra, d'après Priessnitz.
[BULL. gén. de thérap. méd. et chir., 1850, XXXIX, pp. 438-441.]

Wie Vincenz Priessnitz die epidemische Brechruhr behandelt wissen wollte.
[OESTERR. Zeitschr. f. pract. Heilk., 1865, XI, pp. 804-806.]

Hypodermic Injection.

Bauduy (J. K.) Hypodermic medication in cholera.
[ST. LOUIS Med. Reptr., 1867-68, II, pp. 641-643.]

Beigel (H.) Treatment of cholera by hypodermic injections of warm water.
[LANCET, 1866, II, pp. 352-353.]

Bonnemaison (J.) Des injections hypodermiques dans le choléra.
[L'UNION méd., 1873, XVI, 3e s., pp. 562-564.]

Cantani (A.) Sulla cura del cholera con injezioni sottocutanee di grandi quantità d'acqua salata tiepida. 8°. *Venezia*, 1866. S. C.

Drasche. Ueber die Anwendung subkutaner Injektionen bei der Cholera.
[WIEN. med. Wochenschr., 1866, pp. 1083–1085.]

——— Ueber die Wirksamkeit subcutaner Injectionen von Arzneimitteln bei der Cholera.
[WIEN. med. Wochenschr., 1866, pp. 1193–1195, 1209–1211, 1225–1227, 1244–1245, 1260–1261, 1276–1278, 1289–1292.]

Goldbaum. Die hypodermatische Injection im asphyctischen Stadium der Cholera.
[BERLIN. klin. Wochenschr., 1866, III, pp. 341–342.]

Gübner (I.) Letchenie cholery podkojnymi vpryskivaniami.
[MEDYTZYNSKIY Viestnik, St. Petersburg, 1866, No. 22, pp. 211–214.]

Hall (A. R.) The treatment of cholera.
[LANCET, 1875, I, p. 183.]

Lorent (E.) Ueber die Anwendung der hypodermatischen Injectionen in der Cholera.
[ZEITSCHR. f. pract. Heilk. und Med., 1867, IV, pp. 213–220.]

Massart (E.) Des injections hypodermiques dans le choléra.
[L'UNION méd., 1873, XVI, 3e s., pp. 594–596.]

Oser *und* **Drasche.** Ueber subcutane Injectionen by Cholerakranken.
[OESTERR. Zeitschr. f. pract. Heilk., 1866, XII, pp. 799–801.]

Penzel (R.) * Einiges ueber die subcutanen Injectionen bei Cholera. 8°. *Leipsig*, 1867. L.

Ullersperger (J. B.) Ueber subkutane Injectionen bei Cholera.
[WIEN. med. Presse, 1866, VII, p. 729.]

On hypodermic treatment of cholera.
[MED. Circular, XXVII, 1865, p. 456.]

Ice.

Husemann (G.) Die Behandlung der Cholera mit Eis. 8°. *Erlangen*, 1837.

Siegert (A.) Das Eis innerlich gebraucht als Heilmittel der asiatischen Cholera durch eine Menge von Thatsachen bewiesen. Nebst einem Anhange, in dem einige erfolgreiche Versuche des Eises in seiner inneren Anwendung gegen verschiedene Leiden aufgeführt werden. 2te Aufl. 8°. *Leipsig*, 1853.
[1st ed. in 1852.]

Westmacott (J. G.) Ice in the treatment of cholera.
[MED. Times., 1849, XX, p. 98.]

Ignatia.

Cavalsassi-papi (T.) Cenni storici e. cholera morbus del secolo XIXe riflessioni teorico-pratiche sulla polvere di ignazia amara proposta dal prof. Gio. Battista Ghirelli. 8°. *Roma*, 1855.

Inhalation. (See, also, *Oxygen.*)

Coxe (E. J.) Inhalation, and Asiatic cholera.
[BOSTON Med. & Surg. Jour., 1854, I, pp. 3[illegible]

Searle (C.) Inhalations in cholera.
[LONDON Med. Gaz., 1832, IX, p. 597, 1 plate.]

Inhalation in cholera.
[LONDON Med. Gaz., 1832, IX, p. 288.]

Note sur la réapparition du choléra-morbus; son traitement par l'inspiration de substances gazeuses.
[JOUR. de méd. et de chir. prat., 1832, III, pp. 233–234.]

Injections (*Saline, and into veins*).

Albertoni (P.) Injezione di siero di latte nelle vene per un tentativo di cura di cholera.
[GAZ. med. ital. prov. Veneta, 1873, XVI, pp. 241–242, 267.]

Aldred (C. C.) Case of cholera treated by saline injections.
[LONDON Med. Gaz., 1832, X, pp. 453–454.]

Ancell. Recovery from . . . . collapse of cholera after repeated injections of a saline solution into the basilic vein.
[ASSN. Med. Jour., 1854, p. 760.]

Anderson (J.) Memoranda of five cases of cholera in which saline injections were used.
[LONDON Med. Gaz., 1832, X, pp. 383–384.]

Anderson (W. C.) Effects of saline venous injection in cholera.
[LANCET, 1832–33, II, pp. 111.]

Blasius. Infusion in der Cholera.
[MED. Zeitung, 1833, p. 115.]

Carruthers (D. C.) Case of malignant cholera successfully treated by venous injection. Delivery of a child on the third day.
[LANCET, 1831–32, II, pp. 461–462.]

Casper (J. L.) Drei Fälle von Salzinjectionen in die Venen bei Cholera-Kranken.
[WOCHENSCHR. f. d. ges. Heilk., 1833, I, pp. 24–25–32.]

Casson (R.) Injection of saline and of serum into the veins in cholera.
[LONDON Med. Gaz., 1832, X, pp. 418–421.]

Christison (R.) On the new treatment of cholera.
[LONDON Med. Gaz., 1832, X, pp. 451–453.]

Colson. Des injections dans les veines des cholériques.
[BULL. de l'Acad. imp. de méd., 1865–66, XXXI, pp. 949–961.]

Davis (E. G.) Case of spasmodic cholera in which the saline injection was employed three times in succession—apparent improvement—subsequent sinking—death.
[BOSTON Med. & Surg. Jour., 1833, VII, pp. 222–225.]

Duchaussoy (A.) Des injections faites par les veines dans le traitement de choléra épidémique. 8°. *Paris*, 1855. L.

Dujardin-Beaumetz. Des injections d'eau et de solutions salines par les veines dans le traitement de la période algide et ultime du choléra.
[L'UNION méd., 1873, XVI, 3e s., pp. 619–630; *also, in* BULL. et mém. Soc. méd. des hôp., 1873, X, 2e s., p. 321; *also*, reprint in 8°, Paris, 1873.]

Evans (W. P.) Treatment of cholera by saline injections.
[LANCET, 1849, I, p. 19.]

Fearn (S. W.) Trial of venous saline injections in a case of malignant cholera.
[LANCET, 1832–33, I, pp. 47–48.]

Gamba (F.) Injezioni nelle vene per la cura del cholera.
[GAZ. med. ital. prov. Venete, 1873, XVI, pp. 257–258.]

Gaselee (C.) Cholera—saline injections—death.
[LONDON Med. Gaz., 1832, X, pp. 355–356.]

Girdwood (G. F.) Cases of malignant cholera treated by venous injection.
[LANCET, 1831–32, II, pp. 594–596.]

Greenhow (E.) Saline injection in cholera.
[LONDON Med. Gaz., 1832, X, p. 511.]

Harper. Malignant cholera; collapse; partial attempts at reaction; return of collapse in greater intensity; saline alcoholic venous injection. Death. Autopsy.
[LANCET, 1849, II, n. s., pp. 260–262.]

Hénocque (A.) Revue sur le traitement du choléra par les injections veineuses. [Traduit de l'anglais et annoté.]
[GAZ. hebd. de méd. et de chirurg., 1866, 2e s., III, pp. 732–740, 790–791.]

Hope. Saline injections in cholera.
[LONDON Med. Gaz., 1832, X, pp. 353–355.]

Howlett (H.) Case of cholera successfully treated by saline injection.
[MED. Times, 1849, XX, p. 268.]

——— Treatment of cholera by saline injection.
[LANCET, 1849, II, p. 269.]

Jackson (T. C.) Report of a fatal case of cholera, treated by the saline injection.
[LANCET, 1849, II, n. s., pp. 144–145.]

Latta. Injections into the veins in cholera.
[LONDON Med. Gaz., 1832, X, pp. 379–382.]

Latta (T.) Cases of malignant cholera treated by the injection of saline fluids into the veins.
[LANCET, 1831–32, II, pp. 369–373.]

——— Saline venous injection in cases of malignant cholera, performed while in the vapor bath.
[LANCET, 1832–33, I, pp. 173–176, 208–209.]

——— Reply to some objections offered to the practice of venous injections in cholera.
[LANCET, 1831–32, II, pp. 428–430.]

Lawrie (J.) On saline injections in cholera.
[LONDON Med. Gaz., 1832, X, pp. 443–448.]

Lewins (R.) Injection of saline solutions in extraordinary quantities into the veins in cases of malignant cholera.
[LANCET, 1831–32, II, pp. 243–244.]

——— Malignant cholera. Documents communicated by the central board of health, London, relative to the treatment of cholera by the copious injection of aqueous and saline fluids into the veins.
[LANCET, 1831–32, II, pp. 274–280.]

——— Letter on saline injections in a case of cholera.
[LONDON Med. Gaz., 1832, X, pp. 382–383.]

——— Queries put by the central board of health to Dr. Lewins, relative to saline injections into the veins in cholera, with the doctor's reply to the same.
[LONDON Med. Gaz., 1832, X, pp. 289–290.]

Little (L. S.) On the introduction of fluids into the veins in cholera by gravity.
[MED. Times & Gaz., 1867, I, pp. 354–356, 1 pl.]

——— Notes on unsuccessful and successful cases of saline alcoholic injections into the veins for relief of collapse of malignant cholera, treated during the epidemic of 1848–9.
[CLIN. Lec. & Reps. of London Hosp., 1866, III, pp. 132–166.]

——— A case of cholera treated by saline alcoholic injection into the veins; with observations.
[DUBLIN Med. Press & Circ., 1867, III, pp. 186–187.]

——— Cases of cholera successfully treated by saline injection into the veins, and

Little (L. S.)—continued.
autopsies of cases unsuccessfully injected, with remarks.
[CLIN. Lec. & Reps. of London Hosp., 1867-68, IV, pp. 431-442.]

Lorain (P.) Sur un fait de thérapeutique expérimentale dans un cas de choléra. Note de M. P. Lorain présentée à l'Academie des sciences par M. H. Saint-Claire Deville.
[GAZ. des hop., 1867, pp. 14-15.]

McCabe (J.) The treatment of cholera by the injection of saline solutions into the veins, not warranted by the pathological condition of the blood.
[LANCET, 1832, II, pp. 528-529.]

Marcet (W.) Saline injections in cholera.
[MED. Times & Gaz., 1853, VII, n. s., p. 586.]

Meikle (G.) Trial of saline venous injections in malignant cholera at the Drummond street hospital, Edinburgh.
[LANCET, 1831-32, II, pp. 748-750.]

Miller (S.) Saline injections in cholera.
[LONDON Med. Gaz., 1832, X, pp. 540-543.]

Miquel. Traitement du choléra-morbus par des injections salines froides dans la vessie.
[GAZ. des hôp., 1835, IX, p. 429.]

Murchison. Case of cholera treated with saline injections into the veins.
[LANCET, 1866, II, p. 412.]

Murchison (C.) Case of cholera treated with saline injection into the veins of a lower temperature than that of the blood. (Death.)
[TRANS. of Clinic. Soc., 1869, II, pp. 174-178.]

Netter (A.) Des injections qui se pratiquent dans les veines des cholériques, et de la cause des variations de résultats obtenus jusqu'ici avec ce moyen thérapeutique.
[GAZ. des hôp., 1873, p. 1107.]

Rees (G. O.) Saline injections in cholera.
[MED. Times & Gaz., 1853, VII, n. s., p. 612; *also, in* LANCET, 1853, I, n. s., p. 313.]

Scoutetten. Injections veineuses dans le choléra.
[GAZ. hebd. de méd. et de chirurg., 1866, III, 2e s., pp. 553-554.]

Sims. Cases of cholera which were treated by saline injections into the veins, at the St. Marylebone Infirmary.
[LONDON Med. Gaz., 1832, X, pp. 384-386.]

Stevenson (J. G.) Case of cholera treated by saline injections.
[BOSTON Med. & Surg. Jour., 1833, VII, pp. 181-185.]

Tweedie (A.) Saline injections in cholera.
[LONDON Med. Gaz., 1832, X, pp. 289-293.]

Woodman *and* Heckford. Case of cholera—saline injection into the veins—death—autopsy.
[MED. Times & Gaz., 1866, II, p. 252.]

——— ——— Two cases of cholera—saline injections into the veins—recovery of one of the patients.
[MED. Times & Gaz., 1866, II, pp. 312-313.]

Venables (R.) Two cases of malignant cholera in which venous injections were successfully employed.
[LANCET, 1831-32, II, pp. 398-401.]

Weatherill (T.) Case of malignant cholera, in which four hundred and eight ounces of fluid were injected into the veins with success.
[LANCET, 1831-32, II, pp. 688-689.]

Zimmermann. Glücklicher Erfolg der Einspritzung einer Salzauflösung in die Vene einer Cholera-Kranken. Erster Versuch in Tentschland.
[JOUR. der prakt. Heilk., 1832, LXXV, pp. 101-]

Case of sporadic cholera, treated successfully by saline injections into the veins—consecutive fever.
[LONDON Med. & Surg. Jour., 1831, I, pp. 666-6]

Full (A) account of the operation of injecting the veins with aqueous and saline liquids, for the cure of malignant cholera, in the most hopeless case. From the last number of the London Lancet. 8°. *New York*, 1832.

Injection of salts into the veins in cholera.
[LONDON Med. Gaz., 1832, IX, pp. 368-369.]

Injections of large quantities of saline solutions into the veins, successfully adopted in some cases of malignant cholera.
[LONDON Med. & Phys. Jour., 1832, XIII, p. 77-84.]

Results of the injections into the veins in the cholera hospital, Drummond street, Edinburgh.
[LONDON Med. Gaz., 1832, X, p. 453.]

Saline injections in cholera.
[BOSTON Med. & Surg. Jour., 1833, VII, pp. 170.]

Special report on the treatment of cholera by venous injections.
[DUBLIN Med. Press & Circ., 1866, II, pp. 464-466, 507-509, 539, 573, 589-591; III, pp.

Sur les injections intra-veineuses d'eau de solutions salines dans le traitement du choléra.
[BULL. gén. de thérap. méd. et chir., pp. 370-377.]

Traitement (Le) du choléra-morbus par des injections salines.
[Gaz. des hôp., 1832, VI, pp. 253-255, 258-259, 261-262, 268.]

Valeur thérapeutique des injections veineuses dans le choléra.
[Jour. de méd. et de chir. prat., 1873, XLIV, 3e s., pp. 500-501.]

Ipecacuanha.

Alibert. Choléra-morbus traité par l'ipécacuanha et le tartre stibié.
[Gaz. des hôp., 1832, VI, pp. 85-86.]

Briquet. Traitement du choléra-morbus par l'ipécacuanha.
[Revue de thérap. med.-chirurg., 1854, II, p. 36.]

Girard (A.) Traitement du choléra. Emploi de l'ipéca dans la première période. 8°. *Marseille*, 1865.

Hugot (F. C. P.) * Traitement rationnel du choléra par l'emploi méthodique de l'ipécacuanha et de la saignée. 4°. *Paris*, 1853. L.

Kennedy (J.) Ipecacuanha in cholera.
[Lancet, 1834, [illegible] p. 837.]

Lair. Sur le traitement du choléra par l'ipécacuanha.
[Gaz. des hôp., 1832, VI, pp. 82-90.]

Potter (S. H.) Ipecac and prickly ash the best remedies for cholera morbus and cholera infantum.
[Eclectic Med. Jour., 1870, XXX, pp. 396-400.]

Van Leeuwen van Duivenbode (P. J.) De Aanprijzing van Radix Ipecacuanhae tegen Cholera.
[Geneesk. Courant, Tiel, 1853, No. 44.]

Woodhull (A. E.) Clinical studies with large non-emetic doses of ipecacuanha: with a contribution to the therapeusis of cholera.
[Atlanta Med. & Surg. Jour., 1875, XII, pp. 659-673, 705-722; XIII, pp. 10-28, 80-94.]

——— The same. 8°. *Atlanta, Georgia*, 1875. L.

Bons effets de l'ipécacuanha dans la période phlegmorrhagique du choléra morbus.
[Bull. gén. de thérap. méd. et chir., 1853, XLV, pp. 559-560.]

De l'action comparative du tartre stibié et de l'ipécacuanha dans le traitement de l'épidémie cholérique.
[Gaz. méd. de Paris, 1832, III, pp. 596-597.]

De l'emploi de l'ipecacuanha dans le traitement du choléra-morbus.
[Gaz. des hôp., 1832, VI, pp. 136-138, 141-142.]

Iron.

Küchenmeister. Ob man die Cholera in ihrer Weiterverbreitung durch Darreichung von Eisenpräparaten mit Kalksalzen in kleinen Dosen beschränken kann?
[Wien. med. Wochenschr., 1855, p. 637.]

Reynolds (T.) Preparations of iron in cholera.
[Brit. Amer. Jour. of Med. & Phys. Sci., 1849, V, pp. 90-91.]

Santirocco e Profilo. Il ferro contro il cholera. Storie cliniche e fatti analoghi; terapia anticholerica e metodo pratico. 8°. *Napoli*, 1866.

Cholera i zelezo.
[Medytzynskiy Vlestnik, St. Petersburg, 1866, 6th year, No. 18, p. 212.]

Iron (Citrate of).

Andrei (A.) Resultati di cure di malati di cholera trattati col citrato di ferro ammoniacale a S. Vito e a Celie in terra di Otranto.
[L'Imparziale, 1867, VII, pp. 465-462.]

Bizzarri (A.) Sul citrato di sesquiossido di ferro e di ammoniaca, rimedio proposto contro il cholera.
[Sperimentale (Lo), 1867, XX, pp. 287-288.]

Rossi (F.) Sull'azione del citrato di ferro nel cholera asiatico. (6 cases.)
[Gaz. med. it. Lomb., 1867, 5a s., pp. 261-263.]

Sonsino (P.) La terapeutica del cholera e il citrato di ferro. 16°. *Torino*, 1866. S. C.

Iron (Hydrated oxide of).

Preis. Liquor ferri oxydati hydrati gegen die Cholera asiatica angewandt.
[Med. Zeitung, 1848, p. 207.]

Heigl. Eisenoxydhydrat als Heilmittel bei Cholera und Typhus.
[Allg. med. Central-Zeitung, 1857, XXVI, p. 318.]

Iron (Oxide of).

Schwimmer (E.) Zur Cholera-Therapie. Das Ferrum oxydatum dialysatum ein Versuchsmittel bei profusen Diarrhöen.
[Wien. med. Wochenschr., 1866, pp. 1321-1323, 1339-1341, 1356-1357.]

Iron (Perchloride of).

Vaillandel (A.) Du perchlorure de fer associé à l'opium dans le traitement des affections cholériques.
[Bull. gén. de thérap. méd. et chir., 1867, LXXII, pp. 127-132.]

Iron (Persesquinitrate of).

Kerr (W.) Additional evidence of the efficacy of the persesquinitrate of iron in curing diarrhœa, with cases illustrating its power in curing the premonitory diarrhœa of cholera.
[GLASGOW Med. Jour., 1832, v, pp. 215-227.]

Iron (Sesquichloride of).

Buchheister (J. C.) Liquor ferri sesquichlorati gegen Cholera asiatica. (4 cases.)
[DEUTSCHE Klinik, 1859, XI, pp. 313-314, 413-414.]

Hancorn (J. R.) Malignant cholera successfully treated with tincture of the muriate of iron.
[LANCET, 1832-33, I, p. 108.]

Vicente. Choléra; emploi du sesquichlorure de fer; encore un mot sur la strychnine; électricité.
[L'ABEILLE méd., 1854, XI, pp. 321-322.]

——— Emploi du sesquichlorure de fer dans le traitement du choléra. Ouverture d'un paquet cacheté déposé en décembre 1853.
[COMPT. rend. d. séanc. de l'Acad. d. Sci., 1854, XXXIX, pp. 740-742.]

——— Emploi du sesquichlorure de fer dans le traitement du choléra.
[MONIT. des hôp., 1854, II, pp. 1037-1038.]

Iron (Sulphate of).

Hastings (J.) Sulphate of iron administered in malignant cholera.
[LANCET, 1832-33, II, pp. 816-817; *also, in* DOCTOR, 1833-34, II, pp. 116-117.]

Juniperberries (Oil of).

Wachter (F.) Der durch Erfahrung bewährte, heilsame Gebrauch des Wacholderöls bey Behandlung der Cholera-Kranken, etc. 8°. *Tirnau*, 1831.

Laurocerasus.

Taroni (F.) Cura del cholera sporadico con l'acqua coobata delle foglie di lauroceraso.
[OMODEI, Ann. un. di med., 1832, LXI, pp. 447-454.]

Lead (Salts of).

Beckett (C.) Brief notes on the effects of therapeutic agents in cholera. (The lead treatment.)
[LONDON Med. Gaz., 1849, XLIV, pp. 619-621, 704-706, 879-882.]

Colvan (J.) Case of collapsed cholera successfully treated. [Acetate of lead and opium.]
[DUBLIN Med. Press, 1849, XXII, pp. 193-194.]

Drake (D.) Note on the efficacy of the acetate of lead in several cases of epidemic cholera.
[WESTERN Jour. of Med. & Phys. Sci., 1832, VI, pp. 402-408.]

Flemming. Two cases of British cholera: use of acetate of lead and morphia in solution; prompt recovery; remarks.
[BRITISH Med. Jour., 1848, II, pp. 695-697.]

Harlan (R.) On acetate of lead in dysentery and malignant cholera.
[MED. Examiner, 1838, I, pp. 127-131.]

Morehead (C.) Notes on the treatment of cholera with acetate of lead.
[TRANS. Med. & Phys. Soc., Bombay, 1838, III, pp. 237-243.]

Price (A. B.) Observations on the use of sugar of lead in the treatment of cholera and dysentery.
[WESTERN Jour. of the Med. & Phys. Sci., 1832, pp. 19-26.]

Tatham (G.) Case of Asiatic cholera in a child. Recovery. Beneficial effects produced by the acetate of lead.
[LONDON Med. Gaz., 1849, XLIII, pp. 81-82.]

Toms (P.) Case of cholera treated successfully by acetate of lead and opium.
[MED. Times & Gaz., 1854, VIII, pp. 55-57.]

Tostain. Recherches thérapeutiques sur l'acétate de plomb, son efficacité dans les diarrhées, la dyssenterie, le choléra, etc.
[L'ABEILLE méd., 1854, XI, pp. 281-283.]

Ligature.

Clerinx. Emploi de la ligature circulaire des membres, dans le traitement du choléra.
[GAZ. méd. de Paris, 1831, II, p. 407.]

Lime-water.

Blackall (J.) Lime water and milk and spiritus ammoniæ compositus, in the treatment of malignant cholera.
[LANCET, 1832-33, I, pp. 176-178.]

Grandesso-Silvestri (O.) Dell'uso dell'acqua di calce nel cholera.
[GAZ. med. Ital. prov. Veneto, 1858, XI, pp. 53-54.]

Haller (M.) Mittheilungen über angestellte Versuche mit der von Einigen empfohlenen Aqua calcis bei der Cholera.
[OESTERR. Zeitschr. f. pract. Heilk., 1855, I, pp. 109-111.]

Pasquali. Sur l'emploi de l'eau de chaux comme remède du choléra. Rapport verbal de M. Tallois.
[Bull. de l'Acad. roy. de med. de Belgique, 1855-56, xv, pp. 10-12.]

Lime-water in cholera.
[Med. Circular, 1853, iii, p. 323.]

Zur Cholera.
[Deutsche Klinik, 1855, vii, pp. 359-361.]

Lobelia.

Pearson (J.) The lobelia quackery in cases of cholera, and its effects.
[London Med. Gaz., 1849, xliv, p. 472.]

Magnesia (Sulphite of).

Behr. Ueber die Wirkung der Magnesia sulfurosa bei der Cholera asiatica.
[Deutsche Klinik, 1866, xviii, p. 299.]

Magnetism (Animal.)

Wasch (C. J.) Een Woord over der Cholera, in Verband met het animalisch Magnetisme. 8°. *Rotterdam* [*n. d.*]

Matico.

Slipper (T.) On the use of matico in the treatment of cholera.
[London Med. Gaz., 1849, xliv, p. 296.]

Mercury (Bichloride of).

Hart (F. J.) Cases of malignant cholera, treated principally by corrosive sublimate and acetate of lead.
[Lancet, 1831-32, ii, pp. 561-562; *also, in* London Med. Gaz., 1832, x, p. 579.]

Winn (J. M.) Bichloride of mercury in cholera.
[Lancet, 1854, ii, n. s., p. 216.]

Mercury (Frictions with).

Delannoy (W. H.) Treatment of malignant cholera with opium and mercurial frictions.
[Lancet, 1832-33, i, pp. 45-46.]

Godlewski (M.) Effets remarquables des frictions mercurielles dans un cas de choléra-morbus.
[Jour. des connaiss., 1848, xv, p. 149.]

Parkin (H. H.) Mercurial frictions in malignant cholera.
[Lancet, 1834-35, ii, p. 662.]

Tytler (J.) Observations on mercurial frictions in cholera morbus.
[Trans. Med. & Phys. Soc. of Calcutta, 1831, v, pp. 213-236.—Lancet, 1831-32, ii, p. 562.—Gaz. des hôp., 1832, vi, pp. 366-367, 370-371.]

Mercury (Fumigations with).

Penneck (H.) Treatment of the malignant cholera, mercurial fumigations, etc.
[Lancet, 1832-33, i, pp. 108-110.]

Cure for cholera in the collapse stage. [Mercurial vapors.]
[India Jour. of Med. & Phys. Sci., 1838, iii, n. s. p. 157.]

Mercury (Sulphate of).

Cadet (S.) La peste colerica e il solfuro nero di mercurio detto comunemente etiope minerale. 8°. *Roma*, 1869. L.

——— Nouvelles études sur le choléra asiatique. La sulfure noire de mercure proposée pour préserver l'Italie de ce terrible fléau. Traduction du compte Charles des Dorides. 8°. *Rome*, 1872. L.
[Also, 8°, Rome, 1873.]

Knapp (J). Nature and treatment of cholera.
[London Med. Gaz., 1832, ix, pp. 599-600.]

Metals.

Valade-Gabel. Choléra. Préservation et traitement par les métaux. 8°. *Paris*, 1853. L.

Choléra. Préservation et traitement par les métaux . . . . 8°. *Paris*, 1853.

Pure metals a remedy in cholera.
[Med. Times & Gaz., 1853, vii, n. s., p. 462.]

Milk (Injection of).

Herapath (W. B.) On the employment of injections of milk, or milk and water, into the peritoneal cavity, cellular tissue, or venous system, in the collapse of cholera.
[Assn. Med. Jour., 1854, p. 793.]

Milk (Transfusion of).

Hodder (E. M.) Transfusion of milk in cholera.
[Med. Brief, Wilson, N. C., 1873, i, p. 67.]

——— Transfusion of milk in cholera.
[Practitioner, London, 1873, x, pp. 14-16.]

Searle (H.) Proposal to use the serum extracted from cow's milk, instead of the saline solution, for the purpose of injecting the veins of patients in the last stage of malignant cholera.
[Lancet, 1831-32, ii, pp. 619-620.]

Monesia.

Laurand. Quelques observations sur l'efficacité du monésia contre la cholérine.
[Jour. des connaiss. 1846, xiv, pp. 110-111.]

Morphia.

Ashe (I.) The subcutaneous injection of morphia in cholera.
[MED. Times & Gaz., 1862, II, n. s., p. 644.]

Darin. Traitement du choléra par les injections morphinées hypodermiques.
[GAZ. des hôp., 1873, p. 962.]

Gérard (F.) Mémoire sur l'efficacité de l'acétate de morphine dans le choléra-morbus.
[REVUE méd. franç. et étrang., 1836, III, pp. 65–75.]

Irving (J.) Subcutaneous injection of morphia in cholera.
[LANCET, 1871, II, p. 766.]

Patterson (J.) Treatment of cholera by subcutaneous injection of morphine.
[MED. Times & Gaz., 1872, I, pp. 95–96.]

Ritter (F.) Kurze Mittheilungen aus der medicinischen Klinik des Ernst-August-Hospitals zu Göttingen. Subcutane Morphiuminjection, angewendet gegen heftige Crampi bei Cholera nostras.
[ZEITSCHR. für pract. Heilk. u. Med., 1865, II, pp. 590–591.]

Werry (A.) Subcutaneous injection of morphia in cholera.
[LANCET, 1871, II, p. 737.]

Observations sur l'emploi de l'acétate de morphine dans le choléra-morbus.
[JOUR. de méd. et de chir. prat., 1836, VII, pp. 468–471.]

Movement.

Dally (N.) Prophylaxie et curation du choléra par le mouvement. 2e éd. 8°. *Paris*, 1856. L.
[1st ed., 1855.]

Roth (M.) Treatment of diseases by movements, especially of cholera.
[MED. Circular, 1855, VII, p. 164.]

Mechanical treatment of cholera, by a physician. 8°. *London*, 1866. L.

Musk.

Laming (R.) Successful treatment of cholera with musk.
[LANCET, 1831–32, II, p. 754.]

Mustard. (See *Counter-irritation, Emetics.*)

Naptha. (See, also, *Petroleum.*)

Child (H. T.) On the use of acetone or wood naptha in cholera.
[MED. Exam., 1849, V, n. s., pp. 457–459.]

Napthalin.

Atkinson (J. T.) A new remedy in English cholera.
[LANCET, 1848, II, p. 220.]

Nitrous oxide.

Booth (A.) New remedy [nitrous oxide gas] for cholera.
[LONDON Med. & Surg. Jour., 1833, II, p. 4.]

Hancock (J.) Observations on the nature and treatment of cholera and other pestilential diseases, and on the gaseous oxide of nitrogen as a remedy in such diseases: [etc.] 8°. *London*, 1831. L.

Lepage. Rapport sur l'emploi du gaz protoxyde d'azote dans le traitement du choléra-morbus. 8°. *Orléans*, 1832.

On nitrous oxide in cholera.
[MED. Times, 1849, XX, pp. 207–208.]

Oils.

Paterson (G. K. H.) Inquiry into the use of fats or oils in the treatment of cholera.
[MED. Circular, 1854, IV, pp. 169–170.]

Oil (*Cajeput*).

Robinson (R. R.) Cholera treated with cajeput oil.
[LONDON Med. Gaz., 1832, IX, pp. 119–120.]

Tierney (M. I.) Cajeput oil in cholera.
[LONDON Med. Gaz., 1831, VIII, pp. 671, 683–6[illegible].]

Tierny (*Sir* M.) Cajeputi oil in cholera.
[TRANS. Med. & Phys. Soc. of Calcutta, [illegible] p. 485.]

Oil (*Castor*).

Complin (E. J.) Castor oil treatment of cholera.
[MED. Times & Gaz., 1854, IX, n. s., p. 37[illegible].]

——— Castor-oil treatment of cholera on board the hospital-ship "Dreadnought."
[MED. Circular, 1854, V, pp. 161–162.]

——— On the treatment of cholera by castor oil.
[LANCET, 1854, II, n. s., p. 297.]

Johnson. Castor oil treatment of cholera.
[MED. Times & Gaz., London, 1866, II, p. [illegible].]

——— Five cases of cholera—castor oil treatment.
[MED. Times & Gaz., 1866, II, pp. 115–116.]

Johnson (G.) Treatment of cholera by castor oil.
[MED. Times & Gaz., 1854, IX, n. s., pp. [illegible].]

——— Cholera and choleraic diseases admitted during the last fortnight, treated successfully by repeated doses of castor oil, effervescing draughts at intervals, and occasionally brandy.
[LANCET, 1856, II, n. s., pp. 222–223.]

Kelly (J. W.) Castor oil in cholera.
[MED. Circular, 1854, V, pp. 160, 157.]

Oil (*Croton*).

Bartlet (J.) Croton oil in cholera.
[LONDON Med. Gaz., 1832, IX, p. 863.]

Douglas (S.). Efficacy of croton oil in cholera.
[LONDON Med. & Surg. Jour., 1833, II, pp. 408–411.]

Gillespie (P.) Croton oil in cholera.
[LANCET, 1833, I, pp. 181–182.]

Hackett. Croton oil in cholera.
[LONDON Med. & Surg. Jour., 1832, I, p. 92.]

Hancox (H.) Croton oil in cholera.
[LANCET, 1833, II, p. 354.]

Hewett (W. W.) Croton oil in cholera.
[LONDON Med. Gaz., 1832, IX, p. 936.]

Tegart (E.) Croton oil in cholera.
[DOCTOR, 1833, I, p. 53; *also, in* LONDON Med. & Surg. Jour., 1833, II, pp. 119–120.]

Ward (T. O.) On the administration of croton oil in malignant cholera.
[LANCET, 1831–32, II, pp. 773–774.]

——— Croton oil in cholera—recovery under the saline treatment.
[LONDON Med. Gaz., 1832, X, pp. 728–729.]

Croton oil and phosphorus in Asiatic cholera.
[DUBLIN Med. Press, 1846, XVI, p. 218.]

Oil (*Olive*).

Huxley (R.) On the treatment of choleraic diarrhœa by olive oil.
[LANCET, 1854, II, n. s., p. 434.]

Rabe. Brechruhr durch Provencerŏl geheilt.
[WOCHENSCHR. f. d. gesammt. Heilk. (Casper's), 1834, III, p. 567.]

Opium. (See, also, *Morphia.*)

Bagot. On the treatment of spasmodic cholera, and its consecutive fever, by the administration of opium.
[DUBLIN Med. Press, 1853, XXIX, pp. 225–227.]

Beamish (W.) Treatment of Asiatic cholera on the opiate or antidotal and conservative plan.
[DUBLIN Med. Press & Circ., 1866, II, pp. 481–485, 575–577.]

Bou. Remarks on the external application of opium in cholera.
[LONDON Med. & Phys. Jour., 1832, XII, n. s., pp. 355–358; *also, in* BOSTON Med. & Surg. Jour., 1832, VI, pp. 300–301.]

Brown-Séquard (C. E.) Opium and the actual cautery in the treatment of cholera.
[ARCH. of Sci. & Prac. Med., N. Y., 1873, II, pp. 467–468.—BOSTON Med. & Surg. Jour., 1873, LXXXIX, pp. 319–320.—CANADIAN Med. Times, 1873, I, p. 154.]

Chauffard (H.) Mémoire sur le choléra-morbus, et particulièrement sur l'emploi et l'action de l'opium dans cette maladie.
[JOUR. gén. de méd., 1829, 3e s., IX, pp. 8–31.]

Grandesso-Silvestri (O.) Sull'uso dell'opio nella cura del cholera asiatico.
[GAZ. med. it. prov. Veneta, 1867, X, pp. 348–349.]

Greening (J.) Opium in cholera.
[LONDON Med. Gaz., 1832, IX, p. 120.]

Krüger-Hansen (B. C.) Opium, als Hauptmittel in der Cholera. 8°. *Güstrow*, 1832.

M'Kittrick (R.) On the employment of large doses of opium in dysenteric cholera, as it appeared in the district of Ballyhackamore, parish of Holywood, in December 1827 and January 1828.
[EDINB. Med. & Surg. Jour., 1828, XXX, pp. 29–34.]

Macpherson (J.) On the increased fatality of cholera in India, and on the use of opiates and of stimulants.
[MED. Times & Gaz., 1870, I, pp. 62–63.]

Marcusy (M.) * De opio ad sanandam choleram epidemicam remedio. 8°. *Vratislaviensis* [1832]. L.

Michel (A.) De l'efficacité de la poudre de Dover contre le choléra.
[BULL. gén. de thérap. méd. et chir., 1854, XLVII, pp. 147–149.]

Riberi. Traitement du choléra par le cathétérisme opiacé.
[L'UNION méd., 1854, VIII, p. 566; *also, in* GAZ méd. de Paris, 1855, X, pp. 411–414, 454–456, 483–486.]

[**Simon** (F. A., *jun.*)] Abfertigung und Warnung vor einem gewissen Krüger-Hansen, und seinem im Hamburger Correspondenten vom 7. Sept. d. J. empfohlenen Mittel gegen die Cholera. 8°. *Hamburg*, 1831. L.

Simorre. Sur l'emploi de l'opium à haute dose dans le traitement du choléra.
[BULL. gén. de thérap. méd. et chir., 1865, LXIX, pp. 413–414.]

Smith (J. A.) English cholera. On the use of opium and the mustard cataplasm.
[LANCET, 1831, II, pp. 792–793.]

Abfertigung und Warnung vor einem gewissen Krüger-Hansen. *See* [**Simon** (F. A., *jun.*)]

Des indications respectives des opiacés et des évacuants en temps de choléra.
[JOUR. des connaiss., 1849, XVII, pp. 194–195.]

Du traitement adopté dans le service spécial des cholériques de M. Rayer, pendant le mois de décembre.
[MONIT. des hôp., Paris, 1854, II, pp. 17–20.]

Opium (Hypodermic use of).

Wadham. Case of cholera—treatment by the subcutaneous injection of opium.
[MED. Times & Gaz., 1866, II, p. 171, 194–195.]

Oxygen and ozone.

Bertini (P.) Della contagiosità del cholera e dell'ozono come rimedio curativo, etc. *Lucca*, 1856.

Bertolio (A.) Alcuni pensieri su l' ozono e su 'l creosoto per la cura del coléra asiatico.
[GAZ. med. it. Lomb., 1855, VI, 3a s., pp. 353–355.]

Birch (S. B.). Oxygen in the treatment of disease.
[MED. Circular, 1860, XVI, p. 77.]

Coster (J.) Traitement du choléra-morbus, par le gas oxygène. 8°. *Paris* [*n. d.*]
[1st ed. published in "REVUE britannique", 1831.]

Heywood (C. F.) Paper on the inhalation of oxygen gas in cholera.
[N. Y. Med. Record, 1871, VI, p. 356.]

Holmes (H.) Oxigen in cholera; a letter on that subject to every member of the profession. 8°. *London*, 1855. L.

Jütte. Ueber den Gebrauch des Sauerstoffs in der Cholera.
[DEUTSCHE Klinik, 1866, XVIII, pp. 436–437.]

Klein. Inhalationen reinen Sauerstoffs als Förderungsmittel rationeller Therapeutik der Cholera morbus.
[AERZTL. Intell.-Bl., 1873, XX, pp. 617–619, 681–682.]

Stein (J. H.) Treatment of cholera by inhalation of oxygen.
[LANCET, 1831–32, I, pp. 364–365.]

Touzet. Essai sur l'inspiration de l'oxygène, considérée comme moyen préservatif et curatif du choléra-morbus et de quelques autres maladies. 8°. *Paris*, 1832.

Wittmeyer. Sauerstoff- und Wasserdampf-Inhalation im asphyctischen Stadium der Cholera.
[DEUTSCHE Klinik, 1866, XVIII, pp. 366–367.]

Percussion.

Sutton (T.) Percussion in cholera.
[LOND. Med. & Surg. Jour., 1834, IV, pp. 154–155.]

Petroleum.

Guthrie (G. J.) Naphtha a cure for cholera.
[DUBLIN Med. Press, 1848, XX, pp. 24–25.]

——— A new remedy for cholera.
[MED. Times, 1848, XVIII, p. 126.]

Soulby (G.) Petroleum in Asiatic cholera.
[PROV. Med. Jour., 1848, p. 446.]

Tunstall (J.) Petroleum in Asiatic cholera.
[PROV. Med. & Surg. Jour., 1848, p. 328.]

Twining (E.) Remarks on the use of petroleum in Asiatic cholera, and the probable advantages of phosphate of soda as a remedy.
[PROV. Med. Jour., 1848, p. 503.]

Phosphorus.

Adam (J.) On the exhibition of phosphorus in cholera morbus.
[TRANS. Med. & Phys. Soc. of Calcutta, 1831, pp. 69–73.]

Aldis (C. J. B.) Phosphorus in cholera.
[MED. Times, 1849, XX, p. 225.]

Barry (M. B.) Phosphorus in cholera.
[LONDON Med. Gaz., 1832, X, pp. 580–581.]

Batten (W.) Malignant cholera. Treatment of its advanced stages with phosphorus. Preparation of a phosphorus pill.
[LANCET, 1832–33, II, pp. 694–695.]

——— Treatment of malignant cholera in its advanced stages with phosphorus.
[LANCET, 1849, II, n. s., pp. 313–314.]

Mann (J.) Phosphorus in malignant cholera.
[LANCET, 1832–33, II, p. 755.]

Paul (J.) Ueber den Gebrauch des Phosphors in der Cholera epidemica.
[ZEITSCHR. f. klin. Med., 1854, V, pp. 164–181.]

Potassæ liquor.

Corner. Liquor potassæ, &c., in the treatment of cholera.
[LANCET, 1866, II, pp. 276–277.]

Potassium (Bromide of).

Begbie (J.) Note on the use of bromide of potassium in cholera.
[LANCET, 1866, II, pp. 664–665.]

Pepper (W.) Note on the use of injections of solution of bromide of potassium in cholera collapse.
[MED. Times, 1872–73, III, p. 742.]

Richardson (J. G.) Letter suggesting different strength for Dr. Pepper's intravenous injection of bromide of potassium in collapse of Asiatic cholera.
[PHILA. Med. Times, 1873, III, p. 653.]

Sutton. Cholera—treatment by the bromide of potassium—recovery.
[MED. Times & Gaz., 1867, II, p. 342.]

Potassium (Chlorate of).

Cogswell (C.) Employment of chlorate of potash in cholera.
[LANCET, 1853, I, n. s., p. 400.]

Potassium (Permanganate of).

Evezard (E. D.) On the treatment of Asiatic cholera by the internal administration of Condy's disinfecting fluid.
[MADRAS Quar. Jour. of Med. Sci., 1863, VII, pp. 341–346.]

Wienkowski. Ueber das Verhalten der in den Darmentleerungen der Cholerakranken enthaltenen Pilze gegen Kali hypermanganicum und Chinin.
[WIEN. med. Wochenschr., 1873, XXIII, pp. 1027–1028.]

Purgatives.

Beaumont. Sur l'innocuité des vomitifs et des purgatifs dans le traitement du choléra et des affections cholériques. 4°. [*Paris, n. d.*]

Davey (J. G.) Treatment of cholera by purgatives.
[ASSN. Med. Jour., 1857, II, pp. 884–885.]

Grady (W. G.) Purgatives in cholera.
[MED. Circular, 1854, V, p. 141.]

Higgins. Des purgatifs en général; un mot sur leur emploi comme traitement de la cholérine.
[REVUE méd., 1856, I, pp. 654–662.]

——— Note sur les purgatifs. Un mot sur leur emploi comme traitement de la cholérine.
[BULL. gén. de thérap. méd. et chir., 1856, L, pp. 458–464.]

M'Divitt (J.) Three letters on the treatment of malignant cholera with purgatives.
[LANCET, 1831–32, II, pp. 754–759.]

——— Purgative medicines in cholera.
[LONDON Med. Gaz., 1832, X, pp. 771–776.]

Macloughlin (D.) Purgatives and cholera.
[MED. Times & Gaz., 1854, IX, n. s., p. 272.]

Quassia.

Honigberger (J. M.) Heilung der indischen Brechruhr durch Einimpfung des Quassius. [Aus dem Englischen übersetzt.] 8°. *Wien*, 1859. L.

Quassia in the treatment of cholera.
[DUBLIN Med. Press, 1861, IV, n. s., p. 103.]

Quassine (Hypodermic use of).

Rees (O.) Further report of a case of cholera treated by the subcutaneous injection of quassine.
[MED. Times & Gaz., 1866, II, p. 195.]

Quinine.

Bourgogne. Observation d'un cas de choléra asiatique confirmé. Guérison rapide par l'usage du tannate de quinine.
[L'ABEILLE méd., 1865, XXII, pp. 289–290.]

——— Observation de choléra;—guérison rapide obtenue par le tannate de quinine.
[L'UNION méd., 1873, XVI, 3e s., pp. 410–413.]

Brulais (O. des). Épidémie cholérique de la Loire-Inférieure. Emploi du sulfate de quinine.
[JOUR. de méd. et de chir. prat., 1866, XXXVII, pp. 447–448.]

Close (T.) Treatment of cholera by quinine.
[SCALPEL, 1849–50, I & II, pp. 432–438.]

Dagonet. Traitement du choléra.—Sulfate de quinine.
[GAZ. des hôp., 1864, p. 474.]

Gordon (T. W.) Cholera.
[TRANS. Ohio State Med. Soc., 1855, pp. 124–135.]

Grandière (B. de la). Interprétation du fait publié par M. le docteur Bourgogne, relatif au choléra prétendu guér par le tannate de quinine.
[L'ABEILLE méd., 1865, XXII, pp. 322–323.]

Haas. Chinin und Arsen als Präservative gegen die Cholera.
[OESTER. med. Wochenschr., 1848, pp. 1185–1189.]

Herpin. Deux observations de choléra-morbus guéri avec la potion anti-vomitive de Rivière et la décoction de quinquina prise à l'intérieur et en lavemens.
[GAZ. des hôp., 1832, VI, pp. 354–355.]

Parkes (E. A.) Quinine in cholera.
[MED. Times & Gaz., 1853, VII, n. s., p. 407.]

Pompe van Meerdervoort (J. L. C.) Behandeling van Cholera asiatica, met Sulphas Chinine in Japan.
[NEDERL. Tijdschr., V. Geneesk., 1865, I, pp. 449–453.]

Putelli (A.) Dell'utilità del solfato di chinina ad alte dosi nella cura nel cholera-morbus asiatico, somministrato nello stadio algido.
[ANN. univ. di med., 1836, LXXVII, pp. 490–497.]

Ristelhueber. Quelques remarques sur le choléra et sur l'emploi du sulfate de quinine comme préservatif. Suivies de procédés pour vaporiser des substances médicamenteuses sous la couverture d'un lit sans déplacer le malade. 8°. *Strasbourg*, 1832.

Sappington (J.) On quinine and cholera.
[ECLECT. Med. Jour., 1849, I, n. s., pp. 253–256.]

Sargent (F. W.) Notes of a few cases of cholera treated in the summer of 1849; showing the comparative curative powers of sulphate of quinine in large doses.
[MED. Examiner, X, n. s., 1854, pp. 529–548.]

Schlömann (A.) Die Behandlung der asiatishen Cholera durch das schwefelsaure Chinin.
[BERLIN. klin. Wochenschr., 1871, VIII, pp. 431–434, 443–445.]

Strange (W.) On the treatment of cholera by quinine and iron.
[PROV. Med. Jour., 1849, pp. 652–656.]

Vial. De l'emploi du sulfate de quinine comme moyen préventif et curatif du choléra-morbus.
[L'UNION méd., 1860, VII, 2e s., pp. 582–583.]

À propos l'idée de comparer le choléra aux fièvres intermittentes pernicieuses, et de prescrire en conséquence le sulfate de quinine.
[GAZ. des hôp., 1831, V, p. 212.]

Salines. (See, also, *Injections, Saline.*)

Anderson (J.) Unsuccessful trial of Dr. Stevens' saline treatment in malignant cholera.
[LANCET, 1831–32, II, p. 530.]

——— Saline treatment of cholera.
[LONDON Med. Gaz., 1832, X, pp. 547–548.]

Barbier (E.) Le choléra épidémique et l'hydrologie médicale, Vichy et ses eaux minérales, comme médication préventive et effective. 8°. *Vichy* [1866].
[3d ed., 1868.]

Bourgeois. Traitement des affections cholériformes et médication abortive du choléra asiatique par les purgatifs salins.
[L'UNION méd., 1854, VIII, p. 426.]

Cambridge (S.) Successful employment of salines at the cholera hospital St. Luke's.
[LONDON Med. Gaz., 1833, XI, p. 46.]

Edin. Cholera: its treatment by salines, alkalies, and sulphuric acid.
[MED. Circular, 1853, III, pp. 386–387.]

Goss (J.) Collapse of cholera—successfully treated by salines.
[LONDON Med. Gaz., 1832, X, pp. 198–200.]

Greenhow (T. M.) Proposal to administer salines in cholera by the natural process of absorption and assimilation, instead of injecting the veins.
[LONDON Med. Gaz., 1832, X, pp. 545–546.]

Hancock (J.) Remarks on the disinfecting power of heat, . . . on the saline treatment of cholera, . . . ; and on the use of opium, etc., in such disorders.
[LANCET, 1831–32, II, pp. 630–634.]

Knight (P. S.) Saline treatment in typhus fever and cholera asphyxia.
[LANCET, 1831–32, II, p. 170.]

——— Saline treatment in cholera.
[LONDON Med. Gaz., 1832, X, p. 189.]

Leckie (A.) Asiatic cholera: saline treatment.
[MED. Circular, 1853, III, p. 325.]

——— On the saline treatment of cholera.
[LANCET, 1855, II, n. s., p. 76.]

Mair (J.) On saline treatment of cholera.
[MED. Times, 1849, XX, p. 428.]

Marsden (W.) Superiority of the saline treatment [in cholera].
[LONDON Med. Gaz., 1833, XI, pp. 47–49.]

Moss (W.) Saline treatment of cholera.
[LONDON Med. Gaz., 1832, X, pp. 711–712.]

Ousby (J.) Saline treatment in cholera.
[LONDON Med. Gaz., 1832, X, pp. 610–612.]

Reid (J. S.) Saline treatment of Asiatic cholera.
[MED. Times & Gaz., 1853, VII, n. s., pp. 683–684.]

Richardson (R. S.) On the saline treatment of cholera.
[LONDON Med. Gaz., 1832, X, pp. 511–515.]

Richardson (W. L.) On saline treatment of cholera.
[MED. Times, 1849, XX, pp. 345–346.]

Ridgway (T.) On the use of the purgative neutral salts in cholera.
[LONDON Med. & Phys. Jour., 1832, II, pp. 273–275.]

Ross, Stewart, Turley [*and others*] On Dr. Stevens' saline treatment of cholera.
[MED. Times, 1849, XIX, pp. 241–242, 267–268, 294–295, 422–424, 443–444, 509–510, 534–536, 630, 680–682; XX, pp. 15, 207; 1850, XXI, pp. 167, 207.]

Stanley (E.) Saline treatment of cholera.
[LONDON Med. Gaz., 1832, X, pp. 378–379.]

Tardieu. Emploi de l'eau salée et de l'eau de mer dans le traitement du choléra.
[GAZ. des hôp., 1849, pp. 211–212.]

Tucker (J.) On saline treatment of cholera.
[MED. Times, 1849, XX, pp. 327–328.]

Turley (E. A.) On Dr. Stevens's saline treatment of Asiatic cholera.
[MED. Times, 1849, XIX, pp. 423–424, 534–536.]

——— On saline treatment of cholera.
[MED. Times, 1849, XX, p. 273.]

Turley (E. A.)—continued.

——— Saline treatment of cholera.
[MED. Times & Gaz., VII, n. s., 1853, pp. 610–611.]

——— Dr. Turley's rejoinder to Dr. Reid on the saline treatment.
[MED. Times & Gaz., 1854, VIII, p. 98.]

Villard (A.) Le choléra, et M. le prof. J. Aronssohn dans les hôpitaux de Marseille. 8°. *Marseille*, 1865.

Wakefield (H.) Successful treatment of cholera.
[LONDON Med. Gaz., 1832, X, pp. 133–134.]

Cholera—cases in which the saline treatment failed.
[LONDON Med. Gaz., 1832, X, pp. 609–610.]

Hints on the saline treatment of cholera, &c.
[LONDON Med. Gaz., 1832, X, p. 646.]

Investigation (An) into the merits of the saline treatment of cholera.
[MED. Circular, 1853, III, pp. 449–456.]

Non-purgative salts in cholera.
[LONDON Med. Gaz., 1832, X, pp. 89–90.]

Silver (*Nitrate of.*)

Barth. Coup d'œil sur le traitement du choléra-morbus et en particulier sur l'emploi du nitrate d'argent dans cette maladie.
[BULL. gén. de thérap. méd. et. chir., 1849, XXXVII, pp. 241–248.]

Cales. Over het Gebruik van Nitras Argenti bij Cholera.
[NEDERL. Tijdsch. v. Geneesk., 1859, III, p. 613.]

Garlike (J. W.) Nitrate of silver in cholera, and its mode of application.
[MED. Times, 1849, XIX, p. 268.]

Levy (I.) Die Choleraheilung mit saltpetersaurem Silber. 8°. *Breslau*, 1849. L.

Ross (G.) The nitrate of silver in cholera.
[MED. Times, 1849, XX, pp. 224–225; *also, in* MED. Circular, 1854, V, pp. 85–86.]

Silver (*Oxide of*).

Brookes (W. P.) On oxyde of silver in cholera.
[MED. Times, 1849, XX, pp. 187–188.]

Sodium (*Carbonate of*).

Baudrimont. Traitement du choléra par le bicarbonate de soude.
[L'UNION méd., 1849, III, pp. 501–502.]

Cookworthy (J. C.) Cholera cured by carbonate of soda.
[MED. Times & Gaz., 1855, X, n. s., p. 502.]

Cooper (G. L.) Sesquicarbonate of soda and laudanum in cholera.
[LANCET, 1853, II, n. s., p. 353.]

Sodium (*Chloride of*).

Ainsworth. Culinary salt in cholera.
[LONDON Med. Gaz., 1832, IX, p. 522.]

Demarbaix. Note sur l'emploi du chlorure d'oxyde de sodium dans le traitement du choléra.
[JOUR. de méd., de chir. et de pharmacol., 1850, X, pp. 140–141.]

Henry (A.) Lettre sur les inspirations de chlorure de soude contre le choléra.
[GAZ. méd. de Paris, 1835, III, pp. 766–767.]

Pidduck (J.) Treatment of malignant cholera in the parish of St. Giles, London, with remarks on the employment of salt.
[LANCET, 1831–32, II, pp. 778–780.]

——— Successful treatment of cholera by the muriate of soda.
[LONDON Med. Gaz., 1832, X, pp. 673–674.]

——— Successful treatment of cholera by table salt.
[DOCTOR, 1833, I, pp. 67–68.]

Richard. Note sur l'emploi du chlorure de sodium par absorption pulmonaire dans le traitement du choléra-morbus.
[GAZ. méd. de Paris, 1835, III, pp. 587–588.]

Stephens (T.) On the use of muriate of soda in cholera.
[LONDON Med. Gaz., 1832, IX, pp. 938–939.]

Emploi (De l') du chlorure de sodium dans le traitement du choléra.
[BULL. gén. de thérap. méd. et chir., 1865, LXIX, pp. 377–379.]

Traitement du choléra-morbus confirmé par le chlorure de sodium.
[BULL. gén. de thérap. méd. et chir., 1853, XLV, pp. 560–562.]

Sodium (*Sulphate of*).

Calthrop (W. C.) Sulphate of soda in cholera.
[LANCET, 1856, II, n. s., p. 526.]

Stachys anatolica.

Coetsem (Van). Rapport sur l'action thérapeutique de la stachys anatolica dans le traitement du choléra-morbus asiatique.
[BULL. de l'Acad. roy. de méd. de Belgique, 1849–50, IX, pp. 10–14.]

Stimulant.

Dearaly (H. H.) On the pathology of cholera, and its treatment by stimulant remedies.
[LANCET, 1849, II, pp. 233–234.]

François. Rapport sur des documents relatifs à un remède anticholérique, découvert et préconisé par M. Ruiz, de New-York.
[Bull. de l'Acad. roy. de méd. de Belgique, 1867, I, pp. 751–752.]

Freeman (E.) The stimulant treatment in cholera.
[Eclectic Med. Jour., 1874, xxx, pp. 441–443.]

Hancorn (J. R.) Treatment of cholera by stimulants, mercury, and sesquichloride of iron.
[Lancet, 1848, II, pp. 290–291.]

Lacoste. De la méthode stimulante employée à l'hôpital de Bruges pendant l'épidémie de choléra de 1854.
[Arch. belg. de méd. mil., 1856, xvii, pp. 5–9.]

Little (W. J.) Case of malignant cholera, treated at first on Dr. Stevens' plan, temporary improvement following saline injections, and, subsequently, spirituous injections,—excitement,—death.
[Lancet, 1832, II, pp. 454–455.]

Murray (J.) Cholera, new mode of treatment.
[London Med. & Surg. Jour., 1832, I, pp. 31–32.]

Rankin (J. D.) Reply to Dr. Geo. Barnard's article in the Jan. No. of the American Jour. of Med. Science, in reference to pathology and treatment of cholera.
[Galveston Med. Jour., 1869, IV, pp. 1–9.]

Stable (D. N.) Treatment of cholera by stimulants.
[London Med. Gaz., 1834, xiv, pp. 814–815.]

Sutro (S.) Dr. Ottinger's treatment of cholera.
[Med. Times & Gaz., 1854, IX, n. s., pp. 622–623.]

Todd (G.) Report of a case of spasmodic cholera successfully treated by stimulants.
[Lancet, 1856, II, n. s., p. 323.]

Strychnia.

Abeille. Note sur quelques modifications apportées au traitement du choléra par la strychnine.
[Gaz. med. de Paris, 1854, IX, 3e s., pp. 459–460.—Gaz. des hôp., 1854, pp. 347–348.—L'Union méd., Paris, 1854, VIII, pp. 359–360.]

——— Du sulfate de strychnine dans le traitement du choléra.—Preuves de la spécificité de cet médicament.
[Monit. des hôp., 1854, II, pp. 692–693, 740–743, 745–747, 756–758.]

——— The same. 8°. *Paris*, 1854. L.

Abeille—continued.

——— De la strychnine dans le traitement du choléra.
[L'Abeille méd., 1854, XI, p. 290; also, in Revue de thérap., 1854, II, pp. 424–425.]

Alison (S. S.) The use of strychnine indicated in cholera.
[London Med. & Surg. Jour., 1833, II, pp. 265–267.]

Balfour (G. W.) On the treatment of cholera by strychnine.
[Lancet, 1867, I, pp. 8–9.]

Bonnafont. Note sur quelques essais de l'emploi de la strychnine dans le traitement du choléra.
[Bull. gén. de thérap. méd. et chir., 1854, XLVII, pp. 187–190.]

Bossu (A.) Le choléra traité par le sulfate de strychnine.
[L'Abeille méd., 1854, XI, pp. 238–239.]

Brochin. Quelques explications au sujet du traitement du choléra par le sulfate de strychnine.
[Gaz. des hôp., 1854, pp. 385–386.]

Burggraeve. Emploi de la strychnine et de l'électricité dans le choléra.
[Répert. de méd. dosimétr., 1873–73, I, pp. 529–539.]

Davasse (J.) Thérapeutique expérimentale. Étude sur les effets et les indications de la strychnine et de la noix vomique dans le traitement du choléra, suivie d'une réponse aux sophismes d'un adversaire. Extrait du Moniteur des hôpitaux. 8°. *Paris*, 1854. L.

Dechambre (A.) Expériences récentes sur l'emploi de la strychnine dans le choléra.
[Gaz. hebd. de méd. et de chirurg., 1853–54, I, 814–816.]

Ferro-Basile (G.) * Essai sur l'action thérapeutique de la strychnine dans le choléra-morbus. 4°. *Paris*, 1856. L.

Fraser (W.) Strychnine in Asiatic cholera.
[Med. Chronicle, 1854, II, pp. 125–132.]

——— The same. 8°. [*n. d.*] L.

Gérardin. Rapport sur la méthode de M. Abeille du traitement du choléra-morbus par le sulfate de strychnine.
[Revue de thérap., 1854, II, pp. 513–517.]

Hensman (W.) Treatment of cholera with strychnia, with notes of illustrative cases.
[Army Stat., San., & Med. Repts., London, V, pp. 491–493.]

Jenkins (C. E.) Treatment of the malignant cholera with strychnine.
[Lancet, 1834–35, II, pp. 656–657.]

Labrousse. Choléra traité par l'arséniate de strychnine et l'arséniate de quinine.
[RÉPERT. de méd. dosimétr., 1874, II, pp. 89–90.]

Poyet. Emploi de la strychnine contre le choléra.
[GAZ. méd. de Lyon, 1854, VI, pp. 189–191.]

Bee. De la valeur du sulfate de strychnine dans le traitement du choléra.
[BULL. gén. de thérap. méd. et chir., 1854, XLVII, pp. 183–187.]

——— Note sur le traitement du choléra par le sulfate de strychnine.
[MONIT. des hôp., 1854, II, pp. 787–788.]

Verdier (J.) Du sulfate de strychnine dans le traitement du choléra.
[MONIT. des hôp., 1854, II, p. 992.]

Weir (W.) Cases of cholera asphyxia, in which the strychnine was employed.
[GLASGOW Med. Jour., 1832, V, pp. 140–150.]

Efficacy of strychnine in cholera.
[LONDON Med. & Surg. Jour., 1833, II, pp. 186–187.]

Emploi du sulfate de strychnine comme préservatif du choléra.
[ANN. d'hygiène pub., Paris, 1e54, II, 2e s., pp. 461–462.]

Mot (Un) encore sur le traitement du choléra par le sulfate de strychnine, et en particulier sur les essais de médication strychnique à l'hôpital du Roule.
[BULL. gén. de thérap. méd. et chir., 1854, XLVII, pp. 197–200.]

Traitement du choléra par la strychnine.
[GAZ. des hôp., 1854, pp. 401–402.]

Sudorifics. (See, also, *Bath, Hot-air.*)

Fraissinet (C.) Le choléra vaincu par les sudorifiques, ou le meilleur traitement . . . . consigné dans une brochure publiée à Besançon et reproduite, dans l'intérêt de l'humanité. 32°. *Montpellier*, 1854.

Gall (L.) Anweis zum Gebrauch seines Schweisserregungs-Apparats, insbesondere als Heilmittel der Cholera. 2te Aufl. 8°. *Trier*, 1832.

Steinbacher. Schnellste und sicherste Selbsthülfe bei Cholera-Anfällen durch rasche Schweiss-Erzeugung vornehmlich durch das leicht zu konstruirende Hausdampfbad, nach den Erfahrungen bei mehreren Cholera-Epidemien. 8°. *Augsburg*, 1865. L.

Sugar.

Lorenzutti (L.) Aus dem Cholera-Spitale in Triest: Injektion von Traubenzucker in die Venen bei Cholerakranken.
[WIEN. med. Presse, 1866, VII, pp. 1104–1106.]

Mackintosh (J. I.) Treatment of cholera with sugar.
[LANCET, 1854, I, n. s., pp. 384–385.]

Wolff (S.) Treatment of cholera with sugar.
[LANCET, 1854, II, p. 274.]

Sulphur.

Blaise. Du mode d'administration des fumigations de soufre dans le choléra.
[REVUE de thérap. méd.-chirurg., 1854, II, p. 488.]

Cabaret. Du soufre sublimé dans la période algide du choléra.
[JOUR. des connaiss., 1850, XVII, pp. 11–12.]

Canolle. Traitement du choléra par les vapeurs sulfureuses.
[REVUE de thérap. méd.-chirurg., 1854, II, pp. 121–122.]

Giordano. Zolfo e colera.
[GIORN. d. R. accad. di med. di Torino, 1867, IV, 3a s., pp. 322–341.]

Grove (J.) On the treatment of cholera by sulphur.
[LANCET, 1853, II, n. s., p. 304.]

——— On epidemic cholera and diarrhœa: their prevention and treatment by sulphur. 3d ed. 8°. *London*, 1865. L.
[2d ed., 1854.]

Lorie. Du soufre sublime contre le choléra.
[JOUR. des connaiss., 1849, XVII, pp. 150–151.]

Miergues. Guérison d'un cas de choléra intense, par le soufre associé au charbon.
[JOUR. des connaiss., 1850, XVIII, p. 263.]

Pilaski (F.) Potion au carbure de soufre contre le choléra.
[BULL. gén. de thérap. méd. et chir., 1859, LVII, pp. 125–127.]

Sarzana (E.) Sull'uso dello zolfo nel cholera.
[GIORN. R. accad. di med. di Torino, 1862, VII, 2a s., pp. 776–777.]

Graefe (A. v.) Ueber das Tannin als Choleramittel. Eine ärztliche Flugschrift. 8°. *Berlin*, 1848. L.

Temperature.

Arnott (J.) On extreme cold as a remedy for Asiatic cholera.
[LANCET, 1849, II, p. 135.]

——— On the employment of frigorific mixtures or extreme cold in cholera.
[LANCET, 1849, II, n. s., pp. 234–235.]

——— On the use of severe or benumbing cold in cholera.
[LONDON Med. Gaz., 1849, XLIV, pp. 373–374.]

——— On the internal application of a very low temperature in Asiatic cholera. *London*, 1852.

Bulley (F. A.) Case of spasmodic choleraic disease successfully treated by hot water packing.
[MED. Times & Gaz., 1866, II, pp. 139-140.]

Burrows (G.) Application of cold in cholera.
[LONDON Med. Gaz., 1833, XI, pp. 179-182.]

Casper (J. L.) Die Behandlung der asiatischen Cholera durch Anwendung der Kälte, physiologisch begründet, und nach Erfahrungen am Krankenbette dargestellt. 8°. *Berlin*, 1832. L.

Chapman (J.) Cholera at Southampton: its successful treatment by cold and heat along the spine.
[MED. Times & Gaz., 1865, II, pp. 414-417.]

——— Diarrhœa and cholera: their origin, proximate cause, and cure by means of ice.
[MED. Circular, 1865, XXVII, pp. 73-75; *also, in* MED. Times & Gaz., 1865, II, pp. 111-113.]

——— The same. 8°. *London*, 1865. L.
[2d ed., 1866.]

——— The same. 12°. *Philadelphia*, 1866. L.

——— "Ice bags in cholera."
[MED. Times & Gaz., 1865, II, pp. 611-613.]

——— The treatment of cholera by means of ice at Southampton.
[MED. Times & Gaz., 1866, II, pp. 101-102.]

——— Treatment of cholera by the use of ice bags.
[LANCET, 1867, I, p. 727; 1867, II, p. 31.]

——— Cases of diarrhœa and cholera treated successfully through the agency of the nervous system chiefly by means of the spinal ice-bag. 8°. *London*, 1871. L.

Delpeuch (E.) Moyen de calorification dans le choléra.
[L'UNION méd., 1865, XXVIII, 2e s., pp. 184-186.]

Flemming (F.) Erste Hülfe bei Cholera durch rechtzeitige Anwendung der trocknen Wärme. 8°. *Dresden*, 1866. L.

Hooper (W.) Hot-water cushions in cholera.
[MED. Times & Gaz., 1853, VII, n. s., p. 433; *also, in* MED. Circular, 1853, III, p. 365.]

Legroux. Quelques mots sur l'emploi de la chaleur et du froid dans le choléra.
[ACTES de la Soc. méd. des hôp. de Paris, 1850, pp. 68-79.]

——— Quelques considérations sur le traitement du choléra, et spécialement sur l'emploi de la chaleur et du froid.
[BULL. gén. de thérap. méd. et chir., 1854, XLVII, pp. 242-248.]

MacCormack (M. J.) The treatment of cholera by the use of ice bags.
[LANCET, 1867, I, p. 787.]

Müller (F.) Die Cholera und die Anwendung der Kälte als einfachstes Schutz- und Haupt-Heilmittel derselben mit Berücksichtigung der durch die Untersuchung mit dem Horchrohre erhaltenen Resultate. 8°. *Wien*, 1832. L.

Rehner (*jun.*) **und Pulst.** Die kalte Behandlung der Cholera.
[WOCHENSCHR. f. d. gesammt. Heilk., 1851, pp. 638-639.]

Schleiss (v.) Die Anwendung der Eisblasen auf den Unterleib bei der Cholera.
[ARZTL. Intell.-Bl., 1854, I, pp. 418-419.]

Smith (T. H.) Cold affusion in cholera.
[LONDON Med. Gaz., 1832, IX, pp. 508-512.]

Sutherland (A. R.) New mode of applying heat in cholera.
[LONDON Med. Gaz., 1832, IX, p. 782.]

Turner (J.) Suggestions for raising the temperature of the body in cases of malignant cholera. [Heat.]
[LANCET, 1831-32, II, pp. 94-95.]

——— A new method suggested for the restoration of animal heat [by enveloping the body in sheep-skin] in the collapse stage of cholera.
[LANCET, 1848, II, p. 504.]

Applications de la méthode du Dr. Chapman (le froid et la chaleur) au traitement du choléra.
[GAZ. des hôp., 1865, pp. 561-563.]

[Choléra.] De la méthode de traitement par l'application du froid et de la chaleur le long de la colonne vertébrale (méthode du docteur Chapman).
[GAZ. des hôp., 1865, p. 549.]

Dr. James Arnott's treatment of cholera.
[MED. Times, 1849, XX, pp. 286-288.]

Ice bags in cholera.
[MED. Times & Gaz., 1865, II, pp. 577-578.]

Kalte (Die) Behandlung der Cholera das Reactionsstadium. (Mitgetheilt durch Dr. Cohen, Secretair der Gesellschaft.)
[WOCHENSCHR. f. d. gesammt. Heilk., 1851, pp. 819-822.]

Tobacco.

Tobacco in cholera.
[LONDON Med. Gaz., 1852, IX, pp. 54-55.]

Tourniquet.

Wise (T. A.) Remarks on the best mode of treatment of cholera, hemorrhage, exhaustion, &c.
[DUBLIN Quar. Jour. of Med. Sci., 1852, XIII, pp. 59-67.]

On the use of the tourniquet in cholera.
[London Med. Gaz., 1832, IX, p. 598.]

Turpentine.

Bellencontre (E.) De l'emploi de l'essence de térébenthine par la méthode intra-leptique, contre plusieurs cas de choléra très grave.—Guérison.
[Gaz. des hôp., 1854, p. 294.]

Brochin. Traitement du choléra par l'essence de térébenthine d'après le procédé de M. le docteur Bellencontre.
[Gaz. des hôp., 1854, pp. 357-358.]

Brown (R.) Report of a case of cholera treated successfully by rectified oil of turpentine, administered internally as a specific.
[Lancet, 1848, II, p. 530.]

Dru (O.) Traitement du choléra par la térébenthine.
[Monit. des hôp., 1854, II, pp. 950-951.]

Moore (J.) On the internal administration of turpentine in cholera.
[Lancet, 1848, II, p. 478.]

Mudge (J. W.) Remarks on the treatment of cholera by turpentine.
[Madras Quar. Jour. of Med. Sci., 1863, VI, pp. 438-448, 1 table.]

——— Turpentine in cholera.
[Med. Times & Gaz., 1866, II, p. 181.]

Sawyer (G.) Turpentine in cholera.
[London Med. & Surg. Jour., 1835, VI, pp. 149-150; *also, in* Lancet, 1848, II, p. 704.]

Vaccination.

Metsch. Die Vaccination als Heilmittel in der Cholera. (Von dem Med.-Dept. des Ministeriums des Innern zur Veröffentlichung in der Med. Zeitung Russlands officiell mitgetheilt.)
[Med. Zeitung Russlands, 1855, p. 396.]

Veratrum lobelianum.

Hubeny. Bemerkungen über die Wirkungen des Veratrum lobelianum Bernhardi in der Brechruhr.
[Vierteljahrschr. f. d. prakt. Heilk., 1857, II, pp. 111-116.]

Water. (See, also, *Hydrotherapia.*)

Becker (C.) Die Cholera, ihre Ursachen und ihre Heilung durch Wasser. 8°. *Göthen*, 1853. L.

Lautour. Choléra-morbus guéri par le seul usage de l'eau pure; observation recueillie en septembre 1832.
[Ann. de la méd. phys., XXII, pp. 367-368.]

Noguèras (J.) Méthode la plus simple et la plus sûre pour guérir le choléra-morbus avec l'eau seulement . . . . Traduit de l'espagnol par R. P. F. B. S. . . . . 32°. *Avignon*, 1865.
[Original work appeared in 1850.]

Schieferdecker (C. C.) Short essay on the invariably successful treatment of cholera with water. 8°. *Philadelphia*, 1849. L.

Viek (J.) Die Behandlung der Cholera mit Wasser.
[Putzar's Jour. f. naturgem. Gesundh.-Pflege, 1855, III, pp. 307-310.]

Cholera (Die), ihre Ursachen und ihre Heilung durch Wasser.
[Putzar's Jour. f. naturgem. Gesundh.-Pflege, 1853, I, pp. 51-61, 65-84, 97-111, 129-134.]

Heilung der Cholera mit Wasser.
[Putzar's Jour. f. naturgem. Gesundh.-Pflege, 1854, II, pp. 266-268.]

Kritik der bisherigen Cholera-Kuren, nach den Berichten der Herren DD. Radius und Kleinert. Als Ehrenrettung der angefeindeten Wasserheilkunde vom Oertel in Ansbach. 8°. *Sulzbach*, 1832. L.

Water (Cold).

Casper (J. L.) De Behandeling der aziatische Cholera, door het Aanwenden van koud Water, op physiologische Gronden aangeprezen. Uit het Hoogduitsch door I. G. Rosenstein. 8°. *Rotterdam*, 1832. L.

French (J. G.) Cold water treatment of cholera.
[London Med. Gaz., 1832, X, pp. 770-771.]

Gilkrest (J.) Efficacy of copious libations of cold water in cholera.
[London Med. & Surg. Jour., 1833, II, pp. 244-245.]

Grant (J. M.) Remarks on the use of ice and cold water in the collapse of cholera.
[Med. Chronicle, 1854, II, pp. 85-96.]

Menzies (D.) Remarks on the nature and treatment of Asiatic cholera, with special reference to the administration of "small portions of iced water," and the employment of the vapor-bath, in this disease.
[Lancet, 1866, I, pp. 632-634.]

Michaal (C. L.) Gedanken über die Cholera und über die Wirkungen und den Nutzen des innern Gebrauchs des kalten Wassers in derselben. 8°. *Celle*, 1832.

Moore (J. S.) Ice water in the treatment of epidemic cholera.
[St. Louis Med. Reporter, 1868–69, IV, pp. 11–13.]

Netter (A.) Du traitement du choléra par l'administration, coup sur coup, d'énormes quantités de boissons aqueuses (20 litres et plus dans les vingt-quatre).
[Gaz. méd. de Strasbourg, 1862, XXII, pp. 119–125.—Rev. méd., 1862, II, pp. 333–334; *also*, reprint in 8°, Paris, 1862.—Gaz. des hôp., 1872, XLV, pp. 915–916, 932–934, 955–957, 978–980, 987–988.]

Oertel (E. F. C.) Die indische Cholera einzig und allein durch kaltes Wasser vertilgbar. Allen Regierungen, Aerzten und Nichtärzten zur Beherzigung. 4°. *Nürnberg*, 1831. L.

——— Victoria Kaltwasser hat die Cholera besiegt, etc. 16°. *Nürnberg*, 1831.

——— Curiosa medica, des berühmten Wasserdoctors, Hrn. Gymnasialprofessors Oertel in Ansbach "durchgreifende Kaltwassercur für die Cholera" betreffend. [Von einem eifrigen Verehrer der Oertel'schen Wassermuse.]
[Med. Conversbl., 1832, pp. 49–55.]

Peyron. Lettre sur l'emploi de l'eau froide à haute dose dans le traitement du choléra.
[Gaz. méd. de Paris, 1832, III, pp. 784–785.]

Regenhart (J.) Die orientalische Cholera. Populär wissenschaftliche Skizze dieser Weltseuche, nebst einem Anhange, enthaltend: Systematische Behandlung der Cholera mit kaltem Wasser. 8°. *Wien*, 1849. L.

Richter (C. A. W.) Die Cholera durch kaltes Wasser zu verhüten und zu heilen. Abgedruckt aus dem Journal für naturgemässe Gesundheitspflege und Heil-Kunde für 1855. 8°. *Berlin*, 1855. L.

Roberts (R.) Exhibition of cold water in cholera.
[London Med. Gaz., 1832, X, p. 770.]

Ross (A.) Case of cholera treated by copious beverages of cold water.
[Trans. Med. & Phys. Soc., Calcutta, 1835, VII, pp. 475–476.]

Shute (H.) Administration of cold water in the collapse stage of malignant cholera.
[Lancet, 1831–32, II, pp. 774–778.]

——— Internal administration of cold water, exclusively, in the third, or collapse stage, of malignant cholera.
[Lancet, 1831–32, II, pp. 685–687.—Doctor, 1833, I, pp. 99–100.—Med. Mag., 1833, I, pp. 319–322.]

Shute (H.)—continued.

——— On cold water in cholera.
[London Med. Gaz., 1832, X, pp. 707–709.]

Tourrette. Le choléra [traité] par l'eau froide en abondance.
[Revue méd., 1863, I, pp. 143–149.]

Wilson (J.) Case of malignant cholera treated in the collapse stage with cold water.
[Lancet, 1832–33, I, pp. 107–108.]

Whiting (J. B.) Cold water in the collapse stage of malignant cholera.
[Lancet, 1831–32, II, p. 719.]

——— Cholera treated by cold water.
[London Med. Gaz., 1832, X, pp. 738–739.]

Water, cold (*Affusions of*).

Addams (A.) Cases of cholera treated by affusions of cold water.
[Trans. Jour. of Med., 1836, VIII, pp. 61–]

Copland (J.) Affusion of cold water in cholera.
[London Med. Gaz., 1832, IX, p. 565.]

Cuffe (C. MacD.) Treatment of cholera by the cold douche.
[Lancet, 1866, II, p. 484.]

Fournier (A.) Note sur l'emploi des affusions froides dans le choléra typhoïde.
[Gaz. des hôp., 1865, pp. 550–551.]

Noguès (E.) *et* **Petit** (R.) Sur l'emploi des affusions froides dans le traitement du choléra.
[Gaz. hebd. de méd. et de chir., 1866, pp. 635–637.]

Pigeaux. De l'emploi des affusions froides dans le traitement du choléra-morbus.
[Gaz. méd. de Paris, 1832, III, pp. 316–317.]

Water, cold (*Injection of*).

Tourrette. Traitement du choléra par les ingestions d'eau froide.
[Monit. des hôp., 1853, I, pp. 1183–1184.]

Wayte (J.) Successful administration of cold water in the collapse stage of malignant cholera.
[Lancet, 1832–33, I, pp. 79–81.]

Water (*Warm*).

Bulley (F. A.) An account of several cases of bilious cholera treated by warm water applications.
[Med. Times, 1849, XX, pp. 433–436.]

Bulley (J. A.) Cases of choleraic diarrhœa treated by hot-water applications.
[Med. Times & Gaz., 1854, IX, n. s., pp. 42–]

Lasserre. Mémoire sur l'emploi de l'eau chaude contre le choléra. 8°. *Paris*, 1850.

Bons effets de l'emploi de l'eau chaude dans la période algide du choléra.
[Jour. de méd. et de chir. prat., 1849, xx, pp. 495–496.]

Water (Hypodermic use of).

Beigel (H.) Treatment of cholera by hypodermic injections of tepid water.
[Lancet, 1866, II, p. 204.]

Kellett (E. Y.) On the treatment of cholera by subcutaneous injection of water.
[Indian Med. Gaz., 1875, x, pp. 120–121.]

Traitement du choléra par les injections hypodermiques d'eau chaude et les injections salines dans les veines.
[Bull. gén. de thérap. méd. et chir., 1866, lxxi, pp. 373–375.]

Water (Injection of, into peritoneum).

Richardson (B. W.) Suggestion for the treatment of cholera in the stage of collapse by the artificial production of peritoneal or cellular dropsy.
[Assn. Med. Jour., 1854, p. 764.]

Wine.

Joux. Choléra. Efficacité du vin et des lavements vineux.
[Jour. de méd. et de chir. prat., 1865, xxxvi, pp 501–502.]

Goux—continued.

——— Choléra traité par le vin et les lavements vineux. Rectification. Faits à l'appui.
[Jour. de méd. et de chir. prat., 1866, xxxvii, 2e s., pp. 21–22.]

Woorara.

Isambert. Note sur deux essais de traitement du choléra par les injections hypodermiques du curare.
[Gaz. méd. de Paris, 1868, xxiii, pp. 274–276.]

Zinc (Oxide of).

Contini (A.) Dell'ossido di zinco nel trattamento del cholera-morbus.
[Gaz. med. it. Lomb., 1849, II, 2a s., pp. 350–351.]

Zinc (Valerianate of).

Ourgaud. Du valérianate de zinc contre le choléra.
[Revue de thérap., 1854, II, pp. 572–573.]

——— De la sidérose ou choléra-morbus et de son traitement par le valérianate de zinc. 8°. *Pamiers*, 1856. L.

Moura. Le choléra et le valérianate de zinc.
[Gaz. des hôp., 1856, pp. 70–71.]

Choléra. Emploi du valérianate de zinc.
[L'Abeille med., 1856, xiii, pp. 42–44.]

END OF BIBLIOGRAPHY